






AIM

Association for Information and Image Management




1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202



Centimeter




Inches



MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1



***LIFE CYCLE COST
ANALYSIS for the PLASMA
ARC FURNACE***

***Prepared for the Department of
Energy-Office of Technology
Development (EM-50), TTP Number
AL-1212-19.***

March 1994

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MIXED WASTE INTEGRATED PROGRAM

**LIFE CYCLE COST ANALYSIS
FOR THE
PLASMA ARC FURNACE**

**Peter Barnes-Smith
IT, Corp.
Albuquerque, NM
(505)262-8762**

PRELIMINARY ISSUED FOR COMMENT

OCTOBER 20, 1993

DRAFT

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

87B

MIXED WASTE INTEGRATED PROGRAM

LIFE CYCLE COST COMPARISON FOR THE PLASMA ARC FURNACE STUDY

EXECUTIVE SUMMARY

INTRODUCTION

The Mixed Waste Integrated Program requested that the Systems Analysis Group investigate the cost effectiveness of using the Plasma Arc Furnace (PAF) module in place of specified thermal and final forms treatment equipment in the baseline Mixed Waste Treatment Project (MWTP) study as performed by Bechtel Corporation, September 1992.

The attached estimates are based on the process equipment and facilities cost data contained in the Bechtel study. The PAF process equipment and facilities cost data were developed using independent cost estimates for the equipment list provided by SAIC, Waste Management and Technology Division, in cooperation with the Pollution Prevention and Systems Analysis Group of the Oak Ridge National Laboratory, Chemical Technology Division.

ESTIMATE METHODOLOGY

In order to develop the total life cycle cost estimate comparison for this study, it was necessary to use a common base for comparison. Although it was felt that the Bechtel MWTP study did not fully reflect the optimum size for the thermal and final forms treatment equipment, it was the best available data at the time.

Process Equipment

In both the baseline cost evaluation and the alternative treatment cost evaluation, the equipment costs for the major process equipment items were taken from areas 800 and 900 of the MWTP estimate, and factored from the direct cost level to total capital cost level by using the stated cost multipliers as defined in the study estimate. In the alternative treatment evaluation, the total capital cost was developed by replacing or removing certain process equipment items in areas 800 and 900, and applying the same multiplier factors to convert this direct cost to total capital cost.

Support Operations Equipment

The support operations equipment for areas 800 and 900 was factored from the MWTP cost estimate by the ratio of direct cost for the area process equipment against the direct cost for the

total process equipment. This factor was intended to apportion the support operations equipment to the user areas, in a direct ratio of process equipment cost.

Building Facilities

Using the MWTP cost summary for process buildings, the direct costs for building facilities for areas 800,900 and 1000 were factored according to their respective process floor areas versus the total process floor area. These direct costs were then treated to the same multipliers as the total building facilities cost to bring the direct cost to total capital cost.

The building facilities costs included the following:

- Earthwork
- Concrete
- Steel
- Architectural
- HVAC
- Mechanical Equipment
- Piping
- Electrical
- Instrumentation
- Mechanical Utility Pad
- Electrical Utility Pad

Multiplier Factors

The following multipliers were used to expand the direct cost level to total cost:

Process Controls	20% of direct labor and materials
Indirect Field Costs	28% of direct labor for material 75% of direct labor for labor
Contractor's OH&P	5% of materials and subcontracts 15% of labor
Construction Management	10% of contractor's field cost
Architect/Engineer Costs	25% of total field cost
Project Management	6% of subtotal cost

Contingency 25% of total cost

Escalation 4.4% per year

Operations and Maintenance

Trial Burn

A 2 week trial burn period was estimated for the thermal process equipment in order to establish emission parameters, and to determine the optimum processing rate for the equipment.

Startup Cost

Based on the Waste Management Facilities Cost Information Report produced by Idaho National Engineering Laboratory, October 1992, a factor of 100% of the annual operating cost was used for the cost of starting up the process equipment. This factor includes all temporary equipment and utilities, consumable supplies and labor to establish the operability of the process.

Annual Operating Cost

Based on the MWTP study, the annual operating cycle was stated to be 31 weeks per year at 24 hours per day. This varies from most processing facilities which operate at 24 hours per day for 50 weeks per year. We have therefore extended the working year to 50 weeks to conform to industry standards. Operating cost includes direct and indirect labor and material, consumable supplies, utilities, and miscellaneous supplies including personnel protection.

Annual Maintenance Cost

Based on the Waste Management facilities Cost Information report, the cost of annual maintenance was factored at 17% for labor, 7% for materials, and 1% for supervision & expenses against the fixed equipment cost.

Annual Waste Disposal Cost

Based on information received for disposal at Chemnuclear, Barnwell, South Carolina, and transportation from a generic central US facility, the cost of sampling, transport and disposal was calculated for the output from the MWTP flowsheet of 16,953 Kg/week, over the 50 week operating period.

Contingency

Based on the level of estimate development, a contingency of 25% of all costs excluding fixed capital was added to the total life cycle cost. This amount is intended to reflect the confidence of the scope, design and cost data used in this study.

Discounted Cash Outflow

The discounted cash outflow table is intended to normalize the study by bringing all cost back to a common point of reference. The 3.7% Real Discount Rate is extrapolated from the Office of Management and Budget (OMB) Circular A-94, Dated October 29, 1992 (Appendix "C") which indicates the discount rates for Cost-Effectiveness, Lease Purchase, and related analysis. We have used the real discount rate as directed by the OMB circular which basically removes the effect of expected or actual inflation for cost-effectiveness analysis. We have also used the mid-year discount factor rather than the end-of-year discount factor as the cash outflows tend to occur in a steady stream throughout the project life cycle.

ASSUMPTIONS AND EXCLUSIONS

The cost effectiveness analysis is based on the following assumptions:

The cost data presented in the Bechtel MWTP study had been checked for reasonableness and accuracy within the range of a conceptual study estimate.

It is assumed for life cycle comparison that although the construction cost will be averaged over a minimum 5 year construction period, all capital construction costs occur in year "0".

An allowance of 20% of the fixed equipment cost is required every 5 years for replacement of major process equipment items not covered by the annual maintenance account.

The building facilities size and cost data is within the historic range of accuracy for a mixed low level waste treatment facility for the DOE complex.

The capital cost multiplier factors are within the standard American Association of Cost Engineers range of multipliers for capital cost development for process and utility industries.

The cost estimate has centered on the Thermal Treatment (Area 800) and the Final Forms Treatment (Area 900) in order to reflect the major cost differential as determined by the size and cost of redundant equipment. No comparison has been made at the front end of the flowsheet between the baseline and alternative flowsheets to determine what, if any,

impact to the life cycle cost is created by the changes in retrieval, handling, segregation and characterization that may occur when the PAF is introduced into the system.

The estimates for waste disposal are considered to be identical in both cases. No allowance has been made for any potential cost saving that may be realized from the ability of the alternative flowsheet to establish a volume reduction or to dispose of a vitrified or cast metal waste product at a lower cost disposal facility than that needed for the baseline flowsheet.

It is assumed that the Nevada test Site will not be available for long term storage and disposal of the final waste form, and that the Barnwell facility (or some other higher priced facility) will need to be used.

The waste characterization cost for the alternative flowsheet could increase significantly if it is necessary to establish the contents of every drum prior to incineration. It is therefore assumed that there will be no significant difference between the baseline and alternative characterization costs.

It is assumed that the plasma melting operation will not cause any migration from the low level classification of the final waste form, and that the waste form will still meet all disposal criteria for low level waste.

The life cycle cost analysis is sensitive to the availability and receiving costs of a permitted disposal facility. Any significant increase in the cost of transportation and disposal may result in any apparent advantage being minimized or reversed.

The removal of the glass melting facility in the final forms treatment area for the alternative flowsheet changes the criteria from that proposed in the SAIC draft flowsheet of April 02, 1993. It is our understanding that this furnace is not now required due to the anticipated ability of the slag from the plasma furnace to pass any tests for long term disposal criteria. Should this not be the case, then the capital cost for the alternative flowsheet would be increased significantly due to the approximately 3 to 1 ratio for slag to metal from the plasma furnace.

This study assumes the availability of sufficient low cost electric power, water, natural gas and rail/road transportation adjacent to the waste processing facility.

The following costs are excluded from this study:

Salvage costs for process and building equipment at the end of the useful project life cycle.

Decontamination and Decommissioning of process facilities and buildings.

Down-time and consumable costs associated with electrode replacement for the PAF.

Land and land improvements.

Roads and utility lines to the plantsite.

Research and Development costs.

CONCLUSION

As indicated by the attached life cycle cost comparisons, the alternative flowsheet shows a distinct economic advantage over the baseline flowsheet.

The major differences are in process equipment and annual maintenance. Due to the fact that the annual maintenance is factored from the fixed capital equipment, the difference in the cost of the process equipment is the main driver for the large cost delta over the 20 year life cycle.

It should be noted however that this cost analysis is extremely sensitive to the cost of the fixed capital equipment, which is susceptible to large cost swings. Should it be necessary to add back the glass melting process into the final forms treatment, this would add approximately \$11 million to the fixed capital cost, which, when added to the annual maintenance cost would reflect in a \$70 million cost increase over the life cycle of the facility. It can be seen from this example that any major cost changes in the fixed capital cost will be multiplied by a factor of 6 at the total life cycle cost level.

In summary, we would comment that this study indicates that further engineering development work be carried out on the flowsheet definition for both cases. If we can improve the confidence of the flowsheet, capital cost estimates, and therefore the life cycle cost estimate, we would be better able to draw a more definitive conclusion from the data. At this point, there is sufficient uncertainty in both the baseline and alternative flowsheets to require that additional process development be carried out before we can prepare a more definitive cost analysis.

LIFE CYCLE COST COMPARISON
BETWEEN
BASELINE AND ALTERNATIVE FLOWSHEETS

**ALTERNATIVE THERMAL TREATMENT
LIFE CYCLE COST ESTIMATE**

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
ALTERNATIVE THERMAL TREATMENT - BASED ON CHEMICAL TECHNOLOGY DIVISION PLASMA FURNACE												
DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (Sus x 1,000)											
	MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST											
FILENAME: PLASMA1R.XLS	YEAR 0	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	YEAR 6	YEAR 7	YEAR 8	YEAR 9	YEAR 10	
	1.0000	0.9820	0.9470	0.9131	0.8704	0.8370	0.8048	0.7739	0.7441	0.7155	0.6880	
Total Startup	\$9,362	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
ANNUAL OPERATING												
Process Engineers - 2		\$518	\$500	\$482	\$460	\$442	\$425	\$409	\$393	\$378	\$363	
Technician (Operator) - 6		\$1,827	\$1,761	\$1,698	\$1,619	\$1,557	\$1,497	\$1,439	\$1,384	\$1,331	\$1,280	
Operating Engineer - 4		\$1,096	\$1,057	\$1,019	\$971	\$934	\$898	\$864	\$830	\$798	\$768	
Rad. Technician - 2		\$377	\$364	\$351	\$334	\$321	\$309	\$297	\$286	\$275	\$264	
Laborer - 6		\$1,367	\$1,318	\$1,271	\$1,212	\$1,165	\$1,120	\$1,077	\$1,036	\$996	\$958	
Oversight Engineer - 2		\$837	\$807	\$778	\$742	\$713	\$686	\$659	\$634	\$610	\$586	
Electric Power		\$825	\$795	\$767	\$731	\$703	\$676	\$650	\$625	\$601	\$578	
Natural Gas		\$795	\$767	\$740	\$705	\$678	\$652	\$627	\$603	\$580	\$557	
Lubricants		\$61	\$59	\$57	\$54	\$52	\$50	\$48	\$47	\$45	\$43	
Compressed Gas		\$614	\$592	\$571	\$544	\$523	\$503	\$484	\$465	\$447	\$430	
Raw Materials & Chemical Additives		\$491	\$474	\$457	\$435	\$419	\$402	\$387	\$372	\$358	\$344	
Miscellaneous Supplies (Rad. Protection)		\$295	\$284	\$274	\$261	\$251	\$241	\$232	\$223	\$215	\$206	
Supervision & Expenses		\$91	\$88	\$85	\$81	\$78	\$75	\$72	\$69	\$66	\$64	
Total Annual Operating	\$0	\$9,194	\$8,866	\$8,549	\$8,149	\$7,836	\$7,535	\$7,245	\$6,966	\$6,699	\$6,441	
ANNUAL MAINTENANCE												
Maintenance Labor		\$1,975	\$1,904	\$1,836	\$1,750	\$1,683	\$1,618	\$1,556	\$1,496	\$1,439	\$1,383	
Maintenance Materials		\$813	\$784	\$756	\$721	\$693	\$666	\$641	\$616	\$592	\$570	
Supervision & Expenses		\$28	\$27	\$26	\$25	\$24	\$23	\$22	\$21	\$20	\$20	
Total Annual Maintenance	\$0	\$2,816	\$2,715	\$2,618	\$2,496	\$2,400	\$2,308	\$2,219	\$2,133	\$2,051	\$1,973	
ANNUAL WASTE DISPOSAL												
Containers (55 gallon drum)		\$45	\$43	\$42	\$40	\$38	\$37	\$36	\$34	\$33	\$32	
Assay & Storage		\$13	\$12	\$12	\$11	\$11	\$10	\$10	\$10	\$9	\$9	
Transportation		\$26	\$25	\$24	\$23	\$22	\$21	\$20	\$19	\$19	\$18	

		MIXED WASTE INTEGRATED PROGRAM											
19-Oct-93		PLASMA ARC COST EFFECTIVENESS STUDY											
		ALTERNATIVE THERMAL TREATMENT - BASED ON CHEMICAL TECHNOLOGY DIVISION PLASMA FURNACE											
	DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR										(Sus x 1,000)	
		MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST											
FILENAME: PLASMA1R.XLS	YEAR 0	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	YEAR 6	YEAR 7	YEAR 8	YEAR 9	YEAR 10		
	1.0000	0.9820	0.9470	0.9131	0.8704	0.8370	0.8048	0.7739	0.7441	0.7155	0.6880		
Long Term Disposal & Storage		\$3,329	\$3,210	\$3,095	\$2,951	\$2,837	\$2,728	\$2,624	\$2,522	\$2,426	\$2,332		
Supervision & Expenses		\$34	\$33	\$32	\$30	\$29	\$28	\$27	\$26	\$25	\$24		
Total Annual Waste Disposal	\$0	\$3,446	\$3,324	\$3,205	\$3,055	\$2,938	\$2,825	\$2,716	\$2,612	\$2,511	\$2,415		
Subtotal	\$70,576	\$15,456	\$14,905	\$14,371	\$13,699	\$15,154	\$12,667	\$12,180	\$11,711	\$11,261	\$12,456		
Contingency @ 25%	\$2,412	\$3,864	\$3,726	\$3,593	\$3,425	\$3,293	\$3,167	\$3,045	\$2,928	\$2,815	\$2,707		
Annual Life Cycle cost	\$72,987	\$19,320	\$18,631	\$17,964	\$17,124	\$18,447	\$15,834	\$15,226	\$14,639	\$14,077	\$15,163		

		MIXED WASTE INTEGRATED PROGRAM										
19-Oct-93		PLASMA ARC COST EFFECTIVENESS STUDY										
		ALTERNATIVE THERMAL TREATMENT - BASED ON CHEMICAL TECHNOLOGY DIVISION PLASMA FURNACE										
	DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$ us x 1,000)										
		MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST										
FILENAME: PLASMA1R.XLS		YEAR 11	YEAR 12	YEAR 13	YEAR 14	YEAR 15	YEAR 16	YEAR 17	YEAR 18	YEAR 19	YEAR 20	TOTAL
		0.6615	0.6361	0.6116	0.5881	0.5655	0.5437	0.5228	0.5027	0.4834	0.4648	
	Total Startup	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$9,362
	ANNUAL OPERATING											
	Process Engineers - 2	\$349	\$336	\$323	\$311	\$299	\$287	\$276	\$265	\$255	\$245	\$7,316
	Technician (Operator) - 6	\$1,230	\$1,183	\$1,138	\$1,094	\$1,052	\$1,011	\$972	\$935	\$899	\$865	\$25,772
	Operating Engineer - 4	\$738	\$710	\$683	\$656	\$631	\$607	\$583	\$561	\$539	\$519	\$15,463
	Rad. Technician - 2	\$254	\$244	\$235	\$226	\$217	\$209	\$201	\$193	\$186	\$178	\$5,321
	Laborer - 6	\$921	\$885	\$851	\$819	\$787	\$757	\$728	\$700	\$673	\$647	\$19,288
	Oversight Engineer - 2	\$564	\$542	\$521	\$501	\$482	\$463	\$445	\$428	\$412	\$396	\$11,805
	Electric Power	\$556	\$534	\$514	\$494	\$475	\$457	\$439	\$422	\$406	\$390	\$11,639
	Natural Gas	\$536	\$515	\$495	\$476	\$458	\$440	\$423	\$407	\$392	\$376	\$11,223
	Lubricants	\$41	\$40	\$38	\$37	\$35	\$34	\$33	\$31	\$30	\$29	\$866
	Compressed Gas	\$413	\$398	\$382	\$368	\$353	\$340	\$327	\$314	\$302	\$291	\$8,660
	Raw Materials & Chemical Additives	\$331	\$318	\$306	\$294	\$283	\$272	\$261	\$251	\$242	\$232	\$6,928
	Miscellaneous Supplies (Rad. Protection)	\$198	\$191	\$183	\$176	\$170	\$163	\$157	\$151	\$145	\$139	\$4,157
	Supervision & Expenses	\$61	\$59	\$57	\$55	\$52	\$50	\$48	\$47	\$45	\$43	\$1,284
	Total Annual Operating	\$6,193	\$5,955	\$5,726	\$5,506	\$5,294	\$5,090	\$4,895	\$4,706	\$4,526	\$4,352	\$129,723
	ANNUAL MAINTENANCE											
	Maintenance Labor	\$1,330	\$1,279	\$1,230	\$1,183	\$1,137	\$1,093	\$1,051	\$1,011	\$972	\$935	\$27,862
	Maintenance Materials	\$548	\$527	\$506	\$487	\$468	\$450	\$433	\$416	\$400	\$385	\$11,473
	Supervision & Expenses	\$19	\$18	\$17	\$17	\$16	\$15	\$15	\$14	\$14	\$13	\$393
	Total Annual Maintenance	\$1,897	\$1,824	\$1,754	\$1,686	\$1,621	\$1,559	\$1,499	\$1,441	\$1,386	\$1,333	\$39,728
	ANNUAL WASTE DISPOSAL											
	Containers (55 gallon drum)	\$30	\$29	\$28	\$27	\$26	\$25	\$24	\$23	\$22	\$21	\$636

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
ALTERNATIVE THERMAL TREATMENT - BASED ON CHEMICAL TECHNOLOGY DIVISION PLASMA FURNACE												
DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$ us x 1,000)											TOTAL
	MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST											
FILENAME: PLASMA1R.XLS	YEAR 11	YEAR 12	YEAR 13	YEAR 14	YEAR 15	YEAR 16	YEAR 17	YEAR 18	YEAR 19	YEAR 20		
	0.6615	0.6361	0.6116	0.5881	0.5655	0.5437	0.5228	0.5027	0.4834	0.4648		
Assay & Storage	\$9	\$8	\$8	\$8	\$7	\$7	\$7	\$7	\$6	\$6	\$180	
Transportation	\$17	\$17	\$16	\$15	\$15	\$14	\$14	\$13	\$13	\$12	\$360	
Long Term Disposal & Storage	\$2,242	\$2,156	\$2,073	\$1,994	\$1,917	\$1,843	\$1,772	\$1,704	\$1,639	\$1,576	\$46,972	
Supervision & Expenses	\$23	\$22	\$21	\$20	\$20	\$19	\$18	\$17	\$17	\$16	\$481	
Total Annual Waste Disposal	\$2,322	\$2,232	\$2,147	\$2,064	\$1,985	\$1,908	\$1,835	\$1,764	\$1,697	\$1,631	\$48,630	
Subtotal	\$10,411	\$10,012	\$9,626	\$9,256	\$10,238	\$8,557	\$8,228	\$7,912	\$7,608	\$8,415	\$294,701	
Contingency @ 25%	\$2,603	\$2,503	\$2,407	\$2,314	\$2,225	\$2,139	\$2,057	\$1,978	\$1,902	\$1,829	\$56,932	
Annual Life Cycle cost	\$13,014	\$12,515	\$12,033	\$11,570	\$12,463	\$10,697	\$10,285	\$9,890	\$9,510	\$10,244	\$351,633	

**BASELINE THERMAL TREATMENT
COST ESTIMATE SUMMARY**

MIXED WASTE INTEGRATED PROGRAM						
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY					
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE						
	DESCRIPTION			CALCULATIONS		\$ US x 1,000
FILENAME: PLASMA2R.XLS						
BUILDING FACILITIES						
	Building facilities - Area 800			See attached estimate		\$29,610
	Building facilities - Area 900			See attached estimate		\$11,599
	Building facilities - Area 1000			See attached estimate		\$21,367
	Total Building Facilities					\$62,577
PROCESS EQUIPMENT						
	Thermal Treatment - Area 800			See attached estimate		\$26,670
	Final Forms Treatment - Area 900			See attached estimate		\$23,618
	Support Operations equipment - Area 800			See attached estimate		\$4,103
	Support Operations equipment - Area 900			See attached estimate		\$3,585
	Total Process Equipment					\$57,976
TRIAL BURN						
	Process Engineer - 2			2 x 10 Days @ 24 hrs/day @ \$88/hr		\$42
	Technician (Operator) - 3			3 x 10 Days @ 24 hrs/day @ \$62/hr		\$45
	Operating Engineer - 3			3 x 10 Days @ 24 hrs/day @ \$62/hr		\$45
	Rad. Technician - 2			2 x 10 Days @ 24 hrs/day @ \$64/hr		\$31
	Laborer - 4			4 x 10 Days @ 24 hrs/day @ \$58/hr		\$56
	Oversight Engineer - 1			1 x 10 days @ 24 hrs/day @ \$142/hr		\$34
	Consumable Material			10 days @ \$3,000/day		\$30
	Supervision and Expenses			1% of Labor & Materials		\$3
	Total Trial Burn					\$285
STARTUP						
	Startup Cost			100% of 1 years operating cost		\$12,447

MIXED WASTE INTEGRATED PROGRAM						
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY					
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE						
	DESCRIPTION	CALCULATIONS				\$ US x 1,000
FILENAME: PLASMA2R.XLS						
Total Startup						\$12,447
ANNUAL OPERATING						
	Process Engineers - 2	2 x 250 days @ 24 hrs/day @ \$88/hr				\$1,056
	Technician (Operator) - 6	6 x 250 days @ 24 hrs/day @ \$62/hr				\$2,232
	Operating Engineer - 4	4 x 250 days @ 24 hrs/day @ \$62/hr				\$1,488
	Rad. Technician - 2	2 x 250 days @ 24 hrs/day @ \$64/hr				\$768
	Laborer - 6	6 x 250 days @ 24 hrs/day @ \$58/hr				\$2,088
	Oversight Engineer - 2	2 x 250 days @ 24 hrs/day @ \$142/hr				\$1,704
	Electric Power	250 days @ 24 hrs/day @ 1500 kw/hr @ \$0.035/kwhr.				\$315
	Natural Gas	250 days @ 24 hrs/day @ 37 therm/hr @ \$5.00/therm.				\$1,110
	Lubricants	250 days @ \$250/day				\$63
	Compressed Gas	250 days @ \$1500/day				\$375
	Raw Materials & Chemical Additives	250 days @ \$3000/day				\$750
	Miscellaneous Supplies (Rad. Protection)	250 days @ \$1500/day				\$375
	Supervision & Expenses	1% of Labor & Material				\$123
Total Annual Operating						\$12,447
ANNUAL MAINTENANCE						
	Maintenance Labor	17% of fixed equipment cost				\$9,856
	Maintenance Materials	7% of fixed equipment cost				\$4,058
	Supervision & Expenses	1% of Labor & Materials				\$139
Total Annual Maintenance						\$14,053
ANNUAL WASTE DISPOSAL						
	Containers (55 gallon drum)	16,953 kg/week x 50 weeks @ 75 kg/cf @ 7.4 cf/bbl = 1530 bbl x \$30/bbl				\$46
	Assay & Storage	Sampling 1 bbl in 60 = 26 samples @ \$500 each				\$13

**BASELINE THERMAL TREATMENT
LIFE CYCLE COST ESTIMATE**

MIXED WASTE INTEGRATED PROGRAM											
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY										
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE											
DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$us x 1,000)										
	MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST										
FILENAME: PLASMA2R.XLS	YEAR 0	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	YEAR 6	YEAR 7	YEAR 8	YEAR 9	YEAR 10
	1.0000	0.9820	0.9470	0.9131	0.8704	0.8370	0.8048	0.7739	0.7441	0.7155	0.6880
BUILDING FACILITIES											
Building facilities - Area 800	\$29,610										
Building facilities - Area 900	\$11,599										
Building facilities - Area 1000	\$21,367										
Total Building Facilities	\$62,577	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
PROCESS EQUIPMENT											
Thermal Treatment - Area 800	\$26,670					\$4,465					\$3,670
Final Forms Treatment - Area 900	\$23,618					\$3,954					\$3,250
Support Operations equipment - Area 800	\$4,103					\$687					\$565
Support Operations equipment - Area 900	\$3,585					\$600					\$493
Total Process Equipment	\$57,976	\$0	\$0	\$0	\$0	\$9,705	\$0	\$0	\$0	\$0	\$7,978
TRIAL BURN											
Process Engineer - 2	\$42										
Technician (Operator) - 3	\$45										
Operating Engineer - 3	\$45										
Rad. Technician - 2	\$31										
Laborer - 4	\$56										
Oversight Engineer - 1	\$34										
Consumable Material	\$30										
Supervision and Expenses	\$3										
Total Trial Burn	\$285	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
STARTUP											
Startup Cost	\$12,447										
Total Startup	\$12,447	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE												
DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$us x 1,000)											
	MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST											
FILENAME: PLASMA2R.XLS	YEAR 0	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	YEAR 6	YEAR 7	YEAR 8	YEAR 9	YEAR 10	
	1.0000	0.9820	0.9470	0.9131	0.8704	0.8370	0.8048	0.7739	0.7441	0.7155	0.6880	
ANNUAL OPERATING												
Process Engineers - 2		\$1,037	\$1,000	\$964	\$919	\$884	\$850	\$817	\$786	\$756	\$727	
Technician (Operator) - 6		\$2,192	\$2,114	\$2,038	\$1,943	\$1,868	\$1,796	\$1,727	\$1,661	\$1,597	\$1,536	
Operating Engineer - 4		\$1,461	\$1,409	\$1,359	\$1,295	\$1,245	\$1,198	\$1,152	\$1,107	\$1,065	\$1,024	
Rad. Technician - 2		\$754	\$727	\$701	\$668	\$643	\$618	\$594	\$571	\$550	\$528	
Laborer - 6		\$2,050	\$1,977	\$1,907	\$1,817	\$1,748	\$1,680	\$1,616	\$1,554	\$1,494	\$1,437	
Oversight Engineer - 2		\$1,673	\$1,614	\$1,556	\$1,483	\$1,426	\$1,371	\$1,319	\$1,268	\$1,219	\$1,172	
Electric Power		\$309	\$298	\$288	\$274	\$264	\$254	\$244	\$234	\$225	\$217	
Natural Gas		\$1,090	\$1,051	\$1,014	\$966	\$929	\$893	\$859	\$826	\$794	\$764	
Lubricants		\$61	\$59	\$57	\$54	\$52	\$50	\$48	\$47	\$45	\$43	
Compressed Gas		\$368	\$355	\$342	\$326	\$314	\$302	\$290	\$279	\$268	\$258	
Raw Materials & Chemical Additives		\$737	\$710	\$685	\$653	\$628	\$604	\$580	\$558	\$537	\$516	
Miscellaneous Supplies (Rad. Protection)		\$368	\$355	\$342	\$326	\$314	\$302	\$290	\$279	\$268	\$258	
Supervision & Expenses		\$121	\$117	\$113	\$107	\$103	\$99	\$95	\$92	\$88	\$85	
Total Annual Operating	\$0	\$12,223	\$11,787	\$11,365	\$10,834	\$10,418	\$10,017	\$9,633	\$9,262	\$8,906	\$8,563	
ANNUAL MAINTENANCE												
Maintenance Labor		\$9,679	\$9,334	\$8,999	\$8,579	\$8,249	\$7,932	\$7,628	\$7,334	\$7,052	\$6,781	
Maintenance Materials		\$3,985	\$3,843	\$3,706	\$3,532	\$3,397	\$3,266	\$3,141	\$3,020	\$2,904	\$2,792	
Supervision & Expenses		\$137	\$132	\$127	\$121	\$116	\$112	\$108	\$104	\$100	\$96	
Total Annual Maintenance	\$0	\$13,800	\$13,309	\$12,832	\$12,232	\$11,763	\$11,310	\$10,876	\$10,457	\$10,055	\$9,669	
ANNUAL WASTE DISPOSAL												
Containers (55 gallon drum)		\$45	\$43	\$42	\$40	\$38	\$37	\$36	\$34	\$33	\$32	
Assay & Storage		\$13	\$12	\$12	\$11	\$11	\$10	\$10	\$10	\$9	\$9	
Transportation		\$26	\$25	\$24	\$23	\$22	\$21	\$20	\$19	\$19	\$18	
Long Term Disposal & Storage		\$3,329	\$3,210	\$3,095	\$2,951	\$2,837	\$2,728	\$2,624	\$2,522	\$2,426	\$2,332	
Supervision & Expenses		\$34	\$33	\$32	\$30	\$29	\$28	\$27	\$26	\$25	\$24	
Total Annual Waste Disposal	\$0	\$3,446	\$3,324	\$3,205	\$3,055	\$2,938	\$2,825	\$2,716	\$2,612	\$2,511	\$2,415	

		MIXED WASTE INTEGRATED PROGRAM										
19-Oct-93		PLASMA ARC COST EFFECTIVENESS STUDY										
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE												
	DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR										(Us x 1,000)
		MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST										
FILENAME: PLASMA2R.XLS		YEAR 0	YEAR 1	YEAR 2	YEAR 3	YEAR 4	YEAR 5	YEAR 6	YEAR 7	YEAR 8	YEAR 9	YEAR 10
		1.0000	0.9820	0.9470	0.9131	0.8704	0.8370	0.8048	0.7739	0.7441	0.7155	0.6880
Subtotal		\$133,284	\$29,470	\$28,419	\$27,402	\$26,121	\$34,823	\$24,152	\$23,225	\$22,330	\$21,472	\$28,624
Contingency @ 25%		\$3,183	\$7,367	\$7,105	\$6,850	\$6,530	\$6,280	\$6,038	\$5,806	\$5,583	\$5,368	\$5,162
Annual Life Cycle cost		\$136,467	\$36,837	\$35,524	\$34,252	\$32,651	\$41,103	\$30,190	\$29,031	\$27,913	\$26,840	\$33,786

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE												
DESCRIPTION				DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$ us x 1,000)								
MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST												
FILENAME: PLASMA2R.XLS	YEAR 11	YEAR 12	YEAR 13	YEAR 14	YEAR 15	YEAR 16	YEAR 17	YEAR 18	YEAR 19	YEAR 20	TOTAL	
	0.6615	0.6361	0.6116	0.5881	0.5655	0.5437	0.5228	0.5027	0.4834	0.4648		
BUILDING FACILITIES												
Building facilities - Area 800												\$29,610
Building facilities - Area 900												\$11,599
Building facilities - Area 1000												\$21,367
Total Building Facilities	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$62,577
PROCESS EQUIPMENT												
Thermal Treatment - Area 800					\$3,016						\$2,479	\$40,300
Final Forms Treatment - Area 900					\$2,671						\$2,196	\$35,689
Support Operations equipment - Area 800					\$464						\$381	\$6,200
Support Operations equipment - Area 900					\$405						\$333	\$5,417
Total Process Equipment	\$0	\$0	\$0	\$0	\$6,557	\$0	\$0	\$0	\$0	\$0	\$5,389	\$87,605
TRIAL BURN												
Process Engineer - 2												\$42
Technician (Operator) - 3												\$45
Operating Engineer - 3												\$45
Rad. Technician - 2												\$31
Laborer - 4												\$56
Oversight Engineer - 1												\$34
Consumable Material												\$30
Supervision and Expenses												\$3
Total Trial Burn	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$285
STARTUP												
Startup Cost												\$12,447

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE												
DESCRIPTION	DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$ us x 1,000)											TOTAL
	MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST											
FILENAME: PLASMA2R.XLS	YEAR 11	YEAR 12	YEAR 13	YEAR 14	YEAR 15	YEAR 16	YEAR 17	YEAR 18	YEAR 19	YEAR 20		
	0.6615	0.6361	0.6116	0.5881	0.5655	0.5437	0.5228	0.5027	0.4834	0.4648		
Total Startup	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$12,447
ANNUAL OPERATING												
Process Engineers - 2	\$699	\$672	\$646	\$621	\$597	\$574	\$552	\$531	\$510	\$491	\$491	\$14,632
Technician (Operator) - 6	\$1,476	\$1,420	\$1,365	\$1,313	\$1,262	\$1,214	\$1,167	\$1,122	\$1,079	\$1,037	\$1,037	\$30,927
Operating Engineer - 4	\$984	\$947	\$910	\$875	\$841	\$809	\$778	\$748	\$719	\$692	\$692	\$20,618
Rad. Technician - 2	\$508	\$489	\$470	\$452	\$434	\$418	\$402	\$386	\$371	\$357	\$357	\$10,641
Laborer - 6	\$1,381	\$1,328	\$1,277	\$1,228	\$1,181	\$1,135	\$1,092	\$1,050	\$1,009	\$971	\$971	\$28,931
Oversight Engineer - 2	\$1,127	\$1,084	\$1,042	\$1,002	\$964	\$926	\$891	\$857	\$824	\$792	\$792	\$23,611
Electric Power	\$208	\$200	\$193	\$185	\$178	\$171	\$165	\$158	\$152	\$146	\$146	\$4,365
Natural Gas	\$734	\$706	\$679	\$653	\$628	\$604	\$580	\$558	\$537	\$516	\$516	\$15,380
Lubricants	\$41	\$40	\$38	\$37	\$35	\$34	\$33	\$31	\$30	\$29	\$29	\$866
Compressed Gas	\$248	\$239	\$229	\$221	\$212	\$204	\$196	\$189	\$181	\$174	\$174	\$5,196
Raw Materials & Chemical Additives	\$496	\$477	\$459	\$441	\$424	\$408	\$392	\$377	\$363	\$349	\$349	\$10,392
Miscellaneous Supplies (Rad. Protection)	\$248	\$239	\$229	\$221	\$212	\$204	\$196	\$189	\$181	\$174	\$174	\$5,196
Supervision & Expenses	\$82	\$78	\$75	\$72	\$70	\$67	\$64	\$62	\$60	\$57	\$57	\$1,708
Total Annual Operating	\$8,234	\$7,917	\$7,612	\$7,320	\$7,039	\$6,767	\$6,507	\$6,257	\$6,017	\$5,785	\$5,785	\$172,462
ANNUAL MAINTENANCE												
Maintenance Labor	\$6,520	\$6,269	\$6,028	\$5,796	\$5,574	\$5,359	\$5,153	\$4,955	\$4,764	\$4,581	\$4,581	\$136,564
Maintenance Materials	\$2,685	\$2,582	\$2,482	\$2,387	\$2,295	\$2,207	\$2,122	\$2,040	\$1,962	\$1,886	\$1,886	\$56,232
Supervision & Expenses	\$92	\$89	\$85	\$82	\$79	\$76	\$73	\$70	\$67	\$65	\$65	\$1,928
Total Annual Maintenance	\$9,296	\$8,939	\$8,595	\$8,265	\$7,947	\$7,641	\$7,347	\$7,065	\$6,793	\$6,532	\$6,532	\$194,724
ANNUAL WASTE DISPOSAL												
Containers (55 gallon drum)	\$30	\$29	\$28	\$27	\$26	\$25	\$24	\$23	\$22	\$21	\$21	\$636
Assay & Storage	\$9	\$8	\$8	\$8	\$7	\$7	\$7	\$7	\$6	\$6	\$6	\$180

MIXED WASTE INTEGRATED PROGRAM												
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY											
BASELINE THERMAL TREATMENT - BASED ON BECHTEL MWTP DESIGN STUDY & COST ESTIMATE												
DESCRIPTION				DISCOUNTED CASH OUTFLOW BY FISCAL YEAR (\$ us x 1,000)								
				MIDYEAR DISCOUNT FACTORS AT 3.7% REAL INTEREST								
FILENAME: PLASMA2R.XLS	YEAR 11	YEAR 12	YEAR 13	YEAR 14	YEAR 15	YEAR 16	YEAR 17	YEAR 18	YEAR 19	YEAR 20	TOTAL	
	0.6615	0.6361	0.6116	0.5881	0.5655	0.5437	0.5228	0.5027	0.4834	0.4648		
Transportation	\$17	\$17	\$16	\$15	\$15	\$14	\$14	\$13	\$13	\$12	\$360	
Long Term Disposal & Storage	\$2,242	\$2,156	\$2,073	\$1,994	\$1,917	\$1,843	\$1,772	\$1,704	\$1,639	\$1,576	\$46,972	
Supervision & Expenses	\$23	\$22	\$21	\$20	\$20	\$19	\$18	\$17	\$17	\$16	\$481	
Total Annual Waste Disposal	\$2,322	\$2,232	\$2,147	\$2,064	\$1,985	\$1,908	\$1,835	\$1,764	\$1,697	\$1,631	\$48,630	
Subtotal	\$19,851	\$19,089	\$18,354	\$17,649	\$23,528	\$16,316	\$15,689	\$15,086	\$14,507	\$19,338	\$578,730	
Contingency @ 25%	\$4,963	\$4,772	\$4,589	\$4,412	\$4,243	\$4,079	\$3,922	\$3,771	\$3,627	\$3,487	\$107,137	
Annual Life Cycle cost	\$24,814	\$23,862	\$22,943	\$22,061	\$27,770	\$20,395	\$19,611	\$18,857	\$18,133	\$22,825	\$685,867	

**BASELINE THERMAL TREATMENT
CAPITAL COST ESTIMATE**

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE						
FILENAME: PLASMA5.XLW													
OCTOBER 19, 1993													
UNIT FACTORS													
COSTS													
ITEM	DESCRIPTION	UNIT	QTY	LABOR MHRS	LABOR RATE	MAT	EQUIP	S/C	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
THERMAL TREATMENT EQUIPMENT - AREA 800													
370	LOW RESIDUE THERMAL TREATMENT	EA	1	950	27.4		\$270,000		\$26,030	\$0	\$270,000	\$0	\$296,030
CONTROLLED AIR OXIDATION FURNACE													
380	CONC ORGANIC THERMAL TREATMENT	EA	1	500	\$27.40		\$50,000		\$13,700	\$0	\$50,000	\$0	\$63,700
OXIDATION FURNACE BURNER													
470	HIGH RESIDUE THERMAL TREATMENT	EA	1	1,210	\$27.40		\$168,000		\$33,154	\$0	\$168,000	\$0	\$201,154
ROTARY KILN INCINERATOR													
375	HEAVY ORGANIC THERMAL TREATMENT	EA	1	1,030	\$27.40		\$55,000		\$28,222	\$0	\$55,000	\$0	\$83,222
CAR BOTTOM FURNACE													
670	GLASS MELTER	EA	1	12,000	\$27.40	\$0	\$5,304,000		\$328,800	\$0	\$5,304,000	\$0	\$5,632,800
CERAMIC JOULE MELTER W/SPOUT													
770	FERROUS MELT/SLAG	EA	1	1,290	\$27.40		\$1,531,000		\$35,346	\$0	\$1,531,000	\$0	\$1,566,346
CERAMIC ELECTRIC HEATED MELTER W/SPOUT													
775	NON-FERROUS MELT/SLAG	EA	1	1,290	\$27.40		\$1,531,000		\$35,346	\$0	\$1,531,000	\$0	\$1,566,346
CERAMIC ELECTRIC HEATED MELTER W/SPOUT													
480	SECONDARY COMBUSTION	EA	1	1,624	\$27.40		\$263,250		\$44,498	\$0	\$263,250	\$0	\$307,748
REFRACTORY LINED COMBUSTION CHAMBER													
490	OFF-GAS TREATMENT SYSTEM	EA	1	678	\$27.40		\$67,200		\$18,577	\$0	\$67,200	\$0	\$85,777
MISCELLANEOUS EQUIPMENT													
560	MERCURY BAKEOUT	EA	1	1,250	\$27.40		\$120,000		\$34,250	\$0	\$120,000	\$0	\$154,250
ELECTRIC REFRACTORY LINED FURNACE													
562	MERCURY SEPARATION	EA	1	300	\$27.40		\$20,000		\$8,220	\$0	\$20,000	\$0	\$28,220
MERCURY ABSORPTION PACKED BED													
565	MERCURY CONDENSATION	EA	1	844	\$27.40		\$119,500		\$23,126	\$0	\$119,500	\$0	\$142,626
CONDENSER, REACTOR, PUMP, TANK ETC.													
570	NON-METALLICS DRYING	EA	1	2,120	\$27.40		\$238,000		\$58,088	\$0	\$238,000	\$0	\$296,088

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE						
FILENAME: PLASMAS.XLW													
OCTOBER 19, 1993													
UNIT FACTORS													
COSTS													
ITEM	DESCRIPTION	UNIT	QTY	LABOR MHRS	LABOR RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
	ELECTRIC HEATED TUNNEL KILN												
	SUBTOTAL DIRECT EQUIPMENT COST			25,086	\$27.40		9,736,950	0	687,356	0	9,736,950	0	10,424,306
	PROCESS CONTROLS @ 20%	LOT	1	5,017	\$27.40		\$1,947,390		\$137,471	\$0	\$1,947,390	\$0	\$2,084,861
	TOTAL DIRECT EQUIPMENT COST	LOT		30,103			\$11,684,340		\$824,828	\$0	\$11,684,340	\$0	\$12,509,168
	INDIRECT FIELD COST @ 28/75%								\$618,621		\$230,952	\$0	\$849,573
	SUBTOTAL CONTRACTORS FIELD COST								\$1,443,448	\$0	\$11,915,292	\$0	\$13,358,740
	CONTRACTORS O/H & P @ 5/15%								\$216,517	\$0	\$595,765	\$0	\$812,282
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$1,659,966	\$0	\$12,511,056	\$0	\$14,171,022
	CONSTRUCTION MANAGEMENT @ 10%												\$1,417,102
	SUBTOTAL FIELD COSTS - W/CM												\$15,588,124
	ENGINEERING, DESIGN, INSPECT @ 25%												\$3,897,031
	SUBTOTAL - W/ED&I												\$19,485,155
	PROJECT MANAGEMENT @ 6%												\$1,169,109
	SUBTOTAL - W/PM												\$20,654,265
	CONTINGENCY @ 25%												\$5,163,566
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$851,988
	TOTAL THERMAL TREATMENT EQUIPMENT - AREA 800												\$26,669,819
	FINAL FORMS TREATMENT EQUIPMENT - AREA 900												
195	LEAD POLYMER ENCAPSULATION	EA	1	452	\$27.4		\$308,800		\$12,385	\$0	\$308,800	\$0	\$321,185
295	GLASS MELTER	EA	1	6544	\$27.4		\$5,219,000		\$179,306	\$0	\$5,219,000	\$0	\$5,398,306
395	MERCURY POLYMER SOLIDIFICATION	EA	1	36	\$27.4		\$15,700		\$986	\$0	\$15,700	\$0	\$16,686
585	MERCURY DISTILLATION	EA	1	92	\$27.4		\$24,000		\$2,521	\$0	\$24,000	\$0	\$26,521
695	SUPER COMPACTION	EA	1	9004	\$27.4		\$3,170,600		\$246,710	\$0	\$3,170,600	\$0	\$3,417,310
795	GROUTING	EA	1	1144	\$27.4		\$182,400		\$31,346	\$0	\$182,400	\$0	\$213,746
	SUBTOTAL DIRECT EQUIPMENT COST			17,272	\$27.40	\$0	\$8,920,500	\$0	\$473,253	\$0	\$8,920,500	\$0	\$9,393,753

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET										CAPITAL COST ESTIMATE			
FILENAME: PLASMA5.XLW													
OCTOBER 19, 1993													
UNIT FACTORS											COSTS		
ITEM	DESCRIPTION	UNIT	QTY	LABOR MHR	LABOR RATE	MAT	EQUIP	S/C	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
	PROCESS CONTROLS @ 20%	LOT	1	3,454	\$27.40		\$1,784,100		\$94,651	\$0	\$1,784,100	\$0	\$1,878,751
	TOTAL DIRECT EQUIPMENT COST	LOT		20,726			\$10,704,600		\$567,903	\$0	\$10,704,600	\$0	\$11,272,503
	INDIRECT FIELD COST @ 28/75%								\$425,928		\$159,013	\$0	\$584,940
	SUBTOTAL CONTRACTORS FIELD COST								\$993,831	\$0	\$10,863,613	\$0	\$11,857,444
	CONTRACTORS OH & P @ 5/15%								\$149,075	\$0	\$543,181	\$0	\$692,255
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$1,142,906	\$0	\$11,406,794	\$0	\$12,549,699
	CONSTRUCTION MANAGEMENT @ 10%												\$1,254,970
	SUBTOTAL FIELD COSTS - W/CM												\$13,804,669
	ENGINEERING, DESIGN, INSPECT @ 25%												\$3,451,167
	SUBTOTAL - W/ED&I												\$17,255,836
	PROJECT MANAGEMENT @ 6%												\$1,035,350
	SUBTOTAL - W/PM												\$18,291,186
	CONTINGENCY @ 25%												\$4,572,797
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$754,511
	TOTAL FINAL FORMS TREATMENT EQUIPMENT - AREA 900												\$23,618,494
	SUPPORT OPERATIONS EQUIPMENT - AREA 800												
100	FEED AND SEGREGATION HANDLING								\$0	\$51,264			\$51,264
280	SECOND STAGE GAS HANDLING								\$7,804	\$142,400			\$150,204
290	OFF-GAS CLEAN-UP								\$11,159	\$127,733			\$138,892
650	ATMOSPHERIC PROTECTION								\$35,584	\$226,416			\$262,000
900	CONTAINER DECONTAMINATION								\$35,428	\$210,166			\$245,594
1100	LOW LEVEL WASTE HANDLING								\$18,323	\$112,286			\$130,609
1200	PACKAGE ASSAY								\$11,549	\$365,968			\$377,517
1300	ANALYTICAL LABORATORY								\$19,509	\$142,400			\$161,909
1400	RECORD KEEPING								\$7,804	\$28,480			\$36,284

MIXED WASTE INTEGRATED PROGRAM															
PLASMA ARC COST EFFECTIVENESS STUDY															
BASELINE THERMAL FLOWSHEET										CAPITAL COST ESTIMATE					
FILENAME: PLASMA5.XLW															
OCTOBER 19, 1993															
										UNIT FACTORS			COSTS		
										LABOR	LABOR				
ITEM	DESCRIPTION	UNIT	QTY	MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL		
	SUBTOTAL DIRECT SUPPORT OPERATIONS COST								\$147,159	\$1,407,114			\$1,554,272		
	PROCESS CONTROLS @ 20%								\$29,432	\$281,423			\$310,855		
	TOTAL DIRECT SUPPORT OPERATIONS COST								\$176,590	\$1,688,536	\$0	\$0	\$1,865,126		
	INDIRECT FIELD COST @ 28/75%								\$132,443	\$49,445	\$0	\$0	\$181,888		
	SUBTOTAL CONTRACTORS FIELD COST								\$309,033	\$1,737,982	\$0	\$0	\$2,047,015		
	CONTRACTORS O/H & P @ 15/5/5%								\$46,355	\$86,899	\$0	\$0	\$133,254		
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$355,388	\$1,824,881	\$0	\$0	\$2,180,269		
	CONSTRUCTION MANAGEMENT @ 10%												\$218,027		
	SUBTOTAL FIELD COSTS - W/CM												\$2,398,296		
	ENGINEERING, DESIGN, INSPECT @ 25%												\$599,574		
	SUBTOTAL - W/ED&I												\$2,997,870		
	PROJECT MANAGEMENT @ 6%												\$179,872		
	SUBTOTAL - W/PM												\$3,177,742		
	CONTINGENCY @ 25%												\$794,436		
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$131,082		
	TOTAL SUPPORT OPERATIONS EQUIPMENT - AREA 800												\$4,103,260		
	SUPPORT OPERATIONS EQUIPMENT - AREA 900														
100	FEED AND SEGREGATION HANDLING								\$0	\$44,784			\$44,784		
280	SECOND STAGE GAS HANDLING								\$6,817	\$124,400			\$131,217		
290	OFF-GAS CLEAN-UP								\$9,748	\$111,587			\$121,335		
650	ATMOSPHERIC PROTECTION								\$31,086	\$197,796			\$228,882		
900	CONTAINER DECONTAMINATION								\$30,950	\$183,600			\$214,550		
1100	LOW LEVEL WASTE HANDLING								\$16,007	\$98,093			\$114,100		
1200	PACKAGE ASSAY								\$10,089	\$319,708			\$329,797		
1300	ANALYTICAL LABORATORY								\$17,043	\$124,400			\$141,443		

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET													
CAPITAL COST ESTIMATE													
FILENAME: PLASMA5.XLW													
OCTOBER 19, 1993													
UNIT FACTORS													
COSTS													
ITEM	DESCRIPTION	UNIT	QTY	LABOR MHRS	LABOR RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
1400	RECORD KEEPING								\$6,817	\$24,880			\$31,697
	SUBTOTAL DIRECT SUPPORT OPERATIONS COST								\$128,557	\$1,229,248			\$1,357,805
	PROCESS CONTROLS @ 20%								\$25,711	\$245,850			\$271,561
	TOTAL DIRECT SUPPORT OPERATIONS COST								\$154,268	\$1,475,098	\$0	\$0	\$1,629,366
	INDIRECT FIELD COST @ 28/75%								\$115,701	\$43,195	\$0	\$0	\$158,896
	SUBTOTAL CONTRACTORS FIELD COST								\$269,970	\$1,518,293	\$0	\$0	\$1,788,262
	CONTRACTORS O/H & P @ 15/5/5%								\$40,495	\$75,915	\$0	\$0	\$116,410
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$310,465	\$1,594,207	\$0	\$0	\$1,904,673
	CONSTRUCTION MANAGEMENT @ 10%												\$190,467
	SUBTOTAL FIELD COSTS - W/CM												\$2,095,141
	ENGINEERING, DESIGN, INSPECT @ 25%												\$523,785
	SUBTOTAL - W/ED&I												\$2,618,926
	PROJECT MANAGEMENT @ 6%												\$157,136
	SUBTOTAL - W/PM												\$2,776,061
	CONTINGENCY @ 25%												\$694,015
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$114,513
	TOTAL SUPPORT OPERATIONS EQUIPMENT - ARBA 900												\$3,584,589
	BUILDING FACILITIES - ARBA 800												
	EARTHWORK								\$43,776	\$3,819			\$47,595
	CONCRETE								\$1,171,255	\$699,521			\$1,870,776
	STEEL								\$90,486	\$200,978			\$291,464
	ARCHITECTURAL								\$8,903	\$12,731	\$640,681		\$682,315
	HVAC								\$415,636	\$1,901,236		\$173,880	\$2,490,752
	MECHANICAL EQUIPMENT								\$14,153	\$344,355			\$358,508
	PIPING								\$906,081	\$994,664	\$124,740		\$2,025,485

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET													
CAPITAL COST ESTIMATE													
FILENAME: PLASMAS.XLW													
OCTOBER 19, 1993													
UNIT FACTORS													
COSTS													
ITEM	DESCRIPTION	UNIT	QTY	LABOR M/RS	LABOR RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
	ELECTRICAL								\$870,943	\$626,250			\$1,497,193
	INSTRUMENTATION								\$148,683	\$1,329,988			\$1,478,671
	MECHANICAL UTILITY PAD								\$74,365	\$154,910			\$229,275
	ELECTRICAL UTILITY PAD								\$42,304	\$62,145		\$874	\$105,323
	TOTAL DIRECT BUILDING FACILITIES COST								\$3,786,586	\$6,330,596	\$0	\$960,175	\$11,077,357
	INDIRECT FIELD COST @ 28/75%								\$2,839,940	\$1,060,244	\$0	\$0	\$3,900,184
	SUBTOTAL CONTRACTORS FIELD COST								\$6,626,526	\$7,390,840	\$0	\$960,175	\$14,977,540
	CONTRACTORS O/H & P @ 15/5/5%								\$993,979	\$369,542	\$0	\$48,009	\$1,411,530
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$7,620,504	\$7,760,382	\$0	\$1,008,183	\$16,389,070
	CONSTRUCTION MANAGEMENT @ 10%												\$1,638,907
	SUBTOTAL FIELD COSTS - W/CM												\$18,027,977
	ENGINEERING, DESIGN, INSPECT @ 20%												\$3,605,595
	SUBTOTAL - W/ED&I												\$21,633,572
	PROJECT MANAGEMENT @ 6%												\$1,298,014
	SUBTOTAL - W/PM												\$22,931,586
	CONTINGENCY @ 25%												\$5,732,897
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$945,928
	TOTAL BUILDING FACILITIES - AREA 800												\$29,610,411
	BUILDING FACILITIES - AREA 900												
	EARTHWORK								\$17,179	\$1,499			\$18,678
	CONCRETE								\$459,635	\$274,512			\$734,147
	STEEL								\$35,509	\$78,870			\$114,379
	ARCHITECTURAL								\$3,494	\$4,996		\$251,688	\$260,178
	HVAC								\$163,108	\$746,101		\$66,240	\$975,449
	MECHANICAL EQUIPMENT								\$5,554	\$135,135			\$140,689

MIXED WASTE INTEGRATED PROGRAM															
PLASMA ARC COST EFFECTIVENESS STUDY															
BASELINE THERMAL FLOWSHEET										CAPITAL COST ESTIMATE					
FILENAME: PLASMAS.XLW															
OCTOBER 19, 1993															
										UNIT FACTORS				COSTS	
										LABOR	LABOR				
ITEM	DESCRIPTION	UNIT	QTY	MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL		
	PIPING								\$355,573	\$390,335		\$47,520	\$793,428		
	ELECTRICAL								\$341,784	\$245,759			\$587,543		
	INSTUMENTATION								\$58,347	\$521,926			\$580,273		
	MECHANICAL UTILITY PAD								\$29,183	\$60,791			\$89,974		
	ELECTRICAL UTILITY PAD								\$16,601	\$24,387		\$333	\$41,321		
	TOTAL DIRECT BUILDING FACILITIES COST								\$1,485,967	\$2,484,312	\$0	\$365,781	\$4,336,060		
	INDIRECT FIELD COST @ 28/75%								\$1,114,475	\$416,071	\$0	\$0	\$1,530,546		
	SUBTOTAL CONTRACTORS FIELD COST								\$2,600,442	\$2,900,383	\$0	\$365,781	\$5,866,606		
	CONTRACTORS O/H & P @ 15/5/5%								\$390,066	\$145,019	\$0	\$18,289	\$553,375		
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$2,990,509	\$3,045,402	\$0	\$384,070	\$6,419,980		
	CONSTRUCTION MANAGEMENT @ 10%												\$641,998		
	SUBTOTAL FIELD COSTS - W/CM												\$7,061,978		
	ENGINEERING, DESIGN, INSPECT @ 20%												\$1,412,396		
	SUBTOTAL - W/ED&I												\$8,474,374		
	PROJECT MANAGEMENT @ 6%												\$508,462		
	SUBTOTAL - W/PM												\$8,982,836		
	CONTINGENCY @ 25%												\$2,245,709		
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$370,542		
	TOTAL BUILDING FACILITIES - AREA 900												\$11,599,088		
	BUILDING FACILITIES - AREA 1000														
	EARTHWORK								\$31,611	\$2,758			\$34,369		
	CONCRETE								\$845,750	\$505,116			\$1,350,866		
	STEEL								\$65,339	\$145,124			\$210,463		
	ARCHITECTURAL								\$6,429	\$9,193		\$471,915	\$487,537		
	HVAC								\$300,127	\$1,372,862		\$124,200	\$1,797,189		

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
BASELINE THERMAL FLOWSHEET						CAPITAL COST ESTIMATE							
FILENAME: PLASMAS.XLW													
OCTOBER 19, 1993													
				UNIT FACTORS					COSTS				
				LABOR	LABOR								
ITEM	DESCRIPTION	UNIT	QTY	MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
	MECHANICAL EQUIPMENT								\$10,220	\$248,655			\$258,875
	PIPING								\$654,272	\$718,236		\$89,100	\$1,461,608
	ELECTRICAL								\$628,899	\$452,209			\$1,081,108
	INSTRUMENTATION								\$107,362	\$960,370			\$1,067,732
	MECHANICAL UTILITY PAD								\$53,698	\$111,859			\$165,557
	ELECTRICAL UTILITY PAD								\$30,547	\$44,874		\$624	\$76,045
	TOTAL DIRECT BUILDING FACILITIES COST								\$2,734,252	\$4,571,255	\$0	\$685,839	\$7,991,346
	INDIRECT FIELD COST @ 28/75%								\$2,050,689	\$765,591	\$0	\$0	\$2,816,280
	SUBTOTAL CONTRACTORS FIELD COST								\$4,784,941	\$5,336,846	\$0	\$685,839	\$10,807,626
	CONTRACTORS O/H & P @ 15/5/5%								\$717,741	\$266,842	\$0	\$34,292	\$1,018,875
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$5,502,682	\$5,603,688	\$0	\$720,131	\$11,826,501
	CONSTRUCTION MANAGEMENT @ 10%												\$1,182,650
	SUBTOTAL FIELD COSTS - W/CM												\$13,009,151
	ENGINEERING, DESIGN, INSPECT @ 20%												\$2,601,830
	SUBTOTAL - W/ED&I												\$15,610,981
	PROJECT MANAGEMENT @ 6%												\$936,659
	SUBTOTAL - W/PM												\$16,547,641
	CONTINGENCY @ 25%												\$4,136,910
	ESCALATION FROM 1ST QTR FY92 TO 4TH QTR FY93												\$682,590
	TOTAL BUILDING FACILITIES - AREA 1000												\$21,367,141
NOTES													
THERMAL TREATMENT EQUIPMENT COSTS - AREA 800													
THE PURCHASED EQUIPMENT COSTS ARE TAKEN FROM THE BECHTEL MWTP BASELINE PROCESS EQUIPMENT LIST, PAGES 9/14 & 10/14, DATED 9/3/92.													

35

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

BASELINE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA5.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS						COSTS			
				MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
LABOR COSTS FOR INSTALLING THE EQUIPMENT ARE TAKEN FROM THE BECHTEL MWTP BASELINE COST SUMMARY FOR THE THERMAL TREATMENT AREA 800.													
FIELD INDIRECTS, CONTRACTORS OH&P, CONSTRUCTION MANAGEMENT, A/E COSTS AND CONTINGENCY ARE CALCULATED													
USING THE SAME FACTORS AS THE BECHTEL COST ESTIMATE.													
ESCALATION IS ADDED TO BRING THE COSTS FORWARD FROM THE 1ST QUARTER OF FY92, TO THE 4TH QUARTER OF FY93.													
THE ESCALATION FACTORS WERE TAKEN FROM THE DRI - ANTICIPATED ECONOMIC ESCALATION RATES FOR DOE CONSTRUCTION PROJECTS.													
UPDATED FEBRUARY 1993, AS SUPPLIED BY THE ENGINEERING FACILITIES DIVISION OF LOS ALAMOS NATIONAL LABORATORY.													
<u>FINAL FORMS TREATMENT EQUIPMENT COSTS - AREA 900</u>													
THE PURCHASED EQUIPMENT COSTS ARE TAKEN FROM THE BECHTEL MWTP BASELINE PROCESS EQUIPMENT LIST, PAGES 9/14 & 10/14, DATED 9/3/92.													
LABOR COSTS FOR INSTALLING THE EQUIPMENT ARE TAKEN FROM THE BECHTEL MWTP BASELINE COST SUMMARY FOR THE FINAL FORMS TREATMENT AREA 900.													
FIELD INDIRECTS, CONTRACTORS OH&P, CONSTRUCTION MANAGEMENT, A/E COSTS AND CONTINGENCY ARE CALCULATED													
USING THE SAME FACTORS AS THE BECHTEL COST ESTIMATE.													
ESCALATION IS ADDED TO BRING THE COSTS FORWARD FROM THE 1ST QUARTER OF FY92, TO THE 4TH QUARTER OF FY93.													
THE ESCALATION FACTORS WERE TAKEN FROM THE DRI - ANTICIPATED ECONOMIC ESCALATION RATES FOR DOE CONSTRUCTION PROJECTS.													
UPDATED FEBRUARY 1993, AS SUPPLIED BY THE ENGINEERING FACILITIES DIVISION OF LOS ALAMOS NATIONAL LABORATORY.													
<u>SUPPORT OPERATIONS COSTS - AREA 800</u>													
THE DIRECT COSTS FOR SUPPORT OPERATIONS WERE CALCULATED FROM THE DIRECT RATIO OF EQUIPMENT COSTS FOR THE THERMAL TREATMENT, AREA 800													
AGAINST THE TOTAL DIRECT COST FOR ALL PROCESS EQUIPMENT. THIS PERCENTAGE APPROXIMATED 28.5%.													
ALL INDIRECT COSTS WERE ALLOCATED USING THE BECHTEL RATIOS, AND ESCALATION WAS ADDED AS INDICATED IN THE THE PROCESS EQUIPMENT SECTION.													
<u>SUPPORT OPERATIONS COSTS - AREA 900</u>													
THE DIRECT COSTS FOR SUPPORT OPERATIONS WERE CALCULATED FROM THE DIRECT RATIO OF EQUIPMENT COSTS FOR THE FINAL FORMS TREATMENT AREA 900													
AGAINST THE TOTAL DIRECT COST FOR ALL PROCESS EQUIPMENT. THIS PERCENTAGE APPROXIMATED 24.9%.													
ALL INDIRECT COSTS WERE ALLOCATED USING THE BECHTEL RATIOS, AND ESCALATION WAS ADDED AS INDICATED IN THE THE PROCESS EQUIPMENT SECTION.													

MIXED WASTE INTEGRATED PROGRAM														
PLASMA ARC COST EFFECTIVENESS STUDY														
BASELINE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE							
FILENAME: PLASMA5.XLW														
OCTOBER 19, 1993														
				UNIT FACTORS					COSTS					
				LABOR	LABOR									
ITEM	DESCRIPTION	UNIT	QTY	MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL	
BUILDING FACILITIES COSTS - AREA 800														
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING														
THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 20.9% OF THE BUILDING FLOOR AREA (13,500 SF/64,700SF).														
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.														
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.														
BUILDING FACILITIES COSTS - AREA 900														
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING														
THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 8.2% OF THE BUILDING FLOOR AREA (5,300SF/64,700SF).														
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.														
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.														
BUILDING FACILITIES COSTS - AREA 1000														
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING														
THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 15.1% OF THE BUILDING FLOOR AREA (9,750SF/64,700SF).														
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.														
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.														

**ALTERNATIVE THERMAL TREATMENT
COST ESTIMATE SUMMARY**

MIXED WASTE INTEGRATED PROGRAM			
19-Oct-93	PLASMA ARC COST EFFECTIVENESS STUDY		
ALTERNATIVE THERMAL TREATMENT - BASED ON CHEMICAL TECHNOLOGY DIVISION PLASMA FURNACE			
DESCRIPTION	CALCULATIONS		\$ US x 1,000
FILENAME: PLASMA1R.XLS			
Total Startup			\$9,362
ANNUAL OPERATING			
Process Engineers - 2	1 x 250 days @ 24 hrs/day @ \$88/hr		\$528
Technician (Operator) - 6	5 x 250 days @ 24 hrs/day @ \$62/hr		\$1,860
Operating Engineer - 4	3 x 250 days @ 24 hrs/day @ \$62/hr		\$1,116
Rad. Technician - 2	1 x 250 days @ 24 hrs/day @ \$64/hr		\$384
Laborer - 6	4 x 250 days @ 24 hrs/day @ \$58/hr		\$1,392
Oversight Engineer - 2	1 x 250 days @ 24 hrs/day @ \$142/hr		\$852
Electric Power	250 days @ 24 hrs/day @ 4000 kw/hr @ \$0.035/kwhr.		\$840
Natural Gas	250 days @ 24 hrs/day @ 27 therm/hr @ \$5.00/therm.		\$810
Lubricants	250 days @ \$250/day		\$63
Compressed Gas	250 days @ \$2500/day		\$625
Raw Materials & Chemical Additives	250 days @ \$2000/day		\$500
Miscellaneous Supplies (Rad. Protection)	250 days @ \$1200/day		\$300
Supervision & Expenses	1% of Labor & Material		\$93
Total Annual Operating			\$9,362
ANNUAL MAINTENANCE			
Maintenance Labor	17% of fixed equipment cost		\$2,011
Maintenance Materials	7% of fixed equipment cost		\$828
Supervision & Expenses	1% of Labor & Materials		\$28
Total Annual Maintenance			\$2,867
ANNUAL WASTE DISPOSAL			
Containers (55 gallon drum)	16,953 kg/week x 50 weeks @ 75 kg/cf @ 7.4 cf/bbl = 1530 bbl x \$30/bbl		\$46

**ALTERNATIVE THERMAL TREATMENT
CAPITAL COST ESTIMATE**

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

ALTERNATIVE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA6.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS					COSTS					
				LABOR	LABOR	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL	
				MHRS	RATE									
THERMAL TREATMENT EQUIPMENT - AREA 800														
100	DRUM FEED SYSTEM - 700 LB/HR 4' OD X 10' LONG HORIZONTAL CYLINDER	EA	1	1,277	\$27.40		\$350,900			\$35,000	\$0	\$350,000	\$0	\$385,000
110	PRIMARY COMBUSTION CHAMBER 8' OD X 8' HIGH REFRACTORY LINED/WATER JACKETED STEEL VESSEL.	EA	1	5,474	\$27.40		\$1,500,000			\$150,000	\$0	\$1,500,000	\$0	\$1,650,000
380	CONC ORGANIC THERMAL TREATMENT OXIDATION FURNACE BURNER	EA	1	500	\$27.40		50000			\$13,700	\$0	\$50,000	\$0	\$63,700
480	SECONDARY COMBUSTION REFRACTORY LINED COMBUSTION CHAMBER	EA	1	1,624	\$27.40		\$263,250			\$44,498	\$0	\$263,250	\$0	\$307,748
490	OFF-GAS TREATMENT MISCELLANEOUS EQUIPMENT	EA	1	678	\$27.40		\$67,200			\$18,577	\$0	\$67,200	\$0	\$85,777
560	MERCURY BAKEOUT ELECTRIC REFRACTORY LINED FURNACE	EA	1	1,250	\$27.40		\$120,000			\$34,250	\$0	\$120,000	\$0	\$154,250
562	MERCURY SEPARATION MERCURY ABSORPTION PACKED BED	EA	1	300	\$27.40		\$20,000			\$8,220	\$0	\$20,000	\$0	\$28,220
565	MERCURY CONDENSATION CONDENSED, REACTOR, PUMP, TANK, ETC.	EA	1	844	\$27.40		\$119,500			\$23,126	\$0	\$119,500	\$0	\$142,626
	SUBTOTAL EQUIPMENT			11,948	\$27.40		2,489,950	0		327,370	0	2,489,950	0	\$2,817,320
	PROCESS CONTROLS @ 20%	LOT	1	2,390	\$27.40		\$497,990			\$65,474	\$0	\$497,990	\$0	\$563,464
	TOTAL DIRECT EQUIPMENT COST	LOT		14,337			\$2,987,940			\$392,844	\$0	\$2,987,940	\$0	\$3,380,784
	INDIRECT FIELD COST @ 28/75%									\$294,633		\$109,996	\$0	\$404,630
	TOTAL CONTRACTORS FIELD COST									\$687,478	\$0	\$3,097,936	\$0	\$3,785,414
	CONTRACTORS O/H & P @ 5/15%									\$103,122	\$0	\$154,897	\$0	\$258,018
	TOTAL CONTRACTORS FIELD COST									\$790,600	\$0	\$3,252,833	\$0	\$4,043,433
	CONSTRUCTION MANAGEMENT @ 10%													\$404,343
	TOTAL FIELD COSTS													\$4,447,776
	ENGINEERING, DESIGN, INSPECT @ 25%													\$1,111,944
	SUBTOTAL													\$5,599,720
	PROJECT MANAGEMENT @ 6%													\$333,583

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
ALTERNATIVE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE						
FILENAME: PLASMA6.XLW													
OCTOBER 19, 1993													
				UNIT FACTORS						COSTS			
				LABOR	LABOR								
ITEM	DESCRIPTION	UNIT	QTY	MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
SUBTOTAL													\$5,893,303
CONTINGENCY @ 25%													\$1,473,326
ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93													\$243,099
TOTAL THERMAL TREATMENT EQUIPMENT - AREA 800													\$7,609,728
FINAL FORMS TREATMENT EQUIPMENT - AREA 900													
195	LEAD POLYMER ENCAPSULATION	EA	1	452	\$27.4		\$308,800		\$12,385	\$0	\$308,800	\$0	\$321,185
395	MERCURY POLYMER SOLIDIFICATION	EA	1	36	\$27.4		\$15,700		\$986	\$0	\$15,700	\$0	\$16,686
585	MERCURY DISTILLATION	EA	1	92	\$27.4		\$24,000		\$2,521	\$0	\$24,000	\$0	\$26,521
SUBTOTAL DIRECT EQUIPMENT COST				580	\$27.40	\$0	\$348,500	\$0	\$15,892	\$0	\$348,500	\$0	\$364,392
PROCESS CONTROLS @ 20%		LOT	1	116	\$27.70		\$69,700		\$3,213	\$0	\$69,700	\$0	\$72,913
TOTAL DIRECT EQUIPMENT COST				LOT	696		\$418,200		\$19,105	\$0	\$418,200	\$0	\$437,305
INDIRECT FIELD COST @ 28/75%									\$14,329		\$5,349	\$0	\$19,678
SUBTOTAL CONTRACTORS FIELD COST									\$33,434	\$0	\$423,549	\$0	\$456,984
CONTRACTORS O/H & P @ 5/15%									\$5,015	\$0	\$21,177	\$0	\$26,193
TOTAL CONTRACTORS FIELD COST - W/MARKUP									\$38,449	\$0	\$444,727	\$0	\$483,176
CONSTRUCTION MANAGEMENT @ 10%													\$48,318
SUBTOTAL FIELD COSTS - W/CM													\$531,494
ENGINEERING, DESIGN, INSPECT @ 25%													\$132,873
SUBTOTAL - W/ED&I													\$664,367
PROJECT MANAGEMENT @ 6%													\$39,862
SUBTOTAL - W/PM													\$704,229
CONTINGENCY @ 25%													\$176,057
ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93													\$29,049
TOTAL FINAL FORMS TREATMENT EQUIPMENT - AREA 900													\$909,336
SUPPORT OPERATIONS EQUIPMENT - AREA 800													
100	FEED AND SEGREGATION HANDLING								\$0	\$36,936			\$36,936
280	SECOND STAGE GAS HANDLING								\$5,622	\$102,600			\$108,222
290	OFF-GAS CLEAN-UP								\$8,040	\$92,032			\$100,072

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

ALTERNATIVE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA6.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS					COSTS				TOTAL	
				LABOR	LABOR	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.		
				MHRS	RATE									
650	ATMOSPHERIC PROTECTION									\$25,639	\$163,134			\$188,773
900	CONTAINER DECONTAMINATION									\$25,526	\$151,426			\$176,952
1100	LOW LEVEL WASTE HANDLING									\$13,202	\$80,903			\$94,104
1200	PACKAGE ASSAY									\$8,321	\$263,682			\$272,003
1300	ANALYTICAL LABORATORY									\$14,056	\$102,600			\$116,656
1400	RECORD KEEPING									\$5,622	\$20,520			\$26,142
	SUBTOTAL DIRECT SUPPORT OPERATIONS COST									\$106,029	\$1,013,833			\$1,119,862
	PROCESS CONTROLS @ 20%									\$21,206	\$202,767			\$223,972
	TOTAL DIRECT SUPPORT OPERATIONS COST									\$127,234	\$1,216,599	\$0	\$0	\$1,343,834
	INDIRECT FIELD COST @ 28/75%									\$95,426	\$35,626	\$0	\$0	\$131,051
	SUBTOTAL CONTRACTORS FIELD COST									\$222,660	\$1,252,225	\$0	\$0	\$1,474,885
	CONTRACTORS OH & P @ 15/5/5%									\$33,399	\$62,611	\$0	\$0	\$96,010
	TOTAL CONTRACTORS FIELD COST - W/MARKUP									\$256,059	\$1,314,836	\$0	\$0	\$1,570,896
	CONSTRUCTION MANAGEMENT @ 10%													\$157,090
	SUBTOTAL FIELD COSTS - W/CM													\$1,727,985
	ENGINEERING, DESIGN, INSPECT @ 25%													\$431,996
	SUBTOTAL - W/ED&I													\$2,159,981
	PROJECT MANAGEMENT @ 6%													\$129,599
	SUBTOTAL - W/PM													\$2,289,580
	CONTINGENCY @ 25%													\$572,395
	ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93													\$94,445
	TOTAL SUPPORT OPERATIONS EQUIPMENT - AREA 800													\$2,956,421
	SUPPORT OPERATIONS EQUIPMENT - AREA 900													
100	FEED AND SEGREGATION HANDLING									\$0	\$4,410			\$4,410
280	SECOND STAGE GAS HANDLING									\$671	\$12,250			\$12,921
290	OFF-GAS CLEAN-UP									\$960	\$10,988			\$11,948
650	ATMOSPHERIC PROTECTION									\$3,061	\$19,478			\$22,539
900	CONTAINER DECONTAMINATION									\$3,048	\$18,080			\$21,127
1100	LOW LEVEL WASTE HANDLING									\$1,576	\$9,659			\$11,236

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
ALTERNATIVE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE						
FILENAME: PLASMA6.XLW													
OCTOBER 19, 1993													
				UNIT FACTORS					COSTS				
ITEM	DESCRIPTION	UNIT	QTY	LABOR MHRS	LABOR RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
1200	PACKAGE ASSAY								\$994	\$31,483			\$32,476
1300	ANALYTICAL LABORATORY								\$1,678	\$12,250			\$13,928
1400	RECORD KEEPING								\$671	\$2,450			\$3,121
	SUBTOTAL DIRECT SUPPORT OPERATIONS COST								\$12,659	\$121,047			\$133,707
	PROCESS CONTROLS @ 20%								\$2,532	\$24,209			\$26,741
	TOTAL DIRECT SUPPORT OPERATIONS COST								\$15,191	\$145,257	\$0	\$0	\$160,448
	INDIRECT FIELD COST @ 28/75%								\$11,393	\$4,254	\$0	\$0	\$15,647
	SUBTOTAL CONTRACTORS FIELD COST								\$26,585	\$149,510	\$0	\$0	\$176,095
	CONTRACTORS OH & P @ 15/5/5%								\$3,988	\$7,476	\$0	\$0	\$11,463
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$30,572	\$156,986	\$0	\$0	\$187,558
	CONSTRUCTION MANAGEMENT @ 10%												\$18,756
	SUBTOTAL FIELD COSTS - WCM												\$206,314
	ENGINEERING, DESIGN, INSPECT @ 25%												\$51,579
	SUBTOTAL - W/ED&I												\$257,893
	PROJECT MANAGEMENT @ 6%												\$15,474
	SUBTOTAL - W/PM												\$273,366
	CONTINGENCY @ 25%												\$68,342
	ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93												\$11,276
	TOTAL SUPPORT OPERATIONS EQUIPMENT - AREA 900												\$352,904
	BUILDING FACILITIES - AREA 800												
	EARTHWORK								\$25,590	\$2,233			\$27,823
	CONCRETE								\$684,682	\$408,920			\$1,093,601
	STEEL								\$52,895	\$117,486			\$170,381
	ARCHITECTURAL								\$5,205	\$7,442	\$383,824		\$396,471
	HVAC								\$242,969	\$1,111,408	\$101,016		\$1,455,393
	MECHANICAL EQUIPMENT								\$8,273	\$201,300			\$209,573
	PIPING								\$529,669	\$581,452	\$72,468		\$1,183,589
	ELECTRICAL								\$509,128	\$366,088			\$875,216
	INSTRUMENTATION								\$86,916	\$777,472			\$864,388

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

ALTERNATIVE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA6.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS					COSTS					
				LABOR	LABOR									
				MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL	
	MECHANICAL UTILITY PAD									43471.528	90555.72			\$134,027
	ELECTRICAL UTILITY PAD									\$24,730	\$36,328		\$308	\$61,365
	TOTAL DIRBCT BUILDING FACILITIES COST									\$2,213,529	\$3,700,684	\$0	\$357,816	\$6,472,029
	INDIRECT FIELD COST @ 28/75%									\$1,660,147	\$619,788	\$0	\$0	\$2,279,935
	SUBTOTAL CONTRACTORS FIELD COST									\$3,873,675	\$4,320,472	\$0	\$357,816	\$8,751,963
	CONTRACTORS OH & P @ 15/5/5%									\$581,051	\$216,024	\$0	\$27,891	\$824,966
	TOTAL CONTRACTORS FIELD COST - W/MARKUP									\$4,454,727	\$4,536,496	\$0	\$385,707	\$9,576,929
	CONSTRUCTION MANAGEMENT @ 10%													\$957,693
	SUBTOTAL FIELD COSTS - W/CM													\$10,534,622
	ENGINEERING, DESIGN, INSPECT @ 20%													\$2,106,924
	SUBTOTAL - W/ED&I													\$12,641,546
	PROJECT MANAGEMENT @ 6%													\$758,493
	SUBTOTAL - W/PM													\$13,400,039
	CONTINGENCY @ 25%													\$3,350,010
	ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93													\$552,752
	TOTAL BUILDING FACILITIES - AREA 800													\$17,302,800
	BUILDING FACILITIES - AREA 900													
	EARTHWORK									\$10,047	\$877			\$10,924
	CONCRETE									\$268,822	\$160,551			\$429,373
	STEEL									\$20,768	\$46,128			\$66,896
	ARCHITECTURAL									\$2,043	\$2,922		\$150,698	\$155,664
	HVAC									\$95,395	\$436,364		\$39,661	\$571,421
	MECHANICAL EQUIPMENT									\$3,248	\$79,035			\$82,283
	PIPING									\$207,960	\$228,291		\$28,453	\$464,704
	ELECTRICAL									199895.4178	143734.488			\$343,630
	INSTRUMENTATION									\$34,125	\$305,254			\$339,379
	MECHANICAL UTILITY PAD									17067.9196	35554.254			\$52,622
	ELECTRICAL UTILITY PAD									\$9,710	\$14,263		\$199	\$24,172
	TOTAL DIRECT BUILDING FACILITIES COST									\$869,082	\$1,452,973	\$0	\$219,011	\$2,541,067

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

ALTERNATIVE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA6.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS					COSTS					
				LABOR	LABOR	MAT	EQUIP	S/C	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL	
				MHRS	RATE									
	INDIRECT FIELD COST @ 28/75%									\$651,812	\$243,343	\$0	\$0	\$895,155
	SUBTOTAL CONTRACTORS FIELD COST									\$1,520,894	\$1,696,316	\$0	\$219,011	\$3,436,222
	CONTRACTORS O/H & P @ 15/5/5%									\$228,134	\$84,816	\$0	\$10,951	\$323,900
	TOTAL CONTRACTORS FIELD COST - W/MARKUP									\$1,749,028	\$1,781,132	\$0	\$229,962	\$3,760,122
	CONSTRUCTION MANAGEMENT @ 10%													\$376,012
	SUBTOTAL FIELD COSTS - W/CM													\$4,136,134
	ENGINEERING, DESIGN, INSPECT @ 20%													\$827,227
	SUBTOTAL - W/ED&I													\$4,963,361
	PROJECT MANAGEMENT @ 6%													\$297,802
	SUBTOTAL - W/PM													\$5,261,163
	CONTINGENCY @ 25%													\$1,315,291
	ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93													\$217,023
	TOTAL BUILDING FACILITIES - AREA 900													\$6,793,477
	BUILDING FACILITIES - AREA 1000													
	EARTHWORK									\$36,980	\$3,226			\$40,207
	CONCRETE									\$989,421	\$590,922			\$1,580,344
	STEEL									\$76,438	\$169,777			\$246,215
	ARCHITECTURAL									\$7,521	\$10,754	\$554,657		\$572,933
	HVAC									\$351,110	\$1,606,075	\$145,976		\$2,103,162
	MECHANICAL EQUIPMENT									\$11,956	\$290,895			\$302,851
	PIPING									\$765,415	\$840,246	\$104,722		\$1,710,383
	ELECTRICAL									735731.9866	\$29026.936			\$1,264,759
	INSTRUMENTATION									\$125,600	\$1,123,511			\$1,249,112
	MECHANICAL UTILITY PAD									62819.9212	130860.438			\$193,680
	ELECTRICAL UTILITY PAD									\$35,737	\$52,497	\$733		\$88,967
	TOTAL DIRECT BUILDING FACILITIES COST									\$3,198,731	\$5,347,792	\$0	\$806,089	\$9,352,612
	INDIRECT FIELD COST @ 28/75%									\$2,399,048	\$895,645	\$0	\$0	\$3,294,693
	SUBTOTAL CONTRACTORS FIELD COST									\$5,597,779	\$6,243,436	\$0	\$806,089	\$12,647,304
	CONTRACTORS O/H & P @ 15/5/5%									\$839,667	\$312,172	\$0	\$40,304	\$1,192,143

MIXED WASTE INTEGRATED PROGRAM													
PLASMA ARC COST EFFECTIVENESS STUDY													
ALTERNATIVE THERMAL FLOWSHEET							CAPITAL COST ESTIMATE						
FILENAME: PLASMA6.XLW													
OCTOBER 19, 1993													
UNIT FACTORS											COSTS		
ITEM	DESCRIPTION	UNIT	QTY	LABOR		MAT	EQUIP	S/C	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
				MHRS	RATE								
	TOTAL CONTRACTORS FIELD COST - W/MARKUP								\$6,437,445	\$6,555,608	\$0	\$846,394	\$13,839,447
	CONSTRUCTION MANAGEMENT @ 10%												\$1,383,945
	SUBTOTAL FIELD COSTS - W/CM												\$15,223,392
	ENGINEERING, DESIGN, INSPECT @ 20%												\$3,044,678
	SUBTOTAL - W/ED&I												\$18,268,070
	PROJECT MANAGEMENT @ 6%												\$1,096,084
	SUBTOTAL - W/PM												\$19,364,155
	CONTINGENCY @ 25%												\$4,841,039
	ESCALATION FROM 1ST QTR FY92 TO 4 QTR FY93												\$798,771
	TOTAL BUILDING FACILITIES - AREA 1000												\$25,003,965
NOTES													
THERMAL TREATMENT EQUIPMENT COSTS - AREA 800													
THE PURCHASED EQUIPMENT COSTS ARE ESTIMATED FROM THE SAIC WASTE MANAGEMENT TECHNOLOGY DIVISION PROCESS EQUIPMENT LIST, DATED 7/20/93.													
LABOR COSTS FOR INSTALLING THE EQUIPMENT ARE FACTORED AT 20% OF THE DIRECT EQUIPMENT COST.													
FIELD INDIRECTS, CONTRACTORS OH&P, CONSTRUCTION MANAGEMENT, A/E COSTS AND CONTINGENCY ARE CALCULATED													
USING THE SAME FACTORS AS THE BECHTEL COST ESTIMATE.													
ESCALATION IS ADDED TO BRING THE COSTS FORWARD FROM THE 1ST QUARTER OF FY92, TO THE 4TH QUARTER OF FY93.													
THE ESCALATION FACTORS WERE TAKEN FROM THE DRI - ANTICIPATED ECONOMIC ESCALATION RATES FOR DOE CONSTRUCTION PROJECTS,													
UPDATED FEBRUARY 1993, AS SUPPLIED BY THE ENGINEERING FACILITIES DIVISION OF LOS ALAMOS NATIONAL LABORATORY.													
FINAL FORMS TREATMENT EQUIPMENT COSTS - AREA 900													
THE PURCHASED EQUIPMENT COSTS ARE TAKEN FROM THE BECHTEL MWTP BASELINE PROCESS EQUIPMENT LIST, PAGES 9/14 & 10/14, DATED 9/3/92.													
LABOR COSTS FOR INSTALLING THE EQUIPMENT ARE TAKEN FROM THE BECHTEL MWTP BASELINE COST SUMMARY FOR THE FINAL FORMS TREATMENT AREA 900													
FIELD INDIRECTS, CONTRACTORS OH&P, CONSTRUCTION MANAGEMENT, A/E COSTS AND CONTINGENCY ARE CALCULATED													
USING THE SAME FACTORS AS THE BECHTEL COST ESTIMATE.													
ESCALATION IS ADDED TO BRING THE COSTS FORWARD FROM THE 1ST QUARTER OF FY92, TO THE 4TH QUARTER OF FY93.													
THE ESCALATION FACTORS WERE TAKEN FROM THE DRI - ANTICIPATED ECONOMIC ESCALATION RATES FOR DOE CONSTRUCTION PROJECTS.													

MIXED WASTE INTEGRATED PROGRAM

PLASMA ARC COST EFFECTIVENESS STUDY

ALTERNATIVE THERMAL FLOWSHEET

CAPITAL COST ESTIMATE

FILENAME: PLASMA6.XLW

OCTOBER 19, 1993

ITEM	DESCRIPTION	UNIT	QTY	UNIT FACTORS						COSTS			
				LABOR	LABOR								
				MHRS	RATE	MAT	EQUIP	SC	LAB	MAT.	EQUIPT.	SUBCONT.	TOTAL
UPDATED FEBRUARY 1993, AS SUPPLIED BY THE ENGINEERING FACILITIES DIVISION OF LOS ALAMOS NATIONAL LABORATORY.													
SUPPORT OPERATIONS COSTS - AREA 800													
THE DIRECT COSTS FOR SUPPORT OPERATIONS WERE CALCULATED FROM THE DIRECT RATIO OF EQUIPMENT COSTS FOR THE THERMAL TREATMENT, AREA 800 AGAINST THE TOTAL DIRECT COST FOR ALL PROCESS EQUIPMENT. THIS PERCENTAGE APPROXIMATED 20.5%.													
ALL INDIRECT COSTS WERE ALLOCATED USING THE BECHTEL RATIOS, AND ESCALATION WAS ADDED AS INDICATED IN THE THE PROCESS EQUIPMENT SECTION.													
SUPPORT OPERATIONS COSTS - AREA 900													
THE DIRECT COSTS FOR SUPPORT OPERATIONS WERE CALCULATED FROM THE DIRECT RATIO OF EQUIPMENT COSTS FOR THE FINAL FORMS TREATMENT AREA 900 AGAINST THE TOTAL DIRECT COST FOR ALL PROCESS EQUIPMENT. THIS PERCENTAGE APPROXIMATED 2.45%.													
ALL INDIRECT COSTS WERE ALLOCATED USING THE BECHTEL RATIOS, AND ESCALATION WAS ADDED AS INDICATED IN THE THE PROCESS EQUIPMENT SECTION.													
BUILDING FACILITIES COSTS - AREA 800													
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 12.2% OF THE BUILDING FLOOR AREA (6,750 SF/55,300SF).													
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.													
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.													
BUILDING FACILITIES COSTS - AREA 900													
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 4.8% OF THE BUILDING FLOOR AREA (2,650SF/55,300SF).													
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.													
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.													
BUILDING FACILITIES COSTS - AREA 1000													
USING THE DATA SHOWN IN THE DIRECT COSTS SECTION OF THE BECHTEL MWTP BASELINE ESTIMATE FOR THE PROCESS BUILDINGS, THE COSTS WERE FACTORED USING THE RATIO OF BUILDING SPACE ALLOCATION FROM TABLE II OF THE BECHTEL STUDY. THIS FACTOR APPROXIMATED 17.1% OF THE BUILDING FLOOR AREA (9,750SF/55,300SF).													
ALL INDIRECT COSTS WERE FACTORED USING THE BECHTEL STUDY FACTORS.													
ESCALATION WAS ADDED IN THE SAME RATIO AS SHOWN IN THE EQUIPMENT COSTS.													

DATE

FILMED

6/27/94

END

4

4

4

4