

ENGINEERING CHANGE NOTICE

Page 1 of 21. ECN **No** 618304Proj.
ECN

2. ECN Category (mark one) Supplemental <input type="checkbox"/> Direct Revision <input checked="" type="checkbox"/> Change ECN <input type="checkbox"/> Temporary <input type="checkbox"/> Standby <input type="checkbox"/> Supersedure <input type="checkbox"/> Cancel/Void <input type="checkbox"/>	3. Originator's Name, Organization, MSIN, and Telephone No. Alois Kostelnik, 71510, R1-17, 373-0788		4. Date November 28, 1994
	5. Project Title/No./Work Order No. Rotary Mode Core Sample Truck ETN-94-0023-E	6. Bldg./Sys./Fac. No. 200 General	7. Impact Level Q
	8. Document Numbers Changed by this ECN (includes sheet no. and rev.) WHC-SD-WM-ATP-111 Rev. 0	9. Related ECN No(s). N/A	10. Related PO No. 404878

11a. Modification Work <input type="checkbox"/> Yes (fill out Blk. 11b) <input checked="" type="checkbox"/> No (NA Blks. 11b, 11c, 11d)	11b. Work Package No. N/A	11c. Modification Work Complete N/A _____ Cog. Engineer Signature & Date	11d. Restored to Original Condition (Temp. or Standby ECN only) N/A _____ Cog. Engineer Signature & Date
---	------------------------------	---	---

12. Description of Change

ETN-94-0023-E

Complete revision of ATP.

13a. Justification (mark one)	Criteria Change <input checked="" type="checkbox"/>	Design Improvement <input type="checkbox"/>	Environmental <input type="checkbox"/>
As-Found <input type="checkbox"/>	Facilitate Const. <input type="checkbox"/>	Const. Error/Omission <input type="checkbox"/>	Design Error/Omission <input type="checkbox"/>

13b. Justification Details

The original ATP was too difficult to follow in an earlier attempt at testing.

14. Distribution (include name, MSIN, and no. of copies)				RELEASE STAMP
AJ Kostelnik	R1-17 (1)	R Robert	G4-05 (1)	OFFICIAL RELEASE 5 BY WHC DATE DEC 01 1994 <i>Sta. 4</i>
AP Mouse	S6-85 (1)	JJ Verberber	S1-57 (1)	
JL Smalley	R1-17 (1)	BR Johns	S6-85 (1)	
CENTRAL FILES	L8-04 (2)	OSTI	L8-07 (2)	

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

ENGINEERING CHANGE NOTICE

Page 2 of 2

1. ECN (use no. from pg. 1)

618304

15. Design Verification Required

☐ Yes☒ No

16. Cost Impact

ENGINEERING

Additional

☐

\$

Savings

☐

\$

CONSTRUCTION

Additional

☐

\$

Savings

☐

\$

17. Schedule Impact (days)

Improvement

☐

Delay

☐

18. Change Impact Review: Indicate the related documents (other than the engineering documents identified on Side 1) that will be affected by the change described in Block 12. Enter the affected document number in Block 19.

SDD/DD	<input type="checkbox"/>	Seismic/Stress Analysis	<input type="checkbox"/>	Tank Calibration Manual	<input type="checkbox"/>
Functional Design Criteria	<input type="checkbox"/>	Stress/Design Report	<input type="checkbox"/>	Health Physics Procedure	<input type="checkbox"/>
Operating Specification	<input type="checkbox"/>	Interface Control Drawing	<input type="checkbox"/>	Spares Multiple Unit Listing	<input type="checkbox"/>
Criticality Specification	<input type="checkbox"/>	Calibration Procedure	<input type="checkbox"/>	Test Procedures/Specification	<input type="checkbox"/>
Conceptual Design Report	<input type="checkbox"/>	Installation Procedure	<input type="checkbox"/>	Component Index	<input type="checkbox"/>
Equipment Spec.	<input type="checkbox"/>	Maintenance Procedure	<input type="checkbox"/>	ASME Coded Item	<input type="checkbox"/>
Const. Spec.	<input type="checkbox"/>	Engineering Procedure	<input type="checkbox"/>	Human Factor Consideration	<input type="checkbox"/>
Procurement Spec.	<input type="checkbox"/>	Operating Instruction	<input type="checkbox"/>	Computer Software	<input type="checkbox"/>
Vendor Information	<input type="checkbox"/>	Operating Procedure	<input type="checkbox"/>	Electric Circuit Schedule	<input type="checkbox"/>
OM Manual	<input type="checkbox"/>	Operational Safety Requirement	<input type="checkbox"/>	ICRS Procedure	<input type="checkbox"/>
FSAR/SAR	<input type="checkbox"/>	IEFD Drawing	<input type="checkbox"/>	Process Control Manual/Plan	<input type="checkbox"/>
Safety Equipment List	<input type="checkbox"/>	Cell Arrangement Drawing	<input type="checkbox"/>	Process Flow Chart	<input type="checkbox"/>
Radiation Work Permit	<input type="checkbox"/>	Essential Material Specification	<input type="checkbox"/>	Purchase Requisition	<input checked="" type="checkbox"/>
Environmental Impact Statement	<input type="checkbox"/>	Fac. Proc. Samp. Schedule	<input type="checkbox"/>		<input type="checkbox"/>
Environmental Report	<input type="checkbox"/>	Inspection Plan	<input type="checkbox"/>		<input type="checkbox"/>
Environmental Permit	<input type="checkbox"/>	Inventory Adjustment Request	<input type="checkbox"/>		<input type="checkbox"/>

19. Other Affected Documents: (NOTE: Documents listed below will not be revised by this ECN.) Signatures below indicate that the signing organization has been notified of other affected documents listed below.

Document Number/Revision

Document Number/Revision

Document Number Revision

Purchase Requisition 404878

20. Approvals

Signature	Date	Signature	Date
OPERATIONS AND ENGINEERING		ARCHITECT-ENGINEER	
Cog Engineer JL Smalley <i>JL Smalley</i>	12/1/94	PE	
Cog. Mgr. RJ Blanchard <i>RJ Blanchard</i>	11/30/94	QA	
QA JJ Verderber <i>JJ Verderber</i>	12/1/94	Safety	
Safety		Design	
Security		Environ.	
Environ.		Other	
Projects/Programs			
Tank Waste Remediation System			
Facilities Operations			
Restoration & Remediation		DEPARTMENT OF ENERGY	
Operations & Support Services		Signature or Letter No.	
IRM			
Other		ADDITIONAL	
Core Sampling Cog Engineer AP Mousel per Telecom <i>AP Mousel</i>	12-1-94		
Design Engineer AJ Kostelnik <i>AJ Kostelnik</i>	11-28-94		

RELEASE AUTHORIZATION

Document Number: WHC-SD-WM-ATP-111, REV.1


Document Title: Rotary Mode Core Sampling Service Trailer Acceptance Test Plan

Release Date: December 1, 1994

**This document was reviewed following the
procedures described in WHC-CM-3-4 and is:**

APPROVED FOR PUBLIC RELEASE

WHC Information Release Administration Specialist:


Kara M. Broz

December 1, 1994

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy. Available in paper copy and microfiche. Printed in the United States of America. Available to the U.S. Department of Energy and its contractors from:

U.S. Department of Energy
Office of Scientific and Technical Information (OSTI)
P.O. Box 62
Oak Ridge, TN 37831
Telephone: (615) 576-8401

Available to the public from:

U.S. Department of Commerce
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Telephone: (703) 487-4650

SUPPORTING DOCUMENT		1. Total Pages <i>89</i> <i>12-1-94</i>
2. Title Rotary Mode Core Sampling Service Trailer Acceptance Test Plan	3. Number WHC-SD-WM-ATP-111	4. Rev No. 1
5. Key Words ETN-94-0023-E Core Sampling, Service Trailer, WHC-S-056, Aluminum Body Corporation, ABC, Purchase Order 404878, Core Sampling Auxiliary Equipment <i>KMB</i>	6. Author Name: Alois J Kostelnik <i>Alois J. Kostelnik</i> Signature Organization/Charge Code 71510 / N4XB1	
7. Abstract <i>12/1/94</i> PUBLIC RELEASE This Acceptance Test Procedure (ATP) will document compliance with the requirements of specification WHC-S-056 Rev.2 including ECNs 608798 and 616386. The equipment being tested is a furniture type trailer with storage cabinets, lighting and HVAC systems installed. The unit was purchased as a Design and Fabrication procurement activity. The ATP be performed by representatives of the Westinghouse Hanford Company with the assistance of the Seller at the Seller's location.		
<p>8. PURPOSE AND USE OF DOCUMENT - This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, direct, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed.</p> <p>PATENT STATUS - This document copy, since it is transmitted in advance of patent clearance, is made available in confidence solely for use in performance of work under contracts with the U.S. Department of Energy. This document is not to be published nor its contents otherwise disseminated or used for purposes other than specified above before patent approval for such release or use has been secured, upon request, from the Patent Counsel, U.S. Department of Energy Field Office, Richland, WA.</p> <p>DISCLAIMER - This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.</p>		<p>10. RELEASE STAMP</p> <div style="border: 1px solid black; padding: 5px; text-align: center;"> OFFICIAL RELEASE 5 BY WHC DATE DEC 01 1994 <i>Sta. 4</i> </div>
9. Impact Level <i>Q</i>		

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DT

[illegible]

TABLE OF CONTENTS

1.0	SCOPE	3
2.0	TEST PERFORMANCE	3
3.0	TEST RECORDS	3
4.0	APPLICABLE DOCUMENTS	3
5.0	INSPECTION and OPERABILITY	4
	TEST EXCEPTIONS	8

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

57

1.0 SCOPE

This Acceptance Test Procedure shall verify the requirements for the fabrication of a Service Trailer as defined in WHC-S-056 are met. The Service Trailer will be used in conjunction with the Rotary Mode Core Sampling Truck.

2.0 TEST PERFORMANCE

Westinghouse Hanford Company (WHC) will complete the following test with the assistance of Aluminum Body Corporation (ABC) personnel. WHC personnel shall perform the inspection portion of the test. All steps will be completed and any exceptions shall be noted on the attached exception sheet along with the resolution. Only one exception shall be listed on an exception sheet. ABC shall resolve all exceptions with the concurrence of WHC.

3.0 TEST RECORDS

The original test record shall be maintained by WHC. Copies of all documents which are referenced during testing which document requirement compliance or exceptions shall be retained as part of the test results.

4.0 APPLICABLE DOCUMENTS

The following documents, form a part of the Basis of Design defined in specification WHC-S-056. Applicable sections of the document referenced shall be considered for acceptance of the finished item.

4.1 Government Documents

49 CFR	Code of Federal Regulations (Federal Motor Carrier Regulations)
29 CFR	Code of Federal Regulations (Occupational Safety and Health Act Standards)

4.2 Non-Government Documents

NFPA 70	National Electrical Code (1993)
---------	---------------------------------

4.3 Any document determined to be a record of an agreement between the buyer and seller may be referenced and a copy shall be included in this acceptance test results.

5.0 INSPECTION and OPERABILITY

- ____ 5.1 The trailer is identified per the manufacturer's standard markings, as a minimum they shall include the manufacturer's name, model number, serial number, empty trailer weight, maximum payload, and date of fabrication. Record the manufacturer name, manufacture date, model and serial numbers of the Trailer.

Manufacturer / Date	Model / Serial

- ____ 5.2 The trailer is a van trailer, (furniture type), in accordance with all applicable OSHA Standards, and 49CFR, Sections 390 through 397.
- ____ 5.3 The external dimensions of the trailer are nominally 33 feet long, 8 feet wide, and 11 feet overall high. The trailer has a drop deck. The upper deck is 8 feet long minimum.
- ____ 5.4 The trailer has a minimum payload capacity of 25,000 lbs.
- ____ 5.5 The trailer is equipped with a 2-1/2 inch king pin set at 30 inches. Off loading front support consists of a manually operated, multi-speed, landing gear with sand pads. Demonstrate operation of each.
- ____ 5.6 The trailer is equipped with running lights, air suspension air brakes and all typical features required for normal road travel and speeds. Demonstrate that brake lights, clearance lights, and turn lights function.
- ____ 5.7 Two (2) manually operated, 2-speed stabilization jacks are mounted on the rear corners. The jacks are for stationary trailer use only and must be retractable higher than the bottom of the wheel rim. Demonstrate operation of each.
- ____ 5.8 Two rear panel type doors, side hinged, providing a total minimum width opening of 90% of the trailer width is provided. The minimum height of the door opening is 7 feet. The edge of the doors and doorway is edged with steel to provide structural reinforcement against minor impact. The locking mechanism is releasable from the inside and outside. Demonstrate door release operation.
- ____ 5.9 One 36 inch wide curbside, solid, door is located near the front of the trailer. The door is right side hinged and slam lockable with inside/outside lock releases. Demonstrate door release operation.

- ____ 5.10 Locks are supplied to lock the trailer doors when not in use.
- ____ 5.11 Lightweight retractable steps and platform extends across the back of the trailer. Removable handrails are incorporated on both sides of the platform and steps. Handrails are 42" high. Demonstrate rear steps and platform can be folded up and anchored to provide for over the road travel.
- ____ 5.12 Steps and platform are provided for the curbside door. Handrails are incorporated on both sides of the steps. Handrails are 42" high. Steps and platform for the curbside door can be fastened to the trailer and are removable. Handrails are removable.
- ____ 5.13 The inside and outside walls and roof are a minimum of 0.040 inch thick, white, prepainted aluminum. The finish is in good condition.
- ____ 5.14 The flooring is commercial grade, steel safety plate, 1/8 inch minimum thickness.
- ____ 5.15 All seams and penetrations of the trailer have been adequately sealed. Verify roof penetrations will not leak when water is present.
- ____ 5.16 The underside of the trailer is undercoated.
- ____ 5.17 The exterior walls, roof, and floor is insulated with a minimum of 1-1/4 inch polystyrene (styrofoam, R-4/inch) or other material of equal R value.
- ____ 5.18 Three (3) horizontal interior wall fixture support beams are equally spaced on the interior walls. Beams are hardwood, 1"x4" nominal size. Beams are fastened to each vertical stud with bolts.
- ____ 5.19 Two (2) sealed skylights are installed, sized not to interfere with the air condition/heater or interior fluorescent lighting. Located on top of trailer near the front and rear.
- ____ 5.20 A manually operated roof vent is approximately in the center of the trailer. Demonstrate operation of the roof vent.
- ____ 5.21 One (1) cable reel with 4/C #6 W cable is mounted on the front of the trailer. Cable has an Appleton # ACP-1034CD plug. The cable is 225 feet in length ± 25 feet. The reel has a manual hand crank to retract the cable.

- _____ 5.22 The following cabinets are mechanically fastened to the trailer, constructed of steel and painted. All doors and drawers have mechanical latching. The dimensions contained in this section are nominal.
- _____ 5.22.1 One open top work bench, 60" long x 24" wide x 34" high. Steel legs, hardwood top, back and side tabletop stops. A pegboard is mounted on the wall behind the work bench. Pegboard is perforated masonite, 48" high x 60" wide 1/4" thick with 9/32" holes on 1" straight centers.
- _____ 5.22.2 Two steel, seven drawer cabinets, 28 inches wide x 22 inches deep. Two bottom drawers 7 inches deep, 4 upper drawers 5-1/2 inches deep, and one top drawer 2-1/2 inches deep.
- _____ 5.22.3 One steel, five drawer cabinet, 28 inches wide x 22 inches deep. Four lower drawers 11 inches deep and one top drawer 7 inches deep.
- _____ 5.22.4 One steel, two door combination cabinet, 36 inches wide x 18 inches deep x 6 feet high. Left half is a wardrobe with a top shelf, right half has six shelves.
- _____ 5.22.5 One steel, two door cabinet, 36 inches wide x 18 inches deep x 6 feet minimum high with five shelves.
- _____ 5.22.6 Three metal shelves 3 feet wide x 6 feet high minimum x 18 inches deep. Spacing between each shelf is to be a maximum of 1 foot. A 3 inch high retaining strip is on the bottom of each shelf.
- _____ 5.23 Two (2) external roll supports are installed nominally 36" wide with 2" diameter support tube.
- _____ 5.24 Three external roll supports are installed nominally 60" wide with 2" diameter support tube.
- _____ 5.25 Two (2) Type A/B/C fire extinguishers, minimum 20 lbs, are mounted inside trailer at floor level near each door.
- _____ 5.26 A 240 VAC, 1 ϕ , 3 ton capacity electric air condition/heater is installed and is operational. The air conditioner/heater is thermostatically regulated with no outside to inside air exchange. Verify operation for 15 minutes in both cooling and heating mode.
- _____ 5.27 The fluorescent light fixtures have been installed as shown on the sketches contained in WHC-S-056. Demonstrate operation of lighting and controls.

- _____ 5.28 External floodlights: five (5) 300 watt floodlights are installed. Four of the lights are mounted on the sides of the trailer on telescoping shafts extendable to 6 feet above the top of the trailer. The lights are positioned to distribute light evenly. The fifth light is centered over the rear of the trailer at a fixed height. Demonstrate height adjustment, operation, and removal/installation of the lights.
- _____ 5.29 Electrical fixtures and outlets are installed and wired approximately as shown on the sketches contained in WHC-S-056.
- _____ 5.30 All electrical installations conform to the latest edition of the National Electrical Code. Electrical components are UL approved.
- _____ 5.31 Any fasteners with headmarks matching those on the U. S. Customs Fasteners Headmark list contained in WHC-S-056 are not used on this contract.
- _____ 5.32 Review/compare the drawings provided by the Seller with the equipment for As-Built configuration.
- _____ 5.33 All steps of the ATP have been completed and the Exceptions have been dispositioned.

DESCRIPTION of EXCEPTION and RESOLUTION

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.

EXCEPTION and RESOLUTION CONCURRENCE:

PRINT NAME	COMPANY	SIGNATURE	DATE

*** Make additional copies as required.**