

*Exceptional service in the national interest*



## SUPERCRITICAL CARBON DIOXIDE RECOMPRESSION CLOSED BRAYTON CYCLE: FACILITY OPTIMIZATION

Gary Rochau, (505) 285-7543, [gerocha@sandia.gov](mailto:gerocha@sandia.gov)

Jim Pasch, (505) 284-6072, [jipasch@sandia.gov](mailto:jipasch@sandia.gov)

6221 Advanced Nuclear Concepts

Nuclear Energy Systems Laboratory/Brayton Lab ([ne.sandia.gov/nesl](http://ne.sandia.gov/nesl))



Sandia National Laboratories is a multi-program laboratory managed and operated by Sandia Corporation, a wholly owned subsidiary of Lockheed Martin Corporation, for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-AC04-94AL85000. SAND NO. 2011-XXXX

# Test Facility Objectives

- Execute CBC tests in a safe and reliable fashion
- Generate data of sufficient quality to baseline models
- Maximize test assembly availability


# The DOE RCBC at Sandia

Recent picture of the recompression closed Brayton cycle at Sandia  
NESL/Brayton Lab




# Heat Rejection

- Power cycle heat rejection requirements are not the same as for secondary systems cooling.
- Accommodate the two cooling requirements by segregating the cooling circuits.




# Heat Rejection

- Changes in heat rejection can have a dramatic effect on main compressor inlet conditions.
- Effect of operating near the critical point.
- Replace on/off heat rejection functions with graded functionality.




# Power Cycle Heat Rejection

- As a test progresses, the cooling water circuit warms up and the water expands. A hard circuit cannot accommodate the rise in pressure.
- Install a water expansion tank.



# Cooling circuit cleanliness

- FOD in water circuit can clog filters and reduce performance.
- Install appropriate filters.
- Inspect and clean filters on a regular basis.



# Piping Welds



- Early DOE budgets did not afford the highest level of pipe welding rigor.
- An appropriate level of pressure safety assurance was imposed, relying on ASME code B31.3
- When funds became available, pipe welding changes were implemented to comply with the more rigorous B31.1.



No evidence of overheating, fittings properly aligned, 3 weld passes, even penetration, no concavity

# Personnel Safety



- Personnel safety remains a top priority at Sandia, and NESL in particular.
- The NESL facility leads the way at Sandia in implementing engineered safety.
- System modifications that minimize personnel entry into the test room are continuously installed.
- These pictures show that remote control valves have been installed in lieu of manual operation



# Personnel Safety


- Access to heater controller was problematic due to presence of 480 V circuits.
- Method to power the 110 V controller without activating the 480 V circuits was installed.

Power switch 480 V dead while  
and auxiliary 110 V active,  
110 V power accommodating  
receptacle access to heater  
on heater controls.  
control box.




# Personnel Safety

- Additional electrical safety precautions installed in the motor controller.
- Motor controller door can now be open while testing, even with 480 V circuits.




# Personnel Safety

- Hot piping warning system installed.
- Burst disks have been located such that they cannot release onto a person



# Personnel Safety

- Safe CO2 purging operations installed.




# Thermal Insulation

- Old insulation was very thin, had large gaps, and exhibited signs of melting after high temperatures were attained.
- New insulation is 4" thick, and has a jacket specifically designed for these heaters and insulation.
- Similar insulation will be placed on hot piping in near future.




# Data Quality

- Omega pressure transducers replaced with higher accuracy and better precision Honeywell transducers



# Data Quality

- TC temperature measurements at turbomachinery ins and outs replaced with higher accuracy and higher precision RTDs.
- Similar replacement recently completed at recuperator ins and outs.



# Quality of operations at Man-Machine Interface

- Real time windage calculations added in LabView

$$P_{turb} = 0.155\omega^{2.8} \left( \frac{\rho}{21.1 \text{kg/m}^3} \right)^{0.8} \left( \frac{\mu}{1.49 \text{uPa} \cdot \text{s}} \right)^{0.2}$$

- Real time rotor shaft thrust state added. This includes force calculations from pressures on turbine and compressor wheels, and the following thrust bearing load capacity

$$W = (0.0172 \cdot \omega - 209.3) \left( \frac{\rho}{26.1 \text{kg/m}^3} \right)^{0.5} \left( \frac{D_o}{0.1016 \text{m}} \right)^{4.10}$$

- Other improvements in LabView implemented

# Data Quality

- Better grounding of TACs, to prevent noise to the instrumentation signals.



# Improved instrumentation placement

- With  $\text{SCO}_2$  being such a good solvent, it is important to minimize materials in the loop that can introduce undesirable chemicals.
- TAC internal temperature instrument constraint method was chemically based.
- Adhesive replaced with a mechanical constraint.



# Remote diagnostic ports to Motor Controller

- Effective, reliable, and safe instrumentation access ports installed on motor controller box.



# Materials Characterization

- Understanding the chemistry of the working fluid is vital to understanding corrosion and erosion processes.
- Mass Spectrometer installed to obtain necessary data between the heater discharge and the turbine inlets.
- High temperature, high pressure chemistry.



# CO2 Inventory

- Knowledge of the amount of CO2 flowing in the circuit is an important variable.
- Expansion tanks, which comprised 1/3 of the loop volume, introduced a huge uncertainty as they were installed with open communication with the primary flow path.
- Tanks have been removed from open communication, and now siphon CO2 out of loop through a remote control valve.
- Tank skid is mounted on scale to know how much CO2 has been removed during a test.



# Summary

- Numerous improvements have been implemented into the Sandia NESL/Brayton Lab testing infrastructure.
- Sandia is committed to safety, operational, and performance improvements that make sense.
- Objective is to
  - Minimize risk to personnel
  - Maximize controllability
  - Optimize the quality and range of data to inform our understanding of the operational characteristics of an SCO<sub>2</sub> CBC.