



The Water-to-Wire (W2W) Project

Dr. Edward C. Lovelace

Free Flow Power

elovelace@free-flow-power.com, 978-381-4666

November 1-3, 2011

Purpose: evaluate & optimize the performance, environment, and cost factors of the FFP hydrokinetic system for Mississippi River commercial deployment

Problem Addressed:

- limited data on practical resource potential
- commercial immaturity of hydrokinetics; particularly for river applications

Relevance to DOE Mission:

- resource potential: addressed thru seasonal deployment, surveys, and modeling
- commercialization barriers: addressed thru equipment design, electricity generation in a relevant environment, commercial systems financial analysis

Technical Approach/Methods:

Phase I: site identification, turbine performance, environmental effects

Phase I Methods:

- design, fab, test, deployment, & monitoring of generating equipment in a relevant environment
- mapping analysis of river bathymetry, overlaid GIS competing use layers, and location of proposed piling arrays
- field surveys of bathymetry and velocity and analysis with existing flow data
- field observation data for debris, fish, and navigation

Technical Approach/Methods:

Phase II: development of commercial infrastructure (links with piling placement effort in Phase I)

Phase II Methods:

- design of piling, yoke, and cabling systems (conceptual mechanical design, loading analysis, operational analysis for normal and faulted behavior)
- supply chain analysis of capital and operations cost

Key Issues/Significance:

To-date the key accomplishments are 1. the successful continuous electricity generation in a relevant environment. This addresses some of the concerns/risks peculiar to this market (debris, sediment, velocity) and their impact on practical generation from the resource and equipment performance, 2. contributions towards commercial project development (e.g. licensing studies)

Unique Aspects:

FFP is one of the few equipment and project developers focused primarily in rivers, with a piling based approach, and with a significant project pipeline in the FERC commercial licensing process

Schedule

- Initiation date: 2/15/10
- Planned completion date: 2/15/12
- Milestones FY10/11:
 - 1Q11: complete USGS Conte Lab testing of turbine
 - 3Q11: deployed turbine and floating mount test bed for in-river electricity generation

Budget:

- Variances have been minor to account for floating mount hardware cost growth and taken from analysis budget
- Expended as of 7/30/11:
 - \$815,416 DOE funds (59% of total)
 - \$1,381,671 Cost-shared

Budget History					
FY2009		FY2010		FY2011	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
		\$1,384,503	\$2,318,236 (>50%)		

Accomplishments/Significance:

- the successful continuous electricity generation in a relevant environment. This addresses some of the concerns/risks peculiar to this market (debris, sediment, velocity) and their impact on practical generation from the resource and equipment performance,
- contributions towards commercial project development (e.g. licensing studies)

Benchmarks:

- turbine performance meets design expectations
- no performance degradation in continuous operation due to river effects
- steady velocity profile of resource verified (e.g. baseload capability)
- 4 FERC study reports completed (over 1,500 pages of work available for public review)

Challenges:

- cost and schedule management of floating mount test bed

- scheduling coordination between stakeholders and weather for in-river deployment

Impact on Progress

- delayed in-river deployment 6 months

Resolution Approaches:

- minor cost shifting from analytical tasks

- contingency planning with alternate deployment scenarios

Future Milestones FY12:

- 2Q12: complete turbine deployments
- 2Q12: complete piling based systems analysis

Potential Future Activities: supporting negotiated study plan

- in-situ deployment
 - 4 pilings, 1 turbine/piling
 - 6 months pre-deployment monitoring (fish & hydraulics)
 - 12 months operational monitoring
- fish testing
- EMF and acoustic testing