

# Load Planning in the Dark, RH-TRU Waste Container Load Planning at Sandia National Laboratory

*Betty Humphrey*  
Weston Solutions, Inc.

*Randell Salyer, Jesse Bland,  
Michael Spoerner, Warren Strong,*  
**Sandia National Laboratory/New Mexico**



## *Background*

---

- Experiments during the 1970s and 1980s with fresh and irradiated mixed oxide (MOX) and uranium oxide ( $\text{UO}_2$ ) materials
- Designed to simulate various responses under varying reactor conditions
- Research materials from light water and breeder mixed oxide reactors



## *Background*

---

- **Experimental vessels and extraneous piece parts identified as eligible for disposal as remote-handled (RH) transuranic (TRU) waste**
- **Central Characterization Project provided certified Acceptable Knowledge, Visual Examination, and Dose-to-Curie**
- **Sandia required to prepare plan describing how to load each daughter container**



# *What Was Known and Unknown*

---

## *Known*

- Packaged 20-30 years ago
- Had MC&A radiological data, no sampling required
- Had outer dimensions of packaging

## *Unknown*

- No inner dimensions of items
- Limited information regarding packaging
- Extend of outer contamination
- Experiment breached



# *Material*

---

- **Based on outer packaging configuration and radiological data:**
  - **Small FD experimental vessels, Campaign 11**
  - **Pieces and kerf, Campaign 12**
  - **Large experimental vessels, Campaign 14**



# *Campaign 11, Fuel Disruption Casks*

---

- 18 FD casks
- 1 small container
- 55-gallon drum
- 89-769 kilograms





# *Campaign 12, Pieces and Kerf*

---

- 11 containers
- In marked bags, metal tubes, cans, or direct loaded
- 42 to 2,000 kg





## *Campaign 14, Large Vessels*

---

- **Seven assemblies**
  - 5 large vessels
  - FD cask
  - Drum
- **76 cm to 3.1 m in length**
- **~113 kg**





## *Technical Challenges*

---

- **Minimize number of containers**
- **Direct load or shield pots in 30-gallon drums then into 55-gallon**
- **Load 1 parent to 1 daughter, or multiple parents to one daughter, not load 1 parent to 2 daughters**
- **Fit large items into 30-gallon drum**



# *Auxiliary Hot Cell (AHC)*

---






## *Physical Challenges*

---

- Entry into the hot cell is limited through a small roof opening
- Weights of casks between a few hundred to several thousand pounds
- Some containers could not physically fit through the entry port
- Casks opened behind shield wall in a confinement tent



# *Campaign 11 Processing*

---

- Inner container removed in tent
- Transferred to hot cell
- VE into 30-gallon
- Removed and placed into 55-gallon






## *Campaign 11, Daughters*

---

**19 original containers**



**3 55-gallon drums**





# *Campaign 12 Processing*

---

- Removed cans and tubes in tent
- Transferred to hot cell
- Opened cans and tubes
- VE, into shield pots
- 7-gallon/30-gallon
- Removed/placed
- in 55-gallon






# *Campaign 12, Daughters*

---

11 original containers



4 55-gallon drums  
2 with shield pots  
2 direct load





# *Campaign 14 Processing*

---

- Stored in silos in tent
- Removed outer containers
- Transferred to hot cell
- Cut up, VE, 30-gallon
- Removed into 55-gallon






# *Campaign 14 Daughters*

---

**7 original containers**



**5 55-gallon drums**





# *Path Forward*

---


- **February 2014 began repackaging**
- **Two VE operators assigned to this project**
- **Completed VE of campaigns in December 2014**
- **Currently packaging PGW**
- **Dose to Curie will be scheduled in spring 2015**



# *Baseline Report*

---

- Baseline certification program at Sandia closed after 2012 shipment
- EPA, NMED, CTAC in July 2014
- Draft Baseline Report in process



## *Conclusions*

---

- **Sandia, Sandia Field Office, CBFO, and NWP worked together to develop and implement a path forward for the TRU waste**
- **ANL support very beneficial and reduced planning time**
- **End goals for all involved have been the same**



# Thanks

---

- AHCF operators
- TA-V RP
- TA-V management and support staff
- NWP RH Manager, SPM, AKEs, Rad engineers
- VE operators from INL and LANL
- DTC operator from SRS