


Exceptional service in the national interest



Availability and System Failure Modeling

Intersolar North America: Solar Asset Symposium

Geoffrey T. Klise

Sandia National Laboratories

July 12, 2016



Sandia National Laboratories is a multi-program laboratory managed and operated by Sandia Corporation, a wholly owned subsidiary of Lockheed Martin Corporation, for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-AC04-94AL85000.


Current Activities

- **PV Reliability Operations Model** – *A best practice for collecting operational data for reliability analysis*
 - Examples of Logistics Delays from existing data partners
 - Setting up Bill of Materials for new data partner
 - Analyzing raw performance and condition data from owner-operators – Activity starting this summer
- **System Advisor Model**
 - Energy production impacts due to failure modeling and O&M scheduling
 - Different ways to visualize DC and AC components
 - Using reliability data from our PVROM data partners, and any user with reliability data that wants to help test the beta version
- **Adding Reliability Elements to NREL O&M Cost Model**
 - Probabilistic failure elements to drive O&M planning decisions, e.g. financial exposure

Determining Logistics Delays

Fixed DG Sites in AZ

| | |
|----------------------------|--------------|
| Number of Sites | 41 |
| Total Nameplate Power (MW) | 1.26 |
| Total Modules | 7,857 |
| Total Inverters | 47 |
| Total Line Items | 9,160 |
| Total Incidences | 36 |
| Observation Time (months) | 46 |



| Item | Observation / Action |
|--|--|
| <i>1. Plant Site</i> | |
| a. General Cleanliness | dust |
| b. Animal Activity | cobwebs present |
| c. Vegetation | weeds ok |
| <i>2. Solar Modules</i> | |
| a. Inspect for Damaged Modules | ok |
| b. Module Cleanliness (Surface) | heavy dust |
| c. Inspect Wiring (Module) | ok |
| d. Inspect Wiring (Security) | replaced some zip-ties |
| <i>3. Solar Module Support</i> | |
| a. Inspect for Structural Integrity | ok |
| b. Inspect Bolted Connections | ok |
| c. Inspect Wiring (Security) | need some loop clamps |
| d. Concrete/Substructure Connections | ok |
| <i>4. Combiner Enclosures</i> | |
| a. Inspect wiring connections | ok |
| b. Check for Blown Fuses | PV07 blown; Array combiner 2 of 2; second fuse holder from top |
| c. Voc/Isc Test of Source Circuits | See Table 1 (not shown here) |
| <i>5. DC/AC Disconnect Switches</i> | |
| a. Inspect wiring connections | ok |
| b. Visual inspection of wiring | ok |
| c. Visual inspection of connections/Torque connections | ok, not torqued |
| <i>6. Inverters</i> | |
| a. General inspection/cleaning | intake screens cleaned |
| b. Connection and Wiring | ok, not torqued |
| c. Testing | no 5 minute delay after AC disconnect opened |

East Coast Fixed PV System

6 MW: 3 Inverters, 20,000+ modules

- Unknown Fault Codes
- Internal inverter wiring issues
- Most down-time due to internal inverter faults

operational days

| | |
|------|-----|
| 2015 | 37 |
| 2016 | 125 |

Availability (time-based)

| Inverter A | Inverter B | Inverter C |
|------------|------------|------------|
| 84% | 49% | 8% |
| 90% | 91% | 86% |

1160 1050 925 Generation (MWh)

515 Lost Generation (MWh)

New Analysis: Currently Setting up Bill of Materials to match as-built and part level hierarchy. 3 levels being considered.

- Data partner interested in tracking inverter level items as shown in hierarchy
- Certain inverter electrical components will be grouped, but not all


| Hierarchy Order | Part Number | Part Description | Notes |
|-----------------|-------------|--|---|
| 1 | PVSYS | Photovoltaic System-Top Level | No incidents would normally be written against this category. This for organization of the hierarchy of other parts. An incident could be written for events that affected the system in a broad sense. |
| 2 | ECON | System level electrical components | This would be a "basket" part that would capture cabling, connectors, fuses, etc., that are associated with the system as whole and not associated with some other part as specified in the hierarchy. Replacement of any specific items under this part would be |
| 2 | INV | Inverter | |
| 3 | COMMB | Communication Board | |
| 3 | CTRLBD | Control Board | |
| 3 | CTRLSW | Control Software | |
| 3 | FAN | Cooling Fan | |
| 3 | ICONSM | Inverter Consumables | Coolant and oil would be under this "part" |
| 3 | IECON | Inverter level electrical components | Miscellaneous electronics like the capacitors, fuses, interconnect cables, etc. |
| 3 | IGBT | Isolated Gate Bi-Polar Transistor | |
| 3 | ISTACK | Inverter Stack Electronics | Need to determine if this should be broken out more. |
| 2 | DDS | DC Disconnect Switch | |
| 2 | DCCOMB | DC Combiner Box | |
| 3 | DCCFUS | DC Combiner Box Fuses | |
| 3 | DCCSW | DC Switch | |
| 2 | STRING | PV String | No incidents would normally be written against this category. This for organization of the hierarchy of other parts. A incident could be written for events that affected the an string in a broad sense. |
| 3 | MOD | PV Module | |
| 3 | MECON | PV Module Connectors, Cables, Miscell... | This would be a "basket" part that would capture cabling, connectors, fuses, etc., that are directly associated with PV Module under a PV |

Modeling Reliability and Availability


- Integration of reliability algorithms into SAM is almost complete
- Years 2 and 3 will focus on model validation, beta testing and detailed documentation

1-year example of failures/events for 2 MW system with 8 inverters & 9,400 modules

- 379 modules fail and are not replaced
- 12 strings
- 66 dc combiner
- 7 inverter
- 4 ac disconnect
- 1 transformer



The % of ac power that can be delivered to the grid




How can we better understand simulated reliability of the components?

Modeling Reliability and Availability

The SAM Reliability Module will have a feature to estimate component availability over simulation period

| Component | Offline days (annually) | Component time-based availability |
|--------------|-------------------------|-----------------------------------|
| Modules | 28.7 | 99.0 |
| Strings | 1.2 | 99.8 |
| dc Combiners | 12 | 95.0 |
| Inverter | 19.2 | 88.0 |
| Transformer | 0 | 100 |




$$A_{raw_i} = 1 - \frac{DownTime_i}{TotalTime_i}$$

Klise and Balfour (2015) *A Best Practice for Developing Availability Guarantee Language in Photovoltaic (PV) O&M Agreements*


$$A_{raw_sys} = \frac{\sum_{i=1}^n A_{raw_i} \times NP_i}{\sum_{i=1}^n NP_i}$$

Estimates of energy production as a function of failure rates, including confidence intervals

Lifetime energy lost with 20 realizations



Exceptional service in the national interest



Thank You
Geoff Klise
gklise@sandia.gov



Sandia National Laboratories is a multi-program laboratory managed and operated by Sandia Corporation, a wholly owned subsidiary of Lockheed Martin Corporation, for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-AC04-94AL85000.