

Evaluation of Fracture Toughness for Hybrid Aluminum to Fiber Reinforced Polymer Composite Joints



Brian T. Werner, Timothy M. Briggs, Dhego Banga

Sandia National Laboratories

Livermore, CA USA

18th International Conference on Experimental Mechanics

Brussels, Belgium, July 1-5 2018



Sandia National Laboratories is a multimission laboratory managed and operated by National Technology & Engineering Solutions of Sandia, LLC, a wholly owned subsidiary of Honeywell International Inc., for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525.

Composite to Aluminum Bonding

- Terms

- Cobonding – composite is cured in contact with aluminum forming a bond through the matrix curing process
- Secondary bonding – cured composite is bonded to aluminum in a second step with an infusion resin or paste adhesive forming the bond

- Aluminum bonding issues


- Oxide layer
- Anodization
- Primer
- Surface cleanliness

- Current standard for good mechanical bonding

- Phosphoric anodization
- BR-127 primer

- BR-127 has high VOC and hexavalent chromium

- Requires advanced filtration for spray application
- Future environmental regulations may prevent its long term use
- A replacement surface prep must be found



Primer Selection

Product	BR® 127	BR® 6700-1	BR® 252	Hysol® 2000
VOC (g/L)	792	0	12	15
Inhibitor	Chromated	Nonchromated	Nonchromated	Nonchromated
Solids (%)	10% ± 1 sprayable	25% sprayable	18% sprayable	10 - 14% sprayable
Density (g/L)	875	1050	1030	1010
Metal Bond Application	Compatible with most 121-177°C curing adhesives	Compatible with most 121-177°C curing adhesives	Compatible with most 121-177°C curing adhesives	Compatible with most 121-177°C curing adhesives
Mechanical Properties	Maximum environmental resistance and durability with bond line Prevents corrosive undercutting	Mechanical properties and corrosion resistance equal to that of solvent-based primer systems	Mechanical properties equal to that of solvent-based primer systems	Excellent resistance to chemicals and water

All selected primers have no Chromium and VOC levels well below the Federal and California limits


Aluminum Anodization




As-received



Cleaned



Phosphoric Acid Anodized



Materials Cleaning and Anodizing Processes

1. Acetone wipe.
2. Oakite®90 alkaline-clean at 93°F for 3 minutes.
3. D.I. water rinse.
4. De-smut in nitric acid bath (40% vol.) at ambient temperature for 5 minutes.
5. D.I. water rinse.
6. Phosphoric acid anodize at 10 V for 25 minutes.
7. D.I. water rinse.
8. N₂ gas-dry.

Oxide thickness measured by calibrated eddy current was 0.135 ± 0.04 mils (3.43 ± 1 um)

Primer Application



BR[®] 252



- **2** spray cross coats
- Thickness – **0.24 ± 0.08** mils
- Recommended – 0.15 – 0.3 mils

BR[®] 6700-1



- **1** spray cross coat
- Thickness – **0.37 ± 0.1** mils
- Recommended – 0.15 – 0.3 mils


Hysol[®] 2000




- **4** spray cross coats
- Thickness – **0.27 ± 0.07** mils
- Recommended – 0.15 – 0.3 mils

Primer Downselect


- Cobonded aluminum to GFRP panels
 - Phosphorically anodized
 - Each of the candidate primers used
- Rapid Adhesion Testing Performed (RAT)
 - Similar to a climbing drum peel
 - Qualitative – determines fracture mode
 - Quick and simple to perform
- All panels failed cohesively within the GFRP
- Hysol 2000 was selected on input from application team




BR® 252



BR® 6700-1



Hysol® 2000





DCB Testing



- Specimens
 - Aluminum 6061-T6/GFRP[0₇]_s – cobonded
 - Aluminum 6061-T6/GFRP[0₇]_s – secondary bonded with infusion resin (INFI14/HT251)
- Instron 5989 electromechanical test frame
- Constant displacement (1mm/min)
- Tested across wide temperature range
 - -50°C
 - 21°C
 - 70°C
- Strain energy release rate calculated using beam theory




DCB Results



Typical Cobond Failure




70 °C



21 °C


-50 °C

Fracture Surfaces




3362 resin to fiber
interfacial fracture



Al side of fracture



GFRP side of fracture




Interface Cross-section







Cohesive fracture within
primer at Al_2O_3
interface (left)


Interfacial fracture
along primer to
adhesive (right)



Aluminum/Primer Failure



Aluminum/Primer Failure



Al K series

Summary

- Hysol 2000 primer provides adequate bond strength
- Primer/oxide failure for secondary bond at cold temp
 - Potentially due to CTE mismatch
 - Toughness results show higher strength than room or high temp
- Cobonded specimens
 - Adherend failure
 - Bonded joint is not the weak link
- Future work
 - Glass fiber-matrix interface appears to be weak link
 - Fiber sizing
 - Matrix-fiber compatibility
 - Composite surface preparation
 - Plasma cleaning
 - Laser ablation