

# **Annual Status Report (FY 2022): Composite Analysis for Low-Level Waste Disposal in the Central Plateau of the Hanford Site**

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management



**P.O. Box 550**  
**Richland, Washington 99352**

# Annual Status Report (FY 2022): Composite Analysis for Low-Level Waste Disposal in the Central Plateau of the Hanford Site

B. Sun  
INTERA, Inc.

Date Published  
March 2023

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management

 U.S. DEPARTMENT OF ENERGY | Richland Operations Office  
P.O. Box 550  
Richland, Washington 99352

**APPROVED**  
By Lynn M Ayers at 2:22 pm, May 10, 2023

---

Release Approval

Date

**TRADEMARK DISCLAIMER**

Reference herein to any specific commercial product, process, or service by tradename, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

---

This report has been reproduced from the best available copy.

Printed in the United States of America

## Executive Summary

In accordance with DOE M 435.1-1<sup>1</sup> requirements and as implemented by DOE/RL-2000-29,<sup>2</sup> the U.S. Department of Energy (DOE), Richland Operations Office has prepared this annual summary for fiscal year (FY) 2022. Originally reported in PNNL-11800<sup>3</sup> and PNNL-11800, Addendum 1<sup>4</sup> (hereinafter collectively referred to as the Hanford Site Composite Analysis), the Hanford Site Composite Analysis was approved through issuance of a 2002 memorandum.<sup>5</sup>

As required by DOE/RL-2000-29, an annual evaluation of new information and data developed by several onsite programs was completed. The reporting period for this annual evaluation is FY 2022 (October 1, 2021 through September 30, 2022).

The information provided in this evaluation includes the following activities performed in FY 2022 that are considered pertinent to the Hanford Site Composite Analysis:

- Information that could change the source terms considered in the composite analysis, including the following:
  - Performance assessment (PA) development and maintenance activities:
    - 200 East Area Low-Level Burial Grounds PA
    - 200 West Area Low-Level Burial Grounds PA
    - Integrated Disposal Facility PA

---

<sup>1</sup> DOE M 435.1-1 Chg 3 (LtdChg), 2021, *Radioactive Waste Management Manual*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-DManual-1-chg3-ltdchg-1>.

<sup>2</sup> DOE/RL-2000-29, 2018, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1420314>.

<sup>3</sup> PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079141H>.

<sup>4</sup> PNNL-11800, 2001, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1, Pacific Northwest National Laboratory, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0084085>.

<sup>5</sup> Frei, M.W., 2002, "Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Submittal of an Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800 Addendum 1" (memorandum to R. Schepens, U.S. Department of Energy, Office of River Protection, and K.A. Klein, U.S. Department of Energy, Richland Operations Office), U.S. Department of Energy, Office of Environmental Management, Washington, D.C., July 24.

- Waste Management Area C PA
- Environmental Restoration Disposal Facility PA
- Waste Management Area A-AX PA
  - *Resource Conservation and Recovery Act of 1976*<sup>6</sup> remedial activities
  - *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*<sup>7</sup> remedial activities
- Monitoring, including the following:
  - Air monitoring
  - Groundwater flow and contamination monitoring
  - Vadose zone characterization
- Research and Development, including the following:
  - Remediation science and technology
  - Operations studies

This annual evaluation identified no information in any of the above reviewed activities that considered results of data collection and analysis from research, field studies, and monitoring that would invalidate the continued adequacy of the currently approved version of the Hanford Site Composite Analysis. However, based on information reviewed from prior annual status reports, the determination of the FY 2015 annual summary report<sup>8</sup> is that the Hanford Site Composite Analysis requires an update. While the original composite analysis (prepared in 1998, with an addendum in 2001) has been maintained, the accumulation of basis changes reported in the annual summary reports of the preceding 14-year period merits evaluation in an updated analysis. This determination remains in place in this annual summary; new information needs to be incorporated and

---

<sup>6</sup> *Resource Conservation and Recovery Act of 1976*, Pub. L. 94-580, 42 USC 6901 et seq. Available at: <https://www.govinfo.gov/content/pkg/STATUTE-90/pdf/STATUTE-90-Pg2795.pdf>.

<sup>7</sup> *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, Pub. L 107-377 as amended, 42 USC 9601 et seq., December 31, 2002. Available at: <https://www.csu.edu/cerc/researchreports/documents/CERCLASummary1980.pdf>.

<sup>8</sup> DOE/RL-2015-66, 2016, *Annual Status Report (FY 2015): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1364347>.

analyzed using environmental modeling software that meets current DOE quality assurance requirements. Annual maintenance continues under DOE/RL-2000-29 because of the length of time planned for the preparation of an updated Hanford Site Composite Analysis.

On November 21, 2012, DOE issued the final Tank Closure and Waste Management Environmental Impact Statement<sup>9</sup> (hereinafter referred to as the TC & WM EIS) for the Hanford Site pursuant to the *National Environmental Policy Act of 1969*<sup>10</sup> and implementing regulations (Council on Environmental Quality, 2005<sup>11</sup> and 10 CFR 1021<sup>12</sup>). From 2006 until the TC & WM EIS was issued, any revision of the Hanford Site Composite Analysis was deferred. After issuance of the final TC & WM EIS, planning phase activities for preparing an update to the Hanford Site Composite Analysis were completed in FY 2015, and scoping phase activities that commenced in FY 2016 were completed in FY 2017. The culmination of the scoping phase was the preparation of a summary analysis<sup>13</sup> for the composite analysis update. Approval of the summary analysis was granted in May 2017, enabling commencement of the analysis phase. The analysis phase saw the development and application of models fulfilling the summary analysis and resulted in a completed Composite Analysis update that was submitted to the Low-Level Waste Disposal Facility Federal Review Group (LFRG) in December 2020. The onsite review was completed in March 2021 with 8 Key Issues, 15 Secondary Issues, 13 Observations, and 6 Best Management Practices assigned. A revision to the updated Composite Analysis was produced to address all issues and observations, which was submitted to LFRG in May 2022. Two key issues were identified requiring further revision to the updated Composite Analysis before it would be accepted. A second revision is in preparation and planned to be submitted in

---

<sup>9</sup> DOE/EIS-0391, 2012, *Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington (TC & WM EIS)*, U.S. Department of Energy, Office of River Protection, Richland, Washington. Available at: <http://energy.gov/hepa/downloads/eis-0391-final-environmental-impact-statement>.

<sup>10</sup> *National Environmental Policy Act of 1969*, 42 USC 4321 et seq. Available at: <https://www.govinfo.gov/content/pkg/USCODE-2010-title42/pdf/USCODE-2010-title42-chap55-sec4321.pdf>.

<sup>11</sup> Council on Environmental Quality, 2005, *Regulations for Implementing the Procedural Provisions of the National Environmental Policy Act*, Executive Office of the President, Reprint of 40 CFR Parts 1500-1508. Available at: [https://energy.gov/sites/prod/files/NEPA-40CFR1500\\_1508.pdf](https://energy.gov/sites/prod/files/NEPA-40CFR1500_1508.pdf).

<sup>12</sup> 10 CFR 1021, "National Environmental Policy Act Implementing Procedures," *Code of Federal Regulations*. Available at: <https://www.govinfo.gov/content/pkg/CFR-2019-title10-vol4/pdf/CFR-2019-title10-vol4-part1021.pdf>.

<sup>13</sup> CP-60649, 2017, *Summary Analysis: Hanford Site Composite Analysis Update*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1412683>.

2023 to close the remaining key issues and address some secondary issues that remain open.

Following guidance in DOE-STD-5002-2017,<sup>14</sup> this annual summary report is organized as follows:

- Chapter 1 provides an overview of the changes in the reporting period that potentially affect the Hanford Site Composite Analysis.
- Chapter 2 provides an assessment of the cumulative effects of the changes on the Hanford Site Composite Analysis.
- Chapter 3 summarizes sources of information that account for waste receipts during the reporting period.
- Chapter 4 provides a review of recent onsite monitoring and characterization activities relevant to the current Hanford Site Composite Analysis.
- Chapter 5 summarizes research and development and operations studies that could affect the Hanford Composite Analysis.
- Chapter 6 reports on planned or contemplated changes to relevant Hanford Site programs that could affect the Hanford Site Composite Analysis and recommended changes to the Hanford Site Composite Analysis maintenance program.
- Chapter 7 summarizes the status of conditions on the disposal authorization statement, as well as key and secondary issues.
- Chapter 8 provides the required certification of the continued adequacy of the Hanford Site Composite Analysis.
- Chapter 9 provides the references cited in this report.
- Appendix A provides a history of the maintenance of the Hanford Site Composite Analysis.
- Appendix B provides a summary of the status of the update of the Hanford Site Composite Analysis that is in progress.

---

<sup>14</sup> DOE-STD-5002-2017, 2017, *Disposal Authorization Statement and Tank Closure Documentation*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.standards.doe.gov/standards-documents/5000/5002-astd-2017>.

- Appendix C provides a crosswalk of the review criteria for this annual status report to indicate where in this document the required information is provided.

This page intentionally left blank.

## Contents

<b>1</b>	<b>Changes Potentially Affecting the Composite Analysis .....</b>	<b>1-1</b>
1.1	Performance Assessments .....	1-3
1.1.1	200 East and 200 West Low-Level Burial Ground Performance Assessments .....	1-4
1.1.2	Integrated Disposal Facility Performance Assessment .....	1-9
1.1.3	Waste Management Area C Performance Assessment .....	1-14
1.1.4	Environmental Restoration Disposal Facility Performance Assessment .....	1-23
1.1.5	Waste Management Areas A/AX Performance Assessment .....	1-25
1.2	Central Plateau RCRA Remedial Activities.....	1-29
1.2.1	Phase 2 RCRA Facility Investigation and Corrective Measure Studies .....	1-29
1.2.2	Interim Measures .....	1-31
1.3	Central Plateau CERCLA Remedial Activities.....	1-34
1.3.1	Central Plateau Source Operable Units.....	1-39
1.3.2	Central Plateau Groundwater Operable Units.....	1-44
1.3.3	Other Central Plateau Remediation Activities .....	1-63
<b>2</b>	<b>Cumulative Effects of Changes .....</b>	<b>2-1</b>
2.1	Relative Contribution of DOE O 435.1-Regulated Sources to All-Pathways Dose.....	2-2
<b>3</b>	<b>Waste Receipts.....</b>	<b>3-1</b>
<b>4</b>	<b>Monitoring .....</b>	<b>4-1</b>
4.1	Summary of Air Monitoring.....	4-1
4.1.1	Air Effluent Monitoring for Radioactive Airborne Emissions .....	4-2
4.1.2	Air Monitoring for Radionuclides.....	4-2
4.1.3	Perimeter and Offsite Air Monitoring for Radionuclides .....	4-5
4.2	Summary of Groundwater Flow Conditions and Extent of Contamination .....	4-6
4.2.1	Groundwater Flow .....	4-6
4.2.2	Extent of Contamination .....	4-8
4.3	Summary of Vadose Zone Characterization.....	4-14
4.3.1	Characterization Approaches for Source Operable Units .....	4-14
<b>5</b>	<b>Research and Development .....</b>	<b>5-1</b>
5.1	Remediation Science and Technology .....	5-2
5.2	Operations Studies.....	5-4
<b>6</b>	<b>Planned or Contemplated Changes .....</b>	<b>6-1</b>
6.1	Special Analyses.....	6-1
6.2	Changes in Site Land Use and Remediation Plans.....	6-3
6.2.1	Engineered Barriers (in Remediation Plans).....	6-3
6.2.2	Institutional Controls .....	6-4
6.2.3	Operational Controls for Subsidence .....	6-4

<b>7</b>	<b>Status of Disposal Authorization Statement Conditions and Key and Secondary Issues.....</b>	<b>7-1</b>
<b>8</b>	<b>Certification of the Continued Adequacy of the Composite Analysis .....</b>	<b>8-1</b>
<b>9</b>	<b>References .....</b>	<b>9-1</b>

## Appendices

<b>A</b>	<b>History of Hanford Site Composite Analysis Maintenance.....</b>	<b>A-i</b>
<b>B</b>	<b>Status of Hanford Site Composite Analysis Update.....</b>	<b>B-i</b>
<b>C</b>	<b>Crosswalk of LFRG Review Criteria to Annual Status Report Content .....</b>	<b>C-i</b>

## Figures

Figure 1-1.	Location of the Low-Level Burial Grounds.....	1-7
Figure 1-2.	Location of the Integrated Disposal Facility.....	1-9
Figure 1-3.	Photograph of the Integrated Disposal Facility First Expansion (Current Configuration).....	1-10
Figure 1-4.	Location of Waste Management Area C.....	1-15
Figure 1-5.	Location of the Environmental Restoration Disposal Facility.....	1-24
Figure 1-6.	Location of Waste Management Area A-AX .....	1-26
Figure 1-7.	Map of 241-A and 241-AX Tank Farms.....	1-27
Figure 1-8.	Vadose Zone Soil Sampling Locations Near Tanks T-102 and T-105 in 241-T Tank Farm.....	1-32
Figure 1-9.	Vadose Zone Soil Sampling Locations in 241-U Tank Farm.....	1-33
Figure 1-10.	Central Plateau CERCLA Remedial Activities and Operable Units .....	1-35
Figure 1-11.	Hanford Site Groundwater Interest Areas and Groundwater Operable Units.....	1-45
Figure 1-12.	Central Plateau Groundwater Contaminant Plumes and Cleanup .....	1-46
Figure 1-13.	Configuration of Disposal Cells at the Environmental Restoration Disposal Facility.....	1-64
Figure 1-14.	Photograph of the Environmental Restoration Disposal Facility with Indication of Disposal Cells .....	1-65
Figure 4-1.	Water Table and Inferred Groundwater Flow Directions for the Hanford Site, 2021 .....	4-7
Figure 4-2.	Distribution of Radionuclide Contaminant Plumes Originating from the Hanford Site Central Plateau at Concentrations Above Drinking Water Standards in the Unconfined Aquifer .....	4-9
Figure 4-4.	Flow Diagram for the Initiation of the Opportunistic Sampling Process .....	4-18

## Tables

Table 1-1.	Potential Changes Affecting the Composite Analysis .....	1-1
Table 1-2.	Hanford Site Performance Assessments in Planning, Scoping, Analysis, and Maintenance Phases and Fiscal Year 2021 Status .....	1-5
Table 1-3.	Inventory of PUREX Tunnels Evaluated in the Composite Analysis Addendum.....	1-36
Table 1-4.	Central Plateau Source Operable Unit Activity During Fiscal Year 2022 .....	1-40
Table 1-5.	Central Plateau CERCLA/RCRA Deliverables, Fiscal Years 2018 Through 2024.....	1-42
Table 1-6.	Status of Central Plateau Groundwater Remediation in Calendar Year 2021 .....	1-52
Table 4-1.	Compliance Monitoring.....	4-3
Table 4-2.	Hanford Site Radioactive Airborne Emissions in Calendar Year 2021 .....	4-4
Table 4-3.	Conceptual Site Model Grouping Overview and Representative Waste Sites .....	4-15
Table 4-4.	Summary of FY 2022 Opportunistic Sampling During Drilling .....	4-18
Table 5-1.	Research and Development Activities .....	5-1
Table 6-1.	Planned or Contemplated Changes .....	6-1
Table 7-1.	Status of Disposal Authorization Statement Conditions, Key, and Secondary Issues.....	7-2

This page intentionally left blank.

## Contributors

Topic Area	Affiliation	
	Contributors	DOE Authority
Annual Summary Editors	B. Sun (INTERA)	R.D. Hildebrand (DOE-RL) J.M. Capron (DOE-RL)
Low-Level Burial Ground Performance Assessments (Section 1.1.1)	S. Mehta (INTERA) R. Nell (INTERA)	G.L. Pyles (DOE-RL)
Integrated Disposal Facility Performance Assessment (Section 1.1.2)	K.P. Lee (WRPS)	G.L. Pyles (DOE-RL)
Waste Management Area C Performance Assessment (Section 1.1.3)	M.P. Bergeron (WRPS)	Rebecca I Blackwell (DOE-RL)
Environmental Restoration Disposal Facility Performance Assessment (Section 1.1.5)	D.B. Teachout (CPCCo) W.A. Borlaug (CPCCo)	B. Stetter (DOE-RL)
Waste Management Area A/AX Performance Assessment (Section 1.1.5)	M.P. Bergeron (WRPS)	Rebecca I Blackwell (DOE-RL)
Central Plateau CERCLA Remedial Activities (Section 1.3)	M.P. Bergeron (WRPS) James Hamilton	J.M. Capron (DOE-RL) Becky Blackwell (DOE-RL)
Remediation Activities for Central Plateau Source Operable Units (Section 1.3.1)	T.B. Bergman (CPCCo) M.E. Byrnes (CPCCo)	N.M. Jaschke (DOE-RL)
Remediation Activities for Central Plateau Groundwater Operable Units (Section 1.3.2)	A.K. Lee (CPCCo)	N.M. Jaschke (DOE-RL)
Environmental Restoration Disposal Facility Operations (Section 1.3.3.2)	D.B. Teachout (CPCCo) W.A. Borlaug (CPCCo)	B. Stetter (DOE-RL)
Summary of Air Monitoring (Section 4.1)	B. Sun (INTERA)	R.D. Hildebrand (DOE-RL) J.M. Capron (DOE-RL)
Summary of Groundwater Monitoring (Section 4.2)	J.P. McDonald (INTERA)	R.D. Hildebrand (DOE-RL) J.M. Capron (DOE-RL)
Summary of Vadose Zone Characterization (Section 4.3)	S. Sexton (CPCCo)	R.D. Hildebrand (DOE-RL) J.M. Capron (DOE-RL)
Remediation Science and Technology (Section 5.1)	V.L. Freedman (PNNL)	J.P. Hanson (DOE-RL)
Changes in Site Land Use and Remediation Plans (Section 6.2)	T.B. Bergman (CPCCo)	R.D. Hildebrand (DOE-RL) J.M. Capron (DOE-RL)

CERCLA = *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*

DOE-RL = U.S. Department of Energy, Richland Operations Office

CPCCo = Central Plateau Cleanup Company

PNNL = Pacific Northwest National Laboratory

INTERA = INTERA, Incorporated

WRPS = Washington River Protection Solutions

DOE-ORP = U.S. Department of Energy, Office of River Protection

This page intentionally left blank.

## Terms

AEA	<i>Atomic Energy Act of 1954</i>
CERCLA	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>
COC	contaminant of concern
COPC	contaminant of potential concern
CPCCo	Central Plateau Cleanup Company
CSM	conceptual site model
CY	calendar year
DAS	disposal authorization statement
DOE	U.S. Department of Energy
DOE-EM	U.S. Department of Energy, Office of Assistant Secretary for Environmental Management
DOE-HQ	U.S. Department of Energy, Headquarters
DOE-ORP	U.S. Department of Energy, Office of River Protection
DOE-RL	U.S. Department of Energy, Richland Operations Office
DQO	data quality objective
DVZ	deep vadose zone
DWS	drinking water standard
Ecology	Washington State Department of Ecology
EE/CA	engineering evaluation/cost analysis
EPA	U.S. Environmental Protection Agency
ERDF	Environmental Restoration Disposal Facility
ERT	electrical resistivity tomography
ETF	Effluent Treatment Facility
FFS	focused feasibility study
FGR	Federal Guidance Report
FS	feasibility study
FY	fiscal year
H2	Hanford formation unit 2

HLW	high-level waste
IAMIT	Interagency Management Integration Team
IC	institutional control
IDF	Integrated Disposal Facility
ILAW	immobilized low-activity waste
LFRG	Low-Level Waste Disposal Facility Federal Review Group
LLBG	low-level burial ground
LLW	low-level waste
LLWMA	low-level waste management area
MNA	monitored natural attenuation
MSU	modular storage unit
NRC	U.S. Nuclear Regulatory Commission
NRDWL	Nonradioactive Dangerous Waste Landfill
NTCRA	non-time-critical removal action
ODAS	operating disposal authorization statement
OU	operable unit
P&T	pump and treat
PA	performance assessment
PFP	Plutonium Finishing Plant
PNNL	Pacific Northwest National Laboratory
PUREX	Plutonium-Uranium Extraction
QA	quality assurance
RAI	request for additional information
RASCAL	Representative/Analogous Sites Coordinating Agency Liaisons
RCRA	<i>Resource Conservation and Recovery Act of 1976</i>
RD/RAWP	remedial design/remedial action work plan
RI	remedial investigation
RFI/CMS	RCRA Facility Investigation/Corrective Measures Study
ROD	record of decision
SALDS	State-Approved Land Disposal Site

SST	single-shell tank
SSW	secondary solid waste
SVE	soil vapor extraction
SWL	Solid Waste Landfill
TC & WM EIS	Tank Closure and Waste Management Environmental Impact Statement
TED	total effective dose
Tri-Parties	U.S. Department of Energy, U.S. Environmental Protection Agency, and Washington State Department of Ecology
Tri-Party Agreement	<i>Hanford Federal Facility Agreement and Consent Order</i>
TRU	transuranic
TSD	treatment, storage, and disposal
UDQE	unreviewed disposal question evaluation
UWMQ	unresolved waste management question
WESF	Waste Encapsulation and Storage Facility
WIR	waste incidental to reprocessing
WTP	Hanford Site Tank Waste Treatment and Immobilization Plant
WMA	waste management area
WMIS	Waste Management Information System

This page intentionally left blank.

## 1 Changes Potentially Affecting the Composite Analysis

This chapter identifies potential or actual changes, discoveries, proposed actions, and new information identified during the operation of the Hanford Site during the reporting period (fiscal year [FY] 2022, covering the timeframe of October 1, 2021 through September 30, 2022) that potentially affect the basis of PNNL-11800, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, and PNNL-11800, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1 (hereinafter collectively referred to as the Hanford Site Composite Analysis) to include the following:

- Deletion of sources considered in the Hanford Site Composite Analysis
- Addition of new sources not considered in the Hanford Site Composite Analysis
- Changes to existing sources (e.g., completion of remedial activities at *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* [CERCLA] sites)
- Availability of new information that reduces uncertainty in characteristics of existing sources

Maintenance of the Hanford Site Composite Analysis is conducted under DOE/RL-2000-29, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*. Table 1-1 summarizes change control process evaluations arising from PAs supported by the Hanford Site Composite Analysis. There were no unreviewed disposal question or unreviewed disposal question evaluations (UDQEs) for the reporting period for any PA or for the composite analysis itself.

**Table 1-1. Potential Changes Affecting the Composite Analysis**

Disposal Facility/Unit	UDQE/UCAQE or Change Control Process Identification Number	Change, Discovery, Proposed Action, New Information Description	Evaluation Results	Special Analysis Number (if applicable)	Composite Analysis Impacts
<i>No changes for the reporting period.</i>					

UCAQE = unreviewed composite analysis question evaluation

UDQE = unreviewed disposal question evaluation

There was no deletion of any sources considered and no addition of any sources not considered in the Hanford Site Composite Analysis identified during review of FY 2022 information.

No major changes to Hanford Site radionuclide inventories were identified during review of FY 2022 information that would have the potential to alter the basis of the Hanford Site Composite Analysis.

Activities in the following categories are reviewed because they have potential to reveal new information that could constitute changes to existing radionuclide sources and/or new information that reduces uncertainty in characteristics of existing radionuclide sources:

- DOE M 435.1-1, *Radioactive Waste Management Manual* (Section 1.1)
- *Resource Conservation and Recovery Act of 1976* (RCRA) remedial activities (Section 1.2)
- CERCLA remedial activities (Section 1.3)

The U.S. Department of Energy's (DOE's) Office of Enterprise Assessments issued an "Assessment of Low-Level Radioactive Waste Disposal Practices at the Hanford Site" (DOE, 2018, *Office of Enterprise Assessments Assessment of Low-Level Radioactive Waste Disposal Practices at the Hanford Site*) report in February 2018. Regarding the Hanford Site Composite Analysis, this report noted the following:

The Hanford Site [Composite Analysis] CA was originally reported in the Composite Analysis for Low-Level Disposal in the 200 Area Plateau of the Hanford Site in 1998. An addendum was written in 2001. The CA has been maintained without major revisions or additions for the past 16 years while several decisions were made regarding remediation and disposal in the Central Plateau.

A detailed account of that history was succinctly reported in the FY 2016 CA Annual Status Report, which evaluated information based on the updated remediation and disposal decisions and conditions or new information that could change the source terms considered in the CA, including: (1) PA development and maintenance activities for 200 West Area LLBG, 200 East Area LLBG, the Environmental Restoration Disposal Facility (ERDF), Integrated Disposal Facility, and Waste Management Area C; and (2) monitoring, research, and development results, including groundwater flow and contamination monitoring, and remediation and technology programs.

EA concurs that current information and data validate the adequacy of the present version of the Hanford Site CA evaluation, which indicates that the performance objectives are satisfied. However, based on the 2016 annual review, the site determined that the CA modeling requires rebuilding and updated analysis to better reflect anticipated conditions and improve its accuracy as a land use planning tool. The accumulation of basis changes and model parameter validation data reported in the annual summary reports over the past 15 years constitute sufficient new information to merit evaluation in an updated analysis, using environmental modeling software that meets current DOE QA requirements. EA and the site are in agreement with the need for a rebuilt, QA-approved, up-to-date CA. DOE-RL and its contractors are developing plans and gathering all appropriate input data for a complete update of the CA, which is expected to be completed over the next three years. In discussions with the lead modeling subject matter experts (SMEs), EA reviewed the plans and progress for the CA rebuilding effort, including the approach to scoping the new analysis, technical approach, input parameter validation, and analysis and reporting phases.

The site has identified the following new information and requirements as justification for updating the CA analysis:

- When the original 1998 CA was developed, some remedial action decisions were deferred to determine whether alternate remedies were necessary or available based on additional characterization and development of new remediation technologies. Consensus on many of those decisions has now been reached through negotiations.
- The Final Tank Closure and Waste Management Environmental Impact Statement provided an updated inventory basis, new modeling capabilities, and new decisions reached in the associated ROD that need to be incorporated into the CA.
- Pump & Treat systems, which were not evaluated in the original CA, have had significant impact on groundwater flow, contaminant transport, and contaminant removal from groundwater.

- Development of improved cleanup strategies and improvements from cleanup may lead to establishing points of compliance other than the core zone boundary used in the original CA.
- Receding groundwater levels in the unconfined aquifer have led to an improved understanding of future conditions for the flow system.
- The revised ERDF PA (2013) evaluated the updated inventory, as well as the expansion of the facility to about twice the size that was evaluated in the original CA.
- The geologic structural basis for groundwater models has continued to improve with additional data collection and interpretation.
- The risk assessment scenarios currently in use for the Hanford Site CERCLA and RCRA analyses differ from those evaluated in the original 1998 CA.
- The original CA was prepared before DOE required its contractor to apply NQA-1 standards for use of simulation software for environmental modeling. A new analysis, performed with current software tools qualified under DOE O 414.1D, *Quality Assurance*, standards and applied under current, compliant QA plans and procedures, is necessary.

The U.S. Department of Energy, Richland Operations Office (DOE-RL) concurs with the conclusions of the Enterprise Assessment's report with respect to its findings on the Composite Analysis.

Appendix A presents the history of the maintenance of the Hanford Site Composite Analysis, including all prior annual status reports.

## 1.1 Performance Assessments

Table 1-2 lists the Hanford Site PAs, the scope of the PAs, and the FY 2021 status with respect to phases (planning, scoping, analysis, and maintenance) as identified in DOE guidance for modeling at the Hanford Site (1301789, 2012, “Modeling to Support Regulatory Decisionmaking at Hanford”). Detailed summaries of activities associated with each of these PAs are provided in Sections 1.1.1 through 1.1.5.

### 1.1.1 200 East and 200 West Low-Level Burial Ground Performance Assessments

In the annual reviews of the Hanford Site Low-Level Burial Ground (LLBG) PAs for FY 2022 [DOE/RL-2022-45, *Annual Status Report (FY 2022): Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*; DOE/RL-2022-44, *Annual Status Report (FY 2022): Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*], projected dose estimates from radionuclide inventories disposed in the active LLBGs (at locations shown in Figure 1-1) from September 26, 1988 through September 30, 2022, were calculated using the dose estimate methodology developed in the original PAs (WHC-EP-0645, *Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*; WHC-SD-WM-TI-730, *Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*). These estimates were compared with performance objectives defined in DOE O 435.1, *Radioactive Waste Management*, companion documents DOE M 435.1-1;

DOE-STD-5002-2017, *Disposal Authorization Statement and Tank Closure Documentation*.

The performance objectives are currently satisfied. Operational waste acceptance criteria (HNF-EP-0063, *Hanford Site Solid Waste Acceptance Criteria*) and waste acceptance practices continue to be sufficient to maintain compliance with performance objectives.

#### **Relevance of the LLBG PAs to the Hanford Site Composite Analysis**

The LLBG PAs are supported by the Hanford Site Composite Analysis. Solid waste disposal constitutes one of the sources of radioactive waste inventory. The current estimated inventory disposed and projections of future inventory disposal in the LLBGs are refined regularly as additional data continue to be collected and reported through maintenance of the LLBG PAs. This updated information is pertinent to the composite analysis because of its potential to change the LLBG inventory

**Table 1-2. Hanford Site Performance Assessments in Planning, Scoping, Analysis, and Maintenance Phases and Fiscal Year 2021 Status**

Performance Assessment	Scope	FY 2021 Status
200 East LLBGs	This PA is for operation of the LLBGs located in the 200 East Area. The LLBGs are operational and continue to receive small, limited quantities of waste.	<u>Maintenance phase:</u> The original PA (WHC-SD-WM-TI-730) continues to be maintained per the approved 1997 maintenance plan (RFSH-9755566). A new PA for the active trenches in 200 East and 200 West LLBGs has been developed and has been reviewed by LFRG review team. Resolution of key and secondary issues identified by the LFRG review team are currently being evaluated by the LFRG Co-Chair.
200 West LLBGs	This PA is for operation of the LLBGs located in the 200 West Area. The LLBGs are operational and continue to receive small, limited quantities of waste.	<u>Maintenance phase:</u> The original PA (WHC-EP-0645) continues to be maintained per the approved 1997 maintenance plan (RFSH-9755566). A new PA is in development for the active LLBGs in both 200 East and 200 West, and a closure PA is expected to follow for the inactive LLBGs later.
Active LLBGs PA (new PA)	This PA will be for operation of the active LLBGs in 200 East and 200 West Areas (namely, Trenches 31, 34, and 94).	<u>Planning phase:</u> Work commenced on development of a new active LLBG PA in FY 2019 and continued in FY 2021. Rev. 0 of the new active LLBG PA was completed and submitted to LFRG. LFRG reviewed this PA in FY 2021 and provided findings. Preparation of Rev. 1 of this PA to resolve LFRG findings is in progress.
ERDF	This PA is for operation of a CERCLA disposal facility located between the 200 East and 200 West Areas. It is operational and continues to receive waste from Hanford Site CERCLA remedial activities.	<u>Maintenance phase:</u> A revised disposal authorization statement (CCN 173929) based on the revised PA was issued in early FY 2014. Maintenance activities under an approved maintenance plan (CP-60150) continued thereafter.
IDF	A PA for an ILAW disposal facility located in the 200 East Area was approved. This facility was constructed and is currently pre-operational. Plans call for use of this facility for future disposal of stabilized tank waste from the Hanford Site Tank Waste Treatment and Vitrification Plant (under construction). A new IDF PA is required to implement these plans.	<p><u>Analysis phase:</u> Rev. 0 of RPP-RPT-59958 (IDF PA) was completed in FY 2018 and submitted to LFRG for review, which identified 2 key and 30 secondary issues with the Rev. 0 PA and supporting documentation. A conditional ODAS was granted for the facility on June 29, 2018. The IDF PA was revised to address 1 key and 24 of the 30 secondary issues identified in the conditional ODAS. On August 13, 2018, Rev. 1 of the IDF PA was issued with LFRG concurrence to close 1 key issue and 24 secondary issues related to the PA. The remaining key issue requires that a waste acceptance criteria document be prepared to include the findings of the revised PA. Development of the waste acceptance criteria was initiated in the fourth quarter of FY 2018 and is expected to be completed in the third quarter of FY 2019. The remaining secondary issues are being addressed in revisions to the PA maintenance plan, PA monitoring plan, PA closure plan, and unreviewed waste disposal question procedure. Revisions to these documents were initiated in the fourth quarter of FY 2018 and are expected to be completed by the third quarter of FY 2019.</p> <p>The WIR determination approval process was initiated in the second quarter of FY 2018. The WIR is in public review under consultation with the NRC since in March 2019. Following the NRC and public comment period for the WIR, the IDF PA may need to be revised.</p>

**Table 1-2. Hanford Site Performance Assessments in Planning, Scoping, Analysis, and Maintenance Phases and Fiscal Year 2021 Status**

Performance Assessment	Scope	FY 2021 Status
WMA C	This PA will support eventual closure of the C Tank Farm single-shell tank facility following completion of tank retrieval activities.	<u>Analysis phase:</u> The analysis phase was conducted in FYs 2015 and 2016 following the modeling approach set forth in the summary analysis* approved by the Hanford Site Groundwater/Vadose Zone Executive Council. The PA was submitted to the LFRG in FY 2015. The WMA C PA was approved by the LFRG for release and further regulatory review and is currently undergoing regulatory review. In FY 2019, the review of the DOE M 435.1-1 PA document (RPP-ENV-58782) and a WIR evaluation document for WMA C was initiated in FY 2018 with the NRC in support of its consultation role with DOE-ORP. The NRC review was completed in FY 2020.
WMA A-AX	This PA will support eventual closure of the A-AX Tank Farm single-shell tank facilities following completion of tank retrieval activities.	<u>Planning and Analysis Phase:</u> Scoping and planning phase activities commenced in FY 2015 for a new PA, modeled after the scoping approach used for the WMA C PA. Work was suspended in FY 2016 due to funding issues. Work was reinitiated in FY 2017 and a preliminary PA was developed, completed, and submitted to ORP for review at the end of FY 2019. A consultation with the LFRG on the technical adequacy of the preliminary PA and PA updates occurred in FY 2021.

Note: Complete reference citations are provided in Chapter 9 of this document.

\*The summary analysis is a document for demonstration of compliance with DOE guidance provided in 1301789, 2012, “Modeling to Support Regulatory Decision making at Hanford,” which addresses the topical areas covered by both a given PA and TC & WM EIS, evaluation of analyses in the TC & WM EIS, and analyses planned for a given PA, with recommendations for updates to local scale models and a discussion of potential concerns.

1-6

CERCLA	=	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>	LLBG	=	low-level burial ground
DOE-ORP	=	U.S. Department of Energy, Office of River Protection	NRC	=	U.S. Nuclear Regulatory Commission
ERDF	=	Environmental Restoration Disposal Facility	ODAS	=	operating disposal authorization statement
FY	=	fiscal year	PA	=	performance assessment
IDF	=	Integrated Disposal Facility	TC & WM EIS	=	Tank Closure and Waste Management Environmental Impact Statement
ILAW	=	immobilized low-activity waste	WIR	=	waste incidental to reprocessing
LFRG	=	Low-Level Waste Disposal Facility Federal Review Group	WMA	=	waste management area




Figure 1-1. Location of the Low-Level Burial Grounds

For the 200 West Area LLBGs (DOE/RL-2021-57, *Annual Status Report (FY 2021): Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*), low-level waste (LLW) and mixed LLW were disposed in two lined trenches in the 218-W-5 Burial Ground (Trenches 31 and 34), which will continue to be used until they are either filled or closed. Overall, there are no substantive changes to primary PA assumptions and no changes to the PA analysis conclusion that compliance with DOE O 435.1 is being maintained. All performance objectives are currently satisfied, and operational waste acceptance criteria (HNF-EP-0063) and waste acceptance practices continue to be sufficient to maintain compliance with performance objectives. Estimates of inventory and associated dose estimates from future waste disposal actions are unchanged from previous years' evaluations, which indicates potential impacts well below performance objectives. Therefore, future compliance with DOE O 435.1 is expected.

For the 200 East Area LLBGs (DOE/RL-2021-58, *Annual Status Report (FY 2021): Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*), inventory and associated dose estimates from future waste disposal actions are unchanged from previous years' evaluations, which indicates potential impacts well below performance objectives. Therefore, future compliance with DOE O 435.1 is expected. Three naval reactor compartments were disposed in Trench 94 during the reporting period for the 200 East Area LLBGs. Overall, there are no substantive

changes to primary PA assumptions and no changes to the PA analysis conclusion that compliance with DOE O 435.1 is being maintained.

Dose estimate increases from disposed waste for groundwater contamination scenarios occurred only at the 200 West Area LLBGs and were essentially negligible. No dose increase is expected in 200 East Area LLBGs from the disposal of naval reactor compartments in Trench 94. Waste quantities disposed to these trenches in FY 2021 were 151.5 m<sup>3</sup> (5351.8 ft<sup>3</sup>) in Trench 31, 13.5 m<sup>3</sup> (475.3 ft<sup>3</sup>) in Trench 34, and 3,398 m<sup>3</sup> (119,999.4 ft<sup>3</sup>) in Trench 94.

DOE (2018) noted the following:

[T]he computational methods and some assumed parameters and conditions for the PAs for both 200 West Area and 200 East Area LLBGs have become outdated. The software used for both LLBG PAs can be executed only on obsolete computer operating systems. Section 5.3.3 lists several reasons for the rebuilding and reanalysis of the CA, which is currently under way. The PAs for the LLBG provide crucial source input to the CA. With the rebuilding of the CA, it is important to rebuild the LLBG PAs to maintain the required and expected QA standards of the analyses. (OFI-CHPRC-1)

DOE (2018) further noted:

The PA criteria for the 200 East and West Area LLBGs are currently satisfied. However, the 200 West Area PA will require rebuilding and reanalysis to support the reanalysis for the CA expected to be completed over the next three years.

In response to the report, DOE-RL directed CH2M HILL Plateau Remediation Company to commence developing a new PA for the active trenches in 200 East and 200 West LLBGs (namely, Trenches 31, 34, and 94). Work commenced in FY 2019 and continued in FY 2021. Draft A was completed and submitted to LFRG Co-Chair in September 2021. LFRG review team completed their review of the PA in FY 2022 and provided key and secondary issues. Draft B of this PA was developed to resolve the LFRG review comments and was submitted to the LFRG Co-Chair in September 2022. Resolution of key and secondary issues identified by the LFRG review team are currently being evaluated by the LFRG Co-Chair.

Another important consideration overlooked in the LLBG PAs maintenance reports is that these PAs were developed to meet DOE O 5820.2A, *Radioactive Waste Management*, which preceded DOE O 435.1. The PAs were developed to report a peak dose for a 10,000-year (rather than a 1,000-year) performance objective period. The small doses resulting from these PAs updated in the scaling methodology used for annual maintenance for over 20 years have not been explicitly presented as pertaining to a longer performance objective period than DOE O 435.1 requirements. Starting with the FY 2018 annual status reports, appropriate language, and footnotes for tabulated doses in maintenance documents are being applied to clarify the objective performance period of the original PAs and addenda for the LLBG PAs. The new active LLBG PA will report to DOE O 435.1 standards, including a comparison of performance objectives and measures to the 1,000-year compliance and postcompliance periods.

#### **Relevance of the IDF PA to the Hanford Site Composite Analysis**

*The IDF PA is supported by the Hanford Site Composite Analysis. Planned waste disposal at the IDF will constitute the largest source of radioactive waste inventory at the Hanford Site. Estimates of future inventory disposal of glass and secondary waste forms from the Hanford Tank Waste Treatment and Immobilization Plant and tank farms that are considered in the IDF PA must be incorporated into the composite analysis.*

### 1.1.2 Integrated Disposal Facility Performance Assessment

The Integrated Disposal Facility (IDF) is a near-surface disposal facility for low-level and mixed low-level waste generated at the Hanford Site. Waste that will be disposed of in the IDF includes vitrified low-activity waste produced at the Hanford Site Tank Waste Treatment and Immobilization Plant (WTP), secondary wastes from the WTP, and other Hanford secondary waste generated during RCRA-related activities. Figure 1-2 shows the location of the IDF. In a 2001 memorandum (Scott, 2001, “Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Revision 2”), DOE approved DOE/ORP-2000-24, *Hanford Immobilized Low-Activity Waste Performance Assessment: 2001 Version*. Continuation of the disposal authorization statement (DAS) (Frei, 2003, “Review of the Annual Summary of the Hanford Immobilized Low-Activity Waste Preformance Assessment for 2003”) was based in part on RPP-15834, *Integrated Disposal Facility Risk Assessment*. This PA is maintained in accordance with DOE/ORP-2000-01, *Maintenance Plan for the Hanford Integrated Disposal Facility Performance Assessment* until 2012 when the Tank Closure and Waste Management Environment Impact Statement (hereinafter referred to as the TC & WM EIS) (DOE/EIS-0391, *Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington*) was completed.




Figure 1-2. Location of the Integrated Disposal Facility

The first construction phase for IDF was completed on April 28, 2006, which included installing cell liners and leachate collection tanks (Figure 1-3). The IDF has been maintained under a pre-active life status since construction was completed. In accordance with the manual for DOE O 435.1, a waste incidental to reprocessing (WIR) determination and a waste DAS are needed to dispose of waste in the IDF.



**Figure 1-3. Photograph of the Integrated Disposal Facility First Expansion (Current Configuration)**

Revision of the original IDF PA (DOE/ORP-2000-24) was deferred from FYs 2006 through 2012 pending issuance of the TC & WM EIS (DOE/EIS-0391). On November 21, 2012, DOE issued the TC & WM EIS for the Hanford Site pursuant to the *National Environmental Policy Act of 1969* and implementing regulations (Council on Environmental Quality, 2005, *Regulations for Implementing the Procedural Provisions of the National Environmental Policy Act*; and 10 CFR 1021, “National Environmental Policy Act Implementing Procedures”). In the second half of FY 2014, DOE-RL authorized planning phase activities in preparation of a revised IDF PA, which included developing a project management plan and quality assurance (QA) project plan and conducting a technical review of existing data packages and TC & WM EIS models for IDF to prepare for the scoping phase. The annual status reports for the IDF PA were not prepared in FY 2012 due to funding prioritization and in recognition that a new PA was required to implement decisions in the TC & WM EIS Record of Decision (ROD) (78 FR 75913, “Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington”).

Management for preparing the revised IDF PA was transitioned from DOE-RL to the U.S. Department of Energy, Office of River Protection (DOE-ORP) on October 1, 2014. DOE-ORP and its tank operations contractor (Washington River Protection Solutions) completed the planning and scoping phase activities in FY 2015 and continued to meet with the Washington State Department of Ecology (Ecology) to discuss the PA models and parameters.

In December 2015, a summary analysis describing the modeling approach necessary to address comments received at the scoping workshops was approved by the DOE Hanford Site Groundwater/Vadose Zone Executive Council, and modeling for the updated PA commenced. The summary analysis is a tool used to meet DOE direction (1301789, 2012) by describing the technical approach to be taken in the PA, with justification for any departures from the TC & WM EIS modeling platform or approach. In FY 2016, modeling was performed for chemical and radionuclide releases from the immobilized low-activity waste and secondary waste that would be disposed of in the IDF. Subsequent travel through the vadose zone beneath the facility and subsequent transport through the saturated zone to the point of calculation 100 m (328 ft) downstream of the facility were also evaluated. Parameter sensitivity was evaluated using deterministic model runs documented in calculation reports completed in FY 2017. The deterministic analyses results were used to develop abstractions for use in a probabilistic, integrated system model completed in the third quarter of FY 2017. The system model was used to evaluate parameter uncertainty and assess the long-term dose and groundwater impact from constituents that would be released from the facility over the next 10,000 years.

Washington River Protection Solutions completed a draft of the revised IDF PA in the fourth quarter of FY 2017 that later was issued as RPP-RPT-59958, *Performance Assessment for the Integrated Disposal Facility, Hanford Site, Washington*, Rev. 0. In FY 2018, the IDF PA Rev. 0 was reviewed by the Low-Level Waste Disposal Facility Federal Review Group (LFRG) and the U.S. Department of Energy, Headquarters (DOE-HQ). The LFRG identified 2 key and 30 secondary issues with the Rev. 0 PA and supporting documentation. However, the LFRG recommended that an operating disposal authorization statement (ODAS) be granted for the facility. On June 29, 2018, the Associate Principal Deputy Assistant Secretary for Regulatory and Policy Affairs issued a conditional ODAS for the IDF. The IDF PA was revised to address one key issue and 24 of the 30 secondary issues identified in the ODAS. On August 13, 2018, Rev. 1 of the IDF PA (RPP-RPT-59958, *Performance Assessment for the Integrated Disposal Facility, Hanford Site, Washington*, Rev. 1) was issued with LFRG concurrence to close 1 key and 24 secondary issues related to the PA. The remaining key issue required that a waste acceptance criteria document be prepared to include the findings of the revised PA. Development of the waste acceptance criteria document was initiated in the fourth quarter of FY 2018. The waste acceptance criteria were completed in FY 2019 and were provided to the LFRG for review and comment. Five of the six remaining secondary issues have been addressed in revisions to the PA maintenance plan, PA monitoring plan, PA closure plan, and unresolved disposal question procedure. Resolution of these five secondary issues was approved by the LFRG in November 2019. The final secondary issue was addressed when the revision to the Hanford Site Composite Analysis was completed. In September 2020, a letter to the DOE-RL site manager from both the director of the U.S. Department of Energy, Office of Assistant Secretary for Environmental Management (DOE-EM) Office of Waste Disposal and acting director of the DOE-EM Office of Regulatory Compliance acknowledged the resolution of the LFRG key and secondary issues and removed the conditional status of the ODAS.

The WIR determination approval process was initiated in the second quarter of FY 2018. A draft WIR was initiated and has undergone several review cycles with DOE-HQ. In May 2020, the U.S. Nuclear Regulatory Commission (NRC), under consultation with DOE, began a review of the draft WIR evaluation; a public review commenced at the same time. The 6-month-long public comment period ended in November 2020. The NRC provided DOE with 26 requests for additional information, which have been addressed in DOE/ORP-2021-02, *Department of Energy Responses to the Nuclear Regulatory Commission Request for Additional Information on the Draft Waste Incidental to Reprocessing Evaluation for Vitrification of Low Activity Waste*. In May 2022, the NRC published the results of their independent review in *Technical Evaluation Report: Draft Waste Incidental to Reprocessing Evaluation for Vitrified Low-Activity Waste Disposed Onsite at the Hanford Site, Washington* (hereafter referred to as

the VLAW WIR TER). The VLAW WIR TER concluded that DOE had met the NRC's criteria for determining that vitrified low-activity waste could be managed as low-level waste. The VLAW WIR TER did provide several recommendations, which should be addressed in an updated evaluation and in future revisions of the IDF PA. In addition, review comments from Ecology were received in November 2020. The additional information requested by NRC and comments from Ecology, along with new information collected as part of the IDF Maintenance Program resulted in updated analyses that were completed in FYs 2021 and 2022. These updated analyses were incorporated into a final WIR evaluation. The draft WIR evaluation was revised in FYs 2021 and 2022 to address the comments received and included additional information on solid secondary waste. At the end of FY 2022, the revised WIR evaluation was completed, and a draft of the waste determination letter had been prepared. The final WIR evaluation with responses to all comments and the final WIR determination are expected to be published in the second quarter of FY 2023.

Infrastructure upgrades (e.g., utility installation, security installation, administration building construction, and expanding groundwater monitoring network) at the IDF are underway. However, the IDF remains in "Pre-Active Life," which refers to the facility maintenance period between final construction and the start of active life. At the end of FY 2022, a RCRA permit (WA7890008967, *Hanford Facility Resource Conservation and Recovery Act (RCRA) Permit, Dangerous Waste Portion for the Treatment, Storage, and Disposal of Dangerous Waste* [hereinafter referred to as the Hanford RCRA Permit]) modification was underway to change the status from "Pre-Active Life" to "Active Life." Low-activity waste vitrification hot commissioning is forecast to begin in FY 2024.

As required by DOE M 435.1, the IDF PA change control process performs special analyses to evaluate new or changed information that could affect the conclusions of the IDF PA or invalidate the ODAS. Each year completed analyses are used to affirm that the ODAS is still valid. Once completed and approved by DOE-ORP, and if necessary, the LFRG, these special analyses become part of the technical basis supporting the validity of IDF PA and will be incorporated into the next major revision of the IDF PA. In FY 2019, two special analyses were performed. One special analysis evaluated a proposed waste form for liquid secondary waste that was not evaluated in the PA. A powder waste form for liquid secondary waste instead of a solidified waste form was evaluated. Until a decision is made to approve a powder waste form for liquid secondary waste, the contemplated change does not impact the simulated releases provided for the composite analysis update that is underway. A second special analysis evaluated intruder protection requirements necessary to accommodate higher strontium-90 concentrations in vitrified waste. Recent flowsheet modeling that did not account for strontium-90 removal during Direct-Feed Low-Activity Waste operations indicated a potential to have higher strontium-90 concentrations in vitrified waste. The implications on disposal limits were evaluated, but the results of this special analysis would not change the input to the composite analysis.

In FY 2020, two additional special analyses were performed. One special analysis evaluated the potential impacts from periodic maintenance of the Wet Electrostatic Precipitator in the low-activity waste vitrification plant. The periodic maintenance of the Wet Electrostatic Precipitator to maintain efficiency allows more volatile radionuclides to pass through to the offgas treatment system resulting higher loadings on the secondary waste in the offgas treatment system. The impacts of the regular maintenance were not considered in the flowsheet that developed the radionuclide inventories for the secondary waste simulated in the PA. The special analysis showed that secondary waste could exceed disposal limits for technetium-99 and that the impact to groundwater could exceed drinking water standards (DWSs) beyond 1,000 years after closure. A second special analysis investigated the potential consequences of leaving cooling water in the used low-activity waste melters when they are disposed of in the IDF. For safety reasons during an off-normal event, the cooling system was not designed to drain liquids. Leaving liquid in the system is being considered, and an analysis evaluating the potential impact to the release of

radionuclides and hazardous chemicals from other waste streams was requested. Additional water leaking from the cooling system in the future was not considered in the PA simulations. The special analysis concluded that the peak groundwater concentrations would increase by less than 1% if the cooling water were left in the used low-activity waste melters.

In FYs 2021 and 2022, nine additional special analyses were performed. These special analyses addressed new information regarding the projected inventory in the different waste streams that will be disposed of in the IDF and well as information on the performance of the waste streams to immobilize the inventory after it is placed into the IDF. In addition, these special analyses evaluated changes to the flow and transport properties of the vadose zone sediments underneath the IDF and in the aquifer. A cumulative analysis of all of these changes on the two radionuclides that provide the basis for the conclusions of the IDF PA was completed in one of the special analyses. The cumulative evaluation was initiated in FY 2021 but was not finalized until after the FY 2022 special analyses were performed.

- One special analysis completed in FY 2021 evaluated the impact of new moisture content information in the Hanford formation unit 2 (H2) sand that result in a change of the H2 sand hydraulic property values. Sensitivity analyses performed with the updated H2 sand hydraulic property values resulted in a change in the predicted fate and transport of radionuclides in the vadose zone beneath the IDF and the corresponding timing of the peak groundwater concentration and all-pathways dose at the point of compliance.
- A second special analysis initiated in FY 2021 (completed in FY 2022) investigated the impact of new information collected as part of the IDF maintenance program related to the hydraulic and transport properties of grouts used to encapsulate debris secondary solid waste (SSW) and solidify/stabilize nondebris SSW. This new information was combined with the higher technetium-99 loading on HEPA filters identified in the Wet Electrostatic Precipitator maintenance special analysis completed in FY 2020 to develop revised predictions of release rate of mobile radionuclides from SSW.
- A third special analysis initiated in FY 2021 (completed in FY 2022) investigated the impact of new information collected as part of the IDF maintenance program on the corrosion of immobilized low-activity waste (ILAW) glass. This new information included an assessment of the impact of Stage III glass corrosion on radionuclide release rates from ILAW glass.
- The fourth special analysis initiated in FY 2021 but completed in FY 2022 investigated the combined impact of the other three special analyses completed in FY 2021 as well as additional updated vadose zone and saturated zone information collected as part of the IDF maintenance program. This special analysis evaluated the impact of the updated information on the fate and transport of technetium-99 and the associated groundwater concentration and dose at the point of assessment. The special analysis determined that the as-analyzed IDF would not comply with the DOE M 435.1-1 all-pathways dose performance objective without a design modification or other operational or disposal constraints, including but not limited to revised waste acceptance criteria. The special analysis conclusion is a result of the increased release rate of technetium-99 from the HEPA filters combined with the reduced vadose zone radionuclide transport time associated with the updated H2 sand hydraulic properties. The DOE LFRG Site Representative and LFRG Co-chairs were made aware of the preliminary results of this analysis and recommended additional modeling to help inform future decisions.
- A fifth special analysis evaluated the potential impacts of filling the voids in a used low-activity waste melters with grout that could lead to accelerated rates of the vitrified waste left in the melters

when they are disposed of in the IDF. Although the high-pH effluents that flowed past the grout onto the residual waste left in the melters caused accelerated corrosion rates, the volume and inventory of waste impacted by the accelerated corrosion rate would not in of itself change the conclusions of the PA provided that the grouted melters were disposed of away from the containers of vitrified waste.

- Prior to finalization of the FY 2021 special analysis that determined that the as-analyzed IDF would not comply with the DOE M 435.1-1 all-pathways dose performance objective, another special analysis was performed in FY 2022 that updated the exposure factors and dose coefficients used in the dose calculations that are compared to performance objectives. This analysis incorporated recent updates to exposure factors and dose coefficients published by EPA and DOE. Updated exposure factors are reported in chapter-specific updates to EPA/600/R-090/052F, 2011, *Exposure Factors Handbook: 2011 Edition*. Updated dose coefficients for ingestion and inhalation are reported in DOE-STD-1196-2021, *Derived Concentration Technical Standard*. Updated dose coefficients for external exposure to contaminated soil are reported in EPA-402-R19-002, *Federal Guidance Report No. 15, External Exposure to Radionuclides in Air, Water, and Soil*. After incorporation of the updated exposure factors and dose coefficients, the waste concentrations that are protective to a member of the public following a hypothetical inadvertent intrusion into the waste changed. These concentration limits define numerical concentration levels that each waste stream that is disposed of in the IDF must be below to stay below dose limit performance measures specified in DOE M 435.1-1. Consequently, these concentration limits are included in the IDF waste acceptance criteria (IDF-00002, *Waste Acceptance Criteria for the Integrated Disposal Facility*) and must be revised when input to the calculations are revised. At the end of FY 2022, the updated concentration limits had not yet been incorporated into a revision to IDF-00002.
- An additional special analysis that updated waste stream inventories to align with more recent flowsheet modeling of the WTP were also performed in FY 2022. The cumulative impact of all these changes was evaluated in the special analysis that was started in FY 2021. The cumulative impact analysis concluded that the IDF could still meet DOE M 435.1-1 performance objectives if an inventory limit for technetium-99 in encapsulated debris SSW was imposed.
- A special analysis was performed in FY 2022 to develop the inventory limit for technetium-99 in encapsulated debris solid secondary waste. The updated concentration limits and technetium-99 inventory limit for encapsulated debris waste will be incorporated into the IDF waste acceptance criteria in a FY 2023 update to IDF-00002.
- A special analysis was performed in FY 2022 that evaluated newly identified waste streams that were not included in the secondary waste forecast evaluated in the IDF PA. These new waste streams are from on-site sources (e.g., WTP, tank farms, and 222-S Laboratory) that produce liquid waste streams that would be solidified prior to disposal in the IDF. This analysis also includes additional solid secondary waste streams generated at the 222-S Laboratory that are currently disposed of at ERDF but would be disposed of in the IDF as soon as it begins accepting waste. Based on the completed updates to the IDF PA technical basis, the FY 2022 Annual Summary Report for the IDF PA will detail that a new IDF PA base case is established by the recently completed special analyses and that the ODAS would remain valid once an inventory limit for technetium-99 in the encapsulated debris solid secondary waste is added to the IDF waste acceptance criteria.

### 1.1.3 Waste Management Area C Performance Assessment

Waste Management Area (WMA) C includes the C Tank Farm and ancillary equipment located in the eastern portion of the 200 East Area (Figure 1-4). In FY 2009, a scoping process was initiated to

develop the risk assessments and PAs required for closure of WMA C. A series of working sessions were held with the regulatory agencies and stakeholders to solicit input and obtain a common understanding regarding the scope, methods, and data to be used in the planned risk assessments and PAs. In addition to DOE-ORP, Ecology, and Hanford Site contractors, the working session members also included representatives from the U.S. Environmental Protection Agency (EPA), NRC, interested Tribal Nations, other stakeholder groups, DOE-RL personnel and their contractors involved with groundwater/vadose zone or composite analyses efforts, and members of the interested public. NRC staff involvement in the working sessions is a technical resource to assess whether required waste determinations by DOE-RL for the WIR are based on sound technical assumptions, analyses, and conclusions relative to applicable incidental waste criteria. The scoping phase was completed in FY 2011.




Figure 1-4. Location of Waste Management Area C

An initial analysis (modeling) phase of activities resulting from the WMA C PA scoping process completed in FY 2011 was delayed until FY 2013, awaiting issuance of the final TC & WM EIS (DOE/EIS-0391). In FY 2014, an initial set of PA modeling results of impacts from a closed WMA C was completed for the groundwater pathway, air pathway, and hypothetical inadvertent intruder. Key elements of the WMA C PA modeling effort included implementing the conceptual model for flow and contaminant transport into a three-dimensional numerical model of flow and transport at WMA C implemented in the STOMP (Subsurface Transport Over Multiple Phases) computer code and implementing the conceptual model of flow and transport in a system-level model of WMA C based on the GoldSim® computer software, which included implementing waste release models used to represent contaminant release from waste residuals remaining in tanks and ancillary equipment and exposure scenarios used to evaluate performance objectives and measures for the PA. The GoldSim-based system model has also been used to perform a system sensitivity and uncertainty analysis required as a part of the DOE M 435.1-1 PA effort.

In FY 2015, an initial set of PA modeling results for WMA C was supplemented with results from additional modeling cases that were identified in stakeholder interactions during FY 2014. Results of these analyses are being used to satisfy the requirements outlined in Appendix I of Ecology et al., 1989, *Hanford Federal Facility Agreement and Consent Order*

(hereinafter referred to as the Tri-Party Agreement) for assessing the radiological impacts of waste residuals in a closed WMA C under DOE O 435.1 and evaluating hazardous chemical impacts for the same wastes under RCRA.

In September 2015, two detailed documents summarizing the results of the radiological and hazardous chemical impact analyses of tank residuals left in a closed WMA C were completed and transmitted for technical review by DOE-ORP. A revised draft of the WMA C PA (RPP-ENV-58782, *Performance Assessment of Waste Management Area C, Hanford Site, Washington*, Rev. 1) for the radiological impacts from tank residuals was submitted for review by DOE-ORP to the LFRG on December 30, 2015. This review was intended to ensure that the PA was technically sound prior to it being formally submitted to the NRC to initiate consultation under a process like that governed by Section 3116 of the *Ronald W. Reagan National Defense Authorization Act for Fiscal Year 2005*. The results of the LFRG review demonstrated that the PA is technically adequate for its intended purpose. DOE-ORP was then authorized to transmit the PA formally to the NRC for consultation and to EPA, Ecology, and the public for review and comments. In addition to the PA, a draft WIR evaluation was prepared for NRC consultation.

### **Relevance of the WMA C PA to the Hanford Site Composite Analysis**

*When complete, the WMA C PA will be supported by the Hanford Site Composite Analysis.*

*Other PAs discussed in this section were developed to obtain authorization for disposal of radioactive waste in disposal facilities constructed for this purpose. The WMA C PA differs in this respect: its purpose is to authorize closure of a tank waste system with residual waste remaining after retrieval as a disposal system.*

*As the WMA C PA is completed, the information on residual tank waste inventory and predicted releases will serve to update the basis of the Hanford Site Composite Analysis. Other WMA PAs will follow in the future, providing further refinement.*

---

® GoldSim is a registered trademark of GoldSim Technology Group, LLC, Issaquah, Washington.

In September 2016, the following four complementary reports that met the intent of Tri-Party Agreement Appendix I (Ecology et al., 1989) requirements for a PA were transmitted to DOE-ORP for further review by NRC and Ecology:

- RPP-ENV-58782, which addresses the radiological impacts of residual wastes left in tanks and ancillary equipment to meet regulatory requirements in DOE M 435.1-1.
- RPP-RPT-59197, *Analysis of Past Tank Waste Leaks and Losses in the Vicinity of Waste Management Area C at the Hanford Site, Southeast Washington*, which provides input to the baseline risk assessment update (RPP-RPT-58329, *Baseline Risk Assessment for Waste Management Area C*).
- The baseline risk assessment was conducted to support a RCRA facility investigation for WMA C (RPP-RPT-58339, *Phase 2 RCRA Facility Investigation Report for Waste Management Area C*).
- RPP-ENV-58806, *RCRA Closure Analysis of Tank Waste Residuals Impacts at Waste Management Area C, Hanford Site, Washington*, addresses regulatory requirements in WAC 173-303, “Dangerous Waste Regulations.”

In FY 2019, the review of the DOE M 435.1-1 PA document (RPP-ENV-58782) and the draft WIR evaluation for WMA C (DOE/ORP-2018-01, *Draft Waste Incidental to Reprocessing Evaluation for Closure of Waste Management Area C at the Hanford Site*), which was initiated in FY 2018 with NRC in support of its consultation role with DOE-ORP, continued. As a part of the consultation, NRC submitted a set of requests for additional information to DOE by letter dated April 30, 2019. DOE-ORP expended efforts to develop responses to the NRC RAIs through the end of FY 2019.

Review of the other three WMA C analysis complementary documents initiated with Ecology in FY 2017 also continued through the end of FY 2019.

In FY 2020, DOE-ORP provided its formal responses to the NRC RAIs on October 22, 2019 in ORP-63747, *Comment Responses for the NRC Staff Request for Additional Information on the Draft Waste Incidental to Reprocessing Evaluation for Waste Management Area C*. As a final deliverable for their consultation with DOE-ORP, NRC issued their Technical Evaluation Report of the WMA C WIR Evaluation and PA to DOE-ORP by letter dated May 11, 2020.

Updates to the WMA C PA and final WIR evaluation (DOE/ORP-2020-03, *Final Waste Incidental to Reprocessing Evaluation for Closure of Waste Management Area C at the Hanford Site*) based on NRC and internal review comments were completed by the end of FY 2020 and revisions of both the WMA C PA and WIR evaluation was submitted to DOE to be cleared for public release in September 2020.

In FY 2020, the comment resolution process with Ecology on the other three complementary WMA C analysis documents was completed in August 2020. Updates to these three WMA C documents based on Ecology and related internal review comments were completed by the end of FY 2020 and revisions for all three documents were submitted to DOE-ORP to be cleared for public release in early FY 2021.

In FY 2021, public release process for all four complementary WMA C analysis documents to address both NRC and Ecology comments was completed. DOE-ORP also worked closely with DOE-HQ to finalize the final WIR evaluation and closure plans for WMA C to support the issuance of a waste determination for managing residual waste left in WMA C tanks and ancillary equipment as LLW.

As required by DOE M 435.1, the WMA C PA change control process performs unresolved waste management question (UWMQ) evaluations and in some cases, special analyses to evaluate new or changed information that could affect the conclusions of the WMA C PA. In years 2020 and 2021,

completed analyses are used to affirm that the WMA C PA is still valid. Once completed and approved by DOE-ORP, and if necessary, the LFRG, these special analyses become part of the technical basis supporting the validity of WMA C PA and will be incorporated into the next major revision of the WMA C PA.

During 2020-2022, the following UWMQs were evaluated:

**Updated Residual Volume for 241-C-106 tank:** An updated estimate of tank residual waste volume in single-shell tank (SST) 241-C-106 in WMA C has been documented in *RPP-RPT-62021, 2019 Camera/CAD Modeling System Waste Volume Estimate for Tank 241-C-106*.

The tank residual volume and associated waste residual inventory for SST 241-C-106 in WMA C evaluated in the RPP-ENV-58782, Rev. 0 is based on volumes originally estimated using in RPP-19866, *Calculation of the Post-Retrieval Waste Volume Determination in Tank 241-C-106*. The total volume was estimated at 10,486.9 L (370.3 ft<sup>3</sup>) with a 95% UCL of 13,318.9 L (470.3 ft<sup>3</sup>). These residual waste volume estimates for SST 241-C-106 bound the updated residual waste volume estimates for SST 241-C-106 of 8,968.9 L (316.7 ft<sup>3</sup>) with a 95% UCL of 9,484.4 L (334.9 ft<sup>3</sup>) documented in RPP-RPT-62021. Therefore, no additional UWMQ evaluation or special analysis related to this updated residual waste volume for SST 241-C-106 is required.

Consequently, no further action was taken on this UWMQ.

**Updated estimate of tank residual waste volumes and inventories for all SSTs in WMA C.** An updated estimate of tank residual waste volumes and inventories for all SSTs in WMA C has been documented in *RPP-RPT-42323, Post-Closure Hanford C-Farm Tank and Ancillary Equipment Residual Waste Inventory Estimates*.

RPP-RPT-42323 incorporates additional data obtained and changes in tank inventories through January 1, 2019 and presents postretrieval residual waste inventory estimates in C-Farm SSTs and ancillary equipment. The revised estimates of waste volumes and inventories provide a change in both residual waste volumes and inventories evaluated in the initial WMA C PA (RPP-ENV-58782, Rev. 0). A comparison of the new waste volume and inventory estimates with those evaluated in the initial WMA C PA would suggest the inventories evaluated in the PA provide a bounding analysis of groundwater pathway impacts. However, because of new estimates of waste concentration are higher for certain key radionuclides (see attached workbook), inadvertent intruder doses from some sources could have higher impacts than estimated in the initial PA. It is recommended, for transparency's sake, that a special analysis of groundwater and inadvertent intruder impacts for the base case evaluated in the initial WMA CPA be performed with the new waste volumes and inventories from RPP-RPT-42323 to document potential impacts using these estimates for future reference.

Consequently, a special analysis was conducted to evaluate these conditions for radiological constituents (RPP-CALC-64406, *Special Analysis of Updated 2019 Tank Residual Waste Volumes and Inventories for Single-Shell Tanks in Waste Management Area C*). There are no measurements of the residual inventory for ancillary equipment (C-301 catch tank, 244-CR vault tanks, and sump pits, diversion boxes, and waste transfer pipelines). Consequently, the only update to the ancillary equipment inventory was to base it on the updated average composition of waste for C Farm SSTs, which was a very small change. Updates of residual inventories in Tanks C-102, C-105, and C-111 are significantly lower than in the original PA estimates, while the remaining tanks are negligibly different or identical to their prior assumed values. The estimated technetium-99 inventory,

the primary dose contributing radionuclide in the groundwater pathway, has been reduced from about 14.7 to 2.4 Ci. As a result, the peak all-pathways and groundwater doses for the special analysis are about an order of magnitude lower than that calculated in the original PA.

Inadvertent intrusion analyses were conducted for several potential scenarios and several potential assumptions regarding the end of institutional control at the Hanford Site. The evaluation of alternative time periods for the potential time of intrusion was undertaken for consistency with DOE-0431, *Recommendations for Institutional Control Time Period for Conducting DOE Order 435.1 Performance Assessments at the Hanford Site*. The calculated doses in the special analysis from inadvertent intruder scenarios were lower compared to the original PA and met their appropriate performance measures.

The dose contribution from the air pathway in the performance assessment was negligible; consequently, no calculations were performed for the air pathway in this special analysis.

A special analysis was also conducted to evaluate these conditions for hazardous chemicals (RPP-CALC-64598, *Special Analysis of Post-Closure Groundwater Impacts from Updated Tank Residual Waste Volumes and Hazardous Chemical Inventories for Single-Shell Tanks in Waste Management Area C*). The special analysis concluded the following:

“Except for aluminum, total uranium and cyanide, the updated residual inventory estimates are lower than the estimates used in the Waste Management Area C post-closure groundwater Impacts analysis. While nitrate was the primary non-cancer hazard contributing chemical in the base case, the inventory has been reduced from 36,100 kg to 1,730 kg. The estimated cyanide inventory, the primary non-cancer hazard contributing chemical for the special analysis, has increased from about 0.684 kg to 23.7 kg. As a result, the tap water (residential) scenario non-cancer hazards for the Special Analysis are higher (increased from 0.07 to 0.21) than that calculated in the post-closure groundwater impacts analysis (base case).”

**Bio-Concentration Factor Values for Hydrogen.** In 2020, it was discovered in review of models used in the Composite Analysis that the bio-concentration factor values for hydrogen (i.e., tritium) that have been used in the WMA C PA calculations were too high and need to be corrected. The values for hydrogen that need to be corrected are provided in Table 6-23 of RPP-ENV-58782, Rev. 1. The current PA values and the updated new values for bio-concentration factors in Table 6-23 are provided in Attachment 1 of RPP-ENV-58782.

The evaluation of this UWMQ stated the following:

“The new BCF values recommended for use in the WMA C PA (RPP-ENV-58782) has no impact on current impact evaluation because hydrogen (i.e., tritium) in residual wastes in tanks and ancillary equipment decays to very low levels by the time it reaches groundwater and is not a dose driver in the groundwater pathway in the Current WMA C PA evaluation.

However, three actions will be taken as a result of this information:

- BCF values for hydrogen in Table 6-23 of RPP-ENV-58782 will be corrected as shown in Attachment 1.

- BCF values for hydrogen will also be updated in the System Model associated to RPP-RPT-58498, Rev. 0a that uses these factors.
- BCF values for hydrogen will also be updated in Table N-3 of RPP-ENV-58813, Rev. 1a.”

No further action was necessary for corrective actions for this UWMQ.

**Change in Facility Closure Date.** In the original WMA C PA, the date of closure was assumed at year 2020. This evaluation examined the potential impacts to facility releases, particularly for ancillary equipment including waste transfer pipelines, from later closure dates including the potential for the later placement of the engineered surface barrier over WMA C. In addition, in the original PA, the areal extent of the engineered barrier was conservatively placed just over the excavated SST area at WMA C leaving some parts of the ancillary equipment uncovered by the surface barrier system. This activity would also evaluate the potential impacts for more realistic placement of the engineered barrier over all the ancillary equipment within the tank farm as well as areas of unplanned releases associated with WMA C adjacent to and outside of the tank farm fence line.

The evaluation of this UWMQ stated the following:

“While not required by this evaluation, a special analysis is still recommended to:

- quantitatively evaluate the potential impacts on resulting constituent releases and groundwater impacts for the base case from ancillary equipment, particularly waste transfer pipelines, from delays in the assumed site closure and final placement of an engineered surface barrier at WMA C.
- quantitatively evaluate the potential impacts on resultant constituent releases and groundwater impacts in the base case from ancillary equipment, particularly waste transfer pipelines, from a placement of an engineered surface barrier that covers all ancillary equipment, particularly waste transfer pipelines, and areas of unplanned releases associated with WMA C outside of the tank farm fence line.”

A special analysis on this topic (RPP-CALC-64657, *Special Analysis – Reanalysis of Lateral Extent and Timing of Surface Barrier Placement in Waste Management Area C Performance Assessment*) was released in 2021. The analysis evaluated several alternative assumptions about the placement of the surface barrier.

The first analysis evaluated the effect of a surface barrier emplaced in 2020 (consistent with the original PA), but with the extent of the surface barrier consistent with the barrier described in Appendix K of RPP-RPT-49701, *Waste Management Area C – Conceptual Design Report*. This barrier has greater lateral extent than the one evaluated in the original PA. It was found that the extended barrier led to slightly higher concentrations at the compliance point compared to the original PA, as a result of decreased dispersion in the vadose zone. The increase in calculated concentration was small, and not significant for compliance.

RPP-CALC-64657 also evaluated the effect of delayed construction of the surface barrier using three sensitivity analyses. Results were shown for assumed surface barrier construction in 2020 (for consistency to the original PA assumption), an assumed delay of construction until 2070, and an assumed delay until 2070, but with an interim barrier constructed in 2030.

**Updated Version of STOMP with Three-Component Dispersity.** Reevaluation of PA results with updated version of STOMP that now has the capability to evaluate longitudinal, transverse, and vertical dispersivity. The previous version of STOMP has the capability to evaluate longitudinal and transverse dispersivity.

The evaluation of this UWMQ stated the following:

“While not required by this evaluation, a special analysis is still recommended to:

- quantitatively evaluate the potential impacts on resulting groundwater concentrations for tank residual wastes in the PA base case from the use of the updated STOMP code that contains the capability to evaluate longitudinal, transverse, and vertical dispersivity at WMA C. The special analysis will examine the impacts of this updated capability on a selected [sic] case related to the analysis past leaks at WMA C.”

This special analysis is still in the process of being and is expected to be completed in FY 2023.

**Impact of Changes in Exposure Scenario-related Parameters.** Newly published Federal Guidance Report (FGR) No. 15 (EPA-402/R19/002, *Federal Guidance Report No. 15: External Exposure to Radionuclides in Air, Water, and Soil*) provides external gamma DCFs for Adult. The current guidance from EPA is to use the new values instead of values published in FGR No. 12 (EPA-402-R-93-081, *Federal Guidance Report No. 12, External Exposure to Radionuclides in Air, Water, and Soil, Office of Radiation and Indoor Air*).

Parameter uncertainty exists in the intake rates used in the groundwater pathway dose calculations. However, for the WMA C PA calculations, 95th percentile values were used conservatively for dose calculations. The uncertainty in intake rate parameters needs to be evaluated to understand the impact on dose.

This evaluation examined the impact of changes to exposure scenario-related parameters on dose for the WMA C PA (RPP-ENV-58782, Rev. 1) for the groundwater pathway and inadvertent intruder scenario. Also perform evaluation by incorporating the uncertainty in intake rate parameters.

The evaluation of this UWMQ stated the following:

“A special analysis is required to reevaluate selected WMA C PA base case modeling results based on changes in exposure-related parameters in the updated DOE Technical Standard (DOE-STD-2021-1196, 2021, “DOE Standard *Derived Concentration Technical Standard*”) released in CY 2021. The most current analysis is documented in the WMA C PA results developed for the most current residual inventories in FY 2020 (RPP-CALC-64406, Rev. 0 [UWMQ-WMA-C-2020-002-SA])”

A special analysis (RPP-CALC-64865) has been conducted to evaluate this UWMQ was completed and released in June of 2022. Results of the special analysis using updated groundwater pathway and inadvertent intruder exposure-related factors should very little difference between these cases and base case results provided in the original PA (RPP- ENV-58782, Rev. 1).

**Changes in updated DOE Technical Standard (DOE-STD-1196-2021).** PA results (RPP-ENV-58782, *Performance Assessment of Waste Management Area C, Hanford Site, Washington*, Rev. 0) need to be reevaluated based on changes in updated DOE Technical Standard (DOE-STD-1196-2021) released in calendar year 2021.

The evaluation of this UWMQ stated that:

“A special analysis is required to reevaluate selected WMA C PA base case modeling results based on changes in exposure-related parameters in the updated DOE Technical Standard (DOE-STD-2021-1196, 2021, "DOE Standard Derived Concentration Technical Standard) released in CY 2021. The most current analysis is documented in the WMA C PA results developed for the most current residual inventories in FY 2020 (RPP-CALC-64406, Rev. 0 [UWMQ-WMA-C-2020-002-SA])”.

A special analysis was conducted under the IDF PA maintenance to evaluate this UWMQ for the WMA C PA (RPP-CALC-61013, *Groundwater Pathway Dose Calculation for the Integrated Disposal Facility Performance Assessment*). Section 7.6.4 the calculation discusses the general impacts of changes in exposure-related parameters in the updated DOE Technical Standard on results for the WMA C PA.

In FY 2022, an initial PA maintenance status report for maintenance activities in FY 2020 and 2021 (RPP-RPT-63770, *2021 Waste Management Area C Performance Assessment Maintenance Status*) was also prepared and has been reviewed and approved by ORP. This status report provides a summary of the UWMQ evaluations being done under PA maintenance since the PA was updated in FY 2020.

This PA maintenance status report also provides a summary of detailed surface barrier modeling that was conducted under maintenance in FYs 2020 and 2021. Detailed modeling of modified RCRA Subtitle C surface barrier planned for tank farm areas has continued in FY 2022.

In FY 2022, an earlier draft of the WMA WIR evaluation that was updated following the VLA WIR TER went through some additional formatting and technical editing in preparation of an upcoming DOE-HQ review in 2023.

The WMA C PA, WIR evaluation update and closure plans will be used with WMA C PA Maintenance Plan, the Monitoring Plans, and the Maintenance Status Report to support the DOE-HQ decision related to a final tank closure authorization statement for WMA C in FY 2023.

Past and future updates to the Composite Analysis have adopted the tank release and vadose zone transport modeling results from the current and future updates to the WMA C PA.

### 1.1.4 Environmental Restoration Disposal Facility Performance Assessment

DOE/RL-2022-46, *Annual Status Report (FY 2022): Performance Assessment for the Environmental Restoration Disposal Facility*, provides the annual status of the ERDF PA. Constructed in 1996 to receive waste generated by CERCLA remediation areas within the Hanford Site, ERDF is an active operating disposal facility managed by the Central Plateau Cleanup Company (CPCCo) for DOE-RL (Figure 1-5). This section reviews the PA activities during FY 2022. Additional information about ERDF disposal operations during FY 2022 is provided in Section 1.3.3.2.

In 1995, EPA authorized ERDF operations through EPA/ROD/R10-95/100, *Declaration of the Interim Record of Decision for the Environmental Restoration Disposal Facility*, and by DOE-RL with a DAS (Scott, 2001) in accordance with DOE O 5820.2A. The primary technical analyses supporting approval to operate include the remedial investigation (RI)/feasibility study (FS) completed in 1994 (DOE/RL-93-99, *Remedial Investigation and Feasibility Study Report for the Environmental Restoration Disposal Facility*) for the ERDF ROD and a preliminary PA analysis (BHI-00169, *Environmental Restoration Disposal Facility Performance Assessment*) to address DOE O 5820.2A requirements.

A crosswalk analysis (Dronen, 1996, “Environmental Restoration Disposal Facility CERCLA/DOE Order 5820.2a Roadmap”) was completed to show that DOE O 5820.2A facility performance requirements would be satisfied. DOE-RL determined that the RI/FS and the preliminary PA analysis adequately evaluated the ability of ERDF to satisfy specific performance objectives in DOE O 5820.2A and showed a reasonable expectation that these objectives would be met. A second crosswalk [Klein, 2000, “Environmental Restoration Disposal Facility (ERDF) Crosswalk to DOE Order 435.1 Requirements”] was completed to demonstrate compliance with DOE O 435.1, which resulted in the issuance of a DAS on June 18, 2001 (Scott, 2001).

Since completion of the preliminary PA analysis, two factors led to the DOE-RL decision to update the PA analysis and complete the formal review process in accordance with DOE M 435.1-1, as DOE O 435.1 is the successor to DOE O 5820.2A. First, ERDF has accepted additional radioactive waste at higher inventory levels than originally foreseen (although still within the limits provided in the preliminary PA analysis). Second, new information has been developed at the Hanford Site that identifies large conservatisms in the initial analysis. The updated PA analysis is intended to provide a more realistic evaluation of ERDF performance and optimize the capability of ERDF to complete its mission for disposal of CERCLA remediation waste for the remainder of Hanford Site cleanup activities.

#### Relevance of the ERDF PA to the Hanford Site Composite Analysis

*The ERDF PA is supported by the Hanford Site Composite Analysis.*

*Similar to the LLBGs, disposal of solid waste at ERDF constitutes one of the sources of radioactive waste inventory. Because this facility is in active use, the current estimated inventory disposed is adjusted annually to reflect waste received. This updated information is pertinent to the composite analysis because of its potential to change the ERDF inventory evaluated in the composite analysis.*

*Information on the current inventory*




Figure 1-5. Location of the Environmental Restoration Disposal Facility

In FY 2011, WCH-426, *Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility*, was prepared and approved (Einan, 2011, “Approval of the Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility, WCH-426, Revision 0, October 2010”), and WCH-462, *ERDF Performance Assessment Modeling Approach*, was developed for the ERDF PA.

The work plan to prepare the new ERDF PA was revised in FY 2012 (WCH-426, *Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility*, Rev. 1). A draft report was prepared in early FY 2013 for EPA review and was revised to incorporate EPA comments. WCH-520, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford Site, Washington*, Rev. 00, was published in August 2013 (WCH-520 was renumbered to CP-60089, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford, Washington, formerly WCH-520 Rev. 1* in 2016), supported by the following data packages:

- WCH-463, *Hydrogeologic Model for the Environmental Restoration Disposal Facility, Hanford Site*
- WCH-464, *Hydrologic Data Package in Support of Environmental Restoration Disposal Facility Performance Assessment Modeling*
- WCH-475, *Biota Description Data Package for the Post Closure Environmental Restoration Disposal Facility Location*
- WCH-476, *Chemical Reactivity of Radionuclides with Waste Material and Subsurface Soils During Release and Migration from the Environmental Restoration Disposal Facility*

- WCH-477, *Conceptual Models for Release and Transport of Environmental Restoration Disposal Facility Waste Contaminants through the Near-Field Environment*
- WCH-478, *Exposure and Inadvertent Scenarios for the Environmental Restoration Disposal Facility*
- WCH-479, *Inventory Data Package for ERDF Waste Disposal*
- WCH-515, *Parameter Uncertainty for the ERDF Performance Assessment Uncertainty and Sensitivity Analysis*

The LFRG formally reviewed the revised ERDF PA during the second half of FY 2013. The LFRG examined the validity of the analyses documented in the PA and determined that the PA and associated documentation were technically adequate. WCH-520, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford Site, Washington*, Rev. 1 (hereinafter referred to as the revised ERDF PA), published in August 2013, was submitted for compliance evaluation. Based on the LFRG recommendation, DOE issued the DAS in November 2013, which permitted continued ERDF operations.

Stipulated conditions in the revised DAS included developing demonstration that an as low as reasonably achievable analysis is not needed and development of a closure plan, monitoring plan, maintenance plan, UDQE procedure, and revised waste acceptance criteria. The plans and UDQE procedure were all developed and submitted to the LFRG in March 2014. The LFRG comments were received in September 2014, and responses were returned to the LFRG in April 2015. DOE-HQ accepted the responses and removed all outstanding conditions of the DAS in August 2015.

Results of the revised ERDF PA (WCH-520, Rev. 1) and an evaluation thereof against the basis of the Hanford Site Composite Analysis were presented in DOE/RL-2013-40, *Annual Status Report (FY 2013): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site*.

### **1.1.5 Waste Management Areas A/AX Performance Assessment**

WMA A includes the A and AX Tank Farms and ancillary equipment located in the eastern portion of the 200 East Area (Figure 1-6). Figure 1-7 is a map on the scale of the 241-A and 241-AX Tank Farms. The six underground SSTs in A Farm are numbered 241-A-101 (A-101) through 241-A-106 (A-106). The four underground SSTs in AX Farm include tanks 241-AX-101 (AX-101), 241-AX-102 (AX-102), 241-AX-103 (AX-103), and 241-AX-104 (AX-104).

Scoping and planning phase activities for a new WMA A-AX PA were initiated in FY 2015, largely based on the scoping approach used for the WMA C PA. Work was suspended in FY 2016 due to funding issues and was resumed in FY 2017.





Figure 1-6. Location of Waste Management Area A-AX



**Figure 1-7. Map of 241-A and 241-AX Tank Farms**

In FY 2017 and 2018, the preparation of a draft preliminary PA analysis and supporting technical documentation for WMA A-AX was initiated. Other WMA A-AX Tri-Party Agreement Appendix I PA documentation will be prepared to meet federal, state, and Tri-Party Agreement (Ecology et al. 1989a) requirements. The work supports risk assessment and modeling efforts needed to help guide retrieval and RCRA Facility Investigation/Corrective Measures Study (RFI/CMS) characterization activities. The draft preliminary PA documents prepared in FY 2017 and 2018 include model package reports for the geologic framework model and the flow and contaminant transport numerical model, a tank residual data package, a soil inventory data package, and an engineered system data package. Efforts to evaluate the potential impacts from past leaks from WMA A-AX at SST A-105 and A-104 were also initiated.

In FY 2019, a draft preliminary PA for WMA A-AX was prepared to meet the requirements of DOE O 435.1. Other WMA A-AX Tri-Party Agreement PA documentation (see Appendix in Attachment 2, TPA Action Plan) will be prepared to meet federal, state, and TPA (Ecology et al. 1989a) requirements. The work supports risk assessment and modeling efforts needed to help guide retrieval and RCRA Facility RI/CM Study characterization activities. The draft

## *Relevance of the WMA A-AX PA to the Hanford Site Composite Analysis*

*When complete, the WMA A-AX PA will be supported by the Hanford Site Composite Analysis.*

Other PAs discussed in this section were developed to obtain authorization for disposal of radioactive waste in disposal facilities constructed for this purpose. The WMA A-AX PA differs in this respect: its purpose is to authorize closure of a tank waste system with residual waste remaining after retrieval as a disposal system.

As the WMA A-AX PA is completed, the information on residual tank waste inventory and predicted releases will serve to update the basis of the Hanford Site Composite Analysis. Other WMA PAs will follow in the future, providing further refinement.

preliminary PA supporting documents were prepared in CY 2019 that included model package reports of the flow and contaminant transport numerical model and the system model, and environmental model calculation files that document all calculations included in the preliminary PA. Efforts to evaluate the potential impacts from past leaks from WMA A-AX at SST A-105 and A-104 also continued in FY 2019.

In FY 2020, a preliminary PA for WMA A-AX evaluating the radiological impacts from residual wastes in a closed WMA A-AX was completed to meet the requirements of a TPA milestone. A preliminary Closure Analysis, which evaluates the hazardous chemical impacts from residual wastes in a closed WMA A-AX and is complementary to the preliminary PA for WMA A-AX, was also completed as a part of a TPA milestone. The DOE Low-Level Waste Disposal Facility Federal Review Group performed a consultative review of the preliminary PA; this review was completed in April 2020. Revisions to the fate and transport models to address comments from the Low-Level Waste Disposal Facility Federal Review Group consultative review were completed in September 2020. Additional comments made during the consultative review will be addressed in the final PA before seeking a closure authorization from DOE.

Efforts to evaluate the potential impacts from past leaks from WMA A-AX at SST A-105 and A-104 continued through FY 2021 and were completed in FY 2022.

In FY 2022, the PA and supporting technical documentation continued to be updated in response to comments made during the consultative review with LFRG that were not addressed in the preliminary PA. Updates to the PA and supporting documentation have also considered additional comments on preliminary PA and the Closure Analysis made by the Washington State Department of Ecology. The next draft revision of the PA will be prepared and submitted for approval by the DOE-ORP in FY 2023 in preparation for the next more formal review of this revised PA by the LFRG currently planned for FY 2024.

The documentation approach to meet the performance assessment (PA) requirements for the closure process outlined in Appendix I of the Tri-Party Agreement (Ecology et al., 1989a) will produce a six-volume set of documents that are briefly described below.

- Volume 1 provides an introduction to WMA A-AX facilities and waste sources, the regulatory context for WMA A-AX closure, regional and site-specific characteristics, and future land use. It also provides the conceptual model for the evaluations supporting closure decisions.
- Volume 2 presents the software, mathematical model(s), and parameters used to evaluate the fate and transport of contaminants released from past leaks from SSTs in WMA A-AX and the results of the analyses conducted with the models.
- Volume 3 presents the software, mathematical model(s), and parameters used to evaluate the baseline risk from radiological and hazardous chemicals present in the soil for a no-action alternative and the results of the analyses conducted with the models.
- Volume 4 presents the software, mathematical model(s), and parameters used to evaluate the capability of the closed WMA to meet DOE M 435.1-1, *Radioactive Waste Management Manual*, performance objectives and performance measures and the results of the analyses conducted with the models. Together Volumes 1 and 4 make up the DOE O 435.1 PA.
- Volume 5 presents the software, mathematical model(s), and parameters used to evaluate the capability of the closed WMA to meet numerical cleanup levels for hazardous chemicals in groundwater and the results of the analyses conducted with the models.

- Volume 6 presents a summary of the analyses and the cumulative impact to groundwater from all sources in the WMA. The synopsis provides the information that supports closure decisions in closure action plans.

In FY 2022, drafts of volumes 1 and 2 were prepared and are undergoing review by ORP and will be provided to Ecology for review in FY 2023. Current plans call for the preparation of drafts of volumes 4 and 5 to be prepared in FY 2023. Volumes 4 and 5 are updated versions of the preliminary PA and preliminary residual chemical analysis completed in FY 2020. The updated documents will address LFRG review comments on the preliminary PA and Washington State Department of Ecology comments on both of the preliminary documents. Review of the draft volume 4 of the IPA by Ecology is planned for FY 2024. Review of the draft volume 5 of the IPA by DOE-HQ (specifically, LFRG) is planned for FY 2024.

Similar to the approach used in the Composite Analysis for WMA-C, future updates to the Composite Analysis will adopt the tank release and vadose zone transport modeling results from Volume 4, the assessment of radiological constituents in the residual waste, when that information is available.

## 1.2 Central Plateau RCRA Remedial Activities

This section provides a summary of the ongoing activities associated with Phase 2 RFI/CMS and Interim Measures in Tank Farm Areas.

### 1.2.1 Phase 2 RCRA Facility Investigation and Corrective Measure Studies

Phase 2 RCRA RFI/CMS for the Hanford Site single-shell tank (SST) system has been completed at 241-C Tank Farm and have been initiated at 241-A and 241-AX Tank Farms. A summary of each of the RFI/CMS activities are provided below.

#### 1.2.1.1 Waste Management Area C

A Phase 1 RCRA corrective action program characterization effort was completed for Waste Management Area (WMA) C, with the results published in DOE/ORP-2008-01, *RCRA Facility Investigation Report for Hanford Single-Shell Tank Waste Management Areas Tier 1 & 2*. The Phase 1 characterization effort determined that additional data were needed about the nature and extent of contamination in WMA C vadose zone soil. The development of a Phase 2 RCRA RFI/CMS for the Hanford Site single-shell tank (SST) system has also been completed for WMA C (RPP-RPT-58339, Rev. 0 and RPP-RPT-59379, Rev. 0, respectively). The goal of this RFI/CMS process is to identify and evaluate actions that may be necessary to protect human health and the environment from contamination associated with the past operations in the SST system for WMA C.

The corrective measures study recommendation for a preferred alternative for WMA C is implementation of an isolation barrier and infiltration barrier system (Alternative 4). The estimated cost to implement Alternative 4 is between approximately \$19 and \$41 million dollars. Implementation of Alternative 4 would mitigate human health and environment risks by placing concrete isolation barriers over localized areas where shallow soil contamination levels exceed risk thresholds. The infiltration barrier system would reduce infiltration and slow the migration of contaminants to the groundwater. While the infiltration barrier would not reduce the anticipated peak impacts to groundwater, there would be a reduction in contaminant flux over the long-term. The isolation barriers would reduce the risk of direct-contact exposure to acceptable human health risk levels and reduce infiltration, pending placement of the final closure cap that will be installed as a part of WMA C closure. This final closure cap represents the permanent risk-mitigation measure for protecting human health and the environment for WMA C and

will be installed as part of the closure process after implementing the preferred alternative (Alternative 4) of this corrective measures study.

### **1.2.1.2 Waste Management Area A-AX**

A Phase 1 RCRA corrective action program characterization effort was completed for WMA A-AX, with the results published in DOE/ORP-2008-01, *RCRA Facility Investigation Report for Hanford Single-Shell Tank Waste Management Areas Tier 1 & 2*. The Phase 1 characterization effort determined that additional data were needed about the nature and extent of contamination in WMA A-AX vadose zone soil.

The development of a Phase 2 RCRA RFI/CMS for the Hanford Site SST system is under development for WMA A-AX. The goal of the RFI/CMS process is to identify and evaluate actions that may be necessary to protect human health and the environment from contamination associated with the past operations in the SST system for WMA A-AX.

The Phase 2 RFI/CMS process uses the framework established in RPP-PLAN-37243, *Phase 2 RCRA Facility Investigation/Corrective Measures Study Master Work Plan for Single-Shell Tank Waste Management Areas*. RPP-PLAN-37243 describes how the requirements of the *Comprehensive Environmental Response, Compensation and Liability Act*, the *National Environmental Policy Act of 1969* and the *Atomic Energy Act of 1954* will be integrated with the RCRA corrective action requirements. This work plan describes process history, existing site information, the baseline conceptual site model, and the future activities (e.g., data collection) needed to enable corrective measures selection and implementation.

The WMA A-AX study area is the area where vadose zone soil will be characterized and evaluated for corrective action and closure decision-making purposes. The WMA A-AX study area is within the Hanford Site's 10 mi<sup>2</sup> Central Plateau Inner Area. It consists of ten 100-series SSTs, waste transfer lines, tank ancillary equipment, multiple drywells around each SST used as a leak detection system, and laterals under the six 241-A Tank Farm tanks also used for leak detection. The WMA A-AX study area has multiple historical planned and unplanned releases within its boundary.

To date, the following technical documents supporting the RFI/CMS process for WMA A-AX have been completed:

- RPP-RPT-60227, Rev. 2, *Data Quality Objectives for Vadose Zone Characterization at Waste Management Area A-AX* (Ecology approval not required)
- RPP-PLAN-62041, Rev. 0, *Sampling and Analysis Plan for WMA A-AX Focus Area 1 (Tanks 241-A-104 and 241-A-105)* (Approved by Ecology 2/20/2019)
- RPP-PLAN-63020, Rev. 1, *Sampling and Analysis Plan for WMA A-AX Focus Area 2 (Southwestern Area of A Farm)* (Approved by Ecology 4/8/2020)
- RPP-PLAN-64758, Rev. 1, *Sampling and Analysis Plan for the Remainder of WMA A-AX* (Approved by Ecology 11/30/2022)
- RPP-PLAN-64857, Rev. 0, *Phase 2 RCRA Facility Investigation/Corrective Measures Study Work Plan for Waste Management Area A-AX* (under review by Ecology)

The work plan for the WMA A-AX RFI/CMS, currently under review by Ecology, does not address data requirements for SST residual waste sampling (addressed by closure of the SST system) or groundwater characterization (addressed through the 200-PO-1 and 200-BP-5 groundwater operable units). However, information developed as a result of the implementation of this work plan will be integrated with ongoing planning for these groundwater operable units.

## 1.2.2 Interim Measures

Interim measures are being conducted in tank farm areas to support completion of commitments between DOE and Ecology from the Tri-Party Agreement (Ecology et al. 1989) *Milestone M-045-56* Annual Meeting, *HFFACO Milestone M-045-56* states, “Ecology and DOE agree, at a minimum, to meet yearly (by July or as needed to support annual budgeting) for the specific purpose of assessing the adequacy of information, and the need for the establishment of additional Agreement interim measures. Additional Agreement interim measures shall be documented through establishment of interim milestones and associated target dates as agreed necessary by the Parties.

As a part of the commitments made between DOE and Ecology under *HFFACO Milestone M-045-56*, interim surface barriers have been constructed over portions of the 241-T, 241-TY, 241-SX, and 241-TX Tank Farms. The barriers divert meteoric water away from contaminated vadose zone soils within the tank farms. Infiltration of water into subsurface soils with preexisting contamination can accelerate the mobilization of contaminants toward the water table. The interim surface barriers at 241-T Tank Farm and 241-TY Tank Farm were constructed as part of the Interim Surface Barrier Demonstration Project (PNNL-16538 and PNNL-19772) and were completed in 2008 and 2010, respectively. The interim surface barriers at 241-SX Tank Farm were completed in 2019, and the interim surface barrier at 241-TX Tank Farm was completed in 2021. The design for a new interim surface barrier at the 241-U Tank Farm was completed in 2021 and construction of an evapotranspiration basin was completed in FY 2022. Final construction of the interim surface barrier at the 241-U Tank Farm will be completed in 2023.

In FY 2022, as a part of an Agreed Order to mitigate past leaks at Tanks 241-T-111 and 241-B-109 reached agreement with Ecology in Agreed Order Docket No. 21304 to design and construct new interim surface barriers at 241-T and 241-B Tank Farms by September 31, 2028.

The temporary structures were constructed as interim measures under agreement between the DOE, Ecology, and EPA. Monitoring is conducted in accordance with RPP-RPT-61684, *Maintenance and Performance Monitoring Plan for the Interim Barriers Program*. The annual interim surface barrier monitoring report for FY 2020 (RPP-RPT-63200, *FY 2020 Annual Interim Surface Barrier Monitoring Report*) was released in August 2021.

In FY 2022, interim measures direct push characterization work was also conducted in 241-T and U Tank Farms as a part of the commitments made between DOE and Ecology under *HFFACO Milestone M-045-56*.

Field characterization work at 241-T Tank Farm was focused on vadose zone soil sampling in the area around Tank 241-T-102 (T-102) and Tank 241-T-105 (T-105) in 241-T Tank Farm (T Farm). The work performed was expected to provide data to support recommendations in RPP-ASMT-55500, *Leak Assessment Report for Tanks 241-T-102 and 241-T-105*. Work was also recommended in Ecology et al. 1989, *Milestone M-045-56* meeting notes on August 9, 2018 [DOE-ORP and Ecology 2018, *Meeting Notes: Annual Meeting between the US Department of Energy, Office of River Protection (DOE-ORP) and the State of Washington Department of Ecology (Ecology) to Discuss Interim Measures Completed in Fiscal Year 2018 and Planned for Fiscal Year 2019*].

The area to be investigated and the boreholes drilled near tanks T-102 and T-105 in T Farm is shown on Figure 1-8.


Field characterization work at 241-U Tank Farm was completed to provide data to support recommendations in RPP-35485, *Field Investigation for Waste Management Area U* and RPP-RPT-50097, *Hanford 241-U Farm Leak Inventory Assessment Report*. This investigation was

performed to collect samples while still feasible since an interim surface barrier is to be placed over U Tank Farm by the end of October 2023, *HFFACO Milestone M-045-92*.


Work characterization at 241-U Tank Farm was recommended in *HFFACO Milestone M-045-56* meeting notes on July 11, 2019 [DOE-ORP and Ecology 2019, *Meeting Notes: Annual Meeting Between the U.S. Department of Energy, Office of River Protection (DOE-ORP) and the State of Washington, Department of Ecology (Ecology) to Discuss Interim Measures Completed in Fiscal Year 2019 and Planned for Fiscal Year 2020*].

The area investigated and boreholes drilled in U Tank Farm is shown on Figure 1-9.

Interpretative technical reports of these interim measure characterization efforts at 241-T and 241-U Tank Farms are planned in FY 2023.



**Figure 1-8. Vadose Zone Soil Sampling Locations Near Tanks T-102 and T-105 in 241-T Tank Farm**



**Figure 1-9. Vadose Zone Soil Sampling Locations in 241-U Tank Farm**

## 1.3 Central Plateau CERCLA Remedial Activities


CERCLA remedial activities directed by DOE-RL are pertinent to the Hanford Site Composite Analysis because they result in planned redistributions of radioactive inventory considered in the Hanford Site Composite Analysis in time, location, and waste form. Updated knowledge and information acquired while conducting remedial actions have the potential to change the analysis evaluated in the Hanford Site Composite Analysis; these are reviewed in this section to assess any such impact.

The Central Plateau is located near the middle of the Hanford Site and covers an area of approximately 195 km<sup>2</sup> (75 mi<sup>2</sup>). Most activities are concentrated in two main processing areas: the 200 East Area and the 200 West Area. The Central Plateau contains facilities formerly used in the plutonium production process, including five large chemical processing facilities (commonly known as canyons) and the Plutonium Finishing Plant (PFP), which was completely cleaned up as of December 2021, as well as individual waste sites that include both buried solid waste and contaminated soil. Key elements of the Central Plateau are shown on Figure 1-10. The approach for Central Plateau cleanup focuses on the following three major components:

- Inner Area: the final footprint area of the Hanford Site that will be dedicated to waste management and containment of residual contamination.
- Outer Area: contains the balance of the Central Plateau.
- Groundwater: composed of contaminant plumes underlying the Central Plateau and originating from waste sites on the Central Plateau.

Several operating waste disposal facilities in the Inner Area will continue to receive waste from Hanford Site cleanup activities and limited offsite sources. ERDF was constructed for the disposal of waste generated during cleanup of the Hanford Site. Additional cells will be constructed in ERDF as needed to implement cleanup decisions. The LLW or radioactive mixed waste generated from Hanford Site activities may also be disposed in LLBGs or mixed waste trenches, as appropriate. IDF has a final status Hanford RCRA Permit for future disposal of some waste generated from radioactive liquid waste tank cleanup. Additional physical and permit modifications are in progress to enable active operations and include other potential Hanford Site waste streams.

As CERCLA units are remediated, changes will occur in the composite analysis inventory. When waste has been removed from one of these sites, it is considered “generated” waste and is added to the inventory of the specific disposal facility for which it is intended. These inventory changes are tracked in the various PA annual summary reports and have been included in the most recent facility PAs (Chapter 3). These changes will be reflected in the location of the activity but not necessarily as a change in the total site inventory unless unexpected circumstances are encountered. Some residual activity will remain in the waste sites after remediation has been finalized, but it is not expected to contribute significantly at that location in the composite analysis given that cleanup has been based on numerical modeling calculations and is in accordance with regulations.



**Figure 1-10. Central Plateau CERCLA Remedial Activities and Operable Units**

Cleanup activities have already begun for some areas in the Central Plateau. The U Plant facility (221U Building) is one of five massive processing facilities at the Hanford Site. Commonly referred to as a canyon, U Plant was built during World War II to extract plutonium from fuel rods irradiated in Hanford Site production reactors. It was used for training and equipment testing and was later converted to recover uranium from waste generated at other canyon facilities. Issued in October 2005, EPA et al., 2005, *Record of Decision 221-U Facility (Canyon Disposition Initiative) Hanford Site, Washington*, determined that the U Plant Canyon would be disposed in place with a suitable surface barrier to prevent infiltration of water and/or intrusion by human or ecological receptors. In FY 2011, existing contaminated equipment from the canyon deck (near the ground-level portion of the facility) was size-reduced (as necessary), placed in the canyon process cells (below the ground-level portion of the facility), and grouted in place. The upper portion of the canyon building will be demolished to the approximate level of the canyon deck or higher. Debris from the partial demolition will be placed on (or adjacent to) the canyon deck. Appropriate actions (e.g., grouting) will be taken when necessary to minimize void space. The partially demolished building and debris will be covered with a surface barrier.

Final decisions for the remaining canyons and storage tunnels located at the Plutonium-Uranium Extraction (PUREX) Plant will be made as part of future CERCLA and RCRA cleanup decisions.

On May 9, 2017, workers discovered a partial collapse of the timber roof structure in a portion of PUREX Tunnel 1. To mitigate the potential for releases to the environment and eliminate the threat of further failure Tunnel 1 was void filled with engineered concrete/grout (grout) in FY 2018.

A structural evaluation also identified a future threat of failure for Tunnel 2, which contains 28 railcars with contaminated processing equipment and materials generated during Hanford's weapons production mission. DOE-RL addressed this threat by void filling Tunnel 2 with engineered grout in FY 2019. Final closure of the tunnels will be coordinated with future remedial actions of the PUREX canyon as part of the 200-CP-1 Operable Unit (OU). PNNL-11800, Addendum 1 provides a bounding sensitivity analysis for the impact of the composite analysis results of the PUREX tunnels. The inventories of technetium-99 and iodine-129 as representative mobile constituents were used to evaluate potential impact of the PUREX tunnels. The results of the original composite analysis (PNNL-11800) indicated that these two radionuclides were key constituents in the projected dose and could be used as a general indicator of potential impacts. The inventory of technetium-99 and iodine-129 in the PUREX tunnels was obtained from an in-development inventory database (the best available estimate at that time [2001–02]). Table 1-3 provides the inventory of the PUREX tunnels evaluated in PNNL-11800, Addendum 1.

**Table 1-3. Inventory of PUREX Tunnels Evaluated in the Composite Analysis Addendum**

Site Name	Best Estimate of Inventory	
	Technetium-99 (Ci)	Iodine-129 (Ci)
218-E-14 (Tunnel 1)	0.27	0.001
218-E-15 (Tunnel 2)	1.6	27
<b>PUREX Plant Tunnels Total</b>	<b>1.9</b>	<b>27*</b>

\*The inventory in Tunnel 2 analyzed in PNNL-11800, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1, is now considered high. Appendix A of CP-60195, *Hanford Site Composite Analysis Technical Approach Description: Radionuclide Inventory and Waste Site Selection Process*, estimates the inventory of iodine-129 to be in the range 0.60 to 9.49 Ci for the total of processing canyons and PUREX Tunnel 2.

PUREX = Plutonium-Uranium Extraction

The assumed end state for the PUREX tunnels in the composite analysis addendum was injection of grout matrix and placement of an engineered barrier that would reduce facility infiltration rates to 5 mm/yr (PNNL-11800, Addendum 1). The waste form release was assumed to be a diffusion-controlled, cement-release model. The analysis predicted that release would not occur from the PUREX tunnels in the groundwater pathway for the next 500 to 1,000 years. This result was attributed to the assumed end state of grout injection and an engineered barrier. A sensitivity analysis was also evaluated for an upper-end estimate of the inventory, which also predicted no release during the 1,000-year analysis period. The grout fill of void space in PUREX Tunnels 1 and 2 is consistent with the assumed end state in the composite analysis.

Disposition of the remaining facilities (including PFP) is being addressed using a combination of *National Environmental Policy Act of 1969*, CERCLA, and RCRA processes. For example, workers recently completed final cleanup activities at PFP, putting a sand and gravel cap on what was once one of the most hazardous facilities in the DOE complex. Final project demobilization and documentation activities were finished in December 2021.

Radioactive or other hazardous substances resulting from disposition of facilities are removed and treated (if necessary) and then packaged for disposal in approved disposal facilities. Debris and rubble from the demolition process are disposed onsite at ERDF or offsite in solid waste landfills (SWLs), as appropriate. Limited volumes of transuranic (TRU) wastes generated during demolition are packaged for disposal at the Waste Isolation Pilot Plant (WIPP) near Carlsbad, New Mexico. RCRA closure requirements are integrated into the process, where necessary. Potential subsurface contaminants will be addressed in a manner consistent with waste site remedial alternatives, which are provided in the following discussion.

Approximately 15,000 m<sup>3</sup> (20,000 yd<sup>3</sup>) of suspect TRU waste was placed in retrievable storage trenches in four LLBGs beginning in 1970. When waste is retrieved from the trenches, it is characterized to determine whether it is TRU or LLW. Approximately 12,000 m<sup>3</sup> (15,700 yd<sup>3</sup>) have been retrieved to date. The TPA requires a proposal for an interim response action to resume retrieval to be submitted to Ecology in FY 2028. The TPA also requires that DOE initiate treatment of mixed low-level waste and mixed TRU waste (TRUM) or certification and shipment of TRUM waste for disposal at WIPP in FY 2028. The bulk of TRU/TRUM wastes are expected to be shipped to WIPP for disposal by 2040, with the remaining TRU/TRUM wastes to be shipped by 2050.

The following extensive and significant inventory of radionuclides exists in other forms that require disposition:

- **Cesium and strontium capsules:** Approximately 2,000 cesium and strontium capsules are stored underwater at the Waste Encapsulation and Storage Facility (WESF) are now being transferred to a new dry storage facility for long-term storage. A new RCRA permitted storage area near the WESF was completed in FY 2021. Mockup testing is underway to support transfer of the capsules to the capsule storage area.

The capsules are being managed according to the specific hazard they pose to workers, the public, and the environment and as such, are managed as high-activity waste. There has been debate over the years as to whether or not these capsules can be classified as high-level waste (HLW).

If the capsules are eventually classified as HLW, there is no direct disposal option for them with the shutdown of the Yucca Mountain National Repository. OAS-L-14-04, *Audit Report Long-Term Storage of Cesium and Strontium at the Hanford Site*, states that DOE's new goal, as of January 2013, is to have a repository sited by 2026 and to begin operating by 2048. Therefore, an HLW repository will not be available for at least 34 years.

DOE is storing the capsules for the time being, in a manner that is protective of human health and the environment. Because the isotopes in these capsules are short-lived, according to 10 CFR 61.55, storage over the next 34 to 50 years will result in considerable reduction in concentration.

- **German log casks:** Pacific Northwest National Laboratory (PNNL) produced 34 borosilicate glass-filled canisters for the Federal Republic of Germany to serve as isotopic heat sources for a repository-testing program. The “German log” casks were shipped to the Central Waste Complex in the 200 West Area in 1997 and are currently managed as remote-handled TRU waste, pending decisions on final disposition.

The activity level in the German logs is estimated to be 2.1 million Ci of cesium-137 in 2024. Continued storage will be necessary to allow the total activity level to decay before final disposition. Alternative evaluations for Tri-Party Agreement (Ecology et al., 1989) interim Milestone M-091-52

identified a strategy using monitored natural attenuation (MNA) for waste packages containing more than 100 Ci of cesium-137 prior to final disposition (CHPRC-03264, *M-091-52 Alternative Evaluation*).

Since the issuance of DOE O 435.1, baseline characterization information has been evaluated, and it was determined that the calculated TRU activity for each of the eight German log casks is under 100 nCi/g and could be classified as LLW in accordance with DOE M 435.1-1 (HNF-30810, *Acceptable Knowledge Document for the 325 Building Radiochemistry Laboratory Mixed Debris Waste Stream, RLM325D*). A disposal pathway for the German logs was developed in 2012 that considered disposing the waste at ERDF (CHPRC-1203550, "Contract Number DE-AC06-08RL14788 – Disposal Pathway for Hanford's German Logs"). This disposal pathway was supported by engineering calculations [ECF-Hanford-12-0064, *Preliminary Evaluation of Radiological Dose from Burial of German Logs in a Disposal Facility under the Inadvertent Intruder Scenario per DOE Order 435.1 (Radioactive Waste Management)*; ECF-Hanford-12-0065, *Preliminary Evaluation of Thermal Effects from Burial of German Logs in a Disposal Facility*].

- **Spent nuclear fuel is stored in multi-canister overpacks at the Canister Storage Building in the 200 East Area:** Examples include N Reactor and single-pass production reactor fuel received from the K Basins and Shippingport pressurized water reactor core blanket fuel assemblies. Located adjacent to the Canister Storage Building, the 200 Area Interim Storage Area is used to store other nondefense-related spent nuclear fuel in aboveground dry cask storage containers, including material from the Fast Flux Test Facility, commercial origin light water reactor spent nuclear fuel, and TRIGA® (a class of small research nuclear reactors) from the Neutron Radiography Facility and Oregon State University. The Canister Storage Building/interim storage area is designed for interim storage until a suitable, long-term repository is established.

The Central Plateau includes more than 800 soil waste sites consisting of cribs, ponds, ditches, trenches, landfills, pipelines, diversions boxes, unplanned releases, and other types of sites used for liquid or solid waste disposal. Remedial or interim removal actions have been conducted for some of the soil waste sites located in the Outer Area. Sites in the 200 North Area have been remediated in accordance with EPA/ROD/R10-99/039, *Interim Action Record of Decision for the 100-BC-1, 100-BC-2, 100-DR-1, 100-DR-2, 100-FR-1, 100-FR-2, 100-HR-1, 100-HR-2, 100-KR-1, 100-KR-2, 100-IU-2, 100-IU-6, and 200-CW-3 Operable Units, Hanford Site, Benton County, Washington (Remaining Sites ROD)*, issued in 1999. Interim action has been conducted in other parts of the Outer Area to remove surface and shallow contamination and reduce the footprint of areas requiring radiological controls. A fact sheet to incorporate additional Outer Area waste sites into the 200-CW-3 OU for plug-in to the Remaining Sites ROD was developed in FY 2022 to expedite remediation.

Issued in September 2011, EPA et al., 2011, *Record of Decision Hanford 200 Area Superfund Site 200-CW-5 and 200-PW-1, 200-PW-3, and 200-PW-6 Operable Units*, provided remedies for 20 plutonium-contaminated soil waste sites and pipelines in the 200 West Area (near PFP) and five cesium-contaminated soil waste sites in the 200 East Area. The selected remedies included removing, treating, and disposing plutonium-contaminated sludge and soils at 18 sites; constructing a surface barrier over the remaining waste at 9 of the 18 sites; and enhancing existing soil covers over 3 of the 5 cesium-contaminated sites. Two plutonium-contaminated and two cesium-contaminated sites were determined to pose no threat to human health and the environment and require no remedial action.

Implementation of the selected remedies is described in DOE/RL-2015-23, *Remedial Design/Remedial Action Work Plan for the 200-CW-5, 200-PW-1, 200-PW-3, and 200-PW-6 Operable Units* (hereinafter

---

®TRIGA (Training, Research, Isotopes, General Atomics) is a registered trademark of General Atomics and Affiliated Companies, San Diego, California.

referred to as the remedial design/remedial action work plan [RD/RAWP]), approved by DOE-RL and EPA in May 2016 and updated in March 2021. Excavated soils that meet ERDF waste acceptance criteria (ERDF-00011, *Environmental Restoration Disposal Facility Waste Acceptance Criteria*) will be disposed at ERDF. Excavated soils and sludge from 12 of the sites are expected to require disposal at the Waste Isolation Pilot Plant as TRU waste.

Two additional waste sites on the Central Plateau (inactive Nonradioactive Dangerous Waste Landfill [NRDWL] and adjacent inactive SWL) located outside of the 200 Areas are to be closed in accordance with a closure plan being negotiated with Ecology.

Remediation of the remaining Central Plateau soil waste sites will be completed in accordance with CERCLA and RCRA corrective action requirements. CERCLA guidance requires that a range of alternatives be evaluated, including the following:

- No action
- Removal of contaminants as the primary remedy
- Containment as the predominant remedy
- Treatment of the contaminants to reduce their toxicity, mobility, or volume as the primary remedy

Evaluation of remedial alternatives conducted for the Central Plateau OUs will consider these and other alternatives that use a combination of those key features.

Alternatives that involve removal will include treatment (where appropriate) and disposal in an approved facility such as ERDF. Containment remedies may involve maintaining or enhancing existing soil covers, capping with suitable engineered surface barrier, or performing other containment remedies. Treatment-based remedies may involve MNA to allow radioactive materials to decay, immobilization, or other forms of treatment. Surface barriers will be designed to limit the infiltration of water and thereby slow the movement of contaminants currently in the vadose zone into the underlying groundwater. Barriers will also be designed to prevent intrusion by plants and animals so that underlying contamination is not dispersed.

All alternatives are expected to result in the need for institutional controls (ICs) as long as the hazards are present to maintain environmental monitoring and surface barriers, limit access to authorized users, and prevent unapproved excavation and inadvertent intrusion. DOE-RL has committed to retain the Central Plateau and other areas of the Hanford Site under federal control for the foreseeable future.

### 1.3.1 Central Plateau Source Operable Units

The CPCCo Soil and Groundwater Operations and Regulator Strategy and Integration organizations implements the RI/FS process for source OUs in the Central Plateau. The current OUs are organized to facilitate consistent decision making using a geographic approach to implementing cleanup.

The configuration of source OUs can be modified as needed to support the RI/FS and remediation process. In 2020, a joint activity with the Tri-Parties known as the Representative/Analogous Sites Coordinating Agency Liaisons (RASCAL) initiative identified a new approach to characterization and remediation of selected wastes sites that is being incorporated in the RI/FS process where appropriate. Table 1-4 lists the current Central Plateau source OUs and FY 2021 activity. The location of the OUs and key facilities is depicted in Figure 1-10.

The decision-making process for these OUs will incorporate data and analyses previously conducted for the predecessor OUs, as appropriate. The OUs listed in Table 1-4 are subject to completion of the RI/FS

process and remediation in accordance with the negotiated major and interim Tri-Party Agreement (Ecology et al., 1989) milestones to track the progress listed in Table 1-5.

**Table 1-4. Central Plateau Source Operable Unit Activity During Fiscal Year 2022**

OU Group	Description	FY 2020 Activity
<b>Inner Area</b>		
200-PW-1/3/6 and 200-CW-5	Plutonium-contaminated soil sites located near PFP and cesium-contaminated sites near PUREX	Revision 1 of the RD/RAWP with an updated project schedule was issued in April 2021 (DOE/RL-2015-23).
200-WA-1 and 200-BC-1	Soil waste sites located in the 200 West Inner Area that are not included in the 200-SW-2, 200-CR-1, 200-PW-1/6, 200-CW-5, 200-IS-1, and 200-IA-1 OUs  Soil waste sites in the BC cribs and trenches	Revisions to the RI/FS work plan (DOE/RL-2010-49) to incorporate the RASCAL approach were initiated in FY 2021 and continued through FY22. CIE modeling to support draft work plan development has been completed.  Planning is underway for the 200-BC-1 OU to support a separate FFS.
200-EA-1	200 East Inner Area sites not included in the 200-SW-2, 200-CB-1, 200-CP-1, 200-PW-3, and 200-IA-1 OUs	Revisions to the 200-EA-1 RI/FS work plan (DOE/RL-2016-58) incorporating the RASCAL approach were initiated in FY 2021 and continues through FY 2022. DQO sessions with Ecology and EPA began in early September 2022.
200-IS-1	Pipelines, diversion boxes, catch tanks, and neutralization tanks in the 200-IS-1 OU	No activity in FY 2022. Work will resume subject to available funding.
200-SW-2	Solid Waste Burial Grounds and waste sites in the footprint of the burial grounds	No activity in FY 2022. Work will resume subject to available funding.
200-DV-1	Selected soil waste sites in the Inner Area with deep vadose zone contamination	Extraction and treatment of uranium-contaminated water in the perched zone continues in accordance with the RAWP (DOE/RL-2014-37). A new perched water extraction well was completed in FY 2022. Through FY 2022, approximately 7.2 million L (1.9 million gal) of perched water has been treated to remove more than 390 kg of uranium.
200-IA-1	Selected waste sites with shallow contamination suitable for simplified characterization and accelerated remediation	The FFS for the 200-IA-1 OU was transmitted to EPA and Ecology as Draft A in March 2022. Resolution of comments resulted in determination that supplemental characterization of representative sites is needed. A DQO workshop was conducted, and development of the supplemental characterization SAP was initiated.
200-CB-1	B Plant Canyon Associated waste sites	No activity in FY 2022. Work will resume subject to available funding. Removal actions for stabilization/mitigation of canyon hazards and removal of nearby structures, including 224B, are being planned and conducted in accordance with CERCLA policies.
200-CP-1	PUREX Canyon Associated waste sites	Resolution of Ecology comments on the draft RI/FS work plan for the 200 CP 1 OU (DOE/RL 2020-27) and development of the revised draft work plan is ongoing in FY 2022 and will continue in FY 2023. Removal actions for stabilization/mitigation of canyon hazards and removal of nearby structures are being planned and conducted in accordance with CERCLA policies.

**Table 1-4. Central Plateau Source Operable Unit Activity During Fiscal Year 2022**

OU Group	Description	FY 2020 Activity
200-CR-1	REDOX Canyon Associated waste sites	No activity in FY 2022. Work will resume subject to available funding. Removal actions for stabilization/mitigation of canyon hazards and removal of nearby structures are being planned and conducted in accordance with CERCLA policies.
200-CU-1	U Plant Canyon Associated structures	No activity in FY 2022. Work will resume subject to available funding.
<b>Outer Area</b>		
200-OA-1, 200-CW-1, and 200-CW-3	Sites located in the Outer Area	Additional Outer Area waste sites are being added to the 200-CW-3 OU and plugged in to the existing Remaining Sites Interim Action ROD to expedite remediation. The RD/RAWP and SAP for the 200 North Area of the 200-CW-3 OU (DOE/RL-2007-55 and DOE/RL-2007-54, respectively) are being revised to align with this approach. A fact sheet documenting the plug-in to the Remaining Sites ROD was developed in FY 2022.

Note: Complete reference citations are provided in Chapter 9 of this document.

CERCLA	=	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>	PFP	=	Plutonium Finishing Plant
CIE	=	cumulative impact evaluation	PUREX	=	Plutonium-Uranium Extraction
DQO	=	data quality objectives	RASCAL	=	Representative/Analogous Sites Coordinating Agency Liaisons
Ecology	=	Washington State Department of Ecology	RAWP	=	removal action work plan
EPA	=	Environmental Protection Agency	RD/RAWP	=	remedial design/remedial action work plan
FFS	=	Focused feasibility study	REDOX	=	Reduction-Oxidation (Plant)
FS	=	feasibility study	RI	=	remedial investigation
FY	=	fiscal year	ROD	=	record of decision
OU	=	operable unit	SAP	=	sampling and analysis plan

**Table 1-5. Central Plateau CERCLA/RCRA Deliverables, Fiscal Years 2018 Through 2024**

Tri-Party Agreement Milestone Number	Title	Due Date	Status	Completion Date
M-015-21A	<i>Submit 200-BP-5 and 200-PO-1 OU FS Report &amp; PP(s) for an Interim Action to Ecology</i>	March 31, 2019	Completed	March 27, 2019
M-015-38B	<i>Submit a FS Report &amp; PP for 200-CW-1, 200-CW-3 &amp; 200-OA-1 OUs to EPA</i>	July 31, 2023	In negotiation	In progress
M-015-84	<i>Complete RI of 200-WA-1 and 200-BC-1 Waste Sites in Accordance with RI/FS Work Plan</i>	December 31, 2021	In negotiation	In progress
M-015-91B	<i>Submit FS Report &amp; PP for the 200-BC-1/200-WA-1 OUs to EPA</i>	July 31, 2023	In negotiation	In progress
M-015-92A	<i>Submit RCRA RFI/CMS &amp; RI/FS Work Plan for 200-EA-1 OU to Ecology</i>	July 31, 2018	Completed	July 12, 2018
M-015-92B	<i>Submit RFI/CMS &amp; RI/FS Report &amp; PCAD/PP for 200-EA-1 OU to Ecology</i>	November 30, 2022	In negotiation	In progress
M-015-92C	<i>Submit RFI/CMS and RI/FS Report and PCAD/PP for 200-IS-1 OU to Ecology</i>	March 31, 2023	In negotiation	In progress
M-015-93B	<i>Submit RCRA FI/CMS &amp; RI/FS Report &amp; PCAD/PP for 200-SW-2 OU</i>	January 31, 2023	In negotiation	In progress
M-015-93C	<i>Initiate Characterization Field Work for 200-SW-2 OU Landfills</i>	September 30, 2018	In negotiation	In progress
M-015-98	<i>Complete RI of U Plant Related Waste Sites Located in 200-WA-1</i>	June 30, 2019	In negotiation	In progress
M-015-99	<i>Complete RI of PFP Related Waste Sites Located in 200-WA-1</i>	December 31, 2019	In negotiation	In progress
M-015-110B	<i>Submit CMS &amp; FS &amp; PP/PCAD for 200-DV-1 OU to Ecology</i>	September 30, 2023	In negotiation	In progress
M-015-112	<i>Submit Draft B 200-IS-1 RFI/CMS/RI/FS Work Plan to Ecology with Schedule Dates</i>	November 30, 2020	In negotiation	In progress
M-016-193	<i>Investigate Southeast Chromium Plume, Install Wells, Evaluate Groundwater Monitoring Data, &amp; Install Monitoring Wells</i>	September 30, 2018	Completed	September 25, 2018
M-016-200A	<i>Complete U Plant Canyon (221 U Facility) Demolition</i>	September 30, 2024	In negotiation	In progress
M-016-250C	<i>Submit a 3-Year Rolling Prioritized Schedule to Implement Waste Site Removal Actions</i>	March 31, 2018	Completed	March 28, 2018
M-016-250D	<i>Submit a 3-Year Rolling Prioritized Schedule to Implement Waste Site Removal Actions</i>	March 31, 2019	Completed	March 27, 2019

Table 1-5. Central Plateau CERCLA/RCRA Deliverables, Fiscal Years 2018 Through 2024

Tri-Party Agreement Milestone Number	Title	Due Date	Status	Completion Date
M-016-250E	<i>Submit a 3-Year Rolling Prioritized Schedule to Implement Waste Site Removal Actions</i>	September 30, 2020	Completed	September 30, 2020
M-016-250F	<i>Submit a 3-Year Rolling Prioritized Schedule to Implement Waste Site Removal Actions</i>	March 31, 2021	On schedule	In progress
M-085-70	<i>Submit RI/FS Work Plan for 200-CB-1</i>	September 30, 2019	In negotiation	In progress
M-085-72	<i>Submit Removal Action Work Plan for 224-B</i>	September 30, 2020	Completed	September 19, 2019
M-085-80	<i>Submit RI/FS Work Plan for 200-CP-1</i>	September 30, 2020	Completed	September 22, 2020
M-085-80A	<i>Submit Data Quality Objective Report to Ecology on Structural Integrity of the PUREX Storage Tunnels 1 and 2</i>	September 30, 2017	Completed	September 12, 2017
M-085-84A	<i>Complete Electrical/Mechanical Isolation of 211A Building to Support Demolition of PUREX</i>	September 30, 2022	Completed	March 17, 2022
M-085-84B	<i>Complete Demolition of PUREX Ancillary Facilities 203A Building/Tank Yard and 205A Building</i>	September 30, 2023	On schedule	In progress
M-085-84C	<i>Complete Infrastructure Upgrades to Support Demolition Preparation of the PUREX Complex</i>	September 30, 2024	On schedule	In progress
M-085-100	<i>Submit Removal Action Work Plan for 224-T</i>	September 30, 2020	Completed	August 12, 2020

CERCLA = *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*

CAD = corrective action decision

CMS = corrective measures study

Ecology = Washington State Department of Ecology

EPA = Environmental Protection Agency

FS = feasibility study

OU = operable unit

PFP = Plutonium Finishing Plant

PP = proposed plan

PUREX = Plutonium-Uranium Extraction

RCRA = *Resource Conservation and Recovery Act*

RFI = RCRA facility investigation

RI = remedial investigation

Tri-Party = *Hanford Federal Facility Agreement and Consent Order Agreement*

### 1.3.2 Central Plateau Groundwater Operable Units


This section presents the results of the DOE-RL groundwater monitoring program for the Central Plateau groundwater OUs for CY 2021 (January 1, 2021 through December 31, 2021) relating to the Hanford Site Composite Analysis. The groundwater monitoring data and interpreted results for CY 2021 are drawn from information presented in DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*, which describes the monitoring results for RCRA treatment, storage, and disposal (TSD) units; CERCLA groundwater OUs; and the *Atomic Energy Act of 1954* (AEA), as required by DOE orders.

#### 1.3.2.1 Central Plateau Groundwater Background

When the Hanford Site was in operation, irradiated fuel reprocessing, isotope recovery, and associated waste management activities occurred on the Central Plateau. Since the 1990s, DOE-RL has worked to characterize, contain, and treat groundwater and to remove and dispose soil contamination from past operations from all onsite locations. The contaminant sources primarily included unlined cribs, trenches, ponds, ditches, and leakage from underground storage tanks (in WMAs).


Figure 1-11 shows the locations and boundaries of the Hanford Site groundwater OUs and groundwater interest areas. Four groundwater OUs are located within the Central Plateau, and four groundwater interest areas are associated with the OUs. The groundwater OUs are the 200-ZP-1 and 200-UP-1 OUs in the 200 West Area, and the 200-BP-5 and 200-PO-1 OUs in the 200 East Area. Figure 1-12 depicts the extent of groundwater contaminant plumes above cleanup standards in 2021 and the active cleanup systems. Activities for each of the four groundwater OUs that provide new information on radionuclide constituents relevant to the Hanford Site Composite Analysis are discussed below. Remedial actions directed at nonradioactive contaminants are also discussed wherever it was deemed that these actions could potentially influence the characterization, extent, or remediation of radioactive constituents and thereby become relevant to the Hanford Site Composite Analysis.

Cleanup activities on the Central Plateau are being performed to protect human health and the environment, and the Columbia River. Consistent with strategy for Hanford Site remediation (DOE/RL-2009-10, *Hanford Site Cleanup Completion Framework*), more progress has been made remediating waste sites within the River Corridor compared with the Central Plateau to reduce the active cleanup footprint to the 195 km<sup>2</sup> (75 mi<sup>2</sup>) in the center of the Hanford Site. Remediation of the Central Plateau waste sites is expected to accelerate once many of the River Corridor sites transition into long-term stewardship. Until that time, cleanup activities on the Central Plateau are focused on completing decision documents, remediating groundwater plumes in the 200 East and 200 West Areas, decontaminating and decommissioning facilities (including PFP), and initiating waste site cleanup in the Outer Area.



Source: Figure 1-1 in DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*.

Figure 1-11. Hanford Site Groundwater Interest Areas and Groundwater Operable Units



Source: Plume contours from Figure ES-7 in DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*.

**Figure 1-12. Central Plateau Groundwater Contaminant Plumes and Cleanup**

### 1.3.2.2 Central Plateau Groundwater Decisions

Groundwater interim and final remedial actions either were operated during the reporting period or were active in the recent past, including those in the 200-ZP-1 OU (soil vapor extraction [SVE] and groundwater pump and treat [P&T]), 200-UP-1 OU (groundwater P&T), and 200-BP-5 OU (groundwater P&T and perched water P&T). The remedial actions and supporting key documentation are as follows:

- **200-UP-1 OU interim remedial action (1997 and amended in 2009):** A pilot-scale treatability test (DOE/RL-95-02, *Treatability Test Report for the 200-UP-1 Operable Unit – Hanford Site*) consisting of an onsite treatment system and single extraction and injection wells was conducted adjacent to the 216-U-17 Crib. Phase I P&T operations commenced on September 25, 1995 and continued until February 7, 1997. The treatability test demonstrated that the ion exchange resin and granular activated carbon effectively removed technetium-99, uranium, and carbon tetrachloride from groundwater. On

February 25, 1997, EPA/ROD/R10-97/048, *Interim Remedial Action Record of Decision for the 200-UP-1 Operable Unit, Hanford Site, Benton County, Washington*, was issued.

This cleanup action started in 1997 and included operation of extraction wells and transfer of extracted groundwater to the 200 East Effluent Treatment Facility (ETF) for treatment with ultimate infiltration of the treated water at the State-Approved Land Disposal Site (SALDS) located immediately north of 200 West Area. The remedial action objectives were met, and the system was shut down in 2011. This ROD was amended through an explanation of significant differences in 2009 (EPA et al., 2009a, *Explanation of Significant Differences for the Interim Action Record of Decision for the 200-UP-1 Groundwater Operable Unit Hanford Site Benton County, Washington*), which updated the uranium cleanup level from 48 to 30  $\mu\text{g/L}$ . This system removed nearly 886 million L (234 million gal) of contaminated groundwater with 220 kg of uranium, 127 g (2 Ci) of technetium-99, 41 kg of carbon tetrachloride, and 49,000 kg of nitrate.

- **WMA S-SX groundwater extraction system:** A groundwater extraction system for technetium-99 at the WMA S-SX Tank Farms was implemented under the revised DOE/RL-97-36, *200-UP-1 Groundwater Remedial Design/Remedial Action Work Plan* and began operating in CY 2012. The design consists of a three-well extraction system, aboveground pipelines, and a transfer building to pump extracted groundwater to 200 West P&T. This system was designed for a nominal combined flow rate of 300 L/min (80 gal/min). Extracted groundwater co-contaminants are also treated through the 200 West P&T. During CY 2021, 156 million L (41.3 million gal) of water were pumped and treated, removing 0.234 Ci (13.3g) of technetium-99 from the aquifer (plus 1.0 kg of chromium and 8.67 kg of carbon tetrachloride). From system inception through CY 2021, 1.46 billion L (385 million gal) of water were pumped and treated, removing 3.76 Ci of technetium-99 from the aquifer.
- **200-UP-1 OU interim action ROD (2012):** The 1997 ROD was superseded by an interim action ROD approved in September 2012 (EPA et al., 2012, *Record of Decision for Interim Remedial Action Hanford 200 Area Superfund Site 200-UP-1 Operable Unit*) that addresses contamination within the entire OU. The selected remedies identified in the 2012 ROD include a combination of groundwater P&T, MNA, hydraulic containment, and ICs.

An RD/RAWP (DOE/RL-2013-07, *200-UP-1 Groundwater Operable Unit Remedial Design/Remedial Action Work Plan*) was developed to implement the 2012 ROD. The WMA S-SX groundwater extraction system will continue as a remedy under the work plan, and it is being operated in accordance with the requirements of the 2012 ROD.

In CY 2015, a P&T system for the uranium, technetium-99, and nitrate plumes near U Plant and injection wells for hydraulic containment of the iodine-129 plume were implemented as part of the 200-UP-1 OU groundwater remedy. Operation of both remedies started in late CY 2015.

The U Plant P&T system consists of three extraction wells and aboveground, dual-walled pipelines to convey extracted groundwater to the 200 West P&T radiological building for treatment. The U Plant P&T system was designed to operate at a nominal combined flow rate of 568 L/min (150 gal/min). The combined flow rate from the three extraction wells in 2021 was 554 L/min (146 gal/min). The total volume of water extracted from the aquifer during 2021 was 285 million L (75 million gal/min), removing 14 kg of carbon tetrachloride, 0.08 Ci of technetium-99, and 7.9 kg of uranium. From system inception through CY 2021, 1.87 billion L (493 million gal) of water were pumped and treated, removing 142.5 kg of carbon tetrachloride, 101,370 kg of nitrate, 1.33 Ci of technetium-99, and 75.4 kg of uranium from the aquifer.

The iodine-129 plume hydraulic containment system consists of three injection wells where treated effluent from the 200 West P&T is injected at a nominal flow rate of 189 to 379 L/min (50 to 100 gal/min) per well. The wells are located east of the iodine-129 plume boundary. Operation of these wells slows eastward plume migration by increasing the water table elevation downgradient of the plume. The combined average flow rate for all three wells in CY 2021 was 888 L/min (235 gal/min). The total volume of water injected into the aquifer during 2021 was 467 million L (123 million gal). Since startup in October 2015, the total volume of water injected into the aquifer was 2.48 billion L (66.3 million gal).

- **200-ZP-1 OU interim remedial action (1995):** In 1996, a groundwater P&T system was implemented to reduce the mass of carbon tetrachloride and contain the plume where concentrations exceeded 2 mg/L. This action was completed, and the interim P&T system was deactivated in 2012. *EPA/ROD/R10-95/114, EPA Superfund Record of Decision: Hanford 200-Area (USDOE) OU 200-ZP-1, Benton County, WA 5/254/95*, was issued on June 5, 1995.

SVE was implemented as an expedited response action to remove and treat carbon tetrachloride contamination in the vadose zone at 200-PW-1 OU waste sites. The SVE systems that operated from 1992 to 2012 were effective in removing and treating carbon tetrachloride. SVE was incorporated into the September 2011 ROD (EPA et al., 2011) for the vadose waste sites. The systems were maintained in standby mode from October 2012 through 2015 to allow sufficient time for carbon tetrachloride vapor concentrations to rebound. The results for 2014 and 2015 rebound sampling are reported in DOE/RL-2014-48, *Response Action Report for the 200-PW-1 Operable Unit Soil Vapor Extraction Remediation*. Calculations presented in the response action report indicate that remaining contamination in the vadose zone is not causing groundwater cleanup levels to be exceeded.

The response action report established that the removal and remedial actions for carbon tetrachloride and methylene chloride in the vadose zone at the 200-PW-1 OU carbon tetrachloride waste sites have achieved the remedial action objective applicable to the SVE remedy in the 200-PW-1 OU ROD.

The SVE removed over 80,000 kg of carbon tetrachloride during its operation between 1992 and 2012 (DOE/RL-2014-48, Chapter 3). In August 2016, DOE-RL and EPA approved DOE/RL-2014-48, thereby closing the SVE remedy and permanently discontinuing SVE operations and vadose zone monitoring.

- **200-ZP-1 OU ROD (2008):** The use of P&T technology, MNA, flow-path control, and ICs to remediate contaminated groundwater are identified in EPA et al., 2008, *Record of Decision Hanford 200 Area 200-ZP-1 Superfund Site Benton County, Washington*. Groundwater pumping from this activity affects the direction of groundwater flow and the levels of carbon tetrachloride present in the 200 West Area (including the 200-UP-1 OU). Commencing operation in 2012, 200 West P&T receives extracted groundwater from the 200-ZP-1, 200-UP-1, and 200-BP-5 OUs; extracted perched water from the 200-DV-1 OU; and leachate from ERDF. In 2018, conveyance piping was installed to transfer and treat purgewater from the modular storage units (MSUs) to the 200 West P&T as part of an optimization pilot test (DOE/RL-2018-28, *Optimization Test Plan for Treating Water from Modular Storage Units at 200 West Pump and Treat Facility*). The MSU pilot test demonstrated that MSU water can be successfully treated at the 200 West P&T without impact to the facility operations (DOE/RL-2018-70, *Optimization Pilot Test Results of Treating Water from Modular Storage Units at 200 West Pump & Treat Facility*), making the transfer of MSU purgewater from the MSUs to the 200 West P&T a routine feed stream.

In 2019, an optimization study (DOE/RL 2019 38, *200-ZP-1 Operable Unit Optimization Study Plan*) was initiated to evaluate treatment facility modifications, 200 West P&T operational effectiveness, and cost implications for increasing the 200 West P&T treatment design capacity for carbon

tetrachloride. Implementation of the optimization study provides an overall approach to conduct well network optimization to increase overall treatment capacity and accelerate carbon tetrachloride treatment and mass removal. The study will also evaluate transitioning to MNA for nitrate and the effect of suspending the biological treatment component of the 200 West P&T. In 2020, the optimization study implementation continued with completion of layup activities of the biological treatment processes and equipment (suspension of biological treatment for nitrate). The P&T throughput has increased about 13% resulting from improved injection well capacity since the suspension of biological treatment and well fouling mitigation efforts.

The total volume treated in CY 2021 through the 200 West P&T was 4.76 billion L (1.26 billion gal), removing 1,680 kg of carbon tetrachloride, 11.7 kg of chromium (total and hexavalent chromium (Cr(VI)), 9.65kg of trichloroethene (TCE); and 123.7 g (2.10 Ci) of technetium-99. Iodine-129 removal was negligible: 2021 concentrations were at or below the minimum detectable activity in over 75% of the influent and effluent samples.

- **200-PO-1 OU interim remedial action (2021):** The final RI for the 200-PO-1 OU was completed and released in 2012 (DOE/RL-2009-85, *Remedial Investigation Report for the 200-PO-1 Groundwater Operable Unit*). An RI addendum report (DOE/RL-2009-85-ADD1, *Remedial Investigation Report for the 200-PO-1 Groundwater Operable Unit Addendum 1*) released in September 2018 updated the risk assessment and contaminants of potential concern (COPCs) for the OU. The RI identified tritium, iodine-129, nitrate, strontium-90, technetium-99, gross alpha, sulfate, and uranium as final COPCs.

An interim action FS covering both 200-BP-5 and 200-PO-1 OUs (DOE/RL-2018-30, *200-BP-5 and 200-PO-1 Groundwater Operable Units Feasibility Study for Interim Action*) was issued in December 2019 to target remediation of uranium and technetium-99 groundwater contaminants. The proposed plan (DOE/RL-2018-58, *Proposed Plan for Interim Action Remediation of the 200-BP-5 and 200-PO-1 Operable Units*) was issued in March 2020 for public comment in May 2020 and an interim record of decision was approved in September 2021 (EPA et al., 2021, *Interim Record of Decision Hanford 200 Area Superfund Site 200-BP-5 and 200-PO-1 Operable Units*). The ROD selected a combined interim remedy of groundwater extraction and treatment using P&T technology, remedy performance monitoring, and ICs. The selected interim remedial action for the 200-PO-1 OU addresses technetium-99 groundwater contaminant plumes (e.g., concentrations exceeding the 900 pCi/L cleanup level for technetium-99) originating at WMA A-AX and WMA C. Other groundwater contaminants exceeding DWS in the target remediation area (e.g., iodine-129 and nitrate) are identified as collocated or co-contaminants. While cleanup of co-contaminants is not the objective of this interim action, co-contaminants in the target remediation areas for this interim action will be partially captured along with technetium-99. The interim remedy was chosen to allow time for additional source characterization before coming to a final decision for groundwater remediation, and to prevent further technetium-99 plume migration in target remediation areas in the meantime.

- **200-BP-5 OU RI (2013):** Issued in September 2018, DOE/RL-2009-127, *Remedial Investigation Report for the 200-BP-5 Groundwater Operable Unit*, describes the nature and extent of contamination and identifies COPCs to support a future FS. This RI identified 15 COPCs: arsenic, cesium-137, cobalt-60, cyanide, Cr(VI), fluoride, gross alpha, iodine-129, nitrate, plutonium-239/240, strontium-90, sulfate, technetium-99, tritium, and uranium. An interim action FS covering both 200-BP-5 and 200-PO-1 OUs (DOE/RL-2018-30) was issued in December 2019 to target remediation of uranium and technetium-99 groundwater contaminants. The proposed plan (DOE/RL-2018-58) was issued in March 2020 for public comment in May 2020. The preferred alternative includes P&T

to capture and remove uranium and technetium-99 from groundwater in the B Complex plume area, and the C Farm and A-AX Farms plume area. Extracted groundwater would be transferred to the 200 West P&T for treatment. This alternative also includes ICs to prevent exposure to contaminated groundwater until cleanup levels are achieved.

- **200-BP-5 OU Treatability Test (2015):** A three-phase treatability test was initiated in September 2015 (DOE/RL-2010-74, *Treatability Test Plan for the 200-BP-5 Groundwater Operable Unit*). The test consisted of one extraction well located west of the BY Tank Farm. Conveyance of the extracted groundwater to the 200 West P&T radiological building for treatment was completed through an aboveground, dual-walled pipeline. Testing continued through November 19, 2015. The total volume of water extracted from the aquifer during the test was 17.5 million L (4.62 million gal), removing 2.25 kg of uranium and 0.13 Ci of technetium-99. Other contaminants of concern (COCs) removed included 7,419 kg of nitrate, 6.1 kg of cyanide, 0.19 Ci of tritium, and 3.08E-05 Ci of iodine-129. Based on the test results, extraction continued into 2016.
- **200-BP-5 OU removal action (2016):** An engineering evaluation/cost analysis (EE/CA) was submitted to Ecology in June 2015 (DOE/RL-2015-26, *Engineering Evaluation/Cost Analysis for 200-BP-5 Operable Unit Groundwater Extraction*), to transition the extraction of contaminated water from a treatability test to a non-time-critical removal action (NTCRA). Approved in December 2016 by the Tri-Parties with the issuance of DOE/RL-2016-41, *Action Memorandum for 200-BP-5 Operable Unit Groundwater Extraction*, the removal action was implemented to recover elevated levels of groundwater contamination while awaiting completion of the CERCLA RI/FS process and issuance of a 200-BP-5 OU ROD. The B Complex groundwater removal action continued groundwater extraction at well 299-E33-360 and 29-E33-361, in 2021. Approximately 1.59 billion L (419 million gal) of contaminated groundwater has been extracted from the B Complex, of which 321 million L (84.8 million gal) were removed in 2021. Groundwater sample results collected periodically between September 2015 and December 2021 indicate that approximately 7.47 Ci of technetium-99 and 240 kg of uranium have been removed from the B Complex unconfined aquifer.
- **200-BP-5 and 200-PO-1 interim action ROD (2021):** An interim action FS covering both 200-BP-5 and 200-PO-1 OUs (DOE/RL-2018-30) was issued in December 2019 to target remediation of uranium and technetium-99 groundwater contaminants. The proposed plan (DOE/RL-2018-58) was issued in March 2020 for public comment in May 2020 and an interim record of decision was approved in September 2021 (EPA et. al., 2021). The selected remedy includes P&T to capture and remove uranium and technetium-99 from groundwater in the B Complex plume area, and the C Farm and A-AX Farms plume area. Extracted groundwater would be transferred to the 200 West P&T for treatment. Other elements of the selected remedy include P&T system O&M, installation of new groundwater monitoring wells, performance monitoring, and ICs.
- **200-DV-1 OU perched water removal action (2011):** A perched water pumping/pore water extraction treatability test commenced in 2011, near the north boundary of the B Tank Farm as part of the DVZ treatability testing project. By the end of CY 2014, perched water extraction using well 299-E33-344 had removed 945,289 L (249,727 gal) of contaminated perched water, including 53.0 kg of uranium, 0.031 Ci of technetium-99, and 495 kg of nitrate. The following two documents were completed in 2014 for transition of the perched water treatability test to an NTCRA:
  - DOE/RL-2013-37, *Engineering Evaluation/Cost Analysis for Perched Water Pumping/Pore Water Extraction*

- DOE/RL-2014-34, *Action Memorandum for 200-DV-1 Operable Unit Perched Water Pumping/Pore Water Extraction*

In August 2015, perched water extraction was temporarily discontinued to enhance water removal by adding two new wells to the system. The perched water treatability test transitioned to a CERCLA NTCRA (DOE/RL-2014-34) when extraction began using all three wells in 2016. In CY 2020, the perched water extraction wells removed 1,179,945 L (311,700 gal) of perched water containing 70.4 kg of uranium, 3.1 g of technetium-99, and 1,304 kg of nitrate. Since perched water extraction began in 2011, a total of 7,272,353 L (1,921,144 gal) of perched water containing 298 kg of uranium, 15.8 g (0.269 Ci) of technetium-99, and 7,141 kg of nitrate has been removed from the perched zone.

### **1.3.2.3 Central Plateau Groundwater Remedial Activities**

Central Plateau groundwater and vadose zone remediation systems have removed more than 115,914 kg of carbon tetrachloride from groundwater since 1992. During 2021, 19 new wells in the Central Plateau were installed for monitoring, remediation, and/or characterization. Samples from 499 monitoring wells and 16 shoreline aquifer tubes for the Central Plateau groundwater interest areas were collected and analyzed to determine the distribution and movement of contaminants. Many of the wells and aquifer tubes were sampled multiple times during the reporting period, resulting in 1,313 well sampling events. The samples were analyzed for a variety of radionuclides and other constituents.

The P&T systems located in the Central Plateau target radionuclides (including technetium-99 in the 200-ZP-1, 200-UP-1, and 200-BP-5 OUs) and are of direct interest with respect to the Hanford Site Composite Analysis. P&T systems are also of indirect interest because perturbations to the hydraulic flow system induced by P&T systems were not included in the features, events, and processes modeled for the current Hanford Site Composite Analysis. The groundwater model for the Hanford Site Composite Analysis was developed in the 1990s before remedial decisions for groundwater had been made. At that time, it was not possible to anticipate the locations, pumping or injection rates, and pumping or injection durations of extraction and injection wells that since have been used to accomplish groundwater remedial actions. Table 1-6 summarizes the status of Central Plateau P&T systems for the reporting period. The radionuclide activity removed to date and hydraulic perturbations induced by P&T systems reviewed are not yet considered to have a significant impact if they were to be included in the Hanford Site Composite Analysis model. However, it is reasonable to assume that the impact of inclusion of this feature in the model would result in a reduction in the projected radiological dose estimate from the groundwater pathway. The P&T systems are planned to operate for an extended time, and consideration of the impact of these systems on the all-pathways dose will be addressed in the upcoming revision of the Hanford Site Composite Analysis that was prepared in FY 2022 and is under review by the LFRG in FY 2023.

Activities in the four Central Plateau groundwater OUs that provide new information on radionuclide constituents relevant to the Hanford Site Composite Analysis are discussed in the following sections for each respective OU. The remediation status for each OU is presented if remediation information exists for the OU for the reporting period. If remedial action was not in progress during the reporting period, the groundwater concentration status was summarized as well as any other relevant work that occurred during the reporting period.

**Table 1-6. Status of Central Plateau Groundwater Remediation in Calendar Year 2021**

OU	CERCLA Decision Status	Groundwater Contaminants of (Potential) Concern <sup>a</sup>	Current Groundwater Remediation	Mass Removed in 2021 (and Since Startup) <sup>b</sup>
200-BP-5	Implemented treatability test (2015) and action memorandum (2016); FS released in 2019; proposed plan issued in 2020; interim action ROD approved in 2021.	Cyanide, iodine-129, nitrate, strontium-90, technetium-99, tritium, and uranium	Groundwater extraction removal action (2015–2020)	Cyanide: 48.4 kg (270 kg) Technetium-99: 70.2g (437 g) Uranium: 27.7 kg (240 kg)
200-PO-1	FS released in 2019; proposed plan issued in 2020; interim action ROD approved in 2021.	Iodine-129, tritium, nitrate, strontium-90, technetium-99, and uranium	None to date; pending remedy implementation for interim action ROD	Not applicable
200-UP-1	ROD for interim remedial action signed (2012).	Technetium-99, uranium, carbon tetrachloride, Cr(VI), total chromium, iodine-129, nitrate, tritium, trichloroethene, chloroform, tetrachloroethene, strontium-90, and 1,4-dioxane	Interim actions: <ul style="list-style-type: none"> <li>• P&amp;T near U Plant (2015–2021)</li> <li>• P&amp;T at WMA S-SX (2012–2021)</li> <li>• Hydraulic containment for iodine-129 (2015–2021)</li> <li>• MNA</li> </ul>	Technetium-99: 18.4 g (441 g <sup>c</sup> ) Uranium: 7.9 kg (985 kg <sup>c</sup> )
200-ZP-1	ROD for final remedial action signed (2008).	Carbon tetrachloride, Cr(VI), total chromium, iodine-129, nitrate, technetium-99, trichloroethene, and tritium	P&T and MNA (2012–2021)	Carbon tetrachloride: 1,654 kg (34,370 kg <sup>c</sup> ) Chromium: 8.27 kg (520 kg) Technetium-99: 37.3 g (279.5 kg) Trichloroethene: 9.64 kg (93.66 kg)
200-DV-1 <sup>d</sup>	Implemented treatability test (2011) and action memorandum (2016); characterization of the deep vadose zone in progress.	Nitrate, technetium-99, uranium, tritium, total chromium, and Cr(VI) (perched water)	Removal action: Perched water extraction (2011–2021)	Technetium-99: 3.0 g (15.7 g <sup>c</sup> ) Uranium: 66.9 kg (395 kg <sup>c</sup> )

Source: DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*.

a. Contaminants of concern are listed for OUs with RODs for final action and implemented action memoranda. The primary contaminants of potential concern are listed for the other OUs.

b. A total of 2,186,276 kg of nitrate was also removed by the 200 West Area groundwater treatment facility. Nitrate is no longer treated, following suspension of biological treatment in October 2019 for the 200-ZP-1 OU optimization study.

c. Totals includes mass from P&T systems under earlier RODs for interim action and 200-DV-1 OU treatability test.

d. Deep vadose zone OU.

CERCLA = *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*

OU = operable unit

Cr(VI) = hexavalent chromium

P&T = pump and treat

FS = feasibility study

ROD = Record of Decision

MNA = monitored natural attenuation

WMA = waste management area

### 1.3.2.4 200-BP-5 Groundwater Operable Unit

The 200-BP-5 OU includes groundwater beneath the northern portion of 200 East Area and the region to the northwest, where mobile contaminants have migrated between Gable Mountain and Gable Butte.

Nitrate, iodine-129, and technetium-99 form the most extensive contaminant plumes in this OU.

These contaminants originated mainly from local sources except for iodine-129, which migrated into the 200-BP-5 OU from the 200-PO-1 OU in the late 1980s and early 1990s. These mobile contaminants have migrated beyond the 200 East Area to the northwest due to past artificial groundwater gradients.

Cyanide and uranium are present as smaller plumes associated with past releases in the B Complex, located in the northwest corner of the 200 East Area, which includes the BY Cribs and B-BX-BY Tank Farms. Strontium-90 is present as two localized plumes, mainly beneath the originating waste sites 216-B-5 injection well and Gable Mountain Pond. Two other localized plumes are also present at the 216-B-5 injection well: cesium-137 and plutonium-239/240. RI drilling in 2010 provided evidence of a concentrated plume in the lower part of the aquifer near the 216-B-12 Crib and B Plant. Two additional wells, one north (Well 299-E28-31) and one south (Well 299-E28-32) of B Plant, were drilled in this area during 2015 to improve characterization of the extent of tritium at depth. Tritium concentrations in the well north of B Plant ranged from 45,200 to 52,500 pCi/L at three depth-discrete sample intervals: 7.4, 13.5, and 15.8 m (24, 44, and 52 ft) below the water table. In the new well south of B Plant, tritium increased with depth with concentrations of 18,900 pCi/L, 49,000 pCi/L, and 91,600 pCi/L at depth-discrete sample intervals 7.4, 13.2, and 19 m (24, 43, and 62 ft) below the water table, respectively. In 2017, the tritium concentrations were detected in deep wells 299-E28-31 (48,700 pCi/L) and 299-E28-32 (41,200 pCi/L), near the 216-B-12 Crib. Near B Pond, tritium concentrations at well 699-42-40A (27,700 pCi/L) have declined since 2015, consistent with natural decay.

Most groundwater contamination in the 200-BP-5 OU is concentrated beneath WMA B-BX-BY and adjacent waste sites in the northwestern portion of the OU. Radionuclide COPCs for the 200-BP-5 Groundwater OU include cesium-137, cobalt-60, gross alpha, iodine-129, plutonium-239/240, strontium-90, technetium-99, tritium, and uranium (DOE/RL-2009-127). The selected remedy in the 200-BP-5 and 200-PO-1 OU interim ROD (EPA et., al, 2021) targets remediation of uranium and technetium-99 groundwater contaminants. Extracted groundwater would continue to be transferred to the 200 West P&T for treatment.

**RCRA Monitoring.** Six TSD units are monitored under RCRA in coordination with CERCLA and AEA requirements: Low-Level Waste Management Area (LLWMA)-1, LLWMA-2, WMA B-BX-BY, WMA C, the Liquid Effluent Retention Facility, and the 216-B-63 Trench. RCRA monitoring of the six TSD units is conducted in accordance with the following:

- The LLBG WMA-1 is monitored under an interim status indicator evaluation program as described in DOE/RL-2009-75, *Interim Status Groundwater Monitoring Plan for the LLMA-1*, effective in August 2016. The monitoring plan was revised in 2021 for updates to the monitoring well network to include three proposed downgradient wells (with 1 year of quarterly sampling).
- LLBG WMA-2 is monitored under an interim status indicator evaluation program described in DOE/RL-2009-76, *Interim Status Groundwater Monitoring Plan for the LLWMA-2*.
- WMA B-BX-BY is monitored under an interim status assessment program in accordance with DOE/RL-2019-74, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank System*, as modified by RCRA-CN-01\_DOE/RL-2019-74\_R0, *Interim Status Change Number 1: Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank System*, effective in June 2021.

- WMA C is monitored under an interim status assessment program in accordance with DOE/RL-2019-74 as modified by RCRA-CN-01\_DOE/RL-2019-74\_R0.
- Groundwater at the liquid effluent retention facility is monitored under a final status detection monitoring program under the Hanford RCRA Permit (Part III, OUG-3, Addendum D, “Groundwater Monitoring Plan” [modification date of January 23, 2018]).
- 216-B-63 Trench is monitored under an interim status indicator evaluation program as defined in DOE/RL-2008-60, *Interim Status Groundwater Monitoring Plan for the 216-B-63 Trench*, effective in October 2012.

Since 2011, continued declining groundwater elevation in the 200 East Area has resulted in a changing flow direction in the northwest corner of the 200 East Area. Flow began changing from northwest to south-southeast in June 2011. By August 2011, a statistically significant gradient to the south-southeast was measured. The south-southeast flow direction has continued to present. This reversal is further documented by the southeast migration of groundwater contaminants extending from WMA B-BX-BY and the BY Cribs. The effects of the new groundwater flow direction are apparent beneath WMA C. During FY 2013, groundwater contamination west of WMA C began to decrease significantly, while concentrations increased in the south and southeast portion of WMA C. The following quarterly reports for WMA C explain the groundwater flow dynamics:

- SGW-59669, *WMA C October through December 2015 Quarterly Groundwater Monitoring Report*
- SGW-59914, *WMA C January through March, 2016 Quarterly Groundwater Monitoring Report*
- SGW-60442, *WMA C April through June 2016 Quarterly Groundwater Monitoring Report*
- SGW-60494, *WMA C July through September 2016 Quarterly Groundwater Monitoring Report*

Several wells were selected for low-gradient monitoring across the 200 East Area to define the groundwater flow near WMA C more accurately. The wells were precision surveyed and corrected for borehole deviation through gyroscope surveys. Data correction for barometric response was evaluated for these wells and the expanded water-level network in FY 2014. The expanded 200 East Area low hydraulic gradient water level network and the relationship between the Treated Effluent Disposal Facility discharges and gradient magnitude are discussed in SGW-58828, *Water Table Maps for the Hanford Site 200 East Area, 2013 and 2014*.

**Treatability Testing.** DOE-RL designed and published a treatability test (DOE/RL-2010-74) to evaluate P&T of groundwater for remediation of uranium and technetium-99 contamination near WMA B (B-BX-BY Tank Farms). In 2011, installation began for an extraction well to support the test, and the well was completed in 2012.

The treatability test (DOE/RL-2010-74) was completed between August and November 2015 to evaluate the groundwater extraction rate that could be sustained in the unconfined aquifer at the B Complex. The test results are documented in DOE/RL-2015-75, *Aquifer Treatability Test Report for the 200-BP-5 Groundwater Operable Unit*.

**Removal Action.** The EE/CA for B Complex groundwater extraction (DOE/RL-2015-26) was issued in April 2016 to evaluate the implementation of a NTCRA for the extraction and treatment of groundwater near the B Complex in the 200-BP-5 OU. The EE/CA recommended groundwater extraction for conveyance to the 200 West Treatment Plant. The removal scope was approved by the Tri-Parties in December 2016 with the issuance of an action memorandum for 200-BP-5 OU groundwater extraction (DOE/RL-2016-41). The transition to the NTCRA provided authorization to revise the extraction network for more optimal removal of uranium and technetium-99. DOE/RL-2017-11, *Removal Action Work Plan*

for 200-BP-5 Operable Unit Groundwater Extraction, was approved in March 2018 and established a formal removal action-monitoring network to assess the progress of plume size reduction. Four additional monitoring wells were drilled in 2019 to assess concentration changes more thoroughly to the north and south/southeast of B Complex. Comparing the 2015 technetium-99 and uranium plumes to conditions through 2021, the technetium-99 plume areal extent has been reduced 64% and the uranium plume has been reduced 81%.

**Perched Water.** A fine-grained, bowl-shaped geologic unit beneath the B Complex has created an area of saturated sediments (perched water) in the DVZ above the regional water table. The perched water is contaminated with uranium, technetium-99, and other nonradiological contaminants. To address the groundwater impact associated with infiltration from the perching horizon, DOE-RL initiated a perched water pumping treatability test in 2011 (DOE/RL-2011-40, *Field Test Plan for the Perched Water Pumping/Pore Water Extraction Treatability Test*). Well 299-E33-344 was used for extraction during the test. Pumping began in August and continued until early December 2011, when extracted perched water contaminant concentrations increased significantly and required a different waste disposal path. Pumping resumed in April 2012. The uranium concentration increased from 4,500 µg/L in September to 63,600 µg/L in October 2012. The increase in concentration was confirmed in December with a result of 71,500 µg/L. These were the highest uranium concentrations detected at the Hanford Site during 2011.

In December 2014, the action memorandum for 200-DV-1 OU perched water pumping/pore water extraction (DOE/RL-2014-34) was signed to document the selected alternative for perched water removal under CERCLA. The selected alternative extracts perched water and transfers the water by tanker truck or pipeline to the 200 West P&T, where it is treated and injected into the aquifer below the 200 West Area. DOE/RL-2014-37, *Removal Action Work Plan for 200-DV-1 Operable Unit Perched Water Pumping/Pore Water Extraction*, was approved in November 2015.

Two additional perched water extraction wells (299-E33-350 and 299-E33-351) were drilled in 2014. The two new wells were added to the extraction system in 2016.

In 2019, a hydraulic analysis examined extraction well configuration options for increasing the rate of contaminated perched water removal (SGW-63236, *200-DV-1 Future Perched Water Well Evaluation*). The analysis concluded that the low hydraulic conductivity and relatively thin saturated thickness of the perched water zone severely limits the flow of perched water into extraction wells (SGW-65178, *Evaluation of Two Alternative Drilling Scenarios (Horizontal Drilling and Drilling of Vertical Wells within Tank Farms) for Increasing Extraction within the Perched Water Zone*). The outcome of the analysis was that a horizontal well was not recommended for the perched water zone.

This analysis, as well as other existing information for the perched water zone and the overall hydrogeological system, is used to guide planning to install an additional eight extraction wells and four monitoring wells within the perched water zone. Drilling of the first well (299-E33-269) began in 2020 and was completed in 2021. Drilling of the second well (299-E33-270) began in 2021 and the well was completed in February 2022. Post-development perched water sample results from well 299-E33-269 were 95.1 mg/L for uranium; 65,200 pCi/L for technetium-99; and 819 mg/L for nitrate. Construction of well 299-E33-269 (D0112) is complete for future connection as an extraction well to the 200 West P&T. Well 299-E33-270 did not produce sufficient water for well development or sampling. Construction of well 299-E33-270 is complete but it is not suitable for use as an extraction well because of the slow recharge at this well.

**AEA Monitoring.** AEA groundwater monitoring was conducted at 200-BP groundwater interest area wells in accordance with DOE/RL-2015-56, *Hanford Atomic Energy Act Sitewide Groundwater Monitoring*

*Plan.* The primary AEA constituents for 200-BP groundwater interest area are iodine-129, nitrate, technetium-99, strontium-90, uranium, and tritium. For 2021, radionuclide concentrations detected in groundwater samples from 164 wells were used to estimate the cumulative total effective dose (TED) and to compare the cumulative beta/photon emitters, alpha emitters, and uranium mass to DWSs.

The estimated TED exceeded the 100 mrem/yr standard at four groundwater wells in 200-BP.

The cumulative drinking water dose from beta/photon emitters exceeded the 4 mrem/yr standard at 89 locations in the 200-BP groundwater interest area. One well exceeded the DWSs for cumulative alpha emitters, and two wells exceeded the EPA net alpha activity standard. The 30 µg/L uranium DWS was exceeded at 17 locations. None of these locations is adjacent to the Columbia River, which is the primary potential offsite exposure pathway to Hanford Site contaminated groundwater. The public is protected from exposure to onsite groundwater through the implementation of ICs that restrict access to groundwater. Details of the AEA evaluations are presented in Section 9.11 of DOE/RL-2021-51.

Review of FY 2019 CERCLA investigations and CERCLA/RCRA/AEA monitoring activities reported in DOE/RL-2021-51 and evaluated in FY 2022 did not reveal any new information associated with the 200-BP-5 OU with potential to significantly alter the conclusions of the Hanford Site Composite Analysis.

### **1.3.2.5 200-PO-1 Groundwater Operable Unit**

The 200-PO-1 OU is in the southern portion of the 200 East Area. Disposal of large volumes of liquid waste from PUREX and its related facilities created regional groundwater plumes of tritium, iodine-129, and nitrate. Concentrations of tritium are declining as the plume attenuates naturally from radioactive decay and dispersion, and the tritium plume area above the 20,000 pCi/L cleanup level has decreased in size by about 57% since 1996. The area of the iodine-129 plume above the 1 pCi/L DWS has decreased slightly over the past decade, and maximum concentrations have declined due to dispersion. Radioactive decay has not decreased the level of iodine-129 noticeably because the isotope has a low decay rate (15.7 million year half-life). The nitrate plume covers a large area, but concentrations within the far-field area have decreased to below the DWS, except near the 618-11 Burial Ground. Other contaminants include strontium-90, technetium-99, and uranium in smaller areas near their sources. The selected remedy in the 200-BP-5 and 200-PO-1 OU interim ROD (EPA et., al, 2021) targets remediation of uranium and technetium-99 groundwater contaminants by groundwater extraction and treatment. Extracted groundwater would be transferred to the 200 West P&T for treatment.

**Soil Desiccation Test.** A soil desiccation treatability test (DOE/RL-2009-119, *Characterization of the Soil Desiccation Pilot Test Site*) was performed from 2010 to 2011 in an interval containing high moisture and associated technetium-99 contamination near the BC Cribs and Trenches. This technology is being considered as a potential remedy in the DVZ. For 6 months, nitrogen was injected into a well and soil gas was extracted from another well. A combination of in situ sensors and geophysical measurements provided data to monitor performance. As anticipated, desiccation occurred more rapidly from higher permeability sediment. The active portion of the test was completed, and the pilot test results were reported in DOE/RL-2012-34, *Deep Vadose Zone Treatability Test for the Hanford Central Plateau: Soil Desiccation Pilot Test Results*.

Since 2011, posttest monitoring has been conducted and reported annually. Post-test monitoring concluded in 2017, and a final comprehensive post-test monitoring report was issued in February 2018 (PNNL-26902, *Deep Vadose Zone Treatability Test of Soil Desiccation for the Hanford Central Plateau: Final Report*). Overall, the desiccation test at the 200-BC-1 OU field test site provides sufficient information for desiccation to be applied in conjunction with a surface infiltration barrier and consideration as a potential vadose zone remedy in future feasibility studies.

**RCRA Assessment Monitoring.** During 2020, monitoring continued at seven RCRA units: WMA A-AX single-shell tanks, 216-A-36B Crib, 216-A-37-1 Crib, 216-A-29 Ditch, IDF, 216-B-3 Pond, and NRDWL. RCRA monitoring of the seven TSD units are conducted in accordance with the following:

- WMA A-AX was monitored under an interim status assessment program (DOE/RL-2015-49, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area A-AX*) since 2005 when specific conductance exceeded the critical mean value. In September and December 2020, WMA A-AX was monitored under an indicator evaluation monitoring plan (DOE/RL-2019-44, *Interim Status Groundwater Monitoring Plan for the Single-Shell Tank Waste Management Area A-AX*) because a first determination assessment report (DOE/RL-2019-21, *Groundwater Assessment First Determination Report for Waste Management Area A-AX*) concluded that no dangerous waste groundwater contamination is attributed to releases from WMA A-AX. The surface of the uppermost unconfined aquifer at WMA A-AX is extremely flat. In 2021, groundwater near WMA A-AX was interpreted to flow to the east-southeast. The estimated hydraulic gradient was  $9.9 \times 10^{-6}$  m/m, with an estimated average linear velocity of 0.49 m/d (1.6 ft/d).
- The 216-A-36B Crib is monitored under an interim status indicator evaluation program described in DOE/RL-2010-93, *Interim Status Groundwater Monitoring Plan for the 216-A-36B PUREX Plant Crib*.
- The 216-A-37-1 Crib is monitored under an interim status indicator evaluation program described in DOE/RL-2010-92, *Interim Status Groundwater Monitoring Plan for the 216-A-37-1 PUREX Plant Crib*.
- In January 2016, the 216-A-29 Ditch was placed into a groundwater assessment program because specific conductance in wells 299-E25-32P, 299-E25-35, and 299-E25-48 exceeded the critical mean value in 2015. During the second half of 2020, the ditch was monitored under an indicator evaluation program because assessment results indicated that no dangerous waste groundwater contamination was attributed to releases from the 216-A-29 Ditch (DOE/RL-2019-27, *Groundwater Assessment First Determination Report for the 216-A-29 Ditch*). Interim status indicator evaluation monitoring was reinstated under DOE/RL-2008-58, *Interim Status Groundwater Monitoring Plan for the 216-A-29 Ditch*, during the third quarter of 2020.
- The 216-B-3 main pond is monitored under an interim status indicator evaluation program described in DOE/RL-2008-59, *Interim Status Groundwater Monitoring Plan for the 216-B-3 Pond*; as modified by RCRA-CN-01\_DOE/RL-2008-59\_R2, *RCRA Interim Status Change Number 1: Interim Status Groundwater Monitoring Plan for the 216-B-3 Pond*. The January 2021 sampling event indicated a possible exceedance of the critical mean for specific conductance in a downgradient well (699-42-42B). The exceedance was confirmed in February 2021, and the unit entered into a groundwater quality assessment monitoring program in accordance with 40 CFR 265.93(d)(4) in July 2021. Groundwater monitoring at B Pond in the third and fourth quarters of 2021 was conducted under DOE/RL-2021-24, *Interim Status Groundwater Quality Assessment Plan for the 216-B-3 Pond*.
- The IDF is monitored under a pre-operational final status detection monitoring program under the Hanford RCRA Permit (Part III, OUG-11, Chapter 5.0, “Groundwater Monitoring” [modification date of June 30, 2010]). In 2019, DOE submitted a plan for a revised groundwater monitoring program to Ecology (DOE/RL-2019-29, *Groundwater Monitoring Plan for the Integrated Disposal Facility*). The revised monitoring program will be incorporated into the Hanford RCRA Permit in the future. Ecology approved DOE’s request to begin baseline sampling under the revised monitoring

program in 2020. Because the IDF is not yet operating, the current monitoring objective is to collect baseline groundwater information.

- The NRDWL entered a groundwater quality assessment monitoring program in 2017, which continued in 2019 in accordance with DOE/RL-2017-19, *Groundwater Quality Assessment Plan for the Nonradioactive Dangerous Waste Landfill, Hanford Site*. Five-quarters of assessment monitoring data were evaluated for potentially dangerous waste constituents attributable to the NRDWL. Due to a confirmed exceedance of the critical mean for specific conductance at downgradient well 699-25-34B in August 2020, a groundwater quality assessment monitoring program was reinstated at NRDWL in December 2020. Consequently, DOE monitors groundwater beneath NRDWL in accordance with 40 CFR 265.93(d)(4). During 2021 NRDWL was monitored under DOE/RL-2020-57, *Groundwater Quality Assessment Plan for the Nonradioactive Dangerous Waste Landfill*.

**AEA Monitoring.** AEA groundwater monitoring was conducted at 200-PO-1 groundwater wells and aquifer tubes in accordance with DOE/RL-2015-56. The primary AEA constituents for 200-PO-1 are tritium, iodine-129, nitrate, strontium-90, technetium-99, and uranium. Radionuclide concentrations detected in groundwater samples from 126 wells were used to estimate the cumulative TED and to compare the cumulative beta/photon emitters, alpha emitters, and uranium mass to DWSs. None of the wells in 200-PO exceeded the estimated TED 100 mrem/yr standard. None of the DWSs for cumulative alpha emitters and EPA net alpha activity standard were exceeded. The cumulative drinking water dose from beta/photon emitters exceeded the 4 mrem/yr standard at 74 locations in the 200-PO-1 groundwater interest area. One location exceeded the 30 µg/L uranium DWS. One location that exceeded the beta/photon emitters (aquifer tube C6353) is adjacent to the Columbia River, which is the primary potential pathway for offsite exposure to Hanford Site contaminated groundwater. Members of the public are protected from exposure to groundwater through the implementation of ICs that restrict access to groundwater. Details of the evaluation are presented in Section 10.12 of DOE/RL-2021-51.

The review of FY 2020 CERCLA investigations and CERCLA/RCRA/AEA monitoring activities reported in the Hanford Site groundwater monitoring annual report for CY 2021 (DOE/RL-2021-51) did not reveal any new information associated with the 200-PO-1 OU with potential to significantly alter the conclusions of the Hanford Site Composite Analysis.

### **1.3.2.6 200-UP-1 Groundwater Operable Unit**

The 200-UP-1 OU includes the southern portion of the 200 West Area and adjacent areas to the east and south. Primary contaminant sources in the OU include cribs, ditches, ponds, and single-shell tanks associated with Reduction-Oxidation Plant operations for plutonium and uranium separation and the U Plant for uranium recovery. Technetium-99, uranium, tritium, iodine-129, nitrate, chromium, and carbon tetrachloride plumes are present in groundwater, and strontium-90 also exceeds its DWS in one well. The carbon tetrachloride plume originated from the 200-ZP-1 OU. Technetium-99 concentrations in the 200-UP-1 OU are the highest measured in groundwater on the Hanford Site. Near U Plant, the areal extent of the technetium-99 plume above the 900 pCi/L cleanup level has decreased substantially due to operation of an interim action P&T system from 1997 until 2011 and operation of the current P&T system since September 2015. In contrast, the technetium-99 plume near WMA S-SX have persisted due to continuing technetium-99 flux to groundwater beneath the WMA. A groundwater extraction system began operating in 2012 to address the plumes downgradient of the S Tank Farm and the southern portion of the SX Tank Farm (where technetium-99 concentrations are greatest, exceeding 12,000 pCi/L in 2021). A technetium-99 plume also is present downgradient of the U Tank Farm, the extent of which will be investigated with drilling of two new monitoring wells east of the farm in CY 2023. The tritium plume is attenuating due to dispersion and radioactive decay and has not migrated substantially, and the areal

extents of other plumes in the OU have remained largely unchanged or have decreased slightly in the past decade.

A P&T system for the uranium, technetium-99, and nitrate plumes near U Plant and injection wells for hydraulic containment of the iodine-129 plume were implemented as part of the 200-UP-1 groundwater remedy. Operation of both remedies started in late CY 2015.

An iodine-129 treatment technology evaluation was completed in September 2019, as summarized in DOE/RL-2013-07. The conclusion of this evaluation was that the practicability of all candidate remediation technologies for the iodine-129 plume is low, driven by site and contaminant properties that hinder effectiveness and/or implementability of the technologies. Because a viable remediation technology is not available for the iodine-129 plume, a technical impracticability waiver may be pursued in accordance with 40 CFR 300.430(f)(1)(ii)(c), “National Oil and Hazardous Substances Pollution Contingency Plan,” “Remedial Investigation/Feasibility Study and Selection of Remedy.”

**Decision Documents.** In 2012, DOE-RL released the final RI/FS report (DOE/RL-2009-122, *Remedial Investigation/Feasibility Study for the 200-UP-1 Groundwater Operable Unit*) and DOE/RL-2010-05, *Proposed Plan for Remediation of the 200-UP-1 Groundwater Operable Unit*. The ROD for interim remedial action (EPA et al., 2012) was signed in September 2012 for all 200-UP-1 OU COCs.

The selected remedies use a combination of groundwater P&T, MNA, hydraulic containment for iodine-129 while treatment technologies are investigated, and ICs. The RD/RAWP (DOE/RL-2013-07) was issued in September 2013 and revised in August 2020. The PMP (DOE/RL-2015-14, *Performance Monitoring Plan for the 200-UP-1 Groundwater Operable Unit Remedial Action*) was issued in August 2015 (Rev. 0) and revised in August 2020 (Rev. 1).

**Remedial Actions.** Although originally designed as a remedy under the 1997 ROD (EPA/ROD/R10-97/048), the WMA S-SX groundwater extraction system is now operating under the current ROD (EPA et al., 2012). The remedial actions identified in the 2012 ROD for groundwater extraction near U Plant and hydraulic containment of iodine-129 were implemented in CY 2015.

**RCRA Monitoring.** In the 200-UP-1 OU, RCRA monitoring included interim status groundwater quality assessment monitoring at WMA S-SX and WMA U as well as interim status indicator parameter evaluation monitoring at the 216-S-10 Pond and Ditch. The monitoring results did not show major changes in the extent of contamination. Indicator parameters did not exceed statistical comparison values at the 216-S-10 Pond and Ditch during 2021. RCRA monitoring of the three TSD units are conducted in accordance with the following:

- In 2019, the WMA S-SX assessment plan was revised to update the well network (DOE/RL-2009-73, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area S-SX*). The objective of RCRA monitoring at WMA S-SX is to assess the rate and extent of migration and the concentration of the dangerous waste constituent chromium in the groundwater.
- The revised groundwater quality assessment plan (DOE/RL-2009-74, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area U*) was released in 2019.
- In the third and fourth quarters of 2020, monitoring of WMA S-SX and WMA U was performed in compliance with a new assessment plan, DOE/RL-2019-74 (effective in July 2020) implementing the monitoring network recommended in SGW-60577, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area S-SX Groundwater Monitoring*, and SGW-60578,

*Engineering Evaluation Report for Single-Shell Tank Waste Management Area U Groundwater Monitoring.*

- 216-S-10 Pond and Ditch is monitored under an interim status indicator evaluation program described in DOE/RL-2008-61, *Interim Status Groundwater Monitoring Plan for the 216-S-10 Pond and Ditch*.

Groundwater monitoring in the 200-UP-1 OU also includes ERDF monitoring. Groundwater monitoring at ERDF is regulated under a CERCLA ROD (EPA/ROD/R10-95/100). The site was designed to meet RCRA standards, although it is not actually permitted as a RCRA facility. (Note: The ERDF PA is discussed in Section 1.1.5, and ERDF operations are discussed in Section 1.3.3.2 of this report.) In 2021, groundwater monitoring results continued to indicate that the facility has not adversely affected groundwater quality.

**AEA Monitoring.** AEA groundwater monitoring was conducted at 200-UP-1 groundwater wells in accordance with DOE/RL-2015-56. The primary AEA constituents for 200-UP-1 are iodine-129, nitrate, technetium-99, tritium, and uranium. Radionuclide concentrations detected in groundwater samples from 91 wells were used to estimate the cumulative TED and to compare to cumulative beta/photon emitters, alpha emitters, and uranium mass to DWSs. The estimated TED exceeded the 100 mrem/yr standard at one groundwater well in 200-UP. The cumulative drinking water dose from beta/photon emitters exceeded the 4 mrem/yr standard at 41 locations in the 200-UP-1 groundwater interest area. No locations exceeded the DWSs for cumulative or net alpha emitters. The 30 µg/L uranium DWS was exceeded at 10 locations. None of these locations is adjacent to the Columbia River, which is the primary potential pathway for offsite exposure to Hanford Site contaminated groundwater. The public is protected from groundwater exposure through the implementation of ICs that restrict access to groundwater and through remedial action measures (e.g., P&T) to control the migration of contaminated groundwater to exposure points. Details of the evaluation are presented in Section 11.12 of DOE/RL-2021-51.

Review of FY 2020 CERCLA investigations and CERCLA/RCRA/AEA monitoring activities reported in the Hanford Site groundwater monitoring report for CY 2021 (DOE/RL-2021-51) and evaluated in FY 2022 did not reveal any new information associated with the 200-UP-1 OU with potential to significantly alter the conclusions of the Hanford Site Composite Analysis.

### **1.3.2.7 200-ZP-1 Groundwater Operable Unit**

The 200-ZP-1 OU includes groundwater beneath the northern portion of the 200 West Area and adjacent areas to the east and north. The COCs for the 200-ZP-1 OU are carbon tetrachloride, TCE, iodine-129, technetium-99, nitrate, Cr(VI), total chromium, and tritium.

SVE was implemented as an expedited response action to remove and treat carbon tetrachloride contamination in the vadose zone at 200-PW-1 OU waste sites. Two SVE systems for soil vapor remediation operated from 1992 to 2012 to remove and treat carbon tetrachloride. The SVE systems were maintained in standby mode from October 2012 through April 2015 to allow time for carbon tetrachloride vapor concentrations to rebound. The results for the rebound sampling were reported in DOE/RL-2014-48. In August 2016, DOE-RL and EPA approved DOE/RL-2014-48 (agency approvals contained within the document), thereby closing the SVE remedy and permanently discontinuing SVE operations and vadose zone monitoring.

Since 1994, DOE-RL has implemented a groundwater P&T system to prevent carbon tetrachloride in the upper portion of the aquifer from spreading. Operated from 1994 through May 2012, the interim P&T system limited the movement of shallow, high-concentration portions of the plume but did not address contamination deeper in the aquifer and at the periphery of the plume. The current 200 West P&T implements the 2008 200-ZP-1 ROD to remediate groundwater throughout the entire aquifer thickness

and provide treatment for carbon tetrachloride, TCE, iodine-129, technetium-99, nitrate, Cr(VI), and total chromium.

Four monitoring well locations in the 200-ZP groundwater interest area had iodine-129 concentrations exceeding the 1 pCi/L cleanup level in at least one sample since 2020: well 299-W14-13, located east of WMA TX-TY (6.76 pCi/L), and wells 299-W6-17, 299-W11-33Q, and 299-W5-2P, located in the northeastern 200 West Area (1.97 pCi/L, 1.36 pCi/L, and 1.09 pCi/L, respectively). Iodine-129 sources include past leaks from single-shell tanks (containing metal and liquid waste) and chemical processing at T Plant. The minimum detectable activity for iodine-129 varies from about 0.3 to 1.2 pCi/L.

Technetium-99 exceeds the 900 pCi/L final cleanup level in two distinct plumes east of WMA T and WMA TX-TY. Technetium-99 sources in 200-ZP groundwater interest area were leaks from tanks and pipelines, and liquid waste disposal from plutonium-processing operations to cribs and trenches adjacent to the WMAs. Technetium-99 is found primarily in the upper 15 m (50 ft) of the unconfined aquifer (Section 2.8 in DOE/RL-2008-01, *Hanford Site Groundwater Monitoring for Fiscal Year 2007*).

Technetium-99 exceeded the 900 pCi/L cleanup standard at two monitoring wells in the 200-ZP-1 OU in 2021. The biggest change in concentration was at monitoring well 299-W14-18, with a maximum of 13,800 pCi/L in 2021 compared to 24,800 pCi/L in 2020. In 2020, an internal evaluation was performed for technetium-99 and determined that there was strong evidence for continuing sources in this area.

Tritium concentrations in groundwater have declined below the 20,000 pCi/L cleanup level in most of 200-ZP groundwater interest area due to radioactive decay, dispersion, and mixing from groundwater extraction and injection. The only results above the cleanup level in 2020 occurred at well 299-W14-13 (east of WMA TX-TY) where concentrations increased to 170,000 pCi/L in June 2020, then declined to about 1,000 pCi/L in November. Prior to the June 2020 increase, tritium concentrations in well 299-W14-13 had been <10,000 pCi/L since 2013. The tritium spike corresponded to a temporary water-level rise of 2.8 m (9.2 ft). Well 299-W14-13 was not sampled for tritium in 2021.

The 200-ZP-1 OU also includes groundwater beneath four TSD units (LLWMA-3, LLWMA-4, WMA T, and WMA TX-TY), which are monitored under RCRA (in coordination with CERCLA and AEA), and one SALDS unit.

**RCRA Monitoring.** Two LLWMAs, LWMA-3 or LLWMA-4 that overlie the 200-ZP-1 OU, are monitored under RCRA interim status contaminant indicator parameter programs.

RCRA assessment monitoring continued at WMA T and WMA TX-TY. The concentrations and extent of dangerous waste constituents from these facilities are generally declining; however, total cyanide concentrations are trending upward at two monitoring wells downgradient of WMA T and WMA TX-TY. Changes in concentrations of all analytes are expected because of the new wells extracting contaminated groundwater upgradient and downgradient of these WMAs. SALDS receives treated water from the ETF and is regulated under a Washington State waste discharge permit. The declining water table in the 200 West Area has caused several of the SALDS monitoring wells to go dry over the years; this issue is being addressed during the permit renewal process. RCRA monitoring of the four TSD units is conducted in accordance with the following:

- WMA T is monitored under the RCRA assessment program described in DOE/RL-2009-66, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area T*. The revised assessment plan, issued in 2019, implemented the monitoring network recommended in SGW-60575, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area T Groundwater Monitoring*, including three proposed new wells.

- WMA TX-TY is monitored under an interim status assessment program (DOE/RL-2009-67, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area TX-TY*), revised in 2019. The revised assessment plan implements the monitoring network recommended in SGW-60576, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area TX-TY Groundwater Monitoring*.
- Beginning in the third and fourth quarters of 2020, monitoring of WMA T and WMA TX-TY was performed in compliance with a new assessment plan, DOE/RL-2019-74 (effective in July 2020) implementing the monitoring network recommended in SGW-60575 and SGW-60576.
- In 2021, LLBG WMA-3 was monitoring under an interim status groundwater assessment program due to 2019 critical mean exceedances of specific conductance and TOX at wells 299-W10-31 and 299-W10-30, respectively (DOE/RL-2019-32, *Interim Status Groundwater Quality Assessment Plan for the Low-Level Burial Grounds Waste Management Area-3*). The plan was revised in June 2021 to update the monitoring well network, sampling frequency for the new wells, and constituents for the proposed new wells (DOE/RL-2019-32, Rev. 1, *Interim Status Groundwater Quality Assessment Plan for the Low-Level Burial Grounds Waste Management Area-3*).
- RCRA monitoring for LLBG WMA-4 is conducted under DOE/RL-2009-69, *Interim Status Groundwater Monitoring Plan for the LLBG WMA-4*, as modified by TPA-CN-718, *DOE/RL-2009-69 Interim Status Groundwater Monitoring Plan for the LLBG WMA-4 Revision 2*. A new revision of the plan, DOE/RL-2009-69, Rev. 3, was released in 2021 and will be implemented in 2023. Changes to the groundwater monitoring plan include removing deep wells to align with the final status network proposed in SGW-60584, *Engineering Evaluation Report for Low-Level Burial Grounds Waste Management Area-4 Green Islands Groundwater Monitoring*. The revised plan proposes three new upgradient wells and three new downgradient wells.

**AEA Monitoring.** AEA groundwater monitoring was conducted at 200-ZP groundwater interest area wells in accordance with DOE/RL-2015-56. The primary AEA constituents for the 200-ZP groundwater interest area are iodine-129, nitrate, technetium-99, radium-226, and tritium. Radionuclide concentrations detected in groundwater samples from 79 wells were used to estimate the cumulative TED and to compare the cumulative beta/photon emitters, alpha emitters, and uranium mass to DWSs. The estimated TED did not exceed the 100 mrem/yr standard in 200-ZP groundwater interest area wells. The cumulative drinking water dose from beta/photon emitters exceeded the 4 mrem/yr standard at 14 locations in the 200-ZP groundwater interest area. None of the DWSs for cumulative alpha emitters were exceeded. The net alpha dose did not exceed the 15 mrem/yr DWS in 200-ZP. The 30 µg/L uranium DWS was exceeded at one location. None of these locations are adjacent to the Columbia River, which is the primary potential pathway for offsite exposure to Hanford Site contaminated groundwater. Members of the public are protected from exposure to groundwater through the implementation of ICs that restrict access to groundwater and through remedial action measures (e.g., P&T) to control the migration of contaminated groundwater to exposure points. Details of the evaluation are presented in Section 12.13 of DOE/RL-2021-51.

Review of FY 2021 CERCLA investigations and CERCLA/RCRA/AEA monitoring activities reported in the Hanford Site groundwater monitoring report for CY 2021 (DOE/RL-2021-51) and evaluated in FY 2022 did not reveal any new information associated with the 200-ZP-1 OU with potential to significantly alter conclusions of the Hanford Site Composite Analysis.

### 1.3.3 Other Central Plateau Remediation Activities

Other remediation activities on the Central Plateau (aside from source and groundwater OU activities) are presented in this section. For FY 2018, confined aquifer monitoring and ERDF operations are activities reported in this category.

#### 1.3.3.1 Confined Aquifer Monitoring

Although most Hanford Site groundwater contamination is found in the unconfined aquifer, wells in deeper aquifers are monitored because of potential downward movement of contamination and their potential migration offsite through confined aquifers. There is no evidence of offsite migration via the confined aquifers. Appendix D of DOE/RL-2014-32, *Hanford Site Groundwater Monitoring Report for 2013*, provides more detailed information about confined aquifer monitoring.

One confined aquifer occurs within sand and gravel at the base of the Ringold Formation. Carbon tetrachloride, nitrate, and technetium-99 have contaminated this unit in a portion of the 200 West Area where the upper confining unit is absent. New wells were installed in recent years to monitor and remediate this contamination. The Ringold confined aquifer is the uppermost aquifer in a region east of the 200 East Area (within portions of the 200-BP-5 and 200-PO-1 OUs). Iodine-129 and tritium are detected in wells at this location, but the contamination has not migrated farther to the east and/or southeast.

Groundwater within basalt fractures and joints, interflow contacts, and sedimentary interbeds make up the upper basalt-confined aquifer system. No significant contamination is detected in the basalt-confined aquifer except in the northwestern 200 East Area, where poor well construction and temporary drilling effects allowed local migration of groundwater from the overlying unconfined aquifer.

#### 1.3.3.2 Environmental Restoration Disposal Facility Operations

As authorized by CERCLA, Hanford Site low-level radioactive, hazardous, dangerous, and low-level mixed waste generated during waste site closures and remediation activities from Hanford Site contractors is disposed at ERDF.

ERDF began operating in July 1996. Located between the 200 East and 200 West Areas, the facility currently consists of 10 cells and covers an area of approximately 43.3 ha (107 ac). The configuration of ERDF cells is shown in Figure 1-13 and Figure 1-14.





Figure 1-13. Configuration of Disposal Cells at the Environmental Restoration Disposal Facility



**Figure 1-14. Photograph of the Environmental Restoration Disposal Facility with Indication of Disposal Cells**

Requirements associated with the facility are identified in the following RODs and amendments:

- EPA/ROD/R10-95/100, *Declaration of the Record of Decision for the Environmental Restoration Disposal Facility*
- EPA/ESD/R10-96/145, *Explanation of Significant Differences: USDOE Environmental Restoration Disposal Facility, Hanford Site, Benton County, Washington*
- EPA/AMD/R10-97/101, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*
- EPA/AMD/R10-99/038, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*
- EPA/AMD/R10-02/030, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*
- EPA et al., 2007, *Amendment to the Record of Decision for the USDOE Hanford Environmental Restoration Disposal Facility*
- EPA et al., 2009b, *U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site 200 Area Benton County, Washington, Amended Record of Decision and Explanation of Significant Differences*
- EPA et al., 2015a, *Explanation of Significant Differences for the U.S. Department of Energy Environmental Restoration Disposal Facility, Hanford Site – 200 Area Benton County, WA*

- EPA et al., 2015b, *Amendment to the Record of Decision for the USDOE Hanford Environmental Restoration Disposal Facility*

**Leachate Monitoring.** Each ERDF cell is double lined to collect leachate resulting from water added as a dust suppressant and precipitation. The liner is sloped to a sump in each cell, and the leachate is pumped from the sump to holding tanks. The leachate is then pumped to the 200 West Area P&T or the ETF for treatment.

ERDF leachate is sampled for constituents identified in EPA/AMD/R10-99/038 and CP-60070, *Environmental Restoration Disposal Facility Leachate Sampling and Analysis Plan, formerly WCH-173 Rev. 2*. The 1999 ERDF ROD amendment (EPA/AMD/R10-99/038) delisted leachate and identified the necessary sampling parameters. Leachate samples are obtained directly from the holding tanks. Constituents detected in ERDF leachate samples are then compared with the groundwater monitoring analyte list to determine whether additional analytes should be added to the groundwater PA project. Leachate data are also evaluated for trends and compared to specific action levels. Target analytes for groundwater monitoring are consistent with the leachate monitoring program. Based on groundwater sampling and leachate data, no impact to groundwater has occurred from ERDF facility or operations. An annual report is prepared for ERDF that summarizes the leachate and groundwater monitoring data, providing conclusions and recommendations as appropriate. The most recent report is ERDF-00136, *Groundwater, Leachate, and Lysimeter Monitoring and Sampling at the Environmental Restoration Disposal Facility, Calendar Year 2021*.

**Current Inventory Estimates.** DOE/RL- 2022-46 provides the annual activity inventory of key radionuclides placed in ERDF from the inception of ERDF operations (July 1, 1996) through September 30, 2022. In more than two decades since operation began, over 210,000 Ci has been disposed at ERDF. The data source for this summary is the “Inventory Disposed by Radionuclide (WMIS983)” report from the Waste Management Information System (WMIS) database.

A DOE O 435.1 PA (the revised ERDF PA [WCH-520, subsequently renumbered to CP-60089, Rev. 0 in 2016]) was completed in FY 2013 (Section 1.1.5), and the revised DAS was issued in November 2013. The inventory data package developed for that PA (WCH-479) indicates the ERDF inventory estimate is conservative. ERDF inventories are derived from data accumulated in WMIS database, which documents the ERDF waste acceptance process using waste profiles, onsite waste tracking forms (online manifest for wastes that will be shipped to ERDF), truck scale weights, and disposal records to calculate and accumulate the disposed inventory. One of the functions of the WMIS database is to ensure that waste above ERDF waste acceptance criteria limits (ERDF-00011) is not accepted for ERDF disposal. The waste acceptance process biases system inputs (e.g., profiles and onsite waste tracking forms [i.e., ERDF manifest]) to the highest expected levels before comparison with waste acceptance criteria. The net effect of this bias is to inflate ERDF radionuclide inventory. While this bias does not allow for precise knowledge of the actual inventory, it does provide assurance that inventory limits are not being exceeded, which is the intent of this process. Because of this deliberate bias, it is inappropriate to expect that the listed ERDF inventories (DOE/RL- 2022-46) will match best estimate inventories prepared for other purposes (e.g., the PA inventory data package or the inventory for the Hanford Site Composite Analysis).

In the current annual status report for the ERDF PA (DOE/RL-2022-46), there are no unreviewed disposal questions to report for the reporting period (FY 2022).

## 2 Cumulative Effects of Changes

Based on Chapter 1 with respect to the Hanford Site Composite Analysis, information was not noted that would be expected to result in higher dose estimates if included in a revised calculation. The final TC & WM EIS (DOE/EIS-0391) states that DOE would continue to defer the importation of offsite waste at the Hanford Site, at least until the Hanford Tank Waste Treatment and Immobilization Plant is operational. Any future decision to import offsite waste will be subject to appropriate *National Environmental Policy Act of 1969* review.

The radioactive waste management basis for the Hanford Site is provided in CPCC-MP-WM-52872, *Waste Management Basis*. Appendix E of CPCC-MP-WM-52872 provides the facility specific information and documents.

Some activities continue to be considered qualitatively that would be expected to result in lower dose estimates if included in a revised calculation. The CERCLA P&T systems on the Central Plateau that are qualitatively evaluated as likely to reduce the projected dose are the most notable. Such dose reduction would be due to removal of contaminant mass from the groundwater pathway. The Hanford Site Composite Analysis did not account for remedial actions such as P&T systems. Hydraulic perturbations to the unconfined aquifer in the Central Plateau and contaminant mass reduction in groundwater resulting from P&T systems will be considered in the update of the Hanford Site Composite Analysis (Revision 1 expected to be completed in FY 2022). Potential for closure of the 200-SW-2 Burial Ground is another change qualitatively evaluated as likely to reduce the projected dose. The dose reduction for this site would be due to the lower realized inventory than was considered in the Hanford Site Composite Analysis, resulting from cessation of the use of the unlined trenches (with the unused portions being withdrawn from the Hanford RCRA Permit because they will not be used at this time). Based on this change, the inventory reduction at this site will also be considered in a future revision of the Hanford Site Composite Analysis.

The Hanford Site vadose zone is extensive and deep (on the order of 100 m [328 ft] thick in the Central Plateau), and radioactive contamination is present at numerous locations as a result of past practices as simulated in the Hanford Site Composite Analysis. At present, all LLBGs (except Trench 94) in active operation in the 200 West and 200 East Area LLBGs (as discussed in Section 1.1.1) and ERDF (as discussed in Section 1.1.5) have liner/leachate collection and removal systems. Naval reactor disposal site Trench 94 is located in the 200 East Area LLBGs and has an exemption from the liner/leachate collection and removal system requirements because each reactor compartment is sealed; consequently, these PA sites have not affected the vadose zone or groundwater. The presence of radiological contamination in the vadose zone at past-practice disposal sites represent continuing sources of groundwater contamination at several locations in the Central Plateau as well as potential future continuing source that have not emerged in groundwater at several other locations. Many past-practice disposals involved large liquid discharges of waste, with the associated hydraulic influences on vadose zone hydraulics (including transient perched water impacts above the Cold Creek unit in the 200 West Area and the enduring perched water impact below the B Complex in the 200 East Area). These impacts then influence the subsurface transport of radionuclide contaminants in the impacted vadose zone in these locations. The Hanford Site Composite Analysis simulates the vadose zone for the past, present, and future to represent the distribution of water and radiological contaminants in the vadose zone from past practices and future releases. Hanford Site cleanup is being performed under the Tri-Party Agreement (Ecology et al., 1989), which divides the Central Plateau into source OUs (vadose zone only) and groundwater OUs for CERCLA. The source OUs are discussed in Section 1.3.1, and the groundwater OUs are discussed in Section 1.3.2.

## 2.1 Relative Contribution of DOE O 435.1-Regulated Sources to All-Pathways Dose

The initial Hanford Site Composite Analysis presented in PNNL-11800 and PNNL-11800-Addendum-1 (subject of the maintenance program for this annual status report) did not identify the relative contribution to total dose resulting from DOE O 435.1 regulated sources and other sources. The modeling tools used to develop the initial Hanford Site Composite Analysis are no longer available to assess the portion of the total dose estimate attributable to only DOE O 435.1 sources. However, the updated Hanford Site Composite Analysis (currently under LFRG review) includes a sensitivity case that compares the all-pathways dose contributed by DOE O 435.1 facilities only to the total dose calculated for all contributing sources. This calculation is documented in ECF-HANFORD-22-0002, Composite Analysis Vadose Zone Transport of Selected Radionuclides Released from DOE O 435.1 Sources.

The DOE O 435.1-regulated tank closure and waste management facilities evaluated in the sensitivity case are:

- 200 East Area LLBG
- 200 West Area LLBG
- ERDF (active)
- IDF (standby)
- WMA A/AX
- WMA B/BX/BY
- WMA C
- WMA T
- WMA TX/TY
- WMA S/SX
- WMA U

To evaluate the impact of DOE O 435.1 regulated facilities on the predicted releases, transfer to groundwater, and groundwater concentration and dose, the vadose zone models constructed for the updated Hanford Site Composite Analysis are run with only the inventory associated with the DOE O 435.1 regulated facilities. The other radionuclide sources associated with past leaks or anthropogenic liquid discharge sites and other sources not associated with DOE O 435.1, including the US Ecology site, are not included in the sensitivity analysis. The predicted releases to the vadose zone and associated predicted transfer to groundwater for Tc-99, I-129, and U-238 (major dose contributors) for the DOE O 435.1 facilities are presented in ECF-HANFORD-22-0002. The results are compared to the total releases and transfer to groundwater for all radionuclide sources from vadose zone models constructed for the updated Hanford Site Composite Analysis.

The following observations are made in ECF-HANFORD-22-00002 related to the predicted groundwater concentrations associated with the DOE O 435.1 regulated sources:

- The DOE O 435.1 sources do not contribute to any significant predicted Tc 99, I 129, or U 238 concentrations at or beyond the CA compliance boundary, as noted by the observation that the base case and DOE O 435.1 sensitivity case yield similar results in these model zones. The predicted peak concentrations beyond the CA compliance boundary are a result of the initial (2018) contamination of these radionuclides that dissipates with time.
- The predicted groundwater concentration results for the DOE O 435.1 sources are masked by the initial concentration which is assumed to be the observed concentration in 2018. This masking is

evident in the predicted Tc 99 and I 129 concentrations along or beyond the CA compliance boundary which are invariant with time and are the same as the base case results.

- The DOE O 435.1 sources contribute to a low predicted Tc 99 concentration of less than 30 pCi/L at the CA compliance boundary at about CY 4000.
- The timing of the peak groundwater concentrations beneath the DOE O 435.1 sources corresponds to the timing of the peak transfer rate to groundwater.

In summary, the DOE O 435.1 sources do not contribute significantly to groundwater contamination on the Central Plateau of the Hanford Site. Evaluation of dose results confirmed the insignificance of the DOE O 435.1 sources at or beyond the CA compliance boundary.

This page intentionally left blank.

### **3 Waste Receipts**

Waste receipts are accounted for in the following individual PA annual summary reports:

- ERDF PA annual status report: DOE/RL-2022-46
- 200 East Area LLBG PA annual status report: DOE/RL-2022-44
- 200 West Area LLBG PA annual status report: DOE/RL-2022-45
- US Ecology commercial LLW disposal facility annual utilization report: US Ecology, 2016, *US Ecology Washington – 2016 Facility Utilization Report*

Waste disposal authorizations are needed to dispose of waste in the IDF, and so it has not received waste yet.

This page intentionally left blank.

## 4 Monitoring

This chapter describes the Hanford Site monitoring results for CY 2020 (the CY 2020 results are the latest available in the reporting period of FY 2021) relevant to the Hanford Site Composite Analysis. Compliance monitoring activities are summarized in Table 4-1 and discussed in this chapter.

### 4.1 Summary of Air Monitoring

Air monitoring results for CY 2021 are summarized in DOE/RL-2022-08, *Hanford Annual Site Environmental Report for Calendar Year 2021*, specifically Section 6.0, “Air Monitoring.” The following information was drawn from that report.

Air monitoring reported in the annual site environmental report pertains to current conditions that result from radioactive emission point sources (i.e., stacks and vents) that will not be present during the compliance period evaluated in the Composite Analysis. The maintained CA (PNNL-11800; PNNL-11800, Addendum 1) compliance period begins in CY 2050, and the updated CA in development (Appendix B) starts the compliance period in CY 2070; all sources reported in the annual site environmental report will no longer exist after site closure. Hence, the air monitoring results summarized below are provided for reference to current conditions but have limited applicability to the CA basis.

Air quality is monitored using stack sampling at the sources and air monitoring at receptor locations. The specific objectives are to measure airborne radionuclides to calculate the doses to humans, plants, and animals. Measured and calculated results are compared with the DOE, EPA, and/or Washington State Department of Health standards.

Small quantities of radionuclides and industrial air pollutants are emitted to the environment through radioactive emission point sources (i.e., stacks and vents). The federal and state permit requirements contained in the Hanford Site air operating permit (Ecology, 2019, *Hanford Site Air Operating Permit 00-05-06, Renewal 3*) define which stacks require sampling, how and how often to collect the samples, and the isotopes to be measured. The commonly measured isotopes include tritium (i.e., hydrogen-3), strontium-90, iodine-129, cesium-137, plutonium-238, plutonium-239/240, and americium-241. Emission points are sampled and monitored continuously if they have the potential to emit radionuclides that exceeds 1% of the 40 CFR 61, “National Emission Standards for Hazardous Air Pollutants,” Subpart H, “National Emission Standards for Emissions of Radionuclides Other Than Radon from Department of Energy Facilities” public dose limit of 10 mrem/yr or 100 microsievert ( $\mu\text{Sv}$ )/yr. Continuous sampling is defined and described in more detail in the ANSI/HPS N13.1, *Sampling and Monitoring Releases of Airborne Radioactive Substances From the Stacks and Ducts of Nuclear Facilities*. For other release points, periodic confirmatory measurements are made to verify low emissions.

Offsite radiological dose assessments related to stack releases are ideally based on direct measurements of radionuclide concentrations in specific environmental media such as air, water, and food measured at offsite locations. However, amounts of many radioactive materials released to the atmosphere from Hanford Site sources are too small to be measured in media after they are released from stacks and diluted through miles of dispersion in the environment. Radioactive air emissions from the Hanford Site have been generally decreasing over time because the production and processing of nuclear materials ceased more than 30 years ago. For the radionuclides present in measurable amounts, it can be difficult to distinguish the small contribution of Hanford Site stacks from other contributions caused by fallout from historical nuclear weapons testing and naturally occurring radionuclides such as uranium and its decay products. As a result, the dose assessment process incorporates conservative assumptions to ensure that calculated doses are likely to be overestimated. For more information on doses due to radiological releases, the reader is referred to Section 4.2 of DOE/RL-2022-08.

Radioactive air emission points are located on the Hanford Site in the 100, 200, 300, and 400 Areas. The quantity of radionuclide air emissions reported in 2021 were similar in magnitude to those reported in 2020.

#### **4.1.1 Air Effluent Monitoring for Radioactive Airborne Emissions**

DOE contractors monitor airborne pollutants from site facilities to quantify emissions, determine compliance with federal and state regulatory requirements, and assess the effectiveness of emission control equipment. Most facility radioactive air emission point sources are actively ventilated stacks sampled prior to the point of release to the ambient environment. Airborne emissions with potential to contain radioactive materials are sampled for gross alpha, gross beta, and radionuclides specified in the Hanford Site air operating permit (Ecology, 2019).

Small quantities of radionuclides are emitted to the environment through radioactive emission point sources (i.e., stacks and vents) during routine operations. The federal and state permit requirements contained in the air operating permit define which stacks require sampling, how often to collect the samples, and the isotopes to be measured. The commonly measured isotopes include tritium (i.e., hydrogen-3), strontium-90, iodine-129, cesium-137, plutonium-238, plutonium-239/240, and americium-241. Emission points are sampled and monitored continuously if they have the potential to emit radionuclides that exceed 1% of the 40 CFR 61 Subpart H public dose limit of 10 mrem/yr or 100  $\mu$ Sv/yr. Continuous sampling is defined and described in more detail in ANSI/HPS N13.1. For other release points, periodic confirmatory measurements are made to verify low emissions.

The quantity of radionuclide air emissions reported in 2022 were similar in magnitude to those reported in 2021. Table 4-2 summarizes Hanford Site radioactive airborne emissions in 2022.

#### **4.1.2 Air Monitoring for Radionuclides**

Atmospheric releases of radioactive materials from Hanford Site facilities and operations to the surrounding region are potential sources of exposure to humans. Radioactive constituents in air are monitored at Hanford Site facilities and operations at locations away from site facilities, offsite around the perimeter, and in nearby and distant communities. Information about these ambient air monitoring efforts, including detailed descriptions of air sampling and analysis techniques, is provided in the DOE/RL-91-50, *Hanford Site Environmental Monitoring Plan*.

A network of continuously operating samplers at 78 locations across the Hanford Site was used during 2022 to monitor radioactive airborne materials in air near Hanford Site facilities and operations (details are reported in Table 6-4 of DOE/RL-2022-08). The samplers were primarily located at or within approximately 500 m (1,640 ft) of sites and facilities that have the potential for or a history of environmental releases. The samplers were primarily located in the prevailing downwind direction. Samples were collected according to a schedule established before the 2022 monitoring year.

Airborne particle samples were collected at each location by drawing air through a cellulose filter. The filters were collected bi-weekly, field-surveyed for gross radioactivity, held for at least 5 days, and then analyzed for gross alpha and beta activity. The 5-day holding period is necessary to allow for the decay of naturally occurring, short-lived radionuclides that would otherwise obscure the detection of longer-lived radionuclides associated with emissions from nuclear facilities. The gross radioactivity measurements were used to indicate changes in trends in the onsite facility environment.

**Table 4-1. Compliance Monitoring**

<b>Disposal Facility/Unit</b>	<b>Monitoring Type</b>	<b>Monitoring Results and Trends</b>	<b>Performance Objective Measure or Other Regulatory Limit</b>	<b>Action Level</b>	<b>Action Taken</b>	<b>Performance Assessment/ Composite Analysis Impacts</b>
Sitewide	Air	Stable; comparable to widespread background concentrations	--	--	Monitoring	None
Central Plateau groundwater OUs : 200-ZP-1, 200-UP-1, 200-BP-5, and 200-PO-1	Groundwater	Groundwater flow system continues recession since cessation of large-volume liquid discharges in the early 1990s Groundwater radioactive contaminant plumes of tritium, iodine-129, strontium-90, technetium-99, and uranium formed when waste discharged to ponds and cribs reached the aquifer	RCRA, CERCLA, and AEA	Determined in OU decision documents	200 West Area pump and treat system; 200-BP-5 OU treatability tests	Reduction of groundwater contamination not evaluated in the Hanford Site Composite Analysis; this feature will be addressed in composite analysis update
Selected source OUs: 200-DV-1, 200-WA-1, and 200-EA-1	Vadose zone	Characterization	CERCLA	To be determined	Characterization	Data will support refined analysis of vadose zone in Hanford Site Composite Analysis update

Reference: DOE/RL- 2021-15, *Hanford Annual Site Environmental Report for Calendar Year 2020*.

AEA = *Atomic Energy Act of 1954*

CERCLA = *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*

OU = *operable unit*

RCRA = *Resource Conservation and Recovery Act of 1976*

**Table 4-2. Hanford Site Radioactive Airborne Emissions in Calendar Year 2021**

Radionuclide	100 Area (Ci)	200 East Area (Ci)	200 West Area (Ci)	300 Area (Ci)	400 Area (Ci)	Total (Ci)
Actinium-227	N/A	N/A	N/A	2.1E-10	N/A	1.1E-09
Americium-241	3.8E-06	3.1E-07	9.7E-08	5.4E-10	N/A	4.2E-06
Americium-243	N/A	N/A	N/A	2.2E-07	N/A	2.2E-07
Carbon-14	N/A	N/A	N/A	1.10E-04	N/A	1.10E-04
Cesium-137	7.10E-06	1.40E-06	7.40E-07	3.70E-08	1.10E-11	9.30E-06
Cobalt-60	ND	ND	ND	3.70E-08	N/A	1.30E-08
Curium-243/244	N/A	N/A	N/A	ND	N/A	2.70E-10
Europium-152	ND	ND	ND	7.10E-10		7.90E-10
Europium-154	ND	ND	ND	4.30E-08		2.10E-08
Gadolinium-153	N/A	N/A	N/A	4.00E-10	N/A	2.10E-10
Gross Alpha	1.40E-05	5.40E-07	1.40E-06	1.40E-07	2.00E-07	1.60E-05
Gross Beta	2.00E-05	6.80E-06	3.50E-06	5.00E-06	1.20E-06	3.70E-05
Iodine-129	N/A	7.00E-04	N/A	N/A	N/A	7.00E-04
Krypton-85	N/A	N/A	N/A	2.10E-07	N/A	1.90E-07
Neptunium-237	N/A	N/A	N/A	1.40E-08	N/A	1.40E-08
Plutonium-238	6.20E-07	ND	1.80E-08	3.50E-08	N/A	6.60E-07
Plutonium-239/240	5.10E-06	1.80E-07	2.20E-06	5.60E-09	2.30E-13	6.10E-06
Plutonium-241	1.60E-05	ND	1.7E-07	ND	N/A	1.60E-05
Radium-226	N/A	N/A	N/A	3.80E-10	N/A	4.20E-10
Radon-219	N/A	N/A	N/A	3.0E-01	N/A	1.90E+01
Ruthenium-106	ND	ND	ND	7.30E-09	N/A	7.30E-09
Sodium-22	N/A	N/A	N/A	0.0E+00	2.10E-10	2.10E-10
Strontium-90	4.60E-06	2.20E-06	5.30E-07	3.70E-06	N/A	1.10E-05
Technetium-99	N/A	N/A	N/A	4.3E-06	N/A	4.3E-06
Tritium (elemental)	N/A	N/A	N/A	1.40E+02	N/A	1.40E+02
Tritium (tritiated water vapor)	2.20E+02	N/A	N/A	2.21E+02	1.60E-02	2.20E+02
Uranium-232	N/A	N/A	N/A	8.5E-09	N/A	8.5E-09
Uranium-233	N/A	N/A	N/A	1.9E-08	N/A	1.9E-08

Source: Table 6-2 of DOE/RL- 2021-15, *Hanford Annual Site Environmental Report for Calendar Year 2020*.

Ci = curies

N/A = not applicable

ND = not detected

The results of this monitoring program with respect to the Central Plateau (focus of the Composite Analysis) were reported in DOE/RL- 2022-08 as follows:

- **200 East Area:** Air sampling was conducted at 28 locations in the 200 East Area during 2021. Generally, radionuclide levels measured were similar to those measured in previous years. Cesium-137, strontium-90, plutonium-239/240, uranium-233/234, and uranium-238 were detected in a small percentage of the samples collected in the 200-East Area.
- **200 West Area:** Air sampling was conducted at 23 locations in the 200 West Area during 2021. In general, radionuclide levels measured were similar to results for previous years. Cesium-137 and plutonium-239/240 were detected in less than 5% of the samples. All other radionuclides of concern were below analytical detection limits.
- **ERDF:** Air sampling in support of ERDF operations was conducted at five locations at ERDF (200 West Area): three project-specific stations and two upwind stations that are part of the 200 West Area monitoring network. Radionuclide levels measured at this site were similar to those seen in previous years. Uranium-233/234 and uranium-238 were detected in approximately 35% of the samples. All other radionuclides of concern were below analytical detection limits.

#### 4.1.3 Perimeter and Offsite Air Monitoring for Radionuclides

Airborne radionuclide samples were collected in 2021 by 18 continuously operating samplers in the vicinity of the Hanford Site. The stations were grouped into three proximity categories: perimeter (11 stations), nearby Hanford Site communities (6 stations), and distant community (1 station). Perimeter samplers were located around the site boundary with emphasis on prevailing downwind directions to the south and east. Samplers located in Basin City, Benton City, Kennewick, Mattawa, Othello, Pasco, and Richland, Washington, provided data for the nearest population centers. A sampler in Yakima, Washington, provided background data from a community essentially unaffected by Hanford Site operations.

Sample results in 2021 showed low radiological concentrations in air. Gross alpha and gross beta concentrations in the air samples collected in 2021 from the perimeter and nearby Hanford Site communities were comparable to each other and slightly higher than samples from the distant community. Concentrations in 2021 were comparable to concentrations seen in the previous 5 years. Gross beta and gross alpha concentrations in air peak during the fall and winter months, exhibiting a pattern of natural radioactivity fluctuations (Eisenbud, 1987, *Environmental Radioactivity: From Natural, Industrial, and Military Sources*). This fluctuation is seen in both Hanford Site and distant location concentrations.

Uranium-238 was detected in one of the air samples collected in 2021 from all perimeter and offsite locations. Uranium -238 concentration was similar to those measured in previous years.

Tritium was detected in 5 (less than 5%) of the offsite samples at concentrations similar to those seen in previous years. Cesium-137, strontium-90, and plutonium isotopes were not detected in any of the offsite air samples collected during 2021.

## 4.2 Summary of Groundwater Flow Conditions and Extent of Contamination

A plan has been developed to address groundwater and vadose zone contamination from DOE-RL in consultation with EPA and Ecology (EPA, Ecology, and DOE, 2021). Key elements associated with managing the Hanford Site groundwater and vadose zone contamination are to protect the Columbia River and groundwater, develop a cleanup decision process, and achieve final cleanup.

DOE is committed to protecting the Columbia River and human health and the environment from Hanford Site contaminated groundwater. As part of this commitment, the following four cornerstone documents have been developed for the monitoring and remediation of Hanford Site contaminated soils and groundwater:

- DOE/RL-2002-59, *Hanford Site Groundwater Strategy: Protection, Monitoring, and Remediation*
- DOE/RL-2002-68, *Hanford's Groundwater Management Plan: Accelerated Cleanup and Protection*
- DOE/RL-2007-20, *Hanford Integrated Groundwater and Vadose Zone Management Plan*
- DOE/RL-2009-10, *Hanford Site Cleanup Completion Framework*

Due to the reporting cycle for the groundwater monitoring program, the results discussed in the following sections reflect sampling and analyses completed in CY 2021 that were reported in DOE/RL-2021-51. Groundwater at the Hanford Site is monitored under various sampling and analysis plans that are reviewed and/or approved by DOE-RL, Ecology, and EPA.


### 4.2.1 Groundwater Flow

The natural pattern of groundwater flow was altered during Hanford Site operational years by water table mounds created by the discharge of large volumes of wastewater to the ground. The 100 Area's mounds declined as reactor operations ceased, and since effluent disposal in the Central Plateau decreased substantially in the 1990s, the mounds in the 200 Areas have dissipated considerably. Declining water levels from mounding continue to affect groundwater flow and depth to water. Additionally, active groundwater P&T remediation systems in both the 200 East and the 200 West Areas have resulted in local changes to groundwater gradients near associated extraction and injection wells. Figure 4-1 shows the Hanford Site water table and inferred groundwater flow directions for March 2021.

### Relevance of Groundwater Monitoring to the Composite Analysis

The groundwater monitoring program provides additional data that serve to validate or revise the modeling basis used in the Hanford Site Composite Analysis. The unconfined aquifer at the Hanford Site was subject to large volume liquid discharges during the Hanford Site operational phase (1944 to 1989), and the water table is now experiencing a slow decline to pre-Hanford Site flow conditions. It is also subject to pumping stresses associated with P&T actions. Historical water-level data predominantly reflect the operational phase. Consequently, later data continue to support improvement in the predictive capability of groundwater flow models as the system approaches long-term flow conditions.

Similarly, monitoring of groundwater contamination provides important data to validate or revise the modeling basis used.



Sources: Figure 1-2 in DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*. NAVD88, North American Vertical Datum of 1988.

**Figure 4-1. Water Table and Inferred Groundwater Flow Directions for the Hanford Site, 2021**

The determination of hydraulic gradients over much of the Hanford Site is readily accomplished by analyzing water-level measurements from monitoring wells. However, the unconfined aquifer beneath the 200 East Area exhibits a low hydraulic gradient magnitude (i.e., flat water table); therefore, water-level measurements have a low signal-to-noise ratio, making the determination of hydraulic gradients in this region difficult. SGW-54165, *Evaluation of the Unconfined Aquifer Hydraulic Gradient Beneath the 200 East Area, Hanford Site*. To improve measurement accuracy, wells used for water-level mapping have had gyroscopic surveys performed to correct for verticality error, and resurveys of well casings have been performed using a highly accurate leveling technique. The results indicate that flow is toward the southeast over most of the 200 East Area. Hydraulic gradients at 200 East Area RCRA sites generally range between  $4.8 \times 10^{-6}$  m/m at WMA C Tank Farm to  $2.4 \times 10^{-5}$  m/m at the 216-A-29 Ditch (ECF-HANFORD-22-0041, *Hydraulic Gradient and Average Linear Velocity Calculations – Quarter 4 Calendar Year 2021*).


#### 4.2.2 Extent of Contamination

Groundwater contaminant plumes of tritium, iodine-129, strontium-90, technetium-99, and uranium formed when waste that was discharged to ponds and cribs reached the aquifer. Cesium-137 and plutonium-239/240 have also been found in groundwater above their respective DWS values, but only in the 200-BP-5 OU adjacent to the decommissioned 216-B-5 injection well, where waste was discharged directly into the aquifer in the past. In 2021, cesium-137 concentrations exceeded the 200 pCi/L DWS in three wells near the 216-B-5 injection well. Plutonium-239/240 was detected in a single well in this area at a concentration of 35.2 pCi/L, above the 15 pCi/L DWS (for gross alpha). Thus, plume extents for cesium-137 and plutonium-239/240 are not further discussed.

Figure 4-2 shows the distribution of radionuclide contaminant plumes originating from sources on the Central Plateau that are at concentrations above respective DWSs in the unconfined aquifer.

The status of the plumes for tritium, iodine-129, strontium-90, technetium-99, and uranium are summarized as follows:

- Tritium occurs above the 20,000 pCi/L DWS within all four Central Plateau groundwater OUs with a combined plume extent of 57.7 km<sup>2</sup> (the largest plume extent is 54.3 km<sup>2</sup> within 200-PO-1). The highest tritium result detected within a Central Plateau groundwater OU during 2021 was 252,000 pCi/L at the PUREX Cribs (200-PO-1 OU) in the 200 East Area (the highest concentration during 2020 within this area was 273,000 pCi/L). Thus, the PUREX Cribs are a continuing source of tritium to the aquifer. Tritium continues to attenuate in areas away from operational areas due to dispersion and radioactive decay. Within the 200-PO-1 OU, tritium is discharging to the Columbia River, the maximum sampled concentration at the river boundary was equal to the 20,000 pCi/L DWS during 2021.



Source: Figure ES-7 in DOE/RL-2021-51, *Hanford Site Groundwater Monitoring Report for 2021*.

**Figure 4-2. Distribution of Radionuclide Contaminant Plumes Originating from the Hanford Site Central Plateau at Concentrations Above Drinking Water Standards in the Unconfined Aquifer**

- The largest iodine-129 plume occurs within the 200-PO-1 OU, extending from the 200 East Area. At the 1 pCi/L contour level (the DWS), the 200-PO-1 plume extends 12 km (7.5 mi) east of the 200 East Area and covers an extent of 47.1 km<sup>2</sup>; its extent has changed very little over the past 20 years. While the contaminant continues to migrate downgradient, concentrations at the leading edge of the plume are being reduced by dispersion, and the contour position at 1 pCi/L is stable. There is no significant reduction in concentrations due to radioactive decay because iodine-129 has a long half-life (15.7 million years). Concentrations in 200-PO-1 along the Columbia River are less than the DWS. Iodine-129 concentrations also exceed the DWS in plumes from the 200 West Area. The extent of the plumes from all Central Plateau sources is 57.5 km<sup>2</sup>. The maximum concentration beneath the Central Plateau during 2021 was 14.8 pCi/L in the 200-UP-1 OU. An iodine-129 treatment technology evaluation for the 200-UP-1 OU was completed in September 2019 (PNNL-29148, *Assessment of Technologies for I-129 Remediation in the 200-UP-1 Operable Unit*), which concluded that a viable treatment technology for the iodine-129 plume is not available. Thus, a

technical impracticability waiver may be pursued under 40 CFR 300.430(f)(1)(ii)(c), “Remedial Investigation/Feasibility Study and Selection of Remedy.”

- The most substantial uranium plumes occur within the 200-BP-5 and 200-UP-1 OUs. The 200-BP-5 OU plume originates from the B Complex, where uranium is entering the aquifer from a perched zone above the unconfined aquifer. The maximum uranium concentration in this area during 2021 was 213 µg/L, a decline from the maximum 625 µg/L in 2020. A P&T system has been operating in this plume since 2015. The system began as a treatability test and transitioned to a removal action in December 2016. In 2021, an interim ROD was signed that will continue remediation of the plume (EPA et al., 2021). Since startup, this system has removed 240 kg of uranium from the aquifer, and its operation has reduced concentrations in the aquifer and the size of the plume. In December 2014, the Tri-Parties signed an action memorandum (DOE/RL-2014-34) that specifies extraction of water from the perched zone beneath the B Complex and transfer to the 200 West P&T for treatment and injection into the aquifer. Perched water extraction continued in 2021. The maximum measured concentration in the perched zone was 105,000 µg/L, and approximately 67 kg of uranium was removed in 2021. Since 2011, a total of 395 kg of uranium has been removed. To increase the removal rate of uranium from the perched zone, eight additional extraction wells, along with four monitoring wells, are planned for drilling (DOE/RL-2019-42, *Sampling and Analysis Plan for Perched Water Extraction and Monitoring Wells in the 200-DV-1 Operable Unit*). Through early 2022, two of the eight planned extraction wells had been installed. Uranium plumes in the 200-UP-1 OU occur near U Plant, originating from the 216-U-1 and 216-U-2 Cribs and in a second area near the 216-U-10 Pond. The highest uranium concentration in Central Plateau groundwater during 2021 occurred in the 216-U-1 and 216-U-2 Cribs plume at 1,720 µg/L, a decrease from 1,840 µg/L in 2020. A P&T remedy for uranium at the 200-UP-1 OU began operating in September 2015. The system consists of three extraction wells and the water is treated at the 200 West P&T. During 2021, a total of 7.9 kg of uranium was removed from the aquifer, and 77.1 kg has been removed since startup. When including the previous P&T remedies that operated within this plume, a total of 985 kg of uranium has been removed from the aquifer.
- Technetium-99 plumes are present within all four Central Plateau OUs, but the largest (1.0 km<sup>2</sup>) occurs within the 200-BP-5 OU. This plume originates from the B Complex (BY Cribs) and occurs at B Complex and in regions to the northwest beyond the 200 East Area. The highest concentration in this area during 2021 was 22,800 pCi/L, which was the highest concentration in groundwater beneath the Central Plateau (the DWS is 900 pCi/L). Technetium-99 concentrations at the B Complex have been declining in many wells due to operation of a P&T system. Since startup in 2015, the P&T system has removed 7.47 Ci of technetium-99 from the aquifer. Technetium-99 plumes also occur in association with the tank farms in both the 200 East and 200 West Areas. The maximum concentration downgradient from the WMA U Tank Farm had been declining in recent years from a maximum of 13,800 pCi/L in 2018 to 4,250 pCi/L in January 2021. However, the concentration increased substantially by July 2021 to 11,500 pCi/L. Downgradient from the WMA TX-TY Tank Farm, concentrations increased in a single well from 968 pCi/L in 2016 to 24,300 pCi/L in 2019 and 24,800 pCi/L in 2020. The concentration declined to 13,800 pCi/L in 2021. The elevated concentration is likely caused by a continuing source. Technetium-99 is removed from the aquifer by two extraction wells near U Plant, from a P&T system at the WMA S-SX Tank Farm, and from extraction wells near the WMA T and WMA TX-TY Tank Farms. Since startup, 1.31 Ci and 3.7 Ci of technetium-99 have been removed by the U Plant and S-SX Tank Farm extraction wells, respectively. The technetium-99 plume from WMA C and WMA A-AX in 200 East Area has expanded to the southeast since 2015 and may have reached wells just outside the 200 East Area. The highest


technetium-99 concentration in this plume during 2021 was 22,800 pCi/L downgradient from the WMA C Tank Farm. Two extraction wells are planned to be installed in this plume.


- Strontium-90 plumes are present within the 200-BP-5, 200-PO-1, and 200-UP-1 OUs. The highest concentrations occur within the 200-BP-5 OU, where strontium-90 is detected above the DWS (8 pCi/L) at the former Gable Mountain Pond and 216-B-5 reverse well. The maximum concentration at Gable Mountain Pond was 210 pCi/L during 2021. The highest concentration of strontium 90 detected beneath the Central Plateau in 2021 was 524 pCi/ L adjacent to the 216-B-5 reverse well. Concentrations at 216-B-5 are generally trending lower at a faster rate than can be accounted for by radiological decay. Strontium-90 exceeds the DWS in a small area near the PUREX Cribs within the 200-PO-1 OU (9.84 pCi/L during 2021) and in a single well near the 216-S-1 and 216-S-2 Cribs in the 200-UP-1 OU (50.1 pCi/L during 2020 [sampling of the well was not successful during 2021]).

RCRA and *Washington Administrative Code*-regulated groundwater monitoring continued in CY 2021 at facilities in all four Central Plateau OUs. During November 2021, exceedances for specific conductance and total organic carbon occurred in two wells at LLBGs WMA-2, and verification sampling was planned for early 2022. The 216-A-37-1 Crib transitioned to assessment monitoring in 2021 due to exceedances of pH (low) and total organic carbon. The 216-B-3 Main Pond also transitioned into assessment monitoring during 2021 due to an exceedance of specific conductance. The Nonradioactive Dangerous Waste Landfill (NRDWL) and WMA A-AX Tank Farm transitioned into assessment monitoring in 2020 due to exceedances of specific conductance (NRDWL and WMA A-AX) and an initial exceedance of total organic carbon (WMA A-AX). Assessment monitoring of these sites continued in 2021. No other potential new impacts to groundwater quality were detected in CY 2021, although several additional sites remain in assessment monitoring.

Groundwater monitoring to meet AEA requirements was performed for all four Central Plateau groundwater OUs during CY 2021. The objectives of this monitoring are to determine the location of radionuclide contamination in Hanford Site groundwater and to estimate impacts to human health and the environment in terms of the TED received by potential receptors. The TED at each groundwater well was calculated as the cumulative dose from all radionuclides detected in groundwater samples collected from that well in 2021. Estimated TEDs for five wells on the Central Plateau exceeded the DOE 100 mrem/yr dose standard; four of these were in the perched zone beneath the B Complex (200-DV-1 OU). The maximum TED in the regional groundwater was 184 mrem/yr at a well in the U Plant area of the 200-UP-1 OU (uranium plumes). There was no other exceedance of the DOE 100 mrem/yr dose standard in the regional aquifer. Estimates of cumulative dose to beta/photon emitters and alpha emitters were also calculated and are discussed in DOE/RL-2021-51. The AEA monitoring did not identify any new or emerging contamination issues on the Central Plateau during 2021.

Considering all the radionuclide contaminant plumes present in groundwater at the Hanford Site, tritium and iodine-129 have the largest areas with concentrations above DWSs. The most expansive of these plumes have sources in the 200 East Area, extending east and southeast toward the Columbia River. Less expansive tritium, uranium, iodine-129, strontium-90, and technetium-99 plumes are present in the 200 West Area. Figure 4-3 provides a comparison of the areal extent of tritium, iodine-129, technetium-99, and uranium contaminant plumes in groundwater (at levels above DWSs) for CY 2003 through CY 2021.





## 4.3 Summary of Vadose Zone Characterization

A variety of vadose zone characterization efforts have taken place recently at the Central Plateau. The Central Plateau source OUs responsible for characterization of the vadose zone are 200-WA-1/200-BC-1, 200-EA-1, 200-DV-1, 200-IS-1, 200-IA-1, 200-PW-1/3/6/CW-5, 200-SW-2, and 200-OA-1/200-CW-1/3.

### 4.3.1 Characterization Approaches for Source Operable Units

This section provides a summary of the approaches DOE is taking to characterize the vadose zone on the Central Plateau. These include the analogous waste site approach to revising the source OU RI/FS work plans and the opportunistic sampling approach to collecting vadose zone data while drilling groundwater wells. The combination of both approaches should help accelerate cleanup decisions on the Central Plateau.

#### 4.3.1.1 Analogous Waste Site Approach to Characterization

In FY 2020 the Tri-Party Agencies formed the RASCAL team to develop a representative and analogous site approach for the 200-BC-1, 200-EA-1, and 200-WA-1 OUs. The Interagency Management Integration Team (IAMIT) determination number 2020-006, *Representative Analogous Site Coordinating Agency Liaison (RASCAL) Recommendations for Expediting Remedial Cleanup on the Hanford Central Plateau* (IAMIT, 2020), was signed in June of 2020 to implement this approach for the Central Plateau Inner Area. This approach was developed to accomplish the following objectives:

- Accelerate cleanup decisions
- Ensure consistent remedies for analogous waste sites
- Implement early remedial actions
- Reduce characterization pre-ROD
- Conduct focused confirmatory characterization post-ROD

Through the RASCAL approach the waste sites in these OUs were binned into five conceptual site model (CSM) groups and evaluated to select representative and analogous sites, Table 4-3. Representative sites are considered to be a reasonable representation of the range of conditions for the CSM group and analogous sites within. A representative site will be the CSM group specific data source to define a basis for action, evaluate response actions, identify response actions, and select an alternative in the ROD. Analogous sites are considered to be waste sites that pose a similar risk through similar exposure pathways and have similar configuration of contamination.

The RASCAL team identified four CSM groups with representative and analogous sites and one unique CSM group that may have case-by-case representative and analogous site applicability (i.e., a subset of trenches or French drains within a unique CSM subgroup) (CSM 7a-e). In total, 241 waste sites from 200-BC-1, 200-EA-1, and 200-WA-1 have been binned into CSM groups. CSM groups 1c, 2, 4, 6, and 7 applicable to the 200-BC-1, 200-EA-1, and 200-WA-1 OUs. CSM 1a and CSM 1b apply to early action designated 200-IA-1 created by the RASCAL team.

Twenty representative sites were selected from the 200-BC-1, 200-EA-1, and 200-WA-1 OUs. Pre-ROD characterization at these waste sites will be used to define the range of response actions and determine the alternative for each respective CSM group it belongs in. Post-ROD characterization will focus on confirming the remedy selection for analogous sites and implementing a plug-out approach to move waste sites into new CSM groups should confirmatory sampling indicate an analogous site does not fit its current CSM group and selected remedy. Using the representative and analogous site approach for these

CSM groups should reduce pre-ROD characterization needs and accelerate cleanup decisions for waste sites on the Central Plateau.

**Table 4-3. Conceptual Site Model Grouping Overview and Representative Waste Sites**

CSM Group/ Subgroup	Description	Waste Site Count				Representative Site (OU)
		200-IA-1	200-EA-1	200-WA-1	200-BC-1	
1a	Shallow zone only – RTD bias; Moved to new 200-IA-1 OU	46	0	0	0	12
1b	Shallow zone only – CS/NFA bias; Moved to new 200-IA-1 OU	54	0	0	0	0
1c	Shallow zone only but requires coordination with collocated waste sites	0	1	4	0	Not applicable
2	Intermediate and deep zone	0	0	0	0	0
3	Large area plutonium waste sites (addressed in existing ROD)	Not applicable				
4	Small to medium transuranic cribs	0	0	0	0	0
5	Ponds and related waste sites (addressed in other OUs)	Not Applicable				
6a	Shallow and intermediate	0	9	8	4	4
6b	Shallow, intermediate, and deep	0	21	31	22	12
7a	Hot semi-works sites	0	13	0	0	0
7b	Other pipelines in 200-WA-1 or 200-EA-1	0	3	27	0	0
7c	Railroad tracks	0	8	7	0	1 (200-WA-1 OU only)
7d	U Plant barrier sites and other sites under anticipated barriers	0	1	38	0	3 (200-WA-1 OU only)
7e	Unique site	0	19	24	1	0

CSM = conceptual site model

CS/NFA = Confirmatory Sampling and/or No Further Action

OU = operable unit

RASCAL = Representative Analogous Site Coordinating Agency Liaison

**200-IA-1 Operable Unit.** The IAMIT determination number 2020-006 signed in June 2020 recommended creation of an early action Inner Area OU (200-IA-1) to accelerate cleanup at waste sites that have sufficient existing site knowledge to define a remedial action bias toward Removal, Treatment, and Disposal; or Confirmatory Sampling and/or No Further Action. The initial list of 200-IA-1 waste sites were assigned in 2020, per TPA-CCF C-20-02, “Waste Site Re-Assignment from the 200-EA-1 and 200-WA-1 OUs to the new 200-IA-1 OU,” which in accordance with IAMIT Determination 2020-006 reassigned waste sites from the 200-EA-1 and 200-WA-1 OUs to the 200-IA-1 OU. A subset of previously unassigned waste sites was added to 200-IA-1 in 2021, documented in TPA-CCF C-21-01, “Assign Central Plateau Waste Sites in the Tri-Party Agreement, Appendix C”. TPA-CCF C-21-02, “Waste Site Reassignments in Central Plateau Inner Area Operable Units in the Tri-Party Agreement, Appendix C”, reassigned eight

200-IA-1 OU waste sites to other, more appropriate 200 Area OUs and reassigned one waste site from a 200 Area OU to the 200-IA-1 OU.

IAMIT Determination Number 2020-006 stated that waste sites had sufficient existing site knowledge to define a remedial action bias, provided direction to leverage existing waste site data to quantify risk, and recommended development of a focused feasibility study (FFS). Based on the recommendation, an FFS was drafted for the 200-IA-1 OU (DOE/RL-2020-51, 200-IA-1 OU Focused Feasibility Study). The FFS evaluated the 200-IA-1 OU waste sites using waste disposal process or release knowledge; waste site dimensions; and physical attributes of contaminants, media, and underlying geology. Based on this information, a list of effective and implementable technologies/options were developed into a set of remedial alternatives, and then a detailed evaluation of the alternatives was performed. The FFS Draft A was prepared and delivered to Ecology and EPA in March of 2022. Ecology and EPA completed their review in April of 2022. During the review of the FFS, EPA and Ecology commented that the quantitative field characterization information was insufficient to reinforce a basis for remedial action and support decisionmaking for the analogous waste sites prompting development of a supplemental characterization effort. A meeting was held between DOE, Ecology, and EPA on July 11, 2022, to select the 12 representative waste sites to be assessed as part of the supplemental characterization campaign. The 12 representative sites and the supplemental characterization effort were confirmed during the DQO session held August 4, 2022.

The supplemental characterization SAP is under development and the revision 0 of the SAP is planned to be completed in fiscal year 2023. Following completion of the SAP, planning will commence for the field characterization effort. Once all required characterization data is collected, the FSS will be revised to a Draft B and submitted to Ecology and EPA for review. The FFS will be followed by a proposed plan.

A ROD for these Inner Area waste sites using the FFS and RASCAL approach at this OU is expected in approximately 5 years and reduce post-ROD characterization by using focused confirmatory sampling at analogous sites to confirm the remedy selected for a CSM group.

#### **4.3.1.2 Opportunistic Sampling Characterization Approach**

The CERCLA OUs, WMAs, and RCRA facilities of the Central Plateau often overlap geographically. If a borehole is being drilled for one project's monitoring needs, it is possible that another project in the vicinity may have data needs that can be satisfied by collecting data at that borehole site. In the interest of integrating these investigations and maximizing the efficiency of every borehole drilled in the Central Plateau, a collaborative process called opportunistic sampling has been developed. Following the opportunistic sampling process below led to the development of opportunistic sampling instructions implemented in FY 2022.


Figure 4-4 shows the general workflow followed in the opportunistic sampling process. After a borehole location is finalized, the opportunistic sampling process begins with the compilation of integration information about that borehole location to communicate to the various project managers, scientists, SMEs and DOE OU leads. Examples of this borehole information include the following:

- Borehole purpose and objective
- Location (coordinates and map)
- Proposed total depth
- Predicted stratigraphic units and lithologies
- Nearby waste sites and WMAs, including a short description of each

- OUs
- Nearby planned wells from other projects
- Nearby existing boreholes and past sampling
- Model domains
- Planned sampling analyses for the borehole (including standard grab samples, geophysical logs, etc.)
- Special considerations and challenges (e.g., short drilling timeline, milestones, unusual borehole diameter, selected drilling methods)

The information is distributed to the point-of-contact for every nearby identified project, including technical integration and drilling. A collaborative meeting is scheduled with DOE, representatives from each project (may be several different contractors), and other SMEs to discuss whether the borehole being drilled presents an opportunity for characterization that may satisfy other projects' data needs.

If it is determined in the collaborative team meeting that the borehole is in a good location to provide information for one of the other projects or objectives, an opportunistic sampling instruction will be developed. If the data needs are identified in another sampling and analysis plan or data quality objective (DQO), the opportunistic sampling instruction will reference those DQOs and samples will be collected accordingly. If data needs are identified in the team meeting that are not covered by an existing sampling and analysis plan or DQO, the DQO process may be initiated for the opportunistic sampling instruction.



**Figure 4-4. Flow Diagram for the Initiation of the Opportunistic Sampling Process**

Agreements made in the 2020 collaborative meetings between DOE and the various projects and SMEs were documented and form the basis for the opportunistic sampling instructions. Seven opportunistic sampling instructions are in various stages of development for the drilling of 15 RCRA monitoring wells in FY 2022. Table 4-4 shows the summary of vadose zone samples collected during drilling of the RCRA monitoring wells, as well as samples collected during drilling of one Atomic Energy Act well.

**Table 4-4. Summary of FY 2022 Opportunistic Sampling During Drilling**

Well Name	Groundwater OU	OU or TSD of Interest	Number of Samples	Chemical/ Radiological Analyses	Hydraulic/ Physical Properties	OSAI
299-E25-243	200-PO-1	216-A-37-1	13	X		SGW-65280
299-E25-244	200-PO-1	216-A-37-1	8	X		SGW-65280
299-E25-245	200-PO-1	216-A-37-1	17	X		SGW-65280
299-E25-250	200-PO-1	216-A-29	8		X	SGW-65258

**Table 4-4. Summary of FY 2022 Opportunistic Sampling During Drilling**

Well Name	Groundwater OU	OU or TSD of Interest	Number of Samples	Chemical/ Radiological Analyses	Hydraulic/ Physical Properties	OSAI
299-E25-249	200-PO-1	216-A-29	7		X	SGW-65258
299-W7-15 <sup>a</sup>	200-ZP-1	LLWMA-3	4	X		SGW-66549
299-W10-204	200-ZP-1	LLWMA-3	6	X		SGW-66549
299-W10-205	200-ZP-1	LLWMA-3	5	X		SGW-66549
299-W18-45	200-UP-1	LLWMA-4	5	X		SGW-66549
299-W18-46	200-UP-1	LLWMA-4	7	X		SGW-66549
299-W18-47	200-UP-1	LLWMA-4	5	X		SGW-66549
299-E17-58	200-PO-1	216-A-36B	8	X		SGW-65592
299-W19-132*	200-UP-1	200-WA-1	21	X		DOE/RI-2019-07-ADD1

Note: Complete reference citations are provided in Chapter 9 of this document.

\*Well installed in the 200-UP-1 OU as part of the *Atomic Energy Act* monitoring program.

<sup>a</sup> = Drilling started in FY22 but was not completed. Additional samples are planned as drilling continues.

OSAI = Opportunistic Sampling and Analysis Instruction

OU = operable unit

TSD = treatment, storage, and disposal

A total of 93 opportunistic samples and an additional 21 200-WA-1/200-UP-1/AEA samples were collected during drilling. Hydraulic and physical properties analysis samples were 15 of the 93 samples collected, with select samples to be analyzed in the future.

This page intentionally left blank

## 5 Research and Development

This chapter summarizes for the reporting period research and development, including field studies and other details that have the potential to affect the basis of the Hanford Site Composite Analysis, usually through reduction of uncertainty. Table 5-1 is a required table for this report to summarize the research and development documents for the reporting period.

**Table 5-1. Research and Development Activities**

Document Number	Results	Performance Assessment/Composite Analysis Impacts
PNNL-33428	<p>This report describes how time-lapse 3D ERT was used to image the dominant VZ flow paths for liquid discharged to the subsurface from the Treated Effluent Disposal Facility ponds. The primary objective of the work was to provide information to support locating a new monitoring well screened within the presumed perched water zone that develops above the RLM unit. This work demonstrates the successful application of ERT imaging technology for identifying VZ flow paths, travel times of water released through the VZ, and mapping the distribution of intentional or unintended liquid releases to the subsurface.</p>	<p>Strengthening the monitoring program provides for validation of remedial actions and early detection of vadose zone sources of contamination that will be considered with respect to the composite analysis basis.</p>
PNNL-33460	<p>This report documents results from laboratory experiments designed to evaluate the effectiveness of Bi oxyhydroxide (BOH) at removing and retaining U under saturated flow conditions. The results support the continued investigation of BOH for in situ remediation of U at the Hanford Site and other U-contaminated sites across the U.S. Department of Energy complex. Acknowledgments.</p>	
PNNL-33456	<p>This report presents results from laboratory experiments evaluating injectable liquid-phase Bi precursors that would undergo controlled precipitation in the subsurface and form a reactive barrier for immobilization of U and Tc-99 contaminants in the subsurface of the Hanford Site. The results show that liquid-phase <math>\text{Bi}(\text{NO}_3)_3</math> in propylene glycol is a promising candidate to serve as an injectable Bi precursor, which will undergo time-dependent precipitation in the subsurface, forming a reactive barrier for immobilization of U and potentially Tc-99.</p>	<p>Identifying potential remedy approaches for focused treatments of radionuclides in the vadose and perched water zones supports soil remediation activities that are protective of both the groundwater and the Columbia River.</p>

Note: Complete reference citations are provided in Chapter 9 of this document.

3D = three-dimensional

Bi = Bismuth

ERT = electrical resistivity tomography

U = Uranium

VZ = vadose zone

Tc = Technetium-99

TEDF = vadose zone

$\text{NO}_3$  = Nitrate

RLM = Ringold Lower Mud

## 5.1 Remediation Science and Technology

The Hanford Site uses science and technology to provide new knowledge, data, and tools necessary to accomplish the site cleanup mission. This mission includes investigating technologies and approaches to improve characterization and remediation of contaminated soil sites and groundwater, as well as resolving key technical issues that help to inform and influence decisions for remediation, waste management, and site closure. The PNNL has conducted applied science and technology work that supports Hanford soil and groundwater characterization and remediation activities. Work has been funded under the site soil and groundwater contractor (CPCCo), the tank operations contractor (WRPS), and with direct funding from DOE-RL. Summaries of applied science and technology efforts in FY 2021 relevant to radionuclide migration in the Central Plateau are as follows:

- Continued to identify impacts of plutonium and americium co-disposal with high-salt and organic-bearing wastes based on historical waste releases. Although operational conditions enhanced plutonium and americium mobility, their mobility is limited under current conditions. This information provides the technical basis to address the nature of plutonium and americium contamination and to provide defensibility for associated remedy decisions.
- Continued to identify quantitative conceptual models to determine the impacts of the P&T system on the aquifer and provide performance evaluations of operational changes and aquifer-system injection limits. The 200 West P&T system was designed for supporting 200-ZP-1 remedial action objectives, but other current and potential sources vary the geochemical signatures of the influent waste stream. The combined operational and influent changes were characterized in laboratory column experiments to support remedy optimization efforts and short- and long-term remedy decisions related to multiple OUs within the Central Plateau.
- Continued to evaluate the performance of 200 West P&T ion exchange (IX) resins under projected geochemical conditions that will occur as the P&T system expands to treat other regions of the aquifer within the Central Plateau. Other regions of the aquifer contain higher concentrations of nitrate and sulfate, known resin foulants that can reduce P&T performance. Resins were also tested for their ability to capture multiple contaminants to promote efficiency in P&T operations.
- Initiated a multiyear evaluation of remediation technologies to enhance future remediation of the 200-DV-1 OU. Discharged inorganic and radionuclide contaminants within the Hanford Central Plateau have migrated to the deep vadose zone and need to be remediated to protect groundwater. In FY 2022, three remedial technologies for treatment of COCs were evaluated as part of a broader treatability study. These included: liquid phosphate technologies, Sn(II)-apatite solid phase technologies, and combined gas-phase bioreduction and chemical sequestration technologies. Effectiveness was determined by evaluating contaminant transformation, reduction, degradation, and/or immobilized end-product stability. Treatment technologies determined to be effective in laboratory evaluations were considered for future field-scale implementation.
- Continued to evaluate bismuth-based materials for their potential to sequester multiple, collocated radionuclides and metals in situ (e.g., technetium-99, iodine-129, uranium, and chromium). Chemical stabilization relies on the reduction of contaminant mobility by physical or chemical reactions with the contaminant, without unintended interactions due to the presence of other contaminants. These materials are critical for identifying viable treatment options for challenging, waste-specific species of technetium-99 and iodine-129 for which existing commercial methods are ineffective.
- Field-based experiments were performed to reduce the uncertainty associated with effective monitoring of vadose zone contaminant sites through a vadose monitoring test bed. This included

defining approaches for monitoring vadose zone fluxes to groundwater at the Hanford BC Cribs and Trenches site. The vadose zone within the Central Plateau contains large quantities of mobile contaminants that have not yet reached the groundwater. In situ remedies for vadose zone sites, MNA, or other passive approaches will need to identify monitoring appropriate to the remedy. Geophysical and sensor short- and long-term monitoring approaches being tested at the test bed are relevant for vadose zone sites with both active and leave-in-place remedies, MNA, and surface barriers. Platforms include adapting traditional high-resolution geophysical approaches used for monitoring groundwater to unsaturated conditions, integrating geophysics, and the use of autonomous data collection and robust sensors.

- Completed the final design of a multi-level groundwater sampler to quantify depth-discrete aqueous and gas-phase contaminant fluxes to groundwater, known as the Vadose Zone Advanced Monitoring System (VZAMS). VZAMS integrates multiple technologies into a single borehole instrument that provides measurements of pore fluid (liquid and gas), matric potential, humidity, and temperature at multiple depths within a borehole.
- Collected ERT data at the BC Cribs and Trenches site to estimate contaminant distribution and rate of migration. Waste discharges to the BC Cribs and Trenches comprise one of the largest liquid waste volumes released to the ground in the 200 Areas and include the largest inventory of Tc-99 at Hanford and high discharges of nitrate and U-238. An initial ERT survey performed over 15 years ago will be repeated to reveal plume migration over time. This information will be used to estimate the soil properties that govern contaminant migration. This will help demonstrate how ERT measurements can be used to predict future contaminant behavior.
- Continued to identify innovative approaches to using geophysical methods to identify key stratigraphic features that are relevant to contaminant transport and remedy applications. Geophysical methods can be used for fast, cost-effective, and large-scale characterization, and offer the utility of integrating various geophysical methods with other hydrogeological data and the data collection and interpretation needed to characterize stratigraphic features important for contaminant transport. The geophysical methods ERT, electromagnetic, and seismic were used to identify the stratigraphic structure and configuration of a high-permeability channel.
- Provided updates to several web-based tools within SOCRATES ([socrates.pnnl.gov](http://socrates.pnnl.gov)) qualified to NQA-1 standards that support data visualization and analytics for Hanford Site data. Updates included custom charting capabilities to support web-based reporting, and visualization of waste site contaminant inventory data to support risk assessment and prioritization of remedial activities.
- Completed geochemical and physical characterization of borehole sediments to assess contaminant mobility and attenuation in the vadose zone for the WMA A and AX Tank Farm. This supports assessment of contaminant flux in the vadose zone and potential impacts to groundwater, and technical defensibility for tank farm closure activities.
- Continued to support remedy optimization for the 200 West P&T system by integrating optimized remedial methods with site simulations to build a prescreen-level optimization toolset to evaluate remedy configurations. The toolset includes an uncertainty evaluation for alternative conceptual site models and will leverage historical and current 200 West P&T datasets to evaluate future extraction and injection well statistics.
- Provided the technical basis for implementing improved groundwater monitoring and remediation of discrete high-concentration zones. An analytical model was developed to evaluate the impact of well

screen length, sampling method, aquifer heterogeneity, and vertical distribution of contaminant mass on the representativeness for Hanford monitoring and P&T wells.

## 5.2 Operations Studies

The following activities have been pursued in the reporting period (FY 2022):

1. **Optimization study plan:** An optimization study plan (DOE/RL-2019-38, *200-ZP-1 Operable Unit Optimization Study Plan*) has been developed and approved by EPA (TPA-CN-1102, *DOE/RL-2019-38,200-ZP-1 Operable Unit Optimization Study Plan, Rev. 0*) to monitor wells and optimize to carbon tetrachloride remediation as DOE expands treatment capability within the Central Plateau by 1,250 gal/min (284 m<sup>3</sup>/hr) to a total of 3,750 gal/min (852 m<sup>3</sup>/hr) for both 200 West and 200 East OUs with potential to expand the system further. Planning for finalizing decisions and further actions for implementation occurred in FY 2022.
2. **Comprehensive plume evaluation:** A comprehensive plume evaluation is underway to evaluate the shallow groundwater plumes in proximity to continuing source areas (i.e., at T, S/SX, U, B, C/AX Tank Farms and other locations). The current P&T configuration is being reevaluated to capture/contain contaminants in proximity to these locations. Vertical contaminant distribution and well screen intervals are being assessed to address containment of source area plumes as well as additional optimization of carbon tetrachloride and TCE remediation timeframes (carbon tetrachloride is the limiting factor with respect due to the extent of its plume size). Additional characterization within the Ringold a and Ringold b formations are ongoing. The comprehensive plume evaluation is inclusive of the carbon tetrachloride plume and will provide crucial information regarding treatment capacity requirements to address an “integrated cleanup/containment/treatment” of the Central Plateau groundwater. The scope of the comprehensive plume evaluation is currently under development and has been initiated with evaluation of the existing data, as well as the proposed data collection associated with the ongoing optimization study plan. This information is crucial in developing efficient designs for the cleanup/treatment/containment of the Central Plateau and to perform the effort in a timely fashion. In FY 2022, comprehensive plume evaluation recommendations were finalized, and further actions were defined.

## 6 Planned or Contemplated Changes

This chapter summarizes the changes affecting the Hanford Site Composite Analysis that occurred during FY 2022. This summary includes any changes resulting from special analyses (DOE M 435.1-1; DOE-STD-5002-2017) and any expected changes to future conditions (e.g., site land-use plans or remediation plans). Table 6-1 summarizes the planned or contemplated changes.

**Table 6-1. Planned or Contemplated Changes**

Planned or Contemplated Changes	Change Basis	Performance Assessment/Composite Analysis Impacts	Schedule
A project to update the Hanford Site Composite Analysis is in progress (see Appendix B in this document for status) following the technical approach defined in CP-60649, <i>Summary Analysis: Hanford Site Composite Analysis Update</i> , approved by the Hanford Site Groundwater/Vadose Zone Executive Council in May 2017. CP-60649 is supported by a series of technical approach description documents developed under a graded approach in a workshop process with participation by representatives for management of Hanford Site Performance Assessments and leadership from the Low-Level Waste Disposal Facility Federal Review Group.			
Three special analyses were conducted for the updated Hanford Site Composite Analysis in FY 2022 based on issues identified in the first revision to the updated Hanford Site Composite Analysis following LFRG review in anticipation of acceptance of the first revision. However, a second revision is necessary to complete closure of two key issues; the results of the FY 2022 special analyses were applied to complete the changes to the base case calculation in Revision 2 in response to LFRG review of the first revision.			

No outstanding current information needs (e.g., data gaps or uncertainties) were identified in the Hanford Site Composite Analysis or in any of the prior annual reviews.

Based on information reviewed from prior annual status reports, the determination of the FY 2015 annual summary report (DOE/RL-2015-66, *Annual Status Report (FY 2015): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*) is that the Hanford Site Composite Analysis requires an update. While the original composite analysis (prepared in 1998, with an addendum in 2001) has been maintained, the accumulation of basis changes reported in the annual summary reports of the preceding 14-year period merits evaluation in an updated analysis. This determination remains in place in this annual summary: new information needs to be incorporated and analyzed using environmental modeling software that meets current DOE QA requirements. Annual maintenance continues under DOE/RL-2000-29 because of the length of time planned for the preparation of an updated Hanford Site Composite Analysis. The progress on the update of the Hanford Site Composite Analysis is summarized in Appendix B of this document. An updated composite analysis report (DOE/RL-2019-52, *Composite Analysis for Low-Level Waste Disposal in the Hanford Site Central Plateau [FY 2020]*) was issued in November 2020 and submitted to the LFRG for review. The LFRG review commenced in December 2020.

### 6.1 Special Analyses

The following Special Analyses were conducted in FY 2022 for the Composite Analysis:

- UCAQ-22-01: LLBG PA Sensitivity Case with the focus on three solid waste sites 218-E-12B, 218-W-3, 218-W-3A. The special analysis first evaluated the representativeness of the C-14 and Tc-99 inventory in the three solid waste sites followed by generating the updated inventories using the disposal records from the SWIS database. Then, the new radionuclide release modeling was performed to determine the more representative release rates for C-14 and Tc-99 in the three waste sites. Using the new release rates, the vadose zone transport modeling was performed.

- UCAQ-22-02: PA Mass Transfer Footprints Study. This special analysis included literature review, revisit and evaluation of original information used for the STOMP models for the PAs, and preparation of the summary. This analysis determined the adequacy of the distributed flux used for the CA transport modeling.
- UCAQ-22-03: Dose Factor Basis Updates. This special analysis updated the exposure-related parameters used to calculate radionuclide specific UDFs based on FGR 15 (EPA-402/R419/002). The analysis evaluated the use of central tendency, or 50th percentile, instead of the 95th percentile water vapor inhalation, as well as water, crop, beef, poultry, milk, egg, and soil ingestion intake rates for the age- and gender-weighted representative person. Also, the special analysis finalized the elimination of iodine-129 water vapor inhalation dose from UDF calculations.

As noted in Section 1.1.2, four special analyses were performed for the IDF PA in FY 2022:

- Prior to finalization of the FY 2021 special analysis that determined that the as-analyzed IDF would not comply with the DOE M 435.1-1 all-pathways dose performance objective, another special analysis was performed in FY 2022 that updated the exposure factors and dose coefficients used in the dose calculations that are compared to performance objectives. This analysis incorporated recent updates to exposure factors and dose coefficients published by EPA and DOE. Updated exposure factors are reported in chapter-specific updates to EPA/600/R-090/052F, 2011, *Exposure Factors Handbook: 2011 Edition*. Updated dose coefficients for ingestion and inhalation are reported in DOE-STD-1196-2021. Updated dose coefficients for external exposure to contaminated soil are reported in EPA-402-R19-002, *Federal Guidance Report No. 15, External Exposure to Radionuclides in Air, Water, and Soil*. After incorporation of the updated exposure factors and dose coefficients, the waste concentrations that are protective to a member of the public following a hypothetical inadvertent intrusion into the waste changed. These concentration limits define numerical concentration levels that each waste stream that is disposed of in the IDF must be below to stay below dose limit performance measures specified in DOE M 435.1-1. Consequently, these concentration limits are included in the IDF Waste Acceptance Criteria, IDF-00002, *Waste Acceptance Criteria for the Integrated Disposal Facility* and must be revised when input to the calculations are revised. At the end of FY 2022, the updated concentration limits had not yet been incorporated into a revision to IDF-00002.
- An additional special analysis that updated waste stream inventories to align with more recent flowsheet modeling of the WTP were also performed in FY 2022. The cumulative impact of all these changes was evaluated in the special analysis that was started in FY 2021. The cumulative impact analysis concluded that the IDF could still meet DOE M 435.1-1 performance objectives if an inventory limit for technetium-99 in encapsulated debris SSW was imposed.
- A special analysis was performed in FY 2022 to develop the inventory limit for technetium-99 in encapsulated debris solid secondary waste. The updated concentration limits and technetium -99 inventory limit for encapsulated debris waste will be incorporated into the IDF Waste Acceptance Criteria in a FY 2023 update.
- A special analysis was performed in FY 2022 that evaluated newly-identified waste streams that were not included in the secondary waste forecast evaluated in the IDF PA. These new waste streams are from on-site sources (e.g., WTP, tank farms, and 222-S laboratory) that produce liquid waste streams that would be solidified prior to disposal in the IDF. This analysis also includes additional solid secondary waste streams generated at the 222-S Laboratory that are currently disposed of at the Environmental Restoration Disposal Facility but would be disposed of in the IDF as soon as it

begins accepting waste. Based on the completed updates to the IDF PA technical basis, the FY 2022 Annual Summary Report for the IDF PA will detail that a new IDF PA base case is established by the recently completed special analyses and that the ODAS would remain valid once an inventory limit for technetium-99 in the encapsulated debris solid secondary waste is added to the IDF waste acceptance criteria.

## 6.2 Changes in Site Land Use and Remediation Plans

There have been no changes in site land use in FY 2022 that will affect the Central Plateau. Remediation planning continued to implement approved decision documents.

The overall cleanup strategy for the 195 km<sup>2</sup> (75 mi<sup>2</sup>) Central Plateau is described in DOE/RL-2009-10. The cleanup strategy is the result of thousands of hours of work that considered input from the regulatory agencies, Tribal Nations, the public, and stakeholders. Selection of cleanup remedies that are consistent with the reasonably anticipated future land use is one of the foundational elements of the Central Plateau strategy. The strategy calls for cleanup on the Central Plateau to be organized into the following three major components:

- **Inner Area:** The final footprint area of the Hanford Site that will be dedicated to waste management and containment of residual contamination.
- **Outer Area:** All of the Central Plateau beyond the boundary of the Inner Area.
- **Groundwater:** Contaminant plumes underlying the Central Plateau and originating from waste sites on the Central Plateau.

These components are consistent with land uses designated for the Central Plateau in DOE/EIS-0222F, *Final Hanford Comprehensive Land-Use Plan Environmental Impact Statement*; subsequent ROD (64 FR 61615, “Record of Decision: Hanford Comprehensive Land-Use Plan Environmental Impact Statement [HCP EIS]”); 2008 supplement analysis (DOE/EIS-0222-SA-01, *Supplement Analysis: Hanford Comprehensive Land-Use Plan Environmental Impact Statement*); subsequent ROD (73 FR 55824, “Amended Record of Decision for the Hanford Comprehensive Land-Use Plan Environmental Impact Statement”); and 2015 supplement analysis (DOE/EIS-0222-SA-02, *Supplement Analysis of the Hanford Comprehensive Land-Use Plan Environmental Impact Statement*). Designated land uses on the Central Plateau are industrial-exclusive for 50 km<sup>2</sup> (20 mi<sup>2</sup>) at the core of the Central Plateau (including the Inner Area and a portion of the Outer Area) and conservation (mining) in the surrounding 145 km<sup>2</sup> (55 mi<sup>2</sup>) area (which includes the majority of the Outer Area).

### 6.2.1 Engineered Barriers (in Remediation Plans)

In the original Hanford Site Composite Analysis (PNNL-11800), transport through the vadose zone to the water table was simulated under transient flow conditions. The recharge rate in the vadose zone was allowed to vary with the application of different surface treatments and covers (i.e., barriers). Thus, performance was evaluated with and without surface infiltration barriers.

The Hanford Site disposition baseline (PNNL-15829, *Inventory Data Package for Hanford Assessments*) compiled a suite of all remedial actions for waste sites at the Hanford Site. The Hanford Site disposition baseline was developed to represent the most credible end state of the Hanford Site based on information made available by DOE and its contractors, including interim and final RODs. Therefore, the Hanford Site disposition baseline is a combination of remedial actions based on interim and final RODs and remedial actions proposed by DOE, but not yet interim or finally approved by the regulatory agencies. This baseline was updated in preparation for the Hanford Site Composite Analysis (CP-60254, *Hanford*

*Site Composite Analysis Technical Approach Description: Hanford Site Disposition Baseline*) to reflect new decisions and changed projections since the original compilation in 2005 and finalized for use in the updated Hanford Site Composite Analysis in CP-63386, *Hanford Site Disposition Baseline Data Package for Hanford Site Composite Analysis*. The use of infiltration barriers will be evaluated in accordance with the expected use of these barriers at various source sites rather than globally with, and without, as was presented in the original composite analysis (PNNL-11800).

### **6.2.2 Institutional Controls**

ICs are established in accordance with CERCLA and RCRA corrective action decisions to prevent inappropriate uses of land, facilities, and environmental media and to prevent exposure to residual contaminants that could pose risks above levels deemed protective of human health and the environment. ICs generally include non-engineered restrictions on activities and access to land, groundwater, surface water, waste sites, waste disposal areas, and other areas or media that may contain hazardous substances to minimize the potential for human exposure to the substances.

IC requirements for the Hanford Site are summarized in a *Sitewide Institutional Controls Plan for Hanford CERCLA Response Actions and RCRA Corrective Actions* (DOE/RL-2001-41) that is updated when CERCLA decision documents and/or RCRA corrective action documents listing new ICs are issued. Revision 10 was completed in September 2022 to incorporate ICs required by 100-BC OU Final ROD and the 200-BP-5/200-PO-1 Interim ROD.

An annual assessment of the ICs provides for an evaluation of the effectiveness of the controls and the opportunity for cost-effective improvements. The results of the assessment are provided to EPA and Ecology. The FY 2021 assessment is documented in *FY 2021 Annual Sitewide Institutional Control Assessment* (HNF-67155), issued in November 2021. The FY 2022 assessment will be issued in FY 2023.

### **6.2.3 Operational Controls for Subsidence**

The annual status reports for the 200 West and 200 East Area LLBGs (DOE/RL-2019-50, *Annual Status Report [FY 2019]: Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*; DOE/RL-2019-51, *Annual Status Report [FY 2019]: Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*) noted that LLBG waste acceptance criteria (HNF-EP-0063) address disposal in a physically stable configuration with minimal void space, minimal gas emission, and elimination of pyrophoric characteristics. These criteria are also used to minimize long-term subsidence. These requirements are being administered by LLBG operations and typically involve solidification or void-fill processes. As necessary, waste packages are grouted or placed into concrete boxes that are high-integrity containers (or equivalent). Surveillance for local subsidence is performed routinely by LLBG staff, and any cavities that form are filled in with dirt or grout.

The ERDF waste acceptance criteria document (ERDF-00011) states that packaged waste will be structurally stable for ERDF disposal to limit potential subsidence. Packaged waste that is not structurally stable may be accepted at ERDF on a case-by-case basis and stabilized before and during disposal. Depending on the waste stream, stabilization may be accomplished using soil, cement-based agents, or other stabilization agents with acceptable structural characteristics, size reduction, a mixture of biodegradable waste and stabilizing agents, and/or voids filled with stabilization agents. Additional physical limits for waste forms including concrete, steel plate, piping and tube steel, building debris, structural steel, containerized waste, equipment, soft waste, and rebar are defined in ERDF-00003, *Supplemental Waste Acceptance Criteria for the Environmental Restoration Disposal Facility*.

Following the partial collapse of PUREX Tunnel 1 in May 2017, both Tunnel 1 and Tunnel 2 were filled with engineered grout to reduce the risk of further collapse and increase the protection for workers, the public, and the environment from radiological hazards, while not precluding future remedial actions or final closure decisions. Subsequently, other older structures on the Central Plateau were analyzed to determine if any other structures are at risk of significant subsidence or collapse. Twenty-seven structures were identified that may have a potential risk of subsidence that requires mitigation. In 2019, a further structural evaluation was performed for 11 of the 27 structures. The evaluation report identified three underground liquid waste disposal structures (216-Z-2 Crib, 216-Z-9 Crib, and 241-Z-361 Settling Tank) that represented the highest risk, requiring stabilization to prevent a potential collapse that could spread contamination to the environment. Stabilization of the 216-Z-9 and 241-Z-361 by void filling with engineered grout was completed in FY 2021 to mitigate the risk of subsidence without interfering with the final remedy. After further field investigation at 216-Z-2, it was determined that sufficient soil overburden exists to cover/sequester the source term in the event of collapse and no further action was taken. Remaining sites will continue to be evaluated and stabilization plans developed as needed to mitigate potential future risks.

This page intentionally left blank.

## **7 Status of Disposal Authorization Statement Conditions and Key and Secondary Issues**

Table 7-1 summarizes the DAS conditions pertaining to the Hanford Site Composite Analysis. Appendix B in this document provides the status of the current effort to update this Composite Analysis.

**Table 7-1. Status of Disposal Authorization Statement Conditions, Key, and Secondary Issues**

<b>Disposal Facility/Unit</b>	<b>Key/Secondary Issue or Disposal Authorization Statement Condition Number</b>	<b>Issue Description</b>	<b>Initial Resolutions Scheduled Date</b>	<b>Projected Resolution Scheduled Date</b>	<b>Disposition Documentation and Date Completed</b>	<b>Composite Analysis Impact</b>
CA	1	High-level waste tank inventories did not account for chemical effects that may increase inventories of certain radionuclides in the residual tank solids.	2002	2004	Closed; however, requires further evaluation. Closure of this issue was based on “a sitewide effort is underway to address this and other inventory-related concerns.” The SAC effort was suspended in 2006.	This issue will be addressed in the composite analysis update.
CA	2	Use of a $K_d$ “switch depth” needs additional justification.	2002	2004	Closed; addressed in 2002 ASR (Hildebrand and Bergeron, 2002); issue closed in Chung, 2004.	None
CA	3	Need justification for not using reduction-oxidation as a $K_d$ discriminator.	2002	2004	Closed; addressed in 2002 ASR (Hildebrand and Bergeron, 2002); issue closed in Chung, 2004.	None
CA	4	Numerical modeling grid spacing was used as a constraint for selecting the dispersivity values in the analysis. This had no physical basis and leads to increased dispersion.	2002	2004	Closed; addressed in 2002 ASR (Hildebrand and Bergeron, 2002); issue closed in Chung, 2004.	None
CA	5	Sensitivity analysis should be conducted to investigate the effect of potential fast paths.	2002	2004	Addressed in 2002 ASR; issued closed in Chung, 2004. However, closure of this issue was based on major studies of groundwater and vadose zone systems are underway. A new analytical method (SAC) was developed for analytical purposes; however, the SAC effort was suspended in 2006.	This issue will be addressed in the composite analysis update
CA	6	Sensitivity analysis that investigates the consequences of temporally overlapping plumes should be conducted to determine effects of alternative assumptions.	2002	2004	Addressed in 2002 ASR; issue closed in Chung, 2004. However, closure of this issue was based on a new analytical method (SAC) that was developed to address this issue; however, the SAC effort was suspended in 2006.	This issue will be addressed in the composite analysis update

**Table 7-1. Status of Disposal Authorization Statement Conditions, Key, and Secondary Issues**

Disposal Facility/Unit	Key/Secondary Issue or Disposal Authorization Statement Condition Number	Issue Description	Initial Resolutions Scheduled Date	Projected Resolution Scheduled Date	Disposition Documentation and Date Completed	Composite Analysis Impact
CA	7	Modeled releases of technetium-99 from liquid discharge zones are based on quicker and smaller releases than observed with existing plumes.	2002	2004	Addressed in 2002 ASR; issue closed in Chung, 2004. However, closure of this issue was based on studies underway to address this issue. Inventory issues were evaluated and transporting and modeling issues were studied separately. In addition, a new model (SAC) was developed; however, the SAC effort was suspended in 2006.	This issue will be addressed in the composite analysis update.
CA	8	Provide justification for the assumption that the basalt aquifers and interbeds do not contain significant contaminants.	2002	2002	Issue closed in disposal authorization statement (Frei, 2002).	None

7-3

References: Chung, 2004, “Low-Level Waste Disposal Facility Federal Review Group Review of the Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, April 2003.”

Frei, 2002, “Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Submittal of an Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800 Addendum 1.”

Hildebrand and Bergeron, 2002, *Annual Status Report: Composite Analysis for Low-Level Waste Disposal in the 200 Area of the Hanford Site*.

ASR = annual status report

CA = composite analysis

$K_d$  = distribution coefficient

SAC = systems assessment capability

This page intentionally left blank.

## 8 Certification of the Continued Adequacy of the Composite Analysis

The Hanford Site Composite Analysis was approved in 2002 (Frei, 2002, “Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Submittal of an Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800 Addendum 1”). The DAS (Scott, 2001) conditions on the Hanford Site Composite Analysis have all previously been met through PNNL-11800, Addendum 1 and prior maintenance activities. The Hanford Site Composite Analysis has been maintained since that time in accordance with DOE M 435.1-1 requirements.

The Hanford Site Composite Analysis results gave a peak dose of 6 mrem/yr beyond the exclusive waste management area and buffer zone (PNNL-11800, Executive Summary) for the agricultural exposure scenario. The agricultural exposure scenario yielded the highest dose of the four scenarios evaluated (the others were residential, industrial, and recreational scenarios with doses of 2.2, 0.7, and 0.04 mrem/yr, respectively). This peak dose was predicted for a compliance period that began in CY 2050, then considered the best estimated date of final remedial actions at the Hanford Site. This peak dose was also calculated assuming the strontium-90 plume at Gable Mountain Pond, which is just beyond the buffer zone boundary, would be included in the waste management area and buffer zone.

It is noted that the peak dose prediction provided in PNNL-11800 are dominated by sources not regulated under DOE O 435.1. Examination of PA results for the 435.1-regulated disposal facilities (i.e., IDF, ERDF, 200-East and 200-West LLBGs) demonstrate that peak doses from those facilities are expected to occur far later in time (after 1,000-years post-closure) while the peak dose for the Hanford Site Composite Analysis occurs near the beginning of the 1,000-year compliance period. PNNL-11800 notes, “the Composite Analysis has shown that the active and planned dry disposals are safe and will not contribute significantly to radiation dose to hypothetical future members of the public for the 1000-year period following Hanford Site closure.” Here, all 435.1-regulated facilities are covered by “planned dry disposals”. The past-practice liquid discharges are the dominant contributor to the predicted peak dose within the 1,000-year compliance period.

Based on this annual evaluation of new information obtained from a review of PAs, remedial actions, and operations (Chapter 1), a review of the data collected and analyzed from monitoring (Chapter 4), and other changes (Chapter 5), no new information was identified in FY 2021 that would invalidate the continued adequacy of the Hanford Site Composite Analysis. That is, a peak dose well below the 30 mrem/yr dose constraint, as well as below the 100 mrem/yr dose limit, is still expected based on the review of new information identified in FY 2021. However, a determination was reached that an update to the composite analysis is necessary based on information reviewed in a previous annual status report, for FY 2015 (DOE/RL-2015-66) based on all prior annual status reports. The following reasons this determination was made in FY 2015 remain applicable:

- The original Hanford Site Composite Analysis was prepared in 1998 with an addendum in 2001. While maintained since that time, the accumulation of basis changes reported in the annual summary reports over the past 15 years merits evaluation in an updated analysis (DOE/RL-2015-66). The following new information needs to be incorporated in an updated analysis:
  - The original Hanford Site Composite Analysis deferred evaluation of planned remedial actions to the second iteration of the composite analysis because time and information were insufficient to determine if alternate remedies would be necessary from the results of the composite analysis and identify them through the negotiation process. Accordingly, a single remedial action (i.e., leave in place and cover with surface barrier) was analyzed in the composite analysis. Significant changes

have been made through decision making in the CERCLA process since that time, and a detailed Hanford Site baseline disposition was prepared to project remedial activities through site closure that should be incorporated into an updated Hanford Site Composite Analysis.

- Issuance of the TC & WM EIS (DOE/EIS-0391) in FY 2013 provided an updated inventory basis, new modeling capabilities, and new decisions reached in the associated ROD (78 FR 75913) that need to be incorporated into the Hanford Site Composite Analysis. Updates to the Hanford Site Composite Analysis were deferred from 2006 until 2013, awaiting final issuance of DOE/EIS-0391 and transfer of the modeling capability developed for that study. The modeling capability developed for and applied in the TC & WM EIS was transferred from the DOE-ORP to DOE-RL during FY 2013 (DOE-ORP, 2012, *Tank Closure and Waste Management Environmental Impact Statement Technology Transfer Document*). Development of a Hanford Site groundwater model from the baseline provided in DOE-ORP, 2012, commenced in FY 2014 and continued in FYs 2015 and 2016.
- The P&T systems, which were not evaluated in the original Hanford Site Composite Analysis, have had significant impact on behavior of the groundwater flow system, contaminant transport, and contaminant removal from Hanford Site groundwater (Section 1.3.2).
- Development of the Central Plateau cleanup strategy (Section 6.2) may lead to establishing a different point of compliance for evaluation of DOE M 435.1-1 performance metrics for the Hanford Site Composite Analysis than the core zone boundary used in the original 1998 composite analysis (PNNL-11800).
- Data collected as the unconfined aquifer water levels continue to recede since the cessation of large liquid discharges during the operational era (Section 4.1) have led to marked improvement in understanding the flow system for future conditions, particularly regarding northward flow potential in the critical Gable Gap area.
- The revised ERDF PA was completed in 2013 (WCH-520, Rev. 1) (Section 1.1.5). The updated inventory for this PA and evaluation of expanding this facility to about twice the size that was evaluated in the original Hanford Site Composite Analysis are needed.
- The geologic structural basis for groundwater models has continued to improve with additional data collection and interpretation (ECF-HANFORD-13-0020, *Process for Constructing a Three-dimensional Geological Framework Model of the Hanford Site's 100 Area*; ECF-HANFORD-13-0029, *Development of the Hanford South Geologic Framework Model, Hanford Site, Washington*).
- Tank residual inventory estimates have improved with the incorporation of tank retrieval inventory data for those tanks that have completed retrieval. In contrast, the original Hanford Site Composite Analysis (PNNL-11800) was necessarily reliant upon assumptions regarding future retrieval and associated retrieval losses.
- The first PA for a tank farm closure decision was completed in FY 2016 for WMA C. A PA is currently being prepared for WMA A-AX and is expected to be completed during the period required to prepare a revised Hanford Site Composite Analysis.
- An update to the IDF PA was completed in FY 2017, during the period required to prepare a revised Hanford Site Composite Analysis.

- The risk assessment scenarios currently used for Hanford Site CERCLA and RCRA analyses differ from those evaluated in the original 1998 Hanford Site Composite Analysis (PNNL-11800). Therefore, a revision should use current risk assessment scenarios.
- The original Hanford Site Composite Analysis (PNNL-11800) was prepared before DOE required that NQA-1 standards be applied by its contractors for use of simulation software for environmental modeling. A new analysis performed with current software tools qualified under DOE O 414.1D standards and applied under current, compliant QA plans and procedures would support confidence in the analysis.

DOE-RL plans maintenance activities for the original Hanford Site Composite Analysis until the updated composite analysis is completed to maintain the current DAS. Continuing the maintenance program will provide support for periodic collection and reporting of information affecting the basis of the composite analysis in the annual status reports during the period required to develop an updated composite analysis.

This annual summary identifies additional data and information from FY 2022 to be considered for purposes of updating the Hanford Site Composite Analysis. Appendix B in this document summarizes the plans and status for developing an updated composite analysis.

## **Certification by the Field Element Manager or Designee**

I certify to the best of my knowledge, that information presented in this annual status report is true, accurate, and complete and that any proposed or implemented changes associated with the PA or other technical basis documents provide a reasonable expectation that the performance objectives/measures identified in DOE O 435.1 will be met.

---

B.T. Vance, Manager  
DOE Richland Operations Office

---

Date

## 9 References

10 CFR 1021, “National Environmental Policy Act Implementing Procedures,” *Code of Federal Regulations*. Available at: <https://www.govinfo.gov/content/pkg/CFR-2019-title10-vol4/pdf/CFR-2019-title10-vol4-part1021.pdf>.

10 CFR 61.55, “Waste Classification,” *Code of Federal Regulations*. Available at: <https://www.nrc.gov/reading-rm/doc-collections/cfr/part061/part061-0055.html>.

16-AMRP-0187, 2016, “Remedial Design/Remedial Action Work Plan for the 200-CW-5, 200-PW-1, 200-PW-3, and 200-PW-6 Operable Units, DOE/RL-2015-23, Revision 0, Sampling And Analysis Plan for the 200-CW-5, 200-PW-1, and 200-PW-6 Operable Units, DOE/RL-2015-22, Revision 0” (letter to D. A. Faulk, U.S. Environmental Protection Agency, from R.J. Corey), U.S. Department of Energy, Richland Operations Office, Richland, Washington. June 7. Available at: <https://pdw.hanford.gov/document/0076383H>.

20-SGD-0026, 2019, “Groundwater Assessment First Determination Report for Waste Management Area A-AX, DOE/RL-2019-21, Revision 0” (letter to A.K. Smith, Washington State Department of Ecology, from W.F. Hamel), U.S. Department of Energy, Richland Operations Office, Richland, Washington, December 18. Available at: <https://pdw.hanford.gov/document/AR-03385>.

40 CFR 61, “National Emission Standards for Hazardous Air Pollutants,” Appendices A through E, *Code of Federal Regulations*. Available at: <https://www.govinfo.gov/content/pkg/CFR-2019-title40-vol10/pdf/CFR-2019-title40-vol10-part61.pdf>.

Subpart H, “National Emission Standards for Emissions of Radionuclides Other Than Radon from Department of Energy Facilities.”

40 CFR 300.430, “National Oil and Hazardous Substances Pollution Contingency Plan,” “Remedial Investigation/Feasibility Study and Selection of Remedy, *Code of Federal Regulations*. Available at: <https://www.govinfo.gov/content/pkg/CFR-2010-title40-vol27/xml/CFR-2010-title40-vol27-part300.xml#seqnum300.430>.

64 FR 61615, “Record of Decision: Hanford Comprehensive Land-Use Plan Environmental Impact Statement (HCP EIS),” *Federal Register*, Vol. 64, No. 218, pp. 61615–61625, November 12, 1999. Available at: <https://www.govinfo.gov/content/pkg/FR-1999-11-12/pdf/99-29325.pdf>.

73 FR 55824, “Amended Record of Decision for the Hanford Comprehensive Land-Use Plan Environmental Impact Statement,” *Federal Register*, Vol. 73, No. 188, pp. 55824–55826, September 26, 2008. Available at: <https://www.govinfo.gov/content/pkg/FR-2008-09-26/pdf/E8-22676.pdf>.

78 FR 75913, “Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington,” *Federal Register*, Vol. 78, No. 240, pp. 75913–75919, December 13, 2013. Available at: <https://www.govinfo.gov/content/pkg/FR-2013-12-13/pdf/2013-29734.pdf>.

1301789, 2012, “Modeling to Support Regulatory Decisionmaking at Hanford” (memorandum to M.S. McCormick, U.S. Department of Energy, Richland Operations Office, and S.L. Samuelson, U.S. Department of Energy, Office of River Protection, from A.C. Williams), Associate Principal Deputy Assistant Secretary for Environmental Management, U.S. Department of Energy, Washington, D.C., October 9. Available at: <https://pdw.hanford.gov/document/0075608H>.

ANSI/HPS N13.1, 2011, *Sampling and Monitoring Releases of Airborne Radioactive Substances from the Stacks and Ducts of Nuclear Facilities*, American National Standards Institute/Health Physics Society, New York, New York.

*Atomic Energy Act of 1954*, Pub. L. 83-703 as amended, 42 USC 2011 et seq., 68 Stat. 919. Available at: <https://www.govinfo.gov/content/pkg/STATUTE-68/pdf/STATUTE-68-Pg919.pdf#page=30>.

BHI-00169, 1995, *Environmental Restoration Disposal Facility Performance Assessment*, Rev. 00, Bechtel Hanford, Inc., Richland, Washington.

CCN 173929, 2013, “Issuance of the Disposal Authorization for the Environmental Restoration Disposal Facility, Hanford Site, Washington,” (memorandum to M.S. McCormick, Richland Operations Office Manager, from M.A. Gilbertson, Deputy Assistant Secretary for Site Restoration), U.S. Department of Energy, Washington, D.C., November 19.

CHPRC-03264, 2017, *M-091-52 Alternative Evaluation*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0068322H>.

CHPRC-1203550, 2012, “Contract Number DE-AC06-08RL14788 – Disposal Pathway for Hanford’s German Logs” (letter to J.C. Connerly, U.S. Department of Energy, Richland Operations Office, from J.G. Lehew), CH2M HILL Plateau Remediation Company, Richland, Washington, September 18.

Chung, D.Y., 2004, “Low-Level Waste Disposal Facility Federal Review Group Review of the Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, April 2003” (memorandum to R. Schepens, Manager, Office of River Protection, and K.A. Klein, Manager), U.S. Department of Energy, Richland Operations Office, Richland, Washington. May 11.

*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, Pub. L. 107-377 as amended, 42 USC 9601 et seq., December 31, 2002. Available at: <https://www.csu.edu/cerc/researchreports/documents/CERCLASummary1980.pdf>.

Council on Environmental Quality, 2005, *Regulations for Implementing the Procedural Provisions of the National Environmental Policy Act*, Executive Office of the President, Reprint of 40 CFR Parts 1500-1508. Available at: [https://energy.gov/sites/prod/files/NEPA-40CFR1500\\_1508.pdf](https://energy.gov/sites/prod/files/NEPA-40CFR1500_1508.pdf).

CP-60070, 2015, *Environmental Restoration Disposal Facility Leachate Sampling and Analysis Plan, formerly WCH-173 Rev. 2*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-02518>.

CP-60089, 2016, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford, Washington, formerly WCH-520 Rev. 1*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

CP-60150, 2017, *Environmental Restoration Disposal Facility Performance Assessment Maintenance Plan*, Rev. 1, CH2M HILL Plateau Remediation Company, Richland, Washington.

CP-60195, 2017, *Hanford Site Composite Analysis Technical Approach Description: Radionuclide Inventory and Waste Site Selection Process*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1434495>.

CP-60254, 2017, *Hanford Site Composite Analysis Technical Approach Description: Hanford Site Disposition Baseline*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064793H>.

CP-60649, 2017, *Summary Analysis: Hanford Site Composite Analysis Update*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1412683>.

CP-63386, 2020, *Hanford Site Disposition Baseline Data Package for Hanford Site Composite Analysis*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1615522>.

CPCC, 2021. *Waste Management Basis*, CPCC-MP-WM-52872, Central Plateau Cleanup Company, Richland, Washington.

DE-AC06-08RL14788, 2007, *CH2M HILL Plateau Remediation Company Plateau Remediation Contract*, as amended, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.hanford.gov/index.cfm?page=1060&>.

DOE-0431, 2019, *Recommendations for Institutional Control Time Period for Conducting DOE Order 435.1 Performance Assessments at the Hanford Site*, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE, 2018, *Office of Enterprise Assessments Assessment of Low-Level Radioactive Waste Disposal Practices at the Hanford Site*, Office of Nuclear Safety and Environmental Assessments; Office of Environment, Safety and Health Assessments; and Office of Enterprise Assessments; U.S. Department of Energy, Washington, D.C. Available at: <https://www.energy.gov/sites/prod/files/2018/02/f48/Assessment%20of%20Low-Level%20Rad%20Waste%20Disposal%20Practices%20at%20Hanford.pdf>.

DOE/EA-1707D, 2011, *Environmental Assessment: Closure of Nonradioactive Dangerous Waste Landfill (NRDWL) and Solid Waste Landfill (SWL), Hanford Site, Richland, Washington*, Revised Predecisional Draft, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0093731>.

DOE/EIS-0222F, 1999, *Final Hanford Comprehensive Land-Use Plan Environmental Impact Statement*, U.S. Department of Energy, Washington, D.C. Available at: <https://pdw.hanford.gov/document/D199158842>.  
<https://pdw.hanford.gov/document/D199158843>.  
<https://pdw.hanford.gov/document/D199158844>.  
<https://pdw.hanford.gov/document/D199158845>.  
<https://pdw.hanford.gov/document/D199158846>.  
<https://pdw.hanford.gov/document/D199158847>.

DOE/EIS-0222-SA-01, 2008, *Supplement Analysis: Hanford Comprehensive Land-Use Plan Environmental Impact Statement*, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: [https://www.hanford.gov/files.cfm/SAwith\\_signed-R1.pdf](https://www.hanford.gov/files.cfm/SAwith_signed-R1.pdf).

DOE/EIS-0222-SA-02, 2015, *Supplement Analysis of the Hanford Comprehensive Land-Use Plan Environmental Impact Statement*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076998H>.

DOE/EIS-0391, 2012, *Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington (TC & WM EIS)*, U.S. Department of Energy, Office of River Protection, Richland, Washington. Available at: <https://energy.gov/nepa/downloads/eis-0391-final-environmental-impact-statement>.

DOE M 435.1-1 Chg 3 (LtdChg), 2021, *Radioactive Waste Management Manual*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-DManual-1-chg3-ltdchg-1>.

DOE O 414.1D, Admin Chg 1, 2011, *Quality Assurance*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives/0414.1-BOrder-d/view>.

DOE O 435.1 Chg 1, 1999, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder>.

Superseded by:

DOE O 435.1 Chg 1 (PgChg), 2007, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder-chg1-PgChg>.

DOE O 5820.2A, 1988, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. (superseded by DOE O 435.1 Chg 1). Available at: <https://www.directives.doe.gov/directives-documents/5800-series/5820.2-BOrder-a>.

DOE-ORP, 2012, *Tank Closure and Waste Management Environmental Impact Statement Technology Transfer Document*, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE/ORP-2000-01, 2004, *Maintenance Plan for the Hanford Integrated Disposal Facility Performance Assessment*, Rev. 1, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE/ORP-2000-24, 2001, *Hanford Immobilized Low-Activity Waste Performance Assessment: 2001 Version*, Rev. 0, U.S. Department of Energy, Office of River Protection, Richland, Washington. Available at: <https://pdw.hanford.gov/document/D8862887>, <https://pdw.hanford.gov/document/D8862892>.

DOE/ORP-2018-01, 2019, *Draft Waste Incidental to Reprocessing Evaluation for Closure of Waste Management Area C at the Hanford Site*, Draft D, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE/ORP-2020-03, 2020, *Final Waste Incidental to Reprocessing Evaluation for Closure of Waste Management Area C at the Hanford Site*, Rev. 0, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE/ORP-2021-02, 2021, *Department of Energy Responses to the Nuclear Regulatory Commission Request for Additional Information on the Draft Waste Incidental to Reprocessing Evaluation for Vitrification of Low Activity Waste*, Rev. 1, U.S. Department of Energy, Office of River Protection, Richland, Washington.

DOE/RL-91-50, 2018, *Hanford Site Environmental Monitoring Plan*, Rev. 8, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: [https://www.hanford.gov/files.cfm/2018\\_EMP\\_estars.pdf](https://www.hanford.gov/files.cfm/2018_EMP_estars.pdf).

DOE/RL-93-99, 1994, *Remedial Investigation and Feasibility Study Report for the Environmental Restoration Disposal Facility*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/D196061256>.

DOE/RL-95-02, 1995, *Treatability Test Report for the 200-UP-1 Operable Unit – Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/D196008296>.

DOE/RL-97-36, 2010, *200-UP-1 Groundwater Remedial Design/Remedial Action Work Plan*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/1003100445>.

DOE/RL-2000-29, 2018, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1420314>.

DOE/RL-2002-59, 2004, *Hanford Site Groundwater Strategy: Protection, Monitoring, and Remediation*, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0084084>.

DOE/RL-2002-68, 2003, *Hanford's Groundwater Management Plan: Accelerated Cleanup and Protection*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0075638H>.

DOE/RL-2004-60, 2016, *200-SW-2 Radioactive Landfills Group Operable Unit RCRA Facility Investigation/Corrective Measures Study/Remedial Investigation/Feasibility Study Work Plan*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0075017H>.

DOE/RL-2007-20, 2007, *Hanford Integrated Groundwater and Vadose Zone Management Plan*, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0098519>.

DOE/RL-2007-56, 2008, *Deep Vadose Zone Treatability Test Plan for the Hanford Central Plateau*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0804160110>.

DOE/RL-2008-01, 2008, *Hanford Site Groundwater Monitoring For Fiscal Year 2007*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/00098824>.

DOE/RL-2008-59, 2015, *Interim Status Groundwater Monitoring Plan for the 216-B-3 Pond*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0078942H>.

DOE/RL-2008-60, 2012, *Interim Status Groundwater Monitoring Plan for the 216-B-63 Trench*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0091409>.

DOE/RL-2008-61, 2017, *Interim Status Groundwater Monitoring Plan for the 216-S-10 Pond and Ditch*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0069130H>.

DOE/RL-2009-10, 2013, *Hanford Site Cleanup Completion Framework*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076744H>

DOE/RL-2009-66, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single Shell Tank Waste Management Area T*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03377>.

DOE/RL-2009-67, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single Shell Tank Waste Management Area TX TY*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03378>.

DOE/RL-2009-68, 2012, *Interim Status Groundwater Monitoring Plan for the LLBG WMA 3*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0091407>.

DOE/RL-2009-69, 2012, *Interim Status Groundwater Monitoring Plan for the LLBG WMA 4*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0091410>.

DOE/RL-2009-73, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single Shell Tank Waste Management Area S-SX*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03379>.

DOE/RL-2009-74, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area U*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03380>.

DOE/RL-2009-75, 2016, *Interim Status Groundwater Monitoring Plan for the LLWMA-1*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0074656H>.

DOE/RL-2009-76, 2016, *Interim Status Groundwater Monitoring Plan for the LLWMA-2*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0078749H>.

DOE/RL-2009-77, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area C*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03381>.

DOE/RL-2009-85, 2012, *Remedial Investigation Report for the 200-PO-1 Groundwater Operable Unit*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0091415>.

DOE/RL-2009-85-ADD1, 2015, *Remedial Investigation Report for the 200-PO-1 Groundwater Operable Unit Addendum 1*, Draft A, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0080465H>.

DOE/RL-2009-119, 2010, *Characterization of the Soil Desiccation Pilot Test Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0092552>.

DOE/RL-2009-122, 2012, *Remedial Investigation/Feasibility Study for the 200-UP-1 Groundwater Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0092344>.  
<https://pdw.hanford.gov/document/0092342>.  
<https://pdw.hanford.gov/document/0092341>.

DOE/RL-2009-127, 2018, *Remedial Investigation Report for the 200-BP-5 Groundwater Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064655Hhttp://pdw.hanford.gov/arpir/pdf.cfm?accession=TBD>.

DOE/RL-2010-05, 2012, *Proposed Plan for Remediation of the 200-UP-1 Groundwater Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0092248>.

DOE/RL-2010-49, 2016, *Remedial Investigation/Feasibility Study Work Plan for the 200-WA-1 and 200-BC-1 Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072177H>.  
<https://pdw.hanford.gov/document/0072173H>.  
<https://pdw.hanford.gov/document/0072172H>.  
<https://pdw.hanford.gov/document/0072171H>.  
<https://pdw.hanford.gov/document/0072170H>.  
<https://pdw.hanford.gov/document/0072169H>.  
<https://pdw.hanford.gov/document/0072168H>.  
<https://pdw.hanford.gov/document/0072167H>.

DOE/RL-2010-74, 2015, *Treatability Test Plan for the 200-BP-5 Groundwater Operable Unit*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0081243H>.

DOE/RL-2010-92, 2015, *Interim Status Groundwater Monitoring Plan for the 216-A-37-1 PUREX Plant Crib*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079698H>.

DOE/RL-2010-93, 2015, *Interim Status Groundwater Monitoring Plan for the 216-A-36B PUREX Plant Crib*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079701H>.

DOE/RL-2011-40, 2011, *Field Test Plan for the Perched Water Pumping/Pore Water Extraction Treatability Test*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0093355>.

DOE/RL-2011-104, 2012, *Characterization Sampling and Analysis Plan for the 200-DV-1 Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/1202020261>.

DOE/RL-2011-104-ADD-1, 2017, *Characterization Sampling and Analysis Plan for the 200-DV-1 Operable Unit Addendum 1: Attenuation Process Characterization*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0071507H>.

DOE/RL-2011-104-ADD-2, 2017, *Characterization Sampling and Analysis Plan for the 200-DV-1 Operable Unit Addendum 2: Supplemental Shallow Soil Risk Characterization Sampling*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0071506H>.

DOE/RL-2012-34, 2012, *Deep Vadose Zone Treatability Test for the Hanford Central Plateau: Soil Desiccation Pilot Test Results*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0092484>.

DOE/RL-2012-47, 2015, *Mission Needs Statement for the Management of the Cesium and Strontium Capsules*, Rev. 6, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2012-53, 2019, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area B-BX-BY*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03043>.

DOE/RL-2013-07, 2013, *200-UP-1 Groundwater Operable Unit Remedial Design/Remedial Action Work Plan*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0087671>.

DOE/RL-2013-37, 2013, *Engineering Evaluation/Cost Analysis for Perched Water Pumping/Pore Water Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0086598>.

DOE/RL-2013-40, 2014, *Annual Status Report (FY 2013): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1363964>.

DOE/RL-2014-32, 2014, *Hanford Site Groundwater Monitoring Report for 2013*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0084842>.

DOE/RL-2014-34, 2014, *Action Memorandum for 200-DV-1 Operable Unit Perched Water Pumping/Pore Water Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0082284H>.

DOE/RL-2014-37, 2015, *Removal Action Work Plan for 200-DV-1 Operable Unit Perched Water Pumping/Pore Water Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079128H>.

DOE/RL-2014-48, 2016, *Response Action Report for the 200-PW-1 Operable Unit Soil Vapor Extraction Remediation*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0074963H>.

DOE/RL-2015-14, 2015, *Performance Monitoring Plan for the 200-UP-1 Groundwater Operable Unit Remedial Action*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0080202H>.

DOE/RL-2015-14, 2020, *Performance Monitoring Plan for the 200-UP-1 Groundwater Operable Unit Remedial Action*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-04066>.

DOE/RL-2015-23, 2016, *Remedial Design/Remedial Action Work Plan for the 200-CW-5, 200-PW-1, 200-PW-3, and 200-PW-6 Operable Units*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076381H>.

DOE/RL-2015-26, 2016, *Engineering Evaluation/Cost Analysis for the 200-BP-5 Operable Unit Groundwater Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0077225H>.

DOE/RL-2015-49, 2016, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank Waste Management Area A-AX*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0073187H>.

DOE/RL-2015-56, 2015, *Hanford Atomic Energy Act Sitewide Groundwater Monitoring Plan*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076985H>.

DOE/RL-2015-66, 2016, *Annual Status Report (FY 2015): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1364347>.

DOE/RL-2015-67, 2016, *Annual Status Report (FY 2015): Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1364348>.

DOE/RL-2015-68, 2016, *Annual Status Report (FY 2015): Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1364349>.

DOE/RL-2015-75, 2016, *Aquifer Treatability Test Report for the 200-BP-5 Groundwater Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0074649H>.

DOE/RL-2016-41, 2016, *Action Memorandum for 200-BP-5 Operable Unit Groundwater Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0073242H>.

DOE/RL-2016-58, 2018, *200-EA-1 Operable Unit Waste Site RCRA Facility Investigation/Corrective Measures Study and Remedial Investigation/Feasibility Study Work Plan*, Draft A, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0065108H>.

DOE/RL-2017-11, 2018, *Removal Action Work Plan for 200-BP-5 Operable Unit Groundwater Extraction*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0065869H>.

DOE/RL-2017-19, 2017, *Groundwater Quality Assessment Plan for the Nonradioactive Dangerous Waste Landfill, Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072142H>.

DOE/RL-2018-30, 2018, *200-BP-5 and 200-PO-1 Groundwater Operable Units Feasibility Study for Interim Action*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03387>.

DOE/RL-2018-58, 2020, *Proposed Plan for Interim Action Remediation of the 200-BP-5 and 200-PO-1 Operable Units*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03669>.

DOE/RL-2018-70, 2019, *Optimization Pilot Test Results of Treating Water from Modular Storage Units at 200 West Pump & Treat Facility*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-02519>.

DOE/RL-2018-28, 2018, *Optimization Test Plan for Treating Water from Modular Storage Units at 200 West Pump and Treat Facility*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0065718H>.

DOE/RL-2019-21, 2019, *Groundwater Assessment First Determination Report for Waste Management Area A-AX*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03385>.

DOE/RL-2019-22, 2019, *Groundwater Assessment First Determination Report for the Nonradioactive Dangerous Waste Landfill*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03427>.

DOE/RL-2019-27, 2019, *Groundwater Assessment First Determination Report for the 216-A-29 Ditch*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03386>.

DOE/RL-2019-28, 2019, *200-DV-1 Operable Unit Laboratory Treatability Study Test Plan*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03046>.

DOE/RL-2019-29, 2019, *Groundwater Monitoring Plan for the Integrated Disposal Facility*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03232>.

DOE/RL-2019-38, 2019, *200-ZP-1 Operable Unit Optimization Study Plan*. Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03236>.

DOE/RL-2019-44, 2020, *Interim Status Groundwater Monitoring Plan for the Single-Shell Tank Waste Management Area A-AX*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03862>.

DOE/RL-2019-52, 2020, *Composite Analysis for Low-Level Waste Disposal in the Hanford Site Central Plateau (FY 2020)*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1726281>.

DOE/RL-2019-74, 2020, *Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank System*, Rev. 0, Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03908>.

DOE/RL-2020-60, 2021, *Hanford Site Groundwater Monitoring Report for 2020*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-16952>.

DOE/RL-2020-57, *Groundwater Quality Assessment Plan for the Nonradioactive Dangerous Waste Landfill*

DOE/RL-2021-15, 2021, *Hanford Annual Site Environmental Report for Calendar Year 2020*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: [https://hmis.hanford.gov/files.cfm/DOE-RL-2021-15 - Rev\\_003.pdf](https://hmis.hanford.gov/files.cfm/DOE-RL-2021-15 - Rev_003.pdf).

DOE/RL-2022-08, 2022, *Hanford Annual Site Environmental Report for Calendar Year 2021*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: [https://hmis.hanford.gov/files.cfm/DOE-RL-2022-08 - Rev\\_00.pdf](https://hmis.hanford.gov/files.cfm/DOE-RL-2022-08 - Rev_00.pdf)

DOE/RL-2020-27, *Remedial Investigation/Feasibility Study Work Plan for the 200-CP-1 Operable Unit*, pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2021-51, 2022, *Hanford Site Groundwater Monitoring Report for 2021*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-22712>.

DOE/RL-2021-57, *Annual Status Report (FY 2021): Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*, Rev. 0 pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2021-58, *Annual Status Report (FY 2021): Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*, Rev. 0 pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2021-59, *Annual Status Report (FY 2021): Performance Assessment for the Environmental Restoration Disposal Facility*, Rev. 0 pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2022-46, *Annual Status Report (FY 2022): Performance Assessment for the Environmental Restoration Disposal Facility*

DOE-STD-1196-2021, 2021, *Derived Concentration Technical Standard*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.standards.doe.gov/standards-documents/1100/1196-astd-2021/@/images/file>.

DOE-STD-5002-2017, 2017, *Disposal Authorization Statement and Tank Closure Documentation*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.standards.doe.gov/standards-documents/5000/5002-astd-2017>.

Dronen, V.R., 1996, "Environmental Restoration Disposal Facility CERCLA/DOE Order 5820.2a Roadmap" (letter to O. Robertson, U.S. Department of Energy, Richland Operations Office), Bechtel Hanford, Inc., Richland, Washington, November 8.

ECF-200E-19-0081, 2020, *Water Level Groundwater Elevation Mapping and Hydraulic Gradient Calculations for 200 East Area – Quarter 1 Calendar Year 2019*, Rev. 1, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03759>.

ECF-Hanford-12-0064, 2012, *Preliminary Evaluation of Radiological Dose from Burial of German Logs in a Disposal Facility under the Inadvertent Intruder Scenario per DOE Order 435.1 (Radioactive Waste Management)*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

ECF-Hanford-12-0065, 2012, *Preliminary Evaluation of Thermal Effects from Burial of German Logs in a Disposal Facility*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

ECF-HANFORD-13-0020, 2017, *Process for Constructing a Three-dimensional Geological Framework Model of the Hanford Site's 100 Area*, Rev. 5, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064944H>.

ECF-HANFORD-13-0029, 2017, *Development of the Hanford South Geologic Framework Model, Hanford Site, Washington*, Fiscal Year 2016 Update, Rev. 4, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072357H>.

ECF-HANFORD-19-0091, *Hydraulic Gradient and Average Linear Velocity Calculations – Quarter 1 Calendar Year 2019*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03541>.

Ecology, 2019, *Hanford Site Air Operating Permit 00-05-06, Renewal 3*, Washington State Department of Ecology, Richland, Washington. Available at: <https://fortress.wa.gov/ecy/nwp/permitting/AOP/renewal/three/index.html>.

Ecology, EPA, and DOE, 1989, *Hanford Federal Facility Agreement and Consent Order*, 2 vols. as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Olympia, Washington. Available at: <https://www.hanford.gov/?page=81>.

Einan, D.R., 2011, "Approval of the *Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility*, WCH-426, Revision 0, October 2010" (letter to J.R. Franco, U.S. Department of Energy, Richland Operations Office), U.S. Environmental Protection Agency, Richland, Washington, February 3. Available at: <https://pdw.hanford.gov/document/1102081317>.

Eisenbud, M., 1987, *Environmental Radioactivity: From Natural, Industrial, and Military Sources*, Third Edition, Academic Press, Inc., New York, New York

EPA-402/R19/002, 2019, *Federal Guidance Report No. 15: External Exposure to Radionuclides in Air, Water, and Soil*, U.S. Environmental Protection Agency, Washington, D.C. Available at: [https://www.epa.gov/sites/default/files/2019-08/documents/fgr\\_15\\_final\\_52019aug02.pdf](https://www.epa.gov/sites/default/files/2019-08/documents/fgr_15_final_52019aug02.pdf).

EPA-402-R-93-081, 1993, *Federal Guidance Report No. 12, External Exposure to Radionuclides in Air, Water, and Soil, Office of Radiation and Indoor Air*, U.S. Environmental Protection Agency, Washington, D.C. Available at: <https://www.epa.gov/sites/default/files/2015-05/documents/402-r-93-081.pdf>.

EPA, Ecology, and DOE, 2005, *Record of Decision 221-U Facility (Canyon Disposition Initiative) Hanford Site, Washington*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/DA01060264>.

EPA, Ecology, and DOE, 2007, *Amendment to the Record of Decision for the USDOE Hanford Environmental Restoration Disposal Facility*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/DA04316406>.

EPA, Ecology, and DOE, 2008, *Record of Decision Hanford 200 Area 200-ZP-1 Superfund Site Benton County, Washington*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/00098825>.

EPA, Ecology, and DOE, 2009a, *Explanation of Significant Differences for the Interim Action Record of Decision for the 200-UP-1 Groundwater Operable Unit Hanford Site Benton County, Washington*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0903310669>.

EPA, Ecology, and DOE, 2009b, *U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site 200 Area Benton County, Washington, Amended Record of Decision and Explanation of Significant Differences*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0908030975>.

EPA, Ecology, and DOE, 2011, *Record of Decision Hanford 200 Area Superfund Site 200-CW-5 and 200-PW-1, 200-PW-3, and 200-PW-6 Operable Units*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0093644>.

EPA, Ecology, and DOE, 2012, *Record of Decision for Interim Remedial Action Hanford 200 Area Superfund Site 200-UP-1 Operable Unit*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0091413>.

EPA, Ecology, and DOE, 2015a, *Explanation of Significant Differences for the U.S. Department of Energy, Environmental Restoration Disposal Facility, Hanford Site – 200 Area, Benton County, WA*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Richland Operations Office, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0079657H>.

EPA, Ecology, and DOE, 2015b, *Amendment to the Record of Decision for the USDOE Hanford Environmental Restoration Disposal Facility*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0075583H>.

EPA, Ecology, and DOE, 2021, *Interim Record of Decision Hanford 200 Area Superfund Site 200-BP-5 and 200-PO-1 Operable Units*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-16730>.

EPA/AMD/R10-02/030, 2002, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*, U.S. Environmental Protection Agency, Region 10, Washington State Department of Ecology, and U.S. Department of Energy, Seattle, Washington. Available at: <https://semspub.epa.gov/work/HQ/185375.pdf>.

EPA/AMD/R10-97/101, 1997, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*, U.S. Environmental Protection Agency, Region 10, Washington State Department of Ecology, and U.S. Department of Energy, Seattle, Washington. Available at: <https://nepis.epa.gov/Exe/ZyPURL.cgi?Dockey=P100O3EY.TXT>.

EPA/AMD/R10-99/038, 1999, *Record of Decision Amendment: U.S. Department of Energy Environmental Restoration Disposal Facility Hanford Site – 200 Area Benton County, Washington*, U.S. Environmental Protection Agency, Region 10, Washington State Department of Ecology, and U.S. Department of Energy, Seattle, Washington.

EPA/ESD/R10-96/145, 1996, *Explanation of Significant Differences: USDOE Environmental Restoration Disposal Facility, Hanford Site, Benton County, Washington*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Seattle, Washington. Available at: <https://pdw.hanford.gov/document/0093773>.

EPA/ROD/R10-95/100, 1995, *Declaration of the Record of Decision for the Environmental Restoration Disposal Facility*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://nepis.epa.gov/Exe/ZyPDF.cgi?Dockey=9100NW77.PDF>.

EPA/ROD/R10-95/114, 1995, *EPA Superfund Record of Decision: Hanford 200-Area (USDOE) OU 200-ZP-1, Benton County, WA 5/24/95*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://nepis.epa.gov/Exe/ZyPDF.cgi?Dockey=9100NWA2.PDF>.

EPA/ROD/R10-97/048, 1997, *Interim Remedial Action Record of Decision for the 200-UP-1 Operable Unit, Hanford Site, Benton County, Washington*, U.S. Environmental Protection Agency, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0078954H>.

EPA/ROD/R10-99/039, 1999, *Interim Action Record of Decision for the 100-BC-1, 100-BC-2, 100-DR-1, 100-DR-2, 100-FR-1, 100-FR-2, 100-HR-1, 100-HR-2, 100-KR-1, 100-KR-2, 100-IU-2, 100-IU-6, and 200-CW-3 Operable Units, Hanford Site, Benton County, Washington (100 Area Remaining Sites)*, U.S. Environmental Protection Agency, Region 10, Washington State Department of Ecology, and U.S. Department of Energy, Olympia, Washington. Available at: <https://pdw.hanford.gov/document/0078953H>.

ERDF-00003, 2017, *Supplemental Waste Acceptance Criteria for the Environmental Restoration Disposal Facility*, Rev. 2, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: [https://www.emcbc.doe.gov/SEB/CPCC/Documents/Document%20Library/Other/Supplemental%20Waste%20Acceptance%20Criteria%20for%20the%20Environmental%20Restoration%20Disposal%20Facility%20-%20\(ERDF-00003,%20Rev.%202\).pdf](https://www.emcbc.doe.gov/SEB/CPCC/Documents/Document%20Library/Other/Supplemental%20Waste%20Acceptance%20Criteria%20for%20the%20Environmental%20Restoration%20Disposal%20Facility%20-%20(ERDF-00003,%20Rev.%202).pdf).

ERDF-00011, 2018, *Environmental Restoration Disposal Facility Waste Acceptance Criteria*, Rev. 1, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-01205>.

ERDF-00100, 2018, *Groundwater, Leachate, and Lysimeter Monitoring and Sampling at the Environmental Restoration Disposal Facility, Calendar Year 2018*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-04101>.

Frei, M.W., 2002, “Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Submittal of an Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800 Addendum 1” (memorandum to R. Schepens, U.S. Department of Energy, Office of River Protection, and K.A. Klein, U.S. Department of Energy, Richland Operations Office), U.S. Department of Energy, Office of Environmental Management, Washington, D.C., July 24.

Frei, M.W., 2003, “Review of the Annual Summary of the Hanford Immobilized Low-Activity Waste Performance Assessment for 2003” (memorandum to R.J. Schepens, U.S. Department of Energy, Office of River Protection, and K.A. Klein, U.S. Department of Energy, Richland Operations Office), U.S. Department of Energy, Office of Environmental Management, Washington, D.C., December 12.

Hildebrand, R.D. and M.P. Bergeron, 2002, *Annual Status Report: Composite Analysis for Low-Level Waste Disposal in the 200 Area of the Hanford Site*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

HNF-EP-0063, 2017, *Hanford Site Solid Waste Acceptance Criteria*, Rev. 17, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: [https://www.hanford.gov/files.cfm/HNF-EP-0063\\_Rev\\_17\\_Hanford\\_Site\\_Solid\\_Waste\\_Accpetance\\_Criteria.pdf](https://www.hanford.gov/files.cfm/HNF-EP-0063_Rev_17_Hanford_Site_Solid_Waste_Accpetance_Criteria.pdf).

HNF-30810, 2007, *Acceptable Knowledge Document for the 325 Building Radiochemistry Laboratory Mixed Debris Waste Stream, RLM325D*, Rev. 1, Fluor Hanford Inc., Richland, Washington.

IAMIT 2020-06, 2020, *The Interagency Management Integration Team (IAMIT) determination number 2020-006, Representative Analogous Site Coordinating Agency Liaison (RASCAL) Recommendations for Expediting Remedial Cleanup on the Hanford Central Plateau.* Available at: <https://pdw.hanford.gov/document/AR-03865>.

Klein, K.A., 2000, “Environmental Restoration Disposal Facility (ERDF) Crosswalk to DOE Order 435.1 Requirements” (letter to J.J. Fiore and M.W. Frei), U.S. Department of Energy, Richland Operations Office, Richland, Washington, July 17.

*National Environmental Policy Act of 1969*, 42 USC 4321 et seq. Available at: <https://www.govinfo.gov/content/pkg/USCODE-2010-title42/pdf/USCODE-2010-title42-chap55-sec4321.pdf>.

NAVD88, 1988, *North American Vertical Datum of 1988*, as revised, National Geodetic Survey, Federal Geodetic Control Committee, Silver Spring, Maryland. Available at: <https://www.ngs.noaa.gov/datums/vertical/north-american-vertical-datum-1988.shtml>.

NQA-1, 2008, *Quality Assurance Requirements for Nuclear Facility Applications*, American Society of Mechanical Engineers, New York, New York.

*Technical Evaluation Report: Draft Waste Incidental to Reprocessing Evaluation for Vitrified Low-Activity Waste Disposed Onsite at the Hanford Site, Washington*

OAS-L-14-04, 2014, *Audit Report Long-Term Storage of Cesium and Strontium at the Hanford Site*, Office of Audits and Inspections, Office of Inspector General, U.S. Department of Energy, Washington, D.C. Available at: <http://energy.gov/sites/prod/files/2014/04/f14/OAS-L-14-04.pdf>.

ORP-63747, 2019, *Comment Responses for the NRC Staff Request for Additional Information on the Draft Waste Incidental to Reprocessing Evaluation for Waste Management Area C*, Rev. 2, U.S. Department of Energy, Office of River Protection, Richland, Washington.

PNNL, 2020, “SOCRATES.” Available at: <https://socrates.pnnl.gov/>. Accessed on December 31, 2020.

PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079141H>.

PNNL-11800, 2001, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1, Pacific Northwest National Laboratory, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0084085>.

PNNL-15829, 2006, *Inventory Data Package for Hanford Assessments*, Rev. 0, Pacific Northwest National Laboratory, Richland, Washington. Available at: [https://www.pnnl.gov/main/publications/external/technical\\_reports/PNNL-15829rev0.pdf](https://www.pnnl.gov/main/publications/external/technical_reports/PNNL-15829rev0.pdf).

PNNL-26902, 2018, *Deep Vadose Zone Treatability Test of Soil Desiccation for the Hanford Central Plateau: Final Report*, Pacific Northwest National Laboratory, Richland, Washington. Available at: [http://www.pnnl.gov/main/publications/external/technical\\_reports/PNNL-26902.pdf](http://www.pnnl.gov/main/publications/external/technical_reports/PNNL-26902.pdf).

PNNL-29136, 2019, *SX Tank Farm Interim Surface Barrier Vadose Zone Monitoring*, Pacific Northwest National Laboratory, Richland, Washington. Available at: [https://www.pnnl.gov/main/publications/external/technical\\_reports/PNNL-29136.pdf](https://www.pnnl.gov/main/publications/external/technical_reports/PNNL-29136.pdf).

PNNL-29182, *Geophysical Methods for Stratigraphic Identification*, Rev. 1, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-29430, *Electrical Resistivity Tomography of the 216-U-5 and 216-U-6 WA-1 Waste Sites*, pending, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-30000, *Electrical Resistivity Tomography of the 216-U-1&2 and 216-U-16 WA-1 Waste Sites*, pending, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-30440, *Spectral Induced Polarization-Biogeochemical Relationships for Remediation Amendment Monitoring*, pending, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-30441, *Guidance for Monitoring Passive Groundwater Remedies over Extended Time Scales*, pending, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-30466, 2020, *Evaluation of Dose- and Risk-Based Groundwater Cleanup Levels for Low Energy Beta Radioisotopes*, Pacific Northwest National Laboratory, Richland, Washington. Available at: [https://www.pnnl.gov/main/publications/external/technical\\_reports/PNNL-30466.pdf](https://www.pnnl.gov/main/publications/external/technical_reports/PNNL-30466.pdf).

RCRA-CN-01\_DOE/RL-2008-59\_R2, 2020, *Interim Status Change Number 2: Interim Status Groundwater Monitoring Plan for the 216-B-3 Pond*, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03878>.

*Resource Conservation and Recovery Act of 1976*, Pub. L. 94-580, 42 USC 6901 et seq. Available at: <https://www.govinfo.gov/content/pkg/STATUTE-90/pdf/STATUTE-90-Pg2795.pdf>.

RFSH-9755566, 1997, “Transmittal of Program Plan for Maintenance of Hanford Burial Ground Performance Assessment (PA) Analyses, that Fulfills Performance Agreement WM 1.8.1” (memorandum to T.K. Teynor, U.S. Department of Energy, Richland Operations Office, from D.E. McKenney), Rust Federal Services of Hanford, Inc., Richland, Washington, June 25.

RCRA-CN-01\_DOE\_RL-2019-74\_R0, 2021, *Interim Status Change Number 1: Interim Status Groundwater Quality Assessment Plan for the Single-Shell Tank System*, dated June 21, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-14435>.

*Ronald W. Reagan National Defense Authorization Act for Fiscal Year 2005*, Pub. L. 108-375, 118 Stat. 1811. Available at: <https://www.govinfo.gov/content/pkg/PLAW-108publ375/pdf/PLAW-108publ375.pdf>.

RPP-15834, 2003, *Integrated Disposal Facility Risk Assessment*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.

RPP-19866, 2004, *Calculation of the Post-Retrieval Waste Volume Determination in Tank 241-C-106*, Rev. 1, CH2M HILL Plateau Remediation Company, Richland, Washington.

RPP-CALC-61013, 2022, *Groundwater Pathway Dose Calculation for the Integrated Disposal Facility Performance Assessment*, Rev. 1, Washington River Protection Solutions, Richland, Washington.

RPP-CALC-64406, 2021, *Special Analysis of Updated 2019 Tank Residual Waste Volumes and Inventories for Single-Shell Tanks in Waste Management Area C*, Rev. 1, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-14472>.

RPP-CALC-64598, 2021, *Special Analysis of Post-Closure Groundwater Impacts from Updated Tank Residual Waste Volumes and Hazardous Chemical Inventories for Single-Shell Tanks in Waste Management Area C*, Rev. 1, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-14474>.

RPP-CALC-64657, 2021, *Special Analysis – Reanalysis of Lateral Extent and Timing of Surface Barrier Placement in Waste Management Area C Performance Assessment*, Rev. 0, Washington River Protection Solutions, Richland, Washington.

RPP-ENV-58782, 2016, *Performance Assessment of Waste Management Area C, Hanford Site, Washington*, Rev. 0, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072363H>.

RPP-ENV-58782, 2021, *Performance Assessment of Waste Management Area C, Hanford Site, Washington*, Rev. 1, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-14473>.

RPP-ENV-58806, 2016, *RCRA Closure Analysis of Tank Waste Residuals Impacts at Waste Management Area C, Hanford Site, Washington*, Rev. 0, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072360H>.

RPP-RPT-42323, 2019, *Post-Closure Hanford C-Farm Tank and Ancillary Equipment Residual Waste Inventory Estimates*, Rev. 1, Washington River Protection Solutions, Richland, Washington.

RPP-RPT-49701, 2021, *Waste Management Area C – Conceptual Design Report*, Rev. 0, Washington River Protection Solutions, Richland, Washington.

RPP-RPT-58329, 2016, *Baseline Risk Assessment for Waste Management Area C*, Rev. 2, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072361H>.

RPP-RPT-58339, 2016, *Phase 2 RCRA Facility Investigation Report for Waste Management Area C*, Rev. 0, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072359H>.

RPP-RPT-59197, 2016, *Analysis of Past Tank Waste Leaks and Losses in the Vicinity of Waste Management Area C at the Hanford Site, Southeast Washington*, Rev. 1, Washington River Protection Solutions, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072362H>.

RPP-RPT-59958, 2018, *Performance Assessment for the Integrated Disposal Facility, Hanford Site, Washington*, Rev. 0, Washington River Protection Solutions, Richland, Washington.

RPP-RPT-59958, 2018, *Performance Assessment for the Integrated Disposal Facility, Hanford Site, Washington*, Rev. 1, Washington River Protection Solutions, Richland, Washington.

RPP-RPT-60833, *T-TY- Tank Farm Interim Surface Barrier Demonstration – Vadose Zone Monitoring FY17*, Rev. 0, Washington River Protection Solutions, LLC, Richland, Washington.

RPP-RPT-62021, 2020, *2019 Camera/CAD Modeling System Waste Volume Estimate for Tank 241-C-106*, Washington River Protection Solutions, LLC, Richland, Washington.

RPP-RPT-63770, 2023, *2021 Waste Management Area C Performance Assessment Maintenance Status*, Rev. 0, Washington River Protection Solutions, LLC, Richland, Washington.

Scott, R.S., 2001, "Disposal Authorization for the Hanford Site Low-Level Waste Disposal Facilities – Revision 2" (memorandum to H.L. Boston, U.S. Department of Energy, Office of River Protection, and K.A. Klein, U.S. Department of Energy, Richland Operations Office), Office of Environmental Management, U.S. Department of Energy, Washington, D.C., November 1.

SGW-54165, 2014, *Evaluation of the Unconfined Aquifer Hydraulic Gradient Beneath the 200 East Area, Hanford Site*, Rev. 0. CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0085682>.

SGW-58828, 2015, *Water Table Maps for the Hanford Site 200 East Area, 2013 and 2014*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079727H>.

SGW-59669, 2016, *WMA C October through December 2015 Quarterly Groundwater Monitoring Report*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076994H>.

SGW-59914, 2016, *WMA C January through March, 2016 Quarterly Groundwater Monitoring Report*, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072441H>.

SGW-60442, 2016, *WMA C April through June 2016 Quarterly Groundwater Monitoring Report*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0072439H>.

SGW-60494, 2016, *WMA C July through September 2016 Quarterly Groundwater Monitoring Report*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0071832H>.

SGW-60575, 2018, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area T Groundwater Monitoring*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064669H>.

SGW-60576, 2018, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area TX TY Groundwater Monitoring*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064670H>.

SGW-60577, 2018, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area S-SX Groundwater Monitoring*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

SGW-60578, 2018, *Engineering Evaluation Report for Single-Shell Tank Waste Management Area U Groundwater Monitoring*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

SGW-63236, 2019, *200-DV-1 Future Perched Water Well Evaluation*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03701>.

SGW-65178, 2021, *Evaluation of Two Alternative Drilling Scenarios (Horizontal Drilling and Drilling of Vertical Wells within Tank Farms) for Increasing Extraction within the Perched Water Zone*, Rev. 0, Central Plateau Cleanup Company, Richland, Washington.

TPA-CCF C-20-02, 2020, “Waste Site Re-Assignment from the 200-EA-1 and 200-WA 1 OUs to the new 200-IA-1 OU,” U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03973>.

TPA-CN-718, 2016, *Tri-Party Agreement Change Notice Form: DOE/RL-2009-69 Interim Status Groundwater Monitoring Plan for the LLBG WMA-4 Revision 2*, Washington State Department of Ecology, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0076959H>.

TPA-CN-1102, 2020, *Tri-Party Agreement Change Notice Form: DOE/RL-2019-38,200-ZP-1 Operable Unit Optimization Study Plan*, Rev. 0, dated September 29, U.S. Environmental Protection Agency, and U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-04131>.

US Ecology, 2016, *US Ecology Washington – 2016 Facility Utilization Report*, U.S. Ecology, Richland, Washington.

WA7890008967, DRAFT *Facility Resource Conservation and Recovery Act (RCRA) Permit, Dangerous Waste Portion for the Treatment, Storage, and Disposal of Dangerous Waste*, Revision 9, as amended, Washington State Department of Ecology, Richland, Washington. Available at: <https://fortress.wa.gov/ecy/nwp/permitting/hdwp/rev/9/index.html>.

WAC 173-303, “Dangerous Waste Regulations,” *Washington Administrative Code*, Olympia, Washington. Available at: <https://apps.leg.wa.gov/WAC/default.aspx?cite=173-303>.

WCH-426, 2010, *Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility*, Rev. 0, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0084118>.

WCH-426, 2011, *Work Plan for the Revision of a Performance Assessment Analysis for the Environmental Restoration Disposal Facility*, Rev. 1, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0093365>.

WCH-462, 2013, *ERDF Performance Assessment Modeling Approach*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-463, 2013, *Hydrogeologic Model for the Environmental Restoration Disposal Facility, Hanford Site*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-464, 2013, *Hydrologic Data Package in Support of Environmental Restoration Disposal Facility Performance Assessment Modeling*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-475, 2013, *Biota Description Data Package for the Post Closure Environmental Restoration Disposal Facility Location*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-476, 2013, *Chemical Reactivity of Radionuclides with Waste Material and Subsurface Soils During Release and Migration from the Environmental Restoration Disposal Facility*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-477, 2013, *Conceptual Models for Release and Transport of Environmental Restoration Disposal Facility Waste Contaminants through the Near-Field Environment*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-478, 2013, *Exposure and Inadvertent Scenarios for the Environmental Restoration Disposal Facility*, Rev. 1, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0083703>.

WCH-479, 2013, *Inventory Data Package for ERDF Waste Disposal*, Rev. 1, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0083702>.

WCH-515, 2013, *Parameter Uncertainty for the ERDF Performance Assessment Uncertainty and Sensitivity Analysis*, Rev. 0, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0075136H>.

WCH-520, 2013, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford Site, Washington*, Rev. 0, Washington Closure Hanford, Richland, Washington.

WCH-520, 2013, *Performance Assessment for the Environmental Restoration Disposal Facility, Hanford Site, Washington*, Rev. 1, Washington Closure Hanford, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0083701>.

WHC-EP-0645, 1995, *Performance Assessment for the Disposal of Low-Level Waste in the 200 West Area Burial Grounds*, Westinghouse Hanford Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0075582H>.

WHC-SD-WM-TI-730, 1996, *Performance Assessment for the Disposal of Low-Level Waste in the 200 East Area Burial Grounds*, Rev. 0, Westinghouse Hanford Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0071840H>.

This page intentionally left blank.

## **Appendix A**

### **History of Hanford Site Composite Analysis Maintenance**

This page intentionally left blank.

## Contents

<b>A1</b>	<b>History of Hanford Site Composite Analysis Maintenance.....</b>	<b>A-1</b>
<b>A2</b>	<b>References .....</b>	<b>A-3</b>

## Table

Table A-1. Hanford Site Composite Analysis Maintenance Documents.....	A-2
---	-----

This page intentionally left blank.

## A1 History of Hanford Site Composite Analysis Maintenance

DOE O 435.1, *Radioactive Waste Management*, requires that the Hanford Site maintain site performance assessments (PAs) and composite analyses. Requirements for composite analysis maintenance under DOE M 435.1-1, *Radioactive Waste Management Manual*, are the same as those for PA maintenance and are described in Chapter 3 of DOE, 1999, *Maintenance Guide for U.S. Department of Energy Low-Level Waste Disposal Facility Performance Assessments and Composite Analyses*. The plan for maintaining the Hanford Site Composite Analysis (PNNL-11800, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*; PNNL-11800, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1) is described in DOE/RL-2000-29, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington* (multiple revisions). Revision 2 of DOE/RL-2000-29 was approved in 2004 (Talarico, 2004, “Low-Level Disposal Facility Federal Review Group Review of Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, April 2003”). Revision 3 of DOE/RL-2000-29 was prepared in fiscal year (FY) 2017 to conform to DOE-STD-5002-2017, *Disposal Authorization Statement and Tank Closure Documentation*, and was issued in FY 2018.

DOE M 435.1-1 requires routine review and revision of PAs and composite analyses. The objective of routine review and revision is to ensure that the PAs and composite analyses are updated appropriately whenever changes in their bases (e.g., assumptions and parameters) are contemplated or affected in order to maintain the validity and effectiveness of the controls that are based on the PA and composite analysis. These reviews provide a mechanism for routine assessment of the site plans (e.g., remediation, closure, decommissioning, and land use) developed from the results of a composite analysis. This review process allows potential problems to be identified and managed at an early stage. The revisions ensure cohesive documentation, providing a reasonable basis to conclude that U.S. Department of Energy requirements for radiological protection of the public and the environment will be met in the future. The composite analysis is a planning tool that allows for evaluation of the cumulative effects of all sources of radioactive materials that may interact with those in the Low-Level Waste Disposal Facility. The impact of future activities on the dose to hypothetical future members of the public can be evaluated using the composite analysis, and the results can be used to develop land-use plans, remediation plans, or long-term stewardship documents. The annual review of the composite analysis is used to determine whether actual and planned conditions are consistent with those contained in the composite analysis. Revisions and special analyses provide a mechanism for evaluating conditions not originally included in the composite analysis to determine if these conditions could be accommodated without violating the conclusions of the composite analysis.

Chapter 4 in DOE G 435.1-1, *Implementation Guide for use with DOE M 435.1-1*, states the following:

IV.P (4) Performance Assessment and Composite Analysis Maintenance. The performance assessment and composite analysis shall be maintained to evaluate changes that could affect the performance, design, and operating bases for the facility. Performance assessment and composite analysis maintenance shall include the conduct of research, field studies, and monitoring needed to address uncertainties or gaps in existing data. The performance assessment shall be updated to support the final facility closure. Additional iterations of the performance assessment and composite analysis shall be conducted as necessary during the post-closure period.

Performance assessments and composite analyses shall be reviewed and revised when changes in waste forms or containers, radionuclide inventories, facility design and operations, closure concepts, or the improved understanding of the performance of the waste disposal facility in combination with the features of the site on which it is located alter the conclusions or the conceptual model(s) of the existing performance assessment or composite analysis.

The statements also appear in DOE M 435.1-1 and constitute the requirements for maintaining a PA or composite analysis. Further guidance is provided in DOE-STD-5002-2017.

Table A-1 lists the documents that have been prepared to maintain the Hanford Site Composite Analysis (PNNL-11800; PNNL-11800, Addendum 1) since maintenance commenced in FY 2000.

**Table A-1. Hanford Site Composite Analysis Maintenance Documents**

Reporting Period(s)	Document
FY 2000	DOE/RL-2000-29, <i>Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, Rev. 0</i>
	DOE/RL-2000-29, <i>Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, Rev. 1</i>
FY 2001	<i>Hildebrand and Bergeron, 2002, Annual Status Report: Composite Analysis for Low-Level Waste Disposal in the 200 Area of the Hanford Site</i>
FY 2002	<i>DOE/RL-2003-26, Annual Status Report: Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2003	<i>DOE/RL-2000-29, Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, Rev. 2</i>
	<i>DOE/RL-2004-12, Annual Status Report (FY 2003): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2004	<i>DOE/RL-2005-58, 2004 Annual Status Report: Composite Analysis of Low-Level Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2005	<i>DOE/RL-2006-28, Annual Status Report (FY 2005): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2006, FY 2007	<i>DOE/RL-2008-43, Annual Status Report (FY 2007): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Draft B</i>
FY 2008	<i>DOE/RL-2009-82, Annual Status Report (FY 2008): Composite Analysis of Low-level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 1</i>
FY 2009	<i>DOE/RL-2009-132, Annual Status Report (FY 2009): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2010	<i>DOE/RL-2010-105, Annual Status Report (Fiscal Year 2010): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2011	<i>DOE/RL-2011-108, Annual Status Report (Fiscal Year 2011): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 1</i>
FY 2012	<i>DOE/RL-2012-56, Annual Status Report (Fiscal Year 2012): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2013	<i>DOE/RL-2013-40, Annual Status Report (FY 2013): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>
FY 2014	<i>DOE/RL-2014-45, Annual Status Report (FY 2014): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site, Rev. 0</i>

**Table A-1. Hanford Site Composite Analysis Maintenance Documents**

Reporting Period(s)	Document
FY 2015	DOE/RL-2015-66, <i>Annual Status Report (FY 2015): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 1
FY 2016	DOE/RL-2016-62, <i>Annual Status Report (FY 2016): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
FY 2017	DOE/RL-2017-55, <i>Annual Status Report (FY 2017): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
	DOE/RL-2000-29, <i>Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington</i> , Rev. 3
FY 2018	DOE/RL-2018-60, <i>Annual Status Report (FY 2018): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
	DOE/RL-2000-29, <i>Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington</i> , Rev. 4
FY 2019	DOE/RL-2019-49, <i>Annual Status Report (FY 2019): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
FY 2020	DOE/RL-2020-48, <i>Annual Status Report (FY 2020): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
FY 2021	DOE-RL-2021-56, <i>Annual Status Report (FY 2021): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0
FY 2022	DOE-RL-2022-43, <i>Annual Status Report (FY 2022): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site</i> , Rev. 0 (this report)

Notes: Complete reference citations are provided in Chapter A2 in this appendix.

Hanford Site Composite Analysis refers to PNNL-11800, *Composite Analysis for Low Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, and corresponding PNNL-11800, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1.

FY = fiscal year

## A2 References

DOE, 1999, *Maintenance Guide for U.S. Department of Energy Low-Level Waste Disposal Facility Performance Assessments and Composite Analyses*, Rev. 4, U.S. Department of Energy, Washington, D.C. Available at: <https://ehss.energy.gov/deprep/1999/tb99n24a.pdf>.

DOE G 435.1-1, 1999, *Implementation Guide for use with DOE M 435.1-1*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives/0435.1-EGuide-1ch1/view>.

DOE M 435.1-1 Chg 3 (LtdChg), 2021, *Radioactive Waste Management Manual*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-DManual-1-chg3-ltdchg-1>.

DOE O 435.1 Chg 1, 1999, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder>.

Superseded by:

DOE O 435.1 Chg 1 (PgChg), 2007, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder-chg1-PgChg>.

DOE/RL-2000-29, 2000, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2000-29, 2000, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2000-29, 2003, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2000-29, 2018, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1420314>.

DOE/RL-2000-29, 2019, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 4, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1511494>.

DOE/RL-2003-26, 2003, *Annual Status Report: Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2004-12, 2004, *Annual Status Report (FY 2003): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2005-58, 2004, *Annual Status Report: Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2006-28, 2006, *Annual Status Report (FY 2005): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2008-43, 2008, *Annual Status Report (FY 2007): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Draft B, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2009-82, 2009, *Annual Status Report (FY 2008): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1363923>.

DOE/RL-2009-132, 2010, *Annual Status Report (FY 2009): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1363929>.

DOE/RL-2010-105, 2011, *Annual Status Report (Fiscal Year 2010): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1363944>.

DOE/RL-2011-108, 2012, *Annual Status Report (Fiscal Year 2011): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1363957>.

DOE/RL-2012-56, 2012, *Annual Status Report (Fiscal Year 2012): Composite Analysis of Low-Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1363962>.

DOE/RL-2013-40, 2014, *Annual Status Report (FY 2013): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1363964>.

DOE/RL-2014-45, 2015, *Annual Status Report (FY 2014): Composite Analysis of Low Level Waste Disposal in the Central Plateau at the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1364342>.

DOE/RL-2015-66, 2016, *Annual Status Report (FY 2015): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1364347>.

DOE/RL-2016-62, 2017, *Annual Status Report (FY 2016): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/scitech/servlets/purl/1364351>.

DOE/RL-2017-55, 2018, *Annual Status Report (FY 2017): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/servlets/purl/1432690>.

DOE/RL-2018-60, 2019, *Annual Status Report (FY 2018): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at:  
<https://www.osti.gov/servlets/purl/1511495>.

DOE/RL-2019-49, *Annual Status Report (FY 2019): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1606429>.

DOE/RL-2020-48, *Annual Status Report (FY 2020): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0. U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1825524>.

DOE/RL-2021-56, *Annual Status Report (FY 2021): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0 pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/biblio/1897511>

DOE/RL-2022-43, *Annual Status Report (FY 2022): Composite Analysis for Low Level Waste Disposal in the Central Plateau of the Hanford Site*, Rev. 0 pending, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE-STD-5002-2017, 2017, *Disposal Authorization Statement and Tank Closure Documentation*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.standards.doe.gov/standards-documents/5000/5002-astd-2017>.

Hildebrand, R.D. and M.P. Bergeron, 2002, *Annual Status Report: Composite Analysis for Low-Level Waste Disposal in the 200 Area of the Hanford Site*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0079141H>.

PNNL-11800, 2001, *Addendum to Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Addendum 1, Pacific Northwest National Laboratory, Richland, Washington. Available at <https://pdw.hanford.gov/document/0084085>.

Talarico, J., 2004, “Low-Level Disposal Facility Federal Review Group Review of Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington, April 2003” (memorandum to R. Schepens, U.S. Department of Energy, Office of River Protection, and K.A. Klein, U.S. Department of Energy, Richland Operations Office), U.S. Department of Energy, Office of Environmental Management, Washington, D.C., May 11.

## **Appendix B**

### **Status of Hanford Site Composite Analysis Update**

This page intentionally left blank.

## Contents

<b>B1</b>	<b>Status of Hanford Site Composite Analysis Update.....</b>	<b>B-1</b>
<b>B2</b>	<b>References .....</b>	<b>B-5</b>

## Tables

Table B-1.	Planning Phase Activities .....	B-1
Table B-2.	Scoping Phase Activities .....	B-2
Table B-3.	Analysis Phase Activities.....	B-4

This page intentionally left blank.

## B1 Status of Hanford Site Composite Analysis Update

In fiscal year (FY) 2015, the planning phase for preparing an updated Hanford Site Composite Analysis was undertaken and was completed under U.S. Department of Energy, Richland Operations Office (DOE-RL) direction and at the request of U.S. Department of Energy, Headquarters (DOE-HQ) in its review of the FY 2013 annual status report for the composite analysis (Gilbertson and Marcinowski, 2015, “Review of Richland Fiscal Year 2013 Annual Summaries for 200 West and 200 East Burial Grounds, Composite Analysis, Environmental Restoration Disposal Facility, and Integrated Disposal Facility”).

Consistent with DOE-HQ direction (1301789, 2012, “Modeling to Support Regulatory Decisionmaking at Hanford”), a strategy for the update was developed in FY 2015 and used to guide planning phase activities that were completed by the end of FY 2015. DOE-RL approved the baseline change request and funded scoping phase activities that commenced at the start of FY 2016 and completed in FY 2017.

The high-level plan for revision is provided with respect to phases defined in memorandum direction (1301789, 2012); planning phase activities completed in FY 2015 are listed in Table B-1; scoping phase activities completed in FYs 2016 and 2017 are listed in Table B-2; and analysis phase activities completed are listed in Table B-3.

**Table B-1. Planning Phase Activities**

Task	FY	Deliverable	Description	Status
Develop strategy for composite analysis update	2015	White paper	Top-level strategy for the update of the composite analysis (provided to DOE-RL and the Low-Level Waste Disposal Facility Federal Review Group).	<b>COMPLETED:</b> “White Paper: Strategy for Update of the Hanford Site Composite Analysis,” submitted to DOE-RL in June 2015.
Develop project schedule for FY 2016	2015	Detailed project schedule	Support baseline change request.	<b>COMPLETED:</b> Schedule developed for baseline change request in August 2015.
Update Maintenance Plan	2015	Revision to Composite Analysis Maintenance Plan	Current maintenance plan requires update; plans for update of composite analysis to be added.	<b>COMPLETED:</b> DOE/RL-2000-29 (submitted as a companion document to this annual status report).
Hanford Site Scale-Appropriate Fate and Transport Model Development and Maintenance	2015	Revision to CP-57037	Develop multiple fate and transport models that link to the Hanford Site groundwater model for boundary conditions and other information, providing an integrated system of groundwater models to support decision making at appropriate scales.	<b>COMPLETED:</b> CP-57037, issued in July 2015.

**Table B-1. Planning Phase Activities**

Task	FY	Deliverable	Description	Status
Hanford SIM Upgrade: Hardware	2015	Hardware update	Past work demonstrates that development of a sitewide inventory to support composite analysis modeling is the longest duration activity; new data from completed tank retrievals and CERCLA and RCRA activities, as well as inventory basis provided by the TC & WM EIS (DOE/EIS-0391), need to be incorporated into the revised composite analysis basis. Update of the SIM is a key activity.	<b>COMPLETED:</b> SIM computer hardware platform replaced in FY 2015.

Note: Complete reference citations are provided in Chapter B2 in this appendix.

CERCLA	=	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>
DOE-RL	=	U.S. Department of Energy, Richland Operations Office
FY	=	fiscal year
RCRA	=	<i>Resource Conservation and Recovery Act of 1976</i>
SIM	=	Soil Inventory Model
TC & WM EIS	=	Tank Closure and Waste Management Environmental Impact Statement

**Table B-2. Scoping Phase Activities**

Task	FY	Deliverable	Description	Status
Project management planning	2016	Project management plan	Management plan to direct project execution.	<b>COMPLETED:</b> PRC-MP-EP-53107, approved and issued May 2016.
Project quality assurance planning	2016	Quality assurance plan	Quality assurance and quality control planning for control of modeling activities for the composite analysis.	<b>COMPLETED:</b> Project quality assurance plan issued as part of PRC-MP-EP-53107.
Phase 1 scoping	2016	<i>Hanford Site Composite Analysis Technical Scope &amp; Approach</i> document	Establish high-level scope of the composite analysis, including period of evaluation, inclusion or exclusion of Columbia River and atmospheric pathways, inclusion or exclusion of atmospheric pathway, strategy for addressing uncertainty, extent of groundwater pathway domain, handling of historical simulation period, and identification of compliance boundary.	<b>COMPLETED:</b> Key Aspects Workshop conducted in May 2016. Key aspects scope summarized in preliminary summary analysis document submitted to DOE-RL in September 2016.

**Table B-2. Scoping Phase Activities**

Task	FY	Deliverable	Description	Status
Hanford SIM Upgrade: Software	2016	Software update (issue new SIM version and documentation, featuring operational implementation in new, maintainable software framework)	During FY 2016, the focus was on updating the software platform, which is obsolete and cannot be migrated to new hardware.	<b>COMPLETED:</b> New model implementation completed in FY 2016.
Update Hanford Site Disposition Baseline (End States)	2016	Hanford Site disposition baseline 2016 (database and description report)	Update disposition baseline – the database of the evolution of site remedial decisions, surface cover, and other actions (past and future) needed to support vadose zone modeling for the hundreds of waste sites to be simulated in the composite analysis based on Records of Decision, anticipated decisions, and planning.	<b>COMPLETED:</b> CP-60254
Draft data packages	2017	Series of draft data packages to support the composite analysis	Develop draft data packages to define detailed technical approach for models and framework to conduct the composite analysis.	<b>COMPLETED:</b> Draft technical approach description documents were prepared for all facets of the composite analysis update in 2017; these are listed under “Finalize Data Packages.”
Phase 2 scoping	2017	Workshop summary reports	Conduct series of workshop to define the context, scope, and general methodology of the composite analysis.	<b>COMPLETED:</b> Technical Approach Workshop to present and refine detailed technical approach was conducted March 29-30, 2017.
Finalize data packages	2017	Series of final data packages to support the composite analysis	Finalize data packages based on scoping workshops.	<b>COMPLETED:</b> CP-60195 CP-60405 CP-60406 CP-60408 CP-60409 CP-60410

**Table B-2. Scoping Phase Activities**

Task	FY	Deliverable	Description	Status
Develop and submit Summary Analysis	2017	Summary analysis for the Hanford Site Composite Analysis	Define modeling approach and identify departures from TC & WM EIS (DOE/EIS-0391) modeling approach with justification in a summary analysis document and submit to Groundwater/Vadose Zone Executive Council for approval of modeling approach.	<b>COMPLETED:</b> CHPRC-60649, approved May 10, 2017, and issued June 5, 2017.

Note: Complete reference citations are provided in Chapter B2 in this appendix.

DOE-RL = U.S. Department of Energy, Richland Operations Office

FY = fiscal year

SIM = Soil Inventory Model

TC & WM EIS = Tank Closure and Waste Management Environmental Impact Statement

**Table B-3. Analysis Phase Activities**

Task	FY(s)	Deliverable	Notes
Hanford SIM Upgrade: Content	2017-2018	Hanford SIM Version 2	<b>COMPLETED:</b> CP-59798 ECF-HANFORD-17-0079
Update Sitewide Inventory	2018	Comprehensive sitewide inventory dataset to support composite analysis using upgraded SIM and current versions of Hanford Site defined waste model and other source information	<b>COMPLETED:</b> CP-61786
Prototype development and testing for Composite Analysis computational approach	2017	Hanford Site Composite Analysis model integrated computational framework function and requirements specification	<b>COMPLETED:</b> CP-60407 CP-60411
Develop Waste Form Release Model and Software Implementation	2017	Waste form release models for the Hanford Site Composite Analysis	<b>COMPLETED:</b> CP-60410
Implement the approach developed in Hanford Site Composite Analysis Model Integrated Computational Framework Function and Requirements Specification	2019-2020		<b>COMPLETED:</b> Integrated modeling framework constructed and tested. (Work was deferred in FY 2018 due to funding reduction.)

**Table B-3. Analysis Phase Activities**

Task	FY(s)	Deliverable	Notes
Analysis of performance	2017–2020		<b>COMPLETED:</b> Modeling and analyses conducted to provide basis for evaluation of cumulative impacts and supporting sensitivity analyses. (Work was extended into FY 2020 due to funding reductions in FY 2017 and FY 2018. Demonstration runs were completed in FY 2019.)
Prepare Composite Analysis Draft and supporting documentation	2018–2020	Hanford Site Composite Analysis, Draft A	<b>COMPLETED:</b> Documentation prepared. <ul style="list-style-type: none"><li>• Annotated outline prepared in FY 2018.</li><li>• Document will be prepared in FY 2020.</li></ul>
Issue Composite Analysis Decisional Draft for DOE-RL review	2020		<b>COMPLETED:</b> Decisional draft document was submitted to DOE-RL on September 30, 2020.
DOE-RL Comment Resolution	2020		<b>COMPLETED:</b> Comment resolution was completed on October 28, 2020.
Prepare Composite Analysis Revision 0	2021	Hanford Site Composite Analysis, Revision 0	<b>COMPLETED:</b> Revision 0 document was submitted to DOE-RL on November 24, 2020.
Submit Composite Analysis Revision 0 to LFRG	2021		<b>COMPLETED:</b> DOE-RL conveyed the Revision 0 document to the LFRG on December 2, 2020.
Prepare Composite Analysis Revision 1	2022	Hanford Site Composite Analysis, Revision 1	<b>COMPLETED:</b> conveyed the Revision 0 document to the LFRG in May 2022.
Prepare Composite Analysis Revision 2	2023	Hanford Site Composite Analysis, Revision 2	Ongoing. Will be completed in 2023.

Note: Complete reference citations are provided in Chapter B2 in this appendix.

DOE-RL = U.S. Department of Energy, Richland Operations Office

FY = fiscal year

LFRG = Low-Level Waste Disposal Facility Federal Review Group

SIM = Soil Inventory Model

## B2 References

1301789, 2012, “Modeling to Support Regulatory Decisionmaking at Hanford” (memorandum to M.S. McCormick, U.S. Department of Energy, Richland Operations Office, and S.L. Samuelson, U.S. Department of Energy, Office of River Protection, from A.C. Williams), Associate Principal Deputy Assistant Secretary for Environmental Management, U.S. Department of Energy, Washington, D.C., October 9. Available at: <https://pdw.hanford.gov/document/0075608H>.

CHPRC-60649, 2017, *Summary Analysis: Hanford Site Composite Analysis Update*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412683>.

*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, Pub. L. 107-377 as amended, 42 USC 9601 et seq., December 31, 2002. Available at: <https://www.csu.edu/cerc/researchreports/documents/CERCLASummary1980.pdf>.

CP-57037, 2015, *Model Package Report: Plateau to River Groundwater Transport Model Version 7.1*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0080149H>.

CP-59798, 2018, *Model Package Report: Hanford Soil Inventory Model SIM v.2 Build 1*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1441221/>.

CP-60195, 2017, *Hanford Site Composite Analysis Technical Approach Description: Radionuclide Inventory and Waste Site Selection Process*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/biblio/1434495/>.

CP-60254, 2017, *Hanford Site Composite Analysis Technical Approach Description: Hanford Site Disposition Baseline*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://pdw.hanford.gov/document/0064793H>.

CP-60405, 2017, *Hanford Site Composite Analysis Technical Approach Description: Vadose Zone*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1407710>.

CP-60406, 2017, *Hanford Site Composite Analysis Technical Approach Description: Groundwater*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412549>.

CP-60407, 2017, *Hanford Site Composite Analysis Technical Approach Description: Integrated Computational Framework*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1412550>.

CP-60408, 2017, *Hanford Site Composite Analysis Technical Approach Description: Atmospheric Transport Modeling*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412671>.

CP-60409, 2017, *Hanford Site Composite Analysis Technical Approach Description: Groundwater Pathway Dose Calculation*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412672>.

CP-60410, 2017, *Hanford Site Composite Analysis Technical Approach Description: Waste Form Release*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412677>.

CP-60411, 2017, *Hanford Site Composite Analysis Technical Approach Description: Automated Quality Assurance Process Design*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/scitech/servlets/purl/1412679>.

CP-61786, 2019, *Inventory Data Package for the Hanford Site Composite Analysis*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1524617>.

DOE/EIS-0391, 2012, *Final Tank Closure and Waste Management Environmental Impact Statement for the Hanford Site, Richland, Washington (TC & WM EIS)*, U.S. Department of Energy, Office of River Protection, Richland, Washington. Available at: <http://energy.gov/nepa/downloads/eis-0391-final-environmental-impact-statement>.

DOE/RL-2000-29, 2018, *Maintenance Plan for the Composite Analysis of the Hanford Site, Southeast Washington*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1420314>.

ECF-HANFORD-17-0079, 2018, *Hanford Soil Inventory Model (SIM-v2) Calculated Radionuclide Inventory of Direct Liquid Discharges to Soil in the Hanford Site's 200 Areas*, Rev. 0, CH2M HILL Plateau Remediation Company, Richland, Washington. Available at: <https://www.osti.gov/servlets/purl/1441375>.

Gilbertson, M.A., and F. Marcinowski, 2015, "Review of Richland Fiscal Year 2013 Annual Summaries for 200 West and 200 East Burial Grounds, Composite Analysis, Environmental Restoration Disposal Facility, and Integrated Disposal Facility" (memorandum to S. Charboneau, Manager, Richland Operations Office, from M.A. Gilbertson, Deputy Secretary for Site Restoration, and F. Marcinowski, Deputy Assistant Secretary for Waste Management), U.S. Department of Energy, Washington, D.C., March 24.

PRC-MP-EP-53107, 2016, *Hanford Composite Analysis Project Management Plan*, Revision 0, Change 0, CH2M HILL Plateau Remediation Company, Richland, Washington.

*Resource Conservation and Recovery Act of 1976*, Pub. L. 94-580, 42 USC 6901, et seq. Available at: <https://www.govinfo.gov/content/pkg/STATUTE-90/pdf/STATUTE-90-Pg2795.pdf>.

This page intentionally left blank.

## Appendix C

### **Crosswalk of LFRG Review Criteria to Annual Status Report Content**

This page intentionally left blank.

## Contents

<b>C1</b>	<b>Crosswalk of LFRG Review Criteria to Annual Status Report Content.....</b>	<b>C-1</b>
<b>C2</b>	<b>References .....</b>	<b>C-6</b>

## Table

Table C-1. Crosswalk of LFRG Review Criteria to Annual Status Report Content.....	C-2
---	-----

This page intentionally left blank.

## **C1 Crosswalk of LFRG Review Criteria to Annual Status Report Content**

This appendix provides a crosswalk (Table C-1) to support review of this annual status report by identifying where the review criteria specified in DOE-STD-5002-2017, *Disposal Authorization Statement and Tank Closure Documentation*, are met in the content of this report.

**Table C-1. Crosswalk of LFRG Review Criteria to Annual Status Report Content**

ID	Review Criteria*	Where Criteria are Met
ASR-1	<p><b>9.2.1 Executive Summary</b></p> <p>Provide an overview of the documents and data used to make the certification of the continued adequacy of the PA, CA, DAS, other DAS technical basis documents, and the radioactive waste management basis (RWMB) to meet the DOE O 435.1 performance objectives/measures. If these documents need revision a corrective action plan should be developed and implemented.</p> <p>(9.2.1 Executive Summary)</p>	<p>The Executive Summary includes mention of the PA, MP, CA, and DAS. Closure plans, monitoring plans, and UDQE are also addressed in Table 1-2.</p> <p>MPs or activities are addressed in Sections 1.1, 1.2, Table 1-2, and Table 7-1. The WAC is mentioned in Sections 1.1.2 and 1.1.3.</p> <p>Performance Objectives are discussed in Sections 1.1.1, 1.1.3, 1.1.4, and Table 4-1.</p> <p>Directed by DOE-ORP, the RCRA corrective action program is pertinent to the Hanford Site CA because the actions result in planned redistributions of radioactive inventory in time, location, and waste form (Section 1.2).</p> <p>The CERCLA remedial activities directed by DOE-RL are discussed in (Section 1.3). Both maintenance and closure activities will be strongly affected by CERCLA remediation efforts, particularly for the unlined trenches that received DOE O 435.1 waste. Once the remedial decision actions have been clarified, any necessary additional closure actions can be identified, and the maintenance, PA monitoring, and closure plans will be updated as necessary and included in the next iteration of the CA.</p>
ASR-2	<p><b>9.2.2 Changes Potentially Affecting the PA, CA, DAS or RWMB</b></p> <p>All Change Control Process evaluations (called UDQE/UCAQE in Chapter 8) or other change control processes (e.g., non-conformances, corrective action) used to evaluate proposed actions, changes and new information to determine if these activities are within the boundaries analyzed in the approved PA and CA. Their potential effect on the continued adequacy of the DAS, PA, CA and RWMB should be provided. Specific information for each identified change should be described. Specific information for each identified change should be described in Table 9-1 below.</p> <p>(9.2.2 Changes Potentially Affecting the PA, CA, DAS or RWMB)</p>	<p>No change control process evaluations arising from PAs supported by the Hanford Site CA, and no UDQEs were listed for the reporting period for any PA or for the CA itself (Chapter 1 and Table 1-1).</p> <p>Changes potentially effecting the PA, CA, DAS, or RWMB are discussed in Chapter 6, Sections 6.1 and 6.2.</p>

**Table C-1. Crosswalk of LFRG Review Criteria to Annual Status Report Content**

ID	Review Criteria*	Where Criteria are Met
ASR-3	<b>9.2.3 Cumulative Effects of Changes</b>	
	<p>An evaluation and discussion of the cumulative effects of all the changes that have been identified in “Changes Potentially Affecting the PA, CA, DAS or RWMB” during the year.</p> <p>(9.2.3 Cumulative Effects of Changes)</p>	<p>Cumulative effects of information provided in Chapter 1 is discussed in the first three paragraphs in Chapter 2. The land use, engineered barriers, and operational controls for subsidence are not expected to have major changes in the CA results; however, subsidence is routinely surveilled in the active burial grounds (Sections 6.2.1 and 6.2.2).</p>
ASR-4	<b>9.2.4 Waste Receipts</b>	
	<p>The information regarding waste receipts should be provided and discussed. In addition, a discussion regarding waste receipts should be included (Table 9.3).</p> <p>(9.2.4 Waste Receipts)</p>	<p>Waste Receipts are accounted for in the individual PA Summary Reports (Chapter 3 first sentence).</p> <p>There is notice that there were no waste receipts during the reporting period in the 200 East LLBGs and there were 3 naval reactor compartment disposals in Trench 94 during the reporting period (Section 1.1.1).</p>
ASR-5	<b>9.2.5 Monitoring</b>	
	<p>This section should include monitoring results using the following table format. In addition, a discussion regarding monitoring results should be included. For compliance monitoring (Table 9-5), action levels that are exceeded should be documented along with any corrective actions in the ASR. For performance monitoring, results differing from expected behavior should be documented and discussed with any corrective actions.</p> <p>(9.2.5 Monitoring)</p>	<p>The latest summary of groundwater monitoring information (DOE/RL-2021-51) describes data collected during CY 2021 (January 1 through December 31). It represents the latest available information for purpose of this annual summary report.</p> <p>Compliance monitoring information is provided in Table 4-1 in Chapter 4. This table summarizes air and groundwater monitoring as well as ongoing monitoring in the vadose zone.</p> <p>Hanford Site Radioactive Airborne Emissions in CY 2021 are given in Table 4-2. Performance Monitoring is discussed in each PA’s ASR.</p>
ASR-6	<b>9.2.6 Research and Development</b>	
	<p>R&amp;D, field studies, etc. results should be provided and discussed. See Table 9-8 for information. (9.2.6 Research and Development)</p>	<p>Chapter 5 summarizes all R&amp;D activities with potential to affect the CA, including science and technology tools necessary to accomplish the cleanup mission. Table 5-1 summarizes the R&amp;D documents and potential impacts to the CA.</p>

**Table C-1. Crosswalk of LFRG Review Criteria to Annual Status Report Content**

ID	Review Criteria*	Where Criteria are Met
ASR-7	<b>9.2.7 Planned or Contemplated Changes</b>	
	<p>Planned or contemplated changes (including completion schedules) in disposal facility design, construction, operations, closure, R&amp;D, land use or in technical basis documents (MP, CP, WAC, MonP, Change Control Process) presented in a table following the format in Table 9-11.</p> <p>(9.2.7 Planned or Contemplated Changes)</p>	<p>See responses to ASR-1 and ASR-2.</p> <p>The schedules for the PAs covered by this CA are discussed in Table 1-2. The table indicates what phase (i.e., planning analysis, maintenance) each PA covered by this CA is in and expected completion dates as available (see Section 1.1).</p>
ASR-8	<b>9.2.8 Status of DAS Conditions, Key and Secondary Issues</b>	
	<p>Provide a status update on any DAS conditions and key or secondary issues resulting from an LFRG review of the facility's PA and CA and other technical basis documents (e.g., MonP, CP, etc.). See Table 9-13 for information.</p> <p>(9.2.8 Status of DAS Conditions, Key and Secondary Issues)</p>	<p>The CA has eight Key/Secondary Issues or Disposal Authorization Statement Conditions. These are provided in Table 7-1 along with the initial resolutions schedule date, projected resolution Scheduled date and disposition documentation and date completed. Appendix B in this report provides the status of the current effort to update this CA.</p>
ASR-9	<b>9.2.9 Certifications of the Continued of the Adequacy of the PA, CA, DAS and RWMB</b>	
	<p>The following statement signed by the FEM or designee should be included in the ASR.</p> <p><i>I certify to the best of my knowledge that information in this ASR is true, accurate and complete and that any proposed or implemented changes associated with the PA or other technical basis documents provide a reasonable expectation that the performance objectives/measures identified in DOE O 435.1 will be met.</i></p> <p>(9.2.9 Certifications of the Continued of the Adequacy of the PA, CA, DAS and RWMB)</p>	<p>Section 8.1 contains the certification.</p>

Note: Complete reference citations are provided in Chapter C2 in this appendix.

\*Review criteria are verbatim text from Table 9-15 in DOE-STD-5002-2017, *Disposal Authorization Statement and Tank Closure Documentation*.

**Table C-1. Crosswalk of LFRG Review Criteria to Annual Status Report Content**

<b>ID</b>	<b>Review Criteria*</b>	<b>Where Criteria are Met</b>
ASR	= annual status report	LLBG = low-level burial ground
CA	= composite analysis	MonP = monitoring plan
CERCLA	= <i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>	MP = maintenance plan
CP	= closure plan	PA = performance assessment
CY	= calendar year	R&D = research and development
DAS	= disposal authorization statement	RCRA = <i>Resource Conservation and Recovery Act of 1976</i>
DOE-ORP	= U.S. Department of Energy, Office of River Protection	RWMB = radioactive waste management basis
DOE-RL	= U.S. Department of Energy, Richland Operations	UCAQE = unreviewed composite analysis question evaluation
FEM	= field element manager	UDQE = unreviewed disposal question evaluation
LFRG	= Low-Level Waste Disposal Facility Federal Review Group	WAC = waste acceptance criteria

## C2 References

*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, Pub. L. 107-377 as amended, 42 USC 9601 et seq., December 31, 2002. Available at: <https://www.csu.edu/cerc/researchreports/documents/CERCLASummary1980.pdf>.

DOE O 435.1 Chg 1, 1999, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder>.

Superseded by:

DOE O 435.1 Chg 1 (PgChg), 2007, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C. Available at: <https://www.directives.doe.gov/directives-documents/400-series/0435.1-BOrder-chg1-PgChg>.

DOE/RL-2018-66, 2019, *Hanford Site Groundwater Monitoring Report for 2018*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington. Available at: <https://pdw.hanford.gov/document/AR-03138>.

DOE-STD-5002-2017, 2017, *Disposal Authorization Statement and Tank Closure Documentation*, U.S. Department of Energy, Washington, D.C. Available at: [https://www.standards.doe.gov/standards-documents/5000/5002-astd-2017](https://www.standards.doe.gov/standards-documents/5000/5002-astd-2017/@@images/filehttps://www.standards.doe.gov/standards-documents/5000/5002-astd-2017).

*Resource Conservation and Recovery Act of 1976*, Pub. L. 94-580, 42 USC 6901 et seq. Available at: <https://www.govinfo.gov/content/pkg/STATUTE-90/pdf/STATUTE-90-Pg2795.pdf>.