

ORNL/ER-257



**ENVIRONMENTAL
RESTORATION
PROGRAM**

RECEIVED

FEB 27 1996

OSTI

**Structural Analysis of Underground
Gunit Storage Tanks**

MANAGED BY
LOCKHEED MARTIN ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

UCN-17500 (6 8-95)

MASTER

ENERGY SYSTEMS



SCIENCE APPLICATIONS INTERNATIONAL CORPORATION

contributed to the preparation of this document and should not be considered
an eligible contractor for its review.

Energy Systems Environmental Restoration Program

Structural Analysis of Underground Gunite Storage Tanks

Date Issued—August 1995

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared for
U.S. Department of Energy
Office of Environmental Management
under budget and reporting code EW 20

Environmental Restoration and Waste Management Programs
Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831-6285
managed by
LOCKHEED MARTIN ENERGY SYSTEMS
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED
DLC

TABLE OF CONTENTS

PREFACE	vii
EXECUTIVE SUMMARY	ix
1. INTRODUCTION	1
2. DESCRIPTION OF TANKS	3
2.1 GENERAL DESCRIPTION	3
2.2 EXISTING CONDITION OF THE TANKS	4
2.3 PENETRATION IN THE DOME	4
3. ANALYSES	5
3.1 METHODOLOGY	5
3.2 SEISMIC HAZARD CLASSIFICATION	5
3.3 FINITE ELEMENT MODEL	5
3.4 STRUCTURAL LOADING	6
3.4.1 Static Loads	7
3.4.2 Dynamic Loads	7
3.5 LOAD COMBINATIONS	8
3.6 BOUNDARY CONDITIONS AND ASSUMPTIONS	9
3.6.1 Tank Foundations	9
3.6.2 Structural Integrity	9
3.6.3 Opening in Dome	10
3.7 MATERIAL PROPERTIES	10
3.8 ACCEPTANCE CRITERIA	10
3.8.1 Tensile Stress in the Concrete	10
3.8.2 Compressive Stress in the Concrete	11
3.8.3 Tensile Stress in the Reinforcement	11
4. ANALYSIS RESULTS	13
4.1 STRESSES	13
4.1.1 Dome Top Surface	13
4.1.2 Dome Ring	13
4.1.3 Tankwall	13
4.1.4 Dome Ring Bottom Surface	13
4.1.5 Penetrations on Dome	13
4.2 MAXIMUM STRESSES DUE TO TOTAL LOAD	14
4.3 DISPLACEMENTS	17
4.4 EFFECTS OF HOLES IN DOME	17
4.5 ADDITIONAL DOME LOADS	17
4.6 REDUCTION IN SECTION	17
4.7 STABILITY	18
4.8 STRUCTURAL INTEGRITY	18
5. RECOMMENDATION AND SUGGESTIONS	19
5.1 CORE SAMPLING AND OPENINGS	19
5.2 FINITE ELEMENT MODELING	19

5.3	GROUP BEHAVIOR OF TANKS	19
5.4	ADDITIONAL LOADING ON DOME	20
5.5	SOIL SAMPLING AND TESTING	20
5.6	INSTRUMENTATION	20
5.7	OTHER CALCULATION METHODS	20
6.	REFERENCES	21
APPENDIX A	Calculations	A-1
APPENDIX B	Peer Review Comments and Resolutions	B-1
APPENDIX C	Computer Code Verification	C-1
APPENDIX D	GTSTRU DL Input File	D-1

FIGURES

Fig. ES-1.	Cut-up Tank Section of Finite Element Model	xv
Fig. ES-2.	Dome Opening Locations	xvi
Fig. ES-3.	Maximum Hoop Tensile Stress	xvii
Fig. 1.	Cross Sectional View of Tank	23
Fig. 2.	Section View Through Dome	24
Fig. 3.	Full Cross Sectional View of Tank	25
Fig. 4.	Oak Ridge-Site Specific Response Spectra For Horizontal Rock Motion	26
Fig. 5.	Cut-up Section of Tank	27
Fig. 6.	Finite Element Numbering System	28
Fig. 7.	Dome Opening Locations	29
Fig. 8.	General Tank Section Dimensions	30
Fig. 9.	Stress Distribution of External Tank Surface	31
Fig. 10.	Stress Distribution at Tank Wall and Dome Ring Junction	32
Fig. 11.	Principal Stress Distribution of Tank Internal Surface	33
Fig. 12.	Principal Stress Distribution Around Dome Penetrations	34
Fig. 13.	Stress Distribution of Global Stress S_{xx} Around Dome Penetrations	35
Fig. 14.	Stress Distribution of Global Stress S_{yy} Around Dome Penetrations	36
Fig. 15.	Stress Distribution of Global Stress S_{zz} Around Dome Penetrations	37
Fig. 16.	Maximum Hoop Tensile Stress	38
Fig. 17.	Principal Tensile Stress on Exterior Surface of Wall	39
Fig. 18.	Maximum Tensile Stress Distribution in Ring	40
Fig. 19.	Horizontal Displacement of Wall	41
Fig. 20.	Vertical Displacements of Dome	42

TABLES

Table ES-1.	Maximum stresses of overall tank structure	xviii
Table ES-2.	Maximum stresses at top of wall	ixx
Table 1.	Maximum stresses of overall tank structure	21
Table 2.	Maximum stresses at top of wall	22

PREFACE

The original analysis report on the gunite tank was issued in July 1994 as SAIC-94/1106. During the review process, a computer code validation was performed. A cantilever beam was modeled using the GTSTRUDL program and its eight-node brick "IPSL" finite elements. The result showed that GTSTRUDL significantly underpredicts the beam deflections and stresses for a certain geometry and aspect ratios of the finite elements. To confirm the analysis results, it was considered necessary to check the tank stresses using a different finite element program. In addition, the earth loading on top of the dome has been incorrectly applied. Therefore, the loading was corrected and the analysis was performed using GTSTRUDL and a program named SUPERSAP. There were no significant differences between the results. It was concluded that GTSTRUDL is applicable for this geometry and produced acceptable results. The updated analysis results from GTSTRUDL are reported here and the verification results from SUPERSAP are documented in a revised Appendix C. This work was performed under Work Breakdown Structure 1.4.12.6.1.06.01.01 (Activity Data Sheet 3306).

EXECUTIVE SUMMARY

LOCATION

This report documents the structural analysis of the 50-ft diameter underground gunite storage tanks constructed in 1943 and located in the Oak Ridge National Laboratory (ORNL) South Tank Farm, known as Facility 3507 in the 3500-3999 area. The six gunite tanks (W-5 through W-10) are spaced in a 2×3 matrix at 60 ft on centers with 6 ft of soil cover.

GEOMETRY

Each tank (Figures 1, 2, and 3) has an inside diameter of 50 ft, a 12-ft vertical sidewall having a thickness of 6 in. (there is an additional 1.5-in. inner liner for much of the height), and a spherical domed roof (nominal thickness is 10 in.) rising another 6 ft, 3 in. at the center of the tank. The thickness of both the sidewall and the domed roof increases to 30 in. near their juncture. The tank floor is nominally 3-in. thick, except at the juncture with the wall where the thickness increases to 9 in.

CONSTRUCTION

The tanks are constructed of gunite (a mixture of Portland cement, sand, and water in the form of a mortar) sprayed from the nozzle of a cement gun against a form or a solid surface. The floor and the dome are reinforced with one layer of welded wire mesh and reinforcing rods placed in the radial direction. The sidewall is reinforced with three layers of welded wire mesh, vertical ½-in. rods, and 21 horizontal rebar hoops (attached to the vertical rods) post-tensioned to 35,000 psi stress. The haunch at the sidewall/roof junction is reinforced with 17 horizontal rebar hoops post-tensioned with 35,000 to 40,000 psi stress. The yield strength of the post-tensioning steel rods is specified to be 60,000 psi, and all other steel is 40,000 psi steel. The specified 28-day design strength of the gunite is 5,000 psi.

PENETRATIONS IN THE DOME

Penetrations in the dome were made at different stages. The size, number, and location of the penetrations varies from tank to tank. In one case, five 24-in. and one 30-in. penetrations exist on one tank. This analysis considered a conservative structural model (Figure ES-1) with seven non-symmetrical penetrations (Figure ES-2). The assumed penetrations include one 24-in.-diameter hole in the center, four 24-in.-diameter holes along a 20-ft radius circle, one 30-in.-diameter hole and one 12-in.-diameter holes along a 22-ft radius circle. The actual penetrations are reinforced with concrete pads. For simplicity, the structural model did not include the pads nor any penetrations smaller than 12-in. diameter.

ANALYSIS

Engineering analysis of the tanks in recent years was carried out in 1986 and an additional report on further evaluation of the results was published in 1993. In 1995, a simplified calculation performed by Hanskat reported that the tension in the dome ring reinforcement steel has exceeded the code allowable stresses. The 1986 analysis had a limited scope and, as a result, simplified finite element model of a partial tank was used. The 1995 simplified calculation provided safety factors against buckling but not against tensile failure on the dome ring

which is the controlling failure mechanism. This current report uses 3-D finite elements (eight-node bricks) to model the entire tank (Figure ES-1). The liner inside the wall is observed to have partially deteriorated in two of the tanks (W-5 and W-6) and has limited structural strength. Therefore the liner is not included in the structural model.

STRUCTURAL LOADINGS

Static and dynamic loading are considered in this analysis. Dynamic loading is applied to the structure as equivalent static loading. Loads considered are dead load, static soil pressure, static hydraulic load, tank earthquake load, dynamic seismic soil load, and dynamic seismic hydraulic load.

The scope of this report does not include miscellaneous loads such as equipments on the super structure, occasional live loads, etc. Buoyancy effects analyzed previously by Martin Marietta Energy Systems, Inc. concluded uplift was an unlikely event.

SEISMIC HAZARDS

As a result of a hazard screening, the South Tank Farm was placed in the general hazard category. Therefore, following the guidelines of UCRL-15910, the methodology used is a static-equivalent seismic analysis on a three-dimensional model representing the entire tank. Seven however, the tanks have a high safety factor against buckling in both the dome and the vertical wall. Seismic-induced stresses range from 7 to 12% of the maximum static stresses. The maximum principal compressive stress is 642 psi, which is a low value compared to the allowable compressive stress of concrete having an $f'_c=5000$ psi. The maximum directional tensile and shear stresses, and the maximum principal stresses from three typical sections of the model are presented in Table ES-1. Maximum stresses at the top of the wall are presented in Table ES-2. These typical sections are situated at 0° , 90° , and 180° , with respect to the direction of seismic loading. Total stress was due to static load plus seismic load. Loading case 4 represents the case of earthquake applied to an empty tank. It can be seen that the earthquake increases the stress levels by approximately 10%.

For all loading cases considered, the concrete at the top of the tank wall has a high potential to form horizontal cracks on the exterior face according to the maximum principal tensile stress theory. The vertical reinforcement at the top of the wall is insufficient to satisfy flexural requirements and this region of the tank wall is not in compliance with ACI 318, for resisting moments. However, reinforcement is adequate to withstand the hoop tensile forces in the wall and the dome ring as required by ACI 318, ACI 334, and ACI 344R. Another area not fully in compliance with these ACI codes is a 3-ft wide band at the edge of dome adjacent to the dome ring. This region is noncompliant in that the reinforcement cross section provided is not sufficient, by itself, to resist the tensile load on the gross cross section. However, the concrete tensile stress in this area is smaller than the allowable tensile stress limit for flexure in plain concrete and much smaller than the modulus of rupture, therefore cracking is not expected to occur in this region of the tank dome for the load conditions considered.

Openings in the dome do not induce significant stress concentrations. The maximum principal stress, 524 psi, is high, but less than the maximum principal stress, 689 psi, at the top of the wall. Any additional openings larger than 30-in. diameter may induce higher stresses. Further analysis of openings larger than 30-in. diameter is recommended. Reduction in section at the top of the wall may induce cracks under all loadings. At elevations 2 ft below the top of the wall, a reduction of the wall thickness from 6 in. to 5 in., does not increase the concrete stress beyond the rupture stress limit. At 3 ft below the ring, a 2-in. reduction in wall thickness does not overstress the concrete. Deflections from all loading combinations are less than 0.1 in.

It is the conclusion of this analysis that the gunite tank is structurally stable with respect to the load conditions considered. This analysis shows that the dome shell exhibits a safety factor of 51 against buckling. This factor is considerably larger than safety factor of 4 to 6 recommended by ACI 344-70. The structural stability of the tank dome is, however, dependant on the peripheral confinement provided by the dome ring. The dome ring is primarily subjected to tensile loading which is resisted by embedded reinforcement having a yield strength of 60 ksi. This analysis shows the dome ring reinforcement exhibits a capacity to demand ratio of 1.88 with respect to the recommended ACI 318-89 working stress tensile allowable of 24 ksi for prestressed reinforcement (reinforcement resisting all tension in the cross section). With respect to yield, the ring reinforcement exhibits a capacity to demand ratio of 3.5. The cylindrical wall exhibits a safety factor of 44 against buckling.

Some horizontal cracking is expected to occur in a narrow band of the tank wall just below the dome ring. Cracking will primarily be confined to the exterior surface of the wall. The narrow band at the top of the wall below the dome ring was one of two regions of the tank found not to be in compliance with applicable ACI codes. A 3 ft. wide ring at the edge of the dome adjacent to the dome ring was also found to be non-compliant with respect to ACI 344 requirements for tensile reinforcement. With respect to the former noncompliant finding, it should be noted that many tanks of this type have been designed with a through wall joint in this location (e.g. Fig. 2.5.4.2b ACI 344-70). It is evident that should a through wall crack develop in the subject region of the tank wall, the structural integrity of the tank will be maintained. With respect to the latter, calculations show that the tensile stress level on the gross section of plain concrete in the subject region is so low that the section will not crack and the integrity of the section will be maintained when subjected to the load conditions considered. Noncompliance with respect to applicable codes in these instances clearly does not affect the structural integrity or stability of the tanks. The confinement capability of the tanks may be compromised by a through wall crack below the dome ring, however, controlling the elevation of fluids stored in the tanks administratively will mitigate that potential problem.

Table ES-1. Maximum stresses of overall tank structure (psi)

Type of Stress		Location*	Node	Static and Seismic Loads		Static Load		Ratio**
				Loading Case	Stress (psi)	Loading Case	Stress (psi)	
Directional Tensile and Shear Stresses	Sxx	1	8128	6	542	2	488	1.11
	Syy	5	4071	4	549	1	489	1.12
	Szz	3	8592	4	833	1	781	1.07
	Sxy	6	4071	4	544	1	491	1.11
	Sxz	4	8903	8	453	3	410	1.10
	Syz	6	41	4	523	1	488	1.07
Principal Stresses	Tension	6	4071	4	689	1	621	1.11
	Compression	2	8595	4	642	1	597	1.08
	Tmax	6	4071	4	467	1	420	1.11

NOTES:

Stresses shown above are finite fiber stresses for an uncracked section. Stresses may have been recast in calculations in order to evaluate reinforced cross sections.

- *Locations 1: 30-in. opening, bottom surface
 2: 30-in. opening, middle surface
 3: 30-in. opening, top surface
 4: Edge of dome, bottom surface
 5: Bottom of ring
 6: Top of wall, exterior surface

**Ratio = Stress due to static plus seismic load/stress due to static load

Table ES-2. Maximum stresses at top of wall (psi)

Type of stress at Node 4071		Static and Seismic Loads (Loading Case 4)	Static Load (Loading Case 1)	Ratio*
Directional Tensile and Shear Stresses	Sxx	215	196	1.10
	Syy	200	189	1.06
	Szz	250	249	1.00
	Sxy	544	491	1.11
	Sxz	1	1	1.00
	Syz	7	10	0.70
Principal Stresses	S1	689	621	1.11
	S2	250	249	1.00
	S3	-246	-218	1.13

NOTES:

Stresses shown above are finite fiber stresses for an uncracked section. Stresses may have been recast in calculations in order to evaluate reinforced cross sections.

*Ratio = Stress due to static plus seismic load/stress due to static load.

SUGGESTIONS

The structural integrity of the dome ring is very important. As long as the ring is intact, the tank will not collapse regardless of localized spalling in the vertical tank wall. Presently the ring has a reserve capacity of more than 80% with respect to tensile working stress code allowables and a capacity to demand ratio of approximately 3.5 with respect to ultimate tensile capacity. Provided the ring maintains its integrity, the dome has a safety factor of 51 against buckling for the load conditions considered. The cylindrical wall has a safety factor of 44 (assumes hinges form at the top and bottom of the wall, i.e. worst case boundary conditions). The most likely path to failure is that the stiffening ring becomes overstressed due to additional dome loading or severe reduction of the dome ring reinforcing steel cross section, cracks develop in the dome ring and the tank wall immediately below, followed by large deformations in the dome ring in both radial and circumferential directions causing the dome shell to loose edge constraint, eventually the dome collapse follows. Therefore the integrity of the dome ring must be insured. The following precautions are recommended:

Drilling in or near the ring should be avoided as such activity could cause severe weakening of the structure.

The dome roof should not be subjected to any additional soil or equipment load without engineering evaluation. If cracking in the tank wall below the dome ring is acceptable, the dome will accommodate a good deal of additional load.

Any additional openings larger than 30-in. diameter in the dome should be evaluated on a case-by-case basis.




Fig. ES-1. Cut-up Tank Section of Finite Element Model




Fig. ES-2. Dome Opening Locations




Fig. ES-3. Maximum Hoop Tensile Stress

1. INTRODUCTION

This report documents the seismic analysis of the underground gunite storage tanks located in the South Tank Farm at the Oak Ridge National Laboratory (ORNL). The South Tank Farm, known as Facility 3507, is a storage facility located in the 3500-3999 area of the main plant area of ORNL. This analysis was performed in support of the Gunite and Associated Tanks (GAAT) Treatability Study which is being performed to study the feasibility of various remedial action techniques.

The analysis does not represent the behavior of any specific tank, but rather is considered a typical analysis representing a reasonably conservative behavior of the tanks in general. Physical inspection of the tanks was not possible. Remote inspection (Energy Systems, 1992a) indicates some deterioration of the tank inner liners especially in Tank W-5. Effects of deterioration were accounted for in the mathematical model and calculation.

The hand calculations are attached in Appendix A. The peer review comments and resolutions are included in Appendix B. The SuperSAP computer code verification and selection of the finite elements are attached in Appendix C. The input file for the analysis is attached in Appendix D.

This analysis did not address uncertainties in soil or material properties (e.g. degradation of concrete strength), undocumented stress risers (e.g. irregularities in penetration cross section), or undocumented abrupt changes in cross section (e.g. wall spalling). Some simplification in the math model was required due to model size limitations.

2. DESCRIPTION OF TANKS

Section 2.1 provides a description of the tanks as they were constructed in 1943. Section 2.2 gives a description of the tanks based on information obtained more recently during the Sludge Removal Project in 1981 (Fricke, 1993). Section 2.3 discusses the penetrations in the dome. A second video review of these tanks was made in 1992 (Bechtel, 1992). There has been no apparent deterioration of the tanks in addition to that visible in 1981. The details of the condition of the outside of the shell is not known.

2.1 GENERAL DESCRIPTION

Facility 3507 consists of six inactive below-ground waste storage gunite tanks. All pipelines feeding the tanks have been capped, and the tanks are no longer part of the active LLLW system. They were used to collect and store the liquid portion of the radioactive and/or hazardous chemical wastes produced as part of normal facility operations at ORNL. As the tanks were taken out of service, the liquid waste from these tanks was pumped out, although some residual liquid and sludge may be left in them.

The six gunite tanks (W-5 through W-10), originally constructed in 1943, are located at 60-ft centers in a 2×3 matrix in the South Tank Farm (Ref. UCC-ND Drawing C3E-20539 X006). A limited amount of information is available concerning details of tank construction. The following data are obtained from Fricke (1986, 1993). Figures 1 and 2 show the major details of the tanks; these figures are taken from UCC-ND drawings E-56866 and D-56867, respectively. Each tank has an inside diameter of 50 ft, a 12-ft vertical sidewall with a nominal thickness of 6 in. (there is an additional 1.5-in. inner liner for much of the height), and a spherical domed roof (nominal thickness is 10 in.) rising another 6 ft, 3 in. at the center of the tank. The thickness of both the sidewall and the domed roof increases to 30 in. near their juncture. The tank floor is nominally 3-in. thick, except at the juncture with the wall where the thickness increases to 9 in.

The tanks are constructed of gunite (a mixture of Portland cement, sand, and water in the form of a mortar) sprayed from the nozzle of a cement gun against a form or a solid surface (Fricke, 1986). The floor is reinforced with one layer and the dome with two layers of 4 × 4 – W2.1 × W2.1 welded wire mesh and 3/8-in.-diameter reinforcing rods placed in the radial direction. The sidewall is reinforced with three layers of welded wire mesh, vertical 1/2-in. rods, and 21 horizontal rebar hoops (attached to the vertical rods) post-tensioned to 35,000 psi stress. The haunch at the sidewall/roof junction is reinforced with 17 horizontal rebar hoops post-tensioned with 35,000 to 40,000 psi stress. The yield strength of the post-tensioning steel rods is specified to be 60,000 psi, and all other steel is 40,000 psi steel. The specified 28-day design strength of the gunite is 5,000 psi (Union Carbide drawing E-56866). Each tank has approximately 8,000 ft² of wire mesh and over six tons of reinforcing steel rods within the concrete (Fricke, 1986).

Each tank sits on an individual concrete pad. The thickness of soil between tank foundation and top of rock varies from 0 (near Tank W-6) to 14 ft (near Tank W-9). The concrete pad has a raised rim that forms a saucer (Figure 3) which directs drainage and any leakage into a dry well and drain system. The tank sidewall has a 3-ft-thick backfill of crushed stone forming a French drain and providing for passage of groundwater drainage and any leakage to the dry well and drain system. The rest of the surrounding soil is composed of compacted available fill, and clay. The tank domes are covered with 6 ft of compacted earth.

2.2 EXISTING CONDITION OF THE TANKS

The existing condition of the tanks is not well known since a hands-on inspection is not permitted. The details of the condition of the outside of the shell are not known.

As part of the Sludge Removal Project (Fricke, 1993): 1) Schmidt Rebound Hammer readings, to estimate concrete strength, were taken of the dome of all tanks except for W-9, 2) core samples were taken from the dome of Tanks W-5 and W-10 at various locations and cylinder strength tests performed on the cores, and 3) a television camera was lowered into each tank where black and white videotapes and photographs of the interior of the tanks were made. The Schmidt Rebound Hammer test results indicate that the concrete strength (for the dome) varies between 4,700 and 6,400 psi. The cylinder tests of the cores from Tanks W-5 and W-10 show concrete strengths consistently higher than those obtained from the Schmidt Hammer tests; the cores produce strengths between 5,500 and 16,000 psi (10,200 psi average). Since the construction techniques were similar, it is reasonable to assume the walls have the same strength as the dome. A compressive strength of 5,000 psi for the concrete was specified in the design drawing and is assumed for this analysis.

It is obvious from the photographs and the videos of the tank interiors that the existing condition of the tanks varies (Fricke, 1993). Tank W-5 is in the worst condition of the six tanks; parts of its inner 1.5-in. liner appear to be so thin that, in some areas, the wire mesh is exposed; in some areas, the wire mesh has folded back on itself (probably at overlap boundaries where the inner liner is thin). There are also indications that there may be more extensive deterioration of the walls of Tank W-5, such as areas of discoloration indicating possible holes or erosion. The past history of the six tanks indicates that Tank W-5 has been used more extensively as a holding tank for chemicals and has been, on several occasions, exposed to highly acidic liquids, which probably accounts to a large degree for its present condition. Tank W-6 shows similar, but less deterioration. The video tapes and photographs of the remaining four tanks do not reveal deterioration like those found in Tanks W-5 and W-6. None of the other tanks have exposed wire mesh, holes, or discoloration (Fricke, 1993).

2.3 PENETRATION IN THE DOME

Penetrations in the dome were made at different times in the life of each tank. The size, number, and location of the penetrations varies from tank to tank. In one case, five 24-in. and one 30-in. penetrations exist on one tank. This analysis used a conservative structural model with seven nonsymmetrical penetrations. The assumed penetrations include one 24-in. diameter hole in the center, four 24-in. diameter holes along a 20-ft radius circle, one 30-in. diameter hole, and one 12-in. diameter hole along a 22-ft radius circle. The actual penetrations in the field are reinforced with concrete caisson of additional thickness and diameter. For simplicity, the finite element model did not include the caisson nor any penetrations smaller than 12-in. diameter.

3. ANALYSES

This section discusses the methods used in the analysis of the typical gunite tank. Section 3.1 summarizes the methodology, while Section 3.2 discusses the seismic hazard level used in this analysis. Sections 3.3 and 3.4 describe in detail the finite element model and the structural loads applied to the model. Section 3.5 discusses the various loading combinations required to describe the state of stress in a tank accurately.

3.1 METHODOLOGY

The finite element technique was used to perform this study. This approach was selected for modeling the tanks and the loads because it can easily handle complex structures with varied material properties, geometric configurations, and boundary conditions. The computer program selected was GTSTRUDL (GTICES Systems Laboratory, 1991) which is available on the ORNL-RISC computer workstation.

A nonlinear soil-structure interaction (SSI) is beyond the scope of this study. Therefore, only the tank structure is included in the mathematical (three-dimensional finite element using solid elements) model of the system. An equivalent static analysis was performed for the evaluation of the dynamic effects of the surrounding soil.

3.2 SEISMIC HAZARD CLASSIFICATION

The only non-standard industrial hazards associated with the South Tank Farm are a radiation source hazard and a toxic hazard associated with the radioactive liquid waste. Resulted from a hazard screening (Energy Systems, 1992b), the South Tank Farm was placed in the general hazard category. The DOE seismic requirement (UCRL-15910) for a general hazard category structure is to withstand an earthquake with return period of 500 years using the static-equivalent seismic analysis procedures specified in Uniform Building Code (UBC 1994). As shown in Figure 4, the Oak Ridge Site Specific rock PGA for a 500-year return period is 0.08g (Beavers and Hunt, 1994). To account for different site geology and soil characteristics, UBC code specifies a soil and site correction factor S established from substantiated geotechnical data. In locations where the soil properties are not known in sufficient detail to determine the soil profile type, as is the case in this analysis, UBC codes recommends a soil profile factor of $S = 1.5$. This analysis conservatively used a PGA of 0.14g. The tank structure is therefore subjected to static and seismic (dynamic) loads induced by a 0.14-g horizontal and a 0.09-g vertical ground accelerations. (The vertical earthquake component is typically defined to be two-thirds of the horizontal component.)

3.3 FINITE ELEMENT MODEL

The gunite tanks are upright cylindrical tanks having domed roofs and buried 6 ft underground. A three-dimensional model of the full-size tank, as shown in Figure 5, was constructed of eight-node elements using GTSTRUDL's tridimensional "IPSL" elements. Since local stress conditions around the various openings in the tank dome are required by Energy Systems, the entire tank has been modeled. The bottom of the tank was not modeled completely as it contributes little to the stiffness of the tank. The tank wall and the modeled portion of the tank floor were modeled one layer thick. Because of uncertain structural strength and integrity, the inner liner of the wall was assumed to provide no additional structural capacity and was not included in the model.

The dome was modeled as being two layers thick, as shown in Figure 6, with the bottom of the upper layer connected to the lower layer via rigid space trusses (mathematically equivalent to a gap element that transfers only compressive axial force to the lower dome). The dome was modeled in two layers because the original 5-in.-thick dome was thickened after original construction by the addition of a 5-in.-thick over-layer. Available drawings (see list at the end of Attachment A) indicate that a cold joint exists between the two dome layers. The two 5-in. layers of dome may behave like a single 10-in. layer of dome, but uncertainties remain, and it is conservative to assume the two 5-in. layers configuration. The model consists of 8,424 elements, 2,392 rigid links and 16,120 joints. The model is axi-symmetric except for seven openings in the dome (as shown in Figures 7). The tank model is restrained in all translational directions at nodes along the bottom face of the tank floor. All other nodes are free to translate and rotate in three directions.

The material property of the finite element represents uncracked concrete strength. the strength of the reinforcing steel is not included in the element but considered in hand calculations after the stresses in the finite element are reported by the computer. The tank floor, wall, and dome elements are assumed to be homogenous and isotropic (ACI Committee 344, 1981). Wall elements are modeled as being 6-in. thick, dome elements as being 5-in. thick (each layer), and floor elements as being 3-in. thick. Floor elements within a 4-ft band near the wall thicken in the radial direction from 3 in. to 9 in. at the inside face of the tank wall. The stiffening ring at the edge of the dome was represented by a cross section of 15 finite elements. The finite element model is axi-symmetric except the seven openings in the dome are not located axi-symmetrically. See Figure 8 for detailed configuration.

The selection of the 8-node elements over 20-node elements was based on computer capacity, computing time, accuracy of results, and effort required to interpret the results. Detailed assessment of element applicability and accuracy is reported in Appendix C. The most critical stresses used in the analysis are the maximum principal stress and S_{yy} . The maximum principal stress was used for screening purpose. The direction stress S_{yy} is used for the evaluation of vertical wall strength below the haunch. These stresses are almost identical between two programs. It is concluded the results predicted by GTSTRUDL are adequate and compatible with the results obtained from the program SuperSAP.

The model consists of 104 identical pie segments representing the entire tank. Earthquake induced dynamic soil and fluid pressures were treated as static loading conditions. Soils were considered as loads, not as a part of the finite element model. Group behavior due to tank-to-tank interaction during a seismic event was not considered in the model, but was later evaluated (see Appendix A) and found to add only 3% to the maximum combined stresses.

3.4 STRUCTURAL LOADING

Static and dynamic loading considered in this analysis. Dynamic loading is applied to the structure as equivalent static loading. Loads considered are dead load (DL), static soil pressure (H_s), static hydraulic load (F_s), post-tensioning in reinforcing steel (T_s), tank earthquake load (E), dynamic seismic soil load (H_d), and dynamic seismic hydraulic load (F_d).

The scope of this report does not include miscellaneous loads such as equipment on the super structure, occasional live loads, etc. The uplift from buoyancy effects was analyzed previously by Energy Systems and was determined to be unlikely.

3.4.1 Static Loads

Static loads applied to the structure include:

Dead Load (DL) Structure self-weight is accounted for by GTSTRUDL. The unit density of the gunite (0.0868 lb/in³) is input and GTSTRUDL computes unit weights by applying the density to the element volume at 1 g. Element weight is distributed to structural joints in proportion to tributary volume.

Static Soil Pressure (H_s) Consists of dome pressure (H_{SD}) and wall pressure (H_{SW}) :

Dome Pressure (H_{SD}). The 6-ft.-thick soil overburden on the dome is applied to the model as a surface pressure on dome elements. Soil dome pressure is computed based on a unit weight of soil of 110 lb/ft³. The soil overburden is applied in the vertical (global) direction as an element surface load.

Wall Pressure (H_{SW}). Lateral at-rest earth pressures are applied externally and normal to the tank walls. The load diagram is trapezoidal, being 1.604 psi at the top of the tank wall and 5.306 psi at the bottom.

Hydrostatic Pressure (F_s) Hydrostatic pressures from stored fluids are applied to the interior face of the tank wall based on a fluid having a specific gravity of 1.25 (Fricke, 1986) for the full (11-ft fluid depth) and the half full (6.2-ft fluid depth) conditions. Hydrostatic loading is applied internally and normal to the tank walls. Hydrostatic loading is investigated for both the full (F_s) and half-full condition ($F_{s/2}$).

Post-Tensioning (T_s) The hoop reinforcement in the tank walls and the confinement ring at the edge of the tank dome are fabricated from steel with a 60-ksi yield. (ACI Committee 344,1981) recommends that, unless precise methods are used to determine prestress losses, 32-ksi losses should be assumed (Friction loss was compensated in the construction stage to achieve the design prestress). Fricke (1986) predicts that 90% of pretension has been lost. This analysis assumes that all prestress has been lost.

3.4.2 Dynamic Loads

The dynamic loads considered include seismically induced soil pressure, hydrodynamic pressure, seismically induced sloshing, and structural inertial forces. Dynamic loading is applied to the tank model as a set of equivalent static loads. In each case, the equivalent static loads are derived from the estimated peak dynamic loading. The tank is very stiff with respect to lateral loading (height to diameter ratio ≈ 0.25); similarly, in the vertical direction the walls and the dome (as a result of its geometry and applied load distribution) are also stiff. This analysis accounts for that stiffness by neglecting dynamic amplification and damping effects of the structure.

Inertial Loads (E) Equivalent static loading is determined by multiplying model element mass by Design Basis Earthquake (DBE) peak ground accelerations. In reality, the inertia load (E) acts in the opposite direction to the dynamic soil loads (H_D) discussed below. In this analysis, both inertia loads and dynamic soil loads are conservatively combined as if both loads acted together in the same direction.

Dynamic soil loading (H_D) Dynamic soil loading is determined as though the tank were a retaining wall. The methods of Prakash (1981) are used to determine lateral dynamic pressures. Dynamic soil pressures also act along the direction of seismic motion and are distributed to the structure according to proportion of mass acting on each element in that direction. The resulting pressure bulb in plan is crescent shaped at a given elevation above the tank. Vertically, the dynamic earth pressure distribution is non-linear. The resultant in a typical vertical slice is located 0.6 of the wall height (h) from the bottom of the tank. This analysis uses an equivalent trapezoidal stress distribution. Horizontal pressures are distributed over the wall height with pressure intensities in a vertical slice being zero at the bottom, increasing linearly to a maximum value at $0.5h$, remaining constant to $0.8h$, then decreasing linearly to 0 at the top of wall. The resultant from this equivalent distribution is located at $0.56h \approx 0.6h$.

Dynamic soil pressures on the "leeward" side of tank are neglected. The 6-ft-thick soil blanket is treated as dead weight and accelerated vertically at peak ground acceleration.

Hydrodynamic Loads (F_D) When subjected to random vibrations, confined fluids develop inertial forces due to ground acceleration and sloshing forces due to wave action. This analysis uses the methodology of Newmark (1971) to develop equivalent static loadings for both loading types. Newmark's methodology determines the magnitude of the equivalent static forces and their location with respect to the bottom of the tank. These equivalent static loadings are applied to the interior face of the tank shell as a surface pressure on a horizontal band of elements at the elevation of the force center determined by the Newmark method. Distribution of the equivalent load as an equivalent localized pressure is conservative (local stress levels near the loaded elements are overestimated), but is computationally expedient.

Hydrodynamic fluid pressure acts along the direction of seismic motion. The hydrodynamic pressure in each pressure band is distributed to the face of each tank wall (band) element in proportion to the fluid mass acting dynamically on the element. Because of the geometry of the circular tank wall, the resulting pressure bulbs are crescent shaped. Pressures are maximum at the center of the pressure band (e.g., at the 0° azimuth of the tank in plan), tapering off to zero at the pressure band extremes 90° and 180° azimuths). Hydrodynamic loading is investigated for both the full (F_{D+}), half-full condition ($F_{\frac{1}{2}D+}$) and in-phase with the earthquake soil pressure and for (F_{D-}) and ($F_{\frac{1}{2}D-}$) out-of-phase (against) the earthquake soil pressure direction.

When the inertia force and the sloshing force are in phase, the forces exert on the same direction against the same wall. When the forces are out-of-phase, they were exerted on opposite sides of the tank wall. Observation indicates that the total loads on the tank wall are more conservative when the forces act on the same side of the tank wall. In this analysis, the inertia force is added to the sloshing forces as if they act in-phase with each other.

3.5 LOAD COMBINATIONS

The purpose of this analysis is to determine whether the tank has the capacity to resist the DBE for the ORNL site. During a seismic event the probability that the hydrodynamic and dynamic soil loading will occur simultaneously is remote. Structural response to these loadings should be combined probabilistically (e.g., Square

Root of the Sum of the Squares). This analysis conservatively combines responses algebraically. Loading combinations analyzed by the GTSTRUDL program include:

Static Load Cases:

1. $DL + H_{SD} + H_{SW}$ Empty Tank
2. $DL + H_{SD} + H_{SW} + F_S$ Full Tank
3. $DL + H_{SD} + H_{SW} + F_{\frac{1}{2}S}$ Half-full Tank

Dynamic Load Cases:

4. $DL + H_{SD} + H_{SW} + E + H_D$ Empty Tank + Earthquake
5. $DL + H_{SD} + H_{SW} + E + H_D + F_S + F_{D+}$ Full Tank (in-phase) + Earthquake
6. $DL + H_{SD} + H_{SW} + E + H_D + F_S + F_{D-}$ Full Tank (out-of-phase) + Earthquake
7. $DL + H_{SD} + H_{SW} + E + H_D + F_{\frac{1}{2}S} + F_{\frac{1}{2}D+}$ Half Tank (in-phase) + Earthquake
8. $DL + H_{SD} + H_{SW} + E + H_D + F_{\frac{1}{2}S} + F_{\frac{1}{2}D-}$ Half Tank (out-of-phase) + Earthquake

where:

- DL = tank structural self weight
- H_{SD} = static soil top pressure from earth over dome
- H_{SW} = static soil lateral pressure from earth adjacent to tank wall
- E = tank structural force induced by earthquake
- H_D = dynamic soil loading
- F_S = hydrostatic liquid pressure of full tank
- $F_{\frac{1}{2}S}$ = hydrostatic liquid pressure of half-full tank
- F_{D+} = hydrodynamic liquid pressure of full tank that is in-phase with the earthquake
- $F_{\frac{1}{2}D+}$ = hydrodynamic liquid pressure of half-full tank in-phase with the earthquake
- F_{D-} = hydrodynamic liquid pressure of full tank that is out-of-phase with the earthquake
- $F_{\frac{1}{2}D-}$ = hydrodynamic liquid pressure of half-full tank out-of-phase with the earthquake

3.6 BOUNDARY CONDITIONS AND ASSUMPTIONS

3.6.1 Tank Foundations

The soil boring log (Geotech, 1978) reveals that the soil layer beneath the tanks varies from 0- to 14.5-ft thick. It is very unlikely that fill concrete extends 14.5 ft. below the tank bottom. This analysis evaluates the behavior of the tanks in general. All tanks are considered as supported on soil. In accordance with the methodology of the Uniform Building Code (UBC) and this assumption a higher value, 0.14g, of the peak ground acceleration was used in this analysis.

3.6.2 Structural Integrity

Video inspection shows deterioration of concrete walls in Tanks W-5 and W-6 (Bechtel, 1992; Energy Systems, 1992a). The domes are in good condition. For the finite element analysis, wall section thickness without the inside liner is used. Then, evaluation of the wall sections with further deterioration is hand calculated.

3.6.3 Openings in Dome

Openings in dome vary from 3/8-in.-diameter small pipe penetrations to 30-in.-diameter manholes. The number and location of the openings are not uniform in all tanks (Appendix A). A configuration of one 30-in., five 24-in., and one 12-in. openings is used (Figure 7). All smaller openings (3/8 in. to 6 in.) are ignored; stress concentration around smaller openings is assumed not to be a problem.

3.7 MATERIAL PROPERTIES

f'_c = 5,000 psi, compressive strength of concrete

f_y = 40,000 psi, yield strength of non-prestressed reinforcement

f_{py} = 60,000 psi, yield strength of prestressed reinforcement

f_t = 18,000 psi, allowable tensile stress in non-prestressed reinforcement for static loadings with 33% increase for static loading plus seismic loading

f_c = 1,900 psi, allowable compressive stress of concrete

f_r = 300 psi, concrete tensile stress limit in terms of maximum principal tensile stress (S_1)

The yield strength of the post-tensioning steel f_{py} is specified to be 60 ksi in the original design. The steel was tensioned to 30 to 40 ksi. The stress loss can be as high as 32 ksi (ACI Committee 344, 1981). The post-tensioning steel behaves essentially as regular steel, assuming loss of the entire pre-stressing capability.

3.8 ACCEPTANCE CRITERIA

The underground reinforced gunite tank is evaluated as a shell structure. There is no record indicating the tank has been exposed to elevated temperature nor will be subjected to temperature higher than 150° F. Guiding criteria are from the work of ACI Committees 344 (1981& 1970), 318 (1989), and 334 (1982). High tensile stress areas in concrete are determined by the maximum principal tensile stress theory. Von Mises criterion was also considered, but it was dropped because the Von Mises stresses were driven by a large compression value, and not tension.

The acceptance criteria used in this analysis are based on the working strength design (WSD) design philosophy for design of reinforced concrete (ACI Committee 334 (1982). WSD is the reinforced concrete design criterion in general use during the time in which the tank was constructed.

Crack potential of the shell is determined by comparing computed maximum concrete tensile stresses to the tensile stress limit of concrete.

3.8.1 Tensile Stress in the Concrete

In this analysis, allowable tensile capacity for the comparison with principal tensile stress is taken as the concrete tensile stress limit recommended by Chen (1982) viz., $f_t = 4\sqrt{f'_c}$, or approximately 300 psi. This tensile stress is only used as a screening criteria to determine whether a cross section is prone to cracking.

3.8.2 Compressive Stress in the Concrete

The compressive stress in concrete is limited to the WSD-bearing stress allowable for bearing on the full cross section, i.e., $0.38f_c$ or 1900 psi (ACI 344-70).

3.8.3 Tensile Stress in the Reinforcement

Ultimate tensile capacity is generally limited to the yield strength (F_y) of that grade of steel from which the reinforcement is fabricated. ACI Committee 344 (1981), however, suggests that the allowable tensile stress of the non-prestressed steel be taken as 18,000 psi with 33% increase for seismic loadings regardless of yield stress. The rationale for this seemingly non-conservative treatment of reinforcement is that flexure is not the primary behavior in thin shells. Because of the geometry of the shell and the load distribution on the shell, stresses in shell structures are generally compressive or tensile (ACI Committee 318, 1989). ACI 344 (1981) and ACI 334 (1982) recommend that tension in shell structures be carried entirely by the reinforcement and that the reinforcement be sized accordingly. The low allowable stress is conservative for sizing steel in pure tension, however, in flexural situations sizing steel according to this guidance can ultimately lead to brittle behavior. Shell structures generally do not exhibit a large degree of flexural behavior (ACI Committee 334, 1982; ACI Committee 344, 1981; Billington, 1982). The gunite tank in question exhibits bending behavior at the top of the cylindrical wall.

For prestressed reinforcement, the allowable tensile stress is taken as 24,000 psi with 33% increase for seismic loadings.

4. ANALYSIS RESULTS

This section discusses the stresses, displacements, effects of holes in the dome, permissible overloads on top of the dome, permissible reduction in the wall section, tank stability, and structural integrity.

4.1 STRESSES

Of all the load cases considered, the empty tank during earthquake (load case 4) (with no internal hydrostatic pressure to provide counterbalance force to resist the external pressure from the soil) caused highest stress in the tank. The maximum principal stress distribution plot of tank top surface for load case 4 is shown in Figure 9. The stresses for different portions of the tank are discussed in the following paragraphs.

4.1.1 Dome Top Surface

The center portion of the dome is in compression. The maximum principal compressive stress is 642 psi (at midsurface not visible from the plot), which is a low value compared to the allowable compressive stress in concrete (1,900 psi). No further evaluation of compressive stress is needed. There is no significant stress increase near the hole openings. The perimeter of the dome is in tension with stresses less than 150 psi.

4.1.2 Dome Ring

The detailed dome ring stress distribution of Figure 9 is magnified in Figure 10. The dome ring is in tension with stresses ranging from less than 250 psi (in Figure 9) at the top surface to 350 psi at the bottom of the ring (in Figure 10), with an average tensile stress of about 300 psi. The highest principal stress above 650 psi occurs, in a highly localized region viz., at the junction between the dome ring and the top of the wall. The stress decreases very rapidly as the location drops below the dome-wall junction.

4.1.3 Tank wall

As shown in Figure 9, the tank wall is in compression primarily at locations four feet below the top ring-wall junction. The bottom junction with the floor displays slight tensile stress, less than 150 psi, due to flexure caused by lateral earthquake motion.

4.1.4 Dome Ring Bottom Surface

As shown in Figure 11, the center portion of the dome is in compression. Similar to the dome top surface, at locations closer to the edge of the dome, the stresses become tensile. The principal stresses increase to about 200 psi.

4.1.5 Penetrations on Dome

The close-up view of stress distribution around the holes shown in Figure 11 is magnified in Figure 12. The stresses are intensified at the edges of the penetrations. The stress increases around the hole intensify more rapidly at hole locations closer to the dome perimeter (dome ring). The stresses at the bottom edge surface of hole E increase from less than 100 psi to more than 250 psi. The Inner surface of hole E has stress well above 300 psi. Figures 13, 14, and 15 depict the global stress of S_{xx} , S_{yy} , and S_{zz} respectively. The stress intensification around the holes influences only areas within approximately 1.5 diameters of the hole. It can

be seen that when additional holes are drilled, the impact on dome structural integrity can be minimized if the holes are spaced at least three diameters away from other hole center and one diameter away from the dome ring.

4.2 MAXIMUM STRESSES DUE TO TOTAL LOAD

Maximum stresses due to static and seismic loads are presented in Table 1. The directional stresses for node 4071 of element 2126 where stress is maximum are show on page 73 of Appendix A.

For all loading cases, concrete at the top of the wall has a high potential to form horizontal cracks on the exterior surface according to the maximum principal tensile stress theory. The vertical reinforcement at the top of the wall is not in compliance with ACI codes for resisting moments. However, reinforcement is adequate to withstand hoop tensile forces in the wall, dome ring, and stresses in most of the dome as required by ACI-318, ACI-334, and ACI-344. Another area not fully in compliance with the ACI codes on the requirement of reinforcement is the 3-ft band at the edge of dome; however, the concrete tensile stress in this area is relatively low failure is not expected to occur. Figures 16 through 18 show the distribution of stresses.

Table 1. Maximum stresses of overall tank structure (psi)

Type of Stress		Location*	Node	Static and Seismic Loads		Static Load		Ratio**
				Loading Case	Stress (psi)	Loading Case	Stress (psi)	
Directional Tensile and Shear Stresses	Sxx	1	8128	6	542	2	488	1.11
	Syy	5	4071	4	549	1	489	1.12
	Szz	3	8592	4	833	1	781	1.07
	Sxy	6	4071	4	544	1	491	1.11
	Sxz	4	8903	8	453	3	410	1.10
	Syz	6	41	4	523	1	488	1.07
Principal Stresses	Tension	6	4071	4	689	1	621	1.11
	Compression	2	8595	4	642	1	597	1.08
	Tmax	6	4071	4	467	1	420	1.11

NOTES:

Stresses shown above are finite fiber stresses for an uncracked section. Stresses may have been recast in calculations in order to evaluate reinforced cross sections.

- *Locations 1: 30-in. opening, bottom surface
 2: 30-in. opening, middle surface
 3: 30-in. opening, top surface
 4: Edge of dome, bottom surface
 5: Bottom of ring
 6: Top of wall, exterior surface

**Ratio = Stress due to static plus seismic load/stress due to static load

Table 2. Maximum stresses at top of wall (psi)

Type of stress at Node 4071		Static and Seismic Loads (Loading Case 4)	Static Load (Loading Case 1)	Ratio*
Directional Tensile and Shear Stresses	Sxx	215	196	1.10
	Syy	200	189	1.06
	Szz	250	249	1.00
	Sxy	544	491	1.11
	Sxz	1	1	1.00
	Syz	7	10	0.70
Principal Stresses	S1	689	621	1.11
	S2	250	249	1.00
	S3	-246	-218	1.13

NOTES:

Stresses shown above are finite fiber stresses for an uncracked section. Stresses may have been recast in calculations in order to evaluate reinforced cross sections.

*Ratio = Stress due to static plus seismic load/stress due to static load.

4.3 DISPLACEMENTS

All displacements are small. Displacements are listed below and are illustrated in Figures 19 and 20. Although temperature change and shrinkage effects are not included in the analysis, these small displacements indicate that no further evaluation is needed. They also reveal that monitoring the displacements of the dome will not give adequate indication of any potential overall structural failure.

	Maximum Displacement (in.)	Location	Element	Node	Loading Combination
Vertical	0.093	Center of dome	58	152	5
Horizontal	0.023	Top of wall	20	41	5

4.4 EFFECTS OF HOLES IN DOME

The maximum principal tensile stress around the 30-in. manhole is 316 psi. The stress is not high compared to other locations. It is reasonable to conclude that any additional openings smaller than 30-in. diameter and not located within three diameters of another opening or the edge of the dome ring can be made in the dome without inducing stress concentration problems (Timoshenko and Goodier, 1951). Any openings larger than 30-in. diameter should be evaluated on a case-by-case basis.

4.5 ADDITIONAL DOME LOADS

Additional soil or equipment load on the dome may cause horizontal cracks on the exterior surface of the wall in a narrow band just below the dome ring. However, stresses exceeding the cracking strength of the concrete only exist in localized areas. The stability of the tank is not threatened since the stresses in the remainder of the tank wall and the dome ring are not high.

Further analysis should be performed to determine the effects of additional soil load and large concentrated loads on the dome (e.g., platform columns and footings).

4.6 REDUCTION IN SECTION

The 1.5-in. gunite liners on the interior surface of the wall in Tanks W-5 and W-6 show some degree of spalling, patches of welded mesh wires are exposed. Inspection did not show any deterioration in other tanks.

Deterioration at the top of the wall can be a problem. After exposure to the chemicals, the quality of gunite becomes uncertain. The maximum principal tensile stress, already at the code stress limits, may be intensified and additional cracking may occur. No reduction of the wall thickness in the top 2 ft is desirable. A reduction of 1 in. is acceptable for the portion of the wall 2 ft below the top. If the section reduction is located at 3 ft or more below the top of the wall, then a reduction of 2 in. in the wall thickness is acceptable.

4.7 STABILITY

This analysis shows that the dome shell exhibits a safety factor of 51 against buckling. This factor is considerably larger than safety factor of 4 to 6 recommended by ACI 344-70. The structural stability of the tank dome is, however, dependant on the peripheral confinement provided by the dome ring. The dome ring is primarily subjected to tensile loading which is resisted by embedded reinforcement having a yield strength of 60 ksi. This analysis shows the dome ring reinforcement exhibits a capacity to demand ratio of 1.88 with respect to the recommended ACI 318-89 working stress tensile allowable of 24 ksi for prestressed reinforcement (reinforcement resisting all tension in the cross section). With respect to yield, the ring reinforcement exhibits a capacity to demand ratio of 3.5. The cylindrical wall exhibits a safety factor of 44 against buckling.

4.8 STRUCTURAL INTEGRITY

It is the conclusion of this analysis that the gunite tanks are structurally sound and are adequate to perform the functions they were designed for. The structural stability of the tank dome is dependant on the integrity of the dome ring. For the load conditions considered the dome ring exhibits a capacity to demand ratio of 1.88 with respect to working stress limits and a demand capacity ratio of approximately 3.5 with respect to ultimate strength limits.

The hoop tension capacities in both the ring and cylindrical wall are more than adequate to resist the loads considered by this analysis.

Vertical tensile stresses at the top of the wall on the exterior face are high and reinforcement is not adequate to prevent surface cracking. The interior face of the wall in this region of the tank wall is in compression and should prevent both in and out leakage of liquids at this level. The tank will not loose its structural stability even if plastic hinges are formed along the top of the wall below the dome ring.. Historically, many tanks have been constructed with structural hinges between the dome and wall and have performed satisfactorily.

5. RECOMMENDATION AND SUGGESTIONS

These recommendations are presented as guidelines for future studies of the tanks and to reduce the chances of accidents during work in the area of the tanks.

5.1 CORE SAMPLING AND OPENINGS

Core samples should not be taken from the dome inside the three foot wide circumferential band adjacent to the dome ring or within three penetration diameters of an existing penetration. Core samples should not be taken from the wall in the two foot deep circumferential band adjacent to and immediately below the dome ring. Cores should not be taken from any location in the dome ring cross section. The integrity of the thickened ring must be maintained to prevent an overall structural failure.

Core samples may be from all other areas of the tank, however, main reinforcement steel should not be cut without approval of the cognizant engineer.

5.2 FINITE ELEMENT MODELING

For future analysis, a finer grid may be used to model the top 3 ft of the wall and in the areas within 3 ft of the dome edge where the high stresses exist. The finer grid will allow the evaluation of reduced thickness in the deteriorated portions of the wall.

A dynamic SSI analysis, if desired, can be performed on a 2-D slice of the tank and surrounding soils. A 3-D dynamic SSI analysis can be performed on a coarse-grid, simplified model in light of limited computer capability.

5.3 GROUP BEHAVIOR OF TANKS

The 50-ft tanks in the South Tank Farm are located 60 ft apart, center-to-center, and thus the clear distance between tanks is less than 10 ft. The behavior of a tank is modified by adjacent tanks. Different assumptions are made about soil and tank conditions when a single tank is considered than are made when a group of closely spaced tanks are considered. This analysis performed a limited investigation based on a study of the behavior of a group of tanks (Xu et al. 1994). The study found that the maximum stress increase due to tank-to-tank interaction is about 3% over the combined stress of a single tank and does not change the overall structural assessments. However, it is suggested that this phenomenon especially for groups of concrete tanks, be further investigated.

5.4 ADDITIONAL LOADING ON DOME

The dome roof should not be subjected to any additional soil or equipment load without engineering evaluation. Limited additional loads will cause cracking below the dome ring before buckling occurs, if the cracked tank can still meet the functional requirements.

5.5 SOIL SAMPLING AND TESTING

The existing soil boring log gives only limited information on soil; consequently, only conservative assumptions are used in the current analysis.

Standard Penetration Test (SPT) with blow counts, ground water level information, and lab index testing are all required for any important engineering evaluation.

If SSI analysis is attempted, then some additional lab testing of undisturbed soil samples is needed.

5.6 INSTRUMENTATION

It would appear to be ineffective to monitor the deflections of the dome for the detection of impending collapse of the tanks. The analysis shows that deflections are very small under all loading conditions. Monitoring the circumferential displacement or strain of the dome ring will be an effective method to predict impending dome failure.

Video inspection of the interior of the tank, concentrating on the areas near the top of the wall, offers the best chance for detecting structural deterioration.

5.7 OTHER CALCULATION METHODS

A hand calculation on the tank stress was performed by Hanskat (1995) based on design formula in ACI 344 (1988). The tensile stress of the dome ring reinforcement was reported to have exceeded the code-allowable stress of 32,000 psi. This method served well as a conservative design tool and provided favorable comparison of the finite element analysis. The overly conservative design approach does not provide sufficient information about the factor of safety needed to assess the existing dome-ring stress condition under current loads. The calculated safety factors against tank buckling are consistent with the finite element results.

6. REFERENCES

- ACI Committee 318 (1989). "Building Code Requirements for Reinforced Concrete (ACI 318-89) and Commentary (ACI 318R-89)," American Concrete Institute, Detroit, MI.
- ACI Committee 334 (1982). "Concrete Shell Structures Practice and Commentary (ACI 334.1R-64) (Revised 1982)," American Concrete Institute, Detroit, MI.
- ACI Committee 344 (1981). "Design and Construction of Circular Prestressed Concrete Structures (ACI 344R-70) (Reaffirmed 1981)," American Concrete Institute, Detroit, MI.
- ACI Committee 344 (1988). "Design and Construction of Circular Wire and Strand Wrapped Prestressed Concrete Structures (Report by ACI Committee 344, October 1988)" American Concrete Institute, Detroit, MI.
- Bechtel National, Inc. (1992). "Video Inspection Data Manual for Inactive LLLW Storage Tanks at Oak Ridge National Laboratory, Oak Ridge, Tennessee," Report No. ORNL/ER/Sub/87-990053/45, Martin Marietta Energy Systems, Inc., prepared by Bechtel National, Inc./CH2M Hill/OGDEN/PEER, September 1992 (DRAFT).
- Beavers, J and Hunt, J. (1994). "Site Specific Earthquake Response Spectra for The DOE Oak Ridge Reservation." PVP-Vol.271, Proceedings, ASME Pressure Vessels and Piping Conference on Natural Hazard Phenomena and Mitigation, Minneapolis, Minnesota, 1994, pp65-72.
- Billington, D. P. (1982). Thin Shell Concrete Structures, McGraw-Hill Book Co., New York.
- Chen, W. F. (1982). Plasticity in Reinforced Concrete, McGraw-Hill Book Co., New York.
- Fricke, K. (1986). "Seismic Analysis of the Underground Guniting Tank at the ORNL South Tank Farm," Report No. X-OE-313, Martin Marietta Energy Systems, Inc., Oak Ridge, TN, January 10.
- Energy Systems (1992a). "ORNL Inactive Liquid Low Level Waste Storage Tank Video Inspection Summary," Videotape No. 1095, Oak Ridge, Tennessee.
- Energy Systems (1992b). "Phase 1 - Safety Analysis Report (SAR) Update Program, Hazard Screening for South Tank Farm Facility 3507", HS/3507/F/1/RO, July 28, 1992.
- Fricke, K. (1993). "Seismic Analysis of the Underground Guniting Tanks at the ORNL South Tank Farm," Martin Marietta Energy Systems, Inc., Oak Ridge, TN, May.

- Geotek, Inc. (1978). "Subsurface Investigation for Gunitite Tank Decommissioning Building at Oak Ridge, Tennessee," Geotek Project No. 78-552 for Union Carbide Corp., Oak Ridge, Tennessee.
- GTICES Systems Laboratory (1991). GTSTRUDL User's Manual, Rev. M, Georgia Institute of Technology, Atlanta, GA.
- Henskat, C (1995) "Gunitite and Associated Tanks Operable Unit (GAAT), Evaluation of Dome and Wall Strength Under Current Loading." Report from The Crom Corporation to James Blank of Advanced Systems Technology, Inc. at Oak Ridge, TN. May 11, 1995
- Newmark, N. M. and Rosenblueth, E. (1971). Fundamentals of Earthquake Engineering, Prentice-Hall, Inc., Englewood Cliffs, New Jersey.
- Prakash, S. (1981). Soil Dynamics, McGraw-Hill Book Co., New York.
- Timoshenko, S. and Goodier, J. N. (1951). Theory of Elasticity, McGraw-Hill Book Co., New York.
- UBC (1994). Uniform Building Code - Structural Engineering Design Provisions, 1994, Section 1627 and Table 16-J.
- Xu, J., Bandyopadhyay, K., Miller, C., and Costantino, C. (1994). "Spacing Effects on Seismic Responses of Underground Waste Storage Tanks. PVP-Vol. 271, Proceedings, ASME Pressure Vessels and Piping Conference on Natural Hazard Phenomena and Mitigation," Minneapolis, Minnesota, 1994, pp. 13-18.




Fig. 1. Cross-Sectional View of Tank.




Fig. 2. Section View Through Dome





Fig. 3. Full Cross-Sectional View of Tank.



**OAK RIDGE - SITE SPECIFIC UNIFORM HAZARD
RESPONSE SPECTRA FOR
HORIZONTAL ROCK MOTION**

V-GA 92-2374A



Fig. 4. Oak Ridge-Site Specific Response Spectra For Horizontal Rock Motion




Fig. 5. Cut-up Section of Tank




Fig. 6. Finite Element Numbering System




Fig. 7. Dome Opening Locations




Fig. 8. General Tank Section Dimensions





Fig. 9. Stress Distribution of External Tank Surface




Fig. 10. Stress Distribution at Tank Wall and Dome Ring Junction




Fig. 12. Principal Stress Distribution Around Dome Penetrations




Fig. 13. Stress Distribution of Global Stress S_{xx} Around Dome Penetrations




Fig. 14. Stress Distribution of Global Stress S_{yy} Around Dome Penetrations




Fig. 15. Stress Distribution of Global Stress S_{zz} Around Dome Penetrations




Fig. 16. Maximum Hoop Tensile Stress




Fig. 17. Principal Tensile Stress on Exterior Surface of Wall




Fig. 18. Maximum Tensile Stress Distribution in Ring




Fig. 19. Horizontal Displacement of Wall




Fig. 20. Vertical Displacements of Dome

APPENDIX A

Calculations



SCIENCE
APPLICATIONS
INTERNATIONAL
CORPORATION

DIVISION

147

Calculation ID: 010147038832001-1

JOB DESCRIPTION

GUNITE TANK - X-10 TANK FARM

CLIENT

MARTIN MARIETTA ENERGY SYSTEMS

ABSTRACT:

This calculation examines the behavior of a typical underground gunite tank in the 6 tank matrix of the X-10 storage tank farm at DOE's Oak Ridge facility. The typical tank is investigated for seismically induced soil, fluid and inertial loading. Local stress conditions around penetrations in the roof dome are investigated. The typical tank configuration investigated the behavior of the a tank dome having 5 - 24" holes (a central hole at dome top and 4 additional holes symmetrically spaced on a concentric circle having a radius of 20 feet). The investigation also considered a 30" diameter manhole and a 12" diameter process piping penetration. Existing tanks typically had only 3 - 24" diameter holes in the dome in addition to the 30" diameter manhole and 12" diameter process penetration. Consideration of the additional holes was requested by Energy Systems. Dynamic soil and hydraulic loadings were applied to the structure as static equivalent loadings. The dynamic amplification of soil loading on a single tank resulting from the collective dynamic behavior of the tank farm matrix was considered. The effects of tank wall spalling due to degradation was considered. The 1-½" tank wall liner was not considered in analyses of the typical tank.

REVISION	PREPARED BY	DATE	REVIEWED BY	DATE	APPROVED	DATE
0	CNS	7/24/94	MOK	7/24/94	Tony Chung	7/25/94
1	CNS	3/30/95	MOK	3/21/95	Tony Chung	3/31/95

KEYWORDS: Underground Tank, Gunite Tank, Waste Storage Tank, Seismic, Earthquake

SCIENCE APPLICATIONS INTERNATIONAL CORPORATION

DOCUMENT REVIEW RECORD

DOCUMENT PREPARER: M O KELLEY SHEET 1 of 1
DOCUMENT TITLE: GUNITE TANK
DOCUMENT NUMBER: 010147030664009
REVISION: INITIAL ISSUE
DATE TRANSMITTED: 7/22/94 DATE COMMENTS REQUIRED: 7/25/94
REVIEW TYPE: ☒ TECHNICAL ☐ EDITORIAL ☐ PEER ☐ DESIGN VERIFICATION

COMMENTS THAT ARE ANNOTATED WITH AN (*) ARE MANDATORY AND REQUIRE RESPONSE AND RESOLUTION.

PAGE OR SECT./ PARA.	REVIEWER COMMENTS	PREPARER RESPONSE	REVIEWER ACCEPT/ REJECT
	No EXCEPTIONS TAKEN		
REVIEWED BY <u>M O Kelley</u> Signature		RESPONSE BY _____ Signature	
<u>7/24/94</u> Date		 Date	



Science Applications International Corporation

REVISION LOG

SHEET NUMBER	DESCRIPTION
	INITIAL ISSUE PGG 1 - 78 CKD MOK 7/24/94



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT GUNITE TANK

010147030664009

AUTHOR CNS DATE 7/22/94 JOB NO. _____

CHECKED BY MOK DATE 7/29/94 PAGE 3 of _____

Reference

Table of Contents

Top of Rock Elevation

General Loading Conditions

Static Loadings

Dynamic Loadings

Lateral Soil Springs

Penetrations in Dome

Original Construction

24" Diam. Penetrations

Smaller Penetrations

Increase of Concrete Thickness around Penetrations

Penetrations Considered for Analysis

Horizontal Loading Sketches

Dead Load Soil (Vertical)

Static Earth Pressures

Technical Justification for Not Applying Lateral Pressure on Dome

Dynamic Earth Pressures

General Properties of the Tank

Loading Location

Load Distribution

Magnitude as a Percentage of Static Earth Pressure

Coefficients of Dynamic Earth Pressure

Static Fluid Pressures — Full Tank

Static Fluid Pressures — Half Tank



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT GLNITE TANK

010147030669009 -

AUTHOR CNS DATE 7/22/94 JOB NO. _____

CHECKED BY MOIK DATE 7/25/94 PAGE 4 of _____

Rel

Table of Contents (cont.)

Hydrodynamic Loads — Full Tank

Rigid Mass

Spring - Connected Mass

Spring Constant and Fundamental Period

Height of sloshing Waves

Hydrodynamic Pressures

Hydrodynamic Pressure Distribution

Points of Application

Coefficients of Hydrodynamic Pressure

Hydrodynamic Loads — Half Tank

Rigid Mass

Total Fluid Weight

Spring - Connected Mass

Spring Constant and Fundamental Period

Hydrodynamic Forces

Point of Application

Coefficients of Hydrodynamic Pressure

Material Properties

Reinforcing Steel Allowable Stresses

For Prestressed Reinforcement

For Nonprestressed Reinforcement

Concrete Properties

Criteria for Screening High Tensile Stress Areas

~~Von Mises Failure Theory~~

~~General Formulation of Von Mises Theory~~

~~STRUDEL Formulation of Von Mises Theory~~



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT GUKITE TANK

010147030664009

AUTHOR CNJ DATE 7-22-94 JOB NO. _____

CHECKED BY MOK DATE 7-24-94 PAGE 5 of _____

Reference

Table of Contents (cont.)

Evaluation of Existing Structures

Maximum Stresses

Reinforcements

Hoop Reinforcements in the Wall

Circumferential Reinforcement in the Ring

Vertical Reinforcement in the Wall

Tensile Stress Criterion

Empty Tank Plus Seismic Loading

Full Tank Plus Seismic Loading

Other Loading Conditions

Bending Moment Criterion

Principal Tensile Stress

Reinforcement in Dome

Concrete Stresses

Compressive Stress

Tensile Stress

Top of Wall @ Node 4071 from Loading 4

Edge of the Dome

Openings in Dome

Stability

Dome Stability

Cylindrical Wall Stability

Structural Integrity

Group Behavior

Increased Horizontal Acceleration

Increased Vertical Acceleration

Increased Soil Dynamic Loading

Effects on Node 4071

~~Van Mises Stress for Loading Case 4 from STRUDL~~

~~Van Mises Stress for Modified Loading Case 4~~



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT GUNITE TANK

010147030664 009

AUTHOR CAL DATE 7/24/94 JOB NO. _____

CHECKED BY NOK DATE 7/24/94 PAGE 6 of _____

TABLE OF CONTENTS (CONT)

Evaluation of Existing Structures (cont.)

Allowable Reduction in Wall Thickness

Top of Wall

12" Below the Top of the Wall

24" Below the Top of the Wall

36" Below the Top of the Wall

Additional Soil Load on Dome

~~Von Mises Stress @ Node 4071 For Additional Soil Load~~

Vertical Reinforcement in Wall

Calculation References

List of Reference Drawings

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147030664009	DATE		SHEET	7 of
ESO NO.		COMPUTED CNS 4-16-94	CHECKED BY	MOX 7-26-94		

Top of Rock Elevation (Soil Boring Log by D. Crawford 1-30-78)
[Ref. 8]

<u>Boring Number</u>	<u>Location</u>	<u>Top of Ground Elevation</u>	<u>Depth @ Refusal</u>	<u>Top of Rock Elevation</u>
3507-1	N 21,920 E 30,810	804.4	20.5	783.9
-2	N 21,970 E 30,950	800.5	32.25	768.25
-3	N 21,910 E 31,000	800.2	21.3	778.9
-4	N 21,971 E 31,000	801.5	34.0	767.5
-5	N 22,030 E 31,000	803.9	35.0	768.9

The top of floor elevation of the tanks is @ 782' ±
the soil layers beneath the tank floors have thickness
varying from 0 to 14.5 ft.

The tanks are "on soil", not "on rock"
However, effects of SSI was not considered.

General Loading Conditions

Static Loadings

All loadings not due to earthquake:

D.L. Tank, vertical & horizontal static soil pressure,
static fluid pressure.

Dynamic Loadings

Vertical & horizontal dynamic soil pressure, dynamic
fluid pressure, dynamic force induced from D.L. of
tank by seismic excitation. All applied as static
loads.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 3-24-95 JOB NO.

CHECKED BY Tony Dwyer

DATE 3/31/95 PAGE of

Lateral Soil Springs

Lateral soil restraint on the tank is represented by soil springs.

The modulus of subgrade reaction is used to calculate the equivalent cross-sectional area, A , of "truss members."

The modulus of subgrade reaction k_s is assumed to have a low (conservative) value of 40000 lb/ft³ (pp. 409, Bowles, J. E, Foundation Analysis and design.)

$$k_s = 40000 \text{ lb/ft}^3 = 23.15 \text{ lb/in}^3$$

At each node, the value of the spring k depends on the contributing area of the element.

$$k = (18.12)(h)(k_s) \\ = (18.12)(h)(23.15) = 419.5(h) \text{ lb/in}$$

$$\Delta = \frac{PL}{EA} = \frac{P}{k} = \frac{P}{\left(\frac{EA}{L}\right)}$$

$$k = \frac{EA}{L} \text{ or } A = \frac{kL}{E}$$




$$\text{Let } \boxed{E = 1000 \text{ lb/in}^2} \\ \boxed{L = 10 \text{ in}}$$

Then the cross-sectional area of the equivalent truss member is

$$A = \frac{k(10)}{1000} = 0.01 k = (0.01)(419.5)(h) \\ = 4.195 h$$

$$\text{Use } \boxed{A = 4.2 h \text{ in}^2}$$

E , L , & A are input data for STRUDL. See next sheet for h .



301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 3-24-95 JOB NO. _____


CHECKED BY TC

DATE 3-31-95 PAGE _____ of _____

Lateral Soil Springs (cont.)

Distance from
Top of Wall

Elev. @ Center
of Elements.



GENERAL DESIGN AND COMPUTATION SHEET


JOB GUNITE TANKS	010147030664009	DATE	SHEET 8 of
ESO NO.	COMPUTED CNS 4-15-94	CHECKED BY MOX 7-24-94	

Penetrations in Dome


Penetrations in the dome were made at different stages.
Size, number and locations varied.

Original Construction (Ref Dwg. V-68334, E-56860, E-56866
H3D-20539-G004, X3E-20539-

4 Penetrations: 30" Manhole
12" Connection
4" Spare connection } small, will not cross
4" Vent



Typical For Tanks
W-5, W-7, W-9



Typical For Tanks
W-6, W-8, W-10

GENERAL DESIGN AND COMPUTATION SHEET


3

JOB	GUNITE TANKS	010147030664009	DATE		SHEET	9 of
ESO NO.		COMPUTED CNS 4-15-94	CHECKED BY MOIC 7-24-94			

Penetrations in Dome (Cont.)

24" Diam. Penetrations (for 34" Diam Caissons)

Later, more penetrations were drilled. There are three possible arrangements.




3 Penetrations

Ref. Dwg.

C3E-20539-A019
-A021

P3E-20539-C027
-C034

S3D-20539-B033




4 Penetrations

Ref. Dwg.

C3E-20539-A019
-A021

S3D-20539-B033



5 Penetrations

Ref. Dwg.

C3E-20539-X007
H3D-20539-G004

P3E-20539-C007
-C027

-C034

S3D-20539-B011

-B012

-B013

X3E-20539-B001

-B002

Penetration & caisson sections are shown in Dwg.

H-20539-EG002

H3D-20539-G004

X3E-20539-0001

-0002

GENERAL DESIGN AND COMPUTATION SHEET

JOB GUNITE TANKS	010107030664009	DATE	SHEET 10 of
ESO NO.	COMPUTED CNS 4-16-94	CHECKED BY NOK 7-29-94	

Penetrations in Dome (Cont.)

Smaller Penetrations (Ref. Dwg's. J3E-20539-E006
P3D-20539-C014
P3E-20539-C028)

Smaller penetrations having diameters

$\frac{3}{8}$ " , $\frac{3}{4}$ " , 1" , 2" , 5" , & 6"

are small and will not be considered.

Increase of Concrete Thickness Around Penetrations (Ref. Dwg's.
E-56866
V-68334
X3E-20539-A6

<u>Penetration Size</u>	<u>Additional Slab Size</u>	<u>Min. Thickness Increase</u>
30"	42 ±	12"
24"	60 ±	4"
12"	22 ±	4"


Penetrations Considered for Analysis

Two penetrations, 12"φ and 30", typical for Tanks W-6, W-10. Plus the five 24"φ penetrations pattern shown on preceding page.

Increase of concrete thickness* around penetrations is ignored in the analysis.

*CKRS NOTE: SOME OPENINGS HAVE BEEN CAGED. CAGING IS IGNORED IN THESE CALCULATIONS


Horizontal Loadings Sketches



Earthquake Load
on Tank


E

(+X direction)



Soil Static Load


H_{sw}



Soil Dynamic Load


H_D

CR'S NOTE: HYDRODYNAMIC
LOAD ASSUMES FLUID
INERTIAL RESPONSE & SLOSHING
ARE IN PHASE - CONSERVATIVE.



Hydrostatic Load


$F_s, F_{1/2s}$



Hydrodynamic Load
In-Phase

$F_{D+}, F_{1/2D+}$

OR



Hydrodynamic Load
Out-of-Phase

$F_{D-}, F_{1/2D-}$

LOADS SHOWN ABOVE WERE USED IN ANALYSIS
RELATIVE DIRECTIONS USED ARE AS SHOWN ABOVE
SEE SECTION 3.5 OF THE REPORT FOR LOAD
COMBINATIONS USED.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010197030664009	DATE		SHEET	12 of
ESO NO.		COMPUTED CNS 4-21-94	CHECKED BY	MOX 7-26-94		


Dead Load Soil (Vertical)

$6 \times 110 = 660 \text{ psf} = 4.58 \text{ psi}$ on dome elements. (Global Coords
(Ref. 12))


Static Earth Pressure (Horizontal)

The flexible tank wall can easily move away from the soil mass and the soil pressure applied on the wall become the active soil pressure which is smaller than the at-rest soil pressure. A movement of $0.001H = 0.159'$ at the top of wall will induce the active earth pressure condition.

Passive earth pressure is much larger than the at-rest earth pressure and is generally more than 3 times of the active earth pressure. It can become a reality only if the tank wall can be pushed into the soil mass with a deflection of $0.05H = 7.95''$ at the top of the wall. For a building having both superstructure and basement this is possible, the superstructure may apply large horizontal loads on top of the basement wall as a result of wind or seismic loads. For underground tanks this is a very unlikely event, unless the mass of the tank and its contents is much greater than the mass of the soil of equal volume. (Ref. 16). The total mass of the concrete tank and the liquid in the tank being analyzed is smaller than the mass of the soil of the same volume. No extra mass is introduced into the system.



Superstructure Plus
Basement



Underground
Tank

GENERAL DESIGN AND COMPUTATION SHEET

6

JOB GUNITE TANK	010147030664009	DATE	SHEET 13 of
ESO NO.	COMPUTED CNS 4-22-94	CHECKED BY MOK 7-24-94	

Static Earth Pressures (Cont.)

Assume the angle of internal friction of combined crush stone and clay backfill $\phi = 40^\circ$ (Ref. 24, p. 117)

Then the at-rest earth pressure coeff.

$$K_0 = 1 - \sin \phi = 1 - 0.643 = 0.357$$

Use $K_0 = 0.35$ for comparison with previous analysis. (Ref. 12)

Unit weight $\gamma = 110 \text{ pcf}$ (Ref. 12)

The at-rest earth pressure

(a) Top of Wall



$$= K_0 \gamma H_{\text{top}} = 0.35 \times 110 \times 6$$

$$= 231 \text{ psf}$$

(a) Bottom of Wall

$$= K_0 \gamma H_{\text{bot}} = 0.35 \times 110 \times 19.833$$

$$= 764 \text{ psf}$$




(Ref. Dwg. Cement Gun Co. - 679A,
- 700)

Total static at-rest earth pressure for a 12" vertical strip wall area

$$P_{\text{stat.}} = \frac{1}{2} (231 + 764) (13.83) = \underline{6,882 \text{ lb}}$$

Static at-rest earth pressures apply in a direction normal to the entire wall surface.





Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK 010147030664009

AUTHOR CNS

DATE 7-25-94 JOB NO. _____


CHECKED BY MOK

DATE 7-25-94 PAGE 14 of _____

Ref

Static Earth Pressure (Cont.)

Technical Justifications for Not Applying Lateral Soil Pressure on Dome




For an underground structure with flat top it is very clear that there is no lateral (horizontal) soil pressure on the roof top. Lateral soil pressure only applies on the vertical walls.

Static Earth Pressures (Cont.)


Technical Justifications for Not Applying Lateral Soil Pressure on Dome (Cont.)

CKR'S NOTE:
@ THIS
SURFACE
LATERAL
SOIL
PRESSURES
ARE EQUAL
& OPPOSITE
∴ NO NET
LATERAL
PRESSURE
IS RESISTED
BY THE
TOWER.


MOK
7/25/94



Consider a simplified soil & structure form.



At section (A), look at a small soil cube



As the vertical pressure (soil's own weight or external load) is applied $P_v + \Delta P_v$ the soil cube expands until a lateral confining stress develops. (excluding consolidation effects).


By definition $p_h = k_0 p_v = k_0 \gamma h$ where k_0 is the coefficient of earth pressure at rest.

Static Earth Pressure (cont.)

Technical Justification for Not Applying Lateral Soil Pressure on Dome (cont.)

At section (B), it is the same situation as the left corner of the flat-top bldg with lateral stress on wall and vertical stress on roof.

At section (C), look at a typical slice.



$$\Delta L = \frac{\Delta X}{\cos \theta}$$

$$W = xy \gamma$$

The component parallel to the roof $S_a = W \sin \theta$

The component normal to the roof $N_a = W \cos \theta$

The resistance $N_r = N_a = w \cos \theta$

$$S_r = S_a = w \sin \theta$$

Max S_r , resistance along the top of roof
 $= C \Delta L + N_r \tan \phi$

where C is cohesion

ΔL is the length along the base of the slice

ϕ is the angle of internal friction.

(see Ref. 29)

Static Earth Pressure (cont.)


Technical Justification for Not Applying Lateral Soil Pressure on Dome

At section (C) the roof will see the following loads



These loads are the components of the gravity load of the soil slice.

When a vertical stress is applied on the finite element surface as shown below, the load is applied correctly.



This distributed vertical loading is the only loading. No other loads, either lateral or other direction is necessary.

GUNITE TANK
010147030664009

CNS 4-22-94


MOK 7-20-92

20

CKRS NOTE:

PGS 18 & 19

NOT USED MOK 7/24/94



Surface Load on All
Exterior Wall Elements

STATIC SOIL LOAD.


GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	01614763 0664009	DATE		SHEET	21 of
ESO NO.		COMPUTED CNS 4-21-94	CHECKED BY MOK	7-24-94		

Dynamic Earth Pressures

General Properties of the Tank [16]

The active and passive earth pressures are related to the lateral deflections of the wall.



The wall of the tank has a height of 13' and a thickness of 6". It is flexible and will not behave like a thick retaining wall. The rigid body translation and rotation are relatively small and the flexural deformation are relatively large.

During earthquake, these deflections are the relative deflections between the tank and the surrounding soils. Starting from at-rest condition, the soil-structure system vibrates with small magnitudes and in-phase deflections when the ground input motions are small. As the magnitudes of ground accelerations increase, the deflections of the soil mass and the flexible tank wall are larger and possibly out-of-phase. Difference in movements between the soils and the tank induce dynamic earth pressures. As mentioned before, the larger passive dynamic earth pressure will not be materialized, only active dynamic earth pressure is considered.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147030664009	DATE		SHEET	22 of
ESO NO.		COMPUTED CNS 4-21-94	CHECKED BY	MOK	7-29-94	

Dynamic Earth Pressures (Cont.)

Loading Location

Horizontal Load

The horizontal dynamic earth pressure only applies on the portion of the wall below the dome (166" height).


This pressure applies on one side only (180° wall area) as an independent loading condition.

The dynamic soil pressure on the other half of the cylindrical wall is ignored. It will reduce the at-rest static pressure by an unknown amount.

The soil over the top of the dome is assumed to be self supporting for horizontal earth pressures. It will be considered as a static surcharge load. It will not induce any horizontal loads.

Vertical Load

Vertical dynamic soil pressure is considered as an equivalent static load with a multiplier $1 + \frac{2}{3}(0.14) = 1.093$. See input data under "CREAT LOAD COMB."



GENERAL DESIGN AND COMPUTATION SHEET


10

JOB	GUNITE TANK	010147036664009	DATE		SHEET	23 of
ESO NO.		COMPUTED CNS 4-21-94	CHECKED BY	MOK	7-24-94	

Dynamic Earth Pressures (cont.)

Load Distribution

The distribution of the dynamic earth pressure is nonlinear and the resultant is located @ $0.6H$ from the bottom of wall.
[5, 9, 16, 20]



An equivalent trapezoidal stress distribution is used here.

$$P_{dyn} \left[\frac{1}{2} (0.2H) + 0.3H + \frac{1}{2} (0.5H) \right] = P_{dyn} = 0.65 H p_{dyn}$$

$$p_{dyn} = 1.54 (P_{dyn}/H)$$

The centroid of the this trapezoid is located @ $0.56 H$ from the bottom $\approx 0.6 H$.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147630664009	DATE		SHEET	24 of
ESO NO.		COMPUTED CNS 4-22-94	CHECKED BY	MOK	7-28-94	

Dynamic Earth Pressure (cont.)

Magnitude as a Percentage of Static Earth Pressure

The useful tank life < 20 yrs. From Ref 25, pg. 62 with hazard probability of 2×10^{-3} or 500 yr. return period, $ZPA = 140 \text{ cm/sec}^2 = 0.14g$.

By using the procedure proposed by Prakash [18]

$$P_{\text{total}} = P_{\text{static}} + P_{\text{dynamic}}$$

$$\frac{P_{\text{total}}}{P_{\text{static}}} = \lambda$$


From Fig. 5.15, ref. 18, the value of λ can be found by interpolation with $\phi = 40^\circ$, ground acceleration = 0.14 (Ref. 24) and $\alpha = 0$ one obtains


$$\lambda = 1.4$$

$$\therefore P_{\text{dynamic}} = 0.4 P_{\text{static}}$$

From the calculation of dynamic load distribution the max. dynamic earth pressure

$$\begin{aligned} P_{\text{dynamic}} &= 1.54 (P_{\text{dyn}} / H) \\ &= 1.54 (0.4 P_{\text{static}} / H) \\ &= 0.62 (P_{\text{static}} / H) \\ &= 0.62 (6882 / 13.83) \\ &= 306 \text{ psf} \\ &= 2.127 \text{ psi} \end{aligned}$$





FOR INFORMATION ONLY
NO CHECKING REQUIRED

$$\alpha_h = \frac{\ddot{X}_h}{g} = 0.14$$

FROM REFERENCE 18

Figure 5.15 λ vs. angle of internal friction ϕ .
(After Prakash and Saran, 1966.)


**

010147030664009

$$\frac{2.127 \times 0.8 + \frac{1}{2} (2.127 + 1.986) \times 2.2}{3} = 2.075$$

Applied normal to surface
for simplicity.


26



*

$$\frac{2.127 \times 3 + \frac{1}{2} (2.127 + 1.896) \times 9}{12} = 2.041$$

DYNAMIC SOIL LOAD NORMAL TO THE SURFACE



GUNIT TANK

CNS 4-23-94


MOK 7-21-94

010147 03 0664 009

14

$$\phi = \frac{90^\circ}{26} = 3.4615^\circ$$

$$\theta_n = 90^\circ - \frac{1}{2} \left(\frac{90^\circ}{26} \right) - (n-1)\phi$$
$$= 88.269^\circ - (n-1)\phi$$



Use "SURFACE LOAD GLOBAL" command

The intensity of the stress on an inclined element surface is reduced to $p \sin \theta$.

DYNAMIC SOIL LOAD

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	610147030664009	DATE	
ESO NO.		COMPUTED CNS 4-23-94	CHECKED BY MOX	SHEET 28 of 7-24-94

Dynamic Earth Pressure (cont.)

Coefficients of Dynamic Earth Pressure

<u>n</u>	<u>θ_n</u>	<u>$\sin \theta_n$</u>
1	88.269	0.999
2	84.808	0.996
3	81.346	0.989
4	77.885	0.978
5	74.423	0.963
6	70.962	0.945
7	67.500	0.924
8	64.038	0.899
9	60.577	0.871
10	57.115	0.840
11	53.654	0.805
12	50.192	0.768
13	46.731	0.728
14	43.269	0.685
15	39.808	0.640
16	36.346	0.593
17	32.885	0.543
18	29.423	0.491
19	25.961	0.438
20	22.500	0.383
21	19.038	0.326
22	15.577	0.269
23	12.115	0.210
24	8.654	0.151
25	5.192	0.091
26	1.731	0.030

010147030664009

GUNITE TANK


CNS 4-23-94

MOX 7-24-94

16

Dynamic Earth Pressure Coeff

29



Symmetrical about
this axis

Use "SURFACE LOAD GLOBAL" Command.

Same for all elevations

010147030664009

CKD MOK 7-24-94

GUNITE TANK

CNS 4-28-94

Distance from
Top of Wall


30

Static Fluid Pressures - Full Tank

Full tank @ 11 ft.

Distance
from top of
fluid


Elev. @ Center
of Elements.



$$1.25 \times 62.4 \times 11 = 858.0 \text{ psf} = 5.958 \text{ psi}$$

(Ref. 12)

Pressure on the bottom elements is ignored.



010147636664009

GUNITE TANK


CNS 4-29-94

MDK 7-24-94

31


Static Fluid Pressures - 1/2 Tank

1/2 tank @ 74"

Distance from
Top of WallElev. @ Center
of Elements.

$$1.25 \times 62.4 \times \frac{74}{12} = 481 \text{ psf}$$

$$= 3.34 \text{ psi}$$



GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147630664009	DATE		SHEET	32 of
ESO NO.		COMPUTED CHS 4-26-94	CHECKED BY	MOK	7-24-94	

Hydrodynamic Loads — Full Tank [5, 17]

For the analysis of hydrodynamic pressures against dams, water compressibility is important and surface wave effect is negligible. For the analysis of tanks, the reverse is true.


During movement of a tank, the contained fluid is separated into two zones. The upper zone of fluid tends to move in a sloshing mode while the lower zone moves as a rigid body with the tank.

The forces produced by the induced fluid motion are dependent on tank geometry. Most of the fluid moves in a sloshing mode in shallow tank while most of the fluid moves with the tank as a rigid body in tall tanks.

For small vibrations, the solution can be formulated as a system of linear, conservative, multi-degree structures.

The liquid may be replaced with a number of masses attached to the tank by means of linear spring, each mass being associated with each mode.

Bottom of tank is supported by fill conc., pressure is ignored.



The mass M_0 is the portion of the fluid mass moving with the tank as a rigid body. The mass M_1 is the portion of the fluid mass connected to the tank wall with springs.

GENERAL DESIGN AND COMPUTATION SHEET

20

JOB	GUNITE TANK 010147030664009	DATE	SHEET 33 of
ESO NO.	COMPUTED CNS 4-26-94	CHECKED BY MOK	7-24-94

Hydrodynamic Loads - Full Tank (cont.)

Rigid Mass [17]

$$M_0 = \left[\frac{\tanh(1.7R/H)}{1.7R/H} \right] M$$

$$R/H = 25/11 = 2.273$$

$$1.7R/H = 1.7 \times 25/11 = 3.864$$

$$\tanh x = \frac{\sinh x}{\cosh x} = \frac{e^x - e^{-x}}{e^x + e^{-x}}$$

$$e^{3.864} = 47.656$$

$$\tanh(3.864) = 0.999$$

$$\therefore M_0 = \frac{0.999}{3.864} M = 0.26 M$$

$$H_0 = 0.38 H = 0.38 \times 11 = 4.18'$$

Spring-Connected Mass [17]

$$M_1 = 0.71 \left[\frac{\tanh(1.8H/R)}{1.8H/R} \right] M$$

$$1.8H/R = 1.8 \times 11/25 = 0.792$$

$$e^{0.792} = 2.208$$

$$\tanh(0.792) = 0.66$$

$$\therefore M_1 = 0.71 \left[\frac{0.66}{0.792} \right] M = 0.59 M, \quad \frac{M}{M_1} = 1.695$$

$$\begin{aligned} H_1 &= H \left[1 - 0.21 \left(\frac{M}{M_1} \right) \left(\frac{R}{H} \right)^2 + 0.55 \left(\frac{R}{H} \right) \sqrt{0.15 \left(\frac{RM}{HM_1} \right)^2 - 1} \right] \\ &= H \left[1 - 0.21(1.695)(2.273)^2 + 0.55(2.273) \sqrt{0.15(2.273)^2(1.695)^2 - 1} \right] \\ &= 0.546 H = 0.546 \times 11 = 6.0' \end{aligned}$$

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147030664009	DATE	
ESO NO.	COMPUTED	CNS 4-26-94	CHECKED BY	MODK
				7/25/94
			SHEET	34 of

Hydrodynamic Loads — Full Tank (cont.)

Spring Constant & Fundamental Period [17]

$$K = \frac{4.75 g M_1^2 H}{M R^2}$$

$$= 4.75 (W_1) (M_1/M) (H/R^2)$$

where $W_1 = g M_1$

$$\begin{aligned}
 W &= \text{Total fluid weight} = \overset{\text{Specific Gravity}}{1.25} \times 62.4 (\text{Volume}) \\
 &= 1.25 \times 62.4 \times 11 \times \pi \times (25)^2 \\
 &= 1,684,679 \text{ lb} = 1,685 \text{ kips}
 \end{aligned}$$

$$W_1 = W \left(\frac{M_1}{M} \right) = 1685 \times 0.59 = 994 \text{ kips}$$

$$\therefore K = 4.75 (994) (0.59) (11/25^2) = 49 \text{ k/ft}$$

$$T = 2\pi \sqrt{M_1/K} = 2\pi \sqrt{\left(\frac{994}{32.2} \right) / 49} = 4.99 \text{ sec}$$

Checking with the "Oak Ridge Site Specific Uniform Hazard Response Spectra for Horizontal Rock Motion"

There is no amplification of the ground acceleration for $T > 0.4 \text{ sec}$.

The spectral displacement with 5% damping for $T = 4.99 \text{ sec}$ and $ZPA = 0.14g$, UCL 53582 page 63 shows $\Delta \approx 0.14 \left(\frac{1685}{32.2} \right) = 0.14 (52.3) = 7.28 \text{ in}$

GENERAL DESIGN AND COMPUTATION SHEET

22

JOB	GUNITE TANK 61014703064009	DATE	SHEET 35 of
ESO NO.	COMPUTED CNS 4-28-94	CHECKED BY MOK 7-24-94	

Hydrodynamic Loads — Full Tank (cont.)

Height of Sloshing Waves [17]

The amplitude (height) of slosh is ηx where

$$\eta = \frac{0.69 KR / M_1 g}{1 - 0.92 \left(\frac{x}{R} \right) (KR / M_1 g)^2}$$

$$K = 49 \text{ k/ft}, \quad R = 25 \text{ ft}$$

$$M_1 g = W_1 = 994 \text{ k}$$

$$x = 7.28 \text{ in} = 0.61 \text{ ft}$$

$$\therefore \eta = \frac{0.69 \times 49 \times 25 / 994}{1 - 0.92 (0.61 / 25) (49 \times 25 / 994)^2} = 0.88$$

$$\eta x = 0.88 \times 7.28 = 6.41 \text{ in} > 0.02 H \therefore \text{nonlinear [17]}$$

The sloshing wave height of 6.41 inches will not become a loading condition for the dome. The fluid in the tank will not escape from the tank because of this wave height. It is not significant.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	DATE	SHEET
ESO NO.	010147030664009		36 of
	COMPUTED CLS 4-28-94	CHECKED BY MOK	7-20-94

Hydrodynamic Loads — Full Tank (cont.)

Hydrodynamic Pressures

(1) For empty-tank condition:


Only soil & tank are considered, see other sections.

(2) For full-tank condition (11-ft fluid):

Fluid, tank, & soil are all considered.


See other sections for soil and tank loadings.

For horizontal ground acceleration = 0.14g.




$$\begin{aligned}
 P_0 &= 0.14 \left(\frac{M_0}{M} \right) W \\
 &= 0.14 \times 0.26 \times 1685 \\
 &= 61.3 \text{ kips} \\
 &\text{acting @ a height } H_0 = 4.16
 \end{aligned}$$

$$\begin{aligned}
 P_1 &= 0.14 \left(\frac{M_1}{M} \right) W \\
 &= 0.14 \times 0.59 \times 1685 = 139.2 \text{ kips.} \\
 &\text{acting @ a height } H_1 = 6.0 \text{ ft.}
 \end{aligned}$$



These are total loads
acting on a 180° half
circle.

010147030664 009

Hydrodynamic Load — Full Tank (Cont.)Hydrodynamic Pressure Distribution

M_0 and M_1 are distributed to each element in proportion to the contributing "area" shown above. It is proportional to $\sin^2 \theta_n$.

The rigid mass, less than 50% of the spring-connected mass, is assumed to induce a dynamic force in the same direction as that of the spring-connected mass. This assumption is conservative.

010147030664009

GUNITE TANK CNS 4-28-94

CKID MOK

7-24-94

25

Hydrodynamic Loads—Full Tank (Cont)Distance from
Top of WallElev. @ Center
of Elements.

38


Points of Application

$$H_0 = 4.18' = 50.16''$$


$$p_0 = \frac{P_0}{A_{ren}} = \frac{61300}{12.5 \times 18.12} \\ = 270.7 \text{ psi}$$

$$H_1 = 6' = 72''$$

$$p_1 = \frac{P_1}{A_{ren}} = \frac{139200}{9 \times 18.12} \\ = 853.6 \text{ psi}$$



See next page for tabulated values.



Distribute total sloshing dynamic load over a band of elements @ the approximate elevation of the c.g. of the sloshing mass (M₁).

Similarly, distribute total rigid body hydrodynamic load over a band of elements @ the approximate elevation of the c.g. of the rigid mass (M₀).

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147030664009	DATE	SHEET
ESO NO.	COMPUTED	CNS 4-28-94	CHECKED BY	39 of MOK 7-24-94

Hydrodynamic Pressure - Full Tank (Cont.)

Coefficients of Hydrodynamic Pressure



n	θ_n	$\sin^2 \theta_n$	$\sin^2 \theta_n / (2 \sum \sin^2 \theta) \overset{=26}{}$	$P_i (\sin^2 \theta_n / 26)$	$P_r (\sin^2 \theta_n / 26)$
1	88.269	0.999	0.0384	10.40	32.78
2	84.808	0.992	0.0382	10.34	32.61
3	81.346	0.977	0.0376	10.18	32.10
4	77.855	0.956	0.0368	9.96	31.41
5	74.423	0.928	0.0357	9.66	30.47
6	70.962	0.894	0.0344	9.31	29.36
7	67.500	0.854	0.0329	8.91	28.08
8	64.038	0.808	0.0311	8.42	26.55
9	60.577	0.759	0.0292	7.90	24.93
10	57.115	0.705	0.0271	7.34	23.13
11	53.654	0.649	0.0250	6.77	21.34
12	50.192	0.590	0.0227	6.14	19.38
13	46.731	0.530	0.0204	5.52	17.41
14	43.269	0.470	0.0181	4.90	15.45
15	39.808	0.410	0.0158	4.28	13.49
16	36.346	0.351	0.0135	3.65	11.52
17	32.885	0.295	0.0114	3.09	9.73
18	29.423	0.241	0.0093	2.52	7.94
19	25.961	0.192	0.0074	2.00	6.32
20	22.500	0.146	0.0056	1.52	4.78
21	19.038	0.106	0.0041	1.11	3.50
22	15.577	0.072	0.0028	0.76	2.39
23	12.115	0.044	0.0017	0.46	1.45
24	8.654	0.023	0.0009	0.24	0.77
25	5.192	0.008	0.0003	0.08	0.26
26	1.731	0.001	0.00004	0.01	0.03

$$\sum \sin^2 \theta = 13$$

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	01014703066 & 009	DATE		SHEET	40 of
ESO NO.		COMPUTED CNS 4-29-94	CHECKED BY	mox	7-24-94	

Hydrodynamic Loads — Half Tank



Rigid Mass

$$M_o = \left[\frac{\tanh(1.7R/H)}{1.7R/H} \right] M$$

$$1.7R/H = 1.7 \times 25 / 6.167 = 6.892$$

$$\tanh x = \frac{\sinh x}{\cosh x} = \frac{e^x - e^{-x}}{e^x + e^{-x}}$$

$$e^{6.892} = 476.6$$

$$\tanh(6.892) = 1.0$$

$$\therefore M_o = \frac{M}{6.892} = 0.145 M$$

$$H_o = 0.38H = 0.38 \times 6.167 \\ = 2.34'$$

Total Fluid Weight

$$W = 1.25 \times 62.4 \times 6.1667 \times \pi \times (25)^2 \\ = 944,441 \text{ lb} = 944.4 \text{ kips}$$

GENERAL DESIGN AND COMPUTATION SHEET

JOB GUNITE TANK	610147030664009	DATE NOV 7-24-94	28 SHEET 41 of
ESO NO.	COMPUTED CNS 4-29-94	CHECKED BY NOV 7-24-94	

Hydrodynamic Loads — Half Tank (cont.)

Spring-Connected Mass

$$M_1 = 0.71 \left[\frac{\tanh(1.8H/R)}{1.8H/R} \right] M$$

$$1.8H/R = 1.8 \times 6.167/25 = 0.444$$

$$e^{0.444} = 1.559$$

$$\tanh(0.444) = 0.417$$

$$M_1 = 0.71 \left(\frac{0.417}{0.444} \right) M = 0.667M$$

$$\frac{M}{M_1} = 1.5, \quad \frac{R}{H} = \frac{25}{6.166} = 4.054$$

$$\begin{aligned} H_1 &= H \left[1 - 0.21 \left(\frac{M}{M_1} \right) \left(\frac{R}{H} \right)^2 + 0.55 \left(\frac{R}{H} \right) \sqrt{0.15 \left(\frac{RM}{HM_1} \right)^2 - 1} \right] \\ &= H \left[1 - 0.21(1.5)(4.054)^2 + 0.55(4.054) \sqrt{0.15(4.054)^2(1.5)^2 - 1} \right] \\ &= 0.577H = 0.577 \times 6.166 = 3.56' \end{aligned}$$

Spring Constant & Fundamental Period

$$\begin{aligned} K &= \frac{4.759 M_1^2 H}{MR^2} = 4.75(W_1) (M_1/M) (H/R^2) \\ &= 4.75 \times (0.667 \times 944.4) (0.667) (6.166/25^2) = 19.67 \text{ K/ft} \end{aligned}$$

$$T = 2\pi \sqrt{M_1/K} = 2\pi \sqrt{\left(\frac{0.667 \times 944.4}{32.2} \right) / 19.67} = 6.26 \text{ sec.}$$

No amplification of the ground acceleration.


Height of sloshing waves is not significant.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK	010147030664009	DATE	
ESO NO.		COMPUTED CNS 4-29-94	CHECKED BY MOK 7-20-94	SHEET 42 of

Hydrodynamic Loads — Half Tank (cont.)

Hydrodynamic Forces



For horizontal ground acceleration = 0.1

$$\begin{aligned}
 P_0 &= 0.14 \left(\frac{M_0}{M} \right) W \\
 &= 0.14 \times 0.145 \times 944.4 \\
 &= 19.17 \text{ kips}
 \end{aligned}$$

acting @ a height $H_0 = 2.34'$

$$\begin{aligned}
 P_1 &= 0.14 \left(\frac{M_1}{M} \right) W = 0.14 \times 0.667 \times 944.4 = 88.19 \text{ kips} \\
 &\text{acting @ a height } H_1 = 3.56'
 \end{aligned}$$

These are the total hydrodynamic forces acting at certain heights on a 180° half circle.

010147630664609

GUNITE TANK

CNS 4-29-94

CKD MOK

7-26-94

30

43

Hydrodynamic Loads - Half Tank (Cont.)


Points of Application

$$H_0 = 2.34' = 28.1''$$

$$p_0 = \frac{P_0}{\text{Area}} = \frac{19170}{12.5 \times 18.12} = 84.6 \text{ psi}$$

$$H_1 = 3.56' = 42.7''$$

$$p_1 = \frac{P_1}{\text{Area}} = \frac{88190}{12.5 \times 18.12} = 389.4 \text{ psi}$$



GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANK 010147030664009	DATE	3/	SHEET	44 of
ESO NO.	COMPUTED CNS 4-29-94	CHECKED BY mox		7-24-96	

Hydrodynamic Pressure — Half Tank (Cont.)

Coefficients of Hydrodynamic Pressure

n	θ_n	$p_o (\sin^2 \theta_n / 26)$	$p_i (\sin^2 \theta_n / 26)$
1		3.25	14.95
2		3.23	14.88
3		3.18	14.64
4		3.11	14.33
5		3.02	13.90
6		2.91	13.40
7		2.78	12.81
8		2.63	12.11
9		2.47	11.37
10		2.29	10.55
11		2.12	9.74
12		1.92	8.84
13		1.73	7.94
14		1.53	7.05
15		1.34	6.15
16		1.14	5.26
17		0.96	4.44
18		0.79	3.62
19		0.63	2.88
20		0.47	2.18
21		0.35	1.60
22		0.24	1.09
23		0.14	0.66
24		0.08	0.35
25		0.03	0.12
26		0.003	0.02

$\theta_n = 90^\circ - \frac{1}{2}(\phi) - (n-1)\phi$
 $= 90^\circ - (n - \frac{1}{2})\phi$

$\phi = 90^\circ / 26,$

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANKS	010197030664009	DATE		SHEET 45 of 32
ESO NO.	COMPUTED CNS 5-20-94	CHECKED BY MOK 7-24-94			

Material Properties

Reinforcing Steel Allowable Stresses

Codes require that:

The full calculated tensile forces are carried by reinforcing steel [2].

The principal tensile stresses are resisted entirely by reinforcement [3].

For prestressed reinforcement

$$f_s = 0.4 f_y = 0.4 \times 60,000 = 24,000 \text{ psi} \quad [\text{ACI 318-63}]$$

$$\text{For seismic load: allow. tensile stress} = 1.33 \times 24,000 = 32,000 \text{ psi}$$

For nonprestressed reinforcement the allowable tensile stress should not exceed 18.0ksi, exclusive of shrinkage and temperature effects, regardless of yield stress [4].

Use allowable $f_s = 18,000 \text{ psi}$. (working stress design method)

$$\text{For seismic load: allow. tensile stress} = 1.33 \times 18 = \underline{24.0 \text{ ksi}}$$

Concrete Properties

$$\text{Gunite: } f_c' = 5,000 \text{ psi} \quad (\text{dwg E-56866}) \quad , \quad \mu = 0.17$$

$$E_c = 57,000 \sqrt{f_c'} = 4,030,000 \text{ psi} = 4.030 \text{ ksi}$$

$$f_r = \text{tensile stress limit} = 4 \sqrt{f_c'} \approx 300 \text{ psi} \quad (\text{Ref. 30})$$

Criteria for Screening High Tensile Stress Areas

The "Maximum Principal Stress" is used to locate high tensile stress areas in concrete. The following limits are only for identifying these areas, not for code compliance; since all tensile stresses are resisted by reinforcing steel.

Max Principal stress: Use $f_r = 300 \text{ psi}$ as screening reference.

GENERAL DESIGN AND COMPUTATION SHEET

JOB	GUNITE TANKS	01014703066009	DATE		SHEET	46 of
ESO NO.		COMPUTED CNS 5-20-94	CHECKED BY MOIC 7-20-94			

Material Properties (cont.)

Concrete Properties (cont.)

Von Mises Failure Theory

The concrete fails if the multi-axial state of stress reaches a certain level, but concrete properties are determined generally by uniaxial test. To predict failure under a multiaxial state of stress from uniaxial material properties, various theories of failure have been utilized to predict the onset of failure of a material in a combined-stress state from uniaxial data. Failure signifies yielding or actual rupture, whichever is more critical [6].

General Formulation of Von Mises Theory [6]

For principal stresses:

$$\sigma_i = \left[\frac{(\sigma_1 - \sigma_2)^2 + (\sigma_2 - \sigma_3)^2 + (\sigma_3 - \sigma_1)^2}{2} \right]^{1/2}$$

For non-principal stresses:

$$\sigma_i = \left[\frac{(\sigma_x - \sigma_y)^2 + (\sigma_y - \sigma_z)^2 + (\sigma_z - \sigma_x)^2}{2} + 3(\tau_{xy}^2 + \tau_{yz}^2 + \tau_{zx}^2) \right]^{1/2}$$

σ_i is compared with the allowable tensile stress

STRUDEL Formulation of Von Mises Theory [14]

$$\sigma_i^{GT} = \left[\frac{s_{xx}^2 + s_{yy}^2 + s_{zz}^2}{2} + s_{xy}^2 + s_{yz}^2 + s_{zx}^2 \right]^{1/2}$$

Where $s_{xx} = s_{xx} - s_{ave}$, $s_{yy} = s_{yy} - s_{ave}$; $s_{zz} = s_{zz} - s_{ave}$
 $s_{ave} = (s_{xx} + s_{yy} + s_{zz})/3$

σ_i^{GT} is compared with $\frac{1}{\sqrt{3}}$ (allow. tensile stress) The two formulations give identical results.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT GUNITE TANKS
01014703066009

AUTHOR MOK DATE 7-31-94 JOB NO. _____
CHECKED BY CAL DATE 7-21-94 PAGE 47 of _____

Reference

CHECKER'S NOTE :

THE VON MISES STRESSES OUTPUT BY GTSTRUDL HAVE BEEN REDUCED BY A FACTOR OF $\sqrt{3}$ WITH RESPECT TO CLASSICAL VON MISES FORMULATIONS. GTSTRUDL VON MISES SHOULD BE COMPARED AGAINST ALLOWABLE STRESS LIMITS WHICH HAVE ALSO BEEN REDUCED BY $\sqrt{3}$. IN THIS EVALUATION VON MISES STRESSES WILL BE COMPARED TO $7.5\sqrt{f'_c}/\sqrt{3}$ TO DETERMINE THE MARGIN AGAINST TENSILE FAILURE IN UNREINFORCED CONCRETE. (SEE ALSO CAPACITY REDUCTION" IN FOLLOWING PAGES.)

VON MISES STRESSES WILL BE USED TO CHECK FOR GENERAL QUALIFICATION OF THE STRUCTURES CONCRETE SECTIONS. WHERE COMPUTED VON MISES STRESSES ARE LOWER THAN VON MISES ALLOWABLE LEVELS THE XSECTION OF INTEREST IS CONSIDERED QUALIFIED. WHERE VON MISES STRESS ALLOWABLES ARE EXCEEDED CONVENTIONAL REINFORCED CONCRETE ANALYSIS TECHNIQUES WILL BE USED TO ASSESS COMPLIANCE WITH ANALYSIS CRITERIA.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030604009

AUTHOR CNS

DATE 5-25-94 JOB NO.

CHECKED BY MOK

DATE 7-29-94 PAGE 48 of

Ref.

Evaluation of Existing Structures

Evaluation of the tanks was performed by analytical method. Concrete was assumed to be uncracked, homogeneous, and isotropic. The approach and material characteristics are depicted in codes summarized below.

In case load test is not feasible, evaluation by analytical method is permitted according to ACI 318-89 (Ref. 2)

Also in ACI 318-89, it is noted that for members other than simple flexural members (beams), an analytical method is preferred because the criterion for judging the results of load tests are not well established for structures such as shells.

ACI 334, Concrete Shell Structures Practice and Commentary (Ref. 3), states that for an elastic analysis, concrete may be assumed uncracked, homogeneous, and isotropic. Elastic analysis should be used for supporting members such as rings. Similar statements are found in ACI 318-89 (Ref. 2).

Reinforcements are required to take the entire tensile force calculated for concrete as required by ACI 318-89 (Ref. 2) ACI 334 (Ref. 3), and ACI 344 (Ref. 4).

High tensile stress areas in concrete are identified by both maximum principal stress and Von Mises stress criterion.

Minimum dome & wall thickness required by ACI 344 is 3 1/2 in. OK.

Floor thickness required is 2 1/2 inch OK.

Concrete cover per ACI 334: 1/2" for bars not contacting ground, 3/8" for welded wire fabric, 1" for prestressed tendons. OK

Evaluation of Existing Structures (cont.)

Maximum Stresses

The maximum stresses due to both static and seismic loads are tabulated below.

Type of Stress		*	Node	Static + Seismic Load		Static Load		** Ratio
				Loading Case	Stress (psi)	Loading Case	Stress (psi)	
Directional Tensile and Shear Stresses	Sxx	1	8128	6	542	2	488	1.11
	Syy	5	4071	4	549	1	489	1.12
	Szz	3	8592	4	833	1	781	1.07
	Sxy	6	4071	4	544	1	491	1.11
	Sxz	4	8903	8	453	3	410	1.10
	Syz	6	41	4	523	1	488	1.07
Principal Stresses	Tension	6	4071	4	689	1	621	1.11
	Compression	2	8595	4	642	1	597	1.08
	Tmax	6	4071	4	467	1	420	1.11

- * Locations 1: 30-in opening, bottom surface.
2: 30-in opening, middle surface.
3: 30-in opening, top surface.
4. edge of dome, bottom surface.
5. bottom of ring.
6. top of wall, exterior surface.

** Ratio = Stress due to static plus seismic load / stress due to static load



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR C.N.S.

DATE 6-9-94 JOB NO.

CHECKED BY MOK

DATE 7-24-94 PAGE 50 of

Ref

Evaluation of Existing Structures (cont.)

Reinforcements

ACI 334 (Ref. 3) requires providing reinforcement in the principal stress directions. A reduction of 5% in allowable stress for each degree of deviation from the principal stress direction beyond 15° ^{is REQUIRED}. This means that reinforcements placed 35° from the principal stress direction become completely ineffective, the allowable stress becomes zero.

A structure may be subjected to many loads, and different combinations of them. In each situation, the stress pattern will change as well as the magnitude and direction of principal stresses. It is impossible to place reinforcement in principal stress directions for all load combinations. The ACI 334 requirements on placing reinforcements is impractical.

This evaluation proportions reinforcement according to the state of stress in concrete in terms of directional stresses relationship (Ref. 15).



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501

Oak Ridge, Tennessee 37830

Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 6-9-94 JOB NO.

CHECKED BY MOK

DATE 7-24-94

PAGE 51 of

Reference

Evaluation of Existing Structures (cont.)

Reinforcements (cont.)

Hoop Reinforcements in the Wall [Ref. Dwg. E-56866] -56867

The maximum hoop stress, 314 psi, occurred in the top 2 feet of the wall, at node 4069 of element 2125 under loading condition 5 (see figure next page).

@ THE TOP OF THE WALL

The ring has 17 $1\frac{1}{8}"\phi$ bars (13 original + 4 renovation). A part of the ring reinforcement can be counted to resist the hoop tension near the top of the wall. Three $1\frac{1}{8}"\phi$ bars from the ring and one $3/4"\phi$ bar from the wall give a total steel area $A_s = 3 + 0.44 = 3.44 \text{ in}^2 / 2 \text{ ft wall height}$.

The next 2 feet of wall seems to be more critical. The reinforcements are:

$3/4"\phi$ bar @ 8" (prestressed) $A_s = 0.44 \text{ in}^2 / 8 \text{ in}$

3 layers of welded mesh $4\frac{1}{2}"\times 4\frac{1}{2}"\times 8\frac{1}{2}"\times 8$ $A_s = \frac{8}{12} \times 3 \times 0.062 = 0.124$

Allow. tensile force = $32000 \times 0.44 + 24000 \times 0.124 = 17056 \text{ lb}$

Max. tensile force in $8" \times 6"$ concrete wall = $8 \times 6 \times 314 = 15,072 \text{ lb}$

$$\frac{\text{Demand}}{\text{Capacity}} = \frac{15072}{17056} = 0.88 < 1.0 \quad \text{OK}$$

$$\text{OR } \frac{\text{CAPACITY}}{\text{DEMAND}} = \frac{17056}{15072} = 1.13$$




Fig. 1. Maximum Hoop Tensile Stress



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501

Oak Ridge, Tennessee 37830

Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147630664009

AUTHOR CNS

DATE 6-9-94 JOB NO.

CHECKED BY MOK

DATE 7-28-94 PAGE 53 of

Reference

Evaluation of Existing Structures (cont.)

Reinforcements (cont.)

Circumferential Reinf. in the Ring

Maximum tensile stress in the ring = 300 psi
(see figure next page)

$$\begin{aligned} \text{Max. Tensile force in ring} &= 300 \times \frac{1}{2} \times (3+6+30) \times [(31+3) + 11] \\ &= 300 \times 878 = 263,400 \text{ lb} \end{aligned}$$

$$\begin{aligned} \text{Reinforcement: } &15 \text{ } 1\frac{1}{8}" \text{ bar} \quad A_s = 15 \times 1 = 15 \\ &3 \text{ } 3/8" \text{ bar} \quad 3 \times 0.11 = 0.33 \quad \left. \vphantom{\begin{matrix} 15 \\ 0.33 \end{matrix}} \right\} 15.33 \text{ in}^2 \\ &2 \text{ layers } 4" \times 4" \text{ } 8" \times 8" \text{ mesh } 2 \times 2 \times 0.062 = 0.248 \text{ in}^2 \\ &2\text{-ft long} \end{aligned}$$

$$\begin{aligned} \text{Albw. Tensile Force} &= 32,0 \times 15.33 + 24 \times 0.248 = 496.51 \text{ k} \\ &= 496,510 \text{ lb} \end{aligned}$$

$$\frac{\text{Demand}}{\text{Capacity}} = \frac{263400}{496510} = 0.53 < 1.0 \text{ OK}$$

(for code compliance.)

$$\text{Capacity at yield} = 60 \times 15.33 + 40 \times 0.248 = 929,702 \text{ lb}$$

$$\frac{\text{Capacity}}{\text{Demand}} \text{ at yield} = \frac{929,702}{263,400} = 3.5$$

This is the reserved capacity the ring has.

prepared CNS 3/27/95

checked by TC 3/31/95

54




Fig. 2. Maximum Tensile Stress Distribution in Ring



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 6-9-94 JOB NO.

CHECKED BY MOK

DATE 7-24-94

PAGE 55 of

Evaluation of Existing Structures (cont.)

Reinforcements (cont.)

Vertical Reinforcement in the Wall

Tensile stress Criterion

Reinforcement is assumed to take all tensile force.

Empty Tank Plus Seismic Loading

This loading case (loading 4) results
the max. principal tensile stress.

689 psi @ Node 4071
(see sketch next sheet)

The corresponding directional
stresses S_{yy} @ nodes 4071 and 4076
are 200 and -573 psi respectively.

Tensile force in the section

$$= \frac{1}{2} \times 200 \times 1.55 = 155 \text{ lb/in wall}$$

$$= 1860 \text{ lb/12-in wall}$$

For one layer welded mesh



4" x 4" - #8 x #8 $A_s = 0.062 \text{ in}^2/12\text{-in}$

$$\text{Allow. Tensile Force} = 0.062 \times 24,000$$

$$= 1,488 \text{ lb/12-in wall}$$

$$\frac{\text{Demand}}{\text{Capacity}} = \frac{1860}{1488} = 1.25 > 1.0 \text{ NG.}$$

Other loading conditions need be further
investigated.






Fig. 3 Principal Tensile Stress @ Exterior Surface of Wall




Fig. 4 Von Mises Stress @ Exterior Surface of Wall



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 3-28-95 JOB NO. _____

CHECKED BY TL

DATE 3/31/95 PAGE 57 of _____

Evaluation of Existing Structures (cont.)

Reinforcements (cont.)

Vertical Reinforcement in the Wall (cont.)

Tensile Stress Criterion

Full Tank Plus Seismic Loading

Loading cases 5 and 6 represent the hydrodynamic loadings from opposite direction.

Loading Case	S _{xy} @	
	Node 4071	Node 4076
5	114	-467
6	176	-538

Loading case 6 controls for its larger tensile stress.

$$X = \left(\frac{176}{176 + 538} \right) 6$$


$$= 1.48"$$

$$6 - X = 4.52"$$

Tensile force in the section

$$= \frac{1}{2} (176) (1.48) = 130 \text{ lb/in}$$

$$= 1563 \text{ lb/12-in wall}$$



$$\text{Allow. Tensile force} = 1488 \text{ lb/12-in wall}$$

$$\frac{\text{Demand}}{\text{Capacity}} = \frac{1563}{1488} = 1.05 \approx 1.0 \text{ OK}$$

Evaluation of Existing Structures (cont.)

Reinforcements (cont.)

Vertical Reinforcement in the Wall (cont.)

Tensile Stress Criterion (cont.)

Other Loading Conditions

t C N

Loading Type	Loading Case	Condition	Tensile Stress @ Node 4071 (Psi)	Compressive Stress @ Node 4076 (Psi)	Tension in 12-in Long Wall (lb)	Demand Capacity
Static	1	Empty Tank	189	516	1824	1.63
	2	Full Tank	169	495	1548	1.39
	3	Half Full Tank	184	511	1754	1.57
Static + Seismic	4	Empty Tank	200	573	1860	1.25
	5	Full Tank In-Phase	114	467	805	0.54
	6	Full Tank Out-of-Phase	176	538	1563	1.05
	7	Half Tank In-Phase	179	548	1587	1.07
	8	Half Tank Out-of-Phase	192	558	1769	1.19

$$N = 12 \left[\frac{1}{2} (t) \left(\frac{t}{t+c} \right) (16) \right] = \frac{36t^2}{t+c}$$

Tensile Capacity for static loading cases = $0.062 \times 18000 = 1116 \text{ lb/12-in}$

for seismic loading cases = $0.062 \times 24000 = 1488 \text{ lb/12-in}$

The vertical reinforcement is not adequate to resist the tensile force as required by ACI 318 [2] and ACI 334 [3]. However, the stress, S_{yy} , changes sign across the wall, an indication that the wall is under both axial compression load and bending moment. The wall can be evaluated as a "beam-column" subjected to both axial and flexural loads.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 6-13-94 JOB NO. _____

CHECKED BY MOK

DATE 7-24-94

PAGE 59 of _____

Ref


Evaluation of Existing Structure (cont.)

Reinforcements (cont.)


Vertical Reinforcement in the Wall (cont.)

Bending Moment Criterion

The wall can be evaluated as a column or beam-column. Check for the most critical condition, loading ①




Resulting stress from M and P.



From Moment, M.


$$\frac{1}{2} (189 + 516) = 353 \text{ psi}$$

+



From Axial Compressive Force, P.

$$516 - 353 = 163 \text{ psi}$$



For a unit length of 12" wall

$$A = \text{Area} = 6 \times 12 = 72 \text{ in}^2$$

$$S_M = \frac{bh^3}{6} = \frac{12 \times 6^3}{6} = 72 \text{ in}^3$$

$$P/A = P/72 = 163 \therefore P = 11,736 \text{ lb}$$


$$M/S_M = M/72 = 353 \therefore M = 25,416 \text{ lb-in}$$

Evaluation of Existing Structure (cont.)

Reinforcements (cont.)

Vertical Reinforcement in the Wall (cont.)

Bending Moment Criterion (cont.)



Total steel $A_s = 0.2 + 3 \times 0.062 = 0.386 \text{ in}^2$

$d = \frac{0.062 \times 4.83 + 0.324 \times 2.5}{0.386} = 2.874 \text{ inches}$

assumed $\frac{2.5}{4}$

core 4.83 inches

$= 4 + \frac{3}{4} \times 0.08$

Check this section as a beam-column, using

ACI 318-63* Eq. 14-9 & 14-10

* USED FBIL
ASD
METHODOLOGY

$$\frac{f_a}{F_a} + \frac{f_b}{F_b} \leq 1 \quad \text{--- (14-9)}$$

$$F_a = 0.34(1 + p_g m) f_c' \quad \text{--- (14-10)}$$

$$f_a = 163 \text{ psi}, \quad f_b = 353 \text{ psi}$$

$$p_g = \frac{A_s}{A_g} = \frac{0.386}{72} = 0.00536$$

$$m = f_y / (0.25 f_c') = 40,000 / (0.25 \times 5000) = 9.41$$

$$\therefore F_a = 0.34(1 + 0.00536 \times 9.41) \times 5000 = 1,786 \text{ psi}$$

Calculate F_b as follows:

$$n = E_s / E_c = 29,000 / 4,030 = 7.2$$

$$f_s = 18,000 \text{ psi}, \quad f_c = 0.45 f_c' = 0.45 \times 5000 = 2,250 \text{ psi}$$



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

01014703066A009

AUTHOR CNS

DATE 6-13-94 JOB NO.

CHECKED BY MKK

DATE 7-24-94

PAGE 61 of

Evaluation of Existing Structure (cont.)

Reinforcement (cont.)

Vertical Reinforcement in the Wall (cont.)

Bending Moment Criterion (cont.)

$$k = \frac{1}{1 + \frac{f_s}{n f_c}} = \frac{1}{1 + \frac{18,000}{7.2 \times 2250}} = 0.47$$

$$jd = d \left(1 - \frac{k}{3}\right) = 2.874 \left(1 - \frac{0.47}{3}\right) = 2.874 (0.84) = 2.42"$$

$$\text{Moment capacity in steel} = M_s = A_s f_s jd = 0.386 \times 18,000 \times 2.42 = 16,814 \text{ lb-in}$$

$$\begin{aligned} \text{Moment capacity in conc.} &= M_c = \frac{1}{2} f_c k j b d^2 \\ &= \frac{1}{2} \times 2250 \times 0.45 \times 9.85 \times 12 \times 2.874^2 \\ &= 42,652 \text{ lb-in} \end{aligned}$$

M_s controls.

Eq. 14-10 can be rewritten as

$$\frac{f_a}{F_a} + \frac{\text{Applied Moment}}{\text{Moment Capacity}} = \frac{163}{1786} + \frac{25416}{16814} = 1.6$$

The demand/capacity ratio is similar to that obtained from the tensile-stress criterion.

Principal Tensile Stress

The principal tensile stress @ Node 4071 is 689 psi (loading 4) which is higher than 300 psi principal tensile stress limit.

It is concluded that the vertical reinforcement in the wall does not meet code requirements, tensile stress in concrete is too high. Cracks may have occurred.

GENERAL DESIGN AND COMPUTATION SHEET


JOB	GLUNITE TANK	010147030664009	DATE		SHEET	62	of	44
ESO NO.		COMPUTED CNS 5-30-94	CHECKED BY	MXC 7-28-94				

Evaluation of Structures (Cont.)

Reinforcements (cont.)

Reinforcement in Dome (Ref. Dwg E-56866 -56867)

Max principal stress in the dome occurred on node 4091 of element 2142 located at the bottom surface of the dome edge.



It is assumed that the max. circumferential tension existed at similar location.

$\theta = 0$, Loading 5, $S_{xx} = 204 \text{ psi}$ @ node 61
160 psi @ node 62
118 psi @ node 63

Ave. Tensile Stress

$$= \frac{1}{4}(204 + 2 \times 160 + 118)$$

$$= 161 \text{ psi} \ll 300 \text{ psi (fr)}$$

Concrete will not crack.

There are two 5-in thick layers.

For 12" wide band the tensile force is


$$12 \times 10 \times 161 = 19320 \text{ lb}$$

The only reinforcement provided in this direction is the 2 layers of welded mesh 4" x 4" - #8 x #8 (see dwg. E-56866)

$$A_s = 2 \times 0.062 = 0.124 \text{ in}^2$$

$$\text{Allow. Tension} = 0.124 \times 24000 = 2976 \text{ lb} \ll 19320 \text{ lb}$$

Non compliant with ACI-344




Evaluation of Structures (Cont.)

Reinforcements (Cont.)


Reinforcement in Dome (cont.)

This requirement is in accordance of Ref. #3.
Since the tensile stress in concrete is only 161 psi,
structural integrity is not in jeopardy.



A detailed stress distribution from loading 5 is shown
below.



Elements & Nodes



Stresses S_{xx} psi
+ tension
- compression



A slice of the dome-ring shows that
it behaves like a beam with reinforcement.
Concrete below the N.A. will have
tensile stress (for strain compatibility)
which is OK.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010/47030664009

AUTHOR CNS

DATE 2-27-95 JOB NO. _____

CHECKED BY TC

DATE 3/31/95 PAGE 64 of _____

Evaluation of Structures (cont.)

Concrete Stresses

Compressive Stress

The maximum principal compressive stress = 642 psi
@ node 8595 from loading case 4.

Allowable compressive stress due to bending = $0.45f_c' = 2250 \text{ psi}$

Allowable bearing stress = $0.25f_c' = 1250 \text{ psi}$

Both of these allowable stress are greater than 642 psi OK

Tensile Stresses

Top of Wall @ Node 4071 from Loading 4

Principal Tensile Stress = 689 psi $> f_r$ ($f_r = 300 \text{ psi}$)

Directional Tensile Stress $S_{yy} = 549 \text{ psi}$

The principal tensile stress only indicates the location of high stress areas. Comparing with f_r only gives reference as how high these stresses due to applied loads are; it is not an indication of failure of concrete.

If the reinforcement in this area is adequate to resist the entire tensile force then code compliance is met. If the reinforcement provided is not adequate then code compliance is not met and a situation of potential cracks does exist in this small local area; the section may not completely fail since most part of the section is under compression. Also, shear friction still exists at the cracked surface (ACI 318 §11.7).

Across the top of the wall only $1\frac{1}{2}\%$ of the wall thickness (25%) has tensile stress. Cracks may exist along the exterior face, but 75% of the wall thickness is under compression and no crack will occur. Fluid will not leak through the wall.

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 3-27-95 JOB NO.

_ JOB NO.

CHECKED BY TC

DATE 3/31/95 PAGE 65 of

PAGE 65 of

Evaluation of Structures (cont.)

Concrete Stresses (cont.)

Tensile Stresses (cont.)

Edge of the Dome

As discussed in the section of "Reinforcement in Dome"

The reinforcement provided in the edge of dome is not adequate to resist the circumferential tension. But, the tensile stress in concrete is small, 160 psi. Comparing to $f_r = 300$ psi, it is concluded that the concrete will not fail in tension. If a typical slice, including the ring, is considered as a beam, then there is no need to check tensile stress in that area; the rebars in the ring takes all the tensile force.

Openings in Dome

The directional tensile stress, S_{zz} , at the top surface (node 8134) of the 30" ϕ opening is 833 psi, in global coordinates. This element 4434 is not located @ 0° , 90° , 180° , or 270° . The high tensile stress S_{zz} in a non-orthogonal direction and has no particular meaning.

The principal stresses at node 8592 are:

$S_1 = 316 \text{ psi}$, $S_2 = 27 \text{ psi}$, $S_3 = -204 \text{ psi}$

tension compression

The principal stresses are not high comparing to other locations. $\therefore$ OK

Smaller openings are less critical.

Evaluation of Structures (cont.)StabilityDome Stability (Ref. 4, Sect. 2.6.3.1)

The safety factor, S , against buckling is

$$S = \frac{E_c (t/r)^2}{4(g+p)} \quad (\text{ACI 344 require } S \approx 4 \text{ to } 6)$$

where r = radius = 300"

t = thickness : use 5"

$g+p$ = total load

where $g = (10/12)(150)/144 = 0.87 \text{ psi}$ for 10" concrete.

$p = 6 \times 110/144 = 4.58 \text{ psi}$ for 6' soil.

$$\therefore S = \frac{4030000 (5/300)^2}{4(0.87 + 4.58)} = 51.4 > 6 \text{ OK}$$

Cylindrical Wall Stability (Ref. 26)

The buckling stress for a cylinder is

$$\frac{0.3 E t}{r} = \frac{0.3 (4030000) (6)}{300} = 24180 \text{ psi} \gg \text{maximum } S_{yy} \text{ (= 549 psi)}$$

$$S = 24180/549 = 44$$

OK

Structural Integrity

Overall, the gunite tank is structurally sound and adequate to function as a liquid container.

The hoop tension capacities in both the ring and cylindrical wall are more than adequate to resist the loads and to meet the code requirements.


Vertical tensile stress at the top of wall on the exterior face is high and reinforcement is not adequate. The interior face of the wall is under compression and adequate to contain the liquid in the tank.

Evaluation of Structures (cont.)

Group Behavior [27, 28]

The behavior of a single tank is different from that of a group of tanks. The tank-to-tank interaction becomes significant when the clear spacing between the tanks is in the same order as the radii of the tanks.

The procedure in PVP-Vol. 271 [28] is used to calculate the increased horizontal and vertical accelerations of the tank, and the increased soil dynamic load on the tank wall.



$$L/R = 10/25 = 0.4$$

SUBJECT

GLUITE TANK

91C147030664009

AUTHOR CNS

DATE 7-19-94 JOB NO.

CHECKED BY MOIL

DATE 7-24-94

PAGE 68 of

Reference

Evaluation of Structures (Cont.)

Group Behavior (Cont.)

Increased Horizontal Acceleration (see figures on following pages)

	<u>Left Wall</u>	<u>Right Wall</u>
Top of Wall	1.23	1.09
Middle of Wall	1.11	1.00
Bottom of Wall	1.19	1.06

Average = 1.113 Use 1.12 (12% increase)

Increased Vertical Acceleration (see figures on following pages)

	<u>Left Wall</u>	<u>Right Wall</u>
Top of Wall	1.16	1.21
Middle of Wall	1.16	1.14
Bottom of Wall	1.16	1.17

Average = 1.167 Use 1.17 (17% increase)

This increased acceleration is also used for the vertical soil load over the dome of the tank.

Increased Soil Dynamic Loading (one side only, see figures on following pages)

Top of Wall	2.7	} Average = 1.73
Middle of Wall	1.05	
Bottom of Wall	1.45	

Use 2.00 to account the importance of soil masses
(100% increase) at higher elevations.




Figure 4a. Horizontal maximum accelerations on the Left wall of Tank A.

FOR INFORMATION ONLY
NO CHECKING REQUIRED




Figure 3a. Horizontal maximum accelerations on the right wall of Tank A.

Evaluation of Structures (cont.)

CNS 7-14-94

Group Behavior (cont.)

70




Figure 4b. Vertical maximum accelerations on the left wall of Tank A.

FOR INFORMATION ONLY
NO CHECKING REQUIRED




Figure 3b. Vertical maximum accelerations on the right wall of Tank A.

FROM REF. 28




Figure 6. Horizontal nodal forces on the right wall of Tank A.

FOR INFORMATION ONLY
NO CHECKING REQUIRED

FROM REF. 28



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 7-19-94 JOB NO. _____

CHECKED BY MBK

DATE 7-24-94 PAGE 72 of _____

Reference

Evaluation of Structures (cont.)

Group Behavior (Cont.)

Effects on Node 4071

The maximum Von Mises stress is at node 4071: 297 psi for loading cases 4, which is the empty tank condition.

Loading case 4 has the following loading combination

<u>Loading</u>	<u>Direction</u>	<u>Multiplier</u>	<u>New Multiplier</u> * see below
DEADLOAD	Vert.	1.093	1.109
OVERDOME	Vert.	1.093	1.109
EQ-TANK	Horiz.	1.0	1.12
SIDESOIL	Horiz.	1.0	1.0
DYNASOIL	Horiz.	1.0	2.0

- * { The new multiplier for vertical loads is
 $1 + 1.17 \times 0.093 = 1.109$
- * { The new multiplier for EQ-TANK is 1.12
The multiplier for SIDESOIL is the same: 1.0
The new multiplier for DYNASOIL is 2.0



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

01010703060009

AUTHOR CWS

DATE 7-19-94 JOB NO.

CHECKED BY MOU

DATE 7-20-94 PAGE 73 of

Evaluation of Structures (cont.)

Group Behavior (cont.)

Effects on Node 4071 (cont.)

Von Mises Stress @ Node 4071 For Loading Case 4, From STRUDL

From Loading		Stress (psi)					
		1.093*DEADLOAD	1.093*OVERDOSE	EQ-TANK	SIDESOIL	DYNASOIL	TOTAL
S_{xx}	ELE 2126	35.99	175.05	1.46	2.85	0.04	215.39
	ELE 2127	-12.66	-60.96	-0.52	-1.58	-1.50	-77.22
	Ave.						69.09 *
S_{yy}	ELE 2126	29.64	176.60	1.18	0.72	-7.94	200.20
	ELE 2127	82.69	429.53	3.30	20.50	13.07	549.09
	Ave						374.65 *
S_{zz}	ELE 2126	58.13	291.32	5.32	-70.74	-34.16	249.87
	ELE 2127	58.13	291.32	5.32	-70.74	-34.16	249.87
	Ave						249.87 *
S_{xy}	ELE 2126	89.98	437.55	3.62	8.72	4.41	544.28
	ELE 2127	54.59	264.77	2.18	9.24	8.13	338.91
	Ave						441.60 *
S_{xz}	ELE 2126	0.35	1.83	0.14	-1.11	-1.44	-0.23
	ELE 2127	1.09	5.43	0.17	-1.04	-1.42	4.23
	Ave.						2.00 *
S_{yz}	ELE 2126	-3.56	-16.34	0.17	8.16	4.50	-7.07
	ELE 2127	-3.95	-18.18	0.15	8.01	4.34	-9.63
	Ave.						-8.35 *

* Calculated

Following STRUDL's procedure:

$$S_{ave} = (S_{xx} + S_{yy} + S_{zz})/3 = (69.09 + 374.65 + 249.87)/3 = 231.20 \text{ psi}$$

$$S_{xx} = S_{xx} - S_{ave} = 69.09 - 231.20 = -162.11 \text{ psi}$$

$$S_{yy} = S_{yy} - S_{ave} = 374.65 - 231.20 = 143.45 \text{ psi}$$

$$S_{zz} = S_{zz} - S_{ave} = 249.87 - 231.20 = 18.67 \text{ psi}$$

$$\begin{aligned} \text{Von Mises Stress } \sigma_1 &= \left[\frac{(S_{xx}^2 + S_{yy}^2 + S_{zz}^2)}{2} + S_{xy}^2 + S_{yz}^2 + S_{zx}^2 \right]^{1/2} \\ &= \left\{ \frac{(-162.11)^2 + (143.45)^2 + (18.67)^2}{2} + (441.6)^2 + (2.0)^2 + (-8.35)^2 \right\}^{1/2} \\ &= 467.64 \text{ psi vs. 467.635 from STRUDL output.} \end{aligned}$$

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147630664009

AUTHOR CNS

DATE 7-19-94 JOB NO.

CHECKED BY WOK

DATE 7-20-94 PAGE 74 of

Evaluation of Structures (Cont.)

Group Behavior (Cont.)

Effects on Node 4071 (Cont.)

Von Mises Stress @ Node 4071 for Modified Loading Case 4

From Loading		Stress (psi)					
		1.109 * DEADLOAD	1.109 * OVERDOME	1.12 * EQ-TANK	SIDESOIL	2 * DYNASOIL	TOTAL
S_{xx}	ELE 2126	36.52	177.61	1.64	2.85	0.04	218.66
	ELE 2127	-12.85	-61.85	-0.58	-1.58	-3.00	-79.86
	Ave						69.40
S_{yy}	ELE 2126	30.07	179.19	1.32	0.72	-15.88	195.42
	ELE 2127	83.90	435.82	3.70	20.50	26.14	570.06
	Ave						382.74
S_{zz}	ELE 2126	58.98	295.59	5.96	-70.74	-68.32	221.47
	ELE 2127	58.98	295.59	5.96	-70.74	-68.32	221.47
	Ave						221.47
S_{xy}	ELE 2126	91.30	443.96	4.05	8.72	8.82	556.85
	ELE 2127	55.39	268.65	2.44	9.24	16.26	351.98
	Ave						454.42
S_{xz}	ELE 2126	0.36	1.86	0.16	-1.11	-2.88	-1.61
	ELE 2127	1.11	5.51	0.19	-1.04	-2.84	2.93
	Ave						0.66
S_{yz}	ELE 2126	-3.61	-16.58	0.19	8.16	9.00	-2.84
	ELE 2127	-4.01	-18.45	0.17	8.01	8.68	-5.60
	Ave						-4.22

Use STRUDL's procedure:

$$S_{ave} = (S_{xx} + S_{yy} + S_{zz}) / 3 = (69.4 + 382.74 + 221.47) / 3 = 224.54 \text{ psi}$$

$$S_{xx} = S_{xx} - S_{ave} = 69.4 - 224.54 = -155.14$$

$$S_{yy} = S_{yy} - S_{ave} = 382.74 - 224.54 = 158.20$$

$$S_{zz} = S_{zz} - S_{ave} = 221.47 - 224.54 = -3.07$$

$$\text{Von Mises Stress } \sigma_i = \left[\frac{(S_{xx}^2 + S_{yy}^2 + S_{zz}^2)}{2} + S_{xy}^2 + S_{yz}^2 + S_{zx}^2 \right]^{1/2}$$

$$= \left\{ \frac{(-155.14)^2 + (158.2)^2 + (-3.07)^2}{2} + (454.42)^2 + (0.66)^2 + (-4.22)^2 \right\}^{1/2}$$

$$= 480.70 \text{ psi}$$

$$480.7 / 467.64 = 1.03 \text{ a } 3\% \text{ increase in Von Mises stress.}$$



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS


DATE 3-28-95 JOB NO. _____

CHECKED BY TC

DATE 3/31/95 PAGE 75 of _____

Evaluation of Structures (cont.)

Allowable Reduction in Wall Thickness



@ Exterior Surface of Wall
Loading 4
 $\theta = 90^\circ$

Top of the Wall

Both the plots of principal stress and Von Mises stress indicate the top 12" of the wall is the critical zone.

The principal tensile stress exceeds the threshold $f_r = 530$ psi and the Von Mises stress exceeds the threshold $f_r/\sqrt{3} = 306$ psi.

No reduction in wall thickness is allowed.

12" Below the Top of the Wall

The vertical reinforcement in the wall is determined by S_{yy} and S_{yy} is essentially proportional to the principal tensile stress. To comply with the code, S_{yy} needs to be smaller than 110 psi, so is principal tensile stress.


$\therefore$ No reduction in top 24 inches

24" Below Top of the Wall

A 1" local spalling is OK.

36" Below Top of the Wall

A 2" local spalling is OK.





Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK 010147030664009

AUTHOR CNS

DATE 7-25-94 JOB NO.

CHECKED BY NICK

DATE 7-25-94

PAGE 76 of

Reference

Evaluation of Structures (cont.)

Additional Soil Load on Dome

Check the condition of 8' soil on dome (2 ft additional soil).

① Top of Wall:

At-rest pressure

$$= K_a \gamma H = 0.35 \times 110 \times 8$$


$$= 308 \text{ psf} \quad (231 \text{ psf for 6' soil})$$

② Bottom of Wall

At rest pressure

$$= 0.35 \times 110 \times 21.833$$

$$= 840 \text{ psf} \quad (764 \text{ psf for 6' soil})$$



Total soil load for a 12" vertical strip is

$$\frac{1}{2} (308 + 840) \times 13.833 = 7940 \text{ lb}$$

Original total soil load = 6882 lb for 6' soil over dome

$$7940 / 6882 = 1.15$$

∴ The static lateral soil pressure increases by 15%

The over dome soil load increases by 33%
(8' vs 6' soil)

Evaluation of Structures (cont.)

Additional Soil Load on Dome

Loading Case 4 has the following loading combination

<u>Load</u>	<u>Direction</u>	<u>Multiplier</u>	<u>New Multiplier</u>
DEADLOAD	Vert.	1.093	1.093
OVERDOME	Vert.	1.093	1.457 (=1.33 × 1.093)
ER-TANK	Horiz	1.0	1.0
SIDESOIL	Horiz	1.0	1.15 (15% increase)
DYNASOIL	Horiz	1.0	1.15 (" ")

<u>From Loading</u>		<u>stress (psi)</u>					<u>TOTAL</u>
		<u>1.093 × DEADLOAD</u>	<u>1.457 × OVERDOME</u>	<u>ER-TANK</u>	<u>1.15 × SIDESOIL</u>	<u>1.15 × DYNASOIL</u>	
S_{xx}	ELE 2126	35.99	233.35	1.46	3.28	0.05	274.13
	ELE 2127	-12.66	-81.26	-0.52	-1.82	-1.73	-97.99
	Ave						88.07
S_{yy}	ELE 2126	29.64	235.41	1.18	0.83	-9.13	257.93
	ELE 2127	82.69	572.58	3.30	23.58	15.03	697.18
	Ave						477.56
S_{zz}	ELE 2126	58.13	388.34	5.32	-81.35	-39.28	331.16
	ELE 2127	58.13	388.34	5.32	-81.35	-39.28	331.16
	Ave						331.16
S_{xy}	ELE 2126	89.98	583.27	3.62	10.03	5.07	691.97
	ELE 2127	54.59	352.95	2.18	10.63	9.35	429.70
	Ave						560.84
S_{xz}	ELE 2126	0.35	2.44	0.14	-1.28	-1.66	-0.01
	ELE 2127	1.09	7.24	0.17	-1.20	-1.63	5.67
	Ave						2.83
S_{yz}	ELE 2126	-3.56	-21.78	0.17	9.38	5.18	-10.61
	ELE 2127	-3.95	-24.23	0.15	9.21	4.99	-13.83
	Ave						-12.22



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501

Oak Ridge, Tennessee 37830

Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010167030666 009

AUTHOR C.N.S.

DATE 7-25-94 JOB NO.

CHECKED BY WNO

DATE 7-23-94 PAGE 78 of

Reference

Evaluation of Structures (cont.)

Additional Soil Load on Dome (cont.)

Von Mises Stress @ Node 4071 For Added Soil Load

Following STRUDL procedure:

$$S_{ave} = (S_{xx} + S_{yy} + S_{zz}) / 3 = (88.07 + 477.56 + 331.16) / 3 = 298.93 \text{ psi}$$

$$S_{xx} = S_{xx} - S_{ave} = 88.07 - 298.93 = -210.86$$

$$S_{yy} = S_{yy} - S_{ave} = 477.56 - 298.93 = 178.63$$

$$S_{zz} = S_{zz} - S_{ave} = 331.16 - 298.93 = 32.23$$



$$\begin{aligned} \text{Von Mises stress } \sigma_1 &= \left[\frac{(S_{xx}^2 + S_{yy}^2 + S_{zz}^2)}{2} + S_{xy}^2 + S_{yz}^2 + S_{zx}^2 \right]^{1/2} \\ &= \left[\frac{(-210.86)^2 + (178.63)^2 + (32.23)^2}{2} + (569.84)^2 + (2.83)^2 + (-12.22)^2 \right]^{1/2} \\ &= 594.48 \text{ psi} \end{aligned}$$

$$594.48 / 467.64 = 1.27 \text{ a } 27\% \text{ increase in Von Mises stress}$$

Vertical Reinf. in Wall

S_{yy} @ Node 4071 = 257.93 psi
(last page)

S_{yy} @ Node 4076 is calculated
in next page.





Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

010147030664009

AUTHOR CNS

DATE 7-25-94 JOB NO.

CHECKED BY MOK

DATE 7-25-94 PAGE 79 of


Relt

Evaluation of Structures (cont.)

Additional Soil Load on Dome (cont.)

Vertical Reint. in Wall (cont.)


For loading case 4 S_{yy} : 200 psi tension
(P. 55)



For additional 2" soil
 S_{yy} :

$$x = \left(\frac{257.93}{200} \right) (573)$$

$$= 739 \text{ psi}$$



$$b = \left(\frac{739}{258 + 739} \right) \times 6 = 4.4"$$

$$a = 6 - 4.4 = 1.6"$$

Tensile Force in The Section

$$= \frac{1}{2} \times 258 \times 1.6 = 206 \text{ lb/in of wall}$$

$$= 2472 \text{ lb/12 in of wall}$$

$$\text{Capacity of welded mesh} = A_s \times f_s = 0.062 \times 24000$$

$$= 1488 \text{ lb/12 in of wall}$$

$$\frac{\text{Demand}}{\text{Capacity}} = \frac{2472}{1488} = 1.66$$

The original loading 4 demand/capacity ratio = 1.25
(P. 58)

It is concluded that no additional soil or other loads
can be added to the top of the existing 6' soil layer.

CALCULATION REFERENCES

1. ACI Committee 318, *Building Code Requirements for Reinforced Concrete (ACI 318-63)*, American Concrete Institute, Detroit, MI, 1963.
2. ACI Committee 318, *Building Code Requirements for Reinforced Concrete (ACI 318-89) and Commentary (ACI 318R-89)*, American Concrete Institute, Detroit, MI, 1989.
3. ACI Committee 334, *Concrete Shell Structures Practice and Commentary (ACI 334.1R-64) (Revised 1982)*, American Concrete Institute, Detroit, MI, 1982.
4. ACI Committee 344, *Design and Construction of Circular Prestressed Concrete Structures (ACI 344R-70) (Reaffirmed 1981)*, American Concrete Institute, Detroit, MI, 1981.
5. ASCE Manuals and Reports on Engineering Practice - No. 58, "Structural Analysis and Design of Nuclear Plant Facilities," 1980, pp. 237-241, 443-453.
6. Baker, E. H., Kovalevsky, L., and Rish, F. L., *Structural Analysis of Shells*, McGraw-Hill Book Co., 1972.
7. Billington, D. P., *Thin Shell Concrete Structures*, McGraw-Hill Book Co., 1982.
8. Crawford, D., "Guniting Tank Decommissioning Drilling Log," 1978.
9. Das, Braja M., *Fundamentals of Soil Dynamics*, Elsevier Science Publishing Co., New York, 1983.
10. DOE-STD-1020-Draft, *Natural Phenomena Hazards Design and Evaluation Criteria for DOE Facilities*, February 1994.
11. Freedman, S., "Properties of Materials for Reinforced Concrete," Ch. 6, *Handbook of Concrete Engineering*, Mark Fintel editor, Van Nostrand Reinhold Co., 1974.
12. Fricke, K., *Seismic Analysis of the Underground Guniting Tank at the ORNL South Tank Farm*, Report No. X-OE-313, Martin Marietta Energy Systems, Inc., Oak Ridge, TN, January 10, 1986.
13. Fricke, K., *Seismic Analysis of the Underground Guniting Tanks at the ORNL South Tank Farm*, Martin Marietta Energy Systems, Inc., Oak Ridge, TN, May 1993.
14. GTICES Systems Laboratory, *GTSTRUDL User's Manual*, Rev. M, Georgia Institute of Technology, Atlanta, GA, 1991.
15. Gupta, A. K., "Membrane Reinforcement in Shells," ASCE J. of the Structural Division, Vol. 107, No. ST1, January 1981, pp. 41-56.
16. Nazarian, H. N. and Hadjian, A. H., "Earthquake-Induced Lateral Soil Pressures on Structures," ASCE J. of the Geotechnical Eng. Div., Vol. 105, No. GT9, September 1979, pp. 1049-1066.

17. Newmark, N. M. and Rosenblueth, E., *Fundamentals of Earthquake Engineering*, Prentice-Hall, Inc., 1971, pp. 197-201.
18. Prakash, S., *Soil Dynamics*, McGraw-Hill Book Co., 1981, pp. 128-169.
19. Schnubrich, W. C., "Thin Shell Structure," Ch. 14, *Handbook of Concrete Engineering*, Mark Fintel editor, Van Nostrand Reinhold Co., 1974.
20. Seed, H. B. and Whitman, R. V., "Design of Earth Retaining Structures for Dynamic Loads," Proceedings, ASCE Specialty Conference on Lateral Stresses in the Ground and Design of Earth Retaining Structures, Ithaca, N.Y., 1970, pp. 103-147.
21. Timoshenko, S. and Goodier, J. N., *Theory of Elasticity*, McGraw-Hill Book Co., 1951.
22. Uniform Building Code, International Conference of Building Officials, Whittier, CA, 1991.
23. Video and Motion Picture Services, "ORNL Inactive Liquid Low Level Waste Storage Tank Video Inspection Summary," 1992.
24. Winterkorn, H.F. and Fang, H.Y., *Foundation Engineering Handbook*, Van Nostrand Reinhold Company, 1975.
25. Coats, D.W. and Murray, R.C., *Natural Phenomena Hazards Modeling Project: Seismic Hazard Models for Department of Energy Sites*, Lawrence Livermore National Laboratory, November 1984.
26. Roark, R.J. and Young, W.C., *Formulas for Stress and Strain*, McGraw-Hill Book Company, 1980.
27. Bandyopadhyay, K., Cornell, A., Costantino, C., Kennedy, R., Miller, C. and Veletsos, A., *Seismic Design and Evaluation Guidelines for the Department of Energy High-Level Waste Storage Tanks and Appurtenances*. BNL 52361 UC-406 UC-510, January 1993
28. Xu, J., Bandyopadhyay, K., Miller, C., and Costantino, C. *Spacing Effects on Seismic Responses of Underground Waste Storage Tanks*. PVP-Vol. 271, Proceedings, ASME Pressure Vessels and Piping Conference on Natural Hazard Phenomena and Mitigation, Minneapolis, Minnesota, 1994, pp. 13-18.
29. Spangler, M.G., Handy, R.L. *Soil Engineering*. 4th ed. 1982 Harper & Row, Publishers, N.Y.
30. Chen, W.F. *Plasticity in Reinforced Concrete*, 1982, McGraw-Hill Book Company.

LIST OF REFERENCE DRAWINGS

C3D-20539-X008	GUNITE TANK SLUDGE REMOVAL - LOCALITY MAP
C3E-20539-A019	GUNITE TANK SLUDGE REMOVAL - ALTERNATE MECHANICAL PLOT PLAN
C3E-20539-A021	GUNITE TANK SLUDGE REMOVAL - ALTERNATE ACTIVE SLURRY PIPING ARRANGEMENT
C3E-20539-X006	GUNITE TANK SLUDGE REMOVAL - SITE TOPOGRAPH AND SUBSURFACE DATA
C3E-20539-X007	GUNITE TANK SLUDGE REMOVAL - PLOT PLAN
C3E-20539-X009	GUNITE TANK SLUDGE REMOVAL - LOCATION PLAN
D-12205	PROCESS WASTE COLLECTION, RETENTION AND DISPOSAL
E-56866	25' & 50' DIA. GUNITE TANKS W-3 THRU W-10 DETAILS FROM 1943 DWGS.
E-56867	50' GUNITE TANKS W-5 THRU W-10 (5" GUNITE SLAB OVER EXISTING DOME) DETAILS FROM 1943 DWGS.
H-20539-EG002	AIR INLET & EXHAUST - PLAN & SECTIONS
H3D-20539-G004	GUNITE TANK SLUDGE REMOVAL - CONCEPTUAL VENTILATION SCHEMATIC
H3E-20539-G005	GUNITE TANK SLUDGE REMOVAL - TANK CONTAINMENT VENTILATION - ALTERNATE PLAN & NOTES
H3E-20539-G006	GUNITE TANK SLUDGE REMOVAL - TANK CONTAINMENT VENTILATION - DETAILS SH 1 (ALTERNATE)
H3E-20539-G007	GUNITE TANK SLUDGE REMOVAL - TANK CONTAINMENT VENTILATION - DETAILS SH 2 (ALTERNATE)
J3E-20539-E002	GUNITE TANK SLUDGE REMOVAL - MATERIAL BALANCE CONCEPTUAL DESIGN
J3E-20539-E006	GUNITE TANK SLUDGE REMOVAL - SLUICING OPERATION
P3D-20539-C014	GUNITE TANK SLUDGE REMOVAL - LIQUID LEVEL/DENSITY TUBING INSTALLATION & DETAILS
P3D-20539-C007	GUNITE TANK SLUDGE REMOVAL - SOUTH TANK FARM PIPING PLAN
P3E-20539-C027	GUNITE TANK SLUDGE REMOVAL - ALTERNATE SLURRY PIPING PLAN
P3E-20539-C028	GUNITE TANK SLUDGE REMOVAL - ALTERNATE SLURRY PIPING PLAN - SECTIONS & DETAILS
P3E-20539-C034	GUNITE TANK SLUDGE REMOVAL - ALTERNATE UTILITY PIPING PLAN
P3E-20539-C035	GUNITE TANK SLUDGE REMOVAL - ALTERNATE UTILITY PIPING PLAN - ELEV. & DETAILS TANK W-10
P3D-20539-C036	GUNITE TANK SLUDGE REMOVAL - ALTERNATE UTILITY PIPING PLAN - ELEV. & DETAILS TANKS W-5 THRU W-9
S3D-20539-B011	GUNITE TANK SLUDGE REMOVAL - WORK PLATFORMS - FOUNDATION PLAN
S3D-20539-B012	GUNITE TANK SLUDGE REMOVAL - FIXED WORK PLATFORM PLAN
S3D-20539-B013	GUNITE TANK SLUDGE REMOVAL - MOVABLE WORK PLATFORM PLAN
S3D-20539-B014	GUNITE TANK SLUDGE REMOVAL - WORK PLATFORMS SECTIONS
S3D-20539-B015	GUNITE TANK SLUDGE REMOVAL - FOUNDATION PLAN
S3D-20539-B033	GUNITE TANK SLUDGE REMOVAL - ALTERNATE FOUNDATION PLAN
V-68334	50-FT DIA. TANKS ARRANGEMENT PLAN & SECTIONS
X3E-20539-0001	GUNITE TANK SLUDGE REMOVAL - SLUICER ASSEMBLY LAYOUT
X3E-20539-0002	GUNITE TANK SLUDGE REMOVAL - SLUICER ASSEMBLY
X3E-20539-A001	GUNITE TANK SLUDGE REMOVAL - 34" CAISSON INSTALLATION DETAILS - ALTERNATE
X3E-20539-A050	GUNITE TANK SLUDGE REMOVAL - ALTERNATE SIDE OUTLET CAISSONS ORIENTATION - SH. NO. 1
X3E-20539-A051	GUNITE TANK SLUDGE REMOVAL - ALTERNATE SIDE OUTLET CAISSONS ORIENTATION - SH. NO. 2
X3E-20539-A068	GUNITE TANK SLUDGE REMOVAL - PUMP J-03 - SUCTION LEG SUPPORT AND PLATFORM ADAPTOR - DETAIL SH. NO. 3
X3E-20539-B001	GUNITE TANK SLUDGE REMOVAL - PROCESS EQUIPMENT LOCATION - PLAN VIEW
X3E-20539-B002	GUNITE TANK SLUDGE REMOVAL - PROCESS EQUIPMENT LOCATION - SECTIONS
X3E-20539-M100	GUNITE TANK SLUDGE REMOVAL - ALTERNATE - MIXING JET INSTALLATION

APPENDIX B
Peer Review Comments and Resolutions

Eric C. Drumm, P.E.
1239 Forest Brook Road
Knoxville, Tennessee 37919
(615) 584 - 9296

June 2, 1994

Mr. Tony Chung
SAIC
301 Laboratory Rd.
Oak Ridge, TN 37830

RE: Structural Analysis of Underground Guniting Tank

Dear Mr. Chung:

I have completed the requested peer review of the analysis of the underground buried guniting tanks. This review concentrated on the analysis assumptions and the estimation of lateral earth pressures acting on the tank.

It should be kept in mind that dynamic lateral earth pressures are difficult to estimate, and most methods assume cohesionless backfill materials. In this case, very limited information was available on the backfill soil. The crushed stone and clay material could have a wide range of properties depending upon the amount of clay, ranging from behavior expected of pure clay to that expected of pure gravel. This material was treated as crushed stone in the analysis, which is consistent with available design methods for estimating lateral earth pressures.

The calculations I reviewed were well organized, complete, and well documented. My review yielded the following comments which are listed by page number in the calculations:

- pp 1 Dynamic loadings - only horizontal dynamic soil pressures were used in the analysis. While this is perhaps appropriate, statement about vertical dynamic pressures is misleading.
- pp 2 UBC provisions for lateral forces yield 0.065g. On pp 12 and in subsequent calculations, horizontal acceleration of 0.14g was used. This is a reasonable value, and presumably was given by owner. It should be stated if this was an assumption.
- pp 7 Angle of internal friction for crushed stone and clay backfill assumed to be 40 degrees. Seems high if significant clay content, but conservative for static earth pressures.
- pp 8 Is "SURFACE FORCE PLANAR" command for uniformly distributed pressure (stress), with units of psi?
- pp 9 Dynamic earth pressure - assumption of flexible wall is valid. Rough check with characteristic length from beam-on-elastic foundation yields same conclusion. Calcs state that only active earth pressure is considered. In fact, at-rest pressures were used which is appropriate.

- pp 10 Dynamic earth pressure - the dynamic lateral earth pressures on the tank dome were neglected, assuming the "soil is self-supporting for horizontal earth pressure." The height of the dome is about half the height of the tank walls. Perhaps these pressures should be investigated. Lateral pressures on the dome are likely to induce significant stresses in the tank. However, this condition could be neglected if it is assumed that the induced stresses would be confined to the dome area, and hence would not affect the containment function.

Dynamic soil pressure was applied to one half of the tank as an independent loading condition. A reduction of the at-rest static pressures on the opposite side of the tank was acknowledged, but not considered since amount of reduction is unknown. Perhaps conditions with both static and dynamic pressures applied to one side and zero pressure to other side would govern, since the dynamic loading could reduce or remove static pressure. (Nice treatment of vertical and radial distribution of dynamic earth pressures.)

- pp 12 Dynamic earth pressure - assume ground acceleration of 0.14g (Same as pp 2 comment.) Is this OK? Dynamic earth pressures based on at-rest pressures are appropriate.

Computed earth pressures were compared with those from an alternative method (Richards et al. 1990). This method yields dynamic earth pressure coefficients equal to at-rest coefficients (0.35) provided the acceleration ratio, $\tan \theta$, is below 0.295, where:

$$\tan \theta = \frac{\frac{a_h}{g}}{1 - \frac{a_v}{g}}$$


For $a_h = 0.14g$, and assuming $a_v = 0.67 a_h$, $\tan \theta = 0.13$. This would yield $P_{total} = 1.35 P_{static}$ which compares with $P_{total} = 1.40 P_{static}$ used in analysis.

Reference: Richards, R., Elms, D.G., and Budhu, M. (1990) "Dynamic Fluidization of Soils" Journal of Geotechnical Engineering, ASCE, Vol. 116, No. 5, pp. 740-759.

- pp 17 Static and dynamic fluid pressures based on specific gravity of fluid = 1.25. Is this conservative, or representative of actual conditions? Was analysis conducted with no fluid? Do results support use of heavy fluid?
- pp 19 Hydrodynamic pressures - assumed hydrodynamic pressures act on tank walls only, neglected pressures on floor. Appropriate assumption perhaps, but it should be stated.
- pp 26 Hydrodynamic pressures - Applied pressures for the full tank case appear to be about 15% low, based on my understanding of the approach. Attached page shows sum of element stresses*contributory element area yields force of about 52 kips, when assumed force is 61 kips. Mistake could be mine, but this should be checked. Similar approach was used for loading due to half-full tank.

Most of these comments pertain to documentation of the calculations and the relevant assumptions, and therefore do not impact the calculations. However, the comments related to pages 10 and 26 should be reviewed. In spite of the comments above, this was a very well prepared series of calculations. If you have any questions about my review, please contact me at 974-7715 or 584-9296.

Sincerely,



Eric C. Drumm, P.E., Ph.D.

SAIC tank analysis, June 2, 1994

Hydro dynamic pressure check full tank, rigid part

check	theata n	Area	Ele stress	Ele Force
	90	226.50	270.7	61313.55
	88.27	226.40	10.4	2354.53
	84.8	225.57	10.34	2332.37
	81.3	223.89	10.18	2279.24
	77.9	221.47	9.96	2205.82
	74.4	218.16	9.66	2107.39
	70.9	214.03	9.31	1992.63
	67.5	209.26	8.91	1864.50
	64	203.58	8.42	1714.12
	60.6	197.33	7.9	1558.91
	57.1	190.17	7.34	1395.88
	53.6	182.31	6.77	1234.23
	50.2	174.02	6.14	1068.46
	46.7	164.84	5.52	909.92
	43.3	155.34	4.9	761.16
	39.8	144.98	4.28	620.54
	36.3	134.09	3.65	489.43
	32.9	123.03	3.09	380.16
	29.4	111.19	2.52	280.20
	26	99.29	2	198.58
	22.5	86.68	1.52	131.75
	19	73.74	1.11	81.85
	15.6	60.91	0.76	46.29
	12.1	47.48	0.46	21.84
	8.65	34.07	0.24	8.18
	5.19	20.49	0.08	1.64
	1.73	6.84	0.01	0.07

total 26039.66 pounds
 for 2 sides of tank x 2 52079.32
 compare with 61300 lbf $\approx 85\%$



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GLUNITE TANK

AUTHOR CNS DATE 6-10-94 JOB NO. _____

CHECKED BY _____ DATE _____ PAGE _____ of _____


Response to Comments by Dr. Eric C. Drumm

1. Vertical dynamic soil pressure was treated as an equivalent static load in the "load combination" with a multiplier $1 + \frac{2}{3}(0.14) = 1.093$ to the vertical static soil pressure. See added statement on page 9.
2. Agree. See added statement on page 11.
3. Agree. See added reference on page 6.
4. Yes. The "SURFACE FORCE PLANAR" denotes surface stress (psi) normal to the surface.
5. Agree. At-rest static soil pressure is an independent loading condition. Active lateral dynamic soil pressure is another independent loading condition with a magnitude as a fraction of the at-rest static soil pressure.
6. A Look at the static lateral earth pressure first. The soil on the top of the dome has a tendency to slide down hill. No part of the dome will be subjected to a lateral earth pressure in the same direction as the pressure on vertical wall.
(See next page for sketch.)

Response to Comments by Dr. Eric C. Drumm (cont.)

Static Lateral Earth Pressure

(At-rest)





Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

AUTHOR CNS DATE 6-16-94 JOB NO. _____

CHECKED BY _____ DATE _____ PAGE _____ of _____

Ref

Response to Comments by Dr. Eric C. Drumm (Cont.)

6. (Cont.)

B. Dynamic lateral earth pressure on dome is also not important. The reasoning is as follows:

a. Newmark stated in a paper published in 1965 (Fifth Rankine Lecture, "Effects of Earthquakes on Dams and Embankments," *Geotechnique*, Vol. 15, No. 2, Jan. 1965, pp. 139 to 159) that "ground motions in the direction of the downward slope tend to move the mass downhill, but ground motions in the upward direction along the slope leave the mass without relative additional motion except where these are extremely large in magnitude." Our ZPA is 0.14g, a relatively small seismic input for the tank.

Newmark's statement indicates that the soil over the dome may have an earthquake induced movement away from the dome, not toward the dome.

Stress follows movement, also away from the dome.

b. According to the theory on dynamic earth pressure:

dynamic earth pressure is a fraction of static earth pressure, and is applied to the structure in the same direction. If the static earth pressure is zero then the dynamic earth pressure is zero.

If the static earth pressure is in the "opposite" direction, then the dynamic earth pressure is also in the "opposite" direction.



Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

AUTHOR CNS DATE 6-10-94 JOB NO. _____

CHECKED BY _____ DATE _____ PAGE _____ of _____

Reference

Response to Comments by Dr. Eric C. Drumm (cont.)

6. (cont.)

B. (cont.)




- c. Although the composite structure of the soil-tank system is very strong, the structural character of the surrounding soil was ignored in the FE model. Soil could have been modeled as tridimensional elements. Soil was treated as load, not a part of the structure. This, in reality, states that there is no structural tie between soil and concrete. The portion of the soil cover (cross-hatched area, sect. D-D next page) higher than the top of dome is ineffective as far as internal dynamic earth pressure is concerned.
 - d. In over 50% of the roof area the lateral soil pressure is very small, if there is any, due to the small slope of the roof. See sketch next page.
 - e. Because the soil mass over the dome statically tends to act in a direction 180° out of phase with the soil mass acting on the tank wall, any lateral dynamic earth pressure on the dome would be also out of phase with the dynamic earth pressure on the tank wall.
- C. Dynamic soil load only applied from one half of the tank. A reduction of at-rest static soil pressure on the opposite side is possible. The soil dynamic theory available currently is only about increasing in soil pressure, not decreasing. We actually need to include soil on both sides of the tank as a part of the FE model which would be a SSI analysis with seismic input at the supports of the soil-tank system, currently unachievable with our computing facility.

Response to Comments by Dr. Eric C. Drumm

Dynamic Lateral Earth Pressure

In this area
the top of dome
is almost flat,
lateral force
can be ignored.
See Section 0-0

In these two
areas slope of
roof is also small,
see Section (2)-(2)





Science Applications
International Corporation
An Employee-Owned Company

301 Laboratory Road • P. O. Box 2501
Oak Ridge, Tennessee 37830
Phone: (615) 482-9031

SUBJECT

GUNITE TANK

AUTHOR CNS DATE 6-13-94 JOB NO. _____

CHECKED BY _____ DATE _____ PAGE _____ of _____

Reference

Response to Comments by Dr. Eric C. Drumm (cont.)

7. $ZPA = 0.14g$ is OK.
8. Spec. Gm of fluid = 1.25 is consistent with what was used in previous analysis
9. All elements of fundation are assumed supported, any vertical load will go to the ground and have no effect on the tank. See added statement on page 19.
10. The calculated stress will be applied to the entire area of the elements, not projected area. Input data are correct.

*Eric C. Drumm, P.E.
1239 Forest Brook Road
Knoxville, Tennessee 37919
(615) 584 - 9296*

July 21, 1994

Mr. Mike Kelly
SAIC
301 Laboratory Rd.
Oak Ridge, TN 37830

RE: Peer review of the analysis of the underground buried gunite tanks

Dear Mr. Kelly:

I have completed a review of the SAIC response to my peer review (comments of letter dated June 2, 1994) of the analysis of the underground buried gunite tanks. Each of my concerns has been adequately addressed in the response and revised calculations.

If there are further questions about my review, please contact me at 974-7715 or 584-9296.

Sincerely,



Eric C. Drumm, P.E., Ph.D.

APPENDIX C

Computer Code Verification

Computer Code Verification

In order to confirm that the computer program GTSTRUDL used in this analysis produces reliable results, another finite element program SuperSAP was used to duplicate the same problem and compare the predicted stresses at critical structural locations. The program SuperSAP, maintained and enhanced by Algor, Inc. of Pittsburgh, Pennsylvania., is a commercial version of SAP-IV (Structural Analysis Program). The following are the eight load cases that were analyzed by GTSTRUDL program and reported in the main text.

Static Load Cases:

1. $DL + H_{SD} + H_{SW}$ Empty Tank
2. $DL + H_{SD} + H_{SW} + F_S$ Full Tank
3. $DL + H_{SD} + H_{SW} + F_{\frac{1}{2}S}$ Half-full Tank

Dynamic Load Cases:

4. $DL + H_{SD} + H_{SW} + E + H_D$ Empty Tank + Earthquake
5. $DL + H_{SD} + H_{SW} + E + H_D + F_S + F_{D+}$ Full Tank (in-phase) + Earthquake
6. $DL + H_{SD} + H_{SW} + E + H_D + F_S + F_{D-}$ Full Tank (out-of-phase) + Earthquake
7. $DL + H_{SD} + H_{SW} + E + H_D + F_{\frac{1}{2}S} + F_{\frac{1}{2}D+}$ Half Tank (in-phase) + Earthquake
8. $DL + H_{SD} + H_{SW} + E + H_D + F_{\frac{1}{2}S} + F_{\frac{1}{2}D-}$ Half Tank (out-of-phase) + Earthquake

where:

- DL = tank structural self weight
- H_{SD} = static soil top pressure from earth over dome
- H_{SW} = static soil lateral pressure from earth adjacent to tank wall
- E = tank structural force induced by earthquake
- H_D = dynamic soil loading
- F_S = hydrostatic liquid pressure of full tank
- $F_{\frac{1}{2}S}$ = hydrostatic liquid pressure of half-full tank
- F_{D+} = hydrodynamic liquid pressure of full tank that is in-phase with the earthquake
- $F_{\frac{1}{2}D+}$ = hydrodynamic liquid pressure of half-full tank in-phase with the earthquake
- F_{D-} = hydrodynamic liquid pressure of full tank that is out-of-phase with the earthquake
- $F_{\frac{1}{2}D-}$ = hydrodynamic liquid pressure of half-full tank out-of-phase with the earthquake

To minimize the duplicated analysis efforts, only six load cases are analyzed using the SuperSAP program. The 6 load cases are:

Static Load Cases:

1. $DL + H_{SD} + H_{SW}$ Empty Tank
2. $DL + H_{SD} + H_{SW} + F_S$ Full Tank
3. $DL + H_{SD} + H_{SW} + F_{\frac{1}{2}S}$ Half-full Tank

Dynamic Load Cases:

4. $DL + H_{SD} + H_{SW} + E + H_D$ Empty Tank + Earthquake
5. $DL + H_{SD} + H_{SW} + E + H_D + F_S + F_{D+}$ Full Tank (in-phase) + Earthquake
7. $DL + H_{SD} + H_{SW} + E + H_D + F_{\frac{1}{2}S} + F_{\frac{1}{2}D+}$ Half Tank (in-phase) + Earthquake

The applied loading conditions and the exaggerated deflections for each loading condition are presented graphically in the pages that follow (Figures D-1 to D-16). In each of the graphic presentations, only one slice-cross-section view of the tank is shown. The uniform normal pressure, derived from static soil/fluid pressure to the element surfaces, is scaled and represented by an arrow head pointed perpendicular to the element surface. The nodal forces, derived from dynamic soil/fluid pressure, are scaled and represented by horizontal arrow heads. The deflections are exaggerated to show the direction of deflections.

Figure D-17 shows the predicted maximum tensile stress S_{yy} distribution along the vertical direction at the haunch during load case 1, empty tank during gravity load only. The maximum tensile stress occurs on the exterior surface just below the haunch.

Figure D-18 shows the predicted maximum tensile stress S_{yy} distribution along the vertical direction at the haunch during load case 4, empty tank during earthquake load. The maximum vertical tensile stress of 549 psi occurs on the exterior surface immediately below the haunch.

Figure D-19 is the comparison of predicted wall lateral (Z-direction) deflections by GTSTRUDL and SuperSAP.

Figure D-20 is the comparison of predicted tank dome (Y-direction) deflections by GTSTRUDL and SuperSAP.

Figure D-21 is the summary of stress predictions by GTSTRUDL and SuperSAP.

Comparative results from the two programs are summarized in the following paragraphs.

Deflections:

The maximum lateral wall expansion predicted by SuperSAP is 0.024 in. GTSTRUDL predicted the maximum displacement is 0.019 in. SuperSAP predicted the wall will cave in 0.009 in. GTSTRUDL predicted the wall will cave in 0.005 in. The point of curvature reversal predicted by both programs are at the same wall location. The vertical deflections predicted by both programs are about the same. However, the deflected curvature predicted by GTSTRUDL exhibits the characteristics of a stiffer structure.

Principle stress:

SuperSap program predict higher minimum principal stress (compression) by 50% . The maximum principal stress and shear stress are about the same.

Von Mises Stress:

SuperSap predicted higher Von Mises stress by 30%.

Directional Stress:

SuperSAP predicted overall lower shear stresses (S_{xy} , S_{xz} , and S_{yz}) by 40%. and lower radial stress (S_{zz}) by 50%. The vertical stress S_{yy} are about the same between GTSTRUDL and SuperSAP program.

Location of maximum stresses:

The general location of maximum stresses predicted by GTSTRUDL and SuperSAP are very close when the stresses are similar (e.g. maximum principal stress and S_{yy}).

Conclusion

The most critical stresses used in the analysis are the maximum principal stress and S_{yy} . The maximum principal stress was used for screening purpose. The direction stress S_{yy} is used for the evaluation of vertical wall strength below the haunch. These stresses are almost identical between two programs. It is concluded the results predicted by GTSTRUDL is adequate and compatible with the results obtained from the program SuperSAP.




Figure D-1. Load case 1, empty tank with gravity load only




Figure D-2. Load case 1, deflection of empty tank with gravity load only

Gunite tank, finite element model by SuperSap
Load case 2, full tank with gravity only




Figure D-3. Load case 2, full tank with gravity load only

Gunite tank, finite element model by SuperSap
Load case 2, full tank with gravity only




Figure D-4. Load case 2, deflection of full tank with gravity load only




Figure D-5. Load case 3, half tank with gravity load only




Figure D-6. Load case 3, deflection of half tank with gravity load only




Figure D-7. Load case 4, empty tank with earthquake (East) load,
slice angle = 90 degree from East direction




Figure D-8. Load case 4, empty tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 4, empty tank with earthquake




Figure D-9. Load case 4, deflection of empty tank with earthquake (East) load,
slice angle = 90 degree from East direction




Figure D-10. Load case 4, deflection of empty tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 6, full tank with earthquake




Figure D-11. Load case 6, full tank with earthquake (East) load,
slice angle = 90 degree from East direction

Gunitite tank, finite element model by SuperSap
Load case 6, full tank with earthquake




Figure D-12. Load case 6, full tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 6, full tank with earthquake




Figure D-13. Load case 6, deflection of full tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 6, full tank with earthquake




Figure D-14. Load case 6, deflection of full tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 7, half tank with earthquake




Figure D-15. Load case 7, half tank with earthquake (East) load,
slice angle = 0 degree from East direction

Gunite tank, finite element model by SuperSap
Load case 7, half tank with earthquake




Figure D-16. Load case 7, deflection of half tank with earthquake (East) load, slice angle = 0 degree from East direction




Figure D-17. Load case 1, stress contour of S_{yy} at the haunch, empty tank with gravity load only




Figure D-18. Load case 4, stress contour of S_{yy} at the haunch, empty tank with earthquake load

Gunite Tank Side Wall Deflections Gravity load only




Figure D-19. Load case 1, tank side-wall deflections, predicted by GTSTRUDL and SuperSAP, empty tank with gravity load only

Gunite Tank dome deflections Gravity load only




Figure D-20. Load case 1, tank dome deflection,
predicted by GTSTRUDL and SuperSAP,
empty tank with gravity load only

Type of Stress		static+selsmic load				static load			
stress	node	location	loading case	stress	node	location	loading case	stress	
directional tensile and shear stresses	Sxx	8123	edge of 30-in. (E) opening, top surface	psi	8123	edge of 30-in. (E) opening, top surface	1	psi	
	Syy	4070	one element below top of wall, exterior surface	529	4070	one element below top of wall, exterior surface	1	482	
	Szz	12130	one element below top of wall, exterior surface	549	8592	edge of (F)-opening, top surface	1	488	
	Sxy	12131	top of wall, exterior surface	457	11976	top of wall, exterior surface	1	420	
	Sxz	13991	top of wall, exterior surface	330	13991	top of wall, exterior surface	2	302	
	Syz	16006	top of wall, exterior surface	276	41	top of wall, exterior surface	1	246	
				324				302	
Principle Stress	Prin_max	4071	top of wall, exterior surface	674	13066	top of wall, interior surface	1	585	
	Prin-min	4076	top of wall, interior surface	978	4386	top of wall, interior surface	1	862	
Von Mises Stress	Tmax	12129	one element below top of wall, interior surface	474	4386	top of wall, interior surface	1	516	
		12129	one element below top of wall, interior surface	611	4386	top of wall, interior surface	1	545	

Summary of STRESSMODEL'S Evaluation of Quinze Rain									
Type of Stress		static+selsmic load				static load			
		node	location	loading case	stress	node	location	loading case	stress
directional tensile and shear stresses	Sxx	8128	edge of 30-in. (E) opening, bottom surface	6	psi	8128	edge of 30-in. (E) opening, bottom surface	2	psi
	Syy	4071	top of wall, exterior surface	4	542	4071	top of wall, exterior surface	1	488
	Szz	8592	edge of (F)-opening, top surface	4	549	8592	edge of (F)-opening, top surface	1	489
	Sxy	4071	top of wall, exterior surface	4	833	4071	top of wall, exterior surface	1	781
	Sxz	41	top of wall, exterior surface	4	544	41	top of wall, exterior surface	1	491
	Syz	8903	edge of (F)-opening, top surface	8	523	8903	edge of (F)-opening, top surface	3	488
Principle Stress	Prin_max	4071	top of wall, exterior surface	4	689	4071	top of wall, exterior surface	1	621
	Prin_min	8595	edge of 30-in. (E) opening, top surface	4	642	8595	edge of 30-in. (E) opening, top surface	1	597
Von Mises Stress	Tmax	4071	top of wall, exterior surface	4	467	4071	top of wall, exterior surface	1	420
		4071	top of wall, exterior surface	4	468	4071	top of wall, exterior surface	1	421

C-25

APPENDIX D
GTSTRU DL Input File

*TITLE 'X-10 TANK FARM GUNITE TANK ANALYSIS - SAIC 1995'
 STRUDL 'GUNITE96.GTS' '3-D MODEL OF X-10 TANK FARM GUNITE TANK, STATIC LOAD'
 \$ \$
 \$ INPUT FILE NAME: GUNITE96.GTS
 \$ DATE PREPARED: 03/21/95
 \$ RUN NUMBER: 01 03/24/95
 \$ OVERDOME EARTH PRESSURE IS APPLIED TO THE CORRECT (EXPOSED) FACE
 \$ ADD SOIL SPRING FROM SIDE
 \$ \$
 \$ R-DIRECTION, HORIZONTAL
 \$ THETA-DIRECTION, ANGLE PIVOTED ABOUT Y-AXIS, 0 DEG MEASURED FROM Z-AXIS,
 \$ Y-DIRECTION, VERTICAL UP
 \$ \$
 \$ X-DIRECTION, WEST
 \$ Y-VERTICAL, VERTICAL UP
 \$ Z-NORTH
 \$ \$
 UNIT INCH DEGREE POUND
 JOINT COORDINATES CYLINDRICAL
 GENERATE 104 JOINTS CYL ID 1, 155 R 204.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 2, 155 R 216.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 3, 155 R 228.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 4, 155 R 240.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 5, 155 R 252.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 6, 155 R 264.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 7, 155 R 276.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 8, 155 R 288.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 9, 155 R 300.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 10, 155 R 306.00 TH 0.0, 3.4615 LY -3.0 SUPPORT
 GENERATE 104 JOINTS CYL ID 11, 155 R 204.00 TH 0.000, 3.4615 LY 0.000
 GENERATE 104 JOINTS CYL ID 12, 155 R 216.00 TH 0.000, 3.4615 LY 0.000
 GENERATE 104 JOINTS CYL ID 13, 155 R 228.00 TH 0.000, 3.4615 LY 0.000
 GENERATE 104 JOINTS CYL ID 14, 155 R 240.00 TH 0.000, 3.4615 LY 0.000
 GENERATE 104 JOINTS CYL ID 15, 155 R 252.00 TH 0.000, 3.4615 LY 0.000
 GENERATE 104 JOINTS CYL ID 16, 155 R 264.00 TH 0.000, 3.4615 LY 1.500
 GENERATE 104 JOINTS CYL ID 17, 155 R 276.00 TH 0.000, 3.4615 LY 3.000
 GENERATE 104 JOINTS CYL ID 18, 155 R 288.00 TH 0.000, 3.4615 LY 4.500
 GENERATE 104 JOINTS CYL ID 19, 155 R 300.00 TH 0.000, 3.4615 LY 6.000
 GENERATE 104 JOINTS CYL ID 20, 155 R 306.00 TH 0.000, 3.4615 LY 6.000
 GENERATE 104 JOINTS CYL ID 21, 155 R 300.00 TH 0.000, 3.4615 LY 18.500
 GENERATE 104 JOINTS CYL ID 22, 155 R 306.00 TH 0.000, 3.4615 LY 18.500
 GENERATE 104 JOINTS CYL ID 23, 155 R 300.00 TH 0.000, 3.4615 LY 31.000

GENERATE 104 JOINTS CYL ID 24, 155 R 306.00 TH 0.000, 3.4615 LY 31.000
 GENERATE 104 JOINTS CYL ID 25, 155 R 300.00 TH 0.000, 3.4615 LY 43.500
 GENERATE 104 JOINTS CYL ID 26, 155 R 306.00 TH 0.000, 3.4615 LY 43.500
 GENERATE 104 JOINTS CYL ID 27, 155 R 300.00 TH 0.000, 3.4615 LY 56.000
 GENERATE 104 JOINTS CYL ID 28, 155 R 306.00 TH 0.000, 3.4615 LY 56.000
 GENERATE 104 JOINTS CYL ID 29, 155 R 300.00 TH 0.000, 3.4615 LY 65.000
 GENERATE 104 JOINTS CYL ID 30, 155 R 306.00 TH 0.000, 3.4615 LY 65.000
 GENERATE 104 JOINTS CYL ID 31, 155 R 300.00 TH 0.000, 3.4615 LY 74.000
 GENERATE 104 JOINTS CYL ID 32, 155 R 306.00 TH 0.000, 3.4615 LY 74.000
 GENERATE 104 JOINTS CYL ID 33, 155 R 300.00 TH 0.000, 3.4615 LY 86.000
 GENERATE 104 JOINTS CYL ID 34, 155 R 306.00 TH 0.000, 3.4615 LY 86.000
 GENERATE 104 JOINTS CYL ID 35, 155 R 300.00 TH 0.000, 3.4615 LY 98.000
 GENERATE 104 JOINTS CYL ID 36, 155 R 306.00 TH 0.000, 3.4615 LY 98.000
 GENERATE 104 JOINTS CYL ID 37, 155 R 300.00 TH 0.000, 3.4615 LY 110.000
 GENERATE 104 JOINTS CYL ID 38, 155 R 306.00 TH 0.000, 3.4615 LY 110.000
 GENERATE 104 JOINTS CYL ID 39, 155 R 300.00 TH 0.000, 3.4615 LY 122.000
 GENERATE 104 JOINTS CYL ID 40, 155 R 306.00 TH 0.000, 3.4615 LY 122.000
 GENERATE 104 JOINTS CYL ID 41, 155 R 306.00 TH 0.000, 3.4615 LY 132.000
 GENERATE 104 JOINTS CYL ID 42, 155 R 309.00 TH 0.000, 3.4615 LY 135.000
 GENERATE 104 JOINTS CYL ID 43, 155 R 309.00 TH 0.000, 3.4615 LY 147.000
 GENERATE 104 JOINTS CYL ID 44, 155 R 309.00 TH 0.000, 3.4615 LY 159.000
 GENERATE 104 JOINTS CYL ID 45, 155 R 309.00 TH 0.000, 3.4615 LY 166.000
 GENERATE 104 JOINTS CYL ID 46, 155 R 300.00 TH 0.000, 3.4615 LY 135.000
 GENERATE 104 JOINTS CYL ID 47, 155 R 299.62 TH 0.000, 3.4615 LY 141.036
 GENERATE 104 JOINTS CYL ID 48, 155 R 298.84 TH 0.000, 3.4615 LY 150.768
 GENERATE 104 JOINTS CYL ID 49, 155 R 299.13 TH 0.000, 3.4615 LY 160.430
 GENERATE 104 JOINTS CYL ID 50, 155 R 299.71 TH 0.000, 3.4615 LY 166.929
 GENERATE 104 JOINTS CYL ID 51, 155 R 290.00 TH 0.000, 3.4615 LY 143.000
 GENERATE 104 JOINTS CYL ID 52, 155 R 290.23 TH 0.000, 3.4615 LY 148.705
 GENERATE 104 JOINTS CYL ID 53, 155 R 289.70 TH 0.000, 3.4615 LY 156.110
 GENERATE 104 JOINTS CYL ID 54, 155 R 289.27 TH 0.000, 3.4615 LY 161.861
 GENERATE 104 JOINTS CYL ID 55, 155 R 290.43 TH 0.000, 3.4615 LY 167.857
 GENERATE 104 JOINTS CYL ID 56, 155 R 280.00 TH 0.000, 3.4615 LY 151.000
 GENERATE 104 JOINTS CYL ID 57, 155 R 281.77 TH 0.000, 3.4615 LY 152.936
 GENERATE 104 JOINTS CYL ID 58, 155 R 280.71 TH 0.000, 3.4615 LY 158.754
 GENERATE 104 JOINTS CYL ID 59, 155 R 279.41 TH 0.000, 3.4615 LY 163.291
 GENERATE 104 JOINTS CYL ID 60, 155 R 281.14 TH 0.000, 3.4615 LY 168.786
 GENERATE 104 JOINTS CYL ID 61, 155 R 270.00 TH 0.000, 3.4615 LY 159.000
 GENERATE 104 JOINTS CYL ID 62, 155 R 269.55 TH 0.000, 3.4615 LY 164.722
 GENERATE 104 JOINTS CYL ID 63, 155 R 271.86 TH 0.000, 3.4615 LY 169.714
 GENERATE 104 JOINTS CYL ID 64, 155 R 256.51 TH 0.000, 3.4615 LY 165.114
 GENERATE 104 JOINTS CYL ID 65, 155 R 258.52 TH 0.000, 3.4615 LY 169.692

GENERATE 104 JOINTS CYL ID 66, 155 R 258.73 TH 0.000, 3.4615 LY 170.150
GENERATE 104 JOINTS CYL ID 67, 155 R 260.74 TH 0.000, 3.4615 LY 174.727
GENERATE 104 JOINTS CYL ID 68, 155 R 245.48 TH 0.000, 3.4615 LY 169.839
GENERATE 104 JOINTS CYL ID 69, 155 R 247.41 TH 0.000, 3.4615 LY 174.454
GENERATE 104 JOINTS CYL ID 70, 155 R 247.60 TH 0.000, 3.4615 LY 174.915
GENERATE 104 JOINTS CYL ID 71, 155 R 249.53 TH 0.000, 3.4615 LY 179.530
GENERATE 104 JOINTS CYL ID 72, 155 R 234.36 TH 0.000, 3.4615 LY 174.356
GENERATE 104 JOINTS CYL ID 73, 155 R 236.20 TH 0.000, 3.4615 LY 179.005
GENERATE 104 JOINTS CYL ID 74, 155 R 236.39 TH 0.000, 3.4615 LY 179.470
GENERATE 104 JOINTS CYL ID 75, 155 R 238.22 TH 0.000, 3.4615 LY 184.120
GENERATE 104 JOINTS CYL ID 76, 155 R 223.16 TH 0.000, 3.4615 LY 178.662
GENERATE 104 JOINTS CYL ID 77, 155 R 224.91 TH 0.000, 3.4615 LY 183.346
GENERATE 104 JOINTS CYL ID 78, 155 R 225.09 TH 0.000, 3.4615 LY 183.814
GENERATE 104 JOINTS CYL ID 79, 155 R 226.84 TH 0.000, 3.4615 LY 188.498
GENERATE 104 JOINTS CYL ID 80, 155 R 211.88 TH 0.000, 3.4615 LY 182.757
GENERATE 104 JOINTS CYL ID 81, 155 R 213.55 TH 0.000, 3.4615 LY 187.472
GENERATE 104 JOINTS CYL ID 82, 155 R 213.71 TH 0.000, 3.4615 LY 187.944
GENERATE 104 JOINTS CYL ID 83, 155 R 215.37 TH 0.000, 3.4615 LY 192.660
GENERATE 104 JOINTS CYL ID 84, 155 R 200.53 TH 0.000, 3.4615 LY 186.638
GENERATE 104 JOINTS CYL ID 85, 155 R 202.10 TH 0.000, 3.4615 LY 191.385
GENERATE 104 JOINTS CYL ID 86, 155 R 202.26 TH 0.000, 3.4615 LY 191.859
GENERATE 104 JOINTS CYL ID 87, 155 R 203.83 TH 0.000, 3.4615 LY 196.605
GENERATE 104 JOINTS CYL ID 88, 155 R 189.10 TH 0.000, 3.4615 LY 190.306
GENERATE 104 JOINTS CYL ID 89, 155 R 190.59 TH 0.000, 3.4615 LY 195.081
GENERATE 104 JOINTS CYL ID 90, 155 R 190.74 TH 0.000, 3.4615 LY 195.558
GENERATE 104 JOINTS CYL ID 91, 155 R 192.22 TH 0.000, 3.4615 LY 200.333
GENERATE 104 JOINTS CYL ID 92, 155 R 177.61 TH 0.000, 3.4615 LY 193.757
GENERATE 104 JOINTS CYL ID 93, 155 R 179.01 TH 0.000, 3.4615 LY 198.559
GENERATE 104 JOINTS CYL ID 94, 155 R 179.14 TH 0.000, 3.4615 LY 199.039
GENERATE 104 JOINTS CYL ID 95, 155 R 180.54 TH 0.000, 3.4615 LY 203.841
GENERATE 104 JOINTS CYL ID 96, 155 R 166.06 TH 0.000, 3.4615 LY 196.992
GENERATE 104 JOINTS CYL ID 97, 155 R 167.36 TH 0.000, 3.4615 LY 201.819
GENERATE 104 JOINTS CYL ID 98, 155 R 167.49 TH 0.000, 3.4615 LY 202.302
GENERATE 104 JOINTS CYL ID 99, 155 R 168.79 TH 0.000, 3.4615 LY 207.129
GENERATE 104 JOINTS CYL ID 100, 155 R 154.44 TH 0.000, 3.4615 LY 200.009
GENERATE 104 JOINTS CYL ID 101, 155 R 155.65 TH 0.000, 3.4615 LY 204.860
GENERATE 104 JOINTS CYL ID 102, 155 R 155.77 TH 0.000, 3.4615 LY 205.345
GENERATE 104 JOINTS CYL ID 103, 155 R 156.99 TH 0.000, 3.4615 LY 210.196
GENERATE 104 JOINTS CYL ID 104, 155 R 142.77 TH 0.000, 3.4615 LY 202.806
GENERATE 104 JOINTS CYL ID 105, 155 R 143.89 TH 0.000, 3.4615 LY 207.679
GENERATE 104 JOINTS CYL ID 106, 155 R 144.00 TH 0.000, 3.4615 LY 208.166
GENERATE 104 JOINTS CYL ID 107, 155 R 145.12 TH 0.000, 3.4615 LY 213.039

GENERATE 104 JOINTS CYL ID 108, 155 R 131.05 TH 0.000, 3.4615 LY 205.383
GENERATE 104 JOINTS CYL ID 109, 155 R 132.08 TH 0.000, 3.4615 LY 210.277
GENERATE 104 JOINTS CYL ID 110, 155 R 132.18 TH 0.000, 3.4615 LY 210.766
GENERATE 104 JOINTS CYL ID 111, 155 R 133.21 TH 0.000, 3.4615 LY 215.659
GENERATE 104 JOINTS CYL ID 112, 155 R 119.29 TH 0.000, 3.4615 LY 207.740
GENERATE 104 JOINTS CYL ID 113, 155 R 120.22 TH 0.000, 3.4615 LY 212.651
GENERATE 104 JOINTS CYL ID 114, 155 R 120.32 TH 0.000, 3.4615 LY 213.142
GENERATE 104 JOINTS CYL ID 115, 155 R 121.25 TH 0.000, 3.4615 LY 218.054
GENERATE 104 JOINTS CYL ID 116, 155 R 107.48 TH 0.000, 3.4615 LY 209.874
GENERATE 104 JOINTS CYL ID 117, 155 R 108.32 TH 0.000, 3.4615 LY 214.802
GENERATE 104 JOINTS CYL ID 118, 155 R 108.41 TH 0.000, 3.4615 LY 215.295
GENERATE 104 JOINTS CYL ID 119, 155 R 109.25 TH 0.000, 3.4615 LY 220.224
GENERATE 104 JOINTS CYL ID 120, 155 R 95.637 TH 0.000, 3.4615 LY 211.786
GENERATE 104 JOINTS CYL ID 121, 155 R 96.387 TH 0.000, 3.4615 LY 216.729
GENERATE 104 JOINTS CYL ID 122, 155 R 96.462 TH 0.000, 3.4615 LY 217.223
GENERATE 104 JOINTS CYL ID 123, 155 R 97.212 TH 0.000, 3.4615 LY 222.167
GENERATE 104 JOINTS CYL ID 124, 155 R 83.756 TH 0.000, 3.4615 LY 213.474
GENERATE 104 JOINTS CYL ID 125, 155 R 84.413 TH 0.000, 3.4615 LY 218.431
GENERATE 104 JOINTS CYL ID 126, 155 R 84.479 TH 0.000, 3.4615 LY 218.926
GENERATE 104 JOINTS CYL ID 127, 155 R 85.136 TH 0.000, 3.4615 LY 223.883
GENERATE 104 JOINTS CYL ID 128, 155 R 71.846 TH 0.000, 3.4615 LY 214.939
GENERATE 104 JOINTS CYL ID 129, 155 R 72.410 TH 0.000, 3.4615 LY 219.907
GENERATE 104 JOINTS CYL ID 130, 155 R 72.466 TH 0.000, 3.4615 LY 220.404
GENERATE 104 JOINTS CYL ID 131, 155 R 73.030 TH 0.000, 3.4615 LY 225.372
GENERATE 104 JOINTS CYL ID 132, 155 R 59.911 TH 0.000, 3.4615 LY 216.179
GENERATE 104 JOINTS CYL ID 133, 155 R 60.381 TH 0.000, 3.4615 LY 221.157
GENERATE 104 JOINTS CYL ID 134, 155 R 60.428 TH 0.000, 3.4615 LY 221.654
GENERATE 104 JOINTS CYL ID 135, 155 R 60.898 TH 0.000, 3.4615 LY 226.632
GENERATE 104 JOINTS CYL ID 136, 155 R 47.954 TH 0.000, 3.4615 LY 217.194
GENERATE 104 JOINTS CYL ID 137, 155 R 48.330 TH 0.000, 3.4615 LY 222.180
GENERATE 104 JOINTS CYL ID 138, 155 R 48.368 TH 0.000, 3.4615 LY 222.678
GENERATE 104 JOINTS CYL ID 139, 155 R 48.744 TH 0.000, 3.4615 LY 227.664
GENERATE 104 JOINTS CYL ID 140, 155 R 35.981 TH 0.000, 3.4615 LY 217.984
GENERATE 104 JOINTS CYL ID 141, 155 R 36.263 TH 0.000, 3.4615 LY 222.976
GENERATE 104 JOINTS CYL ID 142, 155 R 36.291 TH 0.000, 3.4615 LY 223.475
GENERATE 104 JOINTS CYL ID 143, 155 R 36.573 TH 0.000, 3.4615 LY 228.467
GENERATE 104 JOINTS CYL ID 144, 155 R 24. TH 0.000, 3.4615 LY 218.55
GENERATE 104 JOINTS CYL ID 145, 155 R 24. TH 0.000, 3.4615 LY 223.55
GENERATE 104 JOINTS CYL ID 146, 155 R 24. TH 0.000, 3.4615 LY 224.05
GENERATE 104 JOINTS CYL ID 147, 155 R 24. TH 0.000, 3.4615 LY 229.06
GENERATE 104 JOINTS CYL ID 148, 155 R 18. TH 0.000, 3.4615 LY 218.75
GENERATE 104 JOINTS CYL ID 149, 155 R 18. TH 0.000, 3.4615 LY 223.75

GENERATE 104 JOINTS CYL ID 150, 155 R 18. TH 0.000, 3,4615 LY 224.25
 GENERATE 104 JOINTS CYL ID 151, 155 R 18. TH 0.000, 3,4615 LY 229.25
 GENERATE 104 JOINTS CYL ID 152, 155 R 12. TH 0.000, 3,4615 LY 219.00
 GENERATE 104 JOINTS CYL ID 153, 155 R 12. TH 0.000, 3,4615 LY 224.00
 GENERATE 104 JOINTS CYL ID 154, 155 R 12. TH 0.000, 3,4615 LY 224.50
 GENERATE 104 JOINTS CYL ID 155, 155 R 12. TH 0.000, 3,4615 LY 229.50

 \$ ECHO CONSOLE 'JOINT COORDIANTES FINISHED.....'

 \$ MODIFY DOME GEOMETRY TO PUT IN MANHOLES

 DELETIONS

 JOINTS -
 1618 1619 1620 1621 1622 1623 1624 1625 1626 1627 1628 1629 -
 1773 1774 1775 1776 1777 1778 1779 1780 1781 1782 1783 1784 -
 1928 1929 1930 1931 1932 1933 1934 1935 1936 1937 1938 1939 -
 6268 6269 6270 6271 6272 6273 6274 6275 6276 6277 6278 6279 -
 6423 6424 6425 6426 6427 6428 6429 6430 6431 6432 6433 6434 -
 6578 6579 6580 6581 6582 6583 6584 6585 6586 6587 6588 6589 -
 7966 7967 7968 7969 7970 7971 7972 7973 7974 7975 7976 -
 8121 8122 8123 8124 8125 8126 8127 8128 8129 8130 8131 -
 8276 8277 8278 8279 8280 8281 8282 8283 8284 8285 8286 -
 8586 8587 8588 8589 8590 8591 8592 8593 8594 8595 8596 -
 8741 8742 8743 8744 8745 8746 8747 8748 8749 8750 8751 -
 8896 8897 8898 8899 8900 8901 8902 8903 8904 8905 8906 -
 9678 9679 9680 9681 9682 9683 9684 9685 9686 9687 9688 9689 -
 9833 9834 9835 9836 9837 9838 9839 9840 9841 9842 9843 9844 -
 9988 9989 9990 9991 9992 9993 9994 9995 9996 9997 9998 9999 -
 14328 14329 14330 14331 14332 14333 14334 14335 14336 14337 14338 14339 -
 14483 14484 14485 14486 14487 14488 14489 14490 14491 14492 14493 14494 -
 14638 14639 14640 14641 14642 14643 14644 14645 14646 14647 14648 14649

ADDITION

JOINT COORDINATES CARTESIAN

1618	148.74	169.839	199.23	1624	140.69	179.470	194.81
1619	148.74	174.454	199.23	1625	140.69	184.120	194.81
1620	148.74	174.915	199.23	1626	138.13	178.662	185.99
1621	148.74	179.530	199.23	1627	138.13	183.346	185.99
1622	140.69	174.356	194.81	1628	138.13	183.814	185.99
1623	140.69	179.005	194.81	1629	138.13	188.498	185.99
				1773	157.56	169.839	196.67
				1774	157.56	174.454	196.67
				1775	157.56	174.915	196.67
				1776	157.56	179.530	196.67
				1777	150.06	174.356	187.3
				1778	150.06	179.005	187.3
				1779	150.06	179.470	187.3
				1780	150.06	184.120	187.3
				1781	142.56	178.662	177.94
				1782	142.56	183.346	177.94
				1783	142.56	183.814	177.94
				1784	142.56	188.498	177.94
				1928	161.99	169.839	188.62
				1929	161.99	174.454	188.62
				1930	161.99	174.915	188.62
				1931	161.99	179.530	188.62
				1932	159.42	174.356	179.8
				1933	159.42	179.005	179.8
				1934	159.42	179.470	179.8
				1935	159.42	184.120	179.8
				1936	151.38	178.662	175.38
				1937	151.38	183.346	175.38
				1938	151.38	183.814	175.38
				1939	151.38	188.498	175.38
				6268	161.99	169.839	-188.62
				6269	161.99	174.454	-188.62
				6270	161.99	174.915	-188.62
				6271	161.99	179.530	-188.62
				6272	159.42	174.356	-179.80
				6273	159.42	179.005	-179.80
				6274	159.42	179.470	-179.80
				6275	159.42	184.120	-179.80
				6276	151.38	178.662	-175.38
				6277	151.38	183.346	-175.38
				6278	151.38	183.814	-175.38
				6279	151.38	188.498	-175.38

6423	157.56	169.839	-196.67		8128	.000	168.36	-249.00
6424	157.56	174.454	-196.67		8129	.000	173.79	-249.00
6425	157.56	174.915	-196.67		8130	.000	174.33	-249.00
6426	157.56	179.530	-196.67		8131	.000	179.75	-249.00
6427	150.06	174.356	-187.3		8276	-10.61	156.73	-274.61
6428	150.06	179.005	-187.3		8277	-10.61	162.82	-274.61
6429	150.06	179.470	-187.3		8278	-10.61	168.34	-274.61
6430	150.06	184.120	-187.3		8279	-15.00	161.57	-264.00
6431	142.56	178.662	-177.94		8280	-15.00	167.06	-264.00
6432	142.56	183.346	-177.94		8281	-15.00	167.61	-264.00
6433	142.56	183.814	-177.94		8282	-15.00	173.09	-264.00
6434	142.56	188.498	-177.94		8283	-10.61	166.38	-253.39
6578	148.74	169.839	-199.23		8284	-10.61	171.83	-253.39
6579	148.74	174.454	-199.23		8285	-10.61	172.37	-253.39
6580	148.74	174.915	-199.23		8286	-10.61	177.81	-253.39
6581	148.74	179.530	-199.23		8586	-56.21	156.730	-262.32
6582	140.69	174.356	-194.81		8587	-56.21	162.82	-262.32
6583	140.69	179.005	-194.81		8588	-56.21	168.34	-262.32
6584	140.69	179.470	-194.81		8589	-53.54	165.114	-258.58
6585	140.69	184.120	-194.81		8590	-53.54	169.692	-258.58
6586	138.13	178.662	-185.99		8591	-53.54	170.150	-258.58
6587	138.13	183.346	-185.99		8592	-53.54	174.727	-258.58
6588	138.13	183.814	-185.99		8593	-54.3	169.839	-254.05
6589	138.13	188.498	-185.99		8594	-54.3	174.454	-254.05
7966	10.61	159.00	-274.61		8595	-54.3	174.915	-254.05
7967	10.61	162.82	-274.61		8596	-54.3	179.530	-254.05
7968	10.61	168.34	-274.61		8741	-60.74	154.71	-263.08
7969	15.00	161.57	-264.00		8742	-60.74	160.82	-263.08
7970	15.00	167.06	-264.00		8743	-60.74	166.36	-263.08
7971	15.00	167.61	-264.00		8744	-59.39	165.114	-257.23
7972	15.00	173.09	-264.00		8745	-59.39	169.692	-257.23
7973	10.61	166.38	-253.39		8746	-59.39	170.150	-257.23
7974	10.61	171.83	-253.39		8747	-59.39	174.727	-257.23
7975	10.61	172.37	-253.39		8748	-58.04	169.839	-251.39
7976	10.61	177.81	-253.39		8749	-58.04	174.454	-251.39
8121	.000	154.71	-279.00		8750	-58.04	174.915	-251.39
8122	.000	160.82	-279.00		8751	-58.04	179.530	-251.39
8123	.000	166.36	-279.00		8896	-64.48	156.73	-260.41
8124	.000	161.77	-264.00		8897	-64.48	162.82	-260.41
8125	.000	167.26	-264.00		8898	-64.48	168.34	-260.41
8126	.000	167.80	-264.00		8899	-65.23	165.114	-255.88
8127	.000	173.28	-264.00		8900	-65.23	169.692	-255.88

8901	-65.23	170.150	-255.88	14328	-161.99	169.839	188.62
8902	-65.23	174.727	-255.88	14329	-161.99	174.454	188.62
8903	-62.57	169.839	-252.15	14330	-161.99	174.915	188.62
8904	-62.57	174.454	-252.15	14331	-161.99	179.530	188.62
8905	-62.57	174.915	-252.15	14332	-159.42	174.356	179.8
8906	-62.57	179.530	-252.15	14333	-159.42	179.005	179.8
9678	-148.74	169.839	-199.23	14334	-159.42	179.470	179.8
9679	-148.74	174.454	-199.23	14335	-159.42	184.120	179.8
9680	-148.74	174.915	-199.23	14336	-151.38	178.662	175.38
9681	-148.74	179.530	-199.23	14337	-151.38	183.346	175.38
9682	-140.69	174.356	-194.81	14338	-151.38	183.814	175.38
9683	-140.69	179.005	-194.81	14339	-151.38	188.498	175.38
9684	-140.69	179.470	-194.81	14483	-157.56	169.839	196.67
9685	-140.69	184.120	-194.81	14484	-157.56	174.454	196.67
9686	-138.13	178.662	-185.99	14485	-157.56	174.915	196.67
9687	-138.13	183.346	-185.99	14486	-157.56	179.530	196.67
9688	-138.13	183.814	-185.99	14487	-150.06	174.356	187.3
9689	-138.13	188.498	-185.99	14488	-150.06	179.005	187.3
9833	-157.56	169.839	-196.67	14489	-150.06	179.470	187.3
9834	-157.56	174.454	-196.67	14490	-150.06	184.120	187.3
9835	-157.56	174.915	-196.67	14491	-142.56	178.662	177.94
9836	-157.56	179.530	-196.67	14492	-142.56	183.346	177.94
9837	-150.06	174.356	-187.30	14493	-142.56	183.814	177.94
9838	-150.06	179.005	-187.30	14494	-142.56	188.498	177.94
9839	-150.06	179.470	-187.30	14638	-148.74	169.839	199.23
9840	-150.06	184.120	-187.30	14639	-148.74	174.454	199.23
9841	-142.56	178.662	-177.94	14640	-148.74	174.915	199.23
9842	-142.56	183.346	-177.94	14641	-148.74	179.530	199.23
9843	-142.56	183.814	-177.94	14642	-140.69	174.356	194.81
9844	-142.56	188.498	-177.94	14643	-140.69	179.005	194.81
9988	-161.99	169.839	-188.62	14644	-140.69	179.470	194.81
9989	-161.99	174.454	-188.62	14645	-140.69	184.120	194.81
9990	-161.99	174.915	-188.62	14646	-138.13	178.662	185.99
9991	-161.99	179.530	-188.62	14647	-138.13	183.346	185.99
9992	-159.42	174.356	-179.8	14648	-138.13	183.814	185.99
9993	-159.42	179.005	-179.8	14649	-138.13	188.498	185.99
9994	-159.42	179.470	-179.8	\$ END OF DOME MODIFICATION			
9995	-159.42	184.120	-179.8	\$ ADD SOIL SPRINGS COORDINATES			
9996	-151.38	178.662	-175.38	GENERATE 104 JOINTS CYL ID 16121, 17 R 316.00 TH 0.000, 3.4615 LY -3.000			
9997	-151.38	183.346	-175.38	GENERATE 104 JOINTS CYL ID 16122, 17 R 316.00 TH 0.000, 3.4615 LY 6.000			
9998	-151.38	183.814	-175.38	GENERATE 104 JOINTS CYL ID 16123, 17 R 316.00 TH 0.000, 3.4615 LY 18.500			
9999	-151.38	188.498	-175.38				

GENERATE 104 JOINTS CYL ID 16124, 17 R 316.00 TH 0.000, 3.4615 LY 31.000
GENERATE 104 JOINTS CYL ID 16125, 17 R 316.00 TH 0.000, 3.4615 LY 43.500
GENERATE 104 JOINTS CYL ID 16126, 17 R 316.00 TH 0.000, 3.4615 LY 56.000
GENERATE 104 JOINTS CYL ID 16127, 17 R 316.00 TH 0.000, 3.4615 LY 65.000
GENERATE 104 JOINTS CYL ID 16128, 17 R 316.00 TH 0.000, 3.4615 LY 74.000
GENERATE 104 JOINTS CYL ID 16129, 17 R 316.00 TH 0.000, 3.4615 LY 86.000
GENERATE 104 JOINTS CYL ID 16130, 17 R 316.00 TH 0.000, 3.4615 LY 98.000
GENERATE 104 JOINTS CYL ID 16131, 17 R 316.00 TH 0.000, 3.4615 LY 110.000
GENERATE 104 JOINTS CYL ID 16132, 17 R 316.00 TH 0.000, 3.4615 LY 122.000
GENERATE 104 JOINTS CYL ID 16133, 17 R 316.00 TH 0.000, 3.4615 LY 132.000
GENERATE 104 JOINTS CYL ID 16134, 17 R 319.00 TH 0.000, 3.4615 LY 135.000
GENERATE 104 JOINTS CYL ID 16135, 17 R 319.00 TH 0.000, 3.4615 LY 147.000
GENERATE 104 JOINTS CYL ID 16136, 17 R 319.00 TH 0.000, 3.4615 LY 159.000
GENERATE 104 JOINTS CYL ID 16137, 17 R 319.00 TH 0.000, 3.4615 LY 166.000
\$ END OF SOIL SPRINGS

STATUS SUPPORT 16121 TO 17888

TYPE TRIDIMENSIONAL
ELEMENT INCIDENCE

GEN 103 ELE ID 1 INC 81 F 11 INC 155 T 1 T 2 T 12 T 166 T 156 T 157 T 167
GEN 103 ELE ID 2 INC 81 F 12 INC 155 T 2 T 3 T 13 T 167 T 157 T 158 T 168
GEN 103 ELE ID 3 INC 81 F 13 INC 155 T 3 T 4 T 14 T 168 T 158 T 159 T 169
GEN 103 ELE ID 4 INC 81 F 14 INC 155 T 4 T 5 T 15 T 169 T 159 T 160 T 170
GEN 103 ELE ID 5 INC 81 F 15 INC 155 T 5 T 6 T 16 T 170 T 160 T 161 T 171
GEN 103 ELE ID 6 INC 81 F 16 INC 155 T 6 T 7 T 17 T 171 T 161 T 162 T 172
GEN 103 ELE ID 7 INC 81 F 17 INC 155 T 7 T 8 T 18 T 172 T 162 T 163 T 173
GEN 103 ELE ID 8 INC 81 F 18 INC 155 T 8 T 9 T 19 T 173 T 163 T 164 T 174
GEN 103 ELE ID 9 INC 81 F 9 INC 155 T 10 T 20 T 19 T 164 T 165 T 175 T 174
GEN 103 ELE ID 10 INC 81 F 19 INC 155 T 20 T 22 T 21 T 174 T 175 T 177 T 176
GEN 103 ELE ID 11 INC 81 F 21 INC 155 T 22 T 24 T 23 T 176 T 177 T 179 T 178
GEN 103 ELE ID 12 INC 81 F 23 INC 155 T 24 T 26 T 25 T 178 T 179 T 181 T 180
GEN 103 ELE ID 13 INC 81 F 25 INC 155 T 26 T 28 T 27 T 180 T 181 T 183 T 182
GEN 103 ELE ID 14 INC 81 F 27 INC 155 T 28 T 30 T 29 T 182 T 183 T 185 T 184
GEN 103 ELE ID 15 INC 81 F 29 INC 155 T 30 T 32 T 31 T 184 T 185 T 187 T 186
GEN 103 ELE ID 16 INC 81 F 31 INC 155 T 32 T 34 T 33 T 186 T 187 T 189 T 188
GEN 103 ELE ID 17 INC 81 F 33 INC 155 T 34 T 36 T 35 T 188 T 189 T 191 T 190
GEN 103 ELE ID 18 INC 81 F 35 INC 155 T 36 T 38 T 37 T 190 T 191 T 193 T 192
GEN 103 ELE ID 19 INC 81 F 37 INC 155 T 38 T 40 T 39 T 192 T 193 T 195 T 194
GEN 103 ELE ID 20 INC 81 F 39 INC 155 T 40 T 41 T 46 T 194 T 195 T 196 T 201
GEN 103 ELE ID 21 INC 81 F 41 INC 155 T 42 T 47 T 46 T 196 T 197 T 202 T 201

GEN 103 ELE ID 22 INC 81 F 47 INC 155 T 42 T 43 T 48 T 202 T 197 T 198 T 203
GEN 103 ELE ID 23 INC 81 F 48 INC 155 T 43 T 44 T 49 T 203 T 198 T 199 T 204
GEN 103 ELE ID 24 INC 81 F 49 INC 155 T 44 T 45 T 50 T 204 T 199 T 200 T 205
GEN 103 ELE ID 25 INC 81 F 46 INC 155 T 47 T 52 T 51 T 201 T 202 T 207 T 206
GEN 103 ELE ID 26 INC 81 F 52 INC 155 T 47 T 48 T 53 T 207 T 202 T 203 T 208
GEN 103 ELE ID 27 INC 81 F 53 INC 155 T 48 T 49 T 54 T 208 T 203 T 204 T 209
GEN 103 ELE ID 28 INC 81 F 54 INC 155 T 49 T 50 T 55 T 209 T 204 T 205 T 210
GEN 103 ELE ID 29 INC 81 F 51 INC 155 T 52 T 57 T 56 T 206 T 207 T 212 T 211
GEN 103 ELE ID 30 INC 81 F 57 INC 155 T 52 T 53 T 58 T 212 T 207 T 208 T 213
GEN 103 ELE ID 31 INC 81 F 58 INC 155 T 53 T 54 T 59 T 213 T 208 T 209 T 214
GEN 103 ELE ID 32 INC 81 F 59 INC 155 T 54 T 55 T 60 T 214 T 209 T 210 T 215
GEN 103 ELE ID 33 INC 81 F 56 INC 155 T 57 T 58 T 61 T 211 T 212 T 213 T 216
GEN 103 ELE ID 34 INC 81 F 61 INC 155 T 58 T 59 T 62 T 216 T 213 T 214 T 217
GEN 103 ELE ID 35 INC 81 F 62 INC 155 T 59 T 60 T 63 T 217 T 214 T 215 T 218
GEN 103 ELE ID 36 INC 81 F 61 INC 155 T 62 T 65 T 64 T 216 T 217 T 220 T 219
GEN 103 ELE ID 37 INC 81 F 64 INC 155 T 65 T 69 T 68 T 219 T 220 T 224 T 223
GEN 103 ELE ID 38 INC 81 F 68 INC 155 T 69 T 73 T 72 T 223 T 224 T 228 T 227
GEN 103 ELE ID 39 INC 81 F 76 INC 155 T 72 T 73 T 77 T 231 T 227 T 228 T 232
GEN 103 ELE ID 40 INC 81 F 80 INC 155 T 76 T 77 T 81 T 235 T 231 T 232 T 236
GEN 103 ELE ID 41 INC 81 F 84 INC 155 T 80 T 81 T 85 T 239 T 235 T 236 T 240
GEN 103 ELE ID 42 INC 81 F 88 INC 155 T 84 T 85 T 89 T 243 T 239 T 240 T 244
GEN 103 ELE ID 43 INC 81 F 92 INC 155 T 88 T 89 T 93 T 247 T 243 T 244 T 248
GEN 103 ELE ID 44 INC 81 F 96 INC 155 T 92 T 93 T 97 T 251 T 247 T 248 T 252
GEN 103 ELE ID 45 INC 81 F 100 INC 155 T 96 T 97 T 101 T 255 T 251 T 252 T 256
GEN 103 ELE ID 46 INC 81 F 104 INC 155 T 100 T 101 T 105 T 259 T 255 T 256 T 260
GEN 103 ELE ID 47 INC 81 F 108 INC 155 T 104 T 105 T 109 T 263 T 259 T 260 T 264
GEN 103 ELE ID 48 INC 81 F 112 INC 155 T 108 T 109 T 113 T 267 T 263 T 264 T 268
GEN 103 ELE ID 49 INC 81 F 116 INC 155 T 112 T 113 T 117 T 271 T 267 T 268 T 272
GEN 103 ELE ID 50 INC 81 F 120 INC 155 T 116 T 117 T 121 T 275 T 271 T 272 T 276
GEN 103 ELE ID 51 INC 81 F 124 INC 155 T 120 T 121 T 125 T 279 T 275 T 276 T 280
GEN 103 ELE ID 52 INC 81 F 128 INC 155 T 124 T 125 T 129 T 283 T 279 T 280 T 284
GEN 103 ELE ID 53 INC 81 F 132 INC 155 T 128 T 129 T 133 T 287 T 283 T 284 T 288
GEN 103 ELE ID 54 INC 81 F 136 INC 155 T 132 T 133 T 137 T 291 T 287 T 288 T 292
GEN 103 ELE ID 55 INC 81 F 140 INC 155 T 136 T 137 T 141 T 295 T 291 T 292 T 296
GEN 103 ELE ID 56 INC 81 F 144 INC 155 T 140 T 141 T 145 T 299 T 295 T 296 T 300
GEN 103 ELE ID 57 INC 81 F 148 INC 155 T 144 T 145 T 149 T 303 T 299 T 300 T 304
GEN 103 ELE ID 58 INC 81 F 152 INC 155 T 148 T 149 T 153 T 307 T 303 T 304 T 308
GEN 103 ELE ID 59 INC 81 F 62 INC 155 T 63 T 67 T 66 T 217 T 218 T 222 T 221
GEN 103 ELE ID 60 INC 81 F 66 INC 155 T 67 T 71 T 70 T 221 T 222 T 226 T 225
GEN 103 ELE ID 61 INC 81 F 70 INC 155 T 71 T 75 T 74 T 225 T 226 T 230 T 229
GEN 103 ELE ID 62 INC 81 F 78 INC 155 T 74 T 75 T 79 T 233 T 229 T 230 T 234
GEN 103 ELE ID 63 INC 81 F 82 INC 155 T 78 T 79 T 83 T 237 T 233 T 234 T 238

GEN 103 ELE ID 64 INC 81 F 86 INC 155 T 82 T 83 T 87 T 241 T 237 T 238 T 242
 GEN 103 ELE ID 65 INC 81 F 90 INC 155 T 86 T 87 T 91 T 245 T 241 T 242 T 246
 GEN 103 ELE ID 66 INC 81 F 94 INC 155 T 90 T 91 T 95 T 249 T 245 T 246 T 250
 GEN 103 ELE ID 67 INC 81 F 98 INC 155 T 94 T 95 T 99 T 253 T 249 T 250 T 254
 GEN 103 ELE ID 68 INC 81 F 102 INC 155 T 98 T 99 T 103 T 257 T 253 T 254 T 258
 GEN 103 ELE ID 69 INC 81 F 106 INC 155 T 102 T 103 T 107 T 261 T 257 T 258 T 262
 GEN 103 ELE ID 70 INC 81 F 110 INC 155 T 106 T 107 T 111 T 265 T 261 T 262 T 266
 GEN 103 ELE ID 71 INC 81 F 114 INC 155 T 110 T 111 T 115 T 269 T 265 T 266 T 270
 GEN 103 ELE ID 72 INC 81 F 118 INC 155 T 114 T 115 T 119 T 273 T 269 T 270 T 274
 GEN 103 ELE ID 73 INC 81 F 122 INC 155 T 118 T 119 T 123 T 277 T 273 T 274 T 278
 GEN 103 ELE ID 74 INC 81 F 126 INC 155 T 122 T 123 T 127 T 281 T 277 T 278 T 282
 GEN 103 ELE ID 75 INC 81 F 130 INC 155 T 126 T 127 T 131 T 285 T 281 T 282 T 286
 GEN 103 ELE ID 76 INC 81 F 134 INC 155 T 130 T 131 T 135 T 289 T 285 T 286 T 290
 GEN 103 ELE ID 77 INC 81 F 138 INC 155 T 134 T 135 T 139 T 293 T 289 T 290 T 294
 GEN 103 ELE ID 78 INC 81 F 142 INC 155 T 138 T 139 T 143 T 297 T 293 T 294 T 298
 GEN 103 ELE ID 79 INC 81 F 146 INC 155 T 142 T 143 T 147 T 301 T 297 T 298 T 302
 GEN 103 ELE ID 80 INC 81 F 150 INC 155 T 146 T 147 T 151 T 305 T 301 T 302 T 306
 GEN 103 ELE ID 81 INC 81 F 154 INC 155 T 150 T 151 T 155 T 309 T 305 T 306 T 310

\$ CONNECT ELEMENTS BEWTWEEN FIRST AND LAST SLICES PLAN

ELEMENT INCIDENCE

8344	15976	15966	15967	15977	11	1	2	12
8345	15977	15967	15968	15978	12	2	3	13
8346	15978	15968	15969	15979	13	3	4	14
8347	15979	15969	15970	15980	14	4	5	15
8348	15980	15970	15971	15981	15	5	6	16
8349	15981	15971	15972	15982	16	6	7	17
8350	15982	15972	15973	15983	17	7	8	18
8351	15983	15973	15974	15984	18	8	9	19
8352	15974	15975	15985	15984	9	10	20	19
8353	15984	15985	15987	15986	19	20	22	21
8354	15986	15987	15989	15988	21	22	24	23
8355	15988	15989	15991	15990	23	24	26	25
8356	15990	15991	15993	15992	25	26	28	27
8357	15992	15993	15995	15994	27	28	30	29
8358	15994	15995	15997	15996	29	30	32	31
8359	15996	15997	15999	15998	31	32	34	33
8360	15998	15999	16001	16000	33	34	36	35
8361	16000	16001	16003	16002	35	36	38	37
8362	16002	16003	16005	16004	37	38	40	39
8363	16004	16005	16006	16011	39	40	41	46
8364	16006	16007	16012	16011	41	42	47	46

8365	16012	16007	16008	16013	47	42	43	48
8366	16013	16008	16009	16014	48	43	44	49
8367	16014	16009	16010	16015	49	44	45	50
8368	16011	16012	16017	16016	46	47	52	51
8369	16017	16012	16013	16018	52	47	48	53
8370	16018	16013	16014	16019	53	48	49	54
8371	16019	16014	16015	16020	54	49	50	55
8372	16016	16017	16022	16021	51	52	57	56
8373	16022	16017	16018	16023	57	52	53	58
8374	16023	16018	16019	16024	58	53	54	59
8375	16024	16019	16020	16025	59	54	55	60
8376	16021	16022	16023	16026	56	57	58	61
8377	16026	16023	16024	16027	61	58	59	62
8378	16027	16024	16025	16028	62	59	60	63
8379	16026	16027	16030	16029	61	62	65	64
8380	16029	16030	16034	16033	64	65	69	68
8381	16033	16034	16038	16037	68	69	73	72
8382	16041	16037	16038	16042	76	72	73	77
8383	16045	16041	16042	16046	80	76	77	81
8384	16049	16045	16046	16050	84	80	81	85
8385	16053	16049	16050	16054	88	84	85	89
8386	16057	16053	16054	16058	92	88	89	93
8387	16061	16057	16058	16062	96	92	93	97
8388	16065	16061	16062	16066	100	96	97	101
8389	16069	16065	16066	16070	104	100	101	105
8390	16073	16069	16070	16074	108	104	105	109
8391	16077	16073	16074	16078	112	108	109	113
8392	16081	16077	16078	16082	116	112	113	117
8393	16085	16081	16082	16086	120	116	117	121
8394	16089	16085	16086	16090	124	120	121	125
8395	16093	16089	16090	16094	128	124	125	129
8396	16097	16093	16094	16098	132	128	129	133
8397	16101	16097	16098	16102	136	132	133	137
8398	16105	16101	16102	16106	140	136	137	141
8399	16109	16105	16106	16110	144	140	141	145
8400	16113	16109	16110	16114	148	144	145	149
8401	16117	16113	16114	16118	152	148	149	153
8402	16027	16028	16032	16031	62	63	67	66
8403	16031	16032	16036	16035	66	67	71	70
8404	16035	16036	16040	16039	70	71	75	74
8405	16043	16039	16040	16044	78	74	75	79
8406	16047	16043	16044	16048	82	78	79	83

8407 16051 16047 16048 16052 86 82 83 87
8408 16055 16051 16052 16056 90 86 87 91
8409 16059 16055 16056 16060 94 90 91 95
8410 16063 16059 16060 16064 98 94 95 99
8411 16067 16063 16064 16068 102 98 99 103
8412 16071 16067 16068 16072 106 102 103 107
8413 16075 16071 16072 16076 110 106 107 111
8414 16079 16075 16076 16080 114 110 111 115
8415 16083 16079 16080 16084 118 114 115 119
8416 16087 16083 16084 16088 122 118 119 123
8417 16091 16087 16088 16092 126 122 123 127
8418 16095 16091 16092 16096 130 126 127 131
8419 16099 16095 16096 16100 134 130 131 135
8420 16103 16099 16100 16104 138 134 135 139
8421 16107 16103 16104 16108 142 138 139 143
8422 16111 16107 16108 16112 146 142 143 147
8423 16115 16111 16112 16116 150 146 147 151
8424 16119 16115 16116 16120 154 150 151 155

TYPE SPACE TRUSS

MEMBER INCIDENCE

GEN 104 MEM ID 10001 INC 23 F 65 INC 155 T 66
GEN 104 MEM ID 10002 INC 23 F 69 INC 155 T 70
GEN 104 MEM ID 10003 INC 23 F 73 INC 155 T 74
GEN 104 MEM ID 10004 INC 23 F 77 INC 155 T 78
GEN 104 MEM ID 10005 INC 23 F 81 INC 155 T 82
GEN 104 MEM ID 10006 INC 23 F 85 INC 155 T 86
GEN 104 MEM ID 10007 INC 23 F 89 INC 155 T 90
GEN 104 MEM ID 10008 INC 23 F 93 INC 155 T 94
GEN 104 MEM ID 10009 INC 23 F 97 INC 155 T 98
GEN 104 MEM ID 10010 INC 23 F 101 INC 155 T 102
GEN 104 MEM ID 10011 INC 23 F 105 INC 155 T 106
GEN 104 MEM ID 10012 INC 23 F 109 INC 155 T 110
GEN 104 MEM ID 10013 INC 23 F 113 INC 155 T 114
GEN 104 MEM ID 10014 INC 23 F 117 INC 155 T 118
GEN 104 MEM ID 10015 INC 23 F 121 INC 155 T 122
GEN 104 MEM ID 10016 INC 23 F 125 INC 155 T 126
GEN 104 MEM ID 10017 INC 23 F 129 INC 155 T 130
GEN 104 MEM ID 10018 INC 23 F 133 INC 155 T 134
GEN 104 MEM ID 10019 INC 23 F 137 INC 155 T 138
GEN 104 MEM ID 10020 INC 23 F 141 INC 155 T 142
GEN 104 MEM ID 10021 INC 23 F 145 INC 155 T 146

GEN 104 MEM ID 10022 INC 23 F 149 INC 155 T 150
GEN 104 MEM ID 10023 INC 23 F 153 INC 155 T 154

\$ ADD SOIL SPRINGS

TYPE SPACE TRUSS

MEMBER INCIDENCE

GEN 104 MEM ID 20001 INC 17 F 10 INC 155 T 16121 INC 17
GEN 104 MEM ID 20002 INC 17 F 20 INC 155 T 16122 INC 17
GEN 104 MEM ID 20003 INC 17 F 22 INC 155 T 16123 INC 17
GEN 104 MEM ID 20004 INC 17 F 24 INC 155 T 16124 INC 17
GEN 104 MEM ID 20005 INC 17 F 26 INC 155 T 16125 INC 17
GEN 104 MEM ID 20006 INC 17 F 28 INC 155 T 16126 INC 17
GEN 104 MEM ID 20007 INC 17 F 30 INC 155 T 16127 INC 17
GEN 104 MEM ID 20008 INC 17 F 32 INC 155 T 16128 INC 17
GEN 104 MEM ID 20009 INC 17 F 34 INC 155 T 16129 INC 17
GEN 104 MEM ID 20010 INC 17 F 36 INC 155 T 16130 INC 17
GEN 104 MEM ID 20011 INC 17 F 38 INC 155 T 16131 INC 17
GEN 104 MEM ID 20012 INC 17 F 40 INC 155 T 16132 INC 17
GEN 104 MEM ID 20013 INC 17 F 41 INC 155 T 16133 INC 17
GEN 104 MEM ID 20014 INC 17 F 42 INC 155 T 16134 INC 17
GEN 104 MEM ID 20015 INC 17 F 43 INC 155 T 16135 INC 17
GEN 104 MEM ID 20016 INC 17 F 44 INC 155 T 16136 INC 17
GEN 104 MEM ID 20017 INC 17 F 45 INC 155 T 16137 INC 17
\$ END OF SOIL SPRINGS

MEMBER PROPERTY

10001 TO 12392 AX 10

20001 TO 21752 BY 17 AX 18.90
20002 TO 21753 BY 17 AX 45.15
20003 TO 21754 BY 17 AX 52.50
20004 TO 21755 BY 17 AX 52.50
20005 TO 21756 BY 17 AX 52.50
20006 TO 21757 BY 17 AX 45.15
20007 TO 21758 BY 17 AX 37.80
20008 TO 21759 BY 17 AX 44.10
20009 TO 21760 BY 17 AX 50.40
20010 TO 21761 BY 17 AX 50.40
20011 TO 21762 BY 17 AX 50.40
20012 TO 21763 BY 17 AX 46.20
20013 TO 21764 BY 17 AX 27.30

20014 TO 21765 BY 17 AX 31.50
20015 TO 21766 BY 17 AX 50.40
20016 TO 21767 BY 17 AX 39.90
20017 TO 21768 BY 17 AX 14.70

\$ END OF SOIL SPRING AREA SPECIFICATION

\$

OUTPUT DECIMAL 3

\$

OUTPUT ORDERED

INACTIVE JOINTS -

1777 TO 1780 6427 TO 6430 8124 TO 8127 8744 TO 8747 9837 TO 9840 14487 TO 14490

\$ REMOVE HOLES

INACTIVE ELEMENTS -

848 849 871 872 929 930 952 953 3278 3279 3301 3302 3359 3360 3382 3383 4167 -
4168 4190 4191 4248 4249 4271 4272 4491 4492 4514 4515 4572 4573 4595 4596 5060 -
5061 5083 5084 5141 5142 5164 5165 7490 7491 7513 7514 7571 7572 7594 7595

\$ REMOVE TRUSSES

INACTIVE MEMBERS 10256 10946 11452 12142 11197 11289

UNITS KIPS INCH

ELEMENT PROPERTY

1 TO 8424 TYPE 'IPSL' WITH INTEGRATION ORDER 4 \$ FOR CONSTANT

DISPLACEMENTS

\$

\$ GUNITE PROPERTY

CONSTANT E 4030. MEMBER 1 TO 8424

CONSTANT G 1722. MEMBER 1 TO 8424

CONSTANT DENSITY 0.0000868 1 TO 8424

\$

\$ RIDGID LINKS BETWEEN DOME LAYERS

CONSTANT E 3000. MEMBER 10001 TO 12392

CONSTANT DENSITY 0.0000001 10001 TO 12392

\$ SOIL SPRINGS

CONSTANT E 1.000 MEMBER 20001 TO 21768

CONSTANT DENSITY 0.0000001 20001 TO 21768

\$ PLOT DEVICE PLOTTER NEUTRAL
\$ PLOT PLANE XZ PROJECTION

\$

\$ MEMBER SELF WEIGHT LOAD CASE. INCLUDES ONLY GUNITE TANK

\$

\$ BEGIN DEAD LOAD ON DOME

LOADING 'DEADLOAD' 'VERTICAL GRAVITY LOAD'

UNITS INCH LBS

ELEMENT LOADS

1 THROUGH 8424 BODY FORCES GLOBAL UNIFORM BY -0.0868

\$

LOADING 'EQ-TANK' 'HORIZONTAL ACCELERATION OF TANK MASS'

UNITS INCH LBS

ELEMENT LOADS

\$ 0.14 G TIME DENSITY OF 150 #/CU.FT.

1 THROUGH 8424 BODY FORCES GLOBAL UNIFORM BX 0.0122

\$

LOADING 'OVERDOME' 'WEIGHT OF OVERBEARING SOIL ON DOME'

UNITS INCH LBS

ELEMENT LOADS

\$ FACE 4 = NODE 2, 3, 6, 7

\$ FACE 5 = NODE 3, 7, 8, 4

24 THROUGH 8367 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

28 THROUGH 8371 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

32 THROUGH 8375 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

35 THROUGH 8378 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

59 THROUGH 8402 BY 81 SURFACE FACE 4 GLOBAL UNIFORM PY -4.58

60 THROUGH 8403 BY 81 SURFACE FACE 4 GLOBAL UNIFORM PY -4.58

61 THROUGH 8404 BY 81 SURFACE FACE 4 GLOBAL UNIFORM PY -4.58

62 THROUGH 8405 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

63 THROUGH 8406 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

64 THROUGH 8407 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

65 THROUGH 8408 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

66 THROUGH 8409 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

67 THROUGH 8410 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

68 THROUGH 8411 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

69 THROUGH 8412 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

70 THROUGH 8413 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

71 THROUGH 8414 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

72 THROUGH 8415 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

73 THROUGH 8416 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58

74 THROUGH 8417 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 75 THROUGH 8418 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 76 THROUGH 8419 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 77 THROUGH 8420 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 78 THROUGH 8421 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 79 THROUGH 8422 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 80 THROUGH 8423 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 81 THROUGH 8424 BY 81 SURFACE FACE 5 GLOBAL UNIFORM PY -4.58
 UNITS INCH LBS
 LOADING 'SIDESOIL' 'STATIC SIDE SOIL PRESSURE'
 ELEMENT LOADS
 \$ POSITIVE PRESSURE IN THE LOCAL OR PLANAR SYSTEM ON FACE 2, 3, 4 OF "IPSL"
 \$ ELEMENTS MEANS PRESSURE ACTING INTO THE ELEMENT, CONTRARY TO THE
 GTSTRUDL
 \$ MANUAL INSTRUCTIONS ON PAGE 2.3.5-32. THE ERROR STATEMENT FROM GIT IS
 ON
 \$ FILE WITH KEN FRICKE OF MMIES --- TONY CHUNG (SAIC) 7/19/94
 9 THROUGH 8352 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 5.239
 10 THROUGH 8353 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 5.032
 11 THROUGH 8354 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 4.754
 12 THROUGH 8355 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 4.475
 13 THROUGH 8356 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 4.196
 14 THROUGH 8357 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 3.956
 15 THROUGH 8358 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 3.756
 16 THROUGH 8359 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 3.522
 17 THROUGH 8360 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 3.254
 18 THROUGH 8361 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 2.986
 19 THROUGH 8362 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 2.719
 20 THROUGH 8363 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 2.474
 \$ negative angle on wall, no effect
 \$ 21 THROUGH 8364 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 2.329
 22 THROUGH 8365 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 2.161
 23 THROUGH 8366 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 1.894
 24 THROUGH 8367 BY 81 SURFACE FACE 4 PLANAR UNIFORM PZ 1.682
 UNITS INCH LBS
 LOADING 'DYNASOIL' 'DYNAMIC E/W EARTHQUAKE SOIL PRESSURE'
 ELEMENT LOADS
 \$
 9 SURFACE FACE 4 GLOBAL UNIFORM PX -0.002
 10 SURFACE FACE 4 GLOBAL UNIFORM PX -0.009

11 SURFACE FACE 4 GLOBAL UNIFORM PX -0.019
 12 SURFACE FACE 4 GLOBAL UNIFORM PX -0.029
 13 SURFACE FACE 4 GLOBAL UNIFORM PX -0.039
 14 SURFACE FACE 4 GLOBAL UNIFORM PX -0.047
 15 SURFACE FACE 4 GLOBAL UNIFORM PX -0.054
 16 SURFACE FACE 4 GLOBAL UNIFORM PX -0.064
 17 SURFACE FACE 4 GLOBAL UNIFORM PX -0.064
 18 SURFACE FACE 4 GLOBAL UNIFORM PX -0.064
 19 SURFACE FACE 4 GLOBAL UNIFORM PX -0.064
 20 SURFACE FACE 4 GLOBAL UNIFORM PX -0.064
 21 SURFACE FACE 3 GLOBAL UNIFORM PX -0.063
 22 SURFACE FACE 4 GLOBAL UNIFORM PX -0.048
 23 SURFACE FACE 4 GLOBAL UNIFORM PX -0.025
 24 SURFACE FACE 4 GLOBAL UNIFORM PX -0.007
 90 SURFACE FACE 4 GLOBAL UNIFORM PX -0.007
 91 SURFACE FACE 4 GLOBAL UNIFORM PX -0.028
 92 SURFACE FACE 4 GLOBAL UNIFORM PX -0.057
 93 SURFACE FACE 4 GLOBAL UNIFORM PX -0.086
 94 SURFACE FACE 4 GLOBAL UNIFORM PX -0.115
 95 SURFACE FACE 4 GLOBAL UNIFORM PX -0.140
 96 SURFACE FACE 4 GLOBAL UNIFORM PX -0.161
 97 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 98 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 99 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 100 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 101 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 102 SURFACE FACE 3 GLOBAL UNIFORM PX -0.188
 103 SURFACE FACE 4 GLOBAL UNIFORM PX -0.145
 104 SURFACE FACE 4 GLOBAL UNIFORM PX -0.075
 105 SURFACE FACE 4 GLOBAL UNIFORM PX -0.020
 171 SURFACE FACE 4 GLOBAL UNIFORM PX -0.012
 172 SURFACE FACE 4 GLOBAL UNIFORM PX -0.047
 173 SURFACE FACE 4 GLOBAL UNIFORM PX -0.095
 174 SURFACE FACE 4 GLOBAL UNIFORM PX -0.144
 175 SURFACE FACE 4 GLOBAL UNIFORM PX -0.192
 176 SURFACE FACE 4 GLOBAL UNIFORM PX -0.233
 177 SURFACE FACE 4 GLOBAL UNIFORM PX -0.268
 178 SURFACE FACE 4 GLOBAL UNIFORM PX -0.320
 179 SURFACE FACE 4 GLOBAL UNIFORM PX -0.320
 180 SURFACE FACE 4 GLOBAL UNIFORM PX -0.320
 181 SURFACE FACE 4 GLOBAL UNIFORM PX -0.320
 182 SURFACE FACE 4 GLOBAL UNIFORM PX -0.320

183	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.312
184	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.241
185	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.125
186	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.034
252	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.016
253	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.066
254	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.133
255	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.200
256	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.268
257	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.326
258	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.374
259	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
260	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
261	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
262	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
263	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
264	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.436
265	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.336
266	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.175
267	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.047
333	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.021
334	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.084
335	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.170
336	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.256
337	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.342
338	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.416
339	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.479
340	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
341	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
342	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
343	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
344	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
345	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.557
346	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.430
347	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.224
348	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.060
414	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.025
415	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.102
416	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.207
417	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.312
418	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.416
419	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.506
420	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.581
421	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
422	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
423	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
424	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
425	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
426	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.677
427	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.522
428	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.272
429	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.073
495	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.029
496	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.120
497	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.243
498	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.365
499	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.488
500	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.594
501	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.682
502	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
503	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
504	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
505	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
506	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
507	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.794
508	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.613
509	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.319
510	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.086
576	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.034
577	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.137
578	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.278
579	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.418
580	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.558
581	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.679
582	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.780
583	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.931
584	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.931
585	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.931
586	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.931
587	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.931
588	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.908
589	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.701
590	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.365
591	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.098

657	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.038
658	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.154
659	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.311
660	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.469
661	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.626
662	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.762
663	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.875
664	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
665	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
666	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
667	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
668	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
669	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.045
670	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.019
671	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.787
672	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.409
738	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.111
739	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.042
740	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.170
741	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.344
742	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.519
743	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.692
744	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.842
745	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.968
746	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.155
747	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.155
748	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.155
749	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.155
750	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.127
751	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.869
752	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.452
753	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.122
819	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.046
820	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.186
821	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.376
822	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.566
823	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.756
824	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.919
825	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.056
826	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.261
827	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.261
828	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.261
829	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.261
830	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.261
831	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.230
832	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.949
833	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.494
834	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.133
900	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.049
901	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.201
902	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.406
903	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.611
904	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.816
905	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.993
906	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.141
907	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.362
908	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.362
909	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.362
910	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.362
911	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.362
912	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.328
913	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.025
914	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.533
915	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.144
981	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.053
982	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.215
983	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.435
984	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.655
985	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.874
986	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.063
987	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.221
988	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458
989	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458
990	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458
991	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458
992	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458
993	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.422
994	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.097
995	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
996	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.154
1062	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.056
1063	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.229
1064	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.462
1065	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.695

1066	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.928
1067	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.129
1068	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.298
1069	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
1070	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
1071	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
1072	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
1073	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
1074	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.511
1075	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.166
1076	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.607
1077	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.164
1143	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.059
1144	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.241
1145	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.487
1146	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.734
1147	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.979
1148	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.191
1149	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.369
1150	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
1151	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
1152	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
1153	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
1154	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
1155	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.594
1156	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.230
1157	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.640
1158	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.173
1224	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.062
1225	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.253
1226	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.511
1227	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.769
1228	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.027
1229	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.249
1230	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.435
1231	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713
1232	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713
1233	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713
1234	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713
1235	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713
1236	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.671
1237	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.290
1238	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.671
1239	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.181
1305	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.065
1306	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.264
1307	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.532
1308	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.802
1309	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.071
1310	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.302
1311	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.496
1312	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786
1313	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786
1314	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786
1315	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786
1316	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786
1317	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.743
1318	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.344
1319	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.700
1320	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.189
1386	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.067
1387	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.273
1388	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.552
1389	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.832
1390	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.111
1391	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.351
1392	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.552
1393	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853
1394	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853
1395	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853
1396	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853
1397	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853
1398	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.807
1399	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.394
1400	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.726
1401	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.196
1467	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.069
1468	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.282
1469	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.570
1470	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.859
1471	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.146
1472	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.394
1473	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.602
1474	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912

1475	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
1476	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
1477	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
1478	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
1479	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.866
1480	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.439
1481	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.749
1482	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.202
1548	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.071
1549	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.290
1550	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.586
1551	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.882
1552	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.178
1553	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.433
1554	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.646
1555	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
1556	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
1557	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
1558	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
1559	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
1560	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.917
1561	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.479
1562	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.770
1563	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.208
1629	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.073
1630	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.297
1631	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.599
1632	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.903
1633	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.205
1634	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.466
1635	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.685
1636	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
1637	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
1638	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
1639	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
1640	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
1641	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.961
1642	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.513
1643	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.787
1644	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.213
1710	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.074
1711	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.302

1712	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.611
1713	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.920
1714	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.228
1715	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.494
1716	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.717
1717	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
1718	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
1719	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
1720	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
1721	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
1722	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.999
1723	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.542
1724	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.802
1725	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.217
1791	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.075
1792	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.307
1793	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.620
1794	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.934
1795	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.247
1796	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.516
1797	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.742
1798	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
1799	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
1800	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
1801	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
1802	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
1803	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.029
1804	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.565
1805	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
1806	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.220
1872	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.076
1873	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.310
1874	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.627
1875	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.944
1876	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.260
1877	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.533
1878	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.762
1879	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
1880	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
1881	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
1882	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
1883	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103

1884	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.051	2121	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.781
1885	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.583	2122	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126
1886	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.824	2123	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126
1887	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.222	2124	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126
1953	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.077	2125	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126
1954	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.313	2126	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126
1955	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.631	2127	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.074
1956	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.951	2128	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.600
1957	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.270	2129	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.833
1958	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.545	2130	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.225
1959	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.775	2196	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.077
1960	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118	2197	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.313
1961	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118	2198	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.631
1962	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118	2199	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.951
1963	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118	2200	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.270
1964	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118	2201	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.545
1965	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.066	2202	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.775
1966	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.594	2203	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118
1967	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.830	2204	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118
1968	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.224	2205	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118
2034	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.077	2206	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118
2035	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.314	2207	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.118
2036	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.634	2208	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.066
2037	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.955	2209	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.594
2038	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.274	2210	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.830
2039	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.550	2211	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.224
2040	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.781	2277	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.076
2041	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126	2278	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.310
2042	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126	2279	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.627
2043	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126	2280	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.944
2044	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126	2281	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.260
2045	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.126	2282	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.533
2046	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.074	2283	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.762
2047	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.600	2284	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
2048	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.833	2285	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
2049	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.225	2286	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
2115	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.077	2287	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
2116	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.314	2288	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.103
2117	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.634	2289	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.051
2118	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.955	2290	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.583
2119	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.274	2291	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.824
2120	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.550	2292	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.222

2358	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.075
2359	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.307
2360	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.620
2361	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.934
2362	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.247
2363	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.516
2364	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.742
2365	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
2366	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
2367	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
2368	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
2369	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.080
2370	SURFACE FACE 3 GLOBAL UNIFORM PX	-2.029
2371	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.565
2372	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
2373	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.220
2439	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.074
2440	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.302
2441	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.611
2442	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.920
2443	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.228
2444	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.494
2445	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.717
2446	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
2447	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
2448	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
2449	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
2450	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.049
2451	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.999
2452	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.542
2453	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.802
2454	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.217
2520	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.073
2521	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.297
2522	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.599
2523	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.903
2524	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.205
2525	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.466
2526	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.685
2527	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
2528	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
2529	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
2530	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
2531	SURFACE FACE 4 GLOBAL UNIFORM PX	-2.011
2532	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.961
2533	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.513
2534	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.787
2535	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.213
2601	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.071
2602	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.290
2603	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.586
2604	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.882
2605	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.178
2606	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.433
2607	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.646
2608	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
2609	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
2610	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
2611	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
2612	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.965
2613	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.917
2614	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.479
2615	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.770
2616	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.208
2682	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.069
2683	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.282
2684	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.570
2685	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.859
2686	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.146
2687	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.394
2688	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.602
2689	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
2690	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
2691	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
2692	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
2693	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.912
2694	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.866
2695	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.439
2696	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.749
2697	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.202
2763	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.067
2764	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.273
2765	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.552
2766	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.832

2767	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.111	2939	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.671
2768	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.351	2940	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.181
2769	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.552	3006	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.059
2770	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853	3007	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.241
2771	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853	3008	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.487
2772	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853	3009	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.734
2773	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853	3010	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.979
2774	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.853	3011	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.191
2775	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.807	3012	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.369
2776	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.394	3013	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
2777	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.726	3014	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
2778	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.196	3015	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
2844	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.065	3016	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
2845	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.264	3017	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.634
2846	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.532	3018	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.594
2847	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.802	3019	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.230
2848	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.071	3020	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.640
2849	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.302	3021	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.173
2850	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.496	3087	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.056
2851	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786	3088	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.229
2852	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786	3089	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.462
2853	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786	3090	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.695
2854	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786	3091	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.928
2855	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.786	3092	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.129
2856	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.743	3093	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.298
2857	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.344	3094	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
2858	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.700	3095	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
2859	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.189	3096	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
2925	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.062	3097	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
2926	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.253	3098	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.549
2927	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.511	3099	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.511
2928	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.769	3100	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.166
2929	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.027	3101	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.607
2930	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.249	3102	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.164
2931	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.435	3168	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.053
2932	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713	3169	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.215
2933	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713	3170	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.435
2934	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713	3171	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.655
2935	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713	3172	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.874
2936	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.713	3173	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.063
2937	SURFACE FACE 3 GLOBAL UNIFORM PX	-1.671	3174	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.221
2938	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.290	3175	SURFACE FACE 4 GLOBAL UNIFORM PX	-1.458

3585	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.908
3586	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.701
3587	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.365
3588	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.098
3654	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.029
3655	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.120
3656	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.243
3657	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.365
3658	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.488
3659	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.594
3660	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.682
3661	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
3662	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
3663	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
3664	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
3665	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.814
3666	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.794
3667	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.613
3668	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.319
3669	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.086
3735	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.025
3736	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.102
3737	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.207
3738	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.312
3739	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.416
3740	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.506
3741	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.581
3742	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
3743	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
3744	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
3745	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
3746	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.694
3747	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.677
3748	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.522
3749	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.272
3750	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.073
3816	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.021
3817	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.084
3818	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.170
3819	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.256
3820	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.342
3821	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.416
3822	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.479
3823	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
3824	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
3825	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
3826	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
3827	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.571
3828	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.557
3829	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.430
3830	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.224
3831	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.060
3897	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.016
3898	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.066
3899	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.133
3900	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.200
3901	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.268
3902	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.326
3903	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.374
3904	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
3905	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
3906	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
3907	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
3908	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.446
3909	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.435
3910	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.336
3911	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.175
3912	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.047
3978	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.012
3979	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.047
3980	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.095
3981	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.144
3982	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
3983	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.233
3984	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.268
3985	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.320
3986	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.320
3987	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.320
3988	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.320
3989	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.320
3990	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.312
3991	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.241
3992	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.125
3993	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.034

4059	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.007
4060	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.028
4061	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.057
4062	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.086
4063	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.115
4064	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.140
4065	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.161
4066	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
4067	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
4068	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
4069	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
4070	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.192
4071	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.188
4072	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.145
4073	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.075
4074	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.020
4140	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.002
4141	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.009
4142	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.019
4143	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.029
4144	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.039
4145	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.047
4146	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.054
4147	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.064
4148	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.064
4149	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.064
4150	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.064
4151	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.064
4152	SURFACE FACE 3 GLOBAL UNIFORM PX	-0.063
4153	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.048
4154	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.025
4155	SURFACE FACE 4 GLOBAL UNIFORM PX	-0.007

\$

LOADING 'F-HYDYN+' 'FULL TANK HYDRODYNAMIC LOAD IN +X DIRECTION'

UNITS INCH LBS

ELEMENT LOADS

\$ FULL TANK HYDRODYNAMIC FORCE

15	SURFACE FACE 6 GLOBAL UNIFORM PX	0.03
96	SURFACE FACE 6 GLOBAL UNIFORM PX	0.27
177	SURFACE FACE 6 GLOBAL UNIFORM PX	0.74
258	SURFACE FACE 6 GLOBAL UNIFORM PX	1.45

339	SURFACE FACE 6 GLOBAL UNIFORM PX	2.37
420	SURFACE FACE 6 GLOBAL UNIFORM PX	3.49
501	SURFACE FACE 6 GLOBAL UNIFORM PX	4.81
582	SURFACE FACE 6 GLOBAL UNIFORM PX	6.29
663	SURFACE FACE 6 GLOBAL UNIFORM PX	7.92
744	SURFACE FACE 6 GLOBAL UNIFORM PX	9.68
825	SURFACE FACE 6 GLOBAL UNIFORM PX	11.53
906	SURFACE FACE 6 GLOBAL UNIFORM PX	13.46
987	SURFACE FACE 6 GLOBAL UNIFORM PX	15.42
1068	SURFACE FACE 6 GLOBAL UNIFORM PX	17.41
1149	SURFACE FACE 6 GLOBAL UNIFORM PX	19.37
1230	SURFACE FACE 6 GLOBAL UNIFORM PX	21.30
1311	SURFACE FACE 6 GLOBAL UNIFORM PX	23.15
1392	SURFACE FACE 6 GLOBAL UNIFORM PX	24.91
1473	SURFACE FACE 6 GLOBAL UNIFORM PX	26.54
1554	SURFACE FACE 6 GLOBAL UNIFORM PX	28.02
1635	SURFACE FACE 6 GLOBAL UNIFORM PX	29.34
1716	SURFACE FACE 6 GLOBAL UNIFORM PX	30.46
1797	SURFACE FACE 6 GLOBAL UNIFORM PX	31.38
1878	SURFACE FACE 6 GLOBAL UNIFORM PX	32.09
1959	SURFACE FACE 6 GLOBAL UNIFORM PX	32.56
2040	SURFACE FACE 6 GLOBAL UNIFORM PX	32.80
2121	SURFACE FACE 6 GLOBAL UNIFORM PX	32.80
2202	SURFACE FACE 6 GLOBAL UNIFORM PX	32.56
2283	SURFACE FACE 6 GLOBAL UNIFORM PX	32.09
2364	SURFACE FACE 6 GLOBAL UNIFORM PX	31.38
2445	SURFACE FACE 6 GLOBAL UNIFORM PX	30.46
2526	SURFACE FACE 6 GLOBAL UNIFORM PX	29.34
2607	SURFACE FACE 6 GLOBAL UNIFORM PX	28.02
2688	SURFACE FACE 6 GLOBAL UNIFORM PX	26.54
2769	SURFACE FACE 6 GLOBAL UNIFORM PX	24.91
2850	SURFACE FACE 6 GLOBAL UNIFORM PX	23.15
2931	SURFACE FACE 6 GLOBAL UNIFORM PX	21.30
3012	SURFACE FACE 6 GLOBAL UNIFORM PX	19.37
3093	SURFACE FACE 6 GLOBAL UNIFORM PX	17.41
3174	SURFACE FACE 6 GLOBAL UNIFORM PX	15.42
3255	SURFACE FACE 6 GLOBAL UNIFORM PX	13.46
3336	SURFACE FACE 6 GLOBAL UNIFORM PX	11.53
3417	SURFACE FACE 6 GLOBAL UNIFORM PX	9.68
3498	SURFACE FACE 6 GLOBAL UNIFORM PX	7.92
3579	SURFACE FACE 6 GLOBAL UNIFORM PX	6.29
3660	SURFACE FACE 6 GLOBAL UNIFORM PX	4.81

3741	SURFACE FACE 6 GLOBAL UNIFORM PX	3.49	2848	SURFACE FACE 6 GLOBAL UNIFORM PX	7.34
3822	SURFACE FACE 6 GLOBAL UNIFORM PX	2.37	2929	SURFACE FACE 6 GLOBAL UNIFORM PX	6.75
3903	SURFACE FACE 6 GLOBAL UNIFORM PX	1.45	3010	SURFACE FACE 6 GLOBAL UNIFORM PX	6.14
3984	SURFACE FACE 6 GLOBAL UNIFORM PX	0.74	3091	SURFACE FACE 6 GLOBAL UNIFORM PX	5.52
4065	SURFACE FACE 6 GLOBAL UNIFORM PX	0.27	3172	SURFACE FACE 6 GLOBAL UNIFORM PX	4.89
4146	SURFACE FACE 6 GLOBAL UNIFORM PX	0.03	3253	SURFACE FACE 6 GLOBAL UNIFORM PX	4.27
13	SURFACE FACE 6 GLOBAL UNIFORM PX	0.01	3334	SURFACE FACE 6 GLOBAL UNIFORM PX	3.66
94	SURFACE FACE 6 GLOBAL UNIFORM PX	0.09	3415	SURFACE FACE 6 GLOBAL UNIFORM PX	3.07
175	SURFACE FACE 6 GLOBAL UNIFORM PX	0.24	3496	SURFACE FACE 6 GLOBAL UNIFORM PX	2.51
256	SURFACE FACE 6 GLOBAL UNIFORM PX	0.46	3577	SURFACE FACE 6 GLOBAL UNIFORM PX	2.00
337	SURFACE FACE 6 GLOBAL UNIFORM PX	0.75	3658	SURFACE FACE 6 GLOBAL UNIFORM PX	1.52
418	SURFACE FACE 6 GLOBAL UNIFORM PX	1.11	3739	SURFACE FACE 6 GLOBAL UNIFORM PX	1.11
499	SURFACE FACE 6 GLOBAL UNIFORM PX	1.52	3820	SURFACE FACE 6 GLOBAL UNIFORM PX	0.75
580	SURFACE FACE 6 GLOBAL UNIFORM PX	2.00	3901	SURFACE FACE 6 GLOBAL UNIFORM PX	0.46
661	SURFACE FACE 6 GLOBAL UNIFORM PX	2.51	3982	SURFACE FACE 6 GLOBAL UNIFORM PX	0.24
742	SURFACE FACE 6 GLOBAL UNIFORM PX	3.07	4063	SURFACE FACE 6 GLOBAL UNIFORM PX	0.09
823	SURFACE FACE 6 GLOBAL UNIFORM PX	3.66	4144	SURFACE FACE 6 GLOBAL UNIFORM PX	0.01
904	SURFACE FACE 6 GLOBAL UNIFORM PX	4.27			
985	SURFACE FACE 6 GLOBAL UNIFORM PX	4.89			
1066	SURFACE FACE 6 GLOBAL UNIFORM PX	5.52			
1147	SURFACE FACE 6 GLOBAL UNIFORM PX	6.14			
1228	SURFACE FACE 6 GLOBAL UNIFORM PX	6.75			
1309	SURFACE FACE 6 GLOBAL UNIFORM PX	7.34			
1390	SURFACE FACE 6 GLOBAL UNIFORM PX	7.90			
1471	SURFACE FACE 6 GLOBAL UNIFORM PX	8.42			
1552	SURFACE FACE 6 GLOBAL UNIFORM PX	8.89			
1633	SURFACE FACE 6 GLOBAL UNIFORM PX	9.30			
1714	SURFACE FACE 6 GLOBAL UNIFORM PX	9.66			
1795	SURFACE FACE 6 GLOBAL UNIFORM PX	9.95			
1876	SURFACE FACE 6 GLOBAL UNIFORM PX	10.18			
1957	SURFACE FACE 6 GLOBAL UNIFORM PX	10.33			
2038	SURFACE FACE 6 GLOBAL UNIFORM PX	10.40			
2119	SURFACE FACE 6 GLOBAL UNIFORM PX	10.40			
2200	SURFACE FACE 6 GLOBAL UNIFORM PX	10.33			
2281	SURFACE FACE 6 GLOBAL UNIFORM PX	10.18			
2362	SURFACE FACE 6 GLOBAL UNIFORM PX	9.95			
2443	SURFACE FACE 6 GLOBAL UNIFORM PX	9.66			
2524	SURFACE FACE 6 GLOBAL UNIFORM PX	9.30			
2605	SURFACE FACE 6 GLOBAL UNIFORM PX	8.89			
2686	SURFACE FACE 6 GLOBAL UNIFORM PX	8.42			
2767	SURFACE FACE 6 GLOBAL UNIFORM PX	7.90			

\$
LOADING 'F-HYDYN-' 'FULL TANK HYDRODYNAMIC LOAD IN -X DIRECTION'
UNITS INCH LBS
ELEMENT LOADS

\$	FULL TANK HYDRODYNAMIC FORCE	
4227	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.03
4308	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.27
4389	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.74
4470	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.45
4551	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.37
4632	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.49
4713	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.81
4794	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.29
4875	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.92
4956	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.68
5037	SURFACE FACE 6 GLOBAL UNIFORM PX	-11.53
5118	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.46
5199	SURFACE FACE 6 GLOBAL UNIFORM PX	-15.42
5280	SURFACE FACE 6 GLOBAL UNIFORM PX	-17.41
5361	SURFACE FACE 6 GLOBAL UNIFORM PX	-19.37
5442	SURFACE FACE 6 GLOBAL UNIFORM PX	-21.30
5523	SURFACE FACE 6 GLOBAL UNIFORM PX	-23.15
5604	SURFACE FACE 6 GLOBAL UNIFORM PX	-24.91
5685	SURFACE FACE 6 GLOBAL UNIFORM PX	-26.54
5766	SURFACE FACE 6 GLOBAL UNIFORM PX	-28.02

5847	SURFACE FACE 6 GLOBAL UNIFORM PX	-29.34
5928	SURFACE FACE 6 GLOBAL UNIFORM PX	-30.46
6009	SURFACE FACE 6 GLOBAL UNIFORM PX	-31.38
6090	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.09
6171	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.56
6252	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.80
6333	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.80
6414	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.56
6495	SURFACE FACE 6 GLOBAL UNIFORM PX	-32.09
6576	SURFACE FACE 6 GLOBAL UNIFORM PX	-31.38
6657	SURFACE FACE 6 GLOBAL UNIFORM PX	-30.46
6738	SURFACE FACE 6 GLOBAL UNIFORM PX	-29.34
6819	SURFACE FACE 6 GLOBAL UNIFORM PX	-28.02
6900	SURFACE FACE 6 GLOBAL UNIFORM PX	-26.54
6981	SURFACE FACE 6 GLOBAL UNIFORM PX	-24.91
7062	SURFACE FACE 6 GLOBAL UNIFORM PX	-23.15
7143	SURFACE FACE 6 GLOBAL UNIFORM PX	-21.30
7224	SURFACE FACE 6 GLOBAL UNIFORM PX	-19.37
7305	SURFACE FACE 6 GLOBAL UNIFORM PX	-17.41
7386	SURFACE FACE 6 GLOBAL UNIFORM PX	-15.42
7467	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.46
7548	SURFACE FACE 6 GLOBAL UNIFORM PX	-11.53
7629	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.68
7710	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.92
7791	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.29
7872	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.81
7953	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.49
8034	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.37
8115	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.45
8196	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.74
8277	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.27
8358	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.03
4225	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.01
4306	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.09
4387	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.24
4468	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.46
4549	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.75
4630	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.11
4711	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.52
4792	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.00
4873	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.51
4954	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.07
5035	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.66
5116	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.27
5197	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.89
5278	SURFACE FACE 6 GLOBAL UNIFORM PX	-5.52
5359	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.14
5440	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.75
5521	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.34
5602	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.90
5683	SURFACE FACE 6 GLOBAL UNIFORM PX	-8.42
5764	SURFACE FACE 6 GLOBAL UNIFORM PX	-8.89
5845	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.30
5926	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.66
6007	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.95
6088	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.18
6169	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.33
6250	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.40
6331	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.40
6412	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.33
6493	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.18
6574	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.95
6655	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.66
6736	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.30
6817	SURFACE FACE 6 GLOBAL UNIFORM PX	-8.89
6898	SURFACE FACE 6 GLOBAL UNIFORM PX	-8.42
6979	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.90
7060	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.34
7141	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.75
7222	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.14
7303	SURFACE FACE 6 GLOBAL UNIFORM PX	-5.52
7384	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.89
7465	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.27
7546	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.66
7627	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.07
7708	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.51
7789	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.00
7870	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.52
7951	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.11
8032	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.75
8113	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.46
8194	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.24
8275	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.09

1389	SURFACE FACE 6 GLOBAL	UNIFORM PX	11 36
------	-----------------------	------------	-------

10.11
11.30

1631 SURFACE FACE 8 GLOBAL UNIFORM PX
1632 SURFACE FACE 8 GLOBAL UNIFORM PX

1032 SUHFACE FACE 8 GLOBAL UNIFORM FX
1713 SUHFACE FACE 8 GLOBAL UNIFORM BY

1713 SURFACE FACE 6 GLOBAL UNIFORM PX
1704 SUPEACE EACE 6 GLOBAL UNIFORM PX

1794 SURFACE FACE 6 GLOBAL UNIFORM PX
1875 SURFACE FACE 6 GLOBAL UNIFORM PX

1930	SURFACE FACE 6 GLOBAL UNIFORM PX
2037	SURFACE FACE 6 GLOBAL UNIFORM PX

2037 SURFACE FACE 6 GLOBAL UNIFORM PX
2118 SURFACE FACE 6 GLOBAL UNIFORM PX

2118 SURFACE FACE 6 GLOBAL UNIFORM PX

2199 SURFACE FACE 6 GLOBAL UNIFORM PX
2280 SURFACE FACE 6 GLOBAL UNIFORM PX

2280 SURFACE FACE 6 GLOBAL UNIFORM PX
2361 SURFACE FACE 6 GLOBAL UNIFORM PX

2361 SURFACE FACE 6 GLOBAL UNIFORM PX
2442 SURFACE FACE 6 GLOBAL UNIFORM PX

2442 SURFACE FACE 6 GLOBAL UNIFORM PX
2523 SURFACE FACE 6 GLOBAL UNIFORM PX

2323 SURFACE FACE 6 GLOBAL UNIFORM PX
2604 SURFACE FACE 6 GLOBAL UNIFORM PX

2004 SURFACE FACE 0 GLOBAL UNIFORM PX
2685 SURFACE FACE 6 GLOBAL UNIFORM PX

2063 SURFACE FACE 6 GLOBAL UNIFORM PX
2766 SURFACE FACE 6 GLOBAL UNIFORM PX

2700 SURFACE FACE 0 GLOBAL UNIFORM PX
2847 SURFACE FACE 6 GLOBAL UNIFORM PX

2847 SURFACE FACE 0 GLOBAL UNIFORM PX
2928 SURFACE FACE 6 GLOBAL UNIFORM PX

3090 SURFACE FACE 6 GLOBAL UNIFORM PX

3171 SUBFACE FACE 6 GLOBAL UNIFORM PX

3171 SURFACE FACE 0 GLOBAL UNIFORM PX
3252 SURFACE FACE 6 GLOBAL UNIFORM PX

3232 SURFACE FACE 6 GLOBAL UNIFORM PX
3333 SURFACE FACE 6 GLOBAL UNIFORM PX

3333 SURFACE FACE 0 GLOBAL UNIFORM PX
3414 SURFACE FACE 6 GLOBAL UNIFORM PX

3414 SURFACE FACE 6 GLOBAL UNIFORM PX
3495 SURFACE FACE 6 GLOBAL UNIFORM PY

3493 SURFACE FACE 6 GLOBAL UNIFORM PX
3576 SURFACE FACE 6 GLOBAL UNIFORM PY

3376 SURFACE FACE 6 GLOBAL UNIFORM PX
3657 SURFACE FACE 6 GLOBAL UNIFORM PY

3637 SURFACE FACE 6 GLOBAL UNIFORM PX
3738 SURFACE FACE 6 GLOBAL UNIFORM PY

3738 SURFACE FACE 6 GLOBAL UNIFORM PX
3819 SURFACE FACE 6 GLOBAL UNIFORM PX

3819 SURFACE FACE 6 GLOBAL UNIFORM PX
3900 SURFACE FACE 6 GLOBAL UNIFORM PX

3900 SURFACE FACE 6 GLOBAL UNIFORM PX
3981 SURFACE FACE 6 GLOBAL UNIFORM PX

3981 SURFACE FACE 6 GLOBAL UNIFORM PX
4062 SURFACE FACE 6 GLOBAL UNIFORM PX

4062 SURFACE FACE 6 GLOBAL UNIFORM PX
4143 SURFACE FACE 6 GLOBAL UNIFORM PX

4143 SURFACE FACE 6 GLOBAL UNIFORM PX

11 SLIDEACE EACE 6 CIOBA! INIEORM DV

11	SURFACE FACE 6 GLOBAL UNIFORM PX
02	SURFACE FACE 6 GLOBAL UNIFORM PX

92 SURFACE FACE 6 GLOBAL UNIFORM PX

173 SURFACE FACE 6 GLOBAL UNIFORM PX

1/3 SURFACE FACE 6 GLOBAL UNIFORM PX
2/4 SURFACE FACE 6 GLOBAL UNIFORM PX

254 SURFACE FACE 6 GLOBAL UNIFORM PX

335 SURFACE FACE 6 GLOBAL UNIFORM PX

416 SURFACE FACE 6 GLOBAL UNIFORM PX

Downloaded from <http://ajph.org/> on November 10, 2015

497	SURFACE FACE 6 GLOBAL UNIFORM PX	0.48
578	SURFACE FACE 6 GLOBAL UNIFORM PX	0.62
659	SURFACE FACE 6 GLOBAL UNIFORM PX	0.79
740	SURFACE FACE 6 GLOBAL UNIFORM PX	0.96
821	SURFACE FACE 6 GLOBAL UNIFORM PX	1.14
902	SURFACE FACE 6 GLOBAL UNIFORM PX	1.33
983	SURFACE FACE 6 GLOBAL UNIFORM PX	1.53
1064	SURFACE FACE 6 GLOBAL UNIFORM PX	1.73
1145	SURFACE FACE 6 GLOBAL UNIFORM PX	1.92
1226	SURFACE FACE 6 GLOBAL UNIFORM PX	2.11
1307	SURFACE FACE 6 GLOBAL UNIFORM PX	2.29
1388	SURFACE FACE 6 GLOBAL UNIFORM PX	2.47
1469	SURFACE FACE 6 GLOBAL UNIFORM PX	2.63
1550	SURFACE FACE 6 GLOBAL UNIFORM PX	2.78
1631	SURFACE FACE 6 GLOBAL UNIFORM PX	2.91
1712	SURFACE FACE 6 GLOBAL UNIFORM PX	3.02
1793	SURFACE FACE 6 GLOBAL UNIFORM PX	3.11
1874	SURFACE FACE 6 GLOBAL UNIFORM PX	3.18
1955	SURFACE FACE 6 GLOBAL UNIFORM PX	3.23
2036	SURFACE FACE 6 GLOBAL UNIFORM PX	3.25
2117	SURFACE FACE 6 GLOBAL UNIFORM PX	3.25
2198	SURFACE FACE 6 GLOBAL UNIFORM PX	3.23
2279	SURFACE FACE 6 GLOBAL UNIFORM PX	3.18
2360	SURFACE FACE 6 GLOBAL UNIFORM PX	3.11
2441	SURFACE FACE 6 GLOBAL UNIFORM PX	3.02
2522	SURFACE FACE 6 GLOBAL UNIFORM PX	2.91
2603	SURFACE FACE 6 GLOBAL UNIFORM PX	2.78
2684	SURFACE FACE 6 GLOBAL UNIFORM PX	2.63
2765	SURFACE FACE 6 GLOBAL UNIFORM PX	2.47
2846	SURFACE FACE 6 GLOBAL UNIFORM PX	2.29
2927	SURFACE FACE 6 GLOBAL UNIFORM PX	2.11
3008	SURFACE FACE 6 GLOBAL UNIFORM PX	1.92
3089	SURFACE FACE 6 GLOBAL UNIFORM PX	1.73
3170	SURFACE FACE 6 GLOBAL UNIFORM PX	1.53
3251	SURFACE FACE 6 GLOBAL UNIFORM PX	1.33
3332	SURFACE FACE 6 GLOBAL UNIFORM PX	1.14
3413	SURFACE FACE 6 GLOBAL UNIFORM PX	0.96
3494	SURFACE FACE 6 GLOBAL UNIFORM PX	0.79
3575	SURFACE FACE 6 GLOBAL UNIFORM PX	0.62
3656	SURFACE FACE 6 GLOBAL UNIFORM PX	0.48
3737	SURFACE FACE 6 GLOBAL UNIFORM PX	0.35
3818	SURFACE FACE 6 GLOBAL UNIFORM PX	0.23

3899	SURFACE FACE 6 GLOBAL UNIFORM PX	0.14
3980	SURFACE FACE 6 GLOBAL UNIFORM PX	0.07
4061	SURFACE FACE 6 GLOBAL UNIFORM PX	0.03
4142	SURFACE FACE 6 GLOBAL UNIFORM PX	0.00

\$

LOADING 'H-HYDYN-' HALF TA*J K DYDRODYNAMIC FORCE IN THE -X DIRECTION'

UNITS INCH LBS

ELEMENT LOADS

\$ HALF TANK HYDRODYNAMIC FORCE

4224	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.01
4305	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.12
4386	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.34
4467	SURFACE FACE 6 GLOBAL UNIFORM PX	-0.66
4548	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.08
4629	SURFACE FACE 6 GLOBAL UNIFORM PX	-1.59
4710	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.19
4791	SURFACE FACE 6 GLOBAL UNIFORM PX	-2.87
4872	SURFACE FACE 6 GLOBAL UNIFORM PX	-3.61
4953	SURFACE FACE 6 GLOBAL UNIFORM PX	-4.42
5034	SURFACE FACE 6 GLOBAL UNIFORM PX	-5.26
5115	SURFACE FACE 6 GLOBAL UNIFORM PX	-6.14
5196	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.04
5277	SURFACE FACE 6 GLOBAL UNIFORM PX	-7.94
5358	SURFACE FACE 6 GLOBAL UNIFORM PX	-8.84
5439	SURFACE FACE 6 GLOBAL UNIFORM PX	-9.72
5520	SURFACE FACE 6 GLOBAL UNIFORM PX	-10.56
5601	SURFACE FACE 6 GLOBAL UNIFORM PX	-11.36
5682	SURFACE FACE 6 GLOBAL UNIFORM PX	-12.11
5763	SURFACE FACE 6 GLOBAL UNIFORM PX	-12.78
5844	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.38
5925	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.90
6006	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.32
6087	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.64
6168	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.85
6249	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.96
6330	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.96
6411	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.85
6492	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.64
6573	SURFACE FACE 6 GLOBAL UNIFORM PX	-14.32
6654	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.90
6735	SURFACE FACE 6 GLOBAL UNIFORM PX	-13.38
6816	SURFACE FACE 6 GLOBAL UNIFORM PX	-12.78


```

$ PRINT JOINT COORDINATE
PRINT MEMBER INCIDENCES

$ STIFFNESS ANALYSIS REDUCE BAND
$
$
$ END OF MATRIX FORMULATION CHECK
$
$...LOAD COMBINATIONS
$

LOADING LIST 'DEADLOAD' 'OVERDOME' 'SIDESOIL' 'EQ-TANK' 'F-HYDYN+' '-
'F-HYDYN-' 'FULLSTAT' 'H-HYDYN+' 'H-HYDYN-' 'HALFSTAT'

$
$ STATIC LOADS
$
CREAT LOADING COMB 1 SPEC 'DEADLOAD' 1.0 'OVERDOME' 1.0 'SIDESOIL' 1.0
$

CREAT LOADING COMB 2 SPEC 'DEADLOAD' 1.0 'OVERDOME' 1.0 'SIDESOIL' 1.0 -
'FULLSTAT' 1.0
$

CREAT LOADING COMB 3 SPEC 'DEADLOAD' 1.0 'OVERDOME' 1.0 'SIDESOIL' 1.0 -
'HALFSTAT' 1.0
$
$ DYNAMIC LOADS
CREAT LOAD COMB 4 SPEC 'DEADLOAD' 1.093 'OVERDOME' 1.093 'EQ-TANK' 1.0 -
'SIDESOIL' 1.0 'DYNASOIL' 1.0
CREAT LOAD COMB 5 SPEC 'DEADLOAD' 1.093 'OVERDOME' 1.093 'EQ-TANK' 1.0 -
'SIDESOIL' 1.0 'DYNASOIL' 1.0 'FULLSTAT' 1.0 'F-HYDYN+' 1.0
CREAT LOAD COMB 6 SPEC 'DEADLOAD' 1.093 'OVERDOME' 1.093 'EQ-TANK' -1.0 -
'SIDESOIL' 1.0 'DYNASOIL' 1.0 'FULLSTAT' 1.0 'F-HYDYN-' 1.0
CREAT LOAD COMB 7 SPEC 'DEADLOAD' 1.093 'OVERDOME' 1.093 'EQ-TANK' 1.0 -
'SIDESOIL' 1.0 'DYNASOIL' 1.0 'HALFSTAT' 1.0 'H-HYDYN+' 1.0

```

LIST STRESS ELEMENTS 4000 TO 4729 BY 81
LIST STRESS ELEMENTS 4003 TO 4732 BY 81
LIST STRESS ELEMENTS 4005 TO 4734 BY 81
LIST STRESS ELEMENTS 4006 TO 4735 BY 81
LIST STRESS ELEMENTS 4007 TO 4736 BY 81
LIST STRESS ELEMENTS 4008 TO 4737 BY 81

\$

CALCULATE AVERAGE PRIN STRES VON AND ENVELOPE AT MID SURFACES FOR
ELEMENTS -

1 TO 81 2107 TO 2187 4213 TO 4293 -

4919 TO 5324 BY 81 -

4920 TO 5325 BY 81 -

4921 TO 5326 BY 81 -

4922 TO 5327 BY 81 -

4923 TO 5328 BY 81 -

4924 TO 5329 BY 81 -

4001 TO 4406 BY 81 -

4004 TO 4409 BY 81 -

4028 TO 4433 BY 81 -

4029 TO 4434 BY 81 -

4030 TO 4435 BY 81 -

4031 TO 4436 BY 81 -

4896 TO 5301 BY 81 -

4897 TO 5302 BY 81 -

4898 TO 5303 BY 81 -

4899 TO 5304 BY 81 -

4900 TO 5305 BY 81 -

4901 TO 5306 BY 81 -

4000 TO 4729 BY 81 -

4003 TO 4732 BY 81 -

4005 TO 4734 BY 81 -

4006 TO 4735 BY 81 -

4007 TO 4736 BY 81 -

4008 TO 4737 BY 81

CINPUT

FINISH