

SANDIA REPORT

SAND2024-13083

Printed September 2024

**Sandia
National
Laboratories**

Analysis of Rig Parameter Data Using Drilling Process Modeling Constraints

Volume 3: Utah FORGE Well 56-32

David W. Raymond, Melanie B. Schneider, Adam J. Foris and Jaiden E. Norton

Prepared by
Sandia National Laboratories
Albuquerque, New Mexico
87185 and Livermore,
California 94550

Issued by Sandia National Laboratories, operated for the United States Department of Energy by National Technology & Engineering Solutions of Sandia, LLC.

NOTICE: This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government, nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, make any warranty, express or implied, or assume any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represent that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government, any agency thereof, or any of their contractors or subcontractors. The views and opinions expressed herein do not necessarily state or reflect those of the United States Government, any agency thereof, or any of their contractors.

Printed in the United States of America. This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from

U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62
Oak Ridge, TN 37831

Telephone: (865) 576-8401
Facsimile: (865) 576-5728
E-Mail: reports@osti.gov
Online ordering: <http://www.osti.gov/scitech>

Available to the public from

U.S. Department of Commerce
National Technical Information Service
5301 Shawnee Rd
Alexandria, VA 22312

Telephone: (800) 553-6847
Facsimile: (703) 605-6900
E-Mail: orders@ntis.gov
Online order: <https://classic.ntis.gov/help/order-methods/>



ABSTRACT

Drill rig parameter measurements are routinely used during deep well construction to monitor and guide drilling conditions for improved performance and reduced costs. While insightful into the drilling process, these measurements are of reduced value without a standard to aid in data evaluation and decision making. In the main body of this work (Volume 1), a method is demonstrated whereby rock reduction model constraints are used to interpret drilling response parameters; the method could be applied in real-time to improve decision-making in the field and to further discern technology performance during post-drilling evaluations. Drilling parameters are evaluated using laboratory-validated rock reduction models for predicting the phenomenological response of drag bits (Detournay and Defourny, 1992) in computational algorithms. The method presented has applicability to development of advanced analytics on future geothermal wells using real-time electronic data recording for improved performance and reduced drilling costs. A drilling cost model is also used to show the tradeoff between rate of penetration and bit life and the influence on interval drilling costs.

Details of the bit specifications and performance are cataloged in an independent volume, documented under separate cover, for each of the four wells, and include Volume 2: Utah FORGE 16A(78)-32; Volume 3: Utah FORGE 56-32; Volume 4: Utah FORGE 78B-32 and Volume 5: Utah FORGE 16B(78)-32.

This page left blank

ACKNOWLEDGEMENTS

The authors are indebted to Utah FORGE, Frontier Drilling, Nabors, Pason, NOV, Baker Hughes, Ulterra Drilling Technologies, Smith International, Scout, GeoGuidance and others for permission to use information in preparing this work. The sponsorship of the US Department of Energy Geothermal Technologies Office (DOE/EERE/GTO) is gratefully acknowledged. In particular, funding for drilling activities at the FORGE site was provided by the U.S. DOE under grant DE-EE0007080 “Enhanced Geothermal System Concept Testing and Development at the Milford City, Utah FORGE Site.”

This page left blank

CONTENTS

1. Background and Introduction.....	12
1.1. Utah FORGE.....	12
1.2. Sandia Role	13
2. FORGE Well 56-32 Description.....	14
2.1. Well Program.....	14
2.2. Drilling Parameter Data Acquisition.....	14
2.3. Drilling Narrative.....	14
2.4. Bit Program & Performance Summary	15
2.5. Depth vs Days Summary	17
3. Bit Run Summaries and Processed Data	18
3.1. Bit-01	18
3.2. Bit-02	19
3.3. Bit-03	20
3.4. Bit-04	23
3.5. Bit-05	26
3.6. Bit-06	27
3.7. Bit-07	30
3.8. Bit-08	33
3.9. Bit-09	36
3.10. Bit-10	39
3.11. Bit-11	42
3.12. Bit-12	45
3.13. Bit-13	45
3.14. Bit-14	48
3.15. Bit-15	49
3.16. Bit-16	52
Appendix A. Daily Drilling Reports.....	1

LIST OF FIGURES

Figure 1-1. Frontier Rig 16 used to drill wells 16A(78)-32, 56-32,78B-32 and 16B(78)-32.	13
Figure 2-1. Utah FORGE Well 56-32 Profile.....	14
Figure 2-2. Utah FORGE Well 56-32 Bit Program and Performance Summary.....	16
Figure 2-3. Depth vs Days Summary for Utah FORGE Well 56-32.....	17
Figure 3-1. Post-drill photo of bit #3.	20
Figure 3-2. Post-drill photo of bit #4.	23
Figure 3-3. Post-drill photo of bit #6.	27
Figure 3-4. Post-drill photo of bit #7.	30
Figure 3-5. Post-drill photo of bit #8.	33
Figure 3-6. Post-drill photo of bit #9.	36
Figure 3-7. Post-drill photo of bit #10.....	39
Figure 3-8. Post-drill photo of bit #11.....	42
Figure 3-9. Post-drill photo of bit #15.....	49
Figure 3-10. Post-drill photo of bit #16.....	52

LIST OF TABLES

Table 2-1. FORGE Well 56-32 Bit Summary.....	16
Table 3-1: Bit 1 run summary.	18
Table 3-2: BHA 1 component makeup.	18
Table 3-3: Bit 2 run summary.	19
Table 3-4: Bit 3 run summary.	20
Table 3-5: BHA 2 component makeup.	20
Table 3-6: Bit 4 run summary.	23
Table 3-7: BHA 3 component makeup.	23
Table 3-8: Bit 5 run summary.	26
Table 3-9: BHA 4 component makeup.	26
Table 3-10: Bit 6 run summary.	27
Table 3-11: BHA 4 component makeup.	27
Table 3-12: Bit 7 run summary.	30
Table 3-13: BHA 5 component makeup.	30
Table 3-14: Bit 8 run summary.	33
Table 3-15: BHA 6 component makeup.	33
Table 3-16: Bit 9 run summary.	36
Table 3-17: BHA 7 component makeup.	36
Table 3-18: Bit 10 run summary.	39
Table 3-19: BHA 8 component makeup.	39
Table 3-20: Bit 11 run summary.	42
Table 3-21: BHA 9 component makeup.	42
Table 3-22: Bit 12 run summary.	45
Table 3-23: Bit 13 run summary.	45
Table 3-24: Bit 14 run summary.	48
Table 3-25: Bit 15 run summary.	49
Table 3-26: BHA 10 component makeup.	49
Table 3-27: Bit 16 run summary.	52
Table 3-28: BHA 10 component makeup.	52

EXECUTIVE SUMMARY

The United States Department of Energy has sponsored development of geothermal well construction at the Utah Frontier Observatory for Research in Geothermal Energy (FORGE). Drill rig parameter data were acquired by drilling contractor Frontier Drilling and evaluated for four wells: 1) Utah FORGE 16A(78)-32, a directional injection well with vertical depth to a kick-off point at 5892 ft and a 65 degree tangent to a measured depth of 10987 ft and, 2) Utah FORGE 56-32, a vertical monitoring well to a depth of 9145 ft, 3) Utah FORGE 78B-32, a vertical well drilled to a depth of 9500 ft, and 4) Utah FORGE 16B(78)-32, a directional production well drilled vertically to a kick-off point at 5269 ft, and a 65 degree tangent to a measured depth of 10947 ft. Sandia National Labs has accessed, cataloged, evaluated and recorded drill bit performance information used on the four Utah FORGE wells herein.

The subject drilling program has resulted in a large database of bit performance and durability records for drilling hot, hard rock characteristic of geothermal reservoirs. The majority of the Utah FORGE wells were drilled almost exclusively with Polycrystalline Diamond Compact (PDC) drill bits. The characteristic features of PDC bits and cutters are accordingly reviewed. While synthetic diamond cutter materials and bit design methodologies have improved over time, the recent success of these types of bits in hard rock formations may also be attributed to monitoring of drilling system response parameters using electronic data recorders on the surface rig for preferential performance and bit health monitoring.

Drill rig parameter measurements are routinely used during deep well construction to monitor and guide drilling conditions for improved performance and reduced costs. While insightful into the drilling process, these measurements are of reduced value without a standard to aid in data evaluation and decision making. In the main body of this work (Volume 1), a method is demonstrated whereby rock reduction model constraints are used to interpret drilling response parameters; the method could be applied in real-time to improve decision-making in the field and to further discern technology performance during post-drilling evaluations. Drilling parameters are evaluated using laboratory-validated rock reduction models for predicting the phenomenological response of drag bits (Detournay and Defourny, 1992) in computational algorithms. The method presented has applicability to development of advanced analytics on future geothermal wells using real-time electronic data recording for improved performance and reduced drilling costs.

Bit program and performance summaries are tabulated and presented for each well. These summaries include bit manufacturer model references, drilling system penetration rates, and overall bit lives. Representative drilling parameter data are evaluated to illustrate parameter use to monitor bit response, wear, and cutting structure damage. These bits failed by both normal wear and tear and drilling dynamic dysfunctions resulting in chipped and worn cutters, cutter shear and ring outs. Nevertheless, exemplar bit penetration rates easily exceeded 100 ft/hr and produced several 100 feet of hole construction. The tradeoff between rate of penetration and bit life is addressed with a drilling cost model using representative drilling cost parameters.

Details of the bit specifications and performance are cataloged in an independent volume, documented under separate cover, for each of the four wells, and include Volume 2: Utah FORGE 16A(78)-32; Volume 3: Utah FORGE 56-32; Volume 4: Utah FORGE 78B-32 and Volume 5: Utah FORGE 16B(78)-32. Bottom hole assembly information and daily drilling reports are also included.

This page left blank

ACRONYMS AND DEFINITIONS

Abbreviation	Definition
BHA	Bottom Hole Assembly
DOE	Department of Energy
EDR	Electronic Data Recording
FORGE	Frontier Observatory for Research in Geothermal Energy
GTO	Geothermal Technology Office
ROP	Rate of Penetration
WOB	Weight on Bit

This page left blank

1. BACKGROUND AND INTRODUCTION

Geothermal drilling is difficult as the rock is hot, hard, and often fractured. Wellbore construction costs have historically dominated the cost of geothermal energy development and have been an impediment to widespread development of geothermal energy. Technology improvements are needed to enable improved access and reduced drilling costs.

One technology improvement that can be applied to geothermal wellbore construction is the use of polycrystalline diamond compact (PDC) drill bits. Research and development on PDC drill bits has been sponsored by the United States Department of Energy for years resulting in improved diamond formulations, bonding techniques, bit designs, and hardening features that comprise the state of the art in the drilling industry. The oil and gas industry has benefited widely from these developments as the bits are routinely used to drill the majority of oil and gas wells worldwide. While the geothermal industry has benefited from incidental use of PDC bits for geothermal drilling, recent use of PDC bits at the DOE-sponsored Utah FORGE site has resulted in significant data for evaluation to address the efficacy of PDC bits for geothermal drilling.

1.1. Utah FORGE

The DOE-sponsored program, Utah Frontier Observatory for Research in Geothermal Energy (FORGE) was implemented to foster the development and demonstration of technologies supporting commercial applications of geothermal energy. The site is located near Milford, Utah (Moore, 2019). US DOE sponsorship of the FORGE activities de-risks developing technology for accessing deep geothermal reserves on a broad scale. One of the primary obstacles to commercial geothermal development is high drilling costs. The FORGE campaign applies state-of-the-art drilling technology to demonstrate well construction and completion activities on a utility scale. Multiple wells are planned over the life of the FORGE program. Well 16A(78)-32 is a directional well. Well 56-32 is a vertical monitoring well. Well 78B-32 is a vertical monitoring well. Well 16B(78)-32 is a directional well. These four wells were drilled with the top-drive, triple shown in Figure 1-1.



Figure 1-1. Frontier Rig 16 used to drill wells 16A(78)-32, 56-32,78B-32 and 16B(78)-32.

1.2. Sandia Role

With a long legacy of programmatic research pertaining to the development of synthetic diamond drill bit technology, Sandia is participating with DOE/EERE/GTO and the Utah FORGE drilling program to provide evaluations of the rock reduction technologies used at Utah FORGE. Although not expressly involved in the day-to-day decisions associated with the drilling program, the Sandia team has accessed electronic data recording (EDR) services to review drilling system performance. This effort has primarily been focused on monitoring and evaluation of multiple parameters to identify areas where improved productivity and cost savings can be realized via improved drilling performance. Drilling response parameters have been compared to rock reduction model constraints that have been proven in the laboratory to identify possible performance enhancement areas.

The methods used have been exercised in a post-processing manner. To provide the greatest benefit to the drilling process, a method is needed to enable the intuitive interpretation of response parameters and is amenable to implementation in computational algorithms for real-time evaluation. A method is demonstrated whereby drilling response parameters may be interpreted for improved drilling performance. This analysis is not an exhaustive assessment but rather an overview of representative bit performance that demonstrates the application of the approach using rock reduction constraints. Drilling data from the Utah FORGE site have been used for the analyses.

2. FORGE WELL 56-32 DESCRIPTION

2.1. Well Program

Utah FORGE Well 56-32 was drilled vertically to a depth of 9105 ft. The well will be used for monitoring and research activities. The well profile is shown in Figure 2-1.




Figure 2-1. Utah FORGE Well 56-32 Profile.

2.2. Drilling Parameter Data Acquisition

Pason US DataHub service was used to access EDR.

2.3. Drilling Narrative

FORGE well 56-32 bit runs comprised the following:

- 17-1/2" Diameter Surface Hole
 - Bit Run #1 (Frontier Bit #1) drilled 17-1/2" hole from 128' to 380.5'.
 - 13-3/8" diameter casing was set and cemented.

- 12-1/4" Diameter Vertical Hole
 - Bit Run #2 (Frontier Bit #2) drilled out the cement to 390'.
 - Bit Run #3 (Frontier Bit #3) drilled 12-1/4" hole from 390' to 3309'.
 - Bit Run #4 (Frontier Bit #4) drilled 12-1/4" hole from 3309' to 3500'.
 - 9-5/8" diameter casing was set and cemented.
 - Bit Run #5 (Frontier Bit #5 & #2) was used to drill out the cement.
- 8-3/4" Diameter Vertical Hole
 - Bit Run #6 (Frontier Bit #6) drilled 8-3/4" vertical hole from 3506' to 4595'.
 - Bit Run #7 (Frontier Bit #7) drilled 8-3/4" vertical hole from 4595' to 5143'.
 - Bit Run #8 (Frontier Bit #8) drilled 8-3/4" vertical hole from 5143' to 5610'.
 - Bit Run #9 (Frontier Bit #9) drilled 8-3/4" vertical hole from 5610' to 5999'.
 - Bit Run #10 (Frontier Bit #10) drilled 8-3/4" vertical hole from 5999' to 7208'.
 - Bit Run #11 (Frontier Bit #11) drilled 8-3/4" vertical hole from 7208' to 7620'.
 - Bit Run #12 (Frontier Bit #12) drilled 8-3/4" vertical hole from 7620' to 7628'.
 - Bit Run #13 (Frontier Bit #11) drilled 8-3/4" vertical hole from 7628' to 7663'.
 - Bit Run #14 (Frontier Bit #13) drilled 8-3/4" vertical hole from 7663' to 7667'.
 - Bit Run #15 (Frontier Bit #13) drilled 8-3/4" vertical hole from 7667' to 8900'.
 - Bit Run #16 (Frontier Bit #14) drilled 8-3/4" vertical hole from 8900' to 9145'.

2.4. Bit Program & Performance Summary

The bit program and resulting performance used on FORGE 56-32 are shown in Table 2-1 and Figure 2-2. Individual bit run summaries and processed data for FORGE well 16B(78)-32 is summarized in Section 3. A bit run summary is included for each bit along with BHA component information where pre-drill and post-drill images are included when available. The EDR data acquired for each bit was taken at a rate of one sample per 1 ft. This data is processed for each drill-ahead bit and includes 1) Reduction parameters (WOB, Torque on Bit, Bit Speed, and ROP vs. Depth, 2) Depth of cut per revolution vs. Depth, 3) Specific Energy and Drilling Strength vs. Depth, 4) Specific Energy vs. Drilling Strength (the linear regression does not account for the scatter due to sliding), 5) Rotary Speed Components (Top Drive, Motor and Bit) vs. depth, and 6) Rotary Torque components (Top Drive, Motor and Bit) vs. depth.

Table 2-1. FORGE Well 56-32 Bit Summary

Bit Run No.	Manufacturer	Type	Serial No.	BHA	Bit Dia. (in)	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
1	ReedHycalog	TK59-B1	A252419	1	17.50	134.0	381.0	247.0	1.2	205.8
2	-	M-22	-	-	12.25	381.0	390.0	9.0	0.1	90.0
3	ReedHycalog	TKC66-R1	A266974	2	12.25	390.0	3309.0	2919.0	9.7	300.9
4	ReedHycalog	TK63-A1A	A268226	3	12.25	3309.0	3500.0	191.0	2.6	73.5
5	-	GX-177	-	4	8.75	3500.0	3506.0	6.0	0.8	7.5
6	ReedHycalog	TKC73-H1	A275660	4	8.75	3506.0	4595.0	1089.0	28.9	37.7
7	-	EP5475	5042714	5	8.75	4595.0	5143.0	548.0	26.2	20.9
8	ReedHycalog	TKC63-P1	A277166	6	8.75	5143.0	5610.0	467.0	15.5	30.1
9	ReedHycalog	TKC63-P1	A271436	7	8.75	5610.0	5999.0	389.0	14.8	26.3
10	ReedHycalog	FTKC73-A1	A275803	8	8.75	5999.0	7208.0	1209.0	52.1	23.2
11	ReedHycalog	FTKC73-A1	A276121	9	8.75	7208.0	7620.0	412.0	4.8	85.8
12	E6	Hammer	-	-	8.75	7620.0	7628.0	8.0	0.8	10.0
13	ReedHycalog	FTKC63-A1	A276121	-	8.75	7628.0	7663.0	35.0	1.1	31.8
14	E6	Hammer	-	-	8.75	7663.0	7667.0	4.0	0.8	5.0
15	ReedHycalog	TKC63-P1	A271437	10	8.75	7667.0	8900.0	1233.0	37.0	33.3
16	ReedHycalog	FTKC83-A3	A276071	11	8.75	8900.0	9145.0	245.0	3.2	76.6




Figure 2-2. Utah FORGE Well 56-32 Bit Program and Performance Summary.

Individual bit run summaries and processed data for FORGE well 78B-32 is summarized in Section 3.

2.5. Depth vs Days Summary




Figure 2-3. Depth vs Days Summary for Utah FORGE Well 56-32.

3. BIT RUN SUMMARIES AND PROCESSED DATA

3.1. Bit-01

Table 3-1: Bit 1 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
1	2/8/2021	17.50	ReedHycalog	TK59-B1	A25419
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
1	133	380	247	1.2	205.8

Table 3-2: BHA 1 component makeup.

BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	JETS 5 X 18 PDC BIT TFA=1.243		7.5	3	1.2	1.3
2	9 5/8 MOTOR 6.7L 5.0Stg .13RPG		9.625		33.63	34.83
3	NMST STAB	17.25	8.0625	3	5.4	40.23
4	4 SHOCK TOOL		8.0625	2.875	12.68	52.91
5	NMUBHO		8.125	3.75	3.53	56.44
6	NMDC		7.875	3.25	28.96	85.4
7	XO				3.34	88.74

3.2. Bit-02

Table 3-3: Bit 2 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
2	2/9/2021	12.25	Mill Tooth	M-22	-
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
-	381	390	9	0.1	90.0

3.3. Bit-03

Table 3-4: Bit 3 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
3	2/9/2021	12.25	ReedHycalog	TKC66-R1	A266974
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
2	390	3308	2918	9.7	300.9

Table 3-5: BHA 2 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	JETs 6 x 14 PDC BIT TFA= 0.9019		12.35	3	1.2	1.2
2	8" MOTOR 7:8L 5.9Stg .16RPG		8		33.12	34.32
3	NMUBHO		8.125	3.75	3.53	37.85
4	NM STAB		8	3	4.85	42.7
5	NMDC		7.875	3.25	28.96	71.66
6	SHOCK TOOL		8.0625	2.875	12.68	84.34
7	DRILL COLLAR		8	3	273.61	357.95
8	XO				3.19	361.14
9	24 x HWDP		5	3.25	730.42	1091.56




Images:



Figure 3-1. Post-drill photo of bit #3.

Bit Run Figures:





3.4. Bit-04

Table 3-6: Bit 4 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
4	2/10/2021	12.25	ReedHycalog	TKC63-A1A	A26B2226
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
3	3308	3500	192	2.6	73.5

Table 3-7: BHA 3 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	JETs 6 x 14 PDC BIT TFA= 0.9019		12.35	3	1.2	1.2
2	8" MOTOR 7:8L 5.9Stg .16RPG		8		33.12	34.32
3	NMUBHO		8.125	3.75	3.53	37.85
4	NM STAB		8	3	4.85	42.7
5	NMDC		7.875	3.25	28.96	71.66
6	SHOCK TOOL		8.0625	2.875	12.68	84.34
7	DRILL COLLAR		8	3	273.61	357.95
8	XO				3.19	361.14
9	24 x HWDP		5	3.25	730.42	1091.56




Images:



Figure 3-2. Post-drill photo of bit #4.

Bit Run Figures:





3.5. Bit-05

Table 3-8: Bit 5 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
5	2/11/2021	8.75	Hughes	TOOTH GX-117	
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
4	3500	3506	6	0.8	7.5

Table 3-9: BHA 4 component makeup.

BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets4x13 3x12 PDC TFA=.849		8.75	1.5	0.85	0.85
2	7" Motor 6:7 6.5 1.50Fixed	8.5	7		33.02	33.87
3	NMUBHO		6.8125	3.25	3.04	36.91
4	NM STAB	8.5	6.5	3	4.12	41.03
5	NMDC		6.5	3.25	27.81	68.84
6	SHOCK TOOL		6.75		10.73	79.57
7	12XDC'S		6.5	2.875	368.13	447.7
8	24XHWDP		5	3.25	730.42	1178.12

3.6. Bit-06

Table 3-10: Bit 6 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
6	2/13/2021	8.75	ReedHycalog	TKC73-H1	A275660
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
4	3506	4595	1089	28.9	37.7

Table 3-11: BHA 4 component makeup.




BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets4x13 3x12 PDC TFA=.849		8.75	1.5	0.85	0.85
2	7" Motor 6:7 6.5 1.50Fixed	8.5	7		33.02	33.87
3	NMUBHO		6.8125	3.25	3.04	36.91
4	NM STAB	8.5	6.5	3	4.12	41.03
5	NMDC		6.5	3.25	27.81	68.84
6	SHOCK TOOL		6.75		10.73	79.57
7	12XDC'S		6.5	2.875	368.13	447.7
8	24XHWDP		5	3.25	730.42	1178.12




Images:



Figure 3-3. Post-drill photo of bit #6.

Bit Run Figures:





3.7. Bit-07

Table 3-12: Bit 7 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
7	2/14/2021	8.75	Hughes	EP5475	5042714
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
5	4595	5143	548	26.2	20.9

Table 3-13: BHA 5 component makeup.




BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 3x20 TriCone/TFA .92		8.75	1.5	0.85	0.85
2	7" Motor 6:7 6.5 1.50Fixed	8.5	7		33.07	33.92
3	NMUBHO		6.8125	3.25	3.04	36.96
4	NM STAB	8.5	6.5	3	4.54	41.5
5	NMDC		6.5	3.25	27.81	69.31
6	SHOCK TOOL		6.75		10.69	80
7	12XDC'S		6.5	2.875	368.13	448.13
8	24XHWDP		5	3.25	730.42	1178.55




Images:



Figure 3-4. Post-drill photo of bit #7.

Bit Run Figures:





3.8. Bit-08

Table 3-14: Bit 8 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
8	2/16/2021	8.75	ReedHycalog	TKC63-P1	A277166
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
6	5143	5610	467	15.5	30.1

Table 3-15: BHA 6 component makeup.




BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 6X14 PDC/TFA .902		8.75	1.5	0.85	0.85
2	7" Motor 6:7 6.5 1.50 Fixed	8.5	7		33.02	33.87
3	NMUBHO		6.8125	3.25	3.04	36.91
4	NM STAB	8.5	6.5	3	4.54	41.45
5	NMDC		6.5	3.25	27.81	69.26
6	SHOCK TOOL		6.75		10.69	79.57
7	12XDC'S		6.5	2.875	368.13	448.08
8	24XHWDP		5	3.25	730.42	1178.5




Images:



Figure 3-5. Post-drill photo of bit #8.

Bit Run Figures:





3.9. Bit-09

Table 3-16: Bit 9 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
9	2/17/2021	8.75	ReedHycalog	TKC63-P1	A271436
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
7	5610	5999	389	14.8	26.3

Table 3-17: BHA 7 component makeup.




BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 3X14 3X13 PDC/TFA .846		8.75	1.5	0.85	0.85
2	7" Motor 6:7 6.5 1.50Fixed	8.5	7		33.07	33.92
3	NMUBHO		6.8125	3.25	3.04	36.96
4	NM STAB	8.5	6.5625	3	5.1	42.06
5	NMDC		6.5	3.25	27.81	69.87
6	SHOCK TOOL		6.875		10.8	80.67
7	12XDC'S		6.5	2.875	368.13	448.8
8	24XHWDP		5	3.25	730.42	1178.22




Images:



Figure 3-6. Post-drill photo of bit #9.

Bit Run Figures:





3.10. Bit-10

Table 3-18: Bit 10 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
10	2/18/2021	8.75	ReedHycalog	FTKC73	A275803
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
8	5999	7208	1209	52.1	23.2

Table 3-19: BHA 8 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 3X12 4X13 PDC/TFA .850		8.75	1.5	0.85	0.85
2	7" Motor 7:8 8.5 1.50Fixed	8.5	7		34.24	35.09
3	NMUBHO		6.8125	3.25	3.04	38.13
4	NM STAB	8.5	6.5625	3	4.7	42.83
5	NMDC		6.5	3.25	27.81	70.64
6	12XDC'S		6.5	2.875	368.13	438.77
7	24XHWDP		5	3.25	730.42	1169.19




Images:



Figure 3-7. Post-drill photo of bit #10.

Bit Run Figures:





3.11. Bit-11

Table 3-20: Bit 11 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
11	2/20/2021	8.75	ReedHycalog	FTKC63-A1	A276121
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
9	7208	7620	412	4.8	85.8

Table 3-21: BHA 9 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 3X14 4X13 PDC/TFA .840		8.75	1.5	0.85	0.85
2	7" Motor 7:8 8 6.1 1.50Fixed	8.5	7		30.18	31.03
3	NMUBHO		6.8125	3.25	3.04	34.07
4	NM STAB	8.5	6.5625	2.8125	4.61	38.68
5	NMDC		6.5	3.25	27.81	66.49
6	12XDC'S		6.5	2.875	368.13	434.62
7	24XHWDP		5	3.25	730.42	1165.04




Images:



Figure 3-8. Post-drill photo of bit #11.

Bit Run Figures:





3.12. Bit-12

Table 3-22: Bit 12 run summary.




Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
12	2/22/2021	8.75	E6	Hammer	
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
-	7620	7627	7	0.8	10.0




3.13. Bit-13

Table 3-23: Bit 13 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
13	2/22/2021	8.75	ReedHycalog	FTKC63-A1	AZ276121
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
-	7627	7662	35	1.1	31.8

Bit Run Figures:





3.14. Bit-14

Table 3-24: Bit 14 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
14	2/23/2021	8.75	E6	MH180-04	
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
-	7663	7667	4	0.8	5.0

3.15. Bit-15

Table 3-25: Bit 15 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
15	2/23/2021	8.75	ReedHycalog	TKC63-P1	A271437
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
10	7666	8900	1234	37.0	33.3

Table 3-26: BHA 10 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 3x13 3x14 PDC/TFA .840		8.75	1.5	0.85	0.85
2	7" Motor 7:8 8 6.1 1.50Fixed	8.5	7		30.17	31.02
3	NMUBHO		6.8125	3.25	3.42	34.44
4	NM STAB	8.5	6.5	2.8125	3.2	37.64
5	NMDC		6.5	3.25	27.1	64.74
6	12XDC'S		6.5	2.875	368.05	432.79
7	JARS		6.5	3	33.51	466.3
8	24XHWDP		5	3.25	730.42	1196.72




Images:



Figure 3-9. Post-drill photo of bit #15.

Bit Run Figures:





3.16. Bit-16

Table 3-27: Bit 16 run summary.

Run No.	Run Date	Bit Diameter (in)	Manufacturer	Type	Serial No
16	2/26/2021	8.75	ReedHycalog	TKC83-A3	A276071
BHA No.	Depth Start (ft)	Depth End (ft)	Total Footage (ft)	Time on Bottom (hrs)	Net ROP (ft/hr)
11	8900	9145	245	3.2	76.6

Table 3-28: BHA 10 component makeup.


BHA No.	Component	Stab. OD	OD	ID	Length	Cum. Length
1	Jets 4x12 4x11 PDC/TFA .813		8.75	1.5	0.85	0.85
2	7" Motor 7:8 8.5 1.50Fixed	8.5	7		34.28	35.13
3	NMUBHO		6.8125	3.25	3.42	38.55
4	NM STAB	8.5	6.5	2.8125	4.55	43.1
5	NMDC		6.5	3.25	27.1	70.2
6	12XDC'S		6.5	2.875	368.05	438.25
7	JARS		6.5	3	33.51	471.76
8	24XHWDP		5	3.25	730.42	1202.18




Images:



Figure 3-10. Post-drill photo of bit #16.

Bit Run Figures:





This page left blank

REFERENCES

- [1] Moore, J. D., Characteristics of the Utah FORGE Site,
<https://gdr.openet.org/submissions/1209>, ARMA2019_JMoore-FORGE.pdf, (2019).
- [2] Glowka, D. A., Development of a Method for Predicting the Performance and Wear of PDC Drill Bits, SAND86-1745, (1987).
- [3] Detournay, E., Defourny, P., “A Phenomenological Model for the Drilling Action of Drag Bits,” Int. J. Rock Mech. Min. Sci. & Geomech. Abstr., Vol. 29, No.1, (1992) 13-23.
- [4] Raymond, D., “PDC Bits Demonstrate Benefit Over Conventional Hard-Rock Drill Bits,” Geothermal Resources Council Transactions, Vol. 25, (2001) 125-132.
- [5] Raymond, D., et al, “PDC Bits Outperform Conventional Bit in Geothermal Drilling Project,” Geothermal Resources Council Transactions, Vol. 36, (2012) 307-315.
- [6] Bourgoyne, A.J.T., Chenevert, M.E. & Millheim, K.K., 1986. SPE Textbook Series, Volume 2: Applied Drilling Engineering, Society of Petroleum Engineers.
- [7] Winkler, D., and Swearingen, L., “Summary of Drilling Activities: Well 16A(78)-32,” Mar 2021.
- [8] Stevenson, M., et al, “FORGE 16A(78)-32 Drill Bit Analysis,” January 2021.
- [9] Stevenson, M., et al, “FORGE 56-32 Drill Bit Performance,” 02/27/2021.
- [10] ReedHycalog, Drill Bit Performance, FORGE 56-32 - Complete Well, Feb 27, 2021 (received).
- [11] Scientific Drilling, End of Well Report, Utah FORGE 16B(78)-32, June 2023

This page left blank

APPENDIX A. DAILY DRILLING REPORTS

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 2

Report For 06-Feb-21

Operator:		University of Utah		Rig:	Frontier		Spud Date:		Daily Cost / Mud (\$):			---					
Measured Depth (ft):		128		Last Casing:		20.000 at 129		Wellbore:		Original Wellbore		AFE No.		AFE (\$)		Actual (\$)	
Vertical Depth (ft):		128		Next Casing:		13.375 at 350		RKB Elevation (ft):		28.50		---		---		---	
Proposed TD (ft):		9000		Last BOP Test:				Job Reference RKB (ft):		28.50		---		---		---	
Hole Made (ft) / Hrs:		0 / 0.0		Next BOP Test:				Working Interest:				Totals:		---		---	
Average ROP (ft/hr):												Well Cost (\$):		---		---	
Drilling Days (act./plan):		0/30		Flat Days (act./plan):		0/8		Total Days (act./plan):		0/38		Days On Location:				2	
Pers/Hrs: Operator:		2 / 24		Contractor:		14 / 168		Service:		23 / 276		Other:		0 / 0		Total: 39 / 468	

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Safety meeting and initiating final rig up.

Planned Operations: Rig up on Forge 16A.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	6:00	6.00	128	OTHER	Wait on Day Light.	
6:00	18:00	12.00	128	RIGU	Set in place rig components and heavy loads, Draw works, A-Frame, Derrick and strung blocks. Raised derrick. Rigged up equipment.	
18:00	0:00	6.00	128	OTHER	Wait on Day Light.	

Management Summary

Set in all major components of Frontier's Rig 16 including sub-base, draw works, A-Frame and derrick. Raised derrick and continued nipple up.

Comments

Rig is 100% moved and 40% rigged up. Expected spud late 2-7-2021 or early 2-8-21.

Casing/Tubular Information


Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	29		129						

Safety Information

Meetings/Drills	Time	Description
Safety	30	Rig Move, safety belts, pinch points and working in teams.
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	21 degF	Bar. Pressure:	30.03
Wind Speed/Dir:	15 / N	Wind Gusts:	25

	Daily Drilling Report Well ID: Forge 56-32 Field: Other				Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT			
	Report No: 3				Report For 07-Feb-21			
	Operator: University of Utah		Rig: Frontier		Spud Date:		Daily Cost / Mud (\$): ---	
Measured Depth (ft): 128		Last Casing: 20.000 at 129		Wellbore: Original Wellbore		AFE No. AFE (\$) Actual (\$)		
Vertical Depth (ft): 128		Next Casing: 13.375 at 350		RKB Elevation (ft): 28.50		--- --- ---		
Proposed TD (ft): 9000		Last BOP Test:		Job Reference RKB (ft): 28.50		--- --- ---		
Hole Made (ft) / Hrs: 0 / 0.0		Next BOP Test:		Working Interest:		Totals: --- --- ---		
Average ROP (ft/hr):						Well Cost (\$): ---		
Drilling Days (act./plan): 0/30		Flat Days (act./plan): 0/8		Total Days (act./plan): 0/38		Days On Location: 3		
Pers/Hrs: Operator: 2 / 24		Contractor: 14 / 168		Service: 1 / 12		Other: 0 / 0 Total: 17 / 204		
Safety Summary: No incidents or events reported. Conducted Safety Meeting.								
Current Operations: Morning Safety meeting.								
Planned Operations: Plan to bring in and strap drill pipe and casing. Install riser pipe, mix mud and prepare to spud.								
Toolpusher: Justin Bristol, Steve Caldwell								
Wellsite Supervisors: Virgil Welch, Paul Stroud						Tel No.: 7132807438		
Operations Summary								
From	To	Elapsed	End MD(ft)	Code	Operations Description		Non-Prod	
0:00	6:00	6.00	128	OTHER	Waited on Day Light.			
6:00	18:00	12.00	128	RIGU	Set in Top Drive and track, wind walls and nipped up equipment.			
18:00	0:00	6.00	128	OTHER	Waited on Day Light.			
Management Summary								
Continued rig up. Installed top drive unit, wind walls, connected mud and air lines. Set in fresh water tank. Rigged up solids control unit.								
Comments								
Rig is 100% moved and 80% rigged up. Expected spud late 2-7-2021 or early 2-8-21.								
Casing/Tubular Information								
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	
FULL	20.000	29		129				
Safety Information								
Meetings/Drills	Time	Description						
Safety	30	Working in dark spots, pinch points and team work during rig moves.						
First Aid Treatments:		Medical Treatments:		Lost Time Incidents:		Days Since LTI:		
<input type="checkbox"/> BOP Test		<input type="checkbox"/> Crownamatic Check						
Weather Information								
Sky Condition: Clear		Visibility: 10						
Air Temperature: 27 degF		Bar. Pressure: 29.97						
Wind Speed/Dir: 15 / SSW		Wind Gusts: 20						

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 4

Report For 07-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	128	Last Casing:	20.000 at 129	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	128	Next Casing:	13.375 at 350	RKB Elevation (ft):	30.40	---	---	---	
Proposed TD (ft):	9000	Last BOP Test:		Job Reference RKB (ft): 28.50		---	---	---	
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---	---	
Average ROP (ft/hr):						Well Cost (\$):			---
Drilling Days (act./plan):		0/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	0/38	Days On Location:		4
Pers/Hrs:	Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total: 24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Drilled 17-1/2" hole to 380' casing point, circulating well bore clean for casing run.

Planned Operations: Drill 17-1/2" hole to 380.5' and circulate well bore clean. POH and run 13-3/8" casing and cement in place.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	6:00	6.00	128	WOD	Wait on Day Light	
6:00	10:30	4.50	128	OTHER	Pre-Spud Inspection of Rig	
10:30	17:00	6.50	128	3-34-1	Picked up 112 joints (37 stands) 5" DP and stood back in derrick. Strapped, OD, ID, FN 24 joints of HWDP and nine 8" DC	
17:00	17:30	0.50	128	SERV	Serviced Rig and Top Drive.	
17:30	21:00	3.50	128	3-34-1	Picked up 7 stands of HWDP and 3 stands of 8" DC	
21:00	22:30	1.50	128	OTHER	Cleaned and strapped 13-3/8" casing.	
22:30	23:00	0.50	128	OTHER	Cleaned Rig floor.	
23:00	0:00	1.00	128	3-34-3	Picked up directional tools.	

Management Summary

Waited on Day Light and conducted Pre-Spud Rig Inspection. Picked up 112 joint (37 Stands) of 5" DP and stood back in derrick. Strapped, OD, ID and Fishing Neck of HWDP. Picked up 7 stands of HWDP and stood back in Derrick. Cleaned and strapped 13-3/8" Casing. Made up Directional tools.

Comments

Rig on "Day Rate" at 0600 hours, 2-7-2021.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30		129						

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	CI	Ca	CaCl	10s	10m	30m	In	Out	Loss
07-Feb-21 22:00 at Depth 128 ft																				
8.30	26					8		0				900								

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Gel - OTHER	145	---	lime - OTHER	2	---
micro c - OTHER	32	---	soda ash - OTHER	10	---

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	112	19.5	S-135	4.5IF					



Daily Drilling Report

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 4

Report For 07-Feb-21

Safety Information

Meetings/Drills	Time	Description
Safety	30	Mixing chemical, pinch points, running casing.
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownmatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	30 degF	Bar. Pressure:	29.92
Wind Speed/Dir:	14 / S	Wind Gusts:	17

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 5

Report For 08-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	381	Last Casing:	13.375 at 382	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	381	Next Casing:	9.625 at 3,500	RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:		Job Reference RKB (ft):	28.50	---	---		---
Hole Made (ft) / Hrs:	253 / 2.0	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):	126.5					Well Cost (\$):			---
Drilling Days (act./plan):	1/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	1/38	Days On Location:			5
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	11 / 124	Other:	0 / 0	Total:	27 / 316
Safety Summary: No incidents or events reported. Conducted Safety Meeting.									
Current Operations:	Testing BOPE								
Planned Operations:	Test Bope, make up DA and clean out float, cement and shoe, make 10' of new hole and perform FIT. Drill 12 1/4" hole vertically to 3,500' +/-.								
Toolpusher:	Justin Bristol, Steve Caldwell								
Wellsite Supervisors:	Virgil Welch, Paul Stroud					Tel No.: 7132807438			

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	128	10-6-1	Picked up directional tools.	
1:00	1:30	0.50	128	OTHER	Installed rotating head rubber.	
1:30	2:00	0.50	128	03-051	Filled pipe and hole.	
2:00	4:00	2.00	128	REPR	Trouble shot and replaced swivel packing.	X
4:00	4:30	0.50	128	OTHER	Changed rotating head rubber	
4:30	6:00	1.50	381	03-021	Drilled 17-1/2" hole from 128' to 380.5'.	
6:00	6:30	0.50	381	03-051	Circulated well bore clean.	
6:30	7:00	0.50	381	WIPE	Wiper Trip.	
7:00	7:30	0.50	381	03-051	Circulated well bore clean.	
7:30	8:00	0.50	381	3-6-2	Pulled out of the hole.	
8:00	9:00	1.00	381	11-344	Laid down BHA.	
9:00	12:00	3.00	381	4-12-1	Rigged up and ran 13-3/8", 54.5 ppf, J-55 buttress casing with shoe set at 381'.	
12:00	13:30	1.50	381	5-12-2	Rigged up cementers and circulated hole clean.	
13:30	14:30	1.00	381	5-12-2	Pumped 10 bbls of water ahead followed by 30 bbls of 10.5 sepiolite preflush plus 13 barrels of sodium silicate, 5 bbls of fresh water spacer followed by 79 bbls of 14 ppg RC Thermalite-a cement, dropped wiper plug and displaced with 52.25 bbls of water and bumped plug with 500 psi over. CIP at 1430 hours.	
14:30	21:00	6.50	381	5-13	Waited on cement. Cut off 20" conductor and 13.375" casing.	
21:00	0:00	3.00	381	6-35	Attempted to install well head, had wrong energizer ring, removed and installed new dies and energizer ring. Tested seals, packed off and pulled tested to 10k. Installed casing valves.	

Management Summary

Drilled 17-1/2" hole from 228' to 380'. Circulated hole clean and wiped hole. Circulated well bore clean and pulled out laying down tools. Rigged up and ran 9 joints of 54.5 ppf, J-55 Buttress casing setting shoe at 380. Rigged up Resource cementing and cemented casing in place. Cut off conductor and sized 13-3/8" casing. Attempted to install well head. Replaced dies and energizer seal and installed well head.

Comments

Good cement to surface.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
08-Feb-21 08:00 at Depth 380 ft																				
8.70	52	15	24	9	1	10	4	0	96	1.5		1000	1480		5	12	22	65	85	

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 5

Report For 08-Feb-21

Rig Information

Equipment Problems:

Location Condition:

Transport:

Bulk Inventory

Item Type	Units	Beginning	Used	Received	On Hand	Net
Rig Fuel	GALS	9,282	886		8,396	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	112	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time

Description

Safety 60 Nippling and testing BOPE

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crowmamic Check**Weather Information**

Sky Condition: Clear

Visibility: 10

Air Temperature: 37 degF

Bar. Pressure: 29.94

Wind Speed/Dir: 17 / S

Wind Gusts: 20

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 6

Report For 09-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	2500	Last Casing:	13.375 at 382	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	2500	Next Casing:	9.625 at 3,500	RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:		Job Reference RKB (ft): 28.50		---	---		---
Hole Made (ft) / Hrs:	2,119 / 9.0	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):	235.44					Well Cost (\$):			---
Drilling Days (act./plan):	2/30	Flat Days (act./plan):	0/8	Total Days (act./plan): 2/38		Days On Location:			6
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	2 / 24	Other:	2 / 24	Total:	20 / 240

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Circulating the well bore clean at 3,270' preparing for a wiper trip to the shoe.

Planned Operations: Continue to drill 12-1/4" hole to casing point at 3,500'+/- . Run 9-5/8" casing.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	381	1-14	Installed valves on well head and tightened.	
1:00	5:30	4.50	381	1-14	Installed spool, mud cross, double gates, annular, flow spool, choke line, choke hose and torqued all flanges.	
5:30	10:30	5.00	381	1-15	Tested BOPE system, emailed results to DWR (Jim Goddard).	
10:30	11:00	0.50	381	3-6-1	Ran in the hole with 12-1/4" Bit.	
11:00	12:00	1.00	390	03-021	Drilled out float, shoe and drilled 12-1/4" hole from 380' to 390'.	
12:00	12:30	0.50	390	03-051	Circulated hole clean.	
12:30	13:00	0.50	390	3-46	Performed FIT	
13:00	13:30	0.50	390	3-6-2	Pulled out of the well bore.	
13:30	15:30	2.00	390	4-34-3	Made up Bit #3 with mud motor and tools.	
15:30	16:30	1.00	390	4-6-1	Ran in hole and installed rotating well head.	
16:30	22:30	6.00	2,226	3-2-2	Drilled 12-1/4" hole rotating and sliding from 390' to 2,226'	
22:30	23:00	0.50	2,226	03-051	Circulated well bore clean.	
23:00	0:00	1.00	2,500	3-2-2	Drilled 12-1/4" hole rotating and sliding from 2,226' to 2,500'.	

Management Summary

Installed BOPE, tested BOPE, Made up bit on slick assembly and cleaned out float collar, cement and shoe. Drilled 10' of new hole from 3,80' to 3,90'. Performed FIT. Tripped for PDC bit on mud motor and drilled 12-1/4" hole from 390' to 2,500'.

Comments

Slid from 1,487' to 1,514'

Slid from 1,860' to 1,890'


Clay has cleaned up and hit the top of the granite at around 3,240'.


Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	

Mud Information

%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
09-Feb-21 21:45 at Depth 2,034 ft Mud Pits																				
8.80	44	15	16	7.2	1	10.5	8	0	92	2		1200			6	11	20	47	127	

	Daily Drilling Report Well ID: Forge 56-32 Field: Other										Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT																																																																																																																													
	Report No: 6										Report For 09-Feb-21																																																																																																																													
	Mud Consumables																																																																																																																																							
<table border="1"> <thead> <tr> <th>Item Description</th> <th>Qty.</th> <th>Cost</th> </tr> </thead> <tbody> <tr> <td>Bicarb - OTHER</td> <td>12</td> <td>---</td> </tr> <tr> <td>Desco - OTHER</td> <td>5</td> <td>---</td> </tr> <tr> <td>Drispac - OTHER</td> <td>7</td> <td>---</td> </tr> <tr> <td>PAllets/Wrap - OTHER</td> <td>6</td> <td>---</td> </tr> <tr> <td>walnut Pine - OTHER</td> <td>40</td> <td>---</td> </tr> </tbody> </table>										Item Description	Qty.	Cost	Bicarb - OTHER	12	---	Desco - OTHER	5	---	Drispac - OTHER	7	---	PAllets/Wrap - OTHER	6	---	walnut Pine - OTHER	40	---	<table border="1"> <thead> <tr> <th>Item Description</th> <th>Qty.</th> <th>Cost</th> </tr> </thead> <tbody> <tr> <td>caustic - OTHER</td> <td>2</td> <td>---</td> </tr> <tr> <td>DMA/SPA - 100#SK</td> <td>13</td> <td>---</td> </tr> <tr> <td>Gel - OTHER</td> <td>80</td> <td>---</td> </tr> <tr> <td>SAwdust - OTHER</td> <td>2</td> <td>---</td> </tr> <tr> <td>xanthan gum - OTHER</td> <td>2</td> <td>---</td> </tr> </tbody> </table>										Item Description	Qty.	Cost	caustic - OTHER	2	---	DMA/SPA - 100#SK	13	---	Gel - OTHER	80	---	SAwdust - OTHER	2	---	xanthan gum - OTHER	2	---																																																																																	
Item Description	Qty.	Cost																																																																																																																																						
Bicarb - OTHER	12	---																																																																																																																																						
Desco - OTHER	5	---																																																																																																																																						
Drispac - OTHER	7	---																																																																																																																																						
PAllets/Wrap - OTHER	6	---																																																																																																																																						
walnut Pine - OTHER	40	---																																																																																																																																						
Item Description	Qty.	Cost																																																																																																																																						
caustic - OTHER	2	---																																																																																																																																						
DMA/SPA - 100#SK	13	---																																																																																																																																						
Gel - OTHER	80	---																																																																																																																																						
SAwdust - OTHER	2	---																																																																																																																																						
xanthan gum - OTHER	2	---																																																																																																																																						
Bit/BHA/Workstring Information																																																																																																																																								
<table border="1"> <thead> <tr> <th colspan="2">No Run</th> <th>Make</th> <th>Model</th> <th>Diam</th> <th>Depth In</th> <th>This Run Dist</th> <th>R.O.P. Avg</th> <th>Max</th> <th>WOB</th> <th>RPM</th> <th>Torque</th> <th>Wt</th> <th>Mud Flow</th> <th>Pump Press</th> <th>J. Vel</th> <th>P. Drp</th> <th>HPH</th> <th>JIF</th> </tr> </thead> <tbody> <tr> <td>2</td> <td>1</td> <td>REED</td> <td>M-22</td> <td>12.250</td> <td>380</td> <td>9</td> <td>1</td> <td>9.0</td> <td></td> <td></td> <td></td> <td></td> <td>9</td> <td>800</td> <td>2900</td> <td>327</td> <td>841</td> <td>392</td> <td>1191</td> </tr> <tr> <td colspan="5">Jets: 16 16 16 16</td> <td>Out: 390</td> <td colspan="2">Grade: Cutter: 1 / 1</td> <td>Dull: NO / NO</td> <td>Wear: A</td> <td>Brgs: 0</td> <td>Gge: 1</td> <td colspan="7">Pull: TD</td> </tr> <tr> <td>3</td> <td>1</td> <td>REED</td> <td>TKC66</td> <td>12.250</td> <td>390</td> <td>2,110</td> <td>7</td> <td>301.4</td> <td></td> <td></td> <td></td> <td></td> <td>9</td> <td>800</td> <td>2900</td> <td>285</td> <td>638</td> <td>298</td> <td>1037</td> </tr> <tr> <td colspan="5">Jets: 14 14 14 14 14 14</td> <td>Out:</td> <td colspan="2">Grade: Cutter: /</td> <td>Dull: /</td> <td>Wear:</td> <td>Brgs:</td> <td>Gge:</td> <td colspan="7">Pull:</td> </tr> <tr> <td colspan="20">BHA - No. 3 - BIT, MMTR, XO, STAB, MONEL, SHOCK, 9 DC, XO, 24 HWDP = 1091.56</td> </tr> </tbody> </table>																				No Run		Make	Model	Diam	Depth In	This Run Dist	R.O.P. Avg	Max	WOB	RPM	Torque	Wt	Mud Flow	Pump Press	J. Vel	P. Drp	HPH	JIF	2	1	REED	M-22	12.250	380	9	1	9.0					9	800	2900	327	841	392	1191	Jets: 16 16 16 16					Out: 390	Grade: Cutter: 1 / 1		Dull: NO / NO	Wear: A	Brgs: 0	Gge: 1	Pull: TD							3	1	REED	TKC66	12.250	390	2,110	7	301.4					9	800	2900	285	638	298	1037	Jets: 14 14 14 14 14 14					Out:	Grade: Cutter: /		Dull: /	Wear:	Brgs:	Gge:	Pull:							BHA - No. 3 - BIT, MMTR, XO, STAB, MONEL, SHOCK, 9 DC, XO, 24 HWDP = 1091.56																			
No Run		Make	Model	Diam	Depth In	This Run Dist	R.O.P. Avg	Max	WOB	RPM	Torque	Wt	Mud Flow	Pump Press	J. Vel	P. Drp	HPH	JIF																																																																																																																						
2	1	REED	M-22	12.250	380	9	1	9.0					9	800	2900	327	841	392	1191																																																																																																																					
Jets: 16 16 16 16					Out: 390	Grade: Cutter: 1 / 1		Dull: NO / NO	Wear: A	Brgs: 0	Gge: 1	Pull: TD																																																																																																																												
3	1	REED	TKC66	12.250	390	2,110	7	301.4					9	800	2900	285	638	298	1037																																																																																																																					
Jets: 14 14 14 14 14 14					Out:	Grade: Cutter: /		Dull: /	Wear:	Brgs:	Gge:	Pull:																																																																																																																												
BHA - No. 3 - BIT, MMTR, XO, STAB, MONEL, SHOCK, 9 DC, XO, 24 HWDP = 1091.56																																																																																																																																								
Drilling Parameters																																																																																																																																								
Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure																																																																																																																												
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	psi																																																																																																																										
390	2,500	450.0	950.0	25	40	60	80	2	8	800	800	3,150																																																																																																																												
Annular Velocity:				Drill Collars:		203.0		Drill Pipe:		222.0																																																																																																																														
Miscellaneous Drilling Parameters																																																																																																																																								
Hook Loads (lbs):				Off Bottom Rotate:				Pick Up:		140		Slack Off:		125		Drag Avg/Max:		10 / 12																																																																																																																						

	Daily Drilling Report Well ID: Forge 56-32 Field: Other					Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT				
	Report No: 6					Report For 09-Feb-21				
	Survey Information									
Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		D.L.S.	
							N-S	E-W		
MWD	401.0	0.70	31.4	401.0	1.9	1.3	N 1.3	E 1.4	0.275	
MWD	493.0	0.70	352.1	493.0	2.9	2.4	N 2.4	E 1.6	0.511	
MWD	585.0	1.14	358.3	585.0	4.1	3.9	N 3.9	E 1.5	0.489	
MWD	767.0	1.36	355.0	767.0	5.5	5.5	N 5.5	W 0.3	1.992	
MWD	858.0	1.54	7.2	857.9	7.8	7.8	N 7.8	W 0.2	0.392	
MWD	949.0	1.41	6.3	948.9	10.1	10.1	N 10.1	E 0.1	0.145	
MWD	1,040.0	1.54	10.5	1,039.9	12.4	12.4	N 12.4	E 0.4	0.184	
MWD	1,135.0	1.71	5.6	1,134.8	15.1	15.1	N 15.1	E 0.8	0.230	
MWD	1,230.0	1.85	13.5	1,229.8	18.0	18.0	N 18.0	E 1.3	0.295	
MWD	1,325.0	1.85	16.9	1,324.7	21.1	21.0	N 21.0	E 2.1	0.117	
MWD	1,419.0	2.02	16.7	1,418.7	24.2	24.0	N 24.0	E 3.0	0.181	
MWD	1,514.0	1.36	30.5	1,513.6	26.9	26.6	N 26.6	E 4.1	0.811	
MWD	1,608.0	1.54	37.5	1,607.6	29.0	28.5	N 28.5	E 5.4	0.269	
MWD	1,703.0	1.71	43.6	1,702.6	31.4	30.6	N 30.6	E 7.1	0.254	
MWD	1,798.0	1.98	49.1	1,797.5	34.0	32.7	N 32.7	E 9.4	0.340	
MWD	1,892.0	1.36	55.8	1,891.5	36.2	34.4	N 34.4	E 11.5	0.690	
MWD	1,986.0	1.27	71.7	1,985.5	37.8	35.3	N 35.3	E 13.4	0.398	
MWD	2,081.0	1.45	63.0	2,080.4	39.4	36.2	N 36.2	E 15.5	0.288	
MWD	2,175.0	1.23	72.4	2,174.4	41.0	37.0	N 37.0	E 17.5	0.330	
MWD	2,270.0	1.49	60.7	2,269.4	42.7	37.9	N 37.9	E 19.6	0.399	
MWD	2,365.0	1.36	74.3	2,364.3	44.5	38.9	N 38.9	E 21.7	0.379	
MWD	2,458.0	1.32	71.2	2,457.3	46.1	39.5	N 39.5	E 23.8	0.088	
MWD	2,551.0	1.67	73.7	2,550.3	48.0	40.2	N 40.2	E 26.1	0.383	
MWD	2,648.0	2.02	78.9	2,647.2	50.3	40.9	N 40.9	E 29.2	0.401	
MWD	2,743.0	2.02	85.3	2,742.2	52.6	41.4	N 41.4	E 32.5	0.235	
MWD	2,839.0	1.54	70.3	2,838.1	54.9	42.0	N 42.0	E 35.4	0.691	
MWD	2,934.0	1.27	61.7	2,933.1	57.0	42.9	N 42.9	E 37.5	0.360	
MWD	3,029.0	1.80	66.0	3,028.1	59.3	44.0	N 44.0	E 39.8	0.571	
MWD	3,124.0	0.97	100.4	3,123.0	61.1	44.5	N 44.5	E 41.9	1.199	
MWD	3,219.0	0.70	92.6	3,218.0	62.0	44.3	N 44.3	E 43.3	0.308	
Rig Information										
Equipment Problems:										
Location Condition:										
Transport:										
Solids Control Information										
Screen Sizes:	Top	Bottom								
Shaker No 1:	170									
Shaker No 2:	170									
Shaker No 3:	140									
Drill Pipe Inventory										
DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread	
5	112	19.5	S-135	4.5IF						
Safety Information										
Meetings/Drills	Time	Description								
Safety	60	Drilling								
First Aid Treatments:		Medical Treatments:			Lost Time Incidents:			Days Since LTI:		
<input type="checkbox"/> BOP Test		<input type="checkbox"/> Crowmamic Check								



Daily Drilling Report

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 6

Report For 09-Feb-21

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	34 degF	Bar. Pressure:	29.99
Wind Speed/Dir:	12 / S	Wind Gusts:	15

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 7

Report For 10-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	Daily Cost / Mud (\$):	---
Measured Depth (ft):	3404	Last Casing:	13.375 at 382	Wellbore:	Original Wellbore	AFE No. AFE (\$) Actual (\$)
Vertical Depth (ft):	3403	Next Casing:	9.625 at 3,500	RKB Elevation (ft):	30.40	--- --- ---
Proposed TD (ft):	9000	Last BOP Test:		Job Reference RKB (ft):	28.50	--- --- ---
Hole Made (ft) / Hrs:	904 / 12.0	Next BOP Test:		Working Interest:		Totals: --- --- ---
Average ROP (ft/hr):	75.33					Well Cost (\$): ---
Drilling Days (act./plan):	3/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	3/38	Days On Location: 7
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 136	Service:	8 / 96	Other: 0 / 0 Total: 24 / 256
Safety Summary: No incidents or events reported. Conducted Safety Meeting.						
Current Operations: Pulling out of the well bore to run 9-5/8" casing.						
Planned Operations: Rig up and run 9-5/8" casing and cement in place.						
Toolpusher: Justin Bristol, Steve Caldwell						
Wellsite Supervisors: Virgil Welch, Paul Stroud					Tel No.: 7132807438	

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	2,698	3-2-2	Rotary Drilled 12-1/4" hole from 2,500' to 2,698'	
1:00	1:30	0.50	2,698	03-051	Circulated well bore clean.	
1:30	2:00	0.50	2,730	3-2-2	Slide drilled 12-1/4" hole from 2,698' to 2,730'.	
2:00	2:30	0.50	2,812	3-2-2	Rotary drilled 12-1/4" hole from 2,730' to 2,812'.	
2:30	3:00	0.50	2,852	3-2-2	Slide drilled 12-1/4" hole from 2,812' to 2,852'.	
3:00	4:00	1.00	3,082	3-2-2	Rotary drilled 12-1/4" hole from 2,852' to 3,082'.	
4:00	5:30	1.50	3,270	3-2-2	Rotary drilled 12-1/4" hole from 3,082' to 3,270'.	
5:30	6:30	1.00	3,270	03-051	Circulated and conditioned mud.	
6:30	11:30	5.00	3,270	3-2-7	Wiper trip to 380' with tight hole at 2,300'.	
11:30	13:30	2.00	3,308	3-2-2	Rotary drilled 12-1/4" hole from 3,270' to 3,308'.	
13:30	16:00	2.50	3,208	3-6-2	Pulled out of the well bore for new bit and motor.	
16:00	19:00	3.00	3,208	3-34-4	Laid down tools and picked up new bit with mud motor.	
19:00	20:00	1.00	3,208	3-6-1	Ran in the hole to 2,331'.	
20:00	22:30	2.50	3,305	3-3	Encountered tight spot and reamed 12-1/4" hole from 2,331' to 3,305'.	
22:30	0:00	1.50	3,404	3-2-2	Rotary drilled 12-1/4" hole from 3,305' to 3,404'.	

Management Summary

Drilled 12-1/4" hole from 2,500' to 3,270'. Wiped hole to 380' and reamed tight spot at 2,300'. Drilled 12-1/4" hole from 3,270' to 3,308' and pulled out of the well bore. Changed bit and motor. Ran in the hole and encountered bridge at 2,331'. Reamed 12-1/4" hole from 2,331' to 3,308'. Drilled 12-1/4" hole from 3,308' to 3,404'.

Comments

TD at 3500' is 100% Granodiorite,


After reaching TD at 3500' conducted a wiper trip to 2000' and the hole was clean.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
10-Feb-21 23:30 at Depth 3,358 ft Mud Pits																				
8.80	44	19	17	6.8	1	10.5	8	0	92	2.5		1300	880		5	13	24	70	138	

	Daily Drilling Report Well ID: Forge 56-32 Field: Other										Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT																																																																																																																																																																																																																																																																																																																			
	Report No: 7										Report For 10-Feb-21																																																																																																																																																																																																																																																																																																																			
	Mud Consumables																																																																																																																																																																																																																																																																																																																													
<table border="1"> <thead> <tr> <th>Item Description</th> <th>Qty.</th> <th>Cost</th> </tr> </thead> <tbody> <tr> <td>Barite - OTHER</td> <td>10</td> <td>---</td> </tr> <tr> <td>Desco CF - OTHER</td> <td>2</td> <td>---</td> </tr> <tr> <td>Gel - OTHER</td> <td>5</td> <td>---</td> </tr> <tr> <td>PAllets/Wrap - OTHER</td> <td>5</td> <td>---</td> </tr> </tbody> </table>										Item Description	Qty.	Cost	Barite - OTHER	10	---	Desco CF - OTHER	2	---	Gel - OTHER	5	---	PAllets/Wrap - OTHER	5	---	<table border="1"> <thead> <tr> <th>Item Description</th> <th>Qty.</th> <th>Cost</th> </tr> </thead> <tbody> <tr> <td>caustic - OTHER</td> <td>2</td> <td>---</td> </tr> <tr> <td>DMA/SPA - 100#SK</td> <td>9</td> <td>---</td> </tr> <tr> <td>micro c - OTHER</td> <td>64</td> <td>---</td> </tr> <tr> <td>xanthan gum - OTHER</td> <td>5</td> <td>---</td> </tr> </tbody> </table>										Item Description	Qty.	Cost	caustic - OTHER	2	---	DMA/SPA - 100#SK	9	---	micro c - OTHER	64	---	xanthan gum - OTHER	5	---																																																																																																																																																																																																																																																																													
Item Description	Qty.	Cost																																																																																																																																																																																																																																																																																																																												
Barite - OTHER	10	---																																																																																																																																																																																																																																																																																																																												
Desco CF - OTHER	2	---																																																																																																																																																																																																																																																																																																																												
Gel - OTHER	5	---																																																																																																																																																																																																																																																																																																																												
PAllets/Wrap - OTHER	5	---																																																																																																																																																																																																																																																																																																																												
Item Description	Qty.	Cost																																																																																																																																																																																																																																																																																																																												
caustic - OTHER	2	---																																																																																																																																																																																																																																																																																																																												
DMA/SPA - 100#SK	9	---																																																																																																																																																																																																																																																																																																																												
micro c - OTHER	64	---																																																																																																																																																																																																																																																																																																																												
xanthan gum - OTHER	5	---																																																																																																																																																																																																																																																																																																																												
Bit/BHA/Workstring Information																																																																																																																																																																																																																																																																																																																														
<table border="1"> <thead> <tr> <th colspan="4"></th> <th colspan="2">Depth</th> <th colspan="2">This Run</th> <th colspan="2">R.O.P.</th> <th colspan="10">Mud Pump</th> </tr> <tr> <th>No</th> <th>Run</th> <th>Make</th> <th>Model</th> <th>Diam</th> <th>In</th> <th>Dist</th> <th>Hrs</th> <th>Avg</th> <th>Max</th> <th>WOB</th> <th>RPM</th> <th>Torque</th> <th>Wt</th> <th>Flow</th> <th>Press</th> <th>J. Vel</th> <th>P. Drp</th> <th>HPH</th> <th>JIF</th> </tr> </thead> <tbody> <tr> <td>3</td> <td>1</td> <td>REED</td> <td>TKC66</td> <td>12.250</td> <td>390</td> <td>808</td> <td>5</td> <td>161.6</td> <td></td> <td></td> <td></td> <td></td> <td>9</td> <td>800</td> <td>2900</td> <td>95</td> <td>72</td> <td>33</td> <td>348</td> </tr> <tr> <td colspan="4">Jets: 22 22 22 22 22 22 22 11</td> <td>Out: 3308</td> <td colspan="2">Grade: Cutter: 8 / 1</td> <td colspan="2">Dull: CR / CT</td> <td colspan="2">Wear: C</td> <td colspan="2">Brgs: 0</td> <td colspan="2">Gge: 1</td> <td colspan="2">Pull: PR</td> <td colspan="4"></td> </tr> <tr> <td>4</td> <td>1</td> <td>REED</td> <td>TK63</td> <td>12.250</td> <td>3305</td> <td>192</td> <td>1.5</td> <td>128.0</td> <td></td> <td></td> <td></td> <td></td> <td>9</td> <td>800</td> <td>2900</td> <td>106</td> <td>89</td> <td>42</td> <td>388</td> </tr> <tr> <td colspan="4">Jets: 22 22 22 22 22 22 22 11</td> <td>Out:</td> <td colspan="2">Grade: Cutter: /</td> <td colspan="2">Dull: /</td> <td colspan="2">Wear:</td> <td colspan="2">Brgs:</td> <td colspan="2">Gge:</td> <td colspan="2">Pull:</td> <td colspan="4"></td> </tr> <tr> <td colspan="20">BHA - No. 4 - = 1.20</td> </tr> </tbody> </table>																								Depth		This Run		R.O.P.		Mud Pump										No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF	3	1	REED	TKC66	12.250	390	808	5	161.6					9	800	2900	95	72	33	348	Jets: 22 22 22 22 22 22 22 11				Out: 3308	Grade: Cutter: 8 / 1		Dull: CR / CT		Wear: C		Brgs: 0		Gge: 1		Pull: PR						4	1	REED	TK63	12.250	3305	192	1.5	128.0					9	800	2900	106	89	42	388	Jets: 22 22 22 22 22 22 22 11				Out:	Grade: Cutter: /		Dull: /		Wear:		Brgs:		Gge:		Pull:						BHA - No. 4 - = 1.20																																																																																																																																																																																
				Depth		This Run		R.O.P.		Mud Pump																																																																																																																																																																																																																																																																																																																				
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF																																																																																																																																																																																																																																																																																																											
3	1	REED	TKC66	12.250	390	808	5	161.6					9	800	2900	95	72	33	348																																																																																																																																																																																																																																																																																																											
Jets: 22 22 22 22 22 22 22 11				Out: 3308	Grade: Cutter: 8 / 1		Dull: CR / CT		Wear: C		Brgs: 0		Gge: 1		Pull: PR																																																																																																																																																																																																																																																																																																															
4	1	REED	TK63	12.250	3305	192	1.5	128.0					9	800	2900	106	89	42	388																																																																																																																																																																																																																																																																																																											
Jets: 22 22 22 22 22 22 22 11				Out:	Grade: Cutter: /		Dull: /		Wear:		Brgs:		Gge:		Pull:																																																																																																																																																																																																																																																																																																															
BHA - No. 4 - = 1.20																																																																																																																																																																																																																																																																																																																														
Drilling Parameters																																																																																																																																																																																																																																																																																																																														
<table border="1"> <thead> <tr> <th colspan="2">Depth (ft)</th> <th colspan="2">ROP (ft/hr)</th> <th colspan="2">WOB (lbs)</th> <th colspan="2">RPM</th> <th colspan="2">Torque (ft lbs)</th> <th colspan="2">Flow (gals/min)</th> <th>Pressure</th> </tr> <tr> <th>From</th> <th>To</th> <th>Avg</th> <th>Max</th> <th>Avg</th> <th>Max</th> <th>Avg</th> <th>Max</th> <th>Avg</th> <th>Max</th> <th>Avg</th> <th>Max</th> <th>(psi)</th> </tr> </thead> <tbody> <tr> <td>3,305</td> <td>3,500</td> <td>60.0</td> <td>120.0</td> <td>35</td> <td>35</td> <td>60</td> <td>60</td> <td>11</td> <td>12</td> <td>800</td> <td>800</td> <td>3,100</td> </tr> <tr> <td colspan="2">Annular Velocity:</td> <td colspan="2">Drill Collars:</td> <td colspan="2">203.0</td> <td colspan="2">Drill Pipe:</td> <td colspan="2">222.0</td> <td colspan="4"></td> </tr> </tbody> </table>																				Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure	From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	(psi)	3,305	3,500	60.0	120.0	35	35	60	60	11	12	800	800	3,100	Annular Velocity:		Drill Collars:		203.0		Drill Pipe:		222.0																																																																																																																																																																																																																																																											
Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure																																																																																																																																																																																																																																																																																																																		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	(psi)																																																																																																																																																																																																																																																																																																																		
3,305	3,500	60.0	120.0	35	35	60	60	11	12	800	800	3,100																																																																																																																																																																																																																																																																																																																		
Annular Velocity:		Drill Collars:		203.0		Drill Pipe:		222.0																																																																																																																																																																																																																																																																																																																						
Miscellaneous Drilling Parameters																																																																																																																																																																																																																																																																																																																														
Hook Loads (lbs): Off Bottom Rotate: 150 Pick Up: 160 Slack Off: 140 Drag Avg/Max: 10 / 15																																																																																																																																																																																																																																																																																																																														
Survey Information																																																																																																																																																																																																																																																																																																																														
<table border="1"> <thead> <tr> <th rowspan="2">Survey Type</th> <th rowspan="2">Meas. Depth</th> <th rowspan="2">Inc.</th> <th rowspan="2">Azimuth</th> <th rowspan="2">TVD</th> <th rowspan="2">Closure</th> <th rowspan="2">Vertical Section</th> <th colspan="3">Coordinates</th> </tr> <tr> <th>N-S</th> <th>E-W</th> <th>D.L.S.</th> </tr> </thead> <tbody> <tr> <td>MWD</td> <td>3,410.0</td> <td>1.49</td> <td>110.6</td> <td>3,409.0</td> <td>63.8</td> <td>42.9</td> <td>N 42.9</td> <td>E 47.2</td> <td>0.115</td> </tr> <tr> <td>MWD</td> <td>3,447.0</td> <td>1.45</td> <td>119.5</td> <td>3,446.0</td> <td>64.2</td> <td>42.5</td> <td>N 42.5</td> <td>E 48.1</td> <td>0.631</td> </tr> </tbody> </table>																				Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates			N-S	E-W	D.L.S.	MWD	3,410.0	1.49	110.6	3,409.0	63.8	42.9	N 42.9	E 47.2	0.115	MWD	3,447.0	1.45	119.5	3,446.0	64.2	42.5	N 42.5	E 48.1	0.631																																																																																																																																																																																																																																																																										
Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates																																																																																																																																																																																																																																																																																																																							
							N-S	E-W	D.L.S.																																																																																																																																																																																																																																																																																																																					
MWD	3,410.0	1.49	110.6	3,409.0	63.8	42.9	N 42.9	E 47.2	0.115																																																																																																																																																																																																																																																																																																																					
MWD	3,447.0	1.45	119.5	3,446.0	64.2	42.5	N 42.5	E 48.1	0.631																																																																																																																																																																																																																																																																																																																					
Mud Log Information																																																																																																																																																																																																																																																																																																																														
<table border="1"> <thead> <tr> <th colspan="2">Depth (ft)</th> <th colspan="2">TVD (ft)</th> <th colspan="2">Gas (Units)</th> <th>Gas</th> <th>Drilling</th> <th>Pore</th> <th>Mud</th> <th>Shale</th> <th colspan="2">ROP</th> </tr> <tr> <th>From</th> <th>To</th> <th>From</th> <th>To</th> <th>Avg</th> <th>Max</th> <th>at Depth</th> <th>Connect. Trip</th> <th>Exp.</th> <th>Press</th> <th>Dens.</th> <th>Dens.</th> <th>Shale Sand</th> </tr> </thead> <tbody> <tr> <td>2,470</td> <td>3,050</td> <td>2,470</td> <td>3,050</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 100% Alluvium</td> </tr> <tr> <td>3,050</td> <td>3,180</td> <td>3,050</td> <td>3,180</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 40-80% clay, 10-60% Alluvium, 0-40% granite, 0-10% diorite</td> </tr> <tr> <td>3,180</td> <td>3,230</td> <td>3,180</td> <td>3,230</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 50-80% granite, 20-50% clay</td> </tr> <tr> <td>3,230</td> <td>3,270</td> <td>3,230</td> <td>3,270</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 100% Granite</td> </tr> <tr> <td>3,270</td> <td>3,340</td> <td>3,270</td> <td>3,340</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 60-100% granodiorite, 0-40% Alluvium</td> </tr> <tr> <td>3,340</td> <td>3,380</td> <td>3,340</td> <td>3,380</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name: 80-100% Diorite, 0-20% Granodior</td> </tr> <tr> <td colspan="13">Lithology:</td> </tr> <tr> <td>3,390</td> <td>3,400</td> <td>3,390</td> <td>3,400</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>8.80</td> <td></td> <td></td> </tr> <tr> <td colspan="13">Formation Name:</td> </tr> <tr> <td colspan="13">Lithology: 100% Granodiorite</td> </tr> </tbody> </table>																				Depth (ft)		TVD (ft)		Gas (Units)		Gas	Drilling	Pore	Mud	Shale	ROP		From	To	From	To	Avg	Max	at Depth	Connect. Trip	Exp.	Press	Dens.	Dens.	Shale Sand	2,470	3,050	2,470	3,050							8.80			Formation Name:													Lithology: 100% Alluvium													3,050	3,180	3,050	3,180							8.80			Formation Name:													Lithology: 40-80% clay, 10-60% Alluvium, 0-40% granite, 0-10% diorite													3,180	3,230	3,180	3,230							8.80			Formation Name:													Lithology: 50-80% granite, 20-50% clay													3,230	3,270	3,230	3,270							8.80			Formation Name:													Lithology: 100% Granite													3,270	3,340	3,270	3,340							8.80			Formation Name:													Lithology: 60-100% granodiorite, 0-40% Alluvium													3,340	3,380	3,340	3,380							8.80			Formation Name: 80-100% Diorite, 0-20% Granodior													Lithology:													3,390	3,400	3,390	3,400							8.80			Formation Name:													Lithology: 100% Granodiorite												
Depth (ft)		TVD (ft)		Gas (Units)		Gas	Drilling	Pore	Mud	Shale	ROP																																																																																																																																																																																																																																																																																																																			
From	To	From	To	Avg	Max	at Depth	Connect. Trip	Exp.	Press	Dens.	Dens.	Shale Sand																																																																																																																																																																																																																																																																																																																		
2,470	3,050	2,470	3,050							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 100% Alluvium																																																																																																																																																																																																																																																																																																																														
3,050	3,180	3,050	3,180							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 40-80% clay, 10-60% Alluvium, 0-40% granite, 0-10% diorite																																																																																																																																																																																																																																																																																																																														
3,180	3,230	3,180	3,230							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 50-80% granite, 20-50% clay																																																																																																																																																																																																																																																																																																																														
3,230	3,270	3,230	3,270							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 100% Granite																																																																																																																																																																																																																																																																																																																														
3,270	3,340	3,270	3,340							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 60-100% granodiorite, 0-40% Alluvium																																																																																																																																																																																																																																																																																																																														
3,340	3,380	3,340	3,380							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name: 80-100% Diorite, 0-20% Granodior																																																																																																																																																																																																																																																																																																																														
Lithology:																																																																																																																																																																																																																																																																																																																														
3,390	3,400	3,390	3,400							8.80																																																																																																																																																																																																																																																																																																																				
Formation Name:																																																																																																																																																																																																																																																																																																																														
Lithology: 100% Granodiorite																																																																																																																																																																																																																																																																																																																														

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 7

Report For 10-Feb-21

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	112	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time

Description

Safety 60 Tripping

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crownamatic Check**Weather Information**

Sky Condition: Clear


Visibility: 10

Air Temperature: 28 degF

Bar. Pressure: 30.06

Wind Speed/Dir: 11 / S

Wind Gusts: 15

	Daily Drilling Report Well ID: Forge 56-32 Field: Other										Geothermal Resource Group Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT									
	Report No: 8										Report For 11-Feb-21									
	Operator: University of Utah		Rig: Frontier		Spud Date:		Daily Cost / Mud (\$): ---													
Measured Depth (ft): 3500		Last Casing: 9.625 at 3,494		Wellbore: Original Wellbore		AFE No.		AFE (\$)		Actual (\$)										
Vertical Depth (ft): 3500		Next Casing: 5.500 at 9,000		RKB Elevation (ft): 30.40		---		---		---										
Proposed TD (ft): 9000		Last BOP Test:		Job Reference RKB (ft): 28.50		---		---		---										
Hole Made (ft) / Hrs: 96 / 5.0		Next BOP Test:		Working Interest:		Totals:		---		---										
Average ROP (ft/hr): 19.2						Well Cost (\$):		---		---										
Drilling Days (act./plan): 4/30		Flat Days (act./plan): 0/8		Total Days (act./plan): 4/38		Days On Location:		8												
Pers/Hrs: Operator: 2 / 24		Contractor: 14 / 168		Service: 8 / 96		Other: 9 / 144		Total: 33 / 432												
Safety Summary: No incidents or events reported. Conducted Safety Meeting.																				
Current Operations: Set slips for 9.625" casing in well head. Set in BOPE and tightening connections. Removing flow line to clean out cement.																				
Planned Operations: Test BOPE, Make up tools and clean out cement and shoe. Drill 10' of new hole and perform FIT. Drill 8.75" hole.																				
Toolpusher: Justin Bristol, Steve Caldwell																				
Wellsite Supervisors: Virgil Welch, Paul Stroud										Tel No.: 7132807438										
Operations Summary																				
From	To	Elapsed	End MD(ft)	Code	Operations Description						Non-Prod									
0:00	1:30	1.50	3,500	3-2-2	Drilled 12.25" hole from 3404' to 3500'.															
1:30	2:30	1.00	3,500	03-051	Circulated well bore clean.															
2:30	4:00	1.50	3,500	WIPE	Wiped hole from 3500' to 2000' and backed to bottom at 3500'.															
4:00	5:00	1.00	3,500	03-051	Circulated well bore clean.															
5:00	6:30	1.50	3,500	WIPE	Wiped hole from 3500' to 2000' and back to bottom at 3500'.															
6:30	7:30	1.00	3,500	03-051	Circulated well bore clean.															
7:30	11:00	3.50	3,500	3-6-2	Pulled out of the hole and laid down BHA.															
11:00	11:30	0.50	3,500	3-97	Cleared rig floor for casing run.															
11:30	12:00	0.50	3,500	SERV	Serviced Rig.															
12:00	14:00	2.00	3,500	WOE	Waited on Power Tongs. (Power tong truck had the rear end go out, waited on new truck).															
14:00	19:00	5.00	3,500	CASE	Rigged up and ran 83 joints of 9.625" 36 ppf, J-55, LT&C casing with shoe set at 3488'.															
19:00	21:30	2.50	3,500	03-051	Rigged down casers and circulated well bore clean.															
21:30	0:00	2.50	3,500	5-12-2	Rigged up Resource Cementing and filled lines with water and pressured tested to 2000 psi. Resource Cementing pumped 10 barrels of water ahead followed by 20 barrels of RC Mjud Clean Spacer followed by 30 barrels of 10.5 ppg Sepiolite Spacer followed by 5 barrels of fresh water spacer, followed by 13 barrels of sodium silicate followed by 5 barrels of fresh water spacer and pumped 300.8 barrels of 13.4 ppg RC Thermalite HT cement. Dropped plug and displaced with 270 barrels of mud. Bumped plug with 1500 psi (500 psi over). Floats held. Had 35 barrels of cement to surface. CIP at 0000 hours.															
Management Summary																				
Drilled 12.25" hole from 3404' to 3500' and circulated well bore clean. Conducted 2 wiper trips to 2000' to wipe out swelling issue. Circulated well bore clean. Pulled out of the hole laying down 8" drill collars and directional tools. Rigged up and ran 83 joints of 9.625" 36 ppf, J-55 LT&C casing equipped with float shoe and insert baffle. Rigged up Resource Cementing and cemented casing in place. Had 35 barrels of cement to surface. CIP at 0000 hours.																				
Comments																				
Cement did not fall. Lifted BOPE and set slips.																				
Casing/Tubular Information																				
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)										
FULL	20.000	30	30	129	129	COND														
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55											
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55											
Mud Information																				
%																				
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	Gels 10m	30m	Temp In	Out	Mud Loss
11-Feb-21 07:00 at Depth 3,500 ft Mud Pits																				
8.80	46	19	18	7	1	10.5	8	0	92	2.25		1200	800		6	12	22	53	138	



Daily Drilling Report

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 8

Report For 11-Feb-21

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	60	---	Driscac - OTHER	1	---
micro c - OTHER	10	---	SAwdust - OTHER	2	---
walnut Pine - OTHER	3	---	xanthan gum - OTHER	2	---

Bit/BHA/Workstring Information

				Depth		This Run		R.O.P.				Mud		Pump						
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF	
4	1	REED	TK63	12.250	3305	192	1.5													
Jets: 22 22 22 22 22 11 11					Out:		Grade: Cutter:		/		/		Wear:		Brgs:		Gge:		Pull:	
BHA - No. 4 -					= 1.20															

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	112	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Running casing
First Aid Treatments:		Medical Treatments:
Lost Time Incidents:		Days Since LTI:
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	30 degF	Bar. Pressure:	29.79
Wind Speed/Dir:	17 / S	Wind Gusts:	20

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 9

Report For 12-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	3500	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	3500	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:		Job Reference RKB (ft):	28.50	---	---		---
Hole Made (ft) / Hrs:	0 / 1.5	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):	0.0					Well Cost (\$):			---
Drilling Days (act./plan):	5/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	5/38	Days On Location:			9
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	2 / 24	Total:	26 / 312
Safety Summary: No incidents or events reported. Conducted Safety Meeting.									
Current Operations: Continue to drill 8-3/4" hole with PDC bit at 3,768'									
Planned Operations: Continue to drill 8-3/4" hole with PDC bit.									
Toolpusher: Justin Bristol, Steve Caldwell									
Wellsite Supervisors: Virgil Welch, Paul Stroud									
						Tel No.: 7132807438			

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	6:00	6.00	3,500	1-14	Break stack at well head. Lift stack, cleaned out cement from well head. Set slips in well head around 9-5/8" casing. Set down stack and nipped up. Cleaned BOPE stack of cement.	
6:00	9:00	3.00	3,500	1-15	Tested BOPE. Cleaned flow line of cement.	
9:00	9:30	0.50	3,500	11-343	Strapped drill collars, made up bit.	
9:30	10:30	1.00	3,500	11-6-1	Ran in the hole to 3,200'.	
10:30	13:00	2.50	3,500	3-28	Cleaned out cement stringers from 3,200' to 3,414' and drilled out baffle plate, cement and shoe at 3,488' and cement to 3,500'.	
13:00	14:30	1.50	3,500	03-021	Drilled 8.-3/4" hole from 3,500' to 3,506'.	
14:30	15:00	0.50	3,500	11-99	Performed sFIT with 8.8 ppg mud. Noticed pressure drop at 1,320 surface applied pressure. EMW 16 ppg (0.83 psi/ft frac grad)	
15:00	16:00	1.00	3,500	11-6-2	Pulled out of the hole.	
16:00	0:00	8.00	3,500	10-341	Picked up drill pipe single and stood back in derrick.	

Management Summary

Broke stack and well head and lifted stack. Cleaned out cement inside well head and set slips. Set stack back on well head and secured BOPE. Cleaned out cement in BOPE. Made up bit #5 and ran in the hole. Cleaned out baffle plate, cement and shoe. Drilled 6' of new hole from 3,500' to 3,506' and performed FIT. Pulled out of the hole and picked up drill pipe standing back in derrick.

Comments

Mud Cooler were turned on 2-10-2021.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	

Mud Information

Mud Information																				
%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
12-Feb-21 22:00 at Depth 3,506 ft Mud Pits																				
8.80	50	19	23	8	1	10.5	6	0	94	0.25		1300	880		7	15	26			

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	29	---	Bicarb - OTHER	15	---
Desco - OTHER	6	---	PAlets/Wrap - OTHER	2	---
SAwdust - OTHER	7	---			

**Daily Drilling Report**

Well ID: Forge 56-32

Field: Other

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 9

Report For 12-Feb-21

Bit/BHA/Workstring Information

				Depth	This Run		R.O.P.							Mud		Pump					
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF		
5	1	HTC	GX 117	8.750	3500	6	1.5	4.0					9	800	2900	279	612	286	1016		
Jets: 20 20 20					Out: 3506		Grade: Cutter:		3 / 3	Dull ER /			Wear: A		Brgs: 0		Gge: 1		Pull: TD		
BHA - No. 6 - BIT, MMTR, OTHER, STAB, MONEL, SHOCK, 12 DC, 24 HWDP = 1178.12																					

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Picking up drill and tools

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crowmamic Check**Weather Information**

Sky Condition: Cloudy


Visibility: 10

Air Temperature: 32 degF

Bar. Pressure: 29.88

Wind Speed/Dir: 7 / S

Wind Gusts: 10

	Daily Drilling Report Well ID: Forge 56-32 Field: UTAHFORGE		Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT																		
	Report No: 10		Report For 13-Feb-21																		
	Operator: University of Utah Rig: Frontier Spud Date: Daily Cost / Mud (\$): --- Measured Depth (ft): 4385 Last Casing: 9.625 at 3,494 Wellbore: Original Wellbore AFE No. AFE (\$) Actual (\$) Vertical Depth (ft): 4383 Next Casing: 5.500 at 9,000 RKB Elevation (ft): 30.40 --- --- --- Proposed TD (ft): 9000 Last BOP Test: 12-Feb-21 Job Reference RKB (ft): 28.50 --- --- --- Hole Made (ft) / Hrs: 885 / 19.0 Next BOP Test: Working Interest: Totals: --- --- --- Average ROP (ft/hr): 46.58 LOT (lbs/gal): 16.00 Well Cost (\$): --- Drilling Days (act./plan): 6/30 Flat Days (act./plan): 0/8 Total Days (act./plan): 6/38 Days On Location: 10 Pers/Hrs: Operator: 2 / 24 Contractor: 14 / 168 Service: 8 / 96 Other: 0 / 0 Total: 24 / 288																				
Safety Summary: No incidents or events reported. Conducted Safety Meeting. Current Operations: Drilling 8-3/4" hole at 4,480'. Planned Operations: Continue drilling 8-3/4" hole with Bit # 6 and Trip for Bit #7 and drill 8-3/4" hole. Toolpusher: Justin Bristol, Steve Caldwell Wellsite Supervisors: Virgil Welch, Paul Stroud Tel No.: 7132807438																					
Operations Summary																					
From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod															
0:00	0:30	0.50	3,506	SERV	Serviced Rig.																
0:30	2:30	2.00	3,506	7-34-3	Strapped collars and made up tools.																
2:30	4:30	2.00	3,506	7-6-1	Ran in the hole.																
4:30	5:00	0.50	3,579	DRILR	Rotary drilled 8-3/4" hole from 3,506' to 3,579'.																
5:00	5:30	0.50	3,599	3-2-3	Slide drilled 8-3/4" hole from 3,579' to 3,599'.																
5:30	9:30	4.00	3,938	3-2-2	Rotary drilled 8-3/4" hole from 3,599' to 3,938'.																
9:30	10:00	0.50	3,950	3-2-3	Slide drilled 8-3/4" hole from 3,938' to 3,950'.																
10:00	11:30	1.50	4,033	3-2-2	Rotary drilled 8-3/4" hole from 3,950' to 4,033'.																
11:30	12:00	0.50	4,060	3-2-3	Slide drilled 8-3/4" hole from 4,033' to 4,060'.																
12:00	15:30	3.50	4,214	3-2-2	Rotary drilled 8-3/4" hole from 4,060' to 4,214'.																
15:30	16:00	0.50	4,214	SERV	Serviced Rig.																
16:00	0:00	8.00	4,385	3-2-2	Rotary drilled 8-3/4" hole from 4,214' to 4,385'.																
Management Summary																					
Made up Bit #6 and tools. Ran in the well bore and rotated and slid drilled 8-3/4" hole from 3,506' to 4,385'.																					
Comments																					
Drilling in 0-100% Granodiorite, 0-100% Felsic Dike, rare amounts of epidote and iron pirite																					
Casing/Tubular Information																					
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)											
FULL	20.000	30	30	129	129	COND															
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30											
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00											
Mud Information																					
%																					
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	Gels	Temp	Mud	
																			In	Out	Loss
13-Feb-21 19:00 at Depth 4,287 ft Mud Pits																					
8.80	49	19	25	7.8	1	11	7	0	93	1		1200	720		5	10	16	75	124		
Mud Consumables																					
Item Description		Qty.	Cost	Item Description		Qty.	Cost														
caustic - OTHER		1	---	Defoamer - OTHER		7	---														
Desco - OTHER		4	---	DMA/SPA - 100#SK		6	---														
Drispac - OTHER		3	---	Gel - OTHER		10	---														
micro c - OTHER		20	---	PAllets/Wrap - OTHER		2	---														
SAwdust - OTHER		4	---	walnut Pine - OTHER		14	---														
xanthan gum - OTHER		2	---																		

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 10

Report For 13-Feb-21

Bit/BHA/Workstring Information

					Depth	This Run		R.O.P.				Mud				Pump													
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF										
6	1	REED	TKC73-H	8.750	3506	885	19	46.6	140.0	35	220		9	750	3500	243	465	203	830										
Jets: 13 13 13 14 14 14					Out:		Grade:		Cutter:		/	Dull:		/	Wear:		Brgs:		Gge:		Pull:								
BHA - No. 6 -																				BIT, MMTR, OTHER, STAB, MONEL, SHOCK, 12 DC, 24 HWDP = 1178.12									

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
3,700	4,430	20.0		38		60	100	6		650		2,700
Annular Velocity:		Drill Collars:		310.0	Drill Pipe:		382.0					

Miscellaneous Drilling Parameters

Hook Loads (lbs):		Off Bottom Rotate:		160	Pick Up:		170	Slack Off:		145	Drag Avg/Max:		10 / 12
Slow Circulation Data:													
Pump 1:		20 spm		170 psi		40 spm		290 psi		60 spm		490 psi	
Pump 2:		20 spm		160 psi		40 spm		300 psi		60 spm		520 psi	

Survey Information

Survey Type	Meas.		Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
	Depth							N-S	E-W	D.L.S.
MWD	3,497.0		1.45	119.7	3,496.0	64.6	41.9	N 41.9	E 49.2	0.009
MWD	3,592.0		0.09	235.7	3,590.9	64.9	41.2	N 41.2	E 50.2	1.570
MWD	3,687.0		1.19	275.8	3,685.9	64.2	41.3	N 41.3	E 49.1	1.182
MWD	3,792.0		1.14	257.4	3,790.9	62.5	41.2	N 41.2	E 47.0	0.359
MWD	3,877.0		1.71	259.0	3,875.9	60.7	40.8	N 40.8	E 44.9	0.672
MWD	3,972.0		2.37	239.7	3,970.8	57.5	39.5	N 39.5	E 41.9	0.995
MWD	4,067.0		0.88	14.5	4,065.8	56.3	39.2	N 39.2	E 40.3	3.216
MWD	4,163.0		0.70	68.7	4,161.8	57.4	40.1	N 40.1	E 41.1	0.767
MWD	4,258.0		1.14	248.5	4,256.8	57.1	40.0	N 40.0	E 40.7	1.937
MWD	4,353.0		1.89	253.3	4,351.8	54.8	39.2	N 39.2	E 38.4	0.800

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
3,700	3,800												
Formation Name:													
Lithology:		40-80% Granodiorite, 0-60% Diorite, 0-20% Granite											
3,800	3,900												
Formation Name:													
Lithology:		60-70% Diorite, 30-40% Granodiorite											
3,900	4,000												
Formation Name:													
Lithology:		30-100% Granodiorite, 0-70% Diorite, 0-60% Granite											
4,000	4,100												
Formation Name:													
Lithology:		100% Granodiorite											
4,100	4,380												
Formation Name:													
Lithology:		0-100% Granodiorite, 0-100% Felsic Dike											

Rig Information

Equipment Problems: Number 3 generator down, mechanic called.													
Location Condition:													
Transport:													

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 10

Report For 13-Feb-21

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Drilling connections
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crowmamic Check	

Weather Information

Sky Condition:	Snow	Visibility:	1
Air Temperature:	27 degF	Bar. Pressure:	29.63
Wind Speed/Dir:	13 / NNW	Wind Gusts:	20

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 11

Report For 14-Feb-21

Operator:		University of Utah		Rig:	Frontier		Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):		4702		Last Casing:	9.625 at 3,494		Wellbore:	Original Wellbore		AFE No.	AFE (\$)	Actual (\$)
Vertical Depth (ft):		4700		Next Casing:	5.500 at 9,000		RKB Elevation (ft):	30.40		---	---	---
Proposed TD (ft):		9000		Last BOP Test:	12-Feb-21		Job Reference RKB (ft):	28.50		---	---	---
Hole Made (ft) / Hrs:		317 / 21.0		Next BOP Test:			Working Interest:			Totals:	---	---
Average ROP (ft/hr):		15.1					LOT (lbs/gal):	16.00		Well Cost (\$):	---	
Drilling Days (act./plan):		7/30		Flat Days (act./plan):	0/8		Total Days (act./plan):	7/38		Days On Location:	11	
Pers/Hrs:	Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total:	24 / 288		

Safety Summary: No incidents or events reported. Conducted Crown Check, Safety Meeting.

Current Operations: Drilling 8-3/4" hole at 4,832' with tricone bit

Planned Operations: Drill 8-3/4" hole with tricone bit. When bit wears off, change to continue drilling with PDC bit.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	4,405	3-2-2	Rotary drilled 8-3/4" hole from 4,385' to 4,405'.	
1:00	3:00	2.00	4,420	3-2-3	Slide drilled 8-3/4" hole from 4,405' to 4,420'.	
3:00	12:30	9.50	4,595	3-2-2	Rotary drilled 8-3/4" hole from 4,420' to 4,595'.	
12:30	16:30	4.00	4,595	3-6-4	Pulled out of the hole laying down bit and tools.	
16:30	19:00	2.50	4,595	3-34-3	Made up bit, directional tools and ran in the hole.	
19:00	19:30	0.50	4,595	3-5-1	Filled pipe and circulated.	
19:30	20:30	1.00	4,620	3-2-3	Slide drilled 8-3/4" hole from 4,595' to 4,620'.	
20:30	23:30	3.00	4,692	3-2-2	Rotary drilled 8-3/4" hole from 4,620' to 4,692'.	
23:30	0:00	0.50	4,702	3-2-3	Slide drilled 8-3/4" hole from 4,692' to 4,702'.	

Management Summary

Drilled 8-3/4" hole from 4,385' to 4,598' and tripped for Bit #7 (tricone) and new shock sub. Drilled 8-3/4" hole from 4,598' to 4,702'.

Comments

Drilling break at 4,774' 80% Granodiorite and 20% altered.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

															%			Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss			
14-Feb-21 21:00 at Depth 4,630 ft Mud Pits																							
8.70	46	15	24	8.2	1	10.5	6	0	94	1		1200	720		5	9	16	77	138				

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	20	---	caustic - OTHER	2	---
Defoamer - OTHER	4	---	Desco - OTHER	1	---
Drispac - OTHER	6	---	Gel - OTHER	20	---
micro c - OTHER	10	---	walnut Pine - OTHER		---
xanthan gum - OTHER	1	---			

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 11

Report For 14-Feb-21

Bit/BHA/Workstring Information

				Depth		This Run		R.O.P.			Mud				Pump														
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF										
6	1	REED	TKC73-H	8.750	3506	1,095	31.5	34.8					9	660	2300	214	360	139	643										
Jets: 13 13 13 14 14 14					Out: 4595		Grade: Cutter:		1 / 2		Dull: CT/CT		Wear: S		Brgs: X		Gge: 1		Pull: OTH										
7	1	HTC	EP5475	8.750	4596	107	4.5	23.8					9	660	2300	230	417	160	692										
Jets: 20 20 20					Out:		Grade: Cutter:		/		Dull:		/		Wear:		Brgs:		Gge:		Pull:								
BHA - No. 7 -																				BIT, MMTR, XO, STAB, MONEL, SH/SUB, 12 DC, 24 HWDP = 1178.54									

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
4,595	4,620	21.0	25.0	45	48	0	0			670		
Comments: SLIDING												
4,620	4,692	21.0	31.0	45	48	57	60			671		
Comments: ROTARY												
4,692	4,715	19.0	53.0	45	48	0	0			670		
Comments: SLIDING												

Miscellaneous Drilling Parameters

Hook Loads (lbs):	Off Bottom Rotate:	160	Pick Up:	170	Slack Off:	150	Drag Avg/Max:	10 / 10
Slow Circulation Data:								
Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi		
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	4,448.0	1.19	338.6	4,446.7	53.9	39.7	N 39.7	E 36.5	2.261
MWD	4,544.0	3.34	311.0	4,542.7	54.4	42.4	N 42.4	E 34.0	2.449
MWD	4,640.0	2.02	246.1	4,638.6	53.1	43.6	N 43.6	E 30.4	3.211

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
4,380	4,700	4,376	4,696										
Formation Name:													
Lithology: 100% Granodiorite													

Rig Information

Equipment Problems:
Location Condition:
Transport:

Solids Control Information

Screen Sizes:	Top	Bottom
Shaker No 1:	170	
Shaker No 2:	170	
Shaker No 3:	140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Making connections
First Aid Treatments:		
Medical Treatments:		
Lost Time Incidents:		
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input checked="" type="checkbox"/> Crowmamic Check	



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 11

Report For 14-Feb-21

Weather Information

Sky Condition: Cloudy

Visibility: 10

Air Temperature: 21 degF

Bar. Pressure: 30.06

Wind Speed/Dir: 6 / ENE

Wind Gusts: 10

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 12

Report For 15-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	Daily Cost / Mud (\$):	---
Measured Depth (ft):	5143	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No. AFE (\$) Actual (\$)
Vertical Depth (ft):	5141	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---
Hole Made (ft) / Hrs:	441 / 22.75	Next BOP Test:		Working Interest:		Totals: ---
Average ROP (ft/hr):	19.38			LOT (lbs/gal):	16.00	Well Cost (\$): ---
Drilling Days (act./plan):	8/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	8/38	Days On Location: 12
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other: 0 / 0 Total: 24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Making up new 8-3/4" PDC bit and mud motor.

Planned Operations: Drill 8-3/4" hole with PDC bit.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	4,715	3-2-3	Slide drilled 8.-3/4" hole from 4,702' to 4,715'.	
1:00	11:30	10.50	4,932	3-2-2	Rotary drilled 8.-3/4" hole from 4,715' to 4,932'.	
11:30	12:00	0.50	4,932	SERV	Serviced Rig.	
12:00	23:15	11.25	5,143	3-2-2	Rotary drilled 8-3/4" hole from 4,932' to 5,143'.	
23:15	0:00	0.75	5,143	3-5-1	Circulated bottoms up in preparation for trip out of hole.	

Management Summary

Drilled 8-3/4" hole from 4,702' to 5,143' and circulated bottoms up for trip out of hole due to pressure spike. NOTE: Bit was locked up and ground flat on two cones. Motor also failed.

Comments

Drilling in Granodiorite.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	Gels 10m	30m	Temp In	Out	Mud Loss
15-Feb-21 22:00	at Depth 5,113 ft	Mud Pits																		
8.60	44	11	21	8.8	1	10.5	5	0	95	1		1200	960		4	8	15	124	130	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	10	---	caustic - OTHER	1	---
Defoamer - OTHER	2	---	DMA/SPA - 100#SK	2	---
Driscac - OTHER	1	---	Gel - OTHER	10	---
micro c - OTHER	10	---	SAwdust - OTHER	2	---
walnut Pine - OTHER	10	---	xanthan gum - OTHER	1	---

Bit/BHA/Workstring Information

				Depth	This Run		R.O.P.				Mud				Pump					
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF	
7	1	HTC	EP5475	8.750	4596	535	27.25	19.6	118.9	40	50	7	9	670	2700	234	425	166	705	
Jets: 20					Out: 5143		Grade: Cutter:		8 / 8		Dull: FC / BT		Wear: A		Brgs: 8		Gge: 0.25		Pull: PP	
BHA - No. 7 - BIT, MMTR, XO, STAB, MONEL, SH/SUB, 12 DC, 24 HWDP = 1178.54																				

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 12

Report For 15-Feb-21

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	(psi)
4,702	4,832	18.0	22.0	35	45	50	55	7	8	740	768	2,700
Annular Velocity:		Drill Collars:		538.0		Drill Pipe:		340.0				
Comments: Rotating												
4,832	4,932	20.0	23.0	43	45	40	50	7	8	740	768	27,500
Annular Velocity:		Drill Collars:		538.0		Drill Pipe:		340.0				
Comments: Rotating												

Miscellaneous Drilling Parameters

Hook Loads (lbs):	Off Bottom Rotate:	160	Pick Up:	170	Slack Off:	150	Drag Avg/Max:	10 / 15
Slow Circulation Data:								
Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi		
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	4,734.0	1.27	30.9	4,732.6	52.7	43.8	N 43.8	E 29.4	3.344
MWD	4,829.0	0.70	7.3	4,827.5	54.3	45.3	N 45.3	E 30.0	0.724
MWD	4,924.0	0.84	3.6	4,922.5	55.4	46.6	N 46.6	E 30.1	0.156
MWD	5,018.0	0.75	295.9	5,016.5	56.0	47.5	N 47.5	E 29.6	0.945

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
4,760	4,870	4,758	4,868										
Formation Name:													
Lithology: 80% Granodiorite, 20% altered zone (increase in Hematite * chlorite wash, infreq epidote)													
4,870	5,140	4,868	5,138										
Formation Name:													
Lithology: 100% Granodiorite													

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes:	Top	Bottom
Shaker No 1:	170	
Shaker No 2:	170	
Shaker No 3:	140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Connections and pinch points
First Aid Treatments: Medical Treatments: Lost Time Incidents: Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crowmatic Check	

Weather Information

Sky Condition:	Cloudy	Visibility:	8
Air Temperature:	27 degF	Bar. Pressure:	29.82
Wind Speed/Dir:	9 / SSW	Wind Gusts:	12

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 13

Report For 16-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	5610	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	5608	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft): 28.50		---	---	---	---
Hole Made (ft) / Hrs:	467 / 23.5	Next BOP Test:		Working Interest:		Totals:	---	---	---
Average ROP (ft/hr):	19.87			LOT (lbs/gal): 16.00		Well Cost (\$):			---
Drilling Days (act./plan):	9/30	Flat Days (act./plan):	0/8	Total Days (act./plan): 9/38		Days On Location:			13
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total:	24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Changing out BHA and running in the hole with new 8-3/4" PDC

Planned Operations: Finish running in the hole with BHA #9. Continue drilling 8-3/4" hole to 7,500'.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	5:00	5.00	5,143	3-6-2	Pulled out of the hole and laid down bit and mud motor.	
5:00	7:30	2.50	5,143	3-6-1	Made up new bit and mud motor, ran in the hole to 5,083'.	
7:30	8:00	0.50	5,143	3-53	Filled pipe and washed to bottom at 5,143'.	
8:00	8:30	0.50	5,174	3-2-2	Rotary drilled 8-3/4" hole from 5,143' to 5,174'.	
8:30	9:00	0.50	5,189	3-2-3	Slide drilled 8-3/4" hole from 5,174' to 5,189'.	
9:00	14:30	5.50	5,363	3-2-2	Rotary drilled 8-3/4" hole from 5,189' to 5,363'.	
14:30	15:30	1.00	5,375	3-2-3	Slide drilled 8-3/4" hole from 5,363' to 5,375'.	
15:30	22:00	6.50	5,543	3-2-2	Rotary drilled 8-3/4" hole from 5,375' to 5,543'.	
22:00	22:30	0.50	5,558	3-2-3	Slide drilled 8-3/4" hole from 5,543' to 5,558'.	
22:30	0:00	1.50	5,610	3-2-2	Rotary drilled 8-3/4" hole from 5,558' to 5,610'.	

Management Summary

Tripped for Bit and BHA#8. Rotated and slid drilled 8.75" hole from 4310' to 5610'.

Comments

Bit number 8 looks good. MWD failed and bearing in motor are worn out. Top stabilizer starting to come apart. Drilling in 100% Granodiorite.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
16-Feb-21 22:00 at Depth 5,544 ft Mud Pits																				
8.70	44	12	16	9.8	1	10.5	6	0	94	1.25		1200	960		5	8	17	118	125	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	21	---	caustic - OTHER	4	---
Defoamer - OTHER	3	---	Driscap - OTHER	3	---
Gel - OTHER	20	---	lime - OTHER	3	---
micro c - OTHER	10	---	PALlets/Wrap - OTHER	4	---
soda ash - OTHER	1	---	walnut Pine - OTHER	24	---

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 13

Report For 16-Feb-21

Bit/BHA/Workstring Information

No	Run	Make	Model	Diam	Depth In	This Run		R.O.P.		WOB	RPM	Torque	Wt	Mud		Pump		J. Vel	P. Drp	HHP	JIF
						Dist	Hrs	Avg	Max					Flow	Press						
7	1	HTC	EP5475	8.750	4596	467	15.42	30.3	61.0	40	40	7	8	700	2800	244	416	170	690		
Jets: 20 20 20					Out: 5143			Grade: Cutter: 8 / 8		Dull: FC / BT			Wear: A	Brgs: 8	Gge: 0.25			Pull: PP			
8	1	REED	TKC63	8.750	5143																
Jets: 14 14 14 14 14 14					Out: 5610			Grade: Cutter: 1 / 1		Dull: NO / NO			Wear: A	Brgs: X	Gge: 1			Pull: DTF			
BHA - No. 8 - BIT, MMTR, OTHER, STAB, MONEL, SHOCK, DC, HWDP = 1178.50																					

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
4,143	5,174	30.0	41.0	40	45	40	45	6	7	700	700	2,750
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,174	5,189	20.0	25.0	45	45	0	0			700	701	2,750
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,189	5,363	30.0	31.0	45	45	40	50	6	7	700	700	2,750
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,363	5,375	20.0	21.0	40	44	0	0			700	700	2,780
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,375	5,545	30.0	41.0	40	45	40	45	7	8	700	700	2,800
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,545	5,558	20.0	20.0	40	45	0	0	0	0	700	700	2,800
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
5,558	5,610	33.0	41.0	40	40	40	40	8	8	700	700	2,800
Annular Velocity: Drill Collars:		538.0		Drill Pipe:		340.0						
Comments: Pull out of the well bore due to MWD												

Miscellaneous Drilling Parameters

Hook Loads (lbs): Off Bottom Rotate: 160 Pick Up: 170 Slack Off: 150 Drag Avg/Max: 10 / 12

Slow Circulation Data:

Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TV D	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	5,113.0	1.85	211.0	5,111.5	54.4	46.5	N 46.5	E 28.2	2.035
MWD	5,208.0	2.42	23.9	5,206.5	54.8	47.0	N 47.0	E 28.3	4.486
MWD	5,302.0	2.68	273.6	5,300.4	55.8	48.9	N 48.9	E 26.9	4.455
MWD	5,397.0	1.01	17.6	5,395.4	55.8	49.9	N 49.9	E 24.9	3.246

Mud Log Information

Depth (ft)		TV D (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
5,140	5,370	5,138	5,368							8.70			
Formation Name:													
Lithology: 100% Granodiorite (frequent fluctuations in amount of biotite)													
5,370	5,600	5,368	5,598							8.70			
Formation Name:													
Lithology: 100% Granodiorite (Less overall secondary minerals)													

Rig Information

Equipment Problems:

Location Condition:

Transport:

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 13

Report For 16-Feb-21

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Making connections from derrick.

First Aid Treatments: Medical Treatments: Lost Time Incidents: Days Since LTI:

☐ BOP Test ☐ Crownamatic Check**Weather Information**

Sky Condition: Cloudy Visibility: 8

Air Temperature: 21 degF Bar. Pressure: 29.95

Wind Speed/Dir: 8 / N Wind Gusts: 10

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 14

Report For 17-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	Daily Cost / Mud (\$):	---
Measured Depth (ft):	5978	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No. AFE (\$) Actual (\$)
Vertical Depth (ft):	5976	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---
Hole Made (ft) / Hrs:	368 / 19.0	Next BOP Test:		Working Interest:		Totals: ---
Average ROP (ft/hr):	19.37			LOT (lbs/gal):	16.00	Well Cost (\$): ---
Drilling Days (act./plan):	10/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	10/38	Days On Location: 14
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other: 0 / 0 Total: 24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Picking up new 8-3/4" PDC bit and BHA.

Planned Operations: Run in hole and continue drilling 8-3/4" hole to 7,500'

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:30	1.50	5,610	03-051	Trouble shoot MWD while circulating.	
1:30	6:00	4.50	5,610	3-6-2	Pulled out of the well bore laying down bit, mud motor and tools.	
6:00	8:00	2.00	5,610	3-34-3	Made up tools and ran in the hole.	
8:00	9:00	1.00	5,610	3-57	Filled pipe and took surveys.	
9:00	9:30	0.50	5,649	3-2-1	Rotate drilled 8-3/4" hole from 5,610' to 5,649'.	
9:30	10:00	0.50	5,662	3-2-3	Slide drilled 8-3/4" hole from 5,649' to 5,662'.	
10:00	11:30	1.50	5,742	3-2-1	Rotate drilled 8-3/4" hole from 5,642' to 5,742'.	
11:30	12:30	1.00	5,759	3-2-3	Slide drilled 8-3/4" hole from 5,742' to 5,759'.	
12:30	16:00	3.50	5,827	3-2-1	Rotate drilled 8-3/4" hole from 5,759' to 5,827'.	
16:00	16:30	0.50	5,827	SERV	Serviced Rig.	
16:30	17:00	0.50	5,837	3-2-1	Rotate drilled 8-3/4" hole from 5,827' to 5,837'.	
17:00	19:00	2.00	5,852	3-2-3	Slide drilled 8-3/4" hole from 5,837' to 5,852'.	
19:00	21:00	2.00	5,904	3-2-1	Rotate drilled 8-3/4" hole from 5,852' to 5,904'.	
21:00	22:00	1.00	5,920	3-2-3	Slide drilled 8-3/4" hole from 5,904' to 5,920'.	
22:00	23:30	1.50	5,920	3-2-1	Rotate drilled 8-3/4" hole from 5,920' to 5,973'.	
23:30	0:00	0.50	5,920	3-2-3	Slide drilled 8-3/4" hole from 5,973' to 5,978'.	

Management Summary

MWD and mud motor failed. Tripped for BHA #9. Drilled 8-3/4" hole from 5,610' to 5,978'.

Comments

Pulled out of the hole with green birt, motor had broken shaft.

Drilling in 100% Granodiorite.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

Mud Properties																				
%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
17-Feb-21 20:00 at Depth 5,882 ft Mud Pits																				
8.70	44	15	18	10	1	10.5	6	0	94	1.25		1200	1200		5	8	13	111	125	

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 14

Report For 17-Feb-21

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	24	---	caustic - OTHER	4	---
DC-310/CI-100 - OTHER	1	---	lime - OTHER	1	---
micro c - OTHER	10	---	PAlets/Wrap - OTHER	2	---
walnut Pine - OTHER	10	---	xanthan gum - OTHER	6	---

Bit/BHA/Workstring Information

				Depth	This Run		R.O.P.				Mud		Pump							
No Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF		
8	1	REED	TKC63	8.750	5143	467	17.46	26.7	50.0	45	200	8	9	680	2800	242	455	181	741	
Jets: 14 14 14 14 14 14				Out: 5610		Grade: Cutter:		1 / 1		Dull: NO / NO		Wear: A		Brgs: X		Gge: 1		Pull: DTF		
9	1	REED	TKC63	8.750	5610	368	14.5	25.4	40.0	50	200	8	9	680	2800	260	525	208	796	
Jets: 14 14 14 13 13 13				Out: 5999		Grade: Cutter:		1 / 1		Dull: NO /		Wear: A		Brgs: X		Gge:		Pull: DMF		
BHA - No. 9 - BIT, MMTR, OTHER, STAB, MONEL, SHOCK, 12 DC, 24 HWDP = 1179.22																				

Miscellaneous Drilling Parameters

Hook Loads (lbs):	Off Bottom Rotate:	Pick Up:	Slack Off:	Drag Avg/Max:	/
Slow Circulation Data:					
Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm 490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm 520 psi

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	5,492.0	3.92	267.4	5,490.2	53.3	50.0	N 50.0	E 18.3	2.341
MWD	5,587.0	6.34	263.5	5,584.8	50.2	49.3	N 49.3	E 9.9	2.572
MWD	5,681.0	5.97	255.8	5,678.3	47.5	47.5	N 47.5	W 0.0	0.959
MWD	5,776.0	4.04	248.1	5,772.9	45.7	45.0	N 45.0	W 7.9	2.145
MWD	5,871.0	4.02	254.3	5,867.7	45.1	42.9	N 42.9	W 14.2	0.459

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas		Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max	at Depth	Connect. Trip					Shale	Sand
5,880	5,890	5,878	5,888							8.70			
Formation Name:													
Lithology: 100% Granodiorite (Increase in mafic minerals eg. Hornblende, Biotite)													
5,890	5,990	5,888	5,988										
Formation Name:													
Lithology: 100% Granodiorite (Occasional pink K-spars)													

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 14

Report For 17-Feb-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Operating Fork Lift
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownmatic Check	Days Since LTI:

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	14 degF	Bar. Pressure:	30.22
Wind Speed/Dir:	13 / N	Wind Gusts:	13

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 15

Report For 18-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	6295	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	6293	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft): 28.50		---	---		---
Hole Made (ft) / Hrs:	317 / 18.5	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):	17.14			LOT (lbs/gal): 16.00		Job/Well Cost (\$):			---
Drilling Days (act./plan):	11/30	Flat Days (act./plan):	0/8	Total Days (act./plan): 11/38		Days On Location:			15
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total:	24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Drilling 8-3/4" hole at 6,420' at 0600 hours.

Planned Operations: Drill 8-3/4" hole.

Toolpusher: Justin Bristol, Steve Caldwell

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:30	1.50	5,999	3-2-3	Slide drilled 8-3/4" hole from 5,978' to 5,999'.	
1:30	2:00	0.50	5,999	03-051	Circulated and motor pressured up.	
2:00	5:00	3.00	5,999	3-6-2	Pulled out of the well bore with broken shaft on mud motor.	
5:00	8:30	3.50	5,999	3-34-3	Made up bit and new BHA. Ran in the hole to shoe at 3,512'.	
8:30	9:30	1.00	5,999	CUTDL	Slipped and cut drilling line.	
9:30	10:30	1.00	5,999	3-6-1	Ran in the hole to 5,782'.	
10:30	11:00	0.50	5,999	3-3	Reamed 8-3/4" hole from 5,782' to 5,999'.	
11:00	12:00	1.00	6,053	3-2-2	Rotary drilled 8-3/4" hole from 5,999' to 6,053'.	
12:00	12:30	0.50	6,068	3-2-3	Slide drilled 8-3/4" hole from 6,053' to 6,068'.	
12:30	18:30	6.00	6,197	3-2-2	Rotary drilled 8-3/4" hole from 6,068' to 6,197'.	
18:30	20:00	1.50	6,222	3-2-3	Side drilled 8-3/4" hole from 6,197' to 6,222'.	
20:00	0:00	4.00	6,222	3-2-2	Rotary drilled 8-3/4" hole from 6,222' to 6,295'.	

Management Summary

Tripped for new bit and BHA. Drilled 8-3/4" hole from 5,999' to 6,295' at 2400 hours.

Comments

Drilling in 100% Granodiorite (mnr-com biotite, rare chlorite)

2 new mud motors on location.

Casing and well head on Sunday.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

																			%				Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss								
18-Feb-21 21:00 at Depth 6,236 ft Mud Pits																												
8.70	46	15	15	9.6	1	10.5	6	0	94	1		1200	1200		6	9	17	95	111									

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	50	---	Gel - OTHER	15	---
micro c - OTHER	10	---	PAIlets/Wrap - OTHER	3	---
walnut Pine - OTHER	14	---	xanthan gum - OTHER	4	---

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 15

Report For 18-Feb-21

Bit/BHA/Workstring Information

BHA Drilling Information																				
No	Run	Make	Model	Diam	Depth	This Run	R.O.P.			Mud			Pump			J. Vel	P. Drp	HHP	JIF	
					In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press					
9	1	REED	TKC63	8.750	5610	368	14.5													
Jets: 14 14 14 13 13 13					Out: 5999		Grade: Cutter: 1 / 1		Dull: NO / NO		Wear: A		Brgs: X		Gge: 1		Pull: DMF			
10	1	REED	TKC73	8.750	5999	244	13	18.8					9	670	3300	253	498	195	763	
Jets: 13 13 13 13 12 12 12					Out:		Grade: Cutter: /		Dull: /		Wear:		Brgs:		Gge:		Pull:			
BHA - No. 10 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, 24 HWDP = 1169.59																				

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	(psi)
5,990	6,280	20.0	31.0	40	48	40	55	4	5	671	671	3,100
Annular Velocity:		Drill Collars:		554.0	Drill Pipe:		351.0					
Comments: MSE 75,000												

Miscellaneous Drilling Parameters

Hook Loads (lbs):	Off Bottom Rotate:	205	Pick Up:	240	Slack Off:	160	Drag Avg/Max:	35 / 35
Slow Circulation Data:								
Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi		
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	5,954.0	4.02	231.5	5,950.5	44.6	40.3	N 40.3	W 19.3	1.919
MWD	6,049.0	3.45	191.9	6,045.3	41.9	35.4	N 35.4	W 22.5	2.716
MWD	6,144.0	2.73	190.1	6,140.2	38.4	30.4	N 30.4	W 23.5	0.765
MWD	6,238.0	0.77	198.5	6,234.1	36.6	27.6	N 27.6	W 24.1	2.097

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
5,990	6,280	5,987	6,277										
Formation Name:													
Lithology: 100% Granodiorite (mnr-com biotite, rare chlorite)													

Rig Information

Equipment Problems:
Location Condition:
Transport:

Solids Control Information

Screen Sizes:	Top	Bottom
Shaker No 1:	170	
Shaker No 2:	170	
Shaker No 3:	140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Drilling in reservoir
First Aid Treatments:		Medical Treatments:
Lost Time Incidents:		Days Since LTI:
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32


Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 15

Report For 18-Feb-21

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	21 degF	Bar. Pressure:	30.44
Wind Speed/Dir:	7 / ESE	Wind Gusts:	7

	Daily Drilling Report Well ID: Forge 56-32 Field: UTAHFORGE										Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT									
	Report No: 16										Report For 19-Feb-21									
	Operator: University of Utah		Rig: Frontier		Spud Date:		Daily Cost / Mud (\$): ---													
Measured Depth (ft): 6765		Last Casing: 9.625 at 3,494		Wellbore: Original Wellbore		AFE No.		AFE (\$)		Actual (\$)										
Vertical Depth (ft): 6762		Next Casing: 5.500 at 9,000		RKB Elevation (ft): 30.40		---		---		---										
Proposed TD (ft): 9000		Last BOP Test: 12-Feb-21		Job Reference RKB (ft): 28.50		---		---		---										
Hole Made (ft) / Hrs: 470 / 23.5		Next BOP Test:		Working Interest:		Totals:		---		---										
Average ROP (ft/hr): 20.0				LOT (lbs/gal): 16.00		Well Cost (\$):		---		---										
Drilling Days (act./plan): 12/30		Flat Days (act./plan): 0/8		Total Days (act./plan): 12/38		Days On Location:				16										
Pers/Hrs: Operator: 2 / 24		Contractor: 14 / 168		Service: 8 / 96		Other: 0 / 0		Total:		24 / 288										
Safety Summary: No incidents or events reported. Conducted Safety Meeting.																				
Current Operations: At 0600 hours, drilling 8-3/4" hole at 6,907'.																				
Planned Operations: Rotary and slide drill 8-3/4" hole.																				
Toolpusher: David Seddell, Vince Shaffer																				
Wellsite Supervisors: Virgil Welch, Paul Stroud										Tel No.: 7132807438										
Operations Summary																				
From	To	Elapsed	End MD(ft)	Code	Operations Description						Non-Prod									
0:00	9:30	9.50	6,490	3-2-2	Rotary drilled 8-3/4" hole from 6,295' to 6,490'.															
9:30	11:30	2.00	6,515	3-2-3	Slide drilled 8-3/4" hole from 6,490' to 6,515'.															
11:30	14:00	2.50	6,575	3-2-2	Rotary drilled 8-3/4" hole from 6,515' to 6,575'.															
14:00	14:30	0.50	6,575	SERV	Serviced Rig.															
14:30	15:00	0.50	6,585	3-2-2	Rotary drilled 8-3/4" hole from 6,575' to 6,585'.															
15:00	17:00	2.00	6,606	3-2-3	Slide drilled 8-3/4" hole from 6,585' to 6,606'.															
17:00	19:30	2.50	6,672	3-2-2	Rotary drilled 8-3/4" hole from 6,606' to 6,672'.															
19:30	21:00	1.50	6,697	3-2-3	Slide drilled 8-3/4" hole from 6,672' to 6,697'.															
21:00	0:00	3.00	6,765	3-2-2	Rotary drilled 8-3/4" hole from 6,697' to 6,765'.															
Management Summary																				
Rotary and slide drilled 8-3/4" hole from 6,295' to 6,765' at 0600 hours.																				
Comments																				
Drilling in 100% Granodiorite																				
Casing/Tubular Information																				
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)										
FULL	20.000	30	30	129	129	COND														
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30										
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00										
Mud Information																				
%																				
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	Gels 10m	30m	Temp In	Out	Mud Loss
19-Feb-21 20:00 at Depth 6,680 ft Mud Pits																				
8.80	46	17	19	9.8	1	10.5	7	0	93	1		1100	1200		6	9	16	101	117	
Mud Consumables																				
Item Description			Qty.	Cost	Item Description			Qty.	Cost											
caustic - OTHER			2	---	Gel - OTHER			20	---											
Gel - OTHER			16	---	lime - OTHER			1	---											
micro c - OTHER			10	---	PAllets/Wrap - OTHER			3	---											
walnut Pine - OTHER			36	---	xanthan gum - OTHER			3	---											
Bit/BHA/Workstring Information																				
				Depth	This Run	R.O.P.				Mud				Pump						
No Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF		
10	1	REED	TKC73	8.750	5999	714	36.5	19.6	28.0	45	200		9	670	3200	253	504	197	772	
Jets: 13 13 13 13 12 12 12				Out:	Grade: Cutter: /				Dull: /				Wear: Brgs: Gge: Pull:							
BHA - No. 10 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, 24 HWDP = 1169.59																				

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 16

Report For 19-Feb-21

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
6,420	6,460	23.0	25.0	43	45	29	30	5	5	669	669	3,131
Annular Velocity: Drill Collars:		554.0		Drill Pipe:		351.0						
6,460	6,670	23.0	24.0	44	45	31	32	5	5	669	670	3,200
Annular Velocity: Drill Collars:		554.0		Drill Pipe:		351.0						

Miscellaneous Drilling Parameters

Hook Loads (lbs): Off Bottom Rotate: 210 Pick Up: 220 Slack Off: 180 Drag Avg/Max: 10 / 10

Slow Circulation Data:

Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	6,333.0	1.45	232.3	6,329.1	36.4	26.2	N 26.2	W 25.2	0.965
MWD	6,428.0	2.80	243.7	6,424.0	37.4	24.4	N 24.4	W 28.2	1.482
MWD	6,523.0	2.49	239.0	6,518.9	39.1	22.4	N 22.4	W 32.1	0.396
MWD	6,619.0	2.03	255.2	6,614.9	41.2	20.8	N 20.8	W 35.5	0.814
MWD	6,713.0	0.71	244.5	6,708.8	42.7	20.2	N 20.2	W 37.7	1.424
MWD	6,808.0	1.51	224.0	6,803.8	43.4	19.0	N 19.0	W 39.1	0.928

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas		Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max	at Depth	Connect. Trip					Shale	Sand
6,420	6,460	6,417	6,457							8.80			
Formation Name:													
Lithology: 100% Granodiorite (pervasive hematization of amphiboles)													
6,460	6,670	6,457	6,667							8.80			
Formation Name:													
Lithology: 100% Granodiorite (notable calcite, rare-trace detrital epidote)													

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Measuring casing, pinch points

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crownamatic Check**Weather Information**

Sky Condition: Clear

Air Temperature: 28 degF

Wind Speed/Dir: 14 / SSE

Visibility: 10

Bar. Pressure: 30.08

Wind Gusts: 20

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 17

Report For 20-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	7207	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	7198	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	---
Hole Made (ft) / Hrs:	442 / 23.0	Next BOP Test:		Working Interest:		Totals:	---	---	---
Average ROP (ft/hr):	19.22			LOT (lbs/gal):	16.00	Job/Well Cost (\$):		---	---
Drilling Days (act./plan):	13/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	13/38	Days On Location:			17
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total:	24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Drilling 8-3/4" hole at 7,235'.

Planned Operations: Drill 8-3/4" hole to 7,620' and pull out for "Mud Hammer".

Toolpusher: David Seddell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	8:30	8.50	6,965	3-2-2	Rotary drilled 8-3/4" hole from 6,765' to 6,965'.	
8:30	10:00	1.50	6,990	3-2-3	Slide drilled 8-3/4" hole from 6,965' to 6,990'.	
10:00	12:00	2.00	7,050	3-2-2	Rotary drilled 8-3/4" hole from 6,990' to 7,050'.	
12:00	12:30	0.50	7,050	SERV	Serviced Rig.	
12:30	13:00	0.50	7,060	3-2-2	Rotary drilled 8-3/4" hole from 7,050' to 7,060'.	
13:00	15:00	2.00	7,085	3-2-3	Slide drilled 8-3/4" hole from 7,060' to 7,085'.	
15:00	19:30	4.50	7,207	3-2-2	Rotary drilled 8-3/4" hole from 7,085' to 7,207'.	
19:30	20:00	0.50	7,207	3-5-1	Circulated bottoms up.	
20:00	0:00	4.00	7,207	3-6-2	Pulled out of the well bore laying down BHA and bit.	

Management Summary

Drilled 8-3/4" hole from 6,765' to 7,207'. Pulled out of the well bore laying down Bit #10 and BHA.

Comments

Bit 10 was grooved on shoulder and the discovery mud motor bearings were out.

Drilled in 100% Granodiorite with some heavy alterations at 6960' to 6980' with high percentage of biotite.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

															%			Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss			
20-Feb-21 20:00 at Depth 2,707 ft Mud Pits																							
8.70	47	17	20	10	1	10	6	0	94	0.75		1100	1160		5	9	17	103	111				

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	40	---	caustic - OTHER	2	---
Gel - OTHER	20	---	lime - OTHER	1	---
micro c - OTHER	15	---	PAlets/Wrap - OTHER	2	---
walnut Pine - OTHER	15	---	xanthan gum - OTHER	5	---

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 17

Report For 20-Feb-21

Bit/BHA/Workstring Information

					Depth	This Run		R.O.P.					Mud				Pump			
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF	
10	1	REED	TKC73	8.750	5999	1,156	55.5	20.8	40.0	40	40		9	670	3100	253	498	195	763	
Jets: 13 13 13 13 12 12 12					Out: 7207		Grade: Cutter: 3/8		Dull: BT/RO		Wear: S		Brgs: X		Gge: 1		Pull: PR			
BHA - No. 10 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, 24 HWDP = 1169.59																				

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	(psi)
6,910	6,980	20.0	23.0	40	45	40	50	6	7	670	670	3,100
Annular Velocity: Drill Collars:			554.0	Drill Pipe:		351.0						
Comments: Granodiorite												
6,980	7,200	23.0	30.0	45	50	45	55	7	8	670	670	3,150
Annular Velocity: Drill Collars:			554.0	Drill Pipe:		351.0						
Comments: Granodiorite												
6,670	6,910	22.0	24.0	45	48	40	50	6	7	670	670	3,100
Annular Velocity: Drill Collars:			554.0	Drill Pipe:		351.0						
Comments: Granodiorite												

Miscellaneous Drilling Parameters

Hook Loads (lbs):		Off Bottom Rotate:		210	Pick Up:		220	Slack Off:		180	Drag Avg/Max:		10 / 10
Slow Circulation Data:													
Pump 1:		20 spm	170 psi	40 spm	290 psi	60 spm	490 psi						
Pump 2:		20 spm	160 psi	40 spm	300 psi	60 spm	520 psi						

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
6,670	6,910	6,665	6,905										
Formation Name:													
Lithology:		100% Granodiorite											
6,910	6,980	6,905	6,975										
Formation Name:													
Lithology:		100% Granodiorite (high percentage of biotite, recryst. Qtz, hematite)											
6,980	7,200	6,975	7,195										
Formation Name:													
Lithology:		100% Granodiorite (Increase in pervasive chlorite)											

Rig Information

Equipment Problems:													
Location Condition:													
Transport:													

Solids Control Information

Screen Sizes:		Top	Bottom										
Shaker No 1:		170											
Shaker No 2:		170											
Shaker No 3:		140											

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Making connections, mixing chemicals, pinch points.
First Aid Treatments:		Medical Treatments:
Lost Time Incidents:		Days Since LTI:
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 17

Report For 20-Feb-21

Weather Information

Sky Condition: Cloudy

Visibility: 10

Air Temperature: 21 degF

Bar. Pressure: 30.28

Wind Speed/Dir: 14 / N

Wind Gusts: 14

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 18

Report For 21-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	7620	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	7615	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	---
Hole Made (ft) / Hrs:	413 / 12.0	Next BOP Test:		Working Interest:		Totals:	---	---	---
Average ROP (ft/hr):	34.42			LOT (lbs/gal):	16.00	Job/Well Cost (\$):			---
Drilling Days (act./plan):	14/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	14/38	Days On Location:			18
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	11 / 132	Other:	0 / 0	Total:	27 / 324

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Pulling out of the hole.

Planned Operations: Pull out of the well bore and lay down Eaver 8-3/4" reamers. Run in the hole with Mud Hammer and drill 8-3/4" hole.

Toolpusher: David Seddell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	5:00	5.00	7,207	10-6-2	Made up Bit #11 and new BHA. Ran in the hole to 7,141'.	
5:00	5:30	0.50	7,207	3-3	Washed and reamed 8-3/4" hole from 7,141' to 7,208'.	
5:30	7:30	2.00	7,434	3-2-2	Rotary drilled 8-3/4" hole from 7,208' to 7,434'.	
7:30	8:30	1.00	7,460	3-2-3	Slide drilled 8-3/4" hole from 7,434' to 7,460'.	
8:30	11:00	2.50	7,620	3-2-2	Rotary drilled 8-3/4" hole from 7,560' to 7,620'.	
11:00	12:00	1.00	7,620	3-5-1	Circulated well bore clean.	
12:00	15:30	3.50	7,620	3-6-2	Pulled out of the well bore laying down bit and BHA.	
15:30	18:00	2.50	7,620	3-34-3	Made up mud hammer and BHA.	
18:00	18:30	0.50	7,620	3-6-1	Ran in the hole with BHA.	
18:30	21:30	3.00	7,620	3-34-4	Fill pipe and test hammer, pulled out to trouble shoot Mud Hammer, changed out jet and mud orifice.	
21:30	0:00	2.50	7,620	3-6-1	Ran in the hole with mud hammer	

Management Summary

Made up BHA #11 and ran in the well bore. Washed 8-3/4" hole from 7,141' to 7,208' and drilled 8-3/4" hole from 7,208' to 7,620'. Circulated well bore clean and pulled out of the hole laying down bit and BHA.

Comments

While running in the hole the drill string with mud motor and two full gauge roller reamer, BHA was stuck at 5,778'. The bottom 8-3/4" reamer was stuck 14' above the mud hammer. Worked string with torque and pull. Spotted Torquease around tool and worked pipe free.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
21-Feb-21 19:00 at Depth 7,620 ft Mud Pits																				
8.80	46	12	19	10.2	1	10.5	7	0	93	0.25		1100	1080		5	8	12	106	111	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	80	---	Ben-EX - OTHER	3	---
lime - OTHER	3	---	mica - OTHER	14	---
micro c - OTHER	25	---	PAIlets/Wrap - OTHER	2	---
soda ash - OTHER	1	---	walnut Pine - OTHER	5	---
xanthan gum - OTHER	4	---			

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 18

Report For 21-Feb-21

Bit/BHA/Workstring Information

Running Information																					
No	Run	Make	Model	Diam	Depth	This Run		R.O.P.			Mud			Pump			J. Vel	P. Drp	HHP	JIF	
					In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press						
11	1	REED	TKC63	8.750	7207	413	4.96	83.3	307.0	40	40	6	9	670	3100	222	383	150	669		
Jets: 14 14 14 13 13 13					Out: 7620		Grade: Cutter:		1 / 1		Dull: NO / NO		Wear: A		Brgs: X		Gge: 1		Pull: TD		
12	1		Hammer I	8.750	7620																
Jets:					Out:		Grade: Cutter:		/		Dull: /		Wear:		Brgs:		Gge:		Pull:		
BHA - No. 12 - BIT, 3 OTHER, RR, OTHER, MWD, RR, 12 DC, 24 HWDP, OTHER = 1182.64																					

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
7,141	7,460	90.0	140.0	45	45	200	200			670	700	3,300
Annular Velocity:		Drill Collars:		478.6		Drill Pipe:		318.5				

Miscellaneous Drilling Parameters

Hook Loads (lbs): Off Bottom Rotate: 210 Pick Up: 220 Slack Off: 280 Drag Avg/Max: 10 / 10

Slow Circulation Data:

Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm	490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm	520 psi

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	6,902.0	2.28	226.0	6,897.8	44.6	16.8	N 16.8	W 41.3	0.822
MWD	6,998.0	2.12	223.1	6,993.7	46.1	14.2	N 14.2	W 43.9	0.202
MWD	7,093.0	1.58	233.5	7,088.6	47.7	12.1	N 12.1	W 46.1	0.667

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
7,200	7,330	7,325	7,325										
Formation Name:													
Lithology: 100% Granodiorite (
7,330	7,390	7,325	7,385										
Formation Name:													
Lithology: 100% Granodiorite													
7,390	7,440	7,385	7,435										
Formation Name:													
Lithology: 100% Granodiorite													
7,440	7,560	7,435	7,555										
Formation Name:													
Lithology: 100% Granodiorite													
7,560	7,580	7,555	7,575										
Formation Name:													
Lithology: 100% Granodiorite													
7,580	7,620	7,575	7,615										
Formation Name:													
Lithology: 100% Altered Zone (pervasive chlorite, calcite veining, hematite & epidote													

Rig Information

Equipment Problems:

Location Condition:

Transport:

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 18

Report For 21-Feb-21

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Connections in derrick.

First Aid Treatments: Medical Treatments: Lost Time Incidents: Days Since LTI:

☐ BOP Test ☐ Crownamatic Check**Weather Information**

Sky Condition: Clear Visibility: 10

Air Temperature: 19 degF Bar. Pressure: 30.51

Wind Speed/Dir: 8 / ENE Wind Gusts: 8

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 19

Report For 22-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	Daily Cost / Mud (\$):			---
Measured Depth (ft):	7620	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)
Vertical Depth (ft):	7615	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---
Hole Made (ft) / Hrs:	0 / 16.5	Next BOP Test:		Working Interest:		Totals:	---	---
Average ROP (ft/hr):	0.0			LOT (lbs/gal):	16.00	Job/Well Cost (\$):	---	
Drilling Days (act./plan):	15/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	15/38	Days On Location:	19	
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total: 24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Pulling out of the hole for the Mud Hammer.

Planned Operations: Trip for Mud Hammer and continue drilling 8-3/4" hole with mud hammer

Toolpusher: David Seddell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:00	1.00	7,620	3-6-1	Ran in the well bore with Mud Hammer to 5,790'.	
1:00	5:00	4.00	7,620	3-33	BHA stuck at 5,790' and worked string. Spotted torqueaze and worked pipe free.	
5:00	6:00	1.00	7,620	3-5-1	Circulated well bore clean.	
6:00	9:00	3.00	7,620	3-6-2	Pulled out of the hole laying down reamers.	
9:00	10:00	1.00	7,620	3-6-1	Ran in the hole with mud motor.	
10:00	10:30	0.50	7,620	3-97	Tested MWD.	
10:30	11:00	0.50	7,620	3-6-1	Ran in the hole to 5,790'.	
11:00	12:00	1.00	7,620	3-3	Reamed 8-3/4" hole from 5,790' to 5,850'. (Tagged up at 5,790')	
12:00	12:30	0.50	7,620	3-6-1	Ran in the hole to 6,920'.	
12:30	13:00	0.50	7,620	3-5-1	Circulated well bore clean.	
13:00	13:30	0.50	7,620	3-6-1	Ran in the hole to bottom at 7,620'.	
13:30	15:30	2.00	7,620	3-2-1	Attempted to hammer and rotate drilled 8-3/4" hole from 7,260' to 7,627'.	
15:30	16:00	0.50	7,620	3-5-1	Circulated well bore clean.	
16:00	19:30	3.50	7,620	3-6-2	Pulled out of the hole laying down mud hammer and tools.	
19:30	0:00	4.50	7,620	3-6-1	Made up bit and reaming assembly, RIH to 5,703'.	

Management Summary

Ran in the hole with mud motor to 5,790' and reamed 8-3/4" hole to 7,620'. Ran in the well bore to 7,620'. Attempted to mud hammer drill rotating and drilling 8-3/4" hole from 7,620' to 7,627'. Hammer did not fire. Pulled out of the hole laying down mud hammer and tools. Made up bit and reaming assembly and ran in the hole to 5,703'.

Comments

Reamed tight spots starting at 5,790' to 5,983' reaming several times and then sliding to make sure hole was good. Slid to bottom obstructed. Drilled 8-3/4" hole from 7,626' to 7,662.

When pulling out of hole, no drag or tight spot noticed around reamed areas. Hole slick.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
22-Feb-21 20:00 at Depth 7,627 ft Mud Pits																				
8.90	45	13	17	10.4	1	10.5	9	0	91	0.25		1100	1080		5	7	12	93	111	

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 19

Report For 22-Feb-21

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	40	---	Barite 50# bag - OTHER	80	---
caustic - OTHER	2	---	Defoamer - OTHER	3	---
lime - OTHER	1	---	PAlets/Wrap - OTHER	5	---
TorkEase - OTHER	5	---	xanthan gum - OTHER	1	---

Bit/BHA/Workstring Information

				Depth	This Run		R.O.P.						Mud	Pump					
No Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF	
12	1	Hammer I	8.750	7620	0	0	0.0					9	450	2800					
Jets:				Out: 7620	Grade:		Cutter:	1 / 4	Dull:	WT / RO		Wear: S	Brgs: X	Gge: 1	Pull:				
BHA - No. 12 - BIT, 3 OTHER, RR, OTHER, MWD, RR, 12 DC, 24 HWD, OTHER = 1182.64																			

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Tripping

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crownamatic Check**Weather Information**

Sky Condition: Clear

Visibility: 10

Air Temperature: 27 degF

Bar. Pressure: 30.27

Wind Speed/Dir: 6 / SSE

Wind Gusts: 6

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 20

Report For 23-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	Daily Cost / Mud (\$):			---
Measured Depth (ft):	7666	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)
Vertical Depth (ft):	7657	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---
Hole Made (ft) / Hrs:	46 / 14.0	Next BOP Test:		Working Interest:		Totals:	---	---
Average ROP (ft/hr):	3.29			LOT (lbs/gal):	16.00	Job/Well Cost (\$):		---
Drilling Days (act./plan):	16/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	16/38	Days On Location:		20
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	12 / 144	Other:	0 / 0	Total: 28 / 336

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Slipped and cut drilling line. Running in the hole to drill 8-3/4" hole with PDC.

Planned Operations: Continue drilling 8-3/4" hole with PDC. Trouble shoot mud hammer.

Toolpusher: David Seddell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	3:00	3.00	7,627	3-3	Reamed 8-3/4" hole from 5,703' to 5,983'.	
3:00	4:00	1.00	7,627	3-6-1	Ran in the hole un-obstructed from 5,983' to 7,600'.	
4:00	4:30	0.50	7,627	3-3	Washed and reamed 8-3/4" hole from 7,600' to 7,627'.	
4:30	5:30	1.00	7,662	3-2-2	Rotary drilled 8-3/4" hole from 7,627' to 7,662'.	
5:30	6:00	0.50	7,662	3-5-1	Circulated hole clean.	
6:00	9:00	3.00	7,662	3-6-2	Pulled out of the well bore laying down BHA.	
9:00	13:00	4.00	7,662	3-34-3	Made up mud hammer and ran in the hole to 5500'.	
13:00	17:00	4.00	7,666	3-2-2	Attempt to initiate mud hammer to work. Rotary drilled with hammer from 7,662' to 7,666'.	
17:00	22:00	5.00	7,666	3-6-2	Pulled out of the hole laying down mud hammer and tools.	
22:00	0:00	2.00	7,666	OTHER	Ran mud hammer in mouse hole and tested hammer. Hammer would not fire.	

Management Summary

Reamed 8-3/4" hole from 5,703' to 5,983' with 2 full gauge roller reamers. Ran to bottom and drilled 8-3/4" hole from 7,627' to 7,662'. Pulled out of the hole laying down bit and tools. Made up mud hammer and ran in the hole and attempted to initiate mud hammer firing while rotating from 7,262' to 7,666'. Pulled out of the well bore laying down tools. Ran mud hammer in mouse hole and tested hammer which did not fire.

Comments

Tested Mud Hammer in mouse hole, set weight on mud hammer and started pumps, hammer did not fire

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
23-Feb-21 19:00 at Depth 7,666 ft Mud Pits																				
9.00	42	13	15	11	1	10	8	0	92	0.1		900	1360		4	6	10	103	111	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	32	---	Barite 50# bag - OTHER	80	---
lime - OTHER	1	---	PAlets/Wrap - OTHER	3	---
xanthan gum - OTHER	10	---			

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 20

Report For 23-Feb-21

Bit/BHA/Workstring Information

Drilling Information																							
					Depth		This Run		R.O.P.						Mud		Pump						
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF				
11	2	REED	TKC63	8.750	7627	35	1	35.0	61.0	35	55	12	9	550	3100	210	348	112	526				
Jets: 13 13 13 14 14					Out: 7662		Grade: Cutter:			1 / 1		Dull: CT / NO		Wear: A		Brgs: X		Gge: 1		Pull: TD			
BHA - No. 13 - BIT, STAB, DC, RR, DC, RR, 10 DC, JAR, 24 HWDP = 1150.72																							

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas		Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max	at Depth	Connect. Trip					Shale	Sand
7,620	7,660	7,615	7,655							8.80			

Formation Name:

Lithology: 40-50% altered zone (Abundant biotite, weak foliation, increase in large euhedral epidote, no calcite) 50-60% Granodiorite (overall increase in secondary mineralization)

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Tripping

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crownmatic Check**Weather Information**

Sky Condition: Clear

Visibility: 10

Air Temperature: 21 degF

Bar. Pressure: 30.14

Wind Speed/Dir: 7 / S

Wind Gusts: 7

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 21

Report For 24-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	8353	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	8348	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---	
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	
Hole Made (ft) / Hrs:	687 / 21.0	Next BOP Test:		Working Interest:		Totals:	---	---	
Average ROP (ft/hr):	32.71			LOT (lbs/gal):	16.00	Job/Well Cost (\$):			
Drilling Days (act./plan):	17/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	17/38	Days On Location:			21
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	11 / 132	Other:	0 / 0	Total:	27 / 324

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Drilling 8-3/4" hole at 8,471' at 0600 hours.

Planned Operations: Rotary and slide drill 8-3/4" hole.
Plan to test EAVOR mud hammer in the mouse hole today. If successful, will attempt to drill with hammer, after logs.

Toolpusher: David Seddell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	4:00	4.00	7,666	03-061	Made up bit and tools. Ran in hole to 3,561'.	
4:00	6:00	2.00	7,666	CUTDL	Slipped and cut 100' to drilling line.	
6:00	7:30	1.50	7,666	3-6-1	Ran in the hole to bottom at 7,666'.	
7:30	8:00	0.50	7,751	3-2-2	Rotary drilled 8-3/4" hole from 7,666' to 7,751'.	
8:00	8:30	0.50	7,776	3-2-3	Slide drilled 8-3/4" hole from 7,751' to 7,776'.	
8:30	9:30	1.00	7,846	3-2-2	Rotary drilled 8-3/4" hole from 7,776' to 7,846'.	
9:30	10:30	1.00	7,871	3-2-3	Slide drilled 8-3/4" hole from 7,846' to 7,871'.	
10:30	12:30	2.00	8,000	3-2-2	Rotary drilled 8-3/4" hole from 7,871' to 8,000'.	
12:30	13:00	0.50	8,000	3-5-1	Circulated bottoms up.	
13:00	13:30	0.50	8,000	3-6-2	Pulled out of the hole from 8,000' to 7,750'.	
13:30	14:00	0.50	8,000	3-3	Reamed 8-3/4" hole from 7,750' to 8,000'.	
14:00	14:30	0.50	8,035	3-2-2	Rotary drilled 8-3/4" hole from 8,000' to 8,035'.	
14:30	16:00	1.50	8,065	3-2-3	Slide drilled 8-3/4" hole from 8,035' to 8,065'.	
16:00	18:00	2.00	8,140	3-2-2	Rotary drilled 8-3/4" hole from 8,065' to 8,140'.	
18:00	18:30	0.50	8,147	3-2-3	Slide drilled 8-3/4" hole from 8,140' to 8,147'.	
18:30	0:00	5.50	8,353	3-2-2	Rotary drilled 8-3/4" hole from 8,147' to 8,353'.	

Management Summary

Made up bit and BHA. Ran in the well bore to 3,561'. Slipped and cut 100' of drilling line. Ran to bottom at 7,666'. Rotary and slide drilled 8-3/4" hole from 7,666' to 8,353'.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

Mud Information																				
%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
24-Feb-21 21:00 at Depth 8,238 ft Mud Pits																				
9.00	40	40	12	10.6	1	10.5	8	0	92	0.1		1200	1200		4	5	9	107	127	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Bicarb - OTHER	5	---	caustic - OTHER	4	---
Defoamer - OTHER	1	---	lime - OTHER	2	---
soda ash - OTHER	6	---	xanthan gum - OTHER	11	---

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 21

Report For 24-Feb-21

Bit/BHA/Workstring Information

					Depth	This Run		R.O.P.				Mud				Pump				
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF	
13	1	REED	TKC63	8.750	7666	687	15.5	44.3	120.0	30	190	9	9	670	3250	256	528	206	799	
Jets: 13 13 13 14 14					Out:		Grade: Cutter:		/	Dull		/	Wear:		Brgs:		Gge:		Pull:	
BHA - No. 14 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, 24 HWDP = 1227.95																				

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
8,100	8,110	60.0	107.0	43	45	40	41	8	11	654	654	3,100
Annular Velocity: Drill Collars:		478.0		Drill Pipe:		318.0						
8,110	8,260	32.0	146.0	41	44	55	57	5	15	654	654	3,200
Annular Velocity: Drill Collars:		478.0		Drill Pipe:		318.0						
8,260	8,340	30.0	122.0	40	42	40	43	7	12	654	654	3,300
Annular Velocity: Drill Collars:		478.0		Drill Pipe:		318.0						

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	7,788.0	2.83	205.1	7,783.1	58.8	-9.9	S 9.9	W 58.0	1.040
MWD	7,883.0	2.40	187.5	7,878.0	60.9	-14.0	S 14.0	W 59.2	0.952
MWD	7,977.0	3.49	215.5	7,971.9	63.8	-18.2	S 18.2	W 61.2	1.888
MWD	8,071.0	1.86	235.8	8,065.8	67.6	-21.4	S 21.4	W 64.1	1.979
MWD	8,166.0	0.75	258.7	8,160.8	69.7	-22.4	S 22.4	W 66.0	1.268
MWD	8,260.0	1.39	294.0	8,254.7	71.1	-22.1	S 22.1	W 67.6	0.948
MWD	8,355.0	2.45	290.6	8,349.7	73.6	-20.9	S 20.9	W 70.6	1.122

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)		Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP	
From	To	From	To	Avg	Max							Shale	Sand
7,810	7,860									9.00			
Formation Name:													
Lithology: 100% Granodiorite (increase in secondary mineralization eg. chlorite, calcite, epidote)													
7,860	8,100									9.00			
Formation Name:													
Lithology: 100% Granodiorite (minimal alteration, primarily rare chlorite-minor chlorite)													
8,100	8,110									9.00			
Formation Name:													
Lithology: 100% Quartz Monzonite (possible felsic dike, but contained decreased quartz & increased K-spar)													
8,110	8,210									9.00			
Formation Name:													
Lithology: 100 Granodiorite, (0-80% altered zone, with felsic dike @ 8120') Significant increase in secondary calcite.													
8,210	8,260									9.00			
Formation Name:													
Lithology: 100% Quartz Monzonite from 8210-8240', 100% Granodiorite from 8240-8260'.													
8,260	8,340	8,260								9.00			
Formation Name:													
Lithology: 100% Syenite (except at 8280', appears to be 50/50 Quartz Monzonite/Syenite)													

Rig Information

Equipment Problems:

Location Condition:

Transport:

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 21

Report For 24-Feb-21

Solids Control Information

Screen Sizes: Top Bottom

Shaker No 1: 170

Shaker No 2: 170

Shaker No 3: 140

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills Time Description

Safety 60 Connections


First Aid Treatments: Medical Treatments: Lost Time Incidents: Days Since LTI:


☐ BOP Test ☐ Crownmatic Check**Weather Information**


Sky Condition: Clear Visibility: 10

Air Temperature: 18 degF Bar. Pressure: 30.44

Wind Speed/Dir: 18 / N Wind Gusts: 20

	Daily Drilling Report Well ID: Forge 56-32 Field: UTAHFORGE		Job ID: Original Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT		Geothermal Resource Group Well Name: 56-32	
	Report No: 22				Report For 25-Feb-21	
	Operator: University of Utah		Rig: Frontier		Spud Date:	
Measured Depth (ft): 8810		Last Casing: 9.625 at 3,494		Wellbore: Original Wellbore		
Vertical Depth (ft): 8800		Next Casing: 5.500 at 9,000		RKB Elevation (ft): 30.40		
Proposed TD (ft): 9000		Last BOP Test: 12-Feb-21		Job Reference RKB (ft): 28.50		
Hole Made (ft) / Hrs: 457 / 24.0		Next BOP Test:		Working Interest:		
Average ROP (ft/hr): 19.04		LOT (lbs/gal): 16.00		Totals:		
Drilling Days (act./plan): 18/30		Flat Days (act./plan): 0/8		Total Days (act./plan): 18/38		
Pers/Hrs: Operator: 2 / 24		Contractor: 14 / 168		Service: 12 / 144		
Other: 0 / 0		Total: 28 / 336		Days On Location: 22		
Safety Summary: No incidents or events reported. Conducted Safety Meeting.						
Current Operations: Pulling out of the well bore from 8900' for new BHA.						
Planned Operations: Change bits and BHA and drill 8-3/4" hole to TD.						
Toolpusher: David Seddell, Vince Shaffer						
Wellsite Supervisors: Virgil Welch, Paul Stroud				Tel No.: 7132807438		
Operations Summary						
From	To	Elapsed	End MD(ft)	Code	Operations Description	
0:00	2:00	2.00	8,404	DRILR	Rotate drilled 8-3/4" hole from 8353' to 8404'.	
2:00	4:30	2.50	8,434	DRILS	Slide drilled 8-3/4" hole from 8404' to 8434'.	
4:30	10:30	6.00	8,598	DRILR	Rotate drilled 8-3/4" hole from 8434' to 8598'.	
10:30	12:00	1.50	8,611	DRILS	Slide drilled 8-3/4" hole from 8598' to 8611'.	
12:00	12:30	0.50	8,627	DRILR	Rotate drilled 8-3/4" hole from 8611' to 8627'.	
12:30	14:00	1.50	8,642	DRILS	Slide drilled 8-3/4" hole from 8627' to 8642'.	
14:00	15:00	1.00	8,661	DRILR	Rotate drilled 8-3/4" hole from 8642' to 8661'.	
15:00	16:00	1.00	8,676	DRILS	Slide drilled 8-3/4" hole from 8661' to 8676'.	
16:00	17:00	1.00	8,693	DRILR	Rotate drilled 8-3/4" hole from 8676' to 8693'.	
17:00	18:30	1.50	8,708	DRILS	Slide drilled 8-3/4" hole from 8693' to 8708'.	
18:30	19:00	0.50	8,728	DRILR	Rotary drilled 8-3/4" hole from 8708' to 8728'.	
19:00	20:00	1.00	8,743	DRILS	Slide drilled 8-3/4" hole from 8728' to 8743'.	
20:00	20:30	0.50	8,758	DRILR	Rotary drilled 8-3/4" hole from 8743' to 8758'.	
20:30	21:30	1.00	8,773	DRILS	Slide drilled 8-3/4" hole from 8758' to 8773'.	
21:30	22:00	0.50	8,785	DRILR	Rotary drilled 8-3/4" hole from 8773' to 8785'.	
22:00	0:00	2.00	8,810	DRILS	Slide drilled 8-3/4" hole from 8785' to 8810'.	
Management Summary						
Rotary and slide drilled 8-3/4" hole from 8353' to 8810'.						
Comments						
Fighting strong trend requiring slide drilling to keep angle down. Formation appears to be in transition from Granodiorite to Gneiss with with gneissic banding, rexin of quartz, significant biotite and alternating felds/quartz.						
Drill rate dropped from 42'/hour to 4'/hour at bottom while rotating.						
Casing/Tubular Information						
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	
FULL	20.000	30	30	129	129	
FULL	13.375	0	0	382	382	
FULL	9.625	0	0	3,494	3,488	
Mud Information						
%						
Dens.	Vis	PV	YP	Filt.	Cake	
25-Feb-21 19:30	at Depth 8,737 ft	Mud Pits				
9.00	42	14	16	10.8	1	
10.5	8	0	92	0.1	1200	
1120	4	5	9	108	118	

	Daily Drilling Report		Geothermal Resource Group	
	Well ID: Forge 56-32		Well Name: 56-32	
	Field: UTAHFORGE		Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT	
Report No: 22			Report For 25-Feb-21	
Mud Consumables				
Item Description	Qty.	Cost	Item Description	Qty.
caustic - OTHER	2	---	lime - OTHER	1
PAallets/Wrap - OTHER	3	---	soda ash - OTHER	5
xanthan gum - OTHER	8	---		
Bit/BHA/Workstring Information				
BHA - No. 14 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, 24 HWDP = 1227.95				
Miscellaneous Drilling Parameters				
Hook Loads (lbs):	Off Bottom Rotate:	240	Pick Up:	310
			Slack Off:	190
			Drag Avg/Max:	40 / 70
Slow Circulation Data:				
Pump 1:	20 spm	170 psi	40 spm	290 psi
			60 spm	490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi
			60 spm	520 psi
Mud Log Information				
Depth (ft)	TVD (ft)	Gas (Units)	Gas	Drilling
From To	From To	Avg Max at Depth	Connect. Trip	Exp. Press
8,520	8,610			
Formation Name:				
Lithology: 100% Granodiorite, (absent calcite, rare hematite & chlorite)				
8,610	8,840			
Formation Name:				
Lithology: 100% Granodiorite (rare-trace calcite, trace chlorite)				
8,840	8,870			
Formation Name:				
Lithology: 0-60 Granodiorite, (gneissic banding, granodiorite exhibiting minimal migmatitic texture in quartz)				
8,340	8,400			8.90
Formation Name:				
Lithology: 40-90% Granodiorite, 0-20% Syenite, 0-40% Altered zone with rare to minor epidote.				
8,400	8,520			
Formation Name:				
Lithology: 100% Granodiorite with trace calcite, rare trace chlorite				
Rig Information				
Equipment Problems:				
Location Condition:				
Transport:				
Drill Pipe Inventory				
DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF
Safety Information				
Meetings/Drills	Time	Description		
Safety	60	High temperature mud.		
First Aid Treatments:		Medical Treatments:		Lost Time Incidents:
Days Since LTI:				
<input type="checkbox"/> BOP Test <input type="checkbox"/> Crownamatic Check				
Weather Information				
Sky Condition: Clear		Visibility: 10		
Air Temperature: 19 degF		Bar. Pressure: 30.2		
Wind Speed/Dir: 6 / E		Wind Gusts: 6		

	Daily Drilling Report Well ID: Forge 56-32 Field: UTAHFORGE		Job ID: Original		Geothermal Resource Group, Inc. Well Name: 56-32 Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT																	
	Report No: 23												Report For 26-Feb-21									
	Operator: University of Utah Rig: Frontier Spud Date: Daily Cost / Mud (\$): --- Measured Depth (ft): 8900 Last Casing: 9.625 at 3,494 Wellbore: Original Wellbore AFE No. AFE (\$) Actual (\$) Vertical Depth (ft): 8894 Next Casing: 5.500 at 9,000 RKB Elevation (ft): 30.40 --- --- --- Proposed TD (ft): 9000 Last BOP Test: 12-Feb-21 Job Reference RKB (ft): 28.50 --- --- --- Hole Made (ft) / Hrs: 90 / 16.0 Next BOP Test: Working Interest: Totals: --- --- --- Average ROP (ft/hr): 5.63 LOT (lbs/gal): 16.00 Job/Well Cost (\$): --- Drilling Days (act./plan): 19/30 Flat Days (act./plan): 0/8 Total Days (act./plan): 19/38 Days On Location: 23 Pers/Hrs: Operator: 2 / 24 Contractor: 14 / 168 Service: 8 / 96 Other: 0 / 0 Total: 24 / 288												Safety Summary: No incidents or events reported. Conducted Safety Meeting. Current Operations: Finished drilling 8-3/4" hole to TD (9,145'). Pulling out of the hole for E-Logs. Planned Operations: Finish pulling out of the hole, rig up and run E-Logs and core side wall samples. Toolpusher: David Seddell, Vince Shaffer Wellsite Supervisors: Virgil Welch, Paul Stroud Tel No.: 7132807438									
Operations Summary																						
From	To	Elapsed	End MD(ft)	Code	Operations Description										Non-Prod							
0:00	1:00	1.00	8,855	3-2-2	Rotary drilled 8-3/4" hole from 8,810' to 8,855'.																	
1:00	2:00	1.00	8,871	3-2-3	Slide drilled 8-3/4" hole from 8,855' to 8,871'.																	
2:00	3:00	1.00	8,900	3-2-2	Rotary drilled 8-3/4" hole from 8,871' to 8,900'.																	
3:00	4:00	1.00	8,900	3-5-1	Circulated well bore clean.																	
4:00	9:00	5.00	8,900	3-6-1	Pulled out of the hole laying down bit and tools.																	
9:00	14:00	5.00	8,900	OTHER	Tested 2 mud hammers in "Mouse Hole" with mud and water. Hammers worked with water but not with mud.																	
14:00	21:30	7.50	8,900	3-6-1	Made up bit and BHA 15 and staged in the hole 2,200-7,651' cooling well bore.																	
21:30	22:00	0.50	8,900	3-6-1	Ran in the hole and encountered tight spot at 7651', jarred drill string free and worked tight spot to 8,188'.																	
22:00	0:00	2.00	8,900	3-3	Reamed 8-3/4" hole from 8,188' to 8,923'.																	
Management Summary																						
Drilled 8-3/4" hole from 8,810' to 8,900' sliding and rotating. Pulled out of the well bore and tested mud hammers in "Mouse Hole". Hammers worked on water but failed on mud. Made up BHA15 and ran in the hole to 7,651' and encountered tight hole. Reamed 8-3/4" hole to 8,923'.																						
Comments																						
While tripping in the well bore encountered very tight hole from 7651' to bottom. Drilled 8-3/4" hole from 8810' to TD at 9145' MD, 9138' TVD at 0450 hours, 2-27-2021. Bottom hole samples have not been analyzed yet due to fast P-Rates however samples indicate Gneiss formation with very little alteration.																						
Casing/Tubular Information																						
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)												
FULL	20.000	30	30	129	129	COND																
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30												
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00												
Mud Information																						
										%			Gels			Temp		Mud				
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss		
26-Feb-21 17:00 at Depth 8,900 ft Mud Pits																						
9.00	42	15	14	10.4	1	10.5	8	0	92	0.1		1200	1122		4	5	9	108	118			
Bit/BHA/Workstring Information																						
				Depth	This Run		R.O.P.		Mud Pump													
No Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF				
13	1	REED	TKC63	8.750	7666	1,212	42.5	28.5	61.0	45	40	12	9	697	3100	266	571	232	865			
Jets: 13 13 13 14 14 14				Out: 8900	Grade: Cutter: 8 / 2		Dull: BT / BT		Wear: S		Brigs: X		Gge: 1		Pull: PR							
14	1	REED	TKC813	8.750	8900																	
Jets: 14 14 14 14 11 11 11				Out:	Grade: Cutter: /		Dull: /		Wear:		Brigs:		Gge:		Pull:							
BHA - No. 15 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, JAR, 24 HWDP = 1202.18																						

Printed: 06:05 27-Feb-21

RIMBase 7.5.397.0

Page: 1 of 2

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 23

Report For 26-Feb-21

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
8,810	8,900	30.0	80.0	45	45	190	190	9	9	670	670	
Annular Velocity:		Drill Collars:		478.6	Drill Pipe:		318.5					

Miscellaneous Drilling Parameters

Hook Loads (lbs):	Off Bottom Rotate:	Pick Up:	Slack Off:	Drag Avg/Max:	/
Slow Circulation Data:					
Pump 1:	20 spm	170 psi	40 spm	290 psi	60 spm 490 psi
Pump 2:	20 spm	160 psi	40 spm	300 psi	60 spm 520 psi

Mud Log Information

Depth (ft)		TVD (ft)		Gas (Units)			Gas		Drilling	Pore	Mud	Shale	ROP	
From	To	From	To	Avg	Max	at Depth	Connect.	Trip	Exp.	Press	Dens.	Dens.	Shale	Sand
8,840	8,900										9.00			

Formation Name:

Lithology: 40-100% Gneiss (gneissic banding, significant biotite, rexin & migmatic texture in quartz)

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes:	Top	Bottom
Shaker No 1:	170	
Shaker No 2:	170	
Shaker No 3:	140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills		Time	Description	
Safety		60	Tripping	
First Aid Treatments:		Medical Treatments:		Lost Time Incidents:
Days Since LTI:				
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check			

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	18 degF	Bar. Pressure:	29.73
Wind Speed/Dir:	16 / SW	Wind Gusts:	20

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 24

Report For 27-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:		Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---	---	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	---
Hole Made (ft) / Hrs:	245 / 9.5	Next BOP Test:		Working Interest:		Totals:	---	---	---
Average ROP (ft/hr):	25.79			LOT (lbs/gal):	16.00	Job/Well Cost (\$):			---
Drilling Days (act./plan):	20/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	20/38	Days On Location:			24
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0	Total:	24 / 288

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Circulating to cool well bore for core log.

Planned Operations: Cool well bore and run coring tool on E-Line.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	0:30	0.50	8,900	3-3	Reamed 8-3/4" hole to 8900'.	
0:30	1:00	0.50	8,900	3-2-2	Rotary drilled 8-3/4" hole from 8900' to 8923'.	
1:00	2:00	1.00	8,948	3-2-3	Slide drilled 8-3/4" hole from 8923' to 8948'.	
2:00	2:30	0.50	9,000	3-2-2	Rotary drilled 8-3/4" hole from 8948' to 9000'.	
2:30	3:30	1.00	9,025	3-2-3	Slide drilled 8-3/4" hole from 9000' to 9025'.	
3:30	5:00	1.50	9,145	3-2-2	Rotary drilled 8-3/4" hole from 9025' to TD of 9145'.	
5:00	5:30	0.50	9,145	3-5-1	Circulated well bore clean.	
5:30	10:30	5.00	9,145	3-6-2	Pulled out of the hole laying down bit, tools and drill collars.	
10:30	14:00	3.50	9,145	10-343	Made up logging bit, float and tools on HWDP and ran in the hole to 9145'.	
14:00	15:00	1.00	9,145	10-5-1	Circulated and cooled well bore.	
15:00	18:00	3.00	9,145	10-11	Rigged up loggers and picked up tools. Ran in to bottom through drill pipe with wire line.	
18:00	18:30	0.50	9,145	10-11	Rigged down wire line unit and pump in sub.	
18:30	0:00	5.50	9,145	10-11	Pulled out of the hole with Triple Combo and Gyro 30'/minute.	

Management Summary

Slide and rotary drilled 8-3/4" hole from 8,923' to 9,145' TD. Circulated well bore clean and pulled out of the hole. Laid down bit, tools and drill collars. Made up logging bit and tools. Ran in the hole to 9,145' and circulated to cool well bore. Pulled out of the hole at 30'/min with Gyro and Triple Combo.

Comments

Bottom hole temperature coming off bottom was 305 degrees F. Caliper Density Pad failed.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%															Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
27-Feb-21 15:00 at Depth 9,145 ft Mud Pits																				
9.00	40	13	17	12	1	10	8	0	92	0.1		1200	1100		3	6	9	113	128	

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Barite - OTHER	168	---	Defoamer - OTHER	2	---
soda ash - OTHER	2	---			

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 24

Report For 27-Feb-21

Bit/BHA/Workstring Information

					Depth	This Run		R.O.P.				Mud		Pump					
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HHP	JIF
14	1	REED	TKC813	8.750	8900	245	3.2	76.6	160.0	45	40	15	9	650	3500	214	370	140	649
Jets: 14 14 14 14 11 11 11 11					Out: 9145		Grade: Cutter: 1 / 1		Dull: NO / NO		Wear: A		Brgrs: X		Gge: 1		Pull: TD		
BHA - No. 15 - BIT, MMTR, OTHER, STAB, MONEL, 12 DC, JAR, 24 HWDP = 1202.18																			

Drilling Parameters

Depth (ft)		ROP (ft/hr)		WOB (lbs)		RPM		Torque (ft lbs)		Flow (gals/min)		Pressure (psi)
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	
8,900	945	140.0	80.0	45	45	190	190	9	9	670	670	
Annular Velocity: Drill Collars:				478.6	Drill Pipe: 318.5							

Miscellaneous Drilling Parameters

Hook Loads (lbs):		Off Bottom Rotate:		Pick Up:		Slack Off:		Drag Avg/Max:		/	
Slow Circulation Data:											
Pump 1:		20 spm	170 psi	40 spm	290 psi	60 spm	490 psi				
Pump 2:		20 spm	160 psi	40 spm	300 psi	60 spm	520 psi				

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates		
							N-S	E-W	D.L.S.
MWD	8,927.0	2.44	260.7	8,920.5	99.6	-15.1	S 15.1	W 98.4	4.249
MWD	9,021.0	1.84	230.1	9,014.5	102.9	-16.4	S 16.4	W 101.6	1.348
MWD	9,093.0	2.99	239.9	9,086.4	105.6	-18.1	S 18.1	W 104.1	1.690
MWD	9,145.0	2.99	239.9	9,138.3	108.2	-19.5	S 19.5	W 106.4	0.000

Rig Information

Equipment Problems:												
Location Condition:												
Transport:												

Solids Control Information

Screen Sizes:		Top	Bottom
Shaker No 1:		170	
Shaker No 2:		170	
Shaker No 3:		140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Logging and tripping
First Aid Treatments: Medical Treatments: Lost Time Incidents: Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	16 degF	Bar. Pressure:	30.19
Wind Speed/Dir:	5 / N	Wind Gusts:	5

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 25

Report For 28-Feb-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---		---
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):				LOT (lbs/gal):	16.00	Job/Well Cost (\$):			---
Drilling Days (act./plan):	21/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	21/38	Days On Location:			25
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	9 / 108	Other:	0 / 0	Total:	25 / 300

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Laying down drill pipe.

Planned Operations: Lay down drill pipe and run 5.5" casing.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	2:00	2.00	9,145	10-11	Rigged down loggers and download data.	
2:00	5:00	3.00	9,145	10-6-1	Ran in the hole to 9,145'.	
5:00	7:00	2.00	9,145	10-5-1	Circulate to cool well bore for wire-line coring.	
7:00	10:00	3.00	9,145	10-6-2	Pulled out of the hole.	
10:00	19:00	9.00	9,145	10-11	Rigged up loggers and run side core logs. Rigged down loggers.	
19:00	20:00	1.00	9,145	10-6-3	Ran in the well bore to 3,489'.	
20:00	21:30	1.50	9,145	10-99	Slip and cut 85' of drilling line.	
21:30	23:00	1.50	9,145	10-6-3	Ran in the hole to TD at 9,145'.	
23:00	0:00	1.00	9,145	10-5-1	Circulated to cool well bore.	

Management Summary

Rigged down Schlumberger and ran in the hole to 9145' TD. Circulated to cool well bore. Pulled out of the hole and ran Schlumberger side cores. Ran in the hole and circulated to cool well bore at 2400 hours.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%																Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss	
28-Feb-21 15:00 at Depth 9,145 ft Mud Pits																					
9.00	38	13	6	11	1	10	8	0	92	0.1		1100	320			1	5	93	111		

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
amberguard - OTHER	6	---	caustic - OTHER	2	---
DC-310/CI-100 - OTHER	3	---			

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 25

Report For 28-Feb-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Laying down pipe and pinch points.
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	12 degF	Bar. Pressure:	30.46
Wind Speed/Dir:	7 / NE	Wind Gusts:	7

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 26

Report For 01-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):	---
Measured Depth (ft):	9145	Last Casing:	9.625 at 3,494	Wellbore:	Original Wellbore	AFE No.	---
Vertical Depth (ft):	9138	Next Casing:	5.500 at 9,000	RKB Elevation (ft):	30.40	AFE (\$)	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	Actual (\$)	---
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---
Average ROP (ft/hr):				LOT (lbs/gal):	16.00	Job/Well Cost (\$):	---
Drilling Days (act./plan):	22/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	22/38	Days On Location:	26
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	9 / 108	Other:	0 / 0
				Total:	25 / 300		

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Running 5-1/2" casing.

Planned Operations: Run and cement 5-1/2" 17 ppf, L-80, Buttress casing.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	12:00	12.00	9,145	11-342	Laid down drill pipe and heavy wall drill pipe, bit and subs.	
12:00	15:30	3.50	9,145	6-99	Nippled down BOPE and picked up with rig. Cut off casing and removed slips, installed BOPE.	
15:30	0:00	8.50	9,145	4-12-1	Rigged up and ran 5-1/2" 17 ppf, L-80, Buttress Liner equipped with Fiber Optics cable attached to the liner.	

Management Summary

Laid down drill pipe and tools. Cut and removed 9-5/8" X 13-3/8" slips. Rigged up and ran 5-1/2" 17 ppf, L-80, Buttress Liner equipped with fiber optic cable.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00

Mud Information

%																			Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss				
01-Mar-21 17:00 at Depth 9,145 ft Mud Pits																								
9.00	38	13	7	10	1	10	8	0	92	0.1		1200	320		1	4	10	103	130					

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
amberguard - OTHER	10	---	Bicarb - OTHER	7	---
Gel - OTHER	48	---	mica - OTHER	18	---

Rig Information

Equipment Problems:

Location Condition:

Transport:

Solids Control Information

Screen Sizes:	Top	Bottom
Shaker No 1:	170	
Shaker No 2:	170	
Shaker No 3:	140	

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 26

Report For 01-Mar-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Running casing.
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	19 degF	Bar. Pressure:	30.21
Wind Speed/Dir:	4 / SSE	Wind Gusts:	5

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 27

Report For 02-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---		---
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):						Job/Well Cost (\$):			---
Drilling Days (act./plan):	23/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	23/38	Days On Location:			27
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	17 / 204	Other:	0 / 0	Total:	33 / 396

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Waiting on cement and tools.

Planned Operations: Secure cement and tools. Execute top down cement job.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	7:00	7.00	9,145	4-12-1	Ran 5-1/2" 17 ppf, L-88, Buttress casing equipped with fiber optic cable to 7,280'.	
7:00	8:00	1.00	9,145	03-051	Circulated to cool and clean well bore.	
8:00	9:30	1.50	9,145	4-12-1	Ran 5-1/2" 17 ppf, L-80, Buttress casing equipped with fiber optic cable to 8,192'.	
9:30	10:00	0.50	9,145	03-051	Circulated to cool well bore.	
10:00	11:30	1.50	9,145	4-12-1	Ran 5-1/2" 17 ppf, L-80, Buttress casing equipped with fiber optic cable to 9,130'.	
11:30	13:00	1.50	9,145	03-051	Circulated to cool well bore.	
13:00	16:30	3.50	9,145	5-99	Rigged up cementer, pumped cement with pressure increasing to 6000 psi. Worked pipe to 9,105' attempting to free pack off. Attempted to pump wiper plug with instant pressure build up.	
16:30	17:00	0.50	9,145	11-47	Closed Annular Preventer and pumped 330 barrels down back side to clear annulus of cement.	
17:00	0:00	7.00	9,145	3-32	Waited on cement and tools.	

Management Summary

Ran 5-1/2" 17 ppf L-80 Liner equipped with fiber optic cable to 9,133'. Mixed and pumped cement, pressure increased to 6,000 psi. Casing packed off, attempted to free casing and worked pipe to 9,105'. Attempted to displace liner wiper plug and fluid would not move. Closed annular preventer and displaced 330 barrels of fluid to clear 9-5/8" X 5-1/2" annular for "Top Down" cement job. Waited on cement and tools to top job.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Mud Information

															%			Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss			
02-Mar-21 13:00 at Depth 9,145 ft Mud Pits																							
9.00	34	14	4		1	9	3	0	97	0.1													

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
micro c - OTHER	5	---			

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
5	277	19.5	S-135	4.5IF					

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 27

Report For 02-Mar-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Flashing mud
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	23 degF	Bar. Pressure:	30
Wind Speed/Dir:	12 / SSE	Wind Gusts:	15

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 28

Report For 03-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	---	---		---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---		---
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---		---
Average ROP (ft/hr):						Job/Well Cost (\$):			---
Drilling Days (act./plan):	24/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	24/38	Days On Location:			28
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	3 / 28	Other:	0 / 0	Total:	19 / 220

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Waiting on cement and preparing for Top Squeeze and Top Fill cement job.

Planned Operations: Perform "Top Squeeze" cement job for the 9-5/8" X 5-1/2" casing annulus.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	0:00	24.00	9,145	3-32	Waited on cement for "Top Down" cement job and tools for clean out. Cut and laid down 25' of 5-1/2" liner at KB level. Removed flow line and check valve in kill line. Made preparations for Top Down cement job.	

Management Summary

Made preparations for "Top Squeeze/Top Fill" cement job..

Comments

Received tools for cleaning out cement. Partial load of 2-7/8" drill pipe.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Mud Information

%														Gels			Temp		Mud	
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss
03-Mar-21 17:00 at Depth 9,145 ft Mud Pits																				
8.70	36																			

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
xanthan gum - OTHER	10	---			

Rig Information

Equipment Problems:

Location Condition:

Transport:

Safety Information

Meetings/Drills	Time	Description		
Safety	60	Squeezing		
First Aid Treatments:		Medical Treatments:	Lost Time Incidents:	Days Since LTI:
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check			

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	23 degF	Bar. Pressure:	30.1
Wind Speed/Dir:	4 / SE	Wind Gusts:	4

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 29

Report For 04-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):	---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	---
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	AFE (\$)	---
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	Actual (\$)	---
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---
Average ROP (ft/hr):						Job/Well Cost (\$):	---
Drilling Days (act./plan):	25/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	25/38	Days On Location:	29
Pers/Hrs: Operator:	2 / 24	Contractor:	14 / 168	Service:	8 / 96	Other:	0 / 0
				Total:	24 / 288		

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Making up 4-3/4" bit and tools, running in the hole.

Planned Operations: Clean out cement to 8,967'.

Toolpusher: Steve Caldwell, Vince Shaffer

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	13:30	13.50	9,145	3-13	Waited on cement. Cut off casing and laid down cementing equipment. Rigged down casing equipment and unloaded 2-7/8" drill pipe, 4" drill collars and running tools.	
13:30	17:00	3.50	9,145	5-12-2	Performed "Top Squeeze" cement job with Annular closed and pumping through kill line Resource Cementing pumped 25 barrels of H2O ahead to break down formation at 820 psi, followed by 167 barrels of 15.6 ppg Top Squeeze Cement with 200 psi. CIP at 1624 hours.	
17:00	21:30	4.50	9,145	1-14	Nippled down BOPE and removed 9-5/8" casing head.	
21:30	0:00	2.50	9,145	3-97	Weld on well head.	

Management Summary

Cut off 5-1/2" casing and laid down cementing equipment. Performed "Top Squeeze" cement job pumping 25 barrels of water ahead to break down formation at 820 psi, followed by 167 barrels of 15.6 ppg "Top Squeeze" cement with final pressure of 200 psi. CIP at 1624 hours. Nippled down and removed 9-5/8" well head. Cleaned up and welded on 5-1/2" well head.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Mud Information

Mud Information																			Gels		Temp		Mud
%																			10m	30m	In	Out	Loss
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s								
04-Mar-21 14:00 at Depth 9,145 ft Mud Pits																							
8.50	32	5	4	14	1	8.5	2	0	98	0.1		800	320					3	60				

Mud Consumables

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Bicarb - OTHER	49	---	PAlets/Wrap - OTHER	2	---

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
2.875	295	10.4	G-105	OTHER					



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 29

Report For 04-Mar-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	BOPE
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	25 degF	Bar. Pressure:	30.24
Wind Speed/Dir:	9 / E	Wind Gusts:	9

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 30

Report For 05-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	---	---	---	
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---	---	
Average ROP (ft/hr):						Job/Well Cost (\$):			
Drilling Days (act./plan):	26/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	26/38	Days On Location:			30
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	4 / 48	Other:	0 / 0	Total:	20 / 240

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Cleaning out cement at 3,228'.

Planned Operations: Clean out cement to 8,997'.

Toolpusher: Steve Caldwell, Justin Bristol

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	1:30	1.50	9,145	3-97	Weld on 5-1/5" well head.	
1:30	3:30	2.00	9,145	3-97	Flanged up flow line, installed chains on flow nipple, set catwalk and mouse hole.	
3:30	5:30	2.00	9,145	3-97	Rigged up tongs for 2-7/8" drill pipe and tools, strapped drill pipe.	
5:30	8:00	2.50	9,145	4-6-1	Made up bit collars and tools. Ran in the well bore and tagged top of cement at 731'.	
8:00	10:30	2.50	9,145	4-34-1	Picked up 10 stands of drill pipe and stood back in derrick.	
10:30	16:30	6.00	9,145	7-28	Drilled out cement float at 820' and drilled out cement fro 820' to 1709'.	
16:30	17:00	0.50	9,145	SERV	Serviced Rig.	
17:00	21:30	4.50	9,145	10-6-2	Pulled out of the well bore and changed BHA for mud motor and PDC bit. Ran in the hole.	
21:30	0:00	2.50	9,145	7-28	Cleaned out cement from 1709' to 2666'.	

Management Summary

Welded on 5-1/2" well head and flanged up riser pipe, rotating head and flow line. Rigged up tongs and tools. Made up bit, mud motor and tools. Ran in the well bore and tagged top of wiper plug at 731'. Picked up stands and placed them in the derrick. Cleaned out cement from 731' to 2,366' at 2400 hours.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Bit/BHA/Workstring Information

				Depth	This Run		R.O.P.				Mud				Pump						
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF		
15	1	REED	JZ	4.750	731					3	120	1	8	200	1200	70	37	4	61		
Jets: 20 20 20						Out: 1709		Grade: Cutter:		1 / 1		Dull: NO / NO		Wear: A		Brgs: 1		Gge: 1		Pull: OTH	
BHA - No. 17 - BIT, MMTR, XO, 6 DC = 193.27																					

Rig Information

Equipment Problems:

Location Condition:

Transport:

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
2.875	295	10.4	G-105	OTHER					



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 30

Report For 05-Mar-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Tripping
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownamatic Check	

Weather Information

Sky Condition:	Cloudy	Visibility:	10
Air Temperature:	27 degF	Bar. Pressure:	30.12
Wind Speed/Dir:	4 / SW	Wind Gusts:	4

	Daily Drilling Report		Geothermal Resource Group, Inc.																	
	Well ID: Forge 56-32		Job ID: Original																	
	Field: UTAHFORGE		Well Name: 56-32																	
			Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT																	
Report No: 31			Report For 06-Mar-21																	
Operator: University of Utah Rlg: Frontier Spud Date: 08-Feb-21 Daily Cost / Mud (\$): ---																				
Measured Depth (ft): 9145		Last Casing: 5.500 at 9,105		Wellbore: Original Wellbore AFE No. AFE (\$) Actual (\$)																
Vertical Depth (ft): 9138		Next Casing:		RKB Elevation (ft): 30.40 --- --- ---																
Proposed TD (ft): 9000		Last BOP Test: 12-Feb-21		Job Reference RKB (ft): 28.50 --- --- ---																
Hole Made (ft) / Hrs: 0 / 0.0		Next BOP Test:		Working Interest: Totals: --- --- ---																
Average ROP (ft/hr):		Job/Well Cost (\$): ---																		
Drilling Days (act./plan): 27/30		Flat Days (act./plan): 0/8		Total Days (act./plan): 27/38 Days On Location: 31																
Pers/Hrs: Operator: 2 / 24		Contractor: 14 / 168		Service: 4 / 48 Other: 0 / 0 Total: 20 / 240																
Safety Summary: No incidents or events reported. Conducted Safety Meeting.																				
Current Operations: Cleaning out cement at 7,501'.																				
Planned Operations: Clean out cement to 9,030'.																				
Toolpusher: Steve Caldwell, Justin Bristol																				
Wellsite Supervisors: Virgil Welch, Paul Stroud				Tel No.: 7132807438																
Operations Summary																				
From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod														
0:00	2:30	2.50	9,145	3-28	Cleaned out cement from 1,709' to 2,666'.															
2:30	3:30	1.00	9,145	03-051	Swept hole.															
3:30	10:00	6.50	9,145	3-28	Cleaned out cement from 2,666' to 3,700'.															
10:00	10:30	0.50	9,145	SERV	Serviced Rig.															
10:30	0:00	13.50	9,145	3-28	Cleaned out cement from 3,700' to 6,238' at 2400 hours.															
Management Summary																				
Cleaned out cement from 1,709' to 6,238'.																				
Casing/Tubular Information																				
Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)										
FULL	20.000	30	30	129	129	COND														
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30										
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00										
LINER	5.500	0		9,105																
Mud Information																				
%																				
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	Gels	Temp	Mud
																		In	Out	Loss
06-Mar-21 07:00 at Depth 9,145 ft Mud Pits																				
33.00	9			16	1	11	2.4	0	97.6	0.1		850	280					110	105	
Mud Consumables																				
Item Description				Qty.	Cost	Item Description				Qty.	Cost									
Bicarb - OTHER				1	---	Citric Acid - OTHER				3	---									
Gel - OTHER				155	---	SinWeep/AltaVert - OTHER				1	---									
xanthan gum - OTHER				10	---															
Bit/BHA/Workstring Information																				
BHA - No. 17 - BIT, MMTR, XO, 6 DC = 193.27																				
Rig Information																				
Equipment Problems:																				
Location Condition:																				
Transport:																				
Drill Pipe Inventory																				
DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread											
2.875	295	10.4	G-105	OTHER																

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 31

Report For 06-Mar-21

Safety Information

Meetings/Drills	Time	Description
Safety	60	Mouse Hole Connections
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownmatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	30 degF	Bar. Pressure:	29.85
Wind Speed/Dir:	16 / SSW	Wind Gusts:	50

Geothermal Resource Group, Inc.

Well ID: Forge 56-32

Job ID: Original

Well Name: 56-32

Field: UTAHFORGE

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 32

Report For 07-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	---	---	---	
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---	---	
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---	---	
Average ROP (ft/hr):						Job/Well Cost (\$):			
Drilling Days (act./plan):	28/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	28/38	Days On Location:			32
Pers/Hrs:	Operator: 2 / 24	Contractor:	14 / 168	Service:	4 / 48	Other:	0 / 0	Total:	20 / 240

Safety Summary: No incidents or events reported. Conducted Safety Meeting.

Current Operations: Displacing well with fresh water.

Planned Operations:	Displace well bore with treated water and pull out of the hole laying down drill pipe and tools.
----------------------------	--

Toolpusher: Steve Caldwell, Justin Bristol

Wellsite Supervisors: Virgil Welch, Paul Stroud

Tel No.: 7132807438

Operations Summary

From	To	Elapsed	End MD(ft	Code	Operations Description	Non-Prod
0:00	9:00	9.00	9,145	3-28	Cleaned out cement from 6238' to 8072'.	
9:00	9:30	0.50	9,145	3-5-1	Circulated well bore clean.	
9:30	15:00	5.50	9,145	3-28	Cleaned out cement from 8072' to 9034'.	
15:00	16:00	1.00	9,145	3-5-1	Pumped sweep and circulated well bore clean.	
16:00	21:30	5.50	9,145	10-6-2	Pulled out of the hole laying down 4" drill collars and bit.	
21:30	0:00	2.50	9,145	10-6-1	Made up bit, casing scraper, bumper sub and ran in the hole scraping Liner.	

Management Summary

Cleaned out cement from 6,238' to 9,034' and circulated well bore clean. Pulled out of the well bore and laid down 4" drill collars, mud motor and bit. Made up bit, scraper and bumper sub. Ran in the hole scraping 5-1/2" casing.

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Mud Information

																			%				Gels			Temp		Mud
Dens.	Vis	PV	YP	Filt.	Cake	pH/ES	Solids	Oil	Water	Sand	LGS	Cl	Ca	CaCl	10s	10m	30m	In	Out	Loss								
07-Mar-21 05:00 at Depth 9,145 ft Mud Pits																												
8.60	36	13	12	14	1	10.5	2	0	98	0.1		850	320		4	8	12	123	133									

Mud Consumables

Item Description		Qty.	Cost	Item Description		Qty.	Cost
Citric Acid - OTHER		5	---	SAwdust - OTHER		1	---
TorkEase - OTHER		12	---	xanthan gum - OTHER		18	---

Bit/BHA/Workstring Information

				Depth	This Run	R.O.P.				Mud				Pump						
No	Run	Make	Model	Diam	In	Dist	Hrs	Avg	Max	WOB	RPM	Torque	Wt	Flow	Press	J. Vel	P. Drp	HPH	JIF	
16	1	REED	TK53	1,709.	1709	7,345	24.6	298.6	300.0	3	300	2	9	210	3000	37	10	1	34	
Jets: 20 20 20 20 20					Out: 9034		Grade:		Cutter: 0/0		Dull: NO/NO		Wear: A		Brgs: X		Gge: 0		Pull: TD	
BHA - No. 17 - BIT, MMTR, XO, 6 DC = 193.27																				

Rig Information

Equipment Problems:

Location Condition:

Transport:

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Job ID: Original

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 32

Report For 07-Mar-21

Drill Pipe Inventory

DP Size	Joints	Weight	Grade	Thread	DP Size	Joints	Weight	Grade	Thread
2.875	295	10.4	G-105	OTHER					

Safety Information

Meetings/Drills	Time	Description
Safety	60	Laying down drill pipe.
First Aid Treatments:	Medical Treatments:	Lost Time Incidents:
Days Since LTI:		
<input type="checkbox"/> BOP Test	<input type="checkbox"/> Crownmatic Check	

Weather Information

Sky Condition:	Clear	Visibility:	10
Air Temperature:	45 degF	Bar. Pressure:	29.93
Wind Speed/Dir:	10 / S	Wind Gusts:	50

Comments: High winds today and tomorrow.

**Daily Drilling Report**

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 33

Report For 08-Mar-21

Operator:	University of Utah	Rig:	Frontier	Spud Date:	08-Feb-21	Daily Cost / Mud (\$):			---
Measured Depth (ft):	9145	Last Casing:	5.500 at 9,105	Wellbore:	Original Wellbore	AFE No.	AFE (\$)	Actual (\$)	
Vertical Depth (ft):	9138	Next Casing:		RKB Elevation (ft):	30.40	---	---		
Proposed TD (ft):	9000	Last BOP Test:	12-Feb-21	Job Reference RKB (ft):	28.50	---	---		
Hole Made (ft) / Hrs:	0 / 0.0	Next BOP Test:		Working Interest:		Totals:	---		
Average ROP (ft/hr):						Well Cost (\$):			---
Drilling Days (act./plan):	29/30	Flat Days (act./plan):	0/8	Total Days (act./plan):	29/38	Days On Location:			33
Pers/Hrs: Operator:	1 / 12	Contractor:	14 / 12	Service:	0 / 0	Other:	0 / 0	Total:	15 / 24
Safety Summary: No incidents or events reported. Conducted Safety Meeting.									
Current Operations:	Change valves and seats in pumps and replace 5" liners back to 6". Rig down water pump at 58-32 and take to connex. Inventory connex and lock, Rig released at 06:00 on March 9,2021, Pason released at 06:00 on March 9, 2021								
Planned Operations:	Rig has truck coming Thursday to remove top drive and lay over derrick								
Toolpusher:	Steve Caldwell, Justin Bristol								
Wellsite Supervisors:	Virgil Welch					Tel No.: 7132807438			

Operations Summary

From	To	Elapsed	End MD(ft)	Code	Operations Description	Non-Prod
0:00	2:30	2.50	9,145	10-6-1	RIH scraping casing to 8,933'	
2:30	4:30	2.00	9,145	3-3	Wash and Ream from 8,933' to 9,034'	
4:30	5:00	0.50	9,145	3-5-1	Circulate hole clean	
5:00	6:00	1.00	9,145	3-5-1	Displace the mud in the hole with 200 bbl fresh water	
6:00	8:00	2.00	9,145	3-5-1	Displace the water in the hole with 266 bbl Biocide water	
8:00	16:00	8.00	9,145	10-342	POH laying down all 2-7/8" drill pipe	
16:00	16:30	0.50	9,145	10-344	Lay down BHA	
16:30	18:00	1.50	9,145	1-14	Remove flow line and cut casing at ground level, separate cross over spools, load out 3rd truck of rental tools and 4th truck w/ motors to Casper	
18:00	22:00	4.00	9,145	WELLHD	Weld on wellhead and install master valve. Weld on weldolet and install threaded valve	
22:00	0:00	2.00	9,145	3-97	Clean pits	

Management Summary

Circulate hole clean,
 Displace the mud in the hole with 200 bbl fresh water,
 Displace the water in the hole with 266 bbl Biocide water,
 POH laying down all 2-7/8" drill pipe,
 Lay down BHA, Remove flow line and cut casing at ground level, separate cross over spools, load out 3rd truck of rental tools and 4th truck w/ motors to Casper,
 Weld on wellhead and install master valve.
 Weld on wellhead and install threaded valve,
 Clean pits

Casing/Tubular Information

Type	Size (ins)	Top MD (ft)	Top TVD (ft)	Bottom MD (ft)	Bottom TVD (ft)	Hole Section	OH Diam. (ins)	Nom. Wgt. (lbs)	Nominal Grade	LOT (lbs/gal)
FULL	20.000	30	30	129	129	COND				
FULL	13.375	0	0	382	382	SURF	17.500	55	J-55	16.30
FULL	9.625	0	0	3,494	3,488	INT1	12.250	36	J-55	16.00
LINER	5.500	0		9,105						

Rig Information

Equipment Problems:

Location Condition:

Transport:

Safety Information

Meetings/Drills

Time

Description

Safety 30 LDDP

First Aid Treatments:

Medical Treatments:

Lost Time Incidents:

Days Since LTI:

☐ BOP Test☐ Crowmamic Check



Daily Drilling Report

Well ID: Forge 56-32

Field: UTAHFORGE

Geothermal Resource Group, Inc.

Well Name: 56-32

Sect: 32 Town: 26S Rng: 9W County: Beaver State: UT

Report No: 33

Report For 08-Mar-21

Weather Information

Sky Condition:	clear	Visibility:	10
Air Temperature:	46 degF	Bar. Pressure:	29.91
Wind Speed/Dir:	21 / S	Wind Gusts:	

This page left blank

DISTRIBUTION

Email—Internal

Name	Org.	Sandia Email Address
Erik K. Webb	08910	ekwebb@sandia.gov
Doug A. Blankenship	08930	dablank@sandia.gov
Giorgia Bettin	08916	gbettin@sandia.gov
David W. Raymond	08916	dwrapmo@sandia.gov
Giann Su	08916	jsu@sandia.gov
Melanie Brianna Schneider	08916	mbschne@sandia.gov
Steve Buerger	06530	sbuerge@sandia.gov
Technical Library	01977	sanddocs@sandia.gov

Email—External

Name	Company Email Address	Company Name
Lauren W. Boyd	Lauren.Boyd@ee.doe.gov	DOE/EERE/GTO
Alexis McKittrick	Alexis.McKittrick@ee.doe.gov	DOE/EERE/GTO
Angel Nieto	angel.nieto@ee.doe.gov	DOE/EERE/GTO
Kevin Jones	kevin.jones1@ee.doe.gov	DOE/EERE/GTO
Joseph Moore	jmoore@egi.utah.edu	Energy & Geoscience Institute
John McLennan	jmclennan@egi.utah.edu	EGI/University of Utah
Fred Dupriest	fred.dupriest@tamu.edu	Texas A&M University
Samuel F. Noynaert	noynaert@tamu.edu	Texas A&M University
Tom Roberts	Tom.Roberts@nov.com	NOV
Aaron Schen	Aaron.Schen@nov.com	NOV
Matt Stevenson	Matt.Stevenson@nov.com	NOV
Derek Nelson	DNelson4@slb.com	Smith International
Jordan Self	jself@ulterra.com	Ulterra
Geir Hareland	geir.hareland@okstate.edu	OSU
Mohammed Al Dushaishi	m.aldushaishi@okstate.edu	OSU
Andrew Pauli	Andrew.Pauli@bakerhughes.com	Baker Hughes

Hardcopy—Internal

Number of Copies	Name	Org.	Mailstop
2	David W. Raymond	08916	1033



Sandia
National
Laboratories

Sandia National Laboratories is a multimission laboratory managed and operated by National Technology & Engineering Solutions of Sandia LLC, a wholly owned subsidiary of Honeywell International Inc. for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525.