DISTRIBUTION SHEET

To	From	Page 1 of 2
Distribution	Characterization Support	Date 03-08-95
Project Title/Work Order		EDT No. 610021
Tank 241-SX-106 Tank Characterization Plan (WHC-SD-WM-TP-314		ECN No.

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
ONSITE					
DOE-RL					
C. A. Babel	S7-54	X			
J. M. Clark	S7-54	X			
W. Liou	S7-54	X			
J. F. Thompson	S7-54	X			
N. W. Willis	S7-54	X			
MACTEC					
J. P. Haney	S7-73	X			
D. R. Lincoln	S7-73	X			
J. A. Sheriff	B1-42	X			
Pacific Northwest Laboratories					
B. O. Barnes	P7-14	X			
S. F. Bobrowski	K7-28	X			
J. A. Edwards	P8-08	X			
J. S. Fruchter	K6-96	X			
S. C. Goheen	P8-08	X			
M. W. Ligotke	P7-59	X			
K. L. Silvers	P7-27	X			
Westinghouse Hanford Company					
C. H. Brevick	G7-56	X			
D. R. Carls	R3-01	X			
R. J. Cash	S7-15	X			
S. J. Eberlein	R2-12	X			
D. L. Edwards	S3-90	X			
G. D. Forehand	S7-31	X			
H. Y. Fouad	S1-57	X			
D. J. Green	S7-04	X			
V. W. Hall	H4-19	X			
C. S. Homi	R2-12	X			
W. J. Kennedy	S5-03	X			
J. G. Kristofzski	T6-06	X			
T. J. Kunthara	G7-56	X			
R. D. Mahon	S3-90	X			
J. E. Meacham	S7-15	X			
P. M. Morant	H4-19	X			

ONSITE (cont.)

E. H. Neilsen	S7-12	X
A. D. Olguin	S7-04	X
J. W. Osborne	S7-15	X
P. Sathyanarayana (2)	R2-12	X
R. D. Schreiber (2)	R2-12	X
C. L. Thomas	H4-19	X
T. C. Trible	S1-57	X
R. S. Viswanath	S3-90	X
M. D. Webb	H4-25	X
R. Westberg	S3-90	X
Central Files (2)	L8-04	X
O.S.T.I. (2)	L8-07	X

RECEIVED
MAR 27 1995
OSTI

OFFSITE

U.S. Department of Energy - Headquarters
Office of Environmental Restoration
and Waste Management EM-563
12800 Middlebrook Road
Germantown, MD 20874

K. T. Lang	X
J. A. Poppitti	X

Oak Ridge National Laboratory
Post Office Box 2008
Oak Ridge, TN 37831-6120

R. A. Jenkins	X
A. D. Dindal	X

Los Alamos Technical Associates
750 Swift, Suite 14
Richland, WA 99352

A. T. Dicenso	X
C. J. Lindquist	X
G. P. Westleigh	X
T. T. Tran	X

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

5 dto .4

MAR 08 1995

ENGINEERING DATA TRANSMITTAL

1. EDT 610021

2. To: (Receiving Organization) SAMPLING AND MOBILE LABORATORIES	3. From: (Originating Organization) TWRS/CHARACTERIZATION SUPPORT	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: TWRS ENG/CHAR SUPPORT	6. Cog. Engr.: C. S. HOMI	7. Purchase Order No.: N/A
8. Originator Remarks: N/A		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: 2750E/200E
11. Receiver Remarks:		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: 03/08/95

15. DATA TRANSMITTED

(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition
1	WHC-SD-WM-TP-314		0	TANK 241-SX-106 TANK CHARACTERIZATION PLAN	Q	1	1	

16. KEY

Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.
1	1	Cog.Eng. C. S. HOMI	C S Homi	3/7/95		Proj. J. W. OSBORNE	[signature]	3/8/95		1	1
1	1	Cog. Mgr. S. J. EBERLEIN	S J Eberlein	3/7/95		Proj. D. L. EDWARDS	D L Edwards	3/8/95		1	1
1	1	QA H. Y. FOUAD	H. Fouad	3/8/95		Proj. S. C. GOHEEN	See attached sheet			1	
		Safety				Proj. R. A. JENKINS	See attached sheet			1	
		Env.									

18.	19.	20.	21. DOE APPROVAL (if required)
C. S. HOMI C S Homi 3/7/95 Signature of EDT Originator Date	D. L. EDWARDS D L Edwards 3/8/95 Authorized Representative for Receiving Organization Date	S. J. EBERLEIN S J Eberlein 3-7-95 Cognizant Manager Date	Ctrl. No. [] Approved [] Approved w/comments [] Disapproved w/comments

BD-7400-172-2 (04/94) GEF097

ENGINEERING DATA TRANSMITTAL

1. EDT 610021

2. To: (Receiving Organization) SAMPLING AND MOBILE LABORATORIES	3. From: (Originating Organization) TWRS/CHARACTERIZATION SUPPORT	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: TWRS ENG/CHAR SUPPORT	6. Cog. Engr.: C. S. HOMI	7. Purchase Order No.: N/A
8. Originator Remarks: N/A		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: 2750E/200E
11. Receiver Remarks:		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: 03/08/95

15. DATA TRANSMITTED

(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition
1	WHC-SD-WM-TP-314		0	TANK 241-SX-106 TANK CHARACTERIZATION PLAN	Q	1	1	

16. KEY

Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.
1	1	Cog.Eng. C. S. HOMI	[signature]	3/7/95		Proj. J. W. OSBORNE				1	
1	1	Cog. Mgr. S. J. EBERLEIN	[signature]	3/7/95		Proj. D. L. EDWARDS				1	
1		QA K. Y. FOJAD				Proj. S. D. GOHEEN	[signature]		/FOR SCG	1	1
		Safety				Proj. R. A. JENKINS				1	
		Env.									

18.	19.	20.	21. DOE APPROVAL (if required)
C. S. HOMI [signature] 3/7/95 Signature of EDT Originator Date	D. L. EDWARDS Authorized Representative for Receiving Organization Date	S. J. EBERLEIN [signature] 3-7-95 Cognizant Manager Date	Ctrl. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments

ENGINEERING DATA TRANSMITTAL

Page 3 of 3

1. EDT 610021

2. To: (Receiving Organization) SAMPLING AND MOBILE LABORATORIES	3. From: (Originating Organization) TWRS/CHARACTERIZATION SUPPORT	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: TWRS ENG/CHAR SUPPORT	6. Cog. Engr.: C. S. HOMI	7. Purchase Order No.: N/A
8. Originator Remarks: N/A		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: 2750E/200E
11. Receiver Remarks:		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: 03/08/95

15. DATA TRANSMITTED

(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition
1	WHC-SD-WM-TP-314		0	TANK 241-SX-108 TANK CHARACTERIZATION PLAN	Q	1	1	

16. KEY

Approval Designator (F)	Reason for Transmittal (G)		Disposition (H) & (I)	
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval	4. Review	1. Approved	4. Reviewed no/comment
	2. Release	5. Post-Review	2. Approved w/comment	5. Reviewed w/comment
	3. Information	6. Dist. (Receipt Acknow. Required)	3. Disapproved w/comment	6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.
1	1	Cog.Eng. C. S. HOMI		3/7/95		Proj. J. W. OSBORNE				1	
1	1	Cog. Mgr. S. J. EBERLEIN		3/7/95		Proj. D. L. EDWARDS				1	
1		QA H. Y. FOUAD				Proj. S. C. GONEEN				1	
		Safety				Proj. R. A. JENKINS		3/8/95		1	1
		Env.									

18.	19.	20.	21. DOE APPROVAL (if required)
C. S. HOMI 3/7/95 Signature of EDT Originator Date	D. L. EDWARDS Authorized Representative for Receiving Organization Date	S. J. EBERLEIN 3-7-95 Cognizant Manager Date	Ctrl. No. [] Approved [] Approved w/comments [] Disapproved w/comments

BD-7400-172-2 (06/96) GEF097

RELEASE AUTHORIZATION

Document Number:	WHC-SD-WM-TP-314, REV 0
Document Title:	TANK 241-SX-106 TANK CHARACTERIZATION PLAN
Release Date:	3/8/95

This document was reviewed following the procedures described in WHC-CM-3-4 and is:

APPROVED FOR PUBLIC RELEASE

WHC Information Release Administration Specialist:

Kara M. Broz

March 8, 1995

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy. Available in paper copy and microfiche. Printed in the United States of America. Available to the U.S. Department of Energy and its contractors from:

U.S. Department of Energy
Office of Scientific and Technical Information (OSTI)
P.O. Box 62
Oak Ridge, TN 37831
Telephone: (615) 576-8401

Available to the public from: U.S. Department of Commerce
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Telephone: (703) 487-4650

SUPPORTING DOCUMENT

1. Total Pages 29

2. Title	3. Number	4. Rev No.
TANK 241-SX-106 TANK CHARACTERIZATION PLAN	WHC-SD-WM-TP-314	0

5. Key Words

CHARACTERIZATION, DQO, HEALTH AND SAFETY VAPOR ISSUE, FLAMMABLE, ORGANIC, QUALITY CONTROL, SINGLE-SHELL TANK, VAPOR SAMPLING, ANALYSIS, TANK CHARACTERIZATION PLAN

6. Author

Name: C. S. HOMI

Signature 3/7/95

Organization/Charge Code 71520/N4168

7. Abstract

This document is a plan which serves as the contractual agreement between the Characterization Program, Sampling Operations, Oak Ridge National Laboratory, and PNL tank vapor program. The scope of this plan is to provide guidance for the sampling and analysis of vapor samples from tank 241-SX-106.

8. RELEASE STAMP

OFFICIAL RELEASE BY WHC (5)
DATE MAR 08 1995

Tank 241-SX-106 Tank Characterization Plan

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

Prepared for the U.S. Department of Energy
Office of Environmental Restoration
and Waste Management

by

Los Alamos Technical Associates
8633 Gage Boulevard
Kennewick, Washington 99336

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

1.0 INTRODUCTION 1

2.0 DATA QUALITY OBJECTIVES APPLICABLE TO TANK SX-106 1
2.1 SAFETY SCREENING DATA QUALITY OBJECTIVES 1
2.2 WASTE COMPATIBILITY DATA QUALITY OBJECTIVES 2
2.3 WATCH LIST DATA QUALITY OBJECTIVES 2
2.4 FUGITIVE VAPOR EMISSION DATA QUALITY OBJECTIVES 2

3.0 TANK SX-106 HISTORICAL INFORMATION 3
3.1 FEBRUARY 1995 TANK STATUS 3
3.2 TANK CONFIGURATION 3
3.3 TANK HISTORY 4
3.4 ESTIMATED TANK CONTENTS 4

4.0 STRATEGY FOR WASTE CHARACTERIZATION AND SAFETY ISSUE RESOLUTION 7
4.1 TANK SX-106 SCHEDULED SAMPLING EVENTS 7

5.0 REFERENCES 8

APPENDIX . . . . . A-i

LIST OF FIGURES

Figure 1: Tank SX-106 Fill History 5

LIST OF TABLES

Table 1: Tank SX-106 Estimated Solid Compositions 6
Table 2: Integrated DQO Requirements 7

LIST OF ABBREVIATIONS

EB	Evaporator Bottoms
DNFSB	Defense Nuclear Facilities Safety Board
DOE	Department of Energy
DQO	Data Quality Objective
DST	Double-Shell Tank
HTCE	Historical Tank Content Estimate
NCPLX	Non-complexed Waste
R	REDOX high-level waste
RCRA	Resource Conservation and Recovery Act
REDOX	S Plant
RIX	REDOX ion exchange waste
SST	Single-Shell Tank
SX-106	241-SX-106
TCP	Tank Characterization Plan
TLM	Tank Layering Model
TOC	Total Organic Carbon
TPA	Federal Facility Agreement and Consent Order (Tri-Party Agreement)
USQ	Unreviewed Safety Question
WHC	Westinghouse Hanford Company

1.0 INTRODUCTION

The Defense Nuclear Facilities Safety Board (DNFSB) has advised the Department of Energy (DOE) to concentrate the near-term sampling and analysis activities on the identification and resolution of safety issues (Conway 1993). The data quality objective (DQO) process was chosen as a tool to be used to identify the sampling and analytical needs for the resolution of safety issues. As a result, a revision in the Federal Facility Agreement and Consent Order (Tri-Party Agreement or TPA) milestone M-44 has been made, which states that "A Tank Characterization Plan (TCP) will also be developed for each double-shell tank (DST) and single-shell tank (SST) using the DQO process . . . Development of TCPs by the DQO process is intended to allow users (e.g., Hanford Facility user groups, regulators) to ensure their needs will be met and that resources are devoted to gaining only necessary information." This document satisfies that requirement for tank 241-SX-106 (SX-106) sampling activities.

2.0 DATA QUALITY OBJECTIVES APPLICABLE TO TANK SX-106

The sampling and analytical needs associated with the 177 single-shell and double-shell underground storage tanks have been identified through the DQO process. DQOs identify information needed by a program group concerned with safety issues, regulatory requirements, or the transporting and processing of tank waste. Present characterization objectives for fiscal year 1995 involve sampling of tanks to resolve safety issues. Other samples may be requested for ongoing waste processing and regulatory requirements in active tanks. As of February 1995, the DQOs that may apply to tank SX-106 are discussed in the following sections.

Both Watch List and non-Watch List tanks will be sampled and evaluated to classify the waste tanks into one of three categories: SAFE, CONDITIONALLY SAFE, or UNSAFE. A tank can be removed from a Watch List if it is classified as SAFE. The Watch List and other safety issue DQOs identify the requirements used to determine which classification to place a tank, based on analyses that indicate if certain measures are above or below established thresholds. The measures begin with the determination of the concentration of primary analytes which have been considered indicators of potentially unsafe conditions within a tank. If a specific criteria level on one of these items is exceeded, further analysis and a possible change in tank classification may be required.

2.1 SAFETY SCREENING DATA QUALITY OBJECTIVES

The *Tank Safety Screening Data Quality Objective* (Babad and Redus 1994) describes the sampling and analytical requirements that are used to screen waste tanks for unidentified safety issues. To meet the sampling requirements of this DQO effort, a vertical profile of the waste shall be obtained from at least two widely-spaced risers. This vertical profile may be realized using core, auger, or grab samples. The primary analytical requirements for the safety screening of a tank are energetics, total alpha activity, moisture, and flammable gas concentrations. The safety screening analyses shall be applied to all core samples, DST Resource Conservation and Recovery Act (RCRA) samples, and all auger samples, except auger samples taken exclusively to assess the flammable gas tank crust burn issue.

2.2 WASTE COMPATIBILITY DATA QUALITY OBJECTIVES

The *Data Quality Objectives for the Waste Compatibility Program* (Carothers 1994) identified four safety-related decision elements, criticality, flammable gas accumulation, energetics, and corrosivity, needed to determine potential incompatibility of wastes that may occur from routine waste transfers into and within a DST. A routine transfer has the appropriate historical data necessary for the Waste Compatibility Program to determine the acceptability of the transfer from an engineering process control perspective.

Four operations-related decision elements have been identified for a non-routine transfer: separation of transuranic from non-transuranic waste, limits on heat generation, segregation of complexant waste, and ensuring pumping system capabilities. A non-routine transfer includes waste that has unique chemical and/or physical properties for which no historical data exist to judge compatibility with safety and operations decision rules.

2.3 WATCH LIST DATA QUALITY OBJECTIVES

Based on the current classification of the tank, the Watch List DQOs applicable to tank SX-106 are: *Data Quality Objective to Support Resolution of the Organic Fuel Rich Tank Safety Issue* (Babad et al. 1994) and *Flammable Gas Safety Program: Data Requirements for the Flammable Gas Safety Issue Developed through the Data Quality Objectives (DQO) Process* (McDuffie and Johnson 1994).

The sampling requirements of the organic fuel rich DQO effort are for a minimum of two widely spaced core samples. The primary analyses employed are organic carbon, presence of a free organic liquid phase, moisture content, and tank temperature. Additional analyses, if needed, include major organic species, certain oxidizing agents, hydroxide level, or radiochemical species.

The flammable gas DQO effort focuses on DSTs that contain or may contain, based on safety screening, flammable gases above the established decision thresholds. Data from core samples are needed to provide an understanding of the mechanisms for gas generation, conditions which cause gas retention, the source terms for dose consequence calculations, and to support tank behavior models needed to 1) develop mitigation methods and 2) make appropriate safety analysis decisions on future operations to prevent the creation of additional flammable gas tanks. In order to achieve these objectives, a multitude of chemical and radionuclide composition and physical property analyses are needed along with supporting operational data. The most reliable information can be obtained from one complete core.

2.4 FUGITIVE VAPOR EMISSION DATA QUALITY OBJECTIVES

DQOs concerned with fugitive vapor emissions from tank SX-106 are: *Data Quality Objectives for Generic In-Tank Health and Safety Vapor Issue Resolution* (Osborne et al. 1994) and *Rotary Sampling Core Vapor Sampling Data Quality Objective* (Price 1994). Characterization of the tank headspace is needed to: 1) identify those tanks which can be sampled safely with intrusive equipment without risk of gas ignition; 2) identify and estimate concentrations of toxicologically significant compounds present in the tank headspace to establish worker safety precautions; and 3) support the startup and operation of the portable exhauster used during rotary-mode core sampling.

Data are needed to identify and quantify constituents of the tank headspaces to address potential vapor flammability and toxicity. The resolution of these two issues involves a sequence of sampling events. The first step is a qualitative assessment of a tank's headspace vapor flammability. Following resolution of the flammability issue, tank headspace samples will be taken to assess vapor toxicity. Samples are removed from a single location at or near the midpoint of the tank's headspace. Tanks that are actively ventilated will have samples removed at the exhaust header.

Tank SX-106 is one of the 36 tanks on the "Suspect Tank List" (Osborne and Huckaby 1994b). This list is composed of 20 Ferrocyanide Watch List tanks, 9 Organic Watch List tanks (one of which is also on the Ferrocyanide Watch List), and 8 tanks with a history of vapor incidents.

3.0 TANK SX-106 HISTORICAL INFORMATION

This section summarizes the available information on tank SX-106. Included are the present status and physical description of the tank, its age, process history, and the estimated contents of the tank based on historical information. The fill history information is available in *A History of the 200 Area Tank Farms* (Anderson 1990) and *Historical Tank Content Estimate for the Southwest Quadrant of the Hanford 200 West Area* (Brevick et al. 1994).

3.1 FEBRUARY 1995 TANK STATUS

Tank SX-106, currently categorized as sound in structural integrity, was officially added to the Flammable Gas and the Organic Watch Lists in January 1991. The tank has an Unreviewed Safety Question (USQ) because of the potential consequences of a radiological release resulting from a flammable gas burn. An organic content level of 14.6 wt %, a total organic carbon (TOC) level of 4.3 wt % (dry wt % basis) and a waste moisture content of 84.7 wt % H_2O are listed for tank SX-106 (Hanlon 1994).

The tank waste temperature is monitored manually and on a weekly basis. The highest waste temperature reading taken on November 2, 1994, from riser #16, was 47.8 °C (118 °F), which did not exceed the maximum temperature criteria (Hanlon 1994). The highest temperature taken on February 13, 1995, obtained from Tank Farm Surveillance, is 42.8 °C (109 °F).

This tank contains non-complexed waste (NCPLX) with a total waste volume of 2,040 kL (538 kgal), which is equivalent to 479 cm (189 in) of waste as measured from the baseline of the tank. The surface level is read on a daily basis with an ENRAF gauge located on riser #3. The surface level reading for tank SX-106 as of February 21, 1995 is 506.7 cm (199.5 in). The waste is comprised 45 kL (12 kgal) of sludge and 230 kL (61 kgal) of supernatant liquid, and 1,760 kL (465 kgal) of saltcake. A portion of the waste volume, 734 kL (194 kgal), is considered as drainable interstitial liquid (Hanlon 1994).

3.2 TANK CONFIGURATION

Tank SX-106 is one of fifteen single-shell tanks in the 200 West Area SX Farm. It is 23 m (75 ft) in diameter and 9.4 m (31 ft) in operating depth. It has a concave-shaped base and an operating capacity of 3,800 kL (1,000 kgal). The tank has six

active dry wells monitoring radiation in the surrounding soil (Hanlon 1994). It has an operating exhauster and is actively ventilated. Tank SX-106 is the third tank in a cascade flow series consisting also of tanks 241-SX-104 and 241-SX-105 (Brevick et al. 1994).

3.3 TANK HISTORY

Tank SX-106 was constructed and put into service in 1954. It was filled with REDOX high-level waste (R) from the third quarter of 1954 until the fourth quarter of 1971. From 1972 through 1974, the tank received evaporator bottoms (EB) and REDOX ion exchange waste (RIX). During the period from 1974 to 1980, a mixture of several different types of waste was added to and transferred from tank SX-106. Several thousands of gallons of solids were also deposited in the tank. However, because of the wide array of waste types transferred to and from the tank, it is difficult to determine the make-up of these solids.

Tank SX-106 was labeled inactive and was removed from service in 1980. It was partially isolated in 1985. The tank level was adjusted in December 1979 and October 1980. The last solids volume update was obtained on October 28, 1980 and the last photo was taken on June 1, 1989 (Hanlon 1994). Figure 1 gives a summary of the fill history of tank SX-106 from 1954 through 1993 (Brevick et al. 1994). Although from the assembled photographs it appears that tank SX-106 contains mostly liquid with a thin layer of floating solid salt at the surface, the fill history indicates that the tank contains mostly solid materials. It is possible that the tank contains only a very small quantity of liquid or that it contains evaporator bottoms which were often classified as solid.

3.4 ESTIMATED TANK CONTENTS

Based on its fill history, tank SX-106 is expected to contain several layers of waste (Hill et al. 1990). The bottom-most and also the thinnest layer, from transfers dating through February 1974, should contain R, EB, and RIX wastes. The next layer, which is slightly higher in quantity, should contain coating, ion exchange, EB, B-Plant low-level, laboratory, PUREX low-level, RIX, R, N-Reactor, decontamination, and Battelle Pacific Northwest Laboratories wastes. These wastes originated from transfers dating through January 1976. The next layer, with a considerably larger amount of waste from transfers through February 1978, is classified as complexant concentrate. The top-most layer, which is the largest in quantity relative to the other layers, is classified as non-complexed waste, partial neutralized waste, and complexed waste. This layer includes wastes resulting from transfers through April 1980.

A list of chemical constituents of the waste in tank SX-106 (Brevick et al. 1994), based on the Tank Layering Model (TLM), is given in the second column of Table 1. Although the TOC content of tank SX-106, as obtained from the Historical Tank Content Estimates (HTCE) (Brevick et al. 1994), is listed in the table as 0.16 wt % (wet basis), Turner (1994) reports a higher laboratory measurement of 5.96 wt % TOC (wet basis) for a tank SX-106 supernate sample. In addition, the TRAC data set yields an estimate of 5.02 wt % TOC (dry basis). Development and refinement of the TLM which is the basis of the HTCE is continuing. At this point, the uncertainty of the TLM estimates is unknown.

Figure 1: Tank SX-106 Fill History



Table 1: Tank SX-106 Estimated Solid Compositions[1]

Physical Properties	
Total solid waste	3.38E+06 kg (477 kgal)
Heat load	3.42 kW (1.17E+04 BTU/hr)
Bulk density	1.87 (g/cc)
Void Fraction	0.26
Water wt %	5.85
TOC wt % C(wet)	0.16
Analyte	**Solid Concentration[2] (μg/g)**
Na^+	2.22E+05
Al^{3+}	3.77E+04
Fe^{3+}	3.54E+01
Cr^{3+}	2.25E+02
Ni^{2+}	3.30E+01
Mn^{4+}	8.35E+02
K^+	8.95E+02
OH^-	8.57E+04
NO_3^-	3.65E+05
NO_2^-	1.60E+04
CO_3^{2-}	3.32E+04
PO_4^{3-}	1.66E+04
SO_4^{2-}	4.27E+04
F^-	5.14E+03
U	5.47E+03
Cl^-	7.28E+02
$C_6H_5O_7^{3-}$	2.20E+03
$HEDTA^{-3}$	3.77
$glycolate^-$	1.48E+03
$acetate^-$	7.39E+02
Radiological Constituents	**Solid Concentration (μCi/g)**
$^{239/240}Pu$	1.39E-03
^{137}Cs	2.04E+02
^{90}Sr	8.06

[1](Brevick et al. 1994)
[2]Composite inventory excludes supernatant, diatomaceous earth, and cement.

4.0 STRATEGY FOR WASTE CHARACTERIZATION AND SAFETY ISSUE RESOLUTION

In this section, the DQO requirements for sampling and analysis are integrated and compared with scheduled sampling and analysis activities.

4.1 TANK SX-106 SCHEDULED SAMPLING EVENTS

Several sampling events of tank SX-106 are scheduled: two vapor sampling events in May 1995 and February 1996, a grab sampling event in August 1995, and a rotary sampling event in September 1996. No other sampling is scheduled through fiscal year 1997 (Stanton 1994).

The headspace vapor sampling events shall be performed in accordance with the two DQOs dealing with fugitive vapor emissions: *Data Quality Objectives for Generic In-Tank Health and Safety Vapor Issue Resolution* (Osborne et al. 1994) and *Rotary Sampling Core Vapor Sampling Data Quality Objective* (Price 1994). The grab sampling shall be performed in accordance with the *Data Quality Objectives for the Waste Compatibility Program* (Carothers 1994). The rotary sampling shall be conducted following *Tank Safety Screening Data Quality Objective* (Babad and Redus 1994), *Flammable Gas Safety Program: Data Requirements for the Flammable Gas Safety Issue Developed through the Data Quality Objectives (DQO) Process* (McDuffie and Johnson 1994), and *Data Quality Objective to Support Resolution of the Organic Fuel Rich Tank Safety Issue* (Babad et al. 1994). These sampling and analysis events, if successful, will also satisfy the February 1995 applicable DQO requirements. These requirements are summarized in Table 2. A more complete list of analytical requirements is given, as an appended revision, in the appropriate sampling and analysis plan.

Table 2: Integrated DQO Requirements

Sampling Event	Applicable DQO	Sampling Requirements	Analytical Requirements
Vapor Sampling	-Health & Safety Vapor Issue Resolution DQO -Rotary Sampling Core Vapor Sampling DQO	3 SUMMA® canisters 12 Triple Sorbent Traps 6 Sorbent Trap Systems	Gas Flammability Gas Toxicity -Organic Vapors -Permanent Gases
Rotary Sampling	-Safety Screening DQO -Organic DQO -Flammable Gas DQO	2 cores from risers separated radially to the maximum extent possible	Energetics, TOC, Total Alpha, Moisture, Gas Composition, Major Anions & Cations, Radionuclides, Primary Organics & Organic Products, Physical Properties
Grab Sampling	-Compatibility DQO	3 grab samples	Energetics, Moisture, Major Anions, Cations & Radionuclides, SpG & pH, Separable Organics

SUMMA is a Registered Trademark of Oregon Graduate Institute

5.0 REFERENCES

Anderson, J. D., 1990, *A History of the 200 Area Tank Farms*, WHC-MR-0132, Rev. 0 Westinghouse Hanford Company, Richland, Washington.

Babad, H., S. M. Blacker, K. S. Redus, 1994, *Data Quality Objective to Support Resolution of the Organic Fuel Rich Tank Safety Issue*, WHC-SD-WM-DQO-006, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Babad, H., and K. S. Redus, 1994, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Westinghouse Hanford Company, Richland, Washington.

Brevick, C. H., Gaddis, L. A., and Pickett, W. W., 1994, *Historical Tank Content Estimate for the Southwest Quadrant of the Hanford 200 West Areas*, WHC-SD-WM-ER-352, Rev. 0, ICF Kaiser Hanford Company, Richland, Washington.

Carothers, K. G., 1994, *Data Quality Objectives for the Waste Compatibility Program*, WHC-SD-WM-DQO-001, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Conway, J. T., Letter to H. R. O'Leary, DOE, "DNFSB Recommendation 93-5 to the Secretary of Energy," 9400070, dated July 19, 1993.

Hanlon, B. M., 1994, *Waste Tank Summary for Month Ending October 31, 1994*, WHC-EP-0182-79, Westinghouse Hanford Company, Richland, Washington.

Hill, J. G., W. I., Winters, B. C. Simpson, J. W. Buck, P. J. Chamberlain, V. L. Hunter, 1991, *Waste Characterization Plan for the Hanford Site Single-Shell Tanks*, WHC-EP-0210, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

McDuffie, N. G., and Johnson, G. D., 1994, *Flammable Gas Tank Safety Program: Data Requirements for Core Sample Analysis Developed through the Data Quality Objectives (DQO) Process*, WHC-SD-WM-DQO-004, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Osborne, J. W., J. L. Huckaby, E. R. Hewitt, C. M. Anderson, D. D. Mahlum, B. A. Pulsipher, J. Y. Young, 1994, *Data Quality Objectives for Generic In-Tank Health and Safety Vapor Issue Resolution*, WHC-SD-WM-DQO-002, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Osborne, J. W., and J. L. Huckaby, 1994b, *Program Plan for the Resolution of Tank Vapor Issues*, WHC-EP-0562, Rev. 1, May 1994, Westinghouse Hanford Company, Richland, Washington.

Price, D. N., 1994, *Rotary Core Vapor Sampling Data Quality Objective*, WHC-SD-WM-SP-003, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Stanton, G. A., 1994, *Baseline Sampling Schedule*, Revision 3, (internal memo 7R320-94-03, to distribution, September 22), Westinghouse Hanford Company, Richland, Washington.

Turner, D. A., 1994, *Revision of the Organic Tanks Watch List*, (Letter 9453328 to R. E. Gerton, May 13), Westinghouse Hanford Company, Richland, Washington.

APPENDIX A

TANK SX-106
VAPOR SAMPLING AND ANALYSIS PLAN
FOR FISCAL YEAR 1995

TABLE OF CONTENTS FOR APPENDIX A

A1.0 INTRODUCTION A-1

A2.0 SAMPLING AND ANALYSIS SCHEME A-1
A2.1 VAPOR SAMPLING EVENT A-1
A2.1.1 Flammability Test A-1
A2.1.2 Sample Collection Using SUMMA® Canisters And Sorbent Tubes . . A-2
A2.1.3 Radiation Screening and Sample Transport A-4
A2.2 LABORATORY ANALYSIS A-5
A2.2.1 Preparation of Sample Media Containers A-5
A2.2.2 Sample Analysis A-5
A2.2.3 Insufficient Samples A-5

A3.0 QUALITY ASSURANCE & QUALITY CONTROL A-8
A3.1 SAMPLING OPERATIONS A-8
A3.2 LABORATORY OPERATIONS A-9

A4.0 ORGANIZATION A-10

A5.0 EXCEPTIONS, CLARIFICATIONS, AND ASSUMPTIONS A-11

A6.0 DELIVERABLES A-11
A6.1 FORMAT I REPORTING A-12
A6.2 FORMAT II REPORTING A-12
A6.3 FORMAT VI REPORTING A-12

A7.0 CHANGE CONTROL A-14

A8.0 REFERENCES A-15

LIST OF TABLES FOR APPENDIX A

Table A-1: General Sampling Information for Tank SX-106 . . . . . A-2
Table A-2: List of Samples and Activities for Tank SX-106. . . . . A-3
Table A-3: Limits For Acceptable Radionuclide Activity Levels. A-4
Table A-4: SX-106 Sample Chemical, Physical, and Radiological Analytical Requirements A-7
Table A-5: Tank SX-106 Project Key Personnel List. A-10

LIST OF FIGURES FOR APPENDIX A

Figure A-1: Test Plan Outline and Flowchart for Tank Vapor Space Characterization. A-6

LIST OF ACRONYMS FOR APPENDIX A

BEL	Biological Exposure Limit
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act of 1980
CES	Consensus Exposure Standards
CGM	Combustible Gas Meter
DOE	Department of Energy
DOT	Department of Transportation
DQO	Data Quality Objective
ECN	Engineering Change Notice
EPA	Environmental Protection Agency
ESH&QA	Environmental Safety, Health, and Quality Assurance
FAS	Field Analytical Services
GC/MS	Gas Chromatography/Mass Spectrometry
HEPA	High-Efficiency Particulate Air Filters
IC	Ion Chromatography
IDLH	Immediately Dangerous to Life and Health
LFL	Lower Flammability Limit
OGIST	Oregon Graduate Institute of Science and Technology
ORNL	Oak Ridge National Laboratory
PEL	Permissible Exposure Limit
PNL	Pacific Northwest Laboratory
ppbv	parts per billion by volume
ppmv	parts per million by volume
QAPP	Quality Assurance Project Plan
RCRA	Resource Conservation and Recovery Act
REL	Recommended Exposure Limit
SAP	Sampling and Analysis Plan
SML	Sampling and Mobile Laboratories
SUMMA®	registered trademark for passivated stainless steel canister of the Oregon Graduate Institute of Science and Technology
SX-106	241-SX-106
TCP	Tank Characterization Plan
TLV	Threshold Limit Value
TRP	Toxicology Review Panel
TO-14	EPA Toxic Organics Protocol 14
TST	Triple Sorbent Trap
TWRS	Tank Waste Remediation System
VSS	Vapor Sampling System
WHC	Westinghouse Hanford Company

A1.0 INTRODUCTION

Tank 241-SX-106 (SX-106) is scheduled to be sampled for flammability and toxicity of vapor in the headspace of the tank. This Appendix A is intended to address only the scheduled vapor sampling and analysis for the fiscal year 1995. Present vapor sampling systems include Type 2 (In Situ Sampling, or ISS) and Type 3 (the Vapor Sampling System, or VSS). These two sampling systems are operated by Sampling and Mobile Laboratories (SML). Both the VSS and ISS collect condensible and non-condensible gases from the tank, they just do it differently. The VSS used a heated vapor probe and collects the sample out of the tank. The ISS lowers the sorbents and TST into the tank headspace for the condensible gases and collects SUMMA®s out of the tank for permanent gases.

A2.0 SAMPLING AND ANALYSIS SCHEME

The following sections provide the methodology and procedures to be used in the preparation, retrieval, transport, analysis, and reporting of results from vapor samples retrieved from tank SX-106. The requirements for this sample event, contained within this appendix of the TCP, are within the scope of work specified in the appropriate laboratory work authorizing documents. Any decisions, observations, or deviations to this sampling and analysis plan made during sample receipt, preparation and analysis shall be documented in controlled notebooks and justified in the deliverable report. The general sampling and analysis scheme for Type 3 vapor sampling is presented as a flowchart and narrative in Figure A-1.

A2.1 VAPOR SAMPLING EVENT

The responsibilities of Sampling and Mobile Laboratories (SML) to this sampling event are given in this section. For detailed information regarding applicable operating procedures for the tank SX-106 vapor sampling activity refer to work package WS-95-00037. Additional quality control and deliverable requirements are given in Sections A3.0 and A6.0. of this appendix.

A2.1.1 Flammability Test

Prior to this sampling event and any intrusive work on this tank, an assessment of the flammability of the tank head space gases is required by WHC safety practices. The flammability test is performed by Industrial Hygiene Field Services using a combustible gas meter (CGM). The procedure for this flammability test is included in the sampling event work package.

- If the tank vapor fuel content is greater than or equal to 20% of the lower flammability limit (LFL) under steady state conditions, then all sampling activities must stop until further authorization is given by management.

- If CGM measures a total fuel content between 10% and 20% of the LFL, vapor sampling activity may continue under CGM monitoring to better identify the hazard level.

- If the concentration is below 10% of the LFL, the tank is not considered have a flammability hazard and all sampling work can proceed (Osborne 1994).

A2.1.2 Sample Collection Using SUMMA® Canisters And Sorbent Tubes

SML shall provide sample identification numbers to the laboratories according to the format given in Section A3.1. SML shall use labeled sample containers supplied by the laboratory (see Section A2.2.1, Preparation of Sample Media Containers) to collect vapor samples. The VSS shall be used to collect vapor from tank SX-106 in accordance with laboratory operating procedure WHC-IP-1127(4.5) "Collection of SUMMA® Canisters and Sorbent Tube Sampling Using the Vapor Sampling System (VSS)". The sample type, type of collection media to be used, and the number of samples requested are given in Table A-1.

Table A-1. General Sampling Information for Tank SX-106.

Sample Container	Prepared By	Preparation Procedure	Sample Type	Number of Samples
SUMMA® Canisters	PNL	PNL-TVP-02	Tank Air	3
SUMMA® Canisters	PNL	PNL-TVP-02	Ambient Air [1]	2
Triple Sorbent Traps	ORNL	AC-OP-3000907 CASD-AM-300-WP01[2]	Tank Air	12
	ORNL	AC-OP-300-0907	Field Blank	2
	ORNL	AC-OP-300-0907	Trip Blank	2
Sorbent Trap System for NH_3, NO_2, NO, H_2O	PNL	PNL-TVP-09	Tank Air	6
	PNL	PNL-TVP-09	Trip Blank	3
Tritium Trap	WHC	LA-548-111	Tank Air	1
HEPA Filters	WHC	N/A	Tank Air	4

1 One sample taken through the VSS, one sample taken upwind of the tank.
2 Preparation procedure for samples spiked with surrogate(s).

Table A-2 provides a sequence of sampling activities along with sample collection times and the flow rates through sample collection tubes. A cleanliness check of the sampling system shall be performed in accordance with procedure WHC-IP-1127(4.5) Appendix C. A cleanliness of the VSS shall also be performed by collecting ambient air SUMMA® samples prior to sampling the tanks using the following conditions: 1) with the VSS manifold and transfer line fully heated, and 2) without the VSS, upwind of tank SX-106.

Organic vapors shall be monitored using the GC/FID during the sampling event. The operating procedure for the GC/FID is provided in the procedure WHC-IP-1127(4.5) and Bellus (1993). The sampling team is responsible for documenting any problems and procedural changes affecting the validity of the sample in a field notebook.

Table A-2. List of Samples and Activities for Tank SX-106.

SAMPLE CODE	SAMPLE/ACTIVITY DESCRIPTION	SAMPLER POSITION DURING COLLECTION	GAS FLOW RATE	SAMPLE DURATION
--	Adjust VSS temperature setpoint to 60°C [1]	N/A	N/A	N/A
--	Purge VSS with ambient air [2]	N/A	5,450 mL/min	30 min.
01	Collect ambient air sample SUMMA #1	Upwind of SX-106	N/A	1 min.
--	Perform cleanliness check	N/A	N/A	N/A
02	Collect ambient air sample SUMMA #2	Port 15	N/A	1 min.
--	Leak test	N/A	N/A	N/A
--	Purge VSS with tank air	N/A	5,450 mL/min	30 min.
--	Measure tank pressure	N/A	N/A	N/A
03	Collect Tritium Trap	Sorbent line 8	200 mL/min	5 min.
--	Collect GC sample and initiate GC run [3]	N/A	N/A	N/A
04	Collect SUMMA #3	Port 11	N/A	1 min.
05	Collect SUMMA #4	Port 13	N/A	1 min.
06	Collect SUMMA #5	Port 15	N/A	1 min.
07	Collect Triple Sorbent Trap (TST) sample #1	Sorbent line 9	50 mL/min	4 min.
08	Collect TST sample #2	Sorbent line 10	50 mL/min	4 min.
09	Collect TST sample #3	Sorbent line 8	50 mL/min	4 min.
10	Open, close, & store TST Field Blank #1	In VSS truck	0 mL/min	N/A
11	Collect TST sample #4	Sorbent line 10	50 mL/min	4 min.
12	Collect TST sample #5	Sorbent line 9	200 mL/min	5 min.
13	Collect TST sample #6	Sorbent line 10	200 mL/min	5 min.
14	Collect TST sample #7	Sorbent line 8	200 mL/min	5 min.
15	Collect TST sample #8	Sorbent line 10	200 mL/min	5 min.
16	Collect TST sample #9	Sorbent line 9	200 mL/min	20 min.
17	Open, close, & store TST Field Blank #2	In VSS truck	0 mL/min	N/A
18	Collect TST sample #10	Sorbent line 10	200 mL/min	20 min.
19	Collect TST sample #11	Sorbent line 8	200 mL/min	20 min.
20	Collect TST sample #12	Sorbent line 10	200 mL/min	20 min.
21, 22	Store TST Trip Blanks #1 & #2	None	None	None
23	Collect NH3/NOx/H2O Sorbent Trap #1	Sorbent line 9	200 mL/min	15 min.
24	Collect NH3/NOx/H2O Sorbent Trap #2	Sorbent line 10	200 mL/min	15 min.
25	Collect NH3/NOx/H2O Sorbent Trap #3	Sorbent line 8	200 mL/min	15 min.
26	Collect NH3/NOx/H2O Sorbent Trap #4	Sorbent line 10	200 mL/min	15 min.
27	Collect NH3/NOx/H2O Sorbent Trap #5	Sorbent line 9	200 mL/min	15 min.
28	Collect NH3/NOx/H2O Sorbent Trap #6	Sorbent line 10	200 mL/min	15 min.
29, 30, 31	Store NH3/NOx/H2O Trap Trip Blanks #1, #2, & #3	None	None	None
32	Remove upstream HEPA Filter from HEPA transfer box	Upstream of box	Continuous	
33	Remove downstream HEPA Filter from HEPA transfer box	Downstream of box	Continuous	
34	Remove upstream HEPA Filter from VSS	Upstream of VSS	Continuous	
35	Remove downstream HEPA Filter from VSS	Downstream of VSS	Continuous	

1 Current (2/13/95) waste temperature is 42.8.0 °C.

2 Not required if ambient air purge incorporated in VSS setup.

3 Additional GC runs may be performed to obtain organic data and to assure cleanliness of the system at the discretion of the sampling scientist and shall be identified in the deliverable report. Organic data obtained from the on-line GC is developmental.

A2.1.3 Radiation Screening and Sample Transport

All vapor samples shall be stored under chain-of-custody requirements by SML while performing a radiological survey of certain items used during sampling. Surveys are conducted to assure compliance with Department of Transportation (DOT) shipping regulations and offsite laboratory acceptance criteria. Items surveyed include four HEPA filters and one tritium trap and are analyzed following procedures specified in Table A-4 (Bratzel 1994).

The results from the radiation screening are submitted to and shall be evaluated by Sampling and Mobile Laboratories (SML) to ensure the samples meet the analytical criteria specified in Table A-3. SML shall provide a Format II report to each analytical laboratory to specify survey results (refer to Section A6.2).

Trip blanks and field blanks are to accompany the waste samples to the laboratory. For specific information concerning sample and blank handling, custody, and transport refer to quality assurance/quality control requirements in Section A3.1.

Table A-3. Limits For Acceptable Radionuclide Activity Levels.

Organization	Total α	Total β/γ	Total $\alpha/\beta/\gamma$	Units
PNL Analytical Chemistry Laboratory	$\leq$ 100	$\leq$ 400	N/A	pCi/g
Oak Ridge National Laboratory	$\leq$ 135	$\leq$ 450	N/A	pCi/g
WHC-CM-2-14	N/A	N/A	$\leq$ 2000	pCi/g

A2.2 LABORATORY ANALYSIS

The responsibilities of the analytical laboratories to this sampling event are given in this section. Additional quality control and deliverable requirements are given in Sections A3.0 and A6.0.

A2.2.1 Preparation of Sample Media Containers

The laboratory performing the contracted analytical work shall supply labeled sample containers (SUMMA® canisters and selective sorbent media) to SML at least 48 hours in advance of the scheduled sampling date. Each sample media container shall be certified as clean and prepared according to procedures called out in Table A-1.

A2.2.2 Sample Analysis

Sample material retrieved from the tank SX-106 vapor space and contained within the SUMMA® canisters shall be analyzed for organic compounds following modified EPA procedure TO-14 and for permanent gases CO_2, CO, CH_4, H_2, and N_2O using gas chromatography. The sorbent traps contain analyte-specific sorbent media and shall be analyzed for these specific analytes. The triple sorbent traps contain sorbent media designed to allow a broad range of organic species to be retained. Table A-4 identifies the appropriate laboratory procedures used in each analysis.

One SUMMA® canister shall be archived at the PNL Laboratory following receipt and control procedure PNL-TVP-07 for six months or until instructed by the Tank Vapor Program to clean the canister for reuse. If necessary, requirements for further quantification and speciation shall be conveyed through a Letter of Instruction by the Characterization Program and/or revision to this Tank Characterization Plan.

Any analyses prescribed by this document, but not performed, or other deviations, shall be identified and include justification in the appropriate data report.

A2.2.3 Insufficient Samples

Unlike a solid sample which may have full or partial recovery, vapor sample media contain either good, bad, or no sample. A sample that is bad or empty may not have a proper seal. Partial recovery of a vapor sample is not an issue, however, the number of good samples may be an issue. All good samples, except the SUMMA® canister archive, shall be analyzed. If there are insufficient good samples to perform all requested analyses, the Characterization Program Office and the Tank Vapor Issue Resolution Program shall be notified. The SUMMA® canister archive shall be used if one or more of the SUMMA® canister samples is compromised.

Figure A-1. Test Plan Outline and Flowchart for Tank Vapor Space Characterization.

Step 1. (Labs) Prepare sample and blank containers at contract laboratories. Label containers using sample identification numbers and sampling data provided by SML.

Step 2.(Labs) Ship Containers to SML at least 48 hours in advance of scheduled sampling event. Shipping, receiving, and control of containers shall be guided by procedures WHC-IP-1127(1.3) (for SML), and either PNL-TVP-07 (for PNL) or CASD-AM-300-WP02 (for ORNL).

Step 3. (SML) If tank is safe with regard to flammability, set up vapor sampling system (VSS) and collect samples following procedure WHC-IP-1127(4.5) and guidelines in Table A-2.

Step 4. (SML) Move the vapor sample containers to custody locked storage. Submit the HEPA filters and Tritium trap to the 222-S Laboratory for radiological survey.

Step 5. (SML) Using radiological survey report results, determine if samples are acceptable to ship offsite (see Table A-3)

Step 6. (SML) If determined to be acceptable according to offsite laboratory requirements and WHC-CM-2-14, ship sample and blanks. If not acceptable to ship, maintain samples in storage and contact the Tank Vapor Issue Resolution Program for further direction.

Step 7. (LABS) Perform laboratory analyses (see Table A-4 for procedure numbers).

A. SUMMA® Canisters (PNL): Perform organic vapor analysis by modified EPA-TO-14. Perform permanent gas analysis for the following: H_2, CO, N_2O, CH_4, CO_2.

B. Sorbent Traps (PNL): Perform gravimetric analysis for moisture. Perform selective electrode analysis for NH_3. Analyze NO and NO_2 Traps.

C. Triple Sorbent Traps (ORNL): Perform organic vapor analysis.

Step 8. (Labs and SML): Following the Section A6.0 reporting requirements, deliver a Format VI report to the Tank Vapor Issue Resolution Safety Program.



Table A-4. SX-106 Sample Chemical, Physical, And Radiological Analytical Requirements

SX-106 VAPOR		COMMENTS
Plan Number	WHC-SD-WM-TP-314	Type 3 vapor sampling system (VSS) using heated vapor probes.
Tank	SX-106	
Program Contact	J. W. Osborne	
TWRS Contact	R.D. Schreiber C. S. Homi	
Lab Project Coordinator	S. C. Goheen (PNL) R. A. Jenkins (ORNL)	

REPORT FORMATS	
I	Early Notify
II	Process Control
III	Safety Screen
IV	Waste Management
V	RCRA Compliance
VI	Special

NO. OF SAMPLE/BLANK CONTAINERS PROCESSED				
Organization	WHC	PNL	ORNL	TOTAL
SUMMA® Canister		3[a]/2		5
Sorbent Trap System[b]		6/3		9
Triple Sorbent Trap			12/4	16
HEPA Filter	4			4
Tritium Trap	1			1

PRIMARY ANALYSES						QUALITY CONTROL[c]			CRITERIA				REPORT FORMAT
ANALYSIS METHOD	PRIMARY ANALYTE	PROCEDURE	LAB	SAMPLE PREP	SAMPLE CONTAINER	NO. OF SAMPLES	SURR SPIKE[d]	NO. OF BLANKS	NOTIFICATION LIMIT (NL)[e]	EXPECTED RANGE	PRECN at NL	ACCURACY at NL	
EPA TO-14 GC/MS	Organic* Speciation	PNL-TVP-01 PNL-TVP-02 PNL-TVP-03	PNL	Direct	SUMMA®	3	none	2	≥ 4000 ppmv n-Butanol 50% IDLH for all others*	not available	±25%	70-130%	I, VI
GC/TCD	CO_2 CO CH_4 H_2 N_2O	PNL-TVP-05 PNL-TVP-02	PNL	Direct	SUMMA®	3	none	2	N/A ≥ 20% LFL ≥ 20% LFL ≥ 20% LFL not available	not available	±25% ±25% ±25% ±25% ±25%	70-130%	VI I, VI I, VI I, VI I, VI
IC	NO NO_2	PNL-TVP-09 PNL-ALO-212	PNL	H_2O Extraction	Sorbent Trap	6	none	3	≥ 50 ppmv ≥ 25 ppmv	≥ 2 ppmv ≥ 0.1 ppmv	±25% ±25%	70-130%	I, VI I, VI
Gravimetric	H_2O	PNL-TVP-09	PNL	Direct	Sorbent Trap	6	none	3	N/A	≥ 3 mg/L	±25%	70-130%	VI
Selective Electrode	NH_3	PNL-TVP-09 PNL-ALO-226	PNL	H_2O Extraction	Sorbent Trap	6	none	3	≥ 250 ppmv	≥ 2 ppmv	±25%	70-130%	I, VI
GC/MS	Organics**	AC-MM-1-033153 CASD-OP-300-WP03 CASD-OP-300-WP04 CASD-OP-300-WP05 CASD-OP-300-WP06	ORNL	Thermal Desorption	Triple Sorbent Trap	12	all	4[f]	≥ 4000 ppmv n-Butanol, 50% IDLH for all others**	not available	±25%	70-130%	I, VI
Total α Total β Total γ	Radon Daughters	LA-508-110 LA-508-111 LA-508-162	WHC	Direct	HEPA Filter	4	N/A	N/A	≥60 pCi/g α ≥200pCi/g β ≥200 pCi/g γ	<60 pCi/g α <200 pCi/g β <200 pCi/g γ	±25% ±25% ±25%	70-130%	I, II
Liq. Scin.	Tritium[g]	LA-548-111	WHC	Direct	Tritium Trap	1	N/A	N/A	N/A	not available	N/A	N/A	II
GC/FID	Organics	WHC-IP-1127(4.5)	SML	Direct	On-line	N/A	N/A	N/A	N/A	N/A	N/A	N/A	II, VI

N/A: Not Applicable
a No extra canisters, except archive, will be stored by PNL.
b System contains individual sorbent media sections for NO_X, NH_3, & H_2O.
c Multiple samples and blanks are taken.
d Samples spiked with surrogates.
e Action required if any compound exceed 50% IDLH.
f Includes two trip and two field blanks.
g Survey purpose only.

*Acetone, acetonitrile, benzene, 1,3-butadiene, butanal, n-butanol, n-hexane, methane, propane nitrile. Other organic species detected at levels deemed sufficient by the Toxicology review Panel to be of potential toxicological concern shall be reported following Format I.

**Acetone, acetonitrile, benzene, butanol, n-dodecane, n-hexane, propane nitrile, tributyl phosphate, n-tridecane. Other organic species detected at level deemed sufficient by the Toxicology Review Panel to be of potential toxicological concern shall be reported following Format I.

A3.0 QUALITY ASSURANCE & QUALITY CONTROL

This Tank Characterization Plan and analytical laboratory operations are approved by the WHC Environmental Safety, Health, and Quality Assurance (ESH&QA) Program provided the following conditions are met.

1) Each laboratory has a quality assurance program that meets the applicable requirements of DOE order 5700.6C, or United States 10 CFR 830.120. In addition, it must also meet the requirements of QAPP-013 (Keller 1994) and when implemented in August 1995, the *Hanford Analytical Services Quality Assurance Plan* (DOE 1994).

2) Each analysis and media preparation procedure given in Tables A-1 and A-4 are documented by the laboratory and available to ESH&QA.

3) Any modifications made to, or deviations from, the prescribed procedures are documented in controlled notebooks and justified in the deliverable report.

The PNL tank vapor program is governed by a QA Plan (Barnes 1995). ESH&QA will qualify laboratories for continued use by the TWRS Characterization Program after receipt of a QA plan, followed by an audit and corrective action phase.

A3.1 Sampling Operations

SML shall provide unique sample label and identification numbers to the laboratories. Each sample identification number shall have the following format:

SXXXX-WYY-LLL, where:

XXXX	=	unique number assigned to the sampling event,
W	=	a letter code indicating the day of a multi-day sampling event,
YY	=	a 2-digit sample code found in Table A-2, List of Sample and Activities, column one.
LLL	=	a special lab assigned code.

Once the sample collection media has been received by SML from the laboratory, it shall remain in the physical control of the custodian, locked in a secure area, or prepared for shipping with tamper evident tape under conditions specified on the chain-of-custody form and in accordance with laboratory operating procedure WHC-IP-1127(1.3) "Chain-of-Custody for RCRA and CERCLA Protocol Samples".

Applicable operating procedures for the tank SX-106 vapor space sampling activities are contained in work package WS-95-00037. Vapor samples, trip blanks, and field blanks are to be collected in accordance with Tables A-1 and A-2 and laboratory operating procedure WHC-IP-1127(4.5) "Collection of SUMMA® Canisters & Sorbent Tube Samples Using the Vapor Sampling System (VSS)" and shipped to the laboratory in accordance with Hazardous Material Packaging and Shipping, WHC-CM-2-14.

All sampling activities shall be documented in controlled field logbooks maintained by sampling personnel (SML) and shall contain, but are not limited to:

1) identification of tank and riser number and photographs of the sample location in which the sampling is conducted,

2) if any anomalies are observed, corresponding sample identification numbers, flow rates, pressures, temperatures, and other operational parameters affecting the sample,

3) any conditions that the sampler may observe during the sampling event (i. e., odors, nearby machinery in operation, etc.),

4) names and titles of personnel involved in the field activity and their responsibilities,

5) instrument calibration dates.

SML is responsible for documenting any problems and procedural changes affecting the validity of the sample in a controlled field notebook and shall enter this information in the comment section of the chain-of-custody form for addition to the data reports.

A3.2 Laboratory Operations

The SUMMA® canisters and Sorbent Trap Systems shall be prepared, certified, and labeled by the performing laboratories following the laboratory quality control procedures identified in Table A-1. The laboratory supplying the sample collection media shall initiate the chain-of-custody in accordance with the laboratory operating procedure WHC-IP-1127(1.3), "Chain-of-Custody for RCRA and CERCLA Protocol Samples" using sample label and identification numbers provided by SML.

The sample receipt and control procedure used in the PNL laboratory is PNL-TVP-07. Oak Ridge National Laboratory shipping and receiving is done by procedure CASD-OP-300-WP02. Analyses shall be performed following the procedures in Table A-4.

Method specific quality control such as calibrations and blanks are also found in the analytical procedures. Sample quality control (duplicates, spikes, standards) specified in the applicable DQO's are identified in Table A-4. Due to the developmental work being done with the analysis procedures and potential sample differences (between tanks), changes in procedures may be needed.

A4.0 ORGANIZATION

The organization and responsibility of key personnel involved in this tank SX-106 vapor sampling project are listed in Table A-5.

Table A-5. Tank SX-106 Project Key Personnel List.

Individual(s)	Organization	Responsibility
S. C. Goheen	Pacific Northwest Laboratory	Project Manager for Vapor Sample Characterization
R. A. Jenkins	Oak Ridge National Laboratory	Project Manager for Vapor Sample Characterization
J. G. Kristofzski	WHC 222-S Laboratory	Project Manager for Sample Radiological Survey
C. S. Homi	TWRS Characterization Support	SX-106 Tank Characterization Plan Engineers
J. W. Osborne	TWRS Tank Vapor Issue Resolution Program	Tank Vapor Issue Resolution Program Manager
H. Babad	TWRS Characterization Program	Tank Safety Screening Scientist
R. S. Viswanath	Special Analytical Studies	Vapor Program Technical Lead
R. D. Mahon	Sampling and Mobile Laboratories	Vapor Sampling Program Lead
E. H. Neilsen	Waste Tank Safety Engineering	Vapor Sampling Cognizant Engineer
D. R. Carls	Industrial Hygiene and Safety Program	Industrial Hygiene Point of Contact if Notification Limit is Exceeded (FAX 372-3522)
West Area Shift Operations Manager	Tank Farm Operations	West Tank Farm Point of Contact if Notification Limit is Exceeded (373-3475)

A5.0 EXCEPTIONS, CLARIFICATIONS, AND ASSUMPTIONS

Toxicology Review Panel

The Toxicology Review Panel (TRP) is a group of toxicologists, industrial hygienists, and occupational medicine physicians that convene to review quantitative vapor sample data, identify compounds of toxicological concern, and make recommendations to the WHC Tank Vapor Program Manager concerning potential impacts to worker health and safety.

Toxicological Concern

From a list of 160 analytes found in a previous study for tank C-106, the TRP identified 19 analytes of toxicological interest. These analytes and others may be identified during TRP review of qualitative GC vapor data as being of toxicological concern if they exceed recommended levels inside the tank headspace. Established guidelines for these analytes are base on Consensus Exposure Standards (CES).

Consensus Exposure Standards

A CES is generally defined as the most stringent of known regulatory or recommended toxicological values for the occupational setting including the threshold limit value (TLV), permissible exposure limit (PEL), recommended exposure limit (REL), and biological exposure limit (BEL). For those constituents with unknown toxicological values, the TRP will be responsible for development of a CES.

Trip Blanks and Field Blanks

Trip Blanks are sampling devices prepared and handled in the same manner as samples, except that they are never opened in the field. Field Blanks are sampling devices prepared and handled in the same manner as the samples, but no tank gases are drawn through them. Laboratories supplying blanks may opt to analyze only 1 trip blank unless it is determined to be contaminated, in which case all trip blanks are to be analyzed.

Sample Custodian

The sample custodian is the designated SML cognizant scientist or assisting scientific technician, lead sampler, or laboratory scientist or technician who signs the received by block on the chain-of-custody form. Transfer of custodianship occurs when the custodian signs the relinquished by block on the chain-of-custody form and releases the sample(s) to the new custodian signator.

Physical Control

Physical control of a sample includes being in the sight of the custodian, in a room which shall signal an alarm when entered, or locked in a cabinet.

A6.0 DELIVERABLES

The Pacific Northwest Laboratory, Oak Ridge National Laboratory, and Sampling and Mobile Laboratories VSS sampling and analyses of tank SX-106 vapors shall be reported as Format VI. In addition, the analytical laboratories shall receive Format II reports from Sampling and Mobile Laboratories as described in Section A6.2. Any analyte exceeding the notification limit prescribed in Table A-4 shall be reported as Format I. Other organic species detected at levels deemed sufficient by the Toxicology Review Panel to be of potential toxicological concern shall also be reported following Format I. Additional information regarding reporting formats is given in Schreiber (1994a, 1994b, 1994c).

A6.1 Format I Reporting

Table A-4 contains the notification limits for specific analytes. Analytes that exceed notification limits defined in the DQO processes shall be reported by the Project Manager, delegate, or Health Physics Management by calling the West Area Shift Manager of Tank Farm Operations at (509) 373-3475 immediately. This verbal communication must be followed within 3 working days by written communication to J. W. Osborne of the Tank Vapor Issue Resolution Program, D. R. Carls in the Industrial Hygiene and Safety Program, and D. R. Bratzel of the Characterization Program, documenting the observation(s). A further review of the data, including quality control results and additional analyses for verification of the exceeded analyte, may be contracted between the performing laboratory and the contacts above.

A6.2 Format II Reporting

Results of the 222-S Laboratory's radiological survey shall be reported by Sampling and Mobile Laboratories as Format II to the vapor analytical laboratories listing the picocuries per sample (pCi/g/sample) for each sample submitted for analysis. This Format II report should also provide the sample collection sequence and volumes, verification of trip and field blank use, and any anomalous sampling conditions to accompany, if possible, the shipment of samples. Alternatively, this sampling report may be transmitted by FAX to the analytical laboratories within 48 hours after the samples have been shipped.

A6.3 Format VI Reporting

All Format VI reports shall be delivered to J. W. Osborne of the Tank Vapor Safety Resolution Program, R. S. Viswanath of Special Analytical Studies, the Characterization Program Office, Analytical Services, and the Tank Characterization Resource Center.

Each analytical laboratory and SML should deliver three reports. Sampling and analytical data are requested within 5 weeks after receipt of both the samples and supporting data and shall consist of, at a minimum, data tables reporting sample collection data, industrial hygiene tank monitoring data, and radiation screening results obtained by SML, or the results of each analysis performed by the analytical laboratories. A final report shall be delivered within a nine week period after receipt of both the samples and supporting data. A cleared final report shall be delivered after it has completed the proper clearance. Final reports shall be submitted to clearance in parallel to being submitted to the WHC customers identified above.

The final sampling report from Sampling and Mobile Laboratories shall be a WHC supporting document, with sponsor-limited release. It shall include:

1) A description of sampling equipment used;

2) a description of sampling quality controls applied (e.g., leak and cleanliness tests of the sampling manifold, system temperature and pressure monitoring/alarms, instrument calibration details);

3) sampling event chronology and sample collection schedule (complete list of samples, by ID#, time collected, flow rates, etc.);

4) any industrial hygiene tank monitoring data collected before or during sampling event;

5) an evaluation of sources of sampling errors;

6) sample radiation screening results;

7) sample storage and shipment details; and

8) copies of all chain-of-custody forms.

The cleared final report from the analytical laboratories shall be acceptable for distribution to the public. To the extent possible, the final reports shall include:

1) A summary of analytical results;

2) a description of sample device preparation (and manufacturer if appropriate), citing procedures and logbooks used;

3) references providing traceability of sample device cleanliness;

4) a brief description of analytical methods, with procedures cited;

5) a brief explanation of how analytical systems control was demonstratably maintained;

6) a brief description of sample storage and shipment conditions, citing procedures and logbooks used;

7) a listing of analytes of quantitation (target analytes), with analytical method detection limit, range for which instrumentation is calibrated, number of calibration points used, and statistical data on linearity of calibration;

8) quantitative analytical results, expressed as dimensionless (ppmv or ppbv) concentration, and mass concentration ($\mu g/m^3$, mg/L, etc., calculated at 0 °C and 1 atm) of target analytes (identified by name and Chemical Abstract Service number) in each tank air sample;

9) tentative identification and semi-quantitative analytical results, expressed in both mass and dimensionless concentrations (if possible) of non-target organic analytes (identified by name and Chemical Abstract Service number) in each organic vapor sample;

10) a statistical summary (i.e., mean, standard deviation) for multiple analyses and/or multiple samples for all analytes (positively and tentatively identified compounds) in both mass and dimensionless concentrations (if possible);

11) a summary of all exceptional conditions, such as deviations from procedure or protocol, results obtained outside of instrument calibration range, sorbent trap breakthrough of analytes, or poor surrogate recoveries; and

12) Copies of all chain-of-custody forms.

A7.0 CHANGE CONTROL

Under certain circumstances, it may become necessary for the performing laboratory to make decisions concerning a sample without review of the data by the customer or the Characterization Program. These changes shall be brought to the attention of the project manager and the Characterization Program as quickly as possible and documented accordingly. Changes must be justified in their documentation and follow the protocols defined in the Quality Assurance Manual, WHC-CM-4-2, Section QR 3.0, Design Control and in Standard Engineering Practices, WHC-CM-6-2, Section EP-2.2, Engineering Document Change Control Requirements. All changes shall also be clearly documented in the final data package.

Additional analysis of sample material from this vapor space characterization project at the request of the Characterization Program shall be performed according to a revision of this Tank Characterization Plan.

A8.0 REFERENCES

Barnes, B. O., 1995, *Quality Assurance Plan for PNL TWRS Tank Vapor Program*, MCS-046, Rev. 0, Pacific Northwest Laboratory, Richland, Washington.

Bratzel, D. R., 1994, *Letter of Instruction for Radiological Analyses to Support Fiscal Year 1995 Tank Vapor Sampling*, (internal memo 74310-94-32 to J. G. Kristofzski, November 30), Westinghouse Hanford Company, Richland, Washington.

Bellus, T. H., 1993, *Configuration of Hewlett Packard (HP) 5890 Series II Gas Chromatograph (GC) for DML1*, (internal memo 12240-SAA93-039 to L. L. Lockrem, July 10), Westinghouse Hanford Company, Richland, Washington.

DOE, 1994, *Hanford Analytical Services Quality Assurance Plan*, DOE/RL-94-55, Rev.0, U.S. Department of Energy, Richland field Office, Richland, Washington.

Keller, K. K., 1994, *Quality Assurance Project Plan for Tank for Tank Vapor Characterization*, WHC-SD-WM-QAPP-013, Rev.2, Westinghouse Hanford Company, Richland, Washington.

Schreiber, R. D., 1994a, *Format I Reporting Requirement*, (internal memo 7E720-94-128 to J. G. Kristofzski, August 15), Westinghouse Hanford Company, Richland, Washington.

Schreiber, R. D., 1994b, *Revised Interim Tank Characterization Plan Guidance*, (letter 7E720-94-121 to C. S. Haller, May 13), Westinghouse Hanford Company, Richland, Washington.

Schreiber, R. D., 1994c, *Point of Contact/Distribution List*, (internal memo 7E720-94-141 to J. G. Kristofzski, October 11), Westinghouse Hanford Company, Richland, Washington.

United States Department of Energy Order 5700.6C, of 08-21-91, *Quality Assurance*.

United States Code of Federal Regulations 10 CFR, Part 830, *Nuclear Safety Management;* Section 120, *Quality Assurance Requirements*.

Whelan, T. E., 1994, *TWRS Characterization Program Quality Assurance Program Plan*, WHC-SD-WM-QAPP-025, Westinghouse Hanford Company, Richland, WA.