

JUL 09 1997

Sta 34

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 618973

NEW

(67)

ORIGINAL 7/8/97
gm

2. To: (Receiving Organization) Lockheed Martin Hanford /77C00		3. From: (Originating Organization) Fluor Daniel Northwest		4. Related EDT No.: None	
5. Proj./Prog./Dept./Div.: E61945		6. Design Authority/ Design Agent/Cog. Engr.: E. D. Johnson /454		7. Purchase Order No.: N/A	
8. Originator Remarks: For external release				9. Equip./Component No.: N/A	
				10. System/Bldg./Facility: 209E Facility	
				12. Major Assm. Dwg. No.: N/A	
11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No				13. Permit/Permit Application No.: N/A	
				14. Required Response Date: N/A	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Design- nator	Reason for Trans- mittal	Origina- tor Dispo- sition	Receiv- er Dispo- sition
1	HNF-SD-WM-ES-411	—	0	Engineering Study for Closure of 209E Facility	N/A	1	1	1

16. KEY					
Approval Designator (F)		Reason for Transmittal (G)		Disposition (H) & (I)	
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information	4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment	4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged	

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)											
(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
		Design Authority				1	1	ED Johnson		7/3/97	E6-08
		Design Agent				1	1	WH Hays		7/3/97	E6-08
		Cog.Eng.				1	1	CH Brevicek		7/3/97	E6-08
1	1	Cog. Mgr. MS Harrington									
		QA									
		Safety									
		Env.									

18. CH Brevicek Signature of EDT Originator 7/3/97 Date		19. Authorized Representative Date for Receiving Organization		20. MS Harrington Design Authority/ Cognizant Manager 7-7-97 Date		21. DOE APPROVAL (if required) Ctrl. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments	
--	--	---	--	--	--	---	--

Engineering Study For Closure of 209E Facility

C. H. Brevick, W. H. Hays, E. D. Johnson
Fluor Daniel Northwest, Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200

EDT/ECN: ~~641029-9~~ ⁶¹⁸⁹⁷³ 7/9/97 UC: 2070
Org Code: 408 Charge Code: E61945
B&R Code: EW3120074 Total Pages: 118


Key Words: Critical mass laboratory, CML, 209E Building, non-nuclear classification, Critical Assembly Room, Mix room, criticality experiments, decontamination, decommissioning.

Abstract: This document is an engineering study for evaluating alternatives to determine the most cost effective closure plan for the 209E Facility, Critical Mass Laboratory. This laboratory is located in the 200 East Area of the Hanford Site and contains a Critical Assembly Room and a Mix room were criticality experiments were once performed.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

J. Mahan 7/9/97
Release Approval Date



Release Stamp

Approved for Public Release

Engineering Study

Closure of the 209E Facility

Work Order E61945

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the
U.S. Department of Energy under Contract DE-AC06-96RL13200

Approved for public release; distribution is unlimited

ENGINEERING STUDY
for
CLOSURE OF THE 209E FACILITY

Prepared
for
Lockheed Martin Hanford Corporation
by
Fluor Daniel Northwest

APPROVED:

FLUOR DANIEL NORTHWEST

Judith L. Zimmerman
Technical Documents

6-30-97
Date

Eng. D. Johnson DCL
Lead Engineer

7/3/97
Date

Darryl Salberg
Quality Engineering

6-30-97
Date

Chris H. Brewick
Project Manager

7/3/97
Date

LOCKHEED MARTIN HANFORD CORPORATION

Susan Harrington
Project Manager, TWRS Operations

7/7/97
Date

ACKNOWLEDGEMENT

The authors would like to thank the following people for their assistance in preparing this engineering study.

J. L. Stroup

Babcock & Wilcox Hanford Company

R. W. Bailey

J. P. Hayfield

W. A. Peiffer

L. D. Stefanski

Waste Management Federal Services of Hanford, Inc.

M. E. Lakes

F. C. Schmidt

M. L. Windsor

H. H. Van Tuyl, retired

TABLE OF CONTENTS

I.	INTRODUCTION	1
II.	SUMMARY AND CONCLUSIONS	6
III.	DESCRIPTION OF ALTERNATIVES	7
A.	CRITERIA	7
B.	ALTERNATIVES CONSIDERED	8
1:	Leave As Is	8
2:	Fix In Place	9
3:	Removal and Fix In Place	13
4:	Stage-Wise Removal	17
5:	Turnover to the EM-60 Program	21
IV.	IDENTIFICATION OF PREFERRED ALTERNATIVE	22
A.	EVALUATION OF ALTERNATIVES	22
B.	PREFERRED ALTERNATIVE	23
C.	UNCERTAINTIES	23
V.	REQUIRED CHANGES TO IMPLEMENT PREFERRED ALTERNATIVE	24
VI.	REFERENCES	25
A.	DOCUMENTS	25
B.	DRAWINGS	26

APPENDICES

Appendix A Cost Estimates
Appendix B Schedules
Appendix C Equipment List

ACRONYM AND ABBREVIATIONS LIST

BCCAA	Benton County Clean Air Authority
BHI	Bechtel Hanford, Inc.
BWHC	Babcock & Wilcox Hanford Company
CAR	critical assembly room
CFR	Code of Federal Regulations
CFRP	consolidated fuel reprocessing program
CML	Critical Mass Laboratory
D&D	decontamination and decommission
DOE	U.S. Department of Energy
EA	environmental assessment
Ecology	Washington State Department of Ecology
EM-40	U.S. Department of Energy, Environmental Restoration Division
EM-60	U.S. Department of Energy, Office of Facility Transition
FDNW	Fluor Daniel Northwest, Inc.
FEAS	fuel element assembly system
HEPA	high-efficiency particulate air
HVAC	heating, ventilating, and air conditioning
LMHC	Lockheed Martin Hanford Company
NDA	nondestructive analysis
NEPA	National Environmental Policy Act
NOC	Notice of Construction
PBS	polymeric barrier system
Pu	plutonium
PUREX	Plutonium Uranium Extraction Facility
RCRA	Resource Conservation and Recovery Act
RL	Richland Operations Office (DOE)
ROM	rough order of magnitude
SAR	safety analysis report
SWB	standard waste box
TK	tank
WIPP	Waste Isolation Pilot Plant
WRAP	waste receiving and packaging
WSDOH	Washington State Department of Health

ENGINEERING STUDY for CLOSURE OF THE 209E FACILITY

WORK ORDER E61945

I. INTRODUCTION

The Critical Mass Laboratory (CML) is located in the 200-East Area of the Hanford Site, south of 7th Street and east of Baltimore Avenue (Fig 1). The building is identified as the 209E Facility. The facility was designed to provide a heavily-shielded reactor room where quantities of fissile materials in solution could be brought into critical configurations under carefully controlled and monitored conditions (Fig 2). The facility no longer has a mission and is awaiting final closure and decontamination and decommissioning (D&D).

The CML is not included in any Resource Conservation and Recovery Act (RCRA) Part A or B permit. National Environmental Policy Act (NEPA) documentation was not found in the Hanford Site NEPA files for the 209E Facility.

Two CML rooms identified for remediation are the Critical Assembly Room (CAR) (Fig 3) and the Mix room (Fig 4). The CAR contains contaminated equipment including 4 gloveboxes, 12 tanks, and miscellaneous vessels and bottles. Criticality experiments were conducted in the CAR. The room contains two reactor gloveboxes where the critical test assemblies are contained. The Mix room provided the necessary facilities for receiving, handling, and preparing the various forms of fissile materials during the experiments. The room contains contaminated equipment, including three gloveboxes and eight tanks. An office complex, equipment room, and changeroom are a part of the 209E Facility, but are not addressed for closure in this engineering study.




Figure 1: Hanford Site, 200-East Area




Figure 2: Critical Mass Laboratory, 209E Facility, Facility Layout




Figure 3: Critical Assembly Room Layout




Figure 4: Mix Room Layout

The purpose of this engineering study is to determine the safest method and most cost-effective technology to prepare the 209E Facility for closure. The engineering study will present alternatives for closure and eventual turnover of the facility from Lockheed Martin Hanford Company (LMHC) to the environmental restoration and management contractor, Bechtel Hanford, Inc. (BHI). BHI will presumably perform the D&D of the facility under the U.S. Department of Energy (DOE) EM-40 program.

II. SUMMARY AND CONCLUSIONS

Five alternatives were evaluated for the closure or disposition of the 209E Facility. Table 1 summarizes the total estimated cost, manhours, and time to complete each alternative.

TABLE 1: SUMMARIZATION OF ALTERNATIVES

Alternatives	Total Estimated Cost	Total Estimated Manhours	Estimated Time to Complete (Months)
1. Leave As Is	\$94,188/year	1,202/year	0
2. Fix In Place	\$729,464	8,977	8
3. Removal and Fix In Place	\$1,024,737	13,327	10
4. Stage-Wise Removal	\$1,721,144	19,715	13
5. Turnover to the EM-60 Program*	\$10,000	80	3

* A formal cost estimate was not performed for Alternative 5 due to its minimal cost compared with the other alternatives. The estimated costs represent the cost to turnover the facility "as is" and does not include future deactivation costs to the EM-60 program.

The end-point specification document and safety analysis report (SAR) for the CML closure have not been completed, but both documents are being prepared by Babcock & Wilcox Hanford Company (BWHC) and by LMHC. The documents are important because they explain the acceptance criteria for turnover to BHI. This study was not

based upon BHI acceptance criteria, but on current technology (taking safety and cost effectiveness into account), lessons learned at the Plutonium Uranium Extraction Facility (PUREX), the 308 Building, and personnel (operators and engineers) experience.

Fluor Daniel Northwest (FDNW) recommends that future engineering studies on the closure, decommission, or shutdown of a facility consider having the end-point specification and the SAR completed prior to starting a study.

III. DESCRIPTION OF ALTERNATIVES

A. CRITERIA

The objective of this study is to determine the safest and most cost-effective method for closure of the CML (209E Facility) until turnover to the D&D contractor. The strategy should be similar to that used by BWHC in prior remediation efforts used in the closure of PUREX. It is assumed that a debris removal effort, to be completed before the remediation activities begin, will address all loose waste items in the facility, i.e., trash, waste drums, miscellaneous containers of chemicals, packaged waste, etc.

The original goal was to prepare the building for closure having a nonnuclear classification of "other industrial," however, FDNW determined that this classification is not achievable considering the objective of this study. The following criteria were addressed:

- Determine the best and most cost-effective technology for cleaning and applying a fixative to the remaining plutonium (Pu).
- Investigate the safest and most current methods to decontaminate and remediate the plutonium-handling equipment (i.e., gloveboxes, fume hoods, and piping), ductwork and fixtures. Address both radiochemical and hazardous waste.
- Assess the environmental, regulatory, and permitting requirements.

B. ALTERNATIVES CONSIDERED

A four-step approach was utilized to develop alternatives with each alternative building upon the last. While developing these approaches, an alternative evolved that did not use the same approach as the other four; this concept was added as Alternative 5. The following alternatives were considered:

Alternative 1. Leave As Is

Alternative 2. Fix In Place

Alternative 3. Removal and Fix in Place

Alternative 4. Stage-Wise Removal

Alternative 5. Turnover to the EM-60 Program

Prior to shutdown of the facility, all tanks in the solution handling system were flushed with condensate to remove as much Pu as reasonably possible. All of the tanks were verified as empty and were purged with an air sweep to evaporate most or all of the residual liquid. During unmanned status, an air sweep of nominal 30 liters/hour (one cubic foot/hour) was maintained for all storage tanks. In any of the alternatives where tanks, vessels, etc., are to be sealed or left without decontaminating, they need to be confirmed as dry or dried. This action is necessary, especially for those tanks that are to be sealed, due to the possibility of residual water in vessels being converted, by residual radioactivity, into a mixture of hydrogen and oxygen gases (Van Tuyl 1987). This mixture of gases could possibly lead to a ruptured tank or flammable gases being released into the facility.

Alternative 1: Leave As Is

Alternative 1 would continue with the present facility operations, surveillance, and maintenance schedule. The fire protection system would remain in service; the system is wet pipe to the CAR and dry pipe inside the CAR. The CAR halon system is out of service. The estimated yearly cost for this alternative is \$94,188, with an estimated 1,202 manhours. The estimate also includes the cost of maintaining the office spaces within the facility. Appendix A, pages 1 through 12, contains the detailed cost estimate for Alternative 1.

Electrical

The normal power, emergency power, exhaust fan, and vacuum air sampling electrical systems are still in service. All other electrical compartments are out of service. The batteries for the emergency lights have been removed. The criticality alarm system for the Mix Room has been removed and transferred to the CAR. The intercom was turned off and only one telephone service was left. The electric supply for the annunciator panel has been disconnected.

Heating, Ventilating, and Air Conditioning

The supply ventilation is shut off and air is supplied to the CAR and the Mix room by infiltration. The exhaust fan is operating below maximum capacity.

Environmental

Alternative 1 would not require permits and regulatory notifications because no remediation work would be performed on the facility.

Advantages

No additional costs above those already required would be needed to maintain the facility. Alternative 1 is the simplest of all alternatives and requires no additional work to the facility.

Disadvantages

Alternative 1 does not reduce possible health and environmental risks. It does not further the D&D process or meet the RL objective of remediation of nonactive facilities.

Alternative 2: Fix In Place

Alternative 2 would fix in place all contamination with an acrylic latex contamination fixative (polymeric barrier system [PBSI]) (the fixative) and shut down all building systems except for required safety systems.

Electrical

Normal and emergency power would be turned off in the CAR and the Mix room, except for lighting, fire alarm, receptacles/outlets, air sampler, exhaust ventilation system, and constant air monitoring on the main exhaust stack. The power would be turned off and the cables disconnected and removed before the fixative is applied to the equipment. In addition, all accessible electric components associated with the equipment would be removed. After all the work is completed, the ventilation, receptacle/outlets, lighting and fire protection system would be turned off. For safety purposes, the fire protection system would be drained and disconnected last. Turning off the fire protection system is contingent on being able to zero value the building, i.e., change the building assessed value to zero dollars.

Heating, Ventilating, and Air Conditioning

Currently, the supply ventilation system is turned off and air is supplied by infiltration. The supply ventilation system may need to be restarted if the required number of room air changes cannot be met through increasing the exhaust rate and, thus, the rate of infiltration. The confinement heating, ventilating, and air-conditioning (HVAC) system would need to be reactivated.

Environmental

Since fixing the contamination would be performed in rooms with ventilation controls, there is minimal potential to emit fugitive radioactive air emissions. The Washington State Department of Health (WSDOH) must be contacted, and a Notice of Construction (NOC) may be required. If any of the areas containing asbestos would be disturbed by the work to fix the contamination, a good faith inspection must be performed and the Benton County Clean Air Authority (BCCAA) must be notified ten working days prior to work beginning.

A notice to the Washington State Department of Ecology (Ecology) is unnecessary because there is no apparent route for releasing any hazardous air emissions. A NEPA review would be used to evaluate the environmental impacts of entering the

facility to deactivate, deenergize, and/or isolate unneeded facility systems. This is expected to be allowed by using the existing sitewide Categorical Exclusion.

Description of Alternative

The first step of Alternative 1 would be to isolate the gloveboxes/hoods. All pipe and tubing intrusions would be cut and capped outside the gloveboxes/hoods. A glove bag would be used to cover the pipes during this process. The inside of the gloveboxes/hoods would be wiped down to remove as much surface contamination as possible. Contaminated areas inside the gloveboxes/hoods would then be sprayed with the fixative. The remaining glovebox ports and hood openings would then be sealed. The glovebox ports would be sealed with a metal plate and the hoods sealed with a fabricated metal door (closure).

All gloveboxes contain a high efficiency particulate air (HEPA) filter that vents/inlets directly to the room. These HEPA filters would be removed and the opening sealed. One of the metal plates sealing the glovebox ports would be designed to house a HEPA filter mask canister to allow the gloveboxes to passively vent to their respective rooms, thus eliminating any danger of pressurizing.

The floor and walls of the CAR and the Mix room would be surveyed for areas of contamination. These areas would be wiped clean and any remaining contamination fixed in place with the fixative.

All remaining slab tanks, i.e., not located in a glovebox/hood, would be sealed shut by cutting and capping the inlet to the tanks, using the same method as cutting and capping the pipes and tubing into the gloveboxes/hoods. The only exceptions would be tank (TK) -109, TK-110, and TK-111. These slab tanks are encased in concrete, TK-109 and TK-110 are buried in concrete 1 meter (3 ft) under the CAR while TK-111 is located in the waste hold-up valve pit outside the building, level with the floor of the pit.

A nondestructive analysis (NDA) was not performed on these tanks due to inaccessibility. TK-109 and TK-111 are known to have contained radioactive waste, while TK-110 never received any radioactive waste but, due to its piping configuration, radioactive waste could have entered the tank either by leaks or operator error. The removal of these tanks would present more hazards to workers and the environment than leaving them intact. Therefore, it is recommended that the tanks be sealed utilizing available technologies, i.e., filled with grout (or equivalent), and sealed off completely.

TK-160 (the consolidated fuel reprocessing program [CFRP] water tank) contains CFRP process tanks, TK-161 and TK-162. If TK-160 still contains water, it should be drained. TK-161 and TK-162 would then be sealed by cutting and capping the inlets and outlets, using the same technique used for the slab tanks.

TK-108, the fuel element assembly system (FEAS), contains a 360-mm (14-in.) and a 690-mm (27-in.) experimental vessel. No other information on the dimensions of these tanks could be found, therefore, the tanks would need to be examined before a containment solution could be determined.

The active exhaust ventilation systems for the CAR and the Mix room are interconnected before exiting the stack. All gloveboxes/hoods have a HEPA filter positioned before the ventilation duct. Exhaust ventilation air from each room passes through a bank of HEPA filters. The exhaust ventilation systems connect before the first stage of HEPA filtration outside the building. The active exhaust ventilation system is likely contaminated up to the first bank of HEPA filters outside of the building. The active exhaust ventilation system would be sealed off just down stream from that HEPA filter. This allows the contaminated ducting and gloveboxes/hoods to equalize pressure with the room via the HEPA filtered passive vents in the gloveboxes/hoods. All possible egress points, i.e., aerosol/smoke injection ports and joints, would be sprayed with the fixative.

The hoist and trolley crane located in the Mix room would be removed from service and mothballed.

Minimal maintenance and surveillance would be required until turnover to the D&D contractor. The estimated cost for Alternative 2 is \$729,464 with an estimated 8,977 manhours. Appendix A, pages 13 through 24, contains the detailed cost estimates. Appendix B contains the schedule for Alternative 2.

Advantages

The advantage of Alternative 2 is that it is a quick and inexpensive solution. It is fairly simple to survey the equipment, walls, and floors and fix the contamination in place. Applying the fixative could possibly contain all contamination and, thereby, reduce the overall operating cost of the facility. In addition, an environmental assessment (EA) is not expected to be necessary.

Disadvantages

The likelihood of the fixative being able to contain all of the Pu in place is uncertain. Due to the complexity and inaccessibility inside and under/behind gloveboxes (there is believed to be contamination under some gloveboxes), there would be many areas where contamination may not be fixed in place. TK-105 and TK-106 (located in the CAR) have a history of weeping plutonium, even after attempts to seal the contamination. Attempting to isolate and seal these tanks could be unsuccessful over an extended period of time. The HEPA canister filters fitted into the ports on the gloveboxes/hoods, to be used as passive ventilation, are designed for low airflow. There is the remote possibility that the equalization airflow could exceed the filters design limit.

Alternative 3: Removal and Fix In Place

Alternative 3 is an expansion of Alternative 2. All equipment would be removed from the gloveboxes/hoods before cleaning, applying the fixative, and sealing the gloveboxes/hoods. TK-105 and TK-106 would be removed from the facility.

Electrical

Normal and emergency power should be turned off in the CAR and the Mix room except for lighting, fire alarm, receptacles/outlets, air sampler, exhaust ventilation system, and constant air monitoring on the main exhaust stack. When equipment is removed or sprayed with the fixative, the power would be turned off before disconnecting and removing the cables from the equipment. In addition, all accessible electric components associated with the equipment would be removed. After all the work is completed, the ventilation, receptacle/outlets, lighting, and fire protection system would be turned off. For safety purposes, the fire protection system would be drained and disconnected last. Turning off the fire protection system is contingent on being able to zero value the building.

Heating, Ventilating, and Air Conditioning

Currently, the supply ventilation system is off and air is supplied by infiltration. The supply ventilation system may need to be restarted if the required number of room air changes cannot be met through increasing the exhaust rate and, thus, the rate of infiltration. The confinement HVAC system would need to be reactivated to full functionality.

Environmental

Removing waste and equipment has the potential to emit fugitive radioactive air emissions. An NOC must be submitted to the WSDOH.

If asbestos is suspected, a good faith inspection must be performed and the BCCAA must be notified ten working days prior to work beginning. All asbestos work must comply with Code of Federal Regulations (CFR) 40 CFR 61 and the agreement with the BCCAA. Since the asbestos would be assumed to be radioactively contaminated, the material would be disposed of in burial boxes and sent to the disposal trenches in the 200-West Area.

A notice to Ecology could be necessary if hazardous air emissions from cutting up items of contaminated heavy metals would be released.

Alternative 3 may require an EA to analyze the unknowns associated with the hazardous and radioactive materials (e.g., location and dose exposure levels in areas currently inaccessible as in and around gloveboxes and/or tanks).

Alternative 3 would produce radioactive and mixed waste requiring storage and/or disposal.

Description of Alternative

The first step of Alternative 3 would remove (bag out) all equipment (tanks, pumps, condensers, etc.) in the existing gloveboxes/hoods. Equipment must fit into a waste isolation pilot plant (WIPP) certified container. The equipment would need to be cut into appropriate sized pieces before removal from the glovebox/hood. The pieces would be double bagged with sharp corners and edges taped to prevent ripping of the bags and placed in standard waste boxes (SWB) or 210-L (55-gal.) drums. The SWBs and drums would then be sent to the waste receiving and packaging (WRAP) facility for later permanent disposal at the WIPP.

The gloveboxes/hoods would be decontaminated, sealed, and passively vented in the same manner as Alternative 2. The floors and walls of the CAR and the Mix room would be decontaminated in the same manner as in Alternative 2.

All slab tanks, except TK-105 and TK-106, would be sealed in the same manner as in Alternative 2. TK-105 and TK-106, are too large to place in a glovebox/hood and have a history of weeping plutonium at the south end of the tanks. Attempts to stop the leaks by caulking or painting have been successful for only a short time and had to be repeated as necessary. Attempting to isolate and seal these tanks could be unsuccessful over an extended period of time. Therefore, a greenhouse would be erected and the tanks cut up and placed in SWBs or 210-L drums.

The remaining tanks, piping, tubing, instrumentation, vessels, and ventilation systems would be handled in the same manner as Alternative 2. The hoist and

trolley crane located in the Mix room would be removed from service and mothballed.

Minimal maintenance and surveillance would be required until turnover to the D&D contractor. The estimated cost for Alternative 3 is \$1,024,737 with an estimated 13,327 manhours. Appendix A, pages 25 through 38, contains the detailed cost estimates. Appendix B contains the schedule for Alternative 3.

Advantages

The main advantage of Alternative 3 over Alternative 2 is the removal of equipment from the gloveboxes/hoods and the removal of TK-105 and TK-106. Removing the equipment from the gloveboxes/hoods would allow for better decontamination of the gloveboxes/hoods, thus, lowering the amount of residual plutonium in the facility. With the gloveboxes/hoods cleaner and the remaining contamination stabilized, the concerns with the passively venting HEPA filter (as described in the disadvantages section of Alternative 2) are lessened.

By removing TK-105 and TK-106, the leaking contamination from this source is eliminated.

Disadvantages

Only a portion of the Pu source term would be removed. There is still the possibility that contamination exists under the gloveboxes/hoods that would not get fixed in place. By not removing/moving the gloveboxes/hoods in the CAR, it is not possible to be sure that all contamination is removed or fixed in place.

As in Alternative 2, the HEPA canister filters fitted into the ports on the gloveboxes/hoods, to be used as passive ventilation, are designed for low airflow. There is the remote possibility that the equalization airflow could exceed the filters design limit. Although, with the gloveboxes/hoods being cleaner in Alternative 3, the concern is lessened.

Alternative 4: Stage-Wise Removal

Alternative 4 differs from Alternative 3 in that it removes all major equipment, most minor equipment, and cleans or fixes in place any remaining contamination. Work would take place in a stage-wise manner. Equipment with larger concentrations of materials are removed first.

Electrical

Normal and emergency power would be turned off in the CAR and the Mix room, except for lighting, fire alarm, receptacles/outlets, air sampler, exhaust ventilation system, and constant air monitoring on the main exhaust stack. When equipment is removed, the power would be turned off before disconnecting and removing the cables from the equipment. All accessible electric components associated with the equipment would be removed. After the work in Alternative 4 is completed, the ventilation, receptacle/outlets, lighting, and fire protection system would be turned off. For safety purposes, the fire protection system should be drained and disconnected last. Turning off the fire protection system is contingent on being able to zero value the building.

Heating, Ventilating, and Air Conditioning

Currently, the supply ventilation system is off and air is supplied by infiltration. The supply ventilation system may need to be restarted if the required number of room air changes cannot be met through increasing the exhaust rate and, thus, the rate of infiltration. The confinement HVAC system would need to be reactivated to full functionality.

Environmental

Removing waste and equipment has the potential to emit fugitive radioactive air emissions. An NOC must be submitted to the WSDOH.

If asbestos is suspected, a good faith inspection must be performed and the BCCAA must be notified ten working days prior to work beginning. All asbestos work must comply with 40 CFR 61 and the agreement with the BCCAA. Since the asbestos

would be assumed to be radioactively contaminated, the material would be disposed of in burial boxes and sent to the disposal trenches in the 200-West Area.

A notice to Ecology could be necessary if hazardous air emissions from cutting up items of contaminated heavy metals would be released.

Alternative 4 would probably require an EA to analyze the unknowns associated with the hazardous and radioactive materials (e.g., location and dose exposure levels in areas currently inaccessible as in and around gloveboxes and/or tanks).

Alternative 4 would produce radioactive and mixed waste requiring storage and/or disposal.

Description of Alternative

All equipment is required to be disposed of in a WIPP certified container, either a 210-L drum or an SWB. Equipment too large for either of these containers would be size reduced. Equipment pieces would be double wrapped in plastic with any sharp edges or protrusions covered with tape to protect the plastic from cuts. All containers would be processed through the WRAP facility for certification and stored for eventual shipment to WIPP for disposal.

Stage 1:

The first activity for equipment removal would be to isolate the equipment from all systems except any required safety systems. Piping and tubing systems would be cut and capped using the same method as in Alternatives 2 and 3. The next step would be to remove all accessible equipment within the glovebox and package it for disposal. Most glovebox internal equipment should not require size reduction, except for some of the slab tanks. Removal of equipment would include disassembly and cutting to reduce size. Once internal equipment is removed and the gloveboxes are isolated, the inside and outside if required, would need to be painted with the fixative to provide contamination control in preparation for size reduction. The final step prior to size reduction would be to construct a ventilated greenhouse

around the glovebox and disconnect any remaining safety systems and the active ventilation system.

The first step in size reducing the old style gloveboxes would be to remove the plexiglass windows. The remaining framework would be cut up into manageable pieces.

Tanks would be isolated and removed for disposal. If size reduction is required, the fixative would be applied to accessible contaminated areas. When there are contaminated areas that are not accessible with the fixative, the size reduction would need to be performed inside a ventilated greenhouse. When this stage is completed, the majority of the plutonium would have been removed (an actual percentage of removal is not possible because the total plutonium held in the facility is not known, i.e some equipment and places could not be analyzed by nondestructive analysis).

The estimated cost for the first stage of Alternative 4 is \$1,266,891 with an estimated 14,427 manhours. Appendix A, pages 39 through 51, contain the detailed cost estimate.

Stage 2:

The next logical step would be to remove the other piping and equipment that is known or highly suspected of containing high levels of contamination. Equipment would include the exhaust ventilation system up to the first stage of HEPA filtration outside of the building. Suspect piping and tubing would include the transfer lines, vent lines, and vacuum lines.

Transfer lines have been directly exposed to high levels of contamination and are a prime target for removal. Vessel vent lines are not directly exposed but may contain contamination due to migration or the venting of contaminated air. The exhaust outlet from the gloveboxes and hoods were not originally protected with HEPA filters. The exhaust ventilation system up to the first stage of HEPA filtration

outside the building is most likely contaminated. Therefore, the last step of stage 2 would remove the CAR and the Mix room exhaust ventilation system up to the first stage of HEPA filtration outside the building.

The estimated cost for the second stage of Alternative 4 is an additional \$99,165 with an estimated 1,004 additional manhours. Appendix A, pages 52 through 63, contains the detailed cost estimate.

Stage 3:

Stage 3 would include removal of all remaining equipment, cleaning and applying a fixative to contaminated concrete, and removing the remaining confinement ventilation system (ducts, filters and fans). Once the work performed by stages 1 and 2 is completed, all the remaining piping, wiring, and instrumentation can be removed from the CAR and the Mix room. This activity would leave bare walls exposed that may contain embedded contamination. However, contamination is unlikely due to the application of a fiber glass reinforced resin surface (Amercoat No. 74) that was applied to all the interior concrete surfaces of the CAR and to the concrete walls and plaster ceiling in the Mix room during initial construction. After a radiological survey determines the location of contamination on the walls and floor, the areas would be wiped clean of any contamination not removed by wiping and would be painted over. The hoist and trolley crane located in the Mix room would be removed from service and mothballed. The remaining task would be to remove the Zone 2 confinement HVAC system in its entirety.

The estimated cost for stage 3 of Alternative 4 is an additional \$355,088 with an estimated 4,284 additional manhours. Appendix A, pages 64 through 76, contains the detailed cost estimate.

Minimal maintenance and surveillance would be required until turnover to the D&D contractor. The estimated total cost for Alternative 4 is \$1,721,144 with an estimated total of 19,715 manhours. Appendix B contains the total schedule to complete Alternative 4.

Advantages:

The majority of the contamination source term would be removed, thereby, reducing the possibility of exposure to people and the environment. Work performed in Alternative 4 helps future D&D operations on the facility.

Disadvantages:

It is unlikely that the facility would be clean enough to be classified as "other industrial." The application of Alternative 4 is very costly and more removal than is necessary by any subsequent D&D activity may be performed.

Alternative 5: Turnover to the EM-60 Program

Alternative 5 would turn the CML over to the DOE EM-60 program, managed by BWHC, for use as a D&D training facility and a site for testing new D&D technologies.

After a general housekeeping is performed, Alternative 5 would leave the facility as is and the CML would be turned over to the EM-60 program. The EM-60 program would be responsible for continued maintenance, surveillance, and operation of the facility and grounds. A formal cost estimate was not performed for Alternative 5 due to its relatively low cost compared to the other alternatives. However, a rough order of magnitude (ROM) cost estimate for Alternative 5 is \$10,000 with an estimated 80 manhours mainly for administrative work to turn over the facility. This cost does not include the EM-60 program deactivation costs.

Communications are underway with BWHC, LMHC, and RL regarding the transfer of the 209E Facility to BWHC for use as a training facility.

Advantages

The CML is an isolated self-contained laboratory facility with office space, meeting rooms, a control room, and a changeroom that provides a good setting for training. There are rooms for additional training needs and sufficient parking around the building.

The CAR and the Mix room contain typical gloveboxes and equipment that would be found in other DOE facilities that handled fissile materials. The CML would be an ideal training center for teaching D&D workers the techniques required for safe and efficient D&D operations. It would also provide an ideal facility to test new D&D systems. New decontamination methods and size reduction equipment could be tested in the facility.

Disadvantages

Although contamination levels are not excessive, it would still be a challenge to decontaminate to non-transuranic levels and to provide a realistic evaluation of the methods effectiveness.

IV. IDENTIFICATION OF PREFERRED ALTERNATIVE

A. EVALUATION OF ALTERNATIVES

Alternative 1, Leave As Is, was ruled out as a viable alternative early in the study because it did not meet RL objectives for closure of nonactive facilities. LMHC also expressed their disinterest in this alternative.

Alternative 2, Fix In Place, is one of the more cost effective alternatives, but it does not leave the building in the safest state for personnel and the environment. In a less complex facility, this would be a good solution but it does not meet the needs of the CML.

Alternative 3, Removal and Fix In Place, mitigates the primary concerns encountered in Alternative 2 by removing the equipment in the gloveboxes/hoods and the leaking tanks. Although costs for Alternative 3 are approximately 29% more than costs for Alternative 2, the facility would be left in a safer state for personnel and the environment.

Alternative 4, Stage-Wise Removal, is the most extensive and thorough of all the alternatives, but is also the most expensive. While this alternative aides future D&D

work, it most likely performs more work than is necessary to close the facility. Alternative 4 leaves the facility in a safer state for personnel and the environment than the other alternatives, but does not balance the increase in cost, nearly 60% more than Alternative 3.

Alternative 5, Turnover to the EM-60 Program, is the most cost effective of all alternatives. The alternative does not include any decontamination but turning the facility over to the EM-60 program would result in the facility receiving decontamination via training and testing of new technologies. This is a win-win solution: the building would eventually receive the needed D&D work, a facility would be provided to train workers, and new D&D technologies could be developed.

B. PREFERRED ALTERNATIVE

Alternative 5 is the preferred alternative. It is the most cost effective alternative and maintains the building in a safe state. Hanford and other DOE sites would benefit by implementing this alternative. D&D workers would be trained in new and safer techniques, and new D&D technologies would be developed that may save lives and tax payer dollars in the future.

To execute Alternative 5, RL and LMHC would have to resolve the best course of action to achieve turning over the facility to the EM-60 program. A second alternative was chosen if RL determines that Alternative 5 is not a viable solution. The second preferred alternative is Alternative 3, Remove and Fix In Place, because it presents the best balance of safety and cost effectiveness of the other four alternatives.

C. UNCERTAINTIES

The only uncertainty is if RL will decide that turnover of the facility to the EM-60 program is a viable solution. Therefore, a backup alternative is presented.

The uncertainties in Alternative 3 are whether there is contamination under the gloveboxes in the CAR and if sealing the underground tanks with grout would prove

satisfactory. While contamination under the gloveboxes is not a safety problem while the building is idle, it becomes an unknown for D&D workers. There is some work being performed in Savannah River with "smart grout" that may work better for filling the underground tanks. This process should be considered if Alternative 3 is chosen.

V. REQUIRED CHANGES TO IMPLEMENT PREFERRED ALTERNATIVE

Alternative 5, Turnover to the EM-60 Program, would require the following activities:

- Resolution of the current unresolved safety question, specific to contamination control.
- Completion of the facility SAR.
- Completion of the facility housekeeping and waste disposal effort.
- Completion of a property and equipment transfer form.
- Financial transfer of current and future operating funds.

Alternative 3, Removal and Fix In Place, would require the following actions:

- Resolution of the current unresolved safety question, specific to contamination control.
- Completion of the facility SAR.
- Completion of the facility housekeeping and waste disposal effort.

VI. REFERENCES

A. DOCUMENTS

Byrd, W.H.; March 1959; *Specifications for Critical Mass Laboratory Building 209-E*; HWS-6471; General Electric Company, Richland, Washington.

Divine, J.R.; November 1988; *CML Tube Pits*; Internal Memo; Pacific Northwest Laboratories, Richland, Washington.

Dodd, Edwin III; January 1997; *Preliminary Hazards Category Evaluation For Possible End State Conditions at 244AR Vault and 209E Facilities*; Link Technologies, Incorporated, Richland, Washington.

Flowers, C.D.; December 1988; *Project D-370 Tubing Failure*; Internal Letter; Pacific Northwest Laboratories, Richland, Washington.

Hamrick, D.G. and M.S. Gerber; September 1996; *PUREX/UO₂ Facilities Deactivation Lessons Learned History*; WHC-SP-1147, Rev. 1; Westinghouse Hanford Company, Richland, Washington.

Lakes, M.E.; October 1996; *Preliminary Hazards Analysis, 209-E Bldg, Critical Mass Laboratory*; WHC-SD-WM-TI-789, Rev. 0; Westinghouse Hanford Company, Richland, Washington.

Metcalf, I.L.; August 1993; *308 Building Shutdown Plan*; WHC-SD-FL-SSP-001, Rev. 1; Westinghouse Hanford Company, Richland, Washington.

Morton, M.R.; March 1997; *Facility Transition Instruction*; BHI-00961, Rev. 1; Bechtel Hanford Company, Richland, Washington.

Peterson, R.S.; November 1958; *General Specification for Glove Type Hoods*; HWS-6480; General Electric Company, Richland, Washington.

Radiological Survey Report; WH-001, Rev. 009; Westinghouse Hanford Company, Richland, Washington.

Reardon, W.A., et. al; August 1960; *Hazards Summary Report for the Hanford Plutonium Critical Mass Laboratory*; HW-66266; General Electric Company, Richland, Washington.

Status Report for Hanford's Critical Mass Laboratory, Rev. 0; February 1989; Pacific Northwest Laboratories, Richland, Washington.

Tuyl, T.D.; March 1991; *Fixing Contamination at the Critical Mass Laboratory*; Internal Letter; Pacific Northwest Laboratories, Richland, Washington.

Wilson, B.; February 1996; *Dangerous Waste Compliance Inspection at the 209E Facility on September 15, 1995*; Letter; State of Washington Department of Ecology, Kennewick, Washington.

B. DRAWINGS

H-2-32570, Rev. 2; 1985; *Bellows Tank*; General Electric Company, Richland, Washington.

H-2-32567, Rev. 3; 1988; *Mix Dump & Storage Tank*; General Electric Company, Richland, Washington.

H-2-33854, Rev. 1; 1987; *Alternate Solution Storage Tank TK-103 & TK-104*; Pacific Northwest Laboratories, Richland, Washington.

H-2-33856, Rev. 2; 1987; *CFRP Assembly*; Pacific Northwest Laboratories, Richland, Washington.

H-2-44344, Rev. 4; 1981; *Exhaust System Critical Assembly & Mix rooms*; General Electric Company, Richland, Washington.

H-2-44357, Rev. 3; 1960; *Reactor Hood Assembly*; General Electric Company, Richland, Washington.

H-2-44358, Rev. 3; 1960; *Reactor Hood Frame*; General Electric Company, Richland, Washington.

H-2-44359, Rev. 3; 1960; *Reactor Hood Misc. Details*; General Electric Company, Richland, Washington.

H-2-44361, Rev. 2; 1960; *Reactor Hood Dump Tank*; General Electric Company, Richland, Washington.

H-2-44371, Rev. 5; 1983; *Process Area Flow Diagram*; General Electric Company, Richland, Washington.

H-2-44373, Rev. 4; 1988; *HO-130 U Pump Glovebox Assembly & Details*; Pacific Northwest Laboratories, Richland, Washington.

H-2-44380, Rev. 2; 1960; *Critically Safe Crib Waste Hold-up Tank*; General Electric Company, Richland, Washington.

H-2-95713, Rev. 1; 1985; *Process Piping Engineering Flow Diagram*; Pacific Northwest Laboratories, Richland, Washington.

H-2-95719, Rev. 1; 1988; *HO-140 Assembly Hood #1 Process Piping*; Pacific Northwest Laboratories, Richland, Washington.

H-2-95723, Rev. 2; 1985; *HO-170 Assembly Hood #2 Process Piping*; Pacific Northwest Laboratories, Richland, Washington.

H-2-95754, Rev. 1; 1988; *Fire Protection Sprinkler Sys, Zone Plan*; Pacific Northwest Laboratories, Richland, Washington.

H-2-95757, Rev. 3; 1988; *TK-101 & TK-102 Solution Storage Tanks*; Pacific Northwest Laboratories, Richland, Washington.

H-2-95758, Rev. 2; 1988; *Metallic Bellows*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96013, Rev. 2; 1986; *Flow Diagram Composite Crit Assy Room*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96014, Rev. 2; 1986; *Piping & Instrument Diagram TK-108 & TK-111*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96015, Rev. 2; 1986; *Piping & Instrument Diagram HO-170*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96016, Rev. 2; 1986; *Piping & Instrument Diagram HO-140*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96017, Rev. 2; 1986; *Piping & Instrument Diagram TK-160*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96018, Rev. 2; 1986; *Piping & Instrument Diagram HO-120*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96019, Rev. 2; 1986; *Piping & Instrument Diagram TK-105 & TK-106*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96020, Rev. 2; 1986; *Piping & Instrument Diagram HO-130*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96021, Rev. 2; 1986; *Piping & Instrument Diagram TK-101 & TK-102*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96022, Rev. 2; 1986; *Piping & Instrument Diagram TK-103 & TK-104*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96023, Rev. 2; 1986; *Piping & Instrument Diagram HO-200*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96024, Rev. 2; 1986; *Piping & Instrument Diagram HO-230*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96032, Rev. 1; 1987; *HO-230 Storage Tank Enclosure*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96033, Rev. 0; 1985; *HO-230 Piping & Stor Tanks Instl Details*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96041, Rev. 0; 1985; *Equipment Arrangement HO-200 Mix room Glovebox Plan/Section*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96043, Rev. 0; 1985; *Piping HO-200 Mix room Glovebox Plans*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96046, Rev. 0; 1985; *Vessel Assembly TK-206 Prover Vessel*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96047, Rev. 0; 1985; *Vessel Assembly TK-213 Concentrator*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96048, Rev. 0; 1985; *Vessel Assembly TK-242 Closed Loop Expansion Tank*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96049, Rev. 0; 1985; *Vessel Assembly TK-215 and TK-216 Process Cnds Catch Tk*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96050, Rev. 0; 1985; *Vessel Assembly TK-231, 232 & 233 Pu Storage Tanks*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96051, Rev. 0; 1985; *Vessel Assembly TK-234 & 235 Pu Storage Tanks*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96052, Rev. 0; 1985; *Piping HO-120 Pu Pump Glovebox Plan & Sections*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96054, Rev. 0; 1985; *Piping HO-140 Modifications Critical Assembly Hood #1*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96057, Rev. 0; 1985; *Equipment Arrangement Critical Assy, Mix & Control Rooms*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96060, Rev. 1; 1987; *Glovebox Assembly & Installation HO-200*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96071, Rev. 0; 1985; *Plutonium Pump Glovebox Assembly HO-120*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96072, Rev. 0; 1986; *Piping & Instrument Diagram HVAC Supply & Process Exh*; Pacific Northwest Laboratories, Richland, Washington.

H-2-96073, Rev. 0; 1985; *HVAC Plans & Schedules*; Kaiser Engineers Hanford, Richland, Washington.

H-2-96074, Rev. 0; 1985; *HVAC Sections & Details*, Kaiser Engineers Hanford, Richland, Washington.

H-2-96085, Rev. 0; 1985; *Instm Eqpt Arr Plan Critical Assy Room*, Kaiser Engineers Hanford, Richland, Washington.

APPENDIX A

Cost Estimates

	<u>Page</u>
Alternative 1: Leave As Is	A-1
Alternative 2: Fix In Place	A-13
Alternative 3: Removal and Fix In Place	A-25
Alternative 4: Stage-Wise Removal	
Stage 1	A-39
Stage 2	A-52
Stage 3	A-64

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAB1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHMC01 - PROJECT COST SUMMARY

PAGE 1 OF 9
 DATE 06/17/97 13:04:01
 BY DKH/RNO

SORT	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY %	TOTAL DOLLARS
FDNW	FLUOR DANIEL NORTHWEST	0	0	0
LWHC	LOCKHEED MARTIN HANFORD CORP.	72,452	30	94,188
	SUBTOTAL	72,452	30	94,188
SITE	SITE ALLOCATIONS	0	0	0
	PROJECT TOTAL	72,452	30	94,188

TYPE OF ESTIMATE PLANNING/FEASIBILITY ESTIMATE JUNE 17, 1997

FDNW LEAD
 ESTIMATOR

ESTIMATING
 MANAGER

PROJECT
 MANAGER

Chris H. Brewick

CLIENT

REMARKS:

DRAFT

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAB1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHNCR02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 2 OF 9
 DATE 06/17/97 13:04:06
 BY DKH/RHO

WBS DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL	
	SUBTOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	ALLOCAT'N	DOLLARS		
310100 ALTERNATIVE 1 - LEAVE AS IS	72,452	0.00	0		72,452	30	21,736		94,188	0	0	94,188		
PROJECT TOTAL	72,452	0.00	0		72,452	30	21,736		94,188	0	0	94,188		

PAGE 3 OF 9
DATE 06/16/97 14:17:07
BY DKH/RWO

** TEST - INTERACTIVE ESTIMATING **
2096 FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCROS - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/FFRUL5
FILE NO. 2475A81

1. ESTIMATE PURPOSE

THIS ESTIMATE WILL BE USED FOR A SCOPING STUDY.
2. ESTIMATE TECHNICAL BASIS

A. THIS ESTIMATE HAS BEEN PREPARED FOR LOCKHEED MARTIN HANFORD CORP. AS REQUESTED BY FNDW PROJECT MANAGEMENT.
B. A ROUGH DESCRIPTION OF THE SCOPE OF WORK MAY BE FOUND IN THE OUTLINE OF ALTERNATIVES, AN UNDATED AND UNNUMBERED DOCUMENT.
C. THE FOLLOWING CONSTRAINTS AND/OR SPECIAL CONDITIONS EXIST: ALL WORK DONE IN THE CRITICAL ASSEMBLY ROOM AND IN THE MIXING ROOM WILL REQUIRE FOLLOWING THE APPROPRIATE RADIATION WORK PROCEDURE.
3. ESTIMATE METHODOLOGY

A. DIRECT COSTS:
 - (1) CONSTRUCTION LABOR, MATERIAL AND EQUIPMENT UNITS HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD COMMERCIAL ESTIMATING RESOURCES, PUBLISHED ESTIMATING MANUALS AND R.S. MEANS
- B. DIRECT COST FACTORS
 - (1) SALES TAX HAS BEEN APPLIED TO ALL MATERIALS AND EQUIPMENT PURCHASES AT 3%.
 - (2) NO WAREHOUSING COSTS ARE SHOWN SINCE THEY ARE CONSIDERED TO BE INCLUDED IN THE MATERIAL PROCUREMENT RATE (MPR).
 - (3) AN ESTIMATING FACTOR OF 15% HAS BEEN APPLIED TO DIRECT CRAFT LABOR FOR GENERAL REQUIREMENTS AND
 - (4) 23.58% FOR TECHNICAL SERVICES, 2% OF DIRECT CRAFT LABOR COSTS.
 - (5) CONSUMABLES ARE FACTORED (GROUP 1) FACTORS ARE APPLIED AGAINST DIRECT LABOR FOR ACTUAL TIME LOST DUE TO THE PERSONNEL PROTECTIVE EQUIPMENT AND PROCEDURES. THE RATES WHICH HAVE BEEN APPLIED ARE AS FOLLOWS:
 PROTECTIVE CLOTHING FACTOR HAS BEEN APPLIED AT 15%.
 MASK WORK AT 85% PLUS 15% FOR PROTECTIVE CLOTHING.
 CONTAMINATION RESTRICTIONS ASSOCIATED WITH RADIATION DOSE LIMITS (BURNOUT) HAVE NOT BEEN CALCULATED AS IT IS NOT BELIEVED TO BE A CONCERN FOR THESE ACTIVITIES.
 - (6) OVERTIME REQUIREMENTS AND SHIFT DIFFERENTIAL PAY FOR CRAFT LABOR WILL NOT BE REQUIRED FOR THIS WORK, AS STRAIGHT TIME, 40 HOUR WEEKS ARE DEEMED ADEQUATE TO ACCOMPLISH THIS WORK.
 - (7) GENERAL FOREMAN FACTOR OF 7% HAS BEEN APPLIED TO DIRECT CRAFT LABOR CREWS.
 - (8) A FACTOR OF 10% HAS BEEN APPLIED TO DIRECT CRAFT LABOR TO ALLOW FOR USAGE OF GOVERNMENT OWNED EQUIPMENT CONTROLLED BY DYNACORP.
- C. RATES
 - (1) FLUOR DANIEL NORTHWEST LABOR RATES ARE BASED UPON THE FLUOR DANIEL FEDERAL OPERATIONS (FEDFO) DISCLOSURE STATEMENT AND APPROVED PROVISIONAL BILLING RATES. FOR ESTIMATING PURPOSES, AVERAGE RATES BY OPERATIONS CODE HAVE BEEN DEVELOPED BASED UPON RECENT COST HISTORY.
 - (2) FLUOR DANIEL NORTHWEST SERVICES (CONSTRUCTION CRAFT LABOR) RATES ARE THOSE LISTED IN APPENDIX A TO THE HANFORD SITE STABILIZATION AGREEMENT.
 - (3) FOR & PHMC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) FOST 321R REPORT ORGANIZATION RATES PLUS ADJERS.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED HAZEL HANFORD CORP.
 2100 E. 9TH AVE., SUITE 200
 FILE NO. 2475AAB1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 4 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RMO

- D. SITE ALLOCATIONS FACTORS
- SITE ALLOCATIONS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 14% FOR FDH, 10% FOR FOMUS (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 16.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MPR RATE OF 7.0% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).

FDH APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:

- (1) FDH GFS/G&A CM FACTOR: A COMPOSITE FACTOR OF 33.04% HAS BEEN APPLIED TO TOTAL FDH FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE.
- (2) AECM COSTS = 33.04%, FOMUS CONSTRUCTION LABOR = 28.37%, FOMUS CONSTRUCTION MANAGEMENT LABOR = 35.04%, FDH CONTRACT MANAGEMENT AND ADMINISTRATION = 33.04%, COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDH MATERIAL COST WHICH INCLUDES FDH MPR/G&A AND MATERIAL G&A/FEE OF 16.7%.
- (3) A MPR OF 7%.

4. ESCALATION
- ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FH-50.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR DEFICIENCIES IN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EW-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

C. METHODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:

WBS TANKVY CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO OCCUR THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

PAGE 5 OF 9
DATE 06/16/97 14:17:07
BY DKH/RMO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PMMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCKERD, HUNTERD CORP.
FILE NO. 413647/3RUL5
FILE NO. 2475AAB1

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, PIPE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL PUBLICATIONS, VERIFICATION SAMPLING AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF THESE ARE REQUIRED, THEY WILL BE ADDITIONAL COSTS.
- B.) THESE ASSUMPTIONS WERE MADE BASED ON THE INFORMATION AVAILABLE AND GROSS ASSUMPTIONS WERE MADE.
- C.) THE ESTIMATE ASSURED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE R08 REPORT.

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHNCR04 - COMPANY/WBS SUMMARY
 FLUOR DANIEL NORTHWEST, INC.
 LOCKNEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAB1

PAGE 6 OF 9
 DATE 06/17/97 13:04:10
 BY DKH/RWO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL	
		SUBTOTAL	%	%	TOTAL	TOTAL	%	TOTAL	TOTAL	ALLOCAT'N	DOLLARS				
FDNW	FLUOR DANIEL NORTHWEST														
	310100 ALTERNATIVE 1 - LEAVE AS IS	0	0.00	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL FDNW FLUOR DANIEL NORTHWEST														
LWHC	LOCKNEED MARTIN HANFORD CORP.														
	310100 ALTERNATIVE 1 - LEAVE AS IS	72452	0.00	0	72452	30	21736	94188	0	94188					
	TOTAL LWHC LOCKNEED MARTIN HANFORD CORP.	72452	0.00	0	72452	30	21736	94188	0	94188					
	PROJECT TOTAL	72,452	0.00	0	72,452	30	21,736	94,188	0	94,188					

PAGE 7 OF 9
DATE 06/17/97 13:04:13
BY DKH/RWO

** IEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
PNCROS - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/F3RULS
FILE NO. Z475AAB1

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONSTRUCTION MANAGEMENT %	TOTAL	OTHER COSTS	SUB TOTAL	TOTAL
310100	ALTERNATIVE 1 - LEAVE AS IS	72452	0.00	0	0	0	72452
PROJECT TOTAL		72,452		0	0	0	72,452

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAB1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHMCR06 - SITE ALLOCATIONS BY WBS

PAGE 8 OF 9
 DATE 06/17/97 15:03:42
 BY DKH/RWO

WBS	DESCRIPTION	ESTIMATE	DYN	FDH	GFS/G&A	FDH	MPR	FDH	GFS/G&A	FDH	MPR/G&A	SITE	ALLOC
		SUBTOTAL	EQ.USAGE	CONST.	MGMT	F.P./S.C.	LABOR					SUBTOTAL	
310100	ALTERNATIVE 1 - LEAVE AS IS	72452	0	0	0	0	0	0	0	0	0	0	0
PROJECT TOTAL		72,452	0	0	0	0	0	0	0	0	0	0	0

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAB1

** IEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHMCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 13:04:16
 BY DKH/RMO

WBS	DESCRIPTION	SITE ALLOC	ESCALATION	SUB	CONTINGENCY	TOTAL
		SUBTOTAL	% TOTAL	TOTAL	% TOTAL	DOLLARS
310100	ALTERNATIVE 1 - LEAVE AS IS	0	0.00	0	0	0
	PROJECT TOTAL	0	0.00	0	0	0

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
 PHNCR08 - ESTIMATE DETAIL BY WBS / COST CODE
 1
 PAGE 06/17/97 13:04:19
 BY DKH/RWO

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN MANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAB1

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	SUB- MATERIAL	CONTRACT	EQUIP- MENT	ORSP / B & I DOLLARS	TOTAL
310100	ALTERNATIVE 1 - LEAVE AS IS										
310100.00	TECHNICAL SERVICES										
310100.0001000	***** DEFINITIVE DESIGN, ENGINEER- ING/INSPECTION, PROJ. MGMT. ***** THERE ARE NO COSTS FOR ANY OF THESE IN THIS ALTERNATIVE	000	0	0	0	0	0	0	0	0	0
310100.0001001	***** THERE ARE NO COSTS FOR ANY OF THESE IN THIS ALTERNATIVE	000	0	0	0	0	0	0	0	0	0
	SUBTOTAL				0	0	0	0	0	0	0
	TOTAL				0	0	0	0	0	0	0
310100.02	COST CODE 00000 WBS 310100 (ESCALATION 0.00% - CONTINGENCY 30.00 %)				0	0	0	0	0	0	0
310100.0201000	SITENWORK ***** CONTINUE CURRENT SURVEIL- LANCE AND MAINTENANCE *****	810	0	0	0	0	0	0	0	0	0
310100.0201002	SURVEILLANCE AND MAINTENANCE (209-E)	810	1	L/S	900	45000	0	0	0	0	45000
310100.0201004	SURVEILLANCE AND MAINTENANCE (CR18)	810	1	L/S	10	500	0	0	0	0	500
310100.0201012	HEALTH PHYSICS SURVEILLANCE ACTIVITIES AT 4 HR/NK	810	1	YR	208	9938	0	0	0	0	9938
310100.0201020	***** POWER HVAC WATER AND LIGHTING FOR ONE YEAR *****	810	0		0	0	0	0	0	0	0
310100.0201022	SANITARY WATER AND SEMER AT \$125/PERSON/YR	810	1	YR	84	4014	0	0	0	0	3000
310100.0201024	ELECTRICAL UTILITY MAINTENANCE	810	1	YR	84	4014	0	0	0	0	4014
310100.0201026	BPA ELECTRICITY	810	1	YR	0	0	0	10000	0	0	10000
	SUBTOTAL				1,202	59,452	0	13,000	0	0	72,452
	TOTAL				1,202	59,452	0	13,000	0	0	72,452

PAGE 2
DATE 06/17/97 13:04:19
BY DKH/RWO

** TEST - INTERACTIVE ESTIMATING **
200E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 1
PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/F3RUL5
FILE NO. Z475AAB1

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR USAGE	EQUIP MATERIAL CONTRACT	SUP- EQUIP- MENT	ONSP / 8 & 1 DOLLARS	TOTAL
	(ESCALATION 0.00% - CONTINGENCY 30.00 %)								

TOTAL WBS 310100 ALTERNATIVE 1 - LEAVE AS IS	1,202	59,452	0	13,000	0	0	0	72,452
--	-------	--------	---	--------	---	---	---	--------

PAGE 3
DATE 06/17/97 13:04:19
BY DKH/RWO

[illegible]

1,202	0	0	13,000	0	72,452
59,452					

FLUOR DANIEL NORTHWEST, INC.
 LOCKREED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475ARCI

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PHMCR01 - PROJECT COST SUMMARY

PAGE 1 OF 9
 DATE 06/17/97 13:23:34
 BY DKH/RMO

ESTIMATE	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY %	TOTAL DOLLARS
FDNW	FLUOR DANIEL NORTHWEST	342,006	30	444,608
LWMC	LOCKREED MARTIN HANFORD CORP.	99,804	30	129,745
SUBTOTAL		441,810	30	574,553
SITE	SITE ALLOCATIONS	119,316	30	155,111
PROJECT TOTAL		561,126	30	729,464

TYPE OF ESTIMATE: PLANNING/FEASIBILITY
 DATE: JUNE 17, 1997
 FDNW LEAD: *DKH*
 ESTIMATOR: *DKH*
 PROJECT MANAGER: *Chris H. Breivick*
 CLIENT:

REMARKS:

ESTIMATE NO. 1
 FIX PAGE
DRAFT

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/FSRUL5
 FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
 200E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE ALTERNATIVE 2
 PERCRO2 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 2 OF 9
 DATE 06/17/97 13:23:37
 BY DKH/RMO

WBS DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL DOLLARS
	SUBTOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	ALLOCAT'N		
310200 ALTERNATIVE 2 - FIX IN PLACE	441810	0.00	0		441810	30	132543		574353		155111		729464
PROJECT TOTAL	441,810	0.00	0		441,810	30	132,543		574,353		155,111		729,464

FLUOR DANIEL NORTHWEST, INC.
 10000 NE 15TH AVE, SUITE 200
 LOS ANGELES, CA 90045/39UL
 FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 4 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RMO

- D. SITE ALLOCATIONS FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 1% FOR FDHW, 10% FOR FDNWS (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 16.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MPR RATE OF 7.0% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).

FDHW APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:

- (1) FDH GFS/G&A CM FACTOR: A COMPOSITE FACTOR OF 33.04% HAS BEEN APPLIED TO TOTAL FDHW FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE.
- (2) FDH GFS/G&A LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO TOTAL FDHW LABOR COSTS AS FOLLOWS:
 AE/GFS COSTS = 33.04%, FDNWS CONSTRUCTION LABOR = 28.37%, FDNWS CONSTRUCTION MANAGEMENT LABOR = 33.04%, FDHW CONTRACT MANAGEMENT AND ADMINISTRATION = 33.04%. COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDHW MATERIAL COST WHICH INCLUDES A MPR OF 7.7% AND MATERIAL G&A/FEE OF 16.7%.
- (3) A MPR OF 7.7% AND MATERIAL G&A/FEE OF 16.7%.

4. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FM-50.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EM-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

C. METHODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:
 WBS 210VXX CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO SURFACE THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

FLUOR DANIEL NORTHWEST, INC.
 10000 WEST 10TH AVE.
 JOB NO. E19457/F3RUL5
 FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 5 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RMO

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, PIPE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL PUBLICATIONS, VERIFICATION SAMPLING AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF THESE ARE REQUIRED, THE ESTIMATE WILL BE INFLUENCED.
- B.) THE ESTIMATE ASSUMES THAT ALL MATERIALS WILL BE REMOVED FROM THE SITE.
- C.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE ROB REPORT.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PHCR04 - COMPANY/WBS SUMMARY

PAGE 6 OF 9
 DATE 06/17/97 13:23:40
 BY DKH/RMO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL	
		SUBTOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	ALLOCAT'N	%	DOLLARS	%
F0NW	FLUOR DANIEL NORTHWEST														
	310200 ALTERNATIVE 2 - FIX IN PLACE	342006	0.00	0		342006		30	102602	444608		155111		599719	
	TOTAL F0NW FLUOR DANIEL NORTHWEST	342006	0.00	0		342006		30	102602	444608		155111		599719	
LWMC	LOCKHEED MARTIN HANFORD CORP.														
	310200 ALTERNATIVE 2 - FIX IN PLACE	99804	0.00	0		99804		30	29941	129745		0		129745	
	TOTAL LWMC LOCKHEED MARTIN HANFORD COR	99804	0.00	0		99804		30	29941	129745		0		129745	
PROJECT TOTAL		441,810	0.00	0		441,810		30	132,543	574,353		155,111		729,464	

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAC1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PHMCRO6 - SITE ALLOCATIONS BY WBS

PAGE 8 OF 9
 DATE 06/17/97 15:04:17
 BY DKH/RMO

WBS	DESCRIPTION	ESTIMATE	DYN	FDN	GFS/G&A	FDN	MPR	FDN	GFS/G&A	FDN	MPR/G&A	SITE	ALLOC
=====	=====	SUBTOTAL	EQ.USAGE	CONST.MGMT	F.P./S.C.	LABOR	MATERIAL	SUBTOTAL	=====	=====	=====	=====	=====
310200	ALTERNATIVE 2 - FIX IN PLACE	403837	14518	12546	0	87420	4832	119316					
	PROJECT TOTAL	403,837	14,518	12,546	0	87,420	4,832	119,316					

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAC1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PHMC07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 13:23:45
 BY DKH/RMO

WBS DESCRIPTION	SITE ALLOC SUBTOTAL	ESCALATION % TOTAL	SUR TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
310200 ALTERNATIVE 2 - FIX IN PLACE	119316	0.00	0	30	35795
PROJECT TOTAL	119,316	0.00	0	30	35,795
			119,316		155,111

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE
 FILE NO. Z475AAC1

PAGE 1
 DATE 06/17/97 13:23:48
 BY DKH/SNO

ACCOUNT	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB-CONTRACT	EQUIP-MENT	OH&P / B & I	TOTAL DOLLARS
310200	ALTERNATIVE 2 - FIX IN PLACE										
310200.00	TECHNICAL SERVICES	000	1 L/S	985	65010	0	0	0	0	0	65010
310200.0002100	***** DEFINITIVE DESIGN *****										
310200.0002200	***** AT 25 % OF CONSTRUCTION *****										
310200.0002200	***** ENGINEERING/ INSPECTION *****	000	1 L/S	650	39000	0	0	0	0	0	39000
310200.0002300	***** AT 15% OF CONSTRUCTION *****										
310200.0002300	***** PROJECT MANAGEMENT *****	000	1 L/S	534	38982	0	0	0	0	0	38982
310200.0002300	***** AT 15% OF CONSTRUCTION *****										
SUBTOTAL	TECHNICAL SERVICES			2,169	142,992	0	0	0	0	0	142,992
TOTAL	COST CODE 00000			2,169	142,992	0	0	0	0	0	142,992
310200.01	GENERAL REQUIREMENTS										
310200.0102000	RPT TO MAN STEP-OFF PAD	810 M	1 L/S	990	47302	0	0	0	0	0	47302
310200.0102000	(MASK)			990	47,302	0	0	0	0	0	47,302
310200.0102000	GENERAL REQUIREMENTS			990	47302						47302
310200.0102000	SUP 100.00%			1,980	94,604	0	0	0	0	0	94,604
TOTAL	COST CODE 81001										
310200.02	WBS 310200										
310200.0202100	(ESCALATION 0.00% - CONTINGENCY 30.00 %)										
310200.02	SITework										
310200.0202100	***** SITEWORK *****	810 M	0	0	0	0	0	0	0	0	0
310200.0202100	***** FIX IN PLACE *****										
310200.0202100	***** APPLY FIXATIVE TO ALL *****	810 M	20000 SF	1680	47023	0	14000	0	0	490	61513
310200.0202100	***** SURFACES, 50 MIL EPOXY. *****	810 M	0	0	0	0	0	0	0	0	0
310200.0202100	***** SEAL GLOVE BOX PORTS, ETC. *****										

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PRMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 2
 DATE 06/17/97 13:23:48
 BY DKH/RWO

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RULS
 FILE NO. 2475AAC1

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR USAGE	EQUIP USAGE	SUB- MATERIAL CONTRACT	EQUIP- MENT	OR&P / B & I DOLLARS	TOTAL
310200.0202122	SEAL GLOVE BOX PORTS, INSTALL BLANK-OFFS WITH SEALANTS. OPENINGS SEALANT CAPS AND SEAL OFF.	810 M	1 L/S	48	1737	0	250	0	0	9 1996
310200.0202124	SEALANT. OPENINGS SEALANT CAPS AND SEAL OFF.	810 M	1 L/S	50	1810	0	300	0	0	11 2121
310200.0202126	CUT AND CAP PIPES	810 M	1 L/S	80	3092	0	250	0	0	9 3351
310200.0202140	DISCONNECT VENTILATION	810 M	0	0	0	0	0	0	0	0 0
310200.0202142	DISCONNECT ACTIVE VENTILLOS, 110 GLOVE BOXES/HOODS, CAP OFF	810 M	1 L/S	24	869	0	240	0	0	8 1117
310200.0202160	CONNECT PASSIVE HEPA	810 M	0	0	0	0	0	0	0	0 0
310200.0202162	CHECK PASSIVE HEPA FILTER VENTILATION SYSTEM TO GLOVE BOX/HOODS, SHOULD ALL BE EXISTING.	810 M	1 L/S	16	579	0	0	0	0	0 579
310200.0202180	SYSTEMS SHUTDOWN	810 M	0	0	0	0	0	0	0	0 0
310200.0202182	SHUTDOWN ALL SYSTEMS NOT ALLOWED FOR SAFETY, ADVANCE	810 M	1 L/S	64	2432	0	500	0	0	18 2950
310200.0202200	POWER, HVAC, WATER AND LIGHTING FOR ONE YEAR	810 M	0	0	0	0	0	0	0	0 0
310200.0202204	ELECTRICAL UTILITY	810 M	1 YR	0	0	0	0	0	0	0 4000
310200.0202206	BPA ELECTRICITY, MINIMAL	810 M	1 YR	0	0	0	0	0	0	0 1200
(MASK)										
SUBTOTAL	SITENOTEK			1,962	57,542	0	15,540	0	545	79,827
	CONSUMABLES 3.20 %			1962	57542		1841			57542
	GENERAL JOSEMAN 7.00 %			274	8055					8055
	GENERAL REQUIREMENTS 15.00 %			629	18470					18470
	SALES TAX 8.00 %				1390					1390
	OR&P (ON MARKUPS ONLY)									113

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
 PIMCRO8 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 3
 DATE 06/17/97 13:23:48
 BY DKH/RNO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP SALES	SUB- MATERIAL	EQUIP- RENT	OR&P 1 DOLLARS	TOTAL
	COST CODE 81002									
	WBS 310200			4,828	141,610	0	18,771	0	658	166,240
	(ESCALATION 0.00% - CONTINGENCY 30.00 %)									
TOTAL										
				4,828	141,610	0	18,771	0	658	166,240
TOTAL WBS 310200 ALTERNATIVE 2 - FIX IN PLACE				8,977	379,206	0	18,771	0	658	403,836

```

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/FSRULS
FILE NO. 2475AAC1

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 2
PHMCRO8 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 4
DATE 06/17/97 13:23:48
BY DKH/RMO

=====
ACCOUNT      DESCRIPTION
NUMBER
=====
COST CODE  QUANTITY  MANHOURS  LABOR  USAGE  MATERIAL  CONTRACT  EQUIP-  OH&P  TOTAL
              / 8 & I  DOLLARS
=====
8,977      379,206      0      18,771      5,200      0      658      403,836

REPORT TOTAL

```

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
PHMCR01 - PROJECT COST SUMMARY

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/F3RUL5
FILE NO. Z475AAD1

SORT	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY % TOTAL	TOTAL DOLLARS
FDHJ	FLOOR DANIEL NORTHWEST	392,520	30	510,276
LHMC	LOCKHEED MARTIN HANFORD CORP.	264,194	30	343,452
	SUBTOTAL	656,714	30	853,728
SITE	SITE ALLOCATIONS	131,545	30	171,009
	PROJECT TOTAL	788,259	30	1,024,737

TYPE OF ESTIMATE	PLANNING/FEASIBILITY	JUNE 17, 1997
1. PRELIMINARY		
2. PRELIMINARY		
3. PRELIMINARY		
4. PRELIMINARY		
5. PRELIMINARY		
6. PRELIMINARY		
7. PRELIMINARY		
8. PRELIMINARY		
9. PRELIMINARY		
10. PRELIMINARY		
11. PRELIMINARY		
12. PRELIMINARY		
13. PRELIMINARY		
14. PRELIMINARY		
15. PRELIMINARY		
16. PRELIMINARY		
17. PRELIMINARY		
18. PRELIMINARY		
19. PRELIMINARY		
20. PRELIMINARY		
21. PRELIMINARY		
22. PRELIMINARY		
23. PRELIMINARY		
24. PRELIMINARY		
25. PRELIMINARY		
26. PRELIMINARY		
27. PRELIMINARY		
28. PRELIMINARY		
29. PRELIMINARY		
30. PRELIMINARY		
31. PRELIMINARY		
32. PRELIMINARY		
33. PRELIMINARY		
34. PRELIMINARY		
35. PRELIMINARY		
36. PRELIMINARY		
37. PRELIMINARY		
38. PRELIMINARY		
39. PRELIMINARY		
40. PRELIMINARY		
41. PRELIMINARY		
42. PRELIMINARY		
43. PRELIMINARY		
44. PRELIMINARY		
45. PRELIMINARY		
46. PRELIMINARY		
47. PRELIMINARY		
48. PRELIMINARY		
49. PRELIMINARY		
50. PRELIMINARY		
51. PRELIMINARY		
52. PRELIMINARY		
53. PRELIMINARY		
54. PRELIMINARY		
55. PRELIMINARY		
56. PRELIMINARY		
57. PRELIMINARY		
58. PRELIMINARY		
59. PRELIMINARY		
60. PRELIMINARY		
61. PRELIMINARY		
62. PRELIMINARY		
63. PRELIMINARY		
64. PRELIMINARY		
65. PRELIMINARY		
66. PRELIMINARY		
67. PRELIMINARY		
68. PRELIMINARY		
69. PRELIMINARY		
70. PRELIMINARY		
71. PRELIMINARY		
72. PRELIMINARY		
73. PRELIMINARY		
74. PRELIMINARY		
75. PRELIMINARY		
76. PRELIMINARY		
77. PRELIMINARY		
78. PRELIMINARY		
79. PRELIMINARY		
80. PRELIMINARY		
81. PRELIMINARY		
82. PRELIMINARY		
83. PRELIMINARY		
84. PRELIMINARY		
85. PRELIMINARY		
86. PRELIMINARY		
87. PRELIMINARY		
88. PRELIMINARY		
89. PRELIMINARY		
90. PRELIMINARY		
91. PRELIMINARY		
92. PRELIMINARY		
93. PRELIMINARY		
94. PRELIMINARY		
95. PRELIMINARY		
96. PRELIMINARY		
97. PRELIMINARY		
98. PRELIMINARY		
99. PRELIMINARY		
100. PRELIMINARY		

REMARKS:

FDNW LEAD ESTIMATOR *BA* ESTIMATING MANAGER *[Signature]*

PROJECT
MANAGER

CLIENT

ALTERNATE #3
REMOVAL AND FIX IN

REMARKS:

APPROX. 3
STATIONED
REGIONAL AND FIX
PLACE

DRAB

FL

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/FSRUL5
 FILE NO. 2475AAD1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
 PHMCR02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 2 OF 9
 DATE 06/17/97 13:59:33
 BY DKH/RWO

WBS DESCRIPTION	ESTIMATE SUBTOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	SUB TOTAL	SITE ALLOCAT'N	TOTAL DOLLARS
310300 ALT. 3 - REMOVAL & FIX IN PLACE	656,714	0.00	0	56,714	30	197,014	853,728
PROJECT TOTAL	656,714	0.00	0	56,714	30	197,014	853,728
							1,024,737

PAGE 3 OF 9
DATE 06/16/97 14:17:07
BY DKH/RVO

** TEST - INTERACTIVE ESTIMATING **
205E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
6610417/39015
FILE NO. 24755A01

1. ESTIMATE PURPOSE

THIS ESTIMATE WILL BE USED FOR A SCOPING STUDY.

2. ESTIMATE TECHNICAL BASIS

- A. THIS ESTIMATE HAS BEEN PREPARED FOR LOCKHEED MARTIN HANFORD CORP. AS REQUESTED BY FOMW PROJECT MANAGEMENT. A. A ROUGH DESCRIPTION OF THE SCOPE OF WORK MAY BE FOUND IN THE OUTLINE OF ALTERNATIVES, AN UNDATED AND.
- B. THE FOLLOWING CONSTRAINTS AND/OR SPECIAL CONDITIONS EXIST: ALL WORK DONE IN THE CRITICAL ASSEMBLY ROOM AND
- C. IN THE MIXING ROOM WILL REQUIRE FOLLOWING THE APPROPRIATE RADIATION WORK PROCEDURE.

3. ESTIMATE METHODOLOGY

- A. DIRECT COSTS: TECHNIQUE WAS USED TO COME UP WITH THE LABOR HOURS WHEN NECESSARY DUE TO THE UNDEFINED SCOPE.
(1) CONSTRUCTION LABOR, MATERIAL AND EQUIPMENT UNITS HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD COMMERCIAL ESTIMATING RESOURCES, PUBLISHED ESTIMATING MANUALS AND R.S. MEANS

8. DIRECT COST FACTORS

- (1) SALES TAX HAS BEEN APPLIED TO ALL MATERIALS AND EQUIPMENT PURCHASES AT 8%.
- (2) NO ESTIMATING FACTOR OF 15% HAS BEEN APPLIED TO DIRECT CRAFT LABOR FOR GENERAL REQUIREMENTS AND
- (3) 23.58% FOR TECHNICAL SERVICES.
- (4) CONSUMABLES ARE ESTIMATED AT 3.2% OF DIRECT CRAFT LABOR COSTS.
- (5) SPECIAL WORK PROCEDURE (SWP) FACTORS ARE APPLIED AGAINST DIRECT LABOR FOR ACTUAL TIME LOST DUE TO THE PERSONNEL PROTECTIVE CLOTHING FACTORS IN THE CRITICAL ASSEMBLY ROOM, MIXING ROOM, AND PROTECTIVE CLOTHING FACTORS FOR PROTECTIVE CLOTHING, CONTAMINATION RESTRICTIONS ASSOCIATED WITH RADIATION DOSE LIMITS (BURNOUT) HAVE NOT BEEN CALCULATED AS IT IS NOT BELIEVE TO BE A CONCERN FOR THESE ACTIVITIES.
- (6) PREMIUM PAY
OVERTIME REQUIREMENTS AND SHIFT DIFFERENTIAL PAY FOR CRAFT LABOR WILL NOT BE REQUIRED FOR THIS WORK, AS STRAIGHT TIME 40 HOUR WEEKS ARE DEEMED ADEQUATE TO ACCOMPLISH THE PROJECT CRAFT LABOR CREWS.
(7) GENERAL FOREMAN HAS BEEN APPLIED TO DIRECT CRAFT LABOR TO ALLOW FOR USAGE OF
(8) GOVERNMENT OWNED EQUIPMENT CONTROLLED BY DYNACORP.

C. RATES

- (1) FLUOR DANIEL NORTHWEST LABOR RATES ARE BASED UPON THE FLUOR DANIEL FEDERAL OPERATIONS (FEDFO) DISCLOSURE STATEMENT AND APPROVED PROVISIONAL BILLING RATES FOR ESTIMATING PURPOSES, AVERAGE RATES BY OPERATIONS CODE HAVE BEEN USED.
- (2) FLUOR DANIEL NORTHWEST SERVICES (CONSTRUCTION CRAFT LABOR) RATES ARE THOSE LISTED IN APPENDIX A TO THE HANFORD SITE STABILIZATION AGREEMENT.
- (3) FOM & PHMC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) POST 321R REPORT ORGANIZATION RATES PLUS ADERS.

PAGE 4 OF 9
DATE 06/16/97 14:17:07
BY DKH/RMO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED HANFORD CORP.
651547/3RULS
FILE NO. 2475A01

- D. SITE ALLOCATIONS FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 1% FOR FDNW, 10% FOR FDNMS (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 16.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MPR RATE OF 7.0% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).

FDNW APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:

- (1) MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE.
- (2) FDNW GFS/G&A LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO TOTAL FDNW LABOR COSTS AS FOLLOWS:
AE/CN COSTS = 33.04%, FDNMS CONSTRUCTION LABOR = 28.37%, FDNMS CONSTRUCTION MANAGEMENT LABOR = 33.04%, FDNW CONTRACT MANAGEMENT AND ADMINISTRATION - COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDNW MATERIAL COST WHICH INCLUDES FDNW GFS/G&A LABOR COSTS.
- (3) FDNW GFS/G&A LABOR FACTOR: A COMPOSITE FACTOR OF 16.7%
A MPR OF 7% AND MATERIAL G&A/FEE OF 16.7%

4. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FM-50.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EM-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

C. METHODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:
WBS - CIVIL CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO BE INCURRED THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

PAGE 5 OF 9
DATE 06/16/87 14:17:07
BY DKH/SWO

** TEST - INTERACTIVE ESTIMATING **
2096 FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
CLOSURE ENGINEERING GROUP
100 REVERE STREET, HANFORD CORP.
JOB NO. E21945/FSRULS
FILE NO. 2475AAD1

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, WASTE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL PUBLICATIONS, WASTE TREATMENT, AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF THESE COSTS WERE INCLUDED, THE ESTIMATE WOULD BE INCREASED.
- B.) LIMITED INFORMATION WAS AVAILABLE AND GROSS ASSUMPTIONS WERE MADE.
- C.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE R08 REPORT.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AA01

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
 PIMCR04 - COMPANY/WSS SUMMARY

PAGE 6 OF 9
 DATE 06/17/97 13:39:37
 BY DKH/RMO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL DOLLARS
		SUBTOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL	% TOTAL		
FDNW	FLUOR DANIEL NORTHWEST													
310300	ALT. 3 - REMOVAL & FIX IN PLACE	392520	0.00	0	392520	30	117756	510276	171009	681285				
	TOTAL FDNW FLUOR DANIEL NORTHWEST	392520	0.00	0	392520	30	117756	510276	171009	681285				
LWMC	LOCKHEED MARTIN HANFORD CORP.													
310300	ALT. 3 - REMOVAL & FIX IN PLACE	264194	0.00	0	264194	30	79258	343452	0	343452				
	TOTAL LWMC LOCKHEED MARTIN HANFORD CORP	264194	0.00	0	264194	30	79258	343452	0	343452				
	PROJECT TOTAL	656,714	0.00	0	656,714	30	197,014	853,728	171,009	1,024,737				

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/ESRUL5
 FILE NO. 2475A01
 ** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
 PHMCRO5 - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

PAGE 7 OF 9
 DATE 06/17/97 13:39:42
 BY DKH/RNO

UWS	DESCRIPTION	ESTIMATE SUBTOTAL	CONSTRUCTION %	MANAGEMENT TOTAL	OTHER COSTS	SUB TOTAL	TOTAL
310300	ALT. 3 - REMOVAL & FIX IN PLACE	655333	0.21	1381	0	1381	656714
PROJECT TOTAL		655,333		1,381	0	1,381	656,714

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475RA01

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATES ALTERNATIVE 3
 PHMCR06 - SITE ALLOCATIONS BY NBS

PAGE 8 OF 9
 DATE 06/07/97 15:04:44
 BY DKH/RMO

WBS	DESCRIPTION	ESTIMATE	DYN	FOR GFS/G&A	FOR MPR	FOR GFS/G&A	FOR MPR/G&A	SITE ALLOC
		SUBTOTAL	EQ.USAGE	CONST-MGMT	F.P./S.C.	LABOR	MATERIAL	SUBTOTAL
310300	ALT. 3 - REMOVAL & FIX IN PLACE	655333	13165	456	0	115594	2330	131545
PROJECT TOTAL		655,333	13,165	456	0	115,594	2,330	131,545

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AA01

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
 PHMCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 13:39:47
 BY DKH/RMO

WBS DESCRIPTION	SITE ALLOC SUBTOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
310300 ALT. 3 - REMOVAL & FIX IN PLACE	131545	0.00	0	30	39464
PROJECT TOTAL	131,545	0.00	0	30	171,009

** IEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/F3RUL5
FILE NO. 7475AAD1

COST CODE	DESCRIPTION	QUANTITY	MANHOURS	LABOR	EQUIP RATE	MATERIAL	SUP- CONTRACT	EQUIP- MENT / 8 & 1	TOTAL DOLLARS
310300	ALT. 3 - REMOVAL & FIX IN PLACE								
310300.00	TECHNICAL SERVICES	1 L/S	1667	110022	0	0	0	0	110022
310300.0003100	DEFINITIVE DESIGN								

	AT 25 % OF CONSTRUCTION								
310300.0003200	ENGINEERING/ INSPECTION	1 L/S	1100	66000	0	0	0	0	66000

	AT 15% OF CONSTRUCTION								
310300.0003300	PROJECT MANAGEMENT	1 L/S	904	65992	0	0	0	0	65992

	AT 15% OF CONSTRUCTION								
SUBTOTAL	TECHNICAL SERVICES		3,671	242,014	0	0	0	0	242,014
TOTAL	COST CODE 00000		3,671	242,014	0	0	0	0	242,014
310300.01	GENERAL REQUIREMENTS								
310300.0103226	BURIAL CHARGES FOR 3 BOXES OF LLW @ \$15.25/CF.	3 EA	0	0	0	0	5,856	0	5,856

	GENERAL REQUIREMENTS		0	0	0	0	5,856	0	5,856
SUBTOTAL	GENERAL REQUIREMENTS		0	0	0	0	5,856	0	5,856
TOTAL	COST CODE 81001		0	0	0	0	5,856	0	5,856
310300.01	GENERAL REQUIREMENTS								
310300.0103000	HPT TO MAN STEP-OFF PAD	810 M	1550	74059	0	0	0	0	74059
	(MASK)		1,550	74,059	0	0	0	0	74,059
SUBTOTAL	GENERAL REQUIREMENTS		1,550	74,059	0	0	0	0	74,059
TOTAL	SHP 100.00%		1550	74059	0	0	0	0	74,059
TOTAL	COST CODE 81001		3,100	148,118	0	0	0	0	148,118
	WS 310300								

PAGE 2
DATE 06/17/97 13:39:50
BY DKH/RWO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
PHMCR06 - ESTIMATE DETAIL BY WBS / COST CODE

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/FERUL5
FILE NO. 2475AAD1

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	USAGE	SUB- MATERIAL	EQUIP- CONTRACT	OH&P / B & I DOLLARS	TOTAL
	(ESCALATION 0.00% - CONTINGENCY 30.00 %)									
310300.02	SITEWORK									
310300.0203220	***** REMOVE EQUIPMENT *****	810 M	0	0	0	0	0	0	0	0
310300.0203222	***** REMOVE ALL EQUIPMENT IN *****	810 M	1 L/S	288	10944	0	0	0	0	10944
310300.0203224	***** GLOVE BOXES/HOODS, CUT UP *****	810 M	2 EA	0	0	0	0	0	0	2000
310300.0203240	***** AND PUT INTO BURIAL BOXES. *****	810 M	0	0	0	0	0	0	0	0
310300.0203241	***** DECON / FIXATIVE *****	810 M	0	0	0	0	0	0	0	0
310300.0203242	***** WIPE DOWN GLOVE BOXES/HOODS *****	810 M	0	0	0	0	0	0	0	0
310300.0203244	***** AND FIX IN PLACE REMAINING *****	810 M	1 L/S	48	1311	0	100	0	0	1411
310300.0203250	***** APPLY FIXATIVE, 50 MIL *****	810 M	7000 SF	588	16458	0	4900	0	0	21358
310300.0203252	***** SEAL GLOVE BOX PORTS, ETC. *****	810 M	0	0	0	0	0	0	0	0
310300.0203254	***** SEAL GLOVE BOX PORTS *****	810 M	1 L/S	48	1737	0	250	0	0	1987
310300.0203256	***** SEALANT *****	810 M	1 L/S	50	1810	0	300	0	0	2110
310300.0203258	***** INSTALL CAPS AND SEAL OFF. *****	810 M	1 L/S	80	3092	0	250	0	0	3342
310300.0203260	***** CUT AND CAP PIPES *****	810 M	0	0	0	0	0	0	0	0
310300.0203262	***** DISCONNECT VENTILATION *****	810 M	1 L/S	24	869	0	240	0	0	1109
310300.0203264	***** DISCONNECT ACTIVE VENTIL- *****	810 M	0	0	0	0	0	0	0	0
310300.0203266	***** ACTION TO GLOVE BOXES/HOODS, *****	810 M	0	0	0	0	0	0	0	0
310300.0203268	***** CAP OFF. *****	810 M	0	0	0	0	0	0	0	0
310300.0203270	***** PASSIVE HEPA *****	810 M	1 L/S	16	579	0	0	0	0	579
310300.0203272	***** CHECK PASSIVE HEPA FILTER *****	810 M	0	0	0	0	0	0	0	0
310300.0203274	***** VENTILATION SYSTEM TO GLOVE *****	810 M	0	0	0	0	0	0	0	0
310300.0203276	***** BOXES/HOODS, SHOULD ALL BE *****	810 M	0	0	0	0	0	0	0	0
310300.0203278	***** EXISTING. *****	810 M	0	0	0	0	0	0	0	0
310300.0203280	***** ISOLATE TANKS *****	810 M	0	0	0	0	0	0	0	0

** TEST - INTERACTIVE ESTIMATING **										PAGE 3		
209E FACILITY ENGINEERING STUDY										DATE 06/17/97 13:39:50		
PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3										BY DKH/RNO		
PMCR08 - ESTIMATE DETAIL BY WBS / COST CODE												
ACCOUNT	DESCRIPTION	COST	CODE	QUANTITY	MANHOURS	LABOR-	EQUIP	USAGE	MATERIAL	SUB-	EQUIP-	OHSP
NUMBER										CONTRACT	MENT	/ B & I DOLLARS
=====	=====	=====	=====	=====	=====	=====	=====	=====	=====	=====	=====	=====
310300.0203310	ISOLATE TANKS TK-109, 110	810 M		1 L/S	64	2304	100	50	0	0	0	2454
310300.0203320	ISOLATE TANKS TK-109, 110	810 M		1 L/S	128	4608	200	300	0	0	0	5108
310300.0203340	ISOLATE TANKS TK-101, 102, 103, 104, 161 AND 162.	810 M		0	0	0	0	0	0	0	0	0
310300.0203340	TANKS 105 AND 106	810 M		1 EA	64	1920	5000	500	0	0	0	7420
310300.0203342	ERECT GREENHOUSE, W/HEPA	810 M		1 L/S	32	1216	0	0	0	0	0	1216
310300.0203344	CUT UP TANKS 105 & 106,	810 M		1 EA	0	0	0	0	1000	0	0	1000
310300.0203346	PUT IN BURIAL BOX	810 M		0	0	0	0	0	0	0	0	0
310300.0203360	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203360	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203360	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203362	*****	810 M		1 L/S	36	1303	0	50	0	0	0	1353
310300.0203362	*****	810 M		1 L/S	32	1158	0	100	0	0	0	1258
310300.0203364	*****	810 M		1 L/S	32	1158	0	100	0	0	0	1258
310300.0203380	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203382	*****	810 M		1 L/S	48	1728	0	0	0	0	0	1728
310300.0203390	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203391	*****	810 M		1 L/S	900	45000	0	0	0	0	0	45000
310300.0203392	*****	810 M		1 L/S	10	500	0	0	0	0	0	500
310300.0203394	*****	810 M		1 YR	208	9938	0	0	0	0	0	9938
310300.0203396	*****	810 M		0	0	0	0	0	0	0	0	0
310300.0203398	*****	810 M		1 YR	0	0	0	0	0	0	0	4000
310300.0203398	*****	810 M		1 YR	0	0	0	0	0	0	0	4000
310300.0203398	*****	810 M		1 YR	0	0	0	0	0	0	0	4000

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AA01

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALTERNATIVE 3
 PHRC08 - ESTIMATE DETAIL BY WBS / COST CODE

ACCOUNT DESCRIPTION COST QUANTITY MANHOURS LABOR EQUIP USAGE MATERIAL CONTRACT SUB- EQUIP- OH&P TOTAL
 310300.0203399 BPA ELECTRICITY 810 M 1 YR 0 0 0 0 0 0 0 0 0 1200
 (MASK) 2,664 106,475 5,300 7,040 8,200 0 0 127,015
 SUBTOTAL SITEMARK CONSUMABLES 3.20 % 2664 106475 3407 106475
 SWP 100.00% 372 14906 34178 34178
 GENERAL FOREMAN 7.00 % 855 34178 835 835
 GENERAL REQUIREMENTS 15.00 %
 SALES TAX 8.00 %
 TOTAL COST CODE 81002 6,556 262,034 5,300 11,282 8,200 0 0 286,817
 WBS 310300
 (ESCALATION 0.00% - CONTINGENCY 30.00 %)

TOTAL WBS 310300 ALT. 3 - REMOVAL & FIX IN PLACE 13,327 652,166 5,300 11,282 14,056 0 0 682,805

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475A01

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FERABILITY ESTIMATE ALTERNATIVE 3
 PMRC08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 5
 DATE 06/17/97 13:39:51
 BY DKR/AWO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	SUB- MATERIAL	EQUIP- CONTRACT	OH&P MENT	TOTAL / B & I DOLLARS
				13,327	652,166					
						5,300	11,282	14,056		
									0	682,805

REPORT TOTAL

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/ESRUL5
 FILE NO. 2475AAE1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHMCR01 - PROJECT COST SUMMARY

PAGE 1 OF 9
 DATE 06/17/97 13:49:35
 BY DKH/RMO

SORT	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY %	TOTAL DOLLARS
FDNW	FLUOR DANIEL NORTHWEST	597,979	30	179,394
LWMC	LOCKHEED MARTIN HANFORD CORP.	180,418	30	54,125
SUBTOTAL		778,397	30	233,519
SITE		196,135	30	58,840
PROJECT TOTAL		974,532	30	292,359
				1,266,891

TYPE OF ESTIMATE PLANNING/FEASIBILITY
 DATE JUNE 17, 1997
 ESTIMATOR
 PROJECT MANAGER
 CLIENT

REMARKS:

DRAFT

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/E3RUL5
 FILE NO. Z475AAE1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHMCR02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 2 OF 9
 DATE 06/17/97 13:49:38
 BY DKH/RWO

WBS DESCRIPTION	ESTIMATE SUBTOTAL	ESCALATION %	SUB TOTAL	CONTINGENCY %	SUB TOTAL	SITE ALLOCAT'N	TOTAL DOLLARS
310410 ALTERNATIVE 4 - STAGE 1	778,397	0.00	0	30	233,519	254,975	1,266,891
PROJECT TOTAL	778,397	0.00	0	30	233,519	254,975	1,266,891

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/73RUL5
 FILE NO. 2475AAE1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 3 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/AHO

1. ESTIMATE PURPOSE

THIS ESTIMATE WILL BE USED FOR A SCOPING STUDY.

2. ESTIMATE TECHNICAL BASIS

- A. THIS ESTIMATE HAS BEEN PREPARED FOR LOCKHEED MARTIN HANFORD CORP. AS REQUESTED BY FDMW PROJECT MANAGER.
- B. A THOUGH DESCRIPTION OF THE SCOPE OF WORK MAY BE FOUND IN THE OUTLINE OF ALTERNATIVES, AN UPDATED AND UNNUMBERED DOCUMENT.
- C. THE FOLLOWING CONSTRAINTS AND/OR SPECIAL CONDITIONS EXIST: ALL WORK DONE IN THE CRITICAL ASSEMBLY ROOM AND IN THE MIXING ROOM WILL REQUIRE FOLLOWING THE APPROPRIATE RADIATION WORK PROCEDURE.

3. ESTIMATE METHODOLOGY

A. DIRECT COSTS:

- (1) CONSTRUCTION LABOR, MATERIAL AND EQUIPMENT UNITS HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD COMMERCIAL ESTIMATING RESOURCES, PUBLISHED ESTIMATING MANUALS AND R.S. MEANS

B. DIRECT COST FACTORS

- (1) SALES TAX HAS BEEN APPLIED TO ALL MATERIALS AND EQUIPMENT PURCHASES AT 8%.
- (2) NO WAREHOUSING COSTS ARE SHOWN SINCE THEY ARE CONSIDERED TO BE INCLUDED IN THE MATERIAL PROCUREMENT RATE (MPR).
- (3) AN ESTIMATING FACTOR OF 15% HAS BEEN APPLIED TO DIRECT CRAFT LABOR FOR GENERAL REQUIREMENTS AND 23.56% FOR TECHNICAL SERVICES.
- (4) CONSUMABLES ARE ESTIMATED AT 3.2% OF DIRECT CRAFT LABOR COSTS.
- (5) SPECIAL WORK PROCEDURE (SPECIAL) RATES ARE APPLIED TO DIRECT CRAFT LABOR FOR ACTUAL TIME LOST DUE TO THE PERSONNEL PROTECTIVE CLOTHING PROCEDURE. THE RATES WHICH HAVE BEEN APPLIED ARE AS FOLLOWS:
 PROTECTIVE CLOTHING FACTOR HAS BEEN APPLIED AT 15%,
 MASK WORK AT 85% PLUS 15% FOR PROTECTIVE CLOTHING.
 CONTAMINATION RESTRICTIONS ASSOCIATED WITH RADIATION DOSE LIMITS (BURNOUT) HAVE NOT BEEN CALCULATED AS IT IS NOT BELIEVED TO BE A CONCERN FOR THESE ACTIVITIES.
- (6) PREMIUM PAY REQUIREMENTS AND SHIFT DIFFERENTIAL PAY FOR CRAFT LABOR WILL NOT BE REQUIRED FOR THIS WORK, AS STRAIGHT TIME AND HOUR RATES ARE DEEMED ADEQUATE TO ACCOMPLISH THIS WORK.
- (7) GENERAL FOREMAN FACTOR OF 7% HAS BEEN APPLIED TO DIRECT CRAFT LABOR CREWS.
- (8) A FACTOR OF 10% HAS BEEN APPLIED TO DIRECT CRAFT LABOR TO ALLOW FOR USAGE OF GOVERNMENT OWNED EQUIPMENT CONTROLLED BY DYNACORP.

C. RATES

- (1) FLUOR DANIEL NORTHWEST LABOR RATES ARE BASED UPON THE FLUOR DANIEL FEDERAL OPERATIONS (FEDFO) DISCLOSURE STATEMENT AND APPROVED PROVISIONAL BILLING RATES. FOR ESTIMATING PURPOSES, AVERAGE RATES BY OPERATIONS CODE HAVE BEEN DEVELOPED BASED UPON RECENT COST HISTORY.
- (2) FLUOR DANIEL NORTHWEST SERVICES (CONSTRUCTION CRAFT LABOR) RATES ARE THOSE LISTED IN APPENDIX A TO THE HANFORD SITE STABILIZATION AGREEMENT.
- (3) FDM & PHMC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) POST 321R REPORT ORGANIZATION RATES PLUS ADJERS.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAE1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMC03 - ESTIMATE BASIS SHEET

PAGE 4 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RWO

- D. SITE ALLOCATIONS FACTORS
- SITE ALLOCATION FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 14% FOR FDH, 10% FOR FDMs (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 16.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MPR RATE OF 7.0% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).
- FDH APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:
- (1) FDH GFS/G&A CM FACTOR: A COMPOSITE FACTOR OF 33.04% HAS BEEN APPLIED TO TOTAL FDH FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE.
 - (2) FDH GFS/G&A LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO TOTAL FDH LABOR COSTS AS FOLLOWS:
 WETWORK COSTS = 33.04%, HANFORD CONSTRUCTION LABOR = 28.37%, FDMs CONSTRUCTION MANAGEMENT LABOR = 35.04%, FDM CONTRACT LABOR = 33.04%, SITE LABOR = 33.04%.
 - (3) FDH MPR/G&A MATERIAL FACTOR: A COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDH MATERIAL COST WHICH INCLUDE A MPR OF 7% AND MATERIAL G&A/FEE OF 16.7%.

4. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FM-50.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT, AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EM-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

C. METRODODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:

WBS 31XXXX CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO SURFACE THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAE1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCRO3 - ESTIMATE BASIS SHEET

PAGE 5 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RMO

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, WASTE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL REPORTS, AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF INCLUDED, WOULD NEED TO BE INCLUDED.
- B.) LIMITED INFORMATION WAS AVAILABLE AND GROSS ASSUMPTIONS WERE MADE.
- C.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE R08 REPORT.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E31041/ESRULS
 FILE NO. 2475A01

** TEST - INTERACTIVE ESTIMATING **
 2045 QUALITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATING, STAGE 1
 PHMCR04 - COMPANY/ABS SUMMARY

PAGE 6 OF 9
 DATE 06/17/97 13:49:41
 BY DKH/RMO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB TOTAL	CONTINGENCY %	SUB TOTAL		SITE ALLOCAT'N	TOTAL DOLLARS
		SUBTOTAL	%	%	TOTAL			TOTAL			
FDNW	FLUOR DANIEL NORTHWEST	597979	0.00	0	597979	30	179394	777373	254975	1032348	
	310410 ALTERNATIVE 4 - STAGE 1	597979	0.00	0	597979	30	179394	777373	254975	1032348	
	TOTAL FDNW FLUOR DANIEL NORTHWEST										
LWMC	LOCKHEED MARTIN HANFORD CORP.	180418	0.00	0	180418	30	54125	234543	0	234543	
	310410 ALTERNATIVE 4 - STAGE 1	180418	0.00	0	180418	30	54125	234543	0	234543	
	TOTAL LWMC LOCKHEED MARTIN HANFORD COR										
PROJECT TOTAL		778,397	0.00	0	778,397	30	233,519	1,011,916	254,975	1,266,891	

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. EG1945/F3RUL5
 FILE NO. Z475AAE1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHMCRO5 - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

PAGE 7 OF 9
 DATE 06/17/97 13:49:44
 BY DKH/RMO

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONSTRUCTION MANAGEMENT %	TOTAL	OTHER COSTS	SUB TOTAL	TOTAL
310410	ALTERNATIVE 4 - STAGE 1	718244	8.38	60153	0	60153	778397
PROJECT TOTAL		718,244		60,153	0	60,153	778,397

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/FSRUL5
 FILE NO. Z475AAE1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHMCR06 - SITE ALLOCATIONS BY WBS

PAGE 8 OF 9
 DATE 06/17/97 15:06:02
 BY DK4/RMO

WBS	DESCRIPTION	ESTIMATE	DYN	FDH QCS/G&A	FDH MDR	FDH QCS/G&A	FDH MDR/G&A	SITE ALLOC
		SUBTOTAL	EQ. USAGE	CONST. MGMT	F.P./S.C.	LABOR	MATERIAL	SUBTOTAL
310410	ALTERNATIVE 4 - STAGE 1	718244	21118	19875	0	151318	3824	196135
PROJECT TOTAL		718,244	21,118	19,875	0	151,318	3,824	196,135

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. 2475AAE1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 13:49:47
 BY DKH/RMO

WBS DESCRIPTION	SITE ALLOC SUBTOTAL	ESCALATION % TOTAL	SUR TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
310410 ALTERNATIVE 4 - STAGE 1	196135	0.00	0	30	58840
PROJECT TOTAL	196,135	0.00	0	30	58,840
					254,975

** TEST - INTERACTIVE ESTIMATING **
 FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. 2475AAE1
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHRCR08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 2
 DATE 06/17/97 13:49:50
 BY DKN/RWO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP	SUB- CONTRACT	EQUIP- MENT	OH&P	TOTAL
(ESCALATION 0.00% - CONTINGENCY 30.00 %)										
310410.-02	SITENWORK		810 M	0	0	0	0	0	0	0
310410.-0204000	***** STAGE 1									
310410.-0204002	***** RESTORE SUPPLY VENTILATION AND BALANCE SYSTEM, ASSUME NO NEW EQUIPMENT NEEDED. REMOVE ALLS EQUIPMENT CUT UP AND PUT INTO BURIAL BOXES.		810 M	1 L/S	80	2895	0	0	0	2895
310410.-0204012	BURIAL BOXES		810 M	1 L/S	288	10944	0	0	0	10944
310410.-0204014	BURIAL BOXES		810 M	2 EA	0	0	0	2000	0	2000
310410.-0204022	DISCONNECT PIPES TO GLOVE BOXES AND HOODS, CAP OFF.		810 M	1 L/S	80	3092	0	0	0	3092
310410.-0204034	FIX IN PLACE CONTAMINATION ON GLOVE BOXES AND HOODS		810 M	7000 SF	595	16654	0	5250	0	184 22088
310410.-0204036	ON GLOVE BOXES AND HOODS EPOXY.		810 M	7000 SF	588	16458	0	4900	0	172 21530
310410.-0204042	CONSTRUCT GREENHOUSES AROUND GLOVE BOXES AND HOODS, COSTS INCLUDE 2 HEPA SYSTEMS		810 M	6 EA	384	13824	10000	0	0	0 23824
310410.-0204052	DISCONNECT REMAINING SAFETY		810 M	1 L/S	64	2432	0	0	0	0 2432
310410.-0204062	CUT UP GLOVE BOXES AND HOODS FOR PLACEMENT INTO BURIAL BOXES		810 M	1 L/S	400	13600	0	500	0	18 14118
310410.-0204064	BURIAL BOXES		810 M	6 EA	0	0	0	6000	0	0 6000
310410.-0204082	REMOVE TANKS NOT IN GLOVE BOXES OR HOODS. CUT UP BURIAL CONTAINERS		810 M	1 L/S	80	3040	0	200	0	0 7 3247
310410.-0204084	BURIAL BOXES		810 M	2 EA	0	0	0	2000	0	0 2000
(MASK)										
SUSTOTAL				2,559	82,939	10,000	11,100	10,000	390	114,429
	CONSUMABLES 3.20 %						2654			2654
	FOREMAN 7.00 %			2559	82939					82939
	GENERAL REQUIREMENTS 15.00 %			358	11611					11611
	SALES TAX 8.00 %			821	26623					26623
	OH&P (ON MARKUPS ONLY)						1100		0	1100
									131	131
TOTAL				6,297	204,112	10,000	14,854	10,000	0	239,488
	COST CODE 81002									
	WBS 310410									

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAE1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 1
 PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	CONTRACT	EQUIP- MENT	OR&P / B & I	TOTAL DOLLARS
(ESCALATION 0.00% - CONTINGENCY 30.00 %)											
			14,427	667,252	10,000	14,854	25,616	0	521	718,244	
TOTAL WBS 310410 ALTERNATIVE 4 - STAGE 1											

PAGE 3
 DATE 06/17/97 13:49:51
 BY DKH/RMO

FLUOR DANIEL NORTHWEST, INC.
 LOCKWOOD MARTIN HANFORD CORP.
 JOB NO. E61945/FRUL5
 FILE NO. 2475AAE1
 ** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #8, STAGE 1
 PHMCRO8 - ESTIMATE DETAIL BY WBS / COST CODE
 PAGE 4
 DATE 06/17/97 13:49:51
 BY DKN/RNO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	SUB- MATERIAL	CONTRACT	EQUIP- MENT	OR&P / 8 & 1 DOLLARS	TOTAL
			14,427	667,252	10,000		14,954	25,616	0	521	718,244
REPORT TOTAL											

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. 2475AAF1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHMCR01 - PROJECT COST SUMMARY

PAGE 1 OF 9
 DATE 06/17/97 14:05:52
 BY DKH/RMO

SORT	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY %	TOTAL DOLLARS
FORM	FLUOR DANIEL NORTHWEST	52,302	30	67,992
LMHC	LOCKHEED MARTIN HANFORD CORP.	7,644	30	9,937
SUBTOTAL		59,946	30	77,929
SITE		16,335	30	21,236
PROJECT TOTAL		76,281	30	99,165

TYPE OF ESTIMATE PLANNING/FEASIBILITY JUNE 17, 1997

DN ESTIMATED BY
 ESTIMATOR
 MANAGER

PROJECT MANAGER
 Charles H. B. Borch

CLIENT

REMARKS:

DRAFT
 PRELIMINARY STAGE

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHMCR02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY
 FILE NO. Z475AA1

FLUOR DANIEL NORTHWEST, INC.
 LOCKREED MARTIN HANFORD CORP.
 JOB NO. E61945/E3RUL5
 DATE 06/17/97 14:05:54
 BY DKH/RWO

PAGE 2 OF 9
 DATE 06/17/97 14:05:54
 BY DKH/RWO

WBS	DESCRIPTION	ESTIMATE	ESCALATION	SUB	CONTINGENCY	SUB	SITE	TOTAL
		SUBTOTAL	% TOTAL	TOTAL	% TOTAL	TOTAL	ALLOCAT'N	DOLLARS
310420	ALTERNATIVE 4 - STAGE 2	59946	0.00	0	59946	30	17983	99165
		59,946	0.00	0	59,946	30	17,983	99,165
	PROJECT TOTAL							

PAGE 3 OF 9
DATE 06/16/97 14:17:07
BY DKH/RMO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED 2405/FBI/PLD
FILE NO. 2473AAFI

1. ESTIMATE PURPOSE

THIS ESTIMATE WILL BE USED FOR A SCOPING STUDY.

2. ESTIMATE TECHNICAL BASIS

- A. THIS ESTIMATE HAS BEEN PREPARED FOR LOCKHEED MARTIN HANFORD CORP. AS REQUESTED BY FDMW PROJECT MANAGER.
B. A ROUGH DESCRIPTION OF THE SCOPE OF WORK MAY BE FOUND IN THE OUTLINE OF ALTERNATIVES, AN UNDATED AND
C. THE FOLLOWING CONSTRAINTS AND/OR SPECIAL CONDITIONS EXIST: ALL WORK DONE IN THE CRITICAL ASSEMBLY ROOM AND
IN THE MIXING ROOM WILL REQUIRE FOLLOWING THE APPROPRIATE RADIATION WORK PROCEDURE.

3. ESTIMATE METHODOLOGY

- A. DIRECT COSTS: TECHNIQUE WAS USED TO COME UP WITH THE LABOR HOURS WHEN NECESSARY DUE TO THE UNDEFINED SCOPE.
(1) CONSTRUCTION LABOR, MATERIAL AND EQUIPMENT UNITS HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD
(2) COMMERCIAL ESTIMATING RESOURCES, PUBLISHED ESTIMATING MANUALS AND R.S. MEANS

B. DIRECT COST FACTORS

- (1) SALES TAX HAS BEEN APPLIED TO ALL MATERIALS AND EQUIPMENT PURCHASES AT 8%.
(2) NO ESTIMATING FACTOR OF 15% HAS BEEN APPLIED TO DIRECT CRAFT LABOR FOR GENERAL REQUIREMENTS AND
(3) 23.58% FOR TECHNICAL SERVICES.
(4) CONSUMABLES ARE ESTIMATED AT 3.2% OF DIRECT CRAFT LABOR COSTS.
(5) SPECIAL WORK PROCEDURE (SWP) FACTORS ARE APPLIED AGAINST DIRECT LABOR FOR ACTUAL TIME LOST DUE TO THE PERSONNEL
PROTECTIVE CLOTHING AND PROCEDURES. THE RATES WHICH HAVE BEEN APPLIED ARE AS FOLLOWS:
PROTECTIVE CLOTHING PLUS 15% FOR PROTECTIVE CLOTHING.
CONTAMINATION RESTRICTIONS ASSOCIATED WITH RADIATION DOSE LIMITS (BURNOUT) HAVE NOT BEEN CALCULATED AS IT IS NOT
BELIEVE TO BE A CONCERN FOR THESE ACTIVITIES.
(6) PREMIUM PAY
OVERTIME REQUIREMENTS AND SHIFT DIFFERENTIAL PAY FOR CRAFT LABOR WILL NOT BE REQUIRED FOR THIS WORK. AS STRAIGHT
TIME, 40 HOUR WEEKS ARE BEING APPLIED TO THIS WORK.
(7) GENERAL FOREMAN HAS BEEN APPLIED TO DIRECT CRAFT LABOR CREWS.
(8) GOVERNMENT OWNED EQUIPMENT CONTROLLED BY DYNACORP.

C. RATES

- (1) FLUOR DANIEL NORTHWEST LABOR RATES ARE BASED UPON THE FLUOR DANIEL FEDERAL OPERATIONS (FEDFO) DISCLOSURE STATEMENT
AND APPROVED PROVISIONAL BILLING RATES FOR ESTIMATING PURPOSES, AVERAGE RATES BY OPERATIONS CODE HAVE BEEN
FLUOR DANIEL NORTHWEST HISTORICAL RATES.
(2) FLUOR DANIEL NORTHWEST SERVICES (CONSTRUCTION CRAFT LABOR) RATES ARE THOSE LISTED IN APPENDIX A TO THE HANFORD SITE
STABILIZATION AGREEMENT.
(3) FOR PHMC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) POST 321R REPORT
ORGANIZATION RATES PLUS ADJUSTERS.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/E3RUL5
 FILE NO. 2475AA1

209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 4 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RWO

- D. SITE ALLOCATIONS FACTORS
- SITE ALLOCATIONS FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 14% FOR FDH, 10% FOR FDHMS (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 7.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MATERIALS RATE OF 7.7% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).

FDH APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:

- (1) FOR GFS/G&A CM FACTOR: A COMPOSITE FACTOR OF 30.04% HAS BEEN APPLIED TO TOTAL FDH FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE. OR COSTS AS FOLLOWS:
- (2) FOR GFS/G&A LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO LABOR = 26.37%, FDHMS CONSTRUCTION MANAGEMENT LABOR = 33.04%, FDH CONTRACT MGMT AND ADMINISTRATION = 33.04%
- (3) FOR MPR/G&A MATERIAL FACTOR: A COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDH MATERIAL COST WHICH INCLUDE A MPR OF 7% AND MATERIAL G&A/FEE OF 16.7%

4. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FM-50.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT, AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EW-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

C. METHODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:

WBS 31XXXX CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO SURFACE THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

FLUOR DANIEL NORTHWEST, INC.
 209E FACILITY ENGINEERING STUDY
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET
 FILE NO. 2475AAf1

PAGE 5 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RWO

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, WIDE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL PUBLICATIONS, VERIFICATION TESTING AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF THESE ARE INCLUDED, THE ESTIMATE WOULD BE INCREASED.
- B.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- C.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE R08 REPORT.

FLUOR DANIEL NORTHWEST, INC.
 LOCKNEED MARTIN HANFORD CORP.
 JOB NO. E61945/F38UL5
 FILE NO. Z475AAFI

209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHMCR04 - COMPANY/WBS SUMMARY

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHMCR04 - COMPANY/WBS SUMMARY

PAGE 6 OF 9
 DATE 06/17/97 14:05:57
 BY DKH/RMO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL DOLLARS
		SUBTOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	TOTAL	ALLOCAT'N			
FDNW	FLUOR DANIEL NORTHWEST	52302	0.00	0	52302	30	15690	67992	21236	89228				
	310420 ALTERNATIVE 4 - STAGE 2	52302	0.00	0	52302	30	15690	67992	21236	89228				
	TOTAL FDNW FLUOR DANIEL NORTHWEST													
LMHC	LOCKNEED MARTIN HANFORD CORP.	7644	0.00	0	7644	30	2293	9937	0	9937				
	310420 ALTERNATIVE 4 - STAGE 2	7644	0.00	0	7644	30	2293	9937	0	9937				
	TOTAL LMHC LOCKNEED MARTIN HANFORD CORP.													
	PROJECT TOTAL	59,946	0.00	0	59,946	30	17,983	77,929	21,236	99,165				

PAGE 7 OF 9
DATE 06/17/97 14:06:00
BY DKH/RNO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
PHMC805 - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. 661945/F38UL5
FILE NO. 2475AAFI

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONSTRUCTION MANAGEMENT %	OTHER COSTS	SUB TOTAL	TOTAL
310420	ALTERNATIVE 4 - STAGE 2	53,652	11.73	6,294	62,946	59,946
PROJECT TOTAL		53,652		0	6,294	59,946

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHRC06 - SITE ALLOCATIONS BY WBS

FLUOR DANIEL NORTHWEST, INC.
 LOCKWOOD GREENE/HAMMOND CORP.
 WORKNO 661915/F3RUL5
 FILE NO. Z475AAE1

PAGE 8 OF 9
 DATE 06/17/97 15:06:59
 BY DKH/RNO

WBS	DESCRIPTION	ESTIMATE	DYN	FDH GFS/G&A	FDH MPR	FDH GFS/G&A	FDH MPR/G&A	SITE ALLOC
		SUBTOTAL	EQ.USAGE	CONST./MGMT	F.P./S.C.	LABOR	MATERIAL	SUBTOTAL
310420	ALTERNATIVE 4 - STAGE 2	53652	2033	2080	0	12011	211	16335
	PROJECT TOTAL	53,652	2,033	2,080	0	12,011	211	16,335

FLOOR DANIEL NORTHWEST, INC.
 LOCKED - MARTIN HANFORD CORP.
 JOB NO. 61945/ESRUL5
 FILE NO. 2475AAF1

** TEST - INTERACTIVE ESTIMATING **
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PIMCRO7 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 14:06:03
 BY DKH/RWO

WBS	DESCRIPTION	SITE ALLOC SUBTOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
310420	ALTERNATIVE 4 - STAGE 2	16335	0.00	0	30	4901
	PROJECT TOTAL	16,335	0.00	0	30	4,901
				16,335		21,236

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 2
 PHMCRO8 - ESTIMATE DETAIL BY WBS / COST CODE
 FILE NO. 2475AA1

PAGE 1
 DATE 06/17/97 14:06:05
 BY DKH/RNO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB-CONTRACT	EQUIP-MENT	OH&P	TOTAL DOLLARS
310420	ALTERNATIVE 4 - STAGE 2										
310420.00	TECHNICAL SERVICES	000	1 L/S	133	8778	0	0	0	0	0	8778
310420.0004200	*****ALTERNATIVE DESIGN*****										
310420.0005200	*****AT 25 % OF CONSTRUCTION*****										
310420.0105000	*****ENGINEERING/ INSPECTION*****	000	1 L/S	88	5280	0	0	0	0	0	5280
310420.0005300	*****AT 15% OF CONSTRUCTION*****	000	1 L/S	72	5256	0	0	0	0	0	5256
	*****PROJECT MANAGEMENT*****										
	*****AT 15% OF CONSTRUCTION*****										
	SUBTOTAL TECHNICAL SERVICES			293	19,314	0	0	0	0	0	19,314
TOTAL	COST CODE 00000 WBS 310420 (ESCALATION 0.00% - CONTINGENCY 30.00 %)			293	19,314	0	0	0	0	0	19,314
310420.01	GENERAL REQUIREMENTS	810 M	1 L/S	80	3822	0	0	0	0	0	3822
310420.0105000	RPT TO MAR STEP-OFF PAD (MASK)	80		80	3,822	0	0	0	0	0	3,822
SUBTOTAL	GENERAL REQUIREMENTS	80		80	3,822	0	0	0	0	0	3,822
	SWP 100.00%										
TOTAL	COST CODE 81001 WBS 310420 (ESCALATION 0.00% - CONTINGENCY 30.00 %)	160		160	7,644	0	0	0	0	0	7,644
310420.02	SITework	810 M	0	0	0	0	0	0	0	0	0
310420.0205000	*****STAGE 2*****										
310420.0205002	*****REMOVE SUSPECTED CONTAMINATED PIPING, AIR RECIRCULATION SYSTEM, COOLING UNIT AND ZONE 1 HVAC SYSTEM.*****	810 M	1 L/S	224	8064	0	500	0	0	0	8582

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAF1
 ACCOUNT DESCRIPTION
 ** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #5, STAGE 2
 PHNCR08 - ESTIMATE DETAIL BY WBS / COST CODE
 COST CODE QUANTITY MANHOURS LABOR EQUIP USAGE MATERIAL CONTRACT SUB-EQUIP-OR&P TOTAL
 1,004 46,803 0 818 6,000 0 29 53,651
 REPORT TOTAL

PAGE 7
 DATE 06/17/97 14:06:06
 BY DCH/BJO

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. 2475AAG1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMCR01 - PROJECT COST SUMMARY

PAGE 1 OF 9
 DATE 06/17/97 14:18:14
 BY DKN/RMO

SORT	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY % TOTAL	TOTAL DOLLARS
FDWM	FLUOR DANIEL NORTHWEST	170,802	30	51,241
LMHC	LOCKHEED MARTIN HANFORD CORP.	44,836	30	13,451
	SUBTOTAL	215,638	30	64,692
	SITE	57,506	30	17,252
	SITE ALLOCATIONS			
	PROJECT TOTAL	273,144	30	81,944
				355,088

TYPE OF ESTIMATE: PLANNING/FEASIBILITY

DATE: JUNE 17, 1997

FOR LEAD: *PH* ESTIMATING MANAGER

PROJECT MANAGER: *Chris H. Barwick*

CLIENT: _____

REMARKS:

DRAFT

ALTERNATIVE #4, STAGE 3

PAGE 2 OF 2
 DATE 06/17/97 14:18:17
 BY DKH/RNO

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FERIBILITY ESTIMATE, STAGE 3
 PHRC02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. Z475AAG1

WBS DESCRIPTION	ESTIMATE SUBTOTAL	ESCALATION %	SUB TOTAL	CONTINGENCY %	SUB TOTAL	SITE ALLOCAT'N	TOTAL DOLLARS
310430 ALTERNATIVE 4 - STAGE 3	215638	0.00	0	30	64692	74758	355088
PROJECT TOTAL	215,638	0.00	0	30	280,330	74,758	355,088

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 PROJECT NO. 661945/73RUL5
 FILE NO. 2475A41

209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PIMCRO3 - ESTIMATE BASIS SHEET

PAGE 3 OF 9
 DATE 06/16/97 14:17:07
 BY DKH/RMO

1. ESTIMATE PURPOSE
 THIS ESTIMATE WILL BE USED FOR A SCOPING STUDY.
2. ESTIMATE TECHNICAL BASIS
 A. THIS ESTIMATE HAS BEEN PREPARED FOR LOCKHEED MARTIN HANFORD CORP. AS REQUESTED BY FDMW PROJECT MANAGER.
 B. A DETAILED DESCRIPTION OF THE SCOPE OF WORK MAY BE FOUND IN THE OUTLINE OF ALTERNATIVES, AN UNDATED AND
 C. THE FOLLOWING CONSTRAINTS AND/OR SPECIAL CONDITIONS EXIST: ALL WORK DONE IN THE CRITICAL ASSEMBLY ROOM AND
 IN THE MIXING ROOM WILL REQUIRE FOLLOWING THE APPROPRIATE RADIATION WORK PROCEDURE.
3. ESTIMATE METHODOLOGY
 A. DIRECT LOADING TECHNIQUE WAS USED TO COME UP WITH THE LABOR HOURS WHEN NECESSARY DUE TO THE UNDEFINED SCOPE.
 (1) CONSTRUCTION LABOR, MATERIAL AND EQUIPMENT UNITS HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD
 CONSTRUCTION ESTIMATING RESOURCES, PUBLISHED ESTIMATING MANUALS AND R.S. MEANS
- B. DIRECT COST FACTORS
 (1) SALARIES AND BONUS FACTORS ARE SHOWN SINCE THEY ARE CONSIDERED TO BE INCLUDED IN THE MATERIAL PROCUREMENT RATE (NPR).
 (2) AN ESTIMATING FACTOR OF 15% HAS BEEN APPLIED TO DIRECT CRAFT LABOR FOR GENERAL REQUIREMENTS AND
 23.58% FOR TECHNICAL SERVICES.
 (3) CONSUMABLES ARE ESTIMATED AT 3.2% OF DIRECT CRAFT LABOR COSTS.
 (4) SPECIAL WORK PROCEDURE (SWP) FACTORS ARE APPLIED AGAINST DIRECT LABOR FOR ACTUAL TIME LOST DUE TO THE PERSONNEL
 PROTECTIVE EQUIPMENT AND PROCEDURES THAT HAVE BEEN APPLIED AS FOLLOWS:
 (5) PROTECTIVE EQUIPMENT AND PROCEDURES HAVE BEEN APPLIED AT 15%
 MASK WORK AT 85% PLUS 15% FOR PROTECTIVE CLOTHING,
 CONTAMINATION RESTRICTIONS ASSOCIATED WITH RADIATION DOSE LIMITS (BURNOUT) HAVE NOT BEEN CALCULATED AS IT IS NOT
 BELIEVED TO BE A CONCERN FOR THESE ACTIVITIES.
- (6) PREMIUM PAY
 OVERTIME REQUIREMENTS AND SHIFT DIFFERENTIAL PAY FOR CRAFT LABOR WILL NOT BE REQUIRED FOR THIS WORK, AS STRAIGHT
 TIME AND BONUS ARE USED TO ACCOMPLISH THIS WORK.
 (7) GENERAL CONTRACTOR OF 7% HAS BEEN APPLIED TO DIRECT CRAFT LABOR CREWS.
 (8) A FACTOR OF 10% HAS BEEN APPLIED TO DIRECT CRAFT LABOR TO ALLOW FOR USAGE OF
 GOVERNMENT OWNED EQUIPMENT CONTROLLED BY DYNACORP.
- C. RATES
 (1) FLUOR DANIEL NORTHWEST LABOR RATES ARE BASED UPON THE FLUOR DANIEL FEDERAL OPERATIONS (FEDO) DISCLOSURE STATEMENT
 AND APPROVED FOR THE MOST RECENT COST HISTORY.
 (2) FLUOR DANIEL NORTHWEST SERVICES (CONSTRUCTION CRAFT LABOR) RATES ARE THOSE LISTED IN APPENDIX A TO THE HANFORD SITE
 STABILIZATION AGREEMENT.
 (3) FDM & PHMC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) POST 321R REPORT
 ORGANIZATION RATES PLUS ADJRS.

LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. Z475AA01

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE
 PHMCR03 - ESTIMATE BASIS SHEET

PAGE 4 OF 9
 DATE 06/16/97 14:17:07
 BY DKN/RWO

- D. SITE ALLOCATIONS FACTORS
- SITE ALLOCATION FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.
- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 14% FOR FDNW, 10% FOR FDNWS (CONSTRUCTION).
 - (2) HANFORD SITE G&A RATE OF 16.7% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS.
 - (3) HANFORD SITE MPR RATE OF 7.0% IS APPLIED TO ALL PURCHASED MATERIAL AND 7.7% TO ALL PURCHASED SERVICES TO LIQUIDATE THE COST OF PROCUREMENT (INCLUDING RECEIVING).
- FDNW APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:
- (1) FDNW G&A CM FACTOR: A COMPOSITE FACTOR OF 33.04% HAS BEEN APPLIED TO TOTAL FDNW FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS) AND SITE G&A/FEE. OTHER COSTS AS FOLLOWS:
 - (2) FDNW G&A LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS = 33.04% FDNW LABOR = 28.37%, FDNWS CONSTRUCTION MANAGEMENT LABOR = 33.04%, FDNW CONTRACT AS/CM COSTS = 33.04% FDNW LABOR = 33.04%.
 - (3) FDNW MPR G&A MATERIAL FACTOR: A COMPOSITE FACTOR OF 24.87% HAS BEEN APPLIED TO TOTAL FDNW MATERIAL COST WHICH INCLUDES A MPR OF 7% AND MATERIAL G&A/FEE OF 16.7%.

4. ESCALATION
- CONSTRUCTION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FM-50.

5. CONTINGENCY
- A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE.
- "CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT, AND CONSTRUCTION; AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EW-30) COST AND SCHEDULE GUIDE).

- B. CONTINGENCY ALLOWANCE GUIDELINES
- THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A PLANNING/FEASIBILITY ESTIMATE IS 20% TO 30%.

- C. METHODOLOGY
- CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

- D. ANALYSIS
- AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:
- WBS SIXTHYX CONSTRUCTION, ENGINEERING AND PROJECT MANAGEMENT - A 30% CONTINGENCY HAS BEEN APPLIED TO COVER COSTS LIKELY TO SURFACE THAT HAVE NOT BEEN ANTICIPATED AT THIS EARLY STAGE OF PLANNING. TECHNIQUES TO BE UTILIZED FOR DECONTAMINATION, STABILIZATION AND REMOVAL WILL NEED FURTHER STUDY AND MANY OF THE ACTIVITIES WILL BE SUBJECT TO CHANGE AT ANY TIME DURING THE WORK PROGRESS.

PAGE 5 OF 9
DATE 06/16/97 14:17:07
BY DKH/RHO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE
PHMCRO3 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
LOCAL OFFICE: 10000 13TH AVE. S.W.
TUMACACI, AZ 85625/575-8800
FILE NO. 2475AAG1

6. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A.) COSTS FOR CLOSURE CERTIFICATIONS, WIPE SAMPLES, SAMPLE ANALYTICAL COSTS, CORE SAMPLES, SOIL SAMPLES, TECHNICAL PUBLICATIONS, VERIFICATION AND A DECOMMISSIONING PLAN HAVE NOT BEEN ADDRESSED, AND IF THESE ARE REQUIRED WILL BE INCLUDED.
- B.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- C.) THE ESTIMATE ASSUMED THAT BURN-OUT WOULD NOT BE ENCOUNTERED.
- D.) ENGINEERING AND PROJECT MANAGEMENT COSTS WERE FIGURED AS A PERCENTAGE OF CONSTRUCTION, SEE R08 REPORT.

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. Z475AAG1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMCRO4 - COMPANY/WBS SUMMARY

PAGE 6 OF 9
 DATE 06/17/97 14:18:20
 BY DKH/RMO

SORT CODE/WBS	DESCRIPTION	ESTIMATE		ESCALATION		SUB		CONTINGENCY		SUB		SITE		TOTAL DOLLARS
		SUBTOTAL	%	TOTAL	%	TOTAL	%	TOTAL	%	TOTAL	ALLOCAT'N			
FDNW	FLUOR DANIEL NORTHWEST	170802	0.00	0	170802	30	51241	222043	74758	296801				
	310430 ALTERNATIVE 4 - STAGE 3	170802	0.00	0	170802	30	51241	222043	74758	296801				
	TOTAL FDNW FLUOR DANIEL NORTHWEST													
LMHC	LOCKHEED MARTIN HANFORD CORP.	44836	0.00	0	44836	30	13451	58287	0	58287				
	310430 ALTERNATIVE 4 - STAGE 3	44836	0.00	0	44836	30	13451	58287	0	58287				
	TOTAL LMHC LOCKHEED MARTIN HANFORD COR													
	PROJECT TOTAL	215,638	0.00	0	215,638	30	64,692	280,330	74,758	355,088				

PAGE 7 OF 9
DATE 06/17/97 14:18:23
BY DKM/RMO

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY-ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
PHMCRO5 - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

FLUOR DANIEL NORTHWEST, INC.
LOCKHEED MARTIN HANFORD CORP.
JOB NO. E61945/F3RUL5
FILE NO. Z475AAG1

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONSTRUCTION MANAGEMENT %	TOTAL	OTHER COSTS	SUB TOTAL	TOTAL
310430	ALTERNATIVE 4 - STAGE 3	196381	9.81	19257	0	19257	215638
	PROJECT TOTAL	196,381		19,257	0	19,257	215,638

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/F3RUL5
 FILE NO. Z475AAG1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMC806 - SITE ALLOCATIONS BY WBS

PAGE 8 OF 9
 DATE 06/17/97 14:18:41
 BY DKH/RMO

WBS	DESCRIPTION	ESTIMATE	DYN	FDH GFS/G&A	FDH MPR	FDH GFS/G&A	FDH MPR/G&A	SITE ALLOC
		SUBTOTAL	EQ-USAGE	CONST.MGMT	F.P./S.C.	LABOR	MATERIAL	SUBTOTAL
310430	ALTERNATIVE 4 - STAGE 3	196381	7324	6363	0	43370	449	57506
PROJECT TOTAL		196,381	7,324	6,363	0	43,370	449	57,506

FLUOR DANIEL NORTHWEST, INC.
 LOCKREED MARTIN HANFORD CORP.
 JOB NO. 661945/F3RUL5
 FILE NO. Z475AAG1

** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 9 OF 9
 DATE 06/17/97 14:18:25
 BY DKN/RMO

WBS DESCRIPTION	SITE ALLOC SUBTOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
310430 ALTERNATIVE 4 - STAGE 3	57506	0.00	0	30	17252
PROJECT TOTAL	57,506	0.00	0	30	17,252
					74,758

** TEST - INTERACTIVE ESTIMATING **										
2096 FACILITY ENGINEERING STUDY										
PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3										
PHMC008 - ESTIMATE DETAIL BY WBS / COST CODE										
DATE 06/17/97 14:18:28										
BY DKH/RMO										
PAGE 1										
FLUOR DANIEL NORTHWEST, INC.										
LOCKHEED MARTIN HANFORD CORP.										
JOB NO. E61945/F3RUL5										
FILE NO. Z475AAG1										
ACCOUNT										
DESCRIPTION										
ALTERNATIVE 4 - STAGE 3										
310430										
310430.00										
TECHNICAL SERVICES										

DEFINITIVE DESIGN										

AT 25 % OF CONSTRUCTION										

ENGINEERING/ INSPECTION										

AT 15% OF CONSTRUCTION										

PROJECT MANAGEMENT										

AT 15% OF CONSTRUCTION										

SUBTOTAL										
TECHNICAL SERVICES										
1,060 69,879 0 0 0 0 0 0 0 0 69,879										
TOTAL										
COST CODE 00000										
WBS 310430										
(ESCALATION 0.00% - CONTINGENCY 30.00 %)										
310430.01										
GENERAL REQUIREMENTS										
310430.0106110										
BURIAL COSTS FOR 40 DRUMS OF										
LLW CONCRETE DEBRIS AT										
\$15.25/CF										
SUBTOTAL										
GENERAL REQUIREMENTS										
0 0 0 0 4,270 0 0 0 4,270										
TOTAL										
COST CODE 81001										
WBS 310430										
(ESCALATION 0.00% - CONTINGENCY 30.00 %)										
310430.01										
GENERAL REQUIREMENTS										
310430.0106000										
HPT TO MAN STEP-OFF PAD										
(MASK)										
SUBTOTAL										
GENERAL REQUIREMENTS										
400 19,112 0 0 0 0 0 0 0 0 19,112										
SUP 100.00%										
400 19112										
800 38,224										
TOTAL										
COST CODE 81001										
WBS 310430										

FLUOR DANIEL NORTHWEST, INC.
 2096 FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE
 FILE NO. 2475A61

PAGE 2
 DATE 06/17/97 14:18:28
 BY DKH/RMO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / 8 & 1	TOTAL DOLLARS
(ESCALATION 0.00% - CONTINGENCY 30.00 %)											
310430-.02	SITEWORK	810 M	0	0	0	0	0	0	0	0	0
310430-.0206000	*****STAGE 3*****										
310430-.0206020	REMOVE ALL REMAINING EQUIPMENT.	810 M	1 L/S	160	6080	0	200	0	0	7	6287
310430-.0206022	BURIAL BOX ALLOWANCE	810 M	2 EA	0	0	0	0	2000	0	0	2000
310430-.0206040	REMOVE REMAINING CONFINEMENT	810 M	1 L/S	40	1448	0	200	0	0	7	1655
310430-.0206042	VENTILATION SYSTEM - DUCTS, FILL BURIAL BOX ALLOWANCE	810 M	2 EA	0	0	0	0	2000	0	0	2000
310430-.0206060	SEAL PIPING BETWEEN CAR AND MIX ROOM	810 M	1 L/S	16	618	0	50	0	0	2	670
310430-.0206080	SCABBLE/BUSH HAMMER CONCRETE WALLS AND FLOOR	810 M	6120 SF	447	12208	0	122	0	0	4	12334
310430-.0206082	SCABBLE/BUSH HAMMER CONCRETE WALLS AND FLOOR SECOND TIME	810 M	1 L/S	8	382	0	0	0	0	0	382
310430-.0206090	IN HOT AREAS ONLY	810 M	3000 SF	219	5981	0	60	0	0	2	6043
310430-.0206092	SURVEY	810 M	1 L/S	8	382	0	0	0	0	0	382
310430-.0206100	SCABBLE/BUSH HAMMER CONCRETE WALLS AND FLOOR THIRD TIME	810 M	200 SF	13	410	0	4	0	0	0	414
310430-.0206102	IN SURVEY	810 M	1 L/S	8	382	0	0	0	0	0	382
310430-.0206110	DRUM COSTS, 55 GAL W/LINER	810 M	40 EA	0	0	0	4000	0	0	0	4000
310430-.0206140	ISOLATE TANKS TK-109, 110 AND 111, FILL WITH GROUT.	810 M	1 L/S	64	2304	100	50	0	0	2	2456
(MASK)											
SUBTOTAL				985	30,195	100	4,686	4,000	0	24	39,005
CONSUMABLES 3.20 %											
SVP 100.00%				985	30195		966				966
GENERAL FOREMAN 7.00 %				137	4257						30195
GENERAL REQUIREMENTS 15.00 %				316	9692						9692
SALES TAX 8.00 %							452				452
OR&P (CON MARKUPS ONLY)										0	49
COST CODE 81002				2,424	74,309	100	6,104	4,000	0	73	84,587
WBS 310430											
(ESCALATION 0.00% - CONTINGENCY 30.00 %)											
TOTAL											

```

FLUOR DANIEL NORTHWEST, INC.
LOCKREED MARTIN HANFORD CORP.
JOB NO. 661945/ESRUL5
FILE NO. Z475AAG1

** TEST - INTERACTIVE ESTIMATING **
209E FACILITY ENGINEERING STUDY
PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

ACCOUNT      DESCRIPTION
=====
COST CODE    QUANTITY  MANHOURS  LABOR  USAGE  EQUIP  MATERIAL  CONTRACT  SUB-  EQUIP-  OH&P  TOTAL
=====
TOTAL WBS 310430 ALTERNATIVE 4 - STAGE 3
4,284      182,412  100      6,104      8,270      0      196,960

```

FLUOR DANIEL NORTHWEST, INC.
 LOCKHEED MARTIN HANFORD CORP.
 JOB NO. E61945/ESRUL5
 FILE NO. Z475AAG1


** TEST - INTERACTIVE ESTIMATING **
 209E FACILITY ENGINEERING STUDY
 PLANNING/FEASIBILITY ESTIMATE - ALT #4, STAGE 3
 PHMCR08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 4
 DATE 06/17/97 14:18:29
 BY DKH/RMO

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	CONTRACT	SUB- MENT	EQUIP- / B & I	OH&P DOLLARS	TOTAL
				4,284	182,412	100	6,104	8,270	0	73	196,960	
REPORT TOTAL												

APPENDIX B

Schedules



APPENDIX C

Equipment List

	<u>Page</u>
Mix Room Equipment	C-1
Critical Assembly Room Equipment	C-2

Asset	Name	Capacity (liters)	Contamination	Dimensions	Location	Construction
HO-200	Mix Room Glovebox	—	2g Pu	Mix Room	Center Mix Room	1/2" stainless steel, ASTM A240 304L
ST-217	Load in/out station	—	—	Inner surface area ~300 sq ft	HO-200	1/2" stainless steel, ASTM A240 304L
ST-219	Load in airlock	—	—	Inner surface area ~11 sq ft	HO-200	1/2" stainless steel, ASTM A240 304L
Tk-208	Prover vessel	10	—	circular, 11" dia, 30 1/2" tall	HO-200	glass
Tk-213	Concentrator	18	1 g Pu	circular, 10 7/8" ID, 14 1/2" OD, 29 3/4" tall, encased, 16" OD, 15 1/2" ID, 30 1/2" tall	HO-200	tank, 16" titanium sides, 1/2" titanium top, ASTM B265 GR2 encasement, 1/2" stainless steel, ASTM A240 304L
E-214	Condenser	—	—	—	HO-200	—
P-201	Pump	—	—	—	HO-200	—
P-203	Process condensate catch tank	15	—	—	HO-200	—
Tk-215	Process condensate catch tank	15	—	circular, 6" ID, 36 1/8" tall	HO-200	glass
Tk-216	Closed loop expansion tank	15	—	circular, 6" ID, 36 1/8" tall	HO-200	glass
Tk-242	Pu Storage Tank Enclosure	5	—	7" ID, 19 1/2" tall	HO-200	6" stainless steel sch40 pipe, ASTM A312 TP 304L
HO-230	Pu Storage Tank	—	—	Exposed outer surface area ~180 sq ft	West Wall Mix Room	1/2" stainless steel, ASTM A240 304L
Tk-231	Pu Storage Tank	320	42 g Pu	15 1/2" long, 3" tall, 3" wide	HO-230	1/2" stainless steel, ASTM A240 304L
Tk-232	Pu Storage Tank	320	31 g Pu	15 1/2" long, 3" tall, 3" wide	HO-230	1/2" stainless steel, ASTM A240 304L
Tk-233	Pu Storage Tank	320	47 g Pu	15 1/2" long, 3" tall, 3" wide	HO-230	1/2" stainless steel, ASTM A240 304L
Tk-234	Pu Storage Tank	158	33 g Pu	9" long, 3" tall, 3" wide	HO-230	1/2" stainless steel, ASTM A240 304L
Tk-235	Pu Storage Tank	158	3 g Pu	9" long, 3" tall, 3" wide	HO-230	1/2" stainless steel, ASTM A240 304L
HO-280	Fume hood	—	—	47" wide, 66 1/2" tall, 34" deep	West Wall Mix Room	1/2" stainless steel, ASTM A240 304L

Vessel	Name	Capacity (liters)	Contamination	Dimensions	Location	Construction
HO-120	Pu Pump Glovebox	—	1 g Pu	25" deep, 21 1/8" tall, 35" wide, sloped view port top front	West Wall CAR	3/8" stainless steel, ASTM A240 304L
P-122	Pu Fill Pump	—	—	—	HO-120	—
HO-130	Uranium Pump Glovebox	—	—	18" deep, 18" tall, 30" wide	North Wall CAR	3/16" stainless steel, ASTM A240 304L
P-131	Uranium Mix Pump	—	—	—	HO-130	—
P-132	Uranium Fill Pump	—	—	—	HO-130	—
SPL-133	Sampler	—	—	8" square, 19" tall	Center CAR, Northwest	1/2" stainless steel, ASTM A240 304L
HO-140	Assembly Hood #1	—	—	35" long, 26" tall, 3" wide	Under HO-140, encased in concrete 3' below floor	1/2" stainless steel, ASTM A240 304L
TK-109	Dump tank for HO-140	40	Quantity unknown	24" square, 4.6m tall	Center CAR, Northeast	1/2" stainless steel, ASTM A240 304L
HO-170	Assembly Hood #2	—	Pu sources (oil and scrap), 0.1 lg G-252 source, 10 g U source, tritium sources	8" square, 15" tall	Under HO-170, encased in concrete 3' below floor	1/2" stainless steel, ASTM A240 304L
TK-110	Dump tank for HO-170	40	Assumed, quantity unknown	35" long, 26" tall, 3" wide	Center CAR, Northeast	1/2" stainless steel, ASTM A240 304L
TK-141	Bel lows Tank	Variable	36 g Pu	Bel lows with 1/16" thick, 3' 6" square end plates; expandable from 3" to 9" wide; (9' x 5' x 3' x 3-9")	Under HO-170, encased in concrete 3' below floor	1/2" stainless steel, ASTM A240 304L
TK-142	Bel lows Reflector Tank	—	—	56" long, 37" deep, 27" wide	TK-142	1/2" stainless steel, ASTM A240 304L
TK-101	Condensate storage tank #1	330	1 g Pu	41" tall, 3" wide, 19" long	HO-140	1/2" stainless steel, ASTM A240 304L
TK-102	U Storage tank #2	330	8 g Pu	41" tall, 3" wide, 19" long	North Wall CAR	1/2" stainless steel, ASTM A240 304L
TK-103	Pu Storage tank #3	290	8 g Pu	41" tall, 3" wide, 18" long	North Wall CAR	1/2" stainless steel, ASTM A240 304L
TK-104	Pu Storage tank #4	290	15 g Pu	41" tall, 3" wide, 18" long	North Wall CAR	1/2" stainless steel, ASTM A240 304L
TK-105	Dump storage tank	400	36 g Pu	40" tall, 3" wide, 20 1/2" long	West Wall CAR	1/2" stainless steel, ASTM A240 304L
TK-106	Dump mix tank	400	123 g Pu	40" tall, 3" wide, 20 1/2" long	West Wall CAR	1/2" stainless steel, ASTM A240 304L
TK-108	Pu air tank assembly system (FEAS)	—	—	No information available from drawings	Center CAR, Southwest	No information available from drawings
14"	Experimental Vessel	—	2.7 g Pu	No information available from drawings	FEAS	No information available from drawings
27"	Experimental Vessel	—	4.2 g Pu	No information available from drawings	FEAS	No information available from drawings
TK-111	Waste hold-up tank	220	Quantity unknown	8' long, 31' 10" sloped downward to 4' tall, 3' wide	Outside bldg, south side, under waste pit	1/2" stainless steel, ASTM A240 304L
TK-160	Consolidated Fuel Reprocessing Program (CFRP) water tank	—	—	5' tall, 6' 2" wide, 3' 3" deep; rests upon legs 4' 1/2" above floor	Center CAR, West	1/2" stainless steel, ASTM A240 304L
TK-161	CFRP process tank	110	4 g Pu	14" ID, 42 3/8" tall	TK-160	1/2" stainless steel, ASTM A240 304L
TK-162	CFRP process tank	400	4 g Pu	27" ID, 42 3/8" tall	TK-160	1/2" stainless steel, ASTM A240 304L

DISTRIBUTION SHEET

To Distribution	From C. H. Brevick	Page 1 of 2			
		Date July 7, 1997			
Project Title/Work Order Engineering Study for Closure of 209E Facility/E61945		EDT No. 641029			
		ECN No.			
Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only

Babcock & Wilcox Hanford Company

R. W. Bailey	S6-15	X
J. P. Hayfield	S6-15	X
W. A. Peiffer	S6-15	X
L. D. Stefanski	S6-15	X

Department of Energy Richland Operations

C. A. Ashley	S7-54	X
J. D. Banks	S7-54	X
M. L. Ramsay	S7-54	X

Fluor Daniel Northwest

E. R. Amante	E6-08	X
C. H. Brevick	E6-08	X (5)
S. D. Consort	E6-07	X
L. A. Gaddis	H5-57	X
E. D. Johnson	E6-08	X
W. H. Hays	E6-08	X
D. A. Lauhala	E6-08	X
D. A. Moody	H5-57	X
E. A. Vickery	E6-08	X
Engr. Publications	E6-63	X

Link Technologies, Incorporated

E. N. Dodd III	S4-66	X
----------------	-------	---

Lockheed Martin Hanford Corporation

R. A. Dodd	S5-07	X
L. R. Dunbar	H7-07	X
M. S. Harrington	R2-88	X (10)
M. D. Long	R2-88	X
P. C. Miller	R1-51	X
R. P. Raven	R1-51	X
W. E. Ross	S5-07	X
J. W. Wicks	R2-50	X

Lockheed Martin Services, Inc.

Document Control	R1-29	X
------------------	-------	---

Maintenance Concepts

C. E. Golden	R2-88	X
B. Q. Peery	R2-88	X
D. M. Stenkamp	R2-88	X
M. M. Jennings	R2-88	X

Waste Management Federal Services

P. A. Gagnon	S6-31	X
M. E. Lakes	S6-31	X
F. C. Schmidt	S6-30	X
M. L. Windsor	S6-30	X
