

DATA 4 (2)
JUL 20 1998

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 622270

2. To: (Receiving Organization) Distribution		3. From: (Originating Organization) TWRS Projects/SST Retrieval		4. Related EDT No.: n/a	
5. Proj./Prog./Dept./Div.: W-320 TWRS/TCPN # D2991		6. Design Authority/ Design Agent/Cog. Engr.: JW Bailey, NHC		7. Purchase Order No.: n/a	
8. Originator Remarks: For approval and release of a new supporting document. This document has been generated to ensure retrievability of the Project W-320 "Construction Specification W-320-C7".				9. Equip./Component No.: n/a	
11. Receiver Remarks: 11A. Design Baseline Document? ☒ Yes ☐ No				10. System/Bldg./Facility: 241-C-106	
				12. Major Assm. Dwg. No.: n/a	
				13. Permit/Permit Application No.: n/a	
				14. Required Response Date:	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Designator	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	HNF-2536	-	0	Project W-320, 241-C-106 Sluicing, Construction Specification W-320-C7	NA			-

KEY

16. Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
2		Design Authority	JW Bailey	7/18/98	S2-48						
		Design Agent									
2		Cog. Eng.	M.C. Davenport	7/18/98	S2-48						
2		Cog. Mgr.	JW Bailey	7/18/98	S2-48						
		QA									
		Safety									
		Env.									

18. M.C. Davenport Signature of EDT Originator Date 7/18/98		19. Authorized Representative Signature of Receiving Organization Date		20. JW Bailey Design Authority/ Cognizant Manager Date 7/18/98		21. DOE APPROVAL (if required) Ctrl. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments	
---	--	--	--	---	--	---	--

Project W-320, 241-C-106 Sluicing, Construction Specification, W-320-C7

John W. Bailey

Numatec Hanford Co., Richland, WA 99352

U.S. Department of Energy Contract DE-AC09-96RL13200

EDT/ECN: 622270

UC: 506

Org Code: 8C452

Charge Code: D2991/HANA0600

B&R Code: EW3130010

Total Pages: 182


Key Words: W-320, Sluicing, Tank 241-C-106, Tank 241-AY-102,
WRSS, Specifications, Construction.

Abstract: This supporting document has been prepared to make the construction specifications for Project W-320, readily available.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

[Signature] 7/20/98
Release Approval Date



Approved for Public Release

222 6/25/98

ENGINEERING CHANGE NOTICE

Page 1 of 3

1. ECN 649182

Proj. ECN W-320-809

2. ECN Category (mark one) Supplemental ☐ Direct Revision ☒ Change ECN ☐ Temporary Standby ☐ Supersedeure ☐ Cancel/Void ☐	3. Originator's Name, Organization, MSIN, and Telephone No. DL. Evans, FDNW, S2-47, 373-2688	4. USQ Required? ☐ Yes ☒ No <i>Quick 6/25/98</i> <i>(See block 14b)</i>	5. Date 6/25/98										
12a. Modification Work ☐ Yes (fill out Blk. 12b) ☒ No (NA Blks. 12b, 12c, 12d)	12b. Work Package No. NA	12c. Modification Work Complete NA Design Authority/Cog. Engineer Signature & Date	12d. Restored to Original Condition (Temp. or Standby ECN only) NA Design Authority/Cog. Engineer Signature & Date										
13a. Description of Change 13b. Design Baseline Document? ☒ Yes ☐ No GS As-Built and General Revisions of the construction specification W-320-C7. Changes to include: <table border="0"> <tr> <td>Section Pg Paragraph</td> <td>Change</td> </tr> <tr> <td>01010 1 1.1.1</td> <td>delete ", Sh 6"</td> </tr> <tr> <td>01010 1 1.3.1</td> <td>delete ", Sh 6"</td> </tr> <tr> <td>05055 1 2.2.1</td> <td>change "(Safety Classes 1 and 2)" to "(Safety Class and Safety Significant)"</td> </tr> <tr> <td>05055 1 2.2.2</td> <td>change "(Safety Classes 3 and 4)" to "(General Service)"</td> </tr> </table> Continued on Page 3				Section Pg Paragraph	Change	01010 1 1.1.1	delete ", Sh 6"	01010 1 1.3.1	delete ", Sh 6"	05055 1 2.2.1	change "(Safety Classes 1 and 2)" to "(Safety Class and Safety Significant)"	05055 1 2.2.2	change "(Safety Classes 3 and 4)" to "(General Service)"
Section Pg Paragraph	Change												
01010 1 1.1.1	delete ", Sh 6"												
01010 1 1.3.1	delete ", Sh 6"												
05055 1 2.2.1	change "(Safety Classes 1 and 2)" to "(Safety Class and Safety Significant)"												
05055 1 2.2.2	change "(Safety Classes 3 and 4)" to "(General Service)"												
14a. Justification (mark one) Criteria Change ☐ Design Improvement ☐ Environmental ☐ Facility Deactivation ☐ As-Found ☒ Facilitate Const. ☐ Const. Error/Omission ☐ Design Error/Omission ☐ 14b. Justification Details As-Built construction specification for project turnover. No USQ required because categorical exclusion (TF-96-0690, Rev 2) applies. No project calculations are affected by this work. An independent review of this design change was performed by FDNW in accordance with HNF-PRO-445.													
15. Distribution (include name, MSIN, and no. of copies) CDC, S2-53, 1 TJ Kasnick, S2-47, 1 JW Bailey, S2-48, 1 RL Powers, S5-13, 1 Project Files, R1-29,		RELEASE STAMP DATE: STA: 4 HANFORD RELEASE ID: 2 JUL 08 1998											

ENGINEERING CHANGE NOTICE

Page 2 of 3

1. ECN (use no. from pg. 1)

W-320-809

16. Design Verification Required
☒ Yes
☐ No

17. Cost Impact

ENGINEERING

Additional ☐ \$ NA
 Savings ☐ \$

CONSTRUCTION

Additional ☐ \$ NA
 Savings ☐ \$

18. Schedule Impact (days)

Improvement ☐ NA
 Delay ☐

19. Change Impact Review: Indicate the related documents (other than the engineering documents identified on Side 1) that will be affected by the change described in Block 13. Enter the affected document number in Block 20.

SDD/DD	☐	Selamto/Stress Analysis	☐	Tank Calibration Manual	☐
Functional Design Criteria	☐	Stress/Design Report	☐	Health Physics Procedure	☐
Operating Specification	☐	Interface Control Drawing	☐	Sparse Multiple Unit Listing	☐
Criticality Specification	☐	Calibration Procedure	☐	Test Procedures/Specification	☐
Conceptual Design Report	☐	Installation Procedure	☐	Component Index	☐
Equipment Spec.	☐	Maintenance Procedure	☐	ASME Coded Item	☐
Const. Spec.	☐	Engineering Procedure	☐	Human Factor Consideration	☐
Procurement Spec.	☐	Operating Instruction	☐	Computer Software	☐
Vendor Information	☐	Operating Procedure	☐	Electric Circuit Schedule	☐
OM Manual	☐	Operational Safety Requirement	☐	ICRS Procedure	☐
FSAR/ISAR	☐	IEPD Drawing	☐	Process Control Manual/Plan	☐
Safety Equipment List	☐	Cell Arrangement Drawing	☐	Process Flow Chart	☐
Radiation Work Permit	☐	Essential Material Specification	☐	Purchase Requisition	☐
Environmental Impact Statement	☐	Fac. Proc. Samp. Schedule	☐	Tickler File	☐
Environmental Report	☐	Inspection Plan	☐	None. <i>6/29/98</i>	☒
Environmental Permit	☐	Inventory Adjustment Request	☐		☐

20. Other Affected Documents: (NOTE: Documents listed below will not be revised by this ECN.) Signatures below indicate that the signing organization has been notified of other affected documents listed below.

Document Number/Revision
 NA

Document Number/Revision

Document Number Revision

21. Approvals

Design Authority

Cog. Eng.

Cog. Mgr.

QA

Safety

Environ.

Other

Date

6/29/98

6/29/98

6/29/98

6-28-98

7-1-98

07-08-98

Design Agent

PE

QA

Safety

Design

Environ.

Checker

Other

Signature

Danny L. Evans

D.L. Evans

D.L. Evans

D.L. Evans

D.L. Evans

Date

6/25/98

06-25-98

NA

NA

6/25/98

NA

6/25/98

DEPARTMENT OF ENERGY

Signature or a Control Number that tracks the Approval Signature

ADDITIONAL



EXPIRES 7/2/00

ENGINEERING CHANGE NOTICE CONTINUATION SHEET

Page 3 of 3

ECN W-320-809

Date 6/25/98

Block 13a, continued:

Section Pg Paragraph

Change

15493	2	1.3.1	change "... : Safety products ..." to "... : Safety Significant products ... "
15493	11	PIPE CODE M-9	change "(Safety Class 2)" to "(Safety Significant)"
15493	12	PIPE CODE M-26a	change "(Safety Class 2 3)" to "(General Services)"
15493	12	PIPE CODE M-33b	change "(Safety Class 3)" to "(General Services)"
15507	14	PIPE CODE M-4	change "(Safety Class 3)" to "(General Services)"
16400	3	1.3.2	change "Safety Class 1 (SC1) Products: SC1 ... "
			to "Safety Class (SC) Products: SC ... " delete "1" 3 places
16400	4	1.6.1.2	change "(Safety Class 1)" to "(Safety Class)" delete "1"
16400	10	3.1.2	change "SC1" to "SC" delete "1"
16400	15	3.3.1	change "For SC1 Components: SC1 ... "
			to "For SC Components: SC ... " delete "1" 2 places

AS-BUILT REV 1

TANK 241-C-106 SLUICING
AT TANK FARM

Original Issue: 08/30/95






Prepared By

Fluor Daniel Northwest
Richland, Washington

For

Numatec Hanford Corporation

Contract 651005


Client Concurrence6/29/98
Date
Project Manager06-25-98
Date
Lead Engineer6/25/98
Date
Field Concurrence6/25/98
Date
Checked By6/25/98
Date
Prepared By6/25/98
Date

[illegible]

The ECNs affecting specification are as follows:

HNF-2536, Rev. 0
Page vi

<u>ECN W-320-113</u> 15493-5	<u>ECN W-320-200</u> 13440-16, 17, 18	<u>ECN W-320-499</u> 15507-6, 11
<u>ECN W-320-116</u> 15493-1, 2, 7, 9, 11, 12	<u>ECN W-320-201</u> 15493-8	<u>ECN W-320-525</u> 16640-6
<u>ECN W-320-117</u> 03400-1, 2, 3, 4, 5, 7	<u>ECN W-320-203</u> 15507-11	<u>ECN W-320-548</u> 02200-2, 3, 4 02225-2, 3, 5 09900-5 15507-15
<u>ECN W-320-121</u> 16640-5, 7, 8	<u>ECN W-320-205</u> 15493-12	<u>ECN W-320-588</u> 15507-4, 5
<u>ECN W-320-123</u> 03300-1, 2, 5	<u>ECN W-320-281</u> 03300-3	<u>ECN W-320-597</u> 05500-2 16640-2
<u>ECN W-320-128</u> 13440-6, 10, 11, 17, 19, 20, 23, 24	<u>ECN W-320-290</u> 03300-2, 3, 7	<u>ECN W-320-601</u> 13440-3
<u>ECN W-320-138</u> 05500-1, 3	<u>ECN W-320-294</u> 15493-12	<u>ECN W-320-662</u> 15493-1, 2, 3 15493-Appendix A
<u>ECN W-320-150</u> 16640-6	<u>ECN W-320-335</u> 15493-3 15507-6	<u>ECN W-320-748</u> 15493-9
<u>ECN W-320-166</u> 13440-7, 10, 24	<u>ECN W-320-347</u> 15493-7, 9	<u>ECN W-320-809</u> 01010-1, 2 05055-1 15493-2, 11, 12 15507-14 16400-3, 4, 10, 15
<u>ECN W-320-167</u> 01300-2 16400-7, 9, 10, 17	<u>ECN W-320-419</u> 16400-16	
<u>ECN W-320-170</u> 09900-1, 5	<u>ECN W-320-441</u> 15493-7, 9	
<u>ECN W-320-173</u> 09900-5	<u>ECN W-320-454</u> 15493-9	
<u>ECN W-320-197</u> 15507-6	<u>ECN W-320-458</u> 13440-2	

W-320-C7

CONSTRUCTION SPECIFICATION

TANK 241-C-106 SLUICING
PACKAGE 3 - AY TANK FARM

Work Order ER4319

Prepared By
ICF Kaiser Hanford Company
Richland, Washington

For Westinghouse Hanford Company
Contract WHC 380393

ICF ENGINEERS HANFORD	
CONTROLLED DOCUMENT	
STATION NO. 4	
DATE	SEP 14 1995
PROJ / WO	W-320
NO	PLE-1

APPROVED

ICF Kaiser Hanford Company (ICF KH)

<u>Danny P. Evans</u>	<u>8/16/95</u>	<u>Shirley B. Swan</u>	<u>8-15-95</u>
Principal Lead Engineer	Date	Technical Documents	Date
<u>[Signature]</u>	<u>8/16/95</u>	<u>David L. G. Fort</u>	<u>8/16/95</u>
Safety	Date	Environmental Engineering	Date
<u>C. E. Jackson</u>	<u>8-15-95</u>	<u>[Signature]</u>	<u>8/16/95</u>
Quality Engineering	Date	Construction	Date
<u>[Signature]</u>	<u>8/16/95</u>		
Project Management	Date		

Westinghouse Hanford Company (WHC)

<u>Thomas H. May</u>	<u>8/22/95</u>
Projects Department	Date

OFFICIAL RELEASE
BY WHC
DATE
AUG 30 1995


CONSTRUCTION SPECIFICATION

TANK 241-C-106 SLUICING
PACKAGE 3 - AY TANK FARM


Prepared by
ICF Kaiser Hanford Company
Richland, Washington

CERTIFICATION


I certify that the indicated sections of this Specification were prepared by me or under my supervision and that I am a registered professional engineer under the laws of the State of Washington.




Harish K. Choudhry, PE
Instrumentation
Section 13440




Raymond A. Pina, PE
HVAC
Section 15507, 15990




Ronald W. Davidson, PE
Civil/Structural
Sections 02200, 02225,
02831, 03300, 03400, 05055,
05500, 09805, 09900



Carroll D. Jones, PE
Mechanical
Section 15493



Gregory P. McDonald, PE
Catholic Protection
Section 16640



Timothy J. Kasnick, PE
Electrical
Section 16400

TABLE OF CONTENTS

HNF-2536, Rev. 0
Page a-iii

	Page
Title and Approval Page	i
Certification Page	ii
Table of Contents	iii
	Total Pages
<u>DIVISION 1 - GENERAL REQUIREMENTS</u>	
Section 01010 Summary of Work	2
Section 01019 Items Furnished for Construction	1
Section 01200 Project Meetings	2
Section 01300 Submittals	3
Section 01400 Quality Assurance	3
Section 01610 Delivery, Storage, and Handling	3
Section 01630 Product Options and Substitutions	3
Section 01720 Project Record Documents	3
<u>DIVISION 2 - SITEWORK</u>	
Section 02200 Earthwork	4
Section 02225 Excavating, Backfilling and Compacting for Utilities	5
Section 02831 Chain Link Fences and Gates	3
<u>DIVISION 3 - CONCRETE</u>	
Section 03300 Cast-In-Place Concrete	7
Section 03400 Precast Concrete	8
<u>DIVISION 5 - METALS</u>	
Section 05055 Expansion Anchor Installations	2
Section 05500 Metal Fabrications	5
<u>DIVISION 9 - FINISHES</u>	
Section 09805 Special Protective Coating	5
Section 09900 Painting	5
<u>DIVISION 13 - SPECIAL CONSTRUCTION</u>	
Section 13440 Instrumentation	24
<u>DIVISION 15 - MECHANICAL</u>	
Section 15493 Chemical Process Piping Systems	12
Section 15507 Contaminated Air HVAC Systems	16
Appendix A Identification of Piping Systems	2
Section 15990 Testing, Adjusting, and Balancing	2
<u>DIVISION 16 - ELECTRICAL</u>	
Section 16400 Service and Distribution	17
Section 16640 Cathodic Protection	11

SECTION 01010
SUMMARY OF WORK

PART 1 - GENERAL

1.1 INTRODUCTION

1.1.1 Project W-320, WASTE RETRIEVAL SLUICING SYSTEM (WRSS), is located as shown on Drawing H-2-818423, ~~SH-6-~~ ECN-809

1.1.2 This Specification is for procurement, fabrication and installation of equipment at the "AY" Tank Farm, including some equipment just outside the "AY" Tank Farm fence, necessary to support the sluicing operation.

1.2 STATEMENT OF WORK

1.2.1 Scope: Work consists of furnishing labor, equipment, and materials to provide the means to procure materials and equipment, fabricate items, excavate and place concrete, and install equipment, piping, wiring, and structures in accordance with the Project documents.

1.2.2 Work Included: The following itemization is intended to be broad in scope, and identify major work elements only.

1.2.2.1 Excavation for process piping and electrical conduit trenches, and foundations for small structures.

1.2.2.2 Placement of concrete for foundations and equipment pads.

1.2.2.3 Procurement and installation of double walled piping, electrical conduit, and electrical and instrumentation cable.

1.2.2.4 Core drilling existing concrete.

1.2.2.5 Furnishing and installation of electrical distribution equipment.

1.2.2.6 Fabrication and installation of in-pit pipe "jumpers," including related valves, instruments and wiring.

1.2.2.7 Installation of vertical submersible pump and horizontal booster pump into tank access riser pits (Specification W-320-P17).

1.2.2.8 Installation of the concrete seismic foundation. Assembly and installation of two Seismic Shutdown Systems with Environmental (missile shield) Enclosures (Specifications W-320-P35 and P36).

1.2.2.9 Installation of electrical and cathodic protection equipment. Pulling and termination of power and control wiring at the AY-Farm.

1.2.2.10 Installation of conduit and wiring between tank-top pit devices and the operator station, electrical distribution panel, and motor starters located in the electrical equipment skid just outside the AY-Farm fence.

- 1.2.2.11 Installation of Electrical Equipment Skid (Specification W-320-P33).
- 1.2.2.12 Furnishing and installation of Instrumentation and Controls for Operator Station located on Electrical Equipment Skid.
- 1.2.2.13 Procurement, assembly, and installation of pit cooling system at 241-AY-02E pit.
- 1.2.2.14 Performing construction tests on installed equipment, such as pressure tests on pipe, and insulation and continuity tests on wiring.
- 1.2.3 Work Not Included: The following work elements are part of the Project, are covered by other documents noted, and will be done by others, concurrently with work included in the Project documents.
 - 1.2.3.1 Fabrication and installation of construction support trailers.
- 1.3 DRAWINGS
 - 1.3.1 Drawings which show work required by the Project documents are listed on Drawing H-2-818423, ~~Sh-6-~~ ECN-809
- PART 2 - PRODUCTS
 - Not Used
- PART 3 - EXECUTION
 - Not Used

END OF SECTION

SECTION 01019

ITEMS FURNISHED FOR CONSTRUCTION

PART 1 - GENERAL

1.1 REFERENCES: Not Used

1.2 SUBMITTALS: Not Used

1.3 GENERAL

1.3.1 Material and equipment furnished or made available for incorporation into the Work are identified in this Section. Other services and utilities provided are covered in other sections of this Specification.

1.4 EQUIPMENT

1.4.1 Items listed below will be furnished for incorporation into the Work.

1.4.1.1 Sluice Pumps P-0621 and P-0622, procured under Specification W-320-P17. The Booster Pump includes a variable speed drive.

1.4.1.2 Pump winch, including position indication system procured under Specification W-320-P24.

1.4.1.3 Electrical equipment skid, procured under Specification W-320-P33.

1.4.1.4 Seismic Shutdown System and Enclosures, procured under Specifications W-320-P35 and P36.

1.4.2 Items noted in 1.4.1.1 through 1.4.1.4 are being procured by Operating Contractor and will be delivered to Project site. Notify the Construction Engineer 5 working days before need date to arrange for delivery.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

Not Used

END OF SECTION

SECTION 01200
PROJECT MEETINGS

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS: Not Used
- 1.3 SUMMARY
- 1.3.1 Representatives from ICF KH, CONTRACTOR, and major subcontractors shall participate in project meetings. Representatives from Operating Contractor and DOE may attend, as required by items to be discussed.
- 1.3.2 Meeting times and locations shall be mutually agreed to by CONTRACTOR and ICF KH, and will be held at the Hanford Site in Richland, Washington. Informal design reviews are an exception.
- 1.3.3 ICF KH will issue notices of meetings, and prepare and issue meeting minutes as promptly as possible after each meeting. Minutes will be distributed to project participants.
- 1.3.4 When applicable, minutes will identify action items, with assigned followup. Issues resolved will be reported, as well as closed action items.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

- 3.1 SITE LABOR CONFERENCE
- 3.1.1 Before starting construction at the worksite, CONTRACTOR and subcontractors shall conduct an informational conference concerning Hanford Site labor requirements applicable to the Project. Review the General Conditions relating to labor, and present a proposed work plan with craft utilization requirements.
- 3.1.2 ICF KH will send a meeting notice to representatives from labor organizations, identified by CONTRACTOR as those with members who may be utilized in construction, and are to attend the conference.
- 3.2 PRECONSTRUCTION CONFERENCE
- 3.2.1 A conference will be scheduled and chaired by ICF KH before the start of onsite work. Authorized representatives of CONTRACTOR and major subcontractors shall attend, and ICF KH will advise others having an interest in the Work.

- 3.2.2 The following items will be incorporated into the agenda.
- 3.2.2.1 Points of contact and key personnel representing Operating Contractor, Safety, Quality Assurance/Quality Control, Acceptance Inspection, and Construction Engineering.
- 3.2.2.2 Schedule requirements and restraints, submittals and work limitations.
- 3.2.2.3 Safety, construction progress meetings and their frequency, and certified payrolls.
- 3.2.2.4 Report requirements and their frequency.
- 3.2.2.5 ICF KH forms CONTRACTOR is required to use.
- 3.2.2.6 Quality requirements.
- 3.2.2.7 Major material and equipment lists.
- 3.2.2.8 Other pertinent items.
- 3.3 CONSTRUCTION PROGRESS MEETINGS
- 3.3.1 Meetings will be held every 2 weeks, at times and locations determined at the preconstruction conference, and will be approximately 1 hour long.
- 3.3.2 ICF KH will chair the meetings, and request attendance of key personnel required. Authorized representatives of CONTRACTOR and pertinent subcontractors shall attend.
- 3.3.3 The purpose is to monitor status, and provide a forum for exchanging pertinent information related to the Work. Major topics may include the following.
- 3.3.3.1 Schedule, cost, and construction status.
- 3.3.3.2 Design and scope changes.
- 3.3.3.3 Submittal status, key material, and equipment delivery status.
- 3.3.3.4 Potential problem areas.
- 3.3.3.5 Inspection and testing status.
- 3.3.3.6 Action item status, and goals for the next meeting.
- 3.3.3.7 Other appropriate items.

END OF SECTION

SECTION 01300

SUBMITTALS

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS: Not Used (See the other sections requiring submittals)
- 1.3 SUBMITTAL CONDITIONS
 - 1.3.1 Materials and equipment fabricated or installed without required approved submittals, or which differ from approved drawings or vendor data, are subject to rejection and replacement at CONTRACTOR's expense.
 - 1.3.2 Delays arising from failure to submit required drawings and other related data described in Contract Documents, in a timely manner, will not constitute excusable delays for extensions, unless excusable under other provisions of the Contract.
- 1.4 SUBMITTALS REQUIRED
 - 1.4.1 Required submittals are defined in Part 1 of the Specification Sections.
 - 1.4.2 Submittals are divided into 2 types; those requiring approval and those not requiring approval. Included in the former are submittals of architectural material samples, where ICF KH reserves the right to make final selections. Included in the latter are documents containing vendor information necessary for operations, and information for project records.
 - 1.4.3 Submittals are required no later than the times indicated. Those requiring ICF KH approval must be approved before further submittal related procurement, fabrication, or construction is accomplished. This also applies for ICF KH selections made from samples submitted.
- 1.5 SUBMITTAL REVIEWS
 - 1.5.1 Submittals requiring approval will be reviewed to verify completeness and conformance to requirements. Appropriate dispositions will be made as specified in Part 3.
 - 1.5.2 Allow 21 calendar days for ICF KH review and disposition of submittals. This time period will be measured from date of submittal receipt in ICF KH's office to date of return mailing.
 - 1.5.3 Submittals not requiring approval will be reviewed to verify completeness and adequacy for their intended purposes. If acceptable, these items are filed, and finally delivered to Operating Contractor. Unacceptable items will be handled as specified in Part 3.

- 1.5.4 If a submittal not requiring approval has not been returned within the specified time period, and ICF KH has not informed CONTRACTOR that additional review time is necessary, CONTRACTOR may consider it accepted by ICF KH.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

3.1 SUBMITTAL PROCEDURE

- 3.1.1 Transmit submittals using "Data Transmittal/Review," Form KEH 1838. Copies will be supplied during the Preconstruction Conference (see Section 01200).
- 3.1.2 Identify each submittal by submittal number, section/paragraph number and submittal title as shown on the master submittal log included with Contract Documents. The number of copies required includes 2 copies for return to CONTRACTOR. If necessary, provide additional copies required for return to CONTRACTOR.
- 3.1.2.1 Approval data (for products): Mark each line item package with the specification section and paragraph numbers specifying the product.
- 3.1.2.2 Vendor information (for products): Mark each line item package with the specification section and paragraph numbers specifying the product, and the item name, manufacturer's name, model or part number, and ICF KH tag number (if specified).
- 3.1.2.3 Items that require approval: Submit 6 copies, including 1 reproducible.
- 3.1.2.4 Samples for selections: Submit as required by the Sections of this Specification.
- 3.1.2.5 Items that do not require approval: Submit ~~10~~ 6 copies.
- 3.1.3 Review each submittal for completeness, compliance with Contract Documents, and proper identification before sending to ICF KH. Submittal data shall either be stamped, showing the review process has taken place, or the Data Transmittal form may be stamped "Reviewed for Compliance," and signed. Submittals not stamped or signed will be returned without consideration.
- 3.1.4 Procedures for performing certain types of work must be submitted for approval before work is commenced. Such procedures which have previously been approved by ICF KH, for work similar to that to be accomplished on this Project, may not need to be reapproved. Forward 1 copy of previously approved procedures to ICF KH, by Data Transmittal form, and identify each by section/paragraph number, title, and either procedure number or project number for which the procedure was approved.

ECN-167

Submittals will be reviewed by ICF KH and, if acceptable, retained for record. If a previously approved procedure is not acceptable, the submittal will be returned, with requirements for resubmittal.

3.2 ICF KH PROCESSING

3.2.1 Submittals requiring approval will be stamped by ICF KH, and marked "Approved," "Approved with Exception," or "Not Approved, Revise and Resubmit." Approval of submittals does not relieve CONTRACTOR of responsibility for errors contained therein.

3.2.1.1 Approved submittals are identified by the submittal stamp, with either the "Approved" or "Approved with Exception" box checked. "Approved" signifies general concurrence of submittal conformance with project design concepts and compliance with Contract Document requirements. "Approved with Exception" signifies general concurrence, with noteworthy comments or clarifications. Approval of a specific item shall not be construed as approval of the system or assembly of which that item is a component.

3.2.1.2 A submittal which is not approved is identified as "Not Approved, Revise and Resubmit." The submittal is considered technically deficient, or incomplete, and therefore unacceptable. Resubmittal is required, hence fabrication, procurement, or performance of procedures shall not proceed.

3.2.1.3 Submittals not requiring approval that are found to be incomplete or inadequate will be returned marked "Resubmit." An explanation of the deficiencies will be included, for corrective action by CONTRACTOR.

3.3 RESUBMITTAL

3.3.1 Upon receipt of deficient submittals, make corrections noted on the transmittal, and resubmit complete packages to ICF KH.

END OF SECTION

SECTION 01400
QUALITY ASSURANCE

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS: Not Used
- 1.3 THE ONSITE CONSTRUCTION CONTRACTOR'S QAP WILL BE IMPLEMENTED
- 1.4 INSPECTION AND WITNESS POINTS
 - 1.4.1 Perform specified inspection and testing (see 1.4.3).
 - 1.4.1.1 Provide and maintain an inspection system that will ensure that work performed, including that performed by subcontractors and suppliers, conforms to requirements.
 - 1.4.1.2 Perform, or have performed, inspections and tests required to substantiate conformance to Project requirements. Such inspections shall be documented, indicating the inspector, date, item(s) inspected, and the results of inspection.
 - 1.4.1.3 Perform, or have performed, inspections required by referenced codes and standards. Such inspections shall be documented as in 1.4.1.2 above.
 - 1.4.2 The customer will perform inspections and testing identified in this specification as the customer's responsibility, including the following.
 - 1.4.2.1 Inspection and witness points specified in 1.6.
 - 1.4.2.2 Final acceptance inspection.
 - 1.4.3 Inspection Points: Adhere to inspection points. Personnel shall have completed inspections of, and approved portions of, work in accordance with Project requirements, before notifying the customer for inspection/witnessing.
 - 1.4.3.1 Listed inspection points define the type of inspections required to be performed, and are considered a minimum inspection level for customer involvement.
 - 1.4.3.2 Customer inspection points are defined as follows.
 - a. Receiving (R): Special items of fabrication, equipment, or material scheduled to be delivered to the Project site, or other designated location, which require inspection upon arrival and before installation. Notify the customer within four hours after item arrival.
 - b. Construction inspection (H): Required for witnessing of specific construction features, before further construction is allowed to proceed.

c. Witness (W): Selected for inspection at the option of the customer. Work may proceed upon verbal release by the customer, or upon expiration of one hour beyond the scheduled time of witnessing.

1.4.3.3 R, H, and W points apply to both onsite and offsite work. Except where a longer period is specified, notify the customer at least four working hours before each point for onsite work. For offsite work, notify the customer at least three working days before each required point.

1.4.3.4 R, H, and W points are specified in 1.6.

1.5 ELECTRICAL/ELECTRONIC PRODUCT ACCEPTABILITY

1.5.1 Each product shall be listed for intended use in one of following and shall bear listing organization's label. In absence of label, provide documentation that verifies product listing.

a. UL Electrical Construction Materials Directory.

b. UL Electrical Appliance and Utilization Equipment Directory.

c. FM Approval Guide.

1.5.2 If product is not listed in above directories or guide, provide product which has been tested and certified by a laboratory which has been nationally recognized in accordance with 29 CFR 1910.7. Provide following.

a. OSHA documentation which demonstrates recognition.

b. Laboratory documentation that verifies testing in accordance with national code or standard.

1.5.3 If product is not listed by UL or FM and if a nationally recognized laboratory is not available, submit descriptive literature to ICF KH. Literature shall include product specification and description of intended application.

1.6 SCHEDULE OF HOLD AND WITNESS POINTS

INSPECTION POINT NO.	INSPECTION POINT DESCRIPTION	INSPECT POINT	OFFSITE	ONSITE
<u>02200</u>	<u>EARTHWORK</u>			
02200-1	Approving Backfill Permits	W		X
<u>02225</u>	<u>EXCAVATING, BACKFILLING AND COMPACTING FOR UTILITIES</u>			
02225-1	Approving Backfill Permits	W		X
<u>03300</u>	<u>CAST-IN-PLACE CONCRETE</u>			
03300-1	Approving Pour Slips for Cover Blocks, Seismic Shutdown Pads	H		X
03300-2	Initial SC1 Grout Placement	H		X

05055	<u>EXPANSION ANCHOR INSTALLATIONS</u>		
05055-1	Initial SCI Installation	W	X
09805	<u>SPECIAL PROTECTIVE COATING</u>		
09805-1	Initial Application on Cover Blocks	W	X
13440	<u>INSTRUMENTATION</u>		
13440-1	Electrical Testing	W	X
15507	<u>CONTAMINATED AIR HVAC SYSTEMS</u>		
15507-1	X-Ray Film Reading	W	X
15507-2	Leak/Pressure Testing	W	X
15990	<u>TESTING, ADJUSTING, AND BALANCING</u>		
15990-1	Functional Testing	W	X
15493	<u>CHEMICAL PROCESS PIPING SYSTEM</u>		
15493-1	Initial Welding	W	X
15493-2	X-Ray Film Reading	W	X
15493-3	M-9 Leak/Pressure Testing	H	X
15493-4	Leak/Pressure Testing	W	X
16400	<u>SERVICE AND DISTRIBUTION</u>		
16400-1	Megger Testing	W	X
16400-2	Before Energizing	H	X
16640	<u>CATHODIC PROTECTION</u>		
16640-1	Functional Testing of Reference Electrodes	W	X
PART 2 -	<u>PRODUCTS</u>		
	Not Used		
PART 3 -	<u>EXECUTION</u>		
	Not Used		

END OF SECTION

SECTION 01610

DELIVERY, STORAGE, AND HANDLING

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS: Not Used
- 1.3 SUMMARY
- 1.3.1 This Section contains generally applicable requirements for delivery, inspection, marking, storage, and handling. Product unique requirements are contained in other sections.
- 1.4 RAILROAD DELIVERIES
- 1.4.1 Railroad shipments are possible into boundaries of the Hanford Site. Carload shipments may be made to Richland, Washington, over Washington Central Railroad from Burlington Northern or Union Pacific Railroads.
- 1.4.2 ICF KH will arrange for movement of rail cars from Richland to available spurs or sidings on the Government owned railroad system, within the Hanford Site. ICF KH is not liable for demurrage charges, or loss or damage to cars or lading, unless loss or damage is the fault of or due to negligence by ICF KH.
- 1.4.3 Investigate availability of rail spurs or sidings in the Site vicinity. Use of spurs shall be coordinated with other users at the Site. Notify ICF KH at least 2 working days before scheduled arrival of carload shipments.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

3.1 DELIVERY

- 3.1.1 Provide equipment and labor required for unloading, transporting, and handling delivered products. For railroad deliveries, unload each car within 3 working days after arrival, unless a time extension is granted by ICF KH.

3.2 RECEIVING INSPECTION

- 3.2.1 Arrange for immediate disposal and replacement of products found to be defective, damaged beyond repair, or in otherwise unacceptable condition.
- 3.2.2 Dry or clean products that have become wet or have accumulated foreign substances during shipment, but have not become damaged.

- 3.2.3 Perform additional identification marking of products when necessary to meet the requirements of this section, and other sections of this Specification.

3.3 PRODUCT IDENTIFICATION AND SEGREGATION

- 3.3.1 Provide identification tags or markings for products of similar appearance, or intended for similar use, procured to different specifications, or from different manufacturers.
- 3.3.2 Include the following information, as applicable, on tags, with markings, and preexisting labels: Manufacturer's name, product brand name, specification number, and type, grade or class. Also include additional information required by other sections of this Specification.
- 3.3.3 Segregate tagged or marked products, providing separate storage for each.
- 3.3.4 Preserve the identity of bulk and lot products (those consumed on an "as needed" basis during progress of the work) from the time of receipt at the worksite until use in construction.
- 3.3.4.1 Control the identification and storage of welding materials in accordance with a written filler metal control procedure, maintained at the worksite. The procedure shall specify methods for control by heat or lot number, from receipt of material through consumption during fabrication, and for disposal of contaminated and partially used material.
- 3.3.4.2 When pipe or tube is removed from storage and cut, clearly and permanently remark remaining pieces with either original markings or field code identification symbols, and return to storage.
- 3.3.4.3 Use permanent marking methods on pipe and tube, including pens with water insoluble, indelible ink, crayon, paint, or paint stick. Vibratory etching equipment may be used with the approval of ICF KH. Marking with steel stamps is not acceptable.
- 3.4 STORAGE
- 3.4.1 Basic Storage
- 3.4.1.1 Store packaged products in their original, unbroken packages or containers, with seals and labels intact.
- 3.4.1.2 Store rolled products in an upright position.
- 3.4.1.3 Store products with finished surfaces in a manner to preclude surface damage by mechanical, atmospheric, or other effects.
- 3.4.1.4 Where contact between products could result in damage or rendering useless of 1 or both, store them far enough apart to prevent contact. If close proximity storage is necessary, provide a barrier between them.

- 3.4.1.5 Keep ports, nozzles, ends, and other openings on equipment, tanks, and lengths of pipe and tube capped or plugged during storage.
- 3.4.1.6 Follow manufacturer's recommendations for storage when such recommendations are given.
- 3.4.1.7 Remove, dispose of, and replace products with expired shelf-life dates.
- 3.4.2 Indoor Storage
 - 3.4.2.1 Provide indoor storage for products that can be damaged by, or can deteriorate from, changes in temperature and relative humidity.
 - 3.4.2.2 When required by other sections of this Specification, or when recommended by product manufacturers, provide environmentally controlled storage. Maintain temperature 15.5 to 21 °C (60 to 70 °F), relative humidity below 55%, and provide ventilation.
- 3.4.3 Outdoor Storage
 - 3.4.3.1 Provide skids, pallets, platforms, or other supports for products stored outdoors to prevent ground contact.
 - 3.4.3.2 Provide sunshade protection for products that can be damaged by, or can deteriorate from, exposure to sunlight.
 - 3.4.3.3 Provide weatherproof covers for products that can be damaged by, or can deteriorate from, the effects of contact with rain, snow, ice deposits, or blowing sand and debris.
 - 3.4.3.4 Arrange stacks of stackable products so that condensation, which may accumulate during storage, will drain off.
- 3.5 HANDLING
 - 3.5.1 Provide handling tools and equipment, and use methods designed to prevent occurrence of the following.
 - 3.5.1.1 Impact, rubbing, or other contact damage to ends and surfaces of cylindrical (pipe and tube) type products, or to edges, corners, and surfaces of flat (panel and sheet) type products.
 - 3.5.1.2 Twisting, racking, or other distortion of prefabricated structures and equipment assemblies.
 - 3.5.1.3 Tearing or puncturing of wrappings or coverings, or breaking of seals on packages or cartons.

END OF SECTION

SECTION 01630

PRODUCT OPTIONS AND SUBSTITUTIONS

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS
 - 1.2.1 See Section 01300 for submittal procedures.
 - 1.2.2 Approval Required
 - 1.2.2.1 Substitution Approval Request(s): Before start of construction, submit request(s) as required by 1.3.4 and 1.3.5, prepared in accordance with 3.1.
 - 1.2.3 Approval Not Required: None
- 1.3 SUBSTITUTIONS
 - 1.3.1 Products include those items identified on Drawings as well as in Part 2 of the specification sections.
 - 1.3.2 Product options given in the specification sections represent functionally and physically equivalent items. In addition to generic type, materials, form and size, physical equivalence includes maintainability, reliability, and durability characteristics, as applicable for specific material or equipment items.
 - 1.3.3 A substitute product may be used in place of a product or the product options identified in specification sections, without approval, if it is functionally and physically equivalent as defined above, and is not more hazardous.
 - 1.3.4 Substitution of a product that is functionally but not physically equivalent, as defined above, or is more hazardous, requires submittal of a Substitution Approval Request.
 - 1.3.5 Submittal of a Substitution Approval Request is also required when a product callout in the specification sections includes the phrase "or an approved substitute."
 - 1.3.6 Total quantities of products required in specification sections shall be the same. Differences due to partial quantity substitutions are not acceptable.
 - 1.3.7 Do not use materials and equipment removed from existing structure as substitutes for specified products, unless such use is required or allowed elsewhere in Contract Documents.

1.4 LIMITATIONS AND CONDITIONS

- 1.4.1 Substitutions will not be considered when indicated or implied on fabricator drawings, or product data submittals, without separate Substitution Approval Requests, when requested directly by subcontractors or suppliers, or when acceptance will require substantial revision of Contract Documents.
- 1.4.2 Substitute products that require a substitution approval request shall not be ordered or installed before the request is approved.
- 1.4.3 Only 1 Substitution Approval Request for each product will be considered. When a substitution is not accepted, provide the specified product.
- 1.4.4 ICF KH will review and disposition requests for substitutions within 10 working days, unless evaluation requires extensive comparison or consultation.
- 1.4.5 The same submittals required for original products, by 1.2 of the sections specifying them, are required for accepted substitute products.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

3.1 REQUEST PREPARATION

- 3.1.1 Submit a separate request for each substitution, using "Substitution Approval Request," Form KEH 1151. Copies will be supplied during the Preconstruction Conference (see Section 01200).
- 3.1.2 Identify products by specification section and article or paragraph numbers. Provide manufacturer's name and address, trade name of product, and model or catalog number. List fabricators and suppliers as appropriate.
- 3.1.3 To each Substitution Approval Request attach descriptive information for substitute and original products. The information shall consist of drawings, calculations, and data as appropriate to define operational and physical characteristics of products, and establish a basis for comparison.
- 3.1.4 Give an itemized comparison of proposed substitution with specified product, listing variations, with reference to specification section and article or paragraph numbers.
- 3.1.5 Give a quality and performance comparison between the proposed substitute and specified product.
- 3.1.6 Give a cost data comparison between the proposed substitute and specified product, showing the Contract sum net change.

- 3.1.7 List availability of maintenance services and replacement materials.
- 3.1.8 State effect of the substitution on construction schedule, and changes required in other work or products. If a substitute product requires or necessitates revisions to structures, foundations, footings, services, systems, piping, electrical, etc, engineering costs shall be borne by CONTRACTOR. Submit drawings, calculations, and vendor data, clearly showing revisions to accommodate the substitution, for approval.

END OF SECTION

SECTION 01720

PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS: Not Used
- 1.3 GENERAL
 - 1.3.1 Hanford Site work requires that certain documents, defined herein, be used to record the construction process, and administration of the Contract. ICF KH will assemble pertinent data for final disposition.
 - 1.3.2 Some data required for project records shall be delivered to ICF KH during the course of construction and contract administration, while other data shall be assembled after completion of construction for delivery to ICF KH.
 - 1.3.3 Certain information for project records is to be recorded on standard ICF KH forms. These forms are identified in the specification sections where required. Copies will be supplied during the Preconstruction Conference (see Section 01200).
 - 1.3.4 Project Record Documents, required by the Contract, shall be prepared, preserved, and delivered to ICF KH. These deliverable documents are in addition to submittals required in Section 01300.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

- 3.1 PROCEDURE
 - 3.1.1 Identification and Marking: Mark documents that will become project records before use for construction. Upon completion, identify documents by title or number.
 - 3.1.1.1 Notes or markings added by hand shall be legible, utilizing permanent nonsmearing marking media, such as ink or felt tip markers, in contrasting color.
 - 3.1.1.2 Mark items to record actual construction, including changes to dimensions and details, manufacturer's name, catalog number, and substitute products.
 - 3.1.2 Availability: Keep copies of Project Record Documents in the field office, and make available to ICF KH during progress of the Work.

3.1.3 Storage: Store 1 set in the field office, apart from documents used in Page 19 construction, and maintain in clean, dry, and legible condition.

3.1.4 Delivery: Record delivery of documents by retaining copies of letters of transmittal itemizing delivered items, and reports delivered during the course of work. Retain until construction completion. An alternate means, acceptable to ICF KH, may be used.

3.2 ACTIVITY AND ADMINISTRATIVE DOCUMENTS

3.2.1 Deliver or retain in accordance with the following.

3.2.2 Certified Payrolls: Each week deliver certified payrolls as required by General Conditions, Section 108 to ICF KH and keep copies in the field office until Contract completion. Progress payments will not be processed unless certified payrolls for work periods have been received by ICF KH.

3.2.3 Daily Force and Equipment Reports: Before noon each day, deliver 1 copy of a detailed daily force report, covering labor and supervision of CONTRACTOR and subcontractors for previous day. Report shall include a general description of work performed, and list major items of equipment onsite.

3.2.4 Weekly Manpower Reports: Prepare weekly manpower reports and deliver, before 10 am on Monday, for previous week, during performance of Contract. Forms will be furnished by ICF KH.

3.2.5 Subcontracting Plan Reports: Deliver reports documenting conformance with Subcontracting Plan, as required by General Conditions, Section 89.

3.2.6 Backfill Permit: Retain backfill permits approved for work required in Division 2.

3.2.7 Soil Compaction Procedure: Retain Forms KEH 0382 completed for work required in Division 2.

3.2.8 Pour Slips: After obtaining ICF KH approval of concrete pour slips required in Division 3, deliver copies to ICF KH, and retain CONTRACTOR copies until Contract closeout. After closeout deliver them to ICF KH.

3.2.9 Trip Tickets: Deliver copies to ICF KH with each truck load of concrete required in Division 3, and retain CONTRACTOR copies until Contract closeout. After closeout, deliver them to ICF KH.

3.3 CONSTRUCTION, QUALITY ASSURANCE, AND SUPPORTING DOCUMENTS

3.3.1 Deliver in accordance with the following, when called for in specification sections.

3.3.2 Quality Assurance Programs: 1 copy of each supplier's Quality Assurance Program, 15 days before start of fabrication.

- 3.3.3 Drawings: 3 copies of weld (bond) identification drawings, 5 days before start of fabrication.
- 3.3.4 Expansion Anchor Installation Reports: 1 copy within 5 days after completion.
- 3.3.5 NDE Records: 1 copy of weld (bond) NDE records within 5 days after NDE completion. These records may be either signed NDE record forms, or signed fabrication drawings with each weld (bond) bearing the inspector's stamp.
- 3.3.6 Material Properties Test Records: 1 copy of test results prior to delivery of material. These records are for acceptance tests of bulk materials and of lots or heats of preformed stock materials and parts.
- 3.3.7 Flushing Records: 1 copy of records verifying acceptable completion of flushing, before testing.
- 3.3.8 Leak/Pressure Testing Records: 1 copy of records verifying acceptable completion of leak and pressure testing, within 5 days after completion.
- 3.3.9 Disinfecting Records: 1 copy of records verifying acceptable completion of sanitary water line disinfecting, 5 days after completion.
- 3.3.10 Electrical Testing: 1 copy of records verifying acceptable completion of electrical insulation, continuity, and grounding tests, within 5 days after completion.
- 3.3.11 Operational Testing: 1 copy of records of component or subsystem operational testing, within 15 days before the start of acceptance testing.
- 3.3.12 Completed Acceptance Test Procedure (Test Results): 1 copy of Acceptance Test Procedure, with test results and other required information entered, within 5 days after completion.
- 3.3.13 Completed Certificate of Compliance: 1 copy of completed Certificate of Compliance, based on the above completed acceptance test procedure, along with that procedure.
- 3.4 PRODUCT SAMPLES AND MANUFACTURER'S INSTRUCTIONS
- 3.4.1 In addition to submittals required in Section 01300, and requirements of this Section, information received by CONTRACTOR (from suppliers) that documents products used, and how they were installed, shall be delivered to ICF KH as Project Records.

END OF SECTION

SECTION 02200

EARTHWORK

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 Washington State Department of Transportation (WSDOT)

M 41-10-94 Road, Bridge, and Municipal
Construction

M 41-01-93 Construction Manual

1.2 SUBMITTALS: Not Used

1.3 QUALITY ASSURANCE

1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

<u>Document</u>	<u>Paragraph</u>
Excavation Permit	3.1.1
Backfill Permit	3.2.1.1a
Soil Compaction Procedure	3.2.1.2a
Soil Compaction Test Results	3.3.1

PART 2 - PRODUCTS

2.1 MATERIALS

2.1.1 Obtain specified soils from excavation or other locations designated by the Construction Engineer.

2.1.2 Fill or Backfill

2.1.2.1 Structural: Well graded soil mixtures which may contain cobbles up to 3 inches in greatest dimension if uniformly distributed and not constituting more than 20% of volume of fill.

2.1.2.2 Common: Well graded soil mixtures containing cobbles up to 8 inches in greatest dimension if uniformly distributed and not constituting more than 40% of volume of fill.

- 2.1.3 Stabilization: Crushed rock, with a maximum fragment size of 3/4-inch. ~~for walkways, and under 2 inches for other areas.~~

PART 3 - EXECUTION

3.1 EXCAVATION

- 3.1.1 Obtain an excavation permit before performing excavation. Excavation permits will be provided by the Operating Contractor.
- 3.1.2 If cultural properties (eg, bones, artifacts) are encountered during excavation, stop work. The Hanford Cultural Resources Laboratory will assess the significance of the find.
- 3.1.3 Locate and expose underground utilities by hand tools. Use of heavy equipment and machinery is restricted within 5 feet of suspected underground utilities, and requires approval by the Construction Engineer.
- 3.1.4 Wherever slopes of excavations will intersect existing underground lines or structures such as building foundations, underground piping, electrical ducts or direct buried electrical lines, install shoring or other means of support to prevent overstressing existing structure or underground lines or to prevent interrupting service to existing buildings.
- 3.1.5 Footings and Foundations
- 3.1.5.1 Make excavations for footings to depth shown on the Drawings or additional depth necessary to provide undisturbed surface to receive footing. Make excavations to proper width with allowances made for forms and bracing. Make bottom of excavations compact, level, true, and free of loose material.
- 3.1.5.2 If over-excavation occurs where footings are designed to be placed on undisturbed earth, correct at time of placing concrete by extending concrete down to undisturbed earth, or by placement of backfill, compacted as specified in 3.2.1.2b, Method C.
- 3.1.6 In Situ Soils
- 3.1.6.1 Salvage in situ stabilization material and reuse for backfilling and compacting. Contact the Construction Engineer for acceptability of backfill material, if required.
- 3.1.6.2 Conduct in-place density tests on in situ soils, using nuclear density gage, during excavation. Results of tests will be used for testing compaction of backfill and to ensure that the density of backfill material placed over the tank dome is equal to or less than the density assumed in the tank safety and structural analyses.
- 3.1.6.3 Excavated material containing concentrations of radioactive materials that can be detected by portable survey instruments normally used for performing radiation surveys is considered contaminated, and shall be

sampled and analyzed for content. Contact the Construction Engineer for disposal or reuse within approved contamination level limits set by the Operating Contractor.

ECN-548
ECN-548

~~3.1.7 Where stabilization is required, finish subgrade 3 inches below elevations shown on the Drawings.~~

3.2 PLACEMENT

3.2.1 Fill and Backfill

3.2.1.1 General:

a. Backfill Permit: Obtain signatures required on the backfill permit for each element to be filled or backfilled. Work not started within 5 calendar days from the time a permit is approved shall not be started until a new permit has been approved. A continuing job that has not had backfill installed within the past 5 calendar days will require a new backfill permit.

b. Remove debris and organic matter from the area to be filled or backfilled.

c. Use only specified materials for fill or backfill. Keep materials free of frozen particles, lumps, organic matter, and trash.

d. Do not place fill or backfill on frozen ground.

e. Filling or backfilling by sluicing or flooding with water will not be permitted.

f. Bring fill or backfill up evenly on sides of walls, structures, and utility lines to avoid unbalanced loading. Written approval shall be obtained from the Construction Engineer for other procedures.

g. Do not place fill or backfill against concrete structure or foundation wall less than 14 days after completion of structure or wall unless written permission from the Design Engineer is obtained. Provide wall support, where noted on the Drawings, before filling or backfilling.

3.2.1.2 Compaction:

a. Before placement of fill or backfill, demonstrate by physical test at the worksite, that proposed layer depths and the procedure for compaction of soils will provide compaction specified. Prepare "Soil Compaction Procedure," Form KEH-0382, in accordance with the instructions.

b. Place backfill in accordance with WSDOT M 41-10, Section 2-03.3(14)C and approved procedure as follows.

1) Use Method C under foundations, slabs, and when backfilling around Concrete Pits.

2) Use Method B under pavements and roads, and within 5 feet of buildings, fences, other structures, or poles supporting electric lines or pipe.

c. Compaction control tests will be in accordance with WSDOT M 41-10, Section 2-03.3(14)D.

3.2.1.3 Common:

a. Place fill or backfill in layers not more than 12 inches thick, loose measurement.

b. Compact each layer, full width, by at least 1 pass of vibratory or rammer-type compactor, pneumatic-tired roller, loaded scraper wheel, grader wheel, or power roller.

c. Mound over top layer of backfill to depth of 1 inch for each 12 inches of trench depth to maximum mound height of 6 inches.

3.2.1.4 In situ soils:

a. Compact backfill by depositing soils in 8 inch layers and compacting to density equal to in situ density determined by tests made during excavation. Maintain uniformity of compaction throughout backfill.

b. Do not use soils containing rocks larger than 3 inches in greatest dimension for compacted backfill.

3.2.2 Finish Grading and Stabilization

3.2.2.1 Rake areas disturbed by work, remove surface stones larger than 6 inches and dispose of excess material and debris at an area designated by the Construction Engineer.

3.2.2.2 Stabilize areas disturbed by work with a ~~3 inch course of~~ crushed rock specified in 2.1.3. Finish stabilization course to elevations shown on the Drawings.

ECN-548

3.3 FIELD QUALITY CONTROL

3.3.1 Soil Compaction Tests: Sampling and testing of compacted fill and backfill will be performed. Frequency of testing shall be in accordance with WSDOT M 41-01, Page 9-52 and as directed by the Construction Engineer to ensure uniform compaction of backfill material.

END OF SECTION

SECTION 02225

EXCAVATING, BACKFILLING, AND COMPACTING FOR UTILITIES

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society for Testing and Materials (ASTM)

D 653-90 Standard Terminology Relating to Soil, Rock, and Contained Fluids

1.1.1.2 Washington State Department of Transportation (WSDOT)

M 41-01-93 Construction Manual

M 41-10-94 Road, Bridge, and Municipal Construction

M 46-01-88 w/Revisions Materials Branch Laboratory Manual through 1994

1.2 SUBMITTALS: Not Used

1.3 QUALITY ASSURANCE

1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Excavation Permit

3.1.1

Backfill Permit

3.2.1.1a

Soil Compaction Procedure

3.2.1.2a

Soil Compaction Test Results

3.3.1

PART 2 - PRODUCTS

2.1 MATERIALS

2.1.1 Obtain specified soils from excavation or other locations designated by the Construction Engineer.

2.1.2 Fill or Backfill

- 2.1.2.1 Structural: Well graded soil mixtures which may contain cobbles up to 3 inches in greatest dimension if uniformly distributed and not constituting more than 20% of volume of fill.
- 2.1.2.2 Common: Well graded soil mixtures containing cobbles up to 8 inches in greatest dimension if uniformly distributed and not constituting more than 40% of volume of fill.
- 2.1.3 Bedding for Underground Pipe, Conduit, and Cable: Sand, as defined in ASTM D 653, or excavated sandy material having less than 20% gravel particles, with those particles having a maximum dimension of 1/2-inch.
- 2.1.4 Stabilization: Crushed rock, with a maximum fragment size of 3/4-inch. ~~for walkways, and under 2 inches for other areas.~~ ECN-548
- 2.1.5 Plastic Sheet Marker: 3-inch wide detectable tape imprinted with a warning, such as "CAUTION - BURIED INSTALLATION BELOW", at intervals of 4 feet maximum; Reef Industries "Terra Tape Sentry Line 620," with "Terra Clips," or an approved substitute.

PART 3 - EXECUTION

3.1 EXCAVATION

- 3.1.1 Obtain an excavation permit before performing excavation. Excavation permits will be provided by the Operating Contractor.
- 3.1.2 If cultural properties (eg, bones, artifacts) are encountered during excavation, stop work. The Hanford Cultural Resources Laboratory will assess the significance of the find.
- 3.1.3 Locate and expose underground utilities by hand tools. Use of heavy equipment and machinery requires approval by the Construction Engineer.
- 3.1.4 Where slopes of excavations will intersect existing underground lines or structures such as building foundations, underground piping, electrical ducts or direct buried electrical lines, install shoring or other means of support to prevent overstressing existing structure or underground lines or prevent interrupting service to existing buildings.
- 3.1.5 Make excavations to line and grade shown on the Drawings and wide enough to make connections. Excavate with near vertical sides from bottom of trench up to 1 foot above pipe, conduit, and cable. Excavate trench deep enough to permit placement of compacted bedding, 4 inches minimum thickness, beneath pipe, conduit, and cable except where excavation is in undisturbed sand which will serve as bedding or where lines are to be encased in concrete. Pare holes in trench bottoms for pipe couplings so pipe will bear full length of barrel or section. Excavate trench for transfer lines deep enough for 6 inches of compacted bedding.
- 3.1.6 Install shoring to hold materials and surcharge pressure for full depth of trench.

- 3.1.7 Keep trenches free of standing water when laying is in progress.
- 3.1.8 If over-excavation occurs, correct by placement of structural backfill.
- 3.1.9 In Situ Soils
 - 3.1.9.1 Salvage in-situ stabilization material and reuse for backfilling and compacting. Contact the Construction Engineer for acceptability of backfill material, if required.
 - 3.1.9.2 Conduct in-place density tests on in-situ soils, using nuclear density gage, during excavation. Results of tests will be used for testing compaction of backfill.
 - 3.1.9.3 Excavated material containing concentrations of radioactive materials that can be detected by portable survey instruments normally used for performing radiation surveys is considered contaminated, and shall be sampled and analyzed for content. Contact the Construction Engineer for disposal or reuse within approved contamination level limits set by the Operating Contractor.

~~3.1.10 Where stabilization is required, finish subgrade 3 inches below elevations shown on the Drawings.~~

ECN-54E
ECN-54E

3.2 PLACEMENT

3.2.1 Fill and Backfill

3.2.1.1 General:

- a. Backfill Permit: Obtain signatures required on the backfill permit for each element to be filled or backfilled. Work not started within 5 calendar days from the time a permit is approved shall not be started until a new permit has been approved. A continuing job that has not had backfill installed within the past 5 calendar days will require a new backfill permit.
- b. Remove debris and organic matter from the area to be filled or backfilled.
- c. Use only select materials for fill or backfill. Keep materials free of frozen particles, lumps, organic matter, and trash.
- d. Do not place fill or backfill on frozen ground.
- e. Filling or backfilling by sluicing or flooding with water will not be permitted.
- f. Bring fill or backfill up evenly on sides of walls, structures, and utility lines to avoid unbalanced loading. Written approval shall be obtained from the Construction Engineer for other procedures.

3.2.1.2 Compaction:

a. Before placement of fill or backfill, demonstrate by physical test at the worksite, that proposed layer depths and the procedure for compaction of soils will provide compaction specified. Prepare "Soil Compaction Procedure," Form KEH-0382, in accordance with the instructions.

b. Place backfill in accordance with WSDOT M 41-10, Section 2-03.3(14)C and approved procedure as follows.

1) Use Method C under pipelines.

2) Use Method B within 5 feet of buildings, fences, other structures, or poles supporting electric lines or pipes.

c. Compaction control tests will be in accordance with WSDOT M 41-10, Section 2-03/3(14)D.

3.2.1.3 Common:

a. Place fill or backfill in layers not more than 12 inches thick, loose measurement.

b. Compact each layer, full width, by at least 1 pass of vibratory or rammer-type compactor, pneumatic-tired roller, loaded scraper wheel, grader wheel, or power roller.

c. Mound over top layer of backfill to depth of 1 inch for each 12 inches of trench depth to maximum mound height of 6 inches.

3.2.1.4 Underground piping, conduit, and cable trenches:

a. Bedding placed beneath pipe, conduit, and cable in trenches shall be material specified in 2.1.3. An alternate material, such as select native bedding material, may be used with written approval from the Construction Engineer.

b. Place and compact bedding in trench prepared as specified in 3.1.5 before laying pipe, conduit, and cable. Compact bedding as specified for structural backfill.

c. Place backfill over joints in underground pipes only after pressure testing of line has been completed.

d. Backfill under conduit and haunches of pipe, around sides, and up to 1 foot above top of pipe, conduit, and cable using bedding material. Place and compact material same as specified for structural backfill. Compact with care, to avoid misalignment of pipe and provide uniform bearing along barrel of pipe. Compact bedding and backfill materials of Transfer lines to 98% of WSDOT M 46-01, Section 600, Test Method 606. Do not compact within 5 feet of any buried utility of unknown type or any utility which may be susceptible to damage from compaction efforts. This pertains primarily to process lines, identified on the Drawings.

e. Backfill trenches from elevation 1 foot above top of pipe, conduit, Page 29 and cable as follows.

1) Use structural fill or backfill in locations specified in 3.2.1.2.

2) Use common fill or backfill as specified in 3.2.1.3 for other locations.

f. Do not allow heavy construction equipment to pass over buried lines until at least 2 feet of backfill has been placed over the line or until bridging has been placed across trenching and approved by the Construction Engineer.

3.2.1.5 In situ soils:

a. Compact backfill by depositing soils in 8 inch layers and compacting to density equal to in-situ density determined by tests made during excavation. Maintain uniformity of compaction throughout backfill.

b. Do not use soils containing rocks larger than 3 inches in greatest dimension for compacted backfill.

3.2.2 Plastic Sheet Marker: Place continuously and directly over buried utility lines, 1 foot below finish grade. Place markers over each outside line of multiple lines, if spacing permits. Place intermediate markers spaced 4 feet maximum.

3.2.3 Finish Grading and Stabilization

3.2.3.1 Rake areas disturbed by work, remove surface stones larger than 6 inches, and dispose of excess material and debris at an area designated by the Construction Engineer.

3.2.3.2 Stabilize areas disturbed by work with a ~~3 inch course of gravel~~ *crushed rock* specified in 2.1.4. Finish stabilization course to elevations shown on the Drawings.

ECN-548

ECN-548

3.3 FIELD QUALITY CONTROL

3.3.1 Soil Compaction Tests: Sampling and testing of compacted fill and backfill will be performed. Frequency of testing shall be in accordance with WSDOT M 41-01, Page 9-52 and as directed by the Construction Engineer to ensure uniform compaction of backfill materials.

END OF SECTION

SECTION 02831

CHAIN LINK FENCES AND GATES

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society for Testing and Materials (ASTM)

A 90-81 (1991) Test Method for Weight of Coating on Zinc-Coated Galvanized) Iron or Steel Articles

1.1.1.2 Federal Specifications (FS)

RR-F-191K/Gen Fencing, Wire And Post, Metal (And Gates, Chain-Link Fence Fabric, And Accessories) (General Specification)

RR-F-191/1D Fencing, Wire And Post, Metal (Chain-Link Fence Fabric) (Detailed Specification)

RR-F-191/3D Fencing, Wire And Post, Metal (Chain-Link Fence Posts, Top Rails And Braces) (Detailed Specification)

RR-F-191/4D Fencing, Wire And Post, Metal (Chain-Link Fence Accessories) (Detailed Specification)

1.2 SUBMITTALS: Not Used

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 MATERIALS

2.1.1 Fence Fabric: FS RR-F-191/1, Type I, 2 inch mesh, 11 gage, 84 inch height, top and bottom salvages twisted and barbed.

2.1.2 Posts, Top Rails and Braces: FS RR-F-191/3, Class 1, Grade A or B, of following sizes.

2.1.2.1 Line posts: SP3.

- 2.1.2.2 Terminal posts and posts set at break in grade: SP4.
- 2.1.2.3 Top rails: SP1.
- 2.1.2.4 Braces: Diagonal truss and horizontal brace, hot-dip galvanized steel rods 3/8-inch diameter with turnbuckle.
- 2.1.2.5 Where posts other than Class 1 are used, they shall be Class 3, 4, or 6, and of equal strength and stiffness as posts specified in 2.1.2.
- 2.1.3 Accessories: FS RR-F-191/4.
 - 2.1.3.1 Wire ties and clips: Zinc-coated steel
 - 2.1.3.2 Tension wire: No. 7 gage zinc-coated steel per FS RR-F-191/4.
 - 2.1.3.3 Miscellaneous accessories: Miscellaneous fittings including bolts, nuts and washers shall be malleable iron, cast iron, or steel, and be hot-dip galvanized.
- 2.1.4 Coating: Fence shall have a zinc coating of uniform thickness, weighing at least 1.2 oz/ft² of surface, as determined by ASTM A 90. Apply coating to parts after fabrication. Repair welds or breaks in galvanized coatings with zinc-rich coating such as ZRC or Galvacon.
- 2.2 MIXES
 - 2.2.1 Concrete: Minimum compressive strength of 2000 lb/in² at 28 days.

PART 3 - EXECUTION

3.1 INSTALLATION

- 3.1.1 Install fence true to line and grade in locations shown on the Drawings and in accordance with this Section.
- 3.1.2 Setting Posts
 - 3.1.2.1 Set posts in concrete, plumb and true to line. Space line posts evenly, 10 feet maximum, between end and gate posts.
 - 3.1.2.2 Holes for setting line posts shall be 8 inches to 12 inches in diameter and 3 feet deep. Holes for setting gate and end posts shall be 10 inches to 17 inches in diameter and 3'-6" deep. Set post ends 6 inches above bottom of hole.
 - 3.1.2.3 Firmly support posts to prevent movement or deflection until concrete has set 24 hours minimum.
- 3.1.3 Bracing Posts: Horizontally brace gate, corner and terminal posts with steel pipe using brace attachments, and diagonally brace from the base of gate, corner, and terminal posts to the midheight of adjacent line posts using steel rods with truss attachments.

- 3.1.4 Tension Wires: Install top and bottom tension wires to stabilize wire fabric.
- 3.1.4.1 Install top tension wire through 1/4 inch holes drilled in each post, except gate posts drilled 3 inches below the top in each post.
- 3.1.4.2 Install bottom tension wires through 1/4 inch holes in each post, except gate posts, 4 inches above finish grade.
- 3.1.5 Attaching and Stretching Fabric
- 3.1.5.1 Thread tension bars through end loops of each section of fabric and tie to end, corner, and gate posts with tension bands spaced not more than 15 inches on centers.
- 3.1.5.2 Fasten fabric to posts with ties spaced not more than 14 inches on centers. Topmost tie shall be as near top of fabric as possible; lowest tie as near bottom of fabric as possible.
- 3.1.5.3 Tie fabric to top and bottom tension wires with wire clips or ties spaced 24 inches maximum on centers.
- 3.1.5.4 Stretch fence fabric taut.
- 3.1.5.5 Dress barbed ends of barbed top fabric approximately 2 to 3 inches above top tension wire. Straighten each barb as needed to present unbroken line above and below tension wire.
- 3.1.5.6 Bottom of fabric shall extend to within 2 inches of finish grade.
- 3.1.6 Bolt Heads: Locate bolt heads on outside of fence.

END OF SECTION

SECTION 03300

CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Concrete Institute (ACI)

117-90 Tolerances for Concrete Construction and Materials

301-89 Structural Concrete for Buildings

306.1-90 Cold Weather Concreting

1.1.1.2 American Society for Testing and Materials (ASTM)

A 615-92b Deformed and Plain Billet-Steel Bars for Concrete Reinforcement

A 853-91 Steel Wire, Carbon, for General Use

C 94-92a Ready-Mixed Concrete

C 531-85 (1990) Test Method for Linear Shrinkage and Coefficient of Thermal Expansion of Chemical Resistant Mortars, Grouts and Monolithic Surfaces

C 579-91 Test Method for Compressive Strength of Chemical Resistant Mortars and Monolithic Surfacing

C 827-87 Standard Test Method for Change in Height at Early Ages of Cylindrical Specimens from Cementitious Mixtures

D 1056-91 Flexible Cellular Materials - Sponge or Expanded Rubber

A 185-94 *Steel Welded Wire Fabric, Plain, for Concrete Reinforcement* ECN-123
ECN-123

1.1.1.3 Federal Specifications (FS)

TT-S-00230C Sealing Compound: Elastomeric Type,
AMD 2 Single Component (For Calking, Sealing,
And Glazing In Buildings And Other Structures)

1.1.1.4 Washington State Department of Transportation (WSDOT)

M 41-10-94

Road, Bridge, and Municipal
Construction

1.2 SUBMITTALS: *Not Used*

~~1.2.1 See Section 01300 for submittal procedures.~~

~~1.2.2 Approval Required: None~~

~~1.2.3 Approval Not Required~~

~~1.2.3.1 Commercial grade item documentation: Before fabrication/
installation, submit reports of inspections and tests of
items specified in 2.3.1.~~

ECN-290

1.3 QUALITY ASSURANCE

1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

<u>Document</u>	<u>Paragraph</u>
Pour Slip and Trip Tickets	3.2.2.1
Material Test Results	2.3.1.1 , 3.4.1, 3.4.2

ECN-290

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

2.2.1 Concrete: ACME preapproved mix design No. 6452.

2.2.2 Measuring, Mixing, and Delivery: In accordance with ASTM C 94.

2.2.3 Reinforcing Steel

2.2.3.1 Steel bars: ASTM A 615, deformed, Grade 60.

2.2.3.2 Tie wire: ASTM A 853 carbon steel, 0.062-inch (16-gage) minimum, annealed.

2.2.3.3 *Welded wire fabric: ASTM A 185*

ECN-123

2.2.4 Joint Materials

2.2.4.1 Epoxy resin: In accordance with WSDOT M 41-10, Section 9-26, Type II, Grade 2, Class B or C; QCM Company EAS8 Class A, Adhesive Engineering "Concresive 1001 LPL," or Protex Industries "Probond 822."

2.2.4.2 Sealant: FS TT-S-00230, Type II.

2.2.4.3 Gasket: ASTM D 1056; Williams Products Incorporated, Everlastic Closed Cell Neoprene Type NN-1 1040 series. Page 36

2.2.4.4 Adhesive: Williams Products Incorporated, No. 37A.

2.2.5 Nonshrink Epoxy Grout: ASTM C 827; U.S. Grout Corporation "Five Star HF Epoxy Grout" or approved substitute. (10,000 psi min. in 7 days)

ECN-290

2.2.6 Forms: Wood, steel, plywood, or Masonite Corporation "Concrete Form Presdwood," as required for various specified finishes.

2.2.7 Form Coating Materials: Symons Corporation "Magic Kote," AC Horn Incorporated "Form Shield," or Burke Company "Burke Release No. 1."

2.2.8 Sealer/Hardener: See Section 09900.

~~2.3 MATERIAL QUALITY ASSURANCE~~

ECN-290

~~2.3.1 Commercial Grade Item Acceptance: If the following items, specified in 2.2, are procured as commercial grade items, they shall be inspected or tested as specified below. Document the results in reports.~~

~~2.3.1.1 Nonshrink Epoxy Grout specified in 2.2.5.~~

ECN-290

~~a. Grout shall show no shrinkage (0.0%) and a maximum 2.0% expansion from time of placement when tested according to ASTM C 827, modified to use a ball with a specific gravity between 0.9 and 1.1.~~

ECN-281/
290

~~b. The grout shall show a minimum 7-day compressive strength of 16,000 psi when tested according to ASTM C 579.~~

~~c. The grout shall show a maximum coefficient of thermal expansion of 30×10^{-6} in/in/°F when tested according to ASTM C 531.~~

~~d. The grout shall show creep equal to or less than 5.0×10^{-3} in/in at 180 F for one year with a load of 400 psi when tested according to GPR Creep Test.~~

ECN-281/
290

PART 3 - EXECUTION

3.1 PREPARATION

3.1.1 Form Construction

3.1.1.1 Install formwork in accordance with ACI 301, Section 4.2 and approved submittals. Interior shape and rigidity shall be such that finished concrete will meet the requirements of the Drawings within tolerances specified in ACI 117, Section 4.

3.1.1.2 Prepare form surfaces in accordance with ACI 301, Section 4.4 using specified form coating materials, or as described below.

3.1.1.3 Forms for surfaces which will be permanently concealed from view may be saturated with water, before placing concrete, instead of other treatment. In freezing weather forms shall be treated with oil or stearate.

3.1.1.4 Clean forms of foreign material before placing concrete.

3.1.2 Core Drilling

- 3.1.2.1 Obtain scanning services to locate rebar and embedments, excluding inside surfaces of existing pits and cover blocks.
- 3.1.2.2 Precautions shall be taken for the containment of drilling lubricants/water as required.
- 3.1.2.3 Core drill locations shall be as specifically dimensioned on the Drawings. In the event that a dimension has been specified, and an embedment (rebar, conduit, etc) is detected during scanning, the Construction Engineer shall be contacted for resolution.
- 3.1.2.4 Verify that the kill switch device on the core drill is operational.
- 3.1.2.5 Approach surface "breakthrough" cautiously to minimize and control penetration of the drill.
- 3.1.2.6 Do not cut rebar embedment unless written permission from design engineer is obtained.
- 3.1.2.7 Sketch a grid of the rebar and/or embedment location on the outside surface of concrete.
- 3.1.2.8 Prepare a "Core Drilling Record" form KEH-1969 in accordance with the instructions, identifying the final hole locations and the rebar/grid or embedment.

3.1.3 Joints

- 3.1.3.1 Clean joints and surfaces to be sealed, adhered, or caulked, removing dirt, dust, oil, grease, mortar, and other foreign materials.
- 3.1.3.2 Remove loose particles with wire brush. Blow out joints with dry, oil free compressed air. Remove wax or oil using Inland Technologies "CitraSafe," or Xylol.
- 3.1.3.3 Follow recommendations of manufacturer of sealing, adhesive and caulking materials for each condition of application. Prevent foreign materials from joint and surface cleaning to become intermixed with sealing, adhesive and caulking materials.

3.2 INSTALLATION

3.2.1 Reinforcing Steel

- 3.2.1.1 Fabricate bars to dimensions shown on the Drawings, within tolerances shown in ACI 301, Section 5.6.
- 3.2.1.2 Tag in accordance with the bar list.
- 3.2.1.3 Place as shown on the Drawings, within tolerances specified in ACI 117, Section 2.2.
- 3.2.1.4 Tie to prevent displacement during placement of concrete.

- 3.2.1.5 Do not force into concrete after initial set has started.
- 3.2.1.6 Place with the concrete protection dimension given in ACI 301, Section 5.7, except where shown otherwise on the Drawings.
- 3.2.1.7 Reinforcement shall be supported and fastened together to prevent displacement by construction loads, or placement of concrete beyond specified tolerances. Reinforcement supported from the ground shall rest on precast, square concrete blocks, sized 100 mm (4 inches) minimum, having a compressive strength equal to the specified compressive strength of the concrete being placed. Other means of support require prior approval by the Construction Engineer.
- 3.2.1.8 *Overlap welded wire fabric wherever successive mats or rolls are continuous, in such a way that overlap measured between outermost cross wire of each fabric sheet is spacing of cross wires plus 50 mm (2 inches) minimum. Tie splices with wire.*
- 3.2.2 Concrete
- 3.2.2.1 Before placing:
 - a. Approve the "Pour Slip," including identification of sections of structure to be placed, maximum size of coarse aggregate, and design strength.
 - b. For each truck load, collect the "Trip Ticket." "Trip Tickets" shall contain information listed in ASTM C 94, Paragraphs 16.1.1 through 16.1.10, and the water/cement ratio.
- 3.2.2.2 Place in accordance with ACI 301, Sections 8.1, 8.2, and 8.3. Do not drop (free fall) more than 5 feet. Insert vibrator, vertically if possible, into concrete and reach small distance into concrete in next lower layer. Do not insert vibrators into lower courses that have reached initial set. Take care to avoid allowing head of vibrator to come in contact with forms, reinforcement, or embedded items.
- 3.2.2.3 Temper only as permitted in ACI 301, Section 7.5.
- 3.2.2.4 Place nonshrink epoxy grout where shown on the Drawings, in accordance with manufacturer's recommendations.
- 3.2.2.5 Weather conditions: Protect concrete during placement in accordance with ACI 301, Sections 7.6 and 8.4. Cold weather concreting procedure shall be in accordance with ACI 306.1.
- 3.2.2.6 Construction joints: Make in accordance with ACI 301, Section 6.1. Coat joints with epoxy resin, in accordance with manufacturer's recommendations.
- 3.2.2.7 Embedded items: Install in accordance with ACI 301, Sections 6.4 and 6.5.
- 3.2.2.8 Placing concrete against earth: Place on or against firm, damp surfaces free of frost, ice and free water. Do not place until required compaction has been obtained. Dampen earth surfaces to receive fresh concrete.

ECN-123

ECN-123

3.2.2.9

Consolidation: Consolidate concrete slabs in accordance with ACI 301, Page 40
Section 11.6.

3.2.3 Form Removal and Concrete Repair

3.2.3.1 Form removal: Remove in accordance with ACI 301, Section 4.5.

3.2.3.2 Cut back form ties and examine concrete surfaces for defects. Repair only after permission for patching is given by the Construction Engineer.

3.2.3.3 Place concrete repair mortar within 1 hour after mixing. Do not retemper mortar.

3.2.3.4 Repair surface defects in accordance with ACI 301, Sections 9.1, 9.2 and 9.3. Cure concrete repairs the same as new concrete.

3.2.4 Concrete Finishes and Tolerances

3.2.4.1 Formed surfaces: Start finishing following concrete repair and complete within 96 hours after forms have been removed. Finish in accordance with the following ACI 301 sections.

a. Surfaces exposed to earth backfill Section 10.2.1

b. Interior surfaces Section 10.2.2

c. Exterior surfaces exposed to weather Section 10.2.2

d. Related unformed surfaces Section 10.5

e. Surfaces to receive special protective coating Section 10.3.2

3.2.4.2 Unformed surfaces: Finish in accordance with the following ACI 301 sections.

a. Interior floors Section 11.7.3

b. Exterior equipment slabs Section 11.7.3

c. Exterior slabs subject to foot traffic Section 11.7.4

3.2.5 Sealant and Caulking

3.2.5.1 Apply adhesives and perform sealing and caulking work using specified materials and proper tools in accordance with manufacturer's recommendations for conditions of each application.

3.2.5.2 Apply exterior sealing material when ambient temperature is 40 to 100°F.

3.2.5.3 Apply sealing materials with guns having proper size nozzles and sufficient pressure to fill spaces and voids solid. Where use of guns is impractical, hand tools approved by the Construction Engineer may be used.

- 3.2.5.4 Tool sealant after installation as required to properly fill joint and produce smooth surface.
- 3.2.5.5 Prevent contact of sealants or caulking with adjacent surfaces. If necessary, apply masking tape in continuous strips in alignment with edge of joint. Remove masking tape after joints have been tooled.
- 3.3 CURING
- 3.3.1 Cure concrete in accordance with ACI 301, Section 12.2. Do not use curing compounds on surfaces to receive sealer/hardener.
- 3.4 FIELD QUALITY CONTROL
- 3.4.1 Concrete Testing: Sample and test concrete in accordance with ACI 301, Sections 16.3.4, 16.3.5, 16.3.6 and 16.3.8. Record the results.
- 3.4.2 ~~Nonshrink Epoxy Grout Installation: The quality control inspector will inspect SCI epoxy grout installations in accordance with manufacturer's recommendations and paragraph 2.3.1.1 of this Section.~~ *Nonshrink Epoxy Grout: Test epoxy grout in accordance with ASTM C-579, Method B. Testing is required for only one material formulation. Provide six test specimens for each material formulation. Record the results.*
- ECN-290
- ECN-290
- 3.5 PROTECTION
- 3.5.1 Protect concrete during extreme weather conditions in accordance with ACI 301, Section 12.3.
- 3.5.2 Protect concrete from mechanical damage in accordance with ACI 301, Section 12.4.

END OF SECTION

SECTION 03400
PRECAST CONCRETE

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Concrete Institute (ACI)

- | | |
|----------|---|
| 301-89 | Structural Concrete for Buildings |
| 306.1-90 | Cold Weather Concreting |
| 349-90 | Code Requirements for Nuclear Safety
Related Concrete Structures |

1.1.1.2 American Society for Testing and Materials (ASTM)

- | | | |
|-----------|--|--------------------|
| A 6-94a | General Requirements for Rolled
Structural Steel Bars, Plates,
Shapes, and Sheet Piling | ECN-117 |
| A 29-93a | Steel Bars, Carbon and Alloy,
Hot Wrought and Cold Finished,
General Requirements for | ECN-117 |
| A 36-91 | Structural Steel | |
| A 53-90b | Pipe, Steel, Black & Hot-Dipped, Zinc-
Coated Welded & Seamless | |
| A 108-90a | Steel Bars, Carbon, Cold Finished,
Standard Quality | |
| A 370-94 | Standard Test Methods and Definitions
for Mechanical Testing of Steel
Products | ECN-117
ECN-117 |
| A 615-92b | Deformed and Plain Billet-Steel Bars
for Concrete Reinforcement | |
| A 751-94 | Standard Test Methods, Practices, and
Terminology for Chemical Analysis of
Steel Products | ECN-117 |
| C 31-91 | Standard Practice for Making and Curing
Concrete Test Specimens in the Field | |
| C 33-93 | Concrete Aggregates | ECN-117 |

C 39-93a	Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens	ECN-117
C 94-92a	Ready-Mixed Concrete	
C 143-90a	Standard Test Method for Slump of Hydraulic Cement Concrete	ECN-117
C 150-94	Portland Cement	ECN-117
C 156-93	Test Method for Water Retention by Concrete Curing Materials	
C 173-94	Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method	ECN-117
C 260-94	Air Entraining Admixtures for Concrete	
C 494-92	Chemical Admixtures for Concrete	
C 618-94a	Coal Fly Ash and Raw or Calcinated Natural Pozzolan for Use as a Mineral Admixture in Portland Cement Concrete	ECN-117
1.1.1.3	American Welding Society (AWS)	
D1.1-92	Structural Welding Code-Steel	
1.1.1.4	Prestressed Concrete Institute (PCI)	
MNL-116-85	Manual for Quality Control for Plants and Products of Precast and Prestressed Concrete Products	
1.2	SUBMITTALS: <i>Not Used</i>	ECN-117
1.2.1	See Section 01300 for submittal procedure.	
1.2.2	Approval Required	
1.2.2.1	Concrete data: Before mixing submit proposed mix design for ACME pre approved mix design No. 6452 for review and record purposes.	
1.2.3	Approval Not Required	
1.2.3.1	Commercial grade item documentation: Before fabrication/installation, submit reports of inspections and tests of items specified in 2.3.1.	ECN-117

1.3 QUALITY ASSURANCE

- 1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document control in accordance with Section 01720.

Document

Paragraph

Pour Slip and Trip Tickets

3.2.3.1

Materials Test Results

~~2.3.1~~, 3.4.1, ~~3.4.3~~

ECN-117

1.4 DELIVERY, STORAGE, AND HANDLING

- 1.4.1 See Section 01610 for general requirements

PART 2 - PRODUCTS

2.1 SUBSTITUTES

- 2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

- 2.2.1 Concrete: ACME preapproved mix design No. 6452.

- 2.2.2 Delivery: In accordance with ASTM C 94.

- 2.2.3 Reinforcing Steel

- 2.2.3.1 Steel bars: ASTM A 615, deformed, Grade 60, except No. 3 ties shall be Grade 40.

- 2.2.3.2 Fabricate reinforcing bars within tolerances listed in ACI 301, Sections 5.6 and 5.7, free of bends not required by the Drawings.

- 2.2.3.3 Tag steel in accordance with the bar list.

- 2.2.4 Rolled Steel Shapes, Plates, and Bars: ASTM A 36.

- 2.2.5 Steel Pipe: ASTM A 53 (black), standard weight, Schedule 40.

- 2.2.6 Weld Studs: Nelson Stud Welding Company, Type H4L.

- 2.2.7 Forms: Wood, steel, plywood, or Masonite Corporation "Concrete Form Board," as required for various finishes specified in PCI MNL-116, Article 3.5.3.

- 2.2.8 Bondbreaker: Compatible with adhesive for resilient flooring.

~~2.3 MATERIAL QUALITY ASSURANCE~~

~~2.3.1 Commercial Grade Item Acceptance: If the following items specified in 2.2 are procured as commercial grade items, they shall be inspected or tested as specified below. Document the results in reports.~~

~~2.3.1.1 Pre approved concrete mix design specified in 2.2.1.~~

~~a. Perform an evaluation of the concrete mix proportions in accordance with ACI 301-89, Sections 3.8 and 3.9.3.3 for specified mix design.~~

~~b. Perform an evaluation of the concrete mix ingredients to ensure compliance with specifications and applicable codes and standards. The following is a list of concrete mix ingredients to be evaluated:~~

- ~~1) Cement in accordance with ASTM C 150, Type II.~~
- ~~2) Fly Ash in accordance with ASTM C 618, Class F. Amount of fly ash shall be 25% $\pm$ 1% by weight of cement.~~
- ~~3) Aggregates in accordance with ASTM C 33, maximum size of course aggregate 3/4 inch.~~
- ~~4) Air Entraining Admixture in accordance with ASTM C 260, no chloride added during manufacture.~~
- ~~5) Water Reducing Admixture in accordance with ASTM C 494, Type D, no chloride added during manufacture.~~

~~c. Perform an evaluation of the concrete mix properties to ensure compliance with specifications and applicable codes and standards. The following is a list of concrete mix properties to be evaluated:~~

- ~~1) Slump 4 inch $\pm$ 1 inch.~~
- ~~2) Air Content 5% $\pm$ 1%.~~

~~d. Perform the following test procedures on the concrete mix at the time of placement in the field. Each test procedure shall be performed a minimum of one time for each pour or one time for each 100 yards delivered for a pour, whichever is greater.~~

- ~~1) Slump test in accordance with ASTM C 143, 4 inch $\pm$ 1 inch.~~
- ~~2) Air Content test in accordance with ASTM C 173 5% $\pm$ 1%.~~
- ~~3) Obtain concrete test cylinders in accordance with ASTM C 31 for determination of concrete compressive strength in accordance with ASTM C 39, $f'_c \geq 4000$ psi.~~

~~2.3.1.2 Reinforcing steel specified in 2.2.3: Submit certified test reports (mill test reports) verifying yield strength and chemical composition of rebars in accordance with ASTM A 615, grade 60. The test reports must verify that the material meets the weight, spacing and height of deformation requirements in accordance with ASTM A 615, Grade 60.~~

~~2.3.1.3 Rolled steel shapes, plates, and bars specified in 2.2.4.~~

~~a. Perform a tensile test in accordance with ASTM A 370 to verify the minimum yield strength of the material is greater than 35,000 psi.~~

~~b. Perform a chemical analysis in accordance with ASTM A 751 to verify the material meets the chemical requirements of ASTM A 36 Table 2.~~

~~c. Perform a check of the dimensions to verify the plates or shapes are within permissible variations of ASTM A 6.~~

~~2.3.1.4 Steel pipe specified in 2.2.5.~~

~~a. Perform a tensile test in accordance with ASTM A 370 to verify the minimum yield strength of the material is greater than 35,000 psi.~~

~~b. Perform a chemical analysis in accordance with ASTM A 751 to verify the material meets the chemical requirements of ASTM A 53 Table 1 and 2 for Type S, Grade B.~~

~~2.3.1.5 Weld studs specified in 2.2.6.~~

~~a. Perform a tensile test to verify that the minimum tensile strength of the studs is 60,000 psi. Tensile test will be performed in accordance with ASTM A 370 and samples selected in accordance with ASTM A 29.~~

~~b. Perform a bending, torquing, or tensioning test in accordance with AWS D1.1, Article 7.6.6 to ensure that the weld attaching the weld stud to the base material will not fail.~~

~~c. Perform a check of the stud dimensions to ensure permissible variations in dimensions are in accordance with ASTM A 29.~~

~~d. Perform visual inspection of stud spacings and edge distances to verify that no stud is placed with less than the minimum requirement, as specified by the manufacturer, and more than the maximum requirement, as specified by design.~~

~~e. Certificate of conformance will be required from the manufacturer to ensure that the studs meet the requirements of ASTM A 108.~~

PART 3 - EXECUTION

3.1 PREPARATION

- 3.1.1 Form Construction: Installation, surface preparation, true line setting, and reuse of forms shall be in accordance with PCI MNL-116, Article 5.1.2 and 5.1.3, or as directed by the Construction Engineer.

3.2 INSTALLATION

3.2.1 Reinforcing Steel

- 3.2.1.1 Place as shown on the Drawings, within tolerances specified in PCI MNL-116, Article 6.4.
- 3.2.1.2 Do not force reinforcing bars into concrete after initial set has started.
- 3.2.1.3 Minimum concrete protection for reinforcement shall be in accordance with ACI 349, Section 7.7.2, except where shown otherwise on the Drawings.
- 3.2.1.4 Additional reinforcement required for handling and erection shall be the responsibility of the Contractor and manufacturer.
- 3.2.2 Cast-In Items: Place within tolerances specified in PCI MNL-116, Article 5.1.5. Perform welding and welding inspection in accordance with AWS D1.1.
- 3.2.3 Concrete
- 3.2.3.1 Before Placing:
- a. Approve the "Pour Slip," including identification of sections of structure to be placed, maximum size of coarse aggregate, and design strength.
 - b. For each truck load, collect the "Trip Ticket." "Trip Tickets" shall contain information listed in ASTM C 94, subparagraphs 16.1.1 through 16.1.10, and the water/cement ratio.
- 3.2.3.2 Place in accordance with ACI 301, Sections 8.1, 8.2, and 8.3. Do not drop (free fall) more than 5 feet. Insert vibrator, vertically if possible, into concrete and reach small distance into next lower layer. Do not insert vibrators into lower courses that have reached initial set. Take care to avoid allowing head of vibrator to come in contact with forms, reinforcing, or embedded items.
- 3.2.3.3 Temper only as permitted in ACI 301, Section 7.5.
- 3.2.3.4 Weather conditions: Protect concrete during placement in accordance with ACI 301, Section 8.4. Cold weather concreting procedure shall be in accordance with ACI 306.1.

- 3.2.3.5 Consolidation: In accordance with ACI 301, Section 11.6.
- 3.2.4 Form Removal and Concrete Repair
 - 3.2.4.1 After form removal, cut back form ties and inspect surfaces for defects. Repair only after permission for patching is given by the Construction Engineer.
 - 3.2.4.2 Place concrete repair mortar within one hour after mixing. Do not retemper mortar.
 - 3.2.4.3 Repair surface defects in accordance with PCI MNL-116, Articles 3.5.4 and 3.5.5. Cure concrete repairs the same as new concrete.
- 3.2.5 Concrete Finishes and Tolerances
 - 3.2.5.1 Formed surfaces: Start finishing of concrete following repair and complete within 96 hours after forms have been removed. Finish formed surfaces in accordance with ACI 301, Section 10.3.2.
 - 3.2.5.2 Related unformed surfaces: Finish in accordance with ACI 301, Section 10.5.

3.3 CURING

- 3.3.1 Cure concrete in accordance with ACI 301, Section 12.2. Where curing compound of surface membrane type is used, it shall retain at least 85% of water in concrete for 72 hours after placement as determined in accordance with ASTM C 156.
- 3.3.2 Do not use curing compound on surfaces to receive sealer/hardener or special protective coating.

3.4 FIELD QUALITY CONTROL

- 3.4.1 Concrete Testing: Sample and test concrete in accordance with ACI 301, Sections 16.3.4, 16.3.5, 16.3.6, and 16.3.8. Record the results.
- 3.4.2 Cracking Acceptability: Kinds, causes of cracking, prevention and control, and recommendations for acceptability shall meet the requirements of PCI MNL-116, Article 6.3.2.

- ~~3.4.3 Precast Concrete Cover Blocks: The quality control inspector will ensure acceptance testing of commercial grade items used to fabricate cover blocks is in accordance with the requirements of paragraphs 2.3.1.1, 2.3.1.2, 2.3.1.3, 2.3.1.4, and 2.3.1.5 of this Section. Record the results.~~

ECN-117

ECN-117

3.5 PROTECTION

- 3.5.1 Protect concrete during extreme weather conditions in accordance with ACI 301, Section 12.3.
- 3.5.2 Protect concrete from mechanical damage in accordance with ACI 301, Section 12.4.

END OF SECTION

SECTION 05055

EXPANSION ANCHOR INSTALLATIONS

PART 1 - GENERAL

- 1.1 REFERENCES: Not Used
- 1.2 SUBMITTALS
 - 1.2.1 See Section 01300 for submittal procedures.
 - 1.2.2 Approval Required
 - 1.2.2.1 Expansion anchor evaluation reports: Before delivery, submit reports as specified in Part 2, and installation requirements.
 - 1.2.3 Approval Not Required: None
- 1.3 QUALITY ASSURANCE
 - 1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Expansion Anchor Installation Reports 3.4.2

- 1.4 DELIVERY, STORAGE, AND HANDLING
 - 1.4.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

- 2.1 SUBSTITUTES
 - 2.1.1 See Section 01630 for substitution approvals.
- 2.2 MATERIALS
 - 2.2.1 Expansion anchors (~~Safety Classes 1 and 2~~ *Safety Class and Safety Significant*): Hilti Fastening Systems "Kwik-Bolt II" (no substitutes allowed). ECN-809
ECN-809
 - 2.2.2 Expansion anchors (~~Safety Classes 3 and 4~~ *General Service*): Industry standard wedge type, having a published evaluation report (by the International Conference of Building Officials), with anchor descriptions, tables of allowable tension and shear loads, and test findings. ECN-809

SECTION 05500

METAL FABRICATIONS

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society of Mechanical Engineers (ASME)

B&PVC Boiler and Pressure Vessel Code

Section V Nondestructive Examination

Section IX Welding and Brazing Qualifications

B31.3-1993 Chemical Plant and Petroleum Refinery Piping

1.1.1.2 American Society for Nondestructive Testing (ASNT)

SNT-TC-1A Recommended Practice (1988 Edition)

1.1.1.3 American Society for Testing and Materials (ASTM)

A 36-91 Structural Steel

A 519-94 Seamless Carbon and Alloy Steel Mechanical Tubing

A 307-92a Carbon Steel Bolts and Studs,
60 000 psi Tensile Strength

ECN-138

A 563-92a Carbon Alloy Steel Nuts

F 844-90 Washers, Steel, Plain (Flat),
Unhardened for General Use

ECN-138

1.1.1.4 American Welding Society (AWS)

D1.1-94 Structural Welding Code - Steel

D1.3-89 Structural Welding Code - Sheet Steel

D9.1-90 Sheet Metal Welding Code

QC1-88 Certification of Welding Inspectors

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required

- 1.2.2.1 Drawings: For metal fabrications not shown on manufacturer's data sheets: Before fabrication, submit fabrication drawings and bill of materials. Include plans, elevations, details, sections, and connections. Show thickness, type, grade, class of metal, fasteners, anchorage, and accessory items where applicable.

PART 3 - EXECUTION

3.1 EXAMINATION

- 3.1.1 Examine areas where expansion anchors are to be installed and notify the Construction Engineer in writing of conditions detrimental to proper and timely completion of work as specified in 3.3. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- 3.2.1 Prepare setting drawings, diagrams, templates, and instructions for installation of expansion anchors to be embedded in concrete or masonry construction.

3.3 INSTALLATION

- 3.3.1 Install expansion anchors in accordance with manufacturer's recommendations.

3.4 FIELD QUALITY CONTROL

- 3.4.1 Expansion Anchor Installations: The Quality Control Inspector will inspect Safety Class 1 and 2 installations.
- 3.4.2 Expansion Anchor Inspection: Document inspection results on the "Expansion Anchor Installation Report," Form KEH-1910.

END OF SECTION

~~1.2.2.2 Manufacturer's data: Before delivery, submit the following.~~

- ~~a. Copies of manufacturer's specifications.~~
- ~~b. Dimensioned diagrams.~~
- ~~c. Installation instructions for manufactured items.~~

ECN-597

1.2.3 Approval Not Required: None.

1.3 QUALITY ASSURANCE

1.3.1 Welding Processes - Structural Metal Work

1.3.1.1 Procedures for welding components shall have been qualified in accordance with the following.

- a. For structural steel, in accordance with AWS D1.1.
- b. For sheet steel (structural), in accordance with AWS D1.3.
- c. For sheet metal (seal welding), in accordance with AWS D9.1.

1.3.1.2 Qualification in accordance with the ASME B&PVC Section IX may be substituted for the above requirements.

1.3.2 Welding Personnel - Structural Metal Work

1.3.2.1 Personnel performing welding shall have been qualified in accordance with the respective Codes of 1.3.1.1.

1.3.2.2 Qualification in accordance with the ASME B&PVC Section IX may be substituted for the above requirements.

1.3.3 Welding Nondestructive Examination (NDE) Personnel

1.3.3.1 Visual weld examinations shall be performed, and appropriate documentation prepared by Certified Welding Inspectors (CWI) who have received certification in accordance with AWS QC1. Certified Associate Welding Inspectors (CAWI), certified in accordance with the above standard, may perform examinations when under immediate direction of CWIs.

1.3.3.2 Qualification in accordance with the ASME B&PVC Section V, Article 9 may be substituted for the above requirement.

1.3.3.3 Welding related examination documentation shall be signed or stamped by individuals performing examinations. Where CAWIs perform examinations, documentation shall be signed or stamped by both CAWIs and CWIs under whom examinations were performed.

1.3.3.4 Personnel performing other welding NDE shall be certified in accordance with CONTRACTOR's written practice, which shall meet the requirements of ASNT SNT-TC-1A.

- 1.3.4 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Process and Personnel Qualifications

1.3.2, 1.3.3

Weld Examination Results

3.5.2.1, 3.5.2.2

1.4 DELIVERY, STORAGE, AND HANDLING

- 1.4.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

- 2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

- 2.2.1 Rolled Steel Shapes, Plates, and Bars: ASTM A 36.

- 2.2.2 Steel Pipe: See Section 03400.

- 2.2.3 Round Mechanical Tubing: ASTM A 519, Carbon Steel.

- 2.2.4 Fasteners

- 2.2.4.1 Expansion anchors: See Section 05055.

- 2.2.4.2 Weld studs: Nelson Stud Welding Company Type H4L.

- 2.2.4.3 Bolts: ASTM A 307, Grade A or B.

- 2.2.4.4 Nuts: ASTM A 563, Grade A, heavy hex.

- 2.2.4.5 Washers: ASTM F 844, circular.

- 2.2.5 Welding Electrodes: E70XX.

- 2.2.6 Nonshrink Epoxy Grout: See Section 03300.

- 2.2.7 Paint: See Section 09900.

- 2.2.8 Zinc-Rich Coating: Southern Coating Incorporated "Galvicon," or ZRC Products Company "ZRC."

2.3 FABRICATION

- 2.3.1 General

ECN-138

ECN-138

- 2.3.1.1 Verify measurements and take field measurements necessary before fabrication. Provide miscellaneous bolts and anchors, supports, braces, and connections necessary for completion of metal fabrications. Cut, reinforce, drill, and tap metal fabrications shown to receive finish hardware and similar items. Weld or bolt connections as shown on the Drawings.

- 2.3.1.2 Workmanship: Form metal fabrications to shape and size, with sharp lines, angles, and true curves. Drilling and punching shall produce clean, true lines and surfaces. Execute and finish work in accordance with fabrication drawings.
- 2.3.1.3 Jointing and intersections: Accurately made, tightly fitted, and in true planes with adequate fastenings.
- 2.3.2 Miscellaneous Steel Items: Supply required clips, frames, equipment supports, and other fabrications shown on the Drawings. Fabricate parts from standard structural sections or shapes, to sizes required. Wherever miscellaneous parts are exposed, grind edges, corners, and rough cuts smooth and free of snags. Shop paint parts except those to be embedded in concrete or masonry, or those which require other specific finishes.
- 2.3.3 Finishes: Prime ferrous metal in accordance with Section 09900. Do not coat members to be embedded in concrete or masonry, surfaces and edges to be field welded, or items to be galvanized.

PART 3 - EXECUTION

3.1 EXAMINATION

- 3.1.1 Examine areas where metal fabrications are to be installed and notify the construction Engineer in writing of conditions detrimental to proper and timely completion of work as specified in 3.3. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- 3.2.1 Prepare setting drawings, diagrams, templates, and instructions for installation of anchorages, such as concrete inserts, anchor bolts, and miscellaneous items having integral anchors, to be embedded in concrete. Coordinate with the Construction Engineer for delivery of items to Site.

3.3 INSTALLATION

- 3.3.1 Expansion Anchor Installation: See Section 05055.
- 3.3.2 Install metal fabrications plumb, level or as shown on the Drawings.
- 3.3.3 Make field connections as neatly as possible with joints flush and smooth. Grind smooth exposed field welds and polish before field painting. Repair welds in galvanized work with 2 coats of zinc-rich coating.
- 3.3.4 Where dissimilar metals are in contact, or where aluminum is in contact with concrete, mortar, masonry, wet or pressure-treated wood, or absorptive materials subject to wetting, protect surfaces with isolating tape to prevent galvanic or corrosive action.

3.4 APPLICATION

3.4.1 After installation has been approved, clean and paint connections with primer. Touch-up shop prime coat wherever damaged. Repair breaks in galvanized coatings with zinc-rich coating.

3.5 FIELD QUALITY CONTROL

3.5.1 Perform visual inspection to verify stud spacings and edge distances as specified and shown on Drawings.

3.5.2 Nondestructive Weld Examination (NDE)

3.5.2.1 Perform visual examination of welds in accordance with AWS D1.1, paragraph 6.5.5, unless noted otherwise on the Drawings. Record the results.

3.5.2.2 Visual weld examination performed in accordance with requirements of ASME B31.3, Paragraph 344.2.2 may be substituted for the above requirement. Acceptance criteria shall be in accordance with ASME B31.3, Table 341.3.2A. Record the results.

END OF SECTION

SECTION 09805

SPECIAL PROTECTIVE COATING

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 Steel Structures Painting Council (SSPC)

SP 2-82 Hand Tool Cleaning

SP 3-82 Power Tool Cleaning

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required

1.2.2.1 List of materials: Before delivery, submit complete list of materials, colors and location to be used, to substantiate compliance with the Drawings and this Section. List shall enumerate percentage of volatile and nonvolatile materials and percentage of component parts of each type of material. Colors will be selected by the Construction Engineer.

1.2.3 Approval Not Required: None

1.3 QUALITY ASSURANCE

1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Coating Application Test Results 3.4.1

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 See Section 01610 for general requirements.

1.4.2 Do not open containers before inspection and acceptance by the Quality Control Inspector. Labels shall not be removed under any circumstance.

1.5 PROJECT CONDITIONS

1.5.1 Environment for Coating: Coat exterior surfaces only when ambient and surface temperatures are 50 to 90°F, and ambient temperature is at least 5°F above the dewpoint.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

2.2.1 Coating Materials: Products of Protective Coatings Division of Ameron, Brea, California or approved substitute.

2.2.1.1 Primers, thinners, and coating accessory materials shall be produced and/or approved for use by the same manufacturer as the finish coating system.

2.2.2 Concrete Filler: Nu-Klad 114A Epoxy Filler Compound.

2.2.3 Primers:

2.2.3.1 New cover block concrete surfaces: Nu-Klad 105A Primer and Sealer or Amerlock 400.

2.2.3.2 New cover block/plug ferrous metal surfaces: Amerlock 400.

2.2.4 Finish Coatings:

2.2.4.1 All new cover block/plug surfaces: PSX 700 Siloxane.

PART 3 - EXECUTION

3.1 EXAMINATION

3.1.1 Examine surfaces scheduled to receive coatings for conditions that will adversely affect execution, permanence, or quality of work, and which cannot be put into acceptable condition through preparatory work as specified in 3.2.

3.1.2 Report conditions that could adversely affect proper application of coatings, in writing, to the Construction Engineer as specified in 3.3. Do not begin surface preparation, or coating application, until defects have been corrected, and conditions made suitable.

3.2 PREPARATION

3.2.1 New Cover Block Concrete Surfaces:

3.2.1.1 Before application, sweep and dust space or area to receive coating.

3.2.1.2 Clean concrete surfaces of laitance, oil, stains, dust and other foreign material.

a. Where laitance has not been removed, treat concrete with uniform application of 1 of following solutions.

1) 1 part 10% solution muriatic acid and 3 parts water.

2) 5% solution of trisodium phosphate.

b. When solution ceases to foam, rinse thoroughly with clean water and scrub with stiff bristle brush. Allow treated area to thoroughly dry. Scratches, cracks, holes and abrasions shall be cut back to proper key and filled with Nu-Klad 114A.

c. Allow concrete to cure 30 days before coating is applied, except coating may be applied after concrete has cured 21 days if moisture content of concrete is less than 12%.

3.2.2 New Cover Block/Plug Ferrous Metal Surfaces:

3.2.2.1 Prepare surfaces for finish systems specified in accordance with recommendations of finish material manufacturers and SSPC-SP 2, -SP 3.

3.2.3 Postpriming

3.2.3.1 Feather abrasions, chips, skips, and holidays occurring in prime coat by sanding and recoat with material and color to minimum dry film thickness specified.

3.2.3.2 Previously coated surfaces shall be recoated only after existing film is completely dry.

3.2.3.3 Protect coating from rain until dry to touch.

3.2.4 Protection

3.2.4.1 Provide and install drop cloths, shields, and other protective devices required to protect surfaces adjacent to areas being coated. Keep spatter, smears, droppings, and over-run of coating materials to minimum and remove as coating work progresses. Report all spills to the Construction Engineer.

3.2.4.2 Remove and store electrical fixtures, outlets and switch plates, mechanical diffusers, escutcheons, surface hardware, fittings and fastenings before starting work. Clean and reinstall upon completion of work in each area. Use no solvent or abrasives to clean hardware that will remove lacquer finish normally used on some items.

3.3 APPLICATION

3.3.1 General

3.3.1.1 Before any surface is coated, it shall be clean, dry, undamaged and free of all contaminants. Round off all rough welds and remove all weld splatter.

3.3.1.2 All specified surface preparation shall meet the specification of the Coating Schedule and shall be done before application can begin on the area to be coated.

3.3.1.3 All coatings shall be applied under favorable environmental conditions as specified in manufacturer's product literature.

3.3.1.4 Coating shall be prepared and applied in accordance with manufacturer's recommendations, and proper induction time shall be observed for epoxies when required by manufacturer. Failure to comply with this requirement will be cause for rejection of the work.

3.3.2 Apply with equipment recommended by manufacturer.

3.3.3 Identify each coat of opaque material by its relation to color of finish coat. Prime coat shall be darkest tint of specified color with each succeeding coat lighter, up to finish coat, which shall be color, tint and sheen specified. Tints of identical coats of identical color and material shall not vary.

3.4 FIELD QUALITY CONTROL

3.4.1 Inspection: The Quality Control Inspector will perform tests to ascertain that coating materials have been applied as specified in this Section.

3.5 CLEANING

3.5.1 Furnish and maintain at site, closed metal containers for disposal of waste materials. Place materials spotted or soaked with paint, oil, or solvents in containers.

3.5.2 Brushes, rollers, spatulas, and spray equipment shall be thoroughly cleaned after each use and shall contain no oils, thinners, or other residue after cleaning.

3.5.3 Remove empty cans from site at end of each shift.

3.5.4 At completion of coating work, remove materials, containers, rags, cloths, brushes, and other equipment from site. Clean up spills.

3.6 COATING SCHEDULE

		Minimum Wet Film Thickness and Percentage of Film Forming <u>Solids by Volume</u>	Minimum Dry Film <u>Thickness</u>
3.6.1	New Cover Block Concrete Surfaces		
	Prime and Sealer: Nu-Klad 105A or Amerlock 400	NA	NA
	Second: PSX 700 Siloxane	7	5 mils
	Finish: PSX 700 Siloxane	7	5 mils
3.6.2	New Cover Block Ferrous Metal Surfaces and Lifting Bails		
	Prime: Amerlock 400	NA	NA
	Second: PSX 700 Siloxane	7	5 mils
	Finish: PSX 700 Siloxane	7	5 mils

END OF SECTION.

SECTION 09900

PAINTING

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society for Testing and Materials (ASTM)

D 4258-1983 (R1988)

Surface Cleaning Concrete for Coating

1.1.1.2 Federal Specifications (FS)

SS-S-1996
Reinst

Sealer, Water and Weather Resistant,
for Asphalt, Concrete, and Masonry
Surfaces

1.1.1.3 Painting and Decorating Contractors of America (PDCA)

Architectural Specification
Manual

1984

1.1.1.4 Steel Structures Painting Council (SSPC)

SP 2-82

Hand Tool Cleaning

SP 3-82

Power Tool Cleaning

SP 5-85

Blast Cleaning "White" Metal

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required

1.2.2.1 ~~List of materials: Before delivery, submit list including manufacturers' names, specifications, recommendations, and other data necessary to show compliance with requirements.~~
List of materials: Before delivery, submit complete list of materials, colors and location to be used, to substantiate compliance with the Drawings and this Section. List shall enumerate percentage of volatile and nonvolatile materials and percentage of component parts of each type of material. Colors will be selected by the Construction Engineer.

ECN-170

ECN-170

1.2.2.2 ~~Color samples: Before delivery, submit samples in form of 3 by 5 inch color chips. Describe coating material, manufacturer, and color identification on reverse face of each chip. Colors will be selected by the Construction Engineer. Retain 1 set of approved samples at site for use as quality standard of final finishes.~~

ECN-170

ECN-170

1.2.3 Approval Not Required: None

1.3 QUALITY ASSURANCE

- 1.3.1 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Coating Application Test Results

3.4.1

- 1.3.2 Use manufacturers and products listed in the PDCA Architectural Specification Manual, Chapter 7.

1.4 DELIVERY, STORAGE, AND HANDLING

- 1.4.1 See Section 01610 for general requirements. Store materials indoors.

1.5 PROJECT CONDITIONS

1.5.1 Environmental Requirements

- 1.5.1.1 Temperature: Unless otherwise recommended by paint manufacturer, apply coatings when ambient and surface temperatures are 45 to 95°F, except for water-thinned paints and other special coatings.

a. Apply water-thinned paints when ambient and surface temperature is 50 to 90°F.

b. Apply varnish on surfaces with temperatures above 65°F.

c. Apply epoxy coatings when conditions are within humidity and temperature limits recommended by the coating manufacturer.

d. Provide temporary heat as required until specified surface and air temperatures exist for required time periods. Maintain temporary heat for 24 hours after paint and finish application.

- 1.5.1.2 Weather: Do no exterior work on unprotected surfaces if it is raining or moisture from other source is present or expected before applied finishes can dry or attain proper cure without damage.

a. Allow surfaces to dry and attain required temperatures and conditions specified before proceeding with work or continuation of previously started work.

b. Do not apply finish in areas where dust is being generated.

c. Humidity: Follow manufacturer's directions for extremes.

- 1.5.1.3 Ventilation: Provide adequate continuous ventilation required for drying various materials as recommended by the manufacturer.

- 1.5.1.4 Illumination: Provide temporary lighting to attain minimum surface lighting level of 15 fc/ft².

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

2.2.1 Furnish materials identified in PDCA Architectural Specification Manual, Chapters 5, 6, and 7 for systems scheduled in 3.6.

2.2.2 Furnish ready-mixed materials.

2.2.3 Concrete Sealer/Hardener

2.2.3.1 New concrete pads: FS SS-S-1996, Type II (Top Surface).

2.2.3.2 New cover block surfaces: See Section 09805.

PART 3 - EXECUTION

3.1 EXAMINATION

3.1.1 Examine surfaces scheduled to receive finish for conditions that will adversely affect execution, permanence, or quality of work and which cannot be put into acceptable condition through preparatory work specified in 3.2.

3.1.2 Report conditions that may affect proper application of finish as specified in 3.3, in writing, to the Construction Engineer. Do not begin surface preparation or coating application until defects have been corrected, and conditions are made suitable.

3.2 PREPARATION

3.2.1 Protection

3.2.1.1 Protect finished work of other trades and the following.

a. Brass, bronze, copper, plated metals, and stainless steel not scheduled for further finish.

b. Materials having complete factory finish, such as electrical switchplates, lighting fixtures, and finish hardware.

3.2.1.2 As work proceeds, and upon completion of work, promptly remove spills, splashes, or splatters from products by methods not damaging to affected surfaces.

3.2.1.3 Repair or replace surfaces damaged by painting work as directed by the Construction Engineer.

3.2.1.4 Remove electrical outlet and switch plates, mechanical diffusers, escutcheons, registers, surface hardware, fittings, fastenings, and

similar items before starting work. Carefully store, clean, and reinstall items upon completion of work in each area. Do not use cleaning agents detrimental to permanent lacquer finishes.

3.2.2 Ferrous Metals

3.2.2.1 Prepare surfaces for finish systems specified in accordance with recommendations of finish material manufacturers, the PDCA Architectural Specification Manual, Chapters 3 and 3R, and SSPC-SP 2, -SP3, and -SP5.

3.2.2.2 Obtain written approval for dry or liquid abrasive blasting from the Construction Engineer.

3.2.3 Concrete Surfaces

3.2.3.1 Curing period: Concrete shall be allowed to cure 28 days minimum before the application of a concrete sealer/hardener, or as recommended by the manufacturer of the concrete sealer/hardener.

3.2.3.2 Form release agents: Agents used during concrete construction shall be removed, unless known to be compatible with the concrete sealer/hardener selected.

3.2.3.3 Concrete curing compounds: Compounds shall be removed unless known to be compatible with the concrete sealer/hardener selected.

3.2.3.4 Contaminants: Oil, grease, and materials considered deleterious by the concrete sealer/hardener manufacturer shall be removed in accordance with the manufacturer's written recommendations, followed by washing of contaminated areas with detergent and water in accordance with ASTM D 4258.

3.2.3.5 Sweeping and hosing: Clean areas to be treated with a fine bristle broom, or scrub, hose off with water, and let dry to remove surface dust, dirt, and contamination. Pressurized air may be used provided the equipment is oil-free.

3.3 APPLICATION

3.3.1 Do not open containers until approved by the Quality Control Inspector. Labels must not be removed under any circumstances.

3.3.2 Mix materials in an ambient temperature above 45°F in a well ventilated and heated area, in accordance with the manufacturer's recommendations.

3.3.3 Perform work in accordance with manufacturers instructions, PDCA Architectural Specification Manual, and this Section.

3.3.4 Take precautions to prevent fire hazards and spontaneous combustion. Place cotton waste, cloths, and hazardous materials in containers and remove from the worksite daily.

3.3.5 Improperly treated surfaces, and holidays shall be repaired using the materials specified for the original work, unless otherwise specified, in accordance with written recommendations of the sealer/hardener manufacturer.

3.4 FIELD QUALITY CONTROL

3.4.1 Inspection and testing will be performed by the Quality Control Inspector. Document results of tests.

3.4.2 Meet the requirements of PDCA Architectural Manual for "CUSTOM" material and work, unless otherwise specified.

3.5 CLEANING

3.5.1 Furnish and maintain at site, closed metal containers for disposal of waste materials. Place materials spotted or soaked with paint, oil, or solvents in containers.

3.5.2 Brushes, rollers, spatulas, and spray equipment shall be thoroughly cleaned after each use and shall contain no oils, thinners, or other residue after cleaning.

3.5.3 Remove empty cans from site at end of each shift.

3.5.4 At completion of coating work, remove materials, containers, rags, cloths, brushes, and other equipment from site. Clean up spills.

3.6 SCHEDULES

3.6.1 Paint and Finish

3.6.1.1 Paint exposed miscellaneous carbon steel surfaces, unless otherwise specified, as follows:

~~a. Apply two coats of Amerlock 400, 5 mils thick per coat (DFT), in accordance with the manufacturer's instructions.~~

ECN-173

ECN-173

a. Apply one prime coat of Ameron "Amerlock 400", 5 mil thick (DFT), in accordance with manufacturer's instructions.

ECN-173/548

~~b. Apply one finish coat of Amercoat 450 HS, 2 to 3 mils thick (DFT), in accordance with the manufacturer's instructions.~~

b. Apply one finish coat of Ameron "PSX 700", 3 mils thick (DFT), in accordance with manufacturer's instructions.

ECN-173/548

~~c. In lieu of a. and b. above, paint miscellaneous exposed carbon steel surfaces with Benjamin Moore Ironclad high gloss enamel in accordance with manufacturer's instructions.~~

ECN-170

ECN-170

d-c. Do not paint threaded surfaces before assembly.

ECN-170

e-d. Do not paint nameplates.

ECN-170

END OF SECTION

SECTION 13440

INSTRUMENTATION

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 National Electrical Manufacturers Association (NEMA)

ICS 6-1993

Enclosures for Industrial Controls and Systems

1.1.1.2 National Fire Protection Association

70 (1993)

National Electrical Code (NEC)

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required

1.2.2.1 Approval data: Before installation, submit information listed in the Approval Data List in this Section.

1.2.3 Approval Not Required

1.2.3.1 Vendor information: Before installation, submit information listed in the Vendor Information List in this Section.

1.3 QUALITY ASSURANCE

1.3.1 Electrical/Electronic Product Acceptability: Provide labeling and documentation in accordance with Section 01400.

1.3.2 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Electrical Test Results

3.2.1.3, 3.2.1.4

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

2.2.1 Wiring and other materials required to complete instrumentation installation are specified in Section 16400 and on the Drawings.

2.2.2 Instrument Identification Tags: 3/4 by 2 by 0.0478-inch (18-gage) minimum thickness stainless steel, with 1/8-inch stamped or engraved characters.

2.2.2.1 ~~Tags shall show the following:~~ Field tags, as a minimum, shall show Equipment Part Number:

~~Equipment Part Number
Instrument Range
Purchase Order Number
Project Number (W-320)~~

ECN-458

ECN-458

2.2.2.2 Tag Attachment Wire: 20-gage, solid, stainless steel.

2.2.3 Equipment/Instrument Nameplates: Laminated plastic 1/16 inch thick, white surface and black core as shown on Figure 1.

ECN-458

2.2.3.1 Engrave the nameplates with the information shown on the Drawings and in accordance with Figure 1.

2.2.3.2 Attach nameplates to equipment and panels as shown on the Drawings and in accordance with Figure 1.

2.3 EQUIPMENT

2.3.1 Provide instruments consisting of individual instrument devices as specified in the Data Sheets.

2.3.2 Instrument Enclosure: Procure and assemble instrument enclosure IE-0621 as shown on the Drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

3.1.1 Install material and equipment in accordance with the Drawings and manufacturer's instructions. Attach identification tags or nameplates to instruments with wire, or as shown on the Drawings.

3.1.2 Install equipment into enclosure IE-0621 as shown on the Drawings.

3.1.3 Install the completed enclosure IE-0621 in electrical equipment skid (building 241-AV-51) as shown on the Drawings, and connect all field cabling.

- 3.1.4 Mounting of instruments, and other equipment on the existing instrument panel shall not interfere with access to connections, removal of adjacent instruments, and normal maintenance.
- 3.1.4.1 For pressure and flow instrument sensor installation, see jumper Drawings.
- 3.1.5 Recommended shop equipment for filling the pressure measuring system is shown on Figure 2.
- 3.1.5.1 Remove the plug from the ball valve and install shop equipment.
- 3.1.5.2 With the valve opened, and the 3-way ball positioned to allow evacuation, use the vacuum pump to evacuate air from the pressure measurement system cavity.
- 3.1.5.3 When the pressure gage reads between 25 and 30 inHg, position the 3-way ball to allow silicon oil to be drawn into the system cavity (approximately 30 ml).
- 3.1.5.4 After filling, close the valve, remove shop equipment, and reinstall the plug.
- 3.1.6 Wiring
- 3.1.6.1 ~~Electrical power wiring and signal wiring shall be in accordance with NFPA 70, Section 16400, and the Drawings.~~ *Electrical power wiring, control wiring and signal wiring shall be in accordance with the National Electric Code, NFPA 70 and the Drawings.* ECN-601
ECN-601
- 3.1.6.2 Instrument signal wiring ~~shall be as specified, and shall be~~ No. 16 AWG minimum stranded tinned copper wire shielded and twisted unless otherwise recommended by the instrument manufacturer. ECN-601
- 3.1.6.2.1 *Control wiring shall be Type SIS or THHN and shall not be smaller than 14 AWG.* ECN-601
ECN-601
- 3.1.6.3 Instrument and electrical equipment shall be grounded in accordance with NFPA 70 and as shown on the Drawings.
- 3.1.6.4 Instrument signal wiring routed in parallel with ac power, or control wiring shall be 6 inches minimum distant. Instrument signal wiring crossing power wiring shall be as close to right angles as possible.
- 3.1.6.5 Wiring within instrument cabinets shall be run open, bundled, and bound with cable ties at regular intervals of 12 inches maximum. Wires within a bundle shall be run parallel to one another. Bundles shall have a uniform appearance, a circular cross section, and be securely fastened to the cabinet framework.
- 3.1.6.6 Wires shall be identified as shown on the Drawings, at each end, with imprinted tubular plastic wire markers as specified in Section 16400.
- 3.1.7 Winch Position Indication (ZI-0621): Confirm that the scale of ZI-0621 has been marked to indicate winch position. If it has not, remove the meter and deliver it to the Construction Engineer for processing. When returned by the Construction Engineer, re-install the meter.

3.2 FIELD QUALITY CONTROL

3.2.1 Testing

3.2.1.1 Furnish calibrated instruments required to perform testing.

3.2.1.2 Electrical Tests: Test instrument wiring as specified in Section 16400, and the following.

3.2.1.3 Disconnect wires from instruments and verify continuity of every wire from end to end. Resistance shall be 10 ohms maximum. Record the reading.

3.2.1.4 With conductors disconnected from instruments, but with shields connected to ground, measure and record resistances between each conductor and its related shield. Resistance shall be greater than 100 megohms.

3.2.1.5 Reconnect wires.

Y-0701

Sheet 1 of 2

PRESSURE INSTRUMENTS (Based on ISA S20.40a)

GENERAL

1. Tag Number: See Note 5 Service Sluice Pressure
2. Function: Record ☐ Indicate ☐ Control ☐ Blind ☒
Trans ☐ Other Transducer Element
3. Case: Mfr Std ☒ Nom Size 2" OD x 3" Long
Color: Mfr Std ☒ Other _____
4. Mounting: Flush ☐ Surface ☐ Yoke ☐ Other Direct
5. Enclosure Class: General Purpose ☐ Weather Proof ☐ Explosion Proof ☐
Class _____ For use in intrinsically safe system ☐
Other See Note 2
6. Power Supply: 117 V, 60 Hz ☐ Other _____ V ac See Note 3 V dc

TRANSMITTER

10. Output: 4-20 mA ☐ 10-50 mA ☐ 21-103 kPa (3-15 psig) ☐
Other Compatible with signal conditioner on
Data Sheet Y-0702
For receiver, see Data Sheet Y-0702

ELEMENT

17. Service: Gage Press ☒ Vacuum ☐ Absolute ☐ Compound ☐
18. Element Type: Diaphragm ☐ Helix ☐ Bourdon ☐ Bellows ☐
Other Strain gage bonded foil
19. Material: 316 SST ☒ Ber Copper ☐ Other _____
20. Range: Fixed ☒ Adj Range _____ Set at _____
Overrange protection to 50% (Nom) over range
21. Process Data: Press: Normal 0-312 psig Max 320 psig
Element Range 500 psig (See Note 6)
22. Process Conn: 1/4" npt ☒ 1/2" npt ☐ Other Female thread
Location: Bottom ☒ Back ☐ Other _____

PRESSURE INSTRUMENTS
(Based on ISA S20.40a)

(Continued)

OPTIONS

25. Options: Filter-Rgltr _ Supply Gage _ Output Gage _
 Charts Diaph Seal _ Type _
 Diaph _ Bot Bowl _ Conn _
 Capillary: Length _ Matl _
 Other See Notes 4 and 7
26. Mfr & Model No.: Sensotec Model TJE Code No. AP121CR or an approved ECN-128
 substitute

NOTES:

- (1) Items 7 through 9, 11 through 16, 23 and 24 are not required.
- (2) Item 5: Mfr Std hermetically sealed stainless steel construction, ICS 6, NEMA Type 4X.
- (3) Item 6: DC voltage input from Receiver Instrument on Data Sheet Y-0702.
- (4) Item 25: Mfr standard electrical connector with mating plug, strain relief and 100 feet of cable.
- (5) Tag Numbers: PE-0621 and PE-0622.
- (6) Instruments shall withstand 30 inches Hg vacuum on pressure port with no detrimental effects.
- (7) Ambient temperature range: 30°F - 180°F.

Y-0702

Sheet 1 of 2

RECEIVER INSTRUMENTS (Based on ISA S20.1a)

GENERAL

1. Tag Number: See Note 4 Service Sluice Pressure
2. Function: Record Indicate X Control Blind
 Integ Deviation Other See Note 2
3. Case: Mfr Std X Nom Size 4" W x 2" H x 5" Deep
 Color: Mfr Std X Other
4. Mounting: Flush X Surface Rack Multi-Case
 Other
 For multiple case, see form Y-
5. Enclosure Class: Gen Purpose X Weatherproof X Explosion Proof ECN-166
 Class
 For use in intrinsically safe system Other
6. Power Supply: 117 V, 60 Hz X Other: V ac V dc
9. Scales: Type Digital (PSIG) 4 1/2 Digits
 Range 1 19999 (MAX) 2 3 4

INPUTS

16. Signals: 4-20 mA 10-50 mA 21-103kPa (3-15 psig)
 Other Compatible with Sensor on Data Sheet Y-0701
17. Number: 1 X 2 3 4
18. Power for Xmtr: External This instrument X
 Number of independent supplies One
 For transmitters, see Data Sheet Y-0701

ALARMS

19. Switches: Quantity 2 Form C Rating 1 Amp, 120 V ac
20. Function: Measured Variable X Deviation
 Contacts to actuate on measurement (decreasing)
 Other
22. MFR & Model No.: Sensotec Model GM or an approved substitute
(Model No. AF213, 51b, 52e, 58a, 59b) ECN-166

NOTES:

- (1) Items 7, 8, 10 through 15 and 21 are not required.
- (2) Item 2: Solid state electronic signal conditioner/amplifier and digital display and low alarm switch for transducer element on Data Sheet Y-0701.
- (3) Adjustment: Span, zero and shunt calibration.
- (4) Tag Numbers: PISL-0621 and PISL-0622.
- (5) Accuracy: $\pm 0.25\%$ of Full Scale ± 1 digit.

ANNUNCIATORS
(Based on ISA S20.2a)

GENERAL

1. Tag Number: ANN-0621 Location Elec. Skid 241-AY-51
2. Cabinet Size: 4 Rows High By 4 Columns Wide
3. Mounting: Flush Panel ☒ Surface ☐
4. Cabinet Style: Plug-In Light Boxes ☒ Swing Door ☐
Remote Logic Cabinet ☐ Watertight Door ☐
5. Rating: General Purpose ☒ Weatherproof ☐
Explosion Proof ☐ Class
Group Division
6. Power Supply: 117 V, 60 Hz ☒ 125 V dc ☐ 12 V dc ☐ 24 V dc ☐
Other:

DISPLAY

7. Backlighted
Nameplates: White Translucent ☒ Other See Note 2 Size See Note 3
8. Alarm Points Per
Lightbox: 1 ☐ 2 ☒ 3 ☐ 4 ☐
Lamps Per Alarm: 1 ☐ 2 ☒ 3 ☐ 4 ☐

LOGIC

11. Logic: Electro-Mechanical Relay ☐ Solid-State Electronic ☒
Mercury Bottle ☐ Fluidic ☐
12. Location: In Display Cab ☒ Remote Cab ☐ Strip Chassis ☐
13. Style: Gen Purpose ☒ Weatherproof ☐ Explosion Proof ☐
Class Group Division Intrinsically Safe ☐
14. Field Contact
Voltage: 117 V ac ☐ 12 V dc ☐ 125 V dc ☐ Other 24 V dc
15. On Alarm, Actuating
Contacts: Open ☐ Close ☐ Field Selectable ☒ Form

ANNUNCIATORS
(Based on ISA S20.2a)

FEATURES

16. Required: Lock-In of Momentary Alarms ☒ Auxiliary Contacts ☐
Sequential Alarm Circuit ☐
17. ~~Ring Back Circuit:~~ ~~Via Alarm Audible Signal~~ ☒ ECN-128
~~Via Other Audible Signal~~ ☐ ECN-128
18. Other: Fail-Safe Circuit To Signal Own Failure ☒
Operational Test ☐ Lamp Test ☒
19. Flasher: Remote ☐ In Cabinet ☒
20. Acknowledge: Common ☒ Unit ☐ Light ☒ Audible ☒
Pushbutton
Location: In Cabinet ☒ Remote ☐ Other ☐
21. Reset: Common ☒ Unit ☐ Light ☒ Audible ☐
Pushbutton
Location: In Cabinet ☒ Remote ☐ Other ☐

SEQUENCE

22. STAGE	VISUAL SIGNAL	AUDIBLE SIGNAL	
Normal	OFF	OFF	
Alert	Flashing	ON	
Acknowledge	Steady On	OFF	
Return to Normal	OFF Steady On	OFF	ECN-166
Reset	Steady On OFF	OFF	ECN-166
Test	Flashing	ON	

ISA Sequence Number: A M (ISA S18.1) ECN-166

ANNUNCIATORS
(Based on ISA S20.2a)

OPTIONS

27. Power Supply

Location:

Separate from logic cabinet

28. Accessories:

Auxiliary relays for horn output, flasher
output, and common alarm output shall be
integrally mounted in the logic cabinet
(3 Form C contacts, 5 amps at 120 Vac 60 Hz).
Remote mounted auxiliary relay for
horn output and strobe light (3 form C
contacts, 5 amps at 120 Vac).

ECN-128

ECN-128

29. Manufacturer:

Panalarm

Model No.:

Series 90

NOTES:

- (1) Items 9, 10, 17, 23 through 26 are not required.
- (2) Item 7: Nameplates shall be white. 6 red and 24 yellow colored filters for installation behind white nameplates shall be provided.
- (3) Item 7, Nameplate Size: 1 7/16" H x 3 5/16" W (Nominal) for each alarm point.

ECN-128

MAGNETIC FLOWMETERS
(Based on ISA S20.23a)

1. Tag Number:	<u>FE-0621</u>		
2. Service:	<u>Supernate Flow</u>		
3. Location:	<u>Sluice Pit AY-02E</u>		

METERING ELEMENT - CONN

4. Line Size-Sched:	<u>4 inch Sched 40S</u>		
5. Line Material:	<u>304L SST</u>		
6. Connection Type:	<u>300# Raised face mating flanges (wafer type)</u>		
7. Connection Matl:	<u>Mfg Std</u>		

METERING ELEMENT - METER

8. Tube Material:	<u>303 SST</u>		
9. Liner Material:	<u>TEFZEL</u>		
10. Electrode Type:	<u>Mfg std</u>		
11. Electrode Matl:	<u>Tantalum</u>		
12. Meter Casing:	<u>Mfg std</u>		
13. Power Supply:	<u>From associated instrument FIT/FQI-0621</u>		
Elec Code:			
14. Grounding, Type & Material:	<u>Mfg std</u>		
15. Enclosure Class:	<u>NEMA 4X</u>		

METERING ELEMENT - FLUID

17. Fluid:	<u>Water slurry</u>		
18. Max Flow:	<u>350 gpm</u>		

MAGNETIC FLOWMETERS
(Based on ISA S20.23)

FLUID (cont)

19. Max Velocity:	<u>10 ft/sec</u>	<u> </u>
20. Normal Flow:	<u>250 gpm</u>	<u> </u>
Minimum Flow:	<u>40 gpm</u>	<u> </u>
21. Maximum Temp:	<u>180°F</u>	<u> </u>
Minimum Temp:	<u>80°F</u>	<u> </u>
22. Maximum Press:	<u>320 psig</u>	<u> </u>
Minimum Press:	<u>-30" Hg</u>	<u> </u>
23. Min Fluid		
Conductivity:	<u>10 micromhos/cm</u>	<u> </u>
24. Vacuum		
Possibility:	<u>Full vacuum</u>	<u> </u>

ASSOCIATED INSTRUMENT

26. Tag Number:	<u>FIT/FQI-0621</u>	<u> </u>
27. Function:	<u>Indicate/Transmit/Totalize</u>	<u> </u>
28. Mounting:	<u>Surface</u>	<u> </u>
29. Enclosure Class:	<u>Mfg std</u>	<u> </u>
30. Length Signal		
Cable:	<u>100 feet</u>	<u> </u>
31. Type Span Adj:	<u>Digital DIP switches</u>	<u> </u>
32. Power Supply:	<u>115 V ac 60 Hz</u>	<u> </u>

ASSOCIATED INSTR - TRANSMITTER

33. Output:	<u>4-20 ma DC</u>	<u> </u>
-------------	-------------------	-----------------------------

MAGNETIC FLOWMETERS
(Based on ISA S20.23)

ASSOCIATED INSTR-DISPLAY

35. Scale Size:	<u>Mfg std</u>	
Range:	<u>40-400 gpm</u>	
38. Integrator:	<u>8 Digit, gals.</u>	

ASSOCIATED INSTR-CONTROLLER

45. Manufacturer:	<u>Flow Element</u>	<u>Remote Electronics</u>
	<u>Brooks Model 7400</u>	<u>Brooks Model 3560</u>
	<u>(7404C5B1F6AACA)</u>	<u>(356232A3C1)</u>
	<u>or approved substitutes.</u>	

NOTES: (1) Items 16, 25, 34, 36, 37, 39-44, and 46 and 47 are not required.
(2) Accuracy: $\pm 0.5\%$ of Full Scale flow range.

RECEIVER INSTRUMENTS
(Based on ISA S20.1a)

GENERAL

1. Tag Number: See Note 2 Service Various
2. Function: Record ☐ Indicate ☒ Control ☐ Blind ☐
Integ ☐ Deviation ☐ Other Alarm on high value
3. Case: Mfr Std ☒ Nom. Size 2" H x 4" W x 5" Deep
- Color: Mfr Std ☒ Other _____
4. Mounting: Flush ☒ Surface ☐ Rack ☐ Multi-Case ☐
Other _____
For multiple case, see Form Y-_____
5. Enclosure Class: Gen Purpose ☒ Weatherproof ☐ Explosion Proof ☐
Class _____
For use in intrinsically safe system ☐ Other _____
6. Power Supply: 117 V, 60 Hz ☒ Other: _____ V ac _____ V dc
9. Scales: Type Digital (AMPS) 3 1/2 digits
Range 1 1999 (MAX)

INPUTS

16. Signals: 4-20 mA ☒ 10-50 mA ☐ 21-103 kPa (3-15 psig) ☐
Other (Field selectable)
17. Number: 1 ☒ 2 ☐ 3 ☐ 4 ☐
18. Power for Xmtr: External ☒ This instrument ☐
Number of independent supplies _____
For transmitters, see Form Y-_____

RECEIVER INSTRUMENTS
(Based on ISA S20.1a)

ALARMS

19. Switches: Quantity 2 Form C Rating 1A @ 120 V ac
20. Function: Measured Variable X Deviation _
Contacts to actuate on measurement increasing.
Other Field selectable
21. Options: Filter-Rgltr _ Supply Gage _ Charts _
Internal Illumination _ Other _
22. Manufacturer/ Model: Rochester Instrument Systems model TM 3481 1-1 ECN-200
with TM 341 dual relay alarm card Precision
Digital model PD690 or approved substitute. ECN-200

NOTES:

- (1) Items 7, 8 and 10-15 are not required.
(2) Tag numbers: IISH-0621A
IISH 0622A.
(3) Accuracy: 0.25% Full Scale ± 1 count.

ECN-200
ECN-200

RECEIVER INSTRUMENTS
(Based on ISA S20.1a)

GENERAL

1. Tag Number: See Note 2 Service Various
2. Function: Record ☐ Indicate ☒ Control ☐ Blind ☐
Integ ☐ Deviation ☐ Other Alarm on high and high-value
3. Case: Mfr Std ☒ Nom Size 2" H x 4" W x 5" Deep
Color: Mfr Std ☒ Other _____
4. Mounting: Flush ☒ Surface ☐ Rack ☐ Multi-Case ☐
Other _____
For multiple case, see Form Y- _____
5. Enclosure Class: Gen Purpose ☒ Weatherproof ☐ Explosion Proof ☐
Class _____
For use in intrinsically safe system ☐ Other _____
6. Power Supply: 117 V, 60 Hz ☒ Other: _____ V ac _____ V dc
9. Scales: Type Digital (°F) 3 1/2 Digits
Range 1 1999 (MAX)

INPUTS

16. Signals: 4-20 mA ☐ 10-50 mA ☐ 21-103 kPa (3-15 psig) ☐
Other 100 ohm 3 wire RTD
17. Number: 1 ☒ 2 ☐ 3 ☐ 4 ☐

ALARMS

19. Switches: Quantity 2 Form C Rating 1 Amp @ 120 V ac
20. Function: Measured Variable ☒ Deviation ☐
Contacts to Actuate on measurement increase
Other Field selectable

22. Manufacturer/
Model:

Rochester Instrument Systems Model TM 3483 1-1
with TM 341 dual relay alarm card Precision
Digital model PD750 or approved substitutes.

ECN-128/200

ECN-200

RECEIVER INSTRUMENTS
(Based on ISA S20.1)

NOTES:

(1) Items 7, 8, 10-15, 18 and 21 are not required.

(2) Tag Numbers: ~~TISH/TISHH-0621~~
~~TISH/TISHH-0622~~
~~TISHH/TISHH-0629~~
~~TISH/TISHH-06210~~
~~TISH-0621~~
~~TISH-0621~~
~~TISH-0622A~~
~~TISH-0622B~~

ECN-200

ECN-200

(3) Accuracy: 0.25% Full Scale $\pm$ 1 count.

RECEIVER INSTRUMENTS
(Based on ISA S20.1)

GENERAL

1. Tag Number: ZI-0621 Service Winch Position _____

2. Function: Record ☐ Indicate ☒ Control ☐ Blind ☐
Integ ☐ Deviation ☐ Other Alarm Switches

3. Case: Mfr Std ☒ Nom Size 4" H x 2" W x 6" Deep

Color: Mfr Std ☒ Other _____

4. Mounting: Flush ☒ Surface ☐ Rack ☐ Multi-Case ☐
Other _____
For multiple case, see Form Y- _____

5. Enclosure Class: Gen Purpose ☒ Weatherproof ☐ Explosion Proof ☐
Class _____
For use in intrinsically safe system ☐ Other _____

6. Power Supply: 117 V, 60 Hz ☒ Other: _____ V ac _____ V dc

~~7. Chart:~~ _____ Strip _____ Roll _____ Fold _____ ECN-128
Circular _____ Time Marks _____
Range _____ Number _____

~~8. Chart Drive:~~ Speed _____ Power _____ ECN-128

9. Scales: Type Analog, Vertical
Range 1 0-300 inches

RECEIVER INSTRUMENTS
(Based on ISA S20.1)

INPUTS

16. Signals: 4-20 mA ☒ 10-50 mA _ 21-103 kPa (3-15 psig) _
Other _____
17. Number: 1 ☒ 2 _ 3 _ 4 _
18. Power for Xmtr: External ☒ This instrument _
Number of independent supplies _____
For transmitters, see Form Y-_____

ALARMS

19. Switches: Quantity 2 Form C Rating 5A, 120 V ac
20. Function: Measured Variable ☒ Deviation _
Contacts to _____ on measurement _____
Other Field Selectable, See Note 2
21. Options: Filter-Rgltr _ Supply Gage _ Charts _
Internal Illumination _ Other _____
22. Manufacturer
Model No.: LFE Inc. 371-K or approved substitutes


NOTES: (1) Items 7, 8, 10-15 and 21 are not required.

- (2) One alarm contact to actuate on increasing value (ZSH-0621A);
and another independent alarm contact to actuate on decreasing
value (ZSL-0621A).

- (3) Accuracy: $\pm 0.5\%$ of full scale span.

ECN-128

ECN-128



NOTES:

1. MATERIAL SHALL BE 1/16" THICK LAMINATED PLASTIC STOCK WITH WHITE SURFACE AND BLACK CORE.
2. EDGES OF NAMEPLATES SHALL BE BEVELED AS SHOWN AND SHALL BE SMOOTH AND WITHOUT BURRS. LETTERS SHALL BE SHARP AND CLEAR, SIMILAR TO THE STYLE SHOWN.
3. USE 4-40 x 3/8" LONG, BINDING HEAD, SELF-TAPPING MACHINE SCREWS OR PULL STEM RIVETS TO FASTEN PLATES TO PANELS. DRILL NO. 39 HOLES IN PANEL. CONTACT ADHESIVE SHALL NOT BE USED.

EQUIPMENT NAMEPLATE

Figure 1




Figure 2

Project No. W-320

Project Title Tank 241-C-106 Sluicing

Specification Section 13440

APPROVAL DATA LIST ("X" Indicates Required Data)

1	2	3	4	5								6		
EPM IDENTIFICATION	DESCRIPTION	REFERENCE DRAWING	SPECIFICATION PARAGRAPH	Dimensional Drawings	Equipment Weights	Specifications	Material Description	Performance Data	Circuit or Control Diagrams	Data Sheets	Illustrative Cuts	Installation Instructions	REMARKS	
PE-0621 PE-0622	Transducer Element		Y-0701	X	X	X				X	X	X		
PISL-0621 PISL-0622	Indicating Alarm/Signal Conditioner		Y-0702			X					X			
ANN-0621	Annunciator		Y-0703	X		X			X		X			
FE-0621	Flow Meter		Y-0704	X	X	X				X	X	X		
FIT/FQI-0621	Flow Indicator/Totalizer		Y-0704			X				X				
IISH-0621 IISH-0622	Motor Current Indicator		Y-0705			X					X			
TISH-0621 TISH-0622 TISH-0629 TISH-06210	Motor Temp. Indicator		Y-0706			X					X			
ZI-0621	Winch Position Indicator		Y-0707	X		X					X		ECN-128	
LDS-0621 LSH-0621 LSL-0621	Level/Leak Detection Switches	H-2-818573				X			X		X		ECN-128 ECN-128 ECN-128	

HNH-2536, Rev. 0
Page 93

ICF KH 1986.00 (03/89) KEF

Project No. W-320
 Project Title Tank 241-C-106 Sluicing
 Specification Section 13440

VENDOR INFORMATION LIST
 ("X" Indicates Required Data)

1	2	3	4	5	VENDOR INFORMATION (V/I)										
EPN IDENTIFICATION	DESCRIPTION	REFERENCE DRAWING	SPECIFICATION PARAGRAPH	Dimensional Drawings	Equipment Weights	Specifications	Certified Test	Circuit or Control Diagram	Installation	Operation	Maintenance	Spare Parts List	Data Sheets	Illustrative Cuts	
PE-0621 PE-0622	Transducer Element		Y-0701	X	X	X		X	X	X	X	X		X	ECN-166
P1SL-0621 P1SL-0622	Indicating Alarm/Signal Conditioner		Y-0702	X		X		X	X	X	X	X		X	ECN-166
ANN-0621	Annunciator		Y-0703	X		X		X	X	X	X	X		X	
FE-0621	Flow Meter		Y-0704	X	X	X		X	X	X	X	X		X	ECN-166
FIT/FRI-0621	Flow Indicator/Totalizer		Y-0704	X		X		X	X	X	X	X		X	
IISH-0621 IISH-0622	Motor Current Indicator		Y-0705	X		X		X	X	X	X	X		X	ECN-166
TISH-0621 TISH-0622 TISH-0629 TISH-06210	Motor Temp. Indicator		Y-0706	X		X		X	X	X	X	X		X	ECN-166
ZI-0621	Winch Position Indicator		Y-0707	X		X		X	X	X		X		X	ECN-166
	Terminal Block & Accessories	H-2-818574		X					X					X	
TBX-0621 TBX-0622	Enclosure	H-2-818574		X										X	ECN-128
IE-0621	Enclosure	H-2-818573		X										X	ECN-128
LDS-0621 LSH-0621 LSI-0621	Level/Leak Detection Switches	H-2-818573				X		X	X					X	ECN-128

ICF KH 1985.00 (03/85) REF 007
 Rev. 0
 Page 94

SECTION 15493

CHEMICAL PROCESS PIPING SYSTEMS

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society of Mechanical Engineers (ASME)

B16.5-1988 Pipe Flanges and Flanged Fittings

B16.9-1993 Factory-Made Wrought Steel Buttwelding Fittings

B31.3-1993 Chemical Plant and Petroleum Refinery Piping

NQA-1-1994 Quality Assurance Requirements for Nuclear Facility Applications

1.1.1.2 American Society for Nondestructive Testing (ASNT)

ASNT-TC-1A Recommended Practice (1988 Edition)

1.1.1.3 American Society for Testing and Materials (ASTM)

A 105-92 Forgings, Carbon Steel, for Piping Components

A 106-91 Seamless Carbon Steel Pipe for High Temperature Service

A 312-92a Seamless and Welded Austenitic Stainless Steel Pipes

A 580-95a Stainless Steel Wire ECN-662

A 403-91 Wrought Austenitic Stainless Steel Piping Fittings ECN-116

1.1.1.4 American Water Works Association (AWWA)

C213-91 Fusion Bonded Epoxy coating for the Interior and Exterior of Steel Water Pipelines

1.1.1.5 Manufacturers Standardization Society of the Valve and Fittings Industry (MSS)

SP-58, 1988 Pipe Hangers and Supports - Materials, Design and Manufacture

SP-69, 1991

HNF-2536, Rev. 0
Pipe Hangers and Supports - Selection Page 96
and Application

- 1.1.1.6 Steel Structures Painting Council (SSPC)
SP 3-82 Power Tool Cleaning
SP 6-85 Commercial Blast Cleaning
- 1.1.1.7 American National Standard Institute (ANSI)
ANSI/AWS D1.1-96 Structural Welding Code - Steel
- 1.2 SUBMITTALS
- 1.2.1 See Section 01300 for submittal procedures.
- 1.2.2 Approval Required
- 1.2.2.1 Certified material test reports (CMTRs): Before delivery, submit legible reports, certified by responsible manufacturer of materials used in fabrication of pipe and weld rod for pipe codes and services listed below. Reports shall present results of chemical analysis and physical tests specified in ASME and ASTM Codes and Standard Specifications for production lots and heats of materials. Material traceability shall be maintained through fabrication for materials requiring CMTRs. Submit separate reports for the following.
- a. Pipe Code M-9; Service, Supernate (SN) and Slurry (SL) lines
- b. Pipe Code M-26a; Service, Supernate (SN) and Slurry (SL) line encasements
- 1.2.2.2 Material traceability shall be maintained through fabrication for material requiring CMTRs.
- 1.2.3 Approval Not Required: None
- 1.3 QUALITY ASSURANCE
- 1.3.1 Safety Related Products: ~~Safety~~ Safety Significant products shall be procured from qualified suppliers. These suppliers shall have quality assurance programs meeting the ASME NQA-1 Basic Requirements 1, 2, 4 through 15, and 17.
- 1.3.2 Welding Qualifications:
- 1.3.2.1 Qualification of welding personnel and procedures: Personnel and procedures for welding pressure retaining components along with attachments hereto, and pipe supports, shall be qualified in accordance with ASME B31.3, Paragraph 328.2.
- 1.3.2.2 Qualification of Nondestructive Examination (NDE) Personnel:
- a. Visual weld examination shall be performed in accordance with ASME B31.3.

ECN-662

ECN-662

ECN-116
ECN-116

ECN-809

HNF-2536, Rev. 0
Page 98

b. Personnel performing other NDE shall be certified in accordance with Contractor's written practice, which shall meet the requirements of ASNT-TC-1A. Use Level II personnel to interpret test results.

- 1.3.3 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

<u>Document</u>	<u>Paragraph</u>
Welding Qualification	1.3.2
Welding Examination Documentation	3.2.1
Flushing/Mechanical Cleaning Verification	3.2.2.4
Leak/Pressure Test Certification	3.2.3.1b

1.4 DELIVERY, STORAGE, AND HANDLING

- 1.4.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

- 2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

- 2.2.1 Piping: See the Pipe Codes in this Section, and details on the Drawings.

- 2.2.2 Protective coating for piping in contact with earth.

- 2.2.2.1 Carbon steel piping: Field and factory applied exterior protective coating; AWWA C213, fusion bonded epoxy coating of 14 mils thickness, Scotchkote 206N or approved substitute.

- 2.2.3 Painting: See Section 09900.

- 2.2.4 Nonshrink Grout: See Section 03300.

- 2.2.5 Pipe Supports: Pipe supports shall be as shown on the Drawings. Standard components selected in accordance with MSS SP-69, that satisfy the criteria of MSS SP-58.

- 2.2.6 *Jumpers: Jumper fabrication shall be as shown on the Drawings and in accordance with Appendix A of this Section.*

ECN-662
ECN-662

PART 3 - EXECUTION

3.1 INSTALLATION

3.1.1 General

- 3.1.1.1 Fabricate and install pipe in accordance with ASME B31.3 (for normal service), the Drawings and this Section. *Pipe Codes M-9 and M-26a piping systems shall be fabricated using welded connections unless otherwise shown on the drawings.*

ECN-335
ECN-335

3.1.1.2 Cut pipe using methods which result in clean, straight cuts.

- 3.1.1.3 Ream pipe to nominal inside diameter after cutting. Remove burrs from Page 101 threads before assembly.
- 3.1.1.4 Tools marked for stainless steel shall be used on stainless steel only.
- 3.1.1.5 Bend pipe in accordance with ASME B31.3, and meet tolerances given in ASME B31.3. Use methods and equipment which produce bends substantially free of wrinkles, bulges, or kinks. When wall thickness, diameter, and bend radius indicate possibility of wall collapse during bending, fill pipe with clean silica sand or fusible material similar to Cerro-bend, manufactured by Cerro Corporation.
- a. Application of heat to facilitate a pipe bend shall be brought to the attention of the Construction Engineer for direction and disposition prior to the application of heat.
- b. Cold springing pipe permitted only if specified on the Drawings.
- 3.1.1.6 Carbon steel embedded in concrete shall be bare.
- 3.1.1.7 Keep piping systems clean. Piping systems shall be inspected before, during and after installation. Once fabrication has started, plug or cap ends of piping when installation is not in progress. Cap or plug openings in fabricated pipe spool assemblies until installation in the piping system. Leave ends of spare lines capped or blind flanged when installation has been completed.
- 3.1.1.8 High points shall not be provided on SN and SL piping.
- 3.1.1.9 Pipe supports: Install as shown on the Drawings, in accordance with manufacturer's instructions, and applicable recommended procedures of MSS SP-89.
- 3.1.1.10 Lead shall not be allowed for use in remotely replaceable components for counterweighting.
- 3.1.2 Underground Piping
- 3.1.2.1 Trenches: Excavate, backfill, and compact in accordance with Section 02225.
- 3.1.2.2 Place piping supports on undisturbed soil, or backfill placed and compacted in accordance with Sections 02200 and 02225.
- 3.1.2.3 Survey piping systems for elevation and location before final tie-in welds to pits, risers, or fixed items. Complete placement of supports and meet Specification and Drawing requirements before survey. Elevation and location shall be in accordance with the Drawings. After final tie-ins survey piping system again for final acceptance.
- 3.1.3 Welding
- 3.1.3.1 Weld piping, attachments to pressure retaining components, and pipe supports in accordance with ASME B31.3 and Drawings.

- 3.1.3.2 Protect outdoor welding operation from rain and wind by using barriers to protect welder and weld joint.
- 3.1.3.3 Complete piping welds before tie-in welds to pits, risers, or fixed items.
- 3.1.3.4 Remove backing strips if used.
- 3.1.3.5 *Gas Tungsten Arc Welding (GTAW) process shall be used for root pass welds of carbon steel encasement pipes where stainless steel inner pipes cannot be protected from weld splatter.* ECN-113
ECN-113
- 3.1.4 Weld Identification
- 3.1.4.1 Prepare weld maps using Project Drawings or sketches, which show relative positions of pressure containing welds and attachment welds to pressure retaining components.
- 3.1.4.2 Assign and record weld numbers on weld maps as welds are made.
- 3.1.4.3 Place the welder identification symbol and weld number adjacent to welds upon completion. Place the identification symbol approximately every 3 feet on long seams or large weldments, using one of the marking methods specified in Section 01610.
- 3.1.4.4 Do not reuse weld numbers. If a weld is completely replaced, assign a new number.
- 3.1.4.5 Show heat/lot numbers on weld maps for materials requiring Certified Material Test Reports.
- 3.1.5 Perform NDE, flushing and leak/pressure testing specified in 3.2 before coating application.
- 3.1.6 Exterior Protective Coating
- 3.1.6.1 Protect carbon steel pipe and fittings exposed to earth backfill with specified coating.
- a. Clean carbon steel surfaces to white metal by sandblasting in accordance with SSPC SP 6. Where blasting is impracticable, clean by power wire brushing in accordance with SSPC SP 3.
- b. Heat and apply specified tape in accordance with AWWA C213.
- 3.1.6.2 After installation, examine carbon steel pipe having factory applied exterior protective coating, and joints and short lengths of pipe having field applied exterior protective coating materials.
- a. Use electrical holiday detector in accordance with AWWA C213.
- b. Repair damage to coating in accordance with AWWA C213.

3.2 FIELD QUALITY CONTROL

3.2.1 Nondestructive Examination (NDE) of welds shall be performed to the extent defined in ASME B31.3, Paragraph 341.4.

3.2.1.1 Perform NDE for each pipe code listed in the schedule in 3.3.

3.2.1.2 Visual examination: Perform in accordance with ASME B31.3, Paragraph 344.2. Acceptance criteria shall be in accordance with ASME B31.3, Table 341.3.2A.

3.2.1.3 Radiographic examination (RT): Perform in accordance with ASME B31.3, Paragraph 344.5. Acceptance criteria shall be in accordance with ASME B31.3, Table 341.3.2A.

a. Identify radiographic film with weld identification number and project or work order number assigned to work covered by this Section.

b. Prepare radiographic examination reports as follows.

1) List each radiographic exposure location (0-1, 1-2, ...) individually on radiographic examination report.

2) Indicate location acceptability or rejectability and note discontinuities whether rejectable or not.

3) When report includes radiographs of welds which have been repaired, indicate which welds are repair welds and how many times each weld has been repaired.

c. If additional welding is performed on weld area which has already been examined radiographically, this area is repair area. Identify subsequent radiographs by "R-1, R-2," etc.

3.2.1.4 Perform in-process examination in accordance with ASME B31.3, Paragraph 344.7.

3.2.1.5 Perform random visual examination of piping support welds in accordance with ASME B31.3; Paragraph 344.2.

3.2.1.6 NDE documentation:

a. Document examination of pressure containment welds and welds to pressure containing components for piping systems on "NDE/Weld Record," Form KEH-0433. See Form KEH-0433 for instructions for recording weld maps, weld numbers, welder identification, welding procedure numbers, weld filler material, visual examinations, nondestructive examinations, and for noting satisfactory completion of leak/pressure testing.

b. Required NDE shall be completed and documented before starting leak/pressure testing.

c. NDE/Weld Record information and weld maps specified in 3.1.4 may be incorporated on a single format or traveler for a specific work package.

d. Document examination of pipe supports by recording on sketches or the NDE/Weld Record form. Page 104

3.2.1.7 *Liquid Penetrant (dye penetrant) Examination (PT): Perform in accordance with ASME B31.3, paragraph 344.4. Acceptance criteria shall conform to ASME B31.3, paragraph 341.3.2.* ECN-347
ECN-347

3.2.2 Cleaning and Flushing

3.2.2.1 After NDE is complete and before leak/pressure testing the system, or before connecting the system into existing systems, clean piping internal surfaces mechanically.

3.2.2.2 Mechanical cleaning: Remove loose dirt, scale, and debris by brushing, wiping, high pressure water jetting, or other mechanical method.

a. When high pressure water jetting or other mechanical cleaning method utilizing water is used, and leak/pressure testing will not be performed immediately after cleaning, dry piping systems by blowing dry oil-free air or nitrogen through lines.

b. Dry until the relative humidity of discharge air is equal to that of inlet air. Use drain taps at low points of piping system to ensure complete drainage and drying. Cap lines or reconnect to system to maintain cleanliness.

3.2.2.3 Water flushing

a. Remove strainer screens before flushing, except those protecting control equipment. Clean screens protecting control equipment before flushing, if necessary, and after flushing is complete. Remove steam traps from line before flushing.

b. Flush piping with water for 1 minute minimum, and until effluent is clean and contains no visible particulate matter. Flushing pressure shall not exceed maximum operating pressure specified in pipe codes. Flushing water supply shall have sufficient capacity to produce a flow velocity of 4 to 6 ft/s in largest pipe size, with pipe full. Provide flow measurement in flushing water supply line to be used as basis for verification of flow velocities in piping system by the Construction Engineer.

c. When leak/pressure testing will not be performed immediately after flushing, dry tabulated piping systems by blowing dry, oil-free air or nitrogen through lines. Dry until the relative humidity of discharge air is equal to that of inlet air. Use drain taps at low points of piping systems to ensure complete drainage and drying. Cap lines or reconnect to the systems.

3.2.2.4 *Pneumatic flushing: For encasement (ENC) lines only.* ECN-116

a. *Isolate instruments by valving, plugging or disconnecting.* ECN-116

b. Blow lines clean with dry, oil-free air or nitrogen at 20 to 30 lb/in² gage, until discharge air has no visible particulate matter or for 5 minutes minimum. If pipe code maximum operating pressures are lower, use those pressures.

c. If leak/pressure testing is not performed immediately after flushing, cap lines or reconnect to system to maintain cleanliness.

ECN-116

3.2.2.45 Provide documented evidence that flushing or mechanical cleaning has been accomplished as specified in this Section.

ECN-116

3.2.2.6 Pneumatic flushing: For Nitrogen (N₂)

ECN-441

a. Isolate instruments by valving, plugging, or disconnection.

b. Blow lines clean with dry, oil-free air or nitrogen at 20 to 30 lb/in² gage, until discharge air has no visible particulate matter, or for 5 minutes minimum. If Pipe Code maximum operating pressures are lower, use those pressures.

c. If leak/pressure testing is not performed immediately after flushing, cap lines or reconnect to system to maintain cleanliness.

ECN-441

3.2.3 Leak/Pressure Testing

3.2.3.1 General

a. After completion of flushing, perform leak/pressure testing of pipe in accordance with ASME B31.3 and this Section. Use calibrated gages with ranges 1-1/2 to 2 4 times the test pressure. ECN-201

b. Document testing of each piping system on "Leak/Pressure Test Certification" Form KEH-1757. Use separate forms to describe and record each piping system. Under "Description" describe piping system in enough detail for correlation to weld maps, shop fabrication drawings, or Project Drawings as applicable. For systems tested segmentally, indicate continuity in "Description" to ensure that entire systems have been tested.

c. Pipe joints, welds and other potential leak sources to be tested shall be visible and accessible during tests.

d. Install one temporary relief valve during testing. Relief valve shall have a discharge capacity of 125% of capacity of the pressurizing device, and be set to operate at 1-1/3 maximum of the test pressure for hydrostatic testing and not higher than test pressure plus the lesser of 50 lb/in² or 10% of the test pressure for pneumatic testing. Tag each relief valve used to show serial number, inspector, date, and pressure setting.

e. Install necessary restraining devices, before applying test pressure, to prevent distortion or displacement of piping.

f. Isolate instruments and other items which could be damaged by test pressures.

g. Continuously maintain test pressure for 10 minutes minimum. Examine joints, welds, and connections. Piping system, exclusive of possible localized instances at pump or valve packing, shall show no visual evidence of weeping or leaking.

h. Visually examine piping joints, welds and other potential leak sources, including welds which attach wear plates, anchors, etc to piping systems, during testing.

i. Complete testing of piping before field application of insulation or protective coating. Pipe with factory applied protective coating shall be considered as having been tested before protective coating application.

3.2.3.2 Hydrostatic pressure testing:

a. Perform in accordance with ASME B31.3, Paragraph 345.4.

b. Test piping systems with removable jumper assemblies without jumpers in place. Test jumper assemblies as shown on the Drawings.

c. Purge air from piping systems during filling, before applying pressure.

d. Coat welded piping joints and other potential leak sources, including welds attaching wear plates, anchors, etc, to piping systems, with a mixture of powdered blue chalk and water or isopropyl alcohol. Allow to dry before filling piping with water and inspecting for leaks.

e. Remove water from tabulated piping systems after testing and dry by blowing dry, oil-free air or nitrogen through lines. Dry until the relative humidity of discharge air is equal to that of inlet air. Use drain taps at low points of piping systems to ensure complete drainage and drying.

3.2.3.3 *Pneumatic Pressure Testing: For Encasement (ENC) lines and Nitrogen (N₂) lines only.*

ECN-116/441

ECN-116/441

a. Perform in accordance with ASME B31.3, paragraph 345.5.

ECN-116

b. Perform test with dry, oil free air or nitrogen.

ECN-116

3.2.3.34 *Final Connections:*

ECN-347/454

Final connections, as defined in this section, shall be exempt from the requirements of Leak/Pressure Testing and shall be In-Process Examined. Welds shall have their first and last pass Liquid Penetrant Examined. See paragraphs 3.2.1.4 and 3.2.1.7 respectively. Connection welds are defined as follows:

ECN-347

ECN-347

1. 4" SL-100-M9, and 6" ENC-M26a, at N41611.25' and W47872.29'.

ECN-748/

347

3.3 SCHEDULES

3.3.1 Schedule of Pipe Weld NDE/Testing

NDE/NDT Method	Pipe Codes						
	M-9	M-26a					
Visual							
Fitup							
Root Pass							
Cover Pass	C,D	C,D					
Liquid Penetrant							
Root Pass							
Cover Pass							
Magnetic Particle							
Root Pass							
Cover Pass							
Radiographic							
Completed Weld	E,B						
Leak/Pressure							
Completed Weld	A	A					
Other							

Legend:

- A. Requires witnessing and acceptance by Level II Inspector or higher.
- B. Requires acceptance of radiographs and documentation by Level II Inspector or higher.
- C. Random visual examination for 5% of circumferential welds, full penetration welds on branch connections and attachment welds to pipe greater than 1/16 inch.
- D. 100% visual examination of longitudinal welds.
- E. Random radiography for 5% of all primary circumferential welds. In-process examination may be performed in lieu of radiography.

PIPE CODE M-9 (Safety Class 2 Safety Significant)			
Service	Max Operating Pressure lb/in ² gage	Test Pressure lb/in ² gage	Max Operating Temp °F
Supernate (SN) Slurry (SL)	320 Psig 320 Psig	480 Psig 480 Psig	180°F 180°F
Sizes	All		
Pipe	Stainless Steel, ASTM A 312, Grade TP 304L, seamless.		
Wall Thickness	Schedule 40S		
Fittings	Stainless steel, ASTM A 403, class WPS 304L, butt welding in accordance with ASME B 16.9, wall thickness to match pipe.		

ECN-116

ECN-116

PIPE CODE M-26a (Safety Class 2-3 General Service)			
Service	Max Operating Pressure lb/in ² gage	Test Pressure lb/in ² gage	Max Operating Temp °F
Slurry Line Encasement (ENC)	320	480 352	180°F
Supernate Line Encasement (ENC)	320	480 352	180°F
Sizes	All		
Pipe	Carbon Steel, ASTM A106, Grade B.		
Wall Thickness	Schedule 40.		
Fittings	Wrought carbon steel, ASTM A234, grade WPB, butt welding in accordance with ANSI B16.9 (schedule to match pipe).		

ECN-116

ECN-116

ECN-205

ECN-205

ECN-294/809

PIPE CODE M-33b (Safety Class 3 General Service)			
Service	Max Operating Pressure (PSIG)	Test Pressure (PSIG)	Max Operating Temp °F
Nitrogen Pump Seal Purge (N ₂)	450	495	120
Sizes	1/2" and smaller		Over 1/2"
Tubing	ASTM A269, Grade TP 304, 304L or 316 annealed, seamless, stainless steel. Buried tubing: PVC (or polyethylene) coated 0.032" thick. Parker fluid connectors #1 SST or approved equal.		
Wall Thickness	0.035"		0.049"
Fittings (Above Ground)	Type 316 stainless steel, flareless type; Crawford fittings "Swagelok", or Parker "CPI."		
Fittings (Buried)	Type 316 stainless steel, automatic tube weld type; Crawford fittings, "Cajon", or Parker fluid connectors.		

ECN-294

END OF SECTION

ECN-662

ECN-662

APPENDIX A

JUMPER FABRICATION

TABLE OF CONTENTS

ECN-662

Section	Title	Page
	Table of Contents	2
1	SCOPE	3
2	APPLICABLE DOCUMENTS	3
3	REQUIREMENTS	3
	3.1 Conflicts	3
	3.2 Materials	3
	3.3 Tolerances, Finishes, Positioning, and Bends	4
	3.4 Special Engineered Equipment	5
	3.5 Electrical Requirements	5
	3.6 Welding	6
	3.7 Lubricants	6
	3.8 Threaded Joints	6
	3.9 Balance Requirements	7
	3.10 Testing	8
	3.11 Cleaning and Painting	8
4	QUALITY ASSURANCE PROVISIONS	10
5	PREPARATION FOR DELIVERY AND STORAGE	11
6	NOTES	11

ECN-662

1 SCOPE

- 1.1 *Scope: This Specification establishes the requirements for fabrication, assembly, painting, identification and testing of process pipe and jumpers for use in 241-AY-02A Pump Pit and 241-AY-02E Sluice Pit for Project W-320. Definitions are in Section 6.*

2 APPLICABLE DOCUMENTS

Applicability: The following documents of the MOST RECENT issue form part of this Specification to the extent specified herein. In the event of a conflict between the documents cited and the contents of this Specification, Engineering shall be notified.

Industry Codes and Standards

American Society of Mechanical Engineers (ASME)

B31.3-1993 w/addenda a, b & c Chemical Plant and Petroleum
Refinery Piping

American National Standards Institute (ANSI)

ANSI/AWS D1.1-96 Structural Welding Code - Steel

American Society for Testing and Materials (ASTM)

A 580-95a Stainless Steel Wire

National Fire Protection Association (NFPA)

NFPA-70 National Electrical Code

3 REQUIREMENTS

- 3.1 *Conflicts: The design drawings and this Specification are the primary documents on which shop fabrication of jumpers depends. In the event this Specification conflicts with the design drawings, the drawings shall take precedence.*

- 3.2 *Materials: Materials, or engineering approved equals, shall be as specified on the jumper drawings. Material certification requirements are imposed on the jumper drawings and/or procurement documents. The following is a list of materials used in this Specification. These materials are not specified on the jumper drawings.*

Description

Moly Disulfide (lubricant)

Blue Goop (lubricant)

ECN-662

Nickel Antiseize thread Sealer & Lubricant - Nuclear Grade

Teflon Tape (sealer)

Teflon Paste; Federal Process Co. "JC-30"

Glyptal Red Enamel; Product No. 1201

Amerlock 400 Steel Primer

Amerlock 400 or 351 Base Coating

Amerlock 351 Intermediate and Finish Coating

Statico Anti-Static Spray

3.3 Tolerances, Finishes, Positioning, and Bends

3.3.1 Tolerances

3.3.1.1 "Critical dimensions" are those which locate connectors and nozzles to a close tolerance to ensure proper jumper fit. Unless otherwise specified on the jumper drawing, critical dimensions shall be $\pm 1/16$ inch tolerance.

3.3.1.2 The tolerances for fabrication of individual parts (parts dimensioned in the parts list or detailed individually in the field of drawing) except gussets shall be as follows unless otherwise specified.

Fractions $\pm 1/8$

Angles ± 2 degrees

3.3.1.3 The tolerance for the cutting of structural shapes (dunnage) and gussets shall be as follows unless otherwise specified.

Fractions $\pm \frac{1}{4}$

Angles ± 5 degrees

3.3.1.4 Quality Assurance verification of dimensions of items listed in Paragraphs 3.3.1.2 and 3.3.1.3 are not required unless otherwise specified.

3.3.2 Finishes

3.3.2.1 Remove burrs and break all sharp edges.

3.3.3 Positioning

3.3.3.1 Jumper components and dunnage envelope shall be located within $\pm \frac{1}{2}$ inch of the nominal design jumper dimensions unless otherwise specified on jumper drawing.

3.3.3.2 The sharp edge surfaces of dunnage, kickplates etc., shall have $1/32$ inch minimum chamfer.


3.3.3.2 Angles, unless toleranced otherwise, which locate parts less than 3 feet apart, shall have a tolerance of ± 2 degrees. Angles locating parts more than 3 feet apart shall have a ± 1 degree tolerance. ECN-662

3.3.4 Bends

- 3.3.4.1 Rigid pipe bends shall have a minimum radius of 5 times their diameters (nominal size) and meet the requirements of ASME B31.3, Paragraph 332, "Bending and Forming."
- 3.3.4.2 Tubing bends shall have a minimum radius of three times their diameter.
- 3.3.4.3 Electrical conduits shall have a minimum radius in accordance with Article 346-10 of the NEC.

3.4 Special Engineered Equipment

- 3.4.1 Equipment which requires calibration such as control valves, limit switches, gauges or probes shall be tested, adjusted, calibrated and certified prior to installation into a jumper. Fabrication Services shall be responsible for installation and control of this equipment and shall not alter or adjust calibration. Quality Control shall verify that the equipment is in satisfactory condition and calibration is current prior to actual installation and to assure items were not damaged during fabrication, shipment or storage.
- 3.4.2 Structural and/or dunnage member may be coped to a maximum depth of 3/8 inch, where necessary, to avoid interferences with valve actuation and fit-up. Structural and/or dunnage members requiring coping of more than 3/8 inch shall require engineering approval.
- 3.4.3 Pipe supports utilizing pipe sleeves may require the sleeve to be split for ease of fabrication. In the case of splitting the pipe sleeve, the following weld shall be used for fabrication:



- 3.4.4 Actuators of pneumatically operated ball valve (POV) shall be rotated for proper orientation as shown on the drawing.

3.5 Electrical Requirements

- 3.5.1 Caution shall be used during the installation of cable or wire to avoid scuffing or cutting of insulation.
- 3.5.2 Substitution of cable or wire shall have prior engineering approval.


- 3.5.3 Electrical wiring shall be installed in accordance with the electrical diagram provided on the Drawings.
- 3.5.4 Threaded connections on electrical components shall be assembled and then sealed against moisture penetration using a nuclear grade sealer and lubricant.
- 3.5.5 All materials used shall be compliant with Standing Order 97-01 for applicable Ignition Control Set requirements specified. Questionable materials shall be approved by the Flammable Gas Equipment Advisory Board (FGEAB).
- 3.6 Welding
- 3.6.1 Weld Categories: Piping containment welds, attachments to containment piping, lifting bails, and their attachment welds require individual weld documentation. Carbon and stainless steel bail attachment welds shall be MT/PT examined, as applicable, on their final pass. Carbon steel and stainless steel support structure welds and connector block rotation stops (rattle bars) welds do not require individual weld documentation.
- Steel support dunnage members shall be welded and inspected per AWS D1.1 (cyclically loaded).
- 3.6.2 Welding and inspection of carbon steel and stainless components of all process jumpers shall conform to the requirements of ANSI B31.3. Containment boundary welds shall be VT examined on the first and final passes. In-Process Examination per ASME B31.3 may be substituted for any or all other examination requirements. All other welds shall be VT final pass.
- 3.7 Lubricants
- See Paragraph 3.2.
- 3.8 Threaded Joints
- 3.8.1 Prior to final pressure testing, threaded pipe joints shall be lubricated, see Paragraph 3.2 for lubricants.
- 3.8.2 Connector tie bolts and operating screw threads shall be lubricated, see Paragraph 3.2 for lubricants.
- 3.8.3 Connector tie bolts shall be safety wired in pairs using the double-twist method. Wire shall conform to ASTM A 580, any 300 series stainless steel, condition 'A' wire. Wire size shall be a minimum of 0.032 inch and a maximum of 0.048 inch.
- 3.8.4 Stainless steel flanges shall be bolted using stainless steel stud bolts, double nutting, with 4 nuts per stud bolt (preferred) or 2 nuts and 2 spring lock washers per stud bolt. Stud bolt length may vary depending on flange type and stud bolt locking methods used. Carbon steel flanges shall use carbon steel stud bolts and nuts.

ECN-662

3.9 Balance Requirements

3.9.1 Balancing is performed to locate the point at which to attach a bail for remote handling of jumpers.

3.9.2 The sketch below illustrates the general rule for balancing jumpers having one horizontal and one vertical connector and no dip tubes or entry stubs:



3.9.3 On jumpers where either horizontal or vertical legs exceed 5 feet:

Distance "X" or "Y" = 2 inches maximum for longest leg

3.9.4 On shorter jumpers where neither leg exceeds 5 feet:

Angle "a" or "b" 2 degrees $\pm$ 1 degree

If above dimensions for "X" and "Y" and angles "a" and "b" are exceeded, Design Engineer shall be notified.

3.9.5 The following jumpers shall be balanced so that all connectors or flanges mate at the same time ("X" and "Y" above = zero $\pm$ $\frac{1}{2}$ inch)

- Jumpers having 2 or more horizontal connectors
- Jumpers having 2 or more vertical connectors
- Jumper having trunnions as primary position devices.

3.9.6 Jumpers which do not fit into any of the definitions above shall be balanced by instructions on the engineering drawing.

3.10 Testing

3.10.1 Hydrostatic Testing

- 3.10.1.1 The completed process jumper assembly shall be hydro tested in accordance with ASME B31.3. Hydro test pressure shall be as noted on the drawing. Special equipment/components like pressure transducers that cannot withstand the Hydro test pressure shall be isolated or special engineering instruction shall be provided. The pressure shall be maintained throughout the full test period for a minimum of 10 minutes. No leakage is permitted.
- 3.10.1.2 Jumpers with two-way valves shall be hydro tested with the valve in both the open and closed position. In the closed position both legs shall be independently tested. Jumpers with three-way valves shall be hydro tested with the valve in all operational positions such that the entire jumper is subjected to the pressure test. The three-way valve shall be positioned such that each leg to be isolated by a valve setting shall be independently tested.
- 3.10.1.3 When it is necessary to open or close a POV during testing or flushing of a jumper, the POV shall be operated by using the manual over-ride on the actuator.

3.10.2 Electrical testing.

- 3.10.2.1 After pulling wire or cable through conduit, but before connecting to instrument or electrical devices, test wire installation in accordance with Article 110-7 of the NEC using a megohm meter at 500 volts. An exception to this requirement shall be wire which is factory affixed to an over current protective device and/or an instrument device.
- 3.10.2.1 Instrumentation located in jumpers shall be tested for: (1) resistance, (2) continuity, (3) open circuits, and (4) short circuits after final assembly, using a multi-meter or equal. High voltage on high current test devices shall not be used.

3.11 Cleaning and Painting

- 3.11.1 After testing is completed, the outside of the jumper shall be cleaned in preparation for painting. Removal all carpenter's chalk, grease, rust, etc.
- 3.11.2 Clean and air dry internal components of process jumper.
- 3.11.3 Stainless steel components do not require painting except as needed for identification or for targeting.

- 3.11.4 Carbon steel dunnage, and components shall be painted with Amerlock 400 and 351, or approved equal, applied in accordance with the manufacturer's specifications. The coating schedule shall be as follows:

<u>Coat</u>	<u>Color</u>	<u>Minimum Dry Film Thickness</u>
Prime:	May be applied in single 7.0 mil coat if base coat is self priming	3.0 mils
Base:	May be applied in single 7.0 mil coat if base coat is self priming	4.0 mils
Intermediate:	May be applied in single 8.0 mil coat medium gray	4.0 mils
Finish:	May be applied in single 8.0 mil coat medium gray	4.0 mils

- 3.11.4.1 Carbon steel components of connector assemblies shall not be painted except for those items identified in Section 3.11.6.1 which are painted yellow for targeting (this painting is to assist the crane operator during jumper installation).

- 3.11.5 It is not mandatory to coat inaccessible areas. Some surfaces/ areas of structural shapes may fall into this category. All surfaces shall be drainable when jumper is installed.

- 3.11.6 Special Marking for Targeting

- 3.11.6.1 Parts listed below shall be coated with Amerlock 400 and 351, or approved equal, in the areas specified. The coating shall be applied in accordance with the manufacturer's specifications and to the same schedule as above, para 3.11.4. Final color shall be yellow.

Bails	Top 8 inches
Kickplates	Top face (not nozzle)
Connector operating screw nuts	Top of operating screw only (not threads)
Funnel Guides	Inside Surface Only
Trunnions	All Surfaces

- 3.11.6.2 Remote blank connector assemblies shall be painted red enamel except for operating screw nut.

- 3.11.7 Identification information shall be stenciled on rigid jumpers with the same type of paint applied to the jumper. Letters and numbers shall be $\frac{1}{2}$ to 1-3/4 inch high block type, black on yellow

HNF-2536, Rev. 0
Page 120

background. Combination rigid and flexible jumpers shall be identified per the rigid jumper requirements only. Identification information should be readable from above if possible. Process flexible jumpers shall have a 12" wide yellow bend painted on the braid adjacent to each end.

Information shall include drawing number, drawing revision number, and the location number, which reflects the use-location of the assembly.

The preferred arrangement of the identification information is shown below:

<u>Location No.</u>	<u>Drawing No.</u>	<u>Rev. No.</u>
xx(xx-xx)x	H-2-xxxxx	x

An alternate arrangement may have the location number above the drawing number, eg,

Location number: xx(xx-xx)x
Drawing and revision number: H-2-xxxxx x

NOTE: Location Identification numbers are taken from the drawing title block and indicates the jumper use location.

- 3.11.8 On jumpers, stamp the project Number (Project W-320) with 1/8"-1/4" metal stamps on base of bail or an easily identified area of the dunnage (nearby). If painted, this stamping shall be readable after painting. If jumper has more than one bail stamp one bail only.

4 QUALITY ASSURANCE PROVISIONS

- 4.1 Welding inspection shall be as specified in Section 3.6 of this specification.
- 4.2 Jig inspection shall determine if the critical dimensions for the jumper have been met per the drawing and if the jumper, as designed, can be handled properly. The suggested methods of inspection are:
- 4.2.1 Before fabrication, verify jig settings to determine if critical jumper dimensions are correct.
- 4.2.2 After fabrication, loosen one connector to determine that the jumper "kickoff" is functioning.
- 4.2.3 Remove jumper from jig and determine if jumper can be easily reattached to jig.
- The jig setting shall be inspected and approved by Quality Control (QC).
- 4.3 Hydro test performed, as required by Paragraph 3.10.1, shall be witnessed and approved by QC.
- 4.4 Electrical testing as required by paragraph 3.10.2 shall be witnessed and approved by QC.

5 PREPARATION FOR DELIVERY AND STORAGE

- 5.1 *After final inspection and acceptance by QC of shop fabrication of jumper, it shall be protected/packaged for outside storage. The jumper connectors shall be closed with a plastic plug and wrapped with a double layer of reinforced polyethylene sheeting. Instruments and valves and valve activities shall also be wrapped with a double layer of reinforced polyethylene sheeting. Poly sheeting shall be used with 10 gauge minimum soft aluminum wire.*
- 5.2 *Tapes are prohibited for use when direct contact is made with stainless steel and nonferrous alloys.*
- 5.3 *All adhesive-backed tapes are prohibited form contact with connector of nozzle mating parts.*
- 3.5.6 *After assembly and prior to shipment all exposed plastic/polymer surfaces to include electrical wiring and hoses shall be coated with an anti-static spray.*

6 NOTES

- 6.1 *Jumpers are remotely removable sections of piping. Jumpers are installed in valve pits or in pump pits. They serve to connect permanent wall connections and removable components in the pump pit or between adjacent components or between permanent wall connections. Jumpers are designed to permit remote handling by means of lifting bails. Sealed connections are made by using a remotely operated impact wrench.*

END OF APPENDIX

ECN-662

SECTION 15507

CONTAMINATED AIR HVAC SYSTEMS

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 Air Movement and Control Association (AMCA)

99-1986 Standards Handbook

1.1.1.2 American National Standards Institute (ANSI)

A13.1-1981 Scheme for the Identification of Piping Systems

1.1.1.3 American Society of Mechanical Engineers (ASME)

B16.9-1993 Factory-Made Wrought Steel Buttwelding Fittings

B31.3-1993 Chemical Plant and Petroleum Refinery Piping

1.1.1.4 Air-Conditioning and Refrigeration Institute (AIR)

AIR 590-1986 Reciprocating Water-Chiller Packages

1.1.1.5 American Society for Nondestructive Testing (ASNT)

SNT-TC-1A Recommended Practice (December 1988)

1.1.1.6 American Society for Testing and Materials (ASTM)

A 53-93a Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless

A 106-94 Seamless Carbon Steel Pipe for High Temperature Service

A 234-92a Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and Elevated Temperatures

1.1.1.7 American Water Works Association (AWWA)

C209-90 Cold-Applied Tape Coatings for Exterior of Special Sections, Connections, and Fittings for Steel Water Pipelines

1.1.1.8 Federal Specifications (FS)

TT-S-00230C,
AMD 2Sealing Compound: Elastomeric Type,
Single Component (For Caulking, Sealing
and Glazing In Buildings and Other
Structures)

TT-E-489H

Enamel, Alkyd, Gloss, Low VOC Content

1.1.1.9 Federal Standards (FED STD)

FED-STD-595B

Colors Used in Government Procurement

1.1.1.10 Manufacturers Standardization Society of the Valve and Fitting Industry (MSS)

SP-89, 1991

Pipe Hangers and Supports - Fabrication
and Installation Practices

1.1.1.11 National Electrical Manufacturers Association (NEMA)

MG 1-1993

Motors and Generators

1.1.1.12 Steel Structures Painting Council (SSPC)

SP 3-82

Power Tool Cleaning

SP 6-85

Commercial Blast Cleaning

1.1.1.13 Underwriters Laboratories (UL)

Electrical Construction and
Utilization Equipment
Directory

1994

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required

1.2.2.1 Approval data: Before delivery, submit information listed in the
Approval Data List in this Section.

1.2.3 Approval Not Required

1.2.3.1 Vendor information: Before installation, submit information listed in
the Vendor Information List in this Section.

1.3 SYSTEM DESCRIPTION

1.3.1 System is a chill water system with carbon steel piping. Chill water
system includes a chiller unit, piping and a fan coil unit. The fan
coil unit will be installed in a contaminated sluice pit.

1.4 QUALITY ASSURANCE

1.4.1 Welding Qualifications

1.4.1.1 Qualification of welding and procedures: Personnel and procedures for welding pressure retaining components along with attachments hereto, and pipe supports, shall be qualified in accordance with ASME B31.3, Paragraph 328.2.

1.4.1.2 Qualification of Nondestructive Examination (NDE) personnel:

a. Visual weld examination shall be performed in accordance with ASME B31.3.

b. Personnel performing other NDE shall be certified in accordance with Contractor's written practice, which shall meet the requirements of ASNT-TC-1A. Use Level II personnel to interpret results.

1.4.2 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control (Buyer) in accordance with Section 01720.

<u>Document</u>	<u>Paragraph</u>
Welding Qualification	1.4.2
Welding Examination Documentation	3.2.1.5a
Flushing/Mechanical Cleaning Verification	3.2.5
Leak/Pressure Test Certification	3.2.6.1b

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 See Section 01610 for general requirements.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.1.2 See Section 01019 for items furnished for construction.

2.2 MATERIALS

2.2.1 Pipe and Fittings: See the Pipe Codes in this Section, and details on the Drawings.

2.2.1.1 Material and weight shall be as specified in the Pipe Code for each piping system.

2.2.1.2 Close or butt nipples are not permitted, unless shown on the Drawings.

- 2.2.2 Pipe Joint Sealant (Lubricant) for Threaded Joints
- 2.2.2.1 Use nonhardening teflon paste: Chesterton "Goldend" No. 7298, Federal Process Company "JC-30," or Lake Chemical Company "Slic-Tite."
- 2.2.3 Painting: See Section 09900.
- 2.2.4 Glycol Solution: Glycol solution shall consist of 46% glycol and 54% distilled water by volume. Total system volume is approximately 30 gallons. The glycol shall be an industrially inhibited propylene glycol (phosphate based) with dyed color to facilitate leak detection. Contractor shall be responsible for disposal/handling of glycol.
- 2.2.5 Pipe Supports: Standard, manufactured components as shown on the Drawings. Pipe supports and attachments welded to pressure containment boundaries may be noncertified material, provided the material bears a type identifying mark, is suitable for welding, and compatible with the material to which it is attached.
- 2.2.6 Identification Tags: 0.0478-inch (18-gage) minimum thickness stainless steel. Tag attachment wire: 20-gage, solid, stainless steel.
- 2.2.7 Protective coating for piping in contact with earth or concrete, and not cathodically protected.
- 2.2.7.1 Carbon steel piping: Tapecoat Company Tapecoat "H30" and primer meeting requirements of AWWA C209 specification for cold applied tape.
- 2.2.8 Expansion Anchors: See Section 05055.

2.3 EQUIPMENT

- 2.3.1 Valves: Specified in Pipe Codes, unless shown otherwise on the Drawings.
- 2.3.2 Pit Cooling System: System shall be a split system consisting of a fan coil unit mounted in an existing pit, a packaged outdoor liquid chiller providing chilled propylene glycol/water solution to the fan coil unit, and fan controls and instrumentation. Air moving equipment ratings and sizes are based on AMCA Standard 99. *Fan construction shall be in compliance with AMCA Standard 99-0401-86 Classifications for Spark Resistant Construction. Fan installation shall be in accordance with vendor installation instructions and recommendations.* Equipment ratings shown below are minimum acquirements. ECN-588
|
ECN-588
- 2.3.2.1 Chiller unit (R-0621): The liquid chiller shall be weatherproof for outdoor use, UL approved, in accordance with AIR 590. The packaged outdoor liquid chiller shall be air cooled and deliver 4 gpm of chilled 46% propylene glycol/54% water solution at 60°F to the fan coil and have a maximum coolant return temperature of 80°F. The chiller shall be capable of providing the required cooling to the fan coil in ambient temperatures of 2°F to 106°F dry bulb (FDB)/67°F wet bulb (FWB). The chiller control panel shall have a NEMA-1 enclosure and be inside the raintight chiller enclosure. The chiller shall be an Edwards

- a. The chiller shall contain a low ambient control package, compressor short cycle protection, and a high pressure lock-out circuit. The chiller shall have system bypass and check valve and large coolant reservoir to prevent compressor short cycling.
- b. The chiller shall have a 2 pump circuit, 1 for coolant supply to the process, 1 for coolant circuit by-pass.
- c. The chiller shall be equipped with an expansion tank, automatic air vent, drain provisions and a process pump capable of delivering the propylene glycol/water mixture at 4 gallons per minute at 50 feet total design head.
- d. The chiller shall be provided with a control panel with the necessary instruments and controls for controlling the entire system including the compressor, pumps, condenser fan, and fan coil unit.
- e. In addition to the controls necessary to operate the chiller, a temperature indicating and control system shall be provided and mounted on the control panel to control the pit air temperature between 90°F and 110°F. This indicating controller shall indicate the actual coil air inlet temperature and the setpoint and shall have a separately adjustable alarm contact (SPDT) to actuate at 115°F for Buyer's use.

2.3.2.2

Fan coil unit (FC-0621): The fan coil unit shall be capable of delivering 12,000 Btu/h with an entering air condition of 110°FDB and 91°FWB. Coolant supply temperature shall be 60°F and coolant temperature leaving the fan coil shall not exceed 80°F. The fan coil unit shall be housed in a stainless steel enclosure. The fan coil unit shall be an Edwards Engineering Model No. CSB-18-4-600-H or an approved substitute.

a. ~~The fan coil motor shall be a 120 V/60 Hz/1 phase, Totally Enclosed Fan Cooled (TEFC) and shall be in accordance with NEMA MG 1. The fan coil motor shall be a 120 V/60 Hz/1-phase, Totally Enclosed Fan Cooled (TEFC) and shall be in compliance with NFPA 70 (1996), Class 1, Division 2, Group B criteria (as a minimum, non-sparking under normal operation). Fan coil motor installation shall be in accordance with vendor installation instructions and recommendations.~~ Motor power cable shall be 30 foot length, measured from where cable exits the fan coil, for routing to Buyer's chiller unit (R-0621). Power cable insulation shall be rated for 600 V ac. The cable's overall jacket shall be ultraviolet resistant. The cable shall be cut to length during field installation.

ECN-588

ECN-588

- b. The cooling coil shall be constructed of copper tubing and fins. Water pressure drop across the coils shall not exceed 10 psi maximum.
- c. The fan coil unit shall include a temperature sensor (TE-06213, 100 ohm platinum RTD) to detect the air inlet temperature to the fan coil unit. The sensor and it's attached electrical cable shall be weatherproof and sealed against intrusion of moisture. The conductors shall be tagged to indicate their connection points to the RTD elements.

RTD leads shall be shielded, #16 AWG contained within a cable or sheath and shall be 30 foot length, measured from where cable exits the RTD

Box, for routing to Buyer's chiller unit (R-0621). The cable's overall Page 128 jacket shall be ultraviolet resistant. The cable may be cut to length during field installation.

d. The maximum fan coil enclosure size shall be 40.75 inches long by 6 inches wide by 17.5 inches high. The air intake shall be on the bottom of the unit and the air discharge shall be on the 43 40.75 -inch ECN-197 length side. The inlet and outlet coolant connections, 3/4-inch MNPT, shall be on the left side when facing the air discharge and approximately 4.5 inches from the bottom of the coil unit. Two mounting channels shall be provided on top of the unit running along the 43 40.75-inch length with hex nuts welded to the channel to provide ECN-197 6 attachment points to 3/8 inch 16UNC-2A bolts supplied by Buyer.

PART 3 - EXECUTION

3.1 INSTALLATION

3.1.1 Equipment

3.1.1.1 Install as shown on the Drawings and in accordance with the manufacturer's instructions.

3.1.1.2 Prime and paint carbon steel supports in accordance with Section 09900. Paint containing lead is not acceptable.

3.1.2 Piping

3.1.2.1 Fabricate and install pipe and tubing in accordance with ASME B31.3 (for ~~normal~~ Category D service), the Drawings, and this Section. *Pipe Code M-4 piping system shall be fabricated from carbon steel components using welded connections unless otherwise shown on the drawings.*

ECN-499
ECN-335
ECN-335

3.1.2.2 Cut pipe and tubing using methods which result in clean, straight cuts. Do not use tubing cutters on tubing utilizing compression fittings.

3.1.2.3 Ream pipe and tubing to nominal inside diameter after cutting. Remove burrs from threads before assembly.

3.1.2.4 Bend pipe and tubing in accordance with ASME B31.3, and meet tolerances given in ASME B31.3. Use methods and equipment which produce bends free of wrinkles, bulges, or kinks. When wall thickness, diameter, and bend radius indicate possibility of wall collapse during bending, fill pipe or tubing with clean silica sand or fusible material similar to Cerro-bend, manufactured by Cerro Corporation.

a. Application of heat to facilitate a pipe bend shall be brought to the attention of the responsible engineer for direction and disposition.

b. Cold springing pipe permitted only if specified on the Drawings.

3.1.2.5 Make joints in threaded piping systems with joint sealant specified. Apply sealant to male threads only.

3.1.2.6 Install tubing fittings in accordance with the manufacturer's instructions.

- 3.1.2.7 Carbon steel embedded in concrete shall be bare.
- 3.1.2.8 Keep piping systems clean. Once fabrication has started, plug or cap ends of piping when installation is not in progress. Cap or plug openings in fabricated pipe spool assemblies until installation in the piping system. Leave ends of spare lines capped or blind flanged when installation has been completed.
- 3.1.2.9 Pipe supports: Install as shown on the Drawings, in accordance with manufacturer's instructions, and applicable recommended procedures of MSS SP-89.
- 3.1.3 Underground Piping Excavating
 - 3.1.3.1 Trenches: Excavate, backfill, and compact in accordance with Section 02200 and Section 02225.
 - 3.1.3.2 Survey piping systems for elevation and location before final tie-in welds to valve pits, risers, or fixed items. Complete placement of supports and meet Specification and Drawing requirements before survey. Elevation and location shall be in accordance with the Drawings. After final tie-ins survey piping system again for final acceptance.
- 3.1.4 Welding
 - 3.1.4.1 Weld piping, attachments to pressure retaining components, and pipe supports in accordance with ASME B31.3.
 - a. Protect outdoor welding operation from rain and wind by using barriers to protect welder and weld joint.
 - b. Complete piping welds before tie-in welds to valve pits, risers, or fixed items.
 - c. Remove backing strips if used.
- 3.1.5 Weld Identification
 - 3.1.5.1 Prepare weld maps using Project Drawings or sketches, which show relative positions of pressure containing welds and attachment welds to pressure retaining components.
 - 3.1.5.2 Assign and record weld numbers on weld identification drawings as welds are made.
 - 3.1.5.3 Place the welder identification symbol adjacent to welds upon completion. Place the identification symbol approximately every 3 feet on long seams or large weldments, using one of the marking methods specified in Section 01610.
 - 3.1.5.4 Do not reuse weld numbers. If a weld is completely replaced, assign a new number.

- 3.1.5.5 Maintain material traceability (including heat/lot numbers) through fabrication.
- 3.1.6 Perform NDE, flushing, leak/pressure testing, and disinfecting specified in 3.2 before coating application.
- 3.1.7 Exterior Protective Coating
 - 3.1.7.1 Protect short lengths of bare carbon steel pipe and fittings exposed to earth backfill with specified coating.
 - a. Clean carbon steel surfaces to white metal by sandblasting in accordance with SSPC SP 6. Where blasting is impracticable clean by power wire brushing in accordance with SSPC SP 3.
 - b. Apply specified tape and primer in accordance with AWWA C209, Section 3, and manufacturer's instructions.
 - 3.1.7.2 After installation, examine carbon steel pipe having factory-applied exterior protective coating, and joints, fittings, and short lengths of pipe having field applied exterior protective coating materials.
 - a. Use electrical holiday detector in accordance with AWWA C209, Section 4.4.
 - b. Repair damage to coating in accordance with AWWA C209, Section 3.4.
- 3.1.8 Piping Identification: Identify exposed piping systems as to fluid carried and direction of flow as specified in Appendix A.
- 3.1.9 Identification Tag Features
 - 3.1.9.1 Blanks: 3/4 by 2 inches (unless legends require longer tags), with a 1/8-inch attachment wire hole 3/16 inches in from one end.
 - 3.1.9.2 Characters: Use 1/4-inch stamped or engraved characters.
 - 3.1.9.3 Legends: Provide the following information, unless otherwise specified on the Drawings. Obtain information from the Data Sheets in this Specification, or Drawings.
 - a. Buyer part number.
 - 3.1.9.4 Attach identification tags to valves, instruments and other equipment, as required.
- 3.1.10 Wiring: For wiring requirements refer to Sections 13440 and 16400.

3.2 FIELD QUALITY CONTROL

3.2.1 Nondestructive Examination (NDE) of Welds for Piping

3.2.1.1 Perform NDE for each Pipe Code listed in the schedule in 3.3. Extent of required examination shall be in accordance with ASME B31.3, Paragraph 341.4.1. Acceptance criteria for NDE shall be in accordance with ASME B31.3, Paragraph 341.3.

3.2.1.2 Visual examination: Perform in accordance with ASME B31.3, Paragraph 344.2.

3.2.1.3 Radiographic examination (RT): Perform in accordance with ASME B31.3, Paragraph 344.5.

a. Identify radiographic film with weld identification number and project or work order number assigned to work covered by this Section. In process examination in accordance with ASME B31.3, Paragraph 344.7 may be substituted for radiography.

b. Prepare radiographic examination reports as follows.

1) List each radiographic exposure location (0-1, 1-2, ...) individually on radiographic examination report.

2) Indicate location acceptability or rejectability and note discontinuities whether rejectable or not.

3) When report includes radiographs of welds which have been repaired, indicate which welds are repair welds and how many times each weld has been repaired.

c. If additional welding is performed on weld area which has already been examined radiographically, this area is repair area. Identify subsequent radiographs by "R-1, R-2," etc.

3.2.1.4 Perform 5% random examination of piping supports in accordance with ASME B31.3, Paragraph 344.2.

3.2.1.5 NDE documentation:

a. Document examination of pressure containment welds and welds to pressure containing components for piping systems on NDE/Weld Record Form KEH-0433 or similar. See Form KEH-0433 or similar for instructions for recording weld maps, weld numbers, welder identification, welding procedure numbers, weld filler material, visual examinations, nondestructive examinations, and for noting satisfactory completion of leak/pressure testing.

b. Required NDE shall be completed and documented before starting leak/pressure testing.

c. NDE/Weld Record information and weld maps specified in paragraph 3.1.5 may be incorporated on a single format or traveler for a specific work package.

d. Document examination of pipe supports by recording on Sketches or NDE/Weld Record form.

3.2.2 Flushing/Testing Preparation: Obtain direction for disposal of waste flushing and testing water, prior to generation of wastes, from the Operating Contractor.

3.2.3 Cleaning and Flushing

3.2.3.1 After NDE is complete and before leak/pressure testing the system, or before connecting the system into existing systems, clean piping internal surfaces mechanically or by flushing as follows.

Service	Pipe Code	Cleaning Method
Chill Water	M-4	Water Flush or 3.2.4

3.2.3.2 Mechanical cleaning: Remove loose dirt, scale, and debris by brushing, wiping, high pressure water jetting, or other mechanical method approved by the Construction Engineer (Buyer).

a. When high pressure water jetting or other mechanical cleaning method utilizing water is used, and leak/pressure testing will not be performed immediately after cleaning, dry piping systems by blowing dry oil-free air or nitrogen through lines.

b. Dry until the relative humidity of discharge air is equal to that of inlet air. Use drain taps at low points of piping system to ensure complete drainage and drying. Cap lines or reconnect to system to maintain cleanliness. Note, humidity measurements from inlet and exhaust shall be converted to the same pressure to verify equality.

3.2.3.3 Water flushing:

a. Remove strainer screens before flushing, except those protecting control equipment. Clean screens protecting control equipment before flushing, if necessary, and after flushing is complete.

b. Flush piping with water for 1 minute minimum, and until effluent is clean and contains no visible particulate matter. Flushing pressure shall not exceed maximum operating pressure specified in Pipe Codes. Flushing water supply shall have sufficient capacity to produce a flow velocity of 4 to 6 ft/s in largest pipe size, with pipe full. Provide flow measurement in flushing water supply line to be used as basis for verification of flow velocities in piping system by the Construction Engineer (Buyer).

3.2.4 Mechanical cleaning may be substituted for flushing if approved by the Construction Engineer (Buyer).

3.2.5 Provide documented evidence that flushing or mechanical cleaning has been accomplished as specified in this Section.

3.2.6 Leak/Pressure Testing of Piping

3.2.6.1 General:

a. After completion of flushing, perform leak/pressure testing of pipe in accordance with ASME B31.3, paragraph 345 and this Section. Use calibrated gages with ranges 1-1/2 to 2 4 times the test pressure. ECN-203

b. Document testing of each piping system on "Leak/Pressure Test Certification" Form KEH-1757 or similar form. Use separate forms to describe and record each piping system. Under "Description" describe piping system in enough detail for correlation to weld maps, shop fabrication drawings, and Project Drawings as applicable. For systems tested in segments, indicate continuity in "Description" to assure that entire systems have been tested.

c. Pipe joints, fittings, and other potential leak sources to be tested shall be visible and accessible during tests.

d. Install 1 temporary relief valve during testing. Relief valve shall have a discharge capacity of 125% of capacity of the pressurizing device, and be set to operate at 1-1/3 maximum of the test pressure for hydrostatic testing and not higher than test pressure plus the lesser of 50 lb/in² or 10% of the test pressure for pneumatic testing. Tag each relief valve used to show serial number, inspector, date, and pressure setting.

e. Install necessary restraining devices, before applying test pressure, to prevent distortion or displacement of piping.

f. Isolate instruments and other items which could be damaged by test pressures.

g. Continuously maintain test pressure for 10 minutes minimum. Examine joints and connections. Piping system, exclusive of possible localized instances at pump or valve packing, shall show no visual evidence of weeping or leaking.

h. Visually examine piping and tubing joints, fittings, and other potential leak sources, including welds which attach wear plates, anchors, etc to piping systems, during testing.

i. Complete testing of piping before field application of protective coating. Pipe with factory applied protective coating shall be considered as having been tested before protective coating application.

j. All threaded connections shall be subjected to an initial service test in accordance with ASME B31.3-1993 Edition paragraph 345.7. ECN-499
ECN-499

3.2.6.2 Hydrostatic pressure testing:

a. Perform in accordance with ASME B31.3, Paragraph 345.4.

b. Purge air from piping systems during filling, before applying pressure.

c. Coat welded piping joints, fittings, and other potential leak sources, including welds attaching wear plates, anchors, etc, to piping systems, with a mixture of powdered blue chalk and water or isopropyl alcohol. Allow to dry before filling piping with water and inspecting for leaks.

d. Remove water from tabulated piping systems after testing and dry by blowing dry, oil-free air or nitrogen through lines. Dry until the relative humidity of discharge air is equal to that of inlet air. Use drain taps at low points of piping systems to ensure complete drainage and drying. Note, humidity measurements from inlet and exhaust shall be converted to the same pressure to verify equality.

Service	Pipe Code
Chill Water	M-4

3.2.7

Chilled Water System Filling: After completion of pressure testing, fill the chill water system with glycol/water mixture.

3.3 SCHEDULES

3.3.1 Schedule of Pipe Weld NDE/Testing

	Pipe Codes							
	M-4							
NDE/NDT Method								
Visual	B							
Fitup								
Root Pass								
Cover Pass								
Liquid Penetrant								
Root Pass								
Cover Pass								
Magnetic Particle								
Root Pass								
Cover Pass								
Radiographic								
Completed Weld	C							
Leak/Pressure								
Completed Weld	A							
Other								
Legend: A. Requires witnessing and acceptance by a Level II Inspector or higher. B. Visual examination of at least 5% of fabrication welds. C. Not less than 5% of circumferential butt welds shall be examined fully by random radiography. In-process visual examination may be performed in lieu of radiography.								

PIPE CODE M-4 (Safety Class 3 General Service)			
Service	Max Operating Pressure lb/in ² gage	Test Pressure lb/in ² gage	Max Operating Temp °F
Examples: Chilled Water (CW) Package 3	28	42	60
Sizes	All sizes		
Pipe	ASTM A 53, Type E or S, Grade B black steel or ASTM A 106 GR B		
Wall Thickness	Schedule 40		
Nipples	Same schedule as pipe.		
Fittings	ASTM A 234, Grade WPB, wrought steel, butt welding in accordance with ASME B16.9. Wall thickness to match pipe.		
Unions	As shown on Drawings.		
Valves			
Ball	Pittsburg Brass Manufacturer Co., Model SP, Standard Trim, Carbon steel, Class 150, BW ends		

Specification Section
15507

[illegible]

VENDOR INFORMATION LIST
 ("X" Indicates Required Data)

Project No. W-320

Project Title 241-C-106 Sluicing

Specification Section
15507

[illegible]

1. GENERAL

The identification of piping systems shall be in accordance with the American Standard Scheme for the Identification of Piping Systems, ANSI A13.1, as supplemented herein.

2. LOCATION

a. Except as provided below, identification shall be located adjacent to outlets, valves, flanges, unions, changes-in-direction, where pipes pass through walls, floors, or ceilings, and along an uninterrupted length of pipe at maximum intervals of 50 feet. Each line or branch in a room shall have at least one identification.

b. Where a number of outlets, valves, flanges, unions, or changes of direction make identification at each item impracticable, they may be spaced at approximate 6 foot intervals, preferably adjacent to valves.

c. Legend shall be located on the pipe so that it can be read easily from the operator's normal viewing position. Labels shall be placed on the readily visible lower quadrant of overhead pipes, and on an upper quadrant of pipes below normal eye level. Above ceilings, labels shall be placed in locations most readily visible from access positions.

3. LEGEND

a. Positive identification of a piping system content shall be by lettered legend giving the name of the content in full or abbreviated form. Legends may also be as specified on drawings or in other specifications.

b. Abbreviation of words in the legend may be used only where unavoidable due to space limitations.

c. The legend shall include the nominal operating pressure for steam, compressed air, and when specified, the pressure or temperature for other materials.

d. An arrow indicating the direction of flow shall be placed near the legend on pipes normally having a flow in one direction only. The color and size of the arrow shall be consistent with the color and size of the legend letters.

e. Legend shall be located on or adjacent to the classification color band.

4. APPROVED LABELS

a. Legend and color classification may be accomplished by the use of approved labels conforming to this Standard and which are suitable for the temperature of the surface to which they are to be applied. Approved labels include the following.

ALL-TEMPERATURE PIPE MARKERS
W. H. Brady Company
727 West Glendale Avenue
Milwaukee, Wisconsin 53201

TEL-A-PIPES
Westline Products Division
Thomas & Betts Company
220 South Rose Street
Los Angeles, California 90012

b. Single-word labels may be combined to form complete legends. Individual-letter labels shall not be so combined.

c. Labels shall be installed after painting is complete.

5. CLASSIFICATION COLOR

a. When use of classification colors is specified, they shall conform to Table 1.

Table 1			
Classification	Band or Label Color	Legend/Arrow Color	Approximate Color No. (FED-STD-595)
Dangerous	Yellow	Black (17038)	13655 (yellow)
Safe	Green	Black (17038)	14260 (green)

b. Paint, if used, shall conform to FS TT-E-489, Class A, for synthetic gloss enamel.

c. Classification colors shall conform to Table 2.

Table 2. Classification Colors.	
Material	Color
Chill Water (CW)	Green

SECTION 15990

TESTING, ADJUSTING, AND BALANCING

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 Sheet Metal and Air Conditioning Contractors National Association (SMACNA)

HVAC Systems--Testing, Adjusting and Balancing 1983, 1st Edition

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required: None

1.2.3 Approval Not Required

1.2.3.1 Testing data: Upon completion of testing and adjusting submit records on SMACNA forms or similar forms, dated and signed by the subcontractor who performed the work verifying results of tests per paragraph 3.3.

1.3 QUALITY ASSURANCE

1.3.1 See Section 01400 for quality assurance.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

3.1 EXAMINATION

3.1.1 Testing shall be performed on heating and cooling units AC-0621 and AC-0622 on seismic enclosures (241-AY-51A and 241-AY-51B), air-conditioning unit on electrical equipment skid (241-AY-51).

3.1.2 Examine systems to be tested, and their associated Project Record Documents. Verify that equipment has been prepared for operation in accordance with factory instructions, that equipment operation has been checked in accordance with system specification requirements, and that cleaning has been completed as required.

3.2 PREPARATION

- 3.2.1 Verify that filters of the required sizes and types are in place and clean.

3.2.2 Inspect all factory and field wiring for loose connections.

3.3 FUNCTIONAL TESTING OF HVAC SYSTEMS

3.3.1 Electric Heating Unit(s)

3.3.1.1 Set the thermostat for a heating demand, turn on power to the unit.

3.3.1.2 Check unit voltage with unit running. Power must be within range shown on unit nameplate or vendor data. Check amperage draw of unit. Refer to unit nameplate or vendor data for correct running amps and verify compliance with measured value.

3.3.1.3 Verify unit operates satisfactorily.

3.3.2 Cooling Unit(s)

3.3.2.1 Compressor-condensing (or heat pump, as applicable) unit test and start-up seration (NDE) of necessary tests and make necessary adjustments, such as leak testing, evacuation, and dehydration using a high vacuum pump, charging the unit and piping systems and start-up, in accordance with the manufacturer's specifications.

3.3.2.2 Set the thermostat for a cooling (or heating, as applicable) demand, turn on power to the unit.

3.3.2.3 Check unit voltage with the unit running. Power must be within the unit nameplate range, or vendor data. Check amperage draw of the unit. Refer to the unit nameplate, or vendor data, for correct running amperage. Verify compliance with the measured value.

3.3.2.4 Measure inlet air dry-bulb and wet-bulb temperature. Measure outlet air dry-bulb and wet-bulb temperature. Verify unit performance is within manufacturer's performance specifications.

END OF SECTION

SERVICE AND DISTRIBUTION

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American National Standards Institute (ANSI)

C57.13-1978

IEEE Standard Requirements for
Instrument Transformers

C80.1-1990

Rigid Steel Conduit--Zinc Coated

C80.3-1983

Electrical Metallic Tubing-Zinc Coated

C82.1-1990

Fluorescent Lamp Ballasts

1.1.1.2 American Society of Mechanical Engineers (ASME)

NQA-1-1994

Quality Assurance Requirements for
Nuclear Facility Applications

1.1.1.3 American Society for Testing and Materials (ASTM)

B3-90

Soft or Annealed Copper Wire

1.1.1.4 Code of Federal Regulations (CFR)

Title 47

Telecommunication

Part 18

Industrial, Scientific, and Medical
Equipment

1.1.1.5 Federal Specifications (FS)

W-F-406E

Fittings For Cable, Power, Electrical
And Conduit, Metal, FlexibleTT-S-00230
AMD 2Sealing Compound: Elastomeric Type,
Single Component (For Caulking,
Sealing, And Glazing In Buildings And
Other Structures)

WW-C-566C

Conduit, Metal, Flexible

1.1.1.6 Institute of Electrical and Electronic Engineers (IEEE)

587-1980

Guide for Surge Voltages in Low-Voltage
AC Power Circuits

- 1.1.1.7 National Electrical Manufacturers Association (NEMA)
 - AB 1-1986 Molded Case Circuit Breakers and Molded Case Switches
 - FB 1-1988 Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit and Cable Assemblies
 - FU 1-1986 Low Voltage Cartridge Fuses
 - ICS 2-1993 Controllers, Contractors, and Overload Relays
 - ICS 6-1993 Enclosures
 - WC 7-1988 Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy
- 1.1.1.8 National Fire Protection Association (NFPA)
 - 70 (1993) National Electrical Code (NEC)
- 1.1.1.9 Revised Code of Washington (RCW)
 - Title 19 Business Regulations - Miscellaneous
 - Chapter 19.28 Electricians and Electrical Installations
- 1.1.1.10 Underwriters Laboratories (UL)
 - 467-1993 Grounding and Bonding Equipment
 - 508-1988 Industrial Control Equipment
 - 797-1993 Electrical Metallic Tubing
 - 1062-1993 Unit Substations
- 1.1.1.11 Washington Administrative Code (WAC)
 - Title 296 Department of Labor and Industries
 - Chapter 296-46 Safety Standards - Installing Electrical Wires and Equipment - Administrative Rules
 - Chapter 296-401 Certification of Competency for Journeyman Electricians

1.2 SUBMITTALS

1.2.1 See Section 01300 for submittal procedures.

1.2.2 Approval Required: None

1.2.3 Approval Not Required

1.2.3.1 Vendor information: Before installation, submit information listed in the Vendor Information List in this Section.

1.2.3.2 Electrical contractor's license: Before installation, submit a copy of license required by RCW 19.28 and WAC 296-46-940.

1.3 QUALITY ASSURANCE

1.3.1 Contractor's Quality Assurance Program: See Section 01400.

1.3.2 Safety Class ± (SC±) Products: SC± items shall be procured from qualified suppliers. These suppliers shall have a quality assurance program in accordance with ASME NQA-1.

ECN-809

1.3.3 Electrical/Electronic Product Acceptability: Provide labeling and documentation in accordance with Section 01400.

1.3.4 Maintain electrical contractor's license in current status. Ensure that personnel performing work under this Section have certificates of competence required by RCW 19.28 and WAC 296-401. Certificates shall be available at worksite for review.

1.3.5 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

Document

Paragraph

Electrical Test Results

3.3.2.3

1.4 PERMITS

1.4.1 Obtain and conspicuously post following permits before starting work under this Section.

a. Core Drilling/Tie-In Permit (Form WHC A-5600-118): Required for each element of work involving core drilling or utility tie-in.

b. Hot Work Permit (Form KEH 2235.00): Required for each location in which work involves welding, cutting, grinding, soldering, heating, spark generation or open flame.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 See Section 01610 for general requirements.

1.6 FURNISHED EQUIPMENT

1.6.1 The following items will be furnished for installation under this Section. Upon request, one copy of approved vendor data submittals will also be furnished. See Section 01019.

1.6.1.1 Electrical Equipment Skid. W-320-P33

1.6.1.2 Seismic Shutdown Systems (Safety Class 1) - 2 each. W-320-P35 ECN-809

1.6.1.3 Seismic Shutdown System Environmental Enclosures (Missile Shields) - 2 each. W-320-P36

1.6.1.4 Variable speed drive. W-320-P17

PART 2 - PRODUCTS

2.1 SUBSTITUTES

2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

2.2.1 Conduit, Fittings, and Boxes

2.2.1.1 Conduit: ANSI C80.1, C80.3, FS WW-C-566, and UL 797.

2.2.1.2 All conduit shall have an integral ground conductor.

2.2.1.3 Fittings for rigid steel and EMT conduit: NEMA FB 1. Use compression type, threadless fittings with EMT.

2.2.1.4 Fittings for flexible metal conduit: FS W-F-406, squeeze type.

2.2.1.5 Use "Myers" type watertight fittings, or sealing type locknuts, for conduit entries into sides or tops of NEMA ICS 6 Type 3, 3R, or 4 enclosures.

2.2.1.6 Couplings: Erickson type.

2.2.2 Conductors: NEMA WC7, stranded copper, rated for 90°C, with Type THWN/THHN or XHHW insulation, of type and AWG size specified on the Drawings.

2.2.3 Ground Conductors: Grounding cable shall be stranded copper wire in accordance with ASTM B 3 and size specified on the Drawings.

2.2.4 Ground Rods: Copper bonded ground rods as shown on the Drawings, in accordance with UL 467.

- 2.2.5 Connectors and Terminal Lugs: Solderless, pressure type, rated for use with copper or aluminum conductors, with insulating caps or covers rated for system utilization voltage. Connectors shall be spade type with turned up tips and as specified below. See 2.3.12 for terminal blocks to be used for instrumentation and control circuits.
- 2.2.5.1 For conductors No. 8 AWG and smaller:
- a. Ideal Industries, Incorporated "Wire-Nuts."
 - b. Thomas and Betts Company "Sta-Kon."
 - c. 3M Company "Scotchlok."
- 2.2.5.2 For conductors No. 6 AWG and larger:
- a. Burndy Engineering Company "Screw Pressure Connectors" or "Hylug."
 - b. Thomas and Betts Company "Lock-tite."
- 2.2.5.3 Cable connector: Relief type as shown on the Drawings.
- 2.2.5.4 Ground studs: Burndy Type K2C "Servit Post"; size as required.
- 2.2.6 Wire Pulling Compound: Electro Compound Company "Y-er Eas," or American Polywater Corporation "Polywater."
- 2.2.7 Tape:
- 2.2.7.1 Plastic insulating tape: 3M Company "Scotch No. 33+."
- 2.2.7.2 Conduit protection tape: 3M Company "Scotchrap No. 50."
- 2.2.7.3 Underground conduit plastic sheet marker: See Section 02225.
- 2.2.8 Insulating Putty: 3M Company "Scotchfil," General Electric Company No. 8389, or Kearney Company "Airseal."
- 2.2.9 Conduit Sealing Compound: Porcelain Products Company "Sealex," or Kerite Company "Kerite."
- 2.2.10 Penetration Sealants: FS TT-S-00230, Type II, Class A, 1-component polyurethane, nonsag type, light-colored.
- 2.2.11 Supports
- 2.2.11.1 Individual conduit hangers: Factory-made springable wrought steel clamps, or malleable iron split and hinged rings. For suspended conduit, clamps or rings shall be bolted to, or interlocked with threaded suspension rod.
- 2.2.11.2 Conduit supports: 1-hole clamps with clampbacks, or Unistrut with clamps.

- 2.2.11.3 Equipment supports: 1-5/8-inch channel; Unistrut or Kindorf.
- 2.2.11.4 Expansion anchors: See Section 05055.
- 2.2.12 Wiremarkers: Imprinted tubular plastic.
- 2.2.13 Conduit Labels: Brady marking film.
- 2.2.14 Equipment Nameplates
 - 2.2.14.1 Laminated plastic, 1/16-inch thick with white surface and black core.
 - 2.2.14.2 Manufacturer's standard equipment nameplates may be used instead of those specified herein, if they display the required information, and are equivalent in quality and legibility. They need not be of the same material, or have the same form of imprinting.
 - 2.2.14.3 Nameplate features:
 - a. Blanks: Select sizes appropriate for required characters and legends. Smooth edges and bevel 1/32-inch at 45 degrees.
 - b. Characters: Use 3/16 to 5/16-inch characters for equipment names, and 3/32 to 3/16-inch characters for other information. Engrave sharp and clear. Refer to 13440 Figure 1.
 - c. Legends: Provide the following information, unless otherwise specified on the Drawings. For equipment names use the generic/functional designations shown on the Drawings.
 - 1) Equipment name.
 - 2) Equipment number.
 - 2.2.14.4 Make sheet steel nameplates for equipment items that do not have surfaces suitable for attachment of plastic nameplates. Make nameplates when cylindrical surfaces of adequate size are available. When not, make nametags. Provide the information required above.
- 2.3 EQUIPMENT
 - 2.3.1 Electrical equipment shall be PCB free.
 - 2.3.2 Equipment Enclosures: NEMA ICS 6 Type 1, 3, 3R, and 4, as shown on the Drawings. Use Type 3R (with gaskets) if Type 3 is not commercially available.
 - 2.3.2.1 Motor starter enclosure (inside electrical equipment skid housing): Type 1, "Multi-Pak" group control motor starter enclosure, 48 inches wide by 26 inches high by 7 inches deep for combination starters, Westinghouse No. 6262A70G02 or approved substitute. To be provided as a part of the starter and circuit breaker modules identified in 2.3.5 and 2.3.7.

- 2.3.3 Electrical Equipment Skid Mini-Power Panel: UL 1062, dry-type, 60 Hz, 15 kVA, wall mounted, with minimum of 2 full current 5% taps below nominal rated voltage. Secondary of transformer shall be 120/240 V ac. Insulation system shall be rated 30°C with 60°C winding temperature rise above ambient. Unit shall have a main circuit breaker, a minimum of sixteen 1-pole breakers, a ground bar, and a separate neutral bar. Westinghouse Minipower Center P48G11S15P or Square D MPZ15S40F Mini-Power Zone. A panelboard schedule shall also be included.
- 2.3.4 Power Distribution Blocks (At Pit:PTBX-0621): Copper, 3-pole, as required per Drawings, Square D, No. LBA362101 and LBA364101 or approved substitutes.
- 2.3.5 Combination Motor Starters: NEMA ICS 2, 600 V ac, 3-phase, minimum 14 000 AIC, horsepower rated, capable of starting energy efficient motors. 2 NO and 2 NC auxiliary contacts rated 120 V ac, 10 A continuous with an inductive load, shall be provided in accordance with NEMA AB 1 and UL 508. The coils of contractors and starters shall be rated for 120 V ac. Motor circuit protector (MCP) type circuit breaker having adjustable, magnetic only, instantaneous trip elements. Relays shall be the sealed type. Devices shall be labelled/identified.
- 2.3.5.1 ~~For 75 hp motor: Size 4, full voltage non reversing (FVNR) starter, Westinghouse Starter Module No. 6263A03G01, with larger control transformer (minimum of 300VA) Westinghouse Catalog No. 2045A43G01, or approved substitutes. For 40 HP motor: See paragraph 2.3.10.~~ ECN-167
ECN-167
- 2.3.5.2 For 1.5-hp motor: Size 1, full voltage reversing (FVR) starter, Westinghouse Starter Module No. 6263A04G01 or approved substitute.
- 2.3.5.3 Overload relays: Bimetallic or melting alloy type, complete with heaters, and sized for motor size. Overload relays shall be manually reset on front of cover. Field adjustable solid-state overload trip units are acceptable as an alternative to overload relays.
- NOTE: Order overload heaters separately.
- 2.3.5.4 Control and indication devices shall be provided as shown on the elementary diagrams on Drawing H-2-818698. Control and indication devices shall be corrosion resistant, heavy-duty and oil-tight.
- a. Pilot lights shall be push to test, 120 V ac, 60 Hz, nontransformer type, red (ON), green (OFF), with a legend plate.
- b. Selector switches and pushbuttons shall be momentary and as shown on the elementaries, 120 V ac, 60 Hz, with a legend plate. "Stop" pushbutton to be red. "Start" pushbutton to be green.
- c. Control transformers: 1 for each starter or contractor compartment, rated 480-120 Vac, 60 Hz, and protected by 2 primary fuses, and 1 secondary fuse in the ungrounded side of the control circuit. The control transformer for the 75 HP motor starter is larger than the standard size; refer to 2.3.5.1.

d. Current transformer shall have a minimum ANSI C57.13 metering accuracy class of 0.6 with burden designation B-0.5. At rated amperes and under usual service conditions, no part of the current transformer shall exceed the heating limits as specified in ANSI C57.13. Current transformers shall have a ratio determined by the Seller.

e. Amp transducer shall receive a nominal 0 to 5 ac ampere input signal from Seller supplied current transformer. Output of amp transducer shall be 4 to 20 milliamps dc. Unit shall be powered from control transformer. Unit shall have calibration adjustment which can be accessed while mounted within the motor starter enclosure. Accuracy of unit shall be 0.50% of full scale at $25^{\circ}\text{C} \pm 2^{\circ}\text{C}$. Unit shall be equivalent to Rochester Instrument Systems CCC-1BC5E1XAF60Z0A1.

- 2.3.6 Motor Load Fuses: NEMA FU 1, and be the following types.
- 2.3.6.1 250 V rated: Buss, Fusetron, Catalog No. FRN.
- 2.3.6.2 600 V rated: Buss, Fusetron, Catalog No. FRS.
- 2.3.7 Circuit breaker, for installation in "Multi-Pak" group control unit, 600 V ac.
- 2.3.7.1 For pit cooling system: 30 A, 3-poles, thermal magnetic, Westinghouse Feeder Air Circuit Breaker Module No. 6263A16G03 or approved substitute.
- 2.3.7.2 For mini-power center: 70 A, 3-poles, thermal magnetic, Westinghouse Feeder Air Circuit Breaker Module No. 6263A16G06 or approved substitute.
- 2.3.8 Safety Switch: Heavy-duty, non-fusible, single-throw, NEMA 3R enclosure, UL listed, sized in accordance with following.
- 2.3.8.1 600 V ac, 3-pole, 3-wire, 600 A, "service entrance rated" Westinghouse Catalog No. RHU366 plus equipment ground kit Westinghouse Catalog No. GNK60 or approved substitutes.
- 2.3.8.2 600 V ac, 3-pole, 3-wire, 60 A, Westinghouse Catalog Nos. RHUN362 plus GNK60 or approved substitutes.
- 2.3.9 Tap Bus Assembly: Enclosed NEMA 3R, 3-phase, 4-wire, 600 V ac, 600 A rated, tinned aluminum or bare copper bus bars, Circle AW Catalog No. R1123HDD plus grounding lug kit, Circle AW Catalog No. 10184C or approved substitutes (see 3.2.2.4).
- 2.3.10 "Soft Start" Unit
- 2.3.10.1 The following requirements shall be satisfied:
 - a. Reduced voltage to prevent inrush.
 - b. Starting torque control up to 500% current limit for up to 20 seconds.
 - c. Controlled acceleration for extended start time (2 to 30 seconds).

- d. Controlled deceleration time (2 to 60 seconds)
- e. Jam protection
- k. Status panel.
- l. Acceleration control by voltage or current ramp
- m. Five-cycle "ride-through" capability and phase reversal/phase unbalance protection.
- n. The soft start unit shall use a minimum of 6 power switching devices for reduction of noise to the power system and smoothest input to the motor.
- o. Optional starting modes shall include Kickstart (an initial boost to the motor), full voltage start, and current limited starting.

- 2.3.10.2 ~~Enclosed, non combination motor controller sized to control the starting of a 75 HP, 480 V ac, 3 phase, 60 Hz motor. NEMA Type 1 ventilated enclosure. Allen Bradley Catalog No. 150 A97BBDA (includes "Soft Stop" option) or approved substitute. Solid State Reduced Voltage Starter, for 75 hp motor, Culter-Hammer model EA135PN, with options (Smooth Stop, Kick start, Ammeter), with associated interconnecting cables, mounted in NEMA 12 Enclosure (maximum size 36"H x 24"W x 10"D), configured as shown on elementary diagram on dwg H-2-818698, with ETL label.~~ ECN-167
- 2.3.11 Terminal Cabinet: All weather, NEMA ICS 6 Type 4, size and model as shown on the Drawings.
- 2.3.12 Terminal blocks: For Instrumentation/Control wiring, as shown on the Drawings or an approved substitute.
- 2.3.12.1 For No. 10 AWG conductors and smaller: Either 1-piece or factory-assembled sectional double terminal, barrier type, with binder screw terminals. Terminal ampacities shall be equal to or greater than conductor ampacities; Marathon or Buchanan.
- 2.3.12.2 For No. 8 AWG conductors and larger: Either 1-piece or factory-assembled sectional barrier type with box lug terminals having pressure plate between screw and conductor. Size terminals for conductors to be connected.
- 2.3.12.3 Provide covers to cover live parts of terminations for circuits of 150 V or more to ground. Provide with means for ready inspection and full width marking areas.
- 2.3.13 Equipment Rack (Inside Electrical Equipment Skid): Rack shall be field-assembled "Unistrut" channel as shown on the Drawings. Field modifications are acceptable.
- 2.3.14 Receptacles: GFCI, 15 A, 120 V, 3-wire grounding type with metal covers. Outside receptacles shall have weatherproof wallplate/cover.

- 2.3.15 Lighting: Furnish fixtures with parts and fittings necessary to install in accordance with the manufacturer's instructions.
- 2.3.15.1 Fixtures of each type described shall be from 1 manufacturer, and identical in finish and appearance.
- 2.3.15.2 Fluorescent fixture ballasts: ANSI C82.1, IEEE 587 Category A, 47 CFR 18, Subpart C; high power factor, high performance Class P, with automatic resetting thermal protection and rapid start, rated for the voltage shown on the Drawings or in this Section and suitable for fixture temperature environments. ~~Electronic ballast is for use with T8 series lamps.~~ ECN-167
ECN-167
- 2.3.15.3 Catalog numbers, when specified, are for individual units. Where 2 or more units are combined for continuous row installation, furnish necessary accessories to complete installation.
- 2.3.15.4 Fixture types: As shown on the Drawings.
- 2.3.15.5 Photoelectric cell controls: Diecast aluminum weatherproof housing with hermetically sealed light sensitive element, having manually adjustable light level slide with turn-on range of 2 footcandles, as shown on the Drawings.
- 2.3.16 Toggle Switches for Lighting Inside Electrical Equipment Skid Housing: 3-way, 15 A, 277 V ac, commercial grade, ivory color. The switches located outside shall have a weatherproof wallplate/cover.
- 2.3.17 Pilot Light: Heavy duty, standard, 120 V, 60 Hz, with red glass lens. Light illuminates when the inside lights are on.

PART 3 - EXECUTION

3.1 PREPARATION

- 3.1.1 Field Measurements: Scale dimensions on the Drawings show desired and approximate locations of equipment. Actual locations, distances, and levels shall be governed by field conditions.
- 3.1.2 Contractor shall prepare an installation procedure for installation of SC~~1~~ equipment in accordance with ASME NQA-1. The installation procedure shall be reviewed and approved by the design engineering group. See Section 01400 for witness and hold points. ECN-809

3.2 INSTALLATION

3.2.1 General

- 3.2.1.1 Perform work in accordance with NFPA 70. For the area inside the tank farm boundary fence, buried rigid steel conduits that are 4 inches and smaller are allowed to have a minimum burial depth of 12 inches in accordance with a DOE waiver approval dated August 2, 1995. Refer to the Drawings.

- 3.2.1.2 Fasten equipment to structural members of building or metal supports attached to structure, or to concrete surfaces.
- a. Use clamping devices for attachments to structural steel. When clamping is impractical, obtain approval from the Construction Engineer before drilling, punching, cutting, or welding to building structural steel members for support attachments.
 - b. Fasten equipment to concrete or masonry with expansion anchors.
 - c. Fasten equipment to metal wall panels with weld studs, bolts or self-tapping metal screws.
- 3.2.1.3 Locate equipment, boxes, and conduit approximately where shown in relation to equipment served.
- 3.2.1.4 Do not install conduit, raceways, and boxes in positions that interfere with work done by other trades.
- 3.2.1.5 Identify components with nameplates bearing legends shown on the Drawings.
- 3.2.1.6 Attach nameplates on or near equipment, with metal screws. Attach panelboard nameplates on fronts, above doors. RTV sealant may be used when screws are not practical.
- 3.2.1.7 Use appropriate calibrated special tools when installing devices for which special installation tools are recommended by the manufacturers.
- 3.2.1.8 Expansion anchors: See Section 05055.
- 3.2.2 Grounding Systems
- 3.2.2.1 Underground conductors, electrodes, and connections: Install in accordance with the Drawings. Make joints connecting copper and galvanized steel conductors above grade and in dry locations. Connections may be made with exothermic welds or Burndy Hyground connectors.
- 3.2.2.2 System and equipment grounding: Solidly ground neutral conductor of 3-wire, 1-phase and 4-wire, 3-phase, wye-connected distribution systems. Ground equipment and enclosures in accordance with the Drawings and NFPA 70.
- 3.2.2.3 Static grounding: Ground skid to the grid, as shown on the Drawings. Ground metal siding as noted on the Drawings.
- 3.2.2.4 At tap bus assembly, convert fourth "bottom" bus to a ground bus. Attach fourth "neutral" bus to enclosure and other grounds. Use "equipment" grounding lug kit listed in 2.3.9.

3.2.3 Conduit

3.2.3.1 For excavation and backfill of soil, see Section 02225.

3.2.3.2 Use rigid steel where subject to mechanical damage, or installed in concrete floors and walls, exposed to weather, or 4 feet maximum above floors. Use rigid steel where conduit is in contact with the earth. Electrical metallic tubing may be used elsewhere.

3.2.3.3 Install 14-gage galvanized steel pull wire or 1/8-inch polyethylene rope in spare conduits.

3.2.3.4 Install concealed conduits as directly as possible and with bend radii as long as possible.

3.2.3.5 Make elbows, offsets, and bends uniform and symmetrical. Bend conduit with approved bending devices.

3.2.3.6 Cut conduit ends square, ream, and remove burrs. Conduit shall be clean, dry, and free of debris. Immediately after installation, plug or cap exposed ends with standard accessories until wires are installed.

3.2.3.7 Use galvanized steel locknuts and insulated bushings for attachment to enclosures except threaded hubs or sealing type locknuts shall be used outdoors or where moisture is present. Threadless fittings are not permitted for rigid conduit. Use Erickson-type couplings where required. Do not use running threads.

3.2.3.8 Install without moisture traps wherever possible. Where practicable, provide drain holes in pullboxes or fittings at low points in raceway systems and remove burrs from drilled holes.

3.2.3.9 Flexible conduit:

a. Use to make connections to motors and other equipment subject to vibration. Use liquidtight flexible metal conduit where conduit and fittings are installed outdoors or exposed to moisture or chemical fumes indoors.

b. Use in 4 foot maximum lengths for other equipment as shown on Drawings, with approval of the Construction Engineer.

3.2.3.10 Set up joints in conduit installed in concrete, underground, or exposed to weather, with high temperature, antiseize, conductive thread lubricant and sealant.

3.2.3.11 Verify stub-up locations with final equipment arrangements. Install exposed conduit stubbing up through floor slab straight and plumb, lined up, and uniformly spaced. Install at sufficient depth below slab to eliminate part of bend above top of slab. Cap or plug stub-up before placing concrete.

- 3.2.3.12 Wrap conduit passing from concrete to air or to direct earth burial with conduit protection tape from 3 inches in concrete to 12 inches minimum in earth, or 3 inches in air.
- 3.2.3.13 Seal openings around conduit at concrete or block fire walls and floor penetrations. Use fire barrier sealing compound for openings to 1/4-inch maximum, and grout for larger openings. Make seals water-proof, and finish sealant flush with surrounding wall surfaces.
- 3.2.3.14 Apply sealing compound after installation of conductors, at boxes, in conduits that penetrate walls or floors.
- 3.2.3.15 Cover conduit installed below on-grade floor slab with 3 inches minimum of concrete.
- 3.2.3.16 Permanently label conduits at both ends with numbers shown on the Drawings. For short (10 foot maximum length) conduits, place labels at the centers only.
- 3.2.4 Underground Conduit Banks
 - 3.2.4.1 For excavation and backfill of soil, see Section 02225.
 - 3.2.4.2 Use rigid steel in sand bed, as shown on the Drawings.
 - 3.2.4.3 For single conduit runs, use rigid steel conduit in a sand bed.
 - 3.2.4.4 Install underground conduits in accordance with the Drawings and route without drains where possible.
 - 3.2.4.5 Where drains or risers are required, install in accordance with the Drawings. Seal conduit at both ends with duct sealing compound.
- 3.2.5 Boxes, Enclosures, and Wiring Devices
 - 3.2.5.1 Install boxes firmly in position and plumb.
 - 3.2.5.2 Install dust covers on junction, pull, and outlet boxes, and other types of wiring outlets at initial installation. Replace with permanent covers or devices after wires are installed.
- 3.2.6 Conductors
 - 3.2.6.1 Do not bend cables installed in raceways to less than manufacturer's recommended minimum bending radii. Bind power and control circuits separately with nylon cable ties, at 18-inch intervals. Lay cables in raceways in straight parallel lines, and avoid crossing.
 - 3.2.6.2 Use lubricant recommended by the cable manufacturer, or wire pulling compound specified, when pulling wire and cable through conduit.
 - 3.2.6.3 Do not install or handle wires with thermoplastic insulation or jacket when ambient temperature is 15°F or below.

- 3.2.6.4 Identify conductors, by wire numbers shown on the Drawings, with wiremarkers. Attach wiremarkers at termination points within 2 inches of wire terminations. Marker nomenclature shall be visible without moving wires or markers. Similarly, install "Wire Markers" at and around each wire run identified.
- 3.2.6.5 Paint or pressure-sensitive colored tape may be used for coding conductors instead of colored insulation on No. 8 AWG and larger wire for phase (ungrounded) conductors, and No. 4 AWG and larger wire for neutral (grounded) conductors and equipment grounding conductors only. Maintain phase color coding, in accordance with the following table, for branch and feeder circuits up to and including equipment connections. Use colored tape to properly code existing conductors in which the color does not comply.

Conductor Origin	Conductor	Insulation Color
480Y/277 V, 3-phase systems, transformers, panels, switchboards, etc	Phase A	Red
	Phase B	Yellow
	Phase C	Blue
	Neutral	White or Gray
	Equipment ground	Green (or bare)
120/240 V, 1-phase transformers, panels, switchboards, etc	Hot Number 1	Black
	Hot Number 2	Brown
	Neutral	White or Gray
	Equipment ground	Green (or bare)

3.2.7 Splices, Taps, and Cable Terminations

- 3.2.7.1 Make splices and taps in building wire with solderless connectors specified in 2.2.5. Use connectors in accordance with the manufacturer's instructions.
- 3.2.7.2 Use plastic insulating tape for uninsulated splices and taps. Apply tape to thickness at least equal to conductor insulation. Where bolted splice or connection presents irregular surface, apply insulating putty to joints before taping.
- 3.2.7.3 Use crimp-on type spade lugs with turned up tips for wire terminations of stranded conductors to binder screw or stud type terminals. Lugs shall have insulated sleeves.
- 3.2.7.4 Strip wires for use with pressure plate terminal strips so that no more than 1/8-inch of bare conductor is exposed after insertion beneath plate.
- 3.2.8 Electrical Equipment Skid
- 3.2.8.1 Anchor the skid/shelter to the concrete pad as shown on the Drawings.
- 3.2.8.2 Install equipment wiring as shown on the Drawings.

- 3.2.9 Motor Operated Equipment: Connect the winch and pump drive motors in accordance with the Drawings, this Section, and the manufacturer's instructions. Install wiring to devices which do not appear on the Drawings, but are included in installation shown on the manufacturer's drawings.
- 3.2.10 Variable Speed Drive
- 3.2.10.1 Install in accordance with equipment manufacturer's instructions and this Section.
- 3.2.10.2 Anchor both front and back to the electrical equipment skid floor with 2 anchors minimum, as shown on the Drawings. Ensure floor decking is secured to framing under equipment.
- 3.2.11 Seismic Shutdown System Equipment: Assemble system components on seismic concrete foundations in accordance with manufacturer's instructions. Install interconnect conduit and vendor-supplied cabling. Anchor the cabinets as shown on the Drawings and in accordance with the manufacturer's written procedure.

3.3 FIELD QUALITY CONTROL

- 3.3.1 For SC₁ Components: SC₁ equipment and materials shall be stored, handled and installed in accordance with written procedures that satisfy ASME NQA-1 requirements; see 3.1.2. ECN-809
- 3.3.2 Testing
- 3.3.2.1 Furnish equipment and instruments required to perform testing.
- 3.3.2.2 Use instruments which bear calibration stamps showing dates of calibration and expiration dates of stamps. Calibration and accuracy of instruments shall be certified by an independent testing laboratory having standards traceable to the National Institute of Standards and Technology.
- 3.3.2.3 Test the equipment grounding system for ground continuity, and measure ground resistance. Test the equipment and wiring for continuity and unintentional grounds. Verify proper phase sequence and voltage at equipment served before attempts are made to operate equipment. Notify the Quality Control Inspector before start of tests. Record the results. Additional tests for the wiring are as follows:
- a. Megger conductors rated 600 V and used for services, feeders or branch circuits over 150 V to ground, phase-to-phase, and phase-to-ground. Minimum acceptable value of insulation resistance is 200 megohms. The megger manufacturer's instruction booklet, furnished with megger, shall be used for conducting tests. Disconnect devices not capable of withstanding voltage or current of megger test, such as indicating instruments, relays and lamps, before test is made. Voltage output of megger shall be 1000 V dc nominal.

Pg 15-9

HNF-2536 Rev. 0
ECN-419
Page 159

b. ~~Test wiring operating at less than 150 V to ground for continuity and unintentional ground. Resistance shall not exceed 1 ohm on continuity checks.~~ "Test wiring operating at less than 150 V to ground for continuity and unintentional ground. Resistance shall not exceed 1 ohm for continuity checks of wiring larger than #16 AWG and 3 ohms/for wiring #16 AWG and smaller."

ECN-419

- 3.3.2.4 Calibration of overload protective devices shall be in accordance with UL 508.
- 3.3.2.5 Motors: Check for correct rotation.
- 3.3.3 Reconnect devices disconnected during testing.

Project No.	W-320
Project Title	Tank 241-C-106 Sluicing
Specification Section	16400

[illegible]

CATHODIC PROTECTION

PART 1 - GENERAL

1.1 REFERENCES

1.1.1 The following documents, including others referenced therein, form part of this Section to the extent designated herein.

1.1.1.1 American Society for Testing and Materials (ASTM)

- | | |
|------------------|---|
| C 177-85 | Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus |
| C 518-91 | Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus |
| D 1621-73 (1979) | Test Method for Compressive Properties of Rigid Cellular Plastics |
| D 1622-93 | Test Method for Apparent Density of Rigid Cellular Plastics |
| D 2842-69 (1990) | Test Method for Water Absorption of Rigid Cellular Plastics |
| D 2856-87 | Test Method for Open Cell Content of Rigid Cellular Plastics by the Air Pycnometer |
| D 3487-88 | Mineral Insulating Oil Used in Electrical Apparatus |

1.1.1.2 Federal Specifications (FS)

- | | |
|----------------------|--|
| TT-S-00230C
AMD 2 | Sealing Compound: Elastomeric Type, Single Component (For Calking, Sealing, And Glazing In Buildings And Other Structures) |
|----------------------|--|

1.1.1.3 National Electrical Manufacturers Association (NEMA)

- | | |
|-----------|---|
| WC 5-1992 | Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy |
|-----------|---|

1.1.1.4 Underwriters Laboratories (UL)

- 467-1993 Grounding and Bonding Equipment
- 486A-1992 Wire Connectors and Soldering Lugs for Use with Copper Conductors
- 486C-1992 Splicing Wire Connectors
- 510-1994 Insulating Tape
- 651-1989 5th edition, Rev. through 12/4/89 Schedule 40 and 80 Rigid PVC Conduit

1.1.1.5 National Fire Protection Association (NFPA)

- 70 (1993) National Electrical Code (NEC)

1.2 SUBMITTALS

- 1.2.1 See Section 01300 for submittal procedures.

~~1.2.2 Approval Required~~

ECN-597

~~1.2.2.1 Test Station Sketches: Before installation, submit sketches required in 3.2.3.3.~~

ECN-597

1.2.32 Approval Not Required

ECN-597

1.2.32.1 Vendor information: Before installation, submit information listed in the Vendor Information List in this Section.

ECN-597

1.3 QUALITY ASSURANCE

1.3.1 Electrical/Electronic Product Acceptability: Provide labeling and documentation in accordance with Section 01400.

1.3.2 Deliverable Documentation: The following documents and records, required by this Section, shall be delivered to Construction Document Control in accordance with Section 01720.

<u>Document</u>	<u>Paragraph</u>
Continuity Tests	3.3.1.2
Existing Pipe Exothermic Weld Documents	3.3.2.1
New Pipe Exothermic Weld Documents	3.3.2.1
Functional Test of Reference Electrodes	3.3.2.2

- 1.4 DELIVERY, STORAGE, AND HANDLING
- 1.4.1 See Section 01610 for general requirements.
- 1.5 FURNISHED EQUIPMENT
- 1.5.1 Cathodic protection rectifier and rectifier disconnect switch.

PART 2 - PRODUCTS

2.1 SUBSTITUTES

- 2.1.1 See Section 01630 for substitution approvals.

2.2 MATERIALS

- 2.2.1 Terminal Lugs: UL 486A, crimp type with ring tongue or spade lug with turned-up tips and insulated or noninsulated sleeve.
- 2.2.2 Compression Splice Connectors: UL 486C, for use with cable splice or cable tap, size as required.
- 2.2.3 Exothermic Fusion Weld Molds, Weld Metal, and Conductor Sleeve
 - 2.2.3.1 Existing Pipe: Use a or b below or approved substitute.
 - a. Low emission type mold, part number as shown in manufacturer's catalog based on conductor and pipe size, with electric starter, Erico Products "Cadweld" part number XLB971A1.
 - b. Standard type mold, part number as shown in manufacturer's catalog based on conductor and pipe size.
 - c. Weld metal: Low emission type as recommended by weld mold manufacturer with igniters and filters, or standard type "Cadweld" CA15.
 - d. Sleeve for use with No. 8 AWG conductor "Cadweld" No. CAB-133-1L.
 - e. Ensure manufacturer's installation and inspection procedures are provided with product. Procedures for "Cadweld" items are contained in Enrico Products "Installers and Inspectors Guide" (A-7D-01, 1985).
 - 2.2.3.2 New Pipe: Use a or b below or approved substitute.
 - a. Low emission type mold with electric starter, Erico Products "Cadweld" part No. XLLMCEGIH or approved substitute.
 - b. Standard type mold, "Cadweld" No. LMC, suffix based on size of conductor.
 - c. Weld metal: Low emission type, "Cadweld" No. XL, No. 90 with igniters and filters or standard type "Cadweld" No. 150.
 - d. Sleeve for use with No. 8 AWG conductor "Cadweld" No. CAB-133-1L.

- 2.2.4 Pipe Ground Clamp Connector: UL 467, bronze, size as required.
- 2.2.5 Conduit: UL 651, schedule 40, for use with test stations.
- 2.2.6 Conductors: NEMA WC 5 stranded copper, 600 V rating, high molecular weight low density polyethylene, Type "CP." Size specified on the Drawings.
- 2.2.7 Conductor Splice Kit: Epoxy potting compound for encapsulating electrical wire splices buried underground. Scotchcast Brand, Catalog No. 82-B1 or 90-B1, or approved substitute.
- 2.2.8 Tape
- 2.2.8.1 Plastic insulating: UL 510, 3/4 inch wide.
- 2.2.8.2 Electrical splice insulating: UL 510 self-vulcanizing rubber, 3/4 inch wide.
- 2.2.9 Plastic Sheet Marker: See Section 02225.
- 2.2.10 Wiremarkers: Tubular plastic, imprinted or typed with indelible ink, or plastic tags typed with indelible ink, fastened securely to wire with plastic wire ties.
- 2.2.11 Equipment Nameplates
- 2.2.11.1 Laminated plastic, 1/16-inch thick with white surface and black core.
- 2.2.11.2 Manufacturer's standard equipment nameplates may be used instead of those specified herein, if they display the required information, and are equivalent in quality and legibility. They need not be of the same material, or have the same form of imprinting.
- 2.2.11.3 Nameplate Features
 - a. Blanks: Select sizes appropriate for required characters and legends. Smooth edges and bevel 1/32-inch at 45 degrees.
 - b. Characters: Use 1/8 to 5/16-inch characters for equipment names, and 3/32 to 3/16-inch characters for other information. Engrave sharp and clear. Refer to Section 13440, Figure 1.
 - c. Legends: Provide the following information, unless otherwise specified on the Drawings. For equipment names use the generic/functional designations shown on Drawings.
 - 1) Equipment name.
 - 2) Manufacturer's identification.

3) Manufacturer's model or assembly number.

4) Serial number.

- 2.2.11.4 Make sheet steel nameplates for equipment items that do not have surfaces suitable for attachment of plastic nameplates. Make nameplates when cylindrical surfaces of adequate size are available. When not, make nametags. Provide the information required above.
- 2.2.12 Cable Marker: Metal auger, flush with grade type, 17-inch long by 6-inch circular top with raised words "CATHODIC PROTECTION." A.B. Chance Company, Catalog No. C554-0001 with installation tool, Catalog No. CWFA, or approved substitute.
- 2.2.13 Rigid Polyurethane Insulation: Sprayed foam-in-place 2-component system with minimum apparent overall density of 2.4 lb/ft³ in accordance with ASTM D 1622, approximately 95% closed cells in accordance with ASTM D 2856, water absorption approximately 0.05 lb/ft² of surface area in accordance with ASTM D 2842, "k" Factor of approximately 0.15 Btu·in/h·ft² at 75°F after aging 10 days at 140°F in accordance with ASTM C 177 or ASTM C 518, and minimum compressive strength of 45 lb/in² parallel to rise and 27 lb/in² perpendicular to rise when tested in accordance with ASTM D 1621. Polythane Systems, Incorporated urethane foam PSI-S200-25 systems, Polymer Development Laboratories, Inc 110 system, 3 lb/ft³ density, or Burtin Urethane Corporation "Byc 114," 3 lb/ft³ density, or Universal Foam Systems, Inc. 2.8 lb/ft³ density.
- 2.2.14 Survey Marker Nameplate: Brass, 2-inch diameter, 5/8-inch by 2-1/2-inch shank, Surveyors Service Company, No. 2132 or approved substitute.
- 2.2.15 Sealant: FS TT-S-00230, clear RTV silicone.
- 2.2.16 Duct Sealing Compound
- 2.2.17 Rectifier Oil: ASTM D 3487, Type II.
- 2.2.18 *Liquid epoxy coating, Scotchkote 312 by 3M Company or approved substitute.*
- 2.3 EQUIPMENT
- 2.3.1 Electrical equipment shall be PCB free.
- 2.3.2 Anodes: High silicon, chromium iron, 2-3/16 inch by 24 inch with No. 8 AWG stranded copper lead wire having high molecular weight, polyethylene (HMW PE) insulation. Lead length 20 feet. Anodes prepackaged in 8 inch by 48 inch steel canister with coke breeze backfill. Durichlor 51 Anode Company, Type TAB.
- 2.3.3 Test station, high impact plastic housing, 9 terminal removable plastic terminal board, removable green cover, 7-3/4 inches in diameter, 5 inches high, Street Fink CP Test Station, manufactured by Cott Manufacturing Company or an approved substitute.
- 2.3.4 Permanent Underground Reference Electrode: Saturated gelled copper-copper sulfate with cotton bag and backfill mix, 30 year design life,

ECN-121
ECN-121

PART 3 - EXECUTION

3.1 PREPARATION

- 3.1.1 Field Measurements: Scale dimensions on the Drawings show desired and approximate location of equipment, actual locations, distances, and levels shall be governed by field conditions.

3.2 INSTALLATION

3.2.1 General

- 3.2.1.1 Perform work in accordance with NFPA 70, this specification, and Drawings.

- 3.2.1.2 Use appropriate calibrated special tools when installing devices for which special installation tools are recommended by manufacturer.

- 3.2.1.3 For excavation and backfill of soil, refer to Section 02225.

- 3.2.2 Anodes: ~~Install to depth of 7 feet, $\pm$ 6 inches.~~ *Install vertical anodes to depth of 7 feet ($\pm$) 6 inches and horizontal anodes to depth of 4 feet ($\pm$) 6 inches.*

ECN-150

ECN-150

- 3.2.2.1 Use subsurface radar scanning machine to locate underground structures before augering. Hand auger holes for anodes that are located above or within 4 feet from underground tanks or structures. Power auger may be used for other anodes. Maximum auger size, 12 inches.

- 3.2.2.2 Lower anodes to bottom of holes by rope, and center within holes. Do not use lead wires to lower anodes. If temporary casings have been used, slowly withdraw casings while backfilling.

- 3.2.2.3 Backfill around anodes by sluicing with water.

- 3.2.2.4 Repair damaged anode lead wire insulation by encapsulation with epoxy resin using conductor splice kit.

- 3.2.2.5 Connect anode lead conductor to terminals in anode distribution box using compression type terminal lug.

- 3.2.3 Test Station: Install where shown on the Drawings. Stamp or engrave survey marker nameplate, using 3/16 inch high (minimum) letters, TEST STATION T (numbers shown on the Drawings).

- 3.2.3.1 Identify each terminal in the test station with a nameplate. Engrave with the pipe designation or words "Reference Electrode." Character height 1/8 inch. Secure nameplates to the terminal board by use of clear RTV silicone sealant.

- 3.2.3.2 Place the test station in the 6-inch PVC conduit and seal, as shown on the Drawings.

- 3.2.3.3 A field sketch of each test station shall be made to show the configuration of new and existing pipes exposed by the excavation. This sketch shall also show the proposed connection location of pipe test conductors, the location of pipe bonding jumpers (if required by the Drawings) and the location of the reference electrode.
- 3.2.4 Permanent Underground Reference Electrode: (See paragraph 3.3.2.2 for testing before installation.)
- 3.2.4.1 Follow manufacturer's installation instructions. Do not allow the reference electrode to freeze.
- 3.2.4.2 Install reference electrode horizontally, 6 to 12 inches below the outer surface of pipe. For configuration of 2 parallel pipes, install in center of configuration, and not adjacent to or touching any pipelines. Construction Engineer will assist in positioning reference electrodes if required.
- 3.2.4.3 Bring lead wire to top of hole for termination in test station and install wire marker with words: REFERENCE ELECTRODE.
- 3.2.4.4 Repair damaged lead wire insulation using conductor splice kit.
- 3.2.4.5 Backfill in accordance with Section 02225.
- 3.2.5 Pipe Test Conductors, Bonding Jumpers and Negative Return Cable
- 3.2.5.1 Existing pipes

a. Before work commences, ICF KH will verify usage of each pipe to which conductors are to be connected. If pipes are coated, cut window in coating large enough to accommodate exothermic weld mold. Wire brush each pipe and file to bright metal surface, free of oil and dirt. Make exothermic welds of conductors to metal pipe only in accordance with approved manufacturer's instructions, or use ground clamp connectors on nonprotected metal piping as directed by the Construction Engineer. If ground clamp connectors are used, coat connections using the same materials and installation methods as for exothermic welds. Install bonding jumpers across mechanical pipe joints (such as threaded couplings or bell and spigot connections) that have test conductors attached, with No. 4 AWG copper wire and exothermic weld. Extend bonds to a point 30 feet from the nearest anode.

b. Inspect exothermic welds in accordance with manufacturer's instructions. If weld fails, make another weld at least 12 inches from previous weld attempt and inspect.

c. ~~At pipe connection, apply clear RTV silicone sealant on exposed copper wire, weld material and bared pipe. Overlap sealant on copper wire insulation, on any pipe coating or on bared pipe a minimum of 1 inch. Smooth sealant by hand. At pipe connection, apply liquid epoxy coating on exposed copper wire, weld material and bared pipe. Overlap coating on any pipe coating or on bared pipe a minimum of 1 inch. Wrap exposed copper conductors with electrical splice insulating tape and plastic insulating tape.~~

ECN-121

ECN-121

d. Conductor size specified on the Drawings.

e. Repair damaged pipe test conductor insulation with 2 half-lapped layers of electrical splice insulating tape and 2 half-lapped layers of plastic insulating tape.

f. Make repairs of foam insulation on pipe with sprayed polyurethane as follows.

1) Install in accordance with manufacturer's recommended procedure.

2) Side-wall retainer may be used to assure uniform width and height of sprayed insulation. Obtain approval of retainer wall installation and materials from Construction Engineer.

3) Repair opening in flexible duct liner with plastic sheet material similar to existing.

g. Identify the end of each conductor using specified wiremarker with typewritten or imprinted pipe number to which conductor is connected. Label pipe test conductors connected to unidentifiable pipes with pipe size followed by words "UNKNOWN."

h. Use terminal lugs for conductor terminations in test station.

i. Backfill in accordance with Section 02225.

3.2.5.2 New pipes

a. Wire brush each pipe conductor standoff bracket and file to bright metal surface, free of oil and dirt. Make exothermic weld of conductors to standoff bracket in accordance with approved manufacturer's instructions.

b. Inspect exothermic welds in accordance with manufacturer's instructions. If weld fails, make another weld at least 12 inches from previous weld attempt and inspect.

c. ~~Apply clear RTV silicone sealant on all exposed copper wire, weld material and bared conductor standoff bracket. Overlap sealant on copper wire insulation, on any pipe coating or on bared surface a minimum of 1 inch. Smooth sealant by hand. Apply liquid epoxy coating on exposed copper wire, weld material and bared conductor standoff bracket. Overlap coating on any pipe coating or on bared surface a minimum of 1 inch. Wrap exposed copper conductors with electrical splice insulating tape and plastic insulating tape.~~ ECN-121

ECN-121

d. Conductor size specified on Drawings.

e. Repair damaged pipe test conductor insulation with 2 half-lapped layers of electrical splice insulating tape and 2 half-lapped layers of plastic insulating tape.

f. Identify the end of each conductor using specified wiremarker with typewritten or imprinted pipe number to which conductor is connected.

g. Use terminal lugs for conductor terminations in test station.

h. Backfill in accordance with Section 02225.

- 3.2.6 Conductors: Install anode lead, and negative return cable as follows:
 - 3.2.6.1 Place in trenches prepared in accordance with the Drawings.
 - 3.2.6.2 Identify cables, using specified wiremarkers, at terminations except at inaccessible underground locations. Nomenclature shall be as shown on Drawings.
 - 3.2.6.3 Terminate anode lead cables at anode distribution box. Use terminal lugs for conductor terminations. Terminate negative return cable as shown on the Drawings.
 - 3.2.6.4 Repair damaged cable insulation by using conductor splice kit.
 - 3.2.6.5 Cover cable ends with plastic electrical tape until ready for termination.
 - 3.2.6.6 Cable marker: Install as noted on Drawings.
- 3.2.7 Rectifier: Attach to concrete pad with concrete expansion anchors as shown on the Drawings.
 - 3.2.7.1 Terminate ac wiring on rectifier input terminals and dc wiring on rectifier output terminals.
 - 3.2.7.2 Fill rectifier with specified oil to level shown on rectifier case.
- 3.3 FIELD QUALITY CONTROL
 - 3.3.1 Continuity Testing
 - 3.3.1.1 Furnish instruments and equipment required to conduct testing.
 - 3.3.1.2 Test wiring for continuity, 1 ohm or less is acceptable. Record results.
 - 3.3.2 Exothermic Welds
 - 3.3.2.1 Document exothermic welds of conductors to new and existing pipe. Include following:
 - a. Pipe test conductor: Identification of pipe connected to and associated test station.
 - b. Bonding jumper: Identification of each pipe to which connected and general location.
 - c. Negative return cable: Identification of pipe to which connected.
 - d. Verification of a weld that is in compliance with manufacturer's installation and inspection requirements.

3.3.2.2 Functional Test of Reference Electrodes

a. Before functional test, conduct an accuracy test of 2 MC Miller Model RE-5 portable reference electrodes as follows:

1) Place end of 2 portable reference electrodes in a plastic bucket filled with tap water. Using a digital voltmeter, measure voltage between the electrodes and verify that value is less than 20 mV.

2) Place permanent reference electrodes being tested in a plastic bucket filled with tap water. Soak electrodes for at least 3 hours.

3) Place end of 1 portable reference electrode, that has been tested for accuracy in water, in the plastic bucket or touch end of portable reference electrode to outside bag of permanent reference electrode.

4) Using a digital voltmeter, measure voltage between the permanent reference electrode and the portable reference electrode. Verify that value is less than 50 mV. If difference is equal to or greater than 50 mV, discard and replace permanent reference electrode with another and repeat test.

5) Record voltage between permanent reference electrode and portable reference electrode on Data Sheet (Form KEH 2255) and submit completed form to Construction Engineer.

3.3.2.3 Perform Acceptance Test Procedure (ATP) WHC-SD-W320-ATP-002.

DISTRIBUTION SHEET

To	From	Page 1 of 1			
Distribution	JW Bailey	Date 17 July 1998			
Project Title/Work Order		EDT No. 622270			
Project W-320, 241-C-106 Sluicing, Construction Specification, W-320-C7		ECN No. n/a			
Name	MSIN	Text With All Attach.	Text Only	Attach./Appendix Only	EDT/ECN Only
JW Bailey	S2-48				
W-320 Project Files	R1-29				