

SI. 37-73

APR 9 1998 ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 624079

| | | |
|--|--|---|
| 2. To: (Receiving Organization) Distribution | 3. From: (Originating Organization) TWRS Immobilized Waste | 4. Related EDT No.: N/A |
| 5. Proj./Prog./Dept./Div.: W-464/Retrieval/TRWS | 6. Design Authority/ Design Agent/Cog. Engr.: C.A. Petersen/FDNW/R.B. Calmus | 7. Purchase Order No.: N/A |
| 8. Originator Remarks: The CDR provides the design and cost basis to provide an onsite transportation system and retrofit of the existing CSB (Bldg. 212H) to interim store Phase 1 HLW products. | | 9. Equip./Component No.: N/A |
| 11. Receiver Remarks: 11A. Design Baseline Document? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | 10. System/Bldg./Facility: 212H/CSB |
| | | 12. Major Assm. Dwg. No.: N/A |
| | | 13. Permit/Permit Application No.: N/A |
| | | 14. Required Response Date: 04/03/98 |

| 15. DATA TRANSMITTED | | | | | (F) | (G) | (H) | (I) |
|----------------------|--------------------------|---------------------|--------------------|--|------------------------|-----------------------------------|--------------------------------|-----------------------------------|
| (A) Item No. | (B) Document/Drawing No. | (C) Sheet No. | (D) Rev. No. | (E) Title or Description of Data Transmitted | Approval Designator | Reason for Trans- mittal | Originator Dispo- sition | Receiv- er Dispo- sition |
| 1 | HNF-2298 | | 0 | Conceptual Design Report for Immobilized High-Level Waste Interim Storage Facility (Phase 1) | Q | 1,2 | 1 | |
| | | | | | | | | |

| 16. KEY | | | |
|--|----------------------------|-------------------------------------|--------------------------|
| Approval Designator (F) | Reason for Transmittal (G) | | Disposition (H) & (I) |
| E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7) | 1. Approval | 4. Review | 1. Approved |
| | 2. Release | 5. Post-Review | 2. Approved w/comment |
| | 3. Information | 6. Dist. (Receipt Acknow. Required) | 3. Disapproved w/comment |
| | | | 4. Reviewed no/comment |
| | | | 5. Reviewed w/comment |
| | | | 6. Receipt acknowledged |

| 17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures) | | | | | | | | | | | |
|---|--------------|------------------|--------------------------|----------|----------|---------------|--------------|----------------------|---------------|----------|----------|
| (G) Reason | (H) Disp. | (J) Name | (K) Signature | (L) Date | (M) MSIN | (G) Reason | (H) Disp. | (J) Name | (K) Signature | (L) Date | (M) MSIN |
| 1,2 | 1 | Design Authority | C.A. Petersen | 4/3/98 | | 1,2 | 1 | R.J. Murkowski, LMHC | H6-37 | 4/3/98 | |
| | | Design Agent | N/A | | | 1,2 | 1 | R.W. Root, LMHC | H6-12 | 4/3/98 | |
| 1,2 | 1 | Cog.Eng. | R.B. Calmus, Cogoma Eng. | 4/3/98 | | 1,2 | 1 | D.L. Burt, LMHC | G3-21 | 4/3/98 | |
| 1,2 | 1 | Cog. Mgr. | K.C. Burgard, LMHC | 4/3/98 | | 1,2 | 1 | S.M. O'Toole, LMHC | G3-21 | 4/3/98 | |
| 1,2 | 1 | QA | J.F. Bores, LMHC | 4/3/98 | | 1,2 | 1 | J-N Alibert, NHC | S2-48 | 4/3/98 | |
| | | Safety | N/A | | | 1,2 | 1 | W.T. Thompson, LMHC | G3-21 | 4/3/98 | |
| 1,2 | 1 | Env. | M.L. Deffenbaugh, LMHC | 4/3/98 | | | | | | | |

| | | | |
|---|---|---|---|
| 18. Signature of EDT Originator R.B. Calmus 4/3/98 | 19. Authorized Representative for Receiving Organization K.C. Burgard 4/3/98 | 20. Design Authority/Cognizant Manager K.C. Burgard 4/3/98 | 21. DOE APPROVAL (if required) Ctrl. No. <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/comments <input type="checkbox"/> Disapproved w/comments |
|---|---|---|---|

Conceptual Design Report for Immobilized High-Level Waste Interim Storage Facility (Phase 1)

K.C. Burgard
Lockheed Martin Hanford Corp., Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200


EDT/ECN: EDT 624079 UC: UC-2000
Org Code: 73400 Charge Code: D4NKB
B&R Code: EW3130010 Total Pages: 267

Key Words: Conceptual Design Report, Project W-464, Canister Storage Building, CSB, High-Level Waste, transportation.

Abstract: The Hanford Site Canister Storage Building (CSB - Bldg. 212H) will be utilized to interim store Phase 1 HLW products. Project W-464, Immobilized High-Level Waste Interim Storage, will procure an onsite transportation system and retrofit the CSB to accommodate the Phase 1 HLW products. The Conceptual Design Report establishes the Project W-464 technical and cost basis.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.



JW Whitstrand 4/9/98
Release Approval Date

Release Stamp

Approved for Public Release

Conceptual Design Report

Immobilized High-Level Waste Interim Storage Facility (Phase 1)

Project W-464

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the
U.S. Department of Energy under Contract DE-AC06-96RL13200

W464CDR
CONCEPTUAL DESIGN REPORT
FOR
IMMOBILIZED LOW-ACTIVITY WASTE INTERIM
STORAGE FACILITY PROJECT
(PHASE I)
PROJECT W-464

Prepared by
Fluor Daniel Northwest, Inc.
Richland, Washington


Principal Lead Engineer

3/27/98
Date


Quality Engineering

3/27/98
Date


Project Manager

3/27/98
Date

TABLE OF CONTENTS

| | | |
|-------|---|----|
| I. | INTRODUCTION/BACKGROUND | 1 |
| II. | SUMMARY | 12 |
| III. | JUSTIFICATION | 19 |
| IV. | DESCRIPTION OF PROJECT SCOPE | 20 |
| A. | IMPROVEMENT TO LAND (460) | 20 |
| B. | BUILDINGS (501) | 20 |
| C. | SPECIAL EQUIPMENT AND PROCESS SYSTEMS (700) | 42 |
| E. | DESIGN COMPLIANCE | 47 |
| V. | METHODS OF PERFORMANCE | 47 |
| A. | ARCHITECT-ENGINEER WORK (WBS 1.A AND WBS 1.C) | 47 |
| B. | ONSITE PROJECT INTEGRATOR (WBS 1.D) | 48 |
| C. | PROCUREMENT (WBS 2.0) | 48 |
| D. | CONSTRUCTION (WBS 3.0) | 49 |
| E. | PROJECT INTEGRATION (WBS 4.0) | 49 |
| F. | OTHER PROJECT COSTS (WBS 5.0) | 49 |
| VI. | REQUIREMENTS AND ASSESSMENTS | 49 |
| A. | SAFEGUARDS AND SECURITY | 49 |
| B. | HEALTH AND SAFETY | 50 |
| C. | DECONTAMINATION AND DECOMMISSIONING | 51 |
| D. | PROVISIONS FOR FALLOUT SHELTERS | 51 |
| E. | MAINTENANCE AND OPERATION REQUIREMENTS | 51 |
| F. | AUTOMATED DATA PROCESSING EQUIPMENT | 52 |
| G. | QUALITY ASSURANCE AND SAFETY CLASSIFICATION | 52 |
| H. | ENVIRONMENTAL COMPLIANCE | 53 |
| I. | PERMITS | 55 |
| VII. | IDENTIFICATION AND ANALYSIS OF UNCERTAINTIES | 56 |
| A. | STRUCTURAL | 56 |
| B. | HEATING, VENTILATING, AND AIR CONDITIONING | 56 |
| VIII. | REFERENCES | 57 |
| A. | DOCUMENTS | 57 |
| B. | SKETCHES | 61 |

APPENDICES

- Appendix A. Work Breakdown Structure
- Appendix B. Budget Authorized/Budget Outlay Schedule
- Appendix C. Cost Estimate Summary
- Appendix D. Conceptual Project Schedule
- Appendix E. Outline Specification
- Appendix F. Energy Conservation Report and Analysis
- Appendix G. Preliminary Safety Evaluation
- Appendix H. Economic Analysis and Life Cycle Cost Analysis
- Appendix I. Physically Handicapped Assessment
- Appendix J. Plant Forces Work Review
- Appendix K. Compliance Matrix
- Appendix L. Sketches

ABBREVIATIONS AND ACRONYMS

| | |
|---------|--|
| ACD | advanced conceptual design |
| ALARA | as low as reasonably achievable |
| BNFL | British Nuclear Fuels Limited |
| CDR | conceptual design report |
| CFR | Code of Federal Regulation |
| CSB | Canister Storage Building |
| DBE | design basis earthquake |
| DOE | U.S. Department of Energy |
| DRD | design requirements document |
| DWPF | Defense Waste Processing Facility |
| Ecology | Washington State Department of Ecology |
| FEIS | Final Environmental Impact Statement |
| FFTF | Fast Flux Test Facility |
| FHA | fire hazards analysis |
| FSAR | final safety analysis report |
| HCA | hot conditioning annex |
| HCSA | hot conditioning system annex |
| HLW | high-level waste |
| HVAC | heating, ventilating, and air conditioning |
| HWVP | Hanford Waste Vitrification Project |
| IHLW | immobilized high-level waste |
| JSA | job safety analysis |
| LAW | low-activity waste |
| MCO | multi-canister overpack |
| MHM | multi-canister overpack handling machine |
| MPFL | maximum possible fire loss |
| NEPA | National Environment Policy Act |
| NFPA | National Fire Protection Association |
| NOI | notice of intent |
| NRC | Nuclear Regulatory Commission |
| OSHA | Occupational Safety and Health Administration |
| PGA | peak ground acceleration |
| PHMC | Project Hanford Management Contractor |
| PSAR | preliminary safety analysis report |
| PSE | Preliminary Safety Evaluation |
| QA | Quality Assurance |
| QAPD | Quality Assurance Program Description |
| QAPP | Quality Assurance Project Plan |
| QARD | Quality Assurance Requirements and Description |
| RCRA | Resource Conservation and Recovery Act |
| RL | Richland Operations Office (DOE) |
| ROD | Record of Decision |
| SAR | Safety Analysis Report |
| SC | safety class |

ABBREVIATIONS AND ACRONYMS (continued)

| | |
|-------|---|
| SCT | shielded canister transportation system |
| SNF | spent nuclear fuel |
| S/RID | standard/requirements identification document |
| SRS | Savannah River Site |
| SSI | soil structural interaction |
| TRIGA | Test Reactor and Isotope Production General Atomics |
| TWRS | tank waste remediation system |
| WAC | Washington Administrative Code |
| WBS | work breakdown structure |
| WDOH | Washington State Department of Health |
| WVDP | West Valley Demonstration Project |

CONCEPTUAL DESIGN REPORT

**IMMOBILIZED HIGH-LEVEL WASTE
INTERIM STORAGE FACILITY (PHASE 1)****PROJECT W-464****I. INTRODUCTION/BACKGROUND**

As part of the Tank Waste Remediation System Program, managed by the Project Hanford Management Contractor (PHMC), the U.S. Department of Energy (DOE) has embarked on a course to acquire Hanford Site tank waste treatment and immobilization services using commercial facilities. These will be privately developed, financed, constructed, owned, operated, and deactivated (Reference 5). The successful bidders (i.e., vendor or team of vendors awarded a contract) are to be paid for the immobilized Hanford Site tank waste (product) that they have produced, thereby recouping their investment. This plan uses a two-phased approach. Phase 1 is proof-of-principle and commercial demonstration-scale effort and Phase 2 is a full-scale production effort. The referenced contract (Reference 28 and 29) describes the privatization process for both phases. Contracted work is only for the conceptual design of the Phase 1 facilities, termed Phase 1A. Follow-on contracts will be prepared for the definitive design, construction, and operations portion of Phase 1 work scope, Phase 1B. A separate contract will be prepared for Phase 2 work.

The primary purpose of Phase 1 is to demonstrate the technical and business viability of using privatized facilities to treat and immobilize Hanford Site low-activity waste (LAW) and high-level waste (HLW). This is to be accomplished using demonstration facilities (i.e., low-capacity immobilization plants) based on the successful bidder's design. PHMC planning assumes that two LAW demonstration

vitrification plants and one HLW demonstration vitrification plant will be constructed during Phase 1. In addition, it is assumed that one LAW and one HLW production facility (i.e., high-capacity immobilization plants) will be designed, constructed, and operated during Phase 2. These production facilities are assumed to provide sufficient capacity to immobilize the remaining Hanford Site tank waste.

In accordance with the solicitation of Phase 1, services, transportation, interim storage, and disposal of various products from the demonstration plants are to be provided by the DOE. The Phase 1 products requiring interim storage in the Canister Storage Building (CSB) include immobilized high-level waste (IHLW) or vitrified HLW (glass), separated cesium from the LAW vitrification plant feed (dry free-flowing powder most likely cesium adsorbed onto an inorganic ion-exchange resin) hereafter referred to as Cesium Product, and non-routine HLW (i.e., failed melters and other equipment contacting the HLW products which cannot be practically decontaminated). The Phase 2 HLW products are canisters of IHLW from the balance of high-level tank waste. The Phase 2 IHLW will contain the contents of the cesium canisters generated in Phase 1. The tank waste remediation system (TWRS) program has established a construction project, project W-464, *Immobilized High-Level Waste Interim Storage Facility (Phase 1)*, to provide the capability to interim store the Phase 1 HLW products until they can be transferred to a federal geologic repository for disposal (IHLW and non-routine HLW) or processed further (cesium canisters incorporated into Phase 2 IHLW product).

The selected Phase 1 architecture entails outfitting the spent nuclear fuel (SNF) CSB, constructed under project W-379, to interim-store solidified HLW (References 3 and 30). The SNF Project and project W-464 established an MOA (Hansen) that assigned CSB Vaults 2 and 3 to the IHLW Interim Storage Project. Functions and requirements for the interim storage of Phase 1 HLW products in the CSB were established (Reference 31) and serve as the basis for the Phase 1 Project W-464 Design Requirements Document (DRD) (Reference 2). The DRD

lists applicable constraint documents (i.e., *U.S. Code*, *Code of Federal Regulations*, *Washington Administrative Code* [WAC], DOE directives and standards, and other DOE requirements) and requirement documents (i.e., federal and state codes and standards and Hanford Site standards and miscellaneous documents) and provides system and performance requirements specific to Phase 1 HLW products and quality assurance (QA) provisions. These requirements and QA provisions are the basis for Phase 1 transportation system and CSB conceptual design. The DRD will require revision prior to initiation of the Phase 1 project W-464 definitive design phase to incorporate information developed by the Phase 1 privatization contractors during the Phase 1A contract period (conceptual design). Interface control documents have been established to outline interface activities between the IHLW Interim Storage Project and the private contractors. A detailed discussion of the project W-464 system engineering approach, project integration, interface control documents, and project mission and objectives is provided in the Project W-464 Project Plan (Reference 32).

The CDR was prepared in accordance with the ICF Kaiser Preparation Guides for Engineering Documents, (Reference 27). This document includes guidance for CDR preparation based on compliance with DOE Order 4700.1.

Existing Canister Storage Building (constructed under SNF Project, W-379)

The CSB is located in the 200-East Area of the Hanford Site, approximately 48 km (30 mi) northwest of Richland, Washington. It consists of 3 belowgrade, concrete vaults approximately 15.24 m (50 ft) wide by 41.15 m (135 ft) long by 12.50 m (41 ft) deep. SNF will be stored in the northernmost vault, Vault 1. The CSB structure includes a steel metal building 41 m (134 ft 6 in.) wide by 62 m (203 ft 6 in.) long by 17 m (55 ft 9 in.) tall. The metal building provides an operating area for SNF load-in/load-out. A metal building 15 m (49 ft 3 in.) wide by 37 m (121 ft 5 in.) long by 9 m (29 ft 6 in.) tall houses the mechanical, electrical, and support services. The SNF load-in/load-out area contains two service pits. One is designed specifically for transferring multi-canisters overpacks (MCOs) containing SNF from the onsite

transport cask to the CSB shielded handling machine, referred to as the MCO handling machine (MHM). The second pit is much larger and is designed to accommodate service/transfer of larger SNF packages [i.e., Test Reactor and Isotope Production General Atomics (TRIGA) and Fast Flux Test Facility (FFTF) SNF.

The vaults are covered by a concrete deck and each vault has concrete air plenums on opposite sides. The below-deck concrete partition walls allow independent vault cooling. The northernmost vault, Vault 1, is equipped with carbon steel tubes installed vertically and an air intake and exhaust stack. Storage tubes and intake/exhaust stacks will not be installed in Vaults 2 and 3 as part of project W-379.

Each vault can provide for a storage tube matrix of 22 rows by 10 columns for a total of 220 storage tubes. Each vault can also accommodate six larger diameter tubes for canister overpack. Both the standard and overpack tubes can accommodate two 4.5 m (14-ft 10-in.)-tall by 0.61 m (2-ft)-diameter IHLW canisters and impact limiters at the bottom of the tube and between the canisters. A storage tube provides approximately 11.1 m (36 ft 6 in.) of vertical storage space with a 0.68 m (27-in.) internal diameter. The storage tubes are designed to be closed and sealed with a shielded plug installed at the deck level and a 1.27 cm (½-in.) plate seal-welded to the bottom of the tube. No shield plugs have been designed for or are provided for Vaults 2 and 3 as part of project W-379.

Each vault is designed to allow decay heat to be removed by natural convection. Cooling air is drawn through an inlet duct into a plenum that feeds each vault, flows across the outer surface of the storage tubes, and exits through an elevated exhaust stack that serves the vault. Buoyancy, caused by the different densities of hot air inside the vault and stack, draws cooling air through the vault.

An annex to the southernmost vault, Vault 3, is included as part of project W-379. The SNF annex is referred to as the hot conditioning annex (HCA) and provides the capability to sample gases generated during storage and seal weld the MCOs for long-term interim storage.

The HCA is a reinforced concrete structure that houses mounting plates for the process modules and seven process pits for HCA equipment. The HCA operating deck is 10.7 m (35 ft 3 in.) by 42.3 m (138 ft 11 in.) by 1.5 m (5 ft) thick; the reinforced concrete slab is supported at grade level.

The SNF CSB design does not include a wet-pipe sprinkler system because it has been determined that significant combustible loading does not exist, and the transient combustible loading is controlled, and a sprinkler system would be of minimal benefit. The CSB safety support functions are provided by backup electrical power and fire protection and monitoring systems.

CSB and Transportation System Features Required to Interim Store Phase 1 HLW Products

Use of the CSB for interim storage of Phase I HLW will require installation of equipment and subsystems that are not needed for storage of SNF. The existing CSB will also need to be modified. The transportation system, CSB modifications, and CSB equipment retrofit modifications and added equipment will be designed and constructed in accordance with the project W-464 design basis (References 2 and 26).

The following transportation system and CSB features will be required to support project W-464 objectives:

- A tractor/trailer/shielded-cask system must be procured and be capable of transporting the Phase 1 HLW products from the private contractors facilities to the CSB. The cask must meet all onsite transportation requirements and

provide adequate cooling and shielding of the HLW products. The cask containing HLW product will be transported in a vertical orientation.

- A receipt/unloading area capable of housing the onsite transport system during cask unloading will be provided. This area will also include a transfer pit with ancillary equipment to remotely remove (or replace) the cask lid and store the cask lid during remote transfer of the HLW product from the cask to a CSB HLW canister handling system.
- Provide handling equipment necessary to support transfer operations.
- A shielded handling system and control equipment necessary to lift the HLW products from the onsite cask in the receipt/handling pit into the CSB handling system, transfer the HLW product to any storage tube location within the Vault 2 and 3 storage tube matrix and HLW overpack station (HCA Pit No.# 7), and emplace (or retrieve) the HLW product from the storage tube and overpack pit. This handling system must be capable of handling the 4.5 m long by 0.61 m dia. IHLW and non-routine HLW canisters produced by the HLW private contractors. In addition, the system must be capable of handling the 1.37 m long by 0.33 m dia. cesium canisters, generated by the ILAW private contractor(s) overpacked in a government supplied 4.5 m long canister with critical dimensions and handling features identical to the 4.5 m IHLW canisters. The private contractor will place the cesium canister in the overpack, close the overpack, and place the overpack in the project W-464 shielded onsite transport cask.
- Provide Vaults 2 and 3 (step tube design versus SNF straight tube design) storage tubes, tube shield plugs, tube impact absorbers (e.g., for potential or high-risk canister drop conditions); and cesium canister-handling assemblies.

- Provide CSB facility/structures and equipment to allow canister cooling in accordance with HLW product temperature requirements. This includes addition of inlet/exhaust stacks, temperature and flow monitoring equipment and any other equipment necessary to provide sufficient design margins to ensure canister temperatures are within threshold values.
- Provide CSB instrumentation and control systems; remote operating equipment, welding machines, shielding, and maintenance and other equipment needed to perform HLW product overpack operations in the event of an off-normal breach of the HLW product canister during onsite transportation or CSB handling operations.
- Provide utility services to allow performance of project W-464 construction and operations activities.

Conceptual Design - Constraints

To support the project W-464 objectives, a number of important design constraints were established and implemented by Fluor Daniel Northwest (FDNW), with PHMC concurrence in developing the project W-464 conceptual design. These design constraints were developed with the intent to more fully define the constraints associated with retrofit of the CSB, especially with the necessary integration with SNF operation. In addition, these design constraints were used to develop design solutions in accordance with the general design requirements identified in the project W-464 DRD. This more detailed subset of the design constraints will be included in future revisions of the DRD for definitive design, where necessary.

The subject design constraints used in the conceptual design effort are as follows:

- The project W-464 design will allow for SNF storage operations, safety, and security, according to current SNF schedules.

APPROVAL

HNF-2298, Rev. 0

- No mixing of the different HLW products in an individual storage tube will be allowed (i.e., an individual tube can contain only either IHLW, cesium, or non-routine HLW canisters)
- Design, equipment, and construction practices will be according to industry standards for nonreactor nuclear facilities.
- To the extent practical, the most conservative design approach will be implemented where SNF and HLW design requirements are found to be conflicting.
- The SNF design strategies relative to radiological monitoring, fire hazards mitigation, temperature and air flow monitoring, and canister tracking system will be adopted by project W-464.
- The project W-464 transportation system and CSB design will be developed to provide HLW product centerline temperatures less than 400 °C. For the IHLW product, this requirement is required for disposal in the federal repository. This requirement will also be imposed on the non-routine HLW and cesium product.
- The IHLW 4.5-meter canister will include the same neck configuration as the West Valley Demonstration Project (WVDP) canister. The private contractors may propose one of three IHLW canister configurations using either a WVDP canister neck, a SRS canister neck, or another private contractor qualified neck design. The WVDP canister will be used as the basis for CSB HLW handling equipment design because the WVDP design is a qualified, proven design and allows greater glass capacity per canister.

- The canisters will not be designed to be stacked or to withstand a drop of one canister on top of another. The storage system will be designed to mitigate impacts of credible canister drop conditions.
- The existing CSB MHM crane will be parked at the north end of the CSB during the HLW shielded canister transporter (SCT) operation (no combined loading of the MHM crane and SCT will be on the operation deck at any time).

Programmatic Assumptions

A number of important programmatic assumptions were also generated for use in developing the conceptual design. These assumptions are as follows:

1. High temperature insulating concrete will be installed in Vaults 2 and 3 by project W-379. Installation of the subject concrete is included in project W-379 scope via baseline Change Request W379-025 W-379, *SNF Canister Storage Building*. The cost of adding insulating concrete is not provided in the cost estimate.
2. Project W-464 will not inherit any compliance or technical issues as a result of project W-379 design. The type and degree of issues cannot be assessed at this time. It is reasonable to assume that SNF project W-379 will comply with the respective project requirements.
3. Loading of HLW product canisters into the CSB will not commence until all project W-464 construction activities are completed. Preparation of the design/construction schedule is constrained by hot start-up.
4. HCA Pit No. 7 will be available for project W-464 overpack operations. Pit No. 7 is needed to accommodate the SCT.

5. The construction of the intake and exhaust structure for Vaults 2 and 3 will not be constrained by SNF operations and work can be performed on day shift.
6. SNF MCO sampling and welding operations will require movement of the SNF MHM over Vaults 2 and 3 during installation of project W-464 storage tubes. The subject SNF operations can be performed in two shifts and will allow a minimum of one shift per day to install project W-464 tube assemblies (storage tube, base plate, and bellows). If SNF sampling and welding operations require more than 2 shifts, the ability to install Vaults 2 and 3 tubes could be impacted.
7. The PHMC will amend the Authorization Basis to the CSB to satisfy project W-464 objectives.
8. Studies relative to early procurement of the project W-464 transportation system and long-lead items required for CSB retrofit and thermal and structural analysis will be performed in the advanced conceptual design (ACD) phase prior to initiation of definitive design activities. Project W-464 assumes information will be received from private contractors subsequent to completion of the CDR will be evaluated and impacts assessed in ACD. The DRD will be revised to reflect the design requirements used in preparing the CDR and private contractor information. Information required to revise the DRD is necessary prior to the start of definitive design.
9. No testing of the standard storage tube bellows will be required since project W-464 will use the same bellows used in Vault 1.
10. The characteristics of the 4.5 meter IHLW canister was provided as a supplement to the DRD used as the basis for project W-464 CD (Reference 26). The 4.5 meter canister information was developed based

APPROVAL

HNF-2298, Rev. 0

on the latest (best available information) discussion between U.S. Department of Energy, Richland Operations Office (RL) staff and the federal geologic repository program. It is assumed that the Repository acceptance criteria will be revised to reflect this information.

11. Interior work on project W-464 abovegrade retrofits required before July 1, 2001, will be executed on an off-shift coincident with SNF operations to meet schedule for hot start-up.
12. Approval of the preliminary safety analysis (PSAR) (modified SNF final safety analysis report[FSAR]) prior to start of construction is required in accordance with DOE 6430.1A. The unresolved safety question (USQ) process will be used as applicable.
13. The allowable cesium product temperature has not been formally established at this time but is expected to be near 1000 °C based on adsorption of the cesium on commercially available inorganic ion exchange resins which are currently used (i.e., Zeolite IE-96) or being considered (crystalline silicotitanate or CST) for treatment of radioactive cesium.
14. Thermal evaluations relative to loaded cesium overpack were based on use of a single wall (single air gap) cesium canister design. The thermal evaluations were performed using a 1500 watt cesium canister heat load. This heat load cannot be obtained due to more restrictive dose rate contract requirements. If a double wall (two air gaps) cesium canister design is proposed by the private contractor, the heat load condition associated with the maximum 10^3 Sv gamma and 10^2 Sv neutron dose rate will need to be evaluated but is not expected to present an unacceptable heat load condition based on a higher acceptable centerline temperature.

15. A key permitting assumption identified in the Project W-464 Permitting Plan (Reference 17) is that a Resource Conservation and Recovery Act (RCRA) Part B (final) permit will not be required prior to hot operations. Interim status will be granted.
16. The HLW product characteristics relative to physical configuration and design of canisters and product information, specifically population heat load and source term, will be obtained from the private contractors (HLW and LAW) based on Phase 1 tank waste data/information and in support of definitive design activities. The project W-464 design requirements include very conservative design activities. The project W-464 design requirements include very conservative (worst case) design assumptions relative to HLW product source terms and heat loading. The DRD requirements used in the CDR significantly influence design of project W-464 equipment, primarily the CSB handling equipment.

II. SUMMARY

Project W-464 will procure two new integrated transport systems (includes tractor/trailer and shielded cask) to transport the Phase 1 HLW products from the private contractor facilities to the CSB. The system will consist of a low-boy trailer and transport cask to transport the HLW products vertically with appropriate cask/trailer constraints. The cask will be designed to maintain the HLW products below the maximum temperature requirements and provide shielding in accordance with Hanford Site transportation requirements.

In addition, project W-464 will modify the SNF CSB design to accommodate interim storage of Phase 1 HLW products in Vaults 2 and 3 of the CSB. The major modifications and additions to the CSB and associated equipment include the following:

HLW Load-in/Load-out Annex

A new HLW Load-in/Load-out Annex will be added to the southeast corner of the CSB to provide for receipt of the HLW transport system, unloading of the onsite transfer cask, remote handling of the HLW product during HLW product unloading from the cask, transfer of the HLW product from the cask to the CSB HLW handling system and maintenance of the CSB HLW handling system. The HLW Load-in/Load-out Annex will consist of a concrete slab abutting the CSB HCA operating deck, a 60-ton gantry crane for cask handling, steel superstructure and a transfer pit similar to the SNF MCO transfer pit. In addition the Load-in/Load-out Annex transfer pit will allow for maintenance of the CSB HLW handling system. The Annex will also include a new HVAC system which will include addition of two exhaust fans and filter housing assembly. Operation of cask transfer will require use of a 10-ton remote operated bridge crane located below the shield plug. The bridge crane will remove the cask lid and position it such that transfer activities can be performed. Construction of the new Annex will require rerouting of existing CSB conduit on the south wall of the CSB. The 60-ton receipt gantry crane will be designed and constructed to the same general requirements imposed on design of the SNF 60-ton receipt gantry crane. The Annex structural and building features will be designed and constructed to the same requirements imposed on the SNF receipt/transfer station. A new road supporting the new Load-in/Load-out Annex will also be added.

CSB HLW Handling System

A new handling system will be procured to handle HLW products in the CSB. The CSB HLW handling system will be similar to the handling system used to transfer HLW product canisters at The Savannah River Site (SRS) Defense Waste Processing Facility (DWPF). The DWPF system utilizes a SCT mounted on rubber tires with hydraulic systems for propulsion, raising and lowering the shielded cask, and steering and braking. The DWPF unit is powered by both diesel and electric motors. This system is designed to handle SRS 3.0-meter HLW canisters. The design will be modified to accommodate the longer Hanford 4.5-meter HLW

canisters and HLW product canister configuration. The DWPF system is currently being used to transfer radioactive SRS HLW canisters and relative to this CDR is considered a proven, commercially available, system. This system concept will be used to emplace Hanford HLW canisters in Vaults 2 and 3 storage tubes and overpack station (HCA Pit No. 7) and will provide the flexibility to emplace HLW canisters in conjunction with SNF operations. Originally, the existing SNF MHM was evaluated to accommodate Phase 1 HLW product canisters. Though the MHM may be potentially viable from a technical standpoint, schedule constraints due to SNF operations precluded use of the MHM; therefore, the SCT was selected as the CSB HLW handling system.

Integrated Storage System

An integrated storage tube system will be added to the Vault 2 and 3 standard and overpack storage tube operating deck penetrations (440 standard tube locations and 3 overpack storage locations - see Summary discussion relative to outfitting of IHLW overpacks). The integrated storage system includes the storage tube assemblies (bellows and carbon steel storage tubes), tube shield plugs, tube impact absorbers and tube base assemblies. The storage tubes will be a step tube design to allow for impact absorbers between canisters. The bottom impact absorber will be designed to allow for a full canister drop condition (canister raised to maximum SCT internal height and drop to bottom of tube). The impact absorber between the canisters will rest on the seat of the storage tube step and will accommodate a canister drop to the respective elevation. Project W-464 will provide 10 impact absorbers, the remainder will be provided by Operations.

The bellows/tube assemblies will be brought into the CSB through the existing SNF HCA load-in bay doors and will require a portable crane to rotate the assembly into an upright position and to install the tube assemblies into the operating decks tube penetrations. No other significant construction equipment is required to install the tube assemblies. During conceptual design, the SNF straight tube design was evaluated for Vaults 2 and 3. The straight tube design resulted in the use of

complex impact limiter designs to mitigate the drop of a canister on top of a canister located in the bottom tube position. The selected CDR concept adopts use of the step tube design which results in a simpler impact limiter design.

Natural Convection Cooling and Shielding System

The IHLW produced by the private contractor, responsible for vitrification of the Phase 1 HLW tank waste, must meet a Repository requirement that the canister centerline temperature not exceed 400 °C. Compliance with the Repository temperature requirement is also required for all project W-464 unit operations. Therefore, the project W-464 transportation system and CSB equipment and associated operations must also be designed such that the IHLW canisters do not exceed the subject repository requirement. The CSB HLW receipt/transfer pit, SCT system and storage vault design will provide adequate cooling of the IHLW canisters. The storage vault design is the primary control for HLW product cooling. Project W-464 will add the following vault equipment to provide adequate HLW product cooling. Appropriate sized inlet and exhaust stacks will be designed and constructed to allow cooling air to be drawn through each of the two vaults. Evaluation of the SNF Vault 1 natural convection system (inlet and exhaust stacks) was performed to determine if the SNF stacks provide adequate cooling of HLW products. This system is adequate and is the adopted basis for Vaults 2 and 3 inlet/exhaust stack design. In addition, air foils will be added on vault walls to direct air flow away from the vault walls to the vault storage tube matrix.

Louvers will be added to the exhaust section to reduce radiation sky shine to meet operating deck and environmental radiological requirements. Insulating concrete, added as part of project W-379, will provide protection of the structural concrete from Vaults 2 and 3 thermal conditions. The insulation concrete will also provide additional shielding protection for workers installing Vault 2 equipment (louvers, air foils, tube assemblies and tube base plates). Shielding evaluations have been

performed that indicate that the shared structural wall between Vaults 1 and 2 provides shielding protection; the insulating concrete provides yet another level of shielding protection.

HLW Overpack Station

The SNF HCA Pit No. 7 design was evaluated for use as the HLW overpack station and was determined capable of performing the HLW overpack operation. Pit No. 6 will be covered to permit adequate clearance for the SCT. The following equipment will be added to provide the HLW overpack capability: remote pit shield gate, welding equipment and ancillary support equipment, and equipment necessary for smear testing of welded canister. The SNF MCO welding concept provides the basis for the CSB HLW overpack welding system.

Cesium Product Handling Assembly

Two cesium overpacks will be designed and fabricated as part of project W-464. The balance of cesium overpacks (151) will be provided as part of CSB HLW operations. The cesium overpacks will be designed to shield the cesium product to that of the IHLW canisters. The CSB HLW SCT will be designed to provide shielding for the maximum IHLW product source term. In addition, the cesium overpack will include overall dimensions and handling features identical to the IHLW 4.5 m canister produced by the private contractor. The CSB handling system design is based on use of the WVDP canister neck design.

4.5 Meter Canister Overpack

Two 4.5 meter canister overpacks will be provided by project W-464 in the event that a IHLW or non-routine HLW canister is breached during an off-normal event. The canisters will be designed to allow for the IHLW canister to fit into the overpack providing for IHLW canister and overpack canister design tolerances. The overpack canister will have essentially the same overall design, excluding overall canister diameter, as the 4.5 IHLW canister including a WVDP neck design identical to the IHLW canister (ES-W464-M09) (sketches are shown in Appendix L).

Three overpack tubes will be outfitted to provide for overpack of approximately 1% of total number of IHLW and non-routine HLW canisters produced during Phase 1. Storage tube shield plugs will be provided for the remaining nine overpack deck penetrations. Thermal evaluations of the vault cooling system included consideration of the IHLW overpack.

CDR Design Basis - Viability of Shielded Canister Transporter Concept

There is a high confidence that the SCT can be designed and operated in the CSB to safely perform the project W-464 handling function. The conclusion is based on the conservative structural evaluation performed as part of this CDR and the expected reduction of heat load and shielding requirements based on actual Phase 1 tank waste data.

- **Structural Evaluation**

A conceptual design evaluation was performed to ascertain the viability of utilizing the SCT in conjunction with the existing CSB Vaults 2 and 3 design. The evaluation was performed considering the structural and seismic response associated with SCT operation. Thermal conditions used in the evaluation included SNF maximum vault heat loads (192 kW) in lieu of higher HLW product maximum vault heat loads (556 kW) specified in DRD supplements. The evaluation also included the weight of the SRS SCT with an additional 15% weight increase to account for modification of the SCT to accommodate the 4.5 m canister and included conservative structural design input information (see list of conservative inputs in Section IV.B, Concrete). The evaluation indicates that in some specific cases, the design margin is 1% to 2% too high. A detailed structural analysis including HLW heat loads needs to be performed in the ACD phase to confirm use of the SCT. More reasonable (less conservative) structural design constraints will also be used.

Heat Load and Shielding

The CDR SCT structural evaluation was based on design of an SCT capable of safely handling the Phase 1 HLW products based on product requirements provided in the DRD. The heat load associated with HLW products and required shielding of the products to allow safe operation in the CSB are major factors considered in the design of the SCT and in the evaluation of the deck to support SCT operation. Preliminary evaluations of the heat load and radionuclide inventories expected to be produced by the private contractor are well below the heat load and associated source terms provided in the DRD. The DRD requirements are based on heat load and shielding requirements included in the contract established between DOE and the private contractors. As an example, the cesium heat load design basis used in the CDR is 1500 watts; however, the contract dose rate requirement will limit the heat load to less than 900 watts, with a coincident reduction in radionuclide content. It is also important to note that shielding of the individual cesium canister can be provided by an overpack design specifically designed for storage in the CSB. In addition, the 4.5 m canister heat load design basis is 2450 watts. However, assessment of Phase 1 tank waste data results in a maximum heat load of 850 watts which also results in a much lower (approximately linear) radiation source term. Using the same conservative vault loading strategy used to develop the CDR maximum vault heat load case (556 kW), a vault heat load, calculated using actual tank waste data and containing both IHLW and cesium canisters, is projected to be 150 kW.

Based on receipt of formal private contractor confirmation of the expected HLW product heat loads and source terms, it is assumed that the project W-464 DRD will be revised, with DOE approval, to include more accurate heat load and source term requirements specific to the interim storage function.

The new requirements would allow for design of a much lighter SCT (less shielding required and corresponding reduction in SCT support equipment size and weight) and will significantly increase the operating deck load capacity due to the reduction of thermally induced stresses.

Other General Summary Discussion

Constructibility assessments were performed relative to the identified CSB modifications and equipment retrofits; no significant construction or construction permitting issues were identified.

Procurement of the project W-464 onsite transportation system and identified CSB modifications and equipment retrofits can be accomplished in accordance with a June 2002 CSB radioactive start date.

The rationale relative to the RCRA permit is presented in the Project W-464 Permitting Plan.

Cost estimates and bases for project W-464 design, construction, facility startup, operations and facility closure are provided in this CDR. Project W-464 is a fiscal year 2000 Line Item. Total estimating engineering and construction costs of the project are \$84,700,000; expense funded support costs are \$19,400,000. The total project cost is \$104,100,000.

III. JUSTIFICATION

The retrofit modifications and new installations provided by project W-464 for the SNF CSB supports the TWRS program, the DOE's privatization initiative and, in turn, supports the Tri-Party Agreement milestones for site clean-up, processing, and disposal of the Hanford tank wastes.

IV. DESCRIPTION OF PROJECT SCOPE

A. IMPROVEMENT TO LAND (460)

The existing two-lane service road with an HS-20 load capacity that is planned to service vehicle traffic to the CSB load-in/load-out area and loading/staging area will be extended south and east to the HLW Load-In/Load-Out Annex. A truck maneuvering area south of the main entrance to the Load-In/Load-Out Annex will also be provided. An existing fire hydrant south of the CSB will be removed and replaced as required by the roadway extension.

B. BUILDINGS (501)

1. Existing Canister Storage Building Modifications

Structural

Project W-464 will utilize Vaults 2 and 3 of the SNF CSB. The modifications required by the project to the structural systems of Vaults 2 and 3 include the addition of an air intake structure and air exhaust stack for each vault (ES-W464-M01). Concrete louvers will be added at each exhaust plenum for shielding, based on previous analysis performed for HWVP. The south wall of the operating area shelter structure will be modified to provide an opening, approximately 30 ft wide by 30 ft high, required for the travel of the SCT between the Load-In/Load-Out Annex and the operation deck area.

The existing hot conditioning system annex (HCSA) pits, 6 and 7 will be used to support project W-464 activities.

APPROVAL

HNF-2298, Rev. 0

The existing CSB complex consists of the following buildings and structural systems:

- Vaults.
- Operating deck.
- Vault cooling intake structure (Vault 1).
- Vault cooling exhaust stack (Vault 1).
- Operating Area (including load-in/load-out and HCSA areas).
- Support Area.
- Storage tubes and plugs (Vault 1).

The operations area in the CSB is 41.86 m (137 ft. 4 in.) wide by 68.81 m (225 ft 9 in.) with a 12.50 m (41 ft) deep belowgrade reinforced concrete structure with a 1.73 m (5-ft 8-in.) thick basemat foundation and 1.52 m (5-ft) thick operating deck. Two 0.91 m (3-ft) thick common walls divide the structure into three vaults, each vault having a rectangular concrete intake plenum 3.25 m (10 ft 8 in.) by 4.88 m (16 ft) by 0.61 m (2 ft) thick and 16.92 m (55 ft 6 in.) high and a concrete exhaust plenum with concrete circular stack foundation having 6.25 m (20 ft 6 in.) O.D. by 3.51 m (11 ft 6 in.) I.D. by 3.66 m (12 ft) high. North of Vault 1 is the SNF load-in/load-out area and south of Vault 3 is the hot conditioning annex. Both these areas have concrete floors joined monolithically to the operating deck with the floors all at the same level. The operating deck, the SNF load-in/load-out area, and the hot conditioning annex floor form the

operation deck area and are sheltered by a steel frame metal building (ES-W464-M01).

Each vault is designed to accommodate a storage tube matrix of 22 rows with 10 columns per row for a total of 220 carbon steel storage tubes and one row of 6 columns of overpack storage tubes located west of the canister storage tubes (ES-W464-M01). Existing embedments for the standard and overpack canister storage tube assemblies have been placed in the vault operating deck and in the basemat. The existing operating deck embedments are designed to receive the tube and the floor plug assemblies, the upper end of each tube will be welded to a stainless steel bellow that will be welded to the deck embeds. Tube base assemblies will be welded to the existing basemat embedments. The tube base assemblies are designed for the alignment and anchorage of the tubes (ES-464-M05).

The operation deck area includes crane rails 38.56 m (126 ft 6 in. apart) running east-west near column lines A.1 and E.9 for the MHM handling machine crane. Crane rails are also included in the load-in/load-out area 12.19 m (40 ft apart) running north-south at column lines 1 and 2 for the receiving 60-ton gantry crane (ES-W464-M01).

Vault 1 will be used by the project W-379 and is equipped with the storage tubes and shielded plugs. The intake and exhaust plenums of Vault 1 are equipped with the concrete and steel air intake structure and steel exhaust stack, respectively.

Concrete

Insulating concrete will be added to Vaults 2 and 3 by W-379 project prior to the start of project W-464 (Reference 4). The insulating concrete is required to protect the structural concrete from the higher heat loads produced by the IHLW (Reference 10 and 15).

Ten inches of insulating concrete will be added to the ceiling of the vaults (bottom of concrete operation deck) and the exhaust plenum area, and 0.15 m (6 in.) of insulating concrete will be added to the side walls of the vaults and the exhaust plenum area. The insulating concrete will be light-weight concrete of 960 kg/m³ (60 lb/ft³) density. The insulating concrete anchorage is similar to that designed for HWVP. The stack concrete foundation rings in the exhaust plenum area does not have insulating concrete.

Based on thermal analysis with all vaults loaded (References 10 and 15), the maximum structural concrete temperature at the ceiling is 57 °C (134 °F) (basemat temperature is anticipated to be lower). The maximum structural concrete temperature at the walls due to both convective and radiant heat transfer are as follows:

Long-term Exposure

| | <u>North Side</u> | <u>South Side</u> | <u>ΔT</u> |
|---------------------|-------------------|-------------------|---------------|
| Vaults 1 and 2 Wall | 41 °C (105 °F) | 51 °C (124 °F) | 10 °C (19 °F) |
| Vaults 2 and 3 Wall | 66 °C (150 °F) | 64 °C (148 °F) | 1.2 °C (2 °F) |

Short-term Exposure (6 hours duration)

| | | | |
|----------------|-----------------|-----------------|---------------|
| Vaults 1 and 2 | 81 °C (178 °F) | 91 °C (195 °F) | 10 °C (17 °F) |
| Vaults 2 and 3 | 104 °C (220 °F) | 104 °C (219 °F) | 0 °C (1 °F) |

A review/evaluation of existing design documents (References 20, 21, 22, 23, and 33) was performed to evaluate the impact of the higher temperature on the concrete (increase in temperature will result in an increase in the thermal stresses) and the wheel loads from the SCT.

For the CDR level of evaluation, it was concluded that the existing structural concrete can qualify for the proposed increase in temperature and the wheel loads from the SCT. Additional conservative features exist and have been identified as follows:

- The original design specified a 5,000 psi compressive stress limit for concrete. However, current design reduced this value by 1,000 psi to account for long-term thermal degradation (Reference 8).
- The design thermal conditions in the vaults are based on conservative assumptions such as,
 - The highest and lowest outside air temperatures are 46 °C (115 °F) and -32 °C (-27 °F), respectively, for a duration of 6 hours.
- The seismic analysis utilized a zero point acceleration input at a layer 2.4 m (8 ft) below the surface rather than at the surface (Reference 11).
- The shear modulus values used for the soil-structural interaction (SSI) analysis were varied by an uncertainty factor, $C_v = 1.0$, twice the allowed minimum value of $C_v = 0.5$, per ASCE 4-86 (Reference 11).

- The weight of the HLW canisters to be placed in the storage tubes is considerably less than the SNF canisters. The total maximum weight for two 4.5 m HLW canisters is 8400 kg (18,519 lb) and 17 240 kg (38,000 lb) for the SNF (Reference 26).
- Gravity and seismic loads from the exhaust stack can be reduced with the placing of concrete louvers in the exhaust plenum in lieu of the 12-in. of concrete shielding around the exhaust stack.
- In the evaluation of the demand capacity ratios (actual versus allowable stresses) for the concrete, the values can be reduced by taking into account the cracked section effective moment of inertia.
- Actual compressive strength of the existing concrete (test results) are higher than required design requirements.
- The SCT weight used for the evaluation of the deck is 1.245 MN (280,000 lb). This weight is based on a unit with two 175-hp diesel engines with two generators. The proposed SCT will be electrically driven with a 480 V external power source, therefore, it is expected that the actual weight be reduced.

To validate the above conclusion, a comprehensive evaluation/analysis will be done during advanced conceptual design, taking into account the following:

- Probabilistic heat wave for the site.

- A three dimensional heat transfer model to simulate heat flow through the vaults with alternative storage tube loadings.
- Shielding analysis to validate and size the concrete louvers at the exhaust plenum.
- Wheel loads, from the shielded canister transporter on the operation deck.
- More detailed heat transfer, thermal gradients, and thermal load analyses.
- A comprehensive structural analysis.

Modifications

Project W-464 structural modifications to Vaults 2 and 3 include the addition of air intake structures and air exhaust stacks (ES-W464-MO1). The air intake structures and the air exhaust stacks of Vaults 2 and 3 will be similar to those used by project W-379 in Vault 1. The air intake structures will be anchored to the concrete intake plenums, and the air exhaust stacks will be anchored to the existing concrete stack foundations.

Concrete louvers will be added at the pass-through into the exhaust plenums for shielding (see sketch ES-W464-MO1, sh 4).

Air foils will be installed along the walls of Vaults 2 and 3 similar to those for project W-379.

APPROVAL

HNF-2298, Rev. 0

The existing structural design basis for the SNF CSB project includes the following:

- The design life of the SNF CSB is 40 years, except that the materials for the vault structure, the storage tubes, and other inaccessible structures have an expected life of 75 years.
- The general design criteria for the buildings and structures conform to DOE Order 6430.1A; UBC-1994; ASCE 7-88; HPS Architectural-Civil Design Criteria, HPS-SDC-4.1, Rev. 12; WHC-S-0425, Rev. 1; CSB performance specifications; ANSI/AISC N690-1984; ACI 349-90; and SNF CSB Design Basis Document (Reference 8).
- The CSB vaults belowgrade structures are designed and detailed as a Safety Class (SC) structure as follows:
 - Design basis earthquake (DBE) peak ground acceleration (PGA) of 0.350.
 - Self-straining thermal loads based on short duration concrete surface temperature as high as 57 °C (135 °F).
 - Live load of 100 psf plus MHM and receiving crane loads.
- The operation area structure is designed and detailed as a General Service structure, but is designed to sustain the following SC DBE, wind, tornado, and ashfall loading without collapse:

- Roof live load = 960 Pa (20 psf)
- Roof snow load = 960 Pa (20 psf)
- Design basis ground ash load = 1150 Pa (24 psf)
- Design basis wind load per
ASCE 7-88 exposure "C" = 145 km/h (90 mph)
- DBE load is SC-1, peak
ground acceleration = 0.359
- Design basis tornado wind = 320 km/h
(200 mph)

The support facility is a General Services structure over safety significant items with the following loads:

- Roof live load = 960 Pa (20 psf)
- Roof snow load = 960 Pa (20 psf)
- Wind load per ASCE 7-88
exposure "C" = 113 km/h (70 mph)
- DBE load is SC 2, peak ground
acceleration = 0.219
- Design basis tornado wind = 320 km/h
(200 mph)

Foundations and belowgrade structures are designed for an allowable soil bearing pressure of 287,280 Pa (6,000 psf) with 33% increase allowed for wind or seismic loads. Active and passive earth pressures, including dynamic effects due to earthquake, soil thermal expansion, and surcharge loads due to the construction crane are also considered in the design.

Materials

Structural materials include the following:

- Reinforced concrete:
compressive strength = 41 370 kPa (6,000 psi*) (CSB Vault above Elv. 215.6 m [704 ft])
34 475 kPa (5,000 psi*) (CSB Vault below Elv. 215.6 m [704 ft])
27 580 kPa (4,000 psi) (elsewhere)
* Structural design is based on these values reduced by 6895 kPa (1,000 psi) to account for long-term thermal degradation (Reference 8).
- Reinforcing steel - ASTM A615 ($F_y = 413\ 700\text{ kPa}$ [60,000 psi]).
- Structural steel and embeds - ASTM A36/A36M ($F_y = 248.22\text{ Mpa}$ [36 ksi]).
- Air intake steel structure - ASTM-A588 GR A ($F_y = 344.8\text{ Mpa}$ [50 ksi]).
- Exhaust stack - ASTM-A424 Type 1 or ASTM-A588 GR A ($F_y = 344.8\text{ Mpa}$ [50 ksi]).

Canister Overpack Station

HCSA pit 7 will be used for overpacking damaged or defective canisters. The dimensions of an HCSA pit are adequate for overpacking the solidified HLW canisters. However, the recessed cavity at the top of the pit will be evaluated for methods to accommodate new welding equipment and a new process enclosure

during project W-464 definitive design (ES-W464-MO7). A cover will be welded to the overpack and the process enclosure will provide confinement and shielding during the overpack welding. Project W-464 will provide the cover and welding equipment, (see Section D, Special Equipment and Process Systems). Centering guides and an overpack support pedestal or impact absorber will be installed in the pit (ES-W464-MO7). The centering guides will center the overpack in the pit and the support pedestal will locate the overpack to the proper level for welding.

Heating, Ventilating, and Air Conditioning

The heating, ventilating, and air conditioning (HVAC) and HEPA filtration systems designed for the SNF CSB provide heating, cooling, ventilation, and filtration for the operations area and for the support area. Due to the thermal insulation of Vaults 2 and 3, heat transfer from the vaults to the operating area is small. Based on review of the existing SNF design, capacity for air handlers and condensers is adequate. The existing HEPA filtration system meets the design requirements for project W-464. No modification to the existing systems will be required during construction.

The passive (natural convection) cooling system design for the SNF in Vault 1 will be duplicated for cooling of the HLW in Vaults 2 and 3, with the addition of shielding louvers. No HEPA filters are used on the exhaust as the vault storage tubes provide a containment function. Contamination of the vault airflow is not a credible scenario. The results of the thermal analysis (Reference 7 and 8) show that insulating concrete is required to protect the ceiling and walls in Vaults 2 and 3 (as proposed in earlier studies by Fluor Daniel, Inc.) This insulation is calculated to provide a temperature differential barrier of up to 13 °C (24 °F) at the vault ceiling. Other conclusions from the thermal analysis are:

- At the vault design heat load of 556 kW, (which includes HLW and cesium) the calculated airflow is approximately 53,000 cfm, at a mixed leaving air temperature of approximately 67 °C (152 °F). The peak (hot spot) air temperature in the vault will not exceed 69 °C (157 °F) (Reference 10).
- The maximum storage tube temperature will be approximately 132 °C (270 °F), and will occur at a tube with the maximum load of two HLW canisters at 2.54 kW each. The maximum structural concrete temperature in the vault ceiling is calculated to be 57 °C (134 °F). The maximum short-term temperature (6 hours) at the surface of the structural concrete walls is calculated to be 104 °C (220 °F) (Reference 15).
- The maximum HLW glass canister centerline temperature is calculated to be 283 °C (541 °F). This is well under the maximum allowable centerline temperature of 400 °C (752 °F). The maximum cesium container centerline temperature will be 407 °C (764 °F) which does not have a maximum allowable centerline temperature established at the time of this CDR preparation (see Uncertainties, Section VII).

An analysis of natural convective cooling of the SNF and IHLW has been performed by Fluor Daniel, Inc. The results of this analysis indicates that the convection method will provide adequate and continual cooling. Computer programs used were verified, and the entire analysis for SNF received a level of verification required for SC systems and the results were confirmed by British Nuclear Fuels Limited (BNFL). This analysis was performed for a single exhaust stack system. Project W-464 will have to perform testing to verify that a three stack design does not compromise the cooling capability because of flow interferences between the stacks.

The analytical methods of solution used for this study of IHLW in the CSB were identical to the methods (including computer programs) used by Fluor Daniel Inc., for their SNF and HLW thermal analyses. This natural convection methodology has been used worldwide.

Fire Protection

The abovegrade part of the CSB is Type II (000) noncombustible, nonfire-rated construction per NFPA 220. The belowgrade part of the building is reinforced concrete. The same construction is used for the floor of the building. The CSB is to be considered as a Special Purpose Industrial Occupancy facility per NFPA 101. The unload bay is to be treated as a "Special Purpose Industrial" occupancy. The storage of glass logs will be in a metal tube. Adequate emergency exits in accordance with NFPA 101 are provided.

DOE Orders 6430.1A and 5480.7A require that automatic sprinkler protection be provided in nonreactor nuclear facilities. However, automatic sprinkler protection systems will not be installed in the operations area of the CSB. This is consistent with the CSB fire hazards analysis (FHA) (Reference 12). An exemption to the sprinkler system requirement has been granted by RL (Reference 6). This exemption is based on a maximum possible fire loss (MPFL) being less than \$1 million as defined in DOE Order 5480.7A. To continue this exemption, the materials, construction, operation, and other items can not increase the MPFL above the limit.

The CSB FHA lists the projected MPFL for the operations area to be \$850,000. This would involve a truck fire with 100 gal. of fuel. If the fuel is limited to 40 gal. or less, the MPFL would be \$280,000. The MPFL for the tube vent and purge cart is listed at \$305,000. The MPFL for the SCT is

expected to be less than that of a truck fire. The MPFL is expected to be less than \$750,000. The MPFL is based on the use of the SCT in the CSB at the Savannah River Site, Aiken, South Carolina.

The shipping and handling of the glass log canisters in the CSB will not increase the combustibles in the operations area nor increase the MPFL as noted in the FHA.

During construction, close administrative control will be required to ensure that the bounding conditions (limit of combustibles) of the FHA are not exceeded. This will include limiting combustibles in the building, not allowing trucks into the building, and any other controls required when the CSB FHA is approved.

A pre-engineered CO₂ or inert gas fire extinguishing system may be required to protect enclosed electrical cabinets containing combustible cables. This requirement will minimize fire exposures when the MHM is in the unsprinklered CSB structure. This protection is consistent with recommendations in Factory Mutual Loss Prevention Data Sheet 1-62/17-16, *Cranes*. While this data sheet is listed for cranes, the operation of the SCT and a crane have similar fire potential conditions.

Adequate water supplies for fire protection purposes exist at the jobsite; water supplies were installed as part of the SNF project. The system includes a connection to the 200-Area water system and an onsite water supply (fire pumps taking suction from a tank). The fire pumps are expected to be placed into operation by the end of CSB construction. A 12-in. water loop with fire hydrants was installed to supply water for fire protection. Fire hydrants are located so that hose lays are no more than 300 ft from the

hydrants to the exterior portions of a protected building. Fire hydrants are located more than 50 ft from the CSB. However, one hydrant will be relocated due to the new road for the HLW project.

Electrical

The existing CSB electrical system was evaluated and the system provides adequate services for project W-464. The existing interior/exterior lighting, convenience outlet, grounding and communication systems as installed will provide adequate coverage for IHLW interim storage with little or no changes.

Lightning protection will be installed on the new vault stacks consistent with the existing CSB installation.

Existing conduits and included cables, in the southeast corner installed along the south wall of the CSB, will have to be rerouted to allow for the installation of the HLW Load-in/Load-out Annex access opening.

Electrical power to the new overpack weld station will be provided from the existing CSB electrical system.

Instrumentation

Vault intake air temperature, intake air velocity, and exhaust air temperature will be measured to ensure that the natural air convection used to maintain the air temperature in the vault is achieved. The air measurement signals will be transmitted to a remote monitoring station (see Figure 1). There is a significant calculated margin below the maximum allowable centerline temperatures of the HLW canisters, therefore temperature measurement of individual storage tubes is not required. This strategy of measuring the air velocity and the outlet stack air temperature is also used by the SNF project in Vault 1.




FIGURE 1. - CSB - TYPICAL FOR VAULTS 2 & 3

2. High-Level Waste Load-In/Load-Out Annex

Architectural

The HLW Load-in/Load-out Annex will be constructed as an addition to the existing CSB.

- The design life of this addition will be 40 years.
- The Occupancy Classification will be NFPA 101 Special Industrial Occupancy.
- Type Classification will be NFPA 220 Type II-000 non-rated construction and the area separation between occupancies will be per NFPA.
- Life Safety: Doors will be operable from the inside without excessive force and without keys or special knowledge. Exit ways will be clearly marked and illuminated with at least one footcandle upon path of travel at all times.
- Occupied spaces will be suitably lighted and ventilated for safe habitation at all times.
- Exterior roof drains will be used.
- The roof system will consist of welded metal decking covered with batt isolation having a minimum thermal resistance value of R-30. Standing seam metal roofing will match color, material, slope of the roofing system on the existing CSB.
- The exterior wall system will be insulated metal siding attached to a structural steel framing system. The minimum thermal resistance of

the siding system will be R-19. This system will match color, material, type of siding system on the existing CSB.

- Building envelope of the CSB plus the HLW Load-In/Load-Out Annex will seal sufficiently to allow maintaining an internal negative pressure.

The Annex will accommodate the following:

- The main level of the Annex will be approximately 3,000 ft² and will connect to the south wall of the Operations Area of the CSB maintaining the same floor elevation.
- The main level will provide a HLW cask receiving area and a HLW cask transfer pit.
- The south wall of the HLW cask receiving area will have double swinging exterior doors (20 ft wide by 24 ft high) providing access for entry of a transport trailer delivering a cask.
- The HLW cask transfer pit will be separated from the HLW cask receiving area by a vertical lift door. A full width opening to the CSB operations area is provided on the north side of the HLW cask transfer pit.
- Both the HLW cask transfer pit area and the HLW cask receiving area will be served by a 60-ton gantry crane on rails.
- A corridor on the west side of the Annex will provide an exterior exit, access to the CSB, access to the Annex, and a stairway to the lower level access tunnel.

- The access tunnel (13 ft - 0 in. below the Annex floor level with an 8 ft - 0 in. ceiling height) provides access to cask lid removal area.
- The cask lid removal area (10 ft by 16 ft) provides work and observation space. A cask lid bridge crane is provided.
- On the east side of the personnel access corridor will be an additional access tunnel with an exit ladder up on the east side of the Annex.
- There will be two exhaust fan and filter housing assemblies.
- A 12-in. diameter by 80 ft high stack will be located east of the Annex.

The design of the HLW Load-In/Load-Out Annex, including the building materials, method of construction, and architectural detailing will be coordinated with the existing CSB to provide a simple, unified, and harmonious building.

In some cases, code requirements conflict with necessary security and operational requirements that may be unique to nuclear facilities such as this. This design would comply with all applicable standards and regulations as listed.

Structural

The Load-in/Load-out Annex will be designed to receive HLW canisters by truck. A 60-ton gantry crane capable of handling the transport cask will be included. The transport cask will be picked up by the gantry crane and will be transferred into a below-grade transfer vault/pit. In the transfer vault/pit,

a remotely operated bridge crane will remove the cask lid; the SCT will then remove the floor plug and pick up the HLW canister and transport it to the CSB operating area and place it in the storage tube.

The Load-in/Load-out Annex will be connected to the south wall of the operating area of the CSB. A seismic joint will be provided to isolate the two structures. The Annex area will consist of two sections: a HLW cask receiving area and a HLW cask transfer pit area. The cask receiving area will be isolated from the cask transfer pit area by a sealed door. The HLW cask transfer pit area will be open to the CSB operating area and will maintain the same atmospheric pressure.

The Load-in/Load-out Annex will consist of the following:

- HLW Cask Transfer Pit Area - this structure will be below grade consisting of 0.05 m (2-in.) thick reinforced concrete vault walls and floor approximately 4.88 m (16 ft) by 3.05 m (10 ft). Access to the vault is through a 1.52 m (5 ft) diameter floor plug and a personal labyrinth and door to the west. The floor of the vault includes a 1.52 m (5-ft) diameter by 5.79 m (19-ft) deep by 0.61 m (2-ft) thick reinforced concrete cask transfer pit. The vault will also include a 10-ton bridge crane for the removal and placement of the cask lid. This area also provides capability for access to the bottom of the SCT for maintenance.
- Operation Floor Area - this area consists of two sections: HLW cask receiving area and the HLW cask transfer pit area. The operation floor area will consist of a reinforced concrete floor 1.52 m to 0.61 m (5 ft to 2 ft) thick and will be sheltered by a steel framing structural system with metal roof and siding designed to the CSB design criteria.

The HLW cask receiving area will be isolated from the HLW cask transfer pit area by a vertical lift door. The main entrance to the HLW cask receiving area is through a double swinging exterior door (6.10 m [20 ft] wide by [20 ft] high) at the south wall. The double swinging door will be designed to resist tornado wind and missile loads. The north side of the Annex will be open to the CSB operation deck area.

- A 60-ton gantry crane and crane rails spanning north-south the full length of the floor area.
- A 300 mm (12-in.) diameter by 24.4 m (80-ft) high HVAC stack and stack foundation located east at the east at the north end of the Annex area.

Heating, Ventilating, and Air Conditioning

A new HEPA filter exhaust ventilation system of approximately 2000 cfm capacity will be provided for the new HLW Load-in/Load-out Annex (ES-W464-M01). The air flow will be adequate for personnel needs as well as means of cooling the new HLW cask transfer pit. Supply air will exfiltrate from the operating area as was originally intended for the HCSA. The air will exhaust up a new stack and will be monitored for radiation. The use of HEPA filters is consistent with the design requirements for project W-464 and project W-379.

Fire Protection

The Annex is to be Type II (000) noncombustible, nonfire-rated construction in accordance with NFPA 220. The floor and belowgrade parts of the Annex will be reinforced concrete. The Annex is to be considered a Special Purpose Industrial Occupancy per NFPA 101 and will be used for the

unloading and future loading of the HLW casks. The jeep (motor unit) will not be brought into the Annex for the unloading operation. It will be disconnected from the canister trailer and parked outside of the building. Adequate emergency exit will be provided in accordance with NFPA 101.

DOE Orders 6430.1A and 5480.7A require that automatic sprinkler protection be provided in nonreactor nuclear facilities. However, automatic sprinkler protection systems will not be installed in the Annex. This is consistent with the CSB FHA (Reference 12). An exemption to the sprinkler system requirement has been granted by RL (Reference 6). This exemption is based on a maximum possible fire loss (MPFL) being less than \$1 million as defined in DOE Order 5480.7A. To continue this exemption, the bounding conditions must also be met.

These include the close administrative control will be required to ensure that the bounding conditions (limit of combustibles) of the FHA are not exceeded. This will include limiting combustibles in the building and on trucks and any other controls required when the CSB FHA is approved.

Electrical

Electrical power for the new HLW Load-In/Load-Out Annex will be supplied from the existing CSB 480 V ac power distribution system. A concrete encased duct bank and manhole system from the CSB electrical equipment room to the new Annex will be used to route electrical cables.

A new 480 V/277 V, 3-phase, 4 wire distribution panelboard will be installed in the new annex to provide 480 V power to HVAC equipment, miscellaneous power receptacles, SCT, bridge crane, electric operated doors, high bay light fixtures, and a 208/120 V, 3-phase, 4 wire panelboard.

The new gantry crane will have power provided from an existing CSB motor control center. The existing motor control center is capable of supplying normal power and in case of normal power system failure, diesel driven generated back-up power.

The 208/120 V panelboard will provide power for lighting (incandescent, fluorescent, outdoor, emergency, and exit), convenience outlets (indoor and outdoor), vehicle battery charger(s), air monitoring equipment, and control/monitoring systems.

Lightning protection will be installed on the new Annex and associated HVAC exhaust stack consistent with the existing CSB installation.

The existing CSB communication system will be extended into the new Annex.

Instrumentation

The new Annex exhaust stack will be provided with a continuous air monitoring system that will switch to the standby filter and exhaust fan in an upset condition.

The bridge crane will be provided with remote control capability. A closed circuit TV system will be installed to allow remote operation and monitoring of the transport cask lid removal/placement. The remote monitoring/control station will be located in the main floor of the Annex.

C. SPECIAL EQUIPMENT AND PROCESS SYSTEMS (700)

1. Shielded Canister Transporter

A new electrically powered SCT will be provided for handling and transporting HLW canisters between the HLW cask transfer pit and Vaults 2 and 3 (see Figure 2).




FIGURE 2

SHIELDED CANISTER TRANSPORTER

The SCT is comprised of a 100-ton capacity mobile straddle carrier for transporting a shielded cask and includes a bridge support structure and remote drive components. The shielded transfer cask includes a shielded valve, hoist, and grapple equipment. The control system includes CCTV monitors and controls, programmable controllers, interlock functions, and redundant back-up controls. The SCT will be electrically powered via a 480 V, 3-phase umbilical cord.

2. Transportation System

Two new onsite transportation casks and truck-based transporters will be provided by project W-464 (ES-W464-M01, sh 6). The transportation casks will be constructed of steel which will provide the proper shielding at a minimum thickness of 9 in. This will result in a cask with approximately a 43-in. outside diameter. The transportation cask will be built in only one size and will accommodate both the solidified IHLW canister and the overpack cesium canister. Project W-464 will provide two casks with trailers. Existing tractors will be used to transport the casks/trailers.

3. Storage Tubes

Standard storage tubes will store the IHLW canisters or the overpacked cesium canisters. There are 220 standard storage tubes in each vault. Two 4.5-m IHLW canisters or two overpack cesium canisters will fit in each standard storage tube. The standard storage tube consists of a standard floor embedment, standard tube/bellows assembly, standard tube base assembly, standard tube plug assembly, and a standard tube plug cover assembly (ES-W464-M05).

Overpack storage tubes will store the IHLW canister overpacks. There will be three overpack storage tubes in Vault 3. Two IHLW canister overpacks will fit in each overpack storage tube. The overpack storage tube consists of an overpack floor embedment, overpack tube/bellows assembly, overpack

tube base assembly, overpack tube plug assembly, and an overpack tube plug cover assembly (ES-W464-M05).

The standard and overpack floor embeds are an existing part of the SNF CSB; the embeds have been extended by 10 in. to accommodate the insulating concrete. The standard and overpack tube base assemblies and tube plug cover assemblies will use the SNF designs, but fabrication and installation will be part of project W-464 scope (ES-W464-M05).

The design and fabrication of the standard and overpack tube assemblies will be similar to SNF CSB tube assemblies with two exceptions, a step is required to support the upper impact absorber (ES-W464-M05, sh 4) and the overpack tubes are larger in diameter.

The design and fabrication of the standard and overpack tube plug assemblies will be provided by project W-464 (ES-W464-M05). The design of the tube plug assemblies will be similar to the SNF design, and will be made up of 29.40 in. of concrete, and 8 in. of insulating concrete. (ES-W464-M05, sh 3).

The storage tube assemblies will be transported into Vaults 2 and 3 through the loading/tagging area of the main door at the southwest corner of the CSB and lowered through the operating deck embedment with a portable crane. Air balance will be maintained by construction of a temporary greenhouse. The top of the tube assembly (bellows) will be welded to the embedment in a similar way to the tubes for the SNF project in Vault 1.

4. Cesium Canister Overpacks

Cesium canisters, which are smaller than the IHLW canisters, will be placed in overpacks as shown in sketch ES-W464-M09. The privatization contractor will put the cesium canister into the overpack, and place the

overpack into the transportation cask for shipment. The cesium overpack will have the same outside dimensions as the IHLW canisters which permits the use of the same sized transportation cask. The overpack will also provide additional shielding which will reduce the cesium dose rate at the surface of the overpack down to levels consistent with the IHLW canister dose rate. Project W-464 will provide two cesium overpacks.

5. Overpack Assemblies

Two overpack assemblies, built by project W-464, will be used for overpacking HLW canisters (ES-W464-M10, sh 1) that may become damaged during handling in the CSB. The damaged canister will be put into an overpack canister and the top cap will be welded on at the overpack weld station.

6. Impact Absorbers

Five upper and five lower impact absorbers will be provided by project W-464 for installation into standard (4 upper, 4 lower) and overpack (1 upper, 1 lower) storage tube assembly (ES-W464-MO6). The impact absorbers will be designed to limit the loading of a dropped waste canister to 35g or less, similar to the MCOs for SNF CSB.

7. Gantry Crane

A new 60-ton gantry crane will be provided in the HLW Load-In/Load-Out Annex for transferring the shielded cask from the transport trailer to the HLW cask transfer pit. A 10-ton hook will be provided for moving the cask transfer pit shield plug. Operation will be local.

8. Bridge Crane

A new 10-ton, remote operated, bridge crane will be provided in the HLW cask lid access area for removal of the shielded transport cask lid.

9. Overpack Weld Station

A new weld station will be provided for welding and weld inspections of the HLW overpack cap weld (ES-W464-M08, sh 3). The following remote equipment and systems will be required:

- Electrical power
- Bottled gas
- Mechanical lifting equipment
- Gas tungsten arc welding (GTAW) system
- Ultrasonic inspection equipment
- Weld repair equipment
- Gantry crane (approximately 7-½ ton capacity)
- Exhaust enclosure for confinement of the weld operation
- Local instrumentation and controls
- Overpack support pedestal
- Local shielding (portable).

E. DESIGN COMPLIANCE

The design and construction of project W-464 will comply with the codes, standards, regulations, and laws listed in the project DRD and applicable standard/requirements identification documents (S/RIDs) at the time of contract award for each phase.

V. METHODS OF PERFORMANCE

The methods of performance comply with the work breakdown structure (WBS) in Appendix A. The WBS indicates the major phases of work to be accomplished, i.e., engineering, construction, project management, and other project activities.

A. ARCHITECT-ENGINEER WORK (WBS 1.A AND WBS 1.C)

The contracted architect-engineer will provide definitive design, engineering during construction, construction management, and project management support throughout the life of the project.

Acceptance Inspection and National Electrical Code (NEC) compliance inspection will be acquired by the integrating contractor.

B. ONSITE PROJECT INTEGRATOR (WBS 1.D)

The project integrator will provide the following activities:

- Development of the definitive design DRD.
- Provide design input and reviews from cognizant facility and infrastructure (on-site utilities) personnel for definitive design and construction.
- Provide construction support, as needed.

C. PROCUREMENT (WBS 2.0)

The performance contractor is directly responsible to the PHMC for performing all activities associated with this project. The performance contractor will negotiate performance measures with the PHMC as well as manage and integrate scope, cost, and schedule through the life of the project.

The contracted architect/engineer, for the purpose of cost estimating, will provide project management and construction management resources to the performance contractor to support project execution from the conceptual phase through acceptance testing and project closeout.

The contracted architect/engineer, for the purpose of cost estimating, will procure and provide the following equipment as owner-furnished material for installation to the construction contractors:

- Standard/overpack tube assemblies
- Standard/overpack bellows assemblies
- Standard/overpack tube base assemblies
- Standard/overpack tube shield plug assemblies
- Tube plug cover assemblies
- Transfer pit shield plug assembly

- Motorized 60-ton cask handling gantry crane
- Overpack station enclosure and welding/inspection assembly
- Motorized 10-ton cask lid removal bridge crane.

The contracted architect/engineer will procure and provide the following equipment for use by the performance contractor:

- Two transport cask/trailers
- Ten impact absorbers
- Two cesium canister overpack assembly
- Two canister overpacks
- One SCT.

The balance of equipment for project W-464 will be purchased and installed by the construction contractor (see outline specification in Appendix E).

D. CONSTRUCTION (WBS 3.0)

The construction contractor will be a CM-fixed price contractor who will provide the resources necessary to perform the construction work needed to implement project W-464. Two fixed-price contracts will be utilized to enhance the project schedule.

E. PROJECT INTEGRATION (WBS 4.0)

The project integrator will provide technical and construction coordination.

F. OTHER PROJECT COSTS (WBS 5.0)

The project integrator will coordinate project startup and verification.

VI. REQUIREMENTS AND ASSESSMENTS

A. SAFEGUARDS AND SECURITY

Project W-464 will take place within the 200-East Controlled Area and will require a Level 1 clearance and badging for access. Badge access is required for transport

vehicles past the Wye Barricade and boundaries around this project. No new measures beyond the current site practices will be required as a result of this project.

Project W-464 will perform a vulnerability assessment analysis to determine the risks associated with SNF operations concurrently with project W-464 construction activities. A construction security plan will be prepared prior to the start of construction.

B. HEALTH AND SAFETY

Accommodations for the physically handicapped will not be provided for the CSB (see Appendix I).

Construction contractors will comply with State of Washington and Fluor Daniel Hanford, Inc., (FDH) standards during performance of the work, and will ensure that applicable Occupational Safety and Health Administration (OSHA) standards are enforced during the project. See Section 5.0 of the PSE for construction risk discussion. This will be documented and controlled by a job safety analysis (JSA) prepared and administered by each applicable contractor. These measures include providing continuous access to construction areas for emergency vehicles and personnel, and ensuring that emergency evacuation routes are unobstructed.

Based on the shielding analysis performed for the CSB, the dose rates in Vault 2, with Vault 1 loaded with SNF, will be less than 0.5 mrem/h and therefore will not require radiation protection measures (Reference 25).

Transporting, handling, and storage of IHLW and cesium canisters will involve management of the radiation. Preliminary shielding analysis results are as follows:

- The cesium canister overpack needs 2 in. of stainless steel to reduce it's dose rate to the bare IHLW canister equivalency.

- The cask needs 9 in. of steel to shield both gamma rays and neutrons to meet the NRC Code of Federal Regulations (CFR) 10 CFR 71.51 limitation for a transfer cask.
- Current tube plug assembly (16.515 in. of stainless steel, 29.40 in. of concrete, and 8 in. of insulation) is enough to reduce the dose rate at the top to 1.8×10^{-3} mrem/hr.
- The 18-in. cask transfer pit plug reduces the dose rate on the plug surface to 1.7 mrem/hr (99% from neutrons). Whether the transfer pit plug dose needs to meet the 0.25 mrem/hr facility operation limit depends on the operator occupancy of the location. A decision on ALARA (based on the time-motion analysis) or the administrative control to restrict the access to the area due to remote operation of MHM will be investigated during definitive design.

C. DECONTAMINATION AND DECOMMISSIONING

No decontamination is expected for the CSB. When in operation, all waste canisters will be sealed and contamination-free. Decommissioning of the facility at the end of its life cycle will be addressed by a future project.

D. PROVISIONS FOR FALLOUT SHELTERS

Provisions for fallout shelters are not required for this project.

E. MAINTENANCE AND OPERATION REQUIREMENTS

The project adds two new cask/transport vehicles, one new SCT, a new 60-ton gantry crane, a new 10-ton bridge crane, two new ventilation exhaust fan/filter assemblies, and an overpack welding station. Maintenance for this equipment will

be provided locally or at an existing facility on the Hanford Site. The HLW cask transfer pit area provides maintenance access to the bottom of the SCT. Project W-464 does not provide for any new maintenance facilities or equipment.

An operations and maintenance concept will be established to provide a baseline for future reliability, availability, and maintainability (RAM) analysis for a basis for definitive design criteria.

Based on the operating sequence block diagram, (ES-W464-M02 Sheet 1), a throughput of two waste canisters per a 24-hour day can be achieved, which exceeds the DRD requirement for three waste canisters per week (Reference 2).

F. AUTOMATED DATA PROCESSING EQUIPMENT

The CSB automated data processing equipment will adequately support the IHLW packages. No new equipment will be provided by project W-464.

G. QUALITY ASSURANCE AND SAFETY CLASSIFICATION

Hanford project activities comply with the requirements of 10 CFR 830.120, *Quality Assurance Requirements*; and DOE Order 5700.6C, *Quality Assurance*, as set forth in the FDH *Quality Assurance Program Description (QAPD)*, HNF-MP-599. A comparison of the FDH QAPD and any additional W-464 project-specific regulatory requirements will be performed to determine whether there are additional QA program requirements not covered by the FDH QAPD. The Office of Civilian Radioactive Waste Management's *Quality Assurance Requirements and Description (QARD)*, document RW-0333P, will apply to project W-464. A project-specific QAPD may be required to address any additional requirements.

The highest safety classification for project W-464 modification work is Safety Class. The safety classification of the major components for project W-464 are listed in Table 1 and are the result of the preliminary safety evaluation (PSE), see Appendix G. The classifications will be confirmed or modified as appropriate during

TABLE 1

| Systems, Structures, and Components | Safety Classification | Safety Function |
|---|-----------------------|---|
| Impact Absorber | SS | Mitigate the consequences of a canister drop in the storage tube. |
| Storage Tube | SS SC (Seismic) | Containment of any release following a canister drop (SS). Prevent damage of storage canisters during a seismic event (SC). The safety class function is to hold the canisters within the tubes during a seismic event. |
| SCT, Grapple, & Lifting Devices *** | SS | Containment of any release following a canister drop (alternate safety SSCs). |
| Receiving Crane Grapple Lifting Devices (handling of transportation cask) *** | SS | Prevent the drop of the transportation cask into receiving pit. |
| Transportation Cask ** | SS | Sustain the impact of a cask drop without breach. |
| Transporter Barriers | SC | Prevents transporter from impacting the MHM. |
| Shielding of SCT, receiving pit, storage tubes, plugs, louvers, concrete structures of the vaults | SS | Protect worker from unacceptable radiation doses (EDE Limit). |
| Cask Shielding | SS | Protect workers from unacceptable radiation doses (EDE Limit). |
| CSB Operating Deck | SC (Seismic) | Prevents failure of tube during a seismic event. |
| Vault Ventilation Inlet/Outlet Structures (plenums, louvers, stacks) | SC (Seismic) | Prevents damage to the operating deck and storage tubes that could result in a SC release during a seismic event. |
| CSB Structure | SC (Seismic) | Prevents collapse of building onto storage tubes. |

* This preliminary safety equipment list provides suggested safety SSCs, and further design development may revise or add additional SSCs.

** Consequence results below, but near, guidelines. Should consider designation of cask as safety significant.

*** These are alternative safety SSCs to be considered in lieu of the chosen safety SSC for the prevention/mitigation of the respective accident.

design development and will be documented by revision to the existing CSB preliminary safety analysis report (PSAR) and final safety analysis report (FSAR). The work involved will include the cumulative engineering evaluation of CSB as-built drawings and specifications at completion of project W-464 construction work (Title III per DOE 4700.1). This work will include impact of project W-464 changes to the existing CSB calculations/analysis.

H. ENVIRONMENTAL COMPLIANCE

The RL is responsible for the transportation and interim storage of:

- IHLW produced primarily during Phase 1 vitrification plant operation (glass product);
- Radioactive cesium separated during Phase 1 low-activity waste (LAW) vitrification plant operation (separated cesium).
- Secondary high-level radioactive and high-level mixed waste produced during Phase 1 (HLW and LAW) vitrification plant operations (nonroutine HLW).

The permitting strategies for these products are as follows:

NEPA: The recommended strategy is to adhere to the Record of Decision (ROD) (62 FR 8693) for TWRS. The ROD was based on the Final Environmental Impact Statement (FEIS), *Tank Waste Remediation System, Hanford Site, Richland, Washington, Final Environmental Impact Statement* (DOE/EIS-0189F). This document was co-authored by DOE and Washington State Department of Ecology (Ecology).

SEPA: The recommended approach is to inform Ecology that the TWRS/FEIS (DOE/EIS-0189F) and issuance of permits necessary for construction of the CSB cover this action and request Ecology to adopt the existing NEPA documentation for SEPA. This will be included in the permitting notice of intent (NOI) to expand the capacity of the CSB.

RCRA: The recommended approach is to negotiate with Ecology to grant interim status so that hot operation of the CSB may begin without a final status permit. A de-listing effort needs to be conducted by the private vendor or by RL on a parallel path with this strategy for subsequent shipment of the products to a repository.

CLEAN AIR ACT: Confirmation from the Washington State Department of Health and from Ecology that the hermetically sealed canisters do not constitute a source of regulated emissions should be obtained in writing from each state agency.

TRANSPORTATION: The recommended strategy for the packaging and transporting of canisters of the various products is to conduct the design and safety evaluations within the onsite transportation safe program, taking full advantage of the flexibility and cost efficiency provided by this approach. The packaging design and safety evaluations should be conducted in parallel.

RADIATION PROTECTION STANDARDS/MONITORING: Use of existing data for the baseline limits project W-464 to ongoing monitoring. The ongoing monitoring can be accomplished by use of site programs and the specific monitoring established for storage by project W-379. It is not expected that storage of IHLW canisters will require monitoring beyond that done by routine site programs.

I. PERMITS

The required permits to construct/operate project W-464 are addressed in HNF-SD-ENV-EE-002, Rev. 0 (Reference 17).

VII. IDENTIFICATION AND ANALYSIS OF UNCERTAINTIES

A. STRUCTURAL

An evaluation of the operating deck was performed on the basis of the DWPF SCT weight plus 15% (280,000 lbs) and present SNF thermal loads. The preliminary structural analysis indicates that the operating deck is marginal in a few areas and in two cases slightly exceeds the demand capacity ratio. Because of the identified conservatisms (see Structural in Section IV), there is a high degree of confidence that a detailed analysis will show the structural integrity to be satisfactory. To mitigate this uncertainty, a detailed structural/thermal analysis will be required in the ACDR.

B. HEATING, VENTILATING, AND AIR CONDITIONING

The natural convection cooling design was based on a single exhaust stack and wind tunnel testing was performed for a single stack. Until testing can be completed for a three stack design, the possible flow interferences between stacks is an uncertainty.

C. HLW PRODUCTS HEAT LOAD, SHIELDING AND OTHER CHARACTERISTICS

Current Phase 1 HLW product heat load and source term requirements are based on contract maximums (worst case conditions) which are not practical relative to Phase 1 interim storage in the CSB. The IHLW heat load and source term requirements need to be assessed based on Phase 1 tank data and more accurate requirements established for Phase 1 interim storage in the CSB. In addition, the cesium canisters, design, source terms have not been finalized. Therefore, the shielding, cooling, handling, overpack, and transportation requirements relative to the cesium canisters must be confirmed.

VIII. REFERENCES

A. DOCUMENTS

1. Calmus, R.B., 1996a, *Statement of Work for Conceptual Design of Solidified High-Level Waste Interim Storage System Project (Phase I)*, HNF-SD-W464-SOW-001, Rev. 0, SGN Eurisys Services Corporation, Richland, Washington.
2. Calmus, R.B., 1996b, *Design Requirements Document for the Interim Store Phase 1 Solidified High-Level Waste, Function 4.2.4.1.2*, WHC-SD-WM-DRD-012, Rev. 0, Westinghouse Hanford Company .
3. Calmus, R.B., 1996c, *High-Level Waste Interim Storage Architecture Selection Decision Report*, WHC-SD-WM-TA-183, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
4. Calmus, R.B., 1996d, *High Level Waste (HLW) Interim Storage Modifications, Change Request No. W-379-025*, Rev. 0, (SNF-96-056), SGN Eurisys Services Corporation, Richland, Washington.
5. RL, 1996a, *TWRS Privatization Request for Proposals*, DE-RP-06-96RL13308, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
6. RL, 1996b, Letter, E. D. Sellers (RL) to Mr. H. J. Hatch (Fluor Daniel Hanford, Inc.), FDH, 96-SFD-320, December 12, 1996.
7. Fluor, 1996a, *Canister Storage Building HLW Implementation Study*, prepared by Fluor Daniel, Inc., for Westinghouse Hanford Company, Richland, Washington.

8. Fluor, 1996b, *Spent Nuclear Fuel Canister Storage Building Design Basis Document*, prepared by Fluor Daniel, Inc., for Westinghouse Hanford Company, Richland, Washington.
9. Fluor, 1996c, *Canister Storage Building HLW Implementation Study Supplemental Report*, prepared by Fluor Daniel, Inc., for Westinghouse Hanford Company, Richland, Washington.
10. High-Level Waste Passive Cooling, Calculation No. W464-HV-0001, Fluor Daniel Northwest, Inc., November 12, 1997.
11. WHC-SD-SNF-RPT-004, Rev 7, *Canister Storage Safety Analysis Report Phase 3*, prepared by Westinghouse Hanford Company, May 1997.
12. *Fire Hazards Analysis*, HNF-SD-FHA-002, Rev. 2, (Draft), July 1997.
13. *Canister Storage Building Quality Assurance Program Plan*, WHC-SD-W379-QAPP-001, Rev. 1, prepared by Westinghouse Hanford Company, June 1997.
14. Henderson, 1997, Letter, J. L. Henderson (FDNW) to Mr. K. C. Burgard (LMHC), Project W-464, "Solidified High Level Interim Storage System Work Plan," FDNW-97-TWRS-045, March 14, 1997.
15. Canister Storage Building High-Level Waste Vault Wall Thermal Analysis, Calculation No. W464-HV-0002, prepared by Fluor Daniel Northwest, December 4, 1997.
16. Canister Storage Building High-Level Waste Transportation Cask Thermal Analysis, Calculation No. W464-HV-0003, prepared by Fluor Daniel Northwest, January 5, 1998.

APPROVAL

HNF-2298, Rev. 0

17. HNF-SD-ENV-EE-002, Rev. 0 - Permitting Plan for the HLW Interim Storage Project, April, 23, 1997.
18. Impact Absorber Evaluation, Calculation W464-M-1, prepared by Fluor Daniel Northwest, December 23, 1997.
19. Shielding Analysis, Calculation W464-S-1, prepared by Fluor Daniel Northwest, January 7, 1998.
20. Project W-464 HLW Interim Storage System, Exhaust Stack Base Evaluation Due to Increase in Temperature, Calculation W464-C-0001, Fluor Daniel Northwest, Inc., January 1998.
21. Project W-464 HLW Interim Storage System, Evaluation of Demand/Capacity Ratios, 3 Vaults Full With SNF MCOs, Calculation W464-C-0002, Fluor Daniel Northwest, Inc., January 1998.
22. Project W-464 HLW Interim Storage System, Evaluation of Demand/Capacity Ratios, Vault 1 Full With SNF MCOs and Vaults 2 and 3 Empty, Calculation W464-C-0003, Fluor Daniel Northwest, Inc., January 1998.
23. Project W-464 HLW Interim Storage System, Evaluation of Demand/Capacity Ratios, Operation Deck and Crane Rails, Calculation W464-C-0004, Fluor Daniel Northwest, Inc., January 1998.
24. 4.5 Meter High-Level Waste Canister Study, HNF-SP-1243, R.B. Calmus and G. N. Boechler, dated September 1997.
25. Phase I Bulk Shielding Calculations for CSB, CSB-SH-1002, March 21, 1996.

26. Viita, 1997, Letter, J. W. Viita (FDNW) to B. E. Voisin (NHC), Project W-464, "FDNW Work Plan, CO-98-TWRS-029 (reference g), " October 29, 1997.
27. Preparation Guides for Engineering Documents, ICF Kaiser Hanford Company, November 1994.
28. TWRS Privatization Contract No. DE-RP06-96RL 13308, Contract with British Nuclear Fuels Ltd., U.S. Department of Energy, Richland Operations Office, Richland, Washington, 1996.
29. TWRS Privatization Contract No. DE-RP06-96RL 13309, Contract with Lockheed Martin Advanced Environmental Systems, U.S. Department of Energy, Richland Operations Office, Richland, Washington, 1996.
30. Solidified High-Level Waste Interim Storage Alternative Analysis and Path Forward Recommendation, WHC-SD-WM-SP-011, Rev. 0, Westinghouse Hanford Company, Richland, Washington, May 1996.
31. Tank Waste Remediation System Function and Requirements, WHC-SD-WM-FRO-020, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington, 1996.
32. TWRS Retrieval and Disposal Mission-Immobilized High-Level Waste Storage Plan, HNF-1751, Rev. 0, Fluor Daniel Hanford Company, Richland, Washington, December 1997.
33. Project W-464 HLW Interim Storage System, Evaluation of CSB Deck Demand/Capacity Ratios for the Shielded Canister Transporter Load, Calculation W464-C-0005, Fluor Daniel Northwest, Inc., March 1998.

B. SKETCHES

| | |
|--------------------------|--|
| ES-W464-C00, sh 1, Rev 0 | Title Sheet |
| ES-W464-C00, sh 2, Rev 0 | Title Sheet Site Plan and Drawing List |
| ES-W464-M01, sh 1, Rev 0 | Mechanical Facility Layout Operations Floor Plan |
| ES-W464-M01, sh 2, Rev 0 | Mechanical Facility Layout Vault Floor Plan |
| ES-W464-M01, sh 3, Rev 0 | Mechanical Facility Layout Cross Section |
| ES-W464-M01, sh 4, Rev 0 | Mechanical Facility Layout Longit Section |
| ES-W464-M01, sh 5, Rev 0 | Mechanical Facility Load-in/Load-out Annex Sections |
| ES-W464-M01, sh 6, Rev 0 | Mechanical Facility Layout Transport Trailer |
| ES-W464-M02, sh 1, Rev 0 | Mechanical Operating Sequence CSB Block Diagram |
| ES-W464-M03, sh 1, Rev 0 | Mechanical Misc. Details |
| ES-W464-M04, sh 1, Rev 0 | Mechanical Temporary Covers |
| ES-W464-M05, sh 1, Rev 0 | Mechanical Standard/Overpack Canister Storage Arrangement |
| ES-W464-M05, sh 2, Rev 0 | Mechanical Tube Plug Cover Assemblies |
| ES-W464-M05, sh 3, Rev 0 | Mechanical Standard/Overpack Tube Shield Plug Assemblies |
| ES-W464-M05, sh 4, Rev 0 | Mechanical Standard/Overpack Tube Assemblies |
| ES-W464-M05, sh 5, Rev 0 | Mechanical Standard/Overpack Bellows Assemblies |
| ES-W464-M05, sh 6, Rev 0 | Mechanical Standard/Overpack Tube Base Assemblies |
| ES-W464-M06, sh 1, Rev 0 | Mechanical Impact Absorbers & Overpack Station Canister Guides |
| ES-W464-M07, sh 1, Rev 0 | Mechanical Overpack Station Plan & Section |
| ES-W464-M08, sh 1, Rev 0 | Mechanical Overpack Weld Station Gantry Crane Section |

APPROVAL

HNF-2298, Rev. 0

| | |
|--------------------------|---|
| ES-W464-M08, sh 2, Rev 0 | Mechanical Overpack Weld Station Gantry Crane Installation |
| ES-W464-M08, sh 3, Rev 0 | Mechanical Overpack Weld Station Cap Welder Assembly |
| ES-W464-M09, sh 1, Rev 0 | Mechanical 4.5M Canister and 4.5M Overpack |
| ES-W464-M10, sh 1, Rev 0 | Mechanical Cesium Canister Overpack Assembly |

APPENDIX A

WORK BREAKDOWN STRUCTURE

WORK BREAKDOWN STRUCTURE

1.0 ENGINEERING

- 1.A Definitive Design (Architect/Engineer)
- 1.B Not Used
- 1.C Engineering and Inspection (Architect/Engineer)
- 1.D Project Support and Coordination (Integrating Contractor)

2.0 PROCUREMENT

- 2.1 Early Procurement (Architect/Engineer)
- 2.2 Late Procurement (Architect/Engineer)

3.0 CONSTRUCTION

- 3.1 Not Used
- 3.2 Fixed-Price Construction (Two Contracts)

4.0 PROJECT INTEGRATION

- 4.0 Project Coordination (Integrating Contractor)

5.0 OTHER PROJECT COSTS

- 5.0 Other Project Costs (Integrating Contractor)

APPENDIX B

**BUDGET AUTHORIZED/
BUDGET OUTLAY SCHEDULE**

W-464 IMMOBILIZED HLW INTERIM STORAGE FACILITY PROJECT
TOTAL PROJECT COST (TPC)
BAFO SCHEDULE
\$(000)

| WBS | TOTAL COST | COST TO DATE | FY98 | FY99 | FY00 | | | | FY01 | | | | FY02 | | | |
|-----------------------------------|---------------|-----------------|-------------|-------------|------|---------------|---------------|---|------|---------------|---|---|------|--------------|---|---|
| | | | | | 1 | 2 | 3 | 4 | 1 | 2 | 3 | 4 | 1 | 2 | 3 | 4 |
| 1.0 ENGINEERING | | | | | | | | | | | | | | | | |
| 1.A DEFINITIVE DESIGN | 6400 | 0 | | | | 6400 / 6100 | | | | 0 / 300 | | | | | | |
| 1.C TITLE III | 5500 | 0 | | | | | 950 / 700 | | | 3200 / 2800 | | | | 1450 / 2100 | | |
| 1.D SARP/PSAR/FSAR/PERMITS/STARTU | 2200 | 0 | | | | | | | | 800 / 800 | | | | 400 / 600 | | |
| 2.0 PROCUREMENT | 43500 | 0 | | | | | | | | 21200 / 16300 | | | | 0 / 2400 | | |
| 3.0 CONSTRUCTION | | | | | | | | | | | | | | | | |
| 3.A C1 SITE PREPARATION | 10900 | 0 | | | | | | | | 7500 / 8400 | | | | 0 / 300 | | |
| 3.B C2 CONSTRUCTION | 6700 | 0 | | | | | 3000 / 2200 | | | 6700 / 5300 | | | | 0 / 1400 | | |
| 4.0 PROJECT INTEGRATION | 3100 | 0 | | | | | | | | | | | | | | |
| TOTAL ESTIMATED COST (TEC) | 78400 | 0 | 0 | 0 | | 1400 / 1100 | 33950 / 27200 | | | 1100 / 1100 | | | | 600 / 800 | | |
| 5.0 OTHER PROJECT COSTS (OPC) | 16300 | 140 | | | | | | | | 42000 / 43500 | | | | 2450 / 7700 | | |
| | | | | | | 1515 / 1515 | 2245 / 2245 | | | 3300 / 3300 | | | | 4000 / 4000 | | |
| TOTAL PROJECT COST (TPC) | 94700 | 140 | 1515 / 1515 | 2245 / 2245 | | 38450 / 31700 | 45500 / 47400 | | | | | | | 6450 / 11700 | | |

APPENDIX C

COST ESTIMATE SUMMARY

This appendix includes:

- Total Project Cost (TPC) Estimate
- Total Estimated Cost (TEC) Estimate
- Escalated Total Cost
- Contingency Estimate
- Decontamination and Decommissioning Estimate

FLUOR DANIEL NORTHWEST, INC.
NUMATEC HANFORD CORP.
JOB NO. W4648AA1
FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
IMMOBILIZED HLW INTERIM STORAGE SYSTEM
VAULT 2 & 3 - PHASE I (REV 1)
PHHCRO1 - PROJECT COST SUMMARY

PAGE 1 OF 31
DATE 03/31/98 14:55:24
BY 1LM/CGL/KLN/JJR

| SORT | DESCRIPTION | ESCALATED | | CONTINGENCY | | TOTAL DOLLARS |
|------|--|------------|----|-------------|---|---------------|
| | | TOTAL COST | % | TOTAL | % | |
| 020 | ENGINEERING - TITLE II | 5,360,000 | 19 | 1,010,000 | | 6,370,000 |
| 030 | ENGINEERING - TITLE III | 4,630,000 | 20 | 930,000 | | 5,560,000 |
| 060 | PROJECT MANAGEMENT | 3,160,000 | 0 | 0 | | 3,160,000 |
| 460 | IMPROVEMENTS TO LAND | 440,000 | 35 | 160,000 | | 600,000 |
| 501 | CONSTRUCTION - BUILDINGS | 8,700,000 | 27 | 2,310,000 | | 11,010,000 |
| 700 | SPECIAL EQUIP/PROCESS SYSTEMS | 41,470,000 | 19 | 8,040,000 | | 49,510,000 |
| | (ADJUSTED/ROUNDED) | 40,000 | | (50,000) | | (10,000) |
| | TOTAL ESTIMATED CONSTRUCTION COST (TECC) | 65,800,000 | 20 | 12,400,000 | | 78,200,000 |
| 900 | OTHER PROJECT COST | 18,090,000 | 2 | 360,000 | | 18,450,000 |
| | (ADJUSTED/ROUNDED) | 10,000 | | 40,000 | | 50,000 |
| | TOTAL OTHER PROJECT COST (OPC) | 18,100,000 | 2 | 400,000 | | 18,500,000 |
| | TOTAL PROJECT COST (TPC) | 81,900,000 | 16 | 12,800,000 | | 94,700,000 |

| | | | | |
|--------------------|--------------------|--------------------|--------------------|----------------|
| TYPE OF ESTIMATE | CONCEPTUAL REV. 1 | MARCH 31, 1998 | REMARKS: | REV. 0 3/27/98 |
| FOR LEAD ESTIMATOR | <i>[Signature]</i> | ESTIMATING MANAGER | <i>[Signature]</i> | |
| PROJECT MANAGER | <i>[Signature]</i> | | <i>[Signature]</i> | |
| CLIENT | <i>[Signature]</i> | | | |

(ROUNDED/ADJUSTED TO THE NEAREST "10,000 / 100,000" - PERCENTAGES NOT RECALCULATED TO REFLECT ROUNDING)

FLUOR DANIEL NORTHWEST, INC.
 KUMAR SEC HANFORD CORP.
 JOB NO. W464BAA1
 FILE NO. W464BAA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE I (REV 1)
 PHRCR02 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 2 OF 31
 DATE 03/31/98 14:55:30
 BY TLW/EDL/KLR/JJH

| WBS | DESCRIPTION | ESTIMATE SUBTOTAL | ESTIMATION TOTAL | SUB TOTAL | CONTINGENCY % | TOTAL | ALLOCATION | SITE | TOTAL DOLLARS |
|-------------|------------------------------------|----------------------|---------------------|--------------|------------------|-------|------------|----------|------------------|
| 1AA100 | DRAWINGS | 620888 | 5.63 | 34955 | 655843 | 20 | 131168 | 787012 | 242321 |
| 1AA200 | SPECIFICATIONS | 236215 | 5.63 | 13298 | 249513 | 25 | 62378 | 311892 | 96031 |
| 1AA300 | CHECKING & REVIEW | 261196 | 5.63 | 14705 | 275901 | 20 | 55180 | 331081 | 101940 |
| 1AA400 | REPORTS & STUDIES | 119250 | 5.63 | 6713 | 125963 | 20 | 25192 | 151156 | 453021 |
| 1AA500 | CALCS | 510280 | 5.63 | 28758 | 539008 | 25 | 134732 | 552740 | 881211 |
| 1AA600 | SUPPORT | 1557940 | 5.63 | 87712 | 1645652 | 20 | 388777 | 2034076 | 2338076 |
| 1AA700 | ESTIMATES | 183534 | 5.63 | 13184 | 196718 | 20 | 49472 | 201690 | 545571 |
| 1AA800 | SUBMITTAL REVIEWS | 200760 | 5.63 | 11363 | 212123 | 20 | 51812 | 206934 | 571637 |
| 1AA900 | QUALITY ASSURANCE | 3924281 | 5.63 | 220937 | 4145218 | 15 | 775582 | 4920800 | 589230 |
| SUBTOTAL 1A | DEFINITIVE DESIGN | | | | | 19 | | 243896 | 45174 |
| 1CC100 | TITLE III - ENGINEERING | 3252714 | 8.89 | 289166 | 3541880 | 20 | 708376 | 4250256 | 1308653 |
| SUBTOTAL 1C | TITLE III - ENGINEERING | | | | | 20 | | 4250256 | 1308653 |
| 1DDEE3 | MOBILIZE | 168454 | 0.00 | 0 | 168454 | 20 | 33690 | 202144 | 0 |
| 1DDEE4 | DEFINITIVE DESIGN (TITLE I & II) | 470960 | 0.00 | 0 | 470960 | 20 | 94192 | 565152 | 0 |
| 1DDEE5 | TITLE III | 1181989 | 0.00 | 0 | 1181989 | 20 | 236397 | 1418386 | 0 |
| SUBTOTAL 1D | PROJ SUPPORT (CAPITAL) | 1821403 | 0.00 | 0 | 1821403 | 20 | 364280 | 2185683 | 0 |
| SUBTOTAL 1 | ENGINEERING | 8998398 | 5.67 | 510103 | 9508501 | 19 | 1848239 | 11356740 | 2756723 |
| 210001 | SHIELDED CANISTER TRANSPORTER (P1) | 4860000 | 7.60 | 369360 | 5229360 | 15 | 784404 | 6013764 | 1323028 |
| 210005 | STANDARD STORAGE VEHICLES (P2) | 14054200 | 7.60 | 1220119 | 17274319 | 20 | 3454863 | 20729183 | 4560420 |
| 210007 | CASK TRANSPORT SYSTEMS (P2) | 4374000 | 7.60 | 332424 | 4706424 | 20 | 941284 | 5647708 | 142495 |
| SUBTOTAL 21 | EARLY PROCUREMENT (PHRC) | 25288200 | 7.60 | 1921903 | 27210103 | 19 | 5180552 | 32390655 | 7125944 |
| 220002 | TRANSFER PIT CRANE (P4) | 274320 | 8.11 | 22247 | 296567 | 15 | 44485 | 341052 | 75031 |
| 220003 | 40 TON CRANE (P9) | 1296000 | 8.11 | 105105 | 1401105 | 20 | 285569 | 1686674 | 354679 |
| 220004 | PIT WELD STATION (P5) | 685241 | 8.11 | 13868 | 699109 | 20 | 13868 | 927747 | 204104 |
| 220006 | CANISTER OVERPACKS (P6) | 275384 | 8.11 | 6113 | 281500 | 20 | 50252 | 305157 | 66333 |
| 220010 | CESSION OVERPACKS (P7) | | | | 81497 | 20 | 16299 | 97797 | 21515 |
| SUBTOTAL 22 | LATE PROCUREMENT (PHRC) | 2564641 | 8.11 | 207992 | 2772633 | 18 | 506752 | 3279386 | 721464 |
| SUBTOTAL | | | | | | | | | 4000851 |

FLUOR DANIEL NORTHWEST, INC.
 HUNATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING.**
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE I (REV 1)
 PHCRO2 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 3 OF 31
 DATE 03/31/98 14:55:30
 BY TLW/CDL/KLR/JJN

| WBS DESCRIPTION | ESTIMATE SUBTOTAL | ESTIMATION % | SUP TOTAL | CONTINGENCY % | SUP TOTAL | SITE ALLOCAT'N | TOTAL DOLLARS |
|--|-------------------|--------------|-----------|---------------|-----------|----------------|---------------|
| ***** | ***** | ***** | ***** | ***** | ***** | ***** | ***** |
| SUBTOTAL 2 PROCUREMENT (PHNC) | 27852841 | 7.65 | 2129895 | 19 | 5687305 | 7847409 | 43517451 |
| 320101 VAULTS 2 & 3 INTAKE & EXHAUST | 3766207 | 7.85 | 295647 | 20 | 812370 | 4874285 | 391159 |
| 320104 MODIFY ANNEK PIT (HOLD STATION) | 95026 | 7.85 | 7459 | 25 | 25621 | 128107 | 31342 |
| 320105 STORAGE TUBE & CANISTER OVERPACKS | 2607688 | 7.85 | 204703 | 20 | 52478 | 315649 | 156449 |
| 320106 VAULT 2 & 3 AIR FOILS | 11159 | 7.85 | 8723 | 25 | 13240 | 315649 | 102508 |
| 320108 CONCRETE EXHAUST LOUVERS | 560270 | 7.85 | 43961 | 25 | 131063 | 735315 | 161839 |
| SUBTOTAL 3201 F P CONSTRUCTION - C1 | 7140381 | 7.85 | 560519 | 21 | 1587508 | 9288410 | 1641515 |
| 320209 10-TON GENTRY CRANE (ANNEX) | 28852 | 8.89 | 2565 | 35 | 10996 | 42413 | 9503 |
| 320211 DEMOLITION (ANNEX) | 343482 | 8.89 | 30535 | 35 | 130906 | 504923 | 24347 |
| 320213 EQUIPMENT (ANNEX) | 65886 | 8.89 | 58375 | 35 | 25111 | 108512 | 5505 |
| 320214 CONCRETE (ANNEX) | 113217 | 8.89 | 98808 | 35 | 42378 | 1635344 | 83378 |
| 320215 BUILDINGS (ANNEX) | 23571 | 8.89 | 23449 | 35 | 100327 | 387747 | 18697 |
| 320217 WAREHOUSE (ANNEX) | 55771 | 8.89 | 49581 | 35 | 212355 | 819858 | 39534 |
| 320218 ELECTRICAL (ANNEX) | 310938 | 8.89 | 27642 | 35 | 118503 | 457084 | 82142 |
| 320220 EQUIPMENT RENTAL (CRANES) | 294975 | 8.89 | 26223 | 20 | 64239 | 385437 | 18586 |
| SUBTOTAL 3202 F P CONSTRUCTION - C2 | 4310246 | 8.89 | 383180 | 34 | 1594519 | 6287946 | 372292 |
| SUBTOTAL 32 F P CONSTRUCTION | 11450627 | 8.24 | 943700 | 26 | 3182028 | 15576357 | 2013807 |
| SUBTOTAL 3 CONSTRUCTION | 11450627 | 8.24 | 943700 | 26 | 3182028 | 15576357 | 2013807 |
| 4098A1 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | 0 | 3161944 | 0 | 3161944 |
| SUBTOTAL 40 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | 0 | 3161944 | 0 | 3161944 |
| SUBTOTAL 4 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | 0 | 3161944 | 0 | 3161944 |
| 502KA1 PROJECT MANAGEMENT/ADMIN | 5860413 | 0.00 | 0 | 0 | 5860413 | 0 | 5860413 |
| 502KB1 DESIGN | 1969111 | 0.00 | 0 | 0 | 1969111 | 0 | 1969111 |
| 502KC1 PROCUREMENT | 391461 | 0.00 | 0 | 0 | 391461 | 0 | 391461 |
| 502KD1 ENVIRONMENTAL | 1734994 | 0.00 | 0 | 0 | 1734994 | 0 | 1734994 |

FLUOR DANIEL NORTHWEST, INC.
 NUMATEC HANFORD CORP.
 JOB NO. W464BAA1
 FILE NO. W464BAA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHMC802 - WORK BREAKDOWN STRUCTURE (WBS) SUMMARY

PAGE 4 OF 31
 DATE 05/31/98 14:55:30
 BY TLW/CDL/KLA/JJH

| WBS DESCRIPTION | ESTIMATE | | ESCALATION | | SUB | | CONTINGENCY | | SUB | | SITE | | TOTAL | |
|--------------------------------|------------|---------|------------|------------|-------|------------|-------------|------------|------------|----------|---------|----------|-------|----------|
| | SUBTOTAL | % TOTAL | % TOTAL | % TOTAL | TOTAL | % | TOTAL | TOTAL | ALLOCATION | DOLLARS | DOLLARS | DOLLARS | | |
| 502K61 SAFETY | 3227502 | 0.00 | 0 | 3227502 | 0 | 0 | 0 | 3227502 | 0 | 3227502 | 0 | 3227502 | 0 | 3227502 |
| 502K61 QUALITY ASSURANCE | 126869 | 0.00 | 0 | 126869 | 0 | 0 | 0 | 126869 | 0 | 126869 | 0 | 126869 | 0 | 126869 |
| 502K61 ORR & STARTUP | 2962819 | 0.00 | 0 | 2962819 | 0 | 0 | 0 | 2962819 | 0 | 2962819 | 0 | 2962819 | 0 | 2962819 |
| SUBTOTAL 50 OTHER PROJECT COST | 16273169 | 0.00 | 0 | 16273169 | 0 | 0 | 0 | 16273169 | 0 | 16273169 | 0 | 16273169 | 0 | 16273169 |
| SUBTOTAL 5 OTHER PROJECT COST | 16273169 | 0.00 | 0 | 16273169 | 0 | 0 | 0 | 16273169 | 0 | 16273169 | 0 | 16273169 | 0 | 16273169 |
| PROJECT TOTAL | 67,736,979 | 5.29 | 3,583,699 | 71,320,679 | 15 | 10,717,573 | 82,038,253 | 12,617,940 | 94,656,193 | | | | | |

FLUOR DANIEL NORTHWEST, INC.
NUMATEC HANFORD CORP.
JOB NO. W4648AA1
FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
IMMOBILIZED HLW INTERIM STORAGE SYSTEM
VAULT 2 & 3 PHASE 1
PHRCR03 - ESTIMATE BASIS SHEET

PAGE 5 OF 31
DATE 03/31/98
BY TLW/CDL

1. ESTIMATE PURPOSE

A. CONCEPTUAL COST ESTIMATE: THIS ESTIMATE WILL BE USED TO ESTABLISH THE PROJECT BUDGET(BASELINE).

2. ESTIMATE TECHNICAL BASIS

- A. THIS ESTIMATE HAS BEEN PREPARED FOR THE IMMOBILIZED HLW INTERIM STORAGE SYSTEM VAULT 2 & 3 PHASE 1 PROJECT AS REQUESTED BY NUMATEC HANFORD CO.
- B. A DESCRIPTION OF THE TECHNICAL SCOPE OF WORK MAY BE FOUND IN THE FOLLOWING REFERENCE DOCUMENTS:
 - 1.) DRAFT CONCEPTUAL DESIGN REPORT FOR IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY (PHASE 1). DRAWINGS ES-W464-H01 (SHEETS 1 THROUGH 6), ES-W464-H02, ES-W464-H03, ES-W464-H04, ES-W464-H05, ES-W464-H06, ES-W464-H07, ES-W464-H08 (SHEETS 1 THROUGH 3), ES-W464-H09, ES-W464-H10 (SHEETS 1 THROUGH 6)
 - 2.) REQUEST FOR ESTIMATE DATED 2/4/98.

C. THIS ESTIMATE UTILIZES AN ESTIMATE WORK BREAKDOWN STRUCTURE WHICH INTERFACES WITH THE PROJECT WORK BREAKDOWN STRUCTURE AS PROVIDED BY PROJECT MANAGEMENT/PROJECT CONTROLS.

3. ESTIMATE METHODOLOGY

A. DIRECT COSTS:

- (1) CONSTRUCTION LABOR, MATERIALS, AND EQUIPMENT HAVE BEEN ESTIMATED BASED UPON ONE OR MORE OF THE FOLLOWING STANDARD CONSTRUCTION ESTIMATES FOR LIVE ACTIVITIES, AND PUBLISHED ESTIMATING MANUALS/DATABASES: IN HOUSE DATABASES, CURRENT TASKS. THE UNIT RATES MAY HAVE BEEN FACTORED/ADJUSTED BY THE ESTIMATOR AS APPROPRIATE TO REFLECT INFLUENCES BY CONTRACT, WORK SITE, OR OTHER IDENTIFIED PROJECT OR SPECIAL CONDITIONS.
- (2) FLUOR DANIEL HANFORD DIRECT COSTS HAVE BEEN PROVIDED BY FDNW PROJECT MANAGEMENT FOR INCLUSION INTO THIS ESTIMATE.
- (3) PROJECT INTEGRATION AND OTHER PROJECT COSTS HAVE BEEN PROVIDED BY HNC PROJECT MANAGEMENT.

B. DIRECT COST FACTORS

- (1) SALES TAX HAS BEEN APPLIED TO ALL MATERIALS AND EQUIPMENT PURCHASES AT 8%.
- (2) CONTRACT ADMINISTRATION FACTOR OF 18.75% HAS BEEN APPLIED TO DIRECT CONTRACT VALUE WHICH INCLUDES COST FOR BID PACKAGE PREPARATION, CONTRACT MANAGEMENT & ADMINISTRATION AND PROJECT MANAGEMENT & PLANNING SUPPORT.

C. INDIRECT COSTS

FIXED PRICE CONTRACTOR OVERHEAD, PROFIT, BOND AND INSURANCE COSTS HAVE BEEN APPLIED ARE THE FOLLOWING PERCENTAGES: LABOR = 30%, EQUIPMENT USE = 10%, MATERIAL = 30% AND SUBCONTRACT = 15%, AND ARE REFLECTED IN THE "H04P/H81" COLUMN OF THE ESTIMATE DETAIL REPORT.

D. RATES

- (1) FOR ESTIMATING PURPOSES, AVERAGE FDNW RATES BY OPERATIONS CODE HAVE BEEN DEVELOPED BASED UPON RECENT COST HISTORY AND ADJUSTED TO REFLECT CURRENT MARKET RATES.
- (2) LABOR RATES FOR DIRECT SERVICES (CONSTRUCTION CRAFT) LABOR RATES ARE THOSE LISTED IN APPENDIX A OF THE HANFORD SITE LICENSING AGREEMENT (HSSA). THE HSSA RATES INCLUDE BASE WAGE, FRINGE BENEFITS AND OTHER COMPENSATION AS NEGOTIATED BETWEEN FLUOR DANIEL HANFORD INC. AND THE NATIONAL BUILDING AND CONSTRUCTION TRADES DEPARTMENT, AFL-CIO. FLUOR DANIEL NORTHWEST INCORPORATES FACTORS TO COVER ADDITIONAL COSTS FOR WORKMANS COMPENSATION, FICA AND STATE AND FEDERAL UNEMPLOYMENT INSURANCE TO DEVELOPE A FULLY BURDENED RATE BY CRAFT.

FLUOR DANIEL NORTHWEST, INC.
 NUMATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE I
 PHNCR03 - ESTIMATE BASIS SHEET

PAGE 6 OF 31
 DATE 03/31/98
 BY TLU/CDL

- (3) EDH & PHNC SUBCONTRACTOR STANDARD LABOR RATES ARE THOSE LISTED IN THE FINANCIAL DATA SYSTEM (FDS) FDS1 321R REPORT ORGANIZATION RATES PLUS ADJRS.

E. SITE ALLOCATIONS FACTORS

SITE ALLOCATION FACTORS ARE DEVELOPED AND PROVIDED BY FLUOR DANIEL HANFORD (FDH) FOR ESTIMATING USE.

- (1) GOVERNMENT FURNISHED SERVICES RATE IS APPLIED TO ALL COSTS TO LIQUIDATE GOVERNMENT FURNISHED SERVICES PROVIDED TO THE ENTERPRISE COMPANIES: 7% FOR FDH AND FOR FOMS (CONSTRUCTION).
- (2) HANFORD SITE ESS AND G&A RATE OF 22% IS APPLIED TO ALL COSTS TO LIQUIDATE THE HANFORD GENERAL & ADMINISTRATIVE COSTS AND ESSENTIAL SITE SERVICES (I.E. FIRE, WATER, ELECTRICAL, ETC.).

FDH APPLIES THE ABOVE FACTORS TO ESTIMATED COSTS AS FOLLOWS:

- (1) FDS GFS/G&A/ESS FACTOR: A COMPOSITE FACTOR OF 30.54% HAS BEEN APPLIED TO TOTAL FDH FIXED PRICE CONSTRUCTION MANAGEMENT WHICH INCLUDES GOVERNMENT FURNISHED SERVICES (GFS), SITE G&A, AND ESSENTIAL SITE SERVICES.
- (2) FDS GFS/G&A/LABOR FACTOR: A COMPOSITE FACTOR HAS BEEN APPLIED TO TOTAL FDH LABOR COSTS AS FOLLOWS:
 AE/CH COSTS = 30.54%, FOMS CONSTRUCTION LABOR = 30.54%, FOMS CONSTRUCTION MANAGEMENT LABOR = 30.54%, FDH CONTRACT MANAGEMENT AND ADMINISTRATION = 30.54%
- (3) FDS MPR/G&A MATERIAL FACTOR: A COMPOSITE FACTOR OF 30.54% HAS BEEN APPLIED TO TOTAL FDH MATERIAL COST.

4. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE JANUARY 1997 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FH-50. ESCALATION RATES FOR WBS 10, 40, AND 50 WERE BASED ON THE PROJECT HANFORD MANAGEMENT CONTRACT FY 1998 COMPANY PLANNING RATES AS UTILIZED IN THE FY 1998 MULTI-YEAR WORK PLAN. THEY ARE: FY1999 1.027, FY 2000 1.053, FY 2001 1.083, FY 2002 1.112. THESE RATES ARE INCLUSIVE WITH THE COSTS PROVIDED BY OTHERS. FOR ESCALATION SHOWN IN THIS ESTIMATE SEE ECONOMIC ANALYSIS SCHEDULE.

5. CONTINGENCY

A. DEFINITION OF CONTINGENCY AS PROVIDED BY DOE

"CONTINGENCY COVERS COSTS THAT MAY RESULT FROM INCOMPLETE DESIGN, UNFORESEEN AND UNPREDICTABLE CONDITIONS, OR UNCERTAINTIES WITHIN THE DEFINED PROJECT SCOPE. THE AMOUNT OF CONTINGENCY WILL DEPEND ON THE STATUS OF DESIGN, PROCUREMENT, AND CONSTRUCTION, AND THE COMPLEXITY AND UNCERTAINTIES OF THE COMPONENT PARTS OF THE PROJECT. CONTINGENCY IS NOT TO BE USED TO AVOID MAKING AN ACCURATE ASSESSMENT OF EXPECTED COST" (OFFICE OF WASTE MANAGEMENT (EW-30) COST AND SCHEDULE GUIDE).

B. CONTINGENCY ALLOWANCE GUIDELINES

THE DOE GUIDELINE CONTINGENCY ALLOWANCE FOR A...
 CONCEPTUAL PHASE UPON ORD/CDR)
 STANDARD 15-25%, EXPERIMENTAL/SPECIAL CONDITIONS UP TO 40%.

C. METHODOLOGY

CONTINGENCY IS EVALUATED AT THE LOWEST WORK BREAKDOWN STRUCTURE (WBS) LEVEL WITHIN THE COST ESTIMATE DETAILS. IT IS SUMMARIZED AT UPPER WBS LEVELS AND REPORTED ON THE SUMMARY REPORTS.

FLUOR DANIEL NORTHWEST, INC.
NUMATEC HANFORD CORP.
JOB NO. W4648AA1
FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
IMMOBILIZED HLW INTERIM STORAGE SYSTEM
VAULT 2 & 3 PHASE I
PRMCR03 - ESTIMATE BASIS SHEET

PAGE 7 OF 31
DATE 03/31/98
BY TLM/cdl

D. ANALYSIS

AN ASSESSMENT OF DESIGN MATURITY, WORK COMPLEXITY AND PROJECT UNCERTAINTIES HAS BEEN PERFORMED. AN EXPLANATION OF THIS ASSESSMENT AND CONTINGENCY RATES WHICH HAVE BEEN ADDED TO THE COST OF WORK ARE AS FOLLOWS:

ENGINEERING

WBS 1A AND 1C DEFINITIVE DESIGN/TITLE III
WHEN DOING REMODEL AND RENOVATION WORK.

UNCERTAINTIES THAT ARE GENERALLY ENCOUNTERED

WBS 1D PROJECT SUPPORT (CAPITAL)
CONTINGENCY IS INCLUDED IN THE COSTS PROVIDED TO ESTIMATING BY THE CLIENT.

AVERAGE ENGINEERING CONTINGENCY IS 20%

PROCUREMENT

WBS 21
AN AVERAGE CONTINGENCY OF 19% IS APPLIED FOR THE FOLLOWING REASONS: 1.) THE SHIELDED CANISTER TRANSPORTER IS BASED UPON A SIMILAR UNIT SUPPLIED TO THE SAVANNAH RIVER SITE. DISCUSSION WITH THE SUPPLIER INDICATES THE TRANSPORTER COULD BE BUILT FOR APPROXIMATELY THE SAME PRICE AND CONTINGENCY WOULD COVER POSSIBLE CHANGES TO SUPPORT A 4.5 METER CANISTER. 2.) THE STORAGE TUBES ARE BASED UPON PRELIMINARY QUOTES FOR FABRICATION TO THE INTENT OF ASME SECTION III AND IMPACTS WILL NOT BE KNOWN UNTIL THE SPECIFICATION IS FINALIZED. 3.) THE CASK VENDOR QUOTE IS BASED UPON PRELIMINARY DESIGN INFORMATION (SKETCHES) AND THICKNESS OF CASK WALLS HAS NOT BEEN DETERMINED AND COULD POTENTIALLY IMPACT COST.

WBS 22
AN AVERAGE CONTINGENCY OF 22% IS APPLIED FOR THE FOLLOWING REASONS: 1.) THE CRANE VENDOR PROVIDED PRELIMINARY QUOTES FROM VERBAL DESCRIPTIONS, WITHOUT SKETCHES, AND BECAUSE THE EXISTING CSB 60 TON CRANE COST IS INCREASING. 2.) THE WELD STATION PIT EQUIPMENT COSTS ARE BASED UPON A CSB STUDY ESTIMATE AND EXISTING PURCHASE REQUIREMENTS. 3.) CANISTER OVERPACK QUOTES ARE BASED UPON PRELIMINARY VENDOR QUOTES FOR FABRICATION TO THE INTENT OF ASME SECTION III AND IMPACTS WILL NOT BE KNOWN UNTIL THE SPECIFICATION IS FINALIZED. 4.) THE CRANE LIFTING CAPACITY IS UNKNOWN UNTIL THE CRANE IS SPECIFICALLY ORDERED. THEREFORE THE SHIELDING, COOLING, HANDLING, OVERPACK, AND TRANSPORTATION REQUIREMENTS CAN NOT BE VALIDATED.

AVERAGE PROCUREMENT CONTINGENCY IS 19%

CONSTRUCTION

WBS 3201 C1 CONSTRUCTION
AN AVERAGE CONTINGENCY OF 21% IS APPLIED FOR THE FOLLOWING REASONS: 1.) INTAKE CASK LIFTING EQUIPMENT ATTACHED DETAILS DRAWINGS WERE NOT AVAILABLE AT THE TIME OF SCOPING PREPARATION. 2.) THE 60 TON CRANE INSTALLATION IS BASED UPON A LAST MINUTE SCOPE CHANGE. 3.) STORAGE TUBE AND CANISTER OVERPACKS EQUIPMENT IS

** IEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 .VAULT 2 & 3 PHASE I
 PHMCR03 - ESTIMATE BASIS SHEET

FLUOR DANIEL NORTHWEST, INC.
NUMATEC HANFORD CORP.
JOB NO. W464BAA1
FILE NO. W464BAA1

AS SIMILAR TO THE CSB PROJECT WHICH IS CURRENTLY ON HOLD UNTIL THEY FINISH A DROP TEST. 4.) THE OVERPACK PIT GUIDE INSTALLATION IS PERFORMED IN A CONFINED SPACE. 5.) THE NATURAL CONVECTION COOLING DESIGN IS BASED ON A SINGLE EXHAUST STACK. 6.) THE WIND TUNNEL TESTING WAS PERFORMED FOR A SINGLE STACK. UNTIL TESTING CAN BE COMPLETED FOR A THREE STACK DESIGN, THE POSSIBLE FLOW INTERFERENCES BETWEEN STACKS IS AN UNCERTAINTY.

WBS 3202 C2 CONSTRUCTION
AN AVERAGE CONTINGENT OF 34% IS APPLIED FOR THE FOLLOWING REASONS: 1.) THE TRANSFER PIT GUIDE INSTALLATION IS PERFORMED IN A CONFINED SPACE. 2.) THE ANNEX ADDITION TAKEOFF AND MATERIAL PRICING WAS PERFORMED IN A RESTRAINED UTILITY RELOCATION PERIOD. 3.) UTILITY RELOCATION INSIDE THE CSB, FOR THE ANNEX ADDITION, IS UNCLEAR AND IS NOT DEFINED ON DRAWINGS. 4.) THE TORNADO DOORS DEPICTED ON THE DRAWINGS DO NOT HAVE DEFINITIVE DETAILS OTHER THAN SIZE.

AVERAGE CONSTRUCTION CONTINGENCY IS 26%

WBS 50 PROJECT SUPPORT
CONTINGENCY IS INCLUDED IN THE COSTS PROVIDED TO ESTIMATING BY THE CLIENT.

AVERAGE PROJECT CONTINGENCY IS 15%

6. ROUNDING

THE PROJECT COST SUMMARY REPORT IS SUMMARIZED AND ADJUSTED/ROUNDED AS FOLLOWS:
 THE ESCALATED TOTAL COST COLUMN, CONTINGENCY TOTAL COLUMN AND TOTAL DOLLARS COLUMN SUB-TOTALS ARE SUMMARIZED BY FUNCTION.
 THE COLUMN SUB-TOTALS ARE ADJUSTED/ROUNDED TO THE NEAREST \$10,000. THE PROJECT TOTAL SUMMARY LINE TOTALS ARE
 ADJUSTED/ROUNDED TO THE NEAREST \$100,000.

7. REMARKS

MAJOR ASSUMPTIONS WHICH HAVE BEEN MADE IN THE PREPARATION OF THIS ESTIMATE ARE AS FOLLOWS:

- A. ALLOWED CHARGES FOR WELDING STATION PIT WORK IS RADIOLOGICALLY CLEAN.
- B. ASSUMING THAT THE WELDING STATION PIT WORK IS IN THE SCOPE OF THIS COST ESTIMATE.
- C. INSULATING CONCRETE WILL BE INSTALLED BY THE CSR PROJECT AND IS NOT INCLUDED.
- D. INSTALLATION OF TUBES IS BASED UPON NON RAD/CLEAN WORK AND WITHOUT DISRUPTION FROM PLANT OPERATIONS. ALLOWANCES FOR WORKER SECURITY CLEARANCES IS NOT INCLUDED.
- E. COST ALLOWANCES FOR THE WELD STATION WERE EXTRACTED FROM THE CSR WELD STATION COST ESTIMATE, DATED 23 JAN, 1998.
- F. ALLOWANCES FOR AN ULTRA SONIC TESTER IS INCLUDED, BUT ALLOWANCES FOR SPECIAL DIE CHECK EQUIPMENT IS NOT.
- G. CONSTRUCTION LABOR DOES NOT INCLUDE OVERTIME BUT DOES INCLUDE SHIFT DIFFERENTIAL FOR TUBE INSTALLATION DURING SWING SHIFT.
- H. THIS COST ESTIMATE ASSUMES THAT PDW WILL PROVIDE EQUIPMENT (IDENTIFIED IN PROCUREMENT WBS 2.0) TO THE FP CONTRACTOR.
- I. THE FOLLOWING VENDORS PROVIDED "BUDGET" QUOTES:
 1. OREGON IRON WORKS - TUBE ASSEMBLIES
 2. TRANSCORP - CRANES, CHASSIS AND TRAILERS
 3. TRANSCORP - CRANES, CHASSIS AND TRAILERS
 4. DEER WAGON CRANE - ABSORBERS
 5. DEER WAGON CRANE - ABSORBERS
 6. DEER WAGON CRANE - ABSORBERS
 7. DEER WAGON CRANE - ABSORBERS
 8. DEER WAGON CRANE - ABSORBERS
 9. DEER WAGON CRANE - ABSORBERS
 10. DEER WAGON CRANE - ABSORBERS
 11. DEER WAGON CRANE - ABSORBERS
 12. DEER WAGON CRANE - ABSORBERS
 13. DEER WAGON CRANE - ABSORBERS
 14. DEER WAGON CRANE - ABSORBERS
 15. DEER WAGON CRANE - ABSORBERS
 16. DEER WAGON CRANE - ABSORBERS
 17. DEER WAGON CRANE - ABSORBERS
 18. DEER WAGON CRANE - ABSORBERS
 19. DEER WAGON CRANE - ABSORBERS
 20. DEER WAGON CRANE - ABSORBERS
 21. DEER WAGON CRANE - ABSORBERS
 22. DEER WAGON CRANE - ABSORBERS
 23. DEER WAGON CRANE - ABSORBERS
 24. DEER WAGON CRANE - ABSORBERS
 25. DEER WAGON CRANE - ABSORBERS
 26. DEER WAGON CRANE - ABSORBERS
 27. DEER WAGON CRANE - ABSORBERS
 28. DEER WAGON CRANE - ABSORBERS
 29. DEER WAGON CRANE - ABSORBERS
 30. DEER WAGON CRANE - ABSORBERS
 31. DEER WAGON CRANE - ABSORBERS
 32. DEER WAGON CRANE - ABSORBERS
 33. DEER WAGON CRANE - ABSORBERS
 34. DEER WAGON CRANE - ABSORBERS
 35. DEER WAGON CRANE - ABSORBERS
 36. DEER WAGON CRANE - ABSORBERS
 37. DEER WAGON CRANE - ABSORBERS
 38. DEER WAGON CRANE - ABSORBERS
 39. DEER WAGON CRANE - ABSORBERS
 40. DEER WAGON CRANE - ABSORBERS
 41. DEER WAGON CRANE - ABSORBERS
 42. DEER WAGON CRANE - ABSORBERS
 43. DEER WAGON CRANE - ABSORBERS
 44. DEER WAGON CRANE - ABSORBERS
 45. DEER WAGON CRANE - ABSORBERS
 46. DEER WAGON CRANE - ABSORBERS
 47. DEER WAGON CRANE - ABSORBERS
 48. DEER WAGON CRANE - ABSORBERS
 49. DEER WAGON CRANE - ABSORBERS
 50. DEER WAGON CRANE - ABSORBERS
 51. DEER WAGON CRANE - ABSORBERS
 52. DEER WAGON CRANE - ABSORBERS
 53. DEER WAGON CRANE - ABSORBERS
 54. DEER WAGON CRANE - ABSORBERS
 55. DEER WAGON CRANE - ABSORBERS
 56. DEER WAGON CRANE - ABSORBERS
 57. DEER WAGON CRANE - ABSORBERS
 58. DEER WAGON CRANE - ABSORBERS
 59. DEER WAGON CRANE - ABSORBERS
 60. DEER WAGON CRANE - ABSORBERS
 61. DEER WAGON CRANE - ABSORBERS
 62. DEER WAGON CRANE - ABSORBERS
 63. DEER WAGON CRANE - ABSORBERS
 64. DEER WAGON CRANE - ABSORBERS
 65. DEER WAGON CRANE - ABSORBERS
 66. DEER WAGON CRANE - ABSORBERS
 67. DEER WAGON CRANE - ABSORBERS
 68. DEER WAGON CRANE - ABSORBERS
 69. DEER WAGON CRANE - ABSORBERS
 70. DEER WAGON CRANE - ABSORBERS
 71. DEER WAGON CRANE - ABSORBERS
 72. DEER WAGON CRANE - ABSORBERS
 73. DEER WAGON CRANE - ABSORBERS
 74. DEER WAGON CRANE - ABSORBERS
 75. DEER WAGON CRANE - ABSORBERS
 76. DEER WAGON CRANE - ABSORBERS
 77. DEER WAGON CRANE - ABSORBERS
 78. DEER WAGON CRANE - ABSORBERS
 79. DEER WAGON CRANE - ABSORBERS
 80. DEER WAGON CRANE - ABSORBERS
 81. DEER WAGON CRANE - ABSORBERS
 82. DEER WAGON CRANE - ABSORBERS
 83. DEER WAGON CRANE - ABSORBERS
 84. DEER WAGON CRANE - ABSORBERS
 85. DEER WAGON CRANE - ABSORBERS
 86. DEER WAGON CRANE - ABSORBERS
 87. DEER WAGON CRANE - ABSORBERS
 88. DEER WAGON CRANE - ABSORBERS
 89. DEER WAGON CRANE - ABSORBERS
 90. DEER WAGON CRANE - ABSORBERS
 91. DEER WAGON CRANE - ABSORBERS
 92. DEER WAGON CRANE - ABSORBERS
 93. DEER WAGON CRANE - ABSORBERS
 94. DEER WAGON CRANE - ABSORBERS
 95. DEER WAGON CRANE - ABSORBERS
 96. DEER WAGON CRANE - ABSORBERS
 97. DEER WAGON CRANE - ABSORBERS
 98. DEER WAGON CRANE - ABSORBERS
 99. DEER WAGON CRANE - ABSORBERS
 100. DEER WAGON CRANE - ABSORBERS
- J. TEN ABSORBERS ARE INCLUDED IN THE COST ESTIMATE. THE BALANCE OF ABSORBERS ARE CONSIDERED AN OPERATIONAL EXPENSE.
- K. CONTINGENCY FOR OPC'S IS INCLUDED IN THE COSTS PROVIDED TO ESTIMATING, EXCEPT FOR WBS 1D AS DIRECTED BY THE CLIENT.
- L. ALLOWANCES FOR SECURITY GUARDS, DURING CONSTRUCTION, ARE NOT INCLUDED.
- M. COSTS FOR TITLE III ARE ESTIMATED BASED UPON EXPERIENCE AND LESSONS LEARNED FROM THE CSR. A STAFFING ASSUMPTION HAS BEEN IDENTIFIED AND STAFFING HOURS ARE BASED UPON LEVEL LOADING TO THE SCHEDULE.

FLUOR DANIEL NORTHWEST, INC.
 HUMATEC HANFORD CORP.
 JOB NO. W464BAA1
 FILE NO. W464BAA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIN STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHNCR04 - COMPANY/HBS SUMMARY

PAGE 9 OF 31
 DATE 03/31/98 14:55:54
 BY TLH/COL/KLR/JJH

| SORT | DESCRIPTION | ESTIMATE | % | SUB | CONTINGENCY | SUB | SITE | TOTAL |
|----------|-------------------------------------|----------|------|--------|-------------|---------|------------|----------|
| CODE/HBS | | SUBTOTAL | | TOTAL | % | TOTAL | ALLOCATION | DOLLARS |
| | | | | | | | | |
| FDNW | FLUOR DANIEL NORTHWEST | | | | | | | |
| 1AA100 | DRAWINGS | 620888 | 5.63 | 34955 | 20 | 131168 | 655843 | 1029334 |
| 1AA200 | SPECIFICATIONS | 236215 | 5.63 | 13298 | 25 | 62378 | 249513 | 407924 |
| 1AA300 | CHECKING & REVIEW | 261196 | 5.63 | 14705 | 20 | 5180 | 311892 | 433081 |
| 1AA400 | REPORTS & STUDIES | 119250 | 5.63 | 6713 | 20 | 25192 | 151156 | 101940 |
| 1AA500 | CALCS | 510280 | 5.63 | 29228 | 25 | 125963 | 46541 | 197667 |
| 1AA600 | SUPPORT | 1527940 | 5.63 | 87712 | 25 | 246847 | 1892499 | 881211 |
| 1AA700 | ESTIMATES | 135554 | 5.63 | 10334 | 15 | 38777 | 232465 | 2438076 |
| 1AA800 | SUBMITTAL REVIEWS | 234178 | 5.63 | 13184 | 20 | 49472 | 296834 | 304303 |
| 1AA900 | QUALITY ASSURANCE | 200780 | 5.63 | 11303 | 15 | 31812 | 243896 | 388230 |
| | | | | | | | | 289070 |
| | SUBTOTAL 1A DEFINITIVE DESIGN | 3924281 | 5.63 | 220937 | 19 | 775582 | 4920800 | 6368870 |
| 1CC100 | TITLE III - ENGINEERING | 3252714 | 8.89 | 289166 | 20 | 708376 | 4250256 | 5558910 |
| | | | | | | | | 1308653 |
| | SUBTOTAL 1C TITLE III - ENGINEERING | 3252714 | 8.89 | 289166 | 20 | 708376 | 4250256 | 5558910 |
| 1D9E03 | MOBILIZE | 97735 | 0.00 | 0 | 20 | 19547 | 117282 | 0 |
| 1D9E04 | DEFINITIVE DESIGN (TITLE I & II) | 470960 | 0.00 | 0 | 20 | 94192 | 565152 | 0 |
| 1D9E05 | TITLE III | 1181989 | 0.00 | 0 | 20 | 236397 | 1418386 | 0 |
| | | | | | | | | 0 |
| | SUBTOTAL 1D PROJ SUPPORT (CAPITAL) | 1750684 | 0.00 | 0 | 20 | 350136 | 2100820 | 0 |
| | | | | | | | | 0 |
| | SUBTOTAL 1 ENGINEERING | 8927679 | 5.71 | 510103 | 19 | 1834095 | 11271878 | 14028601 |
| | | | | | | | | 2756723 |
| 320101 | VAULTS 2 & 3 INTAKE & EXHAUST | 3766207 | 7.85 | 295647 | 20 | 812370 | 4874225 | 5263365 |
| 320104 | MODIFY ANNEX PIT (WELD STATION) | 95026 | 7.85 | 7459 | 25 | 25621 | 128107 | 391139 |
| 320105 | STORAGE TUBE & CANISTER OVERPACK | 2607688 | 7.85 | 204703 | 20 | 562478 | 3374870 | 1504498 |
| 320106 | VAULT 2 & 3 AIR FOILS | 111189 | 7.85 | 8728 | 30 | 35975 | 155992 | 4405555 |
| 320108 | CONCRETE EXHAUST LOUVERS | 560270 | 7.85 | 43981 | 25 | 151063 | 755315 | 182401 |
| | | | | | | | | 917134 |
| | SUBTOTAL 3201 F P CONSTRUCTION - C1 | 7140381 | 7.85 | 560519 | 21 | 1587508 | 9288410 | 161839 |
| | | | | | | | | 10929926 |
| 320209 | 10-TON GANTRY CRANE (ANNEX) | 28852 | 8.89 | 2565 | 35 | 10996 | 42413 | 519177 |
| 320211 | DEMOLITION (ANNEX) | 343482 | 8.89 | 30535 | 35 | 139066 | 504923 | 520271 |
| 320213 | EQUIPMENT (ANNEX) | 658886 | 8.89 | 58575 | 35 | 251111 | 968573 | 24347 |
| | | | | | | | | 1015279 |

FLUOR DANIEL NORTHWEST, INC.
 HUNATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHMCR04 - COMPANY/MBS SUMMARY

PAGE 10 OF 31
 DATE 03/31/98 14:55:54
 BY TLM/COL/KLR/JJM

| SORT CODE/USR | DESCRIPTION | ESTIMATE | | ESCALATION | | SUB | | CONTINGENCY | SUB | | SITE ALLOCAT'N | TOTAL DOLLARS |
|--------------------------------------|------------------------------------|----------|------|------------|----------|-------|---------|-------------|----------|----------|-------------------|------------------|
| | | SUBTOTAL | % | TOTAL | % | TOTAL | % | TOTAL | TOTAL | % | | |
| 320214 | CONCRETE (ANNEX) | 759151 | 8.89 | 65710 | 804861 | 35 | 281701 | 1086563 | 52595 | 1138958 | | |
| 320215 | BUILDINGS (ANNEX) | 1112467 | 8.89 | 98898 | 1211366 | 35 | 425978 | 1635344 | 80378 | 1715722 | | |
| 320216 | STEVENWORK (ANNEX) | 263771 | 8.89 | 23449 | 287220 | 35 | 100527 | 387747 | 18697 | 406444 | | |
| 320217 | HVAC (ANNEX) | 557721 | 8.89 | 4581 | 607502 | 35 | 212555 | 819858 | 35934 | 855933 | | |
| 320218 | ELECTRICAL (ANNEX) | 510938 | 8.89 | 27642 | 538581 | 35 | 118505 | 457084 | 82142 | 475826 | | |
| 320220 | EQUIPMENT RENTAL (CRANES) | 294975 | 8.89 | 26223 | 321198 | 20 | 84259 | 385437 | 18586 | 404024 | | |
| SUBTOTAL 3202 F P CONSTRUCTION - C2 | | 4310246 | 8.89 | 383180 | 4693427 | 34 | 1594519 | 6287946 | 372292 | 6660238 | | |
| SUBTOTAL 32 | F P CONSTRUCTION | 11450627 | 8.24 | 943700 | 12394328 | 26 | 3182028 | 15576357 | 2013807 | 17590165 | | |
| SUBTOTAL 3 | CONSTRUCTION | 11450627 | 8.24 | 943700 | 12394328 | 26 | 3182028 | 15576357 | 2013807 | 17590165 | | |
| TOTAL FDNW FLUOR DANIEL NORTHWEST | | 20378306 | 7.13 | 1453804 | 21832111 | 23 | 5016124 | 26848235 | 4770530 | 31618766 | | |
| LNNC LOCKHEED MARTIN HANFORD CORP. | | | | | | | | | | | | |
| 1D9EE3 MOBILIZE | | 17871 | 0.00 | 0 | 17871 | 20 | 3574 | 21445 | 0 | 21445 | | |
| SUBTOTAL 1D PROJ SUPPORT (CAPITAL) | | 17871 | 0.00 | 0 | 17871 | 20 | 3574 | 21445 | 0 | 21445 | | |
| SUBTOTAL 1 ENGINEERING | | 17871 | 0.00 | 0 | 17871 | 20 | 3574 | 21445 | 0 | 21445 | | |
| 210001 | SHIELDED CANISTER TRANSPORTER (P1) | 4860000 | 7.60 | 369360 | 5229360 | 15 | 784404 | 6013764 | 1323028 | 7336792 | | |
| 210003 | STANDARD STORAGE TUBES (P3) | 16054200 | 7.60 | 1220119 | 17274319 | 20 | 3451883 | 20729183 | 45560420 | 25289603 | | |
| 210007 | CASK TRANSPORT SYSTEMS (P2) | 4374000 | 7.60 | 352424 | 4706424 | 20 | 941284 | 5647708 | 125495 | 6890204 | | |
| SUBTOTAL 21 EARLY PROCUREMENT (PHMC) | | 25288200 | 7.60 | 1921903 | 27210103 | 19 | 5180552 | 32390655 | 7125944 | 39516600 | | |
| 220002 | TRANSFER PIT CRANE (P4) | 274320 | 8.11 | 22247 | 296567 | 15 | 44485 | 341052 | 75031 | 416083 | | |
| 220003 | 60 TON CRANE (P5) | 128520 | 8.11 | 10652 | 139172 | 20 | 185509 | 1027747 | 194595 | 194595 | | |
| 220004 | SHIELDING (P6) | 128520 | 8.11 | 10652 | 139172 | 20 | 185509 | 1027747 | 194595 | 194595 | | |
| 220008 | CANISTER OVERPACKS (P6) | 232416 | 8.11 | 18848 | 251264 | 20 | 50522 | 301517 | 304104 | 1113181 | | |
| 220010 | CESIUM OVERPACKS (P7) | 75384 | 8.11 | 6113 | 81497 | 20 | 16299 | 97797 | 21515 | 119312 | | |
| SUBTOTAL 22 LATE PROCUREMENT (PHMC) | | 2564641 | 8.11 | 207992 | 2772633 | 18 | 506752 | 3279386 | 721464 | 4000851 | | |
| SUBTOTAL 2 PROCUREMENT (PHMC) | | 27852841 | 7.65 | 2128895 | 29982736 | 19 | 5687305 | 35670042 | 7847409 | 43517451 | | |

FLUOR DANIEL NORTHWEST, INC.

NUHATEC HANFORD CORP.

JOB NO. W4648AA1

FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHNCR04 - COMPANY/NBS SUMMARY

PAGE 11 OF 31
 DATE 03/31/98 14:55:55
 BY TLM/COL/KLK/JJH

| SORT CODE/URS | DESCRIPTION | ESTIMATE | | ESCALATION | | SUB | | CONTINGENCY | | SUB | | SITE | | TOTAL | |
|------------------|---|----------|------|------------|---|----------|---|-------------|---------|-------|----------|----------|---------|---------|----------|
| | | SUBTOTAL | % | SUBTOTAL | % | TOTAL | % | TOTAL | % | TOTAL | % | ALLOCAT' | % | DOLLARS | % |
| ===== | | | | | | | | | | | | | | | |
| | TOTAL LNHCC LOCKHEED MARTIN HANFORD COR | 27870712 | 7.64 | 2129895 | | 30000607 | | 19 | 5690879 | | 35691487 | | 7847409 | | 43538896 |
| ===== | | | | | | | | | | | | | | | |
| LHS1 | LOCKHEED MARTIN SERVICES, INC. | | | | | | | | | | | | | | |
| | 109EE3 MOBILIZE | 28288 | 0.00 | 0 | | 28288 | | 20 | 5657 | | 33945 | | 0 | | 33945 |
| | TOTAL LHS1 LOCKHEED MARTIN SERVICES, I | 28288 | 0.00 | 0 | | 28288 | | 20 | 5657 | | 33945 | | 0 | | 33945 |
| ===== | | | | | | | | | | | | | | | |
| NHC | NUHATEC HANFORD CORPORATION | | | | | | | | | | | | | | |
| | 109EE3 MOBILIZE | 24560 | 0.00 | 0 | | 24560 | | 20 | 4912 | | 29472 | | 0 | | 29472 |
| | SUBTOTAL 10 PROJ SUPPORT (CAPITAL) | 52848 | 0.00 | 0 | | 52848 | | 20 | 10569 | | 63417 | | 0 | | 63417 |
| | SUBTOTAL 1 ENGINEERING | 52848 | 0.00 | 0 | | 52848 | | 20 | 10569 | | 63417 | | 0 | | 63417 |
| ===== | | | | | | | | | | | | | | | |
| | 409HA1 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | | 3161944 | | 0 | 0 | | 3161944 | | 0 | | 3161944 |
| | SUBTOTAL 40 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | | 3161944 | | 0 | 0 | | 3161944 | | 0 | | 3161944 |
| | SUBTOTAL 4 PROJECT INTEGRATION | 3161944 | 0.00 | 0 | | 3161944 | | 0 | 0 | | 3161944 | | 0 | | 3161944 |
| ===== | | | | | | | | | | | | | | | |
| | 502KA1 PROJECT MANAGEMENT/ADMIN | 5860413 | 0.00 | 0 | | 5860413 | | 0 | 0 | | 5860413 | | 0 | | 5860413 |
| | 502KB1 DESIGN | 1969111 | 0.00 | 0 | | 1969111 | | 0 | 0 | | 1969111 | | 0 | | 1969111 |
| | 502XC1 PROCUREMENT | 391461 | 0.00 | 0 | | 391461 | | 0 | 0 | | 391461 | | 0 | | 391461 |
| | 502KD1 ENVIRONMENTAL | 1734994 | 0.00 | 0 | | 1734994 | | 0 | 0 | | 1734994 | | 0 | | 1734994 |
| | 502KE1 SAFETY | 3227502 | 0.00 | 0 | | 3227502 | | 0 | 0 | | 3227502 | | 0 | | 3227502 |
| | 502KF1 QUALITY ASSURANCE | 126869 | 0.00 | 0 | | 126869 | | 0 | 0 | | 126869 | | 0 | | 126869 |
| | 502KG1 ORR & STARTUP | 2962819 | 0.00 | 0 | | 2962819 | | 0 | 0 | | 2962819 | | 0 | | 2962819 |
| | SUBTOTAL 50 OTHER PROJECT COST | 16273169 | 0.00 | 0 | | 16273169 | | 0 | 0 | | 16273169 | | 0 | | 16273169 |
| | SUBTOTAL 5 OTHER PROJECT COST | 16273169 | 0.00 | 0 | | 16273169 | | 0 | 0 | | 16273169 | | 0 | | 16273169 |
| ===== | | | | | | | | | | | | | | | |
| | TOTAL NHC NUHATEC HANFORD CORPORATION | 19459673 | 0.00 | 0 | | 19459673 | | 0 | 4912 | | 19464585 | | 0 | | 19464585 |

FLUOR DANIEL NORTHWEST, INC.
 NUNATEC NUNFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED RLW INTERIM STORAGE SYSTEM
 VOLUME 2 & 3, PHASE 1 (REV 1)
 PHRCR04 - COMPANY/M8S SUMMARY

PAGE 12 OF 31
 DATE 03/31/98 14:55:55
 BY TLW/CDL/KLR/JJM

| SORT CODE/UBS | DESCRIPTION | ESTIMATE | | ESCALATION | | SUB | | CONTINGENCY | | SUB | | SITE | | TOTAL DOLLARS |
|------------------|-------------|------------|---------|------------|------------|---------|------------|-------------|------------|-----------|--|------|--|------------------|
| | | SUBTOTAL | % TOTAL | % TOTAL | TOTAL | % TOTAL | TOTAL | ALLOCAT'N | TOTAL | ALLOCAT'N | | | | |
| 67,736,979 | | 67,736,979 | 5.29 | 3,583,699 | 71,320,679 | 15 | 82,038,253 | 12,617,940 | 94,656,193 | | | | | |
| PROJECT TOTAL | | | | | | | | | | | | | | |

FLUOR DANIEL NORTHWEST, INC.
 NUNATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 - IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE I (REV 1)
 PHCRUS - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

PAGE 13 OF 31
 DATE 03/31/98 14:56:01
 BY TLV/CDL/KLR/JJN

| WBS | DESCRIPTION | ESTIMATE SUBTOTAL | CONSTRUCTION % TOTAL | MANAGEMENT TOTAL | OTHER COSTS | SUB TOTAL | TOTAL |
|-------------|------------------------------------|----------------------|----------------------------|---------------------|----------------|--------------|----------|
| ===== | ===== | ===== | ===== | ===== | ===== | ===== | ===== |
| 1AA100 | DRAWINGS | 620888 | 0.00 | 0 | 0 | 0 | 620888 |
| 1AA200 | SPECIFICATIONS | 256215 | 0.00 | 0 | 0 | 0 | 256215 |
| 1AA300 | CHECKING & REVIEW | 261196 | 0.00 | 0 | 0 | 0 | 261196 |
| 1AA400 | REPORTS & STUDIES | 119250 | 0.00 | 0 | 0 | 0 | 119250 |
| 1AA500 | CALCS | 151920 | 0.00 | 0 | 0 | 0 | 151920 |
| 1AA600 | ESTIMATES | 133554 | 0.00 | 0 | 0 | 0 | 133554 |
| 1AA700 | ESTIMATES | 133554 | 0.00 | 0 | 0 | 0 | 133554 |
| 1AA800 | SUBMITTAL REVIEWS | 234178 | 0.00 | 0 | 0 | 0 | 234178 |
| 1AA900 | QUALITY ASSURANCE | 200780 | 0.00 | 0 | 0 | 0 | 200780 |
| SUBTOTAL 1A | DEFINITIVE DESIGN | 3924281 | 0 | 0 | 0 | 0 | 3924281 |
| 1CC100 | TITLE III - ENGINEERING | 3252714 | 0.00 | 0 | 0 | 0 | 3252714 |
| SUBTOTAL 1C | TITLE III - ENGINEERING | 3252714 | 0 | 0 | 0 | 0 | 3252714 |
| 1D9EE3 | MOBILIZE | 168454 | 0.00 | 0 | 0 | 0 | 168454 |
| 1D9EE4 | DEFINITIVE DESIGN (TITLE I & II) | 470960 | 0.00 | 0 | 0 | 0 | 470960 |
| 1D9EE5 | TITLE III | 1181989 | 0.00 | 0 | 0 | 0 | 1181989 |
| SUBTOTAL 1D | PROJ SUPPORT (CAPITAL) | 1821403 | 0 | 0 | 0 | 0 | 1821403 |
| SUBTOTAL 1 | ENGINEERING | 8998398 | 0 | 0 | 0 | 0 | 8998398 |
| 210001 | SHIELDED CANISTER TRANSPORTER (P1) | 4840000 | 0.00 | 0 | 0 | 0 | 4840000 |
| 210005 | STANDARD STORAGE TUBES (P3) | 16054200 | 0.00 | 0 | 0 | 0 | 16054200 |
| 210007 | CASK TRANSPORT SYSTEMS (P2) | 4374000 | 0.00 | 0 | 0 | 0 | 4374000 |
| SUBTOTAL 21 | EARLY PROCUREMENT (PHRC) | 25288200 | 0 | 0 | 0 | 0 | 25288200 |
| 220002 | TRANSFER PIT CRANE (P4) | 274320 | 0.00 | 0 | 0 | 0 | 274320 |
| 220003 | 60 TON CRANE (P2) | 1296000 | 0.00 | 0 | 0 | 0 | 1296000 |
| 220004 | 60 TON CRANE (P2) | 1296000 | 0.00 | 0 | 0 | 0 | 1296000 |
| 220006 | CANISTER OVERPACKS (P6) | 232416 | 0.00 | 0 | 0 | 0 | 232416 |
| 220010 | DESIGN OVERPACKS (P7) | 75384 | 0.00 | 0 | 0 | 0 | 75384 |
| SUBTOTAL 22 | LATE PROCUREMENT (PHRC) | 2564641 | 0 | 0 | 0 | 0 | 2564641 |

FLUOR DANIEL NORTHWEST, INC.
 KUMATEC HANFORD CORP.
 JOB NO. W464BAA1
 FILE NO. W464BAA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHMCROS - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

PAGE 14 OF 31
 DATE 03/31/98 14:56:02
 BY TLH/CBL/KLR/JJM

| VBS | DESCRIPTION | ESTIMATE SUBTOTAL | CONSTRUCTION % | CONSTRUCTION MANAGEMENT TOTAL | OTHER COSTS | SUB TOTAL | TOTAL |
|---------------|-----------------------------------|----------------------|-------------------|----------------------------------|----------------|--------------|----------|
| ===== | ===== | ===== | ===== | ===== | ===== | ===== | ===== |
| SUBTOTAL 2 | PROCUREMENT (PHMC) | 27852841 | | 0 | 0 | 0 | 27852841 |
| 320101 | VAULTS 2 & 3 INTAKE & EXHAUST | 3171513 | 18.75 | 594664 | 0 | 594664 | 3766177 |
| 320104 | WOLFEY ANNEX P11 (FUELED STATION) | 80032 | 18.75 | 15004 | 0 | 15004 | 95036 |
| 320105 | STORAGE TUBE & CANISTER OVERPACKS | 2195988 | 18.75 | 413740 | 0 | 413740 | 2609788 |
| 320106 | VAULT 2 & 3 AIR FOLLS | 93633 | 18.75 | 17556 | 0 | 17556 | 111189 |
| 320108 | CONCRETE EXHAUST LOUVERS | 471807 | 18.75 | 88463 | 0 | 88463 | 560270 |
| SUBTOTAL 3201 | F P CONSTRUCTION - C1 | 6012953 | | 1127428 | 0 | 1127428 | 7140381 |
| 320209 | 10-TON GENTRY CRANE (ANNEX) | 21297 | 18.75 | 4555 | 0 | 4555 | 28852 |
| 320511 | EQUIPMENT (ANNEX) | 289268 | 18.75 | 54234 | 0 | 54234 | 343502 |
| 320513 | EQUIPMENT (ANNEX) | 554852 | 18.75 | 104034 | 0 | 104034 | 658886 |
| 320214 | CONCRETE (ANNEX) | 622443 | 18.75 | 118708 | 0 | 118708 | 739151 |
| 320215 | BUILDINGS (ANNEX) | 936815 | 18.75 | 175652 | 0 | 175652 | 1112467 |
| 320216 | STEELWORK (ANNEX) | 228123 | 18.75 | 41648 | 0 | 41648 | 263771 |
| 320217 | HVAC (ANNEX) | 469660 | 18.75 | 88061 | 0 | 88061 | 557721 |
| 320218 | ELECTRICAL (ANNEX) | 261843 | 18.75 | 49095 | 0 | 49095 | 310938 |
| 320220 | EQUIPMENT RENTAL (CRANES) | 248400 | 18.75 | 46575 | 0 | 46575 | 294975 |
| SUBTOTAL 3202 | F P CONSTRUCTION - C2 | 3629681 | | 680565 | 0 | 680565 | 4310246 |
| SUBTOTAL 32 | F P CONSTRUCTION | 9642634 | | 1807993 | 0 | 1807993 | 11450627 |
| SUBTOTAL 3 | CONSTRUCTION | 9642634 | | 1807993 | 0 | 1807993 | 11450627 |
| 409MA1 | PROJECT INTEGRATION | 3161944 | 0.00 | 0 | 0 | 0 | 3161944 |
| SUBTOTAL 40 | PROJECT INTEGRATION | 3161944 | | 0 | 0 | 0 | 3161944 |
| SUBTOTAL 4 | PROJECT INTEGRATION | 3161944 | | 0 | 0 | 0 | 3161944 |
| 502KA1 | PROJECT MANAGEMENT/ADMIN | 5860413 | 0.00 | 0 | 0 | 0 | 5860413 |
| 502XB1 | DESIGN | 1969111 | 0.00 | 0 | 0 | 0 | 1969111 |
| 502KC1 | PROCUREMENT | 391461 | 0.00 | 0 | 0 | 0 | 391461 |
| 502KD1 | ENVIRONMENTAL | 1734994 | 0.00 | 0 | 0 | 0 | 1734994 |

FLUOR DANIEL NORTHWEST, INC.
 HUNATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** IEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHNCR05 - CONSTRUCTION MANAGEMENT/OTHER COST SUMMARY

PAGE 15 OF 31
 DATE 03/31/98 14:56:02
 BY TLW/CDL/KLR/JJH

| WBS | DESCRIPTION | ESTIMATE SUBTOTAL | CONSTRUCTION MANAGEMENT % | CONSTRUCTION MANAGEMENT TOTAL | OTHER COSTS | SUB TOTAL | TOTAL |
|---------------|--------------------|----------------------|------------------------------|----------------------------------|----------------|--------------|------------|
| ===== | ===== | ===== | ===== | ===== | ===== | ===== | ===== |
| 502KE1 | SAFETY | 3227502 | 0.00 | 0 | 0 | 0 | 3227502 |
| 502KF1 | QUALITY ASSURANCE | 126869 | 0.00 | 0 | 0 | 0 | 126869 |
| 502KG1 | ORR & STARTUP | 2962819 | 0.00 | 0 | 0 | 0 | 2962819 |
| SUBTOTAL 50 | OTHER PROJECT COST | 16273169 | 0 | 0 | 0 | 0 | 16273169 |
| SUBTOTAL 5 | OTHER PROJECT COST | 16273169 | 0 | 0 | 0 | 0 | 16273169 |
| PROJECT TOTAL | | 65,928,986 | | 1,807,993 | 0 | 1,807,993 | 67,736,979 |

FLUOR DANIEL NORTHWEST, INC.
 HUNATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED ALN INTERIM STORAGE SYSTEM
 280105 VAULT 2 & 3 AIR FOILS
 PHMCR06 - SITE ALLOCATIONS BY WBS

PAGE 17 OF 31
 DATE 03/31/98 14:56:08
 BY TLM/CGL/KLR/JWR

| WBS | DESCRIPTION | ESTIMATE SUBTOTAL | DYN EQ. USAGE | FDH GFS/G&A CONST. MGMT | FDH MPR F.P./S.C. | FDH GFS/G&A LABOR | FDH MPR/G&A MATERIAL | SITE ALLOC SUBTOTAL |
|---------------|--|----------------------|------------------|----------------------------|----------------------|----------------------|-------------------------|------------------------|
| SUBTOTAL 2 | PROCUREMENT (PHMC) | 27852841 | 0 | 0 | 0 | 0 | 6127625 | 6127625 |
| 320101 | VAULTS 2 & 3 INTAKE & EXHAUST WOLFE CREEK PLY (WELLS STATION) | 3171543 | 0 | 181610 | 0 | 120614 | 0 | 302225 |
| 320102 | WOLFE CREEK PLY (WELLS STATION) | 80022 | 0 | 4582 | 0 | 18666 | 0 | 23249 |
| 320105 | STORAGE TUBE & CANISTER OVERPACKS | 2195948 | 0 | 125745 | 0 | 670642 | 0 | 796387 |
| 320106 | VAULT 2 & 3 AIR FOILS | 93633 | 0 | 5361 | 0 | 13545 | 0 | 18907 |
| 320108 | CONCRETE EXHAUST LOUVERS | 471807 | 0 | 27016 | 0 | 93030 | 0 | 120047 |
| SUBTOTAL 3201 | F P CONSTRUCTION - C1 | 6012953 | 0 | 344316 | 0 | 916500 | 0 | 1260816 |
| 320209 | 10-TON GENTRY CRANE (ANNEX) | 24297 | 0 | 1391 | 0 | 5073 | 0 | 6465 |
| 320211 | DEMOLITION (ANNEX) | 289268 | 0 | 16563 | 0 | 0 | 0 | 16563 |
| 320212 | CONCRETE (ANNEX) | 554852 | 0 | 31772 | 0 | 0 | 0 | 31772 |
| 320215 | BUILDINGS (ANNEX) | 422443 | 0 | 35642 | 0 | 0 | 0 | 35642 |
| 320216 | SITEMARK (ANNEX) | 936815 | 0 | 53644 | 0 | 1034 | 0 | 54678 |
| 320217 | HVAC (ANNEX) | 222123 | 0 | 12719 | 0 | 0 | 0 | 12719 |
| 320218 | ELECTRICAL (ANNEX) | 469660 | 0 | 26893 | 0 | 0 | 0 | 26893 |
| 320220 | EQUIPMENT RENTAL (CRANES) | 261843 | 0 | 14993 | 0 | 40884 | 0 | 55878 |
| SUBTOTAL 3202 | F P CONSTRUCTION - C2 | 3629681 | 0 | 14224 | 0 | 0 | 0 | 14224 |
| SUBTOTAL 32 | F P CONSTRUCTION | 9642634 | 0 | 552161 | 0 | 963493 | 0 | 1515654 |
| SUBTOTAL 3 | CONSTRUCTION | 9642634 | 0 | 552161 | 0 | 963493 | 0 | 1515654 |
| 409RA1 | PROJECT INTEGRATION | 3161944 | 0 | 0 | 0 | 0 | 0 | 0 |
| SUBTOTAL 40 | PROJECT INTEGRATION | 3161944 | 0 | 0 | 0 | 0 | 0 | 0 |
| SUBTOTAL 4 | PROJECT INTEGRATION | 3161944 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KA1 | PROJECT MANAGEMENT/ADMIN | 5860413 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KB1 | DESIGN | 1969111 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KC1 | PROCUREMENT | 571481 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KD1 | ENVIRONMENTAL | 1754994 | 0 | 0 | 0 | 0 | 0 | 0 |

FLUOR DANIEL NORTHWEST, INC.
 NUNATEC HANFORD CORP.
 JOB NO. W464BAA1
 FILE NO. W464BAA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE 1 (REV 1)
 PHNCR06 - SITE ALLOCATIONS BY WBS

PAGE 18 OF 31
 DATE 03/31/98 14:56:08
 BY TLU/COL/KLR/JJR

| WBS | DESCRIPTION | ESTIMATE | DYN | FDH | GFS/G&A | F.D./S.C. | FDH | GFS/G&A | FDH | MPR/G&A | SITE | ALLOC |
|---------------|--------------------|------------|----------|------------|---------|-----------|-----------|-----------|-----|---------|------|-------|
| | | SUBTOTAL | EQUUSAGE | CONST.MGMT | | | | | | | | |
| | | | | | | | | | | | | |
| 502KG1 | SAFETY | 3227502 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KG1 | QUALITY ASSURANCE | 124869 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 502KG1 | ORR & STARTUP | 2962819 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SUBTOTAL 50 | OTHER PROJECT COST | 16273169 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SUBTOTAL 5 | OTHER PROJECT COST | 16273169 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| PROJECT TOTAL | | 65,928,986 | 17,494 | 552,161 | 0 | 3,100,602 | 6,127,625 | 9,797,883 | | | | |

FLUOR DANIEL NORTHWEST, INC.
 RUHATEC HANFORD CORP.
 JOB NO. W4648AA1
 FILE NO. W4648AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMobilized HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3 PHASE I (REV 1)
 PHRC07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 19 OF 31
 03/31/98 14:56:20
 BY TLW/CDL/KLR/JJN

| WBS DESCRIPTION | SITE ALLOC SUBTOTAL | ESCALATION % TOTAL | SUP TOTAL | CONTINGENCY % TOTAL | TOTAL DOLLARS |
|---|------------------------|-----------------------|--------------|------------------------|------------------|
| 1AA100 DRAWINGS | 101171 | 5.63 | 10762 | 20 | 40386 |
| 1AA200 SPECIFICATIONS | 72730 | 5.63 | 4094 | 25 | 19206 |
| 1AA300 CHECKING & REVIEW | 80422 | 5.63 | 4527 | 20 | 16990 |
| 1AA400 REPORTS & STUDIES | 36717 | 5.63 | 2067 | 20 | 7756 |
| 1AA500 CALCS | 157115 | 5.63 | 8845 | 25 | 41590 |
| 1AA600 SUPPORT | 449128 | 5.63 | 25285 | 15 | 17162 |
| 1AA700 ESTIMATES | 25103 | 5.63 | 13818 | 20 | 34576 |
| 1AA800 SUBMITTAL REVIEWS | 72103 | 5.63 | 4050 | 20 | 15332 |
| 1AA900 QUALITY ASSURANCE | 37188 | 5.63 | 2093 | 15 | 5892 |
| SUBTOTAL 1A DEFINITIVE DESIGN | 1153093 | 5.63 | 64919 | 19 | 230056 |
| 1CC100 TITLE III - ENGINEERING | 1001510 | 8.89 | 89034 | 20 | 218108 |
| SUBTOTAL 1C TITLE III - ENGINEERING | 1001510 | 8.89 | 89034 | 20 | 218108 |
| 1DD003 MOBILIZE | 0 | 0.00 | 0 | 0 | 0 |
| 1DD004 DEFINITIVE DESIGN (TITLE I & 14) | 0 | 0.00 | 0 | 0 | 0 |
| 1DD005 TITLE III | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 1D PROJ SUPPORT (CAPITAL) | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 1 ENGINEERING | 2154603 | 7.15 | 153953 | 19 | 448165 |
| 210001 SHIELDED CANISTER TRANSPORTER (P1) | 1049200 | 7.60 | 81259 | 15 | 172568 |
| 210005 STANDARD STORAGE TUBES (P3) | 3521924 | 7.60 | 268426 | 20 | 740070 |
| 210007 CASK TRANSPORT SYSTEMS (P2) | 962280 | 7.60 | 73133 | 20 | 207082 |
| SUBTOTAL 21 EARLY PROCUREMENT (PHRC) | 5563404 | 7.60 | 422818 | 19 | 1139721 |
| 220002 TRANSFER PIT CRANE (P4) | 60950 | 8.11 | 4894 | 15 | 9786 |
| 220003 60 TON CRANE (P5) | 253120 | 8.11 | 2033 | 25 | 75031 |
| 220004 FIELD STATION (P6) | 51131 | 8.11 | 4146 | 20 | 46326 |
| 220010 DESIGN OVERPACKS (P7) | 16384 | 8.11 | 1345 | 20 | 11055 |
| SUBTOTAL 22 LATE PROCUREMENT (PHRC) | 564221 | 8.11 | 45758 | 18 | 111485 |
| SUBTOTAL 22 LATE PROCUREMENT (PHRC) | 564221 | 8.11 | 45758 | 18 | 721464 |

** IEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED HLW INTERIM STORAGE SYSTEM
 VAULT 2 & 3. PHASE I (REV 1)
 PHMCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

FLUOR DANIEL NORTHWEST, INC.
NUMATEC HANFORD CORP.
JOB NO. W464BAA1
FILE NO. W464BAA1

| WBS | DESCRIPTION | SITE ALLOC | ESCALATION | SUB | CONTINGENCY | TOTAL |
|---------------|-----------------------------------|------------|------------|--------|-------------|---------|
| ===== | ===== | SUBTOTAL | % TOTAL | ===== | % TOTAL | DOLLARS |
| SUBTOTAL 2 | PROCUREMENT (PHRC) | 6127625 | 7.65 | 468577 | 19 | 7847409 |
| 320101 | VAULTS 2 & 3 INTAKE & EXHAUST | 302229 | 7.85 | 23724 | 20 | 391139 |
| 320104 | MODIFY ANNEX PIT (WELD STATION) | 23249 | 7.85 | 1925 | 25 | 31342 |
| 320105 | STORAGE TUBE & CAMISTER OVERPACKS | 796387 | 7.85 | 62516 | 20 | 1030685 |
| 320106 | VAULT 2 & 3 AIR FOLLS | 18907 | 7.85 | 1484 | 30 | 26508 |
| 320108 | CONCRETE EXHAUST LOUVERS | 120047 | 7.85 | 9423 | 25 | 161839 |
| SUBTOTAL 3201 | F P CONSTRUCTION - C1 | 1260816 | 7.85 | 98974 | 21 | 1641515 |
| 320209 | 10-TON GANTRY CRANE (ANNEX) | 6465 | 8.89 | 574 | 35 | 9543 |
| 320211 | DEMOLITION (ANNEX) | 16563 | 8.89 | 1472 | 35 | 24307 |
| 320213 | EQUIPMENT (ANNEX) | 31772 | 8.89 | 2824 | 35 | 46705 |
| 320214 | CONCRETE (ANNEX) | 35642 | 8.89 | 3168 | 35 | 52595 |
| 320215 | BUILDINGS (ANNEX) | 42678 | 8.89 | 4860 | 35 | 80378 |
| 320216 | SITWORK (ANNEX) | 12719 | 8.89 | 1130 | 35 | 18697 |
| 320217 | RVAC (ANNEX) | 26893 | 8.89 | 2390 | 35 | 39354 |
| 320218 | ELECTRICAL (ANNEX) | 55878 | 8.89 | 4967 | 35 | 82142 |
| 320220 | EQUIPMENT RENTAL (CRANES) | 14244 | 8.89 | 1264 | 20 | 18586 |
| SUBTOTAL 3202 | F P CONSTRUCTION - C2 | 254837 | 8.89 | 22555 | 34 | 372292 |
| SUBTOTAL 32 | F P CONSTRUCTION | 1515654 | 8.02 | 121629 | 23 | 2013807 |
| SUBTOTAL 3 | CONSTRUCTION | 1515654 | 8.02 | 121629 | 23 | 2013807 |
| 4009A1 | PROJECT INTEGRATION | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 40 | PROJECT INTEGRATION | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 4 | PROJECT INTEGRATION | 0 | 0.00 | 0 | 0 | 0 |
| 5002K1 | PROJECT MANAGEMENT/ADMIN | 0 | 0.00 | 0 | 0 | 0 |
| 5002K1 | DESIGN | 0 | 0.00 | 0 | 0 | 0 |
| 5002C1 | PROCUREMENT | 0 | 0.00 | 0 | 0 | 0 |
| 5002D1 | ENVIRONMENTAL | 0 | 0.00 | 0 | 0 | 0 |

FLUOR DANIEL NORTHWEST, INC.
 KUNATEC HANFORD CORP.
 WBS NO. W042AA1
 FILE NO. W042AA1

** TEST - INTERACTIVE ESTIMATING **
 IMMOBILIZED WLM INTRINSIC SYSTEM
 ANALYSIS & X
 PHKCR07 - SITE ALLOCATION ESCALATION/CONTINGENCY REPORT

PAGE 21 OF 31
 DATE 03/31/98 14:56:20
 BY TLM/CDL/KLR/JUN

| WBS DESCRIPTION | SITE ALLOC SUBTOTAL | ESCALATION % TOTAL | SUB TOTAL | CONTINGENCY % TOTAL | TOTAL DOLLARS |
|--------------------------|------------------------|-----------------------|--------------|------------------------|------------------|
| | | | | | |
| 502K01 SAFETY | 0 | 0.00 | 0 | 0 | 0 |
| 502K01 QUALITY ASSURANCE | 0 | 0.00 | 0 | 0 | 0 |
| 502K01 ORR & STARTUP | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 50 | 0 | 0.00 | 0 | 0 | 0 |
| SUBTOTAL 5 | 0 | 0.00 | 0 | 0 | 0 |
| PROJECT TOTAL | 9,797,883 | 7.60 | 10,542,043 | 20 | 12,617,940 |

STATEMENT OF WORK

Project W-464
Architect/Engineer**IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY
PROJECT W-464 - DEFINITIVE DESIGN/ENGINEERING INSPECTION**CLIENT: NHCCOMPANY W.O. NO.: N-01PREPARED BY: FDNW

DATE: March 1998

PROJECT SCOPE

This statement of work describes the work scope to be performed by Fluor Daniel Northwest, Inc., as primary contractor (hereafter referred to as the architect-engineer [A/E]) under the direction of Lockheed Martin Hanford Company, hereafter referred to as the buyer. Specifically, the A/E shall prepare definitive design (DD) documents for the Immobilized High-Level Waste (IHLW) Interim Storage Facility.

The DD work scope covers the design phase of the IHLW Interim Storage Facility (Project W-464), hereafter referred to as the project. This design phase entails services for producing construction drawings, and construction and procurement specifications for the project. A large fraction of the DD effort will encompass retrofit modifications to the existing Canister Storage Building (CSB) and Vaults 2 and 3 and the addition of a HLW Load-In/Load-Out Annex.

The engineering inspection (EI) work scope covers the construction phase of the project. The construction phase entails engineering services in support of construction with resolution of field problems, review, and disposition of construction submittals, preparing, and issuing engineering change notices (ECNs), resolution, and disposition of nonconformance reports (NCRs), construction management, records management, and the as-built of project drawings.

The overall function of the project is to transport high-level waste (HLW) canisters loaded with vitrified waste (provided by the immobilization vendors) from the HLW Immobilization Facility, provide interim storage for the waste canisters, and if necessary, overpack, and store any damaged canisters.

The project will provide transport casks, equipment, and facilities for accomplishing the transport IHLW function and the interim storage IHLW function. The scope of the project includes the design and construction to provide for IHLW storage space, design and procurement of transport vehicle(s) and shielded casks, and canister handling for placement of IHLW within the CSB storage area.

Project Engineering/Design Administration (201)

The project engineering/design administration will provide overall design coordination between the various design disciplines and the buyer. Project engineering will coordinate/interface with the inspection group(s) and participate in final acceptance activities associated with official acceptance of construction (OAC).

Project Engineering Support (205)

The project engineering support will include:

- Engineering, construction, and submittal document control functions
- Specifications (Procurement and Construction)

Survey (210)

Provide any field conditions required during the design effort.

Architecture (220)

The Architectural group will provide:

- Code Search and Report
- Research and Coordination - existing CSB, Construction and Building Materials, As-Built Drawings, CSB PSAR, DBD
- Assist with HLW Load-In/Load-Out Annex PSAR, DBD
- Human Factor Program Plan Input
- Value Engineering Study Input
- Construction Specification Input
- Systems Engineering Management Plan Compliance Input
- Architectural Drawings (14)
- Critical Design Review
- Early Procurement Submittal Review
- Early Procurement Specification Input
- Management Self Assessments (Incorporate Comments)

Civil/Structural (215)

The civil/structural group will provide:

- Civil Drawings (7)
- Structural Drawings (31)
- Calculations (41)
- Construction Specification Input (C1 & C2)
- Independent Seismic Review
- Transportation Plan Input
- Systems Engineering Management Plan Compliance Input

- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Early Procurement Submittal Review
- Early Procurement Specification Input
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Environmental (230)

The environmental group will provide:

- Project documentation reviews as applicable.

Heating, Ventilating, and Air Conditioning (235)

The HVAC group will provide:

- Drawings (6)
- Construction Specification Input
- Calculations (8)
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Early Procurement Submittal Reviews
- Early Procurement Specification Input
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Fire Protection and Safety Review (245)

The fire protection group will provide:

- Fire Hazards Analysis, Update CSB FHA
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Mechanical (255)

The mechanical systems groups will provide:

- Early Procurement Specification Input (3)
- Procurement Specifications (6)
- Early Procurement Submittal Reviews
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Drawings to be Included in the Procurement Specification (69)
- Construction Drawings (9)
- Drawings (Operations Flow Diagrams) (3)
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Electrical (265)

The electrical group will provide:

- ECN Existing CSB Drawings
- Drawings (23)
- Calculations (3)
- Construction Specification Input
- Input to Three Procurement Specifications
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Early Procurement Submittal Review
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Instrumentation and Control (I&C) (270)

The I&C group will provide:

- Drawings (4)
- Construction Specification Input
- Procurement Specification Input (3)
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input

- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Early Procurement Submittal Review
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Nuclear Engineering/Shielding (290)

The nuclear engineering/shielding group will provide:

- Calculations (9)
- ALARA Report (1)
- Systems Engineering Management Plan Compliance Input
- Human Factors Program Plan Input
- Maintainability Analysis Input
- Alignment and Value Engineering Session
- As-build Review of Existing CSB Drawings
- Critical Design Review
- Early Procurement Submittal Review
- PSAR Support
- Management Self Assessments (Incorporate Comments).

Project Control (300)

The project control engineer will develop and maintain the project schedule and cost baseline, and will provide monthly cost, progress, and schedule reports.

Estimating (310)

The estimating scope includes production of the 30% and final definitive design estimate, plus other estimates as required.

Subcontract/Procurement (430)

The subcontract/procurement specialist will manage the development and placement of early procurement packages, and will provide support during the bid/award cycles for both procurement and fixed-price construction.

Construction Management (501)

Construction management includes both construction forces (CF) and construction management (CM) administration. This support includes performance of the constructibility review, plus input to the construction and procurement specifications, as well as input to the final design estimate and construction schedule.

Construction Engineering (505)

The construction engineering function provides support to the constructibility review and the final design estimate.

ENGINEERING/INSPECTION (EI)

Work provided by the A/E firm on project W-464 during construction will consist of the following discipline efforts.

Civil/Structural (215)

A full-time, civil/structural engineer will be assigned to support the construction efforts during the early civil/structural stage of construction. This support function will include: 1) review and disposition of fixed-price contractor submittals; 2) prepare and issue ECNs; 3) disposition NCRs; 4) attend construction meetings; 5) be available to assist construction personnel in resolving technical issues; and 6) final as-documenting of drawings and specifications.

HVAC Engineering (235)

A full-time HVAC engineer will be assigned to support construction for installation of the HVAC equipment associated with the HLW Load-In/Load-Out Annex. This support function will include: 1) review and disposition of building contractor submittals; 2) prepare and issue ECNs; 3) disposition NCRs; 4) attend construction meetings; and 5) final as-documenting of drawings and specifications.

Safety/Fire Protection Engineering (245)

The safety and fire protection engineer will perform overview safety review and approval of project ECNs and NCRs.

Mechanical Engineering (255)

A full-time, mechanical engineer will be assigned to support the construction effort during the installation phase of mechanical equipment on the project. This support function will include: 1) review and disposition of fixed-price contractor submittals; 2) prepare and issue ECNs; 3) disposition NCRs; 4) attend construction meetings; 5) be available to assist construction personnel in resolving technical issues; 6) provide acceptance test plan (ATP) input, and 7) final as-documenting of drawings and specifications.

Instrumentation Engineering (270)

A full-time, instrumentation engineer will be assigned to support the construction effort during the latter phases of construction while instrumentation installation and check-out activities are in progress. This support function will include: 1) review and disposition

of fixed-price contractor submittals; 2) prepare and issue ECNs, 3) disposition NCRs; 4) attend construction meetings; 5) be available to assist construction personnel in resolving technical issues; 6) provide ATP input, and 7) final as-documenting of drawings and specifications.

Electrical Engineering (265)

A full-time electrical engineer will be assigned to support construction during installation and testing of the electrical system. This support function will include: 1) review and disposition of building contractor submittals; 2) prepare and issue ECNs; 3) disposition NCRs; 4) attend construction meetings; and 5) final as-documenting of drawings and specifications.

Project Engineer/Design Administration (201)

Coordinate interdiscipline activities and provide performance/progress information to support schedule and cost statusung.

Project Management (101)

Provide overall coordination of all EI activities. Responsible for cost and schedule performance and reporting.

Quality Engineering (41)

Provide review of ECNs and NCRs for compliance with appropriate criteria and procedures. Provide auditing services to verify that project work is performed in accordance with appropriate procedures.

Project Controls (300)

Set up and maintain costs and schedule baselines. Provide schedule analysis and cost trending.

Estimating (310)

Provide estimating support during construction as required to support disposition of contractor change requests.

Construction Submittals (206)

Provide contractor submittal control and distribution system to ensure timely disposition of submittals.

Construction Forces Administration (505)

Responsible for managing and coordinating CF activities.

Construction Management (501)

The fixed-price contractor will be managed by FDNW CM.

Records Management and Turnover (205)

Maintain project engineering/management files. Transmit project documents internally and externally. Responsible for project records turnover at project completion.

BASIS FOR ESTIMATE

The basis used to prepare this estimate include:

1. The electrical design is General Services.
2. Existing ventilation systems do not require modification.
3. Procurement and submittal reviews are performed during definitive design for the SCT, transportation system, and storage tubes.
4. Privatization vendors will use the same waste canister design.
5. Welding and inspection of the overpack cap installation will permit some hands-on functions.
6. Seals, venting, or inerting will not be required for HLW canister transporting, handling, and storing.
7. There will be no radioactive contamination affecting this project.
8. The existing designs for the intake and exhaust structures and storage tube assemblies can be used for HLW.
9. The overpack weld station can use SNF's gantry crane, hoists, and ventilation system.
10. Combustible loading and associated fire loss potentials will be less than the DOE limits and a fire suppression system will not need to be installed in the operations area of the CSB.
11. Original CSB definitive design documents shall be used as a reference source for matching methods and materials of construction and reusing similar details and specifications for the HLW load-in/load-out definitive design effort.
12. The 3D thermal analysis for HLW in Vaults 2 and 3 and the confirmatory structural analysis based on the results of the thermal analysis and the SCT loads will be completed as part of the ACDR effort.

APPENDIX D

CONCEPTUAL PROJECT SCHEDULE

This appendix includes the overall project schedule including:

- Schedule for start and completion of definitive design.
- Schedule for start and completion of various project procurements, early procurement, construction, and various closeout activities.

The basis of the DRD was that the SNF CSB operations were complete prior to initiation of project W-464 construction activities. Since the issuance of the DRD, the SNF schedule has slipped by at least 18 months. Therefore, the CDR schedule was prepared to ensure project W-464 integration with the current SNF schedule.

(c) Primavera Systems, Inc.

FLUOR DANIEL NORTHWEST, INC.

PRIMAVERA PROJECT PLANNER

W-464 HLM CDR

REPORT DATE 18MAR98 RUN NO. 1380

START DATE 1JAN97 FIN DATE 31MAY00

9:47

SR-02 MILESTONE DESCRIPTIONS

DATA DATE 2MAR98 PAGE NO. 1

| ACTIVITY ID | ACTIVITY DESCRIPTION | SCHEDULED START | FINISH |
|--------------------------------|---|-----------------|---------|
| 1.0 ENGINEERING | | | |
| 11M10 | START DEFINITIVE DESIGN | 4OCT99 | 1OCT99* |
| | INITIATE DEFINITIVE DESIGN ACTIVITIES | | |
| 11M80 | ISSUE FOR APPROVAL (IFA) DEFINITIVE DESIGN | 12OCT00 | 11OCT00 |
| | PROVIDE C2 DESIGN TO OPERATING CONTRACTOR FOR APPROVAL AND RELEASE FOR CONSTRUCTION | | |
| 11M90 | DESIGN COMPLETE | 9NOV00 | 8NOV00 |
| | ALL DESIGN ACTIVITIES ARE COMPLETED. DESIGN DELIVERABLES ARE APPROVED BY OPERATING CONTRACTOR AND RELEASED FOR CONSTRUCTION. | | |
| 3.0 CONSTRUCTION | | | |
| C1M10 | START C1 CONSTRUCTION | 24APR00 | 21APR00 |
| | INITIATE BID & AWARD FOR C1 FIXED PRICE CONSTRUCTION, AND INITIATE CM SUPPORT ACTIVITIES. C1 ACTIVITIES INCLUDE: | | |
| | - STORAGE TUBE INSTALLATION | | |
| | - FAB & INSTALL INTAKE & EXHAUST STACKS | | |
| | - LOUVERS | | |
| | - AIRFOILS | | |
| C1M20 | NTP C1 CONSTRUCTION | 19JUL00 | 18JUL00 |
| | NOTICE TO PROCEED (NTP) C1 FIELD ACTIVITIES. | | |
| C2M10 | START C2 CONSTRUCTION | 9NOV00 | 8NOV00 |
| | INITIATE BID & AWARD FOR C1 FIXED PRICE CONSTRUCTION, AND INITIATE CM SUPPORT ACTIVITIES. C2 ACTIVITIES INCLUDE: | | |
| | - CONSTRUCTION OF LOAD-IN/LOAD-OUT ANNEX | | |
| | - INSTALLATION OF CRANES (P4 & P9) | | |
| | - CONSTRUCTION OF OVERPACK/WELD STATION | | |
| C2M20 | NTP C2 CONSTRUCTION | 6FEB01 | 5FEB01 |
| | NOTICE TO PROCEED (NTP) C2 FIELD ACTIVITIES | | |
| C1M60 | C1 MECHANICAL/ELECTRICAL COMPLETE | 24SEP01 | 21SEP01 |
| | C1 CONSTRUCTION ACTIVITIES ARE COMPLETE EXCEPT FOR ACCEPTANCE TEST PROCEDURES (ATPs) | | |
| C2M60 | C2 MECHANICAL/ELECTRICAL COMPLETE | 8OCT01 | 5OCT01 |
| | C2 CONSTRUCTION ACTIVITIES ARE COMPLETE EXCEPT FOR ACCEPTANCE TEST PROCEDURES (ATPs) | | |
| C1M70 | C1 CONSTRUCTION COMPLETE (OAC1) | 18DEC01 | 17DEC01 |
| | C1 FIELD CONSTRUCTION AND ATPs COMPLETE FOR USE | | |
| C2M70 | C2 CONSTRUCTION COMPLETE (OAC1) | 3JAN02 | 2JAN02 |
| | C2 FIELD CONSTRUCTION AND ATPs COMPLETE FOR USE | | |
| 4.0 PROJECT INTEGRATION | | | |
| CD2 | CRITICAL DECISION FOR DD, P1, P2, & P3 | 1OCT99 | 30SEP99 |
| | APPROVAL TO INITIATE DEFINITIVE DESIGN AND EARLY PROCUREMENT (P1, P2, & P3) | | |
| | - P1 SHIELDING CANISTER TRANSPORTER | | |
| | - P2 TRANSPORT CASKS | | |
| | - P3 STORAGE TUBES | | |
| CD3 | CRITICAL DECISION FOR C1 CONSTRUCTION | 24APR00 | 21APR00 |
| | APPROVAL TO INITIATE C1 FIXED PRICE CONSTRUCTION | | |
| OAC2 | OAC2 POTPs COMPLETE | 29MAR02 | 28MAR02 |
| | PRE-OPERATIONAL TEST PROCEDURES (POTPs) COMPLETE OFFICIAL ACCEPTANCE OF CONSTRUCTION PART II SIGNED OFF. | | |
| OAC3 | OAC3 PROJECT COMPLETE | 3JUN02 | 31MAY02 |
| | ALL DESIGN AND CONSTRUCTION ACTIVITIES COMPLETE. OFFICIAL ACCEPTANCE OF CONSTRUCTION PART III IS APPROVED. | | |

APPENDIX E

OUTLINE SPECIFICATION

This appendix provides an outline of expected specification elements for design, procurement, construction, and estimating purposes.

OUTLINE SPECIFICATIONS

DIVISION 2 - SITEWORK

Section 02000 Clearing and Grubbing

1. Clear and grub areas affected by excavation or embankment.

Section 02200 Earthwork

1. Excavation and Embankment (fill):

- a. Structural fill: 75 mm (3 in.) maximum aggregate size, compacted Method B, meeting WSDOT M 41-10, Section 2-03.
- b. Common fill: 300 mm (12 in.) maximum loose lifts, 150 mm (6 in.) maximum aggregate size, optimum moisture, compact uniformly over full width by one pass of vibratory equipment.

2. Stabilization: Base course, WSDOT M 41-10.

3. Soil Compaction Testing (Structural fill only).

Section 02235 Road Subgrade and Granular Base

1. Base Course: WSDOT M 41-10.

2. Leveling Course: WSDOT M 41-10.

3. Material and Compaction Testing.

Section 02512 Hot-Laid Asphaltic Concrete Pavement

1. Asphalt Concrete Pavement: WSDOT M 41-10.

- a. Asphalt: AR-4000-W
- b. Aggregate: Class B

2. Material and Density Testing.

Section 02831 Security Chain Link Fences and Gates

1. Fence fabric: FS RR-F-191/1, Type I, 2 inch mesh, 11 gage, 84 inch height, top and bottom selvages twisted and barbed.

2. Posts, top rails and braces: FS RR-F-191/3, Class 1, Grade A or B.
3. End members of gate frames: FS RR-F-191/4, extending 12 inches above tope of fabric for attachment of barbed wire, fitted with ball top or similar fitting to shed water.
4. Hinges, latches, stops, and keepers: FS RR-F-191/2, zinc-coated steel.

DIVISION 3 - CONCRETE

Section 03300 Reinforced Concrete

1. Compressive Strength (f'_c) = 6,000 psi - CSB Vault above Elev 704' - 0"
5,000 psi - CSB Vault below Elev 704' - 0"
4,000 psi - elsewhere
2. Reinforcing Steel: ASTM A 615 (f_y = 60,000 psi)
3. Welded Wire Fabric: ASTM A 185

DIVISION 5 - METALS

Section 05120 Structural Steel

1. Stack: ASTM A 242 TYP1 or ASTM A 588 Grade A (F_y = 50 ksi)
2. Structural Steel: ASTM A 36/A 36M (F_y = 36 ksi)
3. Structural Tubing: ASTM A 500 Grade B (F_y - 46 ksi)
4. Steel Pipe: ASTM A 53 Type E or S Grade B (F_y - 35 ksi)
5. Welding Material: AWS D1.1, E70XX Electrode
6. Crane Rails: ASTM A 759, S3 & S5
7. Stainless Steel:
 - a. Plate: ASTM A 240 Type 304L
 - b. Bars and Shapes: ASTM A276 Type 304L (F_y = 25 ksi)
 - c. Pipe: ASTM A 312/A 312M Grade TP304L
 - d. Welding Material: E/ER 308L Electrode for Stainless to Stainless Steel
E/ER 309L Electrode for Stainless to Carbon Steel

8. Bolts, Nuts, and Washers:
 - a. Common Bolts: ASTM A 36 or A 307
 - b. High Strength Bolts: ASTM A 325
 - c. Nuts: ASTM A 563
 - d. Hardened Washers: ASTM F 436
 - e. Rail Anchor Bolts: ASTM A 449
 - f. Rail Sole Plate: ASTM A 36
 - g. Rail Clips (clamps): ASTM A 572 Grade 50

Section 05515 Ladders and Rungs

1. Structural Tubing: ASTM A 500, Grade B (Fy-36ksi)
2. Welding Material: ASTM A 759

Section 05532 Gratings and Trench Covers

Section 05720 Railings and Handrails

1. Structural Tubing: Fabricate using steel pipe.
2. Welding Fittings: Preformed turns and fittings, using complete penetration welds at connections. Grind smooth.
3. Paint: Prime ferrous metal in accordance with Section 09900.

Section 05800 Expansion Control

Expansion Anchor Installation

DIVISION 7 - THERMAL AND MOISTURE PROTECTION

Section 07100 Dampproofing and Waterproofing

1. Asphalt: ASTM D 449, Type II. Apply to belowgrade exterior surfaces of concrete walls which enclose usable space.

Section 07200 Thermal Protection

1. Conforming to ASTM C 665, Type II, Class C. Installed in Metal Siding and Roof System sandwich panels.
2. Wall Insulation: Minimum thermal resistance of R-19.
3. Roof Insulation: Minimum thermal resistance of R-30.

Section 07410 Standing Seam Roof System

1. Standing Seam Roof System shall match the roof system used on the Canister Storage Building.
2. Resist wind loading defined in ASCE 7-93.
3. Attachment of metal roofing system to the structural decking designed to resist earthquake forces calculated in accordance with UBC Chapter 16.
4. Guarantee:
2-year guarantee warranting the weather tightness of the building.
10-year manufacturer's warranty for finished surfaces.

Section 07465 Metal Wall System

1. Metal Siding Panels to match existing Canister Storage Building metal siding panels. Prefinished steel sandwich construction.
2. System designed to resist wind loading defined in ASCE 7-93.
3. System designed to resist earthquake forces calculated in accordance with UBC Chapter 23.
4. Metal Trim: Metal closure strips, top, base, head, sill, and jamb or corner trims shall be same material, thickness, and finish as siding

Section 07620 Sheet Metal Flashing and Trim

1. Sheet Metal Flashings and Trim to match existing Canister Storage Building.
2. Downspouts and Gutters: Fabricate from same material as siding. Match Canister Storage Building downspouts.

Section 07900 Joint Sealers

DIVISION 8 - DOORS AND WINDOWS

Section 08100 Metal Doors and Frames

1. Doors and Welded Steel Frames shall be constructed and hung according to SDI 100.

Section 08310 Access Doors and Panels

1. Factory fabricated access doors for installation in walls or ceiling shall be of the same level of quality as those manufactured by Milcor.

Section 08342 Industrial Doors

1. Design Wind Load 23 psf.
2. Tornado Wind Impact Load approximately 92 psf.
3. Seismic Load in accordance with UBC Section 1630 for Seismic Zone 2B.

Section 08710 Hardware

DIVISION 9 - FINISHES

Section 09965 Industrial Resinous Coating

1. Materials and system of application shall be in accordance with ANSI N512.

Section 09910 Paints

1. Coating materials shall be applied in accordance with SSPC Paint-1 (Steel Structures Painting Council).

DIVISION 10 - SPECIALTIES

Section 10440 Interior Signage

Section 10520 Fire Protection Specialties

DIVISION 13 - SPECIAL CONSTRUCTION

Section 13440 Instrumentation

1. Intake stack air temperature and velocity measuring system

The mass flow indicating transmitter shall be capable of receiving flow signals (total and static pressures) from probes equipped with temperature sensing

means, and of amplifying, correcting, extracting the square root (linearizing), and scaling to produce a 4–20 mA DC output signal linear and scaled to standard air volume. The mass flow indication transmitter shall contain an integral digital process display capable of continuous indication of standard air volume in SCFM, and selectable displays of air temperature in °F and air pressure in inches water.

2. Stack probe
 - a. Volumetric flow transverse probe
 - b. Material: stainless steel
 - c. Mounting 6" 150 lb flange with 8 3/4" bolt pattern
 - d. Probe: flow measuring manifolds with total pressure, static pressure, and thermocouple probes.
3. Mass flow indicating transmitter
 - a. Adjustable flow span: 0 to 400 fpm
 - b. Accuracy: $\pm 0.5\%$ of span
 - c. Thermocouple ranges -100 °F to 1600 °F
 - d. Indication: digital, 4-digit, 0.5 inch high, LED process displays, continuous in standard air volume (SCFM). Selectable indication of air velocity (SFPM) and air temperature (°F) and air pressure (inches of Hg).
 - e. Output: 4–20 mA DC
 - f. Power: standard 4-wire 120 V AC
4. Exhaust stack temperature probe
 - a. Thermocouple ranges: -100°F to 1600 °F
5. Continuous Air Monitor
 - a. Eberline, Beta/Gamma, AMS' - 4
6. Closed Circuit TV
 - a. Remote controlled camera(s)
 - b. Monitor/control station

DIVISION 15 - MECHANICAL**Section 15500 HVAC****HEPA Filter Housing****Requirements:**

HEPA filter housing assemblies shall be of stainless steel and shall meet the following:

- Capacity: 2000 CFM
- Housing Design Pressure: 10 inches of water gauge
- Medium efficiency filter: 2 inches thick with prefilter single
- HEPA filter: Single stage
- Gas temperature: 10 °C (50 °F) min, 93 °C (200 °F) max

Functional Design Requirements:

The HEPA filter housing shall be a single filter design meeting the requirements of ASME N509 with the following clarifications/exceptions:

- Safety classification is non-ESF
- Paragraphs related to carbon absorber, fan, drive, heating coil, dampers, and duct to not apply
- Lighting is not required
- Vendor standard mechanical design of the housing is acceptable provided they meet the performance requirements of ASME N509
- The filter housing shall be located outdoors
- Injection and sampling manifold for DOP testing are required. The location of injection and sampling ports shall be determined by the vendor for DOP testing in accordance with ASME N510

Maximum airstream relative humidity (RH): 100% RH

Housing ambient conditions: -26 °C (50 °F) to 54 °C (130 °F), 20 to 100% RH

Centrifugal Fan**Equipment Description**

- Fans covered by this section are of carbon steel construction, direct or belt driven, for installation in air filtration units.
- Fan performance shall be as follows:
 - Capacity: 2000 scfm
 - Static Pressure 7 inches of water gauge

- Performance Ratings: The fan shall be tested and certified in accordance with ASHRAE 51-85 and AMCA 210-85 Test Code and shall bear an AMCA Seal.
- Sound Ratings: The fan shall have sound rating per AMCA 301, tested to AMCA 300, and bear the AMCA Certified Sound Rating Seal.
- Ratings are based on AMCA 99 standard for air. Specified equipment ratings for air handling units are minimum requirements. Specified rating for filtration unit exhaust fans are maximum rating (filter train fully loaded). These fan motors will be provided with variable speed drive (VSD) by other.
- The fans shall be selected below the first critical speed and in the stable region of the corresponding performance curves such that even at a lower speed, if applicable, it remains instable operating region. In addition, fans shall be selected for maximum efficiency in the operating range.

Ducting and Accessories

Ducting:

- 12 inches round, 16 ga stainless steel, all weld
- 12 inches diameter isolation dampers no.: 4

Exhaust Stack:

- 12 inches diameter carbon steel, 80 feet tall, 1/4 inches wall

DIVISION 16 - ELECTRICAL

Section 16400 Service and Distribution

1. Lightning protection equipment/materials adhering to NFPA 780, Lightning Protection Code
2. Panelboards, 480Y/277 V or 208/120 V, 3 phase, 4 wire, 60 Hz UL 67, NEMA PB 1
3. Transformer, dry-type, 480-208/120 V, 3 phase, 4 wire, 60 Hz UL1561, NEMA ST 20
4. Lighting Fixtures
 - a. High bay industrial 400 W, metal halide with quartz standby, pendant mount, high efficiency ballast
 - b. Fluorescent industrial, T-8 lamps, electronic high efficiency ballast


- c. Incandescent, industrial, vapor tight
- d. Low pressure sodium, outdoor, 35 W with photo cell control
- e. Emergency, self contained maintenance free battery, UL 924
- f. Roadway, low pressure sodium, pole mounted

APPENDIX F

ENERGY CONSERVATION REPORT AND ANALYSIS

Energy consumption of the high-level waste systems will not be noticeably different from the spent nuclear fuel (SNF) systems. The size of the new Annex is less than the minimum size requirement for an energy conservation report. Therefore, the existing energy conservation features (and report) for the SNF project are appropriate for project W-464.

The heating, ventilating, and air conditioning (HVAC) systems for the SNF project were designed to meet the energy conservation requirements of ASHRAE Standard 90A and DOE Order 6430.1A, Section 0110-12.



APPENDIX G

PRELIMINARY SAFETY EVALUATION

This section will include the preliminary safety evaluation including hazards analysis, hazards classification, preliminary safety classifications, and nuclear/non-nuclear designations when the approved document is provided by Numatec.

**PRELIMINARY SAFETY EVALUATION
FOR PROJECT W-464,
IMMOBILIZED HIGH-LEVEL WASTE
INTERIM STORAGE**

April 1998

This page intentionally left blank.

FOREWORD

As part of the Tank Waste Remediation Systems (TWRS) Project W-464, this Preliminary Safety Evaluation (PSE) identifies and evaluates hazards associated with the construction and operation of the immobilized high level waste interim storage facility (IHLW-ISF). This PSE was developed concurrently with the conceptual design for the IHLW-ISF as part of the Project W-464 design activities. Concurrent preparation of the PSE ensures incorporation of safety considerations into the design and permits the PSE to be issued as part of the Conceptual Design Report (CDR).

The PSE utilizes a Preliminary Hazards Analysis (PHA) for the identification of hazards associated with the operation of the proposed activity. At the time the PHA was developed, the conceptual design for Project W-464 utilized a receiving pit in the Canister Storage Building (CSB) receiving area and the multiccanister overpack (MCO) handling machine (MHM) for unloading the cask and transport of the IHLW and Cesium (Cs) canisters. The receiving area, receiving crane and MHM are being designed and constructed by Spent Nuclear Fuel (SNF) Project W-379 for receipt and handling of the spent nuclear fuel within the CSB. Subsequent to the development of the PHA and preparation of the PSE, the design approach was revised to design and construct a separate receiving area, the High Level Waste Load-in/Load-out Annex, for receipt of the casks containing the IHLW and Cs canisters. A new gantry crane and cask transfer pit will be provided for receipt of the casks and a new handling machine, the Shielded Canister Transporter (SCT), will be provided for transfer of the canisters from the casks to the storage tubes. These systems and components are described in Section IV of the CDR.

The operations associated with the receipt and unloading of the casks and transport of the canisters with the SCT will be similar to those described in the PSE. The hazards and potential accident scenarios identified in the PSE are expected to be typical of those for the revised design approach. In addition, the safety functions required to prevent or mitigate the potential consequences of the accidents developed in the PSE will need to be considered in the design development for the revised approach. These functions include those for prevention or mitigation of the consequences of a cask drop, drop of a canister, and shear of a canister.

The revised design may present additional hazards which will need to be addressed during further design development. The design and operational sequence has not progressed to the point where it would be effective to revise the PHA. However, a revision of the PHA and analysis of new hazards will be done prior to development of the PSAR. Hazards to be considered are the interactions of the new systems for receipt and handling of the IHLW and Cs canisters with other systems in the CSB, and design features which may increase the severity of the potential accidents or introduce new accident scenarios.

As noted above, the PSE does identify safety functions which will need to be considered during the design development. The continued interaction between the safety analysis and the design activities will identify any new hazards and required safety features associated with the design.

TABLE OF CONTENTS

| | |
|---|------|
| LIST OF TABLES | G-6 |
| LIST OF ACRONYMS | G-7 |
| 1.0 INTRODUCTION AND SUMMARY | G-8 |
| 1.1 INTRODUCTION | G-8 |
| 1.2 SUMMARY | G-11 |
| 2.0 DESIGN CRITERIA | G-12 |
| 2.1 DESIGN CRITERIA IDENTIFICATION | G-12 |
| 2.2 COMPLIANCE WITH SAFETY DESIGN CRITERIA | G-12 |
| 2.3 SAFETY STRUCTURES, SYSTEMS, AND COMPONENTS | G-13 |
| 2.4 ASSUMPTIONS | G-15 |
| 3.0 HAZARDOUS MATERIAL INVENTORIES | G-16 |
| 3.1 RADIOLOGICAL INVENTORY | G-16 |
| 3.2 TOXICOLOGICAL INVENTORY (HAZARDOUS CHEMICALS) | G-17 |
| 3.3 BOUNDING INVENTORY | G-18 |
| 3.4 HAZARD CATEGORIZATION | G-18 |
| 4.0 ACCIDENT EVALUATION | G-22 |
| 4.1 PRELIMINARY HAZARDS ANALYSIS | G-22 |
| 4.1.1 Methodology | G-22 |
| 4.1.2 Hazard Analysis Results | G-29 |
| 4.2 ACCIDENT ANALYSIS | G-32 |
| 4.2.1 Consequence Analysis Methodology | G-32 |
| 4.2.2 Source Term | G-32 |
| 4.2.3 Mass Dose Factor | G-34 |
| 4.2.4 Atmospheric Dispersion | G-38 |
| 4.2.5 Breathing Rate | G-38 |
| 4.2.6 Equipment Design Guidelines | G-38 |
| 4.2.7 Analysis of Radiological Accident Scenarios | G-39 |
| 4.2.8 Nuclear Criticality | G-56 |
| 5.0 CONSTRUCTION RISKS | G-57 |
| 6.0 SAFETY DOCUMENTATION | G-59 |
| 7.0 PROJECT INTERFACES | G-61 |
| 8.0 ITEMS REQUIRING FURTHER RESOLUTION | G-63 |
| 8.1 PROJECT DESIGN ASSUMING MHM | G-63 |
| 8.2 PROJECT DESIGN ASSUMING SCT | G-64 |
| 9.0 REFERENCES | G-67 |
| ATTACHMENT A | G-69 |

LIST OF TABLES

| | | |
|-------|---|------|
| 2-1. | Preliminary Safety Equipment List. | G-14 |
| 3-1. | Container Radiological Inventory | G-17 |
| 3-2. | Hazard Categorization | G-20 |
| 4-1. | Binning, Screening, and Representative Accident Selection. | G-27 |
| 4-2. | Derivation of Σ MDF for IHLW Glass. | G-36 |
| 4-3. | Dispersion Factors for Receptors Associated with the Canister Storage Building | G-38 |
| 4-4. | Dropped Glass Canister Accident | G-41 |
| 4-5. | Multiple Glass Canister Drop Accident | G-44 |
| 4-6. | Cs Canister Drop Accident | G-46 |
| 4-7. | Potential Safety SSCs for Canister Drop Accidents | G-47 |
| 4-8. | Transport Cask with Canister Drop Accident | G-50 |
| 4-9. | Seismic Induced Glass Canister Shear Accident | G-51 |
| 4-10. | Seismic Induced Cs Canister Shear Accident | G-52 |
| 4-11. | Truck Impact Induced Canister Shear Accident | G-53 |
| 4-12. | Potential Safety SSCs Associated with Canister Shear/Pinch Accidents | G-54 |
| 4-13. | Seismic Event Causing Tube Failure | G-55 |
| 4-14. | Potential Safety SSCs Associated with Natural Phenomena | G-55 |

LIST OF ACRONYMS

| | |
|----------|---|
| ALARA | as low as reasonably achievable |
| ARF | airborne release fraction |
| BR | breathing rate |
| CDR | Conceptual Design Report |
| CFR | Code of Federal Regulations |
| CSB | Canister Storage Building |
| DBA | design basis accident |
| DBE | design basis earthquake |
| DCF | dose conversion factor |
| DOE | Department of Energy |
| DRD | Design Requirements Document |
| EDE | effective dose equivalent |
| EPA | Environmental Protection Agency |
| FSAR | Final Safety Analysis Report |
| HLW | high level waste |
| HVAC | heating, ventilating, and air conditioning |
| IEEE | Institute of Electrical and Electronics Engineers, Inc. |
| IHLW | immobilized high level waste |
| IHLW-ISF | immobilized high level waste interim storage facility |
| LPF | leak path factor |
| MAR | material at risk |
| MCO | multicanister overpack |
| MDF | mass dose factor |
| MHM | multicanister overpack handling machine |
| PHA | preliminary hazards analysis |
| PNNL | Pacific Northwest National Laboratory |
| PSAR | Preliminary Safety Analysis Report |
| PSE | preliminary safety evaluation |
| RF | respirable fraction |
| SARP | Safety Analysis Report for Packaging |
| SC | Safety Class |
| SCT | Shielded Canister Transporter |
| SNF | Spent Nuclear Fuel |
| SS | Safety Significant |
| SSCs | structures, systems, and components |
| ST | source term |
| TSR | Technical Safety Requirement |
| TWRS | Tank Waste Remediation System |
| USQ | Unreviewed Safety Question |
| WRAP | Waste Receiving and Processing |
| WHC | Westinghouse Hanford Company |

**PRELIMINARY SAFETY EVALUATION FOR PROJECT W-464,
IMMOBILIZED HIGH LEVEL WASTE INTERIM STORAGE FACILITY**

1.0 INTRODUCTION AND SUMMARY

1.1 INTRODUCTION

This PSE evaluates the hazards associated with the IHLW-ISF in the available vaults of the CSB, and ensures that major safety considerations are identified during the conceptual design phase of the project. This PSE for Project W-464 fulfills the safety documentation guidance of HNF-PRO-703, *Safety Analysis Process - New Project*. The format and content of this PSE follows the guidance provided in HNF-PRO-703, Attachment A, "PSE Format and Content."

The Design Requirements Document (DRD, WHC 1996a) identifies the functions, performance requirements, and constraints necessary to define the IHLW-ISF. Based on the preliminary design information available in the DRD (WHC 1996a) and the CDR, this PSE addresses the following specific topics:

- Evaluation of the existing CSB structures, systems, and components (SSCs) that interface with the storage of the IHLW canisters
- Facility radioactive and hazardous material inventories
- Facility hazard categorization
- Preliminary assessment of the design's ability to adequately contain the radioactive and hazardous material inventories
- Evaluation of the design with respect to safety requirements and safety related design criteria
- Identification of SSCs that can prevent and/or mitigate postulated accidents
- Risks to the CSB and surrounding facilities arising from construction activities
- Future safety documentation requirements to support the start of construction and operations
- Interfaces with related projects, facilities, and activities
- Safety related issues that must be resolved prior to the start of operations

Project W-464 will provide interim storage for canisters containing high level waste described in Section 1.0 of the CDR. These canisters contain vitrified high level waste (HLW) which is in the form of glass poured into the canister, canisters of Cs loaded ion exchange resin (free flowing powder), and "nonroutine" canisters containing failed melter material and other equipment contacting the HLW. The canisters of vitrified waste and the "nonroutine" canisters will be collectively referred to as IHLW canisters.

Project W-464 will complete Vaults 2 and 3 of the existing CSB. Project W-464 will require modifications to the existing facility, such as the addition of the storage tubes, MHM/crane modifications, and replacement of the 5-ton cask lid crane with a 10-ton crane. The following items and services, required to complete the IHLW storage system, are not in the Project W-464 scope (i.e., they are existing or planned CSB features):

- CSB above ground structure
- Below grade, shielded storage vaults with storage tube access from the grade level operating area above
- Embedded sleeves through the 5 foot thick reinforced concrete operating deck
- Service building, adjacent to the operating structure, that houses the equipment necessary for compressed air, electrical power, HVAC, security, and fire protection
- The inert gas system that consists of a bottle rack located outside of the building with the gas hard piped into the operating area
- The receiving crane that unloads the transportation cask from the transport vehicle into the receiving area (northwest corner of the operating area)
- The MHM that transports the canister within the CSB. The MHM is a large and complex machine consisting of a cask mounted on a gantry crane which can deposit or retrieve canisters at any of the locations intended for storage
- Monitoring and control systems associated with the equipment which moves, places, stores, and retrieves the canisters
- Remote loading and unloading equipment for moving canisters into and out of the transportation casks
- Addition of insulating concrete in Vaults 2 and 3

Project W-464 will perform the following activities:

- Design, fabricate, construct, test, and qualify Vaults 2 and 3 ventilation inlet and outlet structures, storage tubes, tube plugs, impact absorbers, transportation cask, and truck based transport vehicle
- Replace the existing 5-ton cask lid crane with a 10-ton crane
- Modify the MHM to provide additional shielding, a longer turret body casting, improved controls, increased load capacity, and a new grapple
- Procurement of two cask transport vehicles for cask transportation from the private contractor facility to the CSB

CSB Operations will be responsible for:

- Acceptance and handling of IHLW or Cs canisters
- Storing of the IHLW or Cs canisters on an interim basis
- Retrieving the IHLW or Cs canisters from interim storage

The concept for the IHLW-ISF is to receive IHLW and Cs canisters at the CSB inside of a shielded transportation cask. The transportation cask is lowered into the service pit where additional shielding is put in place and the cask lid is removed. The IHLW or Cs canister is lifted from the transportation cask and into the MHM. The MHM transports the canister to the storage tube located in the floor of the CSB. The MHM inserts the canister into the storage tube and places the storage tube plug. Eventually the canister will be retrieved from storage and prepared for final offsite disposal.

The CSB is located on the western side of the 200 East Area of the Hanford Site, and consists of two major buildings, the operating structure and the service building. The operating structure houses the handling equipment, embedded storage tubes, and three storage vaults. Vault 1 will hold MCOS containing spent nuclear fuel. Vaults 2 and 3 will be completed and then used for the interim storage of the IHLW or Cs canisters. Each vault consists of 22 rows of 10 storage tubes each and 6 additional storage tubes dedicated for possible overpacked canisters for a total of 226 tubes. The vaults are air cooled by natural convection.

The preliminary Fire Hazards Analysis, as required by DOE Order 5480.7A, *Fire Protection*, DOE Order 6430.1A, *General Design Criteria*, HNF-PRO-340, *Fire Protection Program Overview*, and HNF-PRO-703, will be a revision to HNF-SD-SNF-FHA-002, Rev 2, *Phase 2 Fire Hazard Analysis for the Canister Storage Building*, (HNF 1997b) and will be scheduled and completed during preparation of future Project W-464 safety documentation. The PHA (Attachment

A) identifies several process related fire hazard scenarios but does not encompass the construction and industrial fire hazards (e.g., electric cables and equipment, paints, etc.) Therefore, the development of a comprehensive list of hazards is deferred until a more detailed design is available.

1.2 SUMMARY

The results of this PSE are summarized as follows:

- The IHLW-ISF represents a hazard category 2 nuclear facility. This is based upon a preliminary hazard categorization considering total inventory, regardless of form or dispersibility, per DOE-STD-1027-92. The addition of the W-464 inventory does not change the existing CSB hazard category as discussed in Section 3.4.
- The IHLW and Cs canisters serve to provide the first barrier to mitigate a potential release of radioactive waste to the environment. However, the qualification of the canisters to resist impacts such as drops during handling operations was unknown at the time this PSE was developed.
- The analysis of the postulated accidents indicates that some potential dose consequences (without mitigation) exceed the Safety Significant (SS) or Safety Class (SC) thresholds. Therefore Safety Significant and Safety Class SSCs might be required to prevent or mitigate the potential consequences.
- Section 4.1.2.4 lists PHA findings for safety improvements to be considered for enhancing the safety of the facility operation.

2.0 DESIGN CRITERIA

2.1 DESIGN CRITERIA IDENTIFICATION

The DRD Section 3.3.6, "Safety and Regulatory Compliance," specifically identified the following safety design criteria:

- Design Basis Accidents. The project shall be designed to withstand the effects of design basis accidents (DBAs), as delineated in DOE Order 6430.1A, *General Design Requirements*, DOE Order 5480.23, *Nuclear Safety Analysis Reports*, and DOE-STD-3009-94, *Preparation Guide for U.S. Department of Energy Non-Reactor Nuclear Facilities Safety Analysis Report* with confinement of radioactive and toxic materials to maintain potential releases within allowable limits. The performance category PC3 requirements from DOE Order 5480.28, *Natural Phenomena Hazard Mitigation*, shall be applied for the Design Basis Earthquake.
- Abnormal Operation. The design shall include provisions to monitor, and alarm on detection; abnormal conditions such as radioactive particulate release, liquid intrusion, gaseous release, abnormal radiation levels, fires, and overheating or pressurization.
- Personnel Radiation Exposure. Personnel radiation exposure shall be in accordance with as low as reasonably achievable (ALARA) principles, and 10 CFR Part 835, *Occupational Radiation Protection*.

In addition, the design shall comply with DOE Order 5480.24, *Nuclear Criticality Safety* (DOE 1992c) as stated in Section 3.3.8 of the DRD.

2.2 COMPLIANCE WITH SAFETY DESIGN CRITERIA

The W-464 Project has addressed the design criteria as found in DOE Order 6430.1A, *General Design Requirements*; DOE Order 5820.2A, *Radioactive Waste Management*; DOE Order 5480.4, *Environmental Protection, Safety, and Health Protection Standards*; DOE Order 5400.5, *Radiation Protection of the Public and Environment*; DOE Order 5480.28, *Natural Phenomena Hazards*; and DOE Order 5480.7A, *Fire Protection*. There are no planned deviations from the above criteria with the exception of DOE Order 5480.7A. This exception is due to the absence of automatic fire suppression system (sprinklers) over the operating deck as discussed in Section IV of the CDR.

Appendix E of the CDR provides the summary level specifications for the design and construction of the W-464 Project based on the design criteria in the DRD.

2.3 SAFETY STRUCTURES, SYSTEMS, AND COMPONENTS

This section identifies the Safety Significant and Safety Class SSCs per criteria in HNF-PRO-704 and DOE-STD-3009-94, Chapter 4. Suggested Safety Significant and Safety Class SSCs for the safe operation of the IHLW-ISF are shown in Table 2-1. The Safety Class SSCs for the IHLW-ISF are designed to the existing CSB seismic requirements and are qualified to withstand an earthquake with a peak horizontal ground acceleration of 0.35 g. The following existing structures are seismically qualified for an earthquake with a peak horizontal ground acceleration of 0.35 g (HNF 1997c).

- Building structure, including load-in/load-out and Hot Conditioning Annex areas
- Operating deck
- Operating deck penetrations
- Below grade vaults

Table 2-1.. Preliminary Safety Equipment List.*

| SSC | Accident Analysis Section | Safety Classification | Safety Function |
|---|--|-----------------------|---|
| Impact Absorber | 4.2.7.1, 4.2.7.2, & 4.2.7.3 | SS | Mitigate the consequences of a canister drop in the storage tube. |
| Storage Tube | 4.2.7.1 4.2.7.2 4.2.7.3 & 4.2.7.8 | SC | Containment of any release following a canister drop (SS). Hold storage canisters within the tube during a seismic event to prevent possible damage (SC). |
| MHM-Tube Seal | 4.2.7.1, 4.2.7.2,& 4.2.7.3 | SS | Containment of any release following a canister drop. |
| MHM Grapple and Lifting Device *** | 4.2.7.1, 4.2.7.2,& 4.2.7.3 | SS | Prevent the drop of the canister. |
| Receiving Crane, Grapple, Lifting Devices (handling of transportation cask) *** | 4.2.7.4 | SS | Prevent the drop of the transportation cask into the receiving pit. |
| Transportation Cask ** | 4.2.7.4 | SS | Sustain the impact of a cask drop without breach. |
| MHM Brake and Lateral Restraint | 4.2.7.5, 4.2.7.6, & 4.2.7.7 | SC | Maintain the position of the MHM during a seismic event. |
| Truck Barriers | 4.2.7.7 | SC | Prevent truck from impacting the MHM. |
| Shielding of MHM, receiving pit, storage tube plugs, louvers, vault structure, and operating deck | 4.1.2.3 | SS | Protect workers from unacceptable radiation doses during normal operations. |
| Cask Shielding | 4.1.2.3 | SS | Protect workers from unacceptable radiation doses during normal operations. |
| CSB Operating Deck | 4.2.7.8 | SC | Prevent failure of tube during a seismic event. |
| Vault Ventilation Inlet/Outlet Structures (plenums, louvers, stacks) | 4.2.7.8 | SC | Prevent damage to the operating deck and storage tubes that could result in a release during a seismic event. |
| CSB Roof | 4.2.7.8 | SC | Prevent collapse of building onto storage tubes. |

* This preliminary safety equipment list identifies safety SSCs; further design development may revise the list.

** The unmitigated onsite consequence is below, but near, the guideline. Designation of the cask as Safety Significant should be considered.

*** These are alternative safety SSCs to be considered for the prevention/mitigation of the respective accident.

2.4 ASSUMPTIONS

Significant assumptions used in this PSE are listed below.

- The building structure, vault, and operating deck are designed to sustain a Safety Class design basis earthquake, wind, tornado, and ashfall (HNH 1997c).
- The waste packaging process will ensure that no water is present inside the IHLW or Cs canisters when received at the CSB.
- Design provisions at the CSB are adequate to preclude the entrance of water into the storage tubes.
- The facility will be capable of receiving the transportation casks, placing the canisters in their designated interim storage locations, and retrieving the canisters from storage (WHC 1996a).
- The normal operations at the CSB will safely monitor and control the equipment for the canister movement, placement in tubes, and retrieval.
- The CSB handling equipment as modified for the IHLW-ISF will provide the necessary shielding to limit exposure to facility workers (WHC 1996a).
- The canister maintains sufficient integrity following a canister drop to limit the release of radioactive material. The analysis uses a leak path factor (LPF) of 0.1 to account for the limited release.
- The glass fines generated during fragmentation of the glass from the canister drop events are the only significant source of material for release. Any pre-existing glass fines (such as those created by glass fracture from thermal stresses) would not be a significant contributor to the release.
- For a multiple glass canister drop accident, two worst case inventory canisters are involved in the accident (see Section 4.2.6.2).
- Engineered safety features or administrative controls are adequate to prevent the canister from being raised more than 1.5 m above the CSB operating deck.

The above assumptions must be maintained through any design evolution process in order to preserve the conclusions of this PSE. Technical Safety Requirements (TSRs) and safety SSCs may be required to maintain some of these assumptions. Some of the assumptions are also the subject of items requiring further resolution and are addressed in Section 8.0.

3.0 HAZARDOUS MATERIAL INVENTORIES

This section describes the radiological and nonradiological hazardous material inventories to be handled at the facility for use in quantifying accident consequences. Documentation requirements for the canister inventory will be identified in the Interface Control Documents. Future safety analysis will address the hazard associated with exceeding inventory limits and will establish the appropriate control requirements.

3.1 RADIOLOGICAL INVENTORY

The HLW glass canisters are stainless steel, 4.5 m long x 0.61 m in diameter, meeting the leak rate criteria specified in the DRD (WHC 1996a). The maximum capacity is 3,060 kg of glass; the nominal capacity is 2,735 kg of glass. The density of the glass is 2,640 kg/m³. The glass will have a maximum concentration of radionuclides as shown in Table 3-1 (data from WHC 1996a, Table 3-4). The nominal average inventories per container in curies, are also listed in Table 3-1. These inventories were calculated by taking the product of the concentration limits (Ci/kg) and the nominal canister glass mass of 2,735 kg. The inventory in the "nonroutine" canisters is assumed to be bounded by the inventory in the HLW glass canisters.

The overall size of the Cs canisters is the same as for the IHLW canisters. Each stainless steel Cs canister can have up to 3.2×10^5 Ci of ¹³⁷Cs/^{137m}Ba and 2.1 Ci ¹³⁵Cs in each container. However, the aggregate inventory per storage tube will not exceed 3.2×10^5 Ci of ¹³⁷Cs/^{137m}Ba and 2.1 Ci ¹³⁵Cs regardless of the number of containers per storage tube (WHC 1996b). The limit on Cs per tube can all be in one canister with no others present, or in multiple canisters with the sum of the multiple canister curie contents not to exceed 3.2×10^5 Ci of ¹³⁷Cs/^{137m}Ba and 2.1 Ci ¹³⁵Cs. The shipper will determine and certify the Cs content of the canisters and it is the responsibility of the IHLW-ISF operator to allocate placement in the tubes.

Table 3-1. Container Radiological Inventory.

| Isotope | Glass Radionuclide Concentration (Ci/kg) | Nominal Canister Inventory (Ci/Canister) | Isotope | Glass Radionuclide Concentration (Ci/kg) | Nominal Canister Inventory (Ci/Canister) |
|--------------------|--|--|--------------------|--|--|
| ⁵⁵ Fe | 1.6 E-02 | 4.4 E+01 | ¹³⁵ Cs | 4.8 E-04 | 1.3 E+00 |
| ⁵⁹ Ni | 2.3 E-04 | 6.3 E-01 | ¹³⁷ Cs | 4.8 E+01 | 1.3 E+05 |
| ⁶⁰ Co | 4.8 E-02 | 1.3 E+02 | ^{134m} Ba | 4.8 E+01 | 1.3 E+05 |
| ⁶³ Ni | 2.6 E-02 | 7.1 E+01 | ¹⁴⁴ Ce | 1.6 E-03 | 4.4 E+00 |
| ⁷⁹ Se | 6.8 E-06 | 1.9 E-02 | ¹⁴⁴ Pr | 1.6 E-03 | 4.4 E+00 |
| ⁹⁰ Sr | 5.0 E+01 | 1.4 E+05 | ^{144m} Pr | 1.6 E-06 | 4.4 E-03 |
| ⁹⁰ Y | 5.0 E+01 | 1.4 E+05 | ¹⁴⁷ Pm | 2.6 E+00 | 7.1 E+03 |
| ^{93m} Nb | 1.4 E-03 | 3.8 E+00 | ¹⁵¹ Sm | 1.5 E+00 | 4.1 E+03 |
| ⁹³ Zr | 2.3 E-03 | 6.3 E+00 | ¹⁵² Eu | 2.4 E-03 | 6.6 E+00 |
| ⁹⁹ Tc | 7.3 E-02 | 2.0 E+02 | ¹⁵⁴ Eu | 2.6 E-01 | 7.1 E+02 |
| ¹⁰⁶ Ru | 3.2 E-03 | 8.8 E+00 | ¹⁵⁵ Eu | 1.5 E-01 | 4.1 E+02 |
| ¹⁰⁶ Rh | 3.2 E-03 | 8.8 E+00 | ²³⁴ U | 1.2 E-05 | 3.3 E-02 |
| ¹⁰⁷ Pd | 6.5 E-05 | 1.8 E-01 | ²³⁵ U | 5.2 E-07 | 1.4 E-03 |
| ^{110m} Ag | 1.6 E-07 | 4.4 E-04 | ²³⁶ U | 1.3 E-06 | 3.6 E-03 |
| ^{113m} Cd | 1.8 E-02 | 4.9 E+01 | ²³⁸ U | 9.4 E-06 | 2.6 E-02 |
| ^{113m} In | 3.0 E-05 | 8.2 E-02 | ²³⁷ Np | 3.7 E-04 | 1.0 E+00 |
| ¹¹³ Sn | 3.0 E-05 | 8.2 E-02 | ²³⁸ Pu | 1.8 E-03 | 4.9 E+00 |
| ^{115m} Cd | 1.1 E-08 | 3.0 E-05 | ²³⁹ Pu | 1.5 E-02 | 4.1 E+01 |
| ^{119m} Sn | 1.6 E-07 | 4.4 E-04 | ²⁴⁰ Pu | 4.2 E-03 | 1.1 E+01 |
| ^{121m} Sn | 1.5 E-04 | 4.1 E-01 | ²⁴¹ Pu | 1.1 E-01 | 3.0 E+02 |
| ¹²⁶ Sn | 7.7 E-04 | 2.1 E+00 | ²⁴² Pu | 1.1 E-06 | 3.0 E-03 |
| ¹²⁴ Sb | 4.2 E-08 | 1.5 E-04 | ²⁴¹ Am | 6.9 E-01 | 1.9 E+03 |
| ¹²⁶ Sb | 7.8 E-05 | 2.1 E-01 | ²⁴² Am | 5.0 E-04 | 1.4 E+00 |
| ^{126m} Sb | 5.5 E-04 | 1.5 E+00 | ^{242m} Am | 5.2 E-04 | 1.4 E+00 |
| ¹²⁵ Sb | 1.6 E-01 | 4.4 E+02 | ²⁴³ Am | 8.1 E-05 | 2.2 E-01 |
| ^{125m} Te | 4.8 E-02 | 1.3 E+02 | ²⁴² Cm | 6.0 E-04 | 1.6 E+00 |
| ¹²⁹ I | 1.5 E-06 | 4.1 E-03 | ²⁴⁴ Cm | 1.5 E-02 | 4.1 E+01 |
| ¹³⁴ Cs | 1.1 E-01 | 3.0 E+02 | | | |

(1) Inventory per canister obtained by multiplying the concentration limit by the nominal glass mass per canister of 2,735 kg.

3.2 TOXICOLOGICAL INVENTORY (HAZARDOUS CHEMICALS)

There are no process chemicals or waste chemicals present in the IHLW interim storage facility. There are no processing activities or generation of waste streams in this facility.

Ordinary industrial chemicals may be allowed at the facility in the form of solvents and cleaners, paints, printer toner, etc. Specific chemicals have not been identified, but unacceptable hazards are not expected with these chemicals. Unless these chemicals are brought into the facility in inordinate quantities, they represent hazards which are accepted on a daily basis by the general public and are therefore outside the scope of this PSE. If large quantities of these ordinary chemicals or an unusual chemical are brought into the facility or placed in such a location so as to pose a reactivity hazard, then this assumption must be re-evaluated.

3.3 BOUNDING INVENTORY

The CSB design includes three below grade vaults, two of which will be used to store the IHLW or Cs canisters. As discussed earlier, each vault consists of a matrix of 22 rows by 10 columns for a total of 220 steel storage tubes. Six oversized storage tubes are also provided in each vault to accommodate overpacked canisters. With the capacity for two 4.5 m long canisters in each tube, the total per vault loading is potentially 452 canisters. The maximum loading per vault of Cs containers could range from 226 (1 Cs canister per storage tube) to 452. However the aggregate inventory per storage tube will not exceed 3.2×10^5 Ci of $^{137}\text{Cs}/^{137m}\text{Ba}$ and 2.1 Ci ^{135}Cs regardless of the number of containers per storage tube (see Section 3.1).

3.4 HAZARD CATEGORIZATION

For the SNF storage mission, the CSB has been designated as a Hazard Category 2 facility (HNF 1997c) before consideration of the IHLW inventory. The IHLW inventory will be an addition to the inventory of the CSB.

DOE Order 5480.23 defines a facility's hazard category based on the consequences of unmitigated releases determined by a hazard analysis of the facility's nuclear activities. These are then classified as Category 1, 2, or 3 based on the following definitions.

Category 1. The hazard analysis shows the potential for significant offsite consequences.

Category 2. The hazard analysis shows the potential for significant onsite consequences.

Category 3. The hazard analysis shows the potential for significant, but localized consequences.

DOE-STD-1027-92 provides guidance on determination of hazard categories based on comparison of individual radionuclides to the threshold quantities for Hazard Category 2 and 3. The ratios between the facility inventory at risk and the category threshold quantity for each radionuclide are summed if all the individual quantities are less than the threshold quantities. If a

facility falls below the Category 3 threshold, it is exempt from the requirements of DOE Order 5480.23.

The Category 2 threshold quantities are used to determine the facility hazard categorization if the Category 3 facility threshold quantities are exceeded. The facility is Hazard Category 3 if the Category 2 threshold quantities are not exceeded. The facility is Hazard Category 2 if it contains more than the Category 2 threshold quantities of radioactive material and it is not a Category A reactor or designated as Hazard Category 1 by the Program Secretarial Officer.

Table 3-2 provides curie contents of isotopes for a single IHLW canister with the nominal inventory, the Category 2 and 3 threshold values for the isotopes, and the ratio of the isotope inventory to the Category 2 threshold quantity. Many isotope inventories exceed Category 3 thresholds, therefore, the comparison is performed to the Category 2 thresholds. The result is that some of the radionuclides exceed the Category 2 thresholds. Because the ratio of the canister inventory to the Category 2 thresholds exceeds 1.0 for some isotopes, such as ^{90}Sr , ^{137}Cs , and ^{241}Am , the sum of the ratios will also exceed 1.0. Therefore, the IHLW-ISF will be classified preliminarily as a Hazard Category 2 facility on the basis of only one canister.

The CSB was previously described as a Hazard Category 2 facility (HNF 1997c) without consideration of the inventory described above. The IHLW inventory will be an addition to the spent nuclear fuel inventory of the CSB. The designation for the CSB facility will remain as Hazard Category 2.

Table 3-2. Hazard Categorization.

| Isotope | Nominal Canister Inventory from Table 3-1 (Ci/Canister) | Category 3 Threshold Values (Ci) | Category 2 Threshold Values (Ci) | Ratio Inventory/Category 2 |
|--------------------|---|----------------------------------|----------------------------------|----------------------------|
| ⁵⁵ Fe | 4.4 E+01 | 5.4 E+03 | 1.1 E+07 | 4.0 E-06 |
| ⁵⁹ Ni | 6.3 E-01 | -- | 4.3 E+05 | 1.5 E-06 |
| ⁶⁰ Co | 1.3 E+02 | 2.8 E+02 | 1.9 E+05 | 6.8 E-04 |
| ⁶³ Ni | 7.1 E+01 | 5.4 E+03 | 4.5 E+06 | 1.6 E-05 |
| ⁷⁹ Se | 1.9 E-02 | -- | 4.3 E+05 | 4.4 E-08 |
| ⁹⁰ Sr | 1.4 E+05 | 1.6 E+01 | 2.2 E+04 | 6.4 E+00 |
| ⁹⁰ Y | 1.4 E+05 | -- | -- | -- |
| ^{93m} Nb | 3.8 E+00 | -- | 4.3 E+05 | 8.8 E-06 |
| ⁹³ Zr | 6.3 E+00 | 6.2 E+01 | 8.9 E+04 | 7.1 E-05 |
| ⁹⁹ Tc | 2.0 E+02 | 1.7 E+03 | 3.8 E+06 | 5.3 E-05 |
| ¹⁰⁶ Ru | 8.8 E+00 | 1.0 E+02 | 6.5 E+03 | 1.4 E-03 |
| ¹⁰⁶ Rh | 8.8 E+00 | -- | 4.3 E+05 | 2.0 E-05 |
| ¹⁰⁷ Pd | 1.8 E-01 | -- | 4.3 E+05 | 4.2 E-07 |
| ^{110m} Ag | 4.4 E-04 | 2.6 E+02 | 5.3 E+05 | 8.3 E-10 |
| ^{113m} Cd | 4.9 E+01 | 1.1 E+01 | 1.8 E+04 | 2.7 E-03 |
| ^{113m} In | 8.2 E-02 | -- | 4.3 E+05 | 1.9 E-07 |
| ¹¹³ Sn | 8.2 E-02 | 1.3 E+03 | 3.2 E+06 | 2.6 E-08 |
| ^{115m} Cd | 3.0 E-05 | -- | 4.3 E+05 | 7.0 E-11 |
| ^{119m} Sn | 4.4 E-04 | -- | 4.3 E+05 | 1.0 E-09 |
| ^{121m} Sn | 4.1 E-01 | -- | 4.3 E+05 | 9.5 E-07 |
| ¹²⁶ Sn | 2.1 E+00 | 1.7 E+02 | 3.3 E+05 | 6.4 E-06 |
| ¹²⁴ Sb | 1.2 E-04 | 3.6 E+02 | 1.3 E+06 | 9.2 E-10 |
| ¹²⁶ Sb | 2.1 E-01 | 2.8 E+02 | 2.5 E+06 | 8.4 E-08 |
| ^{126m} Sb | 1.5 E+00 | -- | 4.3 E+05 | 3.5 E-06 |
| ¹²⁵ Sb | 4.4 E+02 | -- | 4.3 E+05 | 1.0 E-03 |
| ^{125m} Te | 1.3 E+02 | -- | 4.3 E+05 | 3.0 E-04 |
| ¹²⁹ I | 4.1 E-03 | 9.2 E-01 | 1.8 E+03 | 2.3 E-06 |
| ¹³⁴ Cs | 3.0 E+02 | 4.2 E+01 | 6.0 E+04 | 5.0 E-03 |
| ¹³⁵ Cs | 1.3 E+00 | -- | 4.3 E+05 | 3.0 E-06 |
| ¹³⁷ Cs | 1.3 E+05 | 6.0 E+01 | 8.9 E+04 | 1.5 E+00 |
| ^{137m} Ba | 1.3 E+05 | -- | 4.3 E+05 | 3.0 E-01 |
| ¹⁴⁴ Ce | 4.4 E+00 | 1.0 E+02 | 8.2 E+04 | 5.4 E-05 |
| ¹⁴⁴ Pr | 4.4 E+00 | -- | 4.3 E+05 | 1.0 E-05 |
| ^{144m} Pr | 4.4 E-03 | -- | 4.3 E+05 | 1.0 E-08 |

Table 3-2. Hazard Categorization.

| Isotope | Nominal Canister Inventory from Table 3-1 (Ci/Canister) | Category 3 Threshold Values (Ci) | Category 2 Threshold Values (Ci) | Ratio Inventory/Category 2 |
|--------------------|---|----------------------------------|----------------------------------|----------------------------|
| ¹⁴⁷ Pm | 7.1 E+03 | 1.0 E+03 | 8.4 E+05 | 8.5 E-03 |
| ¹⁵¹ Sm | 4.1 E+03 | 1.0 E+03 | 9.9 E+05 | 4.1 E-03 |
| ¹⁵² Eu | 6.6 E+00 | 2.0 E+02 | 1.3 E+05 | 5.1 E-05 |
| ¹⁵⁴ Eu | 7.1 E+02 | 2.0 E+02 | 1.1 E+05 | 6.5 E-03 |
| ¹⁵⁵ Eu | 4.1 E+02 | 9.4 E+02 | 7.3 E+05 | 5.6 E-04 |
| ²³⁴ U | 3.3 E-02 | 4.2 E+00 | 2.2 E+02 | 1.5 E-04 |
| ²³⁵ U | 1.4 E-02 | 4.2 E+00 | 2.4 E+02 | 5.8 E-06 |
| ²³⁶ U | 3.6 E-03 | -- | 5.5 E+01 | 6.5 E-05 |
| ²³⁸ U | 2.6 E-02 | 4.2 E+00 | 2.4 E+02 | 1.1 E-04 |
| ²³⁷ Np | 1.0 E+00 | 4.2 E-01 | 5.8 E+01 | 1.7 E-02 |
| ²³⁸ Pu | 4.9 E+00 | 6.2 E-01 | 6.2 E+01 | 7.9 E-02 |
| ²³⁹ Pu | 4.1 E+01 | 5.2 E-01 | 5.6 E+01 | 7.3 E-01 |
| ²⁴⁰ Pu | 1.2 E+01 | -- | 5.5 E+01 | 2.0 E-01 |
| ²⁴¹ Pu | 3.0 E+02 | 3.2 E+01 | 2.9 E+03 | 1.0 E-01 |
| ²⁴² Pu | 3.0 E-03 | -- | 5.5 E+01 | 5.5 E-05 |
| ²⁴¹ Am | 1.9 E+03 | 5.2 E-01 | 5.5 E+01 | 3.5 E+01 |
| ²⁴² Am | 1.4 E+00 | -- | 5.5 E+01 | 2.5 E-02 |
| ^{242m} Am | 1.4 E+00 | 5.2 E-01 | 5.6 E+01 | 2.5 E-02 |
| ²⁴³ Am | 2.2 E-01 | 5.2 E-01 | 5.5 E+01 | 4.0 E-03 |
| ²⁴² Cm | 1.6 E+00 | 3.2 E+01 | 1.7 E+03 | 9.4 E-04 |
| ²⁴⁴ Cm | 4.1 E+01 | -- | 5.5 E+01 | 7.5 E-01 |

-- No threshold value for the isotope in this category.

4.0 ACCIDENT EVALUATION

The purpose of this accident evaluation is to identify facility hazards, facility specific safety features and functions, and assess the adequacy of the facility's design to withstand the postulated accidents. Since this project modifies Vaults 2 and 3 of the CSB for the storage of IHLW and Cs canisters, this analysis will not only evaluate the new design, but also the existing CSB SSCs that will be used to prevent/mitigate accidents involving the IHLW or Cs canisters.

4.1 PRELIMINARY HAZARDS ANALYSIS

The PHA is a form driven exploratory procedure for identifying hazards and candidates for controls. The PHA results are used for binning and screening of hazards and the development of accident scenarios.

4.1.1 Methodology

This section presents the methodology used to identify and characterize hazards associated with the handling and storage of the IHLW and Cs canisters in the CSB. The form used for the PHA is shown in Attachment A.

4.1.1.1 Hazard Identification. Hazards identification is the process of identifying material, system, process, and facility characteristics with the potential to initiate accidents having undesirable consequences. The primary method of Hazard Identification/Hazard Evaluation used for Project W-464 was a PHA. A PHA is a systematic approach in which the basic elements of the system and the hazards of interest at the conceptual design stage are identified, potential causes and effects are qualitatively evaluated, and possible corrective and/or preventive measures are proposed. The PHA was performed by personnel with experience in safety analysis methodology and personnel with knowledge of the IHLW-ISF design. The completed Project W-464 PHA table is contained in Attachment A.

4.1.1.2 Recording of Identified Hazards. The PHA table consists of 11 columns as shown in Attachment A. The first column, designated "ID", is an alphanumeric identifier for the line of information in the table. The ID identifier permits cross referencing the information contained in the PHA with assumptions found in the accident scenarios. Block numbers are also shown in this column and originate from a block diagram of the operating sequence that was used for identifying hazards. The task is divided into three phases for the purpose of designating the ID identifier. The phase for receipt of the cask at the CSB is designated with a "D". The phase for handling the canister and placing it in the storage tube with the MHM is designated with an "M". The phase associated with the removal of the cask from the CSB is designated with an "R". The ID identifiers are maintained throughout this document to permit identification of the source of the accident information.

The second column, designated "Operating Sequence Mode/Block", is used to describe the task step being reviewed.

The third column, "Hazard, Energy Source, Material", identifies the specific hazard that is being evaluated.

The fourth column, "Hazardous Condition", identifies the upset state that results from the hazard, energy source, or material identified in the third column.

The fifth column, "Cause", contains a description of the operation and/or conditions necessary for the hazard to become an accident.

The sixth column, "Potential Accident", contains a description of the accidents, that could release hazardous materials and cause consequences to the facility worker, onsite collocated worker, or the offsite receptor.

The seventh column, "Consequence", lists the consequences of the potential accident without mitigation or preventative measures.

The eighth column, "Safety Features", is further divided into "Engineered Features" used to list the physical design features that may be used to mitigate or prevent the event being considered and "Administrative Features" listing the potential administrative controls such as procedures, training, practices, etc., that could mitigate or prevent the event.

The ninth column, "Cons Cat" (for consequence category), contains a qualitative estimate of the result of the event, assuming that no engineered or administrative controls are present. However, naturally occurring phenomena (i.e., physical laws) that limit the consequence of an event are taken into account. The consequence ranking column is a "first cut", qualitative, consensus estimate of the safety severity of the consequences. An alphanumeric system was used to designate the severity, with the following "S" rankings characterizing consequences:

- S0 No effect outside the facility confinement systems and no safety concerns for the environment, the facility worker, the onsite worker, or members of the general public.
- S1 Potential industrial injury, radiological dose consequences or chemical exposure to the facility worker; limited environmental discharge of hazardous material outside the facility.
- S1* Potential life threatening injury or death for a facility worker, including significant internal or acute external exposures leading to medical treatment or care.
- S2 Potential significant radiological dose consequences or chemical exposure to the onsite worker outside of the facility;

environmental discharge of hazardous material within the Hanford site boundary.

- S3 Potential significant radiological dose consequences or chemical exposure to the offsite population; environmental discharges of hazardous material outside the Hanford site boundary or to the groundwater.

The tenth column, "Freq Cat" (for frequency category), contains a "first cut", qualitative, consensus estimate of the frequency for the consequences assuming that no engineered or administrative safety features are present. An alphanumeric system was used to designate the frequency, with the following "F" rankings characterizing frequency ranges:

- F0 Events not expected to occur and categorized as beyond extremely unlikely. The frequency is $< 1 \text{ E-06 yr}^{-1}$.
- F1 Events not expected to occur within the lifetime of a typical facility and categorized as extremely unlikely. The frequency is between 1 E-06 yr^{-1} and 1 E-04 yr^{-1} .
- F2 Events which could occur during the lifetime of the facility and categorized as unlikely. The frequency is between 1 E-04 yr^{-1} and 1 E-02 yr^{-1} .
- F3 Events which are expected to occur one or more times during the lifetime of the facility and categorized as anticipated. The frequency is greater than 1 E-02 yr^{-1} .

The "Remarks" column contains information that the team judged to require documentation. The information presented here includes, but is not limited to, assumptions and/or concerns about the specific step in the task identified in the PHA meeting.

4.1.1.3 PHA Performance Methodology. This section describes the process used in the PHA. The PHA table (Attachment A) is organized in sections to provide a structure that ensures a comprehensive look has been taken at all aspects of the operation associated with canister storage. Each section is oriented either to a Delivery, an MHM operation, or a Return phase. The PHA sections are:

- D-01 through D-25 These are the activities involved in delivery of the transport cask and transfer of the cask to the unloading pit.
- M-01 through M-38 These are the activities involved in the transfer of the canister from the cask (residing in the pit) into the MHM and transport of the canister to a position over a storage tube where it is lowered to its storage position.

R-01

These are the activities involved in removal of the cask from the pit.

Operational activities were evaluated by the team applying questions addressing: (1) the activity or function intended or expected to be seen at specific time intervals, (2) the definition of equipment malfunction and task failure, (3) the characteristics or modes associated with the failure, (4) the hazardous material affected with such a malfunction or failure, and (5) the estimated consequence and frequency.

The qualitative consequence and frequency estimates for accidents potentially resulting from the identified events were generated by the PHA team using a Delphi approach based on the team members' experience and judgment. A Delphi approach can be quite extensive. An example of the Delphi approach is presented in IEEE Standard 500-1984, *IEEE Guide to the Collection and Presentation of Electrical, Electronic, Sensing Component, and Mechanical Equipment Reliability Data for Nuclear Power Generating Stations*. The criteria for the consequence and frequency categories are listed in Section 4.1.1.2.

4.1.1.4 Hazard Evaluation/Accident Selection Methodology. The selection of accidents for further quantitative analysis was then performed with a binning process as recommended by DOE-STD-3009-94 and HNF-PRO-704.

All accidents were binned according to the potential accidents identified in column 6 in the PHA table (Attachment A). The binning was based on grouping similar accidents that challenged similar barriers. The potential accidents were grouped into eight bins: (1) Cask/Lid Drop accidents, (2) Fire/Explosion accidents, (3) Canister Drop Accidents, (4) Canister Pinch/Shear Accidents, (5) High Temperature in Canisters, (6) Loss of Confinement Accidents, (7) Natural Phenomena accidents, and (8) Worker Safety. Affixing the characteristics for the specific hazards to these respective bins is done through the use of the same ID identifier as in the PHA Table (Attachment A). This process is referred to as binning and is presented in Table 4-1.

After binning, the accidents are screened considering the magnitude of their consequences. The accident screening criteria used is based entirely on qualitative consequence rankings from the PHA table. All accidents postulated in the S2 and S3 consequence categories (except those determined as "Beyond Extremely Unlikely") are candidates for later quantitative analysis. This results in a broader spectrum of candidate accidents being considered for quantitative analysis than is recommended by DOE-STD-3009-94, which allows the accident frequency to be considered in determining accidents which do not require further analyses.

The hazards were labeled as accidents which would not have effects of concern outside the facility boundary of the CSB (S0, S1 and S1* category consequences), accidents which could potentially have effects of concern to

the onsite individual (S2 category consequences), and accidents identified as having potential effects to the offsite receptors (S3 category consequences).

The results of the binning and screening process are provided in Table 4-1. The table covers each hazard presented in the PHA. Table 4-1 also includes the selection of the representative accident for each bin. The representative accident and the basis for its selection is given in the last column.

Further discussion of the basis for selection is given in the following section.

Table 4-1. Binning, Screening, and Representative Accident Selection.

| Bin No. | Title | Consequence Category | Representative Accident Basis |
|---------|---|----------------------|--|
| 1. | Cask/Lid Drop | | |
| | D-14 Cask Drops into Pit (Section 4.2.7.4) | S2 | D-14 chosen to be representative accident because its 7 m drop distance into the pit is greater than 1 to 2 m drop for lids. Release fraction for glass is dependent on drop distance. |
| | D-17 Cask Lid Drop | S2 | |
| | D-22 Cask Lid Drop | S2 | |
| | M-03 Cask Lid Drop (Shield Hatch Assembly) | S2 | |
| | Accidents M/S1 or S0 Consequences | | Accidents of S1 and S0 consequence do not require further analysis. |
| | D-7/D-15 Yoke Drops on Cask | S0 | |
| | D-7/D-12 Cask Falls to Floor | S0 | |
| | M-10 Crane Falls on Cask | S0 | |
| | M-18/M-19 Tube Plug Drop (Seismic) | S0 | |
| 2. | Fire/Explosion | | |
| | D-05 Aircraft Strikes Building | S3 | Aircraft accident has a frequency of occurrence determined to be Beyond Extremely Unlikely [HNF 1997d]) so no further analysis is required. |
| | D-20 Ignition at Cask Opening | S1 | |
| | D-04 Truck Fire During Delivery | S0 | Accidents of S1 and S0 consequences do not require further analysis. |
| | | | |
| 3. | Canister Drop | | |
| | M-07 WHM Canister Drop | S3 | Three representative accidents were chosen to be analyzed, since there are several different combinations of radiological sources that could be dropped. |
| | M-08/M-29 Canister Drop (Seismic) | S3 | |
| | M-21 Canister Drop w/no Impact Limiter (Section 4.2.7.1) | S3 | M-21 is representative of a single glass canister drop. |
| | M-23 Canister Drop onto Second Canister (Section 4.2.7.2) | S3 | M-23 is representative of a multiple glass canister drop. |
| | M-24 Canister Drop in Cs Tube (Section 4.2.7.3) | S3 | M-24 is representative of a multiple Cs canister drop. |
| | | | |
| | Accidents M/S0 & S1 Consequences | | Accidents of S1 and S0 consequences do not require further analysis. |
| | M-20 Canister in Wrong Tube | S0 | |
| | M-22 Overload Tube | S0 | |
| 4. | Canister Pinch/Shear | | |
| | D-03 Truck Induced Impact (Section 4.2.7.7) | S3 | D-03 and M-09/M-30 were both chosen to be representative accidents. |
| | M-09/M-30 Seismic Canister Shear (Glass & Cs) (Sections 4.2.7.5, 4.2.7.6) | S3 | |
| | M-10 WHM Canister Pinch | S3 | |
| | M-25 WHM Canister Pinch | S3 | |

Table 4-1. Binning, Screening, and Representative Accident Selection.

| Bin No. | Title | Consequence Category | Representative Accident Basis |
|---------|--|----------------------|--|
| 5. | High Temperature in Canister | | Accidents of S1 and S0 consequence do not require further analysis. |
| | D-21/D-25 High Canister Temp in Pit | S1 | |
| | M-31 High Canister Temp (Seismic) | S1 | |
| | M-06/M-16/M-37 High Canister Temp in MHM | S0 | |
| 6. | Loss of Confinement | | Accidents of S1 and S0 consequence do not require further analysis. |
| | D-18/D-23 Release from Cask | S1 | |
| | M-04 Cask Lid Removed | S1 | |
| | M-14 Cask Lid Removed | S1 | |
| 7. | Canister Corrosion | S0 | Loss of cooling not expected to result in failure of canisters. Thermal analysis based on loss of total ventilation is in progress. M-28 chosen to be representative accident because damage sustained would include any damage from M-29. Consequences from M-28 would bound any from M-29. |
| | Natural Phenomena | | |
| | M-27 Loss of Vault Cooling due to Natural Event (Section 4.2.7.9) | S0 | |
| | D-06 High Wind, Ash and Snow Loading | S3 | |
| 8. | M-28 Earthquake Fails Tubes (Section 4.2.7.8) | S3 | Worker safety issues discussed in Section 4.1.2.3. Accidents designated S1* have consequences that involve worker fatality or serious injury to workers. S1* accidents will require Safety Significant SSCs or administrative controls for prevention or mitigation. Accidents with S0 or S1 consequences do not require further analysis. |
| | M-29 Earthquake Fails Structure (Includes Ventilation Inlet/Outlet Structures) | S3 | |
| | Worker Safety | | |
| | D-19/D-24/M-05 High Radiation Exposure | S1* | |
| | M-11/M-13/M-36 High Radiation at MHM | S1* | Accidents with S0 or S1 consequences do not require further analysis. |
| | M-34 Criticality | S1* | |
| | Accidents W/S0 & S1 Consequences | | |
| | D-01 Transporter Accident | S1 | |
| | D-02 Transporter Accident (Heart attack) | S1 | |
| | D-08/D-16 Yoke Drops on Worker | S1 | |
| | D-11 Crane Falls on Worker | S1 | |
| | D-20 Ignition at Cask Opening | S1 | |
| | M-12/M-02 MHM Strikes Crane | S0 | |
| | M-12/M-15 Crane Falls into Pit | S1 | |
| | M-17/M-38 MHM Traps | S1 | |
| | R-01/D-13 Cask Drop on Worker | S1 | |

4.1.2 Hazard Analysis Results

This section presents the results of the hazards analysis process and lists the accident scenarios to be further analyzed.

4.1.2.1 Hazard Identification Results. Because the PHA consequence ranking is based on the worst case potential consequence, it is important to recognize that accidents with potential consequences of concern affecting the offsite individual would generally also have potential consequences of concern affecting both the onsite individual and the facility worker. Furthermore, even though various accidents would have virtually the same consequences, they could be initiated by a number of events.

The hazards identified during the PHA (Attachment A) are documented as hazards with potential effects to the facility worker, hazards with potential effects to the onsite worker, and hazards with potential effects to the offsite public.

4.1.2.2 Selected Accidents. Accident analysis criteria require that a set of accidents be quantitatively analyzed. The accident selection methodology is described below and the results of the accident selection activity are shown.

For each selected hazard type with an S2 or S3 consequence in Table 4-1, a representative (bounding) accident was chosen for further analysis. A representative accident bounds the consequences of similar accidents or accident types. Similar accidents challenge analogous barriers. Analogous barriers reflect the same design philosophy for prevention and mitigation of the same accident type, even though they may be in different locations.

The accidents determined to be representative and to bound consequences from the bins of accidents are listed below along with the sections where they are evaluated.

1. Glass Canister Drop Accident
(From Bin 3, ID M-21, Section 4.2.7.1)
2. Multiple Glass Canister Drop Accident
(From Bin 3, ID M-23, Section 4.2.7.2)
3. Cs Canister Drop Accident
(From Bin 3, ID M-24, Section 4.2.7.3)
4. Transport Cask with Canister Drop Accident
(From Bin 1, ID D-14, Section 4.2.7.4)
5. Seismic Induced Glass Canister Shear Accident
(From Bin 4, ID M-09/M-30, Section 4.2.7.5)
6. Seismic Induced Cs Canister Shear Accident
(From Bin 4, ID M-09/M-30, Section 4.2.7.6)

7. Truck Impact with MHM Causing Canister Shear
(From Bin 4, ID D-03, Section 4.2.7.7)
8. Seismic Accident Causing Tube Failure
(From Bin 7, ID M-28, Section 4.2.7.8)
9. Loss of Cooling Accident
(From Bin 7, ID M-27, Section 4.2.7.9)

4.1.2.3 Worker Safety. Worker safety for Project W-464 is assured by a combination of confinement and shielding features and institutional practices defined in the SNF and TWRS Health and Safety Plans. These features and practices are integral to the facility design and operation. Accidents identified as worker safety concerns are shown in Table 4.1, Bin 8.

The industrial safety requirements for DOE sites are governed by 29 CFR 1910, which addresses such topics as working surfaces, machinery and machine guarding, compressed gas and compressed air equipment, and electrical requirements. Protection of the facility worker from standard industrial hazards (SI consequences) is achieved through adherence to the requirements of 29 CFR 1910 and does not require specific Safety Significant SSCs or administrative features. The major features of worker protection from SI* consequence accidents are associated with radiation protection and criticality issues. The facility shielding design is designated as Safety Significant for worker protection. This applies to the transportation cask, the MHM, the receiving pit, operating deck, storage tube plugs, and the vault ventilation louvers. The shielding design and the radiological control program are established to meet ALARA goals for radiological exposure. Controls on the glass canisters will be established to address criticality concerns (see Section 4.2.8). A criticality safety evaluation will be performed during definitive design to assess the adequacy of the criticality controls.

4.1.2.4 Design and Operational Safety Improvements Under Consideration. In the process of performing the PHA, the team identified a number of potential opportunities to enhance the safety of the facility operations:

- The cask should be designed for transportation accidents, for the design basis earthquake (DBE) and for other possible hazards while in the CSB.
- The MHM should not be used during trailer movement.
- There should be a fuel limit for the truck.
- The truck should be removed before the outer door is closed and the cask is moved to the receiving pit.
- The cask should be hooked to the crane before the tiedowns are removed.

- A maximum lift height for the cask should be established and/or limited by design.
- The cask lid and cask should be engineered to prevent damage to contents from a drop of the lid.
- Canisters should be designed for impact resistance.
- The cask atmosphere should be checked before opening.
- The process sequence should be evaluated to assure adequate shielding is provided at all times.
- Requirements for cleanliness and dryness of the cask interior should be established.
- The design should ensure that cooling is sufficient to protect the integrity of the IHLW glass, the Cs ion exchange resin, and the canister.
- Limits on cask residence time in the pit should be established if required to maintain temperatures within limits.
- Recovery actions for equipment failures should be developed to prevent overheating.
- Interlocks should be provided to prevent movement of the MHM when the receiving crane is in the area.
- Procedures governing crane and MHM movement should be developed.
- At the MHM/pit interface, an O-ring sealed nose piece should be used to provide confinement.
- A guard should be provided to prevent personnel from closely approaching the MHM when a canister is present.
- The grapple should be designed with sensors that verify the MHM grapple has engaged the canister.
- Requirements should be developed to control the number of canisters in process at a given time.
- The MHM should have a touch bar to stop its motion when an object is contacted.
- An alarm and/or light should be activated when the MHM is in motion.

- Access ports should be provided to allow access to the plug hoist and grapple.
- Accountability Controls should be established to prevent intermingling waste types and to control the Cs radionuclide inventory in the storage tubes.
- Procedures for placement of canisters should be developed.
- Procedures for impact limiter installation should be developed.
- An interlock should be provided to prevent the grapple from opening before the canister reaches the intended position.
- The canister grapple should be designed so that it can not open under load.
- Controls on the quantity and use of water or solvents in the CSB should be established.

4.2 ACCIDENT ANALYSIS

This chapter presents the accident analyses performed for selected accident scenarios. The selected accident scenarios are described, including the key assumptions, and analyzed to determine the unmitigated consequences to onsite and offsite receptors. The consequences are compared to equipment design guidelines for determination of potential safety SSCs.

4.2.1 Consequence Analysis Methodology

Radiological doses to receptors are determined for the accident analysis with the following equation:

$$\text{Dose} = (\text{ST})(\Sigma\text{MDF or DCF})(\chi/Q')(BR)$$

where:

- Dose = inhalation effective dose equivalent (EDE) (rem)
- ST = source term - respirable airborne release (kg or Ci)
- ΣMDF = sum of isotope-specific mass dose factors for IHLW glass (rem/kg glass inhaled)
- DCF = inhalation dose conversion factor (rem/ci)
- χ/Q' = atmospheric dispersion coefficient (s/m^3)
- BR = breathing rate (m^3/s)

4.2.2 Source Term

A specific source term represents the product of the material at risk (MAR), the airborne release fraction (ARF), respirable fraction (RF), and the leak path factor (LPF). The general equation for the determination of a source term is:

Source term (ST) = (MAR)(ARF)(RF)(LPF)

4.2.2.1 MAR. For the purpose of these analyses, the MAR is assumed to be the postulated maximum inventory, which will be the mass of IHLW glass or Cs involved in each accident.

4.2.2.2. ARF and RF. The bases for the postulated releases and their associated ARFs and RFs are taken from DOE-HDBK-3010-94, *Airborne Release Fractions/Rates, and Respirable Fractions for Nonreactor Nuclear Facilities*. This reference provides factors for estimating the radiological releases in deterministic analyses of accident scenarios postulated for nonreactor nuclear facilities. The factors in DOE-HDBK-3010-94 are based on experimental data.

Glass Considerations. Mechanical impact releases from vitrified waste are found in DOE-HDBK-3010-94 in Section 4.3.3, which addresses impactation stress for nonmetallic or composite solids. In this section, it is noted that brittle materials such as glass can be fragmented when impacted or crushed. Data is presented from experiments to measure the fraction and size distribution generated by the impact of falling objects on various brittle materials resting on an unyielding surface. The degree of fragmentation and the size distribution were found to be a function of the material, strength and age of the material, and the energy input per volume. The fraction in the size range $10\mu\text{m}$ aerodynamic equivalent diameter and less for glass was empirically correlated with the energy input. The correlation was presented as:

$$\text{ARF} \times \text{RF (respirable release fraction)} = (A)(P)(g)(h)$$

where:

- ARF = airborne release fraction
- RF = respirable fraction
- A = empirical constant ($2.0 \times 10^{-11} \text{ cm-s}^2/\text{g}$)
- P = specimen density g/cm^3
- g = acceleration of gravity (980 cm/s^2)
- h = height of drop (cm).

The glass samples used in the experiments were uniformly free of cracks and flaws. Vitrified waste, depending on its cool down rate, has been found to develop cracks and generation of glass fines within the cracks. These cracks were evenly distributed throughout the volume of the poured glass cylinders. Impact damage and fragmentation, as covered by the above correlation, is localized near the point of impact so contributions from existing fines would not be significant.

Cs Considerations. The ion exchange media holding Cs as received from the vendor has a particle size of 20 to 50 mesh (397 to $208\mu\text{m}$) as specified in WHC 1996a. Because no information is provided on the percentage of fines in the resin, it is estimated from PNNL 1981, that 0.1% of the resin will have been reduced to particles with a diameter of $< 10\mu\text{m}$ (i.e., the RF).

4.2.2.3 LPF. Using the guidelines of DOE-STD-3009-94, analysis of unmitigated scenarios may take credit for reduction of releases by passive design features (e.g., buildings) that may be assumed to remain in place during and after the accident. The reduction factor assumed for the passive design features is the LPF. In the accident scenarios presented in Section 4.2.7, credit is taken only for the existence of the canister. No credit is taken for the CSB structure or for the ventilation system. Transport of releases by the ventilation system would not affect the amount of material assumed to be released in the accident scenarios since the analyses take no credit for holdup of the releases in the building.

A source term is considered to be the amount of respirable material that has escaped containment and is available for transport to a receptor location. To determine the amount of material that could exit a canister during a mechanical release as the result of a container rupture, crush, or fall, an LPF as described in DOE-HDBK-3010-94 is used. The LPF is the fraction of airborne radioactive material that escapes from containment (e.g., the canister); therefore, the LPF accounts for the fractional release of contents from the damaged but still present container.

Information on damage to, or openings in, the canister as a result of drops or other accidents is not available. In the absence of direct data for the canisters, an LPF is conservatively based on information existing for storage drums. In HNF-SD-WO26-SAR-002, *Final Safety Analysis Report (FSAR) For Waste Receiving and Processing (WRAP) Facility*, (HNF 1997a) an LPF of 0.1 was derived for the release of respirable material escaping from DOT 7A waste drums damaged due to falls or vehicle impacts. This value was based on the estimated area of the opening created by the accident as a percentage of the total surface area of the container. The validity of this LPF for use with the canister damage will be further verified when more information is available.

The LPF multiplied by the respirable release fraction (ARF x RF) yields the total respirable release fraction.

4.2.3 Mass Dose Factor

The consequences used for comparison to the equipment design guidelines are EDEs. The EDE is the sum of the products of the dose equivalent in a tissue or organ and the weighting factor for that tissue or organ. Since there are a significant number of isotopes in the MAR, each with a unique EDE inhalation DCF, the DCF for each isotope is multiplied by the respective activity per kilogram in Table 4-2 to yield an isotope-specific MDF. The isotope-specific MDFs are summed to determine a total MDF (ΣMDF) for glass containing all of the isotopes.

The EDE inhalation DCFs (in Sv/Bq) were obtained from *Limiting Values of Radionuclide Intake and Air Concentration and Waste Package Dose Factors for Inhalation, Submersion, and Ingestion* (EPA 1988). These values are converted to rem/Ci by multiplying by 3.7×10^{12} rem-Bq/Sv-Ci. For example, the

inhalation DCF for insoluble ^{239}Pu (lung clearance class W) is 1.16×10^{-4} Sv/Bq or 4.29×10^8 rem/Ci.

Table 4-2. Derivation of ΣMDF for IHLW Glass.

| Isotope | Inventory from Table 3-1 (Ci/kg) | Inhalation dose conversion factor (Sv/Bq) | Inhalation dose conversion factor (rem/ci) | Mass Dose Factor (rem/kg glass inhaled) |
|--------------------|--|--|---|---|
| ⁵⁵ Fe | 1.6E-02 | 7.26E-10 | 2.69E+03 | 4.30E+01 |
| ⁵⁹ Ni | 2.3E-04 | 3.58E-10 | 1.32E+03 | 3.04E-01 |
| ⁶⁰ Co | 4.8E-02 | 5.91E-08 | 2.19E+05 | 1.05E+04 |
| ⁶³ Ni | 2.6E-02 | 8.39E-10 | 3.10E+03 | 8.06E+01 |
| ⁷⁹ Se | 6.8E-06 | 2.66 E-09 | 9.84 E+03 | 6.69 E-02 |
| ⁹⁰ Sr | 5.0E+01 | 6.47 E-08 | 2.39 E+05 | 1.20E+07 |
| ⁹⁰ Y | 5.0E+01 | 2.28 E-09 | 8.44 E+03 | 4.22E+05 |
| ^{93m} Nb | 1.4E-03 | 7.90E-09 | 2.92E+04 | 4.09E+01 |
| ⁹³ Zr | 2.3E-03 | 8.67E-08 | 3.21E+05 | 7.38E+02 |
| ⁹⁹ Tc | 7.3E-02 | 2.25 E-09 | 8.33 E+03 | 6.08 E+02 |
| ¹⁰⁶ Ru | 3.2E-03 | 1.29 E-07 | 4.71 E+05 | 1.53E+03 |
| ¹⁰⁶ Rh | 3.2E-03 | 5.77 E-11 | 2.13 E+02 | 6.82E-01 |
| ¹⁰⁷ Pd | 6.5E-05 | 3.45 E-09 | 1.27 E+04 | 8.26E-01 |
| ^{110m} Ag | 1.6E-07 | 2.17 E-08 | 8.03 E+04 | 1.28E-02 |
| ^{113m} Cd | 1.8E-02 | 4.13 E-07 | 1.53 E+06 | 2.75E+04 |
| ^{113m} In | 3.0E-05 | 1.11 E-11 | 4.11 E+01 | 1.23E-03 |
| ¹¹³ Sn | 3.0E-05 | 2.88 E-09 | 1.07 E+04 | 3.21E-01 |
| ^{115m} Cd | 1.1E-08 | 1.95 E-08 | 7.22 E+04 | 7.94E-04 |
| ^{119m} Sn | 1.6E-07 | 1.69 E-09 | 6.25 E+03 | 1.00E-03 |
| ^{121m} Sn | 1.5E-04 | 3.11 E-09 | 1.15 E+04 | 1.73E+00 |
| ¹²⁶ Sn | 7.7E-04 | 2.69 E-08 | 9.95 E+04 | 7.66E+01 |
| ¹²⁴ Sb | 4.2E-08 | 6.80 E-09 | 2.52 E+04 | 1.06E-03 |
| ¹²⁶ Sb | 7.8E-05 | 3.17 E-09 | 1.17 E+04 | 9.13E-01 |
| ^{126m} Sb | 5.5E-04 | 9.17 E-12 | 3.39 E+01 | 1.86E-02 |
| ¹²⁵ Sb | 1.6E-01 | 3.30 E-09 | 1.22 E+04 | 1.95E+03 |
| ^{125m} Te | 4.8E-02 | 1.97 E-09 | 7.29 E+03 | 3.50E+02 |
| ¹²⁹ I | 1.5E-06 | 4.69 E-08 | 1.74 E+05 | 2.61 E-01 |
| ¹³⁴ Cs | 1.1E-01 | 1.25 E-08 | 4.63 E+04 | 5.09E+03 |
| ¹³⁵ Cs | 4.8E-04 | 1.23 E-09 | 4.55 E+03 | 2.18E+00 |
| ¹³⁷ Cs | 4.8E+01 | 8.63 E-09 ¹ | 3.19 E+04 ¹ | 1.53E+06 |
| ^{137m} Ba | 4.8E+01 | -- | -- | -- |
| ¹⁴⁴ Ce | 1.6E-03 | 1.01 E-07 | 3.74 E+05 | 5.98 E+02 |
| ¹⁴⁴ Pr | 1.6E-03 | 1.17 E-11 | 4.33 E+01 | 6.93 E-02 |
| ^{144m} Pr | 1.6E-06 | -- ² | -- | -- |

Table 4-2. Derivation of ΣMDF for IHLW Glass.

| Isotope | Inventory from Table 3-1 (Ci/kg) | Inhalation dose conversion factor (Sv/Bq) | Inhalation dose conversion factor (rem/Ci) | Mass Dose Factor (rem/kg glass inhaled) |
|--------------------|--|--|---|---|
| ¹⁴⁷ Pm | 2.6E+00 | 1.06 E-08 | 3.92 E+04 | 1.02 E+05 |
| ¹⁵¹ Sm | 1.5E+00 | 8.10 E-09 | 3.00 E+04 | 4.50 E+04 |
| ¹⁵² Eu | 2.4E-03 | 5.97 E-08 | 2.21 E+05 | 5.30 E+02 |
| ¹⁵⁴ Eu | 2.6E-01 | 7.73 E-08 | 2.86 E+05 | 7.44 E+04 |
| ¹⁵⁵ Eu | 1.5E-01 | 1.12 E-08 | 4.14 E+04 | 6.21 E+03 |
| ²³⁴ U | 1.2E-05 | 3.58 E-05 | 1.32 E+08 | 1.58 E+03 |
| ²³⁵ U | 5.2E-07 | 3.32 E-05 | 1.23 E+08 | 6.40 E+01 |
| ²³⁶ U | 1.3E-06 | 3.39 E-05 | 1.25 E+08 | 1.63 E+02 |
| ²³⁸ U | 9.4E-06 | 3.20 E-05 | 1.18 E+08 | 1.11 E+03 |
| ²³⁷ Np | 3.7E-04 | 1.46 E-04 | 5.40 E+08 | 2.00 E+05 |
| ²³⁸ Pu | 1.8E-03 | 1.06 E-04 | 3.92 E+08 | 7.06 E+05 |
| ²³⁹ Pu | 1.5E-02 | 1.16 E-04 | 4.29 E+08 | 6.44 E+06 |
| ²⁴⁰ Pu | 4.2E-03 | 1.16 E-04 | 4.29 E+08 | 1.80 E+06 |
| ²⁴¹ Pu | 1.1E-01 | 2.23 E-06 | 8.25 E+06 | 9.08 E+05 |
| ²⁴² Pu | 1.1E-06 | 1.11 E-04 | 4.10 E+08 | 4.51 E+02 |
| ²⁴¹ Am | 6.9E-01 | 1.20 E-04 | 4.44 E+08 | 3.06 E+08 |
| ²⁴² Am | 5.0E-04 | 1.58 E-08 | 5.84 E+04 | 2.92 E+01 |
| ^{242m} Am | 5.2E-04 | 1.15 E-04 | 4.26 E+08 | 2.22 E+05 |
| ²⁴³ Am | 8.1E-05 | 1.19 E-04 | 4.40 E+08 | 3.56 E+04 |
| ²⁴² Cm | 6.0E-04 | 4.67 E-06 | 1.73 E+07 | 1.04 E+04 |
| ²⁴⁴ Cm | 1.5E-02 | 6.70 E-05 | 2.47 E+08 | 3.71 E+06 |
| Total(ΣMDF) | | | | 3.34 E+08 |

1 Includes daughter product ^{137m}Ba.

2 No value given for ^{144m}Pr in EPA 1988.

The Cs canisters will contain free flowing ion exchange resin. The maximum inventory in each storage tube is 3.2×10^5 Ci of ¹³⁷Cs/^{137m}Ba and 2.1 Ci ¹³⁵Cs (see Section 3.1). Given that all of this inventory could be present in one Cs canister (in which case only one canister would be allowed in the storage tube), the maximum inventory in a Cs canister is the same as the maximum inventory in the storage tube.

4.2.4 Atmospheric Dispersion

The degree of atmospheric dispersion between the source term release point and a receptor location can be characterized with an atmospheric dispersion coefficient, or X/Q' (where X = airborne concentration at a given receptor, in Ci/m^3 or mg/m^3 ; and Q' = release rate, in Ci/s or mg/s).

The onsite, near river bank, and offsite receptor X/Q' 's are shown in Table 4-3. Calculations for these X/Q' 's are documented in HNF-SD-SNF-RPT-004 (HNF 1997c). Note in Table 4-3 that these X/Q' 's are for a ground level release. The use of a ground level release in all of the calculations is conservative. Releases which could occur if material is released into the vault cooling air flow and carried out the elevated stack would have lower consequences than those calculated for a ground level release.

Table 4-3. Dispersion Factors for Receptors Associated with the Canister Storage Building.

| Worst Case Receptor Locations | | | X/Q' for Ground Level Release (s/m^3) |
|-------------------------------|----------|-----------|---|
| Description | Distance | Direction | |
| Onsite | 100 m | E | 3.41 E-02 |
| Near River | 15.0 km | E | 1.96 E-05 |
| Offsite | 18.3 km | E | 1.32 E-05 |

1 Assuming point source release without building wake

4.2.5 Breathing Rate

For calculation of inhalation doses, a breathing rate is required. The breathing rate used is the acute, light activity rate given in *Reference Man: Anatomical, Physiological, and Metabolic Characteristics* (ICRP 1975). Its value is $3.3 \times 10^{-4} m^3/s$.

4.2.6 Equipment Design Guidelines

Acceptability of accidents from a risk perspective is not evaluated in this analysis since the design has not progressed far enough to estimate accident frequencies accurately. However, for design purposes, unmitigated accident consequences are compared to the Safety Class and Safety Significant thresholds used in HNF-SD-SNF-RPT-004 (HNF 1997c) with consideration only for whether the accident is credible. The Safety Class threshold is 0.5 rem (5 mSv) for the offsite receptor, and the Safety Significant threshold is 5 rem (50 mSv) for the onsite receptor. These thresholds are consistent with those in HNF-PRO-704. Future safety analysis will address the risk associated with the potential accidents.

4.2.7 Analysis of Radiological Accident Scenarios

In the following sections, various accident scenarios associated with ILHW-ISF are evaluated:

- o Four canister drop scenarios (a glass canister drop in Section 4.2.7.1, a multiple glass canister drop in Section 4.2.7.2, a Cs canister drop in Section 4.2.7.3, and a transport cask/canister drop in Section 4.2.7.4)
- o Two seismically induced canister shear scenarios (involving a glass canister in Section 4.2.7.5 and a Cs canister in Section 4.2.7.6)
- o A vehicle-induced glass canister shear scenario in Section 4.2.7.7
- o A seismically induced tube failure in Section 4.2.7.8
- o A loss of cooling accident in Section 4.2.7.9

4.2.7.1 Glass Canister Drop Accident. Dropping a glass canister from the MHM into an empty tube is an operational accident that could be caused by human error or equipment failure.

Scenario and key assumptions. A release is postulated to occur as the result of dropping a glass canister during a transfer from the MHM to a storage tube. An MHM failure or human error during raising or lowering operations could result in dropping a glass canister into an empty tube. The storage tube is not actively ventilated, although it will be vented via a cartridge filter to the operation area. Cooling is provided by natural convection that occurs through the vault. This natural convection flow is around the exterior of the tube, and is then exhausted through the CSB stack. The MHM will be in place over the tube when the drop occurs.

Facility personnel in the vicinity of the accident would be aware immediately of the event upon occurrence and could initiate emergency response actions. However, for this scenario, it is assumed that no response or recovery action occurs.

Source Term Analysis. Information and assumptions used to determine the amount of material released are as follows.

- It is assumed that the impact absorbers are not in place and no other canisters are present. The dropped canister is assumed to rupture when it impacts at the bottom of the tube, releasing airborne particulate from the shattered glass within.
- For the drop of a canister into an empty tube, the height of the drop would be the depth of the tube (12.8 m) plus the distance from the top of the tube to the bottom of the canister when raised inside the MHM (1.5 m) for a total of 14.3 m.
- The release from the canister is assumed to enter the vault area or the CSB area due to a breach of the tube or the MHM-tube seal.

From Section 4.2.2, the respirable release fraction is determined by:

$$ARF \times RF = (A)(P)(g)(h)$$

The drop height is 14.3 m. The density of the vitrified waste is 2.64 g/cm³. The respirable release fraction is therefore:

$$\begin{aligned} ARF \times RF &= (2.0 \times 10^{-11} \text{ cm-s}^2/\text{g})(2.64 \text{ g/cm}^3)(980 \text{ cm/s}^2)(14.3 \times 10^2 \text{ cm}) \\ &= 7.4 \times 10^{-5} \end{aligned}$$

With consideration of the LPF of 0.1 from Section 4.2.2, the total respirable release fraction is:

$$\begin{aligned} (ARF \times RF)(LPF) &= (7.4 \times 10^{-5})(0.1) \\ &= 7.4 \times 10^{-6} \end{aligned}$$

Since a canister can contain up to 3,060 kg of glass (the MAR), the total respirable release (source term) is:

$$\begin{aligned} ST &= (MAR)(ARF \times RF \times LPF) \\ &= (3.060 \times 10^3 \text{ kg})(7.4 \times 10^{-6}) \\ &= 2.3 \times 10^{-2} \text{ kg} \end{aligned}$$

Unmitigated dose consequences.

From Section 4.2.1, the dose is determined by:

$$\text{Dose} = (ST)(\Sigma MDF)(\chi/Q')(BR)$$

The onsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (2.3 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(3.41 \times 10^{-2} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 8.6 \times 10^1 \text{ rem EDE onsite}$$

The near river radiological dose consequence is determined as follows:

$$\text{Dose (rem)} = (2.3 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ \left(1.96 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right)$$

$$\text{Dose (rem)} = 5.0 \times 10^{-2} \text{ rem EDE near river}$$

The offsite radiological dose consequence is determined as follows:

$$\text{Dose (rem)} = (2.3 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ \left(1.32 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right)$$

$$\text{Dose (rem)} = 3.3 \times 10^{-2} \text{ rem EDE offsite}$$

Comparison with equipment design guidelines. As shown in Table 4-4, the unmitigated onsite dose consequence resulting from a dropped glass canister exceeds the guideline.

Table 4-4. Dropped Glass Canister Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|-----------------------------|---------------------------------------|
| Onsite | 8.6 E+01 | 5.0 E+00 |
| Near river | 5.0 E-02 | 5.0 E-01 |
| Offsite | 3.3 E-02 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. If this accident is not mitigated or prevented by designed safety features, the onsite radiological dose consequence exceeds the Safety Significant guideline from Section 4.2.6. If this scenario remains credible in subsequent analyses, Safety Significant SSCs might be required for prevention or mitigation of the accident consequences. For accidents involving a drop of a canister, the preventive or mitigative equipment would be the impact absorber which would cushion the fall and prevent damage to the canister and possible breach of the storage tube. Alternate options for consideration as preventive or mitigative equipment would include the MHM-tube seal, the MHM grapple, and any lifting devices. See Table 4-7 (Section 4.2.7.3) for a summary of the potential safety SSCs for prevention and mitigation of the canister drop accidents.

4.2.7.2 Multiple Glass Canister Drop Accident. Dropping a glass canister from the MHM into a tube that already contains one or more glass canisters is an operational accident that could be caused by human error or equipment failure.

Scenario and key assumptions. The scenario and key assumptions are the same as those in Section 4.2.7.1 except that a glass canister is assumed to be in the tube when a second canister is dropped.

Source Term Analysis. Information and assumptions used to determine the amount of material released are as follows.

- Since a tube can hold two large canisters, it is assumed that one canister is already in the tube.
- Each canister contains the maximum quantity of glass, 3,060 kg.
- The canister is designed to maintain its containment if impact absorbers are in place at the bottom of the tube and above the existing canister in the tube. For this scenario, it is assumed that the impact absorbers are not in place, so the dropped canister is assumed to rupture along with the one already in the tube, releasing airborne particulate from the shattered glass within.
- The release from the canisters is assumed to enter the vault area or the CSB area due to a breach of the tube or the MHM-tube seal.

From Section 4.2.2, the respirable release fraction is determined by:

$$ARF \times RF = (A)(P)(g)(h)$$

Each canister is 4.5 m in height and with one already in tube, the height of the drop is approximately 14.3 m - 4.5 m = 9.8 m. The density of the vitrified waste is 2.64 g/cm³. The respirable release fraction is therefore:

$$\begin{aligned} ARF \times RF &= (2.0 \times 10^{-11} \text{ cm-s}^2/\text{g})(2.64 \text{ g/cm}^3)(980 \text{ cm/s}^2)(9.8 \times 10^2 \text{ cm}) \\ &= 5.1 \times 10^{-5} \end{aligned}$$

With consideration of the LPF Of 0.1 from Section 4.2.2, the total respirable release fraction is:

$$\begin{aligned} ARF \times RF \times LPF &= (5.1 \times 10^{-5})(0.1) \\ &= 5.1 \times 10^{-6} \end{aligned}$$

Since a canister can contain up to 3,060 kg of glass (the MAR), and two canisters are involved, the respirable release (source term) is:

$$\begin{aligned} ST &= (MAR)(ARF \times RF \times LPF) \\ &= 2(3,060 \text{ kg}) (5.1 \times 10^{-6}) \\ &= 3.1 \times 10^{-2} \text{ kg} \end{aligned}$$

Unmitigated dose consequences.

From Section 4.2.1, the dose is determined by:

$$\text{Dose} = (ST)(\Sigma MDF)(\chi/Q')(BR)$$

The onsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (3.1 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(3.41 \times 10^{-2} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 1.2 \times 10^2 \text{ rem EDE onsite}$$

The near river radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (3.1 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(1.96 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 6.7 \times 10^{-2} \text{ rem EDE near river}$$

The offsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (3.1 \times 10^{-2} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(1.32 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 4.5 \times 10^{-2} \text{ rem EDE offsite}$$

Comparison with equipment design guidelines. As shown in Table 4-5, the unmitigated onsite dose consequence resulting from a multiple glass canister drop accident exceeds the guideline.

Table 4-5. Multiple Glass Canister Drop Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 1.2 E+02 | 5.0 E+00 |
| Near river | 6.7 E-02 | 5.0 E-01 |
| Offsite | 4.5 E-02 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. The same design and control considerations presented in Section 4.2.7.1 apply to this scenario. For this scenario, a second impact absorber is needed between the first and second canisters. See Table 4-7 (Section 4.2.7.3) for a summary of the potential safety SSCs for prevention and mitigation of the canister drop accidents.

4.2.7.3 Cs Canister Drop Accident. Dropping a Cs canister during unloading or during placement into a storage tube is an operational accident that could be caused by human error or equipment failure.

Scenario and Key Assumptions. The scenario and key assumptions presented in Section 4.2.7.1 for the glass canister drop are applicable to this scenario except the canister contains Cs instead of glass.

Source Term Analysis. Information and assumptions used to determine the amount of material released are as follows.

- The inventory at risk is the maximum radionuclide inventory in a Cs container, 3.2×10^5 Ci of ^{137}Cs and 2.5 Ci of ^{135}Cs (see Section 3.1). For accidents involving Cs canisters, the dose contribution from the allowable quantity of Cs-135 is insignificant in relation to the allowable quantity of Cs-137 because (a) the quantity of Cs-137 allowed ($3.2\text{E}+5$ Ci) is 5 orders of magnitude larger than the quantity of Cs-135 allowed (2.1 Ci), and (b) the inhalation dose conversion factor for Cs-137 ($3.19\text{E}+4$ rem/Ci inhaled) is nearly an order of magnitude larger than that for Cs-135 ($4.55\text{E}+3$ rem/Ci inhaled). Since the Cs-135 contribution to the accident dose consequences is insignificant, it is not addressed in the consequence calculation.
- This scenario envelopes all scenarios involving Cs containers in a single storage tube because the inventory of Cs postulated for this accident is the maximum allowable for a single storage tube.

- It is assumed that 0.1% of the resin is in respirable particles and that all of the respirable material is made airborne (see Section 4.2.2).
- The LPF from Section 4.2.2 is 0.1.
- For this scenario, it is assumed that the impact absorber is not in place, so the dropped canister is assumed to rupture, releasing airborne particulate from the Cs resin.
- The release from the canister is assumed to enter the vault area or the CSB area due to a breach of the tube or the MHM-tube seal.

Assuming that 0.1% of the resin is in respirable particles and that all of the respirable material is made airborne, the respirable release fraction (ARF x RF) is 1.0×10^{-3} .

With consideration of the LPF of 0.1 from Section 4.2.2 the total respirable release fraction is:

$$\begin{aligned} (\text{ARF} \times \text{RF})(\text{LPF}) &= (1.0 \times 10^{-3})(0.1) \\ &= 1.0 \times 10^{-4} \end{aligned}$$

Since the amount of Cs in a tube is limited to 3.2×10^5 Ci, the respirable release (source term) is:

$$\begin{aligned} \text{ST} &= (\text{MAR})(\text{ARF} \times \text{RF} \times \text{LPF}) \\ &= (3.2 \times 10^5 \text{ Ci } ^{137}\text{Cs})(1.0 \times 10^{-4}) \\ &= 3.2 \times 10^1 \text{ Ci } ^{137}\text{Cs} \end{aligned}$$

Unmitigated dose consequences.

From Section 4.2.1, the dose is determined by:

$$\text{Dose} = (\text{ST})(\text{Inhalation DCF for } ^{137}\text{Cs})(\chi/Q')(BR)$$

The onsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (3.2 \times 10^1 \text{ Ci}) \left(3.19 \times 10^4 \frac{\text{rem}}{\text{Ci}} \right) \\ &\quad \left(3.41 \times 10^{-2} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 1.2 \times 10^1 \text{ rem EDE onsite}$$

The near river radiological dose consequence is determined as follows:

$$\text{Dose (rem)} = (3.2 \times 10^1 \text{ Ci}) \left(3.19 \times 10^4 \frac{\text{rem}}{\text{Ci}} \right) \\ \left(1.96 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right)$$

$$\text{Dose (rem)} = 6.6 \times 10^{-3} \text{ rem EDE near river}$$

The offsite radiological dose consequence is determined as follows:

$$\text{Dose (rem)} = (3.2 \times 10^1 \text{ Ci}) \left(3.19 \times 10^4 \frac{\text{rem}}{\text{Ci}} \right) \\ \left(1.32 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right)$$

$$\text{Dose (rem)} = 4.5 \times 10^{-3} \text{ rem EDE offsite}$$

Comparison with equipment design guidelines. As shown in Table 4-6, the unmitigated onsite dose consequence resulting from a Cs canister drop accident exceeds the guideline.

Table 4-6. Cs Canister Drop Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|-----------------------------|---------------------------------------|
| Onsite | 1.2 E+01 | 5.0 E+00 |
| Near river | 6.6 E-03 | 5.0 E-01 |
| Offsite | 4.5 E-03 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. The same design and control considerations presented in Section 4.2.7.1 apply to this scenario. In this scenario, a second impact absorber is needed if canister inventories are such that two canisters are to be stored in one tube. See Table 4-7 for a summary of the potential safety SSCs for prevention and mitigation of the canister drop accidents.

Table 4-7. Potential Safety SSCs for Canister Drop Accidents
(Bin 3 in Table 4-1).

| ID | Title | Safety Functions | Potential Safety SSCs for Prevention or Mitigation of Accident Consequences | Safety Classification |
|---------|----------------------------|---|---|-------------------------|
| M-21 | Single Glass Canister Drop | 1) Mitigation of Drop 2) Prevention of Drop 3) Containment of Release | 1) Impact absorber 2) Grapple and lifting device that prevents a canister drop * 3) MHM-tube seal, storage tube * | Safety Significant (SS) |
| M-23 | Multiple Canister Drop | Same as M-21 | Same as M-21 | SS |
| M-24 | Cs Canister Drop | Same as M-21 | Same as M-21 | SS |
| M-07 | MHM Canister Drop | Same as M-21 | Same as M-21 | SS |
| M-08/29 | Canister Drop (Seismic) | Same as M-21 | Same as M-21 | SS |

* Alternate options for consideration as preventive or mitigative equipment

4.2.7.4 Transport Cask with Canister Drop Accident. The glass and Cs canisters will be transported to the CSB in an onsite transportation cask via a diesel truck. The truck vestibule is an extension of the CSB that provides a transition area for the receiving crane to unload the cask from the trailer, transport it through the airlock and lower it into the receiving pit. Dropping a cask with a canister from the crane into an empty pit is an operational accident that could be caused by human error or equipment failure.

Scenario and key assumptions. A release is postulated to occur as the result of dropping a cask containing a canister during a transfer to the receiving pit. A crane failure or human error during raising or lowering operations could result in dropping the cask.

Facility personnel in the vicinity of the accident would be aware immediately of the event upon occurrence and could initiate emergency response actions; however, for this scenario, it is assumed that no response or recovery action occurs.

For the postulated drop heights, the consequences of a dropped glass canister (Table 4-4) are higher than the consequences of a dropped Cs canister (Table 4-6). Therefore, the consequences of dropping a transport cask are evaluated assuming the canister in the transport cask is a glass canister, which bounds the scenario where a Cs canister might be involved.

Source Term Analysis. Information and assumptions used to determine the amount of material released are as follows:

- For this scenario, the dropped cask and canister are assumed to rupture or open when the cask impacts the bottom of the pit, releasing airborne particulate from the shattered glass within.
- For the drop of a cask with a canister into the pit, the height of the drop is the depth of the pit (5.0 m), plus the trailer height above the floor (1.0 m), plus the assumed lift height above the trailer before it is lowered (1.0 m), for a total of 7.0 m.
- It is assumed that the cask containment is breached such that the release from the canister enters the CSB area.

From Section 4.2.2, the respirable release fraction is determined by:

$$ARF \times RF = (A)(P)(g)(h)$$

The height of the drop is 7.0 m. The density of the vitrified waste is 2.64 g/cm^3 . The respirable release fraction is therefore:

$$\begin{aligned} ARF \times RF &= (2.0 \times 10^{-11} \text{ cm-s}^2/\text{g})(2.64 \text{ g/cm}^3)(980 \text{ cm/s}^2)(7.0 \times 10^2 \text{ cm}) \\ &= 3.6 \times 10^{-5} \end{aligned}$$

Since shipping casks are qualified to withstand transportation accidents, it is expected that (a) catastrophic failure of the cask would not occur, and (b) very little damage would occur to a dropped cask. As such, application of an LPF of 0.1 for the cask, in addition to an LPF of 0.1 for the canister as discussed in Section 4.2.2, appears to be appropriate. With consideration of these leak path factors, the total respirable release fraction is:

$$\begin{aligned} (ARF \times RF)(LPF) &= (3.6 \times 10^{-5})(0.1)(0.1) \\ &= 3.6 \times 10^{-7} \end{aligned}$$

Since a canister can contain up to 3,060 kg of glass (the MAR), the total respirable release (source term) is:

$$\begin{aligned} ST &= (MAR)(ARF \times RF \times LPF) \\ &= (3.060 \times 10^3 \text{ kg})(3.6 \times 10^{-7}) \\ &= 1.10 \times 10^{-3} \text{ kg} \end{aligned}$$

Unmitigated dose consequences.

From Section 4.2.1, the dose is determined by:

$$\text{Dose} = (\text{ST})(\Sigma\text{MDF})(\chi/Q')(BR)$$

The onsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (1.10 \times 10^{-3} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(3.41 \times 10^{-2} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 4.1 \times 10^0 \text{ rem EDE onsite}$$

The near river radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (1.10 \times 10^{-3} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(1.96 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 2.4 \times 10^{-3} \text{ rem EDE near river}$$

The offsite radiological dose consequence is determined as follows:

$$\begin{aligned} \text{Dose (rem)} &= (1.10 \times 10^{-3} \text{ kg}) \left(3.34 \times 10^8 \frac{\text{rem}}{\text{kg}} \right) \\ &\quad \left(1.32 \times 10^{-5} \frac{\text{s}}{\text{m}^3} \right) \left(3.3 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \right) \end{aligned}$$

$$\text{Dose (rem)} = 1.6 \times 10^{-3} \text{ rem EDE offsite}$$

Comparison with equipment design guidelines. As shown in Table 4-8, the unmitigated dose consequences resulting from a drop of a transport cask with a canister do not exceed the guidelines.

Table 4-8. Transport Cask with Canister Drop Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 4.1 E+00 | 5.0 E+00 |
| Near river | 2.4 E-03 | 5.0 E-01 |
| Offsite | 1.6 E-03 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. The results of the unprevented and unmitigated accident analysis show that the consequences of a cask drop are within the guidelines from Section 4.2.6. However the onsite consequence is sufficiently close to its guideline that preventive or mitigative Safety Significant SSCs should be considered. The cask will be required to withstand transportation accidents and as such may meet the Safety Significant requirements to withstand a drop into the receiving pit. The cask design will be assessed in the Safety Analysis Report for Packaging (SARP) and will be considered for mitigation of the drop accident in future safety analysis. Alternate options for consideration would be to designate the cask handling equipment as Safety Significant.

4.2.7.5 Seismic Induced Glass Canister Shear Accident. It is postulated that an MHM could be moved laterally while lowering or raising a glass canister into or out of a storage tube.

Scenario and key assumptions. A release is postulated to occur as the result of an earthquake moving the MHM such that it shears a canister during a transfer from the MHM to a storage tube. Lateral movement of the MHM during raising or lowering operations could result in shearing a glass canister with the damaged canister falling into a tube.

Analysis of this accident is identical to the analysis of glass canister drop in Section 4.2.7.1 with the exception that no LPF would be applied. The reason for this is that if the canister were sheared in two, the damage to the canister shell would be much greater than for the canister drop and would provide a more open path for release from the damaged glass, possibly with large surfaces of glass exposed.

Source term analysis. In Section 4.2.7.1, the total respirable release fraction of 6.6×10^{-6} was based on an LPF of 0.1. Since the LPF is not applicable in this case, the total respirable release fraction would be 6.6×10^{-5} , and the dose consequences obtained in Section 4.2.7.1 would be increased by a factor of 10.

Unmitigated dose consequences. Dose consequences resulting from a glass canister shear accident resulting from a seismic event are shown in Table 4-9.

Comparison with equipment design guidelines. As shown in Table 4-9, the unmitigated onsite dose consequence resulting from a seismic induced canister shear accident exceeds its guideline, the dose at the near river bank consequence is at its guideline, and the offsite dose consequence is very close to its guideline.

Table 4-9. Seismic Induced Glass Canister Shear Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 8.6 E+02 | 5.0 E+00 |
| Near river | 5.0 E-01 | 5.0 E-01 |
| Offsite | 3.3 E-01 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. If this accident is not mitigated or prevented by designed safety features, the radiological dose consequences exceed the Safety Significant guideline and are at or very close to the Safety Class guideline. (The guidelines are addressed in Section 4.2.6.) If this scenario remains credible in subsequent analyses, SSCs relevant to this scenario might have to be designated as Safety Class.

For accidents involving shearing a container, the preventive equipment could be MHM brakes and a lateral restraint. See Table 4-12 (Section 4.2.7.7) for a summary of potential safety SSCs associated with canister shear events.

4.2.7.6 Seismic Induced Cs Canister Shear Accident. It is postulated that an MHM could be moved laterally while lowering or raising a Cs canister into or out of a storage tube.

Scenario and key assumptions. A release is postulated to occur as the result of an earthquake moving the MHM such that it shears a Cs canister during a transfer from the MHM to a storage tube. Lateral movement of the MHM during raising or lowering operations could result in the shearing of a Cs canister with the damaged canister falling into a tube.

Analysis of this accident is identical to the analysis of a Cs canister drop in Section 4.2.7.3 with the exception that no LPF would be applied. The reason for this is that if the canister were sheared in two, the damage to the canister shell would be much greater than for the canister drop. In the drop event, the canister would remain mostly intact with a rupture opening along either the top or bottom welded seams. This rupture would be the leak path for material to exit from the canister. In the shear event, the canister could possibly end up in two separate parts allowing all of the Cs to be released.

Source term analysis. In Section 4.2.7.3, the total respirable release fraction of 1.0×10^{-4} was based on an LPF of 0.1. Since the LPF is not applicable in this case, the total respirable release fraction would be 1.0×10^{-3} , and the dose consequences obtained in Section 4.2.7.3 would be increased by a factor of 10.

Unmitigated dose consequences. Dose consequences resulting from a Cs canister shear accident resulting from a seismic event are shown in Table 4-10.

Comparison with equipment design guidelines. As shown in Table 4-10, the unmitigated onsite dose consequence resulting from a seismic induced Cs canister shear accident exceeds the onsite guideline.

Table 4-10. Seismic Induced Cs Canister Shear Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment Design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 1.2 E+02 | 5.0 E+00 |
| Near river | 6.6 E-02 | 5.0 E-01 |
| Offsite | 4.5 E-02 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. If this accident is not mitigated or prevented by designed safety features, the onsite radiological dose consequence exceeds the Safety Significant guideline from Section 4.2.6. If this scenario remains credible in subsequent analyses, SSCs might require designation as Safety Significant because of the onsite consequence.

For accidents involving shearing a Cs canister, the preventive equipment could be MHM brakes and a lateral restraint. See Table 4-12 (Section 4.2.7.7) for a summary of potential safety SSCs associated with canister shear events.

4.2.7.7 Truck Impact with MHM Causing Canister Shear. It is postulated that an MHM could be moved laterally while lowering or raising a canister into or out of a cask.

Scenario and key assumptions. A release is postulated to occur as the result of the shear of a container during a transfer from the cask in the pit to the MHM, initiated by a truck backing into the MHM. Lateral movement of the MHM during raising or lowering operations could result in the shearing of a canister with the damaged canister falling into a tube.

Source term analysis. Analysis of this accident is similar to the analyses of the seismically induced glass and Cs canister shear events in Sections 4.2.7.5 and 4.2.7.6. For this accident, the initiating event is a

truck backing into the MHM while at the receiving pit. As such, the preventative or mitigative SSCs will be different than those identified in Sections 4.2.7.5 and 4.2.7.6. The source term is assumed to be the same as for the seismically induced canister shear.

Unmitigated dose consequences. The consequences of a seismically induced glass canister shear (Table 4-9) are higher than the consequences of a seismically induced Cs canister shear (Table 4-10). Therefore, the consequences of a shear event caused by a truck impact to the MHM are evaluated assuming the involved canister is a glass canister, which bounds the scenarios in which a Cs canister might be involved. Dose consequences resulting from a glass canister shear accident resulting from a truck impact are shown in Table 4-11.

Comparison with equipment design guidelines. As shown in Table 4-11, the unmitigated onsite dose consequence resulting from a truck impact induced canister shear accident exceeds its guidelines, the near river bank consequence is at its guideline, and the offsite consequence comes close to its guideline.

Table 4-11. Truck Impact Induced Canister Shear Accident.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 8.6 E+02 | 5.0 E+00 |
| Near river | 5.0 E-01 | 5.0 E-01 |
| Offsite | 3.3 E-01 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of Potential equipment design requirements. If this accident is not mitigated or prevented by designed safety features, the radiological dose consequences exceed the Safety Significant guideline and are at or very close to the Safety Class guideline. (The guidelines are addressed in Section 4.2.6.) If this scenario remains credible in subsequent analyses, SSCs relevant to this scenario might require designation as Safety Class.

For accidents involving shearing a container that results from a truck impact, the preventive equipment could be a barrier to prevent the truck from backing into the MHM. See Table 4-12 for a summary of the potential safety SSCs associated with canister shear/pinch accidents.

Table 4-12. Potential Safety SSCs Associated with Canister Shear/Pinch Accidents (Hazard Bin 4 in Table 4-1).

| ID | Title | Safety Functions | Potential Safety SSCs for Prevention or Mitigation of Accident | Safety Classification |
|---------|--------------------------------|---------------------------|--|-----------------------|
| M-09/30 | Seismic Canister Shear (Glass) | Prevention of shear/pinch | MHM brake/restraint | Safety Class (SC) |
| M-09/30 | Seismic Canister Shear (Cs) | Same as M-09/30 | Same as M-09/30 | SC |
| D-03 | Truck-Induced Impact with MHM | Prevention of shear/pinch | Truck barriers | SC |
| M-10 | MHM Canister Pinch | Same as M-09/30 | Same as M-09/30 | SC |
| M-25 | MHM Canister Pinch | Same as M-09/30 | Same as M-09/30 | SC |

4.2.7.8 Seismic Event Causing Tube Failure. It is postulated that an earthquake could dislodge storage tubes from their fixtures to the vault ceiling, causing them to fall and damage the canisters inside of them.

Scenario and key assumptions. A release is postulated to occur as the result of damage to canisters in storage tubes which fall as the result of an earthquake. Dislodged tubes could result in impact damage to the glass canisters (two per tube) in the tubes.

Source term analysis. Analysis of this accident will utilize the analysis of the multiple glass canister drop in Section 4.2.7.2, because that accident involved the maximum number of canisters in each tube and bounds the same scenario involving Cs canisters.

Unmitigated dose consequences. The dose consequences of the multiple glass canister drop accident are given in Table 4-5. Multiplying these consequences by the total number of tubes in Vaults 2 and 3 (452 tubes from Section 3.3) gives the consequences resulting from a seismic accident involving failure of all 452 tubes in the vaults (see Table 4-13).

Comparison with equipment design guidelines. As shown in Table 4-13, the unmitigated onsite and offsite dose consequences resulting from an earthquake exceed the guidelines.

Table 4-13. Seismic Event Causing Tube Failure.

| Receptor location | Dose consequence (EDE, rem) | Equipment design guideline (EDE, rem) |
|-------------------|--------------------------------|--|
| Onsite | 5.4 E+04 | 5.0 E+00 |
| Near river | 3.0 E+01 | 5.0 E-01 |
| Offsite | 2.0 E+01 | 5.0 E-01 |

EDE = effective dose equivalent.

Summary of potential equipment design requirements. If this accident is not mitigated or prevented by designed safety features, the radiological dose consequences exceed the Safety Significant and Safety Class guidelines from Section 4.2.6. If this scenario remains credible in subsequent analyses, SSCs relevant to this scenario might require designation as Safety Class because of the offsite consequence.

For accidents involving an earthquake, the preventive equipment could be seismically qualified tubes and operating deck. SSCs whose failure could result in damage to the operating deck and storage tubes must also be designed for natural phenomena events (e.g., vault ventilation inlet/outlet structures, and the CSB roof).

Table 4-14 summarizes the potential safety SSCs associated with this seismic event and other natural phenomena events.

Table 4-14. Potential Safety SSCs Associated with Natural Phenomena (Hazard Bin 7 in Table 4-1).

| ID | Title | Safety Functions | Potential SSCs for Prevention or Mitigation of Accident | Safety Classification |
|------|--------------------------------|----------------------------------|--|--------------------------|
| M-28 | Earthquake Fails Tubes | Prevention of structural failure | Storage tubes | Safety Class (SC) |
| M-29 | Earthquake Fails Structure | Same as M-28 | Operating deck Cooling inlets and outlets | SC SC |
| D-06 | High Wind, Ash, & Snow Loading | Same as M-28 | Roof | SC |

4.2.7.9 Loss of Cooling Accident. Decay heat from the glass and Cs canisters will normally be removed by natural convection. Cooling air is drawn through

an inlet duct into a plenum that distributes it into the vault, flows across the tubes, and exits through an exhaust stack. The motive force for drawing cooling air through the vault is natural convection caused by a density difference between hot air inside the vault and stack, relative to cool intake air (WHC 1996a).

Scenario and key assumptions. Debris from high winds, snow, frost, or ashfall accumulations could plug the inlet or outlet to the vault cooling plenums. An external fire could impact natural circulation cooling. The canisters would begin to heat up and may reach temperatures at which the contents degenerate.

Source term analysis. No source term analysis was performed because the CDR does not contain the detail needed to do so for a loss of cooling event. This accident is identified as an item requiring further resolution in Section 8.0.

Unmitigated dose consequences. No accident consequences were developed because the CDR does not contain the detail needed to do so for a loss of cooling event. A separate analysis for a loss of cooling event is being performed and will be available for inclusion in the more detailed safety analyses to follow this PSE.

Summary of potential equipment design requirements. The cooling inlets and outlets might become Safety Class SSCs based on Table 4-14 to protect against a catastrophic failure (e.g., a seismic event that might cause structural failure of the inlets or outlets such that other facility damage could occur). The cooling inlets and outlets might also require designation as Safety Class or Safety Significant to maintain vault cooling in the event of an accident or natural phenomena.

4.2.8 Nuclear Criticality

The IHLW-ISF can contain more than 3% of a minimum critical mass. HNF-PRO-334 is applicable and a criticality safety evaluation will be performed. It will be specified in the contract with the glass vendor that the canisters to be received at the CSB shall be capable of being (a) handled inside casks, (b) handled with the MHM, and (c) stored in the tubes without any additional controls for criticality.

5.0 CONSTRUCTION RISKS

This section addresses the potential risks arising from construction activities associated with Project W-464. These risks include those associated with construction activity hazards, the radiation from the SNF stored canisters during construction, and the fire risk from the storage of construction combustibles on the operating deck area and near the CSB.

The nearest adjacent facility is an underground crib, approximately 150 m northeast of the CSB, that is no longer in use. Another adjacent facility is B Plant whose closest part is located approximately 455 m directly east of the CSB. The 2704HV Building is located approximately 200 m north. These neighboring facilities are far enough away that construction activities should not have any interaction with them.

Any excavation work will be controlled by existing programs and will be unlikely to affect adjacent facilities by interruptions of utilities. The details involved with the handling of storage tubes outside of the building are not available but will probably involve the use of large cranes. The storage tubes will enter the building at the south end of the CSB (opposite end from the stored SNF). The tubes will be moved to their permanent position by a transport vehicle, up-ended, and lowered into the vault. Work in the vault will be limited to aligning the tubes and welding them to the tube base assembly (embedded in the vault floor). Since there will be no lifting or transporting of equipment or materials over Vault 1, the risk to the stored SNF is minimal.

During construction, provisions will be made to protect the workers from the existing stored radioactive SNF canisters in the CSB in compliance with ALARA principles. Adequate shielding in the walls is present to protect the workers by limiting the radiation dose in Vaults 2 and 3 to 0.5 mrem/hr. A security fence (probably chain link) is planned to be installed across the operating deck separating Vault 1 from the construction activities. Storage of construction materials on the operating deck area and near the CSB facility will be limited by reduction of combustibles. The fire hazards related to the storage of construction combustibles will be addressed during definitive design.

Other construction risks to be considered during the definitive design are as follows:

- Welding operations
- Crane operations
- Vehicle operations
- Toxic materials
- Building structure interfaces
- Tripping hazards
- Temporary power distribution
- Ladders and scaffolding use

This page intentionally left blank.

6.0 SAFETY DOCUMENTATION

As discussed throughout this PSE and its associated CDR, Project W-464 provides for the IHLW and Cs canisters produced in privately owned facilities to be built and operated on the Hanford Site. Project W-464 is part of the TWRS Project and is being carried out by the Project Hanford Management Contract subcontractor for the TWRS Project. Therefore, the TWRS Project has responsibility for ensuring that safety is properly addressed in the design and planned operations of the IHLW interim storage facility. The TWRS Project also has the responsibility to develop and obtain DOE approval for the nuclear safety Authorization Basis to operate this facility. The PSE is the first formal step in the process to fulfill these two responsibilities.

The CSB, which will be modified by TWRS Project W-464, is a new facility built by the SNF Project. Ultimately, a portion of the facility (Vault 1) will contain nuclear materials which are part of the SNF Project while another portion of the facility (Vaults 2 and 3) will contain the IHLW from the TWRS Project. Because the building is new and does not yet contain any nuclear materials, the SNF Project is on its own path to seek and obtain a nuclear safety Authorization Basis for the full building, and for Vault 1 operations in particular. The SNF Project is not seeking DOE approval for any activities associated with the interim storage of TWRS IHLW in the CSB. This is solely the responsibility of the TWRS Project; although, the sub-contractors for each project and the integrating contractor for the Hanford Project are coordinating both project efforts. The performance of a formal review of this PSE by SNF Project personnel is an important example of the inter-project coordination.

The TWRS Project is following the standard process for new nuclear facilities to establish the safety documentation for the W-464 Project. As a nuclear facility proceeds through the design stages and into operation, DOE requirements stipulate the need for safety documentation addressing the adequacy of the design and operations. The application of these requirements to Project W-464 is as follows:

- (1) The PSE is the first safety document in the project life cycle. For Project W-464, the PSE is an appendix to the project CDR and is the first formal safety analysis input to project design. The PSE serves primarily to establish a preliminary Hazard Categorization, provide a preliminary identification of Safety Class and Safety Significant SSCs, and to identify major safety concerns and issues. This PSE establishes the TWRS Project portion of the CSB to be a Hazard Category 2 facility. The CSB was previously determined to be a Hazard Category 2 facility for the storage of spent nuclear fuel. For a Hazard Category 2 facility, the applicable nuclear safety Authorization Basis documentation requirements are those found in DOE Orders 5480.21, 5480.22 and 5480.23. The PSE is not a nuclear safety Authorization Basis document.
- (2) The PSE will be followed by a Preliminary Safety Analysis Report (PSAR). The PSAR serves as input to project definitive design and must be

approved by DOE prior to the start of construction. The PSAR documents the detailed analysis of the project definitive design, identifies the safety classification of SSCs, evaluates adequacy of the design for safety considerations, and identifies technical issues requiring further analysis and resolution in a Final Safety Analysis Report (FSAR). No operations or activities involving nuclear materials are authorized by the PSAR. The PSAR is not a nuclear safety Authorization Basis document.

- (3) An FSAR is a nuclear safety Authorization Basis document. Consistent with the definitions in DOE Order 5480.23, approval of an FSAR provides authorization to conduct operations in a nuclear facility. A special consideration for Project W-464 is the dual mission of the CSB to serve both the SNF and TWRS Projects. This consideration has been factored into the overall regulatory strategy for Project W-464 by the plan to amend the CSB FSAR developed for the spent nuclear fuel storage mission as opposed to providing a stand-alone CSB FSAR for TWRS-related operations. This decision has been made in anticipation of having a single operations organization for all activities in the CSB. Having a single nuclear safety Authorization Basis document for the CSB is considered to be beneficial from the standpoints of Conduct of Operations and successfully achieving regulatory approval.

The approved CSB FSAR for spent nuclear fuel storage will allow the SNF Project to use Vault 1. All Project W-464 construction activities in the CSB will have to be screened against the approved CSB FSAR as part of the Unreviewed Safety Question (USQ) process. Subsequent approval of the TWRS amendment to the CSB FSAR will allow concurrent operation of the CSB in support of the SNF and TWRS missions. Once the CSB FSAR, amended to address both the SNF and TWRS missions, has been approved by DOE, all physical and operational changes involving any part of the CSB, must be evaluated in accordance with the USQ process requirements of DOE Order 5480.21.

In addition to the operations to take place within the CSB, the TWRS Project must account for the transport of the IHLW and Cs canisters from the private vitrification facilities to the CSB. Safety considerations for the transport of the IHLW and Cs canisters will be addressed in one or more SARPs. The TWRS Project subcontractor will establish the interface with the Project Hanford Management Contract subcontractor responsible for Hanford Site transportation and packaging, for the preparation of the SARP.

7.0 PROJECT INTERFACES

The IHLW-ISF will provide the capability to: (1) receive IHLW and Cs canisters in transportation containers at the CSB, (2) load and unload a waste canister from its transportation cask, (3) handle IHLW and Cs canisters for placement and retrieval within the CSB storage area, (4) provide space suitable for storing the IHLW canisters safely, (5) survey the integrity of the IHLW and Cs canisters in storage, and (6) retrieve and place IHLW and Cs canisters into transportation containers for transport from the CSB.

The primary interfaces associated with the intended function of the IHLW storage system are components and operations associated with the existing CSB. The existing CSB components include the above ground building structure, the service building, the receiving crane, the receiving pit, the operating deck, and the MHM. Interfaces between the IHLW storage facility and the private contractor facilities that prepare the IHLW for storage are beyond the scope of this PSE, and will be managed through Interface Control Documents.

Potential hazards to the safe operation of the CSB from adjacent facilities or activities in nearby facilities are covered in the CSB SAR (HNF 1997c). Risks associated with adjacent facilities during the construction phase of Project W-464 are addressed in Chapter 5.

This page intentionally left blank.

8.0 ITEMS REQUIRING FURTHER RESOLUTION

As discussed in the Foreword to this PSE, a design change occurred close to the completion of the CDR. This change introduced the use of an SCT in place of the MHM for the handling of the IHLW and Cs canisters in Vault 2 and 3. Section 8.1 documents the items requiring further resolution for the IHLW-ISF design assuming use of the MHM. Section 8.2 documents the additional items requiring further resolution assuming the use of an SCT.

8.1 PROJECT DESIGN ASSUMING MHM

Details of the storage system design and process will be required to strengthen the conclusion of this PSE. However, conservative assumptions were used to the extent possible to assure a bounding analysis. Preventive and mitigative features (Safety Class and Safety Significant) are deemed necessary. However, as the design becomes more firmly established, some conservatisms may be removed. Design and operational considerations which must be further addressed include:

Design Considerations

- The waste packaging process must ensure that no water is present inside the IHLW or Cs canisters when received at the CSB.
- Design provisions for the CSB must be adequate to preclude the entrance of water into the storage tubes.
- The design must provide adequate shielding for worker safety as discussed in Section 4.1.2.3.
- The update of the Fire Hazards Analysis may result in additional fire protection requirements.
- The consequences of a loss of cooling accident need to be determined to show that the maximum temperatures reached in the tubes will not result in unsafe conditions.
- The seismic design of the MHM brake/restraint must be qualified for the new MHM loadings.
- The LPFs for the canister and for the cask after the drop accidents need to be validated.
- Criticality must be addressed in a criticality analysis to establish any associated design and storage requirements.
- The radiological inventory of non-routine canisters must be verified to be bounded by the inventory established for the canisters containing the glass.

- The ARF and RF for the Cs product must be verified to be within the assumptions in the accident analyses.

Operational Considerations

- The facility operations must provide for the receipt of the transportation casks. The placement of the canisters in their designated interim storage locations, and retrieval of the canisters from storage (HNF 1997c).
- The normal operations at the CSB must include safely monitoring and controlling the equipment for the IHLW movement, placement in tubes, control of storage environment, and canister retrieval.
- Controls must be established to maintain the maximum canister radiological inventory within the limits established in Section 3.1.

The path forward for these considerations is to continue the design process as scheduled. The ongoing safety documentation process will incorporate information as it becomes available during detailed design. Based on the results of this PSE, it is judged that Safety Class and Safety Significant SSCs and TSRs can be developed to ensure that the IHLW and Cs canisters can be safely stored within the CSB vaults.

8.2 PROJECT DESIGN ASSUMING SCT

For the design assuming use of the SCT, the operations associated with the receipt and unloading of the cask and the transport of the canisters will be similar to those identified in the current PHA. The operating sequence block diagram will be updated to identify operational steps associated with the design changes. The block diagram and design information for the receiving pit, receiving crane and SCT will provide the basis for revising the PHA. The PHA will provide a systematic evaluation of any new hazards or hazards where consequences may be different than previously considered. The hazards and accident scenarios identified in Section 4.0 are expected to be typical for the revised operating sequence. As such, the safety functions required for the prevention and mitigation of potential accident consequences in Section 4.0 will need to be considered during the design development. Safety considerations which will need to be addressed include:

- The Fire Hazards Analysis may result in additional fire protection requirements to accommodate SCT operations. The combustible loading needs to be minimized to preclude the need for automatic fire suppression in the CSB. Use of water for fire protection in the CSB could result in additional hazards not currently addressed in the CSB SAR (HNF 1997c) or in this PSE.

- The design needs to provide features to prevent the shear of an IHLW or Cs canister during transfer by the SCT as a result of natural phenomena or due to impacts by the cask transporter truck or the MHM.
- The design needs to provide features to prevent the shear of the MCO containing spent nuclear fuel due to impact of the SCT on the MHM.
- Design analysis is needed to ensure that the safety functions of SSCs qualified for the natural phenomena (i.e., seismic loads) are not compromised by loads imposed by the SCT.
- The design needs to address the potential for a spill of fuel or hydraulic fluid from the SCT and the potential for hydrogen generation if the fluid gets into the storage tubes.
- The design requirements for the cask or the canister may need to be revised to account for changes in the potential drop height while being handled in the CSB.

This page intentionally left blank.

9.0 REFERENCES

- 10 CFR Part 835, "Occupational Radiation Protection", *Code of Federal Regulations*, as amended
- 29 CFR 1910, Occupational Safety and Health Standards", *Code of Federal Regulations*
- DOE-HDBK-3010-94, *Airborne Release Fractions/Rates, and Respirable Fractions for Nonreactor Nuclear Facilities*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5400.5, *Radiation Protection of Public and Environment*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.4, *Environmental Protection, Safety, and Health Protection Standards*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.7A, *Fire Protection*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.21, *Unreviewed Safety Questions*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.22, *Technical Safety Requirements*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.23, *Nuclear Safety Analysis Reports*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.24, *Nuclear Criticality Safety*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5480.28, *Natural Phenomena Hazards*, U.S. Department of Energy, Washington, D.C.
- DOE Order 5820.2A, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C.
- DOE Order 6430.1A, *General Design Criteria*, U.S. Department of Energy, Washington, D.C.
- DOE-STD-1027-92, *Hazard Categorization and Accident Analysis Techniques for Compliance with DOE Order 5480.23, Nuclear Safety Analysis Reports*, U.S. Department of Energy, Washington, D.C.
- DOE-STD-3009-94, *Preparation Guide for U.S. Department of Energy Nonreactor Nuclear Facility Safety Analysis Reports*, U.S. Department of Energy, Washington, D.C.

- EPA, 1988, *Limiting Values of Radionuclide Intake and Air Concentration and Waste package dose factors for Inhalation, Submersion, and Ingestion*, EPA-520/1-88-020, Office of Radiation Programs, United States Environmental Protection Agency, Washington, D.C.
- HNF, 1997a, *Final Safety Analysis Report (FSAR) For Waste Receiving and Processing Facility (WRAP) Facility*, HNF-SD-W026-SAR-002, Rev. 0, Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF, 1997b, *Phase 2 Fire Hazard Analysis for the Canister Storage Building*, HNF-SD-SNF-FHA-002, Rev. 2, (currently at DOE for approval) Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF, 1997c, *Canister Storage Building (CSB) Safety Analysis Report Phase 3: Safety Analysis Documentation Supporting CSB Construction*, HNF-SD-SNF-RPT-004, Rev. 7, Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF, 1997d, *Tank Waste Remediation System Basis for Interim Operation*, HNF-SD-WM-BIO-001, Rev. 0-H, Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-PRO-703, *Safety Analysis Process - New Projects*, Rev. 0, Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-PRO-704, *Hazards and Accident Analysis Process*, Rev. 0, Fluor Daniel Hanford, Inc., Richland, Washington.
- IEEE Std 500-1984, *IEEE Guide to the Collection and Presentation of Electrical, Electronic, Sensing Component, and Mechanical Equipment Reliability Data For Nuclear Power Generating Stations*, The Institute of Electrical and Electronic Engineers, Inc., New York, New York.
- ICRP, 1975, *ICRP Publication 23, Report on the Task Group on Reference Man*, International Commission on Radiological Protection (ICRP). Pergamon Press, New York.
- PNNL, 1981, *Aerosols Generated by Free Fall Spills of Powders and Solutions in Static Air (UO_2 and TiO_2)*, CR2139.
- WHC, 1996a, *Design Requirements Document for the Interim Store Phase I Solidified High Level Waste*, WHC-SD-WM-DRD-012, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1996b, *Canister Storage Building Evaluation of Nuclear Safety for Solidified High-Level Waste Transfer and Storage*, WHC-SD-WM-TI-781, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

ATTACHMENT A

PRELIMINARY HAZARDS ANALYSIS TABLE

The PHA was performed by personnel with experience in safety analysis methodology and personnel with knowledge of the IHLW-ISF design. The following personnel were involved:

| | |
|--------------------|---|
| Donald R. Porten | Safety Analysis and Risk Assessment, Fluor Daniel Northwest, Inc. |
| Milton V. Shultz | Safety Analysis and Risk Assessment, Fluor Daniel Northwest, Inc. |
| Kenneth C. Burgard | Project W-464 Manager, Lockheed Martin Hanford Corporation |
| Ronald B. Calmus | CSB Engineering, SGN Eurisys Services Corporation |
| Pascal J. Mouette | Licensing Engineer, Numatec Hanford Corporation |
| Chris A. Petersen | Design Authority, Numatec Hanford Corporation |
| Dean A. Smith | Safety Analysis Support, Fluor Daniel Northwest, Inc. |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------|--|--|-------------------------|---|--|--|---|--|-------------|----------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 1) D-01 | Back Cask Transporter Into Facility and Remove Tractor | Kinetic Linear Energy | Impact on Door/Bldg. | Human Error | Damage Transporter or Damage Inner or Outer Door Possible injury to worker | Process upset | None | None | S1 | F3 | Possible Industrial Accident S1 based on possible injury to worker S0 for process upset |
| D-02 | | | | Human Failure (Heart Attack or Seizure) | Sudden uncontrolled acceleration of truck | Loss of controlled barrier (The Building) Possible injury to worker | Cask design for transport over normal highways and associated accidents | None | S1 | F3 | S1 based on possible injury to worker S0 for loss of control barrier |
| D-03 | | | | Human Failure | Trailer backs into MHM | Damage to the MHM and Possible damage to canister being handled by MHM (shear of canister) | None | MHM not in use during trailer movement | S3 | F3 | Cs Canister may have higher consequence than Glass canister Cs Will be nonexplosive, nonpyrophoric, nonreactive with canister interior |
| D-04 | | Flammable Liquids Fuel | Fire | Human error or random event | Truck fuel fire while in entry area | No cask damage Degraded product for future disposal (degradation addressed in cask design) | Cask design (Cask is qualified by SARP to withstand fire) | 40 gal. Fuel Limit Remove tractor before outer door closed and cask moved to receiving pit | S0 | F3 | Existing RHA for CSB says no structural damage from 100 gal. fire S0 is related to cask design (taking credits for existing passive barrier) Cask is qualified for fire hazards. |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Module/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------------------|---|---|----------------------------------|-------------------------------------|---|----------------------------------|--|---|-------------|----------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| D-05 | | External Events Vehicles in motion | Airplane/ Helicopter Event | Human error or equipment failure | Aircraft strikes building | Building damage possible fire | N/A | N/A | S3 | F0 | Analysis indicates that this event is Beyond Extremely Unlikely (Referenced in Spent Fuel SAR) S3 Engineering estimates of Hazards Team |
| (Block 1 continued) D-06 | | Natural Phenomena | Everything but seismic | | | | Facility qualified for "Design Basis" natural phenomena events | N/A | S2 | F2 | Everything but earthquake covered in CSB SAR Earthquake addressed in CSB SAR. Building structure and components designed for DBE |
| (Block 2) D-07 | Retrieve Yoke from rack or floor and connect to cask | Mass Gravity Height | Drop Yoke on cask | Human error or equipment failure | Cask damage Damage to Yoke | Process delay | Cask design (see remarks) and crane design | Operating process training | S0 | F3 | Based on cask design for impact resistance. (Need to verify this to be true) |
| D-08 | | Mass, Gravity, Height, and Kinetic Linear | | | Drop Yoke on person Horizontal or vertical | Facility worker injury | None | Personnel training and operating procedures | S1* | F3 | Industrial safety |
| (Block 3) D-09 | Remove Tiedowns and platforms from Transport Cask | Natural Phenomena | Cask Movement | Seismic | Cask falls | Damage to cask | Cask design | Cask is hooked to crane before the tie downs removed | S0 | F2 | Need to determine G loading at which cask comes off trailer Design requirement Cask/Trailer attachment, adequately designed |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Model/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------|---|--|------------------------|---|--------------------------------------|---------------------------------------|---|---|-------------|---------------------------------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| D-10 | | | | | Crane falls on cask | Damage to cask | Crane designed to withstand DBE. | None | S0 | F2 | Assumes the crane will withstand seismic and not fail on cask or cask can withstand crane fall |
| D-11 | | | | | Crane falls on worker | Facility worker injury | Crane design | None | S1* | F2 | Assumes the crane will withstand seismic |
| (Block 4) D-12 | Lift and move cask | Natural Phenomena Kinetic Linear Mass, Gravity, Height | Cask drop | Seismic Human error or equipment failure Operating control system failure | Cask falls onto floor | Damage to cask Damage to floor | Cask designed to withstand impact | Procedures specify maximum lift height | S0 | F2 | Assumes the floor withstands cask drop |
| | | | | | | | Crane designed to not fall during seismic event | | S0 | F3 | |
| | | | | | | | Floor design | | S0 | F3 | |
| D-13 | | | | | | Facility worker injury | Lift height limited | Lift height limited | S1* | F3 Human event F2 Seismic | |
| D-14 | Lower cask | Mass, Gravity, Height, Natural Phenomena | Cask drop | Human error Equipment failure Operating/control system failure Seismic | Cask falls in pit | Damage to cask Damage to pit | Lift height limited | | S2 | F3 Human event F2 Seismic | |
| (Block 5) D-15 | Remove Yoke from cask or place on floor | Mass, Gravity, Height | Drop Yoke on cask | Human error or equipment failure | Cask damage Damage to Yoke | Process delay | Cask design (see remarks) and crane design | Operating process training | S0 | F3 | Based on cask design for impact resistance. (Need to verify this to be true) |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Model/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-----------------|---------------------------------------|---------------------------------------|------------------------|-------|--|---------------------------|------------------------|--|-------------|----------|-------------------|
| | | | | | | | Engineered Features | Administrative Features | | | |
| D-16 | | | | | Drop Yoke on facility worker Horizontal or vertical | Facility worker injury | None | Personnel training and operating procedures | S1* | F3 | Industrial safety |

| ID (Block #) | Operating Sequence Model/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------|--|---|------------------------|-------------------------------------|--|---|--|---|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 6) D-17 | Remove Cask Lid and Store in Designated Area | Kinetic Linear Mass, Gravity, Height | Cask lid drop | Equipment failure or Human error | Lid drop can damage top of cask contents and could breach container | Release of material from glass log (distribution of particles tends to large particles) | Cask Lid and Cask will be engineered to prevent damage to contents in a drop of the lid | Operating procedures and training | S2 | F3 | Note: Current block diagram doesn't specify how shielding is provided after removal of cask lid. Canister is designed to withstand a certain level of impact (currently unknown) Consequence assigned for screening purposes Consequence need to be evaluated for more detail With this concept, the canister shell (the bottle) is the only confinement |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-----------------|--------------------------------------|--|------------------------------------|--|---|---|---|---|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| D-18 | | Radioactive material | Release of contamination | Contamination release inside cask during loading or shipping | Cask lid removed and contamination released | Contamination release in building | Canister sealing process performed at the vendor | Check of cask atmosphere before removing cask lid By contact, vendor cleaning and cleanliness requirements | S1 | F3 | Open item in ICO's 13, 14, & 17 (Study team recommends system for secondary confinement) |
| D-19 | | Radioactive material | Exposure to direct radiation | Removal sequence for cask shield lid | Worker exposure due to open cask from direct and shine | Large worker exposure | -- | Process sequence needs to be evaluated to provide shielding of all times | S1* | F3 | Shine is significant Project must evaluate this problem and provide the appropriate solution |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------------------|--------------------------------------|--|------------------------------------|---|--|--|--|--|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 6 continued) D-20 | | Explosives/Pyr o- phorics | Presence of hydrogen | Radiolytic decomposition of canister cleaning solution | Ignition of flammable gas upon cask lid removal | Facility worker injury Possible canister damage Possible equipment damage | | Vendor requirements for cleanliness and dryness of cask interior Vendor demonstrates that any H ₂ O remaining in cask cannot generate significant quantities of hydrogen Vendor will not use cleaning solution that represent significant H ₂ sources due to radiolytic decomposition (organics) | S1 | F2 | Team expects that canister will not be damaged This hazard does not address Cs canister flammability issues. It is assumed that the canister will not contain flammable gas. |
| D-21 | | Thermal | High temperature in canister | Long stay or duration in receiving pit | Possible breaching of canister due to high temperature | Radioactive material release | Design will ensure that cooling is sufficient to protect glass/canister integrity | Time limits established for Cask residence time in receiving pit. Recovery actions for equipment failures to prevent overheating | S1 | F2 | Main concern is Cs canister Glass is highly, stable Seismic event applies as an initiator |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------|--|--|------------------------|-------------------------------------|---|--|--|---|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 7) D-22 | Retrieve and Install Shield Hatch Assembly Over Pit | Kinetic-Linear Mass, Gravity, Height | Shield hatch drop | Equipment failure or Human error | Lid drop can damage top of cask contents and breach container | Release of material from glass log (distribution of particles tends to large particles) Release of Cs Ion Exchange Mat'l (distribution of particles tends to much smaller particles) | Cask Lid and Cask will be engineered to prevent damage to contents by a drop of the lid | Operating procedures and training | S2 | F3 | Unclear at this time how the process sequence will appropriately protect workers from unshielded radiation exposure. Project will need to address this. Note: Current block diagram doesn't specify how shielding is provided after removal of cask lid. Canister is designed to withstand a certain level of impact (currently unknown) Consequence assigned for screening purposes Consequence need to be evaluated for more detail With this concept, the canister shell (the bottle) is the only confinement |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Model/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------------------|---------------------------------------|--|------------------------------------|--|--|---|--|--|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| D-23 | | Ionizing radiation sources | Release of contamination | Contamination release inside cask during loading or shipping | Cask lid removed and contamination released | Contamination release in building | Canister sealing process performed at the vendor | Check of cask atmosphere before removing cask lid By contact, vendor cleaning and cleanliness requirements | S1 | F3 | Open item in ICO's 13, 14, & 17 (Study team recommends system for secondary confinement) |
| (Block 7 continued) D-24 | | Ionizing radiation sources | Exposure to direct radiation | Removal sequence for cask shield lid | Worker exposure due to open cask from direct and shine | Large worker exposure | -- | Process sequence needs to be evaluated to provide shielding of all times | S1* | F3 | Shine is significant Project must evaluate this problem and provide the appropriate solution |
| D-25 | | Thermal | High temperature in canister | Long stay or duration in receiving pit | Possible breaching of canister due to high temperature | Radioactive material release | Design will ensure that cooling is sufficient to protect glass/canister integrity | Time limits established for Cask residence time in receiving pit. Recovery actions for equipment failures to prevent overheating | S1 | F2 | Main concern is Cs canister Glass is highly, stable Seismic event applies as an initiator |
| (Block 8) M-01 | Place MHM over pit | Kinetic-Linear | MHM strikes receiving crane | Human error | MHM strikes receiving crane | Process upset | Interlocks to prevent movement when receiving crane in area | Procedures governing crane movement movement | S0 | F3 | Consequences same as Block 4 |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------|---|--|-----------------------------|-------------------------------------|---|---|--|--|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-02 | | Kinetic-Linear | MHM strikes 10 ton crane | Human error | MHM strikes 10 ton crane | Process upset | | Procedures governing crane and MHM movement | S0 | | Consequences same as Block 6 |
| (Block 9) M-03 | Retrieve and -Install Shield Hatch Assembly Over Pit | Kinetic-Linear | Cask lid drop | Equipment failure or Human error | Lid drop can damage top of cask contents and breach container | Release of material from glass log (distribution of particles tends to large particles) | Cask Lid and Cask will be engineered to prevent damage to contents by a drop of the lid | Operating procedures and training | S2 | F3 | Unclear at this time how the process sequence will appropriately protect workers from unshielded radiation exposure. Project will need to address this. Note: Current block diagram doesn't specify how shielding is provided after removal of cask lid. Canister is designed to withstand a certain level of impact (currently unknown) Consequence assigned for screening purposes Consequence need to be evaluated for more detail With this concept, the canister shell (the bottle) is the only confinement |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------------------|--------------------------------------|--|------------------------------------|--|--|---|--|--|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-04 | | Ionizing radiation sources | Release of contamination | Contamination release inside cask during loading or shipping | Cask lid removed and contamination released | Contamination release in building | Canister sealing process performed at the vendor | Check of cask atmosphere before removing cask lid By contact, vendor cleaning and cleanliness requirements | S1 | F3 | Open item in ICO's 13, 14, & 17 (Study team recommends system for secondary confinement) |
| (Block 9 continued) M-05 | | Ionizing radiation sources | Exposure to direct radiation | Removal sequence for cask shield lid | Worker exposure due to open cask from direct and shine | Large worker exposure | -- | Process sequence needs to be evaluated to provide shielding of all times | S1* | F3 | Shine is significant Project must evaluate this problem and provide the appropriate solution |
| M-06 | | Thermal | High temperature in canister | Long stay or duration in receiving pit | Possible breaching of canister due to high temperature | Radioactive material release | Design will ensure that cooling is sufficient to protect glass/canister integrity | Time limits established for Cask residence time in receiving pit. Recovery actions for equipment failures to prevent overheating | S0 | F2 | Main concern is Cs canister Glass is highly, stable Seismic event applies to all blocks as an initiator |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------|--|--|------------------------|--|---|--|--|----------------------------|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 10) M-07 | Place HLW canister into MHM cask | Mass, Gravity, Height | Canister drop | Human error or Equipment failure | Canister drop results in canister damage or breach | Release of material from glass log (distribution of particles tends to large particles) Release of Cs Ion Exchange Mat'l (distribution of particles tends to much smaller particles) | O ring sealed Nose piece. (MHM interface to pit provides confinement) Active ventilation system in MHM Glass canister qualified for 7 meter drop Cs canister may have impact limiters in bottom of cask Design is considering containing Cs canister in modified glass canister | Operating procedures | S3 | F3 | Glass canisters are less prone to significant release as compared to Cs canisters S3 based on Cs canister breach, Cs canister is assumed to not have flammable gas, based on vendor contract. Assumed that possible glass canister drop does not exceed 7 meters maximum Design requirements needs to address catch points for Cs or glass canister drop |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|---------------------------------|--------------------------------------|---|------------------------|---------------|---|--|--|--|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-08 | | Natural Phenomena; Mass, Gravity, Height | Canister drop | Seismic event | Canister drop results in canister damage or breach | Release of material from glass log (distribution of particles tends to large particles) Release of Cs ion Exchange Mat'l (distribution of particles tends to much smaller particles) | For Shear, there is a seismic qualification of .35 g for MHM nose piece to not shear canister | Design is considering containing Cs canister in modified glass canister | S3 | F2 | Design requirements needs to address catch points for Cs or glass canister drop The MHM confinement system may not be qualified for seismic event. |
| (Block 10 continued) M-09 | | Natural Phenomena; Kinetic, Linear | Canister Shear | Seismic event | Canister drop results in canister damage or breach | Release of material from glass log (distribution of particles tends to large particles) Release of Cs ion Exchange Mat'l (distribution of particles tends to much smaller particles) | For Shear, there is a seismic qualification of .35 g for MHM | Design is considering containing Cs canister in modified glass canister | S3 | F2 | This hazard does not address Cs canister flammability issues. It is assumed that the canister will not contain flammable gas. Building is more seismically qualified than the MHM. |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-------------------------------------|--------------------------------------|--|------------------------|--|---|--|--|----------------------------|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-10 | | Kinetic, Linear | Canister pinch | Human error or equipment failure | Canister shearer from drive activation (shear implies dent or breach) | Release of material from glass log (distribution of particles tends to large particles) Release of Cs ion Exchange Mar'l (distribution of particles tends to much smaller particles) | Movement interlock | Procedures and training | S3 | F3 | S3 based on Cs canister shear Not known whether machine can shear glass or Cs canisters MHM has large mass so large momentum Movement negates confinement |
| (Block 10 continued) M-11 | | Ionizing radiation sources | Direct exposure | Equipment design flaw Events that cause MHM movement away from receiving pit Personnel remaining in near contact with MHM while canister present | High radiation from MCO | Facility worker exposure | Shielding design Guard that prevents personnel from hugging MHM when canister present! | | S1* | F3 | MHM design for shielding keeps exposure within requirements Glass and Cs canisters have higher rad levels as compared to spent fuel There needs to be a FMEA to identify failures High level waste, waste package dose factor exceeds MCO (which is the design criteria for MHM) |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons- Cat | Freq Cat | Remarks |
|--|---|--|------------------------------------|---|--|-----------------------------|---|---|--------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 11) M-12 | Replace Shield Hatch Plate Over Pit | None | Facility worker hazards only | | No accidents identified | | | | | | Nothing in the pit. |
| (Block 12- 19) R-01 | Remove empty cask and return it to the vendor | Various | Facility worker hazards only | | | | | | S1* | F3 | 12-19 deal with an empty cask. Only industrial hazards are significant. |
| (Block 12, 13) M-13 | Decon and Survey of Cask in Receiving Pit | Ionizing radiation sources | Radioactive material | Canister inadvertently left in cask | Facility worker exposed Unshielded radiation source | Facility worker exposure | MHM lead sensors Grapple design with sensors verifies that grapple has engaged canister | Procedures for monitoring the transfer cask | S1* | F2 | May need other positive methods to verify that MHM picked up canister Need to check what features are in current designs |
| (Block 12, 13 continued) M-14 | | Ionizing radiation sources | Radioactive material | Leak in Cs canister | Facility worker is contaminated with radioactive material | Facility worker exposure | Canister design prevents leaks | Procedures for monitoring | S1 | F2 | Expectation is that the cask is "sniffable" before cask cover is removed |
| (Block 20) M-15 | Remove storage tube cover plate | Various | Industrial hazards only | | | | | | | | |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|--------------------|---|--|------------------------|--|---|--|--|---|---------------|--------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 21) M-16 | Move MHM Over Storage Tube | Thermal | Canister overheat | Canister remains in MHM for excessive time | Canister overheats with possible breach | Release of Cs inside MHM | Cooling systems if found to be needed. MHM provides secondary confinement | Time limits on canister residence time in MHM Possible ability to return canister to receiving pit Requirements controlling how many canisters in process at a given time | S0 | F3 | Glass overheating only affects glass quality. If occurs, then can't take to permanent storage. Thermal loading and overheating needs to be evaluated. No ability to detect breached container in MHM. |
| M-17 | | Kinetic-Linear | MHM strikes objects | Objects involved with Spent Fuel Storage is in the way of this MHM travel. | MHM runs into object or personnel associated with Spent Fuel Storage | Facility worker injury Damaged equipment Introduction of air into Spent Fuel Storage Tube | MHM touch bar for stopping when object contracted. Alarm, Buzzer, or light when MHM moving | Lock out of MHM while spent fuel activities in progress | S1* S0 | F3 F3 | MHM moves very slowly |
| (Block 22) M-18 | Remove Storage Tube Plug Assembly | Mass, Gravity, Height | Drop Plug | Human error or equipment failure | Drop plug and damage sealing surface or jam plug | Upset operations | Plug is tapered | Deck and plug capable of withstanding some level of drop Limited lift height | S0 | F3 | Operational upset only |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|---------------------------------|---|--|--|-------------------------------------|--|--|--|---|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-19 | | | Jam Plug in MHM | Human error or equipment failure | Drop plug and damage sealing surface or jam plug | Upset operations | Access ports to plug hoist and grapple | | S0 | F3 | Operational upset only |
| (Block 23) M-20 | Transfer Canister to Storage Tube | Mass, Gravity, Height | Wrong storage tube chosen | Human error | Place glass canister onto Cs canister | Unexpected process upset with possible need to unload tube | | Use designated vault for only one type of canister | S0 | F3 | Loading sequence not currently specified Not intended to mix canister types in storage tubes |
| M-21 | | Mass, Gravity, Height | | Human error | Put an additional canister in the tube with drop | | Impact limiter Ventilation system or MHM | | S3 | F3 | Impact limiter may not be in place since it is a load into a wrong tube. |
| M-22 | | Mass, Gravity, Height | | Human error | Attempt to put an additional canister in the tube without drop | Process upset | Grapple height interlock | Procedures for placement of canisters | S0 | F3 | |
| (Block 23 continued) M-23 | | Mass, Gravity, Height | Drop with wrong storage tube chosen | Human error | Drop of glass canister on to Cs canister | Possible breach of Cs canister | Impact limiter Canisters qualified for 7 meter drop Grapple designed to not open under load. Canister must stop before grapple can be opened | Requirements and procedures for impact limiter installation | S3 | F3 | If Cs canister overpacked with glass canister the drop problem goes away. 7 meter drop qualification is only for the <u>Bottom</u> of the canister |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-----------------|---|--|-------------------------------------|--------------------------------------|--|-----------------------------------|---|---|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-24 | | Mass, Gravity, Height | Drop with correct tube chosen | Human error or mechanical failure | Drop of glass canister on to Cs canister | Possible breach of Cs canister | Grapple designed to not open under load Canisters qualified for 7 meter drop Impact limiter | Requirements and procedures for impact limiter installation | S3 | F3 | Glass on glass or glass on Cs are bad Any drop without impact limiters is bad 7 meter drop qualification is only for the bottom of the canister |
| M-25 | | Kinetic-Linear | Pinch canister with MHM | Human error or mechanical failure | Put 3rd canister tube - No drop. Attempt to index MHM | Possible breach of Cs canister | Grapple height interlock | Procedures for canister placement | S3 | F3 | Study in progress to determine if indexing with canister not fully down will cause shear. (Affects Block 10) (Shear due to indexing) |
| M-26 | Transfer Canister to Storage Tube | Mass, Gravity, Height | Impact Limiter Misplacement | Canister cocks in storage tube | Inability to continue storage in this tube | Process upset | Grapple movement indication | | S0 | F3 | |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|---------------------------------|--------------------------------------|--|------------------------------|---|--|--|--|---|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| (Block 23 continued) M-27 | | Thermal | Overheat in storage tube | Design less than adequate Natural phenomena - High wind with tumble weeds plugging ventilation - Tornado damage to exhaust stack | Vent system plugging Exhaust stack collapse | Canister overheat (exceed product spec) Canister overheat | Exhaust stack designed to withstand tornado | Procedures to keep vault inlet/outlet clean. | S0 | F3 | 1. Heat transfer model will be developed and validated by spent fuel program 2. Heat transfer model will be run to verify storage tube loading configuration do not result in waste temperature in excess of specs. before tube, loaded. |
| M-28 | | Natural Phenomena; Kinetic-Linear | Storage tube failure | Seismic event | Seismic event fails storage tubes | Possible canister rupture | Facility designed for DBE | | S3 | F2 | Seismic damage to other parts of the CSB such as the roof or floor will not result in material release as long as the tubes are intact. |
| M-29 | | | CSB structural failure | Seismic event | Seismic event causes CSB structural failure | Radioactive material release | Facility designed for DBE | | S3 | F2 | |
| M-30 | | Natural Phenomena; Kinetic-Linear | Canister shear | Seismic event | Seismic causes canister shear (see prior node Block 10) | Radioactive material release | Cask lid and cask will be engineered to prevent damage to contents by accidents | Operating procedures and training | S3 | F2 | |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|-----------------------------------|--|--|--------------------------------------|---|--|--|---|--|-------------|-------------|--|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-31 | | Natural Phenomena; Kinetic-Linear | | Seismic event | Loss of ventilation | Storage tubes overheat possible release | Stack qualified to .35 gs | | S1 | F2 | |
| M-32 | | Thermal | High temperature | Long dwell time in MHM | Over heat canister | See other nodes on MHM long hold time | | | S0 | F3 | |
| (Block 23 - continued) M-33 | | Corrosives | Canister breach during storage | Corrosion over long period due to canister/waste interactions | Canister breach due to corrosion failure | Release of rad material into storage tube | Storage tube forms confinement barrier | No water or solvents allowed in building or tubes | S0 | F2 | Study needed to verify problem has been addressed. S0 as long as tube performs confinement function (otherwise F2 or F3) |
| M-34 | | Ionizing radiation sources | Concentrated fissile material | Human error or uncontrolled storage of concentration fissile material Mechanism present to concentrate fissile material | Criticality | Significant facility worker exposure | | Criticality prevention program | S1* | F1 | Fissile material is not highly concentration in waste. Study may be needed. HWVP addressed this. |
| (Block 24) M-35 | Replace storage tube plug assembly | Mass, Gravity, Height | Drop plug | Human error or equipment Seismic | Plug fragments and falls into tube | Inability to retrieve stored waste | Short drop distance due to MHM design | | S0 | F3 | Need procedures and equipment to recover from this event. |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|----------------------------------|--------------------------------------|---|---------------------------------------|--|---|--|--|---|-----------------|----------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| M-36 | | Ionizing radiation sources | Unshielded radioactive material | Human error | Forgot to replace plug before moving the MHM | Facility worker exposure from SHINE | Interlock prevents MHM movement while weight still on plug grapple | Operating procedures | S1* | F3 | |
| (Block 25) M-37 | Move MHM Over Storage Tube | Thermal | Canister overheat | Canister remains in MHM for excessive time | Canister overheats with possible breach | Release of Cs inside MHM | Cooling systems if found to be needed. MHM provides secondary confinement | Time limits on canister residence time in MHM Possible ability to return canister to receiving pit Requirements controlling how many canisters in process at a given time | S0 | F3 | Glass overheating only affects glass quality. If occurs, then can't take to permanent storage. Thermal loading and overheating needs to be evaluated. No ability to detect breached container in MHM. |
| M-38 | | Kinetics | Strike objects | Objects involved with Spent Fuel Storage is in the way of this MHM travel. | MHM runs into object or personnel associated with Spent Fuel Storage | Personnel injury or damaged equipment or introduction of air into Spent Fuel Storage Tube | MHM touch bar for stopping when object contracted. Alarm, Buzzer, or light when MHM moving | Lock out of MHM while spent fuel activities in progress | S1* S0 S0 | F3 F3 F3 | MHM moves very slowly |
| Failed Canister Mitigation | MHM Retrieval | No difference from current hazard ** (except for confinement) | | | | | | Hazards addressed in Book 21 and 22 | | | ** Confinement concerns are present in regard to the level of protection required for specific condition of failed canister recovery. |

Immobilized High-Level Waste Interim Storage Hazard Analysis

Date 8/28/97

Participants: Milt Shultz, Don Porten, Ken Burgard, Pascal Mouette, Ron Calmus, Dean Smith, Chris Petersen

| ID (Block #) | Operating Sequence Mode/ Block | Hazard, Energy Source, Material | Hazardous Condition | Cause | Potential Accident | Consequence | Safety Features | | Cons Cat | Freq Cat | Remarks |
|---|--|--|------------------------|-------|-----------------------|-------------|------------------------|-------------------------------------|-------------|-------------|---|
| | | | | | | | Engineered Features | Administrative Features | | | |
| | MHM Transport | No difference (except confinement) | | | | | | Hazards addressed in Block 23 | | | We need to have good evaluation on frequency of canister failure |
| Failed Canister Mitigation (continued) | MHM Transfer to Overpack Facility | No difference (except confinement) | | | | | | Hazards addressed in Block 23 | | | Putting in impact absorbers in the overpack tubes should have no significant differences from standard impact absorbers |
| | Decontamination of various equipment • MHM • Plugs • Covers • Perform Overpacks - Put canister in overpack - Seal overpack - Decon overpack • Pickup overpack • Transport overpack • Put overpack into storage | Outside anything currently evaluated (to be evaluated at time when process is more defined) | | | | | | | | | Putting impact absorbers is similar to putting in shield plugs - hazards similar, weight less. *Study for Decon Process needed *Need thermal analysis for overpack in detail design *Need study of overpack interaction with existing equipment (identify interfaces) |

APPENDIX H

ECONOMIC ANALYSIS AND LIFE CYCLE COST ANALYSIS

(Provided by Numatec)

(Provided by the Performance Contractor under a separate cover)

This appendix will include significant decisions involving rationale for choosing the Canister Storage Building based upon earlier studies. The remainder of lesser choices was primarily dictated by technical or environmental conditions.

APPENDIX I

PHYSICALLY HANDICAPPED ASSESSMENT

(Provided by Numatec)

ACCOMMODATIONS OF PHYSICALLY HANDICAPPED

PROJECT NO. W-464PROJECT TITLE Immobilized High Level Waste Interim Storage facilityLOCATION 200 East

(area)

BUILDING Canister Storage BuildingPrepared By Ken BurgardTitle Project ManagerDate 02/26/98Type of Project:

- ☒ New Building (or Building Addition)
☐ Building Alteration
☐ Site Development (Grading, Walks, Parking Lots)
☐ Other

Application of Regulations:

DOE Order 6430.1A, "General Design Criteria," General Requirements 0101-4, "Handicapped Provisions."

41 CFR, Public Contracts and Property Management, Subtitle C, 101-19.6, "Accommodations for the Physically Handicapped."

- ☐ All Regulations
☐ Limited Application (indicate in comments section)

Exceptions:

DOE Order 6430.1A, "General Design Criteria," General Requirements 0101-4, "Handicapped Provisions."

- ☒ a. Not intended for occupancy or use by the handicapped
☐ b. Alteration not involving existing stairs, doors, elevators, toilets, etc.
☐ c. Not structurally possible

General Comments:

I-1

Signature Ken Burgard

02/26/98

Date

APPENDIX J

PLANT FORCES WORK REVIEW

(Provided by Numatec)

| | | | | | |
|--|--|---------------------------------------|---|---------------------|---------------------------|
| F D H | Fluor Daniel Hanford, Inc. P.O. Box 1000, Richland, WA 99352-1000 PLANT FORCES WORK REVIEW | | Plant Forces Work Review No. FDH- | Date | Page 1 of 3 |
| | Title PROJECT W-464 - IMMOBILIZED HIGH LEVEL WASTE INTERIM STORAGE FACILITY (PHASE 1) | | JCS Work Pkg or Project No. W-464 | Area 200E | Bldg. No. 212-H |
| R E Q U E S T E R | <u>Estimated Cost of Work:</u> | | | | |
| | *1. Procured Material/Equipment | | | \$ | 39.2M |
| | *2. Materials/Equipment Purchased for Shop Fabrication | | | \$ | 0 |
| | *3. Job-Site Material | | | \$ | 4.0M |
| | 4. Shop Labor | | | \$ | 0 |
| | 5. Job-Site Labor | | | \$ | 4.4M |
| | 6. Other Costs (design, field inspection, and contingency allowance) | | | \$ | 28.6M |
| 7. General Overhead (Labor Only) | | | \$ | 1.1M | |
| <u>*Include estimated fair value of material or equipment acquired on site</u> | | | | Total Job | \$ 77.3M |
| Requester's Name and Phone No. <u>John B. Payne, 372-1386</u> | | | | | Date <u>3/23/98</u> |
| F D H | <u>Reviewed By:</u> | | | | |
| | Area Work Review Agent <u>John E. Allison</u> | | | Date _____ | |
| Company Work Review Agent <u>Gary Maxwell</u> | | | Date _____ | | |
| D O E | The following determination has been made regarding applicability of the Davis-Bacon Act, as amended, to the work described above: | | | | |
| | Applicable <input type="checkbox"/> Not Applicable <input type="checkbox"/> | | Chairman _____ | | |
| | Construction <input type="checkbox"/> | Plant Forces <input type="checkbox"/> | RL-Labor Standards Board <input type="checkbox"/> | Date _____ | |

"Description of Work"Briefly state the reason for this work activity:

This project will provide the transportation and facility infrastructure for the interim storage of Solidified High Level Waste produced by DOE's private vendor. Storage will occur at the current site of the Spent Fuel Canister Storage Facility (See PFWR 263-97).

Job summary:

Project W-464 will require the procurement/fabrication/certification of a transporter, the addition of an ANNEX to the Spent Fuel Canister Storage Building (CSB), and modification to Vaults #2 and #3 of the CSB.

Discuss all programmatic or physically associated work planned, underway, or recently completed in the work area:

No programmatic or physically associated work is planned, underway, or recently completed in the work area.

Describe entire work scope. Fully describe complete job scope using a stepped work flow format. Describe and estimate the cost of labor and material on foundations, structures, utility systems, or other construction type activity. Provide sketches or measurements for all work:

See sketches in Attachment A.

Capital Procurements:

- Shielded canister transporter.
- 10 ton bridge crane - remote.
- 60 ton gantry crane.

| | | | |
|-------------|---|---|-----------------------|
| F D H | Fluor Daniel Hanford, Inc. P.O. Box 1000, Richland, WA 99352-1000 PLANT FORCES WORK REVIEW Continued | Plant Forces Work Review No. FDH- | Page 2 of 3 |
|-------------|---|---|-----------------------|

- Welding station.
- 440 Standard Tube Assemblies.
- 2 canister overpacks.
- 2 new cask transport systems.

Work Scope:

1. Excavate approximately 10,670 cubic yard for annex building and pit.
2. Construct 600 linear feet of new asphalt roadway.
3. Place stabilization gravel on approximately 10,000 square feet.
4. Remove 1,600 square feet of metal siding and girts.
5. Place 883 cubic yards of concrete for annex building slabs, pitwalls, and curbing.
6. Erect 14,000 square feet of ceiling and wall metal liner and install 14,000 square feet of insulation.
7. Install 5 - 3'x7' doors and 1- 20'x24' swing door.
8. Install 72 linear feet of handrail.
9. Erect 1-24"x100' high exhaust stack with stack monitor.
10. Excavate 500 linear feet of trenching, install 1" sch 40 PVC and backfill.
11. Install 3 - 135 watt LPS lights with arm and 30' steel pole.
12. Install 1000 feet of 3/4" conduit with fittings and supports.
13. Install 4 - 35 watt LPS wallmount fixtures and lamps.
14. Install 6 400 watt metal halide fixture with lamp and wire guard.
15. Install 11 emergency battery units.
16. Install bridge, crane power and controls including 2 cctv units.
17. Install 13,750 feet of #10/#12 THHN, #12 XHHW, #4 XHHW, and #2 XHHW wire.
18. Install 1 - 3 phase, 240V, 225A panel board.
19. Install 1 - 3 phase, 600V, 400A, distribution panel board.
20. Install 6 - 5/8" x 10' ground rods with lightning air terminals and down leads.
21. Install 1 welding station with cooling system and helium and argon systems.

| | | | |
|-------------|--|------------------------------|--------|
| F D H | Fluor Daniel Hanford, Inc. P.O. Box 1000, Richland, WA 99352-1000 | Plant Forces Work Review No. | Page |
| | PLANT FORCES WORK REVIEW Continued | FDH- | 3 of 3 |

22. Form 13,640 square feet of walls for new air inlet structures and place 992 feet of key joints, 280,000 pounds of 5381b rebar, and 124 anchor bolts.
23. Place 426 cubic yards of concrete.
Work Scope (continued):
24. Install 94 Tons of steel.
25. Install 200 feet of lightning protection copper cable and 2 new carbon steel exhaust stacks.
26. Install 440 - 40' x 28" carbon steel standard tube assemblies and base assemblies.
27. Install 12 - 40' x 30" carbon steel overpack tube assemblies and base assemblies.
28. Install 60 - 10'8" long 10 gauge carbon steel airfoils.
29. Install 4,900 square feet of forms and place 94,000 pounds of 6001b rebar for placement of 200 cu yds of concrete for exhaust louvers.

APPENDIX K

COMPLIANCE MATRIX

The purpose of the attached matrix is to provide the basis for developing the requirements for the design and construction phases of the project.

The matrix includes the listing of identified requirements at the time that this CDR was developed. The columns marked "Yes" indicate that the requirement is applicable. "NA" indicated that the requirement is not applicable for that column or in its entirety.

Legend:

| | |
|---------|---|
| C | = Constructor/Procurer |
| DRD | = Design Requirement Document |
| EC | = Engineer/Contractor |
| FDH-CON | = Fluor Daniel Contract |
| OC | = Operating Contractor or Performance Contractor |
| SAR | = Safety Analysis Report (includes PSAR = Preliminary Safety Analysis Report and FSAR = Final Safety Analysis Report) |
| SRIDs | = Standards/Requirements Inventory Document |
| WASRD | = Waste Acceptance System Requirements Document |

Note: The WASRD document is only written for 3-meter canisters.

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | ORD | FDH CON | SNF SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|------------------------------|--|------|---------|----------|---------|-------|---------------------|-----------------|--|
| 10 CFR 1021 (1994) | National Environmental Policy Act Implementation Procedures | Yes | | Yes | Yes | | OC | | Not within project scope |
| 10 CFR 1021, 321 | Environmental Assessments | | | Yes | | | NA | | |
| 10 CFR 1021, Part 200 | NEPA | | | Yes | | | NA | | |
| 10 CFR 1021, part 211 | Limitations on the NEPA Process | | | Yes | | | NA | | |
| 10 CFR 1021, Part 300 | EIS, EA Process | | | Yes | | | NA | | |
| 10 CFR 1021, part 322 | NEPA Review Process | | | Yes | | | NA | | |
| 10 CFR 1021, Part 400 | Categorical Exclusions | | | Yes | | | NA | | |
| 10 CFR 1021, Part 410 | Safety and Health Regulations for Construction | | | Yes | Yes | | OC/EC | | |
| 10 CFR 1926 | Standards for Protection Against Radiation | Yes | | | * | | OC/EC | | NRC equivalency and Performance Spec |
| 10 CFR 40.13 (c)(6) | Energy Conservation Voluntary Performance Standards for New Buildings, Mandatory for Federal Building | Yes | | | Yes | Yes | OC | | The degree of applicability |
| 10 CFR 435 (1994) | Federal Energy Management and Planning Programs - Subpart A, Methodology and Procedures for Life Cycle Cost Analysis | | | | Yes | | OC/EC | | Mandated by 10 CFR 435 |
| 10 CFR 436 | Domestic Licensing of Production and Utilization Facilities | *Yes | | | Yes | * | NA | | *WASRD states that this is not required to CRWMS |
| 10 CFR 71 | Licensing Requirements for the Independent Storage of Spent Nuclear Fuel and High-Level Radioactive Waste | Yes | | Yes | Yes | Yes | OC | | |
| 10 CFR 72 (1994) | Nuclear Safety Management - Subpart A, General Provisions, Section 830.120, Quality Assurance Requirement | Yes | | Yes | Yes | | Part 120 only OC/EC | | |
| 10 CFR 75.1 21.113.131.35 | Occupational Radiation Protection | Yes | | Yes | Yes | | OC/EC | | |
| 10 CFR 830 (1994) | Occupational Safety and Health Standards | Yes | | Yes | Yes | Yes | OC/EC | | |
| 10 CFR 835 (1993) | Process Safety Management of Highly Hazardous Chemicals | | | Yes | Yes | Yes | OC/EC | | |
| 10 CFR 961 | Safety and Health | | | Yes | Yes | Yes | OC/EC | | |
| 29 CFR 1904 | | | | Yes | | | | | |
| 29 CFR 1910 (1994) | | Yes | | Yes | Yes | | | | |
| 29 CFR 1910.119 | | | | Yes | Yes | | | | |
| 29 CFR 1915 | | | | Yes | Yes | Yes | | | Via DOE direction ccl:Mail RI#97-011 dated 1/17/97 applicable by law |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNC STRIDS | CS&SAR | WASRD | Responsible | Waiver Required | Comment |
|------------------------------------|---|-----|---------|------------|--------|-------|-------------|-----------------|--|
| 29 CFR 1918 | Safety and Health | | | | Yes | | OC/EC | | Via DOE direction ccl/Mail RU#97-011 dated 1/17/97 applicable by law |
| 29 CFR 1926 | | | | Yes | | | OC/EC | | |
| 29 CFR 1928 | Safety and Health | | | | Yes | | OC/EC | | Via DOE direction ccl/Mail RU#97-011 dated 1/17/97 applicable by law |
| 29 USC 651 et. Seq. (654(a) - (b)) | | | | | | Yes | OC | | |
| 29 USC 655, et. seq. | Occupational Safety and Health Act of 1970 | Yes | | | Yes | | OC/EC | | |
| 36 CFR 1220 | | | | Yes | | | OC | | |
| 36 CFR 1228 | | | | Yes | | | OC | | |
| 36 CFR 1234 | | | | Yes | | | OC | | |
| 40 CFR 1500-1508 (1986) | Regulations for Implementing the Procedural Provisions of the National Environmental Policy Act | Yes | | | Yes | | OC | | |
| 40 CFR 1501, Part 2 | Application NEPA | Yes | | | | | NA | | |
| 40 CFR 1506, Part 3/4 | Actions During NEPA Process | Yes | | | | | NA | | |
| 40 CFR 1508, Part 25 | NEPA Actions | Yes | | | | | NA | | |
| 40 CFR 1508, Part 4 | Categorical Exclusions | Yes | | | | | NA | | |
| 40 CFR 1508, Part 9 | Environmental Assessment | Yes | | | | | NA | | |
| 40 CFR 191 | Radiation Dose Regulations | | | Yes | | | OC/EC | | |
| 40 CFR 261 | | | | | | Yes | OC | | |
| 40 CFR 262 | | | | Yes | | Yes | OC | | |
| 40 CFR 262, Part 32 | Marking | | | Yes | | | OC | | |
| 40 CFR 264 (1986) | Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities | Yes | | | | | NA | | |
| 40 CFR 268, Part 40 (a)(b)(c) | Waste (Restricted) | | | Yes | | | OC | | |
| 40 CFR 279, Part 10(b) | Used Oil | | | Yes | | | NA | | |
| 40 CFR 279, Part 21 | Hazardous Waste Mixing | | | Yes | | | NA | | |
| 40 CFR 279, Part 22 | Used Oil Storage | | | Yes | | | NA | | |
| 40 CFR 279, Part 81 | Disposal | | | Yes | | | NA | | |
| 40 CFR 355 Part 40 | | | | Yes | | | OC | | |
| 40 CFR 61 (1994) | National Emissions Standards for Hazardous Air Pollution* | Yes | | Yes | Yes | OC | NA | | More restrictive than WAC-25-247 (Dose Driver) |
| 40 CFR 61, Part 14(f) | Records Management (Owner) | | | Yes | | | NA | | |
| 40 CFR 61, Part 9 | Construction Startup | | | Yes | | | OC | | |
| 40 CFR 61, Part 92 | | | | Yes | | | OC | | |
| 40 CFR 61, Part 93 | | | | Yes | | | OC | | |
| 40 CFR 61, Part 94 | Compliance Reporting | | | Yes | | | OC | | |
| 40 CFR 61, Part 95 | Recordkeeping Requirements | | | Yes | | | OC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB/SAR | WASRD | Responsible | Water Required | Comment |
|---------------------------------------|---|-----|---------|----------|---------|-------|-------------|----------------|-------------------------------|
| 40 CFR 61, Part 96 | Construction/Modification Applications | | | | | | OC | | |
| 40 CFR 761, Part 40(a)(b)(e)(h) | Waste Labeling | | | Yes | | | OC | | |
| 42 USC 13106 | | | | Yes | | | OC | | |
| 42 USC 4321, et. seq. | National Environmental Policy Act (NEPA) of 1969 | Yes | | | | | OC | | Not within E/C scope - in TPA |
| 42 USC 6901, et. seq. | Resource Conservation and Recovery Act (RCRA) of 1976 | Yes | | | | | OC/E | | Included in TPA |
| 42 USC 2210 | Price-Anderson Amendments Act of 1988 | | | | Yes | | OC/E/C | | |
| 49 CFR 171, Part 3 | Miscellaneous Transportation Requirements | | | Yes | | | OC | | |
| 49 CFR 172 | | | | | | | | | |
| 49 CFR 172, Part 101(c)(8)(9)(10)(12) | Hazardous Substances Packaging | | | Yes | | Yes | OC | | |
| 49 CFR 172, Part 203(c)(6)(9)(10)(12) | Radioactive Packaging | | | Yes | | | OC | | |
| 49 CFR 172, Part 200 | Applicability | | | Yes | | | OC | | |
| 49 CFR 172, Part 201 | General Entries (Packaging) | | | Yes | | | OC | | |
| 49 CFR 172, Part 202 | Description of Hazardous Materials on Shipping Papers | | | Yes | | | OC | | |
| 49 CFR 172, Part 203(f) | Transportation by Air | | | Yes | | | OC | | |
| 49 CFR 172, Part 203(j) | Dangerous When Wet Material Transportation | | | Yes | | | OC | | |
| 49 CFR 172, Part 203(m)(93) | Poisonous by Inhalation Transportation | | | Yes | | | OC | | |
| 49 CFR 172, Part 204 | | | | | | | | | |
| 49 CFR 172, Part 205 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 301 | Marking Non-Bulk Packaging | | | Yes | | | OC | | |
| 49 CFR 172, Part 302 | Marking Bulk Packaging | | | Yes | | | OC | | |
| 49 CFR 172, Part 303 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 304 | Marking Requirements | | | Yes | | | OC | | |
| 49 CFR 172, Part 310 | Radioactive Material Marking | | | Yes | | | OC | | |
| 49 CFR 172, Part 312 | Liquid Hazardous Materials Marking, etc. | | | Yes | | | OC | | |
| 49 CFR 172, Part 313(a) | Poisonous Hazardous Material Marking | | | Yes | | | OC | | |
| 49 CFR 172, Part 313(b) | Non-Bulk Plastic Outer Packaging Marking | | | Yes | | | OC | | |
| 49 CFR 172, Part 324 | Portable Tanks (Marking) | | | Yes | | | OC | | |
| 49 CFR 172, Part 328 | Cargo Tanks (Marking) | | | Yes | | | OC | | |
| 49 CFR 172, Part 332 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 334 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 336 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 400 | General Labeling Requirements | | | Yes | | | OC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB SAR | WASRO | Responsible | Water Required | Comment |
|--------------------------------------|--|-----|---------|----------|---------|-------|-------------|----------------|---------|
| 49 CFR 172, Part 401 | | | | | | | | | |
| 49 CFR 172, Part 402 | Additional Labeling Requirements | | | Yes | | | OC | | |
| 49 CFR 172, Part 403 | Radioactive Material Markings | | | Yes | | | OC | | |
| 49 CFR 172, Part 404 | Labels for Mixed and Consolidated Packaging | | | Yes | | | OC | | |
| 49 CFR 172, Part 405 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 406 | Placement of Labels | | | Yes | | | OC | | |
| 49 CFR 172, Part 500 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 502 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 504 | General Placarding Requirements | | | Yes | | | OC | | |
| 49 CFR 172, Part 505 | Placarding for Subsidiary Material | | | Yes | | | OC | | |
| 49 CFR 172, Part 506 | Highway Placarding | | | Yes | | | OC | | |
| 49 CFR 172, Part 507 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 516 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 600 | | | | Yes | | | OC | | |
| 49 CFR 172, Part 602 | Emergency Response | | | Yes | | | OC | | |
| 49 CFR 172, Part 604 | Emergency Response Telephone Number | | | Yes | | | OC | | |
| 49 CFR 173, Part 12 | Exceptions for Shipments of Waste Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 121(e) | Class 3 Material Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 125 (a) (b) (c) (d) | Class 4 Material Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 127(b) | Assignment of Packing Groups | | | Yes | | | OC | | |
| 49 CFR 173, Part 133 | Packaging Hazard Zones Division 6.1 Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 137 | Assignment of Packing Group | | | Yes | | | OC | | |
| 49 CFR 173, Part 164 (c) | Mercury Transportation | | | Yes | | | OC | | |
| 49 CFR 173, Part 173 (a) (b) | Packaging Paint, Adhesives & Ink | | | Yes | | | OC | | |
| 49 CFR 173, Part 173.2a | Classification of Materials Having More Than One Hazard | | | Yes | | | OC | | |
| 49 CFR 173, Part 20(a) | Non-Bulk Packaging Liquid Hazardous Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 201 | | | | Yes | | | OC | | |
| 49 CFR 173, Part 202(a) | Non-Bulk Packaging Liquid Hazardous Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 203(a) | Non-Bulk Packaging of Class III Liquids | | | Yes | | | OC | | |
| 49 CFR 173, Part 211(a) | Non-Bulk Packaging of Solid Hazardous Materials (Packing Group I) | | | Yes | | | OC | | |
| 49 CFR 173, Part 212(a) | Non-Bulk Packaging of Solid Hazardous Material (Packing Group II) | | | Yes | | | OC | | |
| 49 CFR 173, Part 213(a) | Non-Bulk Packaging of Solid Hazardous Material (Packing Group III) | | | Yes | | | OC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRIDS | USB SAR | WASRD | Responsible | Waiver Required | Comment |
|--------------------------|--|-----|---------|-----------|---------|-------|-------------|-----------------|---------|
| 49 CFR 173, Part 216 | Packaging Asbestos | | | | | | OC | | |
| 49 CFR 173, Part 22 (a) | Exemption Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 226 | Packaging Materials Poisonous by Inhalation (Hazard Zone A) | | | Yes | | | OC | | |
| 49 CFR 173, Part 227 | Packaging Materials Poisonous by Inhalation (Hazard Zone B) | | | Yes | | | OC | | |
| 49 CFR 173, Part 24 A/B | Bulk Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 29 | Empty Packagings | | | Yes | | | OC | | |
| 49 CFR 173, Part 3 | Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 300 | | | | Yes | | | OC | | |
| 49 CFR 173, Part 413 | Waste Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 415 | Authorized Type A Packages | | | Yes | | | OC | | |
| 49 CFR 173, Part 417 | Packaging Fissile Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 419 | Packaging Oxidizing Radioactive Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 421 | Limited Quantity Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 422 | Additional Requirements for Excepted Packages Containing Class 7 Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 423 | Requirements for Multiple Hazard Limited Quantity Class 7 Materials | | | Yes | | | OC | | |
| 49 CFR 173, Part 424 | Excepted Packages for Instruments and Articles | | | Yes | | | OC | | |
| 49 CFR 173, Part 425 | Low Specific Activity Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 427 | Transport Requirements for LSA Class 7 Materials and SCO | | | Yes | | | OC | | |
| 49 CFR 173, Part 428 | Empty Class 7 Material Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 431 | Activity Limits for Type A & B | | | Yes | | | OC | | |
| 49 CFR 173, Part 433 | Requirements for Determining A1 and A2 Values | | | Yes | | | OC | | |
| 49 CFR 173, Part 435 | | | | | | | | | |
| 49 CFR 173, Part 441 | Radiation Level Limitations | | | Yes | | | OC | | |
| 49 CFR 173, Part 442 | Thermal Limitations for Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 443 | Contamination Control | | | Yes | | | OC | | |
| 49 CFR 173, Part 448 | | | | Yes | | | OC | | |
| 49 CFR 173, Part 455 | Classification of Fissile Material Packages | | | Yes | | | OC | | |
| 49 CFR 173, Part 457 | Transporting of Fissile Class III | | | Yes | | | OC | | |
| 49 CFR 173, Part 459 | | | | Yes | | | OC | | |
| 49 CFR 173, Part 471 | Waste Packaging | | | Yes | | | OC | | |
| 49 CFR 173, Part 475 | | | | Yes | | | OC | | |
| 49 CFR 177, Part 848 | | | | Yes | | | OC | | |
| 49 CFR 282, Part 31 | Labeling | | | Yes | | | OC | | |
| 54-FR-3904 | | | | Yes | | | DOEC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|---|--|------|---------|----------|---------|-------|-------------|-----------------|--|
| A/E Standard, GC-LOAD-01, (Kaiser 1993a) | Standard Architectural Civil Design Criteria, Design Loads for Facilities | Yes* | | | | | NA | | *Negated by DOE 5480.28 |
| A/E Standard, GH-CLIM-01, (Kaiser 1993b) | Design Climate for Hanford Site | Yes | | | Yes | | OC/E/C | | |
| All NEPA Codes and Standards | | Yes | | Yes* | | | OC | | *Only when more restrictive than DOE 5480.7A |
| ANSI N300-1975 (ANSI 1975) | Design Criteria for Decommission of Nuclear Fuel Reprocessing Plants | Yes | | | | | NA | | |
| ANSI/ACI 1985 | Code Requirements for Nuclear Safety Related Concrete Structures | | | | Yes | | OC/E/C | | |
| ANSI/ASCE 1984 | Specification for the Design, Fabrication, and Erection of Steel Safety-Related Structures for Nuclear Facilities | | | | Yes | | OC/E/C | | |
| ANSI/ASCE N690-94 | | | | | | | | | |
| ANSI/ANS 1992 | Design Criteria for an Independent Spent Fuel Storage Installation (Dry Type) | | | | Yes | | OC/E/C | | |
| ANSI/ANS-57.9 - 1992 | | | | | | | | | |
| ANSI/ANS-3.2-88 (ANSI/ANS 1988) | Administrative Controls and Quality Assurance for the Operational Phase of Nuclear Power Plants | Yes | | | | | NA | | |
| ANSI/ANS-57.1 - 1992 | Design Requirements for Light Water Reactor Fuel Handling Machine | | | | Yes | | OC/E | | |
| ANSI/ASHRAE/IES 90A-1980 (ANSI/ASHRAE/IES 1980) | Energy Conservation in New Building Design | Yes | | | | | NA | | |
| API Standard 650 (API 1993) | Welded Steel Tanks for Oil Storage | Yes | | | Yes | | OC | | Emergency generator - SC-2 |
| ASCE 1986 ASCE-4-86 | Seismic Analysis of Safety-Related Nuclear Structures and Commentary on Standard for Seismic Analysis of Safety-Related Nuclear Structures | | | | Yes | | OC/E | | |
| ASCE 1995 ASCE7-95 | Minimum Design Loads for Building and Other Structures | | | | Yes | | OC/E | | |
| ASHRAE 52.1-1992 (ASHRAE 1992) | Gravimetric and Dust-Spot Procedures for Testing Air Cleaning Devices Used in General Ventilation for Removing Particulate Matter | Yes | | | * | | NA | | * By reference to Calcs and DRD |
| ASHRAE Handbook (API 1993) | ASHRAE Handbook - Fundamentals | Yes | | | * | | NA | | *By reference to Calcs and DRD |
| ASME 1993 ASME B30.20 - 1993 | Below-the-Hook Lifting Devices | | | | Yes | | OC/E | | |
| ASME B30 Series (ASME 1944a) | Miscellaneous Specifications for Cranes, Hoists, and Hooks | Yes | | | Yes | | NA | | |
| ASME B31.1-1992 (ASME 1992) | Power Piping | Yes | | | Yes | | OC/E | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | WSB SAR | WASRD | Responsible | Waiver Required | Comment |
|---------------------------------------|--|-----|---------|----------|---------|-------|-------------|-----------------|---|
| ASME B31.3-1990 (ASME 1990) | Chemical Plant and Petroleum Refinery Piping | Yes | | | Yes | | OC/E | | |
| ASME N509-1989 (ASME 1989a) | Nuclear Power Plant Air-Cleaning Units and Components | Yes | | | Yes | | OC/E | | |
| ASME N510-1989 (ASME 1989b) | Testing of Nuclear Air Treatment Systems | Yes | | | Yes | | OC/E | | |
| ASME N509-1-1989 (ASME 1989c) | Rules for Construction of Overhead and Gantry Cranes (Top Running Bridge, Multiple Girders) | Yes | | | Yes | | OC/E | | |
| ASME NQA-1-1989 | QA Program Requirements for Nuclear Facilities | | | | Yes | | NA* | | *Will use the 1994 version |
| ASME NQA-1-1994-1A (ASME 1999c) | Quality Assurance Program Requirements for Nuclear Facility Applications | Yes | | | Yes | | OC/E/C | | |
| ASME Section III (ASME 1995a) | Boiler and Pressure Vessel Codes; Section VIII, Rules for Construction of Nuclear Power Plant Components | Yes | | | Yes | | OC | | Will need to make decision on applicability |
| ASME, Section VIII Division 1 (1955a) | Boiler and Pressure Vessel Code | Yes | | | Yes | | OC/E/C | | |
| ASME-NOG-1-1995 | Rules for Construction of Overhead and Gantry Cranes | | | | Yes | | OC/E | | |
| ASME/ANSI B31-9-1988 (ASME/ANSI 1989) | Building Services Piping Code | Yes | | | Yes | | OC | | |
| AWWA | American Water Works Association | Yes | | | Yes | | OC/E/C | | |
| CGA P-1-1991 (CGA 1991) | Safe Handling of Compressed Gas in Containers | Yes | | | Yes | | OC/E/C | | |
| CMAA Specification #70 (CMAA 1994) | Specifications for Top Running Bridge and Gantry Type Multiple Girder Electric Overhead Traveling Cranes | Yes | | | Yes | | NA | | |
| DE-RP06-96RL13308 | TWRS Privatization Request for Proposals | Yes | | | | | OC | | |
| DOE 1220.1A | Congressional & Intergovernmental Affairs | | Yes | | | | NA | | |
| DOE 1230.2 | American Indian Tribal Government Policy | | Yes | | | | OC | | |
| DOE 1240.2B | Unclassified Visits & Assignments by Foreign Nationals | | Yes | | | | OC | | |
| DOE 1270.2B | Safeguards Agreement with the International Atomic Energy Agency | | Yes | | | | OC | | |
| DOE 1300.2A | Department of Energy Technical Standards Program | | Yes | | | | NA | | |
| DOE 1300.3 | Policy on the Protection of Human Subjects | | Yes | | | | OC | | |
| DOE 1324.2A | Records Disposition | | Yes | | | | OC | | *Canceled by DOE 1324.5B |
| DOE 1324.2A | Records Disposition | | | | | Yes | OC | | Canceled by DOE 1324.2A |
| DOE 1324.3 | Files Management | | | *Yes | | | OC | | Canceled ordered see |
| DOE 1324.5.A | Records Management | | | *Yes | | | OC | | *Canceled by DOE 1324.5B |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB-SAR | WASRD | Responsible | Water Required | Comment |
|--------------------------|--|-----|---------|----------|---------|-------|-------------|----------------|---|
| DOE 1324.5B | Records Management Program | | Yes | Yes | | Yes* | NA | | Canceled 1324.2a and 1324.2 |
| DOE 1324.6 | Automated Electronic Recordkeeping | | Yes | Yes | | | OC | | |
| DOE 1330.1D | Computer Software Management | | Yes | Yes | | | OC/E | Potential | |
| DOE 1340.1B | Management of Public Communications Publications & Scientific, Technical, and Engineering Publications | | Yes | | | | OC | | |
| DOE 1350.1 | Audiovisual and Exhibits Management | | Yes | | | | OC/E/C | | Applied to any contractors doing work for DOE |
| DOE 1360.2B | Unclassified Computer Security Program | | Yes | | | | OC | | |
| DOE 1410.2 | Mail Management | | Yes | | | | NA | | Not within scope |
| DOE 1430.1D | Scientific & Technical Information Management | | Yes | | | | NA | | Not within scope |
| DOE 1450.3A | Call Control/Verification Programs & Authorized Use of Government Telephone System | | Yes | | | | OC/E/C | | |
| DOE 1450.4 | Consensual Listening-In To or Recording Telephone/Radio Conversations | | Yes | | | | OC/E/C | | |
| DOE 1500.3 | Foreign Travel Authorizations | | Yes | | | | OC | | Not part of project scope |
| DOE 1540.2 | Hazardous Material Packaging for Transport - Administrative Procedures | | Yes | | | | OC | | |
| DOE 1700.1 | Freedom of Information Program | | Yes | | | | OC/E/C | | |
| DOE 1800.1A | Privacy Act | | Yes | | | | OC/E/C | | |
| DOE 2030.4B | Reporting Fraud, Waste, and Abuse to the Office of Inspector General | | Yes | | | | OC/E/C | | |
| DOE 210.1 - 1985 | Performance Indicators and Analysis of Operations Information | | | | Yes | | OC | | |
| DOE 2100.8A | Cost Accounting, Cost Recovery, & Interagency Sharing of Information Technology Facilities | | Yes | | | | OC | | For major computer network servers |
| DOE 2110.1A | Pricing of Departmental Materials & Services | | Yes | | | | OC/C | | |
| DOE 2300.1B | Audit Resolution & Follow-up | | Yes | | | | NA | | Should apply to DOE only |
| DOE 2320.1C | Cooperation with the Office of the Inspector General | | Yes | | | | OC/E/C | | |
| DOE 2320.2B | Establishment of Departmental Position on Inspector General Reports | | Yes | | | | NA | | Should be DOE only |
| DOE 3220.1A | Management of Contractor Personnel Policies and Programs | | Yes | | | | NA | | Not part of project scope |
| DOE 3220.4A | Contractor Personnel and Industrial Relations Reports | | Yes | | | | OC | | |
| DOE 3220.6A | Federal Labor Standards | | Yes | | | | OC/E/C | | |
| DOE 3309.1A | Reductions in Contractor Employment | | Yes | | | | OC/E/C | | |
| DOE 3790.1A | Federal Employees OSH Program | | | | | *Yes | OC | | *Canceled by DOE 3790.1B |
| DOE 3790.1B | Federal Employees OSH Program | | | | | Yes | OC | | Superseded DOE 3790.1B |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNL STRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|--------------------------|---|-----|---------|-----------|---------|-------|-------------|-----------------|---|
| DOE 3830.1 | Policies & Procedures for Pension Programs Under Operating and Onsite Service Contracts | | Yes | | | | OC | | |
| DOE 3890.1A | Contractor Insurance and Other Health Benefit Programs | | Yes | | | | OC/E/C | | |
| DOE 3900.1B | Parking | | Yes | | | | OC | | Specific parking requirements should be sent to subs |
| DOE 4210.9A | Unsolicited Proposals | | Yes | | | | OC/E/C | | |
| DOE 4300.2C | Non-DOE Funded Work (Work-For-Others) | | Yes | | | | OC/E/C | | |
| DOE 4330.2D | In-House Energy Management | | Yes | | | | OC | | |
| DOE 4330.4B | Management Mgt. Program | | Yes | Yes | | | OC | | |
| DOE 4700.1 - 1987 | Project Management System | | Yes | Yes | Yes | Yes | NA | | |
| DOE 4700.5 | | | Yes | Yes | | | OC | | Cancelled order |
| DOE 5000.3B - 1993 | Occurrence Reporting and Processing | | | | Yes | | NA | | *DOE 232.1 supersedes this order |
| DOE 5300.1C | Telecommunications | Yes | Yes | | | | OC/E/C | | |
| DOE 5300.2D | Telecommunications: Emission | | Yes | | | | OC/E/C | | |
| DOE 5300.3D | Telecommunications: Communications | | Yes | | | | OC/E/C | | |
| DOE 5300.4D | Telecommunications: Protected | | Yes | | | | OC/E/C | | |
| DOE 5400.1 | General Environmental Protection Program | | Yes | | | | OC/E/C | | |
| DOE 5400.2A | Environmental Compliance Issue | | Yes | | Yes | | OC | | |
| DOE 5400.5 | Radiation Protection of the Public and the Environment | Yes | Yes | Yes | Yes | | OC/E/C | | |
| DOE 5440.1E | National Environmental Policy Act Compliance Program | | Yes | | | | OC/E/C | | |
| DOE 5480.10 | Contractor Industrial Hygiene Program | Yes | Yes | Yes | Yes | | OC/E/C | | |
| DOE 5480.11 | Radiation Protection for Occupational Workers | | Yes | | | | OC/E/C | | |
| DOE 5480.13A | Aviation Safety | | Yes | | | | OC | | Not a subcontractor responsibility |
| DOE 5480.16A | Firearms Safety | | Yes | | | | OC | | |
| DOE 5480.17 | Site Safety Representatives | | Yes | | | | OC | | |
| DOE 5480.18B | Nuclear Facility Training Accreditation Program | | Yes | | | | OC | | |
| DOE 5480.19 | Conduct of Operations Requirements for DOE Facilities | | Yes | Yes | Yes | | OC | | |
| DOE 5480.20A | Personnel Selection, Qualifications, and Training Requirements for DOE Nuclear Facilities | | Yes | Yes | Yes | | OC* | | *Only Attachment 1 applies directly to subcontractors |
| DOE 5480.21 | Unreviewed Safety Questions | | Yes | Yes | Yes | | OC* | | *E/C involvement needs to be based on OC procedure |
| DOE 5480.22 | Technical Safety Requirements | | Yes | Yes | Yes | | OC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB/SAR | WASRD | Responsible | Waiver Required | Comment |
|--------------------------|---|-----|---------|----------|---------|-------|-------------|-----------------|---|
| DOE 5480.23 | Nuclear Safety Analysis Reports | Yes | Yes | Yes | Yes | | OC | | |
| DOE 5480.24 | Nuclear Criticality Safety | Yes | Yes | Yes | | | OC | | Design requirements need to be sent to E/C |
| DOE 5480.26 | Trending and Analysis of Operations Information Using Performance Indicators | | Yes | Yes | | | OC | | Reportable Performance Indicator |
| DOE 5480.28 | Natural Phenomena Hazards Mitigation | Yes | Yes | | Yes | | OC/E* | | *E needs performance categories and equipment list |
| DOE 5480.29 | Employee Concerns Management System | | Yes | Yes | | | OC/E/C | | |
| DOE 5480.3 | Safety Requirements for the Packaging and Transportation of Hazardous Materials, Hazardous Substances, and Hazardous Wastes | | Yes | Yes | Yes* | | OC/E/C | | *Interface item- receipt acceptance requirement |
| DOE 5480.30 | Nuclear Reactor Safety Design Criteria | | Yes | | | | NA | | |
| DOE 5480.31 | Startup and Restart of Nuclear Facilities | Yes | Yes | Yes | | | OC | | |
| DOE 5480.4 | Environmental Protection, Safety, and Health Protecting Standards | Yes | Yes | Yes | Yes | | OC/E/C | | |
| DOE 5480.6 | Safety of DOE-Owned Nuclear Reactors | | Yes | | | | NA | | |
| DOE 5480.7 | Fire Protection | | | Yes* | | | OC | | |
| DOE 5480.7A | Fire Protection | Yes | Yes | Yes | | | OC/E/C | | *Canceled by DOE 5480.7A |
| DOE 5480.8A | Contractor Occupation Medical Program | | Yes | Yes | | | OC/E/C | | Required for DBE water supplies/ sprinklers |
| DOE 5480.9A | Construction Project Safety and Health Management | | Yes | Yes | Partial | | OC/E/C | | |
| DOE 5481.1B | Safety Analysis and Review System | | Yes | | Yes | | OC | | Related to tube covers and temporary walls |
| DOE 5482.1B | Environment, Safety, Health, and Quality Assurance Appraisal and Surveillance Program | | Yes | Yes | | | OC/E/C | | |
| DOE 5483.1A | Occupational Safety and Health Program for DOE Contractor Employees at Government-Owned Contractor-Operated (GOCO) Facilities | Yes | Yes | Yes | Yes | | NA | | |
| DOE 5484.1 | Environmental Protection, Safety, and Health Protection Information Reporting Requirements | Yes | Yes | Yes | | | OC/E/C | | |
| DOE 5500.10 | Emergency Readiness Program | | Yes | | Yes | | OC* | | E/C's role should be passed down via OC procedures(s) |
| DOE 5500.1B | Emergency Management System | | Yes | Yes | | | O* | | E/C's role should be passed down via OC procedures(s) |
| DOE 5500.2B | Emergency Categories, Classes, and Notification and Reporting Requirements | | Yes | | | | OC* | | E/C's role should be passed down via OC procedures(s) |
| DOE 5500.3A | Planning and Preparedness for Operational Emergencies | | Yes | Yes | | | OC* | | E/C's role should be passed down via OC procedures(s) |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FOH CON | SNF SRDS | CSRSAR | WASRD | Responsible | Waiver Required | Comment |
|--------------------------|---|-----|---------|----------|---------|-------|-------------|-----------------|---|
| DOE 5500.4A | Public Affairs Policy and Planning Requirements for Emergencies | | Yes | | | | OC/E/C | | |
| DOE 5500.7B | Emergency Operating Records Protection Program | Yes | | | | | OC* | | E/C roll should be passed down via OC procedures |
| DOE 5530.1A | Accident Response Group | | Yes | | | | OC | | |
| DOE 5530.2 | Nuclear Emergency Search Team | | Yes | | | | OC | | |
| DOE 5530.3 | Radiological Assistance Program | | Yes | | | | OC/E/C* | | *As needed basis |
| DOE 5530.4 | Aerial Measuring System | | Yes | | Partial | | OC | | Monitoring of air & site by others |
| DOE 5530.5 | Federal Radiological Monitoring and Assessment Center | | Yes | | | | NA | | Staffing the FRMAC team is DOE's responsibility |
| DOE 5560.1A | Priorities and Allocations Program | | Yes | | | | OC/E/C | | |
| DOE 5610.13 | Joint Department of Energy/Department of Defense Nuclear Weapon Safety, Security, and Control | | Yes | | | | NA* | | This is a facility operator's responsibility to control nuclear weapons |
| DOE 5610.14 | Transportation Safeguards System Program Operations | | Yes | | | | NA* | | Applies to the Albuquerque office only |
| DOE 5610.2 | Control of Weapon Data | | Yes | | | | NA* | | Not related to this project |
| DOE 5630.11 | Safeguard and Security Inspection and Assessment Program | | | Yes* | | | OC | | *Canceled by DOE 5600.12 |
| DOE 5630.12A | Safeguards and Security Inspection and Assessment Program | | Yes | | | | NA* | | Not related to this project |
| DOE 5631.2C | Personnel Security Program (Chapters H-X only) | | Yes | Yes | | | OC/E/C* | | *E/C to the degree directed from OC |
| DOE 5631.4A | Control of Classified Visits | | | Yes* | | | OC | | *Canceled order |
| DOE 5632.1B | Safeguards and Security | | Yes* | Yes* | | | OC | | *Canceled by DOE 5632.1C |
| DOE 5632.1C | Protection and Control of Safeguards and Security Interests | Yes | Yes | Yes | | | OC/E/C | | |
| DOE 5632.7A | Protection Force Program | | Yes | | | | OC | | |
| DOE 5633.3B | Control and Accountability of Nuclear Materials | | Yes | Yes | | | OC* | | Applies to the operator of the facility |
| DOE 5639.5 | Reporting (Safeguards/Security) Violations | | | Yes* | | | OC | | *Canceled order |
| DOE 5650.2B | Identification of Classified Information | | Yes | | | | OC* | | *The OC needs to classify documents |
| DOE 5660.1B | Management of Nuclear Materials | | Yes | | | | OC* | | *An operations functions |
| DOE 5670.1A | Management and Control of Foreign Intelligence | | Yes | | | | OC/E/C | | |
| DOE 5670.3 | Counterintelligence Program | | Yes | | | | NA | | Not applicable to this project |
| DOE 5700.6C | Quality Assurance | | Yes | | | | OC/E/C | | |
| DOE 5700.7C | Work Authorization System | | Yes | | | | NA | | Applies to M+O contractors only |
| DOE 5800.1A | Research and Development Laboratory Technology Transfer Program | | Yes | | | | NA | | Not on this project |
| DOE 5820.2A | Radioactive Waste Management | Yes | Yes | Yes | | | OC/E/C | | id's waste, quantity interface requirements |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNC SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|--------------------------|--|-----|---------|----------|---------|-------|-------------|-----------------|--|
| DOE 6430.1A | General Design Criteria | Yes | Yes | Yes | Yes | | OC/E/C | | SAR exemption for Fire Protection/Sprinklers |
| DOE C 425.1 | | | | Yes | | | OC | | |
| DOE C 471.2 | | | | Yes | | | OC/EC | | |
| DOE M 471.2-1 | Manual for Classified Matter Protection & Control | | Yes | | | | OC | | |
| DOE M 5632.1C-1 | Manual for Protection and Control of Safeguards and Security Interests | Yes | Yes | Yes | | | OC/E/C* | | *E/C's role should be passed down via OC procedures - In CSB Performance Spec. |
| DOE M 5632.7-1 | Firearms Qualifications Courses Manual | | Yes | | | | NA | | Applies to security contractor like Protec |
| DOE M 5639.6A-1 | Manual of Security Requirements for the Classified Automated Information System Security Program | | Yes | | | | NA* | | *Canceled order |
| DOE N 5400.0 | Sealed Radioactive Source | | Yes | | | | OC* | | *E/C involvement should be further defined |
| DOE N 5480.11 | Extension of Radiological Control Manual, Rev. 1 | | Yes | | | | OC/E/C | | |
| DOE O 130.1 | Budget Formulation Process | | Yes | | | | OC/E/C | | |
| DOE O 232.1 | Occurrence Reporting & Processing of Operations Information | | Yes | Yes | Yes | | OC/E/C | | |
| DOE O 430.1 | Life-Cycle Asset Management | | Yes | | | | OC | | |
| DOE O 440.1 | Occupational Safety and Health | | | | | | NA | | |
| DOE O 460.1 (1955a) | Packaging and Transportation Safety | Yes | | | Yes | | OC/E/C | | Not used on CSB (W 464) |
| DOE O 470.1 | Safeguards and Security Program | | Yes | | Yes | | OC | | Via DOE direction cc:Mail RL897-011 dated 1/17/87 applicable by law |
| DOE O 471.1 | Identification & Protection of Unclassified Controlled Nuclear Information | | Yes | Yes | | | OC/E/C | | Receiving and shipping to check compliance |
| DOE O 471.2 | Information Security Program | | Yes | | | | OC/E/C | | |
| DOE O 472.1 | Personnel Security Activities | | Yes | | | | OC/E/C | | |
| DOE O 534.1 | Accounting | | Yes | | | | OC | | |
| DOE-0223 | RI Emergency Implementing Procedures | | Yes | | | | OC/E/C | | |
| DOE-0225 | Hanford Emergency Assessment Resource Manual (HEARM) | | Yes | | | | OC | | To the degree applicable to this job |
| DOE-95-SWT-186 (1995c) | Hazardous Material Packaging and Shipping | Yes | | | Yes | | NA | | No within project scope |
| DOE-M-5632.1C | Safeguards and Security | | | | | | OC/E | | Receiving and Shipping Requirements |
| DOE-RL-HPS-SD-4.1 1993 | AE Civil Design Criteria, Design Loads for Facilities | | Yes | | Yes | | OC | | *Canceled by GC-LOAD and DOE 5480.28 |
| DOE-RWO328P | | | | | | | NA* | | |
| | | | | | | | OC | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | OSB SAR | WASRD | Responsible | Waiver Required | Comment |
|----------------------------|--|-----|---------|----------|---------|-------|------------------|-----------------|---|
| DOE-STD-1020-94 (1994d) | Natural Phenomena Hazard Design and Evaluation Criteria for Department of Energy Facilities | Yes | | | Yes | | OC | | Enveloped by NRC Equivalency |
| DOE-STD-1021-93 (1993a) | Performance Categorization Criteria for Structures, Systems, and Components at DOE Facilities Subject to Natural Phenomena Hazards | Yes | | | Yes | | OC | | Enveloped by NRC Equivalency |
| DOE-STD-1022-94 (1994e) | Natural Phenomena Hazards Site Characterization Criteria | Yes | | | Yes | | OC | | Enveloped by NRC Equivalency |
| DOE-STD-1023-95 (1995b) | Natural Phenomena Hazards Assessment Criteria | Yes | | | Yes | | OC | | Enveloped by NRC Equivalency |
| DOE-STD-1073-93 | Configuration Management | | | Yes | Yes | | OC | | |
| DOE-STD-3009-94 | Preparation Guide for Non-Reactor Nuclear Facility Safety Analysis Report | Yes | | | Yes | | OC | | |
| DOE-STD-3009-95 (1994f) | Preparation Guide for U.S. Department of Energy Non-Reactor Nuclear Facilities Safety Analysis Report | Yes | | | Yes | | OC | | Enveloped by NRC Equivalency |
| DOE/EH 0135 | Training Standards | | | | | | | | |
| DOE/EH 0135 TS.2.12 | | | | Yes | | | OC | | |
| DOE/EH 0135.OA.6 | | | | Yes | | | OC | | |
| DOE/EH 256T Article 616.34 | | | | Yes | | | OC | | |
| DOE/EH-0173T | | | | Yes | | | OC | | |
| DOE/EIS-0189 | Final Environmental Impact Statement for Tank Waste Remediation System | Yes | | | | | OC | | |
| DOE/EM-0093 (DOE/EM 1995) | Waste Acceptance Produce Specifications for Verified High-level Waste Forms (WAPPS) | Yes | | | | | OC | | *HLW Study |
| DOE/EP-0180 | Standard for Fire Protection of AEC Electric Computer | | | Yes | | | OC* | | *But are for computer facilities and should be NA |
| DOE/EV-0043, 8-79 | Standards on Fire Protection for Portable Structures | | | | | | OC | | |
| DOE/EV-016194 | DOE Explosives Safety Manual | | | | | | OC | | |
| DOE/RL 94-02 Rev. 0 | Emergency Program Management | | | Yes | | | OC | | |
| DOE/RL 94-125 | Federal Building Self Protection Plan | | Yes | | | | OC | | |
| DOE/RL-92-36 (RL 1993a) | Hanford Site Housing and Rigging Manual | Yes | Yes | Yes | Yes | | NA | | Not within project scope |
| DOE/RL-92-49 | Radiological Assistance Program Plan - Region 8 | | | | | | OC/E/C | | Enveloped by NOG-1 |
| DOE/RL-93-75 | Hanford Facility Contingency Plan | Yes | | | | | OC | | |
| DOE/RL-94-02 | Hanford Emergency Response Plan | Yes | | | | | Major Contractor | | |
| DOE/RL-94-55 | Hanford Analytical Services QA Plan | Yes | Yes | | Yes | | OC | | |
| DOE/RL-94-97 | Selection of Analytical Methods for Mixed Waste Analysis at Hanford | Yes | Yes | | | | NA | | Not within project scope |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|-----------------------------|---|-----|---------|----------|---------|-------|-------------|-----------------|---|
| DOE/RW-033P (DOE/RW 1995) | Quality Assurance Requirements and Description for Civilian Radioactive Waste Management (QARW) | Yes | | Yes | Yes | | OC/E/C | | |
| DOE/RW-0351P (DOE/RW 1995) | Waste Acceptance System Requirements Documents (WASRD) | Yes | | | | | NA | | |
| FF-01 | Radionuclide Emissions | | | Yes | | | OC/E | | |
| Generic Letter 88-14 | Instrument Air Supply/Safety Related Equipment | | | | Yes | | OC/E | | |
| HNF-MP-599 Rev.1 | FDH Quality Assurance Program Description | Yes | | | | | OC/E | | |
| HSL&T-1 | Hanford Site Lock and Tag Standard Manual | Yes | Yes | | | | OC/E/C | | |
| HSCRM-1 (RL 1993b) | Hanford Site Radiological Control Manual | Yes | | | Yes | | OC/E/C | | |
| ICBO (ICBO 1991) | Uniform Plumbing Code | Yes | | | Yes | | OC/E/C | | |
| ICBO (ICBO 1994) | Uniform Building Code | Yes | | | Yes | | OC/E/C | | |
| IEE C2-1993 (IEEE 1993) | National Electrical Safety Code | Yes | | | Yes | | OC | Required | Difference between UBC and NFPA |
| IES Standards (IES 1993) | Illumination Engineering Society of America | Yes | | | | | OC/E/C | | |
| ISO 9000 Series (ISO 1994) | Quality Management and Quality Assurance Standards | Yes | | | | | OC/E/C | | |
| MIL-STD-1472D (DOD 1993) | Human Engineering Design Criteria for Military System Equipment and Facilities | Yes | | | * | | NA* | | *Not Is CSB SAR |
| NEMA | National Electrical Manufacturers Association | Yes | | | | | OC/E | | By reference to CSB Human Factors and Control Room Analysis |
| NFPA 101 (NFPA 1994b) | Life Safety Code | Yes | | | Yes | | OC/E/C | | |
| NFPA 13 (NFPA 1994a) | Installation of Sprinkler Systems | Yes | | | | | OC/E/C | Required* | *Need decision on UBC or NFPA |
| NFPA 70 (NFPA 1993a) | National Electrical Code | Yes | | | Yes | | OC/E/C | Required | Need decision between UBC/NFPA |
| NFPA 72 (NFPA 1993b) | National Fire Alarm Code | Yes | | | Yes | | OC/E/C | Required* | *Need decision on UBC or NFPA |
| NRC Reg. Guide 1.26 | Quality Group Classification & Standards | | | | Yes | | OC/E/C | Required* | *Need decision on UBC or NFPA |
| NRC Reg. Guide 1.3 | Loss of Coolant Accident | | | | Yes | | OC | | |
| NRC Reg. Guide 1.78 (1974a) | Habitability of Nuclear Power Plant Control Rooms During Postulated Hazardous Chemical Release | | | | Yes | | NA | | Not within project scope |
| NRC Reg. Guide 3.48 | Format for the Safety Analysis Report | | | | Yes | | NA | | Not within project scope |
| NRC Reg. Guide 3.60 | Design of an Independent Spent Fuel Storage Installation | | | | Yes | | OC | | |
| NUREG-0554 (NRC 1979) | Single Failure-Proof Cranes for Nuclear Power Plants | Yes | | | Yes | | OC/E | | |
| | | | | | Yes | | NA | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|------------------------------------|---|-----|---------|----------|---------|-------|-------------|-----------------|---|
| NUREG-0700 (NRC 1981) | Guidelines for Control Room Design Reviews | Yes | | | | | | | *Via the CSB Performance Spec. |
| NUREG-0800 (NUREG/CFR-0098 (1978)) | Standard Review Plan Development Criteria for Seismic Review of Selected Nuclear Power Plants | | | | Yes | | OC | | *Performance Spec |
| OSHA-15-1.12-14 (1978) | Guards for Rotating Equipment | | | | Yes | | NA | | Not within project scope - already established by CSB |
| PNL-6577 (PNL 1988) | Health Physics Manual for Good Practice for Reducing Exposure to Levels that are ALARA | Yes | | | | | OC/E/C | | |
| Public Law 91-596 | | | | | | | NA | | |
| RCRA-B (DM) 940829 | Dangerous Waste Regulations | Yes | | Yes | | | OC/EC | | |
| RLID 1300.1C | Richland Operations Office Facility Representative Program | | Yes | Yes | | | OC | | |
| RLID 1360.2B | Unclassified Computer Security Program | | Yes | | | | NA* | | *Not applicable to this project |
| RLID 232.1 | occurrence Reporting and Processing of Operations Information | | Yes | | | | OC/E/C | | If deemed applicable to this project |
| RLID 425.1 | | | | | | | OC/E/C | | |
| RLID 430.1 | Systems Engineering Criteria Document and Implementing Directive | | Yes | Yes | | | OC | | |
| | | | | | | | OC* | | *E/C's role must be addressed per project/job - see CSB Performance Spec. and System Engineering Functional Requirements Document |
| RLID 471.2 | Informational Security Program | | Yes | | | | OC/E/C | | |
| RLID 473.1 | Protection of Safeguards and Security Interests | | Yes | Yes | | | OC/E/C | | |
| RLID 5000.1 | Baseline Execution and Management Process | | Yes | | | | OC | | |
| RLID 5000.2 | Long Range Planning Process | | Yes | | | | OC | | |
| RLID 5480.7 | Fire Protection | | Yes | | | | OC* | | |
| RLID 5480.13A | Aviation Safety | | Yes | Yes | | | OC | | |
| RLID 5480.19 | Conduct of Operations Requirements for RL | | Yes | | | | NA | Required | Not applicable to this project |
| RLID 5480.29 | RL Employee Concerns Program | | Yes | | | | OC | | Cancelled by DOE 5480.7A |
| RLID 5480.31 | Startup and Restart of Nuclear Facilities | | Yes | | | | OC | | Not applicable to this job scope |
| RLID 5633.3 | Control and Accountability of Nuclear Materials at RL | | Yes | | | | OC/E/C* | | * Only on RL request basis |
| RLID 5635.1 | Special Access and Top Secret Access Authorization | | Yes | | | | NA | | Not within the scope of project |
| RLID 5670.3 | Counterintelligence Program | | Yes | | | | NA | | Not within the scope of project |
| RLIP 1322.1B | RL Forms Management | | Yes | | | | NA | | Not within the scope of project |
| | | | Yes | | | | NA | | Not within the scope of project |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Replication | Title | DRD | FDH CON | SNF SRDS | CSB SAR | WASRD | Responsible | Waiver Required | Comment |
|---------------------------------|--|-----|---------|----------|---------|--------|-------------|-----------------|--|
| RLPD 5484-1A | Environmental Protection, Safety, and Health Protection Information Reporting Requirements | | Yes | | | | OC/E/C | | |
| RLPD 430.1 | Hanford Site Systems Engineering Policy | | Yes | | | | OC* | | *E/C's role must be identified by OC |
| RLPD 5000.1 | Site Management System | | Yes | | | | OC | | |
| SCS-W-98-576 | Drop Analysis of Multi-Canister Overpack in CSB | | Yes | | Yes | | OC/E | | |
| SEN-15-90 | National Environmental Policy Act | Yes | Yes | | | | OC | | |
| SEN-22-90 | DOE Policy on Signatures of RCRA Permit Applications | Yes | Yes | | | | OC | | |
| SEN-30A-92 | Slaying the Course for Technology Transfer at the Department of Energy | | Yes | | | | NA* | | *Not applicable to this project |
| SEN-35-91 | Nuclear Safety Policy | | Yes | Yes | | | NA* | | *Facility operator - this job would be governed by lower tier DOE Orders |
| SEN-39-92 | Department of Energy Occupational Safety and Health (OSH) Incentives Programs | | Yes | | | | OC/E/C | | VFP, etc. programs |
| UBC | Uniform Building Code | Yes | | | | | OC/E/C | | |
| UPC | Uniform Plumbing Code | Yes | | | | | OC/E/C | | |
| WIA 7890008967-DW Part III 2B.h | Containers Utilized for Off-Site Shipment | | Yes | | | | OC | | |
| WAC 170-12 | Marking (Tank Vehicles) | | Yes | | | | OC | | |
| Section 050 (3) | Entrance by State | * | Yes | | | | OC | | |
| WAC 173-216, Section 110 | Underground Injection Control | | Yes | | | | OC | | *Via Performance Spec |
| WAC 173-218 | Dangerous Waste Regulations | Yes | Yes | | | NA | OC/E/C | | See NOC |
| WAC 173-303 | General Air Regulations* | Yes | Yes | * | | OC/E/C | OC/E/C | | See NOC |
| WAC 173-401 | Duty to Apply | Yes | Yes | * | | OC | OC/E | | See NOC |
| WAC 173-460 | Toxic Air Pollutants* | Yes | Yes | * | | OC/E | OC/E | | See NOC |
| WAC 173-480 | Ambient Air Quality Standards and Emission Limits for Radionuclides* | Yes | Yes | * | | OC/E | OC/E | | See NOC |
| WAC 197-11, Section 305 | Categorical Exemptions | | Yes | | | NA | | | |
| WAC 212-80 | Radiation Protection - Air Emissions* | Yes | Yes | | | OC/E/C | | | |
| WAC 246-247 | On Site Sewage System* | Yes | Yes | * | | OC | | | Less restrictive than 40 CFR 50 (Concentration driven) see NOC |
| WAC 246-272 | Public Water Supplies | Yes | | * | | OC | | | See NOC |
| WAC 246-290 | | Yes | | | | OC | | | See NOC |
| WAC 246-292 | | | Yes | | | OC | | | |
| WAC 296-52, Sec. 31.40 | Marking | | Yes | | | OC | | | |
| WAC-173-303 Section 190 (3) | | | Yes | | | OC | | | |

Project W-464 Engineer/Constructor Requirements Matrix

| Requirement & Regulation | Title | DRD | FDH CON | SNF SRDS | CSB/SAP | WASRD | Responsible | Waiver Required | Comment |
|------------------------------|--|-----|---------|----------|---------|-------|-------------|-----------------|---|
| WAC-173-400 | Construction Application | | | Yes | | | OC/C | | |
| WHC-CM-1-5, Section 7.3 | Identifying and Resolving Unreviewed Safety Questions | | | | Yes | | OC/E | | |
| WHC-CM-2-14 | Hazardous Materials Packaging and Shipping | Yes | | | * | | NA | | *Shipping and Receiving requirements |
| WHC-CM-4-29 | Nuclear Criticality Safety Manual | Yes | | | Yes | | OC | | |
| WHC-CM-4-3 | Industrial Safety Manual | Yes | | | Yes | | NA | | |
| WHC-CM-4-40 | Industrial Hygiene Manual | | | | Yes | | OC/E | | *Reference: Sellers 1996 |
| WHC-CM-4-46 | Safety Analysis Manual | Yes | | | * | | OC/E/C | | |
| WHC-CM-6-12 | Project Department Procedures | | | | Yes | | OC/E/C | | |
| WHC-CM-7-5 | Environmental Compliance | Yes | | | Yes | | OC/E/C | | |
| WHC-EP-0063-04 (Willis 1993) | Hanford Site Solid Waste Acceptance Criteria | Yes | | | * | | NA | | *By reference in Waste Treatment Interface Document |
| WHC-IP-1043 (WHC-9959) | WHC Occupational ALARA Program | Yes | | | * | | OC/E/C | | *Equivalency Analysis |
| WHC-S-0425 | Performance Specification for the SNF-CSB | * | | | Yes | | OC/E/C | | *Can't Interface with mission |
| WHC-S-0468 | Specification for Multi-Canister Overpack Handling Machine | * | | | Yes | | OC/E/C | | *Can't Interface with mission |
| WHC-SD-DGS-30011 (WHC 1994) | Radiological Design Guide | Yes | | | * | | OC/E/C | | *Equivalency Analysis |
| WHC-SD-SNF-DB-003 (WHC 1994) | NRC Equivalency | | | Yes | | | OC/E | | |
| WHC-SD-SNF-DB-004 | SNF Seismic DC, NRC Equivalency Report | | | | Yes | | OC/E | | |
| WHC-SD-SNF-DB-009 | CSB Natural Phenomena/Hazards | | | | Yes | | OC/E | | |
| WHC-SD-SNF-FHA-002 (1995) | Fire Hazard Analysis for the CSB Vaults | | | | Yes | | OC/E | | |
| WHC-SD-SNF-HC-007 | Hazard Category Analysis for the Canister Storage Building | | | | Yes | | OC/E | | |
| WHC-SD-SNF-MP-001 (1995b) | SNF - Project Document Management Plan | | | | Yes | | OC/E/C | | |
| WHC-SD-SNF-PLN-012 | SNF - Project Integrated Safety Management Plan | | | | Yes | | OC/E/C | | |
| WHC-SD-SNF-QAPP-004 (1996) | SNF Quality Assurance Plan | | | | Yes | | NA | | QC will provide project QAPP |
| WHC-SD-SNF-TI-029 | Multi-Canister Overpack | | | | Yes | | OC/E | | |
| WHC-SD-W236-TI-002 | Probabilistic Seismic Hazard Analysis, DOE Hanford Site | | | | Yes | | OC/E | | |
| WHC-SR-113 (1995c) | Site Implementation Plan | | | | Yes | | OC | | |
| WHC-SP-1131 Rev. 0 | WHC QA Program Plan | | | Yes | | | OC | | |

APPENDIX L

SKETCHES

PROJECT TITLE:

W - 464



IMMOBILIZED HIGH-LEVEL WASTE
INTERIM STORAGE FACILITY

FOR:

U S DEPARTMENT OF ENERGY
RICHLAND OPERATIONS OFFICE

BY:

FLUOR DANIEL NORTHWEST



| | | | |
|---|------|------------------------------|------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| PROJECT TITLE | | PROJECT TITLE | |
| FLUOR DANIEL NORTHWEST | | IMMOBILIZED HIGH-LEVEL WASTE | |
| INTERIM STORAGE FACILITY | | INTERIM STORAGE FACILITY | |
| Prepared By | Date | Drawn By | Date |
| P. LAINO | | | |
| TITLE SHEET | | ES-W464-C00 | |
| | | 1 of 1 | |
| | | 0 | |

PROJECT TITLE:

W - 464

IMMOBILIZED HIGH-LEVEL WASTE
INTERIM STORAGE FACILITY

FOR:

U S DEPARTMENT OF ENERGY
RICHLAND OPERATIONS OFFICE

BY:

FLUOR DANIEL NORTHWEST



DRAWING SHEET TITLE

CIVIL

ES-W464-C00 SH 1 TITLE SHEET
ES-W464-C00 SH 2 SITE PLAN & DRAWING LIST

MECHANICAL


| | | |
|-------------|------|--|
| ES-W464-M01 | SH 1 | FACILITY LAYOUT OPERATIONS FLOOR PLAN |
| ES-W464-M01 | SH 2 | FACILITY LAYOUT VAULT FLOOR PLAN |
| ES-W464-M01 | SH 3 | FACILITY LAYOUT CROSS SECTION |
| ES-W464-M01 | SH 4 | FACILITY LAYOUT LONGIT SECTION |
| ES-W464-M01 | SH 5 | FACILITY LOAD-IN/LOAD-OUT ANNEX SECTIONS |
| ES-W464-M01 | SH 6 | FACILITY LAYOUT TRANSPORT TRAILER |
| ES-W464-M02 | SH 1 | OPERATION SEQUENCE CSB BLOCK DIAGRAM |
| ES-W464-M03 | SH 1 | MISC DETAILS |
| ES-W464-M04 | SH 1 | TEMPORARY COVERS |
| ES-W464-M05 | SH 1 | STANDARD/OVERPACK CANISTER STORAGE ARRANGEMENT |
| ES-W464-M05 | SH 2 | STANDARD/OVERPACK TUBE SHIELD PLUG ASSEMBLIES |
| ES-W464-M05 | SH 3 | STANDARD/OVERPACK TUBE ASSEMBLIES |
| ES-W464-M05 | SH 4 | STANDARD/OVERPACK TUBE BASE ASSEMBLIES |
| ES-W464-M05 | SH 5 | STANDARD/OVERPACK TUBE BELLows ASSEMBLIES |
| ES-W464-M06 | SH 1 | IMPACT ABSORBER & OVERPACK STATION CANISTER GUIDES |
| ES-W464-M07 | SH 1 | OVERPACK STATION PLAN & SECTION |
| ES-W464-M08 | SH 1 | OVERPACK WELD STATION GANTRY CRANE SECTION |
| ES-W464-M08 | SH 2 | OVERPACK WELD STATION GANTRY CRANE SECTIONS |
| ES-W464-M08 | SH 3 | OVERPACK WELD STATION CAP WELDER ASSEMBLY |
| ES-W464-M09 | SH 1 | 4.5 M CANISTER & 4.5 M OVERPACK |
| ES-W464-M10 | SH 1 | CUSTOM CANISTER OVERPACK ASSEMBLY |



OVERALL SITE PLAN



| | |
|---|---|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLUOR DANIEL NORTHWEST | |
| PROJECT TITLE | IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| DESIGNED BY | FLUOR DANIEL NORTHWEST |
| CHECKED BY | FLUOR DANIEL NORTHWEST |
| DATE | 1986 |
| PROJECT NO. | ES-W464-C00 |
| DRAWING NO. | 1046C008 |
| SCALE | AS SHOWN |
| REVISIONS | |
| NO. | 1 |
| DATE | 1986 |
| BY | FLUOR DANIEL NORTHWEST |
| DESCRIPTION | TITLE SHEET SITE PLAN & DRAWING LIST |




0 10 20


1-3




SURF STORAGE VAULT NO. 1 HLW CANISTER STORAGE VAULT NO. 2 HLW CANISTER STORAGE VAULT NO. 3


FACILITY VAULT PLAN

| | |
|--|-----------------------------------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| PROJECT TITLE FLUOR DANIEL NORTHWEST IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY | DRAWING NO. ES-W464-M01 |
| DRAWN BY  | SCALE 1" = 4'-0" |
| TITLE MECHANICAL FACILITY LAYOUT VAULT FLOOR PLAN | SHEET NO. 1 OF 2 464M01B |
| SHEET NO. 1 OF 2 464M01B | DATE 1-4 |









| | | | | | | | | | |
|---|--|--|------------------------------|--|--|--|--|--|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | | | | | | | |
| FLUOR DANIEL NORTHWEST | | | Project title | | | | | | |
| | | | IMMOBILIZED HIGH-LEVEL WASTE | | | | | | |
| | | | INTERIM STORAGE FACILITY | | | | | | |
| TIME | | | DATE | | | | | | |
| MECHANICAL FACILITY LOCATION | | | REV | | | | | | |
| LONGHILL SECTION | | | 0 | | | | | | |
| DESIGNED BY | | | CHECKED BY | | | | | | |
| DRAWN BY | | | DATE | | | | | | |
| SCALE | | | PROJECT NO. | | | | | | |
| SHEET NO. | | | SHEET TOTAL | | | | | | |




NOTE:
1. THE REGION AREA WITH LID SEVERE AS SET UNDER-CHARGE MAINTENANCE AREA BY PLACING GRATING OVER LID SEVERE AND USING A HOIST MECHANISM TO REMOVE SET COMPONENTS AS NECESSARY




| | | | |
|---|--------------------------|------------------------------|----------------------------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| FLUOR DANIEL NORTHWEST | | PROJECT TITLE | |
| IMMOBILIZED HIGH-LEVEL WASTE | | INTERIM STORAGE FACILITY | |
| Prepared by: CP2 | Title: MECHANICAL | Drawn by: ES-W464-MO1 | Scale: 1/4" = 1'-0" |
| FACILITY LOADING/LOADOUT | | ANNEX SECTIONS | |
| ANNEX SECTIONS | | ES-W464-MO1 | |
| 1/4" = 1'-0" | | 1/4" = 1'-0" | |




TOP VIEW



SIDE VIEW





CASK SECTION



END VIEW

- NOTES:
1. ESTIMATED CASK PLUS HLW CANISTER: 33 TON.
 2. MAXIMUM PAYLOAD AS SHOWN AT 32,000 LBS PER 4 WHEEL AXLE. TOTAL CURB WEIGHT WITH 3 AXLES IS: 48 TON.
 3. DIMENSIONS SHOWN ARE PRELIMINARY AND APPROXIMATE


| | |
|--|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| Prepared by: FLUOR DANIEL NORTHWEST | Project Title: IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| Checked by: P. LANE | Sheet No.: ES-W464-M01 |
| Drawn by: MECHANICAL FACILITY LAYOUT TRANSPORT TRAILER | Scale: 1/8" = 1'-0" |
| Drawn by: ES-W464-M01 | Rev: 0 |



- | | | | |
|---|----------|--|---|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | PROJECT TITLE: | |
| FLUOR DANIEL NORTHWEST | | IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY | |
| Drawn By: | DATE: | TIME: | |
| CSB | 02/28/90 | MECHANICAL | |
| OPERATING SEQUENCE | | ES-W464-M02 | |
| CSB BLOCK DIAGRAM | | 1 | 0 |
| 1 | 2 | 3 | 4 |
| 1640402 | | | |

Technical drawing of a shield plug assembly. The drawing includes a cross-sectional view on the left and a top view on the right. The cross-section shows a plug with a central hole and a flange, secured by a nut and washer. The top view shows the circular profile of the plug with concentric circles and a central hole. A label '2' points to the top view, and a label '3' points to the cross-section.

| UNLESS OTHERWISE SPECIFIED | |
|---|--|
| 1. DIMENSIONS AND TOLERANCES ARE IN INCHES | TOLERANCES: DECIMALS: .1 XX = .2 XX = .3 XX = .010 |
| 2. ALL MACHINED SURFACES SHALL BE 125 MAXIMUM | |
| 3. RIGID BORING AND BRUIN ALL SHARP EDGES .03 MAX | FRACTIONS: 1/16" |
| | MODULO: ± .005 |



The drawing shows a cross-section of a roof structure. A horizontal dimension line at the top indicates a length of 36'-10". Below it, another horizontal dimension line indicates a length of 36'-3 1/2". To the right of the main structure, a vertical dimension line indicates a height of 3 1/4". The structure consists of a series of horizontal lines representing the roof deck and joists, with small circles representing fasteners or nails.


UPPER CASK GUIDE

UPPER CASK GUIDE

UPPER CASK GUIDE


UPPER CASK GUIDE

- 10 GAGE THK ASTM A606
PL x 36"-10" LG WITH
11/16" HOLES TO MATCH
EXST BOLTS CAST IN PLACE



1 STANDARD TEMPORARY COVER ASSEMBLY
EXCESS +40

2 OVERPACK TEMPORARY COVER ASSEMBLY
EXCESS 9



SECTION A-A


NOTES:

1. THIS DRAWING PROVIDED FOR DEMOLITION/EXCESS ESTIMATING ONLY

| | |
|---|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLUOR DANIEL NORTHWEST | PROJECT TITLE: IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| Prepared By: P. LAING | MECHANICAL TEMPORARY COVERS |
| Drawn By: [Signature] | ES-W464-M04 |
| Scale: 1/8" = 1'-0" | Rev: 0 |
| L-11 | |

NO. 2-170811 GEN. EQL. CODES
REV. 10/01
DRAWING SECURITY 1507

| PARTS/MATERIAL LIST | | REFERENCE DRAWING | REV |
|---------------------|--------------------------------|-------------------|-----|
| QTY | DESCRIPTION | | |
| 1 | STANDARD CANISTER STORAGE | | 1 |
| 1 | OVERPACK CANISTER STORAGE | | 2 |
| 1 | STANDARD TUBE BASE ASSEMBLY | ES-W464-M05 SN 6 | 3 |
| 1 | STANDARD TUBE BASE ASSEMBLY | ES-W464-M05 SN 6 | 4 |
| 1 | STANDARD TUBE ASSEMBLY | ES-W464-M05 SN 4 | 5 |
| 1 | OVERPACK TUBE ASSEMBLY | ES-W464-M05 SN 4 | 6 |
| 1 | STANDARD LOWER IMPACT ABSORBER | ES-W464-M05 | 7 |
| 1 | OVERPACK LOWER IMPACT ABSORBER | ES-W464-M05 | 8 |
| 1 | STANDARD CANISTER | ES-W464-M09 | 9 |
| 1 | OVERPACK CANISTER | ES-W464-M09 | 10 |
| 1 | STANDARD UPPER IMPACT ABSORBER | ES-W464-M05 | 11 |
| 1 | OVERPACK UPPER IMPACT ABSORBER | ES-W464-M05 | 12 |
| 1 | STANDARD TUBE SHIELD PLUG ASST | ES-W464-M05 SN 3 | 13 |
| 1 | OVERPACK TUBE SHIELD PLUG ASST | ES-W464-M05 SN 3 | 14 |
| 1 | STANDARD TUBE COVER ASSEMBLY | ES-W464-M05 SN 2 | 15 |
| 1 | OVERPACK TUBE COVER ASSEMBLY | ES-W464-M05 SN 2 | 16 |
| 17 | | | 17 |
| 18 | | | 18 |
| 19 | | | 19 |
| 20 | | | 20 |



PLAN
SCALE 1/2" = 1'-0"

SECTION

1 STANDARD CANISTER STORAGE ARRANGEMENT
SCALE 1/2" = 1'-0"

PLAN
SCALE 1/2" = 1'-0"

SECTION


2 OVERPACK CANISTER STORAGE ARRANGEMENT
SCALE 1/2" = 1'-0"

| | |
|---|---|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| DESIGNED BY FLUOR DANIEL NORTHWEST | PROJECT TITLE IMMUNITIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| MECHANICAL STANDARD OVERPACK CANISTER STG ARRANGEMENT | ES-W464-M05 |
| 1 | 0 |


| ITEM NO. | QTY | UNIT | DESCRIPTION | REMARKS |
|----------|-----|------|--------------|---------|
| 1 | 1 | EA | PLATE 3" DIA | |
| 2 | 1 | EA | PLATE 3" DIA | |
| 3 | 1 | EA | PLATE 3" DIA | |
| 4 | 1 | EA | PLATE 3" DIA | |
| 5 | 1 | EA | PLATE 3" DIA | |
| 6 | 1 | EA | PLATE 3" DIA | |
| 7 | 1 | EA | PLATE 3" DIA | |
| 8 | 1 | EA | PLATE 3" DIA | |
| 9 | 1 | EA | PLATE 3" DIA | |
| 10 | 1 | EA | PLATE 3" DIA | |
| 11 | 1 | EA | PLATE 3" DIA | |
| 12 | 1 | EA | PLATE 3" DIA | |
| 13 | 1 | EA | PLATE 3" DIA | |

NOTES: UNLESS OTHERWISE SPECIFIED

1. FABRICATION AND ASSEMBLY OF THIS EQUIPMENT SHALL BE IN ACCORDANCE WITH SPECIFICATION 116-293-00-018 SECTION 10080.
2. THIS EQUIPMENT IS TO BE FIELDED BY CONSTRUCTION WITH THE FOLLOWING:
 - 3. TWO (2) PLYWOOD SHEETS TO BE USED FOR THE TOP PLATE, BUT IN THE 1/2" AND 1/4" THICKNESSES TO BE SPECIFIED BY CONTRACTOR. DIMENSIONS SHALL BE 14" x 17" AND THREE (3) PLYWOOD SHEETS TO BE USED FOR THE BOTTOM PLATE. DIMENSIONS SHALL BE 14" x 17" AND 1/4" THICK.
 - 4. THREE (3) PAIR STAINES ARE REQUIRED FOR THE EXTERIOR QUANTITY OF THEIR PLY COVER.
5. THE LETTERS REQUIRED ON THE TOP PLATE SHOULD BE AS SHOWN BELOW, USING ALL LETTERS OF THE ALPHABET EXCEPT I, O AND W.



- 1 STANDARD TUBE PLUG COVER ASSEMBLY
QUANTITY 440
- 2 OVERPACK TUBE PLUG COVER ASSEMBLY
QUANTITY 3



B TUBE PLUG COVER NUMBERING

[illegible]

CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1)

FLUOR DANIEL NORTHWEST
PRODUCT TITLE: **IMMOBILIZED HIGH-LEVEL WASTE
INTERMITTENT STORAGE FACILITY**




MECHANICAL
TUBE PLUG COVER

| | | | | |
|---|---------------------|-------------|-------------------------------|----------------------|
| 0 | Card No 1464M058 | ES-W464-M05 | IOBE PLUG COVER ASSEMBLIES | Original D. J. W. |
|---|---------------------|-------------|-------------------------------|----------------------|

| | |
|---------------------------|---------------------|
| M-2-120912 | CSB TUBE PLUG COVER |
| OWC NO | TITLE |
| DRAWING TRACEABILITY LIST | |

NOTES: UNLESS OTHERWISE SPECIFIED

1. FILL BOTTOM OF PLUG CAVITY WITH LIGHT WEIGHT INSULATING CONCRETE




SECTION
SCALE: 1/8

2 OVERPACK TUBE
SHIELD PLUG ASSEMBLY
QUANTITY 3

⑩ SHORT LIFTING LUG
PL-02X

| | |
|---|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLUOR DANIEL NORTHWEST | |
| PROJECT TITLE | IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| TITLE | MECHANICAL STANDARD/OVERPACK TUBE SHIELD PLUG ASSEMBLIES |
| Prepared by DATE DRAWN | ES-W464-M05 |
| REV | 0 |
| DATE | 12/16/80 |
| BY | W464M05C |


| PARTS/MATERIAL LIST | | | | |
|---------------------|-----|---------------|---------------------------|----------|
| QTY | REQ | PART/DASH NO. | MANUFACTURE/DESCRIPTION | MAT./REF |
| 1 | 1 | 010 | OVERPACK TUBE ASSEMBLY | 1 |
| 1 | 1 | 020 | STANDARD TUBE ASSEMBLY | 2 |
| 1 | 1 | 030 | STANDARD BELLOWS ASSEMBLY | 3 |
| 1 | 1 | 040 | OVERPACK BELLOWS ASSEMBLY | 4 |
| 1 | 1 | 050 | PIPE JOINT | 5 |
| 1 | 1 | 060 | CARBON STEEL PIPE | 6 |
| 1 | 1 | 070 | PLATE, 1/2" THK | 7 |





1 STANDARD TUBE ASSEMBLY
QUANTITY 440

2 OVERPACK TUBE ASSEMBLY
QUANTITY 3


| UNLESS OTHERWISE SPECIFIED | |
|---------------------------------|------------|
| 1. DIMENSIONS AND TOLERANCES | DIMENSIONS |
| 2. ALL DIMENSIONS ARE IN INCHES | DECIMALS |
| 3. ALL DIMENSIONS ARE IN INCHES | FRACTIONS |
| 4. DIMENSIONS ARE IN INCHES | FRACTIONS |
| 5. DIMENSIONS ARE IN INCHES | FRACTIONS |



| | |
|---|---------------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLUOR DANIEL NORTHWEST | PROJECT TITLE |
| IMMOBILIZED HIGH-LEVEL WASTE | PROJECT TITLE |
| INTERIM STORAGE FACILITY | PROJECT TITLE |
| MECHANICAL | DESIGN |
| STANDARD/OVERPACK | DESIGN |
| TUBE ASSEMBLIES | DESIGN |
| ES-W464-M05 | DESIGN |
| DESIGNED BY | DESIGNED BY |
| DATE | DATE |
| REV | REV |
| 0 | 0 |




* THIS SURFACE MUST BE PROTECTED DURING ALL MANUFACTURING PROCESSES



| | |
|------------------------|--|
| FLUOR DANIEL NORTHWEST | PROJECT TITLE: IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
|------------------------|--|

| ANALYSIS OF SAMPLES OBTAINED | |
|--|----------------|
| 1. DISINTEGRATION AND TOLUENE EXTRACTS | DISINTEGRATION |
| 2. ALL WOODS | EXTRACTS |
| 3. ALL WOODS | EXTRACTS |
| 4. ALL WOODS | EXTRACTS |
| 5. ALL WOODS | EXTRACTS |
| 6. ALL WOODS | EXTRACTS |
| 7. ALL WOODS | EXTRACTS |
| 8. ALL WOODS | EXTRACTS |
| 9. ALL WOODS | EXTRACTS |
| 10. ALL WOODS | EXTRACTS |
| 11. ALL WOODS | EXTRACTS |
| 12. ALL WOODS | EXTRACTS |
| 13. ALL WOODS | EXTRACTS |
| 14. ALL WOODS | EXTRACTS |
| 15. ALL WOODS | EXTRACTS |
| 16. ALL WOODS | EXTRACTS |
| 17. ALL WOODS | EXTRACTS |
| 18. ALL WOODS | EXTRACTS |
| 19. ALL WOODS | EXTRACTS |
| 20. ALL WOODS | EXTRACTS |
| 21. ALL WOODS | EXTRACTS |
| 22. ALL WOODS | EXTRACTS |
| 23. ALL WOODS | EXTRACTS |
| 24. ALL WOODS | EXTRACTS |
| 25. ALL WOODS | EXTRACTS |
| 26. ALL WOODS | EXTRACTS |
| 27. ALL WOODS | EXTRACTS |
| 28. ALL WOODS | EXTRACTS |
| 29. ALL WOODS | EXTRACTS |
| 30. ALL WOODS | EXTRACTS |
| 31. ALL WOODS | EXTRACTS |
| 32. ALL WOODS | EXTRACTS |
| 33. ALL WOODS | EXTRACTS |
| 34. ALL WOODS | EXTRACTS |
| 35. ALL WOODS | EXTRACTS |
| 36. ALL WOODS | EXTRACTS |
| 37. ALL WOODS | EXTRACTS |
| 38. ALL WOODS | EXTRACTS |
| 39. ALL WOODS | EXTRACTS |
| 40. ALL WOODS | EXTRACTS |
| 41. ALL WOODS | EXTRACTS |
| 42. ALL WOODS | EXTRACTS |
| 43. ALL WOODS | EXTRACTS |
| 44. ALL WOODS | EXTRACTS |
| 45. ALL WOODS | EXTRACTS |
| 46. ALL WOODS | EXTRACTS |
| 47. ALL WOODS | EXTRACTS |
| 48. ALL WOODS | EXTRACTS |
| 49. ALL WOODS | EXTRACTS |
| 50. ALL WOODS | EXTRACTS |
| 51. ALL WOODS | EXTRACTS |
| 52. ALL WOODS | EXTRACTS |
| 53. ALL WOODS | EXTRACTS |
| 54. ALL WOODS | EXTRACTS |
| 55. ALL WOODS | EXTRACTS |
| 56. ALL WOODS | EXTRACTS |
| 57. ALL WOODS | EXTRACTS |
| 58. ALL WOODS | EXTRACTS |
| 59. ALL WOODS | EXTRACTS |
| 60. ALL WOODS | EXTRACTS |
| 61. ALL WOODS | EXTRACTS |
| 62. ALL WOODS | EXTRACTS |
| 63. ALL WOODS | EXTRACTS |
| 64. ALL WOODS | EXTRACTS |
| 65. ALL WOODS | EXTRACTS |
| 66. ALL WOODS | EXTRACTS |
| 67. ALL WOODS | EXTRACTS |
| 68. ALL WOODS | EXTRACTS |
| 69. ALL WOODS | EXTRACTS |
| 70. ALL WOODS | EXTRACTS |
| 71. ALL WOODS | EXTRACTS |
| 72. ALL WOODS | EXTRACTS |
| 73. ALL WOODS | EXTRACTS |
| 74. ALL WOODS | EXTRACTS |
| 75. ALL WOODS | EXTRACTS |
| 76. ALL WOODS | EXTRACTS |
| 77. ALL WOODS | EXTRACTS |
| 78. ALL WOODS | EXTRACTS |
| 79. ALL WOODS | EXTRACTS |
| 80. ALL WOODS | EXTRACTS |
| 81. ALL WOODS | EXTRACTS |
| 82. ALL WOODS | EXTRACTS |
| 83. ALL WOODS | EXTRACTS |
| 84. ALL WOODS | EXTRACTS |
| 85. ALL WOODS | EXTRACTS |
| 86. ALL WOODS | EXTRACTS |
| 87. ALL WOODS | EXTRACTS |
| 88. ALL WOODS | EXTRACTS |
| 89. ALL WOODS | EXTRACTS |
| 90. ALL WOODS | EXTRACTS |
| 91. ALL WOODS | EXTRACTS |
| 92. ALL WOODS | EXTRACTS |
| 93. ALL WOODS | EXTRACTS |
| 94. ALL WOODS | EXTRACTS |
| 95. ALL WOODS | EXTRACTS |
| 96. ALL WOODS | EXTRACTS |
| 97. ALL WOODS | EXTRACTS |
| 98. ALL WOODS | EXTRACTS |
| 99. ALL WOODS | EXTRACTS |
| 100. ALL WOODS | EXTRACTS |




| | |
|---------------------------|------------------------|
| H-2-120393 | SID/OPACK BELLOWS ASSY |
| DWG NO | TITLE |
| DRAWING TRACEABILITY LIST | |


| | | | | |
|---|---|-------------------------------|---------------------------|-----|
| Prepared by: P. LAING MARCH 29, 1964  | Title: MECHANICAL STANDARD/OVERPACK BELLOWS ASSEMBLIES | Sketch no. ES-W464-M05 | Sh. of | Rev |
| | | | 5. Section 0664M05E | |

| PARTS/MATERIAL LIST | | QUANTITY | UNIT |
|---------------------|-----------------------------|----------|------|
| 1 | STANDARD TUBE BASE ASSEMBLY | 1 | |
| 2 | OVERPACK TUBE BASE ASSEMBLY | 3 | |
| 3 | | 4 | |
| 4 | | 5 | |
| 5 | | 6 | |
| 6 | PLATE, 1 THK | 6 | |
| 7 | PLATE, 1/2 THK | 7 | |



NOTES: UNLESS OTHERWISE SPECIFIED
1. INSTALLATION POSITIONS SHALL ALSO VERTICALLY WITH FLOOR EMBLEMERS
IN THE OPENING LEVEL CONCRETE SLAB ABOVE THE WALLS.



1 STANDARD TUBE BASE ASSEMBLY
SCALE: 1/4" = 1'-0"



2 OVERPACK TUBE BASE ASSEMBLY
SCALE: 1/4" = 1'-0"







NOTES: UNLESS OTHERWISE SPECIFIED
1. INSTALLATION POSITIONS SHALL ALSO VERTICALLY WITH FLOOR EMBLEMERS
IN THE OPENING LEVEL CONCRETE SLAB ABOVE THE WALLS.





| | |
|---|---------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLOOR DANIEL NORTHWEST | |
| MECHANICAL | |
| STANDARD/OVERPACK | |
| TUBE BASE ASSEMBLIES | |
| ES-W464-M05 | 164405F |

| PARTS/MATERIAL LIST | | | | QTY | RECD | PART/QUANTITY | MATERIAL/REFERENCE | IND |
|---------------------|--|-----------|---|-----|------|---------------|--------------------|-----|
| 1 | | IMP-001-U | IMPACT ABSORBER UPPER ASSEMBLY | 4 | | | | 1 |
| 2 | | IMP-001-L | IMPACT ABSORBER LOWER ASSEMBLY | 4 | | | | 2 |
| 3 | | IMP-002-U | OVERPACK IMPACT ABSORBER UPPER ASSEMBLY | 1 | | | | 3 |
| 4 | | IMP-002-L | OVERPACK IMPACT ABSORBER LOWER ASSEMBLY | 1 | | | | 4 |
| 5 | | IMP-003-U | IMPACT ABSORBER UPPER ASSEMBLY | 1 | | | | 5 |
| 6 | | IMP-003-L | IMPACT ABSORBER LOWER ASSEMBLY | 1 | | | | 6 |
| 7 | | IMP-004-U | IMPACT ABSORBER UPPER ASSEMBLY | 1 | | | | 7 |
| 8 | | IMP-004-L | IMPACT ABSORBER LOWER ASSEMBLY | 1 | | | | 8 |
| 9 | | IMP-005-U | IMPACT ABSORBER UPPER ASSEMBLY | 1 | | | | 9 |
| 10 | | IMP-005-L | IMPACT ABSORBER LOWER ASSEMBLY | 1 | | | | 10 |







2 STANDARD IMPACT ABSORBER UPPER ASSEMBLY QUANTITY 4

4 OVERPACK IMPACT ABSORBER UPPER ASSEMBLY QUANTITY 1



1 STANDARD IMPACT ABSORBER LOWER ASSEMBLY QUANTITY 4

3 OVERPACK IMPACT ABSORBER LOWER ASSEMBLY QUANTITY 1



LOWER CANISTER GUIDE QUANTITY 4



UPPER CANISTER GUIDE QUANTITY 1

OVERPACK WELD STATION CANISTER GUIDES

NOTES: UNLESS OTHERWISE SPECIFIED
1. IMPACT ABSORBER UPPER PLATE SHALL BE IDENTICAL TO CANISTER CONFIGURATION.


- 1. DIMENSIONS AND TOLERANCES: DIMENSIONS: X = 1/16, Y = 1/32, Z = 1/64, W = 1/8, V = 1/16, U = 1/32, T = 1/64, S = 1/128, R = 1/256, Q = 1/512, P = 1/1024, O = 1/2048, N = 1/4096, M = 1/8192, L = 1/16384, K = 1/32768, J = 1/65536, I = 1/131072, H = 1/262144, G = 1/524288, F = 1/1048576, E = 1/2097152, D = 1/4194304, C = 1/8388608, B = 1/16777216, A = 1/33554432.
- 2. ALL DIMENSIONS ARE TO BE TAKEN FROM THE CENTER OF GRAVITY UNLESS OTHERWISE SPECIFIED.
- 3. DIMENSIONS ARE TO BE TAKEN FROM THE CENTER OF GRAVITY UNLESS OTHERWISE SPECIFIED.
- 4. DIMENSIONS ARE TO BE TAKEN FROM THE CENTER OF GRAVITY UNLESS OTHERWISE SPECIFIED.

| | |
|--|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| FLUOR DANIEL NORTHWEST | PROJECT TITLE: IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY |
| MECHANICAL | DESIGN NO. ES-W464-M06 |
| IMPACT ABSORBERS & OVERPACK WELD STATION CANISTER GUIDES | DATE: 1/15/2006 |
| ES-W464-M06 | REV: 0 |




PLAN


SECTION G




SECTION C



SECTION D




| | | | |
|---|--|------------------------------|--|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| FLUOR DANIEL NORTHWEST | | PROJECT TITLE | |
| PLANNING | | IMMOBILIZED HIGH-LEVEL WASTE | |
| MECHANICAL | | INTERIM STORAGE FACILITY | |
| PLAN & SECTION | | ES-W464-M07 | |
| 1664407 | | 1664407 | |
| 0 | | 0 | |



OVERPACK WELD STATION
GANTRY CRANE SECTION





| | | | |
|---|------|--------------------------|-----|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| PROJECT TITLE | | FLUOR DANIEL NORTHWEST | |
| IMMOBILIZED HIGH-LEVEL WASTE | | INTERIM STORAGE FACILITY | |
| MECHANICAL | | OVERPACK WELD STATION | |
| GANTRY CRANE SECTION | | ES-W464-M08 | |
| Drawn By | Time | Checked By | Rev |
| 1 | 3 | 1 | 0 |
| 1664008 | | | |




ELEVATION
LOOKING NORTH

1 INSTALLATION
LOOKING WEST
ELECTRICAL AND UTILITY
LINES ARE NOT SHOWN


| | | | |
|---|----------|--------------------------|------------------------------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| FLUOR DANIEL NORTHWEST | | PROJECT TITLE | |
| Prepared by: | DATE | MECHANICAL | PROJECT TITLE |
| P. L. AND | 01/10/08 | OVERPACK WELD STATION | IMMOBILIZED HIGH-LEVEL WASTE |
| GANTRY CRANE INSTALLATION | | INTERIM STORAGE FACILITY | |
| ES-W464-M08 | 2 | 3 | 0 |
| 164M08 | | | |



2 INSPECTION ASSEMBLY (ULTRASONIC WELD INSPECTION STATION)



1 ASSEMBLY (OVERPACK CAP WELDER)




| | |
|---|-----------------------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | |
| PROJECT TITLE | |
| FLUOR DANIEL NORTHWEST | |
| IMMOBILIZED HIGH-LEVEL WASTE | |
| INTERIM STORAGE FACILITY | |
| Prepared By | MECHANICAL |
| Checked By | OVERPACK WELD STATION |
| Drawn By | CAP WELDER ASSEMBLY |
| ES-W464-M08 | |
| Rev | 0 |
| Issued | 3 |
| Revised | 3 |
| Revised | 0 |

CANISTER ASSEMBLY NOTES:


TOTAL NOMINAL WEIGHT AS SHOWN = 3751 kg (8,290 lbs)
TOTAL MAXIMUM WEIGHT = 4200 kg (9,282 lbs)

CANISTER OVERPACK NOTES:

ALL WELDED CONSTRUCTION
NEW COVER DESIGN
MATERIAL THICKNESS .95 CM (ASTM A240 304L)



CANISTER
SEE NOTE 1.



CANISTER OVERPACK
SEE NOTE 2.

NOTES:

1. CANISTER PROVIDED BY OTHERS.
2. PROJECT W-464 TO PROVIDE 2 CANISTER OVERPACKS


| | | | |
|---|------------|--|-----|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| PROJECT TITLE | | FLUOR DANIEL NORTHWEST | |
| IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY | | MECHANICAL & 4.5M CANISTER & 4.5M OVERPACK | |
| Prepared by | Checked by | Drawn by | Rev |
| P. LAING | | | |
| 1 | | | 0 |
| 164409 | | | |

NOTES:

- 1. QUANTITY = 2 PROVIDED BY PROJECT W-464
- 2. Cs WASTE CANISTER BY OTHERS.


CARRIAGE ASSEMBLY NOTES

ALL WELDED CONSTRUCTION
NEW COVER DESIGN, MATERIAL ASTM A240 304L
MATERIAL THICKNESS 1/2" UNO




THIS DEVICE IS A COMBINATION OF THE FOLLOWING:
CANISTER COVER ASSEMBLY
LOCKING & LIFTING RING
CANISTER COLLAR


CS MODIFIED COVER/LIFT RING



ELEVATION



SECTION A-A



SECTION B-B

| | | | |
|---|------------------|--|--------|
| CONCEPTUAL DESIGN PROJECT W-464 (PHASE 1) | | | |
| FLUOR DANIEL NORTHWEST | | PROJECT TITLE: IMMOBILIZED HIGH-LEVEL WASTE INTERIM STORAGE FACILITY | |
| Prepared By: P. LAINO | TIME: MECHANICAL | DATE: 1/16/2010 | Rev: 0 |
| CESIUM CANISTER OVERPACK ASSEMBLY | | ES-W464-M10 | |

DISTRIBUTION SHEET

| | | |
|--------------------------|----------------|---------------|
| To | From | Page 1 of 1 |
| DISTRIBUTION | K. C. BURGARD | Date 04-09-98 |
| Project Title/Work Order | EDT No. 624079 | |
| W-464 HLW | ECN No. | |

| Name | MSIN | Text With All Attach. | Text Only | Attach./ Appendix Only | EDT/ECN Only |
|-------------------|-------|-----------------------------|-----------|------------------------------|-----------------|
| CENTRAL FILES | B1-07 | X | | | |
| CA PETERSEN | H6-37 | X | | | |
| RB CALMUS (3) | H6-37 | X | | | |
| KC BURGARD (2) | H6-37 | X | | | |
| JF BORES | G3-21 | X | | | |
| ML DEFFENBAUGH | H6-37 | X | | | |
| RJ MURKOWSKI | H6-37 | X | | | |
| RW ROOT | H6-12 | X | | | |
| DL BURT | G3-21 | X | | | |
| SM O'TOOLE | G3-21 | X | | | |
| JN ALIBERT | S2-48 | X | | | |
| WT THOMPSON | G3-21 | X | | | |
| JB PAYNE | H6-37 | X | | | |
| PROJECT FILES (2) | H6-08 | X | | | |
| FM SIMMONS | S6-60 | X | | | |