

CONF-801107-16

Proposed for Presentation at the
Conference on
Remote Systems Technology
November 17-21, 1980 Washington D.C.

MASTER

A UNIQUE SAMPLING AND TRANSFER SYSTEM FOR
THE FLUORINEL DISSOLUTION AND STORAGE FACILITY

M.E. Jacobson, J.A. Carter, D.M. Paige - Exxon Nuclear Idaho Co.

Liquid sampling, sample transfer and analytical systems for the Fluorinel Dissolution and Storage Facility (FAST) are required for monitoring feed and process solutions on a constant basis during fuel dissolution. This head end system includes three dissolvers that are operated in a sequential batch dissolution process. Due to this sequential type operation, sampling becomes very important in monitoring and tracking the dissolution phase of each dissolver. Liquid samples are taken quite frequently during certain phases of the decladding step and again during the dissolution of the fuel. It is very important in this process that the liquid samplers (Figure 1) function well, are reliable and designed so that the samples can be taken remotely. Samples must be transferred to an analytical cell for analysis. Analytical results are continually returned to operating personnel so that required feed adjustments can be initiated. Liquid samples are also taken from other process vessels in the system. Results of samples taken will then allow complete monitoring of the process.

The sampling cell also contains a pneumatic transfer system sender/receiver (Figure 2) designed for rapid and reliable sample transfer. This transfer system will be operated and maintained remotely so simplicity and reliability has again been emphasized.

To fulfill the process requirements, sample stations are designed to provide representative samples of all process streams and of adequate quantity for analytical needs. Also the samplers must be designed so that they can be

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

REA

easily maintained remotely and operated in a manner that will minimize the spread of contamination and radiation exposure to operating personnel.

The sampling cell is a shielded facility located in the FAST building and adjacent to the dissolver cell. This sampling cell contains 10 liquid samplers, a pneumatic sample transfer sender/receiver, a decontamination service station, plastic transfer capsule capper/decapper and a sample bottle evacuation chamber. This cell will be remotely operated and maintained using two shielding windows, three Model "G" master-slave manipulators and small hand tools. The hand tools have been modified for handling with manipulators. An airlock type entrance with an interlock shielding door has been located at one end to allow access into and out of the cell. This airlock has been sized adequately to allow transfer of all sampling equipment located inside the cell.

A mockup of the sampling cell has been installed for equipment checkout and personnel training in the Remote Maintenance Test Facility (RMTF). This mockup is full scale in cross section and two thirds of the actual sampling cell length. The mockup is equipped with two Model "G" master-slave manipulators, a window simulating the size and viewing angles of an actual window, a shielding door and the utilities required to demonstrate sampling techniques. Equipment installed inside the cell is full scale and consists of a sample station, plastic transfer capsule, capper/decapper, sender/receiver station, sample bottle evacuation chamber and a decontamination service station. This mockup was used extensively for testing and checkout during the early stages of the facility design. Testing and checkout consisted of checking space requirements, viewing capabilities, and remote handling requirements for operation and maintenance. Mockup design also allowed testing of the samplers in three different locations. These locations simulated all of the locations that will be required in the actual facility. Time studies were incorporated into the testing program to assure that sampling, capsule capping, loading capsules into the sender receiver, bottle evacuation, and maintenance could be accomplished readily, reliably and expeditiously using remote techniques.

Page 3

This sampling system is quite unique in design and remote maintenance has been greatly simplified. Sampling and transfer of the samples will reduce radiation exposure to operating personnel and reduce spreading of contamination. Full scale mockup and testing of these systems show them to be reliable, functional and workable. Simplicity in operation and remotability make this system very attractive for use in radioactive liquid handling facilities.




Figure 1 FAST Liquid Sampler



Figure 2 Pneumatic Transfer
Sender/Receiver