

# **NOTICE**

**CERTAIN DATA  
CONTAINED IN THIS  
DOCUMENT MAY BE  
DIFFICULT TO READ  
IN MICROFICHE  
PRODUCTS.**

X-OE-231, Vol. 4

**MARTIN MARIETTA**

Received by NOTJ  
FEB 21 1992

## **Preliminary Decommissioning Study Reports**

### **Volume 4: Gunite Storage Tanks**

J. R. Horton

September 1984

Oak Ridge National Laboratory  
Oak Ridge, Tennessee 37830

operated by  
Martin Marietta Energy Systems, Inc.  
for the  
DEPARTMENT OF ENERGY

OPERATED BY  
MARTIN MARIETTA ENERGY SYSTEMS, INC.  
FOR THE UNITED STATES  
DEPARTMENT OF ENERGY

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

NTIS price codes—Printed Copy: A10 Microfiche A01

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

September 1984

X-OE-231, Vol. 4

ORNL/M--1921

DE92 008112

Engineering Division

PRELIMINARY DECOMMISSIONING STUDY REPORTS

Volume 4: GUNITE STORAGE TANKS

J. R. Horton

Approved by:

F. J. Peretz 9-24-84  
F. J. Peretz, Principal Engineer, Engineering Division

N. W. Durfee 9-24-84  
N. W. Durfee, Project Engineer, Engineering Division

T. E. Myrick 9/24/84  
T. E. Myrick, ORNL Suprlus Facilities Management Program

Prepared for U.S. Department of Energy  
under U.S. Government Contract DE-AC05-84OR-21400

U.41.M

MASTER   
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

## CONTENTS

	<u>Page</u>
LIST OF FIGURES .....	v
LIST OF TABLES .....	v
1. INTRODUCTION .....	1
2. FACILITY DESCRIPTION .....	1
2.1 Location and Adjacent Facilities .....	2
2.2 Tank Construction .....	2
2.3 Tank History, Use, and Contents .....	7
2.4 Radiological Characterization .....	9
3. DECOMMISSIONING ALTERNATIVES ASSESSMENT .....	10
4. DESCRIPTION OF THE DECOMMISSIONING PLAN .....	14
5. COST ESTIMATE .....	16
6. SCHEDULE .....	17
7. REFERENCES .....	17
APPENDIX I.....	21
APPENDIX II .....	33

## LIST OF FIGURES

1	Location of the Gunitite Storage Tanks at the Oak Ridge National Laboratory .....	3
2	Aerial View of the Gunitite Storage Tanks in the South Tank Farm Prior to Sludge Removal Activities .....	4
3	Schematic View of Gunitite Tank Construction Showing Sludge Removal Equipment .....	5
4	Work Platform and Robot Arm .....	15
5	Decommissioning Schedule, Waste Volume Estimates, and Costs by Fiscal Year .....	18

## LIST OF TABLES

1	Estimated inventory of residual waste in each tank .....	11
2	Radiological survey results in the waste tanks in the South Tank Farm .....	12
3	Decommissioning cost for entombing South Tank Farm gunitite tanks .....	16

## 1. INTRODUCTION

The six large gunite storage tanks considered as a group is one of approximately 76 facilities currently managed by the Oak Ridge National Laboratories (ORNL) Surplus Facilities Management Program (SFMP). This program, as part of the Department of Energy (DOE) national SFMP, is responsible for the maintenance and surveillance and the final decommissioning of radioactively contaminated surplus ORNL facilities. A long-range planning effort is being conducted that will outline the scope and objectives of the ORNL program and establish decommissioning priorities based on health and safety concerns, budget constraints, and other programmatic constraints. In support of this SFMP planning activity, preliminary engineering assessments are being conducted for each of the ORNL surplus facilities currently managed under the program. These efforts are designed to: (1) provide an initial assessment of the potential decommissioning alternatives, (2) choose a preferred alternative and provide a justification of the decommissioning plan, including cost and schedule estimates. This report presents the results of the preliminary decommission study for the six gunite storage tanks.

## 2. FACILITY DESCRIPTION

Since 1943, several storage tanks have been installed at ORNL for storage of liquid radioactive waste. Twenty-one of these tanks designated as surplus are involved in the ORNL SFMP. These tanks have been divided into nine groups for SPMP consideration. The decommissioning of eight of

these groups is covered in X-OE-231, Vol. 3. The decommissioning of the group of six large gunite tanks is addressed in this report. These tanks have a nominal capacity at 170,000 gal each.

## 2.1 Location and Adjacent Facilities

The group of six large concrete tanks (W-5 to W-10) considered in this report are located in the south tank farm. The south tank farm is located in the approximate center of the ORNL facilities at the main Bethel Valley site (Fig. 1.) This tank farm (Fig. 2) comprises six underground tanks, constructed in 1943 of reinforced gunite, on a 60-ft center-to-center square matrix. (Gunite is a trade name for a specific method of spraying a mixture of sand, cement, and water against a form.) The three tanks in the north row are identified as W-5, W-7, and W-9, from west to east. The three tanks in the south row are identified as W-6, W-8, and W-10, from west to east. The south row of tanks is at a slightly lower elevation than the north row, conforming to the natural slope of the land. Other surplus facilities in this tank farm include accessories such as six adjacent dry wells and four concrete valve pits that are located in the vicinity of the tanks. Other facilities used in a current project to empty these tanks are described in detail elsewhere.<sup>3</sup> In summary, the primary equipment includes above-tank access platforms and slucing equipment such as pumps, television cameras, and control equipment.

## 2.2 Tank Construction

A sketch of these tanks is provided in Fig. 3. These tanks in the south tank farm (known as the 3507 area) have an inside diameter of 50 ft and



ORO 79-837




Fig. 2 Aerial view of the Gunite Storage Tanks in the south tank farm prior to sludge removal activities.




Fig. 1. Location of the Gunite Storage Tanks at the Oak Ridge National Laboratory.




Fig. 3. Schematic view of Guniting Tank construction showing sludge removal equipment.

a vertical sidewall height of 12 ft (with reference to the tank floor at the center). The tank dome rises an additional 6 ft 3 in. at the center, has no internal supports, and is covered with about 6 ft of compacted dirt. The gunite tank sidewall is 6 in. thick; and the tank dome is believed to be 10 in. thick at the center, increasing in thickness near the tank wall. The tank does not have an interior metal liner. The roof and side walls incorporate 3/8 in. and 1/2 in. steel reinforcement. Welded #8 wire mesh on a 4 x 4 in. pattern is also used in the roof, walls, and bottom.

The tank bottoms are approximately 5 in. thick and rest on slightly sloping (1/2%) saucers that have curbs and gutters surrounding the tanks. An adjacent dry well basin is connected to the saucer under each tank, with a 6-in. vitreous clay pipe that extends into the gutters on the low side of each tank. The dry well basins are 2 ft square on the inside and 3 ft square on the outside. The dry well from the saucer drain basins extend to the surface and are covered with manhole opening covers (see Dwg. 68336).

Valve pits 206-126\* and 206-135\* consist of concrete boxes with overall dimensions of 4 x 5 x 7.5 ft and 3.7 x 6 x 7 ft, respectively. The thickness of the concrete boxes are 6 in. and 9 in., respectively. These valve pits incorporate plug-type valves. Pit 206-135\* previously

---

\*These numbers are original equipment numbers used on the old installation drawings only.

extended to the surface and Pit 206-110\* originally had 5 ft of soil cover. Both pits now have been abandoned and are completely covered with soil.

Two additional concrete valve pits added after the initial installation are adjacent to the dry well for Tank W-7. These pits are visible from the surface. Two other pits are located approximately 40 ft northwest of Tank W-9. Two pits are located to the southeast and southwest of Tank W-6.

New facilities constructed in the area to use while emptying Tank W-5 to W-10 are described elsewhere (see Sect. 7, Ref. 3).

### 2.3 Tank History, Use, and Contents

During the 35 years the gunite tanks have been in service, they have contained the Low Level Liquid Waste (LLW, formerly called ILW) from a large variety of ORNL programs. The standard practice has been to neutralize all acidic LLW by the addition of NaOH or  $\text{CaCO}_3$  until the liquid waste was basic, after which the LLW was transferred to one of the gunite tanks, usually one in the north row (see Sect. 7, Refs. 1 and 2). After a period of storage in the tank, the LLW would be transferred to an evaporator for concentration before the return of the LLW to another gunite tank, usually in the south row, for an additional storage period before final disposal. Organic liquid wastes are not normally routed to

---

\*These numbers are original equipment numbers used on the old installation drawings only.

these tanks (see Sect. 7, Ref. 3). However, small quantities of organic liquid has been handled in the aqueous waste and it was once recommended that addition of a few gallons per day continue to be allowed (see Sect. 7, Ref. 4).

While the LLW was stored in the gunite tanks, various chemical salts (strontium hydroxide, barium hydroxide, various other hydroxides and carbonates, and some sulfates) precipitated because of their limited solubility in basic solutions. These precipitates accumulated in distinct sludge strata of varying compositions due to the different compositions of the LLW from the various input sources. The different sludge layers also vary in thickness. Most of this sludge material has now been removed and disposed of by hydrofracture (see Sect. 7, Ref. 4).

Most of the original valve pits have been out of service for many years since the tanks were either not in service or the functions of the valve pits were provided by newer systems.

The bulk of the sludge in the tanks has now been removed. When the emptying program began in August 1980, several additional holes were bored through the soil cover and concrete dome for inserting 34-in. diam. access shafts (see Ref. 3). These holes remain for access into the tanks.

Access is no longer available to the original valve pits. Pit 206-110\* located approximately 16 ft north of the edge of Tank W-7 is no longer in use and has not been accessed since being covered with soil. Pit 206-136\*, 14 ft to the east of Pit 206-110\* has also been covered. Two newer pits located adjacent to the dry well for Tank W-7 extend to the surface but they are no longer in service. Dry wells located approximately 5 ft from the northwest edge of Tanks W-5, W-7, and W-9 and 5 ft from the southwest edge of Tanks W-6, W-8, and W-10 are accessible.

#### 2.4 Radiological Characterization

These tanks contained highly radioactive material prior to being emptied in the early 1980s. Measurements taken in August 1980 through the new access holes just before removal of the tank contents was initiated provided readings of 400, 600, 900, 900, 150, and 900 mr/hr in tanks W-5 through W-10, respectively. These readings were taken above the contents at dome level. Readings taken in the opening 3 ft above the tanks were 15, 100, 50, 100, 15, and 80 mr/hr, respectively. A concrete plug drilled out of the top of one of the tanks read 80 mr/hr immediately after removal, but fell to 2 mr/hr after two days. The concrete at other parts of the tanks is likely to retain higher levels of activity. The radiation level on the access platforms above the tanks was less than 1 mr/hr, and levels around the chain-link fence surrounding the area were less than 0.5 mr/hr. A typical stainless steel transfer line located in

---

\*These numbers are original equipment numbers used on the old installation drawings only and are not referred to by this number anywhere except there.

the vicinity of tank W-8 read 3 r/hr at 3 in. from the pipe. This agrees with levels of 2 r/hr reported as typical for plug-type valve pits.<sup>6</sup>

The radiation level in these tanks is now lower because most of the sludge, as well as the clear water which previously covered the sludge, has been removed by the gunite tank sludge removal project. A preliminary radiological characterization was made, after the tanks were emptied, as part of the current SFMP planning effort.<sup>5</sup> The inventories of residual material left in tanks W-5 through W-10 following the sludge removal activities are given in Table 1. This material includes a heel of slurried waste left after the tanks were pumped out, as well as a small layer of solids which could not be slurried. A total of 345,000 l of waste remains in the tanks. The most significant radionuclides involved are <sup>90</sup>Sr and <sup>137</sup>Cs. Tanks W-8 and W-10 have the largest inventories of residual radionuclides, with 7.8 and 7.0 kCi of <sup>90</sup>Sr, respectively. Results of a radiation survey of the tank openings and interiors are given in Table 2. Levels of 17 and 20 rad/h were found near the bottoms of tanks W-8 and W-10.

### 3. DECOMMISSIONING ALTERNATIVES ASSESSMENT

The gunite tanks in the south tank farm are not known to leak, but they are old, single-wall tanks that have little or no long-term reuse potential. As with other decommissioning studies of this series, an ad hoc review committee was formed to review summary descriptions of the gunite storage tanks, their condition, and the preliminary radiological



Table 1. Estimated inventory of residual waste in each tank.

Tank <sup>a</sup>	Type of waste <sup>b</sup>		Total volume (l)	Major radionuclides	Total inventory <sup>c</sup>	
	Slurry (l)	Solids (l) <sup>d</sup>			(TBq)	(kCi)
W-5	14,000	9,700	24,000	<sup>90</sup> Sr	11	0.3
				<sup>137</sup> Cs	0.60	0.02
				others	0.43	0.01
W-6	39,000	19,000	58,000	<sup>90</sup> Sr	76	2.0
				<sup>137</sup> Cs	5.5	0.15
				others	1.6	0.04
W-7	39,000	7,800	47,000	<sup>90</sup> Sr	62	1.7
				<sup>137</sup> Cs	4.5	0.12
				others	1.3	0.03
W-8	39,000	3,900	43,000	<sup>90</sup> Sr	290	7.8
				<sup>137</sup> Cs	35	0.96
				others	5.1	0.14
W-9	54,000	0	54,000	<sup>90</sup> Sr	15	0.41
				<sup>137</sup> Cs	9.1	0.25
				others	2.6	0.07
W-10	120,000	0	120,000	<sup>90</sup> Sr	260	7.0
				<sup>137</sup> Cs	36	0.96
				others	12	0.33
Total	305,000	40,000	345,000		820	22

<sup>a</sup>The capacity of each tank is  $6.6 \times 10^5$  l.

<sup>b</sup>Estimated volume based on photographic information.

<sup>c</sup>Based on radioactivity/volume ratios multiplied by the volume shown in column 4 of this table.

<sup>d</sup>High density sludge.

Table 2. Radiological survey results in the waste tanks in the South Tank Farm.

Tank	TLD absorbed dose rate (rad/h)			Direct beta-gamma absorbed dose rate <sup>a</sup> (rad/h)
	B <sup>b</sup>	M <sup>b</sup>	S <sup>b</sup>	
W-5	0.74	0.76	0.94	0.015
W-6	2.5	1.2	0.03	0.020
W-7	1.3	1.6	0.83	0.300
W-8	17.0	2.5	0.62	0.150
W-9	6.5	5.6	0.22	0.100
W-10	20.0	4.4	0.43	0.250

<sup>a</sup>Radiation measured at the opening of the tank access with lid open.

<sup>b</sup>B, M, and S indicate different depth where TLD chips were placed in the tank. B indicates 0.6 m above the bottom of tank W-5 and 0.9 m above the bottom of other tanks. M and S indicate 1.8 m and 3.4 m above B, respectively.

characterization study. The decommissioning alternatives for the large gunite tanks were discussed in conjunction with alternatives for the other groups of waste tanks.<sup>7</sup>

Entombment and complete removal were the two primary options considered for decommissioning the gunite storage tanks. The complete removal option would involve sectioning large concrete tanks in a relatively high radiation background field. Thus, removal would entail significantly larger absorbed doses on the part of the operating personnel. On the other hand, the tanks could be entombed with only moderate personnel exposures.

Cost was also a significant factor in evaluating entombment and complete removal options. The cost estimates for removal of the other, smaller LLW collection tanks had been made prior to selection of the decommissioning mode for the large gunite tanks. Therefore, costs for removal were easily obtained along with entombment costs for the large gunite tanks. Complete removal was found to cost about 30% more than entombment.

Because of the lower personnel doses associated with entombment, lower costs, a lack of alternative land use requirements, acceptable groundwater levels, etc., entombment was selected as the most probable decommissioning mode for the gunite storage tanks.

#### 4. DESCRIPTION OF THE DECOMMISSIONING PLAN

The six gunite tanks discussed in this report will be entombed with a grout after remote cleaning. The remotely operated equipment to be used in the cleaning, shown in Fig. 4, is concepted as being mostly "off-the-shelf" commercial robotic components.<sup>8</sup> The platforms previously used for the sludge removal operations will provide a base for the decommissioning equipment. Tank access will be gained through existing openings under the platforms. Procedures for removing any remaining material will be essentially the same as when the tanks were emptied earlier. Remote decontamination will be accomplished using ultra high-pressure water jet cleaning, without abrasives. However, abrasive jet scarification could be used on hot spots or hard deposits if experience indicates a need for the use of abrasives.

Once the tanks are cleaned, they will be entombed with grout. Each tank will require about 170,000 gal of grout; thus, a total of slightly over 1 million gal of grout will be required. A typical grout mixture which might be considered for use in the gunite tanks consists of 20% bentonite, 70% fly ash, and 10% cement.

The soil in the south tank farm around these tanks will be removed to a depth of approximately 1 m. The associated piping near the surface will be removed. The soil and piping will be placed in low-level waste burial. New soil will replace the old soil and the terrain returned to the natural slope in the area.

Fig. 4. Work platform and robot arm.

The general approach to decommissioning of the six large gunite tanks will be:

1. prepare a project plan, support documentation, and radiological characterization;
2. perform detail design and finalize decommissioning procedures, and
3. implement decommissioning operations.

## 5. COST ESTIMATE AND SCHEDULE

The primary cost for decommissioning the six large gunite tanks in the south tank farm is \$5,900,000 (FY-85, first quarter dollars) plus a small portion of the \$621,000 for special equipment which will be shared with other tank decommissioning projects. The estimated cost is summarized in Table 3.

Table 3. Decommissioning cost for entombing South Tank Farm gunite tanks

Engineering	810,000
Operating Contractor	3,360,000
On-Site Construction Contractor	<u>1,730,000</u>
TOTAL	\$5,900,000

Burial ground cost at \$1,609,000 is a significant part of the operating contractor's portion. Waste volumes are provided in Fig. 5. Contaminated soil accounts for 3,000 m<sup>3</sup> of the total 3,200 m<sup>3</sup> of radioactive solid waste. Metal and general rubble accounts for the other 200 m<sup>3</sup>. A total of 835 m<sup>3</sup> of liquid wastes are anticipated, mostly from the cleaning operations.

The expenditures by fiscal year are provided in Fig. 5. The cost estimate worksheets are provided in Appendix I. The estimate generated for the removal option is also presented as Appendix II.

## 6. SCHEDULE

The schedule for decommissioning the six large gunite tanks is provided in Fig. 5. The first year involves characterization studies and assessments and preliminary engineering. Detailed engineering will be done in the second year and actual decommissioning operations in years three and four.

## 7. REFERENCES

1. L. C. Lasher, Operating Procedures for Radioactive Liquid Gaseous Waste Disposal, Third Revision, ORNL-CF-64-11-62, June 1971, p. 1-8.
2. Departmental Superintendent, Operating Procedures for Radioactive Liquid and Gaseous Waste Disposal, ORNL-CF-64-11-62, November 1964, p. 15.




Fig. 5. Decommissioning schedule, waste volume estimates, and costs by fiscal year.



3. Richard D. Ehrlich and Douglas MacNary, et al., Conceptual Design Report for Gunit Tank Sludge Removal, UCC-ND, X-OE-73, June 1979.
4. W. D. Burch, et al., Waste Management at ORNL: Present Practices--Immediate Needs--The Future (The Final Report of the Committee on ORNL Waste Handling Practices) ORNL-CF-72-9-1, September 1972.
5. S. F. Huang, W. A. Alexander, J. B. Watson and T. W. Oakes, Preliminary Radiological Survey of the Gunit Waste Tanks in the South Tank Farm at Oak Ridge National Laboratory, ORNL/CF-84/206, September 1984.
6. Personal communication, Charlie Guinn, ORNL Industrial Safety and Health Physics Division, to J. R. Horton, April 1983.
7. Letter, minutes of the SFMP Ad Hoc Review Committee Meeting on the Liquid LLW Waste Tanks, T. E. Myrick (Martin Marietta Energy Systems, Operations Div.) to attendees, March 13, 1984.
8. Personal communication, D. P. Kuban of the Martin Marietta Energy Systems Engineering Division, to J. R. Horton, April 1984.

APPENDIX I


COST ESTIMATE SHEETS

JOB TITLE AND BUILDING <b>SURPLUS FACILITIES MANAGEMENT PROGRAM</b>		BILL OF MATERIAL NO. <b>11</b>	
WORK ORDER NO. <b>A-2620</b>		BILL OF MATERIAL SHEET <b>1</b> OF <b>7</b>	
CATEGORY II AND III, B.D.G. AND... ETC.) <b>9</b>		PROJECT ENGINEER <b>N. DURGEE</b>	
CONSTRUCTION BY <b>9</b>		PRINCIPAL ENGINEER <b>F. PERIZ</b>	
PARTICIPANT <b>1</b>			
STUDY <b>9</b>			

# ILW COLLECTION TANKS

LARGE CONCRETE TANKS W-5 TO W-10 (D&D FACILITY 10)

ALTERNATIVE 2: GROUTING ENTOMBMENT



LISTED BY <b>1233</b>	ESTIMATED BY <b>DATE</b>	DATE <b>ESTIMATE SHEET 37</b>
--------------------------	-----------------------------	----------------------------------

1. Computer Estimates Only  
2. Estimate of Construction Costs Only

1. PROJECT NO. 11

2. ACCOUNT NO. A-2620

3. PARTICIPANT 11

4. SUBTITLE ILW COLLECTION TANKS

5. SURPLUS FACILITIES MANAGEMENT PROGRAM

6. CATEGORY I AND IMP. BLDG. AND. ETC. 10

7. CONSTRUCTION BY 11

8. LEVEL OF ESTIMATE STUDY

9. BILL OF MATERIAL NO. 11

10. SHEET PROJECT ENGINEER OF N. DUFFLE

11. PRINCIPAL ENGINEER F. PRETZ

12. LARGE CONCRETE TANKS W-5 TO W-10 (I&D FACILITY 10)

13. ALTERNATIVE 2: GROUTING ENVIROMENT

ITEM	SHEET NO.	MATERIAL	LABOR	TOTAL	(incl. Cont. & Misc.)
1. C/P&F					
2. CIVIL				1,250,000	1,750,000
3. FENCES (incl. Boring Castings)				2,500,000	3,260,000
4.					
5. S/T				3,780,000	5,090,000
6. ENGINEERING				600,000	810,000
7. Contingency				1,320,000	
8.					
9.				5,700,000	
10. S/T				200,000	
11. Escalation To FY 85-1					
12. TOTAL				5,900,000	8,290,000
13.					
14.					
15.					
16.					
17.					
18.					
19.					
20.					
21.					

ESTIMATE SHEET 37A OF



JOB TITLE AND BUILDING SURPLUS FACILITIES MANAGEMENT PROGRAM		SUBTITLE ILW COLLECTION TANKS	
WORK ORDER NO. A-2620		BILL OF MATERIAL NO. 41	
CATEGORY AND IMP. BLDG. AND, ETC. CONSTRUCTION BY JNL		SHEET PROJECT ENGINEER N. DUNN	
PARTICIPANT STUDY		PRINCIPAL ENGINEER F. PRITZ	

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL		TOTAL	HOURS	DATE	C.I.	TOTAL
				UNIT COST	TOTAL					
1	Phase II INSTALL LARX PLATFORM OVER TANKS	1.5	ea	50.51	63	63	63	12/73	12/73	63
2	INSTALL INJURIES ON PLATFORM - CONNECT TO TANK SERVICES AND CONNECT TO TANKS	5	ea				1100			1100
3	REMOVE CONCRETE FROM 10 W-10 TANK TO MANAGEMENT	10	sq yd				401			401
4	RECONSTRUCTIBLE BY REMOVE CLEANABLE SPRAY FOAM AND PAINTING - (40716 FT <sup>2</sup> TOTAL)	410,000	GAL				6000			6000
TOTAL							2120			2120

UCM 8123 11 10-73	LISTED BY	ESTIMATED BY	DATE	ESTIMATE SHEET 39
----------------------	-----------	--------------	------	----------------------

JOB TITLE AND BUILDING		SUBTITLE	
SURPLUS FACILITIES MANAGEMENT PROGRAM		ILM COLLECTION TANKS	
WORK ORDER NO.		SHEET	
A-2620		41	
CATEGORY (LAND IMP., BLDG. ADD., ETC.)		SHEET	
CONSTRUCTION BY <i>ORNL</i>		PROJECT ENGINEER	
LEVEL OF ESTIMATE		41	
STUDY		PRINCIPAL ENGINEER	
DRAWING OR OTHER SOURCE		41	
F. PRETZ		OF	

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL		TOTAL	HOURS		DATE	TOTAL
				UNIT COST	UNIT COST		UNIT	TOTAL		
5	FINAL CLEAN BY INLET PRESSURE WATER SPRAY	33,000	sf				11	3850		
6	FLUSH ALL SPRING LINES TO/FROM TANKS	3,000	GAL				1	3000		
7	REMOVE ALL JEEP CLEAN-UP DEBRIS DESCRIBED ABOVE	1	LOT					400		
8	PORTAL CEMENT (MATERIAL) & MISC. SUPPLIES	6000	CY	200		1,200,000				
TOTAL										

UC-5035A (1-15-71)	DATE	ESTIMATED BY	DATE	ESTIMATE SHEET
				40

For Unaudited Estimates Only  
 UCM 31233  
 11 10 71

1 SUBPROJECT NO.  
 1 ACCOUNT NO.  
 1 PARTICIPANT

100 TITLE AND DURING  
 91 SURPLUS FACILITIES MANAGEMENT PROGRAM

91 WORK UNDER NO.  
 A-2620

91 CATEGORY II AND INF. BLDG. AND, ETC.)

91 CONSTRUCTION BY  
 DENAL

91 LEVEL OF ESTIMATE  
 STUDY

100 TITLE AND DURING  
 91 ILW COLLECTION TANKS

LARGE CONCRETE TANKS W-5 TO W-10 (RED FACILITY 10)

ALTERNATIVE 2: GROUTING ENTOURMENT

BILL OF MATERIAL NO.  
 91  
 BILL OF MATERIAL  
 91  
 PROJECT ENGINEER  
 91 N. DUNLE  
 PRINCIPAL ENGINEER  
 91 F. PEREZ

DRAWING FOR OTHER SOURCE

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL			LAOUR			TOTAL
				UNIT COST	UNIT	TOTAL	UNIT	RATE	CF 1	
1	CEM. Sub TOTAL	30.39	16.07	54.57	1.61	61	65	12.80	70.75	276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276,800
	HP 200000/100000									276,800
	CEM. Sub TOTAL									276



<b>FOR CONSTRUCTION ESTIMATES ONLY</b> CODE NO. _____		<b>JOB TITLE AND BUILDING</b> SUBTITLE _____		<b>SURPLUS FACILITIES MANAGEMENT PROGRAM</b> SUBTITLE _____		<b>ILLW COLLECTION TANKS</b> SUBTITLE _____	
PROJECT _____ ACCOUNT NO. _____ PARTICIPANT _____		WORK ORDER NO. _____ A-2620 CATEGORY (L AND IMP. OR DO. AND. ETC.) _____ CONSTRUCTION BY <i>CRAF</i> LEVEL OF ESTIMATE _____ STUDY _____		BILL OF MATERIAL NO. _____ BILL OF MATERIAL _____ SHEET _____ OF _____ PROJECT ENGINEER _____ PRINCIPAL ENGINEER _____ 11 <i>H. DORRIS</i> 11 <i>F. PERITZ</i>		LARGE CONCRETE TANKS W-5 TO W-10 (RED FACILITY 19) ALTERNATIVE 2: GROUTING ENHANCEMENT	
DRAWING OR OTHER SOURCE							
ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL UNIT COST	TOTAL	LABOR HOURS TOTAL	DATE
1	MASS I	38.19	46.47	150.51	64	65	10/21/84
1	EXCAVATE AND EXPOSE LOOPS IN TANKS. (PRESUMABLY 2 PORTLANDS) FOR EOP. TANKS	NA					
2	CONSTRUCT SUMP UNDER LOW-RESPONSEABLE TANKS FOR COLLECTION. ASPIRE SUMP PUMP.	NA					
3	EXCAVATE AND REPAIR ACROSS SHOPS FOR CLEANING TANKS.	NA					
4	INSTALL FINS FOR PLATFORM	NA					
5	INSTALL PIPING TO W-10 TANK FOR LIQUID CLEAN-UP	NA					
TOTAL							
LISTED BY _____ DATE _____				ESTIMATED BY _____ DATE _____			
UCM 31225 11-10-79				ESTIMATE SHEET <i>42</i>			

JOB TITLE AND BUILDING <b>SURPLUS FACILITIES MANAGEMENT PROGRAM</b>		JOB TITLE <b>ILM COLLECTION TANKS</b>	
WORK ORDER NO. <b>A-2620</b>		BILL OF MATERIAL NO. <b>41</b>	
CATEGORY I AND IMP. BY DR. ADD. ETC. <b>CONSTRUCTION BY</b>		SHEET <b>OF</b>	
LEVEL OF ESTIMATE <b>STUDY</b>		PROJECT ENGINEER <b>H. DURFEE</b>	
PARTICIPANT <b>1</b>		PRINCIPAL ENGINEER <b>F. MROZ</b>	

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL		TOTAL	HOURS		TOTAL	CFI	TOTAL
				UNIT COST	64		UNIT	TOTAL			
5	<b>Phase III</b> <b>Excavate 11-5-8 W-12 Tank</b> <b>Area to Expave &amp; Remove</b> <b>Rebar, Scaffolding, etc. (see 100)</b>	8,000	CY					1,120			
6	<b>Remove Tanks and</b> <b>Move to Burial Ground.</b> <b>Wells Deep Structure and</b> <b>Tank (1750 LF ea. estimate)</b>	NA									
7	<b>Remove Valve Pits and other</b> <b>structures. (see 100)</b>	8	ea					320			
8	<b>Remove piping, etc. 1100</b> <b>(see 100)</b>	3645	LF					1800			
9	<b>Relocate Piping Remaining</b>	950	LF			4800		480			
<b>TOTAL</b>						16,00		4520			

LISTED BY <b>UCN-31233</b>	ESTIMATED BY <b>DATE</b>	DATE <b>43</b>
-------------------------------	-----------------------------	-------------------

FOR TITLE AND BIDDING		SUBTITLE		BILL OF MATERIAL NO.		SHEET		OF	
SURPLUS FACILITIES MANAGEMENT PROGRAM		ILL COLLECTION TANKS							
FORM ORDER NO.		A-2620		LARGE CONCRETE TANKS H-5 TO H-10 (RED FACILITY 10)		PROJECT ENGINEER		H. DURFEE	
CATEGORY II AND III: BLDG. ADD. ETC.				ALTERNATIVE 2: GROUTING ENTOREMENT		PRINCIPAL ENGINEER		F. PEREZ	
CONSTRUCTION BY		CPAF							
LEVEL OF ESTIMATE		STUDY							
DRAWING OR OTHER SOURCE									
ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL UNIT COST	TOTAL	UNIT	HOURS TOTAL	RATE	TOTAL
10	12" x 12" x 12" Limes of Reinforcement (to reason)	31	cc	100	3,100	10	310		
11	Barrel with clean concrete material	6050	cy				600		
12	Concrete, steel & mesh filled	1000	cy		400		160		
13	Steel for Reinforcement Structure (H-5 to H-10)		LS		6000		600		
14	FILL TANKS WITH GROUT 170,000 Gal each	1300,000	gal		250,000		1417		
TOTAL									

ESTIMATED BY: *CPAF* DATE: *10/10/00* ESTIMATE NO.: *1000*


FORM 3123  
11-10-71



APPENDIX II  
COST ESTIMATE SHEETS FOR  
TANK REMOVAL OPTION

JOB TITLE AND BUILDING		SUBTITLE	
SURPLUS FACILITIES MANAGEMENT PROGRAM		ILW COLLECTION TANKS	
WORK ORDER NO. A-2620		BILL OF MATERIAL NO.	
CATEGORY I AND IMP. SI DLG ADD. ETC.		BILL OF MATERIAL SHEET 1 OF 9	
CONSTRUCTION BY		PROJECT ENGINEER	
PARTICIPANT		N. DORFEE	
LEVEL OF ESTIMATE		PRINCIPAL ENGINEER	
STUDY		F. PEREIZ	

LARGE CONCRETE TANKS W-5 TO W-10 (D&D FACILITY 10)  
ALTERNATIVE 1: COMPLETE REMOVAL



ESTIMATE SHEET 28

DATE

ESTIMATED BY

DATE

LISTED BY

UCM-31255

**DRAWING OR OTHER SOURCE**

LISTED BY	DATE	ESTIMATOR BY	DATE	ESTIMATE SHEET
WCM 31753				62
11	10 77			
<b>TOTAL</b>				

JOB TITLE AND BUILDING		SUBTITLE		BILL OF MATERIAL NO.						
SURPLUS FACILITIES MANAGEMENT PROGRAM		ILW COLLECTION TANKS								
SHEET ORDER NO. A-2620		LARGE CONCRETE TANKS W-5 TO W-10 (B&D FACILITY 10)								
CATEGORY II AND MP, BLDG. AND, ETC.		ALTERNATIVE 1: COMPLETE REMOVAL								
CONSTRUCTION BY		SHEET		PROJECT ENGINEER						
LEVEL OF ESTIMATE		N. DUMFEE		PRINCIPAL ENGINEER						
STUDY		F. PEREZ								
DRAWING OR OTHER SOURCE										
ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL UNIT COST	TOTAL	UNIT	HOURS TOTAL	RATE	CTI	TOTAL
1	Phase II									
1	INSTALL WALK PLATFORM OVER TANKS W-5 TO W-9	5	TOTAL				100			1000
2	INSTALL UTILITIES ON PLATFORM - CONNECT TO TANK SERVICES AND TANKS TO TANKS	5	TOTAL				20			1100
3	DECANT SEWAGE W-10 FACILITY									200
3	REMOVE CONTENTS FROM W-10 TANK TO W-10 FACILITY									
4	REMOVE PLATFORM BY REMOVE CONCRETE, ETC. AND REPAIRS - TANKS W-5 TO W-9						20			6000
TOTAL										8100
ESTIMATED BY				DATE		ESTIMATE SHEET		30		



SUBPROJECT 1. SURPLUS FACILITIES MANAGEMENT PROGRAM 2. A-2620 3. CATEGORY II AND IMP. BLDG. ADD. ETC. 4. CONSTRUCTION BY 5. LEVEL OF ESTIMATE 6. STUDY		SUBTITLE 1. ILW COLLECTION TANKS 2. LARGE CONCRETE TANKS W-5 TO W-10 (D&D FACILITY 10) 3. ALTERNATIVE 1: COMPLETE REMOVAL		SHEET 1. H. DORFLE 2. F. FRETZ	
DRAWING OR OTHER SOURCE 1.		MATERIAL 1.		LABOR 1.	
ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
5	FINAL CLEAN BY INCH PRESSURE WATER SPRAY - WRS	35,000	SF		38,500
6	Flush All Sprinkler Lines to Floor Tanks	3,000	COL		5100
7	Remove All Temp. Clean-up Items installed above Incl. Platform over T-10		COL		200
8	ACRIAL, CONCRETE BOLT, INCH, INCH AND SLOTTED	14,500	CS	200	2,900,000
TOTAL				75200	31

	ESTIMATE SHEET	DATE	ESTIMATED BY	DATE	TOTAL
AR 031811					
UICM S17295					
16 11					
00					

JOB TITLE AND BUILDING SURPLUS FACILITIES MANAGEMENT PROGRAM		SUBTITLE ILW COLLECTION TANKS	
WORK ORDER NO. A-2620		SHEET H. DUNFEE	
CATEGORY II AND IMP. BLDG. AND ETC. CONSTRUCTION BY CPAF		SHEET H. DUNFEE	
PARTICIPANT LEVEL OF ESTIMATE STUDY		SHEET H. DUNFEE	
DRAWING OR OTHER SOURCE		SHEET H. DUNFEE	

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL		TOTAL	HOURS		RATE	CFY	TOTAL
				UNIT COST	64		UNIT	TOTAL			
1	PHASE I EXCAVATE AND EXPOSE LEAKS IN TANKS. (PRESUMABLY 6 PARTICIPANTS) FOR EACH TANK	1	16	16	24	64	65	12	73	76	79
2	CONSTRUCT SURFACE UNDER UN-EXPOSEABLE LEAKS FOR COLLECTED. ASYRUE SUP PROP.	1	16	16	24	64	65	12	73	76	79
3	EXCAVATE AND INSTALL ACCESS CHUTTS FOR CLEANING TANKS.	1	16	16	24	64	65	12	73	76	79
4	INSTALL FINS FOR CLASPON	1	16	16	24	64	65	12	73	76	79
5	INSTALL PIPING TO W-10 TANK FOR LEAKED CLEAN UP	1	16	16	24	64	65	12	73	76	79
TOTAL											

LISTED BY UCM-51233 11 10 77	ESTIMATED BY DATE	ESTIMATE SHEET 33
------------------------------------	----------------------	----------------------



JOB TITLE AND BUILDING		SURPLUS FACILITIES MANAGEMENT PROGRAM		SURPLUS		ILW COLLECTION TANKS	
SUBPROJECT		A-2620		CATEGORY II AND IMP. BLDG. ADD. ETC.)		LARGE CONCRETE TANKS W-5 TO W-10 (D&D FACILITY 10)	
ACCOUNT NO.		CONSTRUCTION BY		LEVEL OF ESTIMATE		ALTERNATIVE 1: COMPLETE REMOVAL	
PARTICIPANT		CPAF		STUDY			
DRAWING OR OTHER SOURCE							
1	2	3	4	5	6	7	8
ITEM NO.	QUANTITY	UNIT	MATERIAL AND DESCRIPTION	UNIT COST	TOTAL	HOURS	TOTAL
10	31	ea	Place & app. lines of penetrations (to remove)	100	3,100	10	310
11	12,000	cy	Excavate with clean bottom material	10	120,000	1	1200
12	4,000	sy	Gravel, steel in mesh bed	10	40,000	04	160
13	1	LS	Plans for removed structure (H-pile & timber)		2,000	600	600
TOTAL					122,000	1,170	1,170
ESTIMATED BY				DATE	ESTIMATE SHEET 35		

ITEM NO.		SUBTITLE		BILL OF MATERIAL NO.	
1		11		11	
SURPLUS FACILITIES MANAGEMENT PROGRAM		ILLW COLLECTION TANKS			
A-2620		LARGE CONCRETE TANKS W-5 TO W-10 (108D FACILITY 10)			
CATEGORY II AND IMP. BLDG. AND. ETC.		ALTERNATIVE 1: COMPLETE REMOVAL			
CONSTRUCTION BY CPAF		PROJECT ENGINEER N. DUNFEE			
LEVEL OF ESTIMATE STUDY		PRINCIPAL ENGINEER F. PIRETZ			
DRAWING OR OTHER SOURCE					

ITEM NO.	MATERIAL AND DESCRIPTION	QUANTITY	UNIT	MATERIAL		TOTAL	HOURS		RATE	TOTAL
				UNIT COST	TOTAL		UNIT	TOTAL		
1	Sub TOTAL	10,300				10,300	65	15		229,400
2	Sub TOTAL	2,200				2,200				154,200
3	HP & 50% LBS / 1000 HUR									274,600
4	CPAF Dir TOTAL									187,300
5	WORKING & Bldg / 8722/100									561,100
6	CPAF TOTAL									191,600
7										1,023,500
8										
9										
10										
11										
12										
13										
14										
15										
16										
17										
18										
19										
20										
21										
22										
23										
24										
25										
26										
27										
28										
29										
30										
31										
32										
33										
34										
35										
36										
37										
38										
39										
40										
41										
42										
43										
44										
45										
46										
47										
48										
49										
50										
51										
52										
53										
54										
55										
56										
57										
58										
59										
60										
61										
62										
63										
64										
65										
66										
67										
68										
69										
70										
71										
72										
73										
74										
75										
76										
77										
78										
79										
80										
81										
82										
83										
84										
85										
86										
87										
88										
89										
90										
91										
92										
93										
94										
95										
96										
97										
98										
99										
100										

LISTED BY: \_\_\_\_\_ DATE: \_\_\_\_\_ ESTIMATED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

TOTAL

ESTIMATE SHEET 2/10

**END**

**DATE  
FILMED  
5/05/92**

