

RFP-2734
October 23, 1978

HR. 721
RFP-2734
October 23, 1978

267
11-14-78
MASTER

FLUIDIZED BED INCINERATION SYSTEM FOR
U.S. DEPARTMENT OF ENERGY DEFENSE WASTE
JULY-DECEMBER 1977

David L. Anderson

Frank G. Meyer

Pen K. Feng

Chemistry Research and Development
PILOT PLANT DEVELOPMENT



Rockwell International

Energy Systems Group
Rocky Flats Plant
P.O. Box 464
Golden, Colorado 80401

U. S. DEPARTMENT OF ENERGY
CONTRACT DE-AC04-76DPO3533

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

LEGAL NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Printed in the United States of America
Available from the
National Technical Information Service
U. S. Department of Commerce
Springfield, Virginia 22161
Price: Printed Copy \$4.50 Microfiche \$3.00
Price Is Subject to Change Without Notice

Printed
October 23, 1978

RFP-2734
UC-70 NUCLEAR WASTE
MANAGEMENT
TID-4500-R66

**FLUIDIZED BED INCINERATION SYSTEM FOR
U.S. DEPARTMENT OF ENERGY DEFENSE WASTE
JULY-DECEMBER 1977**

David L. Anderson

Frank G. Meyer

Pen K. Feng

**Chemistry Research and Development
PILOT PLANT DEVELOPMENT**

NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

SUBJECT DESCRIPTORS

**Fluidized Bed
Incinerators
Waste Management**

**ROCKWELL INTERNATIONAL
ENERGY SYSTEMS GROUP
ROCKY FLATS PLANT
P.O. BOX 464
GOLDEN, COLORADO 80401**

**Prepared under Contract DE-AC04-76DP3533
for the
Albuquerque Operations Office
U.S. Department of Energy**

~~DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED~~

- | | |
|---|--|
| <p>1 – Dr. Peter J. Dyne
Atomic Energy of Canada Ltd.
Whiteshell Nuclear Research Establishment
Pinawa, Manitoba
Canada, ROE1LO</p> <p>1 – A. K. Williams
Allied-General Nuclear Services
P. O. 847
Barnwell, South Carolina 29812</p> <p>2 – F. C. Choy, W. B. Stewart
Ontario Hydro
H-17
700 University Ave.
Toronto, Canada M5G1X6</p> <p>2 – J. Goodman, M. C. Gilchrist
Westinghouse Electric Corporation
Nuclear Fuel Division
Box 355
Pittsburgh, Pennsylvania 15230</p> <p>3 – D. H. MacNary
ORM, 8-1000
P. O. Box X
Oak Ridge, TN 37820</p> <p>1 – Dr. D. N. Van De Voorde
Centre d'Etude de l'Energie Nucleaire
Belgium Nucleaire SA, Mol, Belgium
25 rue de Champ-de-Mars, 1050
Brussels 1, Belgium</p> <p>1 – Zentalstelle fur
Atomicernenergie-Dokumentation
(ZAED)
Xernforschungezentrum Karlsruhe
D7501 Leopoldshafen
Federal Republic of Germany
Attn: Dr. Mrs. Bell</p> <p>1 – R. Gardiner
Commonwealth
Scientific & Industrial
Research Organization
P. O. Box 312, Clayton
Victoria, Australia 3168</p> <p>1 – E. P. Bregulla
NUKEM
Hanau
Federal Republic of Germany</p> <p>3 – Dr. A. L. Lotts
Oak Ridge National Laboratory</p> | <p>1 – Dr. H. Krause
Nuclear Research Center Karlsruhe
75 Karlsruhe
Karlsruhe
Federal Republic of Germany</p> <p>1 – E. J. Otis, Jr.
Samborn, Steketee, Otis & Evans, Inc.
1001 Madison Ave.
Coredon, Ohio 43624</p> <p>1 – V. F. Baston
Energy Inc.
P. O. Box 736
Idaho Falls, Idaho 83401</p> <p>1 – Roy Barker
Fuel & Material Examination Facility, HEDC
P. O. Box 1970
Richland, Washington 99352</p> <p>1 – W. J. Dodson
Advanced Technology Division
Kaiser Engineers
300 Lakeside Drive
Oakland, CA 94666</p> <p>1 – P. Dudley Josselyn
FMC Corp.
Box 760
San Jose, CA 95106</p> <p>1 – Gary Simmons
Whiteshell Nuclear Research Establishment
Pinawa, Manitoba
Canada, ROE1LO</p> <p>1 – Dr. M. Laser
Institut For Chemische Technologie
Der Kernforschungsanlage
517 Julich 1, Den
Postfach 365
Federal Republic of Germany</p> <p>1 – Process Systems & Component Development
Nuclear Fuel Division
Box 355
Pittsburg, PA 15230</p> <p>1 – D. E. McKenzie
Atomics Internation Division
Rockwell International
8900 DeSota Ave.
Canoga Park, CA 91304</p> <p>3 – J. D. Dempsey, R. W. Ramsey, R. A. Wolfe
DOE Division of Waste Management</p> |
|---|--|

DISTRIBUTION

- 267 – DTIE Distribution
 2 – Standard Distribution
 20 – TIO (Record)
 1 – Library
 5 – D. L. Anderson
 1 – K. W. Calkins
 1 – G. E. Loudenburg
 1 – S. F. Chung
 1 – F. G. Meyer
 1 – P. T. Faccini
 1 – L. C. Farrell, Jr.
 2 – P. K. Feng
 1 – L. Q. Fong
 1 – R. E. Hayne
 1 – L. G. Thomas
 1 – E. Jiannetti Attn: E. Skulski
 5 – A. J. Johnson
 1 – R. H. Karlsson
 1 – A. L. Kriznar
 1 – L. A. McKinney
 2 – L. J. Meile
 8 – L. L. Richey
 1 – C. E. Baldwin
 1 – J. W. White
 1 – R. N. Velasquez
 1 – D. A. Wiederecht
 10 – D. L. Ziegler
- Additional Distribution
- 1 – R. E. Lerch
 Hanford Engineering
 Development Laboratory
 4 – W. E. Clark, W. C. Ulrich,
 N. C. Bradley, A. W. Tedder
 Oak Ridge National Laboratory
 1 – B. G. Kniazewycz
 Carolina Power & Light Co.
 336 Fayetteville Street
 P. O. Box 1551
 Raleigh, NC 27602
 1 – C. T. Sanders
 Environmental Plutonium
 Data Base Group
 Oak Ridge National Laboratory
- 1 – S. S. Freeman
 Monsanto Research Corporation
 P. O. Box 32
 Miamisburg, Ohio 45342
 3 – Dr. L. R. Hill, P. O'Brian, L. W. Scully
 Sandia Laboratories
 Div. 1142
 P. O. Box 5800
 Albuquerque, NM 87115
 1 – W. B. Kerr
 Idaho Nuclear Corporation
 550 2nd Street
 Idaho Falls, Idaho 83401
 2 – Lamarr Johnson and Lee Bordane
 Los Alamos Scientific Laboratory
 1 – Beryl Eschem
 Stearns Roger, Inc.
 1 – J. R. McClain
 Mound Facility
 1 – Dr. Frank Morgan
 Director Materials Division
 AWRE
 Aldermaston, Berks, England
 1 – W. Hendrickson
 U.S. Department of Energy
 Idaho Operations Office
 550 2nd Street
 Idaho Falls, Idaho 83401
 1 – Calvin Palmer
 U.S. Department of Energy
 Richland Operations Office
 1 – Ervin H. Hardinson
 U.S. Department of Energy
 Oak Ridge Operations Office
 2 – N. H. Mackay
 U.S. Department of Energy
 Albuquerque Operations Office
 1 – Bengt Edwall
 South Swedish Power Co.
 20070 Malmoe 5, Sweden
 1 – Dr. M. L. First
 Harvard University
 School of Public Health
 665 Huntington Ave.
 Boston, Mass. 02115

C O N T E N T S

Abstract	1
Introduction	1
Summary	1
Plant Design	2
Process Description	2
Status of Engineering Work	4
Equipment Installation	4
Process Monitoring and Control Systems	5
Prior Work	5
Future Work	5
Conclusions	6

A C K N O W L E D G M E N T

The authors wish to acknowledge the assistance of the following technical staff members of Rockwell International, Rocky Flats Plant, in the preparation of this report: Jack N. Carlson, Burke A. Bell, and Dean A. Burton.

**FLUIDIZED BED INCINERATION SYSTEM FOR
U.S. DEPARTMENT OF ENERGY DEFENSE WASTE
JULY–DECEMBER 1977**

*David L. Anderson, Frank G. Meyer,
and Pen K. Feng*

Abstract. A fluidized-bed incineration facility has been designed for installation at the Rocky Flats Plant to develop and demonstrate the process for the combustion of transuranic waste. The unit capacity will be about 82 kg/hr of combustible waste. The combustion process will utilize *in situ* neutralization of acid gases generated in the process. The equipment design is based on data generated on a pilot scale unit and represents a scale-up factor of nine. Building modifications are complete and equipment installation has begun.

INTRODUCTION

Fluidized bed incineration is being evaluated at the Rocky Flats Plant (RFP) as an alternative to conventional incineration for processing transuranic (TRU) combustible waste. The fluidized bed concept is being pursued through three channels of activity at the present time: (1) a 9-kg/hour (20-lb/hour) pilot plant system is undergoing operational testing with low concentrations of plutonium contaminated solid and liquid wastes; (2) an 82-kg/hour (180 lb/hour) developmental plant has been designed and is being installed in an existing building; and (3) an integrated laboratory development program is underway to provide specific and timely data for the larger systems. This substantial amount of research is being expended in an effort to overcome inherent problems in conventional incineration of TRU wastes and to develop an improved incineration system for processing existing and/or future waste from nuclear industry in general.

Through the years, operation of the plutonium recovery facilities at the RFP has identified a need for an improved incineration system. The conventional methods employed at RFP, though effective, have

resulted in substantial maintenance problems because of equipment corrosion, short refractory life, and mechanical problems. In addition to frequent maintenance requirements, the process utilizes an aqueous flue gas scrubbing system that requires additional treatment and increases the total plant waste volume. Also, the conventional open flame incinerator produces a high temperature (850 to 1000 °C) refractory type of plutonium dioxide that does not readily lend itself to the plant's aqueous recovery technique. The fluidized bed incinerator was conceived in 1971 as an alternative to the present conventional system. Promising data from subsequent work has led to the present intensive development program to produce a production scale development plant.

The fluidized bed process incorporates three concepts that set it apart from conventional incineration. One unique concept is the *in situ* neutralization of acid gases that are produced when materials such as polyvinyl chloride plastic are burned. Another is the use of a catalytic afterburner, and the third is non-flaming low-temperature combustion throughout the system. These three features are responsible for several advantages of this process over conventional methods. The most significant benefits derived are the elimination of refractory-lined equipment, the elimination of aqueous flue gas scrubbing, and minimization of equipment corrosion. These factors are expected to extend equipment life, decrease maintenance requirements, and improve overall waste volume reduction.

SUMMARY

A fluidized bed incineration system has been designed for combustion of transuranic waste. The

facility is designed for a capacity of about 82 kg/hour (180 lbs/hour) which will correspond to a heat release rate of about 1,600,000 KJ/hour (1,500,000 Btu/hour). The process equipment design is based on data generated in the pilot plant and represents a scale factor of nine based on solid waste feed rates. Approximately 45% of the heat of combustion will be extracted through the walls of the afterburner by a water spray cooling system. In the pilot unit, most of the heat is removed as sensible heat of the combustion products. A water cooled heat exchanger in the flue gas stream will be used to remove approximately 55% of the heat of combustion from the process. In the pilot unit, the flue gas was cooled by dilution with room air. An air jet ejector was used in the pilot unit and high speed blowers will be used in the larger unit to provide motive force for gas flow through the process.

The four stage HEPA exhaust plenum is now operational and is undergoing final adjustments. Phase II equipment installation was 84% complete as of November, 1977. Completion is now scheduled for February, 1978. Operational testing of completed sub-systems will proceed concurrent with the construction effort.

The process monitoring and control system diagnostic and operating software packages are 50% complete. The hardware and software development of the inventory control remote weighing station was complete as of November, 1977.

PLANT DESIGN


Process Description

The fluidized bed incineration process is basically the same for both the pilot plant unit now in operation and the developmental scale unit now under construction. The process used in the developmental unit will vary somewhat from that of the pilot plant in the method of heat removal and motive force for gas flow through the system. In the pilot plant, the heat of combustion is removed by blending the hot flue gas with a large amount of room air as it exhausts from the system. This method becomes impractical when the process

is scaled up by a factor of nine for the development plant; consequently, the latter unit will be equipped with a water-cooled heat exchanger for flue gas cooling. For motive force, the development unit will utilize high speed blowers to replace the air jet ejector that is used in the pilot plant system. These process modifications will reduce both equipment and operating costs of the developmental unit relative to a scaled up pilot plant system. A flow diagram of the development unit is presented in Figure 1.

The actual fluidized bed incineration process for radioactive waste differs considerably from conventional incineration techniques. The entire operation is carried out within a canyon and glovebox system for containment of radioactive contamination. Waste will be received in 0.2-cubic meter (55-gallon) drums. The waste is first passed through an air lock into a feed preparation glovebox where it is hand-sorted for removal of large size tramp metal. Sorted combustibles are then fed into a low-speed, cutter type shredder for coarse shredding. Small pieces of tramp metal that were undetected by hand sorting are shredded along with the combustibles. Coarse shredded material passes through an air classifier for removal of most of the remaining tramp metal. Metal separated by the classifier falls into a glovebox where it can be bagged out for disposal. The waste, containing trace amounts of metal, is pneumatically transferred into a second shredder for final sizing prior to incineration. A constant pitch tapered screw feeds the shredded waste into a primary reactor of heated sodium carbonate (Na_2CO_3) granules that are fluidized by a flow of compressed air and nitrogen gas. Within the hot fluidized bed, the waste is decomposed by partial combustion and pyrolysis which produces sufficient heat to maintain a bed temperature of 550 °C. The air-nitrogen ratio of the fluidization gas is adjusted to promote the desired amount of combustion without open flame burning. Within the fluidized bed of Na_2CO_3 , *in situ* neutralization of acid gases is accomplished. Neutralization is achieved rapidly when nascent hydrogen chloride gas (HCl), formed during the decomposition of PVC plastic, reacts with Na_2CO_3 bed materials to produce sodium chloride (NaCl), carbon dioxide gas (CO_2), and water vapor. Offgas from the primary reactor passes into a

FIGURE 1. Flow Diagram of Fluidized Bed Incineration System for Transuranic Waste



cyclone separator where most of the entrained Na_2CO_3 , NaCl , and fly ash is removed before the gas is introduced into the catalytic afterburner. In the afterburner chamber, combustion air is added to the gas stream as it passes through a fluidized bed of oxidation catalyst. Here, complete combustion is achieved without open flame burning. A bed temperature of 600°C is maintained by a water jacket heat transfer system.

Flue gas leaving the catalytic afterburner contains fly ash, catalyst dust, and small amounts of Na_2CO_3 and NaCl fines that were not removed from the primary reactor offgas by cyclone separation. About 75 to 85% of this dust is removed by passing the gas stream through a second cyclone separator. The remainder is removed as the gas passes through a bank of sintered metal filters prior to cooling to 50°C in a water-cooled heat exchanger. The cooled flue gas is then pulled into four high-speed blowers that provide motive force for the process flow and maintain a slightly negative pressure throughout the system. Offgas from the process passes through a bank of high efficiency particulate air (HEPA) roughing filters prior to exiting through the building plenum system of four-stage HEPA filtration. Dust removed by cyclone separation and sintered metal filtration is cooled in a screw conveyor that transfers the residue into a drum for disposal.

The development plant will feature automatic control systems to regulate bed temperatures within the primary reactor and catalytic afterburner. The primary bed temperature will be controlled by the air-to-nitrogen ratio of the fluidization gas. A drop in bed temperature will activate automatic controls to increase the percent of air until the bed temperature climbs to the desired set point. Conversely, the percent of nitrogen will automatically be increased if a heat spike drives the bed temperature above a predetermined point. Catalytic afterburner temperature will be regulated by the quantity of waste being fed into the system. Deviations in catalyst bed temperature will prompt automatic controls to increase or decrease the speed at which the screw feeder transfers waste into the primary reactor. In this manner, the amount of fuel entering the afterburner will be controlled to maintain a preset catalyst bed temperature.

Status of Engineering Work

The four stage HEPA filter plenum is now operational and undergoing final adjustments. This plenum will be placed in service as soon as roughing filters are installed in the processing area. The filters are required to prevent a spread of contamination in the processing area should a flow reversal occur.

Equipment Installation

Phase II, equipment installation, was 84% complete as of November, 1977. Scheduled completion of the installation will be delayed beyond December 31, 1977. Phase II completion was scheduled for the end of February, 1978. To minimize the impact on later milestones, testing of individual components and systems will be initiated before total installation is complete. Testing was previously scheduled to begin at the completion of installation.

Process equipment installation tasks completed to date include process items previously reported plus the equipment listed below:

1. Catalytic afterburner
2. Sintered metal filter housings
3. Air classifier
4. Hydraulic shredders
5. Flue gas heat exchanger
6. Exhaust blower intercoolers
7. Process cooling water lines
8. Catalyst-carbonate transfer box
9. Preheater fuel storage tank
10. Preheater fuel pump
11. Canyon ventilation ducting and roughing filters
12. Water cooled ash cooling screw
13. Primary fluid bed preheaters
14. Afterburner preheaters
15. Process control valves

Equipment installation tasks in progress as of the end of November, 1977:

1. Process control field wiring
2. Process instrumentation field wiring
3. Process flue gas ducting

Equipment installation tasks remaining in addition to those listed above:

1. Afterburner spray cooling water condenser
2. Afterburner spray cooling water pump
3. Process insulation
4. Feed drum hoist

Process Monitoring and Control Systems

The fluidized bed incineration process will utilize a programmable data processor – 11/10 (PDP-11/10) minicomputer in conjunction with the Foxboro Interspec System for process monitoring and control purposes (refer to previous Progress Report RFP-2733). Field measurements consisting of 25 temperatures, 16 pressures, three flows, one contact closure, one weight, six analysers, and ten control loops will be brought into the Foxboro Interspec System where analog-to-digital conversion will take place. These signals will be sent to the PDP minicomputer to form a process data base from which pertinent information concerning the process can be extracted. A timer will continuously transfer and update the data base at some preset interval (e.g. one minute).

The incorporation of computer process control will take place in two steps. During Phase I, the computer will perform strictly process monitoring and data acquisition operations. As more experience is gained from the operation of the Fluid Bed Incinerator, Phase II will be implemented. It will consist of programming into the computer the control logic necessary for direct digital control (DDC) or supervisory set-point control (SCC). The advantage of such a computerized control system with the

correct analog-digital interface is the great flexibility it offers the user. Once the hardwares (computer, instrumentation, peripheral and interphase equipment, etc.) are in place, any field measurement can control any one or more actuating device by changing the system software (computer programs) environment. Little or no hardware change is necessary.

Prior Work

Work accomplished during this period is divided into two areas:

1. Hardware
 - a. The Remote Weighing Station was completed.
 - b. Hardware hook-up diagram of the Foxboro Interspec System was completed.
 - c. Installation of process sensors was 70% completed.
 - d. Control panel wiring diagram was completed.
2. Software
 - a. Remote weighing station software package was completed.
 - b. Hardware diagnostic routine and operating system routines are 50% finished.

Future Work

1. Hardware
 - a. Testing of all process instrumentation and final control devices.
 - b. Procure and build Graphics Display Panel.
 - c. Order and take delivery of necessary spare parts.

2. Software

- a. Completion of operating system routines with detailed documentation.
- b. Prepare a process control instruction manual.
- c. Indoctrinate and train operating personnel.
- d. Continue to upgrade and increase a package of off-line scientific programs that will analyze data collected during an incineration run.

CONCLUSIONS

1. The four stage HEPA filter plenum is now operational and undergoing final adjustments.

2. Phase II, equipment installation, was 84% complete at the end of November, 1977.
3. The Remote Weighing Station has been completed.
4. The hook-up diagram of the Foxboro Interspec System has been completed.
5. The control panel wiring diagrams have been completed.
6. Installation of process sensors was 70% complete.
7. Hardware diagnostic routine and operating system routines were 50% complete.