


Nevada
Environmental
Restoration
Project

DOE/NV-487



Corrective Action Investigation Plan
for Corrective Action Unit No. 423:
Building 03-60
Underground Discharge Point,
Tonopah Test Range, Nevada

RECEIVED

SEP 16 1998

OSTI

Controlled Copy No.:

~~UNCONTROLLED~~


Revision No: 0

October 1997

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Environmental Restoration
Division



U.S. Department of Energy
Nevada Operations Office

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (423) 576-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA, 22161, telephone (703) 487-4650.

**CORRECTIVE ACTION INVESTIGATION PLAN
FOR CORRECTIVE ACTION UNIT NO. 423:
BUILDING 03-60 UNDERGROUND DISCHARGE POINT,
TONOPAH TEST RANGE, NEVADA**

DOE Nevada Operations Office
Las Vegas, Nevada

UNCONTROLLED
Controlled Copy No.
UNCONTROLLED

Revision No.: 0

October 1997

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible electronic image products. Images are produced from the best available original document.

**CORRECTIVE ACTION INVESTIGATION PLAN
FOR CORRECTIVE ACTION UNIT NO. 423:
BUILDING 03-60 UNDERGROUND DISCHARGE POINT,
TONOPAH TEST RANGE, NEVADA**

Approved by: Janet Appenzeller-Wing
Janet Appenzeller-Wing, Project Manager
Industrial Sites Subproject

Date: 10/23/97

Approved by: Michael O. Giblin
Michael O. Giblin, Acting Project Manager
Nevada Environmental Restoration Project

Date: 10/23/97

Table of Contents

List of Figures	iii
List of Tables	iv
List of Acronyms and Abbreviations	v
1.0 Introduction	1
1.1 Purpose	1
1.2 Scope	5
1.3 CAIP Contents	6
2.0 Facility Description	7
2.1 Physical Setting	7
2.2 Operational History	7
2.3 Waste Inventory	9
2.4 Release Information	10
2.5 Investigative Background	10
3.0 Objectives	13
3.1 Conceptual Site Model	13
3.2 Contaminants of Potential Concern	17
3.3 Preliminary Action Levels	18
3.4 DQO Process Discussion	19
4.0 Field Investigation	22
4.1 Sampling Approach	22
4.1.1 Soil Borings	22
4.1.2 Field Screening	23
4.1.3 Sampling Criteria	25
5.0 Waste Management	29
5.1 Waste Minimization	30

Table of Contents (Continued)

5.2 Potential Waste Streams	30
5.3 Investigation-Derived Waste Management	30
5.3.1 Sanitary Waste Management	31
5.3.2 Low-Level Waste Management	31
5.3.3 Hazardous Waste Management	31
5.3.4 Hydrocarbon Waste Management	33
5.3.5 Mixed Waste Management	33
6.0 Duration and Records Availability	34
6.1 Duration	34
6.2 Records Availability	34
7.0 References	35
Appendix A - Data Quality Objectives Worksheet	A-1
Attachment 1 - Building 03-60 Site Map and Aerial Photograph	A-19
Attachment 2 - Building 03-60 UDP Photographs	A-22
Attachment 3 - Building 03-60 UDP Waste Oil Sampling Results	A-25
Attachment 4 - CAU No. 423 Waste Determination	A-28
Attachment 5 - Uniform Hazardous Waste Manifests	A-36
Appendix B - Nevada Department of Environmental Protection Document Review	
Sheet for Draft CAIP	B-1

List of Figures

Number	Title	Page
1-1	Tonopah Test Range Location Map	2
1-2	Area 3 Location Map, Tonopah Test Range	3
1-3	Building 03-60 UDP Location Map	4
2-1	Conceptual Cross-Section of the Building 03-60 UDP	8
3-1	Exposure Pathway Conceptual Model	15
3-2	Subsurface Release Conceptual Model	16
4-1	Proposed Borehole Locations, Building 03-60 UDP	24
4-2	Schematic of the Core-Barrel Sampler	27

List of Tables

<i>Number</i>	<i>Title</i>	<i>Page</i>
3-1	Site Characterization Laboratory Analytical Requirements	20
4-1	Geotechnical Analyses, Building 03-60 UDP	26
5-1	Action Levels for IDW Contaminants	29

List of Acronyms and Abbreviations

ARAR	Applicable or relevant and appropriate requirement(s)
ASTM	American Society for Testing and Materials
bgs	Below ground surface
CADD	Corrective Action Decision Document
CAIP	Corrective Action Investigation Plan
CAP	Corrective Action Plan
CAS	Corrective Action Site(s)
CAU	Corrective Action Unit(s)
CFR	<i>Code of Federal Regulations</i>
cm	Centimeter(s)
COC	Constituent(s) of concern
DOE	U.S. Department of Energy
DOE/NV	U.S. Department of Energy, Nevada Operations Office
DOT	U.S. Department of Transportation
DQO	Data Quality Objective(s)
EM	Engineering Manual
EPA	U.S. Environmental Protection Agency
EQL	Estimated Quantitation Limit
ERD	Environmental Restoration Division
ERP	Environmental Restoration Project
FFACO	<i>Federal Facility Agreement and Consent Order</i>
ft	Foot (feet)
gal	Gallon(s)
HASP	Health and Safety Plan
IDW	Investigation-derived waste
in.	Inch(es)
IT	IT Corporation
km	Kilometer(s)
L	Liter(s)
m	Meter(s)
mg/kg	Milligram(s) per kilogram

List of Acronyms and Abbreviations (Continued)

mg/L	Milligram(s) per liter
mi	Mile(s)
NAC	<i>Nevada Administrative Code</i>
NAFR	Nellis Air Force Range
NDEP	Nevada Division of Environmental Protection
NTS	Nevada Test Site
NTSWAC	Nevada Test Site Waste Acceptance Criteria
ORERP	Off-Site Radiation Exposure Review Project
PCB	Polychlorinated biphenyl(s)
PPE	Personal protective equipment
ppm	Part(s) per million
QA/QC	Quality assurance and quality control
QAPP	Quality Assurance Project Plan
RCRA	<i>Resource Conservation and Recovery Act</i>
RPD	Relative percent difference
SSHASP	Site-Specific Health and Safety Plan
SVOC	Semivolatile organic compound(s)
TC	Toxicity characteristic
TCLP	Toxicity Characteristic Leaching Procedure
TPH	Total petroleum hydrocarbon(s)
TTR	Tonopah Test Range
UDP	Underground Discharge Point
USACE	United States Army Corps of Engineers
UST	Underground Storage Tank
VOC	Volatile organic compound(s)
$\mu\text{g/L}$	Microgram(s) per liter
%R	Percent recovery

1.0 Introduction

This Corrective Action Investigation Plan (CAIP) has been developed in accordance with the *Federal Facility Agreement and Consent Order* (FFACO) that was agreed to by the U.S. Department of Energy, Nevada Operations Office (DOE/NV), the State of Nevada Division of Environmental Protection (NDEP), and the U.S. Department of Defense. The CAIP is a document that provides or references all of the specific information for investigation activities associated with Corrective Action Units (CAUs) or Corrective Action Sites (CASs) (FFACO, 1996). As per the FFACO (1996), CASs are sites potentially requiring corrective action(s) and may include solid waste management units or individual disposal or release sites. Corrective Action Units consist of one or more CASs grouped together based on geography, technical similarity, or agency responsibility for the purpose of determining corrective actions.

This CAIP contains the environmental sample collection objectives and the criteria for conducting site investigation activities at CAU No. 423, the Building 03-60 Underground Discharge Point (UDP), which is located in Area 3 at the Tonopah Test Range (TTR). The TTR, part of the Nellis Air Force Range, is approximately 225 kilometers (km) (140 miles [mi]) northwest of Las Vegas, Nevada (Figures 1-1 and 1-2). Corrective Action Unit No. 423 is comprised of only one CAS (No. 03-02-002-0308), which includes the Building 03-60 UDP and an associated discharge line extending from Building 03-60 to a point approximately 73 meters (m) (240 feet [ft]) northwest as shown on Figure 1-3.

1.1 Purpose

The UDP is a vertical, 107-centimeter (cm) (42-inch [in.]) corrugated steel culvert approximately 73 m (240 ft) northwest of Building 03-60. The UDP was used between approximately 1965 and 1990 to dispose of waste fluids from the Building 03-60 automotive maintenance shop. It is likely that soils surrounding the UDP have been impacted by oil, grease, cleaning supplies and solvents (IT, 1994) as well as waste motor oil and other automotive fluids released from the UDP.

The purpose of the investigation at the Building 03-60 UDP is to:

- Determine the UDP configuration.




Figure 1-1
Tonopah Test Range Location Map




Figure 1-2
 Area 3 Location Map, Tonopah Test Range




Figure 1-3
Building 03-60 UDP Location Map

- Identify the presence and nature of possible contaminants of potential concern (COCs) within the UDP.
- Determine the vertical and lateral extent of possible contaminant migration.
- Evaluate the potential impact to human health and the environment.
- Provide sufficient information and data to develop and evaluate appropriate corrective actions for the CAS.

This CAIP was developed using the U.S. Environmental Protection Agency (EPA) Data Quality Objectives (DQOs) (EPA, 1994) process to clearly define the purpose(s) for which environmental data will be used and to design a data collection program that will satisfy these goals. A DQO scoping meeting was held prior to preparation of this plan; a summary of the meeting notes is presented in Subsection 3.4 and in an unedited worksheet format as Appendix A.

1.2 Scope

The scope of this investigation includes the following:

- Drilling characterization boreholes using the dry sonic drilling method or another comparable method capable of penetrating potential leach rock materials (e.g., concrete or gravel) and providing suitable core for sample collection and logging of subsurface conditions
- Evaluating the UDP construction and configuration
- Conducting continuous field screening to direct drilling and sampling activities and provide an initial assessment of subsurface impact
- Collecting soil samples for laboratory analysis of environmental and geotechnical parameters
- Logging core to assess soil characteristics

The drilling locations will be selected to target the UDP itself and the area immediately surrounding the UDP which is most likely to be impacted by contaminant migration.

1.3 CAIP Contents

Section 1.0 of this CAIP provides an introduction to this project, including the purpose and scope for this corrective action investigation. The FFACO (1996) requires that CAIPs address the following elements:

- Management
- Technical aspects
- Quality assurance
- Health and safety
- Public involvement
- Field sampling
- Waste management

The managerial aspects of this project are discussed in the DOE/NV Environmental Restoration Project (ERP) *Project Management Plan*, Rev. 0 (DOE/NV, 1994a) and the site-specific Project Management Plan. The technical aspects of this CAIP are contained in the *Corrective Action Unit Work Plan, Tonopah Test Range, Nevada* (hereafter referred to as the TTR Work Plan) (DOE/NV, 1996a) and in Sections 3.0 and 4.0 of this document. General field and laboratory quality assurance and quality control (QA/QC) issues are presented in the *Industrial Sites Quality Assurance Project Plan* (QAPP) (DOE/NV, 1996b), and the specific aspects of field QA/QC are discussed in approved procedures. Collection of field QC samples will be specified in site-specific field instructions which will be written prior to commencement of field activities. The health and safety aspects of this project are documented in the *Environmental Restoration Project Health and Safety Plan* (HASP) (DOE/NV, 1996c) and will also be supplemented with a site-specific HASP written prior to commencement of field work. No CAU-specific public involvement activities are planned at this time; however, an overview of public involvement is documented in the "Public Involvement Plan" in Appendix V of the FFACO (1996). Field sampling activities are discussed in Section 4.0 of this CAIP. Waste management issues are discussed in the TTR Work Plan (DOE/NV, 1996a) and in Section 5.0 of this CAIP. The project schedule and records availability information are discussed in Section 6.0 of this CAIP, and a list of project references is provided in Section 7.0 of this CAIP.

2.0 Facility Description

Corrective Action Unit No. 423 is comprised of the Building 03-60 UDP and an associated waste oil discharge line. Process knowledge and available resources relating to the Building 03-60 and UDP site history were examined during the DQO process (Appendix A). This information includes TTR data reports describing previous field efforts and sampling results, geophysical survey data, historical aerial photographs, and site maps. General background information pertaining to the history of TTR and the Area 3 Compound, a geologic assessment, and an overview of the area hydrogeology including depths to groundwater are provided in the TTR Work Plan (DOE/NV, 1996a). A summary of the information specific to Building 03-60 and the UDP is presented in the following sections.


2.1 Physical Setting

Surface materials around the site consist of sand, gravel, and cobbles with little to no vegetation. The topography slopes gently to the northwest with surface drainage flowing in the same direction. Depth to groundwater beneath the UDP is estimated at 110 to 120 m (361 to 394 ft) below ground surface (bgs). The groundwater flow direction is generally to the north-northwest (DOE/NV, 1996a).

The specific configuration of the UDP is unknown; however, a gravel layer or some type of irregular base is believed to exist at the bottom of the UDP. Based on historical knowledge of typical UDP construction techniques, a gravel or leach rock (e.g., concrete "rip rap") column of unknown vertical extent may exist below the bottom of the UDP. If the UDP base is poured concrete, it may indicate the UDP is part of a concrete holding tank below the UDP base; however, this is unlikely. The most likely UDP configuration is that of a leach rock infiltration column of unknown depth below the bottom of the culvert. A conceptual cross-sectional view of the Building 03-60 UDP is shown in Figure 2-1.

2.2 Operational History

Building 03-60, the Auto Maintenance Shop in the TTR Area 3 compound (Figures 1-2 and 1-3), was constructed in 1962 as a light-duty fleet maintenance shop and is currently in use for the same purpose. Originally, waste oils were drained from Building 03-60 to Septic Tank 33-12 and the associated leachfield (Figure 1-3) to the south of Building 03-60. After the septic tank



NOT TO SCALE

LEGEND

	Former fluid waste
	Alluvial fill and gravel
	Discharge line location (unconfirmed)
	Unknown boundary
	UDP
	Possible leach rock

Figure 2-1
 Conceptual Cross-Section of the Building 03-60 UDP

was abandoned (possibly in 1965), the waste oil products (including anti-freeze, motor oil, and hydraulic oil) were instead discharged into a sump believed to be located at the northwest corner of Building 03-60 (DOE/NV, 1996a). A gravity-fed discharge line from the sump carried the waste oil to a point approximately 73 m (240 ft) to the northwest, where the line fed into what was originally thought to be an underground storage tank (UST) based on interviews and at least one site drawing. It should be noted that Septic Tank 33-12 and its associated leachfield are not included as part of the CAU No. 423 investigation, but are being addressed under CAU No. 427, the Area 3 Septic Waste Systems Numbers 2 and 6.

The specific time period of waste oil discharge to the Building 03-60 sump is unknown, but may have been from 1965 to 1989 or 1990. Sometime prior to 1993, wastes generated at the Auto Maintenance Shop were no longer drained into the UST (UDP); instead, they were containerized and delivered to the United States Air Force for disposal (DOE/NV, 1996a). It is known that a minimum of approximately 1,514 liters (L) (400 gallons [gal]) of waste oil were drained into the UST (UDP) over an indeterminate period of time (see Section 2.3); the actual amount may be significantly greater.

2.3 Waste Inventory

Historical records of product use and disposal at the Building 03-60 Automotive Maintenance Shop have not been located and/or were not maintained. However, based on process knowledge of typical automotive maintenance activities, products likely to have been discharged to the Building 03-60 UDP include oil, grease, cleaning supplies, and solvents (IT, 1994) as well as waste motor oil and other automotive fluids.

On April 10, 1996, a homogenized waste oil sample collected from the 1.5 m (5 ft) of standing liquid in the UDP was submitted for laboratory analysis of volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), *Resource Conservation and Recovery Act* (RCRA) Toxicity Characteristic (TC) metals, total pesticides, total polychlorinated biphenyls (PCBs), flashpoint, and radionuclides. Detected analytes included volatile organic compounds, aromatics, and chlorinated aromatics. A table listing the analytical results for the detected parameters is provided as Attachment 3 of Appendix A.

Based on these sampling results, an extensive research effort was conducted in 1996 as part of the waste determination (see Attachment 4 of Appendix A). Shop surveys conducted by

Reynolds Electrical and Engineering Co., Inc., Industrial Hygiene personnel were located and included in the waste determination package (IT, 1996c). Material Safety Data Sheets were obtained for products identified in the shop surveys to aid in the waste determination (IT, 1996c). A solvent known as "Safety Kleen" (i.e., <10% orthodichlorobenzene by volume) was found to have been used in the building. Although there are no records indicating this solvent was disposed in the UDP, a trace amount of orthodichlorobenzene was detected in the liquid analyzed from the UDP. As a result, the waste determination indicated the UDP liquid contained an "F002" listed waste in the form of orthodichlorobenzene (1,2-dichlorobenzene) (IT, 1996c). It is unknown whether the standing liquid composition represented all waste oil products previously disposed since the UDP inception or only those products from a certain disposal time period.

2.4 Release Information

Approximately 1,514 L (400 gal) of liquid waste was removed from the UDP and properly disposed of in September, 1996 (IT, 1996a). Approximately 950 L (250 gal) of liquid waste is scheduled to be removed from the UDP and properly disposed of in October, 1997. It is unknown whether waste oil releases have occurred, but based on the suspected length of operation of the UDP system (up to 25 years), it is likely that the soils beneath and/or surrounding the UDP culvert have been impacted. It is also unknown whether groundwater has been impacted by a release. However, given the depth to groundwater, the viscous nature of the waste oil removed from the UDP, and the fine-grained native soils, a groundwater impact is unlikely.

2.5 Investigative Background

In July 1993, a ground-penetrating radar geophysical survey was performed to confirm the UST (UDP) location (IT, 1997a). Based on the survey results, a clear anomaly caused by the waste oil UST (UDP) was delineated. In addition, the waste oil line was traced with an electromagnetic line tracer from the UST (UDP) to Building 03-60. No apparent connections to the waste oil line from other sources (i.e., other buildings) were noted during this survey.

During a March 1994 inspection of Building 03-60, the sump could not be located and was suspected to be sealed beneath a more recently emplaced concrete flooring slab (DOE/NV, 1996a). The upgradient end of the discharge line was also not found. Although Building 03-60 is still active, it is assumed that the discharge line and sump are inactive and that no contributions are being made to the UDP from any source.

On March 20, 1996, a soil excavation effort was held to locate the supposed buried waste oil tank (IT, 1996a). During this excavation, it was determined that the subsurface structure was actually an underground discharge point rather than an underground storage tank. The UDP, consisting of a 107-centimeter (cm) (42-inch [in.]) diameter corrugated metal culvert, set vertically in the ground, was identified at a depth of 0.6 m (2 ft) below surface grade (IT, 1996b). The configuration of the culvert was consistent in size and location with the anomaly noted during ground penetrating radar surveys conducted in 1994 (IT, 1997a). Overall, the culvert was observed to be in good condition. However, several small holes were noted near the top. Two of the holes, located on opposite sides of the pipe, may have been used for holding a lowering bar in place. Additional small holes, likely due to corrosion, were also noted near the top.

The culvert opening was covered by a 112-cm (44-in.) diameter, 1.3-cm (0.5-in.) thick, fabricated steel lid. Approximately 30.5 cm (12 in.) below the rim was a 4.4-cm (1.75-in.) diameter galvanized pipe that is believed to be the downgradient end of the discharge line from Building 03-60 sump. A black liquid with a strong hydrocarbon odor was visible 4.6 m (15 ft) below the culvert rim. The liquid was determined to be approximately 1.5 m (5 ft) deep. No rings, indicative of higher fluid levels, were noted (IT, 1996b). It is unknown whether releases from the UDP into the surrounding subsurface have occurred. Building 03-60, the UDP, and the suspected location of the waste oil line are indicated on the site map (SNL, 1989) and aerial photograph (EG&G, 1988) contained in Attachment 1 of Appendix A. Ground-level photographs of the UDP taken during the excavation activities (IT, 1996a) are shown in Attachment 2 of Appendix A.

Following collection and analysis of a waste oil sample in April, 1996 (IT, 1996a), the liquid in the UDP was removed (approximately 1,514 L [400 gal]), characterized, and properly disposed of in September 1996 (see Attachments 3, 4, and 5 of Appendix A). After pumping, a small amount of residual sludge remained at the bottom of the UDP culvert.

In June 1997, the fluid in the UDP was measured at approximately 21.6 cm (8.5 in.) in depth (IT, 1997b). The fluid depth has increased to approximately 1 m (3.3 ft), and a second pumping is scheduled for October 1997. The additional liquid in the UDP is probably the product of three input sources: surface water, minor residual waste oil, and infiltration from surrounding soil. Surface water inflow is the most likely explanation for most of the fluid level increase since liquid was removed from the UDP in September 1996.

It is unlikely that liquid has been added to the UDP through the pipeline from Building 03-60 after the September 1996 pumping event. Wastes generated at the Auto Maintenance Shop are containerized and delivered to the United States Air Force for disposal (see Section 2.2) and there is no known connection between Building 03-60 and the UDP. A pipeline camera survey was conducted to examine the condition of the discharge pipe from Building 03-60 in early September 1997. The survey was conducted from the UDP end of the pipe, and revealed the pipe is damaged approximately 3.7 m (12 ft) from the UDP. The damage to the pipe prevents further investigation using a pipeline camera. Any possibility of additional input of fluid to the UDP through the pipe from Building 03-60 has been eliminated by sealing the pipe with a cap and Teflon tape in early October, 1997.

Recent field observations identified rain-storm produced surface water as a possible contributor to liquid in the UDP. The UDP lid was below grade in a small depression produced by exposing the UDP in March 1996. This depression was below grade at the base of a slope. Ponding of storm runoff in the depression was observed in September 1997 while it was lined with plastic. A field effort in early October 1997 sealed the UDP from further surface water input by extending the top of the UDP above the existing grade with an extension of metal culvert.

The remaining fluid input possibility is infiltration of liquid from the soil surrounding the UDP. This scenario is unlikely, but a depth-recording device was installed within the UDP to monitor any fluctuations of liquid depth. No fluctuations had been detected prior to the scheduled liquid removal in October 1997. The depth recorder will detect and record any increase in liquid level after the pumping event.

3.0 Objectives

The sampling objectives were determined using the DQO process outlined by the EPA in their *Guidance for the Data Quality Objectives Process* (EPA, 1994). The DQOs are qualitative and quantitative statements that specify the quality of the data required to support potential courses of action for the UDP. The DQOs were developed to clearly define the purpose(s) for which environmental data will be used and to guide the design of a data collection program that will satisfy these goals. One tool used in the DQO process is the formulation of site conceptual models.

3.1 Conceptual Site Model

A conceptual model has been developed to postulate a subsurface release scenario and exposure pathways from the potential contaminant sources associated with the UDP. The model encompasses information on the geology, climate, hydrogeology and infrastructure at the TTR Area 3. Topography information is not considered in the model because of the limited areal extent of the CAU. Floodplain studies are not necessary for the model because the CAU is not located within a floodplain. The model is based on assumptions and premises that were discussed during the DQO process and outlined in the DQO worksheet (Appendix A). If the conceptual model is proven incorrect by the results of environmental sampling, then NDEP will be notified and the site rescoped. The following points summarize the primary assumptions that were included in the DQOs (Appendix A) and considered in formulating the site conceptual model:

- The UDP is assumed to have received waste only from Building 03-60 via the discharge line.
- Dates of discharge to UDP are unknown, but are assumed to be approximately 1965 to 1990.
- No discharge to the UDP has occurred since approximately 1990.
- Native soils in the UDP area are comprised of heterogeneous layers of clays, sands, and gravels (alluvium) with possible cobbles or boulders. Bedrock is not anticipated to be encountered in the UDP area.
- Depth to groundwater is between 110 and 120 m (361 to 394 ft) below ground surface (bgs).

- The total volume of waste liquid discharged to the UDP is unknown, but is greater than 400 gal.
- The actual UDP configuration is unknown, but is assumed to contain gravel or leach rock to an unknown depth below the bottom of the corrugated metal culvert.
- Sampling results of liquid in the UDP indicate the presence of orthodichlorobenzene.
- Sampling results obtained during the 1996 sampling effort (see Attachment 3 of Appendix A) are assumed to be representative of COCs in UDP area.
- The impact to soil from COCs is assumed to be less than 15.2 m (50 ft) bgs and less than a 7.6-m (25-ft) lateral radius from the UDP center.
- If leach rock is present, the most significant component of COC migration would be in the downward direction with the area most likely impacted being the leach rock column below the UDP and the soils adjacent to the leach rock.
- If leach rock is not present, lateral migration may be initially more significant than vertical migration.
- Groundwater impact is unlikely because depth to groundwater is extensive (greater than 91.4 m [300 ft] [DOE/NV, 1996a]); the waste oil has a high viscosity which may preclude extensive migration; and the environmental conditions at the site (i.e., arid climate; low permeabilities) are not conducive to downward migration.
- Future use of Building 03-60 is anticipated to be similar to current use (actively used for light-duty automotive maintenance).
- Inadvertent excavation of contaminated material by site workers is the likely potential exposure pathway.
- The dry sonic drilling method (or an equivalent method) is adequate to provide characterization sampling.

Based on these assumptions, Figures 3-1 and 3-2 were developed to depict possible scenarios for receptors and subsurface impact. Figure 3-1 indicates the conceptualization that the site has one exposure route, ingestion of soil through the mouth or nose. Inadvertent intrusion into the site (such as digging with a backhoe or drilling) could disturb the soil or unearth impacted soil and cause a contaminant release to possible receptors (such as site workers). Although site access is currently restricted by fencing, the potential for inadvertent disturbance exists. Figure 3-2





Figure 3-1
Exposure Pathway Conceptual Model



NOT TO SCALE

	Former fluid waste
	Alluvial fill and gravel
	Discharge line location (unconfirmed)
	Possible leach rock
	Unknown boundary
	Direction of possible contaminant release
UDP	Underground discharge point

Figure 3-2
 Subsurface Release Conceptual Model

indicates the conceptualization that a release to the soils surrounding the UDP has likely occurred and that the impact does not extend beyond 9.1 m (30 ft) below the UDP bottom and 7.6 m (25 ft) laterally from the center of the UDP. The most likely affected areas are located immediately beneath and lateral to the UDP bottom. Liquid waste would initially migrate laterally, then vertically downward. Lateral migration may also occur through hole/cracks in the UDP culvert sides. Subsurface variations may also contribute to lateral migration. It is assumed that the leach rock (if present) below the UDP bottom is homogeneous. Infiltration is limited to less than 9.1 m (30 ft) vertically below the UDP culvert bottom and less than a 7.6-m (25-ft) radius from the center of the UDP. Infiltration into the soils below and/or adjacent to the discharge line, either at the discharge line end(s) and/or via cracks or breaks along the length of the line, may also have occurred.

A groundwater impact is possible if downward migration is greater than approximately 91.4 m (300 ft). If it is determined after sampling that groundwater may be impacted, the site may be rescoped, and the groundwater pathway will be investigated. However, based on the estimated depth to groundwater, the viscous nature of the waste oil, and the fine-grained soils, a groundwater impact is not anticipated.

3.2 Contaminants of Potential Concern

The previous waste oil sampling results (Attachment 3 of Appendix A) indicated the presence of volatile organic compounds, aromatics, chlorinated aromatics, and metals (below regulatory action levels). Based on process knowledge of liquid waste products from automotive maintenance activities as well as on the previous sampling results, it is recommended that subsurface soil samples collected in the Building 03-60 UDP study area be analyzed for:

- Total VOCs
- Total SVOCs
- Total RCRA metals
- Total PCBs
- Total petroleum hydrocarbons (TPH)

It should be noted that analysis for gamma-emitting radionuclides (i.e., gamma scan) will only be performed if field screening results indicate radionuclides above two times background. Radionuclides are not anticipated to be detected at this site.

3.3 Preliminary Action Levels

Preliminary action levels for both on-site field screening methods and off-site analytical methods will be used to determine the presence of contamination.

The following action levels will be used for on-site field screening:

- VOC screening at 25 parts per million (ppm) or 2½ times background (closed-bag headspace), whichever is greater
- For TPH, the analytical concentration of 100 ppm TPH or a field screening concentration that is comparable to an analytical concentration of 100 ppm TPH
- For radiation (alpha, beta/gamma) screening, the presence of man-made radionuclides above two times background, or
 - Beta/gamma activity levels > 0.5 millirem (5 microsieverts) per hour (dose rate criteria) at a distance of 30 cm (11.8 in.) above ground surface (DOE/NV, 1996d).
 - Alpha-emitting radionuclides averaged over 100 square meters (1,076 square feet), which could result in airborne radioactivity levels > 1/50 of a Derived Air Concentration.
 - Field screening of material being handled, such as core samples, which indicate surface radioactivity values exceeding those listed in Table 2-2 of the *NV/YMP Radiological Control Manual* (DOE/NV, 1996d).

Off-site laboratory analytical results will also be compared to preliminary action levels to evaluate the need for possible corrective actions. The analytical data will be used to support the preparation of a Corrective Action Decision Document (CADD) in which various corrective action strategies will be examined. These preliminary action levels are as follows:

- RCRA contaminant concentrations above the NDEP Corrective Action Regulations (NDEP, 1996)
- TPH concentrations above the TPH limits per the *Nevada Administrative Code* (NAC) 445A2272 (NAC, 1996a) and NDEP Corrective Action Regulations (NDEP, 1996)
- Background concentrations of radioactive material or concentrations above those listed in the *Offsite Radiation Exposure Review Project (ORERP), Phase II Soils Programs* report (McArthur and Miller, 1989)

3.4 DQO Process Discussion

A DQO Scoping meeting for CAU No. 423 was held in June, 1997. The product of this meeting was a worksheet following the EPA seven step DQO guidance outline (EPA, 1994). The worksheet is attached to this document as Appendix A. The DQO process was used to determine characterization procedures adequate to define the contamination produced by the UDP. The DQO process was also used to define stop points to provide guidance in unexpected situations during the investigation.

Laboratory analysis of the soil samples will provide the means for a quantitative measurement of the potential COCs. The analytical methods and minimum reporting limits for each analyte are provided in Table 3-1.

If environmental sample data indicate that no analytes are above the criteria presented in Section 3.3, then no further action will be recommended. Modeling of the likelihood of future increases in contaminant concentrations may be required to assist in these recommendations and decisions.

Stop Points for Notification

The following represent specific stop points that were determined during the DQO process to provide guidance on unexpected situations that may arise during the field investigation:

- If field screening results indicate that contamination is more extensive than predicted (i.e., drilling advances to the saturated zone), the field investigation will stop; NDEP will be notified; and the site will be rescoped.
- If radiation is encountered above field screening action levels (i.e., two times background), drilling will stop; the NDEP will be notified; and the need to initiate a Radiological Work Permit will be assessed.
- If operations need to stop because of unexpected site conditions, NDEP will be notified.
- If drilling encounters bit refusal that precludes successful investigation of the site, NDEP will be notified for decision concurrence.
- If conditions warrant changing the drilling method, NDEP will be notified, and the investigation will be rescoped.

Table 3-1
Site Characterization Laboratory Analytical Requirements
 (Page 1 of 2)

Analyte	Medium ^a	Analytical Method	Minimum Reporting Limit	Acceptable Precision ^b (RPD)	Acceptable Accuracy ^b (%R)
Total VOCs	Water	8260 ^c	Analyte-specific estimated quantitation limits ^d	14	60 - 132
	Soil			24	59 - 172
Total SVOCs	Water	8270 ^c	Analyte-specific estimated quantitation limits ^d	50	5 - 230
	Soil			50	11 - 142
Total RCRA Metals Arsenic Barium Cadmium Chromium Lead Mercury Selenium Silver	Water	6010/7470 ^c	10 µg/L 200 µg/L 5 µg/L 10 µg/L 3 µg/L 0.2 µg/L 5 µg/L 10 µg/L	20	75 - 125
Total RCRA Metals Arsenic Barium Cadmium Chromium Lead Mercury Selenium Silver	Soil	6010/7470 ^c	2 mg/kg 40 mg/kg 1 mg/kg 2 mg/kg 0.6 mg/kg 0.1 mg/kg 1 mg/kg 2 mg/kg	20	75 - 125
Total Petroleum Hydrocarbons	Water (gasoline)	8015 modified ^c	1 mg/L	20	25 - 145
	Water (diesel)		1 mg/L	20	25 - 145
	Water (oil)		1 mg/kg	20	25 - 145
	Soil (gasoline)		1 mg/kg	30	30 - 130
	Soil (diesel)		30 mg/kg	30	30 - 130
	Soil (oil)		30 mg/kg	30	30 - 130
Total PCBs	Water	8080 ^c	Analyte-specific estimated quantitation limits ^d	30	8 - 160
	Soil			50	8 - 139

Table 3-1
Site Characterization Laboratory Analytical Requirements
 (Page 2 of 2)

Analyte	Medium ^a	Analytical Method	Minimum Reporting Limit	Acceptable Precision ^b (RPD)	Acceptable Accuracy ^b (%R)
Gamma Spectroscopy (Based on Cesium-137)	Water	EPA 901.1 ^e or LAL-91-SOP-0063 ^f	Background levels or ORERP ^g	20	80 - 120
	Soil	HASL 300, 4.5.2.3 ^h LAL-91-SOP-0064 ⁱ		20	80 - 120

^aQC (water) samples are included in table.

^bPrecision and Accuracy requirements are parameter-specific and are referenced from the *Contract Laboratory Program Statement of Work* (EPA, 1990). The high-low range for all parameters for each method is displayed here, but the actual range will vary by analyte.

^cEPA *Test Methods for Evaluating Solid Waste*, 3rd edition, Parts 1-4, SW-846 (EPA, 1996)

^dEstimated Quantitation Limit (EQL) as given in Method SW-846, U.S. EPA (EPA, 1996)

^ePrescribed Procedures for Measurement of Radioactivity in Drinking Water (EPA, 1980)

^fLAS Laboratories, 1996a, Standard Operating Procedure.

^gOffsite Radiation Exposure Review Project (ORERP), Phase II Soils Program Report (DOE/NV/10384-23) (McArthur and Miller, 1989)

^hEnvironmental Measurements Laboratory Procedure Manual, HASL-300, U.S. Department of Energy (DOE, 1992)

ⁱLAS Laboratories, 1996b, Standard Operating Procedure.

EPA = U.S. Environmental Protection Agency

mg/kg = Milligram(s) per kilogram

PCB = Polychlorinated biphenyl(s)

mg/L = Milligram(s) per liter

RCRA = Resource Conservation and Recovery Act

RPD = Relative Percent Difference

SVOC = Semivolatile organic compound(s)

VOC = Volatile organic compound(s)

µg/L = Microgram(s) per liter

%R = Percent recovery

Note: Gamma Spectroscopy analysis will only be performed if field screening levels indicated the presence of gamma-emitting radionuclides at levels greater than two times background.

4.0 Field Investigation

This section of the CAIP contains the sampling approach for investigating the Building 03-60 UDP, including the waste oil discharge line. All sampling activities will be conducted in compliance with the Industrial Sites QAPP (DOE/NV, 1996b) and other applicable, approved procedures which will be described in the site-specific field instructions. Quality assurance and quality control requirements for field and laboratory environmental sampling are contained in the Industrial Sites QAPP (DOE/NV, 1996b) and in Table 3-1. A description of the QC samples to be collected for this project will be included in site-specific field instructions.

4.1 Sampling Approach

The sampling approach for CAU No. 423 will consist of drilling a minimum of one borehole to investigate the presence of waste oil products directly beneath the UDP. Step-out borings will also be drilled if needed to evaluate the extent of lateral and vertical contaminant migration. Continuous field screening and environmental sampling will be conducted during the investigation, and the results will be utilized during the corrective action decision process. In the following sections, the drilling, field screening, sampling, and discharge line investigation approaches are described.

4.1.1 Soil Borings

In order to allow subsurface drilling directly into the UDP, a surface casing (larger in diameter than the drill string) will be installed within the culvert and then the annulus outside the surface casing will be filled with clean pea gravel (approximately 5.4 cubic meters [7 cubic yards]). This will enable a drill rig to position directly over the center of the UDP and samples to be collected directly from the most likely impacted area. One boring will then be advanced directly through the center of the UDP. After reaching the current bottom of the UDP at approximately 20 ft bgs, drilling will continue until two consecutive, 1.5-m (5-ft) interval, non-detect field screening readings (for all three parameters) are obtained (if above 15.2 m [50 ft] bgs). If two consecutive, 1.5-m (5-ft) interval, non-detect field screening readings are not obtained above a depth of 15.2 m (50 ft) bgs, field screening will then be conducted at 3-m (10-ft) intervals; and drilling will continue until two consecutive, non-detect field screening readings are obtained or until groundwater is encountered, whichever occurs first. During drilling, ground surface will be referenced from the top of the UDP backfill.

If COCs above the indicated field screening action levels (Section 3.3) are identified during advancement of the initial boring, a minimum of three step-out borings will be advanced to evaluate the extent of lateral and vertical contaminant migration. The initial step-out borings will be located in a roughly triangular pattern 7.6 m (25 ft) or less from the UDP center. Based on field screening results, additional step-outs (beyond the initial three) may also be needed to delineate the plume boundaries. At a minimum, step-out borings will be advanced to the lowest vertical extent of contamination (based on field screening readings) found in the UDP boring.

The dry sonic drilling method will be used to advance the holes. The method provides a continuous core from the surface to total depth from which to collect environmental samples and examine the native soil and/or leach rock beneath the UDP culvert. The dry sonic drilling method was selected over other investigative methods (i.e., trenching or hollow-stem auger) for the following reasons:

- The volume of investigation-derived waste (IDW) is significantly reduced.
- A vertical profile of the subsurface materials may be obtained via collection of continuous core.
- High quality, relatively undisturbed samples are provided.
- Drill rates are relatively fast, and most types of materials (e.g., leach rock or metal bottom of the UDP) can be penetrated.

A plan view of the UDP borehole location and proposed locations for step-out borings (if needed) is shown on Figure 4-1. Actual locations may be adjusted based on field observations.

4.1.2 Field Screening

Field screening tests will be performed for all borings. In the UDP center boring, field screening will be performed at 1.5-m (5-ft) intervals from the base of the UDP (approximately 6.1 m [20 ft] bgs) to approximately 15.2 m (50 ft) bgs. If drilling should need to continue past 15.2 m (50 ft) bgs, field screening will continue in 3.0-m (10-ft) intervals to total depth. In any




Figure 4-1
 Proposed Borehole Locations, Building 03-60 UDP

step-out borings, field screening will be conducted from ground surface to total depth in the same manner as described for the UDP center boring.

The field screening methods will consist of headspace testing for VOCs, TPH screening, and radiological screening for alpha and beta/gamma emitters. This field screening data will serve three purposes. First, the data will provide continuous semiquantitative measurement of the subsurface environmental impact (providing sufficient material is available to conduct the tests) for site characterization. Second, the data will provide a mechanism for guiding the investigation deeper, if necessary. If field screening results exceed the preliminary action levels listed in Section 3.3, then drilling will continue until two consecutive, non-detect results are recorded. Third, the data will be used to assist with the selection of samples to be submitted for laboratory analysis.

4.1.3 Sampling Criteria

Soil samples will be collected for laboratory analysis based on visual observations (e.g., areas of visible staining) and/or the results of field screening at 1.5-m (5-ft) intervals to a depth of 15.2 m (50 ft) bgs (and at 3-m [10-ft] intervals below 15.2 m [50 ft]) until two consecutive, non-detect field screening samples are obtained. In step-out borings (if performed), samples will be collected for laboratory analysis from the highest field-screening interval and the lowest vertical, non-detect interval. If field screening does not detect any contamination in the step-out borings, a sample from the lowest interval will be submitted for confirmation of the non-detect field screening readings.

Proposed analytical parameters were selected based on process knowledge, the results of the 1996 waste oil characterization sampling (IT, 1996c), and requirements specified by the NDEP for waste characterization. The parameters, methods, and associated QC ranges for precision and accuracy measurements are specified in Table 3-1.

Soil samples will also be collected for evaluation of geotechnical parameters with regard to future corrective action strategies. The geotechnical analysis will be performed by an off-site, fixed-based laboratory. Analytical parameters and methods are presented in Table 4-1.

Table 4-1
Geotechnical Analyses, Building 03-60 UDP

Analysis	Method
Initial moisture content	ASTM ^a D 2216
Dry bulk density	EM ^b -1110-2-1906
Calculated porosity	EM-1110-2-1906
Saturated/unsaturated hydraulic conductivity	ASTM D 5084
Particle-size distribution (preferred method is hydrometer distribution)	ASTM D 422
Water-release (moisture retention) curve	ASTM D 3152
Atterberg Limits	ASTM D 4318-93
Microbial Activity	Laboratory Specific


^a*Annual Book of ASTM Standards*, Section 4, "Construction," Volume 04.08, Soil and Rock (1), and Volume 04.09, "Soil and Rock" (11), 1996.

^bUnited States Army Corps of Engineers (USACE), Engineer Manual 1110-2-1906, "Laboratory Soils Testing," Appendix II, 1970

ASTM = American Society for Testing and Materials

EM = Engineering Manual

Soil samples will be collected from the bottom 0.6 m (2 ft) of each sample interval within the core barrel sampler. Figure 4-2 is a generalized schematic of a core barrel sampler and the sequence to be followed for sample collection. Beginning at the nose of the core barrel, the first two portions will be retained for total VOCs and TPH-gasoline analysis, respectively. The next portion of the core will be retained for VOC and TPH field screening. The fourth portion will be retained for total SVOCs, PCBs, TPH-diesel, and RCRA metals analysis. The fifth portion will be analyzed for gamma-emitting radionuclides, if necessary. The remaining core will be used for analysis of geotechnical parameters. Samples will be submitted to the laboratory in brass sleeves and/or glass jars. The entire core will be field screened for alpha and beta/gamma radiological contamination during sample aliquot collection.



Note: Samplers will be fitted with 3-inch brass sleeves.

Figure 4-2
Schematic of the Core-Barrel Sampler

Discretionary sampling points may also be selected for laboratory analysis based on a visual examination by the site supervisor/geologist. Selection criteria for discretionary samples could include:

- Moist or discolored zones
- Significant changes in soil grain size
- Increases in odor

All equipment which contacts the soil will be decontaminated in accordance with contractor's written and approved procedures consistent with the Environmental Restoration Division Procedure ERD-05-701, "Sampling Equipment Decontamination," Rev. 0 (DOE/NV, 1994b), or as appropriate for special equipment being decontaminated (i.e., steam-cleaning core barrels).

Clean core barrels shall be used for each sampling event. This will minimize the potential for cross-contamination between sample locations. All samples collected for laboratory analysis will be aliquots of fresh media (rather than reusing the sample media used for screening). Records will be kept of the soil description, field screening measurements, and all other relevant data. All pertinent and required sampling information (i.e., date, time, sample interval) will be documented in accordance with the *Industrial Sites QAPP* (DOE/NV, 1996b). Approved Chain of Custody procedures (IT, 1997c) will be followed to assure the defensibility of the data.

5.0 Waste Management

Management of IDW will be based on regulatory requirements, field observations, and the results of laboratory analysis of the Building 03-60 UDP study area samples. Administrative controls (decontamination procedures and the characterization strategy) will minimize waste generated during the investigation.

Solid materials other than soil wastes are waste only by virtue of contact with contaminated media. The same is true of decontamination rinsate. Therefore, sampling and analysis of the IDW (other than soil from the borings), separate from site characterization analyses, will not be required. The data generated as a result of site characterization will be used to assign the appropriate waste type (i.e., ordinary, hydrocarbon, hazardous) to the IDW. Based on process knowledge and the previous sampling results, radioactive and mixed wastes are not anticipated at this site. The action levels for IDW contaminants are presented in Table 5-1.

Table 5-1
Action Levels for IDW Contaminants

Parameter	Action Level	Source	Comments
TPH ^a	100 ppm ^b	NAC445A2272 ^c	Regulated by the NDEP ^d
Total VOCs ^e , SVOCs ^f , and RCRA ^g metals	See note below	40 CFR 261 ^h	-----
Total PCBs ⁱ	50 ppm	40 CFR 761.1(b) ^j NAC444.940 to 444.9555 ^k	NDEP requires manifesting as hazardous waste for shipping and disposal purposes.
Radiological	Isotope specific	10 CFR 30.70 ^l Schedule A <i>'Exempt Concentrations'</i>	-----

^aTotal petroleum hydrocarbons

^bPart(s) per million

^cNevada Administrative Code, 1996b

^dNevada Division of Environmental Protection

^eVolatile organic compound(s)

^fSemivolatile organic compound(s)

^gResource Conservation and Recovery Act

^hCode of Federal Regulations, 1996a

ⁱPolychlorinated biphenyl(s)

^jCode of Federal Regulations, 1996b

^kNevada Administrative Code, 1990

^lCode of Federal Regulations, 1994

Note: Total VOCs, SVOCs, and metal concentrations of the samples will be determined through laboratory analysis. The laboratory-derived concentrations for soil samples (milligram/kilogram) will be divided by a factor of 20 and compared to the toxicity characteristic limit (milligram/liter) for hazardous parameters. If the total value divided by 20 is greater than the TC limit, IDW associated with these samples will be considered hazardous waste.

Ordinary, hydrocarbon, or hazardous waste, if generated, will be managed and disposed of in accordance with applicable U.S. Department of Energy Orders, U.S. Department of Transportation (DOT) requirements, RCRA regulations, agreements and permits between DOE and NDEP, and site-specific requirements. Decontamination activities will be performed according to approved procedures (e.g., IT, 1997c).

5.1 Waste Minimization

Corrective action investigation activities, including the proposed field technique of dry sonic drilling, have been planned to minimize the amount of IDW generated. Borehole or soil waste that does not require management as radioactive or RCRA-regulated waste will be disposed of as ordinary waste. Other waste, such as disposable sampling and personal protective equipment (PPE), will be segregated to the greatest extent possible to avoid generation of hazardous, radioactive, or mixed waste. Hazardous materials will be controlled, minimizing generation of hazardous or mixed waste.

5.2 Potential Waste Streams

Process knowledge and previous sampling results indicate that hydrocarbon waste and potentially hazardous materials were released to the UDP. Radioactive or mixed wastes are not anticipated at this site. Although liquid waste has been removed from the UDP, it is unknown whether an impact has occurred to the surrounding soils. There is a potential that hydrocarbon, hazardous, and/or ordinary wastes will be generated during the field investigation activities. In addition, the reagents used in the TPH field-screening methods will produce small quantities of hazardous wastes.

5.3 Investigation-Derived Waste Management

Wastes generated during the investigation activities may include, but are not limited to, the following:

- Decontamination rinsate
- Contaminated disposable or reusable sampling equipment (such as plastic, paper, sample containers, aluminum foil, or hand augers)
- Personal protective equipment
- Contaminated soil (such as soil retained for headspace testing)

- Soil contaminated by colorimetric TPH testing
- Contaminated core material

For administrative purposes, the waste will be managed as at least three waste streams: soil, contaminated solid trash, and liquid wastes such as decontamination rinsate. Each waste stream will be segregated, and additional segregation may occur within each waste stream. For example, the soil waste and decontamination rinsate will be segregated.

5.3.1 Sanitary Waste Management

Sanitary waste will be contained in plastic bags, dumpsters, or drums and transported to an Nevada Test Site (NTS)-managed or approved off-site sanitary waste landfill. Soils that are not regulated and meet the acceptance criteria for the NTS or approved off-site sanitary landfills will also be disposed of as sanitary waste.

5.3.2 Low-Level Waste Management

Radiological controls will not be instituted unless field screening or laboratory analytical results exceed two times background level (see Sections 3.2 and 3.3). Low-level waste, if generated, will be managed in accordance with DOE Orders and the requirements of the *Nevada Test Site Waste Acceptance Criteria* (NTSWAC) (DOE/NV, 1996e). Investigation-derived waste such as PPE will be placed in plastic bags marked with the date and associated borehole number. The bags will be placed in DOT-compliant drums (49 CFR 172) (CFR, 1997a) which will be properly labeled and locked or fitted with tamper-indicating devices. The drums will be staged at a designated Radioactive Materials Area pending disposal under NTSWAC requirements (DOE/NV, 1996e).

Low-level waste will be characterized in accordance with the requirements of the NTSWAC and the contractor-specific waste certification program plan and implementing procedures. Characterization will be based on laboratory results, field screening, process knowledge, or a combination thereof.

5.3.3 Hazardous Waste Management

Suspected hazardous wastes will be managed in accordance with RCRA and State of Nevada hazardous waste management regulations, interpreted as follows. Suspected hazardous wastes will be placed in DOT-compliant drums (49 CFR 172) (CFR, 1997a) which will be locked or

fitted with tamper-indicating devices. The containers shall be compatible with the waste in accordance with the requirements of 40 CFR 265.172 (CFR, 1996c). Containers shall be handled and inspected in accordance with the requirements of 40 CFR 265.173 and 174, respectively (CFR, 1996c). Based on process knowledge, incompatible wastes shall be managed in accordance with 40 CFR 265.177 (CFR, 1996c) (i.e., shall not be placed in the same container), and they shall be separated so that in the event of a spill, leak, or release, incompatible wastes shall not contact one another. Wastes shall be containerized in a manner to comply with Subpart C of 40 CFR 265 (CFR, 1996c).

Hazardous wastes shall be characterized in accordance with the requirements of 40 CFR 261 (CFR, 1996a). Characterization will be based on laboratory results, field screening results, process knowledge, or a combination thereof. Waste pending characterization will be marked with "Awaiting Analysis" stickers until its regulatory status can be determined through evaluation of laboratory results. The determination of whether the waste is characteristic or listed will be based on the *Code of Federal Regulations* (CFR) Title 40 Part 261, "Identification and Listing of Hazardous Wastes" (CFR, 1996a). Waste shall be traceable to its source and/or samples considered analogous to the waste (such as waste drill core associated with a sample). Traceability shall be maintained by numbering containers and keeping appropriate records which trace waste to samples, areas, or products. After receipt of analytical results, hazardous wastes, if identified, will be labeled and marked in accordance with the requirements of 40 CFR 262.32 (CFR, 1997b) and State of Nevada requirements such as writing the EPA Waste Code on the hazardous waste label. Depending on the nature and amount of waste being generated, the applicable waste management control areas, such as a Satellite Accumulation Area or Hazardous Waste Accumulation Area, will be established.

Hazardous wastes will be accumulated at the site of generation for less than 90 days in accordance with 40 CFR 262.34 (CFR, 1997b). Prior to 90 days after the accumulation start date as specified in 40 CFR 262.34(a) (CFR, 1997b) or generation of wastes in excess of quantity limits specified in 40 CFR 262.34(c)(1) (CFR, 1997b), the waste will be shipped to a permitted hazardous waste treatment, storage, or disposal facility. The waste will be shipped by an appropriately licensed and permitted hazardous waste hauler. A Uniform Hazardous Waste Manifest shall be completed prior to shipping hazardous waste in accordance with the requirements of 40 CFR 262.20, 262.21, 262.22, and 262.23 (CFR, 1997b). A copy of the


manifest shall be provided to the State of Nevada in accordance with state regulatory requirements.

5.3.4 Hydrocarbon Waste Management

Hydrocarbon waste such as contaminated soil containing more than 100 ppm TPH will be properly containerized in bags or drums and will be transported to an appropriately permitted hydrocarbon waste management facility after the waste is fully characterized. Hydrocarbon waste which has come in contact or has had the potential to contact radiologically contaminated media (e.g., cuttings) is to be considered radiological waste and managed in accordance with the handling procedures for low-level radiological waste (see Section 5.6).

5.3.5 Mixed Waste Management

Mixed waste, if generated, shall be managed in accordance with RCRA (40 CFR 262) (CFR, 1997b) and State of Nevada (NAC444) (NAC, 1990) regulations as well as DOE requirements for radioactive waste, interpreted as follows. Where there is a conflict in regulations or requirements, the most stringent shall apply. For example, the 90-day accumulation time limit and weekly inspections per RCRA regulations will be applied to mixed waste even though it is not required for radioactive waste. Conversely, while RCRA does not require documented traceability, the waste acceptance program for low-level radioactive waste does; therefore, traceability shall be documented as described in Section 5.5. In general, mixed waste shall be managed in the same manner as hazardous waste, with added mandatory radioactive waste management program requirements. Suspected mixed waste will be managed in accordance with applicable regulations and requirements and will be marked with "Awaiting Analysis" stickers pending characterization and confirmation of its regulatory status. However, mixed waste shall be transported to the NTS transuranic waste storage pad for storage pending treatment or disposal. Mixed waste with hazardous waste constituents below land disposal restrictions may be disposed of at the NTS Area 5 Radioactive Waste Management Site. Mixed waste not meeting land disposal restrictions will remain in Area 5 and require development of a treatment plan under the requirements of the Mutual Consent Order between DOE and the State of Nevada (NDEP, 1995).



6.0 Duration and Records Availability

6.1 Duration

Following submission of the final CAIP to the Project Manager, DOE/NV Industrial Sites Subproject, the following is a tentative schedule of activities (in calendar days):

- Day 0: Preparation for field work will begin.
- Day 65: NDEP will be notified regarding the field work start date.
- Day 71: The field work, including drilling, field screening, and sampling, will begin.
- Day 91: The field work will be completed and samples shipped to the laboratory for analysis.
- Day 161: The quality-assured laboratory analytical sample data will be available for NDEP review.
- Day 238: The CADD will be submitted to NDEP.

The following information will be reported in the CADD:

- Introduction, including purpose, scope, an FFACO cross-walk, and a discussion about the need for further action
- The results of the corrective action investigation
- A corrective measures study, including initial screening of alternatives, evaluation of alternatives, and comparison of alternatives
- The recommended alternative

6.2 Records Availability

This document is available in the DOE public reading rooms located in Las Vegas and Carson City, Nevada, or by contacting the DOE Project Manager. Historic information and documents referenced in this plan are retained in the project files and can be obtained through written request to the Project Manager, DOE/NV Industrial Sites Subproject.

7.0 References

ASTM, see American Society for Testing and Materials.

American Society for Testing and Materials. 1996. Sections 04.08 and 04.09, "Soil and Rock." In *Annual Book of ASTM Standards*. Philadelphia, PA.

CFR, see *Code of Federal Regulations*.

Code of Federal Regulations. 1994. 10 CFR Part 30.70, "Schedule A - Exempt Concentrations." Washington, DC: U.S. Government Printing Office.

Code of Federal Regulations. 1996a. 40 CFR Part 261, "Identification and List of Hazardous Waste." Washington, DC: U.S. Government Printing Office.

Code of Federal Regulations. 1996b. 40 CFR Part 761.1(b), "Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions." Washington, DC: U.S. Government Printing Office.

Code of Federal Regulations. 1996c. 40 CFR Part 265, "Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities." Washington, DC: U.S. Government Printing Office.

Code of Federal Regulations. 1997a. 49 CFR Part 172, "Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements." Washington, DC: U.S. Government Printing Office.

Code of Federal Regulations. 1997b. 40 CFR Part 262, "Standards Applicable to Generators of Hazardous Waste." Washington, DC: U.S. Government Printing Office.

DOE/NV, see U.S. Department of Energy, Nevada Operations Office.

EG&G. 1988. Aerial Photograph of Tonopah Test Range Area 3 Compound. Perf. No. 5956, Frame 23. 10 April.

EPA, see U.S. Environmental Protection Agency.

FFACO, see *Federal Facility Agreement and Consent Order*.

Federal Facility Agreement and Consent Order. 1996. Agreed to by the State of Nevada, the U.S. Department of Energy, and the U.S. Department of Defense.

IT, see IT Corporation.

IT Corporation. 1994. *Inspection of Building Structures at Sandia National Laboratories/Tonopah Test Range, August 1994*. Prepared for Sandia National Laboratories. Albuquerque, NM.

IT Corporation. 1996a. "Field Activity Daily Logs, Site Photographs, and Sample Collection Logs, Building 03-60 UDP Field Activities." Las Vegas, NV.

IT Corporation. 1996b. IT Corporation Internal Memo from M. Doe to R. Dubiskas, Re: Field Effort Results, Building 03-60, Tonopah Test Range, 21 March. Las Vegas, NV.

IT Corporation. 1996c. Letter to Mr. K. Cabble, DOE/NV, from Mr. R. Dubiskas, IT Corporation, Re: Records for Hazardous Waste Identification of Building 03-60 Waste Oil Underground Discharge Point, 2 July. Las Vegas, NV.

IT Corporation. 1997a. *Initial Surface Geophysical Survey Report for the Tonopah Test Range Environmental Restoration Sites*, DOE/NV-10972--93. Las Vegas, NV.

IT Corporation. 1997b. Field Activity Daily Log, "Building 03-60 Field Measurements," 30 June. Las Vegas, NV.

IT Corporation. 1997c. *IT Corporation Las Vegas Program Procedures Manual*, ITLV/1993/05. Las Vegas, NV.

LAS Laboratories, Inc. 1996a. "Sample Preparations and Analysis for Gamma Activity in Aqueous Samples," Standard Operations Procedure LAL-91-SOP-0063. Las Vegas, NV.

LAS Laboratories, Inc. 1996b. "Sample Preparations and Analysis for Gamma Activity in Solids," Standard Operations Procedure LAL-91-SOP-0064. Las Vegas, NV.

McArthur, R. D., and F.L. Miller, Jr. 1989. *Offsite Radiation Exposure Review Project (ORERP), Phase II Soils Programs*, DOE/NV/10384-23. Las Vegas, NV: Desert Research Institute.

NAC, see *Nevada Administrative Code*.

Nevada Administrative Code. 1990. "Solid Waste Disposal," NAC444.940-444.9555. Carson City, NV.

Nevada Administrative Code. 1996a. NAC445A. Nevada Revised Statute 445A2272, "Contamination of Soil: Establishment of Action Levels." 3 October. Carson City, NV.

Nevada Administrative Code. 1996b. "Storage Tanks," NAC459.9973. Carson City, NV.

NDEP, see *Nevada Division of Environmental Protection*.

Nevada Division of Environmental Protection. 1995. "Mutual Consent Agreement Between the State of Nevada and the Department of Energy for the Storage of Low-Level Land Disposal Restricted Mixed Waste." Transmittal from P. Liebendorfer (NDEP) to D. Elle (DOE/NV), 7 June. Carson City, NV.

Nevada Division of Environmental Protection. 1996. Corrective Action Regulations. Carson City, NV.

SNL, see Sandia National Laboratories.

Sandia National Laboratories. 1989. *Sandia Master Utilities Plan - Plot Plan, Mechanical Utilities West*. Albuquerque, NM.

USACE, see U.S. Army Corps of Engineers.

United States Army Corps of Engineers. 1970. "Laboratory Soils Testing." In *Engineering Manual 1110-2-1906*, Appendix II. Washington, DC.

U.S. Department of Energy. 1992. *Environmental Measurements Laboratory Procedures Manual*, HASL-300, 27th Edition, Volume 1. New York, NY.

U.S. Department of Energy, Nevada Operations Office. 1994a. *Project Management Plan*, Rev. 0. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1994b. "Sampling Equipment Decontamination," ERD-05-701, Rev. 0. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996a. *Corrective Action Unit Work Plan, Tonopah Test Range, Nevada*. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996b. *Industrial Sites Quality Assurance Project Plan, Nevada Test Site, Nevada*, Rev. 1, DOE/NV-372. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996c. *Environmental Restoration Project Health and Safety Plan*, Rev. 2. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996d. *NV/YMP Radiological Control Manual*, Rev. 2, DOE/NV 10630-59. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996e. *Nevada Test Site Waste Acceptance Criteria*, NTSWAC, Rev. 0. Las Vegas, NV.

U.S. Environmental Protection Agency. 1980. *Prescribed Procedures for Measurement of Radioactivity in Drinking Water*. Washington, DC.


U.S. Environmental Protection Agency. 1990. *Contract Laboratory Program Laboratory Statement of Work*, OLM.01.0-0.6/ILM.03.0. Washington, DC.

U.S. Environmental Protection Agency. 1994. *Guidance for the Data Quality Objectives Process*, EPA QA/G-4. Washington, DC.

U.S. Environmental Protection Agency. 1996. *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods*, SW-846, 3rd Edition, CDROM, PB89-148076. Washington, DC.

Appendix A

Data Quality Objectives Worksheet



DATA QUALITY OBJECTIVES WORKSHEET FOR THE BUILDING 360 UNDERGROUND DISCHARGE POINT - CAU NO. 423

Results of the Data Quality Objectives (DQOs) Scoping Meeting: The following notes are based on the DQO meeting held by the members of the Scoping Team (see below) on June 3, 1997. These notes follow the outline of the DQO guidance (EPA, 1994). The steps systematically build on the data acquired during background research for the CAU No. 423 Corrective Action Investigation Plan (CAIP). Copies of the background data are available in the project files of IT Corporation in Las Vegas. The operational details of the CAIP are summarized in Step VII of this worksheet.

Team Members:

Scoping Team

DOE/NV

Janet Appenzeller-Wing
Kevin Cabble
Lori Arent

IT Corporation

Kenneth Beach
Randy Dubiskas
Barbara Deshler
Syl Hersh
Jeanne Wightman
Cheryl Prince
Bonnie Blake

NDEP

Dean Mierau
Harry van Drielen

Bechtel

Dave Madsen
Steve Nacht

Core Decision Team

Janet Appenzeller-Wing
Kevin Cabble
Kenneth Beach
Dave Madsen

Primary Decision Makers

Janet Appenzeller-Wing
Kevin Cabble
Kenneth Beach
Dave Madsen

DATA QUALITY OBJECTIVES WORKSHEET

I. PROBLEM DESCRIPTION

A. State the Problem: Regulated wastes may have been released into the subsurface at CAU No. 423 (CAS 03-02-002-0308).

B. Summarize the contamination problem - combine the relevant background information into a concise description of the problem to be resolved.

1. Problem to be resolved

Determine whether the former contents of the Building 03-60 Underground Discharge Point (UDP) in Area 3 of the Tonopah Test Range (TTR) have migrated beyond the UDP physical boundaries. If so, determine whether these materials are regulated contaminants and if they have impacted underlying soil or groundwater above regulatory action levels or to the extent that a hazard is posed to potential receptors. If an impact has occurred, determine the lateral and vertical extent in order to close the site under Nevada Division of Environmental Protection (NDEP), *Resource Conservation and Recovery Act* (RCRA), and Department of Energy (DOE) requirements.

2. Describe the site history and known or suspected sources of contamination

Building 03-60, in the Area 3 compound at the Tonopah Test Range (TTR), was constructed in 1962 and is used as a light-duty fleet shop. Originally, waste oils were drained from Building 03-60 to Septic Tank 33-12 and the associated leachfield (CAU No. 427). After the septic tank was abandoned, the waste oil products (including waste anti-freeze, waste motor oil, and waste hydraulic oil) were discharged into a sump at the northwest corner of Building 03-60. A gravity-fed discharge line from the sump carried the waste oil to a point approximately 240 feet to the northwest where the line fed into what was originally thought to be an underground storage tank (UST). The specific time frame of fluid discharge to the sump is unknown, but may have been during the period from 1965 to 1989 or 1990.

In July 1993, a ground-penetrating radar geophysical survey was performed to confirm the UST location. In addition, the waste oil line was traced with an electromagnetic line tracer from the UST to Building 03-60.

During a March 1994, inspection of Building 03-60, the sump could not be located and was suspected to be sealed beneath a more recently emplaced concrete flooring slab. The upgradient end of the discharge line was also not found. Although Building 03-60 is still active, it is assumed that the discharge line and sump are inactive and that no contributions are being made to the UDP from any source.

DATA QUALITY OBJECTIVES WORKSHEET

On March 20, 1996, a soil excavation effort was held to locate the buried waste oil tank. As a result of this effort, it was determined that an underground storage tank was not present. Instead, an underground discharge point (UDP) consisting of a 42-inch diameter corrugated culvert, set vertically in the ground, was found at a depth of 2 feet below surface grade. The culvert opening was covered by a 44-inch diameter, 1/2-inch thick, fabricated steel lid. Approximately 12 inches below the rim was a 1 3/4-inch diameter galvanized pipe that is believed to be the downgradient end of the discharge line from Building 03-60. A black liquid with a strong hydrocarbon odor was visible 15 feet below the culvert rim. The liquid was determined to be approximately 5 feet deep. No rings, indicative of higher fluid levels, were noted. It is unknown whether releases from the UDP into the surrounding subsurface have occurred. The location of Building 03-60, the waste oil line, and the UDP are shown on the site map and aerial photograph in Attachment 1. Ground-level photographs of the UDP taken during the excavation activities are shown in Attachment 2.

Following collection and analysis of a waste oil sample in April 1996, the liquid in the UDP was removed (approximately 400 gallons). However, a small amount of residual sludge is believed to remain at the bottom of the UDP culvert.

The specific configuration of the UDP is unknown; however, a gravel layer, or some type of irregular base, is believed to exist at the bottom of the UDP. If gravel is present, it may be indicative of the presence of a gravel or leach rock column of unknown vertical extent below the bottom of the UDP. If the UDP base is concrete, it may indicate the UDP is part of a concrete holding tank below the UDP base (unlikely).

Uncertainties:

- Quantity of waste disposed
- Time frame of UDP operation
- UDP construction configuration (below culvert bottom)
- Sump location and the possibility of discharge line connection to other buildings

C. List known or potential routes of migration

Known routes of migration have not been established. Potential routes include the following conceptual models:

1. Primary Model

- a. Infiltration of contaminants in the form of liquid waste into the soil directly below the corrugated culvert UDP. Liquid waste would initially migrate laterally, then vertically downward. Lateral migration may also occur through hole/cracks in the

DATA QUALITY OBJECTIVES WORKSHEET

UDP culvert sides. Subsurface variations may also contribute to lateral migration.

It is assumed that the leachrock (if present) below the UDP bottom is homogeneous.

- b. Infiltration limited to less than 30 feet of vertical below the UDP culvert bottom and less than a 25-foot radius of lateral migration from the center of the UDP.
- c. Infiltration into the soils below and/or adjacent to the discharge line, either at the discharge line end(s) and/or via cracks or breaks along the length of the line.

2. Alternate Model

- a. Infiltration greater than 30 feet of vertical migration beneath UDP bottom and greater than 25 feet lateral migration.
- b. If migration is greater than approximately 360 feet in the downward direction, the COCs have potentially contaminated groundwater.

D. List known human and environmental receptors

1. On-site personnel - potential exists for inadvertent intrusion
2. Plants and animals - potential for exposure is assumed to be low
3. Groundwater - low potential for contaminant impact due to depth to groundwater
4. Other worker scenarios - to be addressed in Corrective Action Plan (CAP) and the Site-Specific Health and Safety Plan (SSHASP)

E. Define the exposure scenario

1. Define the exposure pathway(s)

- a. Oral ingestion, inhalation, or dermal contact (absorption) of constituents of concern in the soil after inadvertent excavation.
- b. Exposure potential related to groundwater contamination which is estimated to be at least 360 feet below the site.

2. Define the current and future land use

The Building 03-60 UDP area is currently used for fleet maintenance and is classified as light industrial. Future land use is also anticipated to be light industrial.

3. Define applicable or relevant and appropriate requirements (ARARs)

The following guidelines will be used to establish screening levels in order to establish stop points for the characterization activities: Nevada Division of Environmental Protection (NDEP) Corrective Action Levels for hazardous constituents, metals, TPH, and PCBs, and DOE NTS/YMP RadCon Manual (DOE/NV, 1996d, Rev. 2) Table 2.2 screening criteria for radiological constituents. Any potential remediation and/or closure activities to be conducted on the site will be

DATA QUALITY OBJECTIVES WORKSHEET

conducted using NDEP-mandated risk-based evaluation methods for hazardous and TPH constituents (e.g., Risk-based Corrective Action Guidance) in order to support one of the following options:

- a. Closure in place.
- b. Partial remediation and closure in place.
- c. Remediation.

Note: ARARs will be discussed in additional detail in the CAIP.

4. Develop the exposure scenario

The exposure scenario will be discussed in additional detail in the SSHASP and the CAIP. The main exposure scenarios include the following:

- a. On-site personnel (field workers) - Ingestion, inhalation or dermal contact with contaminated soil or airborne dust as a result of inadvertent intrusion into contaminated material during site activities.
- b. Plants and animals - Minimum or negligible impact to vegetation. Ingestion of or dermal contact with contaminated soil unlikely but possible as a result of animal burrowing or digging activities.
- c. Groundwater - Exposure to groundwater would only occur if subsurface investigation activities extended to approximately 360 feet below ground surface or if groundwater was impacted such that contaminants were detected in nearby supply wells.

F. Specify the available resources

1. Specify monetary budget for the field investigation

Monetary budget has been established as determined by the DOE/NV baseline.

2. Equipment resources

Equipment resources needed to accomplish the specified investigation tasks will include drilling and sampling equipment.

3. Manpower resources

The appropriate level of manpower resources will be utilized to accomplish the investigation tasks within specified time, budget, and health and safety constraints. Manpower resources will likely include, at a minimum, a 2 to 3 person field crew to oversee drilling activities, log soil characteristics, conduct field screening, collect soil samples for laboratory analysis, and document ongoing field activities.

DATA QUALITY OBJECTIVES WORKSHEET

II. IDENTIFY THE DECISION

A. Select the appropriate decision for the current phase of the site assessment process

1. Contaminant Identification - Determine, with a *Yes* or *No* answer, whether regulated contaminants are present.
2. Action level exceedence - If regulated contaminants are present, determine with a *Yes* or *No* answer, whether contamination exceeds NDEP Corrective Action Levels or DOE NTS/YMP RadCon Table 2.2 radiological screening levels (DOE/NV, 1996d).
3. Contaminant migration - If regulated contaminants exceed screening levels, determine with a *Yes* or *No* answer whether regulated contaminant concentrations exceed the spatial boundaries proposed in the conceptual model for the site.

The level of management responsible for each decision is the DOE Subproject Manager in communication with the NDEP point of contact.

B. Identify relationships among decisions

1. Prioritize decisions

1 > 2 > 3

2. Determine the logical sequence of actions

The following sequence of actions will be considered in greater detail in the CADD; however, because data obtained during the corrective action investigation will provide the basis for the CADD, the following actions must also be considered at this time.

a. Contaminant Identification -

- (1) If regulated contaminants have not been identified in the Building 03-60 UDP study area, then further assessment is not necessary. (*No* answer)
- (2) If regulated contaminants have been identified in the Building 03-60 UDP study area, then further assessment is necessary; go to Step b. (*Yes* answer)

b. Action Level Exceedence -

- (1) If the Building 03-60 UDP study area has not been impacted above applicable screening levels and will not be impacted further, then further assessment at this location is not necessary; go directly to CAP. (*No* answer)
- (2) If the Building 03-60 UDP study area has been impacted above applicable screening levels, further assessment may be warranted; if so, go to Step c. (*Yes* answer)

DATA QUALITY OBJECTIVES WORKSHEET

c. Contaminant Migration -

- (1) If regulated constituents exceed the proposed spatial boundaries, then the conceptual model needs modification, and further assessment is required to evaluate the new (alternate) model. If so, mitigate imminent hazards; rescope investigation; submit revised CAIP. (No answer)
- (2) If regulated constituents do not exceed the proposed spatial boundaries, then the conceptual model does not need to be modified, and further assessment at this location is not necessary. (Yes answer)

III. IDENTIFY THE INPUTS TO THE DECISION

A. List types of contaminants and affected media

On April 10, 1996, a homogenized waste oil sample was obtained for laboratory analysis of volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), RCRA Toxicity Characteristic (TC) metals, total pesticides, total polychlorinated biphenyls (PCBs), flashpoint, and radionuclides (IT, 1996c). Detected analytes included volatile organic compounds, aromatics, and chlorinated aromatics. A table listing the analytical results for the detected parameters is provided as Attachment 3. Results of a waste determination (Attachment 4) indicated the UDP waste liquid contained an "F002" listed waste in the form of orthodichlorobenzene (1,2-dichlorobenzene).

It is recommended that subsurface soil samples collected in the Building 03-60 UDP study area be analyzed for:

- a. Total VOCs
- b. Total SVOCs
- c. Total RCRA metals
- d. Total PCBs
- e. TPH
- f. Gamma-emitting radionuclides (i.e., gamma scan) (if field screening results indicate radionuclides above two times background)

If contaminants have migrated beyond the UDP confines, affected media include subsurface soil and may include groundwater. The extent to which these contaminants may have impacted surrounding and underlying soil and/or groundwater is currently not known but must be determined in order to close the site under NDEP, RCRA, and DOE requirements.

DATA QUALITY OBJECTIVES WORKSHEET

B. Identify the information inputs needed to resolve the decision, and how to generate the necessary data

Information is needed on contaminant identity, the potential for action level exceedence, and the extent of contaminant migration. Listed below are the methods to be used to generate the necessary data:

1. Contaminant Identification:
 - a. Collect subsurface soil samples via drilling.
 - b. Conduct field screening for selected parameters.
 - c. Obtain analytical chemical data results.
2. Action Level Exceedence:
 - a. Obtain analytical chemical data results.
 - b. Determine regulatory action levels.
 - b. Review results against regulatory action levels.
3. Contaminant Migration:
 - a. Evaluate the boundaries of contaminant migration from indicator parameters and/or analyses of soils for the parameters listed in Section III.A.
 - b. Determine the soil moisture content below and adjacent to the UDP from field screening results and/or laboratory analysis of geotechnical soil parameters.
 - c. Determine soil physical characteristics (hydrological and geotechnical) via *in situ* testing or soil sampling and laboratory analysis of geotechnical parameters.
 - d. Based on process knowledge, modeling, and analysis of soil parameters and infiltration potential, evaluate the capacity for sludge to generate liquid waste, and the capacity for migration to continue and increase in the future.
4. Waste Management: NTSWAC analyses (DOE/NV, 1996e)

C. Identify potential sources for each environmental input and list those inputs that are obtained through environmental measurements - identify existing sources of information that can support the decision

The following investigative strategies have been listed here as possible methods for gathering the data needed to address the objectives of the corrective action investigation. Additional information on the actual investigative approach selected for field implementation will be discussed in the CADD.

DATA QUALITY OBJECTIVES WORKSHEET

Existing sources of information will be listed in the references section of the CAIP. Potential sources, all of which require environmental measurements, for each environmental input include:

1. Vertical borings in and adjacent to the UDP - drill one boring directly through center of UDP; conduct a minimum of three step-out borings around the UDP to define lateral extent of contamination
2. Angled borings beneath the UDP - possible (but not preferred) alternative for obtaining subsurface data in UDP vicinity
3. Pressure testing or swabbing the waste oil line - determine if line may have other connections, if all liquid waste has been drained in the line, or if the line may have cracks or leaks along its length
4. Test pits along waste oil line - use a backhoe to excavate small pits to evaluate extent and magnitude of leakage (if present) along waste oil discharge line
5. Soil gas survey (active or passive) - measure flux of gasses by installing subsurface monitoring points around the UDP
6. Groundwater monitoring wells - install as needed if impact is likely
7. Hydrologic data - review existing hydrologic data from TTR water wells, and collect undisturbed soil samples for hydrologic/geotechnical analyses

D. Determine the basis for establishing contaminant-specific action level(s) - list the possible basis for establishing the action level (e.g., regulatory threshold, risk or exposure assessment, technological limits, reference based, standards, etc.)

The relationship of contaminant concentrations identified in the soils surrounding the Building 03-60 UDP to specified action levels will be considered during formulation of the CADD. However, designation and consideration of these action levels during the corrective action investigation phase is necessary: (1) because data collected during the corrective action investigation phase will be used to directly support formulation of the CADD, and (2) to ensure that data collected during the corrective action investigation phase are adequate to address the data needs of the CADD with regard to appropriate analytical parameters and detection limits.

Contaminant-specific action levels have been identified as follows:

1. Risk-based levels through the implementation of RCRA, CERCLA, and/or ASTM risk assessment techniques, as necessary and/or appropriate.
2. NDEP Corrective Action Levels for hazardous, metallic, and PCB constituents, and application of DOE NV/YMP RadCon Manual Table 2.2 standards for radionuclides (DOE/NV, 1996d).
3. RCRA toxicity characteristic concentrations (40 CFR 261.24) and RCRA TC and RCRA F-listed standards (CFR, 1996a).

DATA QUALITY OBJECTIVES WORKSHEET

4. Waste Management
 - a. Listed wastes
 - (1) Designation as a hazardous waste - presence above detection limits with a one-to-one correlation to specific process knowledge information indicating a >10% concentration of a specific contaminant.
 - (2) Disposal - concentrations above the LDR levels.
 - b. Characteristic wastes
 - (1) Concentrations above the TC levels for hazardous waste designation and for disposal.

E. Identify potential sampling approaches and appropriate analytical methods

The preferred sampling approach can be selected only after the conceptual model is formulated and the DQOs are chosen. Potential sampling approaches, from which the preferred approach may be selected, include the following:

1. Soil Borings:
 - Backfill UDP with appropriate clean backfill material (approximately 7 cubic yards would be needed).
 - Advance one soil boring directly through the center of the UDP.
 - Continue drilling until 2 consecutive (5-foot interval), non-detect field screening readings are obtained (if above 50 feet below ground surface).
 - If 2 consecutive, 5-foot-interval non-detect field screening readings are not obtained above a depth of 50 feet below ground surface, begin field screening at 10-foot intervals and continue drilling until 2 consecutive, non-detect field screening readings are obtained or until drilling capabilities have reached maximum vertical extent.
 - If contaminants are identified above field screening action levels, advance a minimum of 3 step-out borings in a roughly triangular pattern flanking the UDP at approximately 25 feet from the UDP center. Additional step-outs may be recommended to delineate the plume boundaries. Perform field screening of step-out boring samples according to the strategy described above. Advance the step-out borings to the lowest vertical extent of contamination (based on field screening readings) found in the UDP boring.
2. Field Screening: Conduct field screening on a continuous basis (starting at approximately 20 feet below ground surface) for TPH, VOCs, and radionuclides.
3. Sample Collection: Collect samples for laboratory analysis based on visual observations (e.g., areas of visible staining) and/or the results of field screening at 5-foot intervals from a depth of 20 to 50 feet below ground surface (and at 10-foot intervals below 50 feet) until 2 consecutive non-detect field screening samples are obtained. In step-out

DATA QUALITY OBJECTIVES WORKSHEET

borings (if performed), collect samples from highest field-screening reading interval and lowest vertical non-detect interval.

4. **Laboratory Analysis:** In the UDP center boring and in any step-out borings, submit samples for laboratory analysis obtained from the interval with the highest field screening readings and from the bottom non-detect interval. If field screening does not detect any contamination in the step-out borings, samples from these borings will not be shipped for laboratory analysis.

Proposed analytical parameters were selected based on process knowledge, the results of the 1996 waste oil characterization sampling, and analytical requirements specified by the NDEP (see Tables 3-1 and 4-1 of the CAIP). These analytical parameters include:

- Total VOCs - EPA 8260
- Total SVOCs - EPA 8270
- Total RCRA Metals - EPA 6010/7470
- PCBs - EPA 8080
- TPH - EPA 8015
- Nevada Test Site Waste Acceptance Criteria (NTSWAC)

An off-site, fixed-base laboratory may be used for analysis of the following soil properties:

- Initial moisture content
- Dry bulk density
- Calculated porosity
- Saturated/unsaturated hydraulic conductivity
- Particle size distribution
- Moisture retention characteristics
- Atterberg limits

5. **Waste Oil Discharge Line:** The connection of the line from the UDP to Building 03-60 must be verified, and the potential for leaks to have occurred from the line must also be evaluated. Confirm the location of the line using a utility line locator or air knife. Excavate at the building footprint to uncover the pipe. If possible, locate the sump inside the building utilizing a tracer or concrete cutter. Cut the pipe at the building corner, and confirm the pipe is empty via swabbing (such as using forced air injected from the building end of the pipe toward the UDP). Possibly conduct pressure testing of the line to evaluate leak potential. If the line passes pressure test, grout line; cap both ends. If the line fails the pressure test, consider options such as shallow test pits or advancement of additional soil borings to evaluate extent and magnitude of subsurface impact.

DATA QUALITY OBJECTIVES WORKSHEET

IV. DEFINE THE STUDY AREA BOUNDARIES

A. Define the geographic areas of the field investigation

1. Define the domain or geographic area within which all decisions must apply

The Building 03-60 UDP geographic study area (CAU No. 423; CAS 03-02-002-0308) includes the UDP and waste oil line and the lateral and vertical geographic region which may have been impacted by releases of liquid from the UDP. See Attachment 1 for two-dimensional delineation of the CAU No. 423 boundaries.

2. Specify the characteristics that define the population of interest; when applicable, divide the population into appropriate sampling media or strata

The population of interest is the type, quantity, and distribution of contaminants within the Building 03-60 study area. In order to determine the type, quantity, and distribution of contaminants, four sampling media have been identified:

a. Disturbed/Construction materials -

- (1) Construction materials to a depth of 20 feet below ground surface (i.e., the bottom of the UDP), including the UDP culvert (corrugated metal) and sludge.
- (2) Construction materials (homogeneous gravel or leach rock) to an unknown depth below the bottom of the UDP (i.e., the most likely interval for contamination).

b. Undisturbed materials/native soils -

- (1) Unsaturated native soil below the base of the UDP (less likely to be impacted due to viscosity of waste oil).
- (2) Native soils lateral to the UDP which may have been impacted by contaminant migration.

c. Waste oil discharge line (and possible connections) from Building 03-60 to the UDP, as well as the surrounding soil potentially impacted by a leak from the line.

d. Groundwater (to be sampled only if an impact is suspected).

3. Define the scale of decision making

The scale of decision making will be based on the strata into which the site have been divided and the length of time required by ARARs. In the UDP center boring, the vertical extent of migration will be evaluated at 5-foot intervals from 20 to 50 feet below ground surface and at 10-foot intervals thereafter or until two consecutive, non-detect measurements are obtained from field screening efforts. In the step-out borings (if performed), the vertical extent of migration will be evaluated to, at a minimum, the

DATA QUALITY OBJECTIVES WORKSHEET

lowest depth of contamination identified from field screening readings in the UDP center boring in accordance with the field screening and sampling strategy described previously.

B. Define the temporal boundaries of the decision

1. Determine the time frame to which the study data apply

Temporal boundaries for this project include the following constraints:

- a. the period of time for which the analytical data will be valid (based on the expected constituents of concern at this site, contaminant migration is anticipated to be imperceptible; therefore, the data should be valid for a significant period of time)
- b. laboratory analytical holding times
- c. legal deadlines such as:
 - (1) the time period following CAIP approval but enough prior to the CADD due date to ensure the deadline can be met
 - (2) finalization of the data report which will provide sufficient information to generate at CADD
- d. Investigation-derived waste holding time.

2. Determine when to collect data

Data collection will commence following NDEP approval of the CAIP. The time frame for data collection has been tentatively established as November 9 through 21, 1997. Following data collection, the data will be compiled for generation of the final CADD due to NDEP on May 3, 1998.

Characterization activities will be conducted only during favorable weather conditions (i.e., no rain, no significant wind); however, engineering controls may be used to improve conditions. Seasonal variations are not expected to affect data quality and activities can be conducted as scheduled.

3. Define relevant time constraints

- a. Mitigation of imminent hazards (if applicable)
- b. CADD due to NDEP May 3, 1998

C. Identify any practical constraints on data collection

1. Testing operations (TTR security constraints)
2. Meteorological
3. Health and safety
4. Heavy equipment availability

DATA QUALITY OBJECTIVES WORKSHEET

5. Surface and subsurface obstacles/impediments
6. Remoteness of site
7. Approval of CAIP

V. DEVELOP A DECISION RULE - DEFINE A LOGICAL BASIS FOR CHOOSING AMONG ALTERNATIVE ACTIONS

The decision to be made is whether the data (both historical and current) collected during the corrective action investigation process are of sufficient quality to meet the investigation objectives and to support a CADD.

A. Specify the parameter that characterizes the population of interest

The population of interest is discussed in Step IV.A.2 and consists of the type, quantity, and distribution of contaminants. The parameter used to characterize the population of interest is the analytical result from each sampling point within the UDP study area. Sampling results, when compiled for the entire study area, can then be used to evaluate the population of interest.

B. Specify the action level or preliminary action level for the decision

Action levels that trigger the *Yes* decisions described in Step II include:

- 1. On-site field screening methods**
 - a. Radiation levels above twice background
 - b. VOC screening (25 ppm or 2 1/2 times background [closed-bag headspace], whichever is greater; or 5 ppm for safety in breathing zone)
 - c. TPH above 100 ppm
- 2. Off-site analysis**
 - a. RCRA-listed contaminant concentrations above the NDEP Corrective Action Regulations for initial site screening and characterization and above risk-based levels
 - b. TPH concentrations above the TPH limits per the NAC 445A (NAC, 1996a) and NDEP Corrective Action Regulations (NDEP, 1996).
 - c. Presence of man-made radionuclides above background for initial gamma scan field screening, followed by application of DOE NTS/YMP RadCon Table 2.2 screening levels (i.e., 2 times background) for evaluation of laboratory analysis data, and finally risk-based analysis using RESRAD for remediation/closure evaluation.

DATA QUALITY OBJECTIVES WORKSHEET

C. Develop the decision rule - Combine the outputs of the previous DQO steps into "if ... then ..." decision rules that include the parameters of interest, the action levels, and the alternative actions

1. Contaminant Identification

- a. If the field screening and verification samples (validated laboratory analyses) do not detect contaminants, then recommend that the current study area is not contaminated (and will not be contaminated in the future) and that further assessment (at this location) is not required.
- b. If the field screening and verification samples (validated laboratory analyses) detect contaminants, then further assessment (at this location) may be warranted (i.e., determine if action levels have been exceeded). If so, go to action level exceedence assessment.

2. Action Level Exceedence

- a. If the verification samples (validated laboratory analyses) do not detect contaminants above action levels, then recommend that the current study area is not contaminated above applicable levels (and will not be contaminated further) and that further assessment (at this location) is not required.
- b. If the verification samples (validated laboratory analyses) detect contaminants above action levels, then recommend that the current study area is contaminated above applicable levels and further assessment (at this location) may be warranted. If so, go to contaminant migration assessment.

3. Contaminant Migration

- a. If the verification samples (validated laboratory analyses) do not detect contaminants above action levels beyond the boundaries, recommend that the regulated contaminant concentrations do not exceed the proposed spatial boundaries, the conceptual model does not need to be modified, and that further assessment (at this location) is not required.
- b. If the verification samples (validated laboratory analyses) detect contaminants above action levels beyond the boundaries, recommend that the regulated contaminant concentrations exceed the proposed spatial boundary and the model must then be modified, and further assessment is required to evaluate the new (alternate) model. If further assessment is necessary to address migration, modeling or monitoring may be required to provide assurance over the required time.

DATA QUALITY OBJECTIVES WORKSHEET

VI. SPECIFY ACCEPTABLE LIMITS ON DECISION ERRORS - SPECIFY DECISION ERROR LIMITS BASED ON THE CONSIDERATION OF THE CONSEQUENCES OF MAKING AN INCORRECT DECISION

A. Determine the upper and lower bounds for the parameter of interest using relevant historical site data

The parameters of interest are the concentrations of the contaminants of concern. The upper bound is the region above the action limit where there is a very high comfort level that sample analysis results would correctly identify the sample as contaminated. The lower bound is the detection limit as specified in the laboratory Statement of Work.

B. Define both types of decision errors and identify the potential consequences of each

If the contaminated area is determined to be larger than it actually is (false positive), then more resources could be committed to the corrective action then are necessary. If the contaminated area is determined to be smaller than it actually is (false negatives), less corrective action might be undertaken than is needed to ensure protection of human health or the environment.

VII. OPTIMIZE THE DESIGN - OUTLINE A SAMPLING DESIGN, SPECIFYING THE OPERATIONAL DETAILS OF THE SAMPLING PLAN WHICH FALLS WITHIN THE PROJECTS CONSTRAINTS

A. Review the DQO outputs and existing environmental data - compile outputs from previous steps of the DQO process

The technical approach to the completion of characterization activities will involve the following steps:

1. Locating the discharge line at the building footprint.
2. Testing the discharge line to ensure liquids are not present, to verify the connection to the UDP, to verify (if possible) that additional connections along the line are not present, and to verify that leaks are not present in the line.
3. Swabbing the discharge line, followed by plugging or capping of both ends.
4. Determining the construction of the UDP and the vertical extent of contamination directly beneath the UDP by advancing one boring through the UDP center or immediately adjacent to the UDP if advancement through the center is technically unfeasible.

DATA QUALITY OBJECTIVES WORKSHEET

5. If contamination is detected in the UDP center boring (based on field screening results), establishing the horizontal and vertical extent of contaminant migration by advancing at least three step-out borings flanking the UDP.
6. Field screening soil samples collected from the boreholes, and collecting soil samples for laboratory analysis of parameters listed in III.A.

Complete details of this investigation approach will be described in the CAIP.

B. Develop general sampling and analysis design alternatives. For each design alternative, verify that the DQOs are satisfied

The only reasonable alternative for this investigation is the option of advancing a boring directly adjacent to the UDP as opposed to down the center of the UDP. In either case, if contamination is encountered, step-out borings will be required and the DQOs satisfied in that the lateral and vertical extent of contamination will be defined. However, by advancing a boring directly into the UDP, the level of confidence in determining the UDP configuration and the specific vertical extent of contamination in the area believed to be most highly impacted is slightly higher than with the design alternative.

C. Select the most resource-effective design that satisfies all of the DQOs


The most resource-effective design that satisfies all of the DQOs is to advance one boring directly through the center of the UDP, advance step-out borings as needed to bound the lateral and vertical extent of contamination, and collect samples for laboratory analysis as outlined in Step III.E.

D. Document the operational details and theoretical assumptions of the selected design in the sampling and analysis plan

Detailed documentation of sampling and analysis operations will be contained in the Corrective Action Investigation Plan and associated field instructions and operating procedures.

Attachment 1


Building 03-60 Site Map and Aerial Photograph



NOTE:
ALL SEPTIC TANKS AND LEACH FIELDS
HAVE BEEN ABANDONED AS SHOWN
BY DASHED LINE - - -


NOTE: UTILITIES ARE SHOWN BASED ON EXISTING SURFACE FEATURES AND AS-BUILT DRAWINGS.

INTER LINE OF EXISTING ROAD



CAIP CAU No. 423
Attachment 1
Revision: 0
Date: 10/27/97
Page A-20 of A-38

MICAL WEST




KEY MAP
NOT TO SCALE

BAR CODE

P.D. OR E.O. PROJECT NO.	REV	DATE	DESCRIPTION	DM	CD	AP
U.S. DEPARTMENT OF ENERGY MANAGEMENT SUPPORT DIVISION						
KIRTLAND AIR FORCE BASE EAST ALBUQUERQUE, NEW MEXICO						
SANDIA NATIONAL LABORATORIES PLANT ENGINEERING ALBUQUERQUE, NEW MEXICO; LIVERMORE, CALIFORNIA; TORONTO, NEVADA						
PLOT PLAN - MECHANICAL UTILITIES WEST						
SANDIA MASTER UTILITIES PLAN						
ARCHITECTURAL TTR 9/30/89						
Raytheon Raytheon Services Nevada						
DRAWN BY	A SPATA					
CHECKED BY	R MERRIMAN					
APPROVED BY						
DATE	9/30/89					

G3 1 OF 2

DRAFT ALBUQUERQUE



Attachment 2

Building 03-60 UDP Photographs

BUILDING 0360 UST SITE



VIEW OF DISCHARGE PIPE FROM
BUILDING 0360.

BUILDING 0360 UST SITE



VIEW OF COVERED CORRUGATED PIPE
WITH 1/2" STEEL COVER.

BUILDING 0360 UST SITE




VIEW OF CORRUGATED PIPE WITH
THE 1/2" STEEL LID OPEN

BUILDING 0360 UST SITE




VIEW OF 1/2" STEEL LID COVERING
CORRUGATED PIPE SET IN GROUND
FOR WASTE OIL DISPOSAL.

BUILDING 0360 UST SITE




VIEW OF CORRUGATED PIPE EXCAVATED

BUILDING 0360 UST SITE




VIEW OF EXCLUSION ZONE

BUILDING 0360 UST SITE



VIEW LOOKING AT EXCAVATED CORRUGATED PIPE WITH THE LID OPEN,

BUILDING 0360 UST SITE



VIEW LOOKING DOWN INTO THE EXCAVATED CORRUGATED PIPE. NOTE REFLECTION ON SURFACE OF OIL.

Attachment 3

Building 03-60 UDP Waste Oil Sampling Results

Detected Analytes for Building 03-60 UDP Fluid Sample TTR00023

Analysis	Method	Compounds	MDL ^a ($\mu\text{g/mL}$) ^b	Concentration ($\mu\text{g/mL}$)
Total VOA ^c	SW-846-8260	Benzene	13	18
Total VOA	SW-846-8260	n-Butylbenzene	13	458
Total VOA	SW-846-8260	sec-Butylbenzene	13	51
Total VOA	SW-846-8260	2-Chlorotoluene	13	763
Total VOA	SW-846-8260	4-Chlorotoluene	13	45
Total VOA	SW-846-8260	1,2-Dichlorobenzene	13	70
Total VOA	SW-846-8260	1,3-Dichlorobenzene	13	26
Total VOA	SW-846-8260	1,4-Dichlorobenzene	13	29
Total VOA	SW-846-8260	Ethylbenzene	13	172
Total VOA	SW-846-8260	Isopropylbenzene	13	40
Total VOA	SW-846-8260	p-Isopropyltoluene	13	79
Total VOA	SW-846-8260	Naphthalene	13	361
Total VOA	SW-846-8260	Toluene	13	269
Total VOA	SW-846-8260	1,2,4-Trimethylbenzene	13	620
Total VOA	SW-846-8260	1,3,5-Trimethylbenzene	13	322
Total VOA	SW-846-8260	Total Xylenes	13	948
Total SVOA ^d	SW-846-8270/625	Naphthalene	200,000	339,000
Total SVOA	SW-846-8270/625	2-Methylnaphthalene	200,000	493,000
Total SVOA	SW-846-8270/625	2-&/or 3-Methylphenol	200,000	291,000
Analysis	Method	Compound	Results (mg/L) ^e	
TCLP ^f Metals	SW-846-1311/6010	Lead (TCLP)	1.17	
TCLP Metals	SW-846-1311/6010	Arsenic (TCLP)	<0.08	

TCLP Metals	SW-846-1311/6010	Barium (TCLP)	0.04	
TCLP Metals	SW-846-1311/6010	Cadmium (TCLP)	<0.02	
TCLP Metals	SW-846-1311/6010	Selenium (TCLP)	<0.20	
TCLP Metals	SW-846-1311/6010	Chromium (TCLP)	<0.03	
TCLP Metals	SW-846-1311/6010	Silver (TCLP)	<0.01	
TCLP Metals	SW-846-1311/7470	Mercury (TCLP)	<0.001	
Flashpoint	SW-846-1010		>230 °F	
Analysis	Method	Parameter	Result (pCi/L) ^g	MDA (pCi/L) ^h
Gamma Spec.	HASL 300, 4.5.2.3 ⁱ	Cesium-137	ND ^j	13.2
Gamma Spec.	HASL 300, 4.5.2.3	Potassium-40	248	137
Gamma Spec.	HASL 300, 4.5.2.3	Lead-212	17.4	14.4

^aMethod Detection Limit

^bMicrograms per milliliter

^cVolatile Organic Analysis

^dSemivolatile Organic Analysis

^eMilligrams per Liter

^fToxicity Characteristic Leaching Procedure

^gPicocuries per Liter

^hMinimum Detectable Activity

ⁱEnvironmental Methods Laboratory Procedure Manual, HASL-300 (U.S. DOE)

^jNot Detected

Attachment 4

CAU No. 423 Waste Determination



INTERNATIONAL
TECHNOLOGY
CORPORATION

CAIP CAU No. 423
Attachment 4
Revision: 0
Date: 10/27/97
Page A-29 of A-38

July 2, 1996

Project No.: 764038.02010100

Mr. Kevin Cabble
U.S. Department of Energy
Nevada Operation Office
P.O. Box 98518
Las Vegas, Nevada 89193-8518

Contract No. DE-AC08-92NV10972
Records For Hazardous Waste Identification Of
Building 0360 Waste Oil Underground Discharge Point

Dear Mr. Cabble:

Enclosed are the records used to make a hazardous waste determination for the liquid waste contained in the Building 0360 Underground Discharge Point (UDP) located in Area 3, at the Tonopah Test Range (TTR). Please transmit a copy of this Record to the Nevada Division of Environmental Protection (NDEP) for Karen Beckley's review and concurrence.

If you have any questions or comments, please call me at 4-1539.

Sincerely,

IT Corporation
Richard A. Dubiskas
Technical Lead

Cindy L. Dutro
Cindy L. Dutro
Regulatory Analyst

cc: P. A. Sanders DOE/EPD (with enclosure)
Enclosure

LV7-2-96/GAUDP.LET

Regional Office

4340 South Valley View, Suite 114 • Las Vegas, Nevada 89103-4047 • 702-794-1700

RECORDS FOR HAZARDOUS WASTE IDENTIFICATION OF BUILDING 0360 WASTE OIL UNDERGROUND DISCHARGE POINT

Introduction

Building 0360 is located at the Tonopah Test Range (TTR) in Area 3 an Under Ground Discharge (UDP) was discovered at this location. The UDP was previously incorrectly identified as an Underground Storage Tank (UST) in a geophysics survey. An Environmental Protection Agency (EPA) Form 7530-1, Notification for Underground Storage Tanks was submitted to the Nevada Division of Environmental Protection (NDEP) on January 25, 1996. Subsequent investigation activities showed that a UDP existed, not a UST. An amended EPA Form 7530-1, Notification for Underground Storage Tanks will be submitted to NDEP.

Overview of Historical Knowledge

Building 0360 is used as a Light Duty Fleet Shop that for an undetermined period discharged waste oil to the UDP. The UDP is adjacent to a barbed-wire fence near the south end of the boxcar storage yard at Area 3. This location is approximately 150 feet northwest of Building 0360. The location of the UDP is shown in the Site Map (Attachment 1). No records were found that showed the amount of waste oil that was discharged to the UDP. Currently, waste oil generated at the Light Duty Fleet Shop is containerized and delivered to the United States Air Force (USAF) for disposal.

The UDP is approximately 20 feet deep and 42 inches in diameter; the liquid contained in the UDP is estimated to be approximately 400 gallons. Samples were collected and sent to SouthEastern Analytical Services, Incorporated (SEAS), for analyses as reported in (Attachment 2). The UDP contains waste oil, volatile organic compounds, aromatics, and chlorinated aromatics.

Hazardous Waste Identification

A review of the laboratory analysis was conducted in accordance with 40 CFR 261.2 requirements to determine if the waste contained in the UDP met the definition of a solid waste. It was determined that the contents of the UDP met the definition of a solid waste. Next, 40 CFR 261.3(a)(2)(iv), 261.4, and 261.6(a)(3) were reviewed to determine if the waste was excluded from regulation as a solid waste or hazardous waste. It was determined that the waste was not excluded from regulation as a solid or hazardous waste. Then a review of 40 CFR 261.11, 261.30, 261.32, and 261.33 was conducted to determine if the waste was a "listed waste." It was determined that the waste liquid contained an "F002" listed waste in the form of ortho-dichlorobenzene.

The State of Nevada's position has typically been that if there is no demonstrated evidence that a waste is "listed" (such as documentation showing that spent solvents would be likely to be present due to historic operations), that the waste should be considered to be "characteristic" rather than "listed." It is not assumed that a waste is "listed" just because a given constituent is detected.

Therefore, it was necessary to review historical records for Building 0360 to determine if ortho-dichlorobenzene was an ingredient in any product in excess of 10% or more by volume of the original product (the amount necessary to make the waste an "F002" waste). Records reviewed included Chemical Inventories, and Preliminary Hazard Assessment for Building 0360 (Attachment 3). Material Safety Data Sheets (MSDSs) were obtained for products on the Chemical Inventories for Building 0360. Upon receipt, the MSDSs were reviewed to determine if any products contained ortho-dichlorobenzene as an ingredient. None of the MSDSs identified its use in the product formulation.

The next step was a review of the Uniform Hazardous Waste Manifests (Attachment 4) for Building 0360 to determine if an "F002" waste was shipped from Building 0360. This review identified that an "F002" waste was collected from Building 0360 by Safety-Kleen Corporation from 1988 through 1990 under a contract with Sandia National Laboratory.

Safety-Kleen Corporation's Las Vegas Office was contacted and a request was made for MSDSs for all products that Safety-Kleen Corporation supplied for use in Safety-Kleen Corporation's parts washers that were located in Building 0360. Safety-Kleen Corporation reviewed their records and provided MSDSs for "Immersion Cleaner and Cold Parts Cleaner" and "Safety-Kleen 105 Solvent" (Attachment 5) the MSDSs were reviewed and they did not identify ortho-dichlorobenzene as part of the products formulation.

After this review, Safety-Kleen Corporation's Product Development Center was contacted and asked whether Safety-Kleen products used in Building 0360 were reformulated or was an administrative error made on the manifest (i.e., the waste should not have been shipped as an "F002" waste). Safety-Kleen supplied the formulation history for "Immersion Cleaner and Cold Parts Cleaner" and the MSDS issued in 1989 (Attachment 6). These records show that the product contained more than 10% by volume of ortho-dichlorobenzene at the time of its use in Building 0360. Therefore, the waste contained in the UDP will be managed as an "F002" "listed" waste.

The liquid from the UDP will be pumped and transported to a permitted treatment, storage, or disposal (or recycling) facility. The NDEP will be notified prior to the waste being transported from TTR to a permitted facility.

Attachment 3

Date: October 24, 1990

To: Distribution

From: L.M. Christie 7513

Attached are printouts of the Chemical Inventory for your Organization and buildings.

All buildings must have Bldg. #/Rm. # such as 02-50/101. Floor plans are provided for reference. Outlying trailers such as 51-01/B71 and 39-01/B6 are good locations.

See back of Manual Entry Form for the following..

1. Maximum Quantity is numeric value representing the total amount present in a single location, see item #7.
2. Quantity Unit must be as stated in item #8.
3. Physical State must be as stated in item #10.
4. Storage Code must be 3 digit code, see chart.

Forms for additions and deletions are available upon request.

Please return your corrected copies to L. Christie, 7511 before November 20, 1990.

Distribution:

7511 R.R. Beasley
7512 I.C. Alexander
7513 G.L. West
7514 C.E. Smith
Recco B.C. McNeill
ASI P.T. Morey

JUN 19 '96 01:22PM ER&TDD/ERS A-23

CAIP CAU No. 423
 Attachment 4
 Revision: 0
 Date: 10/27/97
 Page A-33 of A-38

P. 3/3

ORG. BLDG./ROOM	PRODUCT	MAX. QUANT.	STOR	PHYS.	MANUFACTURER
		CODE	STATE		
REECO 03-60	BATTERY TERMINAL CLEANER & PROTECTOR SPRAY	13.0 (ozd)	S		MCKAY MFG. CO.
REECO 03-60	BERRYMAN BRAKE CLEANER	22.0 (ozd)	F24	L	BERRYMAN PRODUC
REECO 03-60	CAL-TINT TI	16.0 (ozd)		L	NU DEK INC.
REECO 03-60	CHEM-DIP CARBURETOR & PARTS CLEANER	5.0 (gal)		L	BERRYMAN PRODUC
REECO 03-60	CHEVRON PINION GREASE MS-SP	13.0 (ozd)		S	CHEVRON USA
REECO 03-60	ENGINE DEGREASER B-33	16.0 (ozd)		S	BERRYMAN
REECO 03-60	FIFTH WHEEL LUBE #19912	14.0 (ozd)		S	LAWSON PRODUCTS
REECO 03-60	FLOWAY MOTOR CLEANER	1.0 (gal)		L	KANO LABORATORI
REECO 03-60	GRINDING OIL #34253	1.0 (gal)		L	BLACK & DECKER
REECO 03-60	IGNITION WIRE DRYER #89224	14.7 (ozd)		S	LAWSON PRODUCTS
REECO 03-60	LAWSON ELECTRIC VARNISEAL RED INSULATING VARNISH #89227	12.7 (ozd)		S	LAWSON PRODUCTS
REECO 03-60	MCKAY INSTANT DE-ICER	0.0 ()			
REECO 03-60	RUBBER UNDERKOAT #89154	17.7 (ozd)		S	LAWSON PRODUCTS
REECO 03-60	RUST OLEUM 641 THINNER	1.0 (gal)	F14	L	RUST OLEUM CORP
REECO 03-60	RUSTO-PRO JELL #84852	7.0 (ozd)		L	LAWSON PRODUCTS
REECO 03-60	SILIKROIL	1.0 (gal)		L	KANO LABORATORI
REECO 03-60	STARTING FLUID #1070A	11.0 (ozd)		S	LOCTITE CORP
REECO 03-60	SUPER 77 KWIKUT CUTTING OIL #82288	0.0 ()			LAWSON PRODUCTS
REECO 03-60	THE STRIPPER GASKET REMOVER #83841	13.0 (ozd)		S	LAWSON PRODUCTS
REECO 03-60	THERMO AID	5.0 (gal)		L	NAPA
REECO 03-60	WINDO-WELD RESEALANT #51135-08633	1.0 (pt)		L	3M
REECO 03-60	1011 GROUP 2A FAULT FINDER CLEANER	12.0 (ozd)	F24	L	CROWN INDUSTRIA
REECO 03-60	1012 GROUP 2A FAULT FINDER PENETRANT	12.0 (ozd)	F24	L	CROWN INDUSTRIA
REECO 03-60	1013 GROUP 2A FAULT FINDER DEVELOPER	12.0 (ozd)	F24	L	CROWN INDUSTRIA
REECO 03-60	140 SOLVENT	1.0 (drw)			D&G Oil Co. G43
REECO 03-60	3M 77 SPRAY ADHESIVE	17.0 (ozd)	F24	L	3M
REECO 03-60	3M GENERAL PURPOSE ADHESIVE CLEANER #51135-08984	1.0 (qt)		L	3M
REECO 03-60	3M IVI-SPRAY 1602 RED SEALER	13.0 (ozd)		S	3M
REECO 03-60	3M RELEASE AGENT 51135-08971	18.2 (ozd)		S	3M
REECO 03-60	B-12 CHEMTOOL CARBURATOR CHOKE CLEANER	13.0 (ozd)		S	BERRYMAN PRODUC
REECO 03-60	BATTERY & TERMINAL CLEANER #19913	13.7 (ozd)		S	LAWSON PRODUCTS



CAIP CAU No. 423
Attachment 4
Revision: 0
Date: 10/27/97
Page A-34 of A-38

Department of Energy
Nevada Operations Office
P.O. Box 98518
Las Vegas, NV 89183-8518

01-22-1996

RECEIVED

AUG-25 1997

IT/LV

Paul. J. Liebendorfer, P.E. Chief
Bureau of Federal Facilities
Nevada Division of Environmental Protection
State of Nevada
333 W. Nye Lane
Carson City, NV 89710

**SUBMITTAL OF RECORDS FOR HAZARDOUS WASTE IDENTIFICATION OF
BUILDING 0360 WASTE OIL UNDERGROUND DISCHARGE POINT, TONOPAH TEST
RANGE**

IT Corporation has completed a record search for hazardous waste identification of the Area 3, Building 0360 Underground Discharge Point (UDP), Corrective Action Unit 406, Corrective Action Site 03-02-002-03-008 at the Tonopah Test Range. Enclosed for your review and concurrence are the records used to make a hazardous waste determination for the liquid waste in the UDP.

(1) → The next phase of this project will be to pump out the free liquids from the UDP. This activity is planned for the week of July 22-25, 1996.

If you have any questions regarding this activity, please contact Kevin J. Cabbie, of my staff, at (702) 295-5000.

David S. Shafer

David S. Shafer, Acting Director
Environmental Restoration Division

ERD:KJC

Enclosures:
As stated

cc w/o encls:

K. K. Beckley, NDEP,
Carson City, NV

Post-It® Fax Note	7871	Date	8/25	# of pages	4
To	Randy Dubois	From	Kevin Cabbie		
Co./Dept.	IT	Co.	DOE		
Phone #	5-1539	Phone #	5-5000		
Fax #	4-1794	Fax #	5-1113		

Paul. J. Liebendorfer

2.

CAIP CAU No. 423
Attachment 4
Revision: 0
Date: 10/27/97
Page A-35 of A-38

bcc w/o encl:




K. C. Beach, IT, Las Vegas, NV
R. A. Dubiskas, IT, Las Vegas, NV
D. S. Shafer, ERD, DOE/NV, Las Vegas, NV
K. J. Cabbie, ERD, DOE/NV, Las Vegas, NV
S. T. Curtis, ERD, DOE/NV, Las Vegas, NV
J. N. Romo, ERD, DOE/NV, Las Vegas, NV

Attachment 5

Uniform Hazardous Waste Manifests

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No. N V 3 8 9 0 0 9 0 0 0 1 9 6 0 2 5	Manifest Document No.	2. Page 1 of 1	Information in the shaded areas is not required by Federal law.	
3. Generator's Name and Mailing Address U.S. Department of Energy/Nevada Operations Office/ERD P.O. Box 98518, Las Vegas, NV 89109 Attn. David Shafer		A. State Manifest Document Number				
4. Generator's Phone (702) 295-0542		B. State Generator's ID				
5. Transporter 1 Company Name Laidlaw Environmental Services of CA		6. US EPA ID Number C A D 0 0 0 0 8 3 1 2 4	C. State Transporter's ID			
7. Transporter 2 Company Name		8. US EPA ID Number	D. Transporter's Phone (702) 331-9400			
9. Designated Facility Name and Site Address Laidlaw Environmental Services S.W. 1340 W. Lincoln Street Phoenix, AZ 85007		10. US EPA ID Number A Z D 0 4 9 3 1 8 0 0 9	E. State Transporter's ID			
11. US DOT Description (Including Proper Shipping Name, Hazard Class and ID Number)		12. Containers No.	13. Total Quantity	14. Unit Wt/Vol	1. Waste No.	
a. <input checked="" type="checkbox"/> Hazardous Waste, solid, n.o.s., 9, NA3077, PGIII (PPE and debris w/ orthodichlorobenzene, F002)	2	2 D M 146 0.0 1 F 0.300 P			F002	
b. <input checked="" type="checkbox"/> Hazardous Waste, liquid, n.o.s., 9, NA3077, PGIII (orthodichlorobenzene, water) NA3082	1	1 D M 146 0.0 1 D-F 0.025 G			F002	
c. Non-RCRA, Regulated Solid (Empty Drums)	2	2 D M 100 P			N/A	
d. Non-RCRA, Regulated Solid (Soil)	1	1 D M 0.100 P			N/A	
J. Additional Descriptions for Materials Listed Above			K. Handling Codes for Wastes Listed Above			
15. Special Handling Instructions and Additional Information ERG# 171 Emergency Contact: (702) 295-6400 Approvals 11a) NVDPE0001 11b) NVPPE0002 11c) NVDP0004 11d) NVDPE0003 Certificate of Disposal Requested						
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations. If I am a large quantity generator, I certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and that I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment; OR, if I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.						
Printed/Typed Name Matthew Wilson for DOE/NV/ERD		Signature / 1430 Month Day Year Matthew Wilson for DOE/NV/ERD 10/19/01 4/96				
17. Transporter 1 Acknowledgement of Receipt of Materials Printed/Typed Name <u>SCOTT SELLERS</u> Signature <u>SCOTT SELLERS</u> Month Day Year 10/19/01 4/96						
18. Transporter 2 Acknowledgement of Receipt of Materials Printed/Typed Name Signature Month Day Year						
19. Discrepancy Indication Space						
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in item 19. Printed/Typed Name <u>Scott Weber</u> Signature <u>Scott Weber</u> Month Day Year 10/11/01 4/96						

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No.	Manifest Document No.	2. Page 1 of 1		Information in the shaded areas is not required by Federal law.		
3. Generator's Name and Mailing Address		U.S. Department of Energy/Nevada Operations Office, ERD P.O. Box 98518, Las Vegas, NV 89109 Attn. David Shafer						
4. Generator's Phone (702) 295-0542								
5. Transporter 1 Company Name		6. US EPA ID Number						
Laidlaw Environmental Services of CA		C.A.D.0.0.0.0.8.3.1.2.4						
7. Transporter 2 Company Name		8. US EPA ID Number						
9. Designated Facility Name and Site Address		10. US EPA ID Number						
Laidlaw Environmental Services S.W. 1340 W. Lincoln Street Phoenix, AZ 85007		A.Z.0.0.4.9.3.1.8.0.0.9						
11. US DOT Description (Including Proper Shipping Name, Hazard Class and ID Number)		12. Containers No.	13. Total Quantity	14. Unit Wt/Vol	15. Waste No.			
a. X Hazardous Waste, Liquid, n.o.s., 9, NA3082, PGIII (Oil contaminated w/ orthodichlorobenzene, F002)		DOE	1004.006		F002			
b.								
c.								
d.								
J. Additional Descriptions for Materials Listed Above		I. Handling Codes for Waste Listed Above						
15. Special Handling Instructions and Additional Information ERG #: 171 Emergency Contact: (702) 295-6400 Approval 11a) NVDPE0002 Certificate of Destruction Requested 5692 25601								
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations.								
If I am a large quantity generator, I certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and that I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment; OR, If I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.								
Printed/Typed Name Matthew Wilson for DOE/NV/ERD		Signature  1455 Month Day Year 10/1/1996						
17. Transporter 1 Acknowledgement of Receipt of Materials Printed/Typed Name Phil Setters		Signature  Month Day Year 10/1/1996						
18. Transporter 2 Acknowledgement of Receipt of Materials Printed/Typed Name		Signature Month Day Year						
19. Discrepancy Indication Space								
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.								
Printed/Typed Name Leonard Hogan		Signature  Month Day Year 10/9/1996						

Appendix B

Nevada Department of Environmental Protection Document Review Sheet for Draft CAIP

NEVADA ENVIRONMENTAL RESTORATION PROJECT

DOCUMENT REVIEW SHEET

1. Document Title/Number	2. Document Date			
Corrective Action Investigation Plan for CAU No. 423: Area 3, Building 03-60, Underground Discharge Point, Tonopah Test Range, Nevada	July 1997			
3. Revision Number	4. Originator/Organization			
Draft	IT Corporation			
5. Responsible DOE/NV ERP Subproject Mgr.	6. Date Comments Due			
Janet Appenzeller-Wing	8/09/97			
7. Review Criteria	8. Reviewer/Organization/Phone No.			
	Bureau of Federal Facilities, NDEP Reviewer: Dean Mierau			
10. Comment Number/Location	11. Type ^a	12. Comment	13. Comment Response	14. Accept
1. Page 9 of 37, Paragraph 1	M	In the first paragraph, the second sentence states only "a small amount of residual sludge" was left in the UDP following pumping. In the third sentence it is stated there was 8.5 inches of liquid standing in the UDP over a year later. Where did the liquid come from? What will be done with the liquid (listed waste)? Is the facility in Building 03-60 still actively adding to the UDP? Was the UDP sealed during the time interval from pumping to the second measurement? Is the pipe from building 03-60 sealed?	Text has been added in Section 2.5 to reflect the following: Potential liquid input to the UDP is currently considered as a three variable system. The first variable is the addition of surface water (i.e., storm runoff) due to water standing on the poorly sealed lid of the UDP. The top of the UDP is now above grade, eliminating further surface water input. The second variable is the addition of liquid through the Building 03-60 discharge pipe. The discharge pipe is now capped, eliminating further liquid input from the discharge line. The third variable is possible infiltration of liquid from saturated soils surrounding the UDP. A Stevens Depth Recorder has been installed to monitor any fluctuations of liquid level within the UDP. Liquid in the UDP is scheduled to be removed and properly disposed of in October, 1997.	Yes
2. Page 26 of 37, Paragraph 3, Sentence 3	M	In the third paragraph, the third sentence indicates a fresh media grab sample will be used for laboratory samples. This statement is counter to the schematic in Figure 4-2. Is a fresh core to be drawn following screening? Is the fresh media simply a fresh aliquot of the same core media?	The text on Page 28, paragraph 3, sentence 3 has been changed so "grab samples" is replaced with aliquots.	Yes

NEVADA ENVIRONMENTAL RESTORATION PROJECT

DOCUMENT REVIEW SHEET

CAIP CAU No. 423

Appendix B

Revision: 0

Date: 10/27/97

Page B-3 of B-3

Document Title/Number Corrective Action Investigation Plan for CAU No. 423:

Area 3, Building 03-60, Underground Discharge Point, Tonopah Test Range, Nevada

Revision Number Draft

Reviewer/Organization Dean Miera, Bureau of Federal Facilities, NDEP

10. Comment Number/Location	11. Type ^a	12. Comment	13. Comment Response	14. Accept
3. Appendix A, Page A-31 of A-33	M	In the Appendix, the last paragraph is a statement regarding storage and disposal. The statement concerns the liquid pumped from the UDP (approximately 400 gallons). The statement is part of an enclosure: Records for Hazardous Waste Identification of Building Q360 Waste Oil Underground Discharge Point, which was included in a letter dated July 2, 1996 from Richard A. Dubiskas and Cindy L. Dutro to Kevin Cabbie. The letter indicates (on Page A-29 of A-33) that Karen Beckley of NDEP/ICC should receive a copy of this letter for review. Karen has not received a copy of this letter, nor the information involved. It has not come to the attention of NDEP until this report was received July 11, 1997. What has happened to the liquid from the UDP (400 gallons) in the interim? Where is the notification to NDEP? How was the listed waste disposed ² , and where ² , and when?	Attachment 4 has been modified and Attachment 5 has been added to support the following: Correspondence between D. S. Shafer and P. J. Liebendorfer regarding the completion of a record search for hazardous waste identification for the UDP has been added to Attachment 4.	Yes

^aComment Types: M = Mandatory, S = Suggested.
Return Document Review Sheets to DOE/NV Environmental Restoration Division, Attn: QAC, M/S 505.