

no
330

737

DOE/NASA CONTRACTOR REPORT

MASTER

DOE/NASA CR-150627

DEVELOPMENT OF PROTOTYPE AIR/LIQUID SOLAR COLLECTOR
SUBSYSTEM (Quarterly Report)

Prepared by


Owens-Illinois
Post Office Box 1035
Toledo, Ohio 43666

950 0500

Under Contract NAS8-32259 with

National Aeronautics and Space Administration
George C. Marshall Space Flight Center, Alabama 35812

For the U. S. Department of Energy



U.S. Department of Energy



Solar Energy

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

NOTICE

This report was prepared to document work sponsored by the United States Government. Neither the United States nor its agents the United States Department of Energy, the United States National Aeronautics and Space Administration, nor any federal employees, nor any of their contractors, subcontractors or their employees, make any warranty, express or implied, or assume any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represent that its use would not infringe privately owned rights.

1. REPORT NO. DOE/NASA CR-150627		2. GOVERNMENT ACCESSION NO.		3. RECIPIENT'S CATALOG NO.	
4. TITLE AND SUBTITLE Development of Prototype Air/Liquid Solar Collector Subsystem (Quarterly Report)				5. REPORT DATE January 1978 ✓	
				6. PERFORMING ORGANIZATION CODE	
7. AUTHOR(S)				8. PERFORMING ORGANIZATION REPORT #	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Owens-Illinois P. O. Box 1035 Toledo, Ohio 43666				10. WORK UNIT NO.	
				11. CONTRACT OR GRANT NO. NAS8-32259	
12. SPONSORING AGENCY NAME AND ADDRESS National Aeronautics and Space Administration Washington, D. C. 20546				13. TYPE OF REPORT & PERIOD COVERED Contractor Report Nov 1, 1977 - Jan 31, 1978	
				14. SPONSORING AGENCY CODE	
15. SUPPLEMENTARY NOTES This work was done under the technical management of Mr. John Caudle, George C. Marshall Space Flight Center, Alabama.					
16. ABSTRACT This quarterly report covers the progress made in the development of the SEC-601 collector subsystem by Owens-Illinois under NASA/MSFC Contract NAS8-32259. The reports describes the installation and layout design, and parts fabrication. The master development schedule for the design of the system is also included.					
17. KEY WORDS				18. DISTRIBUTION STATEMENT UC-59c Unclassified-Unlimited <i>William A. Brooksbank, Jr.</i> WILLIAM A. BROOKSBANK, JR. Mgr, Solar Heating and Cooling Projects Office	
19. SECURITY CLASSIF. (of this report) Unclassified		20. SECURITY CLASSIF. (of this page) Unclassified		21. NO. OF PAGES 8	22. PRICE NTIS

**THIS PAGE
WAS INTENTIONALLY
LEFT BLANK**

TABLE OF CONTENTS

	<u>Page</u>
Summary	1
Technical Performance	1
General Description of Work Accomplished during the Reporting Period	1
Forecast of Activities to Complete Tasks	4
Identification of Major Problems Areas or Difficulties	5

fcg

Contract: NAS8-32259
Fifth Quarterly Report
November 1, 1977 to January 31, 1978

Summary. The principal activities during the reporting period included the fabrication, receipt and physical inspection of the tool try out unit of the Model SEC-601 collector, the construction of test fixtures for the physical testing of the collector and the initiation of documentation for the IPC detail verification test procedure. One subsection (2.6) was completed and submitted to MSFC. In addition, the 144 tube ERDA collector testing was continued in conjunction with the air/liquid heat exchanger and liquid storage element. Also, the Quality Assurance Plan was completed and submitted.

Technical Performance.

A. General description of work accomplished during the reporting period.

1. Installation and layout design, parts fabrication.

The first or tool try out unit of the collector was received in early December, 1977, on schedule. The Module was assembled with no interface problems experienced; viz., the form and fit functions were satisfied. The manifold was then sectioned for detail physical inspection and the construction of test units such as those required for outdoor exposure tests and hail resistance tests. It was determined that the assembly process of the manifold was inadequate and that severe air leakage from the manifold was experienced. One of the principal problems was the sealant material (MS-1002) used for caulking and sealing all of joints in the manifold. An inadequate amount of material was used and the sealant is air cured. The cure cycle was not completed where air penetration was retarded and inadequate bonding was observed. A high temperature silicone sealant, catalytically activated, was selected and sample bonds were tested in a 450°F air stream for in excess of 60 hours. Good bonding was demonstrated and the material retained the desired flexibility (rubberlike characteristics) following such exposure.

The partially completed No. 2 and No. 3 manifolds were returned to the Development Center so that the sealant could be applied under controlled conditions. The process was completed in January and the manifolds are scheduled to be shipped to the foaming vendor by February 2. The second and third manifold assemblies are expected to be completed by February 6, 1978. The extreme weather conditions experienced contributed to the delay in the program. Testing of the units the week of February 6, 1978, will determine program schedules towards the completion of contract requirements.

2. Prototype Design Review.

The revised Model SEC-601 collector design was submitted to MSFC in November, 1977. The physical inspection of the tool try out unit will result in minor changes in design and material specifications to reflect the modifications incorporated in the fabrication of the No. 2 and No. 3 units.

3. Verification Tests.

The revised Verification Test Plan and the Detail Test Procedures were submitted to MSFC in November, 1977. Acceptance of the Plan and Procedures has been indicated informally with the condition that the sensible heat parameter be eliminated from the collector characteristic equation. This was acceptable to O. I. Section 2.6 of the IPC was completed by review and analysis. The documentation was formally submitted to MSFC as a test case for procedures to be used in the completion of certification of the remaining sections of the I.P. C.

The load test fixture was completed. This will be used for structural load tests and cyclical load tests. Air bags will be used for the application of the loads. Completion of the construction of the components for outdoor exposure, hail resistance, and vibration tests was interrupted pending the selection of a suitable sealant and acceptable assembly procedures. Verification testing is expected to be initiated in early February, 1978, approximately one month behind schedule. The severe weather conditions existing in Ohio will also likely delay the initiation of outdoor performance testing. All factors will be reviewed and a revised test schedule issued in February, 1978.

4. Air Collector Performance and Operational Testing.

The final report of the thermal performance and operational testing of the 144 tube ERDA air collector was issued in December, 1977. The closed cycle test loop incorporating the air liquid heat exchanger was operational in December and January. The data acquisition system continued to malfunction and was sent back to the supplier for repair. The data read out section was operational and two good days of performance data were analyzed by manual procedures. Certain preliminary judgements of significance can be drawn.

The effectiveness of the simple air/liquid heat exchanger is too low at a value of less than 30%. However, the pressure drop in the air side of the exchanger is very low. Baffling is being added to modify the air flow path towards attaining a significant increase in the heat exchanger effectiveness.

The data indicates a significant heat loss in the air side of the loop. The pressure at the inlet to the air fan is somewhat less than minus one inch of water. It is believed that this is causing an injection of cold ambient air of the order of 10% (5.6% calculated) into the air circulation loop. Air leakage is likely occurring in the manifold at the cups used to retain the sealing "O" rings in a small number of tubes. This causes a dumping of high temperature air to ambient. The minimal leakage expected in the Model SEC-601 collector manifold is expected to correct the problem. Time, cost, and severe weather conditions preclude corrective actions in the present system.

The analysis of data suggests that air mass flow was overstated by a few percent in reporting the performance of the 144 tube ERDA air collector. The air flow sensing element was located in the inlet duct to the array. The collector performance derived by the analysis of the closed loop test data is probably understated since the air flow sensing element was relocated to the collector air return duct. The weather conditions were clear and relatively warm on December 16, 1977. The collector elements were free from snow and frost. The backing screen was partially snow covered. The daily efficiency was .423 and the $\Delta T / \bar{T}_{TP}$ was .57. This operating point is above the contact specification but below the previously reported characteristic curve for the ERDA air collector. January 22, 1978, was clear and cold with a wind chill factor well below zero. The collector was almost 50% snow covered and all exposed glass surfaces covered with heavy frost. The backing surface was entirely snow covered. The daily efficiency was .31 and the $\Delta T / \bar{T}_{TP}$ was .7. This point falls right on the contract performance specification curve. It is apparent that the collector performance remains high even under severe snow and frost conditions.

A 350 gallon tank filled with 265 gallons of water is used for thermal storage. An analysis of heat loss overnight indicates a factor of 16 BTU/Hr.°F. This converts to a U_L of .19 BTU/Hr. Ft.²°F. A two inch fiber glass blanket was used to insulate the storage tank. Another two inch blanket will be added towards reducing the storage tank heat loss to a more acceptable value. The heat loss in the lines between the /tank/pump and heat exchanger appears to be negligible.

An Eppley PSP pyrometer was used to sense the total radiation value. A recent model of an Eppley 8-48 pyrometer was calibrated by Desert Sunshine Exposure Testing, Inc. A second Eppley 8-48 pyrometer had been

used as the radiation sensor during the previous testing and analysis of the 144 tube ERDA air collector. All three units were tested side by side during a relatively clear and cloudless day. It was found that both of the Model 8-48 sensors appear to yield readings approximately 10% lower in value compared to the PSP pyrometer. It is not clear why there is such a discrepancy between the PSP and the calibrated 8-48 unit. This will be subject to further investigation. The collector performance values, reported above, were based on the PSP sensed values and reflect the impact of the higher apparent radiation levels.

All sensors and the data acquisition signal conditioning elements were recalibrated in November. The temperature sensors in the air and liquid loops were evaluated under steady state temperature conditions and found to track one to the other within $\pm .5^\circ\text{F}$. The liquid flow meter was calibrated by mass flow measurements for five minute increments for flow rates of 10.5 to 15 pounds per minute (approximately 1.25 to 2.0 times the air $\dot{m}_{c,p}$ value at design air flow). Agreement to within $\pm .5\%$ between indicated and measured liquid flow values was demonstrated. Water temperatures of 55°F and 140°F were investigated in the calibration of the turbine flow meter.

The collector test loop operating characteristics are considered to be fully investigated and understood. Conversion to the Model SEC-601 collector can be accomplished as soon as the unit is available and weather permitting.

5. Installation, Operation and Maintenance Manual.
Revisions to the preliminary drafts of those manuals were held pending the availability of actual hardware.
6. Quality Assurance Plan.
The Quality Assurance Plan was transmitted to MSFC on January 18, 1978.

B. Forecast of Activities to Complete Tasks.

1. The completion of fabrication of the No. 2 and No. 3 test units of the Model SEC-601 collector is now anticipated by early February, 1978. Structural and thermal cycling tests will be initiated upon receipt of the hardware.
2. The installation of unit No. 3 for thermal performance testing will be expedited. However, unusually severe weather conditions, not predicted in the forecasting of current schedules, could introduce unanticipated delays.
3. All activities will be rescheduled during February

when the necessary hard facts of hardware availability and the results of early on shake down tests are known.

4. The air-liquid test loop operation will continue to be operated with the ERDA collector array until the conversion to the Model SEC-601 collector can be accomplished. Emphasis of testing will be on the evaluation of changes to the air side of the heat exchanger towards an improvement in its effectiveness. Also, the effect of changing the degree of insulation around the liquid storage tank will be investigated.

5. The rewriting of the drafts of the Installation, Operation, and Maintenance Manuals will be initiated.

C. Identification of Major Problems Areas or Difficulties.

1. The attainment of the leak tight manifold has proven to be a major problem. Test coupon evaluation of the sealants selected at flowing air tests up to 450°F continuous for in excess of 60 hours have been promising. The results of the completed manifolds during February will be critical relative to the status of the overall program.

2. Unforeseen severe weather during late December and January has impacted schedules because of plant shutdowns and travel between vendors. The time will be difficult to recover due to the already tight schedule forecast in November, 1977.

D. Data Submittals

<u>Reference</u>	<u>Description</u>
259-47	Proposed Verification and Test Prod. Change
259-49	Revised Baseline Drawings
259-50	October Status Report
259-51	Fourth Quarterly Status Report
259-52	1st, 2nd and 3rd Revised Quarterly Reports
259-53	Progress as of 9/30/77
259-54	November Status Report
259-55	Correlation Between Detailed Schedule & Budget
259-56	Interim New Technology Report
259-57	Qual. Test & Anal. Report-IPC 2.6
259-59	Quality Assurance Plan

DETAILED SCHEDULE

