RE VED
JUL 03 2000
OSTI

DOE/EIS-0305-F

468674

FINAL ENVIRONMENTAL IMPACT STATEMENT FOR TREATING TRANSURANIC (TRU)/ALPHA LOW-LEVEL WASTE AT THE OAK RIDGE NATIONAL LABORATORY OAK RIDGE, TENNESSEE



VOLUME 1

June 2000

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

COVER SHEET

RESPONSIBLE AGENCY: U.S. Department of Energy (DOE)

TITLE: Final Environmental Impact Statement for Treating Transuranic (TRU)/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee (DOE/EIS-0305)

CONTACT: For further information concerning the Final EIS, contact

Dr. Clayton Gist, Waste Management Integration Team Leader
U.S. Department of Energy
Oak Ridge Operations
55 Jefferson Avenue
P.O. Box 2001
Oak Ridge, TN 37831
Telephone: (865) 241-3498 • Facsimile (865) 576-5333 • E-Mail: gistcs@oro.doe.gov

For general information on DOE's National Environmental Policy Act (NEPA) process, contact:

Ms. Carol M. Borgstrom, Director
Office of NEPA Policy and Assistance (EH-42)
U.S. Department of Energy
1000 Independence Avenue, SW
Washington, DC 20585
Telephone: (202) 586-4600, or leave a message at (800) 472-2756

ABSTRACT: The DOE proposes to construct, operate, and decontaminate/decommission a TRU Waste Treatment Facility in Oak Ridge, Tennessee. The four waste types that would be treated at the proposed facility would be remote-handled TRU mixed waste sludge, liquid low-level waste associated with the sludge, contact-handled TRU/alpha low-level waste solids, and remote-handled TRU/alpha low-level waste solids. The mixed waste sludge and some of the solid waste contain metals regulated under the Resource Conservation and Recovery Act and may be classified as mixed waste.

This document analyzes the potential environmental impacts associated with five alternatives—No Action, the Low-Temperature Drying Alternative (Preferred Alternative), the Vitrification Alternative, the Cementation Alternative, and the Treatment and Waste Storage at Oak Ridge National Laboratory (ORNL) Alternative.

PUBLIC COMMENTS: The Draft Environmental Impact Statement (EIS) was issued to the public for review and comment on March 3, 2000. The public comment period ended on April 17, 2000. All comments were considered in preparation of the Final EIS. Changes in the Draft EIS are indicated by vertical bars in the margins of the Final EIS. The DOE will use the analysis in this Final EIS and prepare a Record of Decision on the treatment of TRU and alpha low-level wastes at ORNL. This decision will be made no sooner than 30 days after the U.S. Environmental Protection Agency Notice of Availability of the Final EIS appears in the *Federal Register*.

THIS PAGE INTENTIONALLY LEFT BLANK

CONTENTS

SUMMARY S-1
S1.1 INTRODUCTION S-1
S1.2 BACKGROUND S-2
S1.2.1 Waste Types S-2
S1.2.2 Waste Storage at ORNL S-3
S1.2.3 Public Participation S-3
S1.3 PURPOSE AND NEED FOR AGENCY ACTION S-5
S1.4 PROPOSED ACTION AND ALTERNATIVES S-6
S1.4.1 Proposed Action S-6
S1.4.2 Alternatives S-10
S1.4.3 Vitrification Alternative S-14
S1.4.4 Cementation Alternative S-16
S1.4.5 Treatment and Waste Storage at ORNL Alternative S-18
S1.5 ALTERNATIVES CONSIDERED BUT NOT EVALUATED IN DETAIL S-20
S1.5.1 Off-site Waste Treatment S-20
S1.5.2 Alternate On-site Treatment Facility Locations S-20
S1.5.3 Alternative Disposal Locations S-21
S1.5.4 Alternative Treatment Technologies S-21
S1.6 AFFECTED ENVIRONMENT S-21
S1.6.1 Land Use S-21
S1.6.2 Cultural Resources S-21
S1.6.3 Ecological Resources S-21
S1.6.4 Geology and Seismicity S-22
S1.6.5 Water and Water Quality S-22
S1.6.6 Waste Management S-23
S1.6.7 Climate and Air Quality S-23
S1.6.8 Transportation S-23
S1.6.9 Utility Requirements S-23
S1.6.10 Human Health S-23
S1.6.11 Accidents S-24
S1.6.12 Noise S-24
S1.6.13 Socioeconomics S-24
S1.6.14 Minority and Low-income Populations S-24
S1.7 ENVIRONMENTAL CONSEQUENCES S-25
S1.8 CUMULATIVE IMPACTS S-38
S1.9 MITIGATION S-39
S1.10 UNAVOIDABLE ADVERSE IMPACTS AND IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES S-39
S1.11 APPLICABLE LAWS AND REGULATIONS S-39
S1.12 REFERENCES S-41

1. INTRODUCTION AND BACKGROUND 1-1
1.1 INTRODUCTION 1-1
1.2 BACKGROUND 1-2
1.2.1 Waste Types 1-2

1.2.2 Waste Storage at ORNL 1-3
1.3 PURPOSE AND NEED FOR DOE ACTION 1-5
1.4 SCOPE OF ENVIRONMENTAL IMPACT STATEMENT 1-7
1.5 PUBLIC PARTICIPATION 1-8
1.6 RELATIONSHIP TO OTHER NEPA DOCUMENTS 1-10
1.7 REFERENCES 1-10

2. DESCRIPTION OF THE PROPOSED ACTION AND ALTERNATIVES 2-1
2.1 PROPOSED ACTION 2-1
2.2 CONSIDERATION OF ALTERNATIVES 2-4
2.3 NO ACTION ALTERNATIVE 2-5
2.3.1 Facility Description 2-5
2.3.2 Treatment Description 2-6
2.3.3 Schedule of Activities 2-7
2.4 LOW-TEMPERATURE DRYING ALTERNATIVE (PREFERRED ALTERNATIVE) 2-7
2.4.1 Facility Description 2-7
2.4.2 Waste Treatment Description 2-8
2.4.3 Schedule of Activities 2-13
2.5 VITRIFICATION ALTERNATIVE 2-15
2.5.1 Facility Description 2-15
2.5.2 Waste Treatment Description 2-15
2.5.3 Schedule of Activities 2-21
2.6 CEMENTATION ALTERNATIVE 2-23
2.6.1 Facility Description 2-23
2.6.2 Waste Treatment Description 2-23
2.6.3 Schedule of Activities 2-26
2.7 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE 2-28
2.7.1 Facility Description 2-28
2.7.2 Waste Treatment Description 2-29
2.7.3 Schedule of Activities 2-29
2.8 ALTERNATIVES CONSIDERED BUT NOT EVALUATED IN DETAIL 2-31
2.8.1 Off-site Waste Treatment 2-31
2.8.2 Alternate On-site Treatment Facility Locations 2-31
2.8.3 Alternative Disposal Locations 2-32
2.8.4 Alternative Treatment Technologies 2-32
2.9 SUMMARY OF ENVIRONMENTAL IMPACTS 2-34
2.10 REFERENCES 2-47

3. AFFECTED ENVIRONMENT 3-1
3.1 LAND USE 3-1
3.1.1 Past Land Use 3-1
3.1.2 Current Land Use 3-1
3.1.3 Planned Land Use 3-2
3.1.4 Parks, Preserves, and Recreational Resources 3-2
3.1.5 Scenic Resources 3-3
3.2 CULTURAL AND HISTORIC RESOURCES 3-3
3.3 ECOLOGICAL RESOURCES 3-4
3.3.1 Terrestrial Resources 3-4
3.3.2 Terrestrial Threatened and Endangered Species 3-6
3.3.3 Aquatic Resources 3-7
3.3.4 Aquatic Threatened and Endangered Species 3-9

3.4 GEOLOGY AND SEISMICITY 3-9
3.4.1 Stratigraphy 3-12
3.4.2 Structure 3-13
3.4.3 Soils 3-15
3.4.4 Site Stability 3-18
3.5 WATER AND WATER QUALITY 3-23
3.5.1 Surface Water 3-23
3.5.2 Groundwater 3-31
3.5.3 Wetlands and Floodplains 3-39
3.6 WASTE MANAGEMENT 3-41
3.7 CLIMATE AND AIR QUALITY 3-42
3.7.1 Climate 3-42
3.7.2 Air Quality 3-43
3.8 TRANSPORTATION 3-46
3.8.1 Local Transportation 3-46
3.8.2 National Transportation 3-47
3.9 UTILITY REQUIREMENTS 3-50
3.10 HUMAN HEALTH 3-51
3.10.1 Exposure Pathways 3-51
3.10.2 Pathway Modeling 3-52
3.10.3 Radionuclides 3-52
3.10.4 Chemicals 3-57
3.11 ACCIDENTS 3-59
3.12 NOISE 3-60
3.13 SOCIOECONOMIC AND DEMOGRAPHIC ENVIRONMENT 3-60
3.13.1 Demographic Characteristics 3-60
3.13.2 Housing 3-65
3.13.3 Infrastructure 3-65
3.13.4 Local Economy 3-66
3.14 ENVIRONMENTAL JUSTICE 3-69
3.15 REFERENCES 3-72

4. ENVIRONMENTAL CONSEQUENCES 4-1
4.1 LAND USE IMPACTS 4-2
4.1.1 Methodology 4-2
4.1.2 No Action Alternative 4-2
4.1.3 Low-Temperature Drying Alternative 4-2
4.1.4 Vitrification Alternative 4-3
4.1.5 Cementation Alternative 4-3
4.1.6 Treatment and Waste Storage at ORNL Alternative 4-3
4.1.7 Land Use Impacts Summary 4-4
4.2 CULTURAL AND HISTORIC RESOURCES 4-4
4.2.1 Methodology 4-4
4.2.2 No Action Alternative 4-4
4.2.3 Low-Temperature Drying Alternative 4-5
4.2.4 Vitrification Alternative 4-5
4.2.5 Cementation Alternative 4-5
4.2.6 Treatment and Waste Storage at ORNL Alternative 4-5
4.2.7 Cultural and Historic Resource Impacts Summary 4-5
4.3 ECOLOGICAL RESOURCES 4-6
4.3.1 Methodology 4-7

4.3.2 No Action Alternative 4-7
4.3.3 Low-Temperature Drying Alternative 4-8
4.3.4 Vitrification Alternative 4-9
4.3.5 Cementation Alternative 4-10
4.3.6 Treatment and Waste Storage at ORNL Alternative 4-10
4.3.7 Ecological Impacts Summary 4-10
4.4 GEOLOGY AND SEISMICITY IMPACTS 4-11
4.4.1 Methodology 4-11
4.4.2 No Action Alternative 4-11
4.4.3 Low-Temperature Drying Alternative 4-12
4.4.4 Vitrification Alternative 4-13
4.4.5 Cementation Alternative 4-13
4.4.6 Treatment and Waste Storage at ORNL Alternative 4-14
4.4.7 Geology and Seismicity Impacts Summary 4-14
4.5 WATER AND WATER QUALITY IMPACTS 4-14
4.5.1 Surface Water Impacts 4-14
4.5.2 Groundwater Impacts 4-20
4.5.3 Wetlands and Floodplains Impacts 4-22
4.6 WASTE MANAGEMENT AT ORNL 4-27
4.6.1 Methodology 4-31
4.6.2 No Action Alternative 4-31
4.6.3 Low-Temperature Drying Alternative 4-32
4.6.4 Vitrification Alternative 4-33
4.6.5 Cementation Alternative 4-34
4.6.6 Treatment and Waste Storage at ORNL Alternative 4-35
4.6.7 Waste Management Impacts Summary 4-36
4.7 AIR QUALITY 4-38
4.7.1 Methodology 4-38
4.7.2 No Action Alternative 4-38
4.7.3 Low-Temperature Drying Alternative 4-38
4.7.4 Vitrification Alternative 4-40
4.7.5 Cementation Alternative 4-40
4.7.6 Treatment and Waste Storage at ORNL Alternative 4-41
4.7.7 Air Quality Impacts Summary 4-41
4.8 TRANSPORTATION IMPACTS 4-41
4.8.1 Methodology 4-41
4.8.2 No Action Alternative 4-46
4.8.3 Low-Temperature Drying Alternative 4-46
4.8.4 Vitrification Alternative 4-51
4.8.5 Cementation Alternative 4-54
4.8.6 Treatment and Waste Storage at ORNL Alternative 4-55
4.8.7 Transportation Impacts Summary 4-57
4.9 UTILITY REQUIREMENT IMPACTS 4-59
4.9.1 Methodology 4-59
4.9.2 No Action Alternative 4-59
4.9.3 Low-Temperature Drying Alternative 4-60
4.9.4 Vitrification Alternative 4-62
4.9.5 Cementation Alternative 4-63
4.9.6 Treatment and Waste Storage at ORNL Alternative 4-63
4.9.7 Utility Impacts Summary 4-63
4.10 HUMAN HEALTH IMPACTS 4-63

4.10.1 Methodology 4-64
4.10.2 Exposure pathways 4-65
4.10.3 No Action Alternative 4-66
4.10.4 Low-Temperature Drying Alternative 4-66
4.10.5 Vitrification Alternative 4-68
4.10.6 Cementation Alternative 4-69
4.10.7 Treatment and Waste Storage at ORNL Alternative 4-69
4.10.8 Human Health Impacts Summary 4-70
4.11 ACCIDENT IMPACTS 4-71
4.11.1 Methodology 4-71
4.11.2 Accidental Breach of the Melton Valley Storage Tanks 4-73
4.11.3 Breach of the Transfer Line Between the Melton Valley Storage Tanks and the Proposed TRU Waste Treatment Facility 4-76
4.11.4 A Slurry Line Failure Within the TRU Waste Treatment Facility 4-78
4.11.5 Failure of the Slurry Line and the HEPA Filters in the Proposed TRU Waste Treatment Facility 4-79
4.11.6 Failure of Contact-Handled or Remote-Handled Solid Waste Containers Before, During, and After Waste Treatment 4-80
4.11.7 Accidents Unique to An Alternative 4-84
4.11.8 Industrial Accidents 4-87
4.11.9 Summary of Accident Analysis Results 4-88
4.12 NOISE IMPACTS 4-93
4.12.1 Methodology 4-93
4.12.2 No Action Alternative 4-93
4.12.3 Low-Temperature Drying Alternative 4-93
4.12.4 Vitrification Alternative 4-93
4.12.5 Cementation Alternative 4-93
4.12.6 Treatment and Waste Storage at ORNL Alternative 4-93
4.12.7 Noise Impacts Summary 4-93
4.13 SOCIOECONOMIC IMPACTS 4-94
4.13.1 Methodology 4-94
4.13.2 No Action Alternative 4-94
4.13.3 Low-Temperature Drying Alternative 4-95
4.13.4 Vitrification Alternative 4-98
4.13.5 Cementation Alternative 4-98
4.13.6 Treatment and Waste Storage at ORNL Alternative 4-103
4.13.7 Summary of Socioeconomic Impacts 4-105
4.14 ENVIRONMENTAL JUSTICE 4-105
4.14.1 Methodology 4-105
4.14.2 No Action Alternative 4-105
4.14.3 Low-Temperature Drying Alternative 4-108
4.14.4 Vitrification Alternative 4-108
4.14.5 Cementation Alternative 4-108
4.14.6 Treatment and Waste Storage at ORNL Alternative 4-108
4.14.7 Summary of Environmental Justice Impacts 4-108
4.15 REFERENCES 4-109

5. CUMULATIVE IMPACTS 5-1
5.1 LAND USE 5-4
5.2 ECOLOGICAL RESOURCES 5-5
5.3 WATER RESOURCES 5-5

5.3.1 White Oak Creek Embayment Project 5-7
5.3.2 Old Melton Valley Road Upgrade 5-7
5.3.3 Waste Area Group 5 Seep C and D 5-7
5.3.4 Waste Area Group 4 Seeps 5-8
5.3.5 Other CERCLA Actions 5-8
5.3.6 Waste Area Group 6 SWSA 6 Monitoring 5-8
5.3.7 Summary of Water Resource Impacts 5-9
5.4 WASTE MANAGEMENT 5-9
5.5 AIR QUALITY 5-9
5.6 TRANSPORTATION 5-10
5.7 HUMAN HEALTH 5-11
5.8 SOCIOECONOMICS 5-11
5.9 REFERENCES 5-12

6. MITIGATION MEASURES 6-1
6.1 REFERENCES 6-2

7. UNAVOIDABLE ADVERSE IMPACTS AND IRREVERSIBLE IRRETRIEVABLE COMMITMENT OF RESOURCES 7-1
7.1 UNAVOIDABLE ADVERSE IMPACTS 7-1
7.2 IRREVERSIBLE AND IRRETRIEVABLE COMMITMENT OF RESOURCES 7-1

8. APPLICABLE LAWS AND REGULATIONS 8-1
8.1 FEDERAL AND STATE ENVIRONMENTAL STATUTES AND REGULATIONS 8-1
8.2 OTHER PERTINENT REQUIREMENTS 8-3
8.3 REGULATORY COMPARISONS BETWEEN ALTERNATIVES 8-4

9. LIST OF PREPARERS 9-1

10. DISTRIBUTION 10-1

11. ORGANIZATIONAL CONFLICTS OF INTEREST STATEMENT 11-1

INDEX I-1

APPENDIXES
A NOTICE OF INTENT, ENVIRONMENTAL SYNOPSIS, AND PUBLIC ISSUES A-1
B EMISSIONS AND MATEIRALS BALANCE DATA FOR THE PROPOSED ACTION AND THE VITRIFICATION AND CEMENTATION ALTERNATIVES B-1
C FINDINGS OF SURVEYS FOR WETLANDS, TERRESTRIAL ANIMALS, RARE PLANTS, BASELINE NOISE, AND RADIOLOGICAL CONTAMINATION C-1
D RIMS II INPUT-OUTPUT METHODOLOGY D-1
E AGENCIES CONTACTED E-1
F CALCULATIONS PACKAGES F-1
G CATEGORICAL EXCLUSION FOR CONSTRUCTION/RELOCATION OF ACCESS ROAD AT OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE G-1

FIGURES

S-1 Location of Oak Ridge National Laboratory in relation to the City of Oak Ridge and other DOE facilities on the Oak Ridge Reservation, and in the State of Tennessee. S-1
S-2 Aerial view of the Melton Valley Storage Tanks–Capacity Increase Project during installation of the six 100,000-gallon tanks, which are located south of the eight 50,000-gallon Melton Valley Storage Tanks. S-3
S-3 General site location of the proposed TRU Waste Treatment Project facility on the Oak Ridge Reservation. S-7
S-4 DOE would lease the Melton Valley Storage Tanks facility and an adjacent area of land to construct the waste treatment facility S-9
S-5 Tank waste treatment flow diagram for the Low-Temperature Drying Alternative. S-12
S-6 Solid waste treatment flow diagram for the Low-Temperature Drying Alternative. S-13
S-7 Treatment flow diagram for sludge, supernate, and solid waste smaller than RCRA definition of debris for the Vitrification Alternative S-14
S-8 Vitrification Alternative flow diagram for solid waste treatment. S-15
S-9 Flow diagram for tank waste treatment for the Cementation Alternative. S-17
1-1 Location of Oak Ridge National Laboratory in relation to the City of Oak Ridge, other DOE facilities in the area, and the State of Tennessee. 1-1
1-2 Aerial view of the Melton Valley Storage Tanks–Capacity Increase Project during installation of the six 100,000-gallon (gal) tanks located south of the Melton Valley Storage Tanks. 1-4
1-3 Stakeholder meetings have been held as part of the TRU Waste Treatment Project. 1-8
2-1 General site location of the proposed TRU Waste Treatment Facility at Oak Ridge National Laboratory (ORNL) on the Oak Ridge Reservation (ORR) 2-1
2-2 DOE would lease the Melton Valley Storage Tanks facility and an adjacent area of land to construct the waste treatment facility. The location is isolated from ORNL by Haw Ridge. 2-2
2-3 Proposed site layout for the Low-Temperature Drying Alternative facility, including the locations of the existing Melton Valley Storage Tanks, the process building with truck access and turnaround areas to the first and third floors, and storm water drainage modifications. Site excavation would be minimized by optimizing the topography of the site with the layout of the Low-Temperature Drying Alternative facility. 2-9
2-4 Tank waste treatment flow diagram for the Low-Temperature Drying Alternative. 2-11
2-5 Solid waste treatment flow diagram for the Low-Temperature Drying Alternative. 2-12
2-6 The Low-Temperature Drying Alternative would take place over a period of approximately 11.5 years. 2-14
2-7 Waste treatment would be completed in approximately 5 years utilizing the Low-Temperature Drying Alternative 2-14
2-8 Treatment flow diagram for sludge, supernate, and solid waste smaller than the RCRA definition of debris for the Vitrification Alternative. 2-16
2-9 Vitrification Alternative flow diagram for solid waste treatment. 2-20
2-11 Vitrification Alternative waste treatment schedule. 2-22
2-12 Flow diagram for tank waste treatment for the Cementation Alternative. 2-25
2-14 The Cementation Alternative waste treatment schedule would take approximately 6 years. 2-27
3-1 Archeological sites near the proposed TRU Waste Treatment Facility site at ORNL include the Jones Site and the Jenkins Site. 3-5
3-2 Locations of sightings of protected bird species on the ORR – 1995 survey. 3-10
3-4 Stratigraphic column for the Oak Ridge Reservation 3-13
3-5 Geologic map for Melton Valley 3-14
3-6 Geologic cross-section of the Oak Ridge Reservation 3-16

3-7 Southeast region basement structures and major earthquakes. Depending on the method of measurements when the earthquake occurred, this graphic indicates the measurements as either intensity (Modified Mercalli Index) or magnitude. 3-20
3-8 Peak ground acceleration and associated annual probability of exceedance for the Oak Ridge Reservation. 3-22
3-9 Map showing the location of the White Oak Creek Watershed in relation to the Oak Ridge Reservation and the proposed TRU Waste Treatment Facility Site. 3-24
3-10 Map of surface water monitoring locations in White Oak Creek Watershed near the proposed TRU Waste Treatment Facility. 3-26
3-11 Discharge (in curies) of various radionuclides at White Oak Dam, 1993–97. 3-29
3-12 Distribution of geologic units in the Melton Valley Watershed Remedial Investigation Area that are assigned to two broad hydrologic groups: the Knox Aquifer and the ORR aquitards. 3-32
3-13 Near-surface hydrogeologic zones. 3-33
3-14 Average water table elevation in the Melton Valley Watershed. 3-37
3-15 Locations of the hydrofracture facility sites, contaminated brine area, injected waste/grout sheets, and groundwater wells. 3-38
3-16 Wetlands, 100-, and 500-year floodplains near the proposed TRU Waste Treatment Facility site. 3-40
3-17 Wind rose detected at the ORNL Tower MT2 (@ 100 m) for 1991–1995. 3-44
3-18 Transportation route from the ORNL in east Tennessee to the Waste Isolation Pilot Plant in southeast New Mexico. 3-48
3-19 Transportation route from the ORNL in east Tennessee to the Nevada Test Site. 3-49
3-20 Eleven noise monitoring stations were located on, or near the proposed TRU Waste Treatment Facility site boundary. 3-61
3-21 Region of Influence for the Oak Ridge Reservation. 3-63
3-22 Census tracts with a minority population greater than the national average of 24.1%. 3-70
3-23 Census tracts with a low-income population greater than the national average of 13.1%. 3-71
4-1 Wetlands near the proposed TRU Waste Treatment Facility site. 4-25
4-2 Location of additional power source. 4-61
4-3 Census tracts with a minority population greater than the national average of 24.1%. All residences are restricted to locations outside the ORR boundaries, even though the tract boundaries shown on this map include portions of the ORR. 4-106
4-4 Census tracts with a low-income population greater than the national average of 13.1%. All residences are restricted to locations outside the ORR boundaries, even though the tract boundaries shown on this map include portions of the ORR. 4-107
5-1 Melton Valley Watershed Remedial Investigation site map with proposed Treatment Site Location 5-6

TABLES

S-1 Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (including D&D waste), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities S-19
S-2 Calculated effective dose equivalent to the maximally exposed off-site individual and the collective population effective dose equivalent from airborne releases of radionuclides in 1997 (ORNL 1998) S-24
S-3 Comparison of impacts among alternatives S-26
2-1 Summary of projected waste volumes for the Low-Temperature Drying Alternative 2-10
2-2 Summary of projected waste volumes for the Vitrification Alternative 2-17

2-3 Summary of projected waste volumes for the Cementation Alternative 2-24
2-4 Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (includes D&D waste), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities 2-30
2-5 Summary of alternatives considered but not evaluated for sludge and supernate waste treatment 2-33
2-6 Comparison of impacts among alternatives 2-35
3-1 State-listed terrestrial plant species with compatible habitats exhibited in the proposed site 3-6
3-2 Tennessee State-listed "in need of management" terrestrial animal species with compatible habitats exhibited in the proposed site 3-7
3-3 Doses of radionuclides to aquatic receptors at ORNL surface water locations in 1997 3-8
3-4 Select properties of soils at the proposed TRU Waste Treatment Facility site 3-17
3-5 Modified Mercalli Intensity Scale for earthquakes, developed 1931 3-19
3-6 Richter Scale of earthquake magnitude 3-19
3-7 Maximum historical earthquakes and the maximum Modified Mercalli Intensity and their peak ground accelerations at the ORR 3-21
3-8 Seismic ground acceleration for soil-supported facilities 3-23
3-9 ORNL NPDES Permit TN0002941 permit limits and compliance statistics (1997) 3-27
3-10 Locations, frequency, and parameters for the Environmental Monitoring Plan surface water sampling at ORNL 3-30
3-11 Summary of radionuclide activities during the 1997 Environmental Monitoring Plan surface water sampling 3-30
3-12 Historical and projected remote-handled TRU and contact-handled TRU debris generation rates at ORNL 3-42
3-13 Summary of 1997 air monitoring data in the vicinity of the ORR 3-45
3-14 Radionuclide parameter concentrations and other parameters measured at ORNL air monitoring stations, 1997 3-45
3-15 Calculated effective dose equivalent to the maximally exposed individual and the collective population effective dose equivalent from airborne releases in 1997 3-53
3-16 Five-year trends in the total effective dose equivalent for selected pathways 3-56
3-17 Actual versus allowable air emissions from ORNL steam production during 1997 3-57
3-18 Chemical Hazard Quotients for metals in fish (ORNL 1997) 3-58
3-19 Chemical Hazard Quotients for drinking water (ORNL 1997) 3-59
3-20 Noise monitoring data for Melton Valley proposed TRU waste facility 3-62
3-21 Regional population trends and projections in the Oak Ridge Region of Influence 3-64
3-22 Population for incorporated areas within the ORR region 3-64
3-23 1990 Population by race and ethnicity for the ORR region 3-64
3-24 Housing summary for the ORR region, 1990, by county 3-65
3-25 Public school statistics in the ORR region, 1996–97 school year 3-65
3-26 Hospital capacity and usage in the ORR region 3-66
3-27 Region of Influence employment data, 1991–96 3-66
3-28 Distribution of DOE-related employment in Region of Influence, 1996 3-67
3-29 Employment distribution by industry for the four-county Region of Influence 3-67
3-30 Per capita income data for the four-county Region of Influence and the State of Tennessee 3-68
3-31 Percent of individuals with incomes below poverty line in the four-county Region of Influence and the State of Tennessee, 1990 3-68
3-32 Municipal and county general fund revenues in the ORR region, Fiscal Year 1997 3-69
4-1 Comparison of waste volumes generated by the alternatives that include waste treatment 4-27
4-2 Summary of projected waste volumes for the Low-Temperature Drying Alternative (the total of each waste category is summarized in 4-1) 4-28

4-3 Summary of projected waste volumes for the Vitrification Alternative (the total of each waste category is summarized in 4-1) 4-29
4-4 Summary of projected waste volumes for the Cementation Alternative (the total of each waste category is summarized in 4-1) 4-30
4-5 Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (including D&D wastes), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities 4-37
4-6 Estimated air emissions from the proposed Low-Temperature Drying treatment facility and State of Tennessee permit exemptions 4-39
4-7 Average concentrations of hazardous air pollutants measured at ORR and projected maximum concentrations from the Low-Temperature Drying Alternative 4-39
4-8 Estimated consequences for the most severe accidents involving shipments of low-level waste 4-46
4-9 Calculated non-accident radiological LCFs for the Low-Temperature Drying Alternative 4-48
4-10 Projected waste shipment schedule for the Low-Temperature Drying Alternative 4-50
4-11 Calculated non-accident radiological LCFs for the Vitrification Alternative 4-51
4-12 Projected shipment schedule for the Vitrification Alternative 4-53
4-13 Calculated non-accident radiological LCFs for the Cementation Alternative 4-54
4-14 Projected shipment schedule for the Cementation Alternative 4-56
4-15 Summary of Treatment and Waste Storage at ORNL Risks 4-57
4-16 Comparison of alternatives (calculated transportation accidents/fatalities based on total off-site shipments) 4-58
4-17 Utility requirements of the Low-Temperature Drying Alternative facility 4-62
4-18 Facility energy requirements (connected load) for the Low-Temperature Drying Alternative 4-62
4-19 Dose and risk due to radionuclide emissions from the Low-Temperature Drying Alternative 4-67
4-20 Summary of health effect endpoints 4-68
4-21 Dose and risk due to radionuclide emissions from the Vitrification Alternative 4-69
4-22 Dose and risk due to radionuclide emissions from the Cementation Alternative 4-69
4-23 Total probability of cancer fatality summary for the treatment alternatives during institutional control 4-70
4-24 Frequencies and consequences of the No Action Alternative for Melton Valley Storage Tanks storage accidents 4-74
4-25 Estimated source terms for the No Action Alternative contact-handled and remote-handled waste storage accidents 4-82
4-26 Estimated frequencies and consequences for the No Action Alternative contact-handled and remote-handled waste storage accidents 4-82
4-27 Frequency and consequences of contact-handled and remote-handled solid waste treatment accidents for the Low-Temperature Drying Alternative 4-83
4-28 Summary of accident consequences and frequencies for the alternatives 4-89
4-29 Summary of total risks to the surrounding public and ETTP populations for the alternatives 4-90
4-30 Summary of risks for the public MEI and non-involved worker 4-91
4-31 Summary of the treatment alternatives accident frequencies and consequences 4-92
4-32 Manpower plan for the Low-Temperature Drying Alternative 4-96
4-33 Estimated region of influence employment impacts by year for the Low-Temperature Drying Alternative 4-97
4-34 Estimated region of influence earnings impacts by year for the Low-Temperature Drying Alternative 4-97
4-35 Manpower plan for the Vitrification Alternative 4-99

4-36 Estimated region of influence employment impacts by year for the Vitrification Alternative 4-100
4-37 Estimated region of influence earnings impacts by year for the Vitrification Alternative 4-100
4-38 Manpower plan for the Cementation Alternative 4-101
4-39 Estimated region of influence employment impacts by year for the Cementation Alternative 4-102
4-40 Estimated region of influence earnings impacts by year for the Cementation Alternative 4-102
4-41 Estimated employment impacts by year for the Treatment and Waste Storage at ORNL Alternative for the region-of-influence 4-103
4-42 Manpower plan for the Treatment and Waste Storage at ORNL Alternative 4-104
4-43 Estimated earnings impacts by year for the Treatment and Waste Storage at ORNL Alternative for the region-of-influence 4-104

THIS PAGE INTENTIONALLY LEFT BLANK

ACRONYMS AND ABBREVIATIONS

Note: These acronyms and abbreviations represent a combined list for both Volume 1 and Volume 2. Acronyms and abbreviations may not all be used in each volume. Less familiar acronyms are sometimes redefined within the document to enhance readability for the general public.

AEA	Atomic Energy Act of 1954
ALARA	as low as reasonably achievable
ANS	Advanced Neutron Source
CAA	Clean Air Act
CBOD	carbonaceous biochemical oxygen demand
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	*Code of Federal Regulations*
CH	contact-handled
CX	categorical exclusion
D&D	decontamination and decommissioning
DOE	U.S Department of Energy
DOT	U.S. Department of Transportation
DSSI	Diversified Scientific Services, Inc.
EA	environmental assessment
EIS	environmental impact statement
EM	Environmental Management
EPA	U.S. Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act of 1986
ETTP	East Tennessee Technology Park
FFA	Federal Facilities Agreement
Foster Wheeler	Foster Wheeler Environmental Corporation
FR	*Federal Register*
FSAR	Final Safety Analysis Report
FY	fiscal year
HEME	high-efficiency mist eliminator
HEPA	high-efficiency particulate air
HVAC	heating, ventilation, and air conditioning
ICRP	International Commission on Radiological Protection
INEEL	Idaho National Engineering and Environmental Laboratory
ISCST3	Industrial Source Complex Modeling Code, Version 3
LCF	latent cancer fatality
LDR	Land Disposal Restriction
MEI	maximally exposed individual
MSRE	Molten Salt Reactor Experiment
MVSTs	Melton Valley Storage Tanks
NAAQS	National Ambient Air Quality Standards
NEPA	National Environmental Policy Act
NESHAPs	National Emission Standards for Hazardous Air Pollutants
NFS	Nuclear Fuel Services
NHPA	National Historic Preservation Act
NPDES	National Pollutant Discharge Elimination System
NRC	Nuclear Regulatory Commission
NTS	Nevada Test Site
ORNL	Oak Ridge National Laboratory

ORO	Oak Ridge Operations
ORR	Oak Ridge Reservation
PCB	polychlorinated biphenyl
PCF	probability of cancer fatality
PPE	personal protective equipment
PSD	prevention of significant deterioration
QA/QC	quality assurance/quality control
Rad-NESHAP	National Emission Standards for Hazardous Air Pollutants for Radionuclides
RCRA	Resource Conservation and Recovery Act
REDC	Radiological Engineering Development Center
RH	remote-handled
RIMS II	Regional Input-Output Modeling System II
ROI	Region of Influence
SCR	selective catalytic reduction
SS	stainless steel
SWSA 5 North	Solid Waste Storage Area 5 North
SWSA	Solid Waste Storage Area
TAAQS	Tennessee Ambient Air Quality Standards
TCLP	Toxicity Characteristic Leaching Procedure
TDEC	Tennessee Department of Environment and Conservation
TEDE	total effective dose equivalent
TPDES	Tennessee Pollutant Discharge Elimination System
TRC	total residual chlorine
TRU	transuranic
TSCA	Toxic Substances Control Act
TSP	total suspended particulates
TVA	Tennessee Valley Authority
UBC	uniform building code
UTS	Universal Treatment Standard
WM PEIS	*Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (DOE/EIS-0200-F, May 1997)
WIPP	Waste Isolation Pilot Plant
WIPP SEIS-II	*Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (DOE/EIS-0026-S-2, September 1997)

UNITS OF MEASURE

Bq	becquerel
Bq/g	becquerels per gram
C	Celsius
Ci	curie
Ci/g	curies per gram
cm	centimeter
dBA	decibel
dscf	dry standard cubic foot
dscfm	dry standard cubic feet per minute
F	Fahrenheit
ft	feet
ft^2	square feet
ft^3	cubic feet
gal	gallon
gpd	gallons per day
gpm	gallons per minute
gr/dscf	grains per dry standard cubic foot
Gy/d	gray (absorbed dose, energy) per day
h	hour
ha	hectare
hr	hour
in	inch
km	kilometer
kV	kilovolt
kW	kilowatt
L	liter
lb	pound
lb/ft^3	pounds per cubic foot
lbs/h	pounds per hour
Leq	equivalent sound or noise level
m	meter
m^3	cubic meters
mg/L	milligrams per liter
mph	miles per hour
mrem	millirem (one thousandth of a rem)
mrem/h	millirem per hour
MW	megawatt
nCi/g	nanocuries per gram
ng/L	nanograms per liter
pCi/g	picocuries (one trillionth of a curie) per gram
ppm	parts per million
psig	pounds per square inch gauge
rad/d	rads per day
rem	roentgen equivalent man
rpm	revolutions per minute
wt %	weight percent
$\mu g/m^3$	micrograms per cubic meter
µR	microroentgen

Metric Conversion Chart

To Convert From U.S. Customary Into Metric			To Convert From Metric Into U.S. Customary		
If you know	**Multiply by**	**To get**	**If you know**	**Multiply by**	**To get**
Length					
inches	2.540	centimeters	centimeters	0.3937	inches
feet	30.48	centimeters	centimeters	0.03281	feet
feet	0.3048	meters	meters	3.281	feet
yards	0.9144	meters	meters	1.094	yards
miles	1.609	kilometers	kilometers	0.6214	miles
Area					
square inches	6.452	square centimeters	square centimeters	0.1550	square inches
square feet	0.09290	square meters	square meters	10.76	square feet
square yards	0.8361	square meters	square meters	1.196	square yards
acres	0.4047	hectares	hectares	2.471	acres
square miles	2.590	square kilometers	square kilometers	0.3861	square miles
Volume					
fluid ounces	29.57	milliliters	milliliters	0.03381	fluid ounces
gallons	3.785	liters	liters	0.2642	gallons
cubic feet	0.02832	cubic meters	cubic meters	35.3	cubic feet
cubic yards	0.7646	cubic meters	cubic meters	1.308	cubic yards
Weight					
ounces	28.35	grams	grams	0.03527	ounces
pounds	0.4536	kilograms	kilograms	2.205	pounds
short tons	0.9072	metric tons	metric tons	1.102	short tons
Temperature					
Fahrenheit (°F)	subtract 32, then multiply by 5/9	Celsius (°C)	Celsius (°C)	multiply by 9/5, then add 32	Fahrenheit (°F)
kelvin (°k)	subtract 273.15	Celsius (°C)	kelvin (°k)	multiply by 9/5, then add 306.15	Fahrenheit (°F)
Note: 1 sievert = 100 rems					

Metric Prefixes

Prefix	Exponent Converted to Whole Numbers	Prefix	Exponent Converted to Whole Numbers
pico	$10^{-12} = 0.000,000,000,001$	dekta-	$10^{1} = 10$
nano-	$10^{-9} = 0.000,000,001$	hecto-	$10^{2} = 100$
micro-	$10^{-6} = 0.000,001$	kilo-	$10^{3} = 1,000$
milli	$10^{-3} = 0.001$	mega-	$10^{6} = 1,000,000$
centi	$10^{-2} = 0.01$	giga-	$10^{9} = 1,000,000,000$
deci-	$10^{-1} = 0.1$	tetra-	$10^{12} = 1,000,000,000,000$
Note: $10^{0} = 1$			

THIS PAGE INTENTIONALLY LEFT BLANK

SUMMARY

S1.1 INTRODUCTION

U.S. Department of Energy (DOE) facilities on the Oak Ridge Reservation (ORR) in the Oak Ridge, Tennessee, area have performed nuclear energy research and radiochemical production since the early 1940s. The reservation encompasses 13,974 contiguous hectares (ha) (34,516 acres), and the Y-12 Plant, the East Tennessee Technology Park (ETTP), and the Oak Ridge National Laboratory (ORNL) are major DOE facilities within it.

ORNL was constructed during World War II as a pilot-scale plant to support nuclear energy research and the construction of larger plutonium production facilities at Hanford, Washington. ORNL is located on approximately 1,174 ha (2,900 acres) (Figure S-1) in a water-rich environment, with numerous small tributaries that flow into the Clinch River located to the south and west. ORNL is in the Tennessee Valley between the Great Smoky Mountains (located approximately 80 km or 50 miles east) and the Cumberland Plateau (about 45 km or 25 miles west).




Figure S-1. Location of Oak Ridge National Laboratory in relation to the City of Oak Ridge and other DOE facilities on the Oak Ridge Reservation, and in the State of Tennessee.

ORNL continues to be used for DOE operations and is internationally known as a premier research facility. Research and development activities support national defense and energy initiatives. Ongoing waste management and environmental management activities continue to address legacy[1] and newly generated low-level radioactive[2], transuranic (TRU)[3], and hazardous wastes resulting from research and development activities. As the ORR is on the National Priorities List, meeting the cleanup challenges at the site, including those associated with legacy wastes at ORNL, is a high priority for the DOE Oak Ridge Operations (ORO), the Tennessee Department of Environment and Conservation (TDEC), the U.S. Environmental Protection Agency (EPA), and stakeholders. The treatment and disposal of legacy TRU waste at ORNL, is an important component of the DOE cleanup at the site. Currently, no facilities exist at ORNL, or the ORR, for treating TRU mixed[4] waste sludges and associated low-level waste supernate, and contact-handled[5] and remote-handled[6] TRU/alpha low-level[7] waste solids, before disposal.

S1.2 BACKGROUND

During early research activities, little was known about the effects of exposure to radiation and other hazardous substances. Wastes generated from research and development activities and isotope production were managed using the best available practices at the time. Liquid radioactive waste was stored in underground storage tanks. Contaminated solid waste was buried in pits and trenches. Although waste management practices have changed as the hazards became better understood, legacy waste remains in storage at ORNL as described below.

S1.2.1 Waste Types

The four legacy waste types that would be treated under the proposed action are:

- remote-handled TRU mixed waste sludge,
- low-level radioactive waste supernate (liquid portion) associated with the TRU sludge waste,
- contact-handled TRU/alpha low-level waste solids, and
- remote-handled TRU/alpha low-level waste solids.

[1]Legacy waste is defined as waste generated from past isotope production and research and development activities.

[2]Low-level waste is defined as any radioactive waste not classified as high-level, spent nuclear fuel TRU, byproduct material, or mixed waste [based on *Implementation Guide for Use with DOE M 435.1-1*, DOE G 435.1-1, July 1999 (DOE 1999)].

[3]TRU waste is waste not classified as high-level radioactive waste but as waste which contains more than 100 nanocuries per gram (nCi/g) of alpha-emitting TRU isotopes (atomic numbers greater than 92) with half-lives greater than 20 years (based on DOE 1999).

[4]Mixed waste is a waste that contains radioactive waste regulated under the Atomic Energy Act of 1954 as amended, and a hazardous component subject to the Resource Conservation and Recovery Act (based on DOE 1999).

[5]Contact-handled TRU waste contains beta- and gamma-emitting isotopes in addition to alpha-emitting isotopes, with a surface dose rate of 200 millirem per hour (mrem/h) or less [*Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS-II), DOE/EIS-0026-S-2, "Glossary," p. GL-3 (DOE 1997a)].

[6]Remote-handled TRU waste contains beta- and gamma-emitting isotopes in addition to alpha-emitting isotopes, with a surface dose rate greater than 200 mrem/h [WIPP SEIS-II, "Glossary," p. GL-14 (DOE 1997a)].

[7]Alpha low-level radioactive waste is low-level waste that contains alpha-emitting isotopes.

ORNL currently has the largest inventory of remote-handled TRU waste in the DOE complex, and a smaller portion of the contact-handled TRU waste. The remote-handled TRU waste sludges are solids that precipitated out of the liquid waste during waste storage and settled to the bottom of the underground storage tanks. The contact-handled and remote-handled TRU/alpha low-level waste solids at ORNL are a heterogeneous mixture of paper, glass, rubber, cloth, plastic, and metal from glove boxes, fuel processing facilities, hot cells, and reactors. Based on generator records, the stored solid wastes have been classified as either TRU or alpha low-level radioactive waste. Because the nature of the solid waste can only be confirmed after retrieval and characterization, these solid wastes were characterized as "TRU/alpha low-level radioactive waste" in the Notice of Intent for this Draft Environmental Impact Statement (EIS) [*Federal Register* (*FR*) Vol. 64, No. 17, January 27, 1999] to note the current uncertainty.

The remote-handled TRU waste sludge and potentially some of the contact-handled and remote-handled TRU/alpha low-level waste solids contain metals regulated under the Resource Conservation and Recovery Act (RCRA) and, therefore, may be classified as mixed waste due to toxicity. Generator records for the solid wastes do not indicate the presence of any RCRA-regulated materials in the solid waste containers; however, if found, solid mixed waste would be segregated from solid non-mixed waste.

Supernate (the liquid portion of the waste stored in the underground storage tanks at ORNL) is generally characterized as low-level waste.

S1.2.2 Waste Storage at ORNL

The inactive tanks at ORNL that contain legacy waste are currently undergoing waste retrieval operations. The retrieved sludge and supernate wastes are being transferred to the Melton Valley Storage Tanks (Figure S-2). See additional discussion in Section S1.3 below. The remainder of ORNL's TRU mixed waste sludge is already stored in the Melton Valley Storage Tanks. Sampling and analyses have been performed on all of the tank waste at ORNL. The radiological and chemical properties of the sludge and supernate have been measured, and a bounding analysis was performed on each constituent to provide a range of waste characteristics. The legacy contact-handled and remote-handled TRU/alpha low-level solid wastes at ORNL are currently stored in subsurface trenches, bunkers, and metal buildings.




Figure S-2. Aerial view of the Melton Valley Storage Tanks–Capacity Increase Project during installation of the six 100,000-gallon tanks, which are located south of the eight 50,000-gallon Melton Valley Storage Tanks.

S1.2.3 Public Participation

A Notice of Intent to prepare an EIS for the TRU Waste Treatment Project was published in the *Federal Register* (*FR*) on January 27, 1999 (in Appendix A.1). The Notice of

Intent identified the public scoping period to encourage early public involvement in the EIS process and to solicit public comments on the proposed scope of the EIS, including the issues and alternatives it would analyze. Two meetings were held in Oak Ridge, Tennessee, on February 11 and 16, 1999, to provide an opportunity for people to comment or make a presentation. Oral and written comments from the scoping meetings are summarized in Appendix A.3. Most of the comments requested clarification of the proposed action and the alternatives. There was some concern that the upgrade of the Old Melton Valley Road (also referred to as the High Flux Isotope Reactor access road) and the construction of the proposed TRU Waste Treatment Facility would have an impact on the Old Hydrofracture Facility wells. However, these wells are located away from the road and proposed facility and would not be disturbed during any construction activities. The scoping period ended on February 26, 1999.

The Draft EIS was released to the public for review and comment on March 3, 2000. On March 21, 2000, a public hearing was held in the Oak Ridge Mall. Oral comments were received on the Draft EIS and a transcript was made of the hearing. The public comment period ended on April 17, 2000. All public comments received on the Draft EIS and responses to these comments are contained in the Comment Response Document, Volume 2, of this Final EIS. Information provided below contains an overview of comments and responses on the Draft EIS and discusses those areas for which DOE received multiple comments.

Many commentors supported DOE's proposed action, although some were concerned that the processes for treating the wastes in the Melton Valley Storage Tanks may not have been done before at this scale or by the selected contractor. Some commentors were concerned about the uncertainty of using the various treatment processes (e.g., technical implementability), especially vitrification. While DOE acknowledges that there is some uncertainty in treating TRU waste using any of the technologies, there are successful examples of these specific technologies being used in similar situations. Examples of successful use of drying technology include the Hanford 200 Area evaporator in Hanford, Washington, the Palo Verde Nuclear Generating Station near Phoenix, Arizona, and the Three-Mile Island-2 Evaporation Project, Harrisburg, Pennsylvania. Examples of successful waste solidification operations using hydraulic cement include DOE's Hanford, Rocky Flats, Savannah River sites, and Melton Valley Storage Tank waste at ORNL. Examples of successful DOE use of vitrification include the Savannah River M-Area, the Fernald Minimum Additive Waste Unit, and the West Valley Vitrification Plant.

Some commentors took issue with the Treatment and Waste Storage at ORNL Alternative, maintaining that 100 years of institutional control was an insufficient timeframe for analysis of impacts, and that the alternative was contrary to a Tennessee Department of Environment and Conservation (TDEC) Commissioner's Order to ship treated waste offsite; thus, the alternative was not reasonable under the National Environmental Policy Act (NEPA). Other commentors noted that the alternative should not be for 100 years, but that 30 years was the maximum DOE should consider for interim storage. Some commentors indicated that the impacts associated with the No Action Alternative were also understated because the impact analysis period was limited to 100 years. DOE considers this alternative reasonable and has provided additional analysis in the Final EIS for the No Action Alternative and Treatment and Waste Storage at ORNL that examined potential impacts from loss of institutional control, assumed to occur for analysis purposes, after 100 years. A 30-year timeframe as compared to a 100-year timeframe would show lower impacts for both utility usage and worker exposure.

Several commentors stated that DOE unduly restricted the impact analysis by omitting analysis of on-site transport of the wastes to the treatment facility. DOE agrees and has added several subsections to Chapter 4, in Section 4.8, that discuss transportation analysis of the Final EIS. These sections address the impacts of routine operations to the involved workers, and accidents to the involved workers,

non-involved workers, and the public from exhumation or removal of wastes from the subsurface trenches, buildings, and bunkers, and transport of wastes to the proposed treatment facility.

The U.S. Department of the Interior (DOI) asked for additional information on protected species, including the Indiana Bat. DOE has submitted to DOI a draft Biological Assessment (BA) based on information in the Draft EIS and from site walkovers, and DOE will continue informal consultation with DOI under the Endangered Species Act. A copy of the draft BA is included in Appendix E of the Final EIS.

One commentor questioned the adequacy of the accident analysis for the Low-Temperature Drying Alternative, pointing out that for high-level waste, explosions and criticality are typically evaluated. DOE considered a wide range of accident scenarios and selected those that were determined to be credible for detailed analysis. Because low-temperature drying is a low-energy process and is conducted in small, 1-m^3 batches, an explosion would be unlikely. Further, this waste treatment process would be performed in an area with 2-ft-thick walls for radiological protection. Workers are not allowed in the area when treatment is occurring. As a result, there is little risk to involved and non-involved workers. With regard to criticality accidents, DOE has no process knowledge suggesting that any enriched materials would be part of the waste stream. In addition, administrative and process controls would be followed that avoid criticality.

S1.3 PURPOSE AND NEED FOR AGENCY ACTION

DOE needs to treat the legacy TRU and alpha low-level waste at ORNL in order to reduce the risk to human health and the environment and to comply with legal mandates from the TDEC and the ORNL Site Treatment Plan. In addition, newly generated TRU waste needs to be treated and is included in the waste volumes described below.

The approximate quantities[8,9] of the waste streams requiring treatment and analyzed in this EIS are:

- 900 m^3 (31,770 ft^3) of remote-handled TRU sludge (mixed waste), which is, or will be, located in the Melton Valley Storage Tanks;
- 1,600 m^3 (56,480 ft^3) of low-level supernate associated with the TRU mixed waste sludge, which is, or will be, located in the Melton Valley Storage Tanks;
- 550 m^3 (19,415 ft^3) of remote-handled TRU waste/alpha low-level radioactive waste solids (may consist of some mixed waste), located in bunkers and subsurface trenches; and
- 1,000 m^3 (35,300 ft^3) of contact-handled TRU waste/alpha low-level radioactive waste solids (may consist of some mixed waste), located in metal buildings.

Legal mandates require DOE to address legacy TRU waste management. DOE has been directed by the TDEC and the EPA to address environmental issues, including disposal of its legacy TRU waste. DOE is under a TDEC Commissioner's Order (September 1995) to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and

[8]Potential impacts of the off-site waste (15 m^3 from Paducah) are considered in Section 5. DOE would need to conduct further NEPA review as appropriate for any proposal for the Paducah site, or any other site within the DOE complex, ships any TRU waste to ORNL for treatment.

[9]Waste volume estimates provided herein have not been rounded and may contain more than the significant numbers of digits.

disposal of ORNL's TRU waste. The primary milestone in the TDEC Commissioner's Order requires that DOE begin treating legacy TRU mixed waste sludge in order to make the first shipment to the Waste Isolation Pilot Plant by the end of January 2003.

Waste retrieval operations are currently under way to prepare many of the inactive TRU waste storage tanks, including the gunite tanks at ORNL, for closure. A majority of the wastes retrieved from the ORNL inactive tanks are being consolidated into the Melton Valley Storage Tanks and have been included in the stated waste quantities needing treatment. Waste retrieval and consolidation activities for the ORNL Inactive Tanks Program are planned for completion by the end of fiscal year (FY) 2001.

Due to the water-rich environment in East Tennessee, legacy TRU/alpha low-level solid wastes contained in the subsurface trenches at ORNL pose a risk to the area's water quality. Removal, treatment, and disposal of the retrievable TRU waste from portions of the Solid Waste Storage Area 5 North (SWSA 5 North) is a major component of the proposed remedy for the Melton Valley Watershed at ORNL according to the Draft Record of Decision for the Melton Valley Watershed at ORNL (DOE 1997b). In addition, an Interim Record of Decision [issued in connection with the Federal Facilities Agreement (FFA) among EPA, TDEC, and DOE under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)] for the Gunite and Associated Tanks Remediation Project (DOE 1997c), and an Action Memorandum for the Old Hydrofracture Facility Tanks Remediation Project (DOE 1997d), require that the waste contained in these tanks be treated and disposed of along with the TRU waste contained in the Melton Valley Storage Tanks. This tank waste is included in the total waste volume proposed for treatment in the TRU Waste Treatment Project. Currently, no facilities exist at ORNL, or on the ORR, for treating TRU or alpha low-level radioactive waste.

S1.4 PROPOSED ACTION AND ALTERNATIVES

S1.4.1 Proposed Action

DOE proposes to construct, operate, and decontaminate and decommission (D&D) a waste treatment facility (Figure S-3) for the treatment of legacy ORNL TRU, alpha low-level waste, and newly generated TRU waste. All the legacy waste DOE proposes to treat is currently stored at ORNL. The newly generated TRU waste would be treated in the proposed facility until it is closed for D&D. TRU waste generated after closure of the proposed facility is not within the scope of the proposed action. Following the waste treatment and packaging operations at the proposed treatment facility, DOE would certify the TRU waste for shipment and disposal at the Waste Isolation Pilot Plant, located near Carlsbad, New Mexico [*Record of Decision for the Department of Energy's Waste Isolation Pilot Plant Disposal Phase, FR*, Vol. 63, No. 15, January 1998 (DOE 1998a)]. Low-level waste resulting from the treatment processes would be certified by DOE for disposal at the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* [*FR*, Vol. 65, No. 38, February 25, 2000 (DOE 2000)].

DOE prepared a characterization report for the site of the proposed action and sponsored an independent study of treatment technologies and contracting alternatives, known as the Parallax study [ORNL/M-4693, *Feasibility Study for Processing ORNL TRU Waste In Existing and Modified Facilities*, September 15, 1995 (Parallax 1995)]. This facility is needed to reduce the risk to human health and the environment, and to comply with the TDEC Commissioner's Order of 1995, which




Figure S-3. General site location of the proposed TRU Waste Treatment Project facility on the Oak Ridge Reservation.

requires DOE to make the first shipment of treated TRU sludge to the Waste Isolation Pilot Plant in New Mexico by January 2003.

This EIS is being prepared according to the NEPA of 1969, the Council on Environmental Quality NEPA regulations [40 *Code of Federal Regulations* (*CFR*) 1500–1508], and DOE's NEPA Implementing Procedures (10 *CFR* Part 1021). This Final EIS incorporates pertinent analyses performed as part of the DOE's *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS-II) (DOE 1997a), and the *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F (WM PEIS) (DOE 1997e). Treatment of ORNL TRU waste onsite, and disposal at the Waste Isolation Pilot Plant, is consistent with the Record of Decision for the Waste Isolation Pilot Plant disposal phase (DOE 1998a) and for DOE's WM PEIS Record of Decision for treatment and storage of TRU waste [*FR*, Vol. 63, No. 15, January 23, 1998 (DOE 1998b)], both issued for management of the TRU waste. The disposal of low-level radioactive waste is consistent the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

DOE has awarded a contract to the Foster Wheeler Environmental Corporation (Foster Wheeler) for the construction, operation, and D&D of a treatment facility for the TRU and alpha low-level wastes, contingent upon the completion of the NEPA review (if it includes a Record of Decision

selecting the contractor's proposed treatment process). The contract would be carried out in four phases including:

- Phase I, Permitting (includes DOE's NEPA analysis and contractor preliminary design activities);
- Phase II, Construction and Pre-Operational Testing;
- Phase III, Waste Treatment, Packaging, and Certification; and
- Phase IV, Decontamination and Decommissioning.

Phase I is a 2.5-year period during which the permitting and preliminary design process is completed for the proposed facility. DOE will complete the NEPA process concurrent with Phase I of the contract. If the current NEPA review results in the selection of a treatment process other than the selected contractor's proposal, Phase II of the contract would not be implemented. The contract also allows DOE to identify, during Phase I, other potential waste streams for treatment at this facility (e.g., small amounts of legacy TRU waste from other sites). An example of such waste is discussed under cumulative impacts. As part of any consideration to send additional waste to ORNL, further NEPA review, as appropriate, would be conducted.

The phased procurement approach described above is consistent with DOE's NEPA regulations at 10 *CFR* 1021.216, which address integration of DOE's procurement and NEPA review processes, and provides for a phased procurement that is contingent upon completion of the NEPA review process before a "go/no-go" decision. DOE's Request for Proposal required bids to include environmental data and analysis, to the extent that they were available. The environmental data provided in the three bids received were independently evaluated, and an Environmental Critique was prepared. DOE also prepared an Environmental Synopsis that was issued in January 1999 (Appendix A.2), which was based on the Environmental Critique. The Synopsis was filed with EPA and is publicly available. In addition, prior to selection of the contractor, DOE held two public meetings with stakeholders and had ongoing discussions with regulators.

The proposed site for the treatment facility is adjacent to the Melton Valley Storage Tanks (the storage area for the TRU mixed waste sludge and associated low-level supernate). DOE would lease the Melton Valley Storage Tanks and an adjacent land area totaling up to approximately 4 ha (10 acres) to the contractor selected for the construction of the facility (Figure S-4), subject to notification of the EPA and the State of Tennessee. Once the facility is closed and D&D of the facility is completed by the contractor per a D&D plan approved by DOE, the land used for the facility would no longer be leased to the selected contractor and would revert to DOE.

The proposed facility location is based on the factors listed below:

- The treatment facility should be located close to the existing Melton Valley Storage Tanks to minimize the length of a new sludge/supernate transfer line and reduce the environmental disturbance due to construction as recommended in the *Feasibility Study for Processing ORNL Transuranic Waste in Existing and Modified Facilities* (Parallax 1995).
- The existing terrain should provide natural shielding for the proposed facility and facilitate material handling.

DOE would require that all activities associated with the proposed action be performed safely and in compliance with applicable federal and state regulatory requirements. The contractor would be responsible for achieving compliance with all applicable environmental and safety and health laws and

regulations as required in the awarded contract. Regulatory agencies would be responsible for monitoring compliance by the contractor. The State of Tennessee would regulate the contractor according to permits under the state's purview (the RCRA Part B permit issued by the State of Tennessee). DOE would regulate occupational safety and health and nuclear safety according to specific environment, safety, and health requirements, as stipulated in the contract between DOE and Foster Wheeler.




Figure S-4. DOE would lease the Melton Valley Storage Tanks facility and an adjacent area of land to construct the waste treatment facility. The location is isolated from ORNL by Haw Ridge.

S1.4.2 Alternatives

DOE analyzed five alternatives for the proposed action: a no action alternative; three alternative technologies for treating the wastes followed by shipment to an appropriate disposal facility; and treatment by any of the three alternative treatment technologies, followed by long-term storage at ORNL. Section S1.4.2 summarizes the following five alternatives:

1. **No Action** (i.e., continued on-site storage and no waste treatment) for all of the legacy TRU tank waste stored in the Melton Valley Storage Tanks and the legacy contact-handled and remote-handled TRU/alpha low-level solid wastes stored in trenches, vaults, and metal buildings.

2. **Low-Temperature Drying (Preferred Alternative)** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).

3. **Vitrification** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).

4. **Cementation** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).

5. **Treatment and Waste Storage at ORNL** would provide treatment by one of the above treatment alternatives followed by interim waste storage at ORNL.

The Treatment and Waste Storage at ORNL Alternative was analyzed as a contingency in case off-site waste disposal facilities would not be available for any reason.

Each treatment alternative analyzed included treatment approaches that would solidify the sludges and supernate, compact the solid wastes, and provide treatment for some mixed wastes to meet the land disposal restriction (LDR) standards. After waste treatment, DOE would certify the waste for disposal as low-level radioactive waste (including remote-handled low-level and alpha low-level radioactive waste), mixed low-level waste, or contact-handled and remote-handled TRU waste (including mixed TRU waste). The contractor would be required to treat all wastes to meet specified waste acceptance criteria for disposal. For each treatment alternative, this section describes the treatment approach and general features (with simplified flow diagrams), waste products generated, waste minimization measures, land use requirements, and the proposed schedule.

Treated TRU waste resulting from the proposed action would be disposed of at the Waste Isolation Pilot Plant, consistent with the Records of Decision from the WIPP SEIS II (DOE 1998a) and the WM PEIS (DOE 1998b). The waste treatment methods analyzed in this EIS will treat remote-handled TRU sludge waste to meet RCRA LDR standards. This will allow the treated remote-handled TRU sludge waste to be stored onsite in the event that the Waste Isolation Pilot Plant is not accepting remote-handled TRU waste in time to meet the TDEC Commissioner's Order.

The treated supernate associated with the tank sludge, which is generally classified as low-level waste, would be disposed of at the Nevada Test Site, consistent with the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

Because most of the current solid waste containers do not meet U.S. Department of Transportation (DOT) regulations (49 *CFR* 173), the solid waste would need to be repackaged prior to shipment. DOE would better characterize the solid waste during the repackaging efforts to achieve final DOE waste certification before disposal. Contact-handled and remote-handled solids containing RCRA regulated wastes would be isolated and treated to meet RCRA LDR standards, which is addressed in more detail in Chapter 2.

S1.4.2.1 No Action Alternative

The No Action Alternative involves continued storage of mixed waste (RCRA hazardous and radioactive) TRU sludges and the associated low-level waste supernate in the Melton Valley Storage Tanks. Storage of contact-handled and remote-handled TRU/alpha low-level waste solids in the SWSA 5 North trenches would also continue. The remote-handled TRU/alpha low-level waste solids that are stored in Buildings 7855 and 7883 would remain in these units, and contact-handled TRU/alpha low-level solids currently stored in Buildings 7572, 7574, 7842, 7878, and 7879 would also remain in those units. In addition, the remote-handled TRU and certain contact-handled TRU wastes currently stored in the below-grade concrete cells in SWSA 5 North (Buildings 7826 and 7834) would be removed as part of a removal action under CERCLA and moved to existing facilities for remote-handled and contact-handled wastes at ORNL (described in Section 2.3.1 of this Draft EIS).


No treatment facility would be constructed under the No Action Alternative. The No Action Alternative assumes institutional control for 100 years followed by a loss of institutional control, which for analysis purposes, is assumed to be after 100 years. Implementation of this alternative would result in noncompliance with the milestone established in the TDEC Commissioner's Order requiring the submittal of a Project Management Plan, which includes schedules for treatment and shipment of ORNL's TRU waste, by September 30, 2001, and would jeopardize the existing milestone established in the Commissioner's Order for initiation of shipment of the treated remote-handled TRU sludges to the Waste Isolation Pilot Plant by January 2003.

S1.4.2.2 Low-Temperature Drying Alternative

The Low-Temperature Drying Alternative (Preferred Alternative: contingent contract to Foster Wheeler) would treat the TRU mixed waste sludge and associated low-level waste supernate by low-temperature drying. The solid wastes would be characterized, sorted, and compacted to result in stable waste forms for final disposal. A waste treatment facility would be constructed immediately adjacent to the Melton Valley Storage Tanks. Construction of the treatment facility would require the development of 2 ha (5 acres) of forested land for industrial use.

This alternative would entail evaporating the supernate and free liquids contained in the sludges, and drying the TRU mixed waste sludges contained in the Melton Valley Storage Tanks. Treatment by low-temperature drying is expected to substantially reduce the waste volume, generate minimal amounts of secondary wastes, and meet the waste acceptance criteria of the final disposal facilities. All waste streams would meet the RCRA LDR standards in the event that unanticipated, on-site storage of the waste is required in order to coincide with the schedules of the appropriate disposal facilities. TRU waste streams would be treated to meet the waste acceptance criteria of the Waste Isolation Pilot Plant. Low-level waste streams would be treated to meet the current waste acceptance criteria of the Nevada Test Site.

The simplified block flow diagram for the tank waste treatment system (TRU mixed waste sludge and associated low-level supernate) is illustrated in Figure S-5. Treatment of the supernate and sludge could occur independently. Supernate would be pumped from the existing Melton Valley Storage Tanks through a double-contained, aboveground pipeline to the proposed treatment facility and collected into mixing/sample tanks. The supernate may be transferred to an evaporator for volume reduction before transfer to the mixing/sample tanks. In order to meet waste acceptance criteria for the Nevada Test Site, additives would be mixed with the supernate in these tanks. The supernate dryer would receive feed batches from the mixing/sample tanks for final concentration and drying into a stabilized particulate product. The treated waste would be loaded directly into a disposal container that is pre-loaded in a transportation cask for certification by DOE and shipment to the Nevada Test Site. Vapors from the dryer would be routed through an air-cooled condenser. Condensate may be stored in a reservoir for reuse in sludge retrieval, or evaporated and discharged as part of the building ventilation flow through appropriate high-efficiency particulate air (HEPA) filtration.



1. MVSTs = Melton Valley Storage Tanks
2. Supernate may be evaporated
3. Air emission controls include charcoal filters and High-Efficiency Particulate Air (HEPA) filter systems
4. Cross-flow filter is optional
5. LLW = Low-level waste

Figure S-5. Tank waste treatment flow diagram for the Low-Temperature Drying Alternative.

Sludge would be retrieved from the Melton Valley Storage Tanks by sluicing. The sluiced sludge would be transferred in a double-contained, aboveground pipeline to the sludge collection/decant tanks in the facility. The sludge would be concentrated by gravity settling in these tanks. Sluiced sludge may be filtered before transfer to the dryer. For optimum efficiency, the containers of dried sludge solids would be packaged and loaded directly into Waste Isolation Pilot Plant transportation canisters for certification by DOE and shipment to the Waste Isolation Pilot Plant.

DOE would deliver drums and boxes of the contact-handled and remote-handled TRU/alpha low-level solid wastes to the proposed treatment facility. Foster Wheeler would perform visual inspections and radiation and contamination surveys prior to acceptance of the waste containers. Wastes not conforming to Foster Wheeler acceptance criteria would be brought into compliance or processed by another contractor. The drum contents would be characterized by performing a non-destructive examination and assay in an adjoining enclosure before transfer to a staging area. Any

alpha low-level waste drums that do not contain TRU waste, or RCRA-regulated waste, would be treated in a drum compactor for a 50% volume reduction, overpacked, weighed, and conveyed back to the shipping/receiving area for final certification by DOE. The simplified block flow diagram for the solid waste treatment systems is illustrated in Figure S-6.




Figure S-6. Solid waste treatment flow diagram for the Low-Temperature Drying Alternative.

The remote-handled TRU/alpha low-level waste drums would be moved to a hot cell in order to sort and separate any contact-handled waste from the remote-handled waste. Any contact-handled and remote-handled waste containing RCRA-regulated waste would be treated to meet LDR standards by macroencapsulation. Macroencapsulation refers to a process where waste materials are embedded in an inert material. Waste that is compliant with LDR standards would be compacted and loaded into canisters docked at a load-out port on the hot cell. Over-sized remote-handled waste would be size reduced to fit into the canisters.

The contact-handled TRU/alpha low-level waste drums contents would be moved to a glovebox after the initial characterization, where RCRA-regulated waste would be segregated for treatment by macroencapsulation to meet LDR standards. Unrestricted, contact-handled solid waste would be compacted in drums before transfer to the assay area for DOE certification. Secondary waste, such as empty waste containers and personal protective equipment (PPE), etc., would be compacted prior to DOE certification for disposal at an appropriate facility.

The Low-Temperature Drying Alternative would result in a total of approximately 10,833 m^3 (382,405 ft^3) of primary, secondary, and D&D waste; the largest portion of the total waste volume (5,550 m^3 or 195,915 ft^3) would be debris from D&D activities. Approximately 607 m^3 (21,427 ft^3) of

treated TRU waste; 23 m^3 (812 ft^3) of mixed low-level waste, and 2,778 m^3 (98,063 ft^3) of low-level waste would be generated by this alternative. Pollution prevention and waste minimization measures would be implemented. For example, storm water would be diverted around the treatment facility, and gate valves would be installed in the diversion basins, in the event of a spill.

The total project duration for the Low-Temperature Drying Alternative is 11.5 years with a treatment time of approximately 5 years, during which off-site shipments of treated waste volumes would occur.

S1.4.3 Vitrification Alternative

The Vitrification Alternative would include vitrification (melting the waste to form a stabilized waste glass) of the TRU mixed waste sludge and associated low-level supernate in the Melton Valley Storage Tanks (Figure S-7). The contact-handled and remote-handled TRU/alpha low-level solid wastes would be segregated and compacted in a supercompactor. Some solids, however, that are smaller than the RCRA definition of debris, would be treated by vitrification. The vitrification waste treatment facility would be constructed next to the Melton Valley Storage Tanks. Construction of the treatment facility would require the development of 2.8 ha (7 acres) of forested land for industrial use.




Figure S-7. Treatment flow diagram for sludge, supernate, and solid waste smaller than RCRA definition of debris for the Vitrification Alternative.

Tank waste sludge and supernate would be pumped to the treatment facility through an aboveground, double-contained pipeline after retrieval by pulsed jet mixing. The waste would be homogenized in mix/sample tanks and the required glass-former blend would be determined after sampling the homogenized waste.

Dry glass-forming chemicals would be mixed with the homogenized waste, which would then be fed into the vitrification melter. The resulting molten glass waste would be poured into waste

containers and allowed to harden. The final glass waste form would be certified by DOE as TRU or low-level waste for disposal at the appropriate disposal facility.

Off-gas from the melter would be minimized by maintaining a cold cap floating on top of the melted glass surface. The off-gas system, including a scrubber, demisters, and HEPA filters would remove over 99% of the off-gas particulates. Excess scrubbing agents and liquid from the demisters would be recycled or collected, treated, and packaged for DOE certification as TRU, mixed, or low-level waste before disposal at the appropriate disposal facility.

The remote-handled and contact-handled TRU/alpha low-level solid waste containers would be delivered to the facility by DOE (Figure S-8). Upon receipt, the surface dose rate would be monitored. The containers would be characterized and then their contents sorted in a hot cell. Some solid waste classified as smaller than the RCRA definition of debris would be sent to the vitrification treatment train. Any contact-handled or remote-handled waste containing RCRA-regulated wastes would be macroencapsulated. Special waste materials such as batteries, aerosol cans, or glass bottles would be sent to a special treatment cell for treatment and packaging, or the vitrification treatment train if the waste matrix is compatible. The remaining remote-handled and contact-handled solid wastes would be sorted and segregated, and then volume and size reduced if required. Sorted waste containers would be characterized and weighed before compaction to provide DOE with information for waste certification. The compacted waste pucks would be placed in 55-gallon drums, grouted, and then placed in a buffer storage area until the grout hardens.

The Vitrification Alternative would result in an estimated total of 34,000 m^3 (1,200,200 ft^3) of waste. Approximately 20,712 m^3 (731,134 ft^3) of debris from D&D activities and 6,283 m^3 (221,790 ft^3) of sanitary wastewater account for the largest portion of the total waste volume.




Figure S-8. Vitrification Alternative flow diagram for solid waste treatment.

Approximately 1,060 m^3 (37,418 ft^3) of TRU waste, 4 m^3 (141 ft^3) of mixed low-level waste, and 4,983 m^3 (175,900 ft^3) of low-level waste would result from the implementation of the Vitrification Alternative.

Pollution prevention and waste minimization measures would be implemented. For example, storm water would be diverted around the treatment facility, and gate valves would be installed in the diversion basins, in the event of a spill.

The total project duration of the Vitrification Alternative would be approximately 10 years, with about 3 years of waste treatment. Following 3 months of cold operations (with non-radioactive materials) after construction of the facility, hot operations (with radioactive materials) would be conducted for about 2.75 years, during which off-site shipments of treated waste volumes would occur.

S1.4.4 Cementation Alternative

The Cementation Alternative would include hydrocyclone and centrifuge pre-treatment separation of the TRU mixed waste sludge and associated low-level supernate contained in the Melton Valley Storage Tanks, followed by cementation of the pre-treated wastes. The contact-handled and remote-handled TRU/alpha low-level solid wastes would be characterized, then segregated and compacted similar to the treatment methods described in the Vitrification Alternative for solid waste. The Cementation Alternative would require the construction of a treatment facility that would be located on 2 ha (5 acres) of land that would change from forested land to industrial use.

Sludge and supernate would be retrieved from the Melton Valley Storage Tanks by sluicing. The waste slurry would be pumped through an aboveground double-contained pipeline to storage tanks inside the cementation treatment facility (Figure S-9). A hydrocyclone in series with a centrifuge would separate the sludge from the supernate. The majority of supernate would be recycled through the Melton Valley Storage Tanks to aid in sludge retrieval operations. The slurry discharge from the centrifuge would be maintained at 25% weight total suspended solids and would be collected in feed tanks, which would allow continuous transfer to the cementation facility mixer.

A dry blend storage tank would store premixed cementation/stabilization agents. Treatment would oscillate between the supernate and sludge wastes from the feed tanks. Approximately 3.1 kg (7 lbs) of dry blend would be added per gallon of sludge from the centrifuge process, and 5 kg (11 lbs) of dry blend would be added per gallon of supernate from the centrifuge process to obtain a stabilized waste form. The dry blend would be transferred to the cementation mixer via a weigh belt feeder. After mixing the dry blend and waste, the resulting grout mixture would be pumped into 50-gallon drum liners, which would remain on a conveyor system until hardened, and then be placed inside 55-gallon carbon steel overpack drums. After passing remote external surface contamination analysis, the drums would be placed in remote-handled canisters and then into 72-B casks. The treated TRU sludge waste would be certified by DOE and disposed at the Waste Isolation Pilot Plant. The treated supernate would be remote-handled low-level waste and would be disposed of at the Nevada Test Site.

The Cementation Alternative would treat the contact-handled and remote-handled TRU/alpha low-level solid wastes with the same methods described previously for the Vitrification Alternative (Section S1.4.3), with the exception that none of the solid waste classified as smaller than debris by RCRA would be segregated and treated separately. This waste would be treated with the larger solid waste. Any RCRA-regulated waste would be segregated and treated by macroencapsulation.

The Cementation Alternative would result in an estimated total of 28,826 m^3 (1,017,558 ft^3) of waste. Debris from D&D activities (14,111 m^3 or 498,118 ft^3) and sanitary wastewater and solids




Figure S-9. Flow diagram for tank waste treatment for the Cementation Alternative.

(7,237 m^3 or 255,466 ft^3) account for most of the total waste volume. The Cementation Alternative would result in 1,793 m^3 (63,293 ft^3) of treated TRU wastes, 2,540 m^3 (89,662 ft^3) of remote-handled low-level waste, 2,833 m^3 (100,005 ft^3) of low-level waste, and 3 m^3 (106 ft^3) of mixed low-level waste.

Pollution prevention and waste minimization measures would be implemented. For example, storm water would be diverted around the treatment facility, and gate valves would be installed in the diversion basins, in the event of a spill. The off-gas system would minimize air emissions, and liquid used for the decontamination of the cementation treatment system would be transferred back into the cementation treatment system as waste minimization measures.

The total project duration of the Cementation Alternative is approximately 12.5 years, with 6 years involving waste treatment, during which off-site shipments of treated waste volumes would occur. The Cementation Alternative would require a longer waste treatment time than the other waste treatment alternatives, which would reduce the radiochemical and particulate emissions in a given year. The longer treatment time is the result of the shipment capacity allotment given by the Waste Isolation Pilot Plant to each approved shipper of certified TRU waste. If the shipment allotment from the Waste Isolation Pilot Plant were not a limiting factor, and an assumption was made that the treated waste could be stored at ORNL in the interim, then the sludge and supernate could be treated by the cementation treatment method in 1 or 2 years.

S1.4.5 Treatment and Waste Storage at ORNL Alternative

This alternative analyzes the treatment of the sludge and supernate contained in the Melton Valley Storage Tanks, by either low-temperature drying, vitrification, or cementation. The contact-handled and remote-handled TRU/alpha low-level solid waste currently stored in bunkers, subsurface trenches, and metal buildings would be sorted, segregated, and treated by compaction as described in the previous treatment alternatives. This alternative would include storage of the treated waste at ORNL following waste treatment in the event that off-site waste disposal facilities are not available. DOE intends to ship treated waste offsite for disposal as soon as the waste is treated. However, in the event that disposal capacity is unavailable immediately upon completion of waste treatment, DOE has included the Treatment and Waste Storage at ORNL Alternative to provide safe, interim, on-site storage capacity until off-site disposal capacity becomes available. For purposes of analysis, institutional control is assumed for a period of 100 years, after which there would be a loss of institutional control. Depending upon the selected treatment method, an additional 0.3 to 0.8 ha (0.75 to 2.0 acres) of land would be required for on-site storage of the low-level and TRU waste that would result from the treatment method selected (Table S-1). Implementation of this alternative would result in noncompliance with the milestone established in the TDEC Commissioner's Order requiring the submittal of a Project Management Plan (which includes schedules for treatment and shipment) by September 30, 2001, and would also jeopardize the existing milestone established in the Commissioner's Order that requires the initiation of shipment of the stabilized remote-handled TRU sludges to the Waste Isolation Pilot Plant by January 2003.

It may be possible to use the existing remote-handled TRU waste bunkers for storage of the treated TRU, mixed low-level waste, and remote-handled low-level wastes; however, these two bunkers (Buildings 7855 and 7883) only have a total waste storage capacity of 320 m^3 (11,296 ft^3). It is also assumed that the existing facilities for contact-handled TRU waste, which have a combined capacity of 1,631 m^3 (57,574 ft^3), could be used for treated low-level waste storage. Table S-1 provides a summary of the resulting waste volumes of the three waste treatment alternatives and the space required for the construction of the waste storage facilities. If this alternative were chosen, it is assumed that an engineering analysis would indicate that the existing TRU waste bunkers could be used to store treated remote-handled TRU waste, remote-handled low-level waste, and mixed waste. It is assumed that new waste storage facilities would be located in the Melton Valley area of ORNL, preferably near the waste treatment facility, or the existing TRU waste storage facilities. It was also assumed that the new storage building footprints (including shielding) would be similar to the existing storage facilities, and have a similar waste storage capacity [approximately 150 m^3 (5,295 ft^3) for remote-handle TRU waste, remote-handled low-level waste, and mixed waste, and approximately 300 m^3 (10,590 ft^3) for other waste types].

The schedule for waste treatment for the Treatment and Waste Storage at ORNL Alternative would be similar to the schedule for the treatment alternatives selected (please refer to previous sections for a description of the schedules that would be implemented for waste processing by low-temperature drying, vitrification, or cementation). However, there would be no off-site shipments of treated wastes, only transport to the designated on-site storage facilities. It is assumed that the time needed to construct waste storage facilities would be similar to the time needed to construct the treatment facility (about 2 years).

Table S-1. Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (including D&D waste), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities

	Low-Temperature Drying	Vitrification	Cementation
Table S-1a. Summary of the TRU, mixed low-level, and remote-handled low-level waste volumes and new storage space required			
Treated TRU waste volume (m^3)[a]	607	1,060	1,793
Mixed low-level waste volume (m^3)	23	4	3
Treated remote-handled low-level waste volume (m^3)	–	–	2,540[b]
Total TRU, mixed, and remote-handled low-level waste requiring on-site storage (m^3)	630	1,064	4,336
Existing waste bunkers storage capacity (m^3)	320	320	320
New storage capacity needed (m^3)[c]	310	744	4,016
Assumed capacity of single new waste bunker (m^3)	150	150	150
Number of new waste bunkers needed	3	5	27
Assumed area of new waste bunker (m^2)	234	234	234
Total Storage Facility Area required for TRU, mixed, and remote-handled low-level wastes (m^2)	702	1,161	6,265
Table S-1b. Summary of low-level waste volumes and new storage space required			
Total low-level waste requiring on-site storage (m^3)	2,778[a]	4,983[a]	2,833[a]
Existing storage capacity (metal building)	1,631	1,631	1,631
New storage capacity needed (m^3)[c]	1,147	3,352	1,202
Assumed capacity of single new metal building (m^3)	300	300	300
Number of new metal buildings needed	4	11	4
Area of new metal buildings (m^2)	375	375	375
Total area required for low-level wastes (m^2)	1,434	4,190	1,503
Table S-1c. Total area required for all waste types and the associated land requirements for the new storage facilities			
TOTAL FACILITY SPACE REQUIRED FOR ALL WASTE TYPES (m^2)	**2,136**	**5,351**	**7,768**
TOTAL HECTARES REQUIRED FOR NEW WASTE STORAGE FACILITIES[d]	**0.3**	**0.6**	**0.8**

[a]TRU waste volumes include both remote-handled and contact-handled waste.
[b]Total waste volumes include alpha-low-level waste.
[c]Determined by subtracting available capacity from resulting waste volume and dividing by assumed storage capacity of new facility (150 m^3 for TRU, mixed, and remote-handle low-level wastes, and 300 m^3 for low-level wastes).
[d]Determined by summing storage space required for all waste types, for each treatment method, and converting to hectares.

S1.5 ALTERNATIVES CONSIDERED BUT NOT EVALUATED IN DETAIL

S1.5.1 Off-site Waste Treatment

Currently there is no facility available or planned at any DOE other site that could treat remote-handled TRU mixed waste sludge and the associated low-level waste supernate stored at ORNL. The Idaho National Engineering and Environmental Laboratory (INEEL) is planning to process its contact-handled TRU waste on-site at the planned Advanced Mixed Waste Treatment Project facility. DOE is not currently legally prohibited from shipping waste to the INEEL to be treated so long as the waste is treated and leaves INEEL within a specified time period. However, using the planned INEEL facility to treat ORNL TRU waste would be difficult for the following reasons:

- Because the planned INEEL facility is being constructed to process the contact-handled TRU waste at INEEL, the ORNL remote-handled TRU waste is not likely to meet the planned facility's waste acceptance criteria.

- Most of the ORNL remote-handled and contact-handled TRU/alpha low-level solid waste containers do not meet DOT standards (49 *CFR* 173). These containers would require repackaging prior to transport offsite; therefore, it would be safer and more economical for the treatment of solid waste to be conducted at ORNL, and for the treated TRU waste to be shipped directly to the Waste Isolation Pilot Plant, and the treated low-level waste to be shipped directly to the Nevada Test Site.

- After treatment at INEEL, the ORNL treated waste would require a second redundant step of repackaging and DOE certification before the waste could be transported to the Waste Isolation Pilot Plant or the Nevada Test Site, resulting in additional worker exposures and cost.

Treatment of the ORNL TRU wastes at INEEL is unreasonable because of the increased costs and risks associated with preparing the tank waste for shipment, repackaging and certifying the solid waste twice, transporting the waste to INEEL for treatment, and then transporting the treated waste to the Waste Isolation Pilot Plant or the Nevada Test Site as appropriate.

S1.5.2 Alternate On-site Treatment Facility Locations

Several factors were considered in selecting the site of the proposed on-site treatment facility. These factors are discussed in Section S1.4 and include minimizing the length of any sludge/supernate waste transfer line from the Melton Valley Storage Tanks to the proposed treatment facility, using the terrain to provide natural shielding for the proposed facility, and considering recommendations made in a Feasibility Study that focused on dealing with the tank wastes (Parallax 1995).

The proposed site is directly west of the Melton Valley Storage Tanks, which is the current storage area for the TRU mixed waste sludge and associated low-level supernate. This location reduces the potential risks associated with transporting the liquid and sludge tank wastes from the Melton Valley Storage Tanks to the proposed treatment facility over public or laboratory roads. Since the solid waste storage facilities are also located in Melton Valley, the transportation of the solid wastes would only occur on laboratory roads, also reducing the risk to the public. Melton Valley, while considered part of ORNL, is separated from the ORNL main plant area by the Haw Ridge (Figure S-1), thus reducing potential risks to the main body of workers at ORNL from accidental releases. Alternative site locations were not evaluated in detail because other on-site locations did not meet the siting factors.

S1.5.3 Alternative Disposal Locations

TRU waste will be disposed of at the Waste Isolation Pilot Plant in accordance with the WIPP SEIS-II Record of Decision (DOE 1998a) for TRU waste. The analysis in this EIS assumes that all low-level waste resulting from the ORNL TRU Waste Treatment Facility will be disposed of at the Nevada Test Site, since the waste acceptance criteria would allow disposal of alpha low-level waste. The disposal of any low-level waste generated from this action is consistent with the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

S1.5.4 Alternative Treatment Technologies

Sixteen stabilization and solidification technologies were identified and evaluated as candidates for processing TRU waste sludge in the *Feasibility Study for Processing ORNL Transuranic Waste at Existing and Modified Facilities* (Parallax 1995), but were not analyzed further because they were not considered reasonable (see Chapter 2, Table 2-5). One of the technologies, plasma arc vitrification, was also identified as potentially useful for solid remote-handled and contact-handled TRU/alpha low-level waste. However, it would not be feasible to use a technology for the solid wastes unless it was also used for the sludge and supernate. Because of cost, scaling, and permitting issues, this technology was eliminated from further consideration.

S1.6 AFFECTED ENVIRONMENT

Chapter 3 of this EIS describes the existing environment in and around ORNL, which would be affected by the construction, operation, and D&D of the proposed TRU Waste Treatment Project facility. Site-specific information for the area surrounding the proposed facility site and the adjacent Melton Valley Storage Tanks at ORNL is also included. Current, pertinent information is provided for the Region of Influence for the various resource areas, and the supporting references are cited.

S1.6.1 Land Use

The proposed site is in a forested area immediately west and adjacent to the Melton Valley Storage Tanks and approximately 2 km (1.25 miles) east of Tennessee State Route 95. The Melton Valley Storage Tanks are active waste storage tanks, which store legacy TRU mixed waste sludge and its associated low-level supernate. The area west of the proposed facility site is industrial. The proposed site for the treatment facility does not contain prime or unique farmland. The landscape at the proposed site is a mixture of industrial facilities, roads, and utility buildings and equipment.

S1.6.2 Cultural Resources

The proposed site has no known archaeological, cultural, or historic resources. This has been confirmed by site investigations and by consultation with the State Historic Preservation Officer. However, two pre-1940s home sites—known respectively as the Jenkins and Jones sites—are located within 600 ft of the proposed site location. There are no known areas of historical importance to Native Americans at the proposed project site.

S1.6.3 Ecological Resources

Succession on the fields of former homesteads has produced a relatively young to mid-age open forest of pines and cedars with dominant tree species of shortleaf and Virginia pine, yellow poplar, red

bud, and maples in the vicinity of the proposed project site. Vertebrate fauna at the site include rat snakes, black racers, red-eyed vireos, pine warblers, scarlet tanagers, wild turkey, red-tailed hawks, white-footed mice, coyotes, gray squirrels, flying squirrels, white-tailed deer, skunks, and opossums. There are no Federally-listed terrestrial plant species on the proposed site; the only Federally-listed animal species recently observed on the ORR are the gray bat and the bald eagle, and these are migratory or transient individuals and not permanent residents. The Federally-endangered Indiana bat has not been identified in the project area, but the ORR is within its geographic range.

No Federally-listed aquatic plant species was found in the proposed project site area; however, two Tennessee State-listed wetland species, the purple fringeless orchid and the river bulrush, may be present in wetlands adjacent to the proposed site. The only Tennessee State-listed aquatic-related fauna is the osprey, which is a common nester in Melton Valley. The Federally-endangered pink mucket pearly mussel is unlikely to be present in or near the proposed facility area because there is no suitable habitat.

S1.6.4 Geology and Seismicity

The ORR is located in the Tennessee Section of the Valley and Ridge physiographic province. The Conasauga Group underlies the Melton Valley, and the proposed project site would be situated over the Cambrian-age Nolichucky Shale. Tectonic activity has produced extensive fracturing and localized folding of bedrock units. Soil contamination exists in many locations in the Melton Valley area of ORNL, which is heavily used for waste storage.

The ORR is located in Seismic Zone 2, where the probability of seismic damage is moderate.

S1.6.5 Water and Water Quality

The proposed project site is within the Melton Valley Watershed portion of the White Oak Creek Watershed, which has a drainage area of 6.15 square miles. Although there are no permanent water bodies within the site boundary, two perennial streams (White Oak Creek and Melton Branch) and an unnamed tributary to White Oak Creek, and one lake (White Oak lake) would be close to the proposed facility.

Surface water from White Oak Creek, White Oak Lake, and Melton Branch contains elevated levels of radionuclides, mercury, and polychlorinated biphenyls (PCBs) relative to reference streams. However, overall water quality is good, such that no toxicity to aquatic organisms had been observed for several years and the toxicity testing was discontinued in 1997.

Groundwater is being contaminated from wastes in the unlined trenches at SWSA 5 North. According to the *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge, Tennessee* (DOE 1997f), these unlined trenches at SWSA 5 North are estimated to contain 14,000 curies and contribute about 6% of the total strontium-90 and 3.6% of the cesium-137 released to surface water in Melton Valley. The rate of release of radioactive constituents will likely reduce with respect to time because of radioactive decay. The contaminated soils around the underground trenches, and between the trenches and White Oak Creek, will also act as a secondary source of contamination to groundwater. Well samples taken adjacent to the SWSA 5 North trenches also showed elevated levels of americium-241 and curium-244 ranging as high as 5,940 pCi/L.

There are six wetlands within 0.8 km (0.5 miles) of the proposed TRU Waste Treatment Facility. The 100-year and 500-year floodplains associated with White Oak Creek are immediately north of the

proposed site, but the site is not within a floodplain: therefore, a floodplain assessment under 10 *CFR* 1022 is not required.

S1.6.6 Waste Management

The estimated waste volumes associated with CERCLA cleanup actions for the ORR range between 170,506 m^3 and 841,060 m^3 (223,000 to 1.1 million yd^3). Remote-handled TRU sludge will no longer be generated at ORNL after FY 2000, but approximately 5.5 m^3 of remote-handled TRU waste would be generated annually at the Radiological Engineering Development Center at ORNL.

S1.6.7 Climate and Air Quality

The proposed facility is in an air quality control region, which is an attainment area for all criteria pollutants. ORR and ORNL are in compliance with all federal air regulations and TDEC air-permit requirements for non-radioactive hazardous air pollutants. The ORR is within a Class II prevention of significant deterioration area. Prevailing winds in the area are up-valley in the daytime and down-valley at night.

S1.6.8 Transportation

Transportation corridors in the region and immediately adjacent to the ORR boundary consist of local access roads such as Tennessee State Routes 95, 1700, and 62, and Interstates I-40 and I-75. The Old Melton Valley Road provides direct access from Tennessee State Route 95 to the proposed site. This road has been upgraded under a categorical exclusion (CX) and additional information on the CX can be found in Section 5.3.2 and Appendix E.

S1.6.9 Utility Requirements

The Tennessee Valley Authority provides electric power to the ORR, which has a current site load of 166 megawatts (MW). Water is supplied to ORNL by the City of Oak Ridge Water Treatment Facility, which draws water from the Clinch River.

S1.6.10 Human Health

The calculated doses to the off-site (public) maximally exposed individual at ORNL and ORR are shown in Table S-2 (ORNL 1998). Airborne releases of radionuclides for the ORNL maximally exposed individual in 1997 resulted in a probability of cancer fatality of 2E-07. ORNL contributed about 58% of the ORR collective effective dose equivalent, or about 5.8 person-rem for the population, which corresponds to a Latent Cancer Fatality (LCF) of 3E-03 annually. For airborne releases the estimated probability of cancer fatality for the maximally exposed individual at ORR in 1997 was 2E-07, and the LCF for the collective population was 5E-03 annually.

Table S-2. Calculated effective dose equivalent to the maximally exposed off-site individual and the collective population effective dose equivalent from airborne releases of radionuclides in 1997 (ORNL 1998)

Location	Effective dose equivalent to a maximally exposed individual (mrem)	Probability of cancer fatality for the maximally exposed individual	Collective population effective dose equivalent (person-rem)	Latent cancer fatalities for collective population
ORNL	0.38	2E-07	5.8	3E-03
ORR	0.41	2E-07	10.0	5E-03

Doses from ingestion of fish contaminated from the Clinch River are estimated at 0.045 mrem (effective dose equivalent) for a maximally exposed individual, which would result in the probability of a cancer fatality of 2.3E-08. The collective population dose is 0.017 person-rem, which would result in an LCF of 8.5E-06. A fisherman spending 250 hours per year along the bank of the Clinch River would receive a dose from direct radiation of 1 mrem, which would result in a probability of a cancer fatality of 5E-07.

External exposure rates from background sources in Tennessee average about 6.4 microroentgens per hour (μR/hour) and range from 2.9 to 11 μR/hour. These exposure rates are equivalent to an average annual effective dose equivalent of 56 mrem/year and range from 25 to 96 mrem/year. The total average dose due to background radiation received by an individual in the United States each year, including the 56 mrem, is about 300 mrem.

Operations at ORNL result in the release of small quantities of chemicals (National Ambient Air Quality Standards criteria pollutants) to the atmosphere. A steam plant and two small, oil-fired boilers are the largest emission sources and account for 98% of all allowable emissions at ORNL. Data for these non-radiological sources are presented in Table 3-17 of this EIS.

S1.6.10 Accidents

The total recorded injuries at ORNL for 1999 were 170 or 4.65 per 100 full-time employees working one year.

S1.6.11 Noise

The results of a noise survey conducted at the site for the proposed treatment facility in July 1999 indicated the area was relatively quiet. Daily equivalent noise levels ranged from 50 to 70 dBA and were highest when the Old Melton Valley Road was under construction. A secondary night-time noise peak reflected wildlife noises.

S1.6.12 Socioeconomics

Approximately 7,500 people reside within 8 km (5 miles) of the center of the proposed project site, and 880,000 people reside within 80 km (50 miles) of the proposed facility. Total regional income in 1996 was $12.0 billion.

S1.6.13 Minority and Low-income Populations

Oak Ridge City census tracts in 1990 indicated a 10% or less African-American population, with the exception of one tract, which had a 34.4% African-American population. These values compare to an African-American population of 24.1% nationally and 17% for the State of Tennessee. There are

two census tracts with low-income populations exceeding both the national average and the Tennessee state average. There are no federally recognized Native American groups within 80 km (50 miles) of the proposed site.

S1.7 ENVIRONMENTAL CONSEQUENCES

Table S-3 provides a summary of the potential environmental impacts associated with implementing the alternatives, and allows a comparison of the alternatives. Acronyms used in this summary table are defined on the pages on which they appear. All impacts are expected to be small. The primary differences among alternatives are in potential impacts to water resources, the volume of waste generated, the number of transportation shipments and associated accidents, and utility requirements.

Table S-3. Comparison of impacts among alternatives

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Land use (Chapter 4, Section 4.1)	• No change in land use, land use classifications, or impacts to visual resources during 100-year institutional control period • Assuming loss of institutional control, the land would be permanently committed to waste storage	• No change in land use classification • 2 hectares (ha) (5 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 to 2.8 ha (5 to 7 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 ha (5 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 to 2.8 ha (5 to 7 acres) would change from underdeveloped to industrial use • For waste storage after treatment, an additional 0.3 ha (0.75 acre) of land would be required if treatment was by low-temperature drying, 0.6 ha (1.5 acres) of land if by vitrification, or 0.8 ha (2.0 acres) of land if by cementation • Buildings and other structures would be visible to workers but not the public • Assuming loss of institutional control, the land would be permanently committed to waste storage
Cultural and historic resources (Chapter 4, Section 4.2)	• No cultural, archeological, or historic resources in project area	• Same as No Action Alternative	• Same as No Action Alternative	• Same as No Action Alternative	• Same as No Action Alternative

ha = hectare.
ORNL = Oak Ridge National Laboratory.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Ecological resources (Chapter 4, Section 4.3)	• Continued release of waste constituents from SWSA 5 North trenches to soils and groundwater affecting biota • No habitat destruction under continued storage • Minimal impact (HQ for aquatic biota at steady-state would be 7×10^{-7}) from slow release of MVSTs wastes after loss of institutional control • Assuming loss of institutional control, wastes from SWSA 5 North trenches, bunkers, and buildings would serve as long-term contaminant sources	• 2 ha (5 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• 2 to 2.8 ha (5 to 7 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• 2 ha (5 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from trenches SWSA 5 North under CERCLA	• 2 to 2.8 ha (5 to 7 acres) of forested habitat lost and converted to industrial use • Low-quality habitat indefinitely lost for on-site waste storage facility construction; 0.3 ha (0.75 acre) of land required if treatment by low-temperature drying, 0.6 ha (1.5 acres) of land if by vitrification, and 0.8 ha (2.0 acres) of land if by cementation • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA • Assuming loss of institutional control, waste constituents would eventually be released but impacts would be less than No Action because the wastes are treated and better contained

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
D&D = decontamination and decommissioning.
ha = hectare.
HQ = hazard quotient.
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Geology and seismicity (Chapter 4, Section 4.4)	• No impact to geology or regional seismicity • No construction-related impacts to soils or geology • Continued release of waste constituents from the SWSA 5 North trenches to soils during and after loss of institutional control • Eventual release of wastes from MVSTs and SWSA 5 North bunkers and building into soils after loss of institutional control	• No impact to geology or regional seismicity • 2 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2.8 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2 to 2.8 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA • Eventual release of constituents from treated wastes after loss of institutional control

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
ha = hectare.
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Surface water (Chapter 4, Section 4.5.1)	• Continued release of waste constituents from the SWSA 5 North trenches to surface water during and after loss of institutional control • Eventual release of long-lived radionuclides from MVSTs and SWSA 5 North bunkers and buildings into surface water after loss of institutional control	• Potential for increased siltation in White Oak Creek, Melton Branch, and an unnamed tributary • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative for period of institutional control • After loss of institutional control, waste constituents would eventually be released but impacts would be less than No Action because wastes are treated and better contained
Groundwater (Chapter 4, Section 4.5.2)	• No groundwater use • Continued release of waste constituents from SWSA 5 North trenches during and after loss of institutional control • Eventual release of wastes from MVSTs and SWSA 5 North bunkers, buildings, and trenches into groundwater after loss of institutional control	• No groundwater use • Positively impacts groundwater due to waste removal and treatment of waste from SWSA 5 North trenches	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative • Eventual release of constituents after loss of institutional control, but impacts would be less than No Action because wastes are treated and better contained

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Wetlands & Floodplains (Chapter 4, Section 4.5.3)	• Continued impacts to White Oak Creek floodplain due to SWSA 5 North contamination • No impact to wetlands during institutional control • After loss of institutional control wastes would eventually contaminate wetlands • After loss of institutional control wastes continue to impact floodplains	• Small impact from sedimentation to the 100-year or 500-year floodplains during construction phase • Wetland B (0.012 ha or 0.03 acres) would be eliminated by construction, but will be mitigated	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during institutional control • Eventual release of treated waste constituents after loss of institutional control

ha = hectare.
ORNL = Oak Ridge National Laboratory.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Waste Management (Chapter 4, Section 4.6)	• TRU sludge wastes and associated low-level supernate in the MVSTs solid wastes in SWSA 5 North trenches, and solid waste in storage facilities would remain untreated • Would require continued surveillance and maintenance of untreated legacy waste inventory and associated on-site facilities indefinitely at ORNL • Would result in violation of legal mandate due to continued waste storage, potentially resulting in fines	• All legacy wastes in proposed action would be treated • Approximately 10,833 m^3 of total generated waste, including: - 607 m^3 CH and RH TRU waste; - 2,778 m^3 low-level waste; - 23 m^3 of low-level mixed waste; - 1,560 m^3 of sanitary wastewater; and - 5,550 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative • Approximately 34,128 m^3 of total waste generated, including: - 1,060 m^3 CH and RH TRU waste; - 4,980 m^3 low-level waste; - 4 m^3 of low-level mixed waste; - 7,201 m^3 of sanitary wastewater; and - 20,760 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative - Approximately 28,826 m^3 of total waste generated, including: - 1,793 m^3 CH and RH TRU waste; - 2,833 m^3 low-level waste; - 2,540 m^3 of remote-handled low-level waste; - 3 m^3 of low-level mixed waste; - 7,437 m^3 of sanitary wastewater; and - 14,143 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative • 10,833 to 34,128 m^3 of waste generated, depending on the treatment selected, and stored on-site • Would require continued surveillance and maintenance of waste inventory for interim onsite storage at ORNL • Would require construction of additional waste storage facilities—using 0.3 to 0.8 ha of land depending upon treatment process selected

CH = contact-handled.
D&D = decontamination and decommissioning.
m^3 = cubic meters.
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory.
RH = remote-handled.
SWSA 5 North = Solid Waste Storage Area 5 North.
TRU = transuranic.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Climate and Air Quality (Chapter 4, Section 4.7)	• No impact to air quality	• Minor emissions during normal operations; slightly higher volatile organic emissions	• Minor emissions during normal operations; slightly higher nitrogen dioxide emissions	• Minor emissions during normal operations; slightly higher particulate emissions.	• Minor emissions during normal operations
Transportation (Chapter 4, Section 4.8)	**On-site Retrieval and Transport** • No on-site waste shipments	**On-site Retrieval and Transport** • 300 shipments of RH waste from trenches and bunkers, and 245 shipments of CH waste to treatment facility • Retrieval accidents could result in 6.3E-05 LCFs (public) and 7.5E-04 industrial fatalities to involved workers • Transportation accidents could result in 2.9E-05 LCF (public) and 3.3E-05 non-radiological fatalities • Total risks to non-involved workers and public MEI are 5.3E-07 and 6.2E-09 probability of cancer fatality, respectively • 8.0E-03 LCF (involved worker (based on 1 rem/year assumed dose limit)	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative for retrieval accidents and radiological transportation accidents • 3,339 shipments of treated waste to storage facility (using Cementation process as bounding case) • 2.0E-04 transportation related fatalities • 3.4E-04 construction fatalities (involved workers) • 2.5E-03 loading and unloading accident fatalities (involved workers)

CH = contact-handled.
LCFs = latent cancer fatalities.
MEI = maximally exposed individual.
ORNL = Oak Ridge National Laboratory.
RH = remote-handled.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Transportation (continued) (Chapter 4, Section 4.8)	**Off-site Transport** • No off-site shipments	**Off-site Transport** • 397 shipments of TRU waste with 3.2E-01 accidents and 4.4E-02 fatalities predicted • Non-accident LCFs of 8.7E-03 for CH TRU and 3.1E-02 for RH TRU waste • 277 low-level waste shipments with 2.6E-01 accidents and 3.6E-02 accident fatalities predicted • 2.1E-09 non-accident LCFs predicted	**Off-site Transport** • 989 shipments of TRU waste with 8.0E-01 accidents and 1.1E-01 fatalities predicted • Non-accident LCFs of 5.3E-03 for CH TRU and 9.3E-02 for RH TRU waste • 281 low-level waste shipments with 2.6E-01 accidents and 3.6E-02 accident fatalities • 2.1E-09 non-accident LCFs predicted	**Off-site Transport** • 2,425 shipments of TRU waste with 2.2 accidents and 3.0E-01 fatalities predicted • Non-accident LCFs of 5.3E-03 for CH TRU and 2.7E-01 for RH TRU waste • 914 low-level waste shipments with 8.8E-01 accidents and 1.2E-01 accident fatalities predicted • 7.5E-09 non-accident LCFs predicted	**Off-site Transport** • No off-site shipment of TRU waste or low-level waste

CH = contact-handled.
LCFs = latent cancer fatalities.
ORNL = Oak Ridge National Laboratory.
RH = remote-handled.
TRU = transuranic.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Utility Requirements (Chapter 4, Section 4.9)	• Total estimated power usage 2,200 MW • 5 million gallons of water use projected over 100-year institutional control period	• About 15,000 MW of total electricity usage • 5 million gallons of water use during project life	• About 45,000 MW of total electricity usage • 7 million gallons of water use during project life	• About 11,250 MW of total electricity usage • 15 million gallons of water use during project life	• Electricity use varies by alternative from 13,450 MW to 47,200 MW total, which includes electricity use for interim storage • Water use varies by alternative (10 million to 20 million gallons), which includes water use for interim storage
Human Health (Chapter 4, Section 4.10)	• LCFs for involved worker population estimated to be 2E-02 • Risk to public and non-involved worker would be negligible during institutional control period • After loss of institutional control, higher risks to public from contaminated surface water, groundwater, and food supplies	• PCF from radiological releases to involved worker estimated to be 3.0E-08; non-involved worker estimated to be 2.0E-08; and off-site MEI estimated to be 1.0E-08 • Collective dose to the affected off-site public population would be 1.2E-01 person-rem, resulting in 6.0E-05 LCFs	• PCF from radiological releases to involved worker estimated to be 9.0E-08; non-involved workers estimated to be 7.0E-08; off-site MEI estimated to be 5.0E-08 • Collective dose to the affected off-site public population would be 6.8E-01 person-rem, resulting in 3.0E-04 LCFs	• PCF from radiological releases to involved worker estimated to be 6.0E-09; non-involved workers estimated to be 5.0E-09; and off-site MEI estimated at 3.0E-09 • Collective dose to the affected off-site public population would be 2.8E-02 person-rem, resulting in 1.0E-05 LCFs	• LCF for involved worker population estimated to be 2E-02 • PCF for the non-involved worker and off-site MEI would be equal to that estimated for the treatment technology selected • Collective dose and number of fatalities for the affected off-site population would be equal to that for the treatment technology selected • After loss of institutional control, higher risks to public from contaminated surface water, groundwater, and food supplies, but less risk than No Action Alternative since wastes are treated and better contained

LCFs = latent cancer fatalities.
MEI = maximally exposed individual.
MW = megawatt(s)
ORNL = Oak Ridge National Laboratory
PCF = probability of cancer fatality

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Noise (Chapter 4, Section 4.12)	• Noise levels at 50 to 60 dBA	• Site construction and D&D noise up to 70 dBA • Noise levels during operations at 50 to 60 dBA • Noise increases are temporary and minor	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during treatment and would decrease, similar to the levels of No Action, during interim storage

dBA = decibels as recorded on the A-weighted scale of a standard sound level meter.
D&D = decontamination and decommissioning.
ORNL = Oak Ridge National Laboratory.

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Accidents (Chapter 4, Section 4.11)	• **MVSTs Breach**[1] · MEI – 1.1E-05 PCF · Population – 1.1 LCF during institutional control and 11 LCF after loss of institutional control · Non-involved workers – 9.2E-04 PCF • **Vehicle impact (CH TRU and RH TRU waste)**[3] · MEI – 1.6E-06 PCF · Population – 0.024 LCF · Non-involved workers – 1.3E-04 PCF • **Earthquake**[4] · MEI – 1.6E-05 PCF · Population – 0.24 LCF · Non-involved workers – 1.4E-03 PCF • **Vehicle impact/fire (CH TRU and RH TRU waste)**[5] · MEI – 1.4E-07 PCF · Population – 2.1E-03 LCF · Non-involved workers – 1.2E-05 PCF	• **MVSTs Breach**[1] - NA • **MVSTs transfer line failure**[2] · MEI – 3.2E-06 PCF · Population – 0.16 LCF · Non-involved workers – 2.8E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake**[4] · MEI – 4.8E-07 PCF · Population – 7.2E-03 LCF · Non-involved workers – 4.2E-05 PCF • **Vehicle impact/fire**[5] - negligible	• Same as Low-Temperature Drying Alternative	• **MVSTs Breach**[1] - NA • **MVSTs transfer line failure**[2] · MEI – 6.3E-06 PCF · Population – 0.31 LCF · Non-involved workers – 5.5E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake**[4] · MEI – 9.6E-07 PCF · Population – 0.014 LCF · Non-involved workers – 8.4E-05 PCF	• **MVSTs transfer line failure**[2] · MEI – 3.2E-06 to 6.6E-06 PCF · Population – 0.16 to 0.31 LCF · Non-involved workers – 2.8E-04 to 5.5E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake (CH TRU and RH TRU waste)**[4] · MEI – 4.8E-07 to 9.6E-07 PCF · Population – 7.2E-03 to 1.4E-02 LCF · Non-involved workers – 4.2E-05 to 8.4E-05 PCF • **Vehicle impact/fire (after processing)**[6] · MEI – 1.4E-07 PCF · Population – 2.1E-03 LCF · Non-involved workers – 1.2E-05 PCF

CH = contact-handled.
LCFs = latent cancer fatalities.
MEI = maximally exposed individual.
MVSTs = Melton Valley Storage Tanks
NA = not applicable.
ORNL = Oak Ridge National Laboratory
PCF = probability of cancer fatality.
RH = remote-handled.
TRU = transuranic.

[1]Melton Valley Storage Tanks (MVSTs) breach accident would be initiated by an earthquake with a 50,000-gallon release to the environment.

[2]MVSTs transfer line failure accident assumes the line between the MVSTs and the treatment facility fails during waste transfer operations.

[3]Vehicle impact (CH TRU and RH TRU waste) accident assumes a forklift breaches a package of solid waste.

[4]Earthquake accident assumes that packages of solid waste fall causing the packages to breach.

[5]Vehicle impact/fire (CH TRU and RH TRU) accident assumes a vehicle accident resulting in breach of the waste package and an ignition of the vehicle fuel that results in burning of the wastes.

[6]Vehicle impact/fire (after processing) accident assumes a vehicle accident resulting in breach of the waste package and an ignition of the vehicle fuel that results in burning of the treated wastes (only applies following Low-Temperature Drying Alternative with assumed combustible macroencapsulant).

Table S-3. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Socioeconomic (Chapter 4, Section 4.13)	• No change in economic activity	• No significant impacts • Earnings represent 0.1% of the income for the region	• No significant impacts • Earnings represent 0.2% of the income for the region	• No significant impacts • Earnings represent 0.1% of the income for the region	• No significant impacts • Earnings represent 0.1% of the income for the region
Environmental Justice (Chapter 4, Section 4.14)	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations

ORNL = Oak Ridge National Laboratory.

S1.8 CUMULATIVE IMPACTS

The evaluation of cumulative impacts couples impacts of the proposed action and, where appropriate, the bounding alternative for each resource area, with impacts from other past, present, and reasonably foreseeable future actions.

The proposed action would be consistent with the existing industrial land use classification in Melton Valley. The cumulative impact on land use would be small because only 3.4 ha (8.4 acres) would be developed for the treatment and storage facilities (based on the Treatment and Waste Storage at ORNL Alternative, using vitrification as the treatment technology for the bounding case). Construction and operation of a vitrification treatment facility would only result in 2.8 ha (7 acres) of forested land disturbed for a period of at least a decade, thereby resulting in a small incremental increase in the loss of habitat in the lower reaches of Melton Valley.

Cumulatively, impacts to water resources in the White Oak Creek Watershed are expected to be mostly beneficial. The proposed action would augment several ongoing CERCLA actions in the watershed designed to reduce strontium-90 and other contamination in groundwater and in the soil. By implementing the proposed action, waste in the SWSA 5 North trenches would be treated. Sedimentation that could occur from the proposed action would be small and would help renew ongoing sediment depletions in the White Oak Embayment; sedimentation is beneficial because it provides shielding. However, a 0.016-ha (0.03-acre) wetland on the proposed project site eastern boundary is expected to be eliminated by construction.

There are 65 ha (160 acres) of land in Melton Valley devoted to waste storage and operation (DOE 1997b). For the Treatment and Waste Storage at ORNL Alternative, additional on-site storage space up to 0.8 ha (2 acres) would be required using cementation as the bounding alternative. Given the extensive area already devoted to waste storage in Melton Valley, this would not be cumulatively significant.

Ongoing and future projects involving ground disturbance activities that would likely result in fugitive dust emissions include the proposed Spallation Neutron Source. There should not be a direct cumulative impact to air quality from fugitive dust emissions from the proposed action; however, deposition of particulates from the proposed action, combined with emissions from the Spallation Neutron Source, could indirectly affect vegetation by coating leaves with dust.

The Toxic Substances Control Act (TSCA) Incinerator at the ETTP, the Bull Run Steam Plant 8 km (5 miles) east of ORNL, and the Kingston Steam Plant [approximately 48 km (30 miles) northwest of ORNL] near Kingston, Tennessee, are major atmospheric emission sources in the region which affect the air quality at ORNL. The TSCA Incinerator is a source of radionuclide emissions at the ETTP. All action alternatives considered for the proposed action would contribute a small amount to the overall emissions in the air shed.

The transportation of TRU Waste Treatment Project waste would be a subset of the total volume of waste evaluated in the DOE WM PEIS. At ORR, the DOE WM PEIS estimated that transport of all waste types would result in 8.1E-04 accidents per shipment and 1.1E-04 fatalities per shipment (DOE 1997d). For the proposed action, the greatest number of waste shipments would occur under the Cementation Alternative (2,425 shipments of TRU and 914 shipments of low-level waste), which represents the bounding alternative. Under the Cementation Alternative, the TRU waste shipments are estimated to result in 2.2 accidents and 3.0E-01 fatalities.

Regarding human health risk, all action alternatives would eventually result in reducing long-term exposure to chemical and radiological contaminants; however, during the treatment and repackaging effort, some minor process air emissions and resulting risks to humans would occur. The bounding alternative for this resource area, the Vitrification Alternative, would contribute 6.8E-01 person-rem to the affected population and a corresponding 3E-04 LCFs risk to that population. Cumulatively, this risk, combined with existing risks and risks from the Spallation Neutron Source Project, would result in 3.1E-01 LCFs.

The proposed TRU Waste Treatment Project would contribute very little additional employment, and the project's contribution to cumulative socioeconomics impacts would be very small.

S1.9 MITIGATION

Several best management practices are identified as mitigation measures. These practices include erosion and dust control measures, covering open truck beds during hauling, minimizing time that vehicles idle, and periodic vehicle inspections.

A 0.016-ha (0.03-acre) wetland on the proposed project site is expected to be eliminated by construction. Potential mitigation measures include avoidance, minimization, or compensation. Redesigning the layout of the TRU Waste Treatment Facility could potentially avoid or minimize impact to this wetland. Should this not be practical, then compensatory mitigation, such as new wetland construction, would be done. For example, redesign of the sediment/storm water detention basin could result in a constructed wetland. Mitigation measures to achieve no net loss of wetlands will be in a Mitigation Action Plan provided to state regulations.

S1.10 UNAVOIDABLE ADVERSE IMPACTS AND IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES

Despite mitigation measures, there would be some small, but unavoidable adverse impacts resulting from the implementation of the proposed action. Depending on the treatment process, 2 to 2.8 ha (5 to 7 acres) of forested land would be used for construction of the proposed waste treatment facility, resulting in the loss of this habitat by plants and animals for a period of at least a decade (Sections 4.1 and 4.3). The area would be revegetated after closure and D&D of the facility.

Approximately 0.8 ha (2 acres) of land would be required indefinitely for the waste storage facilities if the Treatment and Waste Storage at ORNL Alternative is implemented. Land indefinitely committed as storage space would be approximately 0.3 ha (0.75 acres) for the low-temperature drying treatment, 0.6 ha (1.5 acres) for the vitrification treatment, or 0.8 ha (2.0 acres) for the cementation treatment (Section 4.1). This would constitute an irreversible and irretrievable commitment of land. There would, however, be no loss of federally-protected threatened or endangered species or critical habitat (Section 4.5.3). The proposed action would also involve the irreversible or irretrievable commitment of energy and materials. Approximately 11,250 to 45,000 MW of electrical energy would be committed and consumed depending on the alternative selected (Section 4.9).

S1.11 APPLICABLE LAWS AND REGULATIONS

A number of laws, regulations, and agreements would apply to the Proposed Action. These are discussed in detail in Chapter 8, and some highly relevant ones are summarized here.

RCRA, as amended (42 U.S.C. §6901 et seq.), regulates the treatment, storage, and disposal of hazardous wastes. Regulation is by permit, meaning that the State of Tennessee studies the alternative chosen by DOE and then establishes a permit specific to the project that describes how the project is to be carried out. Whether DOE chooses the No Action Alternative, or any other alternative under consideration in this EIS, some type of RCRA permit will be required. Selection of any of the action alternatives would require a RCRA permit to treat and store the waste. The LDR standards would be addressed though the TDEC Commissioner's Order (dated September 1995).

Under the TDEC Commissioner's Order, DOE is required to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and shipment of ORNL's mixed TRU waste. The primary milestone in the Commissioner's Order is that DOE begin treating legacy TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant (a DOE transuranic waste disposal facility) in New Mexico by January 2003. If the No Action Alternative were selected, DOE is potentially subject to fines and penalties due to non-compliance with the Tennessee Commissioner's Order, which requires treatment and shipment offsite of the TRU waste. Should the Treatment and Waste Storage at ORNL Alternative be undertaken, modification of the Commissioner's Order would be required, as the Order requires wastes to be treated and shipped. In addition, new storage units could be required in order to accommodate increasing volumes of stored wastes.

CERCLA, as amended (42 U.S.C. §9601 et seq.), is the authority under which the TRU wastes currently stored in the SWSA 5 North trenches would be removed. After removal of the waste from the SWSA 5 North trenches, residual contamination in the surrounding media (soils and groundwater) may still need to be addressed under a subsequent CERCLA action. In addition, from a cumulative impacts perspective, the proposed action would assist the CERCLA cleanup at Melton Valley, which is a watershed to be remediated under the FFA (see Section 8.2).

The Endangered Species Act of 1973, as amended (16 U.S.C. 1931 et seq.) is important since three Federally-listed endangered species (gray bat, Indiana bat, and pink mucket pearly mussel) are known to occur near the project area. Informal consultations are ongoing with the U.S. Fish and Wildlife Service on these species.

S1.12 REFERENCES

DOE 1997a. *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS-II), DOE/EIS-0026-S-2, U.S. Department of Energy, Washington, D.C., September 1997.

DOE 1997b. *Draft Record of Decision for the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1826&D1.

DOE 1997c. *Record of Decision for Interim Action: Sludge Removal from the Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/OR2-1591&D3, August 1997.

DOE 1997d. *Action Memorandum for the Old Hydrofracture Facility Tanks and Impoundment, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1751&D3.

DOE 1997e. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (WM PEIS), DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1997f. *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee, Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1576/V1&V2, May 1997.

DOE 1998a. *WIPP SEIS-II, Record of Decision for the Department of Energy's Waste Isolation Pilot Plant Disposal Phase, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3624–3629.

DOE 1998b. *WM PEIS, Record of Decision for the Department of Energy's Waste Management Program: Treatment and Storage of Transuranic Waste, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3629–3633.

DOE 1999. *Implementation Guide for Use with DOE M 435.1-1*, DOE G 435.1-1, July 1999.

DOE 2000. *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-Level and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site, Federal Register*, Vol. 65, No. 38, 10061–10066, February 25, 2000.

ORNL 1998. *Oak Ridge Reservation Site Environmental Report for 1997*, ES/EH-78, Oak Ridge, Tennessee, October 1998.

Parallax, Inc. 1995. *Feasibility Study for Processing ORNL Transuranic Waste in Existing and Modified Facilities, Oak Ridge, Tennessee*, ORNL/M-4693, September 15, 1995.

THIS PAGE INTENTIONALLY LEFT BLANK

1. INTRODUCTION AND BACKGROUND

1.1 INTRODUCTION

U.S. Department of Energy (DOE) facilities have performed nuclear energy research and radiochemical production since the early 1940s. The Oak Ridge Reservation (ORR) encompasses 13,974 contiguous hectares (ha) (34,516 acres) owned by the DOE in the Oak Ridge, Tennessee, area. The Y-12 Plant, the East Tennessee Technology Park (ETTP), and the Oak Ridge National Laboratory (ORNL) are major DOE facilities within the ORR.

ORNL was constructed during World War II as a pilot-scale plant to support nuclear energy research and the construction of larger plutonium production facilities at Hanford, Washington. ORNL is located on approximately 1,174 ha (2,900 acres), 40 km (25 miles) northwest of the City of Knoxville, in eastern Tennessee (Figure 1-1). The site is located in a water-rich environment that contains numerous small tributaries that flow into the Clinch River located south and west of the site. ORNL is located in the Tennessee Valley between the Great Smoky Mountains (located approximately 80 km or 50 miles east) and the Cumberland Plateau (about 45 km or 25 miles west).




Figure 1-1. Location of Oak Ridge National Laboratory in relation to the City of Oak Ridge, other DOE facilities in the area, and the State of Tennessee.

ORNL continues to be used for DOE operations and is internationally known as a premier research facility. Research and development activities support national defense and energy initiatives. Ongoing waste management and environmental management activities continue to address legacy[1] and newly generated low-level radioactive[2], transuranic (TRU)[3], and hazardous wastes resulting from research and development activities. As the ORR is on the National Priorities List, meeting the cleanup challenges at the site, including those associated with legacy wastes at ORNL, is a high priority for the DOE Oak Ridge Operations (ORO), the Tennessee Department of Environment and Conservation (TDEC), U.S. Environmental Protection Agency (EPA), and stakeholders. The treatment and disposal of legacy TRU waste at ORNL is an important component of the DOE cleanup at the site. Currently, no facilities exist at ORNL, or the ORR, for treating TRU mixed waste[4] sludges and associated low-level waste supernate, and contact-handled[5] and remote-handled[6] TRU/alpha low-level[7] waste solids, before disposal.

1.2 BACKGROUND

During early research activities, little was known about the effects of exposure to radiation and other hazardous substances. Waste management practices changed as the hazards were better understood. Wastes generated from research and development activities and isotope production were managed with the best available practices at the time. Liquid radioactive waste was stored in underground storage tanks. Lower activity liquid waste was transferred to ponds for storage and settling before release into White Oak Creek. Contaminated solid waste was buried in pits and trenches.

1.2.1 Waste Types

Legacy waste stored at ORNL resulted from past isotope production, and from research and development activities at DOE facilities. The four legacy waste types that would be treated under the proposed action are remote-handled TRU mixed waste sludge, low-level radioactive waste supernate (liquid portion) associated with the TRU sludge waste, contact-handled TRU/alpha low-level waste solids, and remote-handled TRU/alpha low-level waste solids. Much of the sludge waste contains metals regulated under the Resource Conservation and Recovery Act (RCRA) and, therefore, may be classified as mixed waste. ORNL currently has the largest inventory of remote-handled TRU waste in the DOE complex and a smaller portion of the contact-handled TRU waste.

Supernate, the liquid portion of the waste stored in the underground storage tanks at ORNL, is generally characterized as low-level waste. Sludge waste, found on the bottoms of the underground

---

[1]Legacy waste is defined as waste generated from past isotope production and research and development activities.

[2]Low-level waste is defined as any radioactive waste not classified as high-level, spent nuclear fuel TRU, by-product material, or mixed waste [based on *Implementation Guide for Use with DOE M 435.1-1*, DOE G 435.1-1, July 1999 (DOE 1999a)].

[3]TRU waste is waste not classified as high-level radioactive waste but as waste which contains more than 100 nanocuries per gram (nCi/g) of alpha-emitting TRU isotopes (atomic numbers greater than 92) with half-lives greater than 20 years (based on DOE 1999a).

[4]Mixed waste is a waste that contains radioactive waste regulated under the Atomic Energy Act of 1954 as amended, and a hazardous component subject to the Resource Conservation and Recovery Act (based on DOE 1999a).

[5]Contact-handled TRU waste contains beta- and gamma-emitting isotopes in addition to alpha-emitting isotopes, with a surface dose rate of 200 millirem per hour (mrem/h) or less [*Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS-II), DOE/EIS-0026-S-2, "Glossary," p. GL-3 (DOE 1997a)].

[6]Remote-handled TRU waste contains beta- and gamma-emitting isotopes in addition to alpha-emitting isotopes, with a surface dose rate greater than 200 mrem/h [WIPP SEIS-II, "Glossary," p. GL-14 (DOE 1997a)].

[7]Alpha low-level radioactive waste is low-level waste that contains alpha-emitting isotopes.

storage tanks, formed from precipitants that settled out of the supernate during waste storage. The sludge waste has been characterized as TRU mixed waste.

The solid waste at ORNL is a heterogeneous mixture consisting of paper, glass, rubber, cloth, plastic, and metal from glove boxes, fuel processing, hot cells, and reactors. Based on generator records, the solid waste has been classified as either TRU or alpha low-level radioactive waste. Because the nature of the solid waste can only be confirmed after retrieval and characterization, solid wastes were characterized as "TRU/alpha low-level radioactive waste" in the Notice of Intent to note the current uncertainty. The solid waste may contain metals regulated under RCRA, but generator records do not indicate the presence of any RCRA-listed constituents.

1.2.2 Waste Storage at ORNL

The legacy TRU waste is in the form of sludge, which is currently stored in aging, underground storage tanks that are undergoing waste retrieval operations. The retrieval operations are scheduled to be completed by the end of fiscal year (FY) 2001. The retrieved waste is being transferred to the Melton Valley Storage Tanks. The remainder of the TRU sludge waste is already stored in the Melton Valley Storage Tanks. Sampling and analysis has been performed on all of the tank waste at ORNL. The radiological and chemical properties of the sludge and supernate have been measured, and a bounding analysis was performed on each constituent to provide a range of waste characteristics. The legacy TRU solid waste at ORNL is currently stored in subsurface trenches, vaults, and metal buildings.

Approximately 60 m^3 (15,850 gal) of low-level liquid waste and about 20 m^3 (706 ft^3) of TRU waste (5 m^3 of remote-handled TRU solid, 10 m^3 of contact-handled TRU solid, and 5 m^3 of sludge) are generated each year at ORNL. New waste generated after the proposed TRU Waste Treatment Facility is closed and decontamination and decommissioning (D&D) begins is not within the scope of this Environmental Impact Statement (EIS). When the proposed TRU Waste Treatment Facility is closed for D&D, DOE plans to treat TRU liquid wastes at the main TRU waste generator facility known as the Radiological Engineering Development Center (REDC) in order to avoid future large inventories of TRU liquid or sludge waste. Newly generated liquid low-level waste would be processed through the ORNL waste management system and stored in the Melton Valley Storage Tanks–Capacity Increase Project tanks (Figure 1-2). Solid TRU waste would be packaged at the generating facility for disposal at the Waste Isolation Pilot Plant.

1.2.2.1 Liquid and sludge wastes storage

The liquid low-level waste system at ORNL includes underground storage tanks for the accumulation of mixed (RCRA constituents and radioactive) TRU and low-level sludges and liquids. The supernate (liquid layer covering the sludge in underground storage tanks) is considered a low-level waste. It does not contain hazardous constituents and is not regulated under RCRA. The sludge developed from particulates settling out of the liquid waste and forming a sludge layer on the tank bottoms. The sludge waste is characterized as TRU waste, and it contains RCRA metals including mercury, chromium, cadmium, and lead, so it is also classified as mixed waste.

From 1966 until 1984, the primary method for liquid low-level waste disposition at ORNL was hydrofracture. Hydrofracture involved mixing the waste with grout and injecting the resulting waste slurry into shale formations located more than 1,000 ft below ground. Liquid low-level and some TRU waste was prepared and disposed of primarily at the Old Hydrofracture Facility. The New Hydrofracture Facility was also used for a short period of time. Since 1984, underground piping has been used to transfer liquid low-level waste to the ORNL evaporator facility for volume reduction. The evaporator

bottoms are pumped in shielded, aboveground lines to the Melton Valley Storage Tanks following volume reduction operations.

Wastewater treatment units are specifically excluded from federal RCRA permitting requirements pursuant to 40 *Code of Federal Regulations* (*CFR*) 170.1(c)(2)(v). The Melton Valley Storage Tanks are classified as waste water treatment units under TDEC's administered water program and are subject to ORNL's Tennessee Pollutant Discharge Elimination System Permit (TPDES). The Melton Valley Storage Tanks are also permitted by rule under the State of Tennessee's RCRA program because, under Tennessee rules [TNRule 1200-1-11-.07(1)(c)], TPDES-permitted units are granted permit by rule status. Under the Federal Facilities Agreement (FFA) between the EPA, TDEC, and DOE, the Melton Valley Storage Tanks are classified as existing, in-service tanks with secondary containment. Under the FFA, these tanks must continue to undergo annual integrity assessments and maintain their release detection monitoring capabilities throughout their active lives. The tanks are allowed to remain in service unless a release is detected. Results of the assessments continue to demonstrate that the Melton Valley Storage Tanks are not releasing hazardous constituents or radionuclides to the environment.

The Melton Valley Storage Tanks facility (Figure 1-2) provides a number of measures to prevent, detect, and minimize potential releases to the environment and groundwater. Each of the eight cylindrical tanks is of 3.7-m (12-ft) diameter and is 18.7 m (61.3 ft) long. The tanks are constructed from welded, 0.5-in.-thick, type 304L stainless steel (SS) that is compatible with the primary components of the waste and provides optimum structural integrity. Type 304L SS is very corrosion resistant to neutral or alkaline oxidizing salts such as nitrates, nitrites, or chromates. The tanks were designed for service pressure of 15 pounds per square inch, gauge (psig) and service temperatures up to 150°F. The tanks were hydrostatically tested at 22.5 psig prior to operation. The tanks are fitted with level switches and specific gravity and temperature elements that are connected to recorders/alarms in the local control house.




Figure 1-2. Aerial view of the Melton Valley Storage Tanks–Capacity Increase Project during installation of the six 100,000-gallon (gal) tanks located south of the Melton Valley Storage Tanks.

Two underground concrete vaults provide secondary containment for the Melton Valley Storage Tanks (Figure 1-2). Each vault provides containment for four tanks. Both vaults are 19.5 m (64 ft) wide by 20 m (66 ft) long and have an internal height of 5.8 m (19 ft). The walls, floors, and ceilings of the vaults are constructed from 0.8- to 1.5-m (2.6- to 5.0-ft)-thick reinforced concrete. The vaults are internally lined by a 16-gauge, type 304 SS, welded construction "floor pan" to a height of about 2 m (7 ft). The vaults contain an integral sump pump for the collection and detection of any tank leakage. The vaults meet the requirements for Seismic Zone 2 under the Uniform Building Code (UBC). The tanks' piping, valve, and pump gallery is located in an adjacent, similarly constructed underground vault that is internally lined with a type 304 SS floor pan to a height of about 0.9 m (3 ft).

The waste volumes in the Melton Valley Storage Tanks began to approach capacity limits in the early 1990s from the continued generation of liquid low-level waste at ORNL. The Emergency Avoidance Solidification Campaign solidified about 25,000 gal of the supernate layer that had separated from the sludge during storage in an effort to reduce some of the waste volume in the Melton Valley Storage Tanks. ORNL conducted additional volume reduction campaigns and other operations, including in-tank evaporation and out-of-tank evaporation to maintain capacity at the Melton Valley Storage Tanks.

In 1998, ORNL completed the Melton Valley Storage Tanks–Capacity Increase Project, which involved construction of facilities adjacent to the existing Melton Valley Storage Tanks and installation of six 100,000-gal cylindrical, SS storage tanks (Figure 1-2). An Environmental Assessment (EA) was completed for these tanks in 1995 (*Environmental Assessment of the Melton Valley Storage Tanks–Capacity Increase Project*, DOE/EA-1044) (DOE 1995). The new facility has the capability to transfer liquids and pumpable sludges between the six new tanks and the eight original Melton Valley Storage Tanks. Pipes from the new tanks also allow transfers of waste to the liquid low-level waste evaporator and the solidification facility at ORNL. Based on a projected generation rate of approximately 60 m^3/year (15,770 gal/year) of liquid low-level waste from the evaporator bottoms (sludge and supernate), the new tanks will provide sufficient storage capacity for low-level waste for approximately 24 years.

1.2.2.2 Solid waste storage

Solid remote-handled and contact-handled TRU waste is currently packaged in metal boxes, drums, and concrete overpacks, and stored in RCRA-permitted facilities (metal buildings and bunkers). Most of the legacy solid waste containers do not meet the current U.S. Department of Transportation (DOT) regulations and would require repackaging prior to shipment offsite.

Solid TRU waste is also buried in metal and wood boxes found in 23 trenches and 8 auger holes used for the retrievable storage of TRU waste in the Solid Waste Storage Area 5 North (SWSA 5 North). The trenches have seasonal infiltration and inundation of groundwater intermittently throughout the year that causes a "bathtubbing" effect. Soil sampling around the trenches and White Oak Creek indicate gamma contamination at the soil surface equal to 50 μRem/h. These trenches also contribute to surface water and groundwater contamination in the Melton Valley Watershed. The primary contamination sources in the SWSA 5 North area are soils and sediments found on 1.54 ha (3.8 acres). The primary source volume is 1.1 million ft^3 of waste, soils, and sediment containing a total of 14,000 curies. Secondary contamination of soil and groundwater ocurrs on 1.54 ha (3.8 acres). The secondary contamination media include contaminated soils and groundwater between the TRU trenches and White Oak Creek. The SWSA 5 North trenches are estimated to contribute to 6% of the total strontium-90 and 3.6% of the cesium-137 released to surface water in Melton Valley [*Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee, Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1576/V1&D2, May 1997 (DOE 1997b)].

1.3 PURPOSE AND NEED FOR DOE ACTION

DOE has a need to treat the legacy TRU waste at ORNL in order to reduce the risk to human health and the environment and to comply with legal mandates from the TDEC and the ORNL Site Treatment Plan. Due to the water-rich environment in East Tennessee, legacy TRU waste contained in underground trenches at ORNL poses a threat to the area's water quality. These wastes are continually releasing radionuclides into the surrounding soil, groundwater, and surface water. In addition, the liquid and sludge wastes in the Melton Valley Storage Tanks would, if accidentally released by an earthquake, be rapidly transported into nearby streams threatening wildlife and severely degrading water quality.

The four types of legacy TRU waste that require treatment at ORNL are: remote-handled TRU waste sludge; low-level radioactive waste supernate associated with the sludge; contact-handled TRU/alpha low-level radioactive waste solids; and remote-handled TRU/alpha low-level radioactive waste solids. The approximate quantities[8] of the four waste streams[9] requiring treatment and analyzed in this EIS are:

- 900 m^3 (31,770 ft^3) of remote-handled TRU sludge (mixed waste), which is, or will be, located in the Melton Valley Storage Tanks;
- 1,600 m^3 (56,480 ft^3) of low-level supernate (associated with the TRU sludge), which is, or will be, located in the Melton Valley Storage Tanks;
- 550 m^3 (19,415 ft^3) of remote-handled TRU waste/alpha low-level radioactive waste solids, located in vaults and trenches; and
- 1,000 m^3 (35,300 ft^3) of contact-handled TRU waste/alpha low-level radioactive waste solids, located in metal buildings.

There are legal mandates that require DOE to address legacy TRU waste management needs. DOE has been directed by the TDEC and the EPA to address environmental issues including disposal of its legacy TRU waste. DOE is under a TDEC Commissioner's Order (September 1995) to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and disposal of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin treating legacy TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant (a DOE transuranic waste disposal facility) in New Mexico by January 2003.

Waste retrieval operations are currently under way to prepare many of the inactive TRU waste storage tanks, including the gunite tanks, at ORNL for closure. A majority of the wastes retrieved from the ORNL inactive tanks are being consolidated into the Melton Valley Storage Tanks, prior to treatment at the proposed TRU Waste Treatment Facility, and have been included in the stated waste quantities needing treatment. DOE will ensure the safe and efficient retrieval, and transfer, of legacy TRU tank waste to the Melton Valley Storage Tanks at ORNL for consolidation. Waste retrieval and consolidation activities for the ORNL Inactive Tanks Program are planned for completion by the end of FY 2001.

Removal, treatment, and disposal of the retrievable TRU waste from portions of the SWSA 5 North area is considered a major component of the selected remedy for the Melton Valley Watershed at ORNL according to the Draft Record of Decision for the Melton Valley Watershed (DOE 1997c). In addition, an Interim Record of Decision [issued in connection with the FFA among EPA, TDEC, and DOE under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)] for the Gunite and Associated Tanks Remediation Project (DOE 1997d), and an Action Memorandum for the Old Hydrofracture Facility Tanks Remediation Project (DOE 1997e), require the waste from these tanks to be treated and disposed of along with the TRU waste from the Melton Valley Storage Tanks. This tank waste is included in the total waste volume slated for treatment in the TRU Waste Treatment Facility. Currently, no facilities exist at ORNL or the ORR for treating TRU sludges and the associated low-level waste supernate, or the contact-handled and remote-handled TRU/alpha low-level radioactive solid waste.

[8]Waste volume estimates provided herein have not been rounded and may contain more than the significant number of digits.

[9]Potential impacts of off-site waste (15 m^3 from Paducah) are considered in Section 5. DOE would need to conduct further NEPA review as appropriate for any proposal for the Paducah site, or any other site in the DOE complex to ship any TRU waste to ORNL for treatment.

1.4 SCOPE OF ENVIRONMENTAL IMPACT STATEMENT

DOE has prepared this EIS under the National Environmental Policy Act (NEPA) and its implementing regulations on the proposed construction, operation, and D&D of a TRU Waste Treatment Facility at ORNL in Oak Ridge, Tennessee. As part of this EIS, DOE evaluated alternative approaches for achieving the proposed action. Since much of the tank sludge waste displays RCRA characteristics, the proposed facility would be permitted under RCRA. Most of the waste is currently stored in the Melton Valley area of ORNL in underground waste storage tanks, bunkers, metal buildings, and subsurface trenches.

This EIS has been prepared according to the NEPA of 1969, the Council on Environmental Quality NEPA regulations (40 *CFR* 1500–1508), and DOE's NEPA Implementing Procedures (10 *CFR* Part 1021). In accordance with the NEPA process, a Notice of Intent was published in the *Federal Register* (Appendix A.1). This Final EIS incorporates pertinent analyses performed as part of the DOE's *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS-II), DOE/EIS-0026-S-2, September 1997 (DOE 1997a) and the *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F (WM PEIS) (DOE 1997f). Treatment of ORNL TRU waste onsite, and disposal at the Waste Isolation Pilot Plant, is consistent with the Records of Decision issued for management of the transuranic waste for the aforementioned EISs (63 *FR* 3624 and 3629, respectively, January 23, 1998) (DOE 1998a; DOE 1998b). The disposal of low-level radioactive waste at the Nevada Test Site is consistent with the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

DOE addressed issues associated with the potential environmental impacts of the alternatives for the proposed action in this Final EIS, including:

- potential effects on air, soil, and water quality from normal operations and reasonably foreseeable accidents;
- potential effects on the public, including minority and low-income populations, and workers from exposure to radiological and hazardous materials from normal operations and reasonably foreseeable accidents;
- compliance with applicable federal, state, and local requirements and agreements;
- pollution prevention, waste minimization, and energy and water use reduction technologies to eliminate or reduce use of energy, water, and hazardous substances and to minimize environmental impacts;
- potential socioeconomic impacts, including potential impacts associated with the workforce needed for operations;
- potential cumulative environmental impacts of past, present, and reasonably foreseeable future operations; and
- potential irreversible and irretrievable commitment of resources.

1.5 PUBLIC PARTICIPATION

A Notice of Intent to prepare an EIS for the TRU Waste Treatment Facility was published in the *Federal Register* on January 27, 1999. The Notice of Intent identified the public scoping period to encourage early public involvement in the EIS process and to solicit public comments (Figure 1-3) on the proposed scope of the EIS, including the issues and alternatives it would analyze. Two meetings were held in Oak Ridge, Tennessee, on February 11 and 16, 1999, to provide an opportunity for all people who wished to comment or make a presentation. The scoping period ended on February 26, 1999. Transcripts from the public scoping meeting are summarized in Appendix A.3.



Figure 1-3. Stakeholder meetings have been held as part of the TRU Waste Treatment Project.

The Draft EIS was released to the public for review and comment on March 3, 2000. On March 21, 2000, a public hearing was held in the Oak Ridge Mall. Oral comments were received on the Draft EIS and a transcript was made of the hearing. The public comment period ended on April 17, 2000. All public comments received on the Draft EIS and responses to these comments are contained in the Comment Response Document, Volume 2 of this Final EIS, and summarized below.

Information provided below contains an overview of comments and responses on the Draft EIS and discusses those areas for which DOE received multiple comments.

Many commentors supported DOE's proposed action, although some were concerned that the processes for treating the wastes in the Melton Valley Storage Tanks may not have been done before at this scale or by the selected contractor. Some commentors were concerned about the uncertainty of using the various treatment processes (e.g., technical implementability), especially Vitrification. While DOE acknowledges that there is some uncertainty in treating TRU waste using any of the technologies, there are successful examples of these specific technologies being used in similar situations. Examples of successful use of drying technology include the Hanford 200 Area evaporator in Hanford, Washington, the Palo Verde Nuclear Generating Station near Phoenix, Arizona, and the Three-Mile Island-2 Evaporation Project, in New York. Examples of successful waste solidification operations using hydraulic cement include DOE's Hanford, Rocky Flats, and Savannah River sites, and the Melton Valley Storage Tank waste at ORNL. Examples of successful DOE use of vitrification include the Savannah River M-Area, the Fernald Minimum Additive Waste Unit, and the West Valley Vitrification Plant.

Some commentors took issue with the Treatment and Waste Storage at ORNL Alternative, maintaining that 100 years of institutional control was an insufficient timeframe for analysis of impacts, and that the alternative was contrary to a Tennessee Department of Environment and Conservation (TDEC) Commissioner's Order to ship treated waste offsite; thus, the alternative was not reasonable under NEPA. Other commentors noted that the alternative should not be for 100 years, but that 30 years was the maximum DOE should consider for interim storage. Some commentors indicated that the impacts associated with the No Action Alternative were also understated because the impact analysis period was limited to 100 years. DOE considers this alternative reasonable and has provided additional analysis in the Final EIS for the No Action Alternative and Treatment and Waste Storage at ORNL that examined potential impacts from loss of institutional control, assumed to occur for analysis purposes, after

100 years. A 30-year timeframe as compared to a 100-year timeframe would show lower impacts for both utility usage and worker exposure.

Several commentors stated that DOE unduly restricted the impact analysis by omitting analysis of on-site transport of the wastes to the treatment facility. DOE agrees and has added several subsections to Chapter 4, in Section 4.8, that discuss transportation analysis of the Final EIS. These sections address the impacts of routine operations to the involved worker, and impacts of accidents to the involved worker, non-involved worker, and the public from the exhumation or removal of wastes from the subsurface trenches, buildings, and bunkers, and the transport of wastes to the proposed treatment facility.

The U.S. Department of the Interior (DOI) asked for additional information on protected species, including the Indiana Bat. DOE has submitted to DOI a draft Biological Assessment (BA) based on information in the Draft EIS and from site walkovers, and DOE will continue informal consultation with DOI under the Endangered Species Act. A copy of the draft BA is included in Appendix E of the Final EIS.

One commentor questioned the adequacy of the accident analysis for the Low-Temperature Drying Alternative, pointing out that for high-level waste, explosions and criticality are typically evaluated. DOE considered a wide range of accident scenarios and selected those that were determined to be credible for detailed analysis. Because low-temperature drying is a low-energy process and is conducted in small, 1-m^3 batches, an explosion would be unlikely. Further, this waste treatment process would be performed in an area with 2-ft-thick walls for radiological protection. Workers are not allowed in the area when treatment is occurring. As a result, there is little risk to involved and non-involved workers. With regard to criticality accidents, DOE has no process knowledge suggesting that any enriched materials would be part of the waste stream. In addition, administrative and process controls would be followed that avoid criticality.

Project-related and other environmental materials are available for public review in the following reading rooms:

Washington, D.C.	U.S. Department of Energy Freedom of Information Public Reading Room, Forrestal Building, Room I E-190, 1000 Independence Avenue, S.W. Washington, DC 20585 Telephone: (202) 586-3142
Oak Ridge, Tennessee	U.S. Department of Energy, Oak Ridge Operations Office 200 Administration Road, Room G-217 Oak Ridge, TN 37831 Telephone: (423) 241-4780

1.6 RELATIONSHIP TO OTHER NEPA DOCUMENTS

DOE has prepared and issued a number of EISs and EAs that present analysis of environmental consequences that are relevant to the proposed action. These include:

- *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (WM PEIS), DOE/EIS-0200-F, May 1997 (DOE 1997f). Low-level waste will be treated to meet the waste acceptance criteria for the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000). The treatment of TRU waste onsite at ORNL is consistent with DOE's January 1998 WM PEIS Record of Decision (DOE 1998b) for TRU waste treatment and storage, which decided that DOE sites would treat and store their own TRU wastes onsite, before shipment to the Waste Isolation Pilot Plant for disposal.

- *Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement*, DOE/EIS-0026-S-2, September 1997 (DOE 1997a). The WIPP SEIS-II evaluates the impacts of various treatment options; the transportation of TRU waste to the Waste Isolation Pilot Plant, using trucks, and both regular and dedicated rail service; and the disposal of the waste at the Waste Isolation Pilot Plant. The Waste Isolation Pilot Plant has waste acceptance criteria that Oak Ridge TRU waste must meet following treatment.

- *Advanced Mixed Waste Treatment Project at the Idaho National Engineering and Environmental Laboratory Environmental Impact Statement* (AMWTP EIS), DOE/EIS-0290-F, issued in January 1999 (DOE 1999b). This EIS analyzes the environmental impacts of several similar treatment alternatives and the construction of the Advanced Mixed Waste Treatment Facility in Idaho.

- *Final Environmental Impact Statement for the Construction and Operation of the Spallation Neutron Source*, DOE/EIS-0247, April 1999 (DOE 1999c). This document addresses the regional environment on the ORR.

1.7 REFERENCES

DOE (U.S. Department of Energy) 1995. *Environmental Assessment of the Melton Valley Storage Tanks–Capacity Increase Project*, DOE/EA-1044, U.S. Department of Energy, Washington, D.C.

DOE 1997a. *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement*, DOE/EIS-0026-S-2, U.S. Department of Energy, Washington, D.C., September 1997.

DOE 1997b. *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee, Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1576/V1&D2, May 1997.

DOE 1997c. *Draft Record of Decision for the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1826&D1.

DOE 1997d. *Record of Decision for Interim Action: Sludge Removal from the Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/OR2-1591&D3, August 1997.

DOE 1997e. *Action Memorandum for the Old Hydrofracture Facility Tanks and Impoundment, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1751&D3.

DOE 1997f. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (WM PEIS), DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1998a. *WIPP SEIS-II, Record of Decision for the Department of Energy's Waste Isolation Pilot Plant Disposal Phase, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3624–3629.

DOE 1998b. *WM PEIS, Record of Decision for the Department of Energy's Waste Management Program: Treatment and Storage of Transuranic Waste, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3629–3633.

DOE 1999a. *Implementation Guide for Use with DOE M 435.1-1*, DOE G 435.1-1, July 1999.

DOE 1999b. *Advanced Mixed Waste Treatment Project Final Environmental Impact Statement*, DOE/EIS-0290, U.S. Department of Energy, Idaho National Engineering and Environmental Laboratory, Idaho Falls, Idaho, January 1999.

DOE 1999c. *Final Environmental Impact Statement for the Construction and Operation of the Spallation Neutron Source*, DOE/EIS-0247, U.S. Department of Energy, Office of Science, Washington, D.C., April 1999.

DOE 2000. *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-Level and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site, Federal Register*, Vol. 65, No. 38 10061–10066, February 25, 2000.

THIS PAGE INTENTIONALLY LEFT BLANK

2. DESCRIPTION OF THE PROPOSED ACTION AND ALTERNATIVES

2.1 PROPOSED ACTION

DOE proposes to construct, operate, and decontaminate and decommission (D&D) a waste treatment facility for the treatment of legacy ORNL TRU, alpha low-level waste, and newly generated TRU waste (Figure 2-1) in order to reduce the risk to human health and the environment, and to comply with the TDEC Commissioner's Order of 1995, which has a primary milestone that requires DOE to make the first shipment of treated TRU sludge to the Waste Isolation Pilot Plant in New Mexico by January 2003. Impacts relative to the construction, operation, and D&D[1] of any treatment facility are presented in Chapter 4, in detail, for each treatment alternative evaluated in this EIS. All the legacy waste DOE proposes to treat as part of the TRU Waste Treatment Facility Project is currently stored at ORNL. The newly generated TRU waste would be treated at the proposed facility until it is closed for D&D. TRU waste generated after closure of the proposed facility is not within the scope of the proposed action.




Figure 2-1. General site location of the proposed TRU Waste Treatment Facility at Oak Ridge National Laboratory (ORNL) on the Oak Ridge Reservation (ORR).

DOE's proposed action would entail the award of a privatization contract, contingent upon the completion of the NEPA review, for the construction, operation, and D&D of the proposed waste treatment facility to a private contractor. DOE solicited bids from contractors for a treatment facility for the TRU wastes. The privatization contract request for proposal was structured so that the selected

[1]Specific information on impacts resulting from D&D activities can be found in Chapter 4 in Sections 4.1.3, 4.1.4, 4.1.5, 4.1.6, 4.3.7, 4.4.3, 4.4.5, 4.4.7, 4.5.2, 4.5.3, 4.7.3, 4.7.5, 4.7.6, 4.7.7, 4.8.3, 4.8.4, 4.8.5, 4.8.6, and 4.10.5.

contractor would be required to use its own funds for the construction of the facility, and so that payment for the construction portion of the contract would not be made until the waste was treated to meet the appropriate waste acceptance criteria and certified by DOE. Three bids were received and evaluated. DOE incorporated environmental information very early in the project planning. For example, DOE required proposals to include environmental data and analysis. Prior to selection of the contractor, DOE held two public meetings with stakeholders and had ongoing discussions with regulators. In addition, DOE prepared a characterization report for the site of the proposed action and sponsored an independent study of treatment technologies and contracting alternatives, known as the Parallax study [ORNL/M-4693, *Feasibility Study for Treatment ORNL TRU Waste In Existing and Modified Facilities*, September 15, 1995 (Parallax 1995)]. DOE independently evaluated the environmental information provided in the bids. DOE developed an environmental synopsis of the environmental information in accordance with 10 *CFR* 1021.216 and published the *Environmental Synopsis for the Transuranic Waste Treatment Project at the Oak Ridge Reservation* in January 1999 (Appendix A.2). This synopsis has been filed with the EPA and made available to the public.

The proposed site for the treatment facility is adjacent to the Melton Valley Storage Tanks (the current storage area for the waste sludge and supernate). DOE would lease the Melton Valley Storage Tanks and an adjacent land area totaling up to 4 ha (10 acres) to the selected contractor for the construction of the facility (Figure 2-2), subject to notification of the EPA and the State of Tennessee to clarify the change in land use. Once the facility is closed and D&D of the facility is completed, the Melton Valley Storage Tanks and the land used for the facility would no longer be leased to the selected contractor.




Figure 2-2. DOE would lease the Melton Valley Storage Tanks facility and an adjacent area of land to construct the waste treatment facility. The location is isolated from ORNL by Haw Ridge.

The proposed facility location is based on two factors listed below:

- The treatment facility should be located close to the existing Melton Valley Storage Tanks to minimize the length of a new sludge/supernate transfer line and reduce the environmental disturbance due to construction as recommended in the *Feasibility Study for Processing ORNL Transuranic Waste in Existing and Modified Facilities* (Parallax 1995).

- The existing terrain should provide natural shielding for the proposed facility and facilitate material handling.

The location of the proposed facility near the Melton Valley Storage Tanks would reduce the risk associated with transporting the liquid and sludge tank waste from the Melton Valley Storage Tanks to the proposed treatment facility over public or laboratory roads. The Melton Valley Storage Tanks are located in Melton Valley, separated from the main plant area at ORNL by the Haw Ridge. The proposed treatment facility site would be fenced, with controlled access to Tennessee State Highway 95, which is located west of the proposed site. DOE would provide electrical, water, and telephone service to the edge of the leased area on the east side of the facility. DOE upgraded the existing single-lane road (Old Melton Valley Road, referred to as High Flux Isotope Reactor access road by some sources) from State Route 95 to the proposed facility to provide improved emergency access from the High Flux Isotope Reactor. This road will become the main access to the proposed facility. A categorical exclusion under NEPA was executed for this road upgrade (CX-TRU-98-007, *Categorical Exclusion for Construction/Relocation of Access Road at Oak Ridge National Laboratory*) (DOE-ORO 1998). Because most of the sludge is regulated under RCRA, the proposed facility would be permitted under RCRA.

The proposed action would be carried out in four phases:

- Phase I, Licensing and Permitting [includes DOE's NEPA analysis and contractor preliminary design activities; U.S. Nuclear Regulatory Commission (NRC) license is not required as the facility will only be treating DOE wastes];

- Phase II, Construction and Pre-Operational Testing;

- Phase III, Waste Treatment, Packaging, and Certification; and

- Phase IV, Decontamination and Decommissioning.

DOE will complete the NEPA process concurrent with Phase I of the contract. Phase I is a 2.5-year period during which the permitting and preliminary design process is completed for the proposed facility. If the NEPA review results in another alternative being selected, the contract would be terminated before Phase II of the contract begins.

DOE requires that all activities associated with the proposed action be performed safely and in compliance with applicable federal and state regulatory requirements. The selected contractor would be responsible for achieving compliance with all applicable environmental, safety, and health laws and regulations. Regulatory agencies would be responsible for monitoring compliance by the contractor. The State of Tennessee would regulate the selected contractor according to permits under the state's purview (the RCRA Part B permit issued by the State of Tennessee). DOE would regulate occupational safety and health and nuclear safety according to specific environment, safety, and health requirements.

Waste volume reduction would be a major consideration for the proposed action. Waste volume reduction would minimize waste generation during the treatment process, conserve resources, and would

result in lower disposal costs. The waste treatment technique used in the proposed action would need to be flexible enough to address a wide range of waste properties, substantially reduce the TRU waste volume, and generate minimal secondary waste during treatment. After waste treatment, DOE would certify the waste for disposal as low-level radioactive waste, alpha low-level radioactive waste, or TRU waste. The contractor would be required to treat all wastes to meet specified waste acceptance criteria for disposal. In the event that the Waste Isolation Pilot Plant is not accepting remote-handled TRU waste in time to meet the TDEC Commissioner's Order, the selected contractor would be required to reduce the solubility of the RCRA metals in the sludge waste in order to form stable compounds. The stabilized sludge would not exceed the RCRA Toxicity Characteristic Leaching Procedure (TCLP) limits and would no longer exhibit RCRA characteristics. This would ensure that the treated waste meets RCRA Land Disposal Restriction (LDR) standards, required by the ORNL Site Treatment Plan, in the event that the treated waste is stored onsite before transport to the Waste Isolation Pilot Plant.

The proposed action calls for the segregation of the legacy sludge and supernate contained in the waste storage tanks. The segregation of these wastes would result in significant life cycle cost avoidance when compared to disposal of both the sludge and supernate at the Waste Isolation Pilot Plant. The supernate, which is generally classified as low-level waste, would be reduced in volume during waste treatment, and packaged for final disposal at the Nevada Test Site consistent with the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

Because most of the current solid waste containers do not meet DOT regulations, the proposed action would provide for repackaging the solid waste prior to shipment. The waste would be certified for disposal by DOE as either low-level radioactive, alpha low-level radioactive, or TRU waste and transported to appropriate disposal facilities that are consistent with the WM PEIS. The proposed action includes repackaging with some compaction to obtain a 50% volume reduction for the bulk of the solid waste that is not regulated under RCRA. The solid waste would be better characterized during the repackaging efforts to achieve final waste certification by DOE before disposal. Any items displaying RCRA characteristics would be isolated and treated to meet RCRA LDR standards.

2.2 CONSIDERATION OF ALTERNATIVES

DOE analyzed five alternatives in this EIS: a no action alternative; three alternative technologies for treating the legacy wastes followed by shipment to an appropriate disposal facility; and treatment by any of the three alternative treatment technologies, followed by interim storage at ORNL. Shipment of the TRU wastes to other DOE sites for treatment was also considered, but not analyzed in detail for reasons discussed in Section 2.8.1. Other potential treatment technologies were also evaluated, but were not analyzed in detail for various reasons (Table 2-5, Section 2.8.4).

A summary of the environmental impacts for the five alternatives is included in Section 2.9. The remainder of Chapter 2 discusses the following five alternatives in detail:

1. **No Action** (i.e., continued on-site storage and no waste treatment) for all of the legacy TRU tank waste stored in the Melton Valley Storage Tanks and the legacy contact-handled and remote-handled TRU/alpha low-level solid wastes stored in trenches, vaults, and metal buildings.
2. **Low-Temperature Drying (Preferred Alternative)** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).
3. **Vitrification** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).
4. **Cementation** for the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris).
5. **Treatment and Waste Storage at ORNL** would provide treatment by one of the above treatment alternatives followed by interim waste storage at ORNL.

2.3 NO ACTION ALTERNATIVE

Under the No Action Alternative, DOE would continue to store legacy TRU waste at ORNL in underground waste storage tanks, subsurface trenches, vaults, bunkers, and metal buildings. Long-term storage, consistent with the No Action Alternative, is not permissible under RCRA, which does not allow storage of untreated hazardous wastes indefinitely.

2.3.1 Facility Description

No facility would be constructed under the No Action Alternative for the treatment of legacy TRU waste. Existing facilities at ORNL would be used for the continued storage of the legacy TRU waste. Legacy mixed (RCRA hazardous and radioactive) TRU sludge and the associated low-level supernate wastes would continue to be stored in the Melton Valley Storage Tanks and the Melton Valley Storage Tanks–Capacity Increase Project tanks (Figure 2-2). There is slightly over 1,400 m^3 (about 370,000 gal) of storage capacity available in the existing storage tanks.

Legacy solid remote-handled and contact-handled wastes would be stored in their current facilities described below.

- Solid Waste Storage Area 5 North (SWSA 5 North) is at capacity and stores remote-handled TRU solid wastes and TRU mixed wastes in casks buried underground in trenches.

- Buildings 7855 and 7883 are bunkers, which would continue to store remote-handled TRU waste. Building 7855 is at capacity, with 157.2 m^3 (5,552 ft^3) of remote-handled TRU waste in storage. Building 7883 currently stores 10.7 m^3 (377 ft^3) of remote-handled TRU solids and has an available storage capacity of 146.7 m^3 (5,179 ft^3).

- Buildings 7572, 7574, 7842, 7878, and 7879 are metal buildings that would continue to store contact-handled TRU waste. These storage buildings currently store over 906 m^3 (32,000 ft^3) of contact-handled TRU wastes. Building 7842 is at capacity, but the other buildings have a combined available storage capacity of 722 m^3 about (25,500 ft^3) for contact-handled TRU wastes.

- Buildings 7826 and 7834, the below-grade concrete cells in SWSA 5 North, which currently store a total of about 68 m^3 (2,400 ft^3) of remote-handled TRU and contact-handled waste, are not RCRA permitted. This waste is scheduled to be moved to the appropriate existing facilities for contact-handled and remote-handled wastes (described above) as a legacy waste action under CERCLA in FY 2000, thus reducing the amount of permitted storage space that is available.

2.3.2 Treatment Description

There would be no waste treatment under the No Action Alternative for TRU wastes.

2.3.2.1 Sludge and supernate

The No Action Alternative involves continued storage of legacy mixed (RCRA constituents and radioactive) TRU sludge and associated low-level supernate waste in the Melton Valley Storage Tanks at ORNL.[2] If this alternative were chosen, the Interim Record of Decision for the Gunite and Associated Tanks (DOE 1997a) and the Action Memorandum for the Old Hydrofracture Facility tanks (DOE 1997b) would require amendment since these documents indicated that the waste would be consolidated in the Melton Valley Storage Tanks in preparation of treatment prior to disposal at the Waste Isolation Pilot Plant. In addition, the continued storage of this waste onsite at ORNL would be in violation of DOE Order 435.1.

2.3.2.2 Remote-handled and contact-handled solid wastes

Remote-handled and contact-handled solid wastes would continue to be stored at ORNL in the existing solid waste storage facilities and in the SWSA 5 North trenches under the No Action Alternative.[3] If this alternative were chosen, the Record of Decision for the Melton Valley Watershed (DOE 1997c) would have to be amended, since removal of the retrievable TRU waste in the SWSA 5 North trenches is a main component of the selected remedy for the Melton Valley Watershed.

---

[2]Basic research and environmental remediation activities at ORNL would continue to generate new waste at a rate of approximately 60 m^3 (15,850 gal) of liquid low-level waste and 5 m^3 (175 ft^3) of TRU sludge annually. These wastes would be added to the legacy sludge and supernate to be treated in the proposed facility. After the proposed treatment facility is closed, newly generated waste would be stored in the Melton Valley Storage Tanks and Capacity Increase Project tanks, which have enough tank capacity for approximately 21 years. In the event that construction of any new waste storage tanks would be needed, these facilities would be evaluated in a separate NEPA review.

[3]There would be enough storage capacity for newly generated remote-handled TRU solid waste for approximately 14.5 years, assuming a generation rate of approximately 10 m^3 (350 ft^3) per year. There would be enough storage space for contact-handled TRU waste for approximately 100 years, assuming a generation rate of approximately 5 m^3 (175 ft^3) per year. In the event that construction of any additional storage facilities for newly generated remote-handled and contact-handled solid waste would be needed, these facilities would be evaluated under a separate NEPA review.

2.3.3 Schedule of Activities

For purposes of analyses, the No Action Alternative assumes institutional control of the waste identified for treatment under the proposed action in this EIS for 100 years, after which there would be a loss of institutional control.

2.4 LOW-TEMPERATURE DRYING ALTERNATIVE (PREFERRED ALTERNATIVE)

DOE has awarded a contract with the Foster Wheeler Environmental Corporation (Foster Wheeler) to construct a waste treatment facility and to treat and package the TRU wastes for disposal offsite. The contract with Foster Wheeler was awarded contingent on the completion of the NEPA review and selection of the Foster Wheeler proposed treatment process in the Record of Decision. DOE continues to analyze environmental impacts and evaluate alternative actions while Phase I (Licensing and Permitting) of the contract awarded to Foster Wheeler is under way. If the current NEPA review results in the selection of an alternative other than the preferred alternative, Phase II (construction and pre-operational testing) of the contract would not be executed.

Foster Wheeler proposes to use a low-temperature drying treatment for the tank waste, and sorting, compaction, and repackaging for the solid waste, before the waste is certified by DOE for final disposition. TRU waste would be disposed at the Waste Isolation Pilot Plant, consistent with the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Storage of Transuranic Waste* (DOE 1998b). Low-level waste would be disposed at the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000). The contract allows DOE and Foster Wheeler to identify other potential waste streams for treatment at this facility during Phase I of the contract and may include newly generated waste from the ORR, or small amounts of legacy TRU waste from other sites. Before any such waste streams would be considered or shipped to ORNL, they would be subject to further NEPA review, as appropriate.

2.4.1 Facility Description

The Low-Temperature Drying Alternative (Preferred Alternative) would involve the construction of a three-and-one-half-story waste treatment facility approximately 37 m (120 ft) west of the Melton Valley Storage Tanks area. The proposed site would encompass 2 ha (5 acres) of the approximately 4 ha (10 acres) that would be included in the lease.

The proposed waste treatment facility would have a partial floor for treatment of the supernate between the first and second floors. The facility would be a steel-framed structure with concrete and steel shielding. An attached steel building would house the administrative and personnel areas on the north side of the facility, and trailers for the nondestructive examination and assay of the contact-handled solid wastes would be located on the south side of the facility. The total floor area of the facility would be approximately 3,440 m^2 (37,000 ft^2), comprised of an estimated 1,160 m^2 (12,500 ft^2) of process area, 1,720 m^2 (18,500 ft^2) of process support area, and 560 m^2 (6,000 ft^2) of administration area.

The first floor would contain the remote-handled solid waste cask receiving and staging area as well as the treated solid waste cask and load-out area. Supernate treatment would be performed on the partial floor above the low-level waste load-out area. The dried supernate would be discharged by gravity to liners positioned on truck trailers for final packaging and shipping. The second floor would contain the contact-handled solid waste receiving and characterization area and the contact-handled and remote-handled solids treatment equipment. Facilities to support the building heating, ventilation, and air

conditioning (HVAC) and equipment maintenance activities would be located on the third floor. TRU sludge treatment equipment would be located on the fourth floor to receive and dry sludge that would be discharged to canisters located on the second floor. The facility ventilation exhaust stack would be located on the southeast corner of the building and would extend approximately 9 m (30 ft) above the highest point on the building. As shown in Figure 2-3, the facility's first floor elevation would be approximately 235 m (770 ft) above mean sea level, which is above the 100- and 500-year flood elevations. Site development would require an approximate 6-m (20-ft) cut into the west ridge, with fill in the low areas around the facility and roadway areas. Detailed information about the proposed floor plans can be found in Appendix B.

Storm water drainage would be directed around the facility by a series of culverts and drainage ditches as shown in Figure 2-3. This would prevent the facility from receiving storm water runoff from the ridgeline south of the facility. This runoff would be diverted west of the facility by a ditch along the third floor access ramp, and to the east by a berm and culvert arrangement. The drainage ditches would be lined with riprap, as required. Culverts carrying storm water off the facility site would be equipped with gate valves to allow sampling and analysis of the storm water and to provide storm water containment in case of potential contamination. Storm water collected from the top of the Melton Valley Storage Tank vaults would be controlled in a similar manner. In addition, drainage grates would be installed at paved exits to capture and direct runoff from paved areas to the culverts equipped with the gate valves.

2.4.2 Waste Treatment Description

This alternative would entail evaporating and drying the sludges and supernates and is flexible enough to cover a wide range of waste properties. Treatment by low-temperature drying would substantially reduce the waste volume, generate minimal amounts of secondary wastes, and meet the waste acceptance criteria of the final disposal facilities. All waste streams would meet the RCRA LDR standards. TRU waste streams would be treated to meet the waste acceptance criteria of the Waste Isolation Pilot Plant. Low-level waste streams would be treated to meet the waste acceptance criteria of the Nevada Test Site selected for low-level waste disposal in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000). Several pollution prevention and waste minimization measures would be implemented with the Low-Temperature Drying Alternative. As pollution prevention measures, storm water would be diverted around the treatment facility and gate valves would be installed in the diversion basins to contain spills. Waste minimization is accomplished by the following methods:

- The Melton Valley Storage Tanks would be sluiced with recycled supernate during sludge retrieval activities.
- Sludge would be washed with recycled condensate from the air-cooled condenser, which receives the ventilation from the low-temperature dryers.
- Dried sludge solids would be loaded directly into TRU canisters to avoid additional secondary waste.
- Low-level solid waste drums that do not contain RCRA waste would be sent directly to the compactor for a 50% volume reduction.
- Secondary solid waste would be compacted for a 50% volume reduction.
- The off-gas system would minimize air emissions.

A summary of the projected volumes of primary, secondary, and D&D waste is included in Table 2-1. The primary waste volumes would be reduced by low-temperature drying from 4,050 m^3 to 1,391 m^3.





Figure 2-3. Proposed site layout for the Low-Temperature Drying Alternative facility, including the locations of the existing storm water drainage modifications. Site excavation would be minimized by optimizing the



elton Valley Storage Tanks, the process building with truck access and turnaround areas to the first and third floors, and pography of the site with the layout of the Low-Temperature Drying Alternative facility.

Table 2-1. Summary of projected waste volumes for the Low-Temperature Drying Alternative


Waste Stream	Category	Projected Volume Out[a]	Treatment Requirement
Primary Waste Streams			
Sludge (remote-handled)	TRU	180 m^3	Dry, stabilize
Supernate/sludge wash water	Low-level waste	588 m^3	Dry, stabilize
Contact-handled solids	TRU	324 m^3	Various
Remote-handled solids	TRU	99 m^3	Various
Solids	Low-level waste	200 m^3	Various
Secondary Waste Streams			
Primary waste containers			
Remote-handled casks	Low-level waste	1,217 m^3	None
Contact-handled drums and boxes	Low-level waste	44 m^3	Compaction
Construction debris	Sanitary	~200 m^3	None
PPE (gloves, booties, etc.)	Low-level waste	214 m^3	Compaction
HEPA filters	Low-level waste	88 m^3	Compaction
Consumables (rags, towels, etc.)	Low-level waste	272 m^3	Compaction
Mechanical parts	Low-level waste/TRU	4 m^3	None
Aqueous waste filter media	Low-level waste	<20 m^3	Compaction
Steam from wet treatment	N/A	N/A	Condense/HEPA filter
Changing/maintenance fluids	Low-level waste/mixed waste	<1 m^3	Stabilize, if required
Laboratory solvents and residues	Low-level waste/mixed waste/TRU	1 m^3	Thermal, none
Laboratory acid digistatis	Mixed waste	<20 m^3	Neutralize stabilize
Sanitary wastewater	Sanitary	1,560 m^3	Capture
Decontamination and Decommissioning Waste Streams			
Category C, Concrete rubble	Construction debris	5,510 m^3	None
Category A, Free release metals	Recycle, reuse	115 m^3	None
Category B, Non-contaminated metals	Construction debris	30 m^3	None
Category B, Contaminated materials	Low-level waste	135 m^3	Compaction
Category D, Miscellaneous	Construction debris	<10 m^3	None
Category E, Special materials	Low-level waste/mixed waste	<1 m^3	Stabilize

[a]Volumes are waste product volumes in final disposal containers based on total inventory of waste (base + optional volumes) expected to be processed at the facility.

HEPA - High-Efficiency Particulate Air.
PPE - personal protective equipment.
TRU - transuranic
~ - approximately.

2.4.2.1 Tank waste treatment (sludge and supernate)

The simplified block flow diagram for the tank waste treatment systems is illustrated in Figure 2-4. Supernate would be pumped from the existing Melton Valley Storage Tanks using equipment moved from tank to tank. The supernate would be pumped through a double-contained, aboveground pipeline to the proposed treatment facility and collected into mixing/sample tanks. The supernate from the Melton Valley Storage Tanks may be transferred to an evaporator for volume reduction before transfer to the mixing/sample tanks. In order to meet RCRA LDR standards and waste acceptance criteria for the Nevada Test Site, additives would be mixed with the supernate in these tanks, as required for the downstream treatment operations. The supernate dryer would receive feed batches. The treated waste would be loaded directly into a disposal container that is pre-loaded in a transportation



1. MVSTs = Melton Valley Storage Tanks
2. Supernate may be evaporated
3. Air emission controls include charcoal filters and High-Efficiency Particulate Air (HEPA) filter systems
4. Cross-flow filter is optional
5. LLW = Low-level waste

Figure 2-4. Tank waste treatment flow diagram for the Low-Temperature Drying Alternative.

cask for shipment. Vapors from the dryer would be routed through an air-cooled condenser. Condensate may be stored in a reservoir for reuse in sludge retrieval, or evaporated and discharged as part of the building ventilation flow through appropriate high-efficiency particulate air (HEPA) filtration.

Sludge would be retrieved from the Melton Valley Storage Tanks by sluicing with recycled liquids (supernate or condensate) or water. Recycled condensate or water would be preferentially used to allow washing of the sludge solids to separate soluble solids. The sluiced sludge would be transferred in a double-contained, aboveground pipeline to the sludge collection/decant tanks in the facility. These tanks would have the potential for concentrating the sludge by gravity settling. Sluiced sludge would be analyzed, mixed with appropriate additives, and concentrated for drying.

After analysis, the concentrated sludge/additive mixture would be transferred in batches to the sludge dryer. The sludge drying system would function in a similar fashion to the supernate dryer. For optimum efficiency, the dried sludge solids would be loaded directly into Waste Isolation Pilot Plant TRU canisters. Sludge distillate may be condensed or directed to the supernate treatment system.

2.4.2.2 Solid waste treatment (remote-handled and contact-handled solids)

DOE would deliver drums and boxes of the contact-handled solid waste to the proposed treatment facility. Foster Wheeler would perform visual inspections and radiation and contamination surveys prior to acceptance of the waste containers. The drum contents would be characterized by performing a non-destructive examination and assay in an adjoining enclosure before transfer to a staging area. The low-level waste drums that do not contain RCRA waste would be treated in a drum compactor for a 50% volume reduction, overpacked, weighed, and conveyed back to the shipping/receiving area for final certification by DOE. The simplified block flow diagram for the tank waste treatment systems is illustrated in Figure 2-5.




Figure 2-5. Solid waste treatment flow diagram for the Low-Temperature Drying Alternative.

The remaining drums would be transported to the process line area. The drums would be moved into a glovebox, opened, and the contents would be tipped onto a sorting tray where restricted/RCRA waste materials would be segregated manually via glove ports. The segregated low-level waste would be treated as described above. The RCRA/restricted waste materials would be treated by macroencapsulation or other techniques to meet RCRA LDR standards. Following treatment, the solid waste would be volume and size reduced. Depending on the TRU activity, the waste would be repackaged to meet the appropriate waste acceptance criteria, and certified for shipment by DOE.

Incoming boxes of waste would be moved into a glovebox. Waste would be removed from the boxes and placed on the sorting trays using waste removal tools attached to manipulators. RCRA/restricted waste would be segregated for handling in an adjacent treatment station. The remaining waste would be placed in drums and compacted "in-drum" prior to transfer back to the nondestructive examination and assay area for final certification by DOE and shipment to the Waste Isolation Pilot Plant. Secondary waste, such as empty waste containers, personal protective equipment, etc., would also be compacted prior to final certification by DOE and shipment offsite by the contractor to an appropriate disposal facility.

DOE would deliver the concrete casks containing remote-handled solid waste to the proposed waste treatment facility. Foster Wheeler would inspect and survey the waste upon receipt and then transfer the cask inside the facility. Treatment is initiated by raising the cask into a docking position with a hot cell to

allow access to the cask lid from inside the hot cell. The contents of the cask would be removed using waste removal tools mounted on an overhead crane. Any oversized remote-handled TRU waste that is too large to fit into a canister would be size reduced. Waste would be placed in trays and conveyed through a nondestructive examination and assay station. A local gamma detector would identify any contact-handled waste, which would be routed directly to the contact-handled solids treatment glove box for treatment as discussed above. Waste that is compliant with LDR standards would be compacted and loaded into canisters docked at the load-out port on the hot cell. Higher activity low-level waste segregated in the sorting operation would be loaded into shielded drums at a separate load-out port for waste certification by DOE. Waste that does not meet RCRA LDR standards will be treated via macroencapsulation or other methods to meet RCRA LDR standards in the event that unanticipated storage is required. Macroencapsulation refers to a process where waste materials are embedded in an inert material.

2.4.3 Schedule of Activities

The total duration of the Low-Temperature Drying Alternative would be approximately 11.5 years, with less than 5 years of waste treatment, during which off-site shipments of treated waste to the appropriate disposal facility would occur. The proposed waste treatment schedule minimizes environmental impacts by combining the tank and solid waste treatment timelines, thus optimizing the sorting and segregation of TRU wastes for shipment to the Waste Isolation Pilot Plant and low-level waste for shipment to the Nevada Test Site. The schedule is designed to enable shipments to be certified by DOE for acceptance at the designated disposal facility within a reasonable time frame. It also allows the reduction in peak personnel loading and related personnel support facilities. The Low-Temperature Drying Alternative would consist of four phases. The four phases are depicted in Figure 2-6, with further schedule detail provided in Figure 2-7 for the treatment of the tank wastes and solid wastes, during which time off-site shipment of treated waste would occur.




Figure 2-6. The Low-Temperature Drying Alternative would take place over a period of approximately 11.5 years.




Figure 2-7. Waste treatment would be completed in approximately 5 years utilizing the Low-Temperature Drying Alternative.

2.5 VITRIFICATION ALTERNATIVE

The Vitrification Alternative would convert the sludge and supernate waste into a stabilized glass form, and segregate and super-compact the solid contact-handled TRU and remote-handled TRU solid wastes.

2.5.1 Facility Description

The facility for the Vitrification Alternative would be located on 2 to 2.8 ha (5 to 7 acres) west of the Melton Valley Storage Tank facility as indicated in the Proposed Action. The vitrification facility would be a three-and-one-half-story, steel-framed structure measuring 46 m × 76 m × 14 m (150 ft × 250 ft × 45 ft) with concrete and steel shielding. The total floor area would be approximately 7,400 m^2 (80,000 ft^2), with an estimated 2,800 m^2 (30,000 ft^2) for the process area and 4,600 m^2 (50,000 ft^2) for the process support area. Doublewide trailers would be brought onsite to provide a detached administration area of approximately 740 m^2 (8,000 ft^2).

2.5.2 Waste Treatment Description

The waste treatment for the Vitrification Alternative consists of sorting, compaction, grouting, and vitrification (changing the waste to a stable glass form by melting) to treat the waste (Figure 2-8). The vitrification system would treat liquids, soils, sludges, and other materials that are smaller than the RCRA definition of debris. A first-pass material balance for the vitrification treatment of remote handled TRU sludges, a material balance for the contact-handled TRU solid waste, and three material balances for the remote-handled TRU solid waste are presented in Appendix B, in the section covering Vitrification Alternative details. Assumptions used to develop these material balances and to determine a final stabilized waste form were based on information about the vitrification facilities at West Valley, New York, and Hanford, Washington, and the Melton Valley Storage Tanks treatability studies (Spence and Gilliam 1998). The assumptions also considered the characteristics of the existing waste. The Vitrification Alternative would implement several pollution prevention and waste minimization measures. As pollution prevention measures, storm water would be diverted around the facility and gate valves would be installed in the diversion basins to contain spills. Waste minimization would be accomplished by the following methods:

- Tank supernate would be used as the mixing media for sludge retrieval in the Melton Valley Storage Tanks.
- A cold cap would be maintained on the molten glass in the melter to minimize the loss of volatile organics to the atmosphere. A cold cap is molten glass that has cooled to form an impermeable layer (i.e., solid glass layer) on top of the molten glass.
- The solid waste drums would go through an initial characterization process. Drums not needing sorting and repackaging would be sent directly to the super-compactor for a 50% to 80% volume reduction.
- The off-gas system would minimize air emissions.

A summary of volumes of primary, secondary, and D&D waste streams are included in Table 2-2.




Figure 2-8. Treatment flow diagram for sludge, supernate, and solid waste smaller than the RCRA definition of debris for the Vitrification Alternative.

Table 2-2. Summary of projected waste volumes for the Vitrification Alternative

Waste Stream	Category	Projected Volume Out[a]	Treatment Requirement
Primary Waste Streams			
Sludge/Supernate	TRU	577 m^3	Vitrification
Contact-handled solids	TRU	260 m^3	Various
Remote-handled solids	TRU	116 m^3	Various
Remote-handled solids	Low-level waste	87 m^3	Various
Secondary Waste Streams			
Primary waste containers			
Remote-handled casks	Low-level waste	946 m^3	Volume reduction
Contact-handled drums and boxes	Low-level waste	44 m^3	Volume reduction
Construction debris	Sanitary	200 m^3	None
PPE (gloves, booties, etc.)[b]	Low-level waste	315 m^3	Volume reduction
HEPA filters[b]	Low-level waste	82 m^3	Volume reduction
Consumables (rags, towels, etc.)[b]	Low-level waste	181 m^3	Volume reduction
Mechanical/maintenance items	Low-level waste/TRU	97 m^3	Volume reduction
Industrial waste water	Low-level waste/ sanitary	1,108 m^3	Capture
Evaporator concentrate	Low-level waste	326 m^3	Cementation
Laboratory solvents and residues	Low-level waste/mixed waste/TRU	2 m^3	Vitrification, stabilization
Sanitary solids	Sanitary	718 m^3	Capture
Sanitary wastewater	Sanitary	6,283 m^3	Capture
Decontamination and Decommissioning Waste Streams			
Concrete rubble	Construction debris	20,712 m^3	None
Free release metals	Recycle, reuse	120 m^3	None
Non-contaminated metals	Construction debris	48 m^3	None
Contaminated materials	Low-level waste	1,894 m^3	Volume reduction
Vitrified and residual material	TRU	10 m^3	None
Special materials	Low-level waste/mixed waste	2 m^3	Stabilize, special treatment

[a]Volumes are waste product volumes in the final disposal containers.
[b]If the waste is determined to be hazardous, the waste would also be macroencapsulated
HEPA - High-Efficiency Particulate Air. TRU - transuranic.
PPE - personal protective equipment.

2.5.2.1 Tank waste treatment (sludge and supernate)

Retrieved sludge and supernate from the Melton Valley Storage Tanks would remain commingled and then immobilized in a soda-lime-silica glass matrix to form a TRU waste product that meets both RCRA LDR standards and the Waste Isolation Pilot Plant waste acceptance criteria. In the Melton Valley Storage Tanks sludge treatability study (Spence and Gilliam 1998), tests were conducted on the Melton Valley Storage Tanks sludge using soda-lime-silica glass formers. The treated waste (i.e., glass sample - Melton Valley Storage Tank - V-18) had a specific gravity of 2.8, which indicated a waste loading (by mass) of 41%. The specific gravity helps to correlate the leachability of the waste and the stability of the waste form, and helps determine if the volume of treated waste is optimized. The sludge and supernate treatment process can be subdivided into four subsystems: the waste retrieval/receipt system, the melter feed preparation system, the melter system, and the off-gas treatment system.

Retrieved waste sludge and supernate would enter the treatment facility through the waste retrieval/receipt system (Figure 2-8). This system would provide buffer storage between the treatment facility and the waste retrieval system, and homogenize the sludge and supernate mixture for feed characterization (which will also determine the required glass former blend). Sludge and supernate retrieval operations would be conducted in the Melton Valley Storage Tanks using pulsed jet mixing, rather than sluicing, which would allow the existing supernate in the Melton Valley Storage Tanks to be used as the "mixing" media. Treating one tank at a time, the sludge would be mobilized and pumped to one of two sludge/supernate waste receipt tanks at the facility. Waste retrieval operations would be conducted only during day shifts with operations personnel stationed at a control module at the Melton Valley Storage Tanks and at the treatment facility control room.

The stainless steel waste receipt tanks would provide feed for 7 days of full operations for the melter system. This would minimize the impact on waste treatment due to downtime in the retrieval system, or hard-to-retrieve sludge. The waste receipt tank would be isolated from the retrieval system once it is filled. The second tank, if available, becomes the waste retrieval tank. A mechanical agitator would homogenize the waste to prevent solids from settling in the waste receipt tank. Homogenized waste would be sampled to determine the chemical and radiochemical composition for Waste Isolation Pilot Plant waste certification requirements, and to confirm that the treatment facility is meeting operational parameters. Once the analysis results confirm that the composition is acceptable, the waste receipt tank is considered part of the melter feed preparation system.

The melter feed operations include preparation of the dry glass-forming chemicals, mixing the dry chemicals with the homogenized waste stream, and feeding the resultant slurry to the melter. Glass-forming chemicals anticipated to be used for waste treatment include: soda (Na_2CO_3 - to get the alkali component: Na_2O), lime (CaO), and silica (SiO_2 - for glass forming). Alumina may also be used for glass forming. Based on the average concentrations and information provided from the treatability studies (Spence and Gilliam 1998), the glass former blend would be approximately 14.3% $CaCO_3$, 41% dried waste, and 44.7% SiO_2. Batches of waste and glass-forming compounds would be prepared for 24 hours of melter operations. The appropriate quantity of glass-forming components would be measured and fed into a hopper. An appropriate amount of homogenized waste would be transferred into a feed preparation tank along with the glass-forming chemicals from the hopper. Once the waste and dry chemicals are blended, a pump would transfer the blend to the melter feed tank. A mechanical agitator in the feed tank would keep the contents homogenous and to prevent solids settling.

The melter would have a throughput of 2 metric tons of glass per day and a minimum availability of 70%, equivalent to 260 operating days per year on a 7-day, around-the-clock basis. The glass product would occasionally be sampled to confirm that chemical composition is within the required range to produce acceptable quality glass. The melter would be a slurry-fed, joule-heated, ceramic unit, operating at a temperature of approximately 1,150°C (2,100°F). The melter would include a few safety features, such as a water-cooled refractory to contain the glass and a cold cap of unmelted glass floating on the glass surface. The cold cap helps minimize the loss of volatile chemicals to the off-gas system. Most of the feed components would be converted to their oxides, which dissolve in the molten glass. During the decomposition process, gases would be formed, heated, and released into the melter plenum and routed to the off-gas system. A fraction of the feed components would be directly carried over to the off-gas system without incorporation into the glass. However, some components would be volatile in the melter, and a significant fraction of these materials would be released to the off-gas system. The solids and semi-volatile components would be recycled back to the melter from the off-gas system to increase the incorporation rate for these components in the glass.

The major components of the off-gas resulting from the melter's thermal processes would be nitrogen and oxygen due to air in-leakage to the melter and decomposition reactions occurring in the

melter. Other major components of the off-gas would be superheated steam from the evaporation of water, and NO_x from decomposition of metal nitrates. Chloride, fluoride, and SO_x would also be present due to feed decomposition, although in low concentrations compared to NO_x. The off-gas treatment system would exhaust gases from the melter plenum, maintain the melter at a negative pressure in relation to its cell, and clean the off-gas prior to stack discharge. The off-gas treatment system would consist of a primary system and a secondary system.

The primary off-gas treatment system would consist of three components: a film cooler, an off-gas quencher/scrubber, and a demister. This system would remove particulate carryover from the melter into the off-gas, the majority of radionuclides, a substantial amount of the acid gasses, and cool the off-gas prior to further treatment. The film cooler would cool the exiting off-gas to between 350 and 400°C (662 to 752°F) by injecting compressed air into the off-gas stream. The off-gas would then be drawn into an off-gas quencher/scrubber to further cool the off-gas. Hastelloy C or other similar metal alloys would be used for construction of the scrubber due to the high corrosion rate [> 0.05 in./year (Perry and Chilton 1973)] caused by the heat and high concentrations of halogen acid gases in the off-gas. The scrubbing agent could be water or slightly basic caustic. The scrubbing agent liquid would be collected and recycled back into the treatment process (as sluicing water that has better solubility capacity than supernate), or treated and disposed of as a secondary waste. Immediately downstream of the scrubber would be a pair of demisters. The demisters would remove mist and particulates from the off-gas stream, including the 90% or more of the remaining radionuclides in particulate form. The demisters would be washed regularly to prevent damaging downstream equipment such as pumps. Used demister wash liquid would be collected in a sump and recycled to help mobilize the sludge, or reprocessed.

The secondary off-gas treatment system performs final particulate filtration prior to stack discharge and consists of four HEPA filters in parallel sets of two. Each HEPA filter removes up to 99.95% of the remaining particulates in the off-gas stream. Gases (primarily air) leaving the HEPA filters are directed to the off-gas stack. Previous vitrification analysis conducted at DOE's Hanford site indicates that approximately 40% of the nitrate feed would be converted to nitrogen by the melter. Thus, it is possible that emissions from this treatment method would be below the Tennessee permit exemption levels without additional off-gas treatment systems.

2.5.2.2 Solid waste treatment (remote-handled and contact-handled solids)

In general, the remote-handled and contact-handled solid wastes would be sorted, treated, repackaged, compacted, overpacked, grouted, certified by DOE, and packed in appropriate transport containers. Certified TRU waste would be disposed at the Waste Isolation Pilot Plant, and low-level waste would be disposed at the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000). A small amount of the contact-handled and remote-handled solid wastes would be treated by vitrification if their size is smaller than what RCRA defines as debris. Mixed wastes that are primarily solids with RCRA metal constituents are expected to meet the definition of debris and would be macroencapsulated (embedded in an in inert material) per the alternative treatment standards found in 40 *CFR* 268.45, Table 1. The treated waste would meet RCRA LDR standards in the event that unanticipated storage is required onsite. Materials not considered debris would be segregated and treated at the facility to allow disposal.

The solid waste treatment train would be remotely operated, and primary subsystems include solid waste receipt, the solid waste pretreatment system, the compaction and repackaging systems, and the macroencapsulation system (Figure 2-9). Solid waste containers would be unloaded in the solid waste receipt area and monitored for surface radiation dose level and contamination. Remote-handled solid waste would not be received until all of the contact-handled solid waste is processed. The wastes would

be brought to the second floor bay area. This buffer storage area would remain at a minimal level (approximately one full week of treatment).




Figure 2-9. Vitrification Alternative flow diagram for solid waste treatment.

Solid waste would be characterized by nondestructive examination and assay methods, such as High Resolution Gamma Spectroscopy and passive and active neutron analysis, to determine the fissile content. Some containers may not require repackaging if their contents are confirmed as debris by real-time radiography. All other waste containers would be transferred to the hot cell for characterization. Solid wastes that may contain hazardous constituents, such as lead and mercury, would be treated in the Special Treatment Operations area. Special waste material such as batteries, aerosols, and gas bottles, would be sorted from the debris waste, collected, and sent to a special treatment cell, or some other applicable treatment facility. The sorting would be done with a remote manipulator; however, if dose limits are sufficiently low (e.g., less than 10 mrem/hour), some of the wastes contained in 30- and 55-gal drums may be sorted by hand. Some material (e.g., metal) may be resized in order to maximize the waste volume in a sorted container. Sorted waste containers would be sent to the supercompactor.

Drums of repackaged contact-handled and remote-handled solid wastes would be characterized and weighed before compaction to provide the information for DOE waste certification. The compacted repackaged waste would be in the form of a puck between one-half to one-fifth of the height of the original container. Waste pucks would be cataloged for size, weight, and activity and then placed in 55-gal drums in such a manner to ensure full encapsulation by the grout (the assumed macroencapsulating

material). Grout would be metered to ensure encapsulation around the pucks. The grouted overpack container would be placed into the buffer storage area until the grout has set.

2.5.3 Schedule of Activities

The total project duration of the Vitrification Alternative would be approximately 10 years, with about 3 years of waste treatment, during which offsite shipments of treated waste to the appropriate disposal facility would occur. Following 3 months of cold commissioning after construction of the facility, hot operations would be conducted for a period of 2.75 years. This treatment schedule combines the tank and solid waste treatment timelines and adjusts shift requirements to balance the life cycle of operations while minimizing duplication of treatment unit operations and treatment equipment. This approach would allow for reduction in peak personnel loading (except during construction activities) and related personnel support facilities. Contact-handled solids would be treated first and would normally proceed at a rate of approximately 13 drum equivalents per day on a 2-shift, 5-day basis. The remote-handled solids treatment would proceed at a rate of approximately 0.7 casks per shift on a 2-shift, 5-day basis. Contact-handled solid waste treatment would require approximately 1.25 years of operations, and remote-handled solid waste treatment would require 1.5 years. The overall project schedule is depicted in Figure 2-10, and details of the waste treatment schedule are provided in Figure 2-11.

Vitrification Alternative Schedule




Figure 2-10. Vitrification Alternative project schedule.

Vitrification Alternative Waste Treatment Schedule




Figure 2-11. Vitrification Alternative waste treatment schedule.

2.6 CEMENTATION ALTERNATIVE

The Cementation Alternative consists of sludge and supernate separation by hydrocyclone/centrifuge pre-treatment and subsequent cementation for the tank wastes, and segregation and supercompaction for the contact-handled and remote-handled solid wastes.

2.6.1 Facility Description

The facility for the Cementation Alternative would be located within an approximate 2-ha (5-acre) plot of land located immediately west of the Melton Valley Storage Tanks. The process building would be a three-and-one-half-story structure. The facility would be a 37 m × 61 m × 14 m (120 ft × 200 ft × 45 ft) steel-framed structure with concrete and steel shielding. The total floor area of the cementation facility would be approximately 5,575 m^2 (60,000 ft^2), with an estimated 1,860 m^2 (20,000 ft^2) for the process area and 3,720 m^3 (40,000 ft^2) for the process support area. Doublewide trailers would be brought onto the site to provide approximately 560 m^2 (6,000 ft^2) for the administration area that would be detached from the process building.

2.6.2 Waste Treatment Description

The cementation technology is based on operations conducted at DOE's Hanford facility near Richland, Washington, and information provided in a feasibility study (Parallax 1995). As pollution prevention measures, storm water would be diverted around the facility and gate valves would be installed in the diversion basins to retain spills. The off-gas system would minimize air emissions, and liquid used for the decontamination of the cementation treatment system would be transferred back into the cementation treatment system as waste minimization measures. A summary of volumes of primary, secondary, and decontamination and decommissioning waste is included in Table 2-3.

2.6.2.1 Tank waste treatment (sludge and supernate)

Supernate and sludge would be transferred to the proposed facility though an above ground double-contained pipeline. Sludge would be removed from the tank by sluicing. The Cementation Alternative would use hydrocyclone and centrifuge waste pre-treatment to separate the supernate from the sludge. The majority of the liquids would be recycled through the Melton Valley Storage Tanks for sludge mobilization. After separation, the pretreated sludges and supernates would be treated by cementation (Figure 2-12). The facility would oscillate between treatment for supernate and treatment for sludge.

The initial step would be pretreatment to remove excess liquid from the sludge/supernate mixture following sludge retrieval. The pretreatment process would include storage tanks for the sludge/supernate, feed tanks for the cement mixer, metering equipment for pH adjustment additives, and associated pumps and instrumentation. A hydrocyclone in series with a centrifuge would separate the sludge from the supernate. The hydrocyclone is a centrifugal device with no moving parts. Solids from the hydrocyclone would gravity drain into the feed tank. The centrifuge would receive the effluent from the hydrocyclone and then provide a sufficiently high gravity force to effectively remove suspended solids ranging from 1 to 20% weight, with particle sizes ranging from 2 to 150 μm, at a flow rate up to 60 gal per minute (actual flow rate would be dependent on the rate of sludge and supernate retrieval from the Melton Valley Storage Tanks). A back-drive system would be included with the centrifuge design to maintain a desired slurry discharge of 25% weight total suspended solids. A supernate collection tank would temporarily hold the liquid streams from the hydrocyclone and centrifuge before the supernate is pumped back for sludge mobilization.

Table 2-3. Summary of projected waste volumes for the Cementation Alternative

Waste Stream	Category	Projected Volume Out[a]	Treatment Requirement
Primary Waste Streams			
Sludge	TRU	1,287 m^3	Cementation
Supernate	Remote-handled low-level waste	2,453 m^3	Cementation
Contact-handled solids	TRU	260 m^3	Various
Remote-handled solids	TRU	116 m^3	Various
Remote-handled solids	Remote-handled low-level waste	87 m^3	Various
Secondary Waste Streams			
Primary waste containers			
Remote-handled casks	Low-level waste	946 m^3	Volume reduction
Contact-handled drums and boxes	Low-level waste	36 m^3	Volume reduction
Construction debris	Sanitary	200 m^3	None
PPE (gloves, booties, etc.)[b]	Low-level waste	384 m^3	Volume reduction
HEPA filters[b]	Low-level waste	83 m^3	Volume reduction
Consumables (rags, towels, etc.)[b]	Low-level waste	257 m^3	Volume reduction
Mechanical/maintenance items	Low-level waste/TRU	130 m^3	Volume reduction
Laboratory solvents and residues	Low-level waste/ mixed waste/TRU	2 m^3	Vitrification, stabilization
Sanitary solids	Sanitary	2,217 m^3	Capture
Sanitary wastewater	Sanitary	5,020 m^3	Capture
Decontamination and Decommissioning Waste Streams			
Concrete rubble	Construction debris	14,111 m^3	None
Free release metals	Recycle, reuse	77 m^3	None
Non-contaminated metals	Construction debris	32 m^3	None
Contaminated materials	Low-level waste	1,127 m^3	Volume reduction
Special materials	Low-level waste/ mixed waste	1 m^3	Stabilize, special treatment

[a]Volumes are waste product volumes in the final disposal containers.
[b]If the waste is determined to be hazardous, the waste would also be macroencapsulated.
HEPA - High-Efficiency Particulate Air. TRU - transuranic.
PPE - personal protective equipment.

The stainless steel feed tanks would be sized to allow continuous transfer of the sludge and supernate to the cementation facility. The feed tanks would be filled by the bottoms discharge of the hydrocyclone and centrifuge, and would contain approximately 25% weight total suspended solids. The feed tanks could also perform as settling tanks, if maintenance downtime is required for the centrifuge or hydrocyclone. Agitators would provide the required continuous mixing of the sludge, and a decant pump would remove any excess effluent. The feed tanks would be plumbed for metering the pH adjustment solution (e.g., HCl and NaOH). The metered waste slurry would be transferred from the feed tanks to the cementation batch process system using positive displacement pumps (Figure 2-12).

A dry blend storage tank assembly would store the premixed cementation/stabilization agents, and would consist of feed input, storage, and feed transfer systems. Premixed cementation/stabilization blends would be conveyed pneumatically to the storage bin. In-line sampling capability would be provided for the pneumatic feed conveyance system to verify the premix chemistry. Storage of the stabilization




Figure 2-12. Flow diagram for tank waste treatment for the Cementation Alternative.

mixture would be provided by a vibrating bottom hopper fitted with mechanically activated level switches, and air pulse mixing that would be ducted to a baghouse and eventually to HEPA filters for air discharge. The feed transfer system would include a weigh belt feeder, transfer conveyor, transport blower, and tramp screen that feeds stabilization mixtures through a rotary valve. A truck would deliver the dry blend to the treatment facility, for deposit into the dry blend storage tank, which would contain enough premixed blend to process sludge for 5 to 7 days. Approximately 7 lbs of dry blend consisting of 33, 20, 19, 20, and 20% weight of slag, cement, fly ash, perlite, and Indian Red Pottery Clay, respectively, (Spence and Gilliam 1998) would be added per gallon of sludge to obtain a stable treated waste product. Approximately 11 lbs of dry blend would be added per gallon of supernate, and would consist of 40, 40, 16, and 4% weight of slag, cement, fly ash, and perlite, respectively.

The dry blend premix would be transferred through the vibrating bin bottom and injected with air for fluidization, then through a rotary airlock to a weigh belt feeder into the cementation mixer. The feed tank metering pump would transfer the waste slurry to the mixer. The cementation mixer is a high-energy, low-shear, twin-screw device that gravity discharges the cement blend into a conical surge tank. The surge tank includes an agitator, and an integral pump controls its level. A grout pump would discharge the waste slurry mixture into 50-gal drum liners. The drum liners would be filled by weighing and float control instrumentation. Approximately three 50-gal carbon steel liners could be filled on an hourly basis. The filled liners would remain on the conveyor system for a minimum of 4 hours to allow the cement to

harden, then the liners would be placed inside 55-gal carbon steel overpack drums. A remote manual manipulator would perform external surface contamination analysis of the overpack drums. After passing the analysis, the drums would be transferred to the interim storage area before placement into remote-handled canisters and, ultimately, 72-B casks. It is anticipated that operations would oscillate between cementation of sludge and cementation of supernate on a weekly basis. The treated supernate would be remote-handled low-level waste and would be disposed of at the Nevada Test Site. The treated TRU sludge would be disposed of at the Waste Isolation Pilot Plant.

In addition to the dust collection and filtration (i.e., a baghouse and HEPA filters) for the grout dry blending mixture, particulate emissions would be collected using HEPA filters. The cementation mixing process would contain several spray nozzles to clean the mixer, conveyors, surge tank, and the liquid collection tank. Decontamination chemicals would be used with a cementation pipeline-clearing pump to flush the lines each time the process is stopped, with discharge routed to a liquid collection tank. The contents of the liquid collection tank would be pumped to the pretreatment process for separation and transfer to the supernate collection tank for cementation treatment.

2.6.2.2 Solid waste treatment (remote-handled and contact-handled solids)

In general, treatment of the remote-handled and contact-handled solid waste would include waste receipt, assaying, opening, sorting, treatment, repacking, compaction, overpacking, grouting, DOE certification, packing in transport containers, and transport to the appropriate disposal facility. The solids treatment for the Cementation Alternative is identical to the Vitrification Alternative. Please refer to Section 2.4.2.2 for detailed information about this process.

2.6.3 Schedule of Activities

The total project duration of the Cementation Alternative is approximately 12.5 years, with 6 years involving waste treatment, during which offsite shipments of treated waste to the appropriate disposal facility would occur. The Cementation Alternative would require a longer waste treatment time, which would reduce the radiochemical and particulate emissions in a given year. The longer treatment time is due to the availability of shipments to the Waste Isolation Pilot Plant. The longer treatment time is a result of the shipment capacity allotment given by the Waste Isolation Pilot Plant to each approved shipper of certified TRU waste. (If the allocated shipment allotment from the Waste Isolation Pilot Plant were not a limiting factor, the sludge and supernate could be treated by this alternative treatment method in 1 or 2 years. The Cementation Alternative's treatment schedule for the waste streams was developed to keep the same number of operating shifts as required for sludge treatment to minimize operating the equipment. This approach would also allow for reduction in peak personnel loading and related personnel support facilities. The overall project schedule is depicted in Figure 2-13. Further schedule detail for the tank and solid waste treatment is provided in Figure 2-14.

Waste treatment would be conducted in the cementation facility for a period of 6 years with a designed treatment rate of 1.25 gal per minute of sludge/supernate. In order to process the sludge and supernate in 6 years, the cementation facility would need to be operational at least 70% of the year and would require one 8-hour shift per day for 5 days a week. Contact-handled solids would be treated first and would normally proceed at a rate of approximately 6.5 drum equivalents per day on a 1-shift, 5-day basis. Contact-handled solid waste treatment would require approximately 2.5 years of operations. The remote-handled solid wastes would be treated after the contact-handled solids and would proceed at a rate of approximately 0.7 casks per shift on an 8-hour shift per day, 5-day basis. Remote-handled solid waste treatment would require 3 years, based on the facility being operational 80% of the year.




Figure 2-13. The Cementation Alternative Schedule shows the project would take approximately 12.5 years to complete.




Figure 2-14. The Cementation Alternative waste treatment schedule would take approximately 6 years.

2.7 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE

DOE intends to ship treated waste offsite for disposal as soon as the waste is treated. However, in the event that disposal capacity is unavailable immediately upon completion of waste treatment, DOE has included the Treatment and Waste Storage at ORNL Alternative to provide safe, interim, on-site storage capacity until off-site disposal capacity is available.

This alternative would entail waste treatment by any of the three previous treatment alternatives (low-temperature drying, vitrification, or cementation) and interim waste storage at ORNL rather than immediate shipment to an off-site disposal facility (i.e., the Waste Isolation Pilot Plant for TRU waste, and the Nevada Test Site for low-level waste). Treated remote-handled wastes would require remote handling during on-site storage at ORNL because of the associated doses. Implementation of this alternative would result in noncompliance with the milestone established in the TDEC Commissioner's Order requiring the submittal of a Project Management Plan (which includes schedules for treatment and shipment) by September 30, 2001. In addition, this alternative would jeopardize the existing "target date" established in the TDEC Commissioner's Order for initiation of shipment of the stabilized remote-handled TRU sludges to the Waste Isolation Pilot Plant by January 2003. For purposes of analysis, DOE has evaluated a 100-year institutional control period, after which there would be a loss of institutional control.

2.7.1 Facility Description

2.7.1.1 Waste treatment facility

Because this alternative would include waste treatment by any of the three treatment alternatives previously described, please refer to these previous sections for a description of the waste treatment facilities for low-temperature drying, vitrification, and cementation.

Waste Treatment Facility Description	Section
Low-Temperature Drying	Section 2.4.1
Vitrification	Section 2.5.1
Cementation	Section 2.6.1

2.7.1.2 Waste storage facilities

On-site waste treatment would result in primary, secondary, and D&D waste streams that would consist of remote-handled TRU waste; contact-handled TRU wastes; low-level waste; remote-handled low-level waste; and mixed waste, which would require on-site storage at ORNL. This alternative would require the construction of new waste storage facilities. Several assumptions were made to determine the storage space required for the waste streams resulting from waste treatment.

1. It was assumed that a required engineering analysis would indicate that the existing storage bunkers for remote-handled and mixed waste (Buildings 7855 and 7883) could be used to store treated TRU and remote-handled low-level wastes. These bunkers would provide 320 m^3 of storage capacity.
2. It was assumed that the existing metal buildings that store contact-handled TRU waste (Buildings 7572, 7574, 7842, 7878, and 7879) would be used for treated low-level waste storage. These buildings would provide 1,631 m^3 (57,632 ft^3) of storage capacity for low-level waste.
3. It was assumed that the new storage facilities would have similar waste storage capacities [approximately 150 m^3 for each remote-handled waste bunker, and approximately 300 m^3 (10,600 ft^3) for each metal building].

4. It was assumed that the building footprints (area) for the new storage facilities, and for their construction, would be similar to the existing storage facilities (234 m^2 remote-handled waste storage bunkers and 375 m^2 metal storage buildings for low-level waste).
5. It was assumed that the new waste storage facilities would be located in the Melton Valley area of ORNL, preferably near the waste treatment facility or the existing TRU waste storage facilities.

Tables 2-4a, -b, and -c provide a summary of the resulting waste volumes of the three waste treatment alternatives and the new storage space required for the resulting waste streams. The construction of new waste storage facilities would need to coincide with the construction of the selected waste treatment facility in order to be ready for the receipt of the treated waste streams. The number of new storage facilities needed for the treated wastes would be dependent on the treatment method chosen. DOE considered the need for additional shielding when the space requirements for additional storage capacity were calculated.

2.7.2 Waste Treatment Description

This alternative would include waste treatment by any of the three treatment approaches previously described (low-temperature drying, vitrification, or cementation), and then interim storage onsite at ORNL. Please refer to these previous sections for the descriptions of the waste treatments that would be implemented if this alternative were selected.

Waste Treatment Description	Section
Low-Temperature Drying	Section 2.4.2
Vitrification	Section 2.5.2
Cementation	Section 2.6.2

2.7.3 Schedule of Activities

This alternative would include interim storage of the waste at ORNL following waste treatment. For purposes of analyses, institutional control is assumed for a period of 100 years, followed by a loss of institutional control. The schedules for waste treatment were discussed in previous sections, as noted below. Construction of additional waste storage facilities would need to coincide with the construction of the waste treatment facility in order to have facilities available to store the treated wastes following waste treatment and repackaging. It is assumed that the schedules would be similar to the facility construction schedule, which would allow for about 2 years for construction.

Waste Treatment and D&D Schedule	Section
Low-Temperature Drying Alternative	Section 2.4.3
Vitrification Alternative	Section 2.5.3
Cementation Alternative	Section 2.6.3

Table 2-4. Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (includes D&D waste), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities

	Low-Temperature Drying	Vitrification	Cementation
Table 2-4a. Summary of the TRU, mixed low-level, and remote-handled low-level waste volumes and new storage space required			
Treated TRU waste volume (m^3)[a]	607	1,060	1,793
Mixed low-level waste volume (m^3)	23	4	3
Treated remote-handled low-level waste volume (m^3)	–	–	2,540[b]
Total TRU, mixed, and remote-handled low-level waste requiring on-site storage (m^3)	630	1,064	4,336
Existing waste bunkers storage capacity (m^3)	320	320	320
New storage capacity needed (m^3)[c]	310	744	4,016
Assumed capacity of single new waste bunker (m^3)	150	150	150
Number of new waste bunkers needed	3	5	27
Assumed area of new waste bunker (m^2)	234	234	234
Total Storage Facility Area required for TRU, mixed, and remote-handled low-level wastes (m^2)	702	1,161	6,265
Table 2-4b. Summary of low-level waste volumes and new storage space required			
Total low-level waste requiring on-site storage (m^3)	2,778[a]	4,983[a]	2,833[a]
Existing storage capacity (metal building)	1,631	1,631	1,631
New storage capacity needed (m^3)[c]	1,147	3,352	1,202
Assumed capacity of single new metal building (m^3)	300	300	300
Number of new metal buildings needed	4	11	4
Area of new metal buildings (m^2)	375	375	375
Total area required for low-level wastes (m^2)	1,434	4,190	1,503
Table 2-4c. Total area required for all waste types and the associated land requirements for the new storage facilities			
TOTAL FACILITY SPACE REQUIRED FOR ALL WASTE TYPES (m^2)	**2,136**	**5,351**	**7,768**
TOTAL HECTARES REQUIRED FOR NEW WASTE STORAGE FACILITIES[d]	**0.3**	**0.6**	**0.8**

[a]TRU waste volumes include both remote-handled and contact-handled waste.
[b]Total waste volumes include alpha-low-level waste.
[c]Determined by subtracting available capacity from resulting waste volume and dividing by assumed storage capacity of new facility (150 m^3 for TRU, mixed, and remote-handle low-level wastes, and 300 m^3 for low-level wastes).
[d]Determined by summing storage space required for all waste types, for each treatment method, and converting to hectares.

2.8 ALTERNATIVES CONSIDERED BUT NOT EVALUATED IN DETAIL

2.8.1 Off-site Waste Treatment

Currently there is no facility available or planned at any other DOE site that could treat remote-handled TRU mixed waste sludge and associated low-level waste supernate stored at ORNL. The Idaho National Engineering and Environmental Laboratory (INEEL) is planning to process its contact-handled TRU waste on-site at the planned Advanced Mixed Waste Treatment Project facility. DOE is not currently legally prohibited from shipping waste to the INEEL to be treated so long as the waste is treated and leaves INEEL within a specified time period. However, using the planned INEEL facility to treat ORNL TRU waste would be difficult for the following reasons:

- Because the planned INEEL facility is being constructed to process the contact-handled TRU waste at INEEL, the ORNL remote-handled TRU waste is not likely meet the planned facility's waste acceptance criteria.

- Most of the ORNL remote-handled and contact-handled TRU/alpha low-level solid waste containers do not meet DOT standards (49 *CFR* 173). These containers would require repackaging prior to transport offsite; therefore, it would be safer and more economical for the treatment of solid waste to be conducted at ORNL, and for the treated TRU waste to be shipped directly to the Waste Isolation Pilot Plant, and the treated low-level waste to be shipped directly to the Nevada Test Site.

- After treatment at INEEL, the ORNL treated waste would require a second redundant step of repackaging and DOE certification before the waste could be transported to the Waste Isolation Pilot Plant or the Nevada Test Site, resulting in additional worker exposures and cost.

Treatment of the ORNL TRU wastes at INEEL is unreasonable because of the increased costs and risks associated with preparing the tank waste for shipment, repackaging and certifying the waste twice, transporting the waste to INEEL for treatment, and then transporting the treated waste to the Waste Isolation Pilot Plant or the Nevada Test Site as appropriate.

2.8.2 Alternate On-site Treatment Facility Locations

Several factors were considered in selecting the site of the proposed on-site treatment facility. These factors are discussed in Section 2.1 and include minimizing the length of any sludge/supernate waste transfer line from the Melton Valley Storage Tanks to the proposed treatment facility, using the terrain to provide natural shielding for the proposed facility, and considering recommendations made in a Feasibility Study that focused on dealing with the tank wastes (Parallax 1995).

The proposed site is directly west of the Melton Valley Storage Tanks, which is the current storage area for the TRU mixed waste sludge and associated low-level supernate. This location reduces the potential risks associated with transporting the liquid and sludge tank wastes from the Melton Valley Storage Tanks to the proposed treatment facility over public or laboratory roads. Since the solid waste storage facilities are also located in Melton Valley, the transportation of the solid wastes would only occur on laboratory roads, also reducing the risk to the public. Melton Valley, while considered part of ORNL, is separated from the ORNL main plant area by the Haw Ridge (Figure 2-1), thus reducing potential risks to the main body of workers at ORNL from accidental releases. Alternative site locations were not evaluated in detail because other on-site locations did not meet the siting factors.

2.8.3 Alternative Disposal Locations

TRU waste will be disposed of at the Waste Isolation Pilot Plant in accordance with the WIPP SEIS-II Record of Decision (DOE 1998) for TRU waste. All low-level waste resulting from the ORNL TRU Waste Treatment Facility will be disposed of at the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

2.8.4 Alternative Treatment Technologies

Sixteen stabilization and solidification technologies were identified and evaluated as candidates for processing TRU waste sludge in the *Feasibility Study for Processing ORNL Transuranic Waste at Existing and Modified Facilities* (Parallax 1995), but were not analyzed further because they were not considered reasonable (Table 2-5). One of the technologies, plasma arc vitrification, was also identified as potentially useful for solid remote-handled and contact-handled TRU/alpha low-level waste. However, it would not be feasible to use a technology for the solid wastes unless it was also used for the sludge and supernate. Because of cost, scaling, and permitting issues, this technology was eliminated from further consideration.

Table 2-5. Summary of alternatives considered but not evaluated for sludge and supernate waste treatment

Treatment name	Summary description	Rationale for not evaluating
Aquaset II-H[S]	A non-thermal process that utilizes a powdered solidification agent developed for the immobilization of sludge through the action of complex bonding mechanisms and ion exchange reactions.	Not a proven technology, inability to treat multiple waste streams, its lack of ease with retreatment capabilities, and the excess amount of water used during the process.
Catalytic extraction	A thermal process that introduces sludge into a molten metal bath that acts as a catalyst to break down the waste into its elemental constituents.	Extensive chemical formulation is required for each changing waste stream.
Glass-ceramic vitrification	A thermal process that combines sludge with a ceramic feed material, then calcines in a spray calciner.	Not a proven technology for this type of waste and has a low tolerance to feed variations.
Bitumen solidification	A non-thermal process that uses either bitumen or asphalt as a high molecular weight hydrocarbon to encapsulate the sludge.	Gas generation from the degradation of the hydrocarbon material by alpha-emitting radionuclides.
Ceramic vitrification	A thermal process that combines sludge with ceramic powder and glass frits and then forms and heats into bricks in a brick former.	Not a proven technology for this type of waste and has a lower flexibility with treatment various wastes.
Microwave vitrification	A thermal process that combines glass frits and sludge, places the mixture into a microwave cavity, and melts.	Not proven at large scale; lower flexibility with treatment various waste.
In-can glass melting	A thermal process that first dries the sludge to a fine powder in a spray calciner, then combines the fine powder with glass frits and feeds it into a drum for heating.	Lacks multiple waste stream capabilities, lacks retreatment capabilities, and is not a proven technology for ORNL's waste stream.
Titanate	A thermal process that involves mixing supercalcine (a silicate-based material) with sludge and then calcining.	Increased waste loading, sensitivity to sodium waste streams, lack of multiple waste stream capabilities, lack of retreatment capabilities, and not being a proven technology for ORNL's waste stream.
Synroc hot-isostatic pressing	A thermal process that involves calcination of the sludge and then mixing it with synroc additives. Synroc is an acronym for a synthetic, igneous rock system that consists of thermodynamic-compatible minerals having the ability to capture radioactive waste elements in their crystal lattices.	Similar to the Titanate process.
Supercalcine hot-isostatic pressing	A thermal process that involves mixing supercalcine (a silicate-based material) with sludge and then calcining.	Similar to the Titanate process.
Cermet	A thermal process that involves dissolving and mixing sludge and cermet-forming additives in molten urea.	Similar to the Titanate process.
Fluetap concrete	This process combines the sludge with water, cement, fly ash, and clay in a mixer, then transfers the mix into a drum, and places it into an autoclave for 64 hours to accelerate hardening. The drum is then placed in an air-storage for several years to remove the free water from the concrete.	Failed to meet the schedule constraints.
Molten salts	A thermal process that introduces air to the sludge under a surface of a sodium carbonate-containing melt.	Failed to meet Resource Conservation and Recovery Act (RCRA) Land Disposal Restrictions (LDR) standards.
Supercalcine pellets-in-metal	A thermal process that combines supercalcine with sludge. Binders are added and the material is pelletized. The pellets are sintered to form the desired mineral phase, placed in drums, and encapsulated in lead.	Failed to meet RCRA LDR standards.
Marbles-in-lead matrix	A thermal process that creates marbles from a joule-heated molten glass/sludge mixture and then casts the marbles in lead.	Failed to meet RCRA LDR standards.
Polymer encapsulation	A non-thermal process that involves mixing vinyl ester styrene with sludge and then allows to cure in an in-drum mixer.	Failed to meet the Waste Isolation Pilot Plant waste acceptance criteria.

2.9 SUMMARY OF ENVIRONMENTAL IMPACTS

Table 2-6 is a summary of the potential environmental impacts associated with implementing the various alternatives considered in the EIS. These impacts are discussed in detail in Chapter 4, but are summarized here to allow comparison of the alternatives.

Table 2-6. Comparison of impacts among alternatives

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Land use (Chapter 4, Section 4.1)	• No change in land use, land use classifications, or impacts to visual resources during 100-year institutional control period • Assuming loss of institutional control, the land would be permanently committed to waste storage	• No change in land use classification • 2 hectares (ha) (5 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 to 2.8 ha (5 to 7 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 ha (5 acres) would change from underdeveloped to industrial use • Buildings and other structures would be visible to workers but not the public	• No change in land use classification • 2 to 2.8 ha (5 to 7 acres) would change from underdeveloped to industrial use • For waste storage after treatment, an additional 0.3 ha (0.75 acre) of land would be required if treatment was by low-temperature drying, 0.6 ha (1.5 acres) of land if by vitrification, or 0.8 ha (2.0 acres) of land if by cementation • Buildings and other structures would be visible to workers but not the public • Assuming loss of institutional control, the land would be permanently committed to waste storage
Cultural and historic resources (Chapter 4, Section 4.2)	• No cultural, archeological, or historic resources in project area	• Same as No Action Alternative	• Same as No Action Alternative	• Same as No Action Alternative	• Same as No Action Alternative

ha = hectare.
ORNL = Oak Ridge National Laboratory.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Ecological resources (Chapter 4, Section 4.3)	• Continued release of waste constituents from SWSA 5 North trenches to soils and groundwater affecting biota • No habitat destruction under continued storage • Minimal impact (HQ for aquatic biota at steady-state would be 7×10^{-7}) from slow release of MVSTs wastes after loss of institutional control • Assuming loss of institutional control, wastes from SWSA 5 North trenches, bunkers, and buildings would serve as long-term contaminant sources	• 2 ha (5 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• 2 to 2.8 ha (5 to 7 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from trenches under SWSA 5 North CERCLA	• 2 ha (5 acres) of forested habitat lost and converted to industrial use (revegetated after facility D&D) • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• 2 to 2.8 ha (5 to 7 acres) of forested habitat lost and converted to industrial use • Low-quality habitat indefinitely lost for on-site waste storage facility construction; 0.3 ha (0.75 acre) of land required if treatment by low-temperature drying, 0.6 ha (1.5 acres) of land if by vitrification, and 0.8 ha (2.0 acres) of land if by cementation • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA • Assuming loss of institutional control, waste constituents would eventually be released but impacts would be less than No Action because the wastes would be treated and better contained

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
D&D = decontamination and decommissioning.
ha = hectare.
HQ = hazard quotients.
MVSTs = Melton Valley Storage Tanks
ORNL = Oak Ridge National Laboratory
SWSA 5 North = Solid Waste Storage Area 5 North

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Geology and seismicity (Chapter 4, Section 4.4)	• No impact to geology or regional seismicity • No construction-related impacts to soils or geology • Continued release of waste constituents from the SWSA 5 North trenches to soils during and after loss of institutional control • Eventual release of wastes from MVSTs and SWSA 5 North bunkers and buildings into soils after loss of institutional control	• No impact to geology or regional seismicity • 2 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2.8 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• No impact to geology or regional seismicity • 2 to 2.8 ha of soil disturbed • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA • Eventual release of constituents of treated waste after loss of institutional control

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
ha = hectare.
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Surface water (Chapter 4, Section 4.5.1)	• Continued release of waste constituents from the SWSA 5 North trenches to surface water during and after loss of institutional control • Eventual release of long-lived radionuclides from MVSTs and SWSA 5 North bunkers and buildings into surface water	• Potential for increased siltation in White Oak Creek, Melton Branch, and an unnamed tributary • Reduction of soil and water contamination because treatment would be available for waste to be removed from SWSA 5 North trenches under CERCLA	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during institutional control • After loss of institutional control, waste constituents would eventually be released but impacts would be less than No Action because wastes are treated and better contained
Groundwater (Chapter 4, Section 4.5.2)	• No groundwater use • Continued release of waste constituents from SWSA 5 North trenches during and after loss of institutional control • Eventual release of wastes from MVSTs and SWSA 5 North bunkers and building into groundwater after loss of institutional control	• No groundwater use • Positively impacts groundwater due to waste removal and treatment of waste from SWSA 5 North trenches	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during institutional control • Eventual release of constituents of treated waste after loss of institutional control, but impacts would be less than No Action because wastes are treated and better contained

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act (see Table 5-1).
MVSTs = Melton Valley Storage Tanks
ORNL = Oak Ridge National Laboratory
SWSA 5 North = Solid Waste Storage Area 5 North.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Wetlands & Floodplains (Chapter 4, Section 4.5.3)	• Continued impacts to White Oak Creek floodplain due to SWSA 5 North contamination • No impact to wetlands during institutional control • After institutional control period, wastes would eventually contaminate wetlands • After loss of institutional control, continue to impact floodplain	• Small impact from sedimentation to the 100-year or 500-year floodplains during construction phase • Wetland B (0.012 ha or 0.03 acres) would be eliminated by construction, but would be mitigated	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during institutional control • Eventual release of constituents of treated waste after loss of institutional control

ha = hectare.
ORNL = Oak Ridge National Laboratory
SWSA 5 North = Solid Waste Storage Area 5 North.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Waste Management (Chapter 4, Section 4.6)	• TRU sludge wastes and associated low-level supernate in the MVSTs solid wastes in SWSA 5 North trenches, and solid waste in storage facilities would remain untreated • Would require continued surveillance and maintenance of untreated legacy waste inventory and associated on-site facilities indefinitely at ORNL • Would result in violation of legal mandate due to continued waste storage, potentially resulting in fines	• All legacy wastes in proposed action would be treated • Approximately 10,833 m^3 of total generated waste, including: - 607 m^3 CH and RH TRU waste; - 2,778 m^3 low-level waste; - 23 m^3 of low-level mixed waste; - 1,560 m^3 of sanitary wastewater; and - 5,550 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative • Approximately 34,128 m^3 of total waste generated, including: - 1,060 m^3 CH and RH TRU waste; - 4,980 m^3 low-level waste; - 4 m^3 of low-level mixed waste; - 7,201 m^3 of sanitary wastewater; and - 20,760 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative - Approximately 28,826 m^3 of total waste generated, including: - 1,793 m^3 CH and RH TRU waste; - 2,833 m^3 low-level waste; - 2,540 m^3 of remote-handled low-level waste; - 3 m^3 of low-level mixed waste; - 7,437 m^3 of sanitary wastewater; and - 14,143 m^3 debris from D&D activities	• Same as Low-Temperature Drying Alternative • 10,833 to 34,128 m^3 of waste generated, depending on the treatment selected, and stored on-site • Would require continued surveillance and maintenance of waste inventory for interim onsite storage at ORNL • Would require construction of additional waste storage facilities—using 0.3 to 0.8 ha of land depending upon treatment process selected

CH = contact-handled.
D&D = decontamination and decommissioning.
m^3 = cubic meters.
MVSTs = Melton Valley Storage Tanks.
ORNL = Oak Ridge National Laboratory
RH = remote-handled.
SWSA 5 North = Solid Waste Storage Area 5 North.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Climate and Air Quality (Chapter 4, Section 4.7)	• No impact to air quality	• Minor emissions during normal operations; slightly higher volatile organic emissions	• Minor emissions during normal operations; slightly higher nitrogen dioxide emissions	• Minor emissions during normal operations; slightly higher particulate emissions.	• Minor emissions during normal operations
Transportation (Chapter 4, Section 4.8)	**On-site Retrieval and Transport** • No on-site waste shipments	**On-site Retrieval and Transport** • 300 shipments of RH waste from trenches and bunkers, and 245 shipments of CH waste to treatment facility • Retrieval accidents could result in 6.3E-05 LCFs (public) and 7.5E-04 industrial fatalities to involved workers • Transportation accidents could result in 2.9E-05 LCF (public) and 3.3E-05 non-radiological fatalities • Total risks to non-involved workers and public MEI are 5.3E-07 and 6.2E-09 probability of cancer fatality, respectively • 8.0E-03 LCF (involved worker (based on 1 rem/year assumed dose limit)	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative	**On-site Retrieval and Transport** • Same as Low-Temperature Drying Alternative for retrieval accidents and radiological transportation accidents • 3,339 shipments of treated waste to storage facility using cementation as a bounding case • 2.3E-04 transportation related fatalities • 3.4E-04 construction fatalities (involved workers) • 2.5E-03 loading and unloading accident fatalities (involved workers)

CH = contact-handled.
LCF = latent cancer fatalities.
ORNL = Oak Ridge National Laboratory.
MEI = maximally exposed individual.
RH = remote-handled.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Transportation (continued) (Chapter 4, Section 4.8)	**Off-site Transport** • No off-site shipments	**Off-site Transport** • 397 shipments of TRU waste with 3.2E-01 accidents and 4.4E-02 fatalities predicted • Non-accident LCFs of 8.7E-03 for CH TRU and 3.1E-02 for RH TRU waste • 277 low-level waste shipments with 2.6E-01 accidents and 3.6E-02 accident fatalities predicted • 2.1E-09 non-accident LCFs predicted	**Off-site Transport** • 989 shipments of TRU waste with 8.0E-01 accidents and 1.1E-01 fatalities predicted • Non-accident LCFs of 5.3E-03 for CH TRU and 9.3E-02 for RH TRU waste • 281 low-level waste shipments with 2.6E-01 accidents and 3.6E-02 accident fatalities • 2.1E-09 non-accident LCFs predicted	**Off-site Transport** • 2,425 shipments of TRU waste with 2.2 accidents and 3.0E-01 fatalities predicted • Non-accident LCFs of 5.3E-03 for CH TRU and 2.7E-01 for RH TRU waste • 914 low-level waste shipments with 8.8E-01 accidents and 1.2E-01 accident fatalities predicted • 7.5E-09 non-accident LCFs predicted	**Off-site Transport** • No off-site shipment of TRU waste or low-level waste

CH = contact-handled.
LCFs = latent cancer fatalities.
ORNL = Oak Ridge National Laboratory.
RH = remote-handled.
TRU = transuranic.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Utility Requirements (Chapter 4, Section 4.9)	• Total estimated power usage 2,200 MW • 5 million gal of water use projected over 100-year institutional control period	• About 15,000 MW of total electricity usage • 5 million gal of water use during project life	• About 45,000 MW of total electricity usage • 7 million gal of water use during project life	• About 11,250 MW of total electricity usage • 15 million gal of water use during project life	• Electricity use varies by alternative from 13,450 MW to 47,200 MW total, which includes electricity use for interim storage • Water use varies by alternative (10 million to 20 million gal), which includes water use for interim storage
Human Health (Chapter 4, Section 4.10)	• LCFs for involved worker population estimated to be 2E-02 • Risk to public and non-involved worker would be negligible during institutional control period • After loss of institutional control, higher risks to public from contaminated surface water, groundwater, and food supplies	• PCF from radiological releases to involved worker estimated to be 3.0E-08; non-involved worker estimated to be 2.0E-08; and off-site MEI estimated to be 1.0E-08 • Collective dose to the affected off-site pubic population would be 1.2E-01 person-rem, resulting in 6.0E-05 LCFs	• PCF from radiological releases to involved worker estimated to be 9.0E-08; non-involved workers estimated to be 7.0E-08; off-site MEI estimated to be 5.0E-08 • Collective dose to the affected off-site public population would be 6.8E-01 person-rem, resulting in 3.0E-04 LCFs	• PCF from radiological releases to involved worker estimated to be 6.0E-09; non-involved workers estimated to be 5.0E-09; and off-site MEI estimated at 3.0E-09 • Collective dose to the affected off-site public population would be 2.8E-02 person-rem, resulting in 1.0E-05 LCFs	• LCF for involved worker population estimated to be 2E-02 • PCF for the non-involved worker and off-site MEI would be equal to that estimated for the treatment technology selected • Collective dose and number of fatalities for the affected off-site population would be equal to that for the treatment technology selected • After loss of institutional control, higher risks to public from contaminated surface water, groundwater, and food supplies, but less risk than No Action Alternative since wastes are treated and better contained

LCFs = latent cancer fatalities.
MEI = maximally exposed individual.
MW = megawatt(s).
ORNL = Oak Ridge National Laboratory.
PCF = probability of cancer fatality.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Noise (Chapter 4, Section 4.12)	• Noise levels at 50 to 60 dBA	• Site construction and D&D noise up to 70 dBA • Noise levels during operations at 50 to 60 dBA • Noise increases are temporary and minor	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative	• Same as Low-Temperature Drying Alternative during treatment and would decrease, similar to the levels of No Action, during interim storage

dBA = decibels as recorded on the A-weighted scale of a standard sound level meter.
D&D = decontamination and decommissioning.
ORNL = Oak Ridge National Laboratory.

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Accidents (Chapter 4, Section 4.11)	• **MVSTs Breach**[1] · MEI – 1.1E-05 PCF · Population – 1.1 LCF during institutional control and 11 LCF after loss of institutional control · Non-involved workers – 9.2E-04 PCF • **Vehicle impact (CH TRU and RH TRU waste)**[3] · MEI – 1.6E-06 PCF · Population – 0.024 LCF · Non-involved workers – 1.3E-04 PCF • **Earthquake**[4] · MEI – 1.6E-05 PCF · Population – 0.24 LCF · Non-involved workers – 1.4E-03 PCF • **Vehicle impact/fire (CH TRU and RH TRU waste)**[5] · MEI – 1.4E-07 PCF · Population – 2.1E-03 LCF · Non-involved workers – 1.2E-05 PCF	• **MVSTs Breach**[1] - NA • **MVSTs transfer line failure**[2] · MEI – 3.2E-06 PCF · Population – 0.16 LCF · Non-involved workers – 2.8E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake**[4] · MEI – 4.8E-07 PCF · Population – 7.2E-03 LCF · Non-involved workers – 4.2E-05 PCF • **Vehicle impact/fire**[5] - negligible	• Same as Low-Temperature Drying Alternative	• **MVSTs Breach**[1] - NA • **MVSTs transfer line failure**[2] · MEI – 6.3E-06 PCF · Population – 0.31 LCF · Non-involved workers – 5.5E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake**[4] · MEI – 9.6E-07 PCF · Population – 0.014 LCF · Non-involved workers – 8.4E-05 PCF	• **MVSTs transfer line failure**[2] · MEI – 3.2E-06 to 6.6E-06 PCF · Population – 0.16 to 0.31 LCF · Non-involved workers – 2.8E-04 to 5.5E-04 PCF • **Vehicle impact**[3] - negligible • **Earthquake (CH TRU and RH TRU waste)**[4] · MEI – 4.8E-07 to 9.6E-07 PCF · Population – 7.2E-03 to 1.4E-02 LCF · Non-involved workers – 4.2E-05 to 8.4E-05 PCF • **Vehicle impact/fire (after processing)**[6] · MEI – 1.4E-07 PCF · Population – 2.1E-03 LCF · Non-involved workers – 1.2E-05 PCF

CH = contact-handled.
LCFs = latent cancer fatalities.
MEI = maximally exposed individual
MVSTs = Melton Valley Storage Tanks
NA = not applicable
ORNL = Oak Ridge National Laboratory
PCF = probability of cancer fatality.
RH = remote-handled
TRU = transuranic.

[1]Melton Valley Storage Tanks (MVSTs) breach accident would be initiated by an earthquake with a 50,000-gal release to the environment.

[2]MVSTs transfer line failure accident assumes the line between the MVSTs and the treatment facility fails during waste transfer operations.

[3]Vehicle impact (CH TRU and RH TRU waste) accident assumes a forklift breaches a package of solid waste.

[4]Earthquake accident assumes that packages of solid waste fall causing the packages to breach.

[5]Vehicle impact/fire (CH TRU and RH TRU) accident assumes a vehicle accident resulting in breach of the waste package and an ignition of the vehicle fuel that results in burning of the wastes.

[6]Vehicle impact/fire (after processing) accident assumes a vehicle accident resulting in breach of the waste package and an ignition of the vehicle fuel that results in burning of the treated wastes (only applies following Low-Temperature Drying Alternative with assumed combustible macroencapsulant).

Table 2-6. Comparison of impacts among alternatives (continued)

	No Action Alternative	Low-Temperature Drying Alternative (Preferred)	Vitrification Alternative	Cementation Alternative	Treatment and Waste Storage at ORNL Alternative
Socioeconomic (Chapter 4, Section 4.13)	• No change in economic activity	• No significant impacts • Earnings represent 0.1% of the income for the region	• No significant impacts • Earnings represent 0.2% of the income for the region	• No significant impacts • Earnings represent 0.1% of the income for the region	• No significant impacts • Earnings represent 0.1% of the income for the region
Environmental Justice (Chapter 4, Section 4.14)	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations	• No disproportionately high and adverse impact expected to minority and low-income populations

ORNL = Oak Ridge National Laboratory.

2.10 REFERENCES

DOE (U.S. Department of Energy) 1997a. *Record of Decision for Interim Action: Sludge Removal from the Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/OR2-1591&D3, August 1997.

DOE 1997b. *Action Memorandum for the Old Hydrofracture Facility Tanks and Impoundment, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1751&D3.

DOE 1997c. *Record of Decision for the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1826&D1.

DOE 1998. *WIPP SEIS-II, Record of Decision for the Department of Energy's Waste Isolation Pilot Plant Disposal Phase, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3624–3629.

DOE 1998b. *WM PEIS, Record of Decision for the Department of Energy's Waste Management Program: Treatment and Storage of Transuranic Waste, Federal Register*, Vol. 63, No. 15, January 23, 1998, pages 3629–3633.

DOE 2000. *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-Level and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site, Federal Register*, Vol. 65, No. 38, 10061–10066, February 25, 2000.

DOE-ORO (U.S. Department of Energy-Oak Ridge Operations Office) 1998. *Categorical Exclusion for Construction/Relocation of Access Road at Oak Ridge National Laboratory*, CX-TRU-98-007, Oak Ridge, Tennessee.

Parallax, Inc. 1995. *Feasibility Study for Treatment ORNL Transuranic Waste in Existing and Modified Facilities, Oak Ridge, Tennessee*, ORNL/M-4693, September 15, 1995.

Perry, R. H., and C. H. Chilton 1973. *Chemical Engineer's Handbook*, 5th Ed., McGraw-Hill.

Spence, R. D., and T. M. Gilliam 1998. *Grout and Glass Performance in Support of Stabilization/Solidification of the MVST Tank Sludges*, ORNL/TM-13652, Oak Ridge National Laboratory, Oak Ridge, Tennessee, November 1998.

THIS PAGE INTENTIONALLY LEFT BLANK

3. AFFECTED ENVIRONMENT

Chapter 3 of this EIS describes the existing environment in and around Oak Ridge National Laboratory (ORNL) and the Oak Ridge Reservation (ORR), which would be affected by the construction, operation, and D&D of the proposed TRU Waste Treatment Facility. ORNL is one of three major DOE facilities located within the ORR. Site-specific information for the area surrounding the proposed facility site and the adjacent Melton Valley Storage Tanks at ORNL is also included. Current, pertinent information is provided for the regions influenced in the various resource areas, and the supporting references are cited.

3.1 LAND USE

This section describes the past, current, and planned land uses on and around the proposed TRU Waste Treatment Facility site, which would be located within the boundaries of ORNL and the ORR. The ORR contains approximately 140 square miles of federally owned land in Anderson and Roane Counties of East Tennessee. The area includes forests, public use areas, and operational areas. The facility is located within the city limits of Oak Ridge, Tennessee, and the surrounding lands are predominantly rural with residences, small farms, forests, and cattle pastures. This section includes descriptions of environmentally sensitive land areas on and around the ORR that are set aside for public use, environmental protection, or research. These sensitive land areas include parks, natural areas, environmental education centers, and public recreation areas.

3.1.1 Past Land Use

The land surrounding the ORR was predominantly forested wilderness prior to the 18th century. During the late 18th and early 19th centuries, the area was settled by emigrants who established three major uses of the land, including forestry, agriculture, and residential. Gradually, commercial, mining, transportation, waterways, and industrial land uses developed. The land that composes the ORR was purchased from private landowners by the United States Government in 1942. The predominant land uses at that time were forestry, agriculture, and residential. Government activities during World War II changed the overall pattern of land use on the ORR to industrial with the establishment of the X-10 Plant (ORNL), the Y-12 Plant (Y-12), the K-25 Site [now known as the East Tennessee Technology Park (ETTP)], and various support facilities. With the exception of some agriculture-related research activities in later years, agricultural use of the land on the ORR nearly disappeared, and the land was allowed to revert to an increasingly natural forested state after its purchase by the government. Residential land use ended over most of the ORR with the exception of the northeastern corner, which housed government workers. Residential and commercial land uses increased rapidly on the north side of the reservation, and in the late 1950s this area was separated from the ORR and incorporated as the City of Oak Ridge. The current land use pattern on the ORR and at ORNL gradually evolved between 1942 and the present day (DOE 1999a).

3.1.2 Current Land Use

The current uses of land in the vicinity of the ORR are forestry, agriculture, residential, commercial, industrial, mining, transportation, waterways, recreation, and several other uses. The largest use is commercial forestry, followed in order by agriculture, other uses, residential, waterways, and transportation. The remaining uses are quite small, each accounting for less than 3,000 ha

(7,410 acres) of land. The closest urban center to the reservation is the City of Oak Ridge. The predominant land use in most urban areas is residential (MMES 1994).

DOE classifies land use on the ORR according to five primary categories: Institutional/Research, Industrial, Mixed Industrial, Institutional/Environmental Laboratory, and Mixed Research/Future Initiatives. The Institutional/Research category applies to land occupied by the central research facilities at ORNL. Land in the Industrial category includes the Y-12 Plant, which is used for defense support, manufacturing, and storage. The Mixed/Industrial category includes the ETTP, which is used for environmental management and reindustrialization of DOE land by private sector businesses. The Oak Ridge Institute for Science and Education, operated by Oak Ridge Associated Universities, provides training and research support to DOE and uses the land within the boundaries of the Institutional/Environmental Laboratory category. The Mixed Research/Future Initiatives category applies to land currently used, or available for use, in field research, and land reserved for future DOE initiatives, including new research facilities.

The proposed TRU Waste Treatment Facility site is a small 2- to 2.8-ha (5- to 7-acre), forested area almost immediately west of the Melton Valley Storage Tanks and approximately 2 km (1.25 miles) east of Tennessee State Route 95. The Melton Valley Storage Tanks are active waste storage tanks, which store legacy TRU sludge waste and its associated remote-handled low-level supernate. The area east of the proposed facility site is industrial and contains the Melton Valley Storage Tanks, associated waste bunkers, and Melton Valley Storage Tanks–Capacity Increase Project tanks. Just west of the proposed TRU Waste Treatment Facility site, the Old Melton Valley Road (High Flux Isotope Reactor access road) was upgraded. This road would be the main road running to the proposed waste treatment facility site. The proposed site for the waste treatment facility does not contain prime or unique farmland.

3.1.3 Planned Land Use

The Spallation Neutron Source is a national research project being developed as a cooperative effort of the national laboratories. The Spallation Neutron Source will be located at ORNL 4 km (2.5 miles) from the proposed TRU Waste Treatment Facility. A CERCLA waste disposal facility is also planned for construction at the Y-12 Plant and would be located in Bear Creek Valley, approximately 6 km (3.7 miles) from the proposed TRU Waste Treatment Facility. These planned projects have already undergone an environmental review as discussed in the "Cumulative Impacts" section of DOE 1999a, and a Record of Decision has been issued for the disposal site.

3.1.4 Parks, Preserves, and Recreational Resources

The University of Tennessee Arboretum is located approximately 0.4 km (0.25 mile) east of the ORR. This facility contains 101 ha (250 acres) of land and functions as a living botanical education center for the general public. Several trails with botanical themes run throughout the arboretum and are open to the public for hiking. The University of Tennessee also operates a forest experiment station on 810 ha (2,000 acres) of land adjacent to the arboretum (LMES 1996). This area is not open to the public.

Large portions of the ORR are devoted to nature preservation and biological research. About 8,899 ha (21,980 acres) of undeveloped and geographically fragmented areas of land at ORNL, Y-12 Plant, and ETTP comprise the Oak Ridge National Environmental Research Park. The National Environmental Research Park is used by the U.S. scientific community as an outdoor environmental science laboratory to study the current and future environmental consequences of the DOE mission in Oak Ridge (LMES 1995a). Numerous areas within the National Environmental Research Park are

designated for the protection of rare species. A number of reference areas have been established to serve as examples of regional plant communities and unique biotic features (Pounds et al. 1993). A portion of the ORR is operated as the Oak Ridge Wildlife Management Area through a cooperative agreement between DOE and the Tennessee Wildlife Resources Agency (DOE-ORO 1996). This agreement was initiated in 1984 to reduce traffic accidents involving deer by opening the ORR to hunting by the public (Saylor et al. 1990).

The Clark Center Recreational Park, located on the north shore of Melton Hill Lake, occupies 36 ha (90 acres) of land within the southeast corner of the ORR. It is open to the public for swimming, picnicking, fishing, pleasure boating, and athletic activities such as softball. Management of the Freels Bend area, directly east of the Clark Center Recreational Area on the north side of Melton Hill Lake, was recently granted to the State of Tennessee by the Secretary of Energy. Several public recreation areas are located along Melton Hill Lake, which is outside the ORR but adjacent to a large portion of the ORR's southeast boundary. This body of water is a Tennessee Valley Authority (TVA) reservoir that was formed by impounding the Clinch River with Melton Hill Dam. The body of water on the downstream side of Melton Hill Dam is Watts Bar Lake, which is adjacent to the southwest boundary of the ORR. Melton Hill Dam is located approximately 4.3 km (2.7 miles) southwest of the central ORNL plant, but land used for laboratory activities extends south to the shore of Melton Hill Lake. A large TVA public recreation area is located at the Melton Hill Dam on the opposite shore from ORNL land and the ORR. This recreation area is used for pleasure boating, fishing, swimming, and picnicking. Other TVA recreational areas with similar uses are located along Melton Hill Lake upstream from the dam and ORNL, including 425 ha (1,051 acres) of recreational lands within the city limits of Oak Ridge (MMES 1994). A TVA boat ramp is located on the ORNL side of Watts Bar Lake, approximately 2.4 km (1.5 miles) downstream from Melton Hill Dam. Watts Bar Lake is used for pleasure boating, fishing, and swimming.

3.1.5 Scenic Resources

The steep, linear ridges; intervening valleys; and lakes in the vicinity of ORNL create beautiful, natural scenery. However, many parcels of rural land are used for agricultural and residential purposes so the visual field at many locations includes various combinations of houses, barns, roads, and utility features. In heavily developed areas of Oak Ridge, views are predominated by these features, along with numerous commercial structures, industrial plants, and public service buildings. Natural scenery abounds on the ORR, since much of it has been allowed to return to its natural state. However, the landscape in developed areas of the ORR, such as those in the vicinity of ORNL and the proposed TRU Waste Treatment Facility site, is a mixture of natural features with buildings, industrial facilities, roads, and utility features.

3.2 CULTURAL AND HISTORIC RESOURCES

The ORR area is rich in cultural resources, both prehistoric and historic. Preservation of these resources is mandated by Section 106 of the National Historic Preservation Act [16 U.S.C. 470(f)]. Several reconnaissance-level (walkover) surveys for cultural resources have been conducted on the ORR in the vicinity of the proposed project. These include Faulkner (1988) and DuVall (1992a, 1993b, and 1996). Based on these previously conducted investigations, it appears that the proposed TRU Waste Treatment Facility site has no known archaeological, cultural, or historical resources. In addition, no such resources are known to exist in areas immediately contiguous to the proposed site. The nearest potential site, located approximately 183 m (600 ft) southwest of the project site, is the pre-1942 homestead site known as the Jenkins Site (State of Tennessee registration number 40RE188). The pre-1942 homestead site known as the Jones Site (State of Tennessee registration number

40RE189) is located approximately 244 m (800 ft) northeast of the project site (Figure 3-1). An archaeological assessment of these two sites utilized subsurface testing to determine if artifact concentrations were present on the two sites (Faulkner 1988). The Jones Site and support structures were recommended for inclusion in the National Register of Historic Places due to the relatively intact nature of the site and its early occupation date (ca. 1820). The Jenkins Site has been severely affected by modern intrusions and was not considered eligible for inclusion in the National Register of Historic Places.

In accordance with the programmatic agreement concerning management of historical and cultural properties at the ORR among the DOE-Oak Ridge Operations Office, the Tennessee State Historic Preservation Officer, and the Advisory Council on Historic Preservation, DOE sent a letter submitted to the State Historic Preservation Officer on June 28, 1999, to address Section 106 for the TRU Waste Treatment Facility. Enclosed with the letter was a summary of the Archaeological and Historical Review for the TRU Waste Treatment Facility site prepared for the proposed action. DOE requested and received concurrence with their findings from the State Historic Preservation Officer regarding this proposed project (Appendix E).

DOE has consulted with Native American groups regarding the status of the ORR as a site of potential importance to Native Americans. While some isolated findings of arrowheads, pottery shards, and charcoal have been found in some project studies over the years, no tribe or group representing Native Americans has ever expressed interest in the ORR as a site of historical importance to Native Americans (Moore 1999). There are no known sensitive areas near the proposed project site.

3.3 ECOLOGICAL RESOURCES

This section provides descriptions of the terrestrial and aquatic resources, including threatened and endangered species, identified at the proposed TRU Waste Treatment Facility site. Basis for the following information was derived from the 1988 field surveys conducted in preparation of the previously proposed Waste Handling and Packaging Plant (Campbell et al. 1989). The field surveys included an area located southeast of the proposed TRU Waste Treatment Facility site. The southwestern boundary of the surveys slightly overlaps the southeastern most corner of the proposed site. The survey area's northern edge came within less than 91 m (300 ft) of the proposed TRU waste facility's northeast corner fence line. Surveys for sensitive plant and animal species were completed for the proposed site in April 1999, and a report on survey findings is included in Appendix C.

3.3.1 Terrestrial Resources

The proposed site for the TRU Waste Treatment Facility is at the northwest base of Copper Ridge and Melton Hill and includes a small portion of Copper Ridge. During the 1988 surveys, the area was noted to have been previously disturbed by homesteading prior to 1942 (Campbell et al. 1989). A thin layer of deciduous leaf litter accompanies slash, moss-covered surface debris, and small rocks on the soil surface. The soil surface is firm and gravelly, with a minimum buildup of organic matter. No caves or large rock outcrops are present in the proposed area.




Figure 3-1. Archeological sites near the proposed TRU Waste Treatment Facility site at ORNL include the Jones Site and the Jenkins Site.

3.3.1.1 Flora

Succession on the fields of the former homesteads has produced a relatively young to mid-age open forest of pines and cedars with some hardwood species at the proposed TRU Waste Treatment Facility site. No hollow trees, living or dead, were observed in the parcel. The dominant tree species identified included shortleaf and Virginia pines in the west, fading to hardwood species such as yellow-poplar, oaks, hickories, red bud, and maples in the east (Appendix C.3). The forest on the steep slopes of Melton Hill above the proposed site is relatively undisturbed. In open areas, herbaceous species make up the ground cover of the area. Species identified in the 1999 surveys include exotic species, such as Japanese honeysuckle and Nepal grass, as well as blueberries, rusty viburnum, juneberry, and hophornbeam (Appendix C.3). A previously fenced small area is to be included in the proposed site. This area currently contains no native vegetation and consists of buildings, paved areas, and lawns.

3.3.1.2 Fauna

Because of its small size, the proposed TRU Waste Treatment Facility site possesses relatively few habitat types and supports only a fraction of the number of faunal species found within the ORR. The site's vertebrate fauna consists of species common to the second-growth, mixed hardwood-pine forest. A few species suspected to be present are snakes (rat snake and black racer); birds (red-eyed vireo, pine warbler, scarlet tanager, wild turkey, and red-tailed hawk); rodents (white-footed mouse); and mammals (coyote, gray squirrel, flying squirrel, opossum, striped skunk, and white-tailed deer).

3.3.2 Terrestrial Threatened and Endangered Species

3.3.2.1 Flora

Surveys for sensitive plant species that are specific to the proposed TRU Waste Treatment Facility site were completed in May 1999 and were accomplished by walking the entire proposed area. No Federally-listed terrestrial plant species have been reported on the proposed site (Appendix C.3). No State-listed terrestrial plant species were observed at the proposed site during the 1999 survey. Compatible habitats for four State-listed terrestrial species that are known to occur on the ORR exist within the proposed area. These species and their preferred habitats are represented in Table 3-1. Two additional rare wetland species may occur in the site. These are discussed in Section 3.3.4.1.

Table 3-1. State-listed terrestrial plant species with compatible habitats exhibited in the proposed site

Common name	Species	Preferred habitat
Heavy sedge	*Carex gravida*	Dry woods or open areas
Pink Lady's Slipper	*Cypripedium acaule*	Pine or mixed pine-hardwood
Butternut	*Juglans cinera*	Deciduous forest
Canada Lily	*Lilium canadense*	Moist, shaded drainages

3.3.2.2 Fauna

A sensitive animal survey was completed in April 1999 and was accomplished by visual identification, trapping, and installation of artificial ground covers at the proposed TRU Waste Treatment Facility site. The only Federally-listed animal species that have been recently observed on the ORR (the gray bat, bald eagle, and peregrine falcon) are represented by migratory or transient individuals rather than by permanent residents. The Federally-endangered Indiana bat has not been

identified in the area, but the ORR does fall into its geographic range. Suitable habitat for the bat at the proposed site is marginal (Appendix C.2).

Several local species are listed by the State of Tennessee as "in need of management." These species may be present in the vicinity of the proposed site based on the reasoning that the proposed TRU Waste Treatment Facility site falls within their acceptable home ranges and the proposed area contains compatible habitat for them. Species listed as "in need of management" that may occur in the proposed area are presented in Table 3-2, although none of these species was observed or captured during the 1999 survey (Appendix C.2).

Table 3-2. Tennessee State-listed "in need of management" terrestrial animal species with compatible habitats exhibited in the proposed site

Common name	Scientific name	In home range	Suitable habitat present
	Aves		
Cooper's hawk	*Accipiter cooperii*	Yes	Yes
Sharp-shinned hawk	*Accipiter striatus*	Yes	Yes
Bachman's sparrow	*Aimophila aestivalis*	Yes	Marginal
Grasshopper sparrow	*Ammodramus savannarum*	Yes	Marginal
Lark sparrow	*Chondestes grammacus*	Yes	Marginal
Vesper sparrow	*Pooecetes gramineus*	Yes	Marginal
Yellow-bellied sapsucker	*Sphyrapicus varius*	Winter only	Yes
Bewick's wren	*Thryomanes bewickii bewickii*	Yes	Marginal
	Mammals		
Star-nosed mole	*Condylura cristata parva*	Marginal	Marginal
Eastern big-eared bat	*Corynorhinus rafinesquii*	Yes	Marginal
Eastern small-footed bat	*Myotis leibii*	Yes	Marginal
Hairy-tailed mole	*Parascalops breweri*	Yes	Marginal
Southeastern shrew	*Sorex longirostris*	Yes	Yes
Southern bog lemming	*Synaptomys cooperi*	Yes	Yes
Meadow jumping mouse	*Zapus hudsonius*	Yes	Marginal
	Amphibians		
Four-toed salamander	*Hemidactylium scutatum*	Yes	Marginal
	Reptiles		
Northern coal skink	*Eumeces A. anthracinus*	Marginal	Marginal
Southern coal skink	*Eumeces anthracinus pluvialis*	Marginal	Marginal
Eastern slender glass lizard	*Ophisaurus attenuatus longicaudus*	Yes	Yes
Northern pine snake	*Pituophis M. melanoleucus*	Yes	Marginal

3.3.3 Aquatic Resources

A thorough description of the hydrology of the White Oak Creek Watershed is found in Section 3.5. The proposed TRU Waste Treatment Facility site is located in the White Oak Creek Watershed. Surface water draining from the site would flow either into White Oak Creek, or the lower portions of the Melton Branch, a tributary to White Oak Creek. From there the surface water route would continue to White Oak Lake and on to the Clinch River. White Oak Creek, Melton Branch, and White Oak Lake receive treated and untreated process wastewater, treated sanitary sewage effluent, and reactor cooling water from ORNL facilities. A small, unnamed tributary drains into the headwaters of White Oak Lake near the proposed facility site on the northern slope of Copper Ridge. The tributary is

believed to be an intermittent stream, although it is not gauged and there are no known hydrological or water quality data available (Campbell et al. 1989).

White Oak Lake is a shallow impoundment created in 1941 by the construction of White Oak Lake Dam located approximately 1 km (0.6 mile) above the confluence of White Oak Creek with the Clinch River. White Oak Lake functions as a final settling basin for waste effluents discharged to White Oak Creek, Melton Branch, and other small streams in the White Oak Creek Watershed. White Oak Lake extends 0.7 km (0.4 mile) upstream from the dam and has a surface area of about 8 ha (20 acres).

Off-site aquatic invertebrate and fish surveys in the 1980s were reported to have observed several invertebrate species, and 3, 12, and 18 fish species in the Melton Branch, White Oak Creek, and White Oak Lake, respectively (ORNL 1998). Bioaccumulation studies in sunfish and largemouth bass (*Micropterus salmoides*) to monitor mercury and polychlorinated biphenyl (PCB) contamination in White Oak Creek and White Oak Lake have been conducted since at least 1994. In 1997, mercury concentrations in redbreast sunfish (*Lepomis auritis*) from White Oak Creek (White Oak Creek kilometer 2.9) and bluegill sunfish (*L. macrochirus*) and largemouth bass from White Oak Lake were approximately five-fold higher than concentrations in fish from sampled reference streams. Concentrations in the largemouth bass were greater than those in the sunfish, which is consistent with the bass's position in the food chain. In 1997, no fish from the White Oak Creek Watershed contained mercury concentrations higher than 0.50 mg/kg. Mean PCB concentrations in sunfish from White Oak Creek kilometer 2.9 and White Oak Lake during 1997 were 0.39 ± 0.10 mg/kg and 0.69 ± 0.06 mg/kg, respectively. Reference location sunfish that were analyzed at the same time averaged <0.02 mg/kg PCB. The PCB concentrations in largemouth bass from White Oak Lake ranged from 0.43 to 3.8 mg/kg PCB. Since 1994, the PCB concentrations in sunfish and largemouth bass from White Oak Creek have remained approximately two- to three-fold higher than the concentrations reported from the early 1990s (ORNL 1998).

DOE Order 5400.5, Chapter II, sets an interim absorbed dose rate limit of 1 rad/day (0.01 Gy/day) to native aquatic organisms. ORNL demonstrated compliance with this limit for aquatic biota exposed to surface water and sediments in the White Oak Creek Watershed by calculating absorbed doses to fish, crustacea (such as crayfish), and muskrats (*Mustela erminea*) (ORNL 1998). Doses to these receptors at Melton Branch kilometer 0.2, as well as at White Oak Creek kilometer 2.6, and White Oak Lake Dam kilometer 1.0, were all significantly less than the 1 rad/day limit (Table 3-3).

Table 3-3. Doses of radionuclides to aquatic receptors at ORNL surface water locations in 1997[a,b]

	Fish		Crustacea		Muskrat	
Measurement location	Avg. (rad/day)	Max. (rad/day)	Avg. (rad/day)	Max. (rad/day)	Avg. (rad/day)	Max. (rad/day)
Melton Branch (K 0.2)	1E-03	2E-03	3E-04	6E-04	3E-03	6E-03
White Oak Creek (K 1.0)	8E-04	2E-03	3E-04	5E-04	2E-03	3E-03
White Oak Creek (K 2.6)	4E-04	7E-04	1E-04	2E-04	1E-03	2E-03
White Oak Creek (K 6.8)	7E-08	1E-07	7E-08	1E-07	1E-07	2E-07

[a]Total dose rate includes the contribution of internally deposited radionuclides, sediment exposure (derived from water concentration), and water immersion.

[b]To convert from rad/day to Gy/day, divide by 100.

K = kilometer

ORNL = Oak Ridge National Laboratory.

Source: Adapted from ORNL 1998.

3.3.4 Aquatic Threatened and Endangered Species

3.3.4.1 Flora

Surveys for sensitive plant species that are specific to the proposed TRU Waste Treatment Facility area were completed on May 12, 1999, and were accomplished by walking the entire proposed impact area. No Federally-listed aquatic plant species were found to occur on, or adjacent to, the survey area. Two Tennessee State-listed wetland species, the purple fringeless orchid (*Platanthera peramoena*) and river bulrush (*Scirpus fluviatilis*), have been identified on the ORR and may be present in wetland areas adjacent to the proposed site. Neither of these species was identified during the 1999 field survey report for rare plants (Appendix C.3).

3.3.4.2 Fauna

According to the U.S. Fish and Wildlife Service, the pink mucket pearly mussel *(Lampsilis arbrupta,* previously known as *L. orbiculata)*, a Federally-listed endangered species in the family Unionoidae of mollusks, is known to occur near the potential project impact area (Appendix E). This species is found in medium to large rivers, with habitat characterized by moderate- to fast-flowing water 0.5 to 8.0 m deep, and substrates including silt, gravel, sand, cobble, and boulders (CMI-FWIE 1996). Although small populations of the pink mucket pearly mussel have been found in the Clinch River in Tennessee (EPA 2000), this species is highly unlikely to be present in Melton Branch or White Oak Creek near the TRU Waste Treatment Facility site because the two streams are too small to provide proper habitat. In addition, the impoundment of White Oak Creek to form White Oak Lake near the proposed facility site further reduces the likelihood of pink mucket occurrences because impoundments have adverse impacts to the species. Thus, the pink mucket pearly mussel is unlikely to be present in the affected environment for the proposed faciliyy.

No Federally-listed aquatic animal species were found to occur on or adjacent to the survey area (Appendix C.2). The only Tennessee State-listed aquatic-related species observed in 1995 near the proposed site was the osprey, which occurred at the nearby White Oak Lake. Platforms have been established on Melton Lake, and this bird has become a common nester of the Melton Valley area (Mitchell et al. 1996). Species in the surrounding area listed as "in need of management" by the State of Tennessee include the little blue heron and great egret. Both species were sighted on White Oak Lake during the 1995 ORO survey (Figure 3-2) and are considered to be uncommon migrant species to the area (Mitchell et al. 1996).

3.4 GEOLOGY AND SEISMICITY

The ORR is located in the Tennessee Section of the Valley and Ridge physiographic province (Figure 3-3). This province extends more than 1,287 km (800 miles) from northeast Alabama into central Pennsylvania. Four main features distinguish the Valley and Ridge Province: long, parallel ridges and valleys oriented from northeast to southwest; similar ridge summit elevations suggesting former erosional surfaces; major traverse streams that cut through ridges with subsequent streams forming a trellis drainage pattern parallel to the valleys; and numerous water and wind gaps through the ridges. The Tennessee section encompasses the southwestern half of the Valley and Ridge province extending from northeast Alabama into southwestern Virginia. This section of the Valley and Ridge province ranges from 40 to 113 km (25 to about 70 miles) wide. In the vicinity of the ORR, the width is approximately 80 km (50 miles). Within the ORR, the principal valley and ridge landforms include, from southeast to northwest, Copper Ridge, Melton Valley (containing the proposed TRU Waste




Figure 3-2. Locations of sightings of protected bird species on the ORR – 1995 survey.




Figure 3-3. Physiographic map of the Southern Appalachian Region.

Treatment Facility site), Haw Ridge, Bethel Valley (containing the main ORNL plant area), Chestnut Ridge (separating ORNL and the Y-12 Plant), Bear Creek Valley (containing the Y-12 Plant), and Pine Ridge (separating the Y-12 Plant from the City of Oak Ridge). The proposed TRU Waste Treatment Facility site lies within Melton Valley at an elevation of about 224 m (735 ft) above mean sea level. Elevations on the ORR range from 212 to 386 m (695 to 1,266 ft) above mean sea level.

The characteristic structure and resulting topography that defines this province is largely a result of regional tectonic activity that occurred during the Alleghenian orogeny from the middle Pennsylvanian through the early Permian periods (300 to 250 million years ago). This tectonism produced a majority of the prominent Appalachian structures and deformed underlying bedrock through intense compressional folding and low-angle (<10°) thrust faulting (overthrusting). The folding and faulting process produced repeated stratigraphic sequences aligned northeast-southwest, perpendicular to the direction of greatest stress, and characteristically dipping to the southeast. Differential erosion of alternating bedrock units subsequently produced the characteristic topography, with resistant units forming ridges and easily eroded units forming valleys. Typically, the scarp (northwest facing) slopes of the ridges are relatively short, steep, and smooth. The dip slopes (southeast facing) are longer, have a gentler slope, and are dissected by surface streams.

3.4.1 Stratigraphy

Bedrock in the ORR vicinity is of Early Cambrian (about 570 million years ago) to Mississippian age (320 to 345 million years ago) (Figure 3-4). The bedrock units encompass a wide variety of lithologies ranging from pure limestone to dolostone to fine sandstone. The total thickness of the stratigraphic section on the ORR is about 2.5 km (1.6 miles). Four primary geologic units occur on the ORR; these include (from oldest to youngest) the Rome Formation, Conasauga Group, Knox Group, and Chickamauga Group. Younger geologic formations, including Silurian-, Devonian-, and Mississippian-age units, occur in East Fork Valley immediately north of the ORR. The Conasauga Group, Knox Group, and Chickamauga Group are comprised of individual geologic formations that have been combined based on general lithology types and age. Because of their unique lithologies, each of the major stratigraphic units possesses different mechanical characteristics and has responded differently to the strains imparted on them through time. In general, the Maynardville Limestone of the Conasauga Group, the Knox Group, and most of the overlying Chickamauga Group act as brittle, but competent, units within the major thrust sheets in the ORR vicinity. The Rome Formation, all of the Conasauga Group below the Maynardville Limestone, and the Moccasin Formation of the Chickamauga Group (weak units) readily deform under stress; these units often contain fault planes along which movement has occurred. These faults have been largely inactive in recent geologic time. The Rome Formation and Knox Group are chemically resistant to weathering; thus, these units form the principal ridges on the ORR. The Chickamauga Group and Conasauga Group formations underlie the valleys.

The Consauga Group underlies the Melton Valley which contains the proposed TRU Waste Treatment Facility site (Figure 3-5). Strata within the Consauga Group include (from the oldest to youngest) the Pumpkin Valley Shale, Rutledge Limestone, Rogersville Shale, Maryville Limestone, Nolichucky Shale, and the Maynardville Limestone. Strata within the Conasauga Group consist of variable limestone and shale lithologies. The Pumpkin Valley, Rogersville, and Nolichucky Shale are comprised primarily of shale with subordinate limestone content present as thin interbeds or discontinuous stringers. The Rutledge Limestone and Maryville Limestone contain a significant percentage of carbonate (about 40%, respectively); limestone beds up to 6 m (20 ft) thick exist at the base of the Rutledge Limestone, whereas limestone beds typically are 0.5 m (1.7 ft) in the Maryville Liimestone (Hatcher et al. 1992). The Maynardville Limestone consists of relatively pure limestone and dolostone; only a minor percentage of shale occurs in the upper portion of the unit.




Figure 3-4. Stratigraphic column for the Oak Ridge Reservation.

The TRU Waste Treatment Facility site would be situated over the Cambrian-age Nolichucky Shale. At the proposed location, the Nolichucky Shale consists of dark gray to lesser amounts of dark green, olive green, brown, and black shale and silty shale. Shale beds range from about 2.5 cm (1 in.) to 3 m (9.8 ft) thick and are often fissile in outcrop. The shale-to-limestone content ratio is about 1:1.75. Informally, the Nolichucky is divided into lower, middle, and upper members. The total thickness of the Nolichucky Shale is approximately 57 m (187 ft) in the Copper Creek Thrust Sheet. The surface contact with the Maynardville Limestone lies about 230 m (754 ft) south of the proposed TRU Waste Treatment Facility site. The underlying Maryville Limestone is about 160 m (525 ft) to the north.

3.4.2 Structure

Strata at the proposed TRU Waste Treatment Facility site are oriented in a northeast-southwest direction (average geologic strike is about north 55° east) and dip about 45° to the southeast. The regional compressive tectonic activity that produced the orientation of the bedrock strata also resulted in the development of two major thrust faults: the Copper Creek Fault and the White Oak Mountain




Figure 3-5. Geologic map for Melton Valley.

Fault (Figure 3-6). The strata that overlie and are bounded by these faults are referred to as thrust sheets. The White Oak Mountain thrust sheet is bounded at depth (i.e., soled) by the White Oak Mountain thrust fault and includes all strata between Pine Ridge and Copper Ridge (Figure 3-5). The Copper Creek thrust sheet includes strata south of Copper Ridge extending off of the ORR. Both thrust faults are regional in extent and exhibit several kilometers of translation. As noted previously, these faults formed during the Pennsylvanian-Permian Alleghenian orogeny and have not been historically active.

Bedrock on the ORR is covered with a mantle of residual soil formed by weathering of bedrock in place (saprolite). These residual soils tend to have a high clay content over limestone and dolostone bedrock units and are silty clays over shale-dominated units. The saprolite tends to retain visible parent bedrock characteristics such as fractures and bedding planes and normally has a higher porosity and permeability than the parent material. The residual soils tend to be absent where erosion has removed them near streams and thicker in upland areas and where bedrock contains higher limestone or dolostone content.

Localized folding of bedrock units is prevalent on the ORR. Incompetent strata, such as the Nolichucky Shale, exhibit numerous small-scale folds ranging from less than a meter to several meters in size. Folds within the Copper Creek Thrust Sheet are typically parallel (flexural slip), range from symmetric to asymmetric, plunge gently (<30°) to the northeast or southwest, generally are open, and are upright to steeply inclined (axial surface dip >60°) (Hatcher et al. 1992).

Ancient tectonic activity has also produced extensive fracturing and localized folding of bedrock units. Fractures are abundant within shallow and intermediate bedrock [to depths of about 91 m (300 ft)] and are also retained in bedrock that has been weathered in place (i.e., saprolite). Studies of the orientation of fractures indicate three orientation sets are evident: one that roughly parallels bedding, one steeply dipping set that parallels bedding, and one that is steeply dipping and perpendicular to bedding (Dreier et al. 1987). The fractures form a three-dimensional rectangular network within the bedrock (DOE 1997a). The average fracture density within the Maynardville Limestone and Nolichucky Shale is about 5 per meter in unweathered bedrock. Up to 200 fractures per meter have been measured within saprolite. Fracture densities between 3 and 200 per meter have been observed in outcrops near ORNL (Dreier et al. 1987). Typical fracture lengths are short, ranging from a few centimeters to several meters. Within the Maynardville Limestone, and to a lesser degree in the carbonate sections of the Rutledge Limestone and Maryville Limestone Formations, chemical weathering and solution enlargement of fractures have produced karst features (i.e., conduits and cavities). Cross-cutting fractures and fracture zones play a significant role in the movement of groundwater across the geologic structure of the area. The presence of such features is of concern when considering movement of contaminant at depth, such as deep hydrofracture-injected wastes (DOE 1997a). Additional discussion of groundwater fracture flow is presented in Section 3.5.2.

3.4.3 Soils

Soil contamination exists in many locations of the Melton Valley at ORNL. This valley is primarily used for waste storage and contains many existing above grade and below grade waste storage facilities. TRU constituents have been identified in the soil at the SWSA 5 North trench area.

TRU waste is stored in SWSA 5 North in underground trenches. The waste was stored in either 4-inch-thick concrete casks, or a combination of wood and metal boxes, and then buried in identified trenches. In 1983, one of the casks was removed to evaluate the integrity of the containment




Figure 3-6. Geologic cross-section of the Oak Ridge Reservation.

vessel. Although the hoisting cables were severely rusted and eventually broke during removal, the vessel itself remained in generally good condition. Similar evaluation steps have not been taken for the other containment vessels. Water level data collected in 1993 from in-trench standpipes and nearby monitoring wells show that most of the TRU trenches in the main group of trenches are at least partially inundated during the wet season (DOE 1995). The trench inundation and/or bathtubbing are the most likely mechanisms responsible for the potential release from the TRU trenches to the surrounding soils. Impacted groundwater from these trenches has the potential of discharging into White Oak Creek to the west or to the D-1 Tributary to the south and impacting the subsurface soils and bedrock along this flow path.

Soils at the site are closely tied to local geology and geomorphic processes. Soils at the proposed site formed from rock weathered in place from the underlying Nolichucky Shale bedrock (residuum), from soil and rock transported downslope by gravity from higher topographic positions (colluvium), or from soil and rock transported by Melton Branch and other tributary streams (alluvium) (Hatcher et al. 1992). Soil properties are summarized in Table 3-4.

Table 3-4. Select properties of soils at the proposed TRU Waste Treatment Facility site

Series Number	Parent material	Drainage	Depth	Erosion potential	Roads		Small buildings
					Paved	Unpaved	
300	Nolichucky residuum	Moderately well to somewhat poorly drained	50 to 125 cm (20 to 49 in.)	Low to moderate	Poor	Poor (wetness and high clay content)	Poor (wetness)
301	Nolichucky residuum	Moderately well drained	50 to 100 cm (20 to 39 in.)	High	Fair	Poor (high clay content)	Fair to poor (differential settling)
302	Nolichucky residuum	Moderately well to well drained	50 to 125 cm (20 to 49 in.)	Moderate to high	Poor (high clay content)	Poor (unstable base)	Fair (high clay content)
221	Colluvium from Maynardville and Copper Ridge	Well drained	>150 cm (>59 in.)	High	Fair	Fair (unstable base)	Fair to good
995	Alluvium	Moderately well to well drained	50 to 125 cm (20 to 49 in.)	Very high	Poor (high silt content)	Very poor (very unstable base and high silt content)	Very poor (wetness and high silt content)

3.4.3.1 Residual soils

Soils formed in Nolichucky residuum at the proposed TRU Waste Treatment Facility site include three unnamed soil series, coded as Series Numbers 300, 301, and 302 (Hatcher et al. 1992). Number 300 soils occur on lower side slopes where overland flow and subsurface lateral flow keep the lower subsoil horizons wet during winter and spring. Number 301 soils occupy topographic positions higher in the landscape than Number 300 soils and occupy the largest area underlain by the Nolichucky Shale. Most areas of Number 301 soils were cultivated in the past and led to severe erosion. The high silt and clay content throughout Number 301 soils contributes to frequent downslope movement when these soils become saturated with water. Number 302 soils occur on very gentle slopes (<6%) underlain by the Nolichucky Shale. They are most often found near the top of the formation where beds of clayey

limestone are interspersed among the shale layers. Number 302 soils have a clay-enriched subsurface horizon, which is related somewhat to the high clay content of the parent material.

3.4.3.2 Colluvial soils

Colluvial soils at the site include Series Number 221 (Hatcher et al. 1992). These soils formed in material that was transported downslope by gravity from the Maynardville Limestone or Copper Ridge Dolomite, which overlie the Nolichucky on Copper Ridge. Number 221 soils overlie Nolichucky residuum on toeslopes along the bottom of ridges and fan terraces at the bottom of first-order drainageways. Different hydraulic properties of the colluvium and the underlying residuum interrupt the vertical migration of water through the soil profile, resulting in a seasonally perched water in the top part of the soil profile in winter and spring.

3.4.3.3 Alluvial soils

Alluvial soils, coded Series Number 995, formed in alluvium deposited in floodplains of larger (second-order and higher) streams (Hatcher et al. 1992). Number 995 soils occur in the floodplain of Melton Branch, which abuts the proposed TRU Waste Treatment Facility site on the northwest. These soils generally have a high silt and fine sand content in the upper part of the soil profile, which leads to some significant engineering problems. Number 995 soils cannot be compacted and have a very low load-bearing capacity.

3.4.4 *Site Stability*

A 1989 site characterization study conducted for a previously proposed TRU waste handling and packaging plant about 287 m (1,000 ft) west of the Melton Valley Storage Tanks included installation of 47 soil borings and collection of samples for geotechnical parameters (MMES 1989; EDGE 1989). Data from this investigation showed that residual soils at the site ranged from depths of 0.48 to 5.7 m (1.7 to 20.1 ft). No evidence for sinkhole or karst development was observed. Soils overlying limestone-dominant bedrock were cohesive and stiff to very stiff. Blow counts for these types of soils typically ranged between 2 to 8 counts per 0.14 m (0.5 ft). Samples of residual soil overlying the shale-dominant zones of the Nolichucky Shale were dense and noncohesive. Blow counts typically ranged between 10 and 50 per 0.14 m (0.5 ft). The 1989 geotechnical studies were conducted for the purpose of construction suitability testing in the region around the Melton Valley Storage Tanks, located east of the proposed TRU Waste Treatment Facility site. Borings were generally excavated to 5 m (15 ft) below ground surface or auger refusal, whichever came first. Standard penetration tests were collected in the field, and select samples were collected by standard engineering characteristics analysis (e.g., grain size analysis, moisture content, specific gravity, and Atterberg limits) (EDGE 1989). In general, the results of these suitability tests found that the soils on the proposed TRU Waste Treatment Facility site are typical of the ORR, suitable for construction, and not susceptible to liquefaction or mass movement.

Regional seismicity data for the southeastern United States presented in this EIS are derived from the assessment for the Advanced Neutron Source (ANS) site (Blasing et al. 1992). The ANS site was located about 1.6 km (1 mile) north of the proposed TRU Waste Treatment Facility site. Five tectonic provinces in the southeastern United States have experienced historical strong-motion earthquakes: the Mississippi Embayment, the Atlantic Coastal Plain, the Appalachian Basin, the Piedmont Plateau, and the Interior Low Plateau. The ORR is located within the Appalachian Basin province. Strong-motion earthquakes are those with a Modified Mercalli Intensity of VII or higher (Table 3-5). The Modified Mercalli Intensity scale is currently the preferred indicator for identifying the relative strength of earth movements. The older Richter Scale is shown for comparison (Table 3-6).

Table 3-5. Modified Mercalli Intensity Scale for earthquakes, developed 1931

Intensity	Earthquake Effects
I	Not felt except by a few under exceptionally favorable circumstances.
II	Felt by a few persons at rest, especially on upper floors of buildings.
III	Felt quite noticeably indoors, especially on upper floors of buildings, but many people do not recognize it as an earthquake. Vibration like the passing of a truck.
IV	Felt indoors by many; outdoors by few during the day. Dishes, windows, doors disturbed; walls make creaking sounds. Sensation like a heavy truck striking the building.
V	Felt by nearly everyone; many awakened if sleeping. Some objects broken; cracked plaster in a few places. Disturbances of trees, poles, and other tall objects sometimes noticed.
VI	Felt by all; many scared and run outdoors. Some heavy furniture moved. Structural damage is slight.
VII	Everybody runs outdoors. Damage negligible in buildings of good design and construction. Slight to moderate damage in well built ordinary structures; considerable damage in poorly built or badly designed structures.
VIII	Damage slight in specially designed structures; considerable in ordinary substantial buildings with partial collapse; great damage in poorly built or badly designed structures. Fall of chimneys, factory stacks columns, monuments, and walls. Sand and mud ejected in small amounts. Changes in well water levels.
IX	Damage considerable in specially designed structures; well-designed frame structures thrown out of plumb; great damage in substantial buildings. Buildings shifted off of foundations. Underground pipes broken.
X	Some well-built structures destroyed most masonry and frame structures with foundations destroyed. Steel rails bent. Ground badly cracked. Landslides considerable from riverbanks and steep slopes.
XI	Few if any structures remain standing. Bridges destroyed. Steel rails bent greatly. Broad fissures in the ground. Underground pipelines out of service. Earth slumps and land slips in soft ground.
XII	Damage total. Waves seen on ground surface. Lines of sight and level distorted. Objects thrown into the air.

Table 3-6. Richter Scale of earthquake magnitude

Magnitude	Earthquake Effects
<3.5	Generally not felt, but recorded by instrumentation
3.5 – 5.4	Often felt, but only minor damage detected
5.5 – 6.0	Slight damage to structures
6.1 – 6.9	Can be destructive to populous regions
7.0 – 7.9	Major earthquake inflicting serious damage
>8.0	Great earthquake with total destruction to nearby communities

Historical seismicity in the southeastern United States has largely been correlative with surface or shallow geologic structures above the crystalline basement rock. A large majority of seismic activity associated with geologic structures above basement rocks is of low intensity. Of the large historical earthquakes in the southeastern United States, most have been determined to be associated with two types of structures: basement rifts and Triassic Basins. Some large earthquakes have not been correlated with any specific geologic structures. Little is known about the precise relationships between earthquakes and basement structures because the historical seismic record is too short, and the types and locations of basement structures are poorly understood. Basement rifts typically are late Precambrian to early Cambrian age and underlie the Interior Low Plateau, Mississippi Embayment, and Appalachian Basin provinces. The Precambrian rift basins are believed to have formed about 820 million years ago during separation of the North American ancestral continent from the African, European, and South American ancestral continent. Triassic basins are rift basins associated with the early opening of the Atlantic Ocean during the late Triassic period (about 200 million years ago). Triassic rift basins are buried beneath the Atlantic Coastal Plain in Georgia and South Carolina, are exposed at the surface in North Carolina and Virginia, and are exposed within the Appalachian Basin from Maryland to Connecticut. The closest Triassic Basin is located about 515 km (320 miles) east of the ORR. Earthquakes detected in association with Triassic Basins are thought to be a result of reactivated faults bounding them. The following discussion presents information regarding the 10 strongest historical quakes in the southeastern United States.

The strongest historical earthquakes in the southeast occurred in the Mississippi Embayment in 1811 along the New Madrid Seismic Zone in northwest Tennessee, northeast Arkansas, and southeast Missouri (Figure 3-7). This seismic zone, associated with the Precambrian Reelfoot Rift and Rough Creek Graben, is sourced from basement rock and offsets Holocene (recent) rocks of the Mississippi




Figure 3-7. Southeast region basement structures and major earthquakes. Depending on the method of measurements when the earthquake occurred, this graphic indicates the measurements as either intensity (Modified Mercalli Index) or magnitude.

Embayment. The strongest quake within the Atlantic Coastal Plain province occurred in 1886 and had an epicenter located at Charleston, South Carolina (Site Number 5; Figure 3-7). The geologic structure suspected of producing this earthquake is faulting associated with the rifted eastern continental margin (Triassic age). Within the Appalachian Basin, the strongest historical quake occurred in 1897 near Giles County, Virginia (Site Number 7; Figure 3-7). The epicenter for this quake correlates to a late Precambrian to early Cambrian basement rift structure buried beneath Paleozoic sedimentary rocks. Another strong-motion quake occurred in northeast Alabama and is not associated with any known basement structure or Triassic rift basin. The strongest known earthquake within the Piedmont Plateau province occurred in 1913 with an epicenter near Spartanburg, South Carolina (Site Number 9; Figure 3-7). This quake is not associated with any known basement structure or Triassic Rift basin. Within the Interior Low Plateau province, the strongest known earthquake occurred near Anna, Ohio, in

1937. The epicenter for this earthquake was near the junction of two Precambrian basement rift zones. Within 100 km (60 miles) of the ORR, the strongest historical earthquake occurred near Maryville and Alcoa, Tennessee, in 1973 and had a magnitude of 4.7. The intensity at ORNL has been estimated at about IV (Modified Mercalli), and there was no observed damage (DOE 1979). An earthquake having a magnitude of 4.2 was recorded in 1844 in the vicinity of west Knoxville, located about 38 km (25 miles) from the proposed TRU Waste Treatment Facility site (USGS 1999). An additional quake having a magnitude of 4.1 occurred in 1913 in the west Knoxville vicinity. No associated basement structure is identified with these seismic events.

According to Johnston et al. (1995) and Powell et al. (1994), a well-defined, linear zone of seismic activity exists along the southeastern border of Tennessee and North Carolina. Powell et al. (1994) states, "This zone produced the second highest release of seismic strain energy in the United States east of the Rocky Mountains during the last decade." This linear seismic zone is only second to the New Madrid seismic zone in Western Tennessee. The zone in eastern Tennessee is approximately 300 km long by 50 km wide and has not produced a damaging earthquake in historical time. The largest recorded earthquake had a magnitude of 4.6 (Powell et al. 1994).

No evidence for capable faults exists within the Appalachian Basin in the vicinity of the ORR (Blasing et al. 1992). Available seismic data and geologic studies do not indicate that regional Paleozoic faults have been reactivated during modern times. The closest capable fault (defined as having the capacity for seismic movement) is within the New Madrid seismic zone, approximately 480 km (300 miles) west of the ORR. However, earthquake energies could be transmitted from adjacent physiographic provinces where strong earthquakes have occurred in historical times. The ORR is located in Seismic Zone 2, where a probability of seismic damage is moderate (BOCA 1990). Based on available historical seismic data and factoring in dampening effects of distance, the expected earthquake intensities for the ORR as a result of historical strong-motion earthquakes may be estimated. Table 3-7 presents the maximum expected seismic intensity at the ORR based on the strongest intensity historical earthquakes in each of the five tectonic provinces discussed above.

Table 3-7. Maximum historical earthquakes and the maximum Modified Mercalli Intensity and their peak ground accelerations at the ORR[a]

Province	Maximum historical MMI[b]	Distance to ORR km (miles)	Maximum MMI[b] expected at ORR
Appalachian Basin	VIII	N/A[c]	VIII
Atlantic Coastal Plain	X	320 (200)	VII
Interior Low Plateau	VIII	50 (30)	VII
Reelfoot Rift Zone	XI–XII	400 (250)	VII
Piedmont Province	VII–VIII	200 (125)	V–VI

[a]Blasing et al. 1992.
[b]MMI - Modified Mercalli Intensity.
[c]The ORR is located within the Appalachian Basin; maximum expected intensity for this province is based on the 1897 Giles County, Virginia, earthquake.

Additional studies of potential seismic movement on the ORR have been conducted in support of final safety analysis reports (FSARs) in accordance with DOE-STD-1020. Specific studies have not been conducted at the proposed TRU Waste Treatment Facility site; however, data compiled for the South Tank Farm, located in the main plant area of ORNL in Bethel Valley, and ground-supported facilities at the Y-12 Plant in Bear Creek Valley (DOE 1998a) provide reasonable indicators of annual probability of exceedance and expected peak ground acceleration. Figure 3-8 shows the results of these seismic hazard studies for peak horizontal rock acceleration.




Figure 3-8. Peak ground acceleration and associated annual probability of exceedance for the Oak Ridge Reservation.

Those soil-supported facilities include an amplification factor of about 2.5 and are shown in Table 3-8. The design earthquake for a 50-year-life facility, with a 100-year seismic event probability is 0.06 peak ground acceleration.

Table 3-8. Seismic ground acceleration for soil-supported facilities[a]

Effective peak ground acceleration (g)	Recurrence interval (year)
0.15	500
0.20	1,000
0.30	2,000
0.65	10,000

[a]Source: DOE 1998a.
g = g force.

3.5 WATER AND WATER QUALITY

This section discusses the surface water resources (Section 3.5.1) and groundwater resources (Section 3.5.2) for the White Oak Creek Watershed, which includes the Melton Valley Watershed, where the site of the proposed TRU Waste Treatment Facility is located. The White Oak Creek Watershed defines the resource area most likely to be effected by the proposed action.

3.5.1 Surface Water

The proposed TRU Waste Treatment Facility site would be located within the Melton Valley Watershed portion of the White Oak Creek Watershed (Figure 3-9). The total drainage area of the White Oak Creek Watershed is approximately 6.15 square miles. There are no permanent surface water bodies or springs within the proposed facility site borders. However, there are two perennial streams (White Oak Creek and Melton Branch), one unnamed wet-weather tributary to White Oak Creek, and one lake (White Oak Lake) within close proximity to the proposed facility, which the State of Tennessee has determined to be Waters of the State. Melton Branch, a tributary to White Oak Creek, is about 61 m (200 ft) from the northern border of the proposed facility. White Oak Creek, which flows south into White Oak Lake, is approximately 152 m (500 ft) to the west of the proposed facility site border and is the main nearby surface water body. White Oak Lake is approximately 0.4 km (0.25 mile) downstream from where the proposed facility is adjacent to White Oak Creek. White Oak Lake discharges into the Clinch River, approximately 2.4 km (1.5 miles) downstream from the proposed TRU Waste Treatment Facility site.

White Oak Creek is a fourth-order stream that originates from springs on the southeast slopes of Chestnut Ridge, which separates ORNL from the Y-12 Plant. The creek receives natural runoff and water from the spring, as well as process water discharges, treated sewage effluent, and cooling water from ORNL facilities located in Bethel Valley, before flowing though the gap in Haw Ridge where it enters Melton Valley. Melton Branch is a third-order stream (relative to the branching of the primary stream and defines the stream's or tributary's position in the watershed) and the primary tributary to White Oak Creek. Melton Branch flows westerly in the Melton Valley portion of the White Oak Creek Watershed, joining White Oak Creek approximately 114 m (375 ft) from the proposed TRU Waste Treatment Facility site border. White Oak Lake is impounded by White Oak Dam and has a normal pool elevation of 227.1 m (745 ft) above mean sea level. Flow from the White Oak Dam discharges into the White Oak Creek Embayment, approximately 0.97 km (0.6 mile) above the confluence with the Clinch River.




Figure 3-9. Map showing the location of the White Oak Creek Watershed in relation to the Oak Ridge Reservation and the proposed TRU Waste Treatment Facility Site.

Continuous stream discharge data have been collected from several water monitoring stations on the White Oak Creek Watershed for years. Monitoring locations that are relatively close to the proposed TRU Waste Treatment Facility site are shown in Figure 3-10. Average discharges at these locations for 1993 and 1994 are summarized in the Melton Valley Remedial Investigation (DOE 1997a). The average discharge at White Oak Creek weir, which is approximately 183 m (600 ft) upstream of the confluence of Melton Branch into White Oak Creek, was 328 L/s. This discharge represents the surface water input to the system. The average discharge at Melton Branch weir on Melton Branch, which is approximately 213 m (700 ft) upstream of the proposed facility border, is 87.9 L/s. The average discharge at the White Oak Dam was 481 L/s, which represents output from the White Oak Creek Watershed.

Surface water sampling for chemical and radionuclide analyses has been ongoing for several years in White Oak Creek (Sample Station X14), Melton Branch (Sample Station X13), and White Oak Lake Dam (Sample Station X15) as part of the Biological Monitoring and Abatement Program requirements for the ORNL 1997 National Pollutant Discharge Elimination System (NPDES) Permit TN0002941, as well as the ORR Environmental Monitoring Plan. The permit limits and compliance statistics for the NPDES sampling are presented in Table 3-9. Table 3-9 shows the daily and monthly permit limits for a variety of water quality parameters. It also shows the number of noncompliances per parameter in relation to the number of samples taken for that parameter. For example, in 1997 there were two exceedances of in-stream chlorine at the Melton Branch X-16 location out of 147 samples [14 of the 19 noncompliance measurements were for total residual chlorine (TRC)]. Dechlorination systems were upgraded to guard against reoccurrences (ORNL 1998), resulting in only two noncompliances for TRC at ORNL in 1998 (ORNL 1999a). The exceedances for the daily maximum concentration and daily maximum loading of the carbonaceous biochemical oxygen demand (CBOD) limit on October 9, 1997, were addressed by a corrective measure on the dechlorination system feed modification at the Sewage Treatment Plant, which resulted in no more exceedances after the one on October 9, 1997 (ORNL 1999a). One Category IV outfall, 302, had one pH measurement of 9.1 on November 17, 1997, which exceeded the permit upper limit of 9.0. A corrective action to identify and repair an underground leak in a waste treatment system component prevented any additional pH noncompliances at the outfall that year, but did allow an additional exceedance of pH 9.6 on January 13, 1998 (ORNL 1999a).

Concentrations of total strontium at all three locations were greater than 4% of the relevant derived concentration guides in 1997 (ORNL 1998). Concentrations of tritium at Melton Branch (Sample Station X-13) and White Oak Lake Dam (Sample Station X15) were greater than 4% of the derived concentration guidelines in 1997 sampling. Figure 3-11, from the Annual Site Environmental Report (ORNL 1998), shows the discharges in curies of several radionuclides at White Oak Dam from 1993–97.

Water samples were collected from four locations on White Oak Creek in November 1997 and analyzed for mercury (ORNL 1998). The most upstream location from ORNL (White Oak Creek kilometer 6.8) had 11 ng/L, which was similar to background or reference streams in East Tennessee. The mercury concentrations at White Oak Creek kilometer 2.9 and White Oak Lake Dam were 160 and 63 ng/L, respectively.




Figure 3-10. Map of surface water monitoring locations in White Oak Creek Watershed near the proposed TRU Waste Treatment Facility.


Table 3-9. ORNL NPDES Permit TN0002941 permit limits and compliance statistics (1997)

Discharge point	Effluent parameters	Permit limits					Permit compliance		
		Monthly avg. (kg/d)	Daily max. (kg/d)	Monthly avg. (mg/L)	Daily max. (mg/L)	Daily min. (mg/L)	Number of noncompliances	Number of samples	Percentage of compliance[a]
X01 (Sewage Treatment Plant)	96-h LC_{50} for *Cerodaphnia* (%)					41.1	0	3	100
	96-h LC_{50} for fathead minnows (%)					41.1	0	3	100
	Ammonia, as N (summer)	2.84	4.26	2.5	3.75		0	79	100
	Ammonia, as N (winter)	5.96	8.97	5.25	7.9		0	64	100
	Carbonaceous biochemical oxygen demand	8.7	13.1	10	15		2	143	99
	Dissolved oxygen					6	0	144	100
	Fecal coliform (col/100 ml.)			1000	5000		0	144	100
	No-observed-effect conc. for *Ceriodaphnia* (%)					12.3	0	3	100
	No-observed-effect conc. for fathead minnows (%)					12.3	0	3	100
	Oil and grease	8.7	13.1	10	15		0	144	100
	pH (std. units)				9	6	0	144	100
	Total residual chlorine			0.038	0.066		2	147	99
	Total suspended solids	26.2	39.2	30	45		0	143	100
X02 (Coal Yard Runoff Treatment Facility)	96-h LC_{50} for *Ceriodaphnia* (%)					4.2	0	4	100
	96-h LC_{50} for fathead minnows (%)					4.2	0	4	100
	Copper, total			0.07	0.11		0	22	100
	Iron, total			1.0	1.0		0	22	100
	No-observed-effect conc. for *Ceriodaphnia* (%)					1.3	0	2	100
	No-observed-effect conc. for fathead minnows (%)					1.3	0	2	100
	Oil and grease			10	15		0	48	100
	pH (std. Units)				9.0	6.0	0	48	100
	Selenium, total			0.22	0.95		0	22	100
	Silver, total				0.008		0	22	100
	Total suspended solids				50		0	48	100
	Zinc, total			0.87	0.95		0	22	100


Table 3-9. ORNL NPDES Permit TN0002941 permit limits and compliance statistics 1997 (continued)

Discharge point	Effluent parameters	Permit limits					Permit compliance		
		Monthly avg. (kg/d)	Daily max. (kg/d)	Monthly avg. (mg/L)	Daily max. (mg/L)	Daily min. (mg/L)	Number of noncompliances	Number of samples	Percentage of compliance[a]
X12 (Nonradiological Wastewater Treatment Facility)	96-h LC$_{50}$ for *Ceriodaphnia* (%)					100	0	4	100
	96-h LC$_{50}$ for fathead minnows (%)					100	0	4	100
	Cadmium, total	0.79	2.09	0.008	0.034		0	48	100
	Chromium, total	5.18	8.39	0.22	0.44		0	48	100
	Copper, total	6.27	10.24	0.07	0.11		0	48	100
	Cyanide, total	1.97	3.64	0.008	0.046		0	4	100
	Lead, total	1.3	2.09	0.028	0.69		0	48	100
	Nickel, total	7.21	12.06	0.87	3.98		0	48	100
	No-observed-effect conc. for *Ceriodaphnia* (%)					30.9	0	4	100
	No-observed-effect conc. for fathead minnows (%)					30.9	0	4	100
	Oil and grease	30.3	45.4	10	15		0	48	100
	pH (std. units)				9.0	6.0	0	144	100
	Silver, total	0.73	1.3		0.008		0	48	100
	Temperature (°C)				30.5		0	144	100
	Total toxic organics		6.45		2.13		0	11	100
	Zinc, total	4.48	7.91	0.87	0.95		0	48	100
In-stream chlorine monitoring points	Total residual oxidant			0.011	0.019		2	242	99
Steam condensate outfalls	pH (std. units)				9.0/8.5	6.0/6.5	0	17	100
Groundwater/ pump water outfalls	pH (std. units)				9.0/8.5	6.0/6.5	0	8	100
Cooling tower blowdown outfalls	pH (std. units)				9.0	6.0	0	2	100
Category I outfalls	pH (std. units)				9.0	6.0	0	13	100
Category II outfalls	pH (std. units)				9.0	6.0	0	15	100
Category III outfalls	pH (std. units)				9.0	6.0	0	63	100
Category IV outfalls	pH (std. units)				9.0	6.0	1	296	100
Cooling tower blowdown/ cooling water outfalls	pH (std. units)				9.0	6.0	0	44	100
	Total residual oxidant			0.11	0.019		12	53	77


[a]Percent compliance = 100 [(number of noncompliances/number of samples) * 100].
d = day; kg = kilogram; L = liter; and mg = milligram.
NPDES = National Pollutant Discharge Elimination System.
Period of coverage January 1 to December 31, 1997.
Source Oak Ridge National Laboratory (1998)




(a) Cobalt-60 discharges at White Oak Dam, 1993–97.




(b) Cesium-137 discharges at White Oak Dam, 1993–97.




(c) Gross alpha discharges at White Oak Dam, 1993–97.



(d) Gross beta discharges at White Oak Dam, 1993–97.



(e) Total radioactive strontium discharges at White Oak Dam, 1993–97.



(f) Tritium discharges at White Oak Dam, 1993–97.

Figure 3-11. Discharge (in curies) of various radionuclides at White Oak Dam, 1993–97.

In-stream toxicity monitoring at White Oak Creek, Melton Branch, and White Oak Lake, as part of the Biological Monitoring and Abatement Program, was terminated in 1997 because toxicity had not been detected for the previous several years (ORNL 1998). Although wastewater from the Sewage Treatment Plant and two other facilities at ORNL is evaluated for toxicity, these facilities are too far upstream from the proposed TRU Waste Treatment Facility site for the toxicity results to be relevant.

Detailed results of the water sampling under the Environmental Monitoring Plan for White Oak Creek, White Oak Lake, and Melton Branch for 1997 are presented in ORNL 1998. The sampling frequency and sample parameters for these locations are presented in Table 3-10.

Table 3-10. Locations, frequency, and parameters for the Environmental Monitoring Plan surface water sampling at ORNL

Location (K indicates kilometer)	Frequency	Parameters
Melton Branch (K 0.2); Melton Branch downstream from ORNL	Bimonthly (Jan., Mar., May, July, Sept., Nov.)	Gross alpha, gross beta, gamma scan, total radioactive strontium, tritium, and field measurements[a]
White Oak Creek (K 1.0); White Oak Lake at White Oak Dam	Monthly	PCBs, gross alpha, gross beta, gamma scan, total radioactive strontium, tritium, and field measurements[a]
White Oak Creek (K 2.6); White Oak Creek downstream from ORNL	Bimonthly (Jan., Mar., May, July, Sept., Nov.)	Gross alpha, gross beta, gamma scan, total radioactive strontium, tritium, and field measurements[a]
White Oak Creek (K 6.8); White Oak Creek upstream from ORNL	Quarterly (Feb., May, Aug., Nov.)	Gross alpha, gross beta, gamma scan, total radioactive strontium, tritium, and field measurements[a]

[a]Dissolved oxygen, pH, and temperature.
ORNL = Oak Ridge National Laboratory.
PCB = polychlorinated biphenyl.
Source: ORNL (1998).

Radionuclides were detected (statistically significant at the 95% confidence interval) at all three locations (Table 3-11). The highest levels of gross beta, total radioactive strontium, and tritium were at these three locations; however, there is no regulatory standard for gross levels of radioactivity, as standards are done on a radionuclide basis. PCB Aroclor-1254 was detected in 5 of 12 samples at the White Oak Lake Dam (0.36 ± 0.087 mg/L).

Table 3-11. Summary of radionuclide activities during the 1997 Environmental Monitoring Plan surface water sampling

Parameter (all activities are pCi/L, mean ± one standard deviation)	Location		
	White Oak Creek (White Oak Creek kilometer 2.0) M = 12	White Oak Lake (White Oak Creek kilometer 1.0) M = 6	Melton Branch (Melton Branch kilometer 0.2) M = 6
Gross beta	280 ± 19	180 ± 20	490 ± 63
Total radioactive strontium	130 ± 8.3	82 ± 7.7	250 ± 41
Tritium	99,000 ±12,000	18,000 ± 2,000	470,000 ± 90,000

M = number of samples.
Source = ORNL (1998).

ORNL treats over 180 million gal per year of non-radiological wastewater, and typically has over 650,000 gal of hold-up capacity for this type of wastewater upon receipt at their waste water treatment facility. The Y-12 Plant is permitted to discharge up to 1.4 million gal per day to the City of Oak Ridge's wastewater treatment system, and during 1996, this flow averaged about 0.854 million gal per day. The ETTP provides its own treatment of sanitary wastewater and is currently operating under capacity. The City of Oak Ridge has overall design capacity for treating up to 5.87 million gal per day and is currently operating under capacity (Roy 1999).

In summary, the surface water from White Oak Creek, White Oak Lake, and Melton Branch contains elevated concentrations of radionuclides (total strontium and tritium), mercury, and PCBs relative to background or reference streams. The elevated surface water concentrations of mercury and PCBs have resulted in elevated concentrations of these constituents in fish from these locations as indicated in Section 3.3.3. However, the overall water quality is good, such that no toxicity to aquatic organisms had been observed for several years and the toxicity testing was discontinued in 1997.

3.5.2 Groundwater

The *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee* (DOE 1997a), served as the primary source of information for the current groundwater conditions in the Melton Valley Watershed on the ORR.

3.5.2.1 Regional conceptual model

Solomon et al. (1992) developed a generalized conceptual hydrologic framework for the entire ORR including the Melton Valley Watershed at ORNL. The geologic units of the ORR were assigned to two broad hydrologic groups: (1) the Knox aquifer (formed by the Knox Group and the Maynardville Limestone), which is dominated by solution conduits and stores and transmits relatively large volumes of water, and (2) the ORR aquitards (made up of all other geologic units of the ORR), in which flow is controlled by fractures that may store fairly large volumes of groundwater, but transmit only limited amounts. The Melton Valley Watershed is underlain by both geologic units as shown in Figure 3-12. In vertical cross-sections, both the Knox aquifer and the ORR aquitards are further divided into zones, including the storm flow zone, the vadose zone, and the groundwater zone, shown conceptually in Figure 3-13. The storm flow zone is a thin region at the surface in which transient, precipitation-generated flow accounts for a large portion of the water moving through the subsurface. This zone is a major pathway for transporting contaminants from the subsurface to the surface. The vadose zone is a mostly unsaturated zone above the water table. The groundwater zone, which is continuously saturated, is the region where most of the remaining subsurface flow occurs. Zones where permeability is low and groundwater movement is extremely slow are called aquitards.

In most of the Melton Valley Watershed, the water table lies at or somewhat above the bedrock/soil weathering interface. Recharge to the water table can occur both as porous medium flow through the soil and as flow through relict bedding planes and fractures in the soil connecting the surficial soil to the water table. Below the water table, the spatial density, aperture, orientation, and connectivity of fractures control the transmissivity and actual flow paths of groundwater. The predominant groundwater flow and contaminant migration direction in the shallow groundwater system is parallel to local geologic strike because of the abundance of open bedding planes and bed-normal fractures. Small-scale (tens of meters) folds and fracture sets control seepage pathways. Shallow groundwater is observed to migrate via fractures, generally along strike, to local surface water streams. Anthropogenic features, including pipeline trenches and waste burial trenches, can conduct groundwater along their orientations and provide pathways for contaminant transport.




Figure 3-12. Distribution of geologic units in the Melton Valley Watershed Remedial Investigation Area that are assigned to two broad hydrologic groups: the Knox Aquifer and the ORR aquitards.




Figure 3-13. Near-surface hydrogeologic zones.

The hydraulic conductivity of subsurface materials is observed to decrease rapidly with increasing depth below the water table. At increasing depths below the water table, the degree of bedrock weathering decreases; thus, fractures tend not to be enlarged. Additionally, overburden pressure tends to keep fractures tightly closed at great depths. Analysis of conductivity tests in screened wells suggests that the spacing of hydraulic active fractures ranges from 7 m (23 ft) near the water table to >35 m (115 ft) at depths of >60 m (197 ft) (Solomon et al. 1992). This decrease in fracture density equates to a decrease in water-transmitting capability in the rock mass with increasing depths. The geochemical profile typically observed in the ORR groundwater system is $CaHCO_3$ groundwater in the water table interval, Na-Ca-HCO_3 groundwater in the Intermediate interval, and NaCl brines in the Deep interval, which reflects fresh water flushing near surface, mixing of water types at intermediate depths, and stagnation of groundwater in the Deep interval.

A compilation of information from numerous investigations performed at specific locations throughout the ORR allowed the development of a valley-wide conceptual model of groundwater flow in Melton Valley. From the large-scale groundwater flow concept, general conditions can be inferred that will control solute of contaminant transport. The key factors that determine the groundwater flow system are soil characteristics, land cover, topography, stratigraphy, and geologic structure. Soil characteristics exert a strong influence on the amount of precipitation that infiltrates the soil and is available for lateral storm flow movement in undisturbed areas of percolation to the water table in areas of disturbed soil profiles. Land cover type exerts a strong influence on evapotranspiration, which effectively removes water from the shallow soils by plant transpiration. Soil characteristics are also important in groundwater flow because much of the "soil" in Melton Valley is residuum of bedrock, and numerous relict fractures are retained in the deeply weathered material. These fractures form a network of avenues for percolation of recharge downward to the water table and also provide avenues for groundwater flow in areas where the water table interval lies in the base of the soil. Stratigraphy and geologic structure influence the groundwater flow system in Melton Valley by determining the types of solid material, and flaws in those materials, through which the groundwater flows. Most of the bedrock materials that underlie Melton Valley have extremely low effective porosity (connected intergranular pores), and most groundwater movement occurs in weathered zones (including residuum near the water table) or in fractures (either in residuum or in bedrock).

Geologic structure in Melton Valley occurs at several scales, each of which has importance to the groundwater flow system. The regional geologic structure is defined by the regional thrust faults such as the Copper Creek Fault. At the regional scale, strike and dip of geologic formations define the three-dimensional orientation and location of the geologic formations. Water-bearing and transmitting properties of the geologic formations vary with the stratigraphic makeup and degree of structural deformation. In Melton Valley the geologic formations with the best water-bearing potential include the Rome Formation and the Maryville Limestone. At the valley-wide scale, there are zones of intraformational folds and faults and various cross-cutting fracture and shear zone orientations that are locally important to groundwater flow. The dimensions of these zones are difficult to define in the Valley and Ridge Province because of extensive soil cover over bedrock. These zones are best identified in large excavations. The thickness of such zones, or outcrop width, is highly variable and, to date, no correlations of individual features within this type of deformation zone have been demonstrated. There is evidence of such intraformational folding and faulting in the Maryville Limestone in a nearly strike-parallel band extending just north of the proposed TRU Waste Treatment Facility. The hydrogeologic importance of such zones varies depending upon the type of bedrock and structural deformation involved. In cases where limestone bedrock is intensely deformed, fracture density can be increased, bedrock weathering may be enhanced, and groundwater flow may increase. Conversely, if such deformation involves mostly shaley bedrock and the deformation causes extensive shearing, fractures may become sealed with rock flour or "gouge," and such zones can become less permeable than surrounding, less deformed bedrock. At the outcrop scale and smaller, individual folds,

fractures, or shears ranging from meter or centimeter size down to microscopic features exist. Structural features at these scales are important when they are part of a connected network of fractures and are capable of transmitting groundwater along with its dissolved or suspended constituents. Outcrop-scale structural features are sometimes the observed points of groundwater emanation in seeps or springs.

Hydraulic conductivity measurements have been taken in many wells in the Melton Valley Watershed. Most of the available test results are from various types of single-well tests such as slug tests, rising head recovery tests, and packer tests. Hydraulic conductivity values, obtained by such methods in fractured rock, represent a value obtained by dividing the discharge of the test by the total borehole length included in the test, and thus provide an averaged conductivity value. Such tests overestimate the conductivity of unfractured materials and underestimate the conductivity of the fractures themselves. Hydraulic conductivity measurements collected from the Melton Valley Watershed suggest much higher conductivity in the shallow portion of the groundwater zone than at greater depths.

Borehole testing and empirical observations indicate that in the ORR the combination of stratigraphy (and the orientation of more soluble bedrock zones) and geologic structure combine to provide many dipping, strike-parallel zones of high transmissivity (Lee and Ketelle 1987; Ketelle and Lee 1992). Detailed site investigations at several sites throughout the ORR demonstrate that highly transmissive zones in bedrock are frequently on the order of one to several meters thick. Many of these transmissive zones are confined between lower transmissivity zones, and groundwater flow is parallel to the direction of highest permeability. An example of this condition is seen in the confined freshwater zone in the Upper Rome Formation beneath Melton Valley (DOE 1995). The results of a three-dimensional monitored pumping test (Lee et al. 1992) show that there may be little or no hydraulic connection in the direction perpendicular to confining beds.

In classical analyses of groundwater flow derived from porous media hydraulics, groundwater flow lines that originate from recharge areas near a stream or discharge boundary follow shallow pathways. In the same idealized porous medium case, groundwater flow lines that originate from recharge areas near a groundwater basin boundary show seepage downward and laterally beneath the shallower seepage paths to the discharge boundary. The conceptual model of groundwater movement in the Melton Valley area, derived from site observations, includes similarities and differences in comparison to the classical flow net concept.

Historically, groundwater system descriptions for the Melton Valley area have postulated groundwater zonation on the basis of depth below ground surface citing observed depth-dependent decreases in hydraulic conductivity measurements and geochemical stratification. These observations broadly describe the general conditions; however, they lead the reader to infer that groundwater flow zones are, likewise, nearly horizontally distributed. The combination of interbedded stratigraphy, dipping and fractured structural conditions, and rugged topography leads to highly discrete, local-scale groundwater flow zones with irregular geochemical interfaces in the subsurface. Hydrogeologic investigations performed in the Melton Valley Watershed within the past several years reveal the strong roles that stratigraphy, geologic structure, and topographically derived head differentials play in the groundwater system.

The most prominent features with respect to hydraulic head are a high-head zone in the Rome Formation extending down-dip beneath Haw Ridge and extending beneath the confining layer formed by the Pumpkin Valley Shale. Fresh water recharge on Haw Ridge associated with the Rome Formation and fractured and weathered bedrock in the Copper Creek Fault Zone are responsible for this feature (DOE 1995). A well that penetrated this interval flowed artesian at 40 gal per minute for several days

before it was plugged with no apparent decrease. Fresh water was observed to flow down-dip in this system and actually lies beneath the transition zone sodium-calcium bicarbonate groundwater present in overlying beds. Wells that penetrate this zone tend to be flowing artesian, and springs are observed in this interval along Haw Ridge where stream erosion has dissected the ridge. Head pressure derived from this zone may extend down-dip in the Rome Formation beneath the axis of Melton Valley; although deep monitoring data from hydrofracture-associated wells indicate that artesian heads are present, the water is saline in this zone at depth. No estimates have been made of the volume of groundwater flow in this confined zone. The proposed TRU Waste Treatment Facility site is located over the Nolichucky Shale. The Nolichucky Shale outcrops along the southeastern floor of Melton Valley and underlies Melton Branch and lower White Oak Creek and White Oak Lake. The Nolichucky acts as a weak confining unit overlying the Maryville Limestone. In general, the hydraulic head observed in the Nolichucky Shale is consistent with its low topographic position. All factors favor regional groundwater flow parallel to strike toward White Oak Lake and the Clinch River.

3.5.2.2 Site-specific groundwater conceptual model

Flow within the shallow groundwater flow system is generally limited to the uppermost 31 m (100 ft) of saturated regolith, saprolite, and bedrock (DOE 1996a). This area is generally a zone of groundwater discharge, and any contributions to the groundwater from surface sources from the proposed TRU Waste Treatment Facility site could be expected to discharge to either White Oak Creek or Melton Branch. These general points of discharge (White Oak Creek and Melton Branch) are illustrated on the water table map presented as Figure 3-14. Any groundwater recharge at the proposed TRU Waste Treatment Facility site would be expected to remain in the Nolichucky Shale until discharge at the nearby stream(s). In a worst-case scenario, recharge would reach the underlying Maryville Limestone, but even then groundwater would only flow into the more conductive Maryville Limestone in order to more quickly reach the discharge boundary (Melton Branch or White Oak Creek).

Details of the deep groundwater flow system, as outlined previously in the regional conceptual model, generally hold for the deep flow system at the proposed TRU Waste Treatment Facility site. However, at great depth [approximately 305 m (1,000 ft) below ground surface and in the presence of natural brines], waste/grout mixtures were injected by the hydrofracture waste disposal process into the underlying lower Pumpkin Valley Shale. The injected material is suspected to have moved primarily updip, or to the north (DOE 1996a), simultaneously propagating and filling fractures. The hydrofracture waste disposal process resulted in the emplacement of approximately 38,228 m^3 (10.1 million gal) of radioactive wastes and grout containing an aggregate of approximately 1.4 million curies of radioactivity in the 43 grout injections performed between 1959 and 1984. Most of these injections took place at the New Hydrofracture Facility located adjacent to and east of the proposed TRU Waste Treatment Facility site location, or at the Old Hydrofracture Facility located to the northeast across Melton Branch. These waste/grout injection actions are expected to have reduced the permeability of this deep flow system, and consequently limited groundwater flow at this depth. The locations of the Old and New Hydrofracture Facilities, and the anticipated lateral extent of the waste/grout sheets, and of the impacted brine water, are illustrated in Figure 3-15.

3.5.2.3 Groundwater quality

According to the *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge, Tennessee* (DOE 1997a), the unlined trenches at SWSA 5 North are estimated to contain 14,000 curies and contribute about 6% of the total strontium-90 and 3.6% of the cesium-137 released to surface water in Melton Valley. This rate of release will likely reduce with respect to time because of radioactive decay. The contaminated soils around the underground trenches, and between the trenches




Figure 3-14. Average water table elevation in the Melton Valley Watershed.




Figure 3-15. Locations of the hydrofracture facility sites, contaminated brine area, injected waste/grout sheets, and groundwater wells.

and White Oak Creek, will also act as a secondary source of contamination to groundwater. Well samples taken adjacent to the SWSA 5 North trenches also showed elevated levels of americium-241 and curium-244 ranging as high as 5,940 pCi/L.

Groundwater quality at the location for the proposed TRU Waste Treatment Facility site must be considered in two separate categories: (1) deep groundwater quality and (2) shallow groundwater quality. The deep groundwater brine approximately 305 m (1,000 ft) below ground surface has been impacted with the radioactive waste injected during the operation of the hydrofracture facilities. However, these past waste disposal processes have done little to impact the shallow groundwater quality. There has been some minor impact to the shallow groundwater as would be expected near a historic industrial facility.

3.5.2.4 Groundwater exit pathways

Shallow groundwater at the proposed TRU Waste Treatment Facility site can be expected to discharge to the north into either Melton Branch or White Oak Creek. Due to the site's close proximity to this regional discharge boundary, it is unlikely that groundwater from the site could discharge anywhere else. A contaminant groundwater discharge point known as "Seep D" is located in the Melton Branch streambed just upstream of the Melton Branch-White Oak Creek confluence. This seep contains high concentrations of strontium-90 and tritium and was part of a previous removal/remedial action. The contaminant source for Seep D is suspected to be groundwater originating in Solid Waste Storage Area 5 and not from the hydrofracture grout sheets. The presence of this seep suggests a good connection with the underlying Nolichucky Shale.

3.5.3 Wetlands and Floodplains

There are six wetlands within 0.8 km (0.5 mile) of the proposed TRU Waste Treatment Facility site, herein labeled as Wetlands A, B, C, D, E, and F (Figure 3-16). The wetlands were identified using three sources of information, including: (1) a report on wetland delineation on the proposed TRU Waste Treatment Facility site (Jacobs and Rosensteel 1999); (2) an on-site reconnaissance by wetland scientists from SAIC on June 2, 1999; and (3) review of National Wetland Inventory maps. The six wetlands are briefly described below. A wetlands assessment was also performed (Appendix C.6).

Jacobs and Rosensteel (1999) identified and delineated four small wetlands (Wetlands A, B, C, and D) on, or adjacent to, the TRU Waste Treatment Facility site (Figure 3-16). A copy of the report, which contains detailed descriptions of the wetlands along with copies of the field data sheets, is presented in Appendix C.1. Wetlands A, B, and C were delineated during the field survey of the TRU Waste Treatment Facility site on April 20, 1999. Wetland D was initially identified in April 1992 by B. Rosensteel and was not delineated again. Wetland A is approximately 0.146 ha (0.36 acres) and is located approximately 91 m (298 ft) south of the southwest corner of the TRU Waste Treatment Facility site (Figure 3-16). It is a saturated, temporarily flooded, palustrine emergent wetland in an intermittent stream drainage. The stream originates upslope near the base of Copper Ridge and flows through a clearing where the wetland has developed around seeps that contribute to the stream flow. Soil samples from several locations in the wetland had low chroma color matrix, mottles, and oxidized rhizopheres (root channels). Dominant vegetation at Wetland A included several obligate species [sweetflag (*Acorus calamus*), black willow (*Salix nigra*), monkey flower (*Mimulus ringens*), bugleweed (*Lycopus virginicus*), and cattail (*Typha latifolia*)], as well as several faculative wet species [soft rush (*Juncus effusus*), silky dogwood (*Cornus amomum*), boxelder (*Acer negundo*), green ash (*Fraxinus pennsylvanica*), and turnflower rush (*Juncus biflorus)*].




Figure 3-16. Wetlands, 100-, and 500-year floodplains near the proposed TRU Waste Treatment Facility site.

Wetland B is only 0.012 ha (0.03 acres) and is located in an intermittent stream along the eastern side of the proposed TRU Waste Treatment Facility site (Figure 3-16). This wetland is temporarily flooded and saturated and is palustrine scrub-shrub (Jacobs and Rosensteel 1999). An old road-crossing culvert located downstream from the site acts to slow and retain stream flow, thereby causing the riparian zone saturation at the wetland. The soil included fine gravel alluvium and silt loam with low chroma matrix, mottles, and partially decomposed plant fragments. Dominant plant species include sweetgum (*Liquidambar styraciflua*), green ash saplings, silky dogwood, sedges (*Carex* spp. and *Scirpus* spp.), sweetflag, and meadow spike-moss (*Selaginella apoda*).

Wetland C is 0.036 ha (0.09 acres) and is located approximately 91 m (298 ft) south of the proposed TRU Waste Treatment Facility site's southeast corner (Figure 3-16). Wetland C is saturated, palustrine emergent, and located in a disturbed, grassy area upslope (Jacobs and Rosensteel 1999). Wetland C is periodically mowed, so the wetland is in a topographic low area that might have contained a section of intermittent stream prior to land disturbance and hydrological alterations. Water discharges from seeps in the wetland and then re-enters the ground at the downslope end of the wetland.

Wetland D is 0.016 ha (0.04 acres) and is located in the northwest corner of the proposed TRU Waste Treatment Facility site (Figure 3-16). This wetland is a saturated, emergent wetland. The wetland has developed in a seep area, but there is wetland hydrology due to slowing of the water flow by a culvert under the Old Melton Valley Road. Standing and flowing water were present in the wetland during the April 1999 site visit. The soil matrix color during the initial delineation in April 1992 was described as dark gray (per Munsell soil color charts) and grayish brown, with strong brown, and very dark gray mottles. Dominant plant species identified in the April 1992 survey included several obligate species such as black willow, soft rush, monkey flower, cattail, fox sedge (*Carex vulpinoidea*), shallow sedge (*Carex lurida*), and rice cutgrass (*Leersia oryzoides*).

Wetland E includes most of the floodplain of Melton Branch north of the Old Melton Valley Road along the northern perimeter of the proposed TRU Waste Treatment Facility (Figure 3-16). This wetland covers several hectares (acres). Because of potential radiological contamination of the floodplain soils, walkover and intrusive sampling of the floodplain area were not performed. This wetland was identified from National Wetland Inventory maps, which depict the area as palustrine forested wetland dominated by broad-leaved deciduous trees. Dominant plant species include boxelder, sycamore (*Platanus occidentalis*), and black willow.

Wetland F includes the shoreline and upper reaches of White Oak Lake and covers several hectares (Figure 3-16). National Wetland Inventory maps depict this area as lacustrine wetland. The shoreline includes a mixture of trees, shrubs, and persistent and nonpersistent wetland plants.

The proposed TRU Waste Treatment Facility site is not within a floodplain. The 100-year and 500-year floodplains associated with White Oak Creek are immediately north of the proposed site location, with the 500-year floodplain bordering the Old Melton Valley Road (Figure 3-16).

3.6 WASTE MANAGEMENT

The estimated waste volumes associated with the CERCLA cleanup actions for the ORR range between 170,495 m^3 and 841,005 m^3 (223,000 to 1.1 million yd^3) (DOE 1999b). In addition to the existing legacy TRU waste at ORNL, stored in the Melton Valley Storage Tanks and various storage buildings and bunkers, an additional 3,500 m^3 (4,578 yd^3) of TRU wastes are expected to be generated over the life cycle of operations (DOE 1998b). Approximately 41,000 m^3 (53,624 yd^3) of mixed

low-level waste are currently in the DOE ORR inventory, and nearly 31 million cubic meters (40.5 million yd^3) are expected to be generated over the life cycle of operations (DOE 1998b). After undergoing a range of treatments, approximately 16 million cubic meters (20.9 million yd^3) of treated effluent will be discharged under an NPDES permit (DOE 1998b). The existing legacy liquid, sludge and solid wastes, and waste storage facilities at ORNL are described in Chapter 1, Section 1.2.2. Recent historical and projected generation rates for remote-handled TRU and contact-handled TRU debris are shown in Table 3-12.

Table 3-12. Historical and projected remote-handled TRU and contact-handled TRU debris generation rates at ORNL

Waste	FY 1997	FY 1998	FY 1999	FY 2000
Remote-handled TRU	5.0 m^3	6.6 m^3	6.6 m^3	5.0 m^3
Contact-handled TRU	12.2 m^3	23.6 m^3	7.5 m^3	10.0 m^3

FY = fiscal year.
ORNL = Oak Ridge National Laboratory.
TRU = transuranic.
Source: Bechtel Jacobs (1999).

Remote-handled TRU sludge will no longer be generated after Fiscal Year 2000 due to the completion of the ORNL inactive tank wastes retrieval projects, but approximately 5.5 m^3 of TRU waste are projected to be generated annually at the Radiological Engineering Development Center at ORNL. Pretreatment of this newly generated waste is expected to be conducted in the Radiological Engineering Development Center hot cells beginning in Fiscal Year 2001 and will be an ongoing operation at the facility. Thus, over 20 m^3 of TRU waste per year is projected to be generated at ORNL. Low-level waste generation is estimated at approximately 60 m^3 per year (Scott 1999).

3.7 CLIMATE AND AIR QUALITY

3.7.1 Climate

The Oak Ridge area has a temperate, continental climate. Summers are warm and humid; winters are typically cool. Spring and fall are transitional seasons, normally warm and sunny. Severe weather—such as tornadoes or high winds, severe thunderstorms with damaging lightning or precipitation, extreme temperatures, or heavy precipitation—is uncommon. The Cumberland Mountains to the northwest help to shield the region from cold air masses that frequently penetrate far south over the plains and prairies in the central United States during winter months. During the summer, tropical air masses from the south provide warm and humid conditions that often produce thunderstorms; however, anticyclonic circulation around high-pressure systems centered in the western Gulf of Mexico can bring dry air from the southwest into the region, leading to periods of drought.

3.7.1.1 Temperature

Over the period from January 1990 through December 1996, the mean annual temperature for the Oak Ridge area was 14.6°C (58.3°F) (NOAA 1997). The coldest month is usually January, with temperatures averaging about 3.7°C (38.7°F). July is usually the hottest month of the year, with temperatures averaging 25.8°C (78.4°F).

3.7.1.2 Wind

Winds in the Oak Ridge area are controlled, in large part, by the Valley and Ridge topography. Prevailing winds are either up-valley (northeasterly) daytime winds or down-valley (southwesterly) nighttime winds. Wind speeds are less than 11.9 km/hour (7.4 mph) 75% of the time; tornadoes and winds exceeding 30 km/hour (18.5 mph) are rare. Air stagnation is relatively common in eastern Tennessee (about twice that of western Tennessee). An average of about two multiple-day air stagnation episodes occurs annually in eastern Tennessee, to cover an average of about 8 days/year. August, September, and October are the most likely months for air stagnation episodes. Figure 3-17 presents the diurnal wind patterns for the ORR.

3.7.1.3 Precipitation


The 30-year annual average precipitation is 138.5 cm (54.5 in.), including about 24 cm (9.3 in.) of snowfall (NOAA 1997). Regional precipitation for the period 1990–96 was 149.1 cm (58.7 in.) with a maximum of 169 cm (66.5 in) in 1995 and a minimum of 111.8 cm (44 in.) in 1992. Precipitation in the region is greatest in the winter months (December through February). Precipitation in the spring exceeds the summer rainfall, but the summer rainfall may be locally heavy because of thunderstorm activity. The driest periods generally occur during the fall months, when high-pressure systems are most frequent.

3.7.2 Air Quality

The proposed TRU Waste Treatment Facility site is located in the EPA Air Quality Control Region 207, which includes east Tennessee and southwest Virginia. As of 1991, the Air Quality Control Region was designated as an attainment area with respect to all National Ambient Air Quality Standards (NAAQS) criteria pollutants (ORNL 1998). The Oak Ridge area also is an attainment area with respect to NAAQS for all criteria pollutants (SO_2, particulate matter, NO_2, CO, ozone, and Pb) (ORNL 1998). ORR and ORNL sources are in compliance with all federal air regulations and TDEC air-permit requirements for non-radioactive hazardous air pollutants (Table 3-13).

The ORR is located within a Class II prevention-of-significant deterioration (PSD) area. The Great Smoky Mountains National Park is the only PSD Class I area in the vicinity of ORNL, and it is located approximately 35 miles (56 km) southeast of ORR. All areas not designated as Class I PSD areas are designated as Class II. No PSD permits have been required for any emissions source at ORNL since the promulgation of the regulations.

Air monitoring at the DOE Oak Ridge installations consists of both facility exhaust stack and ambient air monitoring adjacent to the facilities to measure radiological parameters (Table 3-14). Ambient air monitoring allows facility personnel to determine the relative level of contaminants at the monitoring locations during an emergency, measures the contributions of fugitive and diffuse sources, and permits checks on dose-modeling calculations. There are four ambient air monitoring stations in the ORNL network. Station 1 is west, southwest of ORNL; station 2 is southeast of ORNL; station 3 is on the northeast corner of the ORNL site; and station 7 is nearly on the northwest corner of ORNL (Table 3-14). Station 52 is a reference station located at Fort Loudon Dam, approximately 16 km (10 miles) from ORNL. Sampling is conducted at each station to measure absorbable gases (e.g., iodine), and gross alpha, gross beta, and gamma-emitting radionuclides, and then compared with air sampling data from the reference station (station 52).



Adapted from 1996 ORNL Permit Application for TRU and Class III/IV Storage Areas (TNHW-097).

FOSTER WHEELER ENVIRONMENTAL CORPORATION

Figure 3-17. Wind rose detected at the ORNL Tower MT2 (@ 100 m) for 1991–1995.

Table 3-13. Summary of 1997 air monitoring data in the vicinity of the ORR

Pollutant/averaging time	Nearest monitor location	Maximum per quarter 1st	2nd	3rd	4th	NAAQS TAAQS	Number of exceedances
Particulate Matter-10/24 hours	Knox Co.	69.0 μg/m^3	67.0	61.0	60.0	150 μg/m^3	0
Particulate Matter-10/annual	Knox Co.	33.0 μg/m^3				50 μg/m^3	0
Total Suspended Particles/24 hours	Knox Co.	107.0 μg/m^3	87.0	77.0	77.0	260.0 μg/m^3[a]	0
Ozone/1 hour	Anderson Co.	0.109 ppm	0.107	0.106	0.105	0.12 ppm	0
Nitrogen Oxide/annual	Loudon Co.	0.015 ppm				0.05 ppm	0
Sulfur Dioxide/3 hours	Anderson Co.	0.152 ppm	0.125			0.5 ppm	0
Sulfur Dioxide/24 hours	Anderson Co.	0.032 ppm	0.025			0.14 ppm	0
Sulfur Dioxide/annual	Anderson Co.	0.005 ppm				0.03 ppm	0
Carbon Monoxide/1 hour	Knox Co.[b]	10.3 ppm	9.6			35.0 ppm	0
Carbon Monoxide/8 hours	Knox Co.[b]	4.9 ppm	4.8			9.0 ppm	0
Lead/quarterly	Roane Co.[c]	0.13 μg/m^3	0.11	0.07		1.5 μg/m^3	0

[a]260.0 μg/m^3 primary standard, 150.0 μg/m^3 secondary standard for total suspended particulates (TSP).
NAAQS -National Ambient Air Quality Standards.
[b]Lead measurements taken from Rockwood, Tennessee.
[c]Carbon monoxide data taken from Knoxville, Tennessee.
ORR - Oak Ridge Reservation.
ppm - parts per million.
TAAQS - Tennessee Ambient Air Quality Standards.
μg - micrograms.
Source: DOE 1999a. Final EIS for Construction and Operation of the Spallation Neutron Source.

Table 3-14. Radionuclide parameter concentrations and other parameters measured at ORNL air monitoring stations, 1997

Parameter	Stations 1 (μCi/mL)	2 (μCi/mL)	3 (μCi/mL)	7 (μCi/mL)	52[a] (μCi/mL)
Beryllium-7	1.6E-14	1.0 E-14	9.8E-15	9.9E-15	1.6E-14
Cesium-137	3.1E-17	2.0E-17	5.2E-17	2.1E-17	2.3E-17
Cobalt-60	3.0E-17	ND	1.6E-17	ND	1.1E-17
Hydrogen-3	ND	7.8E-11	ND	2.6E-12	ND
Iodine-131	8.5E-16	1.5E-15	2.4E-15	9.4E-16	NA
Iodine-133	ND	2.3E-15	2.6E-15	3.7E-15	NA
Iodine-135	7.5E-15	5.6E-14	1.5E-14	ND	NA
Potassium-40	8.3E-16	9.1E-16	1.2E-15	9.3E-16	2.3E-15
Uranium-234	3.0E-17	3.6E-17	2.9E-17	4.0E-17	4.1E-17
Uranium-235	3.5E-18	ND	ND	ND	3.6E-18
Uranium-238	2.9E-17	2.6E-17	3.3E-17	3.0E-17	3.7E-17
Gross alpha	5.3E-15	4.5E-15	4.2E-15	6.3E-15	
Gross beta	1.1E-14	1.1E-14	1.0E-14	1.1E-14	

[a]Reference station located at Fort Loudon Dam.
NA = not available. ND = not detected. ORNL = Oak Ridge National Laboratory.
Source: Adapted from ORNL 1998.

3.7.2.1 Clean Air Act

Authority for enforcement of the Clean Air Act (CAA) is shared between the TDEC for nonradioactive emission sources, and the EPA for radioactive emission sources. The EPA also enforces

rules issued pursuant to the 1990 CAA Amendments, Title VI - Stratospheric Ozone Protection. The TDEC Air Permit Program ensures compliance with most of the federal CAA and TDEC rules for air emission sources.

There are a number of sources at ORNL that are exempt from the permitting requirements under the State of Tennessee rules. At the end of Calendar Year 1997, ORNL had 21 active TDEC-issued operating permits covering 250 sources.

3.7.2.2 National Emission Standards for Hazardous Air Pollutants for Radionuclides (Rad-NESHAPs)

All ORNL facilities met the emissions and test procedures found at 40 *CFR* 61, Subpart H, in 1997. Operations at ORNL are in compliance with all Federal and State air regulations and TDEC air permit requirements. In addition, continuous air monitoring is conducted at seven stacks at ORNL (Table 3-14).

The ORR facilities were in compliance with the National Emission Standards for Hazardous Air Pollutants for Radionuclides (RAD-NESHAPs) dose limit of 10 mrems/year to the maximally exposed individual of the public during 1997 (Table 3-14). Based on modeling of emissions from major and minor sources, the effective dose equivalent was 0.41 mrem/year in 1997.

3.8 TRANSPORTATION

Section 3.8.1 addresses local transportation routes, ongoing and planned road upgrade, and waste shipment information. In Section 3.8.2, national transportation routes and waste shipment data are provided as baseline information.

3.8.1 Local Transportation

Transportation in the region in and immediately adjacent to the ORR boundary consists of local access roads (such as Tennessee State Routes 95, 1700, and 62) and major interstates. The main access to the cities of Nashville and Knoxville, Tennessee, is provided by I-40, located 2.4 km (1.5 miles) south of the ORR boundary and 8 km (5 miles) from the proposed TRU Waste Treatment Facility site. The major interstate running north and south is provided by I-75, located 24 km (15 miles) south of the proposed TRU Waste Treatment Facility site. Railroad service is provided by the Southern Railway and the L&N Railway. An L&N rail line runs adjacent to the proposed TRU Waste Treatment Facility site boundary.

Transportation elements include the number of rail and truck shipments to and from the DOE sites. According to the 1993 Shipment Mobility/Accountability Collection and the Waste Manifest System for Fiscal Year 1993, ORR had 197 incoming radioactive truck shipments with a total weight of 175,662 kg (387,269 lbs), and 843 outgoing radioactive truck shipments weighing 10,496,492 kg (23,140,823 lbs). There were also 8 outgoing radioactive rail shipments totaling 451,623 kg (995,658 lbs). This shipment information includes all radioactive material, not just radioactive waste. In 1998, a total of 3,080 m^3 (108,825 ft^3) of waste was shipped from the ORR to a commercial facility (EnviroCare) in Utah without incident.

The Old Melton Valley Road begins near the south end of White Oak Dam on the east side of Tennessee State Route 95 and continues east along the north side of the proposed TRU Waste Treatment Facility site. DOE prepared a categorical exclusion (CX-TRU-98-007) for the upgrade of

this road (Appendix G). Scheduled road improvements at the intersection of Tennessee State Route 95 and the Old Melton Valley Road will accommodate Tennessee Department of Transportation sight distance and other technical requirements. The Tennessee Department of Transportation reported that 6,140 vehicles used Tennessee State Route 95 in 1998. A portion of Tennessee State Highway 58, located west of the ETTP, is scheduled to be upgraded to four lanes in the near future. Tennessee State Route 62 leading into the City of Oak Ridge, from Knoxville, bordering the ORR on the east side, is currently being upgraded.

3.8.2 National Transportation

Transportation of hazardous and radioactive materials, substances, and wastes is governed by DOT, NRC, and EPA regulations, and by the Hazardous Materials Transportation Act. These regulations are found in 49 *CFR* Parts 171-178, 49 *CFR* Parts 383-397, 10 *CFR* Part 71, and 40 *CFR* Parts 262 and 265.

Transportation mode and routing analyses were presented by DOE for TRU wastes in both the *Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (WIPP SEIS-II) (DOE 1997b) and the *Final Waste Management Programmatic Environmental Imaact Statement* (WM PEIS) (DOE 1997c). These documents established the national transportation environment in terms of the applicable government regulations and DOE policy related to transporting radiological and hazardous material, general risk criteria, and the methodology for determining national transportation routes. Transportation routes described in the *Final Waste Management Programmatic Environmental Impact Statement* (WM PEIS) (DOE 1997c) were derived from the HIGHWAY program model and the INTERLINE model, which consider population densities along the routes. These routes are depicted in the following figures: Figure 3-18 describes the TRU waste route to the Waste Isolation Pilot Plant, and the low-level waste route to the Nevada Test Site is described in Figure 3-19.




Figure 3-18. Transportation route from the ORNL in east Tennessee to the Waste Isolation Pilot Plant in southeast New Mexico.




Figure 3-19. Transportation route from the ORNL in east Tennessee to the Nevada Test Site.

TRU waste route description (Waste Isolation Pilot Plant SEIS-II Fact Sheet) (DOE 1999c)

Old Melton Valley Road west to Tennessee State Route 95, west of ORNL
Tennessee State Route 95 south to I-40 south of Oak Ridge, Tennessee
I-40 east to I-75, southwest of Knoxville, Tennessee
I-75 south to I-24, east of Chattanooga, Tennessee
I-24 west to I-59, southwest of Chattanooga, Tennessee
I-59 to I-459, northeast of Birmingham, Alabama
I-459 to I-20, southwest of Birmingham, Alabama
I-20 west to I-220, east of Shreveport, Louisiana
I-220 to I-20, around the north side of Shreveport, Louisiana
I-20 west to US-285, at Pecos, Texas
US-285 to US-180/62, at Carlsbad, New Mexico
US-180/62 to the Waste Isolation Pilot Plant, North Access Road
Waste Isolation Pilot Plant, North Access Road

Low-level waste route description (ORNL Transportation Work Instructions) (LMES 1995b)

Old Melton Valley Road west to Tennessee State Route 95, west of ORNL
Tennessee State Route 95 south to I-40, south of Oak Ridge, Tennessee
Continue on I-40, west to U.S-95, north of Needles, California
U.S-95 north to Mercury, Nevada

On the national level, about 100 million packages, classified as hazardous materials, are shipped each year (NRC 1997). A more recent radioactive materials transport study stated that, excluding DOE shipments, approximately 2 million shipments of radioactive materials consisting of 2.79 million packages are made each year (DOE 1997a). For more than 40 years, radioactive materials have been shipped in the United States with no known adverse health effects due to accidental releases. Information about accidents involving radioactive materials has been collected over a 23-year period. During that period, 349 air, highway, and rail transportation accidents occurred. Of these accidents, 307 were highway, 20 were rail related, and the remaining 22 were air related. Packages used for shipping quantities or types of radioactive materials, which could have serious consequences if released, are designed to withstand accident conditions. Accidents involving these packages have resulted in no release of radioactive material. The NRC has concluded that at least half of the radiation exposure resulting from shipments of radiological materials would be received by transportation workers, but the doses would be below allowable limits (DOE 1997a).

3.9 UTILITY REQUIREMENTS

The Tennessee Valley Authority (TVA) supplies power to the ORR, which has a current site load of 116 MW. Coal and natural gas are also used (DOE 1997b), although no gas pipeline exists in the vicinity of the proposed TRU Waste Treatment Facility site. Water is supplied to ORNL by the City of Oak Ridge Water Treatment Facility located on Pine Ridge in the northeastern portion of the ORR. This facility draws water from the Clinch River (near the Y-12 Plant, upriver from ORNL) and provides approximately 1.2 million gal per day to ORNL, 4.0 million gal per day to Y-12, and 8.8 million gal per day to the City of Oak Ridge. The facility is currently operating at approximately 50% of its 28 million gal per day capacity (McWilliams 1999).

3.10 HUMAN HEALTH

This section contains an overview of the potentially affected environment on and around the ORR and discusses the potential exposure pathways, and cites pertinent references concerning population exposure and its effects. This information has been used to evaluate the impacts and potential risks to the off-site maximally exposed individual and the collective dose to the population within 80 km (50 miles) from current ORR operations.

3.10.1 Exposure Pathways

The analyzed human exposure pathways included in this EIS are inhalation, direct radiation, ingestion, and direct contact. A primary exposure pathway is inhalation of contaminants from stack emissions. Radiological airborne effluents from ORNL consist mainly of ventilation air from radioactively contaminated areas and ventilation from reactor facilities. These discharges are treated and pass through HEPA filters before being released to the environment. NESHAPs regulations and DOE orders define a major radionuclide effluent source as an emission point that has the potential to discharge radionuclides in quantities that could result in an effective dose equivalent of 0.1 mrem or more to the public. ORR has a comprehensive air monitoring program to ensure regulatory compliance. Four exhaust stacks located in the Bethel and Melton valleys at ORNL are major radionuclide emission point sources. In 1997, ORNL had 21 minor sources, 3 of which were continuously sampled (ORNL 1998). In 1997, ORNL released approximately 148 curies of hydrogen-3 and 0.55 curies of iodine-131. The major contributor to off-site dose in 1997 was argon-141, of which 10,000 curies were released (ORNL 1998). In addition to exhaust stack monitoring, ambient air monitoring is performed to directly measure the airborne concentrations of radionuclides and pollutants at the site perimeter. Reference data are collected from a remote location not affected by activities at the ORR. Airborne radionuclides and airborne chemicals and their effects on the population within the Region of Influence are discussed in Sections 3.10.2.1 and 3.10.3.1, respectively.

Direct radiation is also an exposure pathway of concern. External gamma radiation measurements are recorded weekly at the ORR boundary to ensure that radioactive effluents from the ORR are not increasing external radiation levels significantly above background radiation levels. Direct radiation, and its effects on the nearby population, is discussed in Section 3.10.2.4. Another exposure pathway is the ingestion of contaminated vegetation and animal products produced in the surrounding areas. Samples of food that could be potentially contaminated are collected and analyzed to determine their effects and potential exposure through ingestion. This information is presented in Section 3.10.2.2

Additional exposure pathways include contact with contaminated surface water and drinking contaminated groundwater. Under the ORR Environmental Monitoring Plan, samples are collected and analyzed from 22 locations around the ORR to determine the quality of local surface water. Surface water at ORNL is collected downstream from the facility and compared to the surface water at reference locations. The water is analyzed for radionuclides and inorganic pollutants. Most residents in the Oak Ridge area do not rely on groundwater for potable supplies. Local groundwater provides some potable, domestic, municipal, farm, irrigation, and industrial uses. DOE samples residential wells in the area. These nearby residential wells are located across the Clinch River, and are hydrologically separate from the Melton Valley Watershed. Storm water and most groundwater at ORR discharge at surfacce water drainages. Therefore, monitoring springs, seeps, and surface water quality is a way to assess the extent to which groundwater from a large portion of the ORR transports contaminants. The groundwater monitoring program at ORNL consists of a network of two types of wells: (1) water quality monitoring wells built to RCRA specifications and used for site characterization and compliance purposes, and (2) piezometer wells used to characterize groundwater flow conditions.

Melton Valley is one of the major waste storage areas on the reservation. In addition to surface structures, it is the location of shallow waste burial trenches and auger holes, landfills, tanks, impoundments, seepage pits, hydrofracture wells and grout sheets, and waste transfer pipelines and associated leak sites, all of which can affect the groundwater of the region. Groundwater plumes within Melton Valley generally enter the surface water system where contaminants may be encountered. Information on the affected population due to surface water and groundwater exposure is presented in Section 3.10.3.3.

3.10.2 Pathway Modeling

Risks from the ORR operations are calculated for the maximally exposed off-site individual and the collective off-site population. The off-site population is defined as the public within 80 km (50 miles) of the ORR (ORNL 1995). The computer software program CAP-88 was used to perform the radiological dose and risk assessments for the collective off-site population and the maximally exposed off-site individual from radionuclides released into the atmosphere from ORR operations. Small quantities of chemicals are released into the atmosphere due to operations at ORR. These chemical releases are allowable under air pollution controls and are not a threat to human health. Therefore, chemical modeling is not required (ORNL 1998).

The radiological consequences from airborne contaminants are calculated using the CAP-88 program, which is a package of computer codes (contains the EPA-approved version of the AIRDOS and DARTAB) designed to demonstrate compliance with the Rad-NESHAPs, 40 *CFR* 61, Subpart H. CAP-88 is only applicable for chronic low-level exposures and is not appropriate for modeling short-term or accidental releases. The program uses a Gaussian plume equation to determine the average dispersion of radionuclides emitted from a source or stack. This model assumes that an effluent is released from a point source and is normally distributed around the central axis of the plume. It is also assumed that the atmospheric stability and wind speed determine how the contaminant is dispersed downwind from the source. Uneven terrain and fluctuations in meteorological conditions contribute to the uncertainty of the model. The CAP 88 program also models the ingestion and immersion pathways and determines the radionuclide concentrations in air and rates of deposition on ground surfaces. The concentrations in food, and intake rates to people from ingestion of vegetation and animal products in the affected area, are calculated by using Regulatory Guide 1.109 (NRC 1997) food-chain models. Radionuclide concentrations are estimated for produce, leafy vegetables, milk, and meat. Total dose and risk estimates are then calculated by combining the inhalation and ingestion intake rates with the air and ground surface concentrations. Risks are based on a lifetime risk of 5E-04 cancers per rem (risk of cancer in a lifetime is 5 in 10,000 individuals per rem of exposure) (DOE 1997d).

3.10.3 Radionuclides

3.10.3.1 Airborne Radionuclides

In 1997, 42 emission points on the ORR were modeled with CAP-88, including 25 points at ORNL, in order to estimate the effective dose equivalent to the off-site maximally exposed individual and the collective effective dose equivalent to persons residing within 80 km (50 miles) of the ORR. The effective dose equivalent calculations are conservative, and it is assumed that each person remained outside of the house, unprotected for the entire year. It was also assumed that 70% of the vegetables and produce, 44.2% of the meat, and 39.9% of the milk consumed by each individual were produced locally (e.g., a home garden). It was assumed that the remaining portion of food was produced within 80 km (50 miles) of the ORR (ORNL 1998).

The effective dose equivalent received by the off-site maximally exposed individual from airborne emissions was estimated to be 0.41 mrem for the ORR and 0.38 mrem for ORNL. This corresponds to a fatal cancer risk of 2E-07 for each of the effective dose equivalents, and can be calculated by multiplying the effective dose equivalent by the probability of an individual dying of cancer (4.1E-04 rem × 5E-04/rem). The fatal cancer risk for the general public is 5E-04/rem based on International Commission on Radiological Protection (ICRP) Publication No. 60 (ICRP 1991). The NESHAPs standard is 10 mrem, so the risk associated with these doses is minimal. In perspective, the average person receives approximately 300 mrem annually from natural background radiation. The collective effective dose equivalent to the affected population, about 879,546 persons, within 80 km (50 miles) was estimated to be 10 person-rem. This corresponds to a fatal cancer risk of 5E-03. A person-rem is the collective dose to a population group; for example, a dose of 1 rem to 10 individuals results in a collective dose of 10 person-rem. Emissions from ORNL contributed about 58% of the ORR collective effective dose equivalent, or about 5.8 person-rem, which corresponds to a calculated cancer risk of 3E-03. The estimated doses to the off-site maximally exposed individual and the affected population are shown in Table 3-15 (ORNL 1998).

Table 3-15. Calculated effective dose equivalent to the maximally exposed individual and the collective population effective dose equivalent from airborne releases in 1997

Location	Effective dose equivalent to a maximally exposed individual (mrem)	Fatal cancer risk to a maximally exposed individual	Collective population effective dose equivalent (person-rem)	Fatal cancer risk to collective population
ORNL	0.38	2E-07	5.8	5E-03
ORR	0.41	2E-07	10.0	3E-03

ORNL - Oak Ridge National Laboratory.
ORR - Oak Ridge Reservation.

These estimated doses were compared to the dose calculated from measured air concentrations of radionuclides at monitoring stations located at the ORR perimeter and remote locations. A hypothetical individual residing at the perimeter in 1997 could have received an effective dose equivalent from 0.11 to 0.32 mrem, which would result in a calculated fatal cancer risk of 6E-08 and 2E-07, respectively. This dose would include contributions from naturally occurring airborne radionuclides, radionuclides released from the ORR, and radionuclides released from any other non-DOE source. Other potential sources of radioactive emissions include a waste processing facility, a depleted uranium processing facility, a decontamination facility in Oak Ridge, and a waste processing facility in Kingston. A hypothetical person residing at the remote monitoring location would have received an effective dose equivalent of 0.13 mrem (ORNL 1998), which corresponds to a fatal cancer risk of 7E-08.

3.10.3.2 Radionuclides in food

Samples of hay, tomatoes, lettuce, turnips, milk, and fish are collected and analyzed to determine potential exposure through ingestion. The CAP-88 program was used to determine radiation doses from the ingestion of meat, milk, and vegetables due to the deposition of radionuclides from the ORR. A total of 5.3 mrem was calculated for the maximally exposed individual from all sources, which are discussed below. When compared to the average annual background radiation for individuals of 300 mrem the risk associated with the ingestion is small.

The milk sampling program in 1997 consisted of grab samples collected every other month from three locations near the ORR. The milk samples are analyzed at ORNL for iodine-131, potassium-40,

total strontium (strontium-89 and strontium-90), and hydrogen-3, all of which are found in the natural environment. Only strontium and potassium-40 were detected in the milk, and potassium-40 is not emitted from the ORR. It was assumed that if a hypothetical person drank 310 liters (328 quarts) of this milk during the year, the individual would receive an effective dose equivalent between 0.66 and 1.5 mrem (ORNL 1998), which corresponds to a hypothetical cancer risk of 3E-07 and 8E-07, respectively. Hay samples were cut from six areas in 1997, and an additional site, near Fort Loudon, was used as a reference site. The samples were analyzed for gross alpha and beta, and gamma emitters. Composite samples (from areas 1, 2, and 3, and areas 2, 4, and 5) had statistically significant results for cesium-137, gross beta, and beryllium-7. The two individual locations, area 6 and area 8 (the reference location), had statistically significant results for gross beta and beryllium-7. Beryllium-7 is a naturally occurring isotope. There were no other statistically significant radiological results in the 1997 hay samples.

Tomatoes, lettuce, and turnips were purchased from five farmers near the ORR in 1997. These vegetables represent the fruit-bearing, leafy, and root vegetables. The sampled locations were chosen based on availability and the likelihood of the produce being affected by routine operations on the ORR. A hypothetical person was assumed to have eaten 32 kg (71 lbs) of homegrown tomatoes, 10 kg (22 lbs) of homegrown leafy vegetables, and 37 kg (82 lbs) of homegrown root vegetables during the year. This would result in a conservative total effective dose equivalent of 3.4 mrem, practically all of which results from potassium-40, which is a naturally occurring radionuclide and is not emitted from the ORR. If potassium-40 is excluded, this hypothetical person would receive about 0.008 mrem (ORNL 1998), which corresponds to a calculated cancer risk of 4E-09.

Annual deer, geese, and wild turkey hunts are held on the ORR. Bone and tissue samples are analyzed from each group of animals, and the geese and turkey are subjected to whole-body gamma scans. Hunters take their deer to various stations on the ORR where bone and tissue samples are analyzed in the field to ensure that release criteria are met. If 20 picocuries per gram (pCi/g) of beta activity is found in the bone or 5 pCi/g of cesium-137 in edible tissue, the deer is confiscated. In 1997, 429 of the 438 deer killed were released to hunters. An individual who consumed one average-weight deer (about 37 kg or 82 lbs) with the average concentration of 0.07 pCi/g of cesium-137 would have received an effective dose equivalent of about 0.07 mrem; a calculated fatal cancer risk would be 4E-08. Tissue samples were not analyzed for strontium-90 in 1997, but the maximum concentration in 1996 was 0.002 pCi/g. The maximum hypothetical effective dose equivalent, about 3 mrem, was assumed to result from eating the heaviest deer with the highest concentration of cesium-137 (1.37 pCi/g) and of strontium-90 (0.002 pCi/g) (ORNL 1998). This would result in a hypothetical cancer risk of 2E-06.

During 1997, 83 geese were collected and only 1 was retained. Approximately one-half of the weight of the goose is edible, and the average cesium-137 concentration in 1997 was 0.07 pCi/g. Analysis for strontium-90 was not performed in 1997, but in 1995, the average concentration in tissue was approximately 7 pCi/g. Most hunters kill an average of one or two geese per hunting season. If a person consumed an average-weight goose (about 4 kg or 9 lbs) with 0.07 pCi/g of cesium-137 and 7 pCi/g of strontium-90, the individual would receive an effective dose equivalent of about 2 mrem. The calculated fatal cancer risk would be 1E-06. The highest possible effective dose equivalent in 1997 would have been about 4.5 mrem, which corresponds to a hypothetical cancer risk of 2E-06, and would have resulted from eating a hypothetical goose (the heaviest goose with the maximum cesium-137 and strontium-90 concentrations) (ORNL 1998).

A total of 90 wild turkeys were killed on the ORR during 1997, and one of these was retained. The average weight of the turkeys was 8.5 kg (19 lbs), and the average cesium-137 concentration was 0.1 pCi/g. The strontium-90 concentration was determined from tissue samples analyzed in 1997 to be

0.22 pCi/g. A person who ate an average turkey would have received an effective dose equivalent of about 0.021 mrem. A person who ate a hypothetical turkey (a combination of the heaviest turkey and the highest cesium-137 concentration) would have received an effective dose equivalent of about 0.17 mrem (ORNL 1998).

Dose estimates were also performed from eating fish from the Clinch and Tennessee River systems. Fish are collected from three locations on the Clinch River, and the edible portion is analyzed for selected metals, pesticides, PCBs, cobalt-60, cesium-137, and total strontium. A maximally exposed individual was assumed to have eaten 21 kg (46 lbs) of fish in 1997 for this analysis, with the average person consuming 6.9 kg (15 lbs). Based on the fish samples, a maximally exposed individual would have received an effective dose equivalent of 0.045 mrem, and the collective population effective dose equivalent was 0.017 person-rem (ORNL 1998).

3.10.3.3 Waterborne radionuclides

Radionuclides discharged to surface waters from the ORR enter the Tennessee River system via the Clinch River and various feeder streams. Discharges from ORNL enter the Clinch River via White Oak Creek and White Oak Lake. Two methods are used to estimate radiation doses to persons who drink the water, swim, boat, and use the shoreline at various locations along the Clinch and Tennessee Rivers. The first method analyzes water samples for radionuclide concentrations. This allows for the direct measurement of contaminants in the samples, but also includes naturally occurring radionuclides. The presence of some radionuclides may be overstated, since all radionuclides are reported even if the concentration is below the detection limit (ORNL 1998). The second method uses radionuclide concentrations in water that were calculated from measured radionuclide discharges and known or estimated stream flows. The advantage of this method is that most, if not all, radionuclides discharged from ORR are quantified, and naturally occurring radionuclides are not considered. The disadvantage is that computer models estimate the concentrations of radionuclides in fish and water.

A maximally exposed individual drinking water directly from Melton Hill Lake would have received an effective dose equivalent of about 0.096 mrem according to the analyzed water samples. The collective population dose for the estimated 37,510 persons who would drink this water would be about 1.8 person-rem. This would result in a calculated fatal cancer risk of 9E-04. The dose estimates obtained from the water samples are high, since it was assumed that the individuals drank the water directly from Melton Hill Lake. If the dose estimates are calculated using the amount of radionuclides discharged from ORR to Melton Hill Lake, the doses would be about 300 times lower (ORNL 1998).

There are several water treatment plants along the Clinch and Tennessee River systems that could be affected by discharges from the ORR. The ETTP water plant draws water from the upper Clinch River. Based on water samples taken from the Clinch River, a worker who drank 370 liters (391 quarts) of this water in 1997 would have received an effective dose equivalent of about 0.15 mrem (calculated cancer risk of 8E-08), and the collective population effective dose equivalent to the approximately 2,000 workers at ETTP would have been about 0.29 person-rem (fatal cancer risk of 1E-04). Using radionuclide discharge data, the maximally exposed individual was estimated to receive 0.025 mrem (fatal cancer risk of 1E-08), and the collective effective dose equivalent was 0.05 person-rem (fatal cancer risk of 3E-05) (ORNL 1998). The Kingston municipal water plant is located near the upper Watts Bar Lake and draws water from the Tennessee River. Dose assessments were performed assuming a maximally exposed individual drank 730 liters (771 quarts) of water during 1997 and an average person drank 370 liters (391 quarts). Based on water samples, a maximally exposed individual would receive about 0.40 mrem (calculated cancer risk of 2E-07), and the collective population effective dose equivalent to the approximately 7,438 users from the Kingston plant would be about 1.5 person-rem (ORNL 1998), which would result in a calculated cancer risk of 9E-06.

Other potential exposure pathways analyzed by the ORR for radionuclides in water include swimming or wading, boating, and use of the shoreline. A maximally exposed individual was assumed to swim or wade 27 hours/year, boat for 63 hours/year, and use the shoreline for 67 hours/year. Based on water samples collected around the ORR, a maximally exposed individual would have received a maximum effective dose equivalent of 0.015 mrem (calculated cancer risk of 8E-09) at Melton Hill Lake, and the maximum collective population dose was 0.032 person-rem, which would result in a calculated cancer risk of 2E-05.

After summing the worst-case effective dose equivalents for all water pathways in the Region of Influence, the maximum estimated effective dose equivalent would have been about 1.4 mrem in 1997, with a calculated cancer risk of 7E-07. The maximum estimated collective population effective dose equivalent would have been about 5.7 person-rem (ORNL 1998).

3.10.3.4 Direct radiation

External exposure rates from background sources in Tennessee average about 6.4 microroentgens per hour (μR/hour) and range from 2.9 to 11 μR/hour. These exposure rates are equivalent to an average annual effective dose equivalent of 56 mrem/year and range from 25 to 96 mrem/year. The total average background exposure received by an individual each year is about 300 mrem. Contributing to this background dose is direct exposure from terrestrial radiation, inhalation and ingestion of naturally occurring radionuclides, and exposure to cosmic radiation. The average exposure rate at the perimeter of the ORR during 1997 was about 5.4 μR/hour or 36 mrem/year. All of the measured exposure rates at, or near, the ORR are near background levels except for two locations. Exposure rate measurements taken along a 1.7-km (1.1-mile) length of Clinch River bank averaged 8.4 μR/hour and were about 3 μR/hour above the average exposure rate at the perimeter of ORR. The potentially maximally exposed individual is a hypothetical fisherman who was assumed to have spent 5 hours/week (250 hours/year) near the point of average exposure, which would have resulted in an effective dose equivalent of about 0.25 mrem. The calculated cancer risk from this exposure would be 1E-07. The second elevated exposure measurement is at Poplar Creek, which runs through ETTP. Exposure rate measurements taken at nine locations along Poplar Creek in 1997 ranged from 3.5 to 9.5 μR/hour. The average reading was 6.1 μR/hour or 0.0046 mrem/h. Using the hypothetical fisherman who spent 250 hours/year along the bank, the effective dose equivalent would be about 1 mrem. The calculated risk for this exposure would be 5E-07.

3.10.3.5 Five-year trends

The dose equivalents associated with various exposure pathways for the years 1993–97 are provided in Table 3-16. The dose estimates for direct radiation along the Clinch River and Poplar Creek have been corrected for background. The estimates for direct radiation along the Clinch River in 1994, 1995, and 1996 are overestimated because the source of the radiation was remediated in 1993 and 1994 (ORNL 1998).

Table 3-16. Five-year trends in the total effective dose equivalent for selected pathways

Pathway	Effective dose equivalent (mrem)				
	1993	1994	1995	1996	1997
All inhalation	1.4	1.7	0.5	0.45	0.41
Fish ingestion	0.2	1.6	0.9	1.2	0.96
Water ingestion (Kingston)	0.07	0.04	0.15	0.32	0.40
Direct radiation (Clinch River)	1	1	1	1	0.25
Direct radiation (Poplar Creek)	1	1	1	1	1

3.10.4 Chemicals

Non-radioactive emissions are regulated by the TDEC Division of Air Pollution Control. The small quantities of chemicals released by the ORR to the atmosphere are allowed under the air pollution control rules and do not pose a threat to human health.

3.10.4.1 Airborne chemicals

Operations at ORNL result in the release of small quantities of chemicals to the atmosphere and do not require stack sampling or monitoring. A steam plant and two small, oil-fired boilers are the largest emission sources and account for 98% of all allowable emissions at ORNL. Airborne contaminants released by ORNL are shown in Table 3-17 (ORNL 1998).

Table 3-17. Actual versus allowable[a] air emissions from ORNL steam production during 1997

Pollutant	Emissions (tons/year)		Percentage of allowable
	Actual	Allowable	
Particulate	2	441	0.5
Sulfur dioxide	1072	9062	11.8
Nitrogen oxides	103	531	19.4
Volatile organic compounds	1	3	33.3
Carbon monoxide	82	336	24.4

[a]Per the Clean Air Act Title V permit.
ORNL = Oak Ridge National Laboratory.

There have been a total of 14 6-minute release periods of excess emissions and 7 occasions where air monitors were out of service at the Y-12 Plant in 1997. The majority of nonradiological contaminants were from the Y-12 Steam Plant. Nonradiological emissions include sulfur oxides, nitrogen oxides, particulates, hydrochloric acid, and carbon monoxide. The ETTP operated 12 major emission sources under the Tennessee Title V Major Source Operating Permit Program Rules. The major sources of emissions were the three remaining steam-generated units in operation at the K-1501 Steam Plant and the Toxic Substances Control Act Incinerator. The major contaminants emitted included sulfur dioxide, nitrogen oxides, volatile organic compounds, and carbon monoxide (ORNL 1998).

3.10.4.2 Waterborne chemicals

Current risk assessment methodology uses the term "hazard quotient" to evaluate noncarcinogenic health effects. A hazard quotient value less than one indicates that the potential for adverse health effects is unlikely. The hazard quotient is a ratio that compares the estimated exposure dose or intake to a reference dose. The reference dose is an estimate of a daily exposure level in humans that is unlikely to result in harmful effects during a lifetime. Most of the reference doses are obtained from research involving animals. Therefore, a safety factor of 10 to 1,000 is added for use in humans (i.e., the safe doses in humans are set at 10 to 1,000 times lower than the dose that results in no effect or a non-life-threatening effect in animals) (ORNL 1998).

Fish samples were taken upstream and downstream of the ORR and analyzed for a number of metals, pesticides, and PCBs. The hazard quotients for 1997 from the fish samples are summarized in Table 3-18. In many cases, the hazard quotients, especially for pesticides and PCBs, were calculated using concentrations estimated at or below the analytical detection limit. Because of the analytical

Table 3-18. Chemical Hazard Quotients for metals in fish (ORNL 1997)

Parameters	Sunfish			Catfish		
	CRK70[a]	CRK32[b]	CRK16[c]	CRK70[a]	CRK32[b]	CRK16[c]
Hazard Quotients for Metals						
Antimony	[d]			<3E+00	<3E+00	<3E+00
Arsenic				<4E+00	<4E+00	<4E+00
Beryllium				<4E-03	<4E-03	<4E-03
Cadmium				<1E-01	<2E-01	<1E-01
Chromium	~4E-02[e]		~7E-02	<5E-02	<5E-02	<5E-02
Copper	7E-03	8E-03	5E-03			
Lead				<3E+0	<3E+0	<3E+00
Mercury	~6E-01	6E-01	2E+00			
Nickel			~8E-03	<1E-02	<1E-02	<1E-02
Selenium		<2E-01		<2E-01	<3E-01	<2E-01
Silver				<3E0-2	<3E-02	<3E-02
Zinc	4E-02	4E-02	5E-02			
Hazard Quotients for Pesticides and Aroclors						
Chlordane			1E-01			
Benzine Hexachloride			~1E+00			
Gamma BHC			~6E-01			
4,4'DDT			~2E-02			
Endosulfan I			~7E-04			
Endosulfan II			~1E-03			
Endosulfan sulfate			~3E-03			
Endrin			~3E-02			
Endrin aldehyde			~4E-01			
Heptachlor			~8E-03			
Heptachlor epoxide			~3E-01			
Methoxychlor			~8E-03			
Aroclor-1016			~7E-01			
Aroclor-1221			~4E+03			
Aroclor-1232			~4E+03			
Aroclor-1242			~4E+03			
Aroclor-1248			~4E+03			
Aroclor-1254			~3E+00			
Aroclor-1260	~2E+03	~1E+03	~2E+03			

[a]Melton Hill Reservoir, above Oak Ridge City input.
[b]Clinch River, downstream of ORNL.
[c]Clinch River, downstream of all DOE inputs.
[d]A blank space indicates the parameter was undetected.
[e]A tilde (~) indicates that estimated values and/or detection limits were used in the calculation.
Source: Adapted from ORNL 1998.

detection limitations, the actual fish tissue concentrations are unknown. Drinking water was analyzed upstream and downstream of the ORR discharge points for various metals and chemicals. Elevated aluminum and iron hazard quotients were found both upstream and downstream of the ORR. The hazard quotients for drinking water are shown in Table 3-19.

For carcinogens, the estimated dose or intake from ingestion of water or fish is divided by the chronic daily intake, which corresponds to a 1E-05 lifetime risk of developing cancer. In sunfish collected downstream of the ORR and analyzed for carcinogens, there was a cancer risk of 1E-05 due to aldrin, dieldrin, and toxaphene. Because of analytical detection limitations, the actual fish tissue concentrations are not known (ORNL 1998).

Table 3-19. Chemical Hazard Quotients for drinking water (ORNL 1997)

Chemical	Hazard Quotient		
	CRK 70[a]	CRK 23[b]	CRK 16[c]
Metals			
Aluminum	~1.3[d]	~1.4	~2.1
Antimony	[e]	~3.2	
Barium	~3E-02	~3E-02	4E-02
Boron	6E-03	7E-03	7E-03
Chromium	~5E-02	~5E-02	~5E-02
Copper	~4E-03	~7E-03	
Iron	~1E-02	~1	1.6
Lead	~3E+01	~3	
Manganese	~4E-02	3E-02	4E-02
Strontium	4E-03	4E-03	4E-03
Thallium	~2E+01		
Uranium	~4E-03	~4E-03	~4E-03
Vanadium	~1.3	~1.3	
Zinc	~3E-03	~2E-03	~2E-03
Volatile Organics			
Acetone	~2E-03	~2E-03	~2E-03
2-Butanone	~4E-04	~4E-04	~4E-04
Toluene	~6E-04		
Xylene	~6E-05		

[a]Melton Hill Reservoir, above Oak Ridge City input.
[b]Clinch River, downstream of ORNL.
[c]Clinch River, downstream of all DOE inputs.
[d]A tilde (~) indicates that estimated values and/or detection limits were used in the calculation.
[e]A blank space indicates the parameter was undetected.
Source: Adapted from ORNL 1998.

3.11 ACCIDENTS

The potential for accidents from human error, equipment failure, or natural phenomena would result in the release of radiation, radioactive materials, or hazardous materials. Based on data obtained from the ORNL Safety Information Database Module on the Injury/Illness Historical Performance Report for January 1, 1999, through December 31, 1999, the total recorded injuries at ORNL for 1999 were 170, which is a rate of 4.56 per 100 full-time employees working for one year (ORNL 1999b).

3.12 NOISE

The area around the Melton Valley Storage Tanks is industrial, with the site serving as a waste storage area. The activities in this area are sporadic and associated with traffic and occasional equipment use. A baseline noise survey was conducted for the project site area in July 1999 by Bechtel Jacobs; details of the survey are included in Appendix C.4. The Old Melton Valley Road that connects with Tennessee State Route 95 [roughly 1.6 km (1 mile) west of the proposed site] was being upgraded during the survey, so heavy construction equipment was in use. Eleven noise monitoring stations were established (Figure 3-20). The monitoring stations ranged in location from west of the proposed site and immediately adjacent to Tennessee State Route 95, to east of the proposed site adjacent to the Melton Valley Storage Tanks. The entire surveyed area is relatively quiet. Daily equivalent noise level (Leq) values were generally in the 50 to 70 dBA range. By comparison, normal human speech is approximately 60 to 65 dBA. The Leq is a metric that measures all noise within the frequency range of the instrument over a given time interval (in this case one hour), computes an average noise level, and assumes this noise level was continuous over the total interval measured. Results of the monitoring effort are presented in Appendix C.4.

The noise levels adjacent to State Route 95 (monitoring location 1) were relatively constant over a 24-hour period with daily Leqs of 61.1 and 64.7 for the 2 days data were collected (Table 3-20). Monitoring location 2, adjacent to the Old Melton Valley Road, showed substantially greater noise levels (20 dBA Leqs greater) during hours when heavy equipment associated with the road upgrade was present. For one day, monitoring location 7 also shows noise levels greatest during periods when construction workers were present. The other locations either had a relatively constant noise environment or they showed diurnal peaks when workers were not generally present. It is probable that wildlife such as frogs and crickets contributed to the late-night noise peaks at several locations (Table 3-20).

3.13 SOCIOECONOMIC AND DEMOGRAPHIC ENVIRONMENT

The Region of Influence for the proposed action includes Anderson, Knox, Loudon, and Roane Counties (Figure 3-21). Approximately 90% of ORR employees reside in this region (DOE 1998c). The region includes the cities of Clinton, Oak Ridge, Knoxville, Loudon, Lenoir City, Harriman, and Kingston. This section provides a description of the characteristics, housing, infrastructure, and the local economy.

3.13.1 Demographic Characteristics

Approximately 7,500 people live within 8 km (5 miles) of the center of the proposed project site. Excluding the residential area of Oak Ridge with a population of 27,310, the population density within 10 km (6 miles) of the proposed TRU Waste Treatment Facility generally averages less than 38 people/square kilometer (100 people/square mile). Oliver Springs lies 11 km (7 miles) northwest of the ORR and has a population of 3,400. Clinton, Tennessee, located 16 km (10 miles) to the northeast of the ORR, has a population of 9,000. Approximately 6,100 people live in Lenoir City, 11 km (7 miles) southeast of the ORR. Kingston is located 11 km (7 miles) to the southwest of the ORR and has 4,600 residents. Approximately 7,100 people reside in Harriman, Tennessee, which is 13 km (8 miles) west of the ORR. Knoxville is the largest metropolitan area within 80 km (50 miles) of the facility and has a population of 165,000 people. In all, approximately 880,000 people reside within 80 km (50 miles) of the facility (ORNL 1995).




Figure 3-20. Eleven noise monitoring stations were located on, or near the proposed TRU Waste Treatment Facility site boundary.

Table 3-20. Noise monitoring data for Melton Valley proposed TRU waste facility

[noise levels (Leq per hour) in Melton Valley, Oak Ridge, Tennessee]

Location number and sample event	1a	1b	2a	2b	2e	3a	3b	3d	4a	4b	4c	5a	5b	6e	7c	7e	8d	9d	9e	10d	10e	11d
Hour (military)																						
0	60.5	61.9	53.1	53.5	55.4	56.1	61.2	58.2	58.4	58.7	59.3	59.6	59.0	57.4	55.9	63.6	63.1	60.5	59.9	57.2	58.8	62.6
1	59.0	60.3	51.7	51.3	54.5	53.3	54.5	57.4	55.8	55.5	57.7	58.6	58.2	56.0	53.8	58.6	60.5	59.4	58.9	56.3	57.6	61.5
2	56.7	56.6	49.4	48.7	53.3	50.1	50.4	55.1	52.3	51.1	55.3	57.8	56.9	54.5	51.9	57.9	59.3	58.0	57.9	54.1	55.3	60.4
3	52.7	55.9	46.6	46.6	51.3	49.3	49.9	53.1	50.6	49.5	51.3	57.3	56.4	52.9	49.8	56.2	58.5	54.0	55.2	51.0	51.6	57.1
4	52.9	57.5	42.9	42.4	47.6	47.6	48.2	47.3	49.1	48.2	48.9	57.1	56.2	54.2	48.0	56.4	57.6	48.8	53.5	46.9	52.9	55.0
5	60.9	64.6	43.4	43.2	46.6	46.6	48.5	45.1	48.2	47.9	47.8	57.1	55.9	47.5	47.0	53.2	57.1	48.5	49.1	42.5	43.5	54.6
6	60.6	68.4	45.6	45.3	47.0	50.6	50.5	58.8	49.3	48.1	50.3	56.6	56.3	48.3	51.8	57.6	60.8	57.3	49.3	61.7	43.5	61.4
7	59.4	67.8	45.8	66.2	71.0	50.4	52.5	52.1	49.6	51.1	49.6	56.8	57.1	49.0	56.7	50.0	58.4	54.5	51.2	52.8	43.4	57.9
8	58.9	66.3	44.8	73.1	72.5	50.3	52.5	55.1	49.9	53.0	51.8	57.3	57.0	51.8	72.6	55.2	59.3	56.0	59.2	56.5	46.9	60.7
9	55.6	64.9	43.9	78.2	74.7	50.0	52.4	51.3	50.1	51.4	53.5	58.0	56.8	50.9	77.4	52.7	57.7	51.0	57.0	49.8	52.1	57.3
10	54.0	63.1	43.8	69.6	71.7	49.8	50.2	47.1	49.0	52.3	58.2	57.7	57.2	54.2	80.7	55.6	57.0	52.4	59.0	47.5	54.5	55.3
11	55.9	64.7	45.8	48.5	65.0	49.5	51.3	46.1	49.2	51.3	54.0	57.8	56.7	51.9	71.2	50.7	56.3	48.4	56.5	45.3	51.8	56.5
12	55.8	63.5	44.9	46.4	59.4	51.6	50.1	50.3	51.2	49.9	58.7	58.0	56.8	49.3	51.9	51.1	57.2	55.8	55.3	51.8	50.5	56.8
13	55.6	64.0	63.5	47.4	70.3	50.4	49.8	50.8	49.7	49.9	53.6	57.8	57.2	48.6	51.9	51.2	56.1	56.2	55.1	51.0	51.1	58.4
14	56.4	64.0	54.7	55.8	61.7	50.8	49.7	48.9	50.5	49.0	53.0	57.2	56.5	50.7	50.8	52.5	55.4	54.2	54.5	48.2	51.6	55.4
15	59.7	67.7	46.3	54.5	77.2	49.9	48.9	49.6	49.4	48.8	52.3	56.9	56.4	49.4	57.1	46.3	54.7	64.2	50.3	49.7	47.4	57.7
16	59.7	67.0	46.4	49.7		49.4	47.6	59.0	49.6	48.5	52.4	57.1	56.2	51.1	52.3		56.1	53.2		54.3	46.4	54.9
17	63.1	67.1	45.6	49.3	49.4	48.1	46.0	58.6	48.5	48.3	49.4	57.0	56.3	53.4	47.3	46.4	55.0	53.3	47.8	53.7	44.7	53.3
18	61.7	64.3	44.1	46.2	49.8	47.8	47.1	42.4	48.9	48.3	47.7	57.4	56.4	49.0	44.8	45.6	55.7	45.8	44.1	41.1	42.9	53.0
19	60.8	64.2	43.3	43.7	50.3	47.7	46.3	43.2	48.7	48.3	47.9	57.6	56.9	51.2	44.7	44.5	56.1	43.9	46.1	42.0	42.6	52.8
20	58.1	61.5	45.3	43.8	56.5	48.0	49.0	47.5	48.8	49.5	48.9	57.8	57.3	52.2	46.1	47.4	57.1	48.7	49.4	46.1	48.8	54.6
21	63.0	65.2	50.6	52.7	57.2	55.4	58.1	58.8	55.8	57.7	59.2	60.2	59.5	60.1	57.9	61.8	62.8	60.7	61.0	57.7	58.5	64.6
22	62.3	64.7	54.9	56.2	57.0	59.1	60.4	60.4	60.1	60.5	61.1	61.1	59.9	59.7	63.5	65.7	62.6	62.1	62.5	58.9	60.2	65.4
23	57.9	63.4	53.8	55.0	57.0	58.1	59.8	59.9	59.8	59.4	60.4	60.4	59.4	58.6	59.0	66.7	61.8	61.3	62.2	57.9	59.6	63.8
daily Leq	61.1	64.7	61.0	66.4	67.3	52.7	53.6	55.4	53.6	53.7	55.5	58.2	57.4	54.3	69.4	58.7	58.9	57.0	57.1	54.5	54.1	59.7
Lmax	87.6	90.0	87.8	104.4	96.8	70.0	64.8	78.8	72.1	73.2	75.9	74.4	68.0	81.5	90.5	82.7	81.6	93.0	88.8	90.1	81.7	82.5

For locations, see Figure 3-20 and text descriptions.

Sample Events: a - 7/13-14/99
b - 7/14-15/99
c - 7/15-16/99
d - 7/19-20/99
e - 7/20-21/99




Figure 3-21. Region of Influence for the Oak Ridge Reservation.

Population trends and projections for each of the counties in the four-county Region of Influence are presented in Table 3-21. Of the four counties, Knox has the largest population, with 70% of the 1996 regional population of 523,252. Anderson County accounted for 14% of the regional population, Roane County for 9%, and Loudon County accounted for the remaining 7%. The region represents approximately 10% of the state's population. The TDEC has indicated that the population in the region will likely decline to 512,399 by year 2000 and then increase slightly by year 2005. Roane County is the exception to this trend, as it is projected to grow 24%.

Table 3-21. Regional population trends and projections in the Oak Ridge Region of Influence

County	1980	1990	1996	2000	2005
Anderson	67,346	68,250	71,587	68,181	66,347
Knox	319,694	335,749	364,566	353,721	360,033
Loudon	28,553	31,255	37,240	34,149	36,458
Roane	48,425	47,277	49,859	56,348	61,984
Region Total	464,018	482,531	523,252	512,399	524,822
State	4,591,023	4,877,185	5,235,358	5,178,587	5,305,137

Sources: U.S. Bureau of Census 1990a; TEDC 1994–97.

Population data for the cities in the region are presented in Table 3-22. Between 1990 and 1996, the populations of the four-county region and the state both grew less than 1% per year.

Table 3-22. Population for incorporated areas within the ORR region

Communities	1990	1996	Percent growth
Clinton	8,972	9,320	3.9
Oak Ridge	27,310	27,742	1.6
Knoxville	169,761	167,535	-1.3
Loudon	4,288	4,544	6.0
Lenoir	6,147	8,890	44.6
Harriman	7,119	7,006	-1.6
Kingston	4,552	4,935	8.4

ORR - Oak Ridge Reservation.
Source: U.S. Bureau of Census 1990a; DOE 1999a.

Population by race and ethnicity for the region is presented in Table 3-23. The 1990 census data reflect racial and ethnic compositions in the four counties. There is little variation among the four counties, and Caucasians make up more than 90% of the combined population. African-Americans compose 7% of the population.

Table 3-23. 1990 Population by race and ethnicity for the ORR region

All persons, race/ ethnicity	Anderson		Knox		Loudon		Roane		Total	
	Number	%[a]	Number	%[a]	Number	%[a]	Number	%[a]	Number	%[a]
All Persons	68,250	100	335,749	100	31,255	100	47,277	100	482,531	100
Caucasian	64,745	95	301,788	90	30,762	98	45,422	96	442,717	92
African-American	2,681	4	29,299	9	362	1	1,534	3	33,876	7
American Indian[b]	195	<1	996	<1	46	<1	87	<1	1,324	<1
Asian/ Pacific Islander	540	<1	3,136	<1	55	<1	177	<1	3,908	1
Hispanic of any race[c]	582	1	1,935	1	107	<1	273	1	2,897	1
Other races	89	<1	530	<1	30	<1	57	<1	706	<1

[a]Percentages may not total to 100 due to rounding.
[b]Numbers for Aleuts and Eskimos were placed in the "other" category, given their small number.
[c]In the 1990 Census, Hispanics classified themselves as White, Black, Asian/Pacific Islander, American Indian, Eskimo, or Aleut To avoid double counting, the number of Hispanics was subtracted from each of the race categories.
ORR - Oak Ridge Reservation.
Source: U.S. Bureau of Census 1990a.

3.13.2 Housing

Regional housing characteristics are presented in Table 3-24. In 1990, vacancy rates in the region ranged between a low of 6% in Loudon County to a high of 9% in Roane County. Among all occupied housing units in the region, approximately two-thirds were owner occupied.

Housing vacancy rates for selected regional cities and towns are similar to county rates. In 1990, the county vacancy rate for all units was 7%, while the combined vacancy rate for the seven selected communities (refer to Table 3-24) was 8%. Median home value was similar in Roane, Loudon, and Anderson Counties, ranging between $48,700 to $55,100. Knox County median home values were higher at $63,900. Rents ranged from $280 to $351 across the Region of Influence.

Table 3-24. Housing summary for the ORR region, 1990, by county

	Anderson County		Knox County		Loudon County		Roane County	
	Number	%[a]	Number	%[a]	Number	%[a]	Number	%[a]
Total housing units	29,323	100	143,582	100	12,995	100	20,334	100
Occupied	27,384	93	133,639	93	12,155	93	18,453	91
Vacant	1,939	7	9,943	7	840	6	1,881	9
Median home Value	$55,100	NA	$63,900	NA	$51,000	NA	$48,700	NA
Gross rent	$342	NA	$351	NA	$280	NA	$287	NA

ORR = Oak Ridge Reservation
NA = Not applicable.
[a]May not total 100 due to rounding.
Sources: U.S. Bureau of Census 1990a; U.S. Bureau of Census 1996.

3.13.3 Infrastructure

The infrastructure section characterizes the region's community services with indicators such as education, health care, and public safety.

3.13.3.1 Education

There are eight school districts within the four-county Region of Influence. Information regarding these districts is presented in Table 3-25. The school districts in the region receive funding from local, state, and federal sources, but the percentage received from each source varies. Local funding varies from a low of 31% in Loudon County to a high of 52% in Knox County. State funding varies between 43% in Knox County and 63% in Loudon County, and federal funding ranges between a low of 5% in Knox County and a high of 12% in Anderson County.

Table 3-25. Public school statistics in the ORR region, 1996–97 school year

County	Number of schools	Student enrollment[a]	Teachers[a]	Teacher/student ratio	Per-student operational expenditures
Anderson	27	13,867	840	1:16	$5,206
Knox	84	57,693	3153	1:18	$4,191
Loudon	13	6,900	335	1:21	$3,870
Roane	19	8,356	455	1:18	$4,343

ORR= Oak Ridge Reservation.
[a]Full-time equivalent figures.
Source: Tennessee Department of Education 1997.

3.13.3.2 Health care

There are eight hospitals currently serving the region. Table 3-26 presents data on hospital capacity and usage. Average statistics for the hospitals indicate that there are approximately 2,400 acute-care hospital beds in the region, about 46% of which are available on any given day. This capacity is considered adequate to serve the health needs of the local population.

Table 3-26. Hospital capacity and usage in the ORR region

Hospital	Number of hospitals	Number of beds[a]	Annual bed-days used[b] (%)
Anderson	1	281	63
Knox	5	1923	53
Loudon	1	62	23
Roane	1	94	50

ORR = Oak Ridge Reservation.
[a]The number of acute-care beds.
[b]Based on the number of people discharged and the average length of stay divided by total beds available annually.
Source: The American Hospital Directory, Inc. 1999.

3.13.3.3 Police and fire protection

The Knoxville Police Department has 400 officers with an approved Fiscal Year 1998 budget of $26.4 million. In addition, the Oak Ridge Police Department has 45 officers with an approved Fiscal Year 1996 budget of $2.3 million. The Knoxville County Fire Department has 13 fire stations, staffed by 118 Fire Department personnel. The Oak Ridge Fire Department provides fire suppression, medical/rescue, and fire prevention services to both ORNL and the Oak Ridge community (DOE 1999a).

3.13.4 Local Economy

This subsection provides information on the economy of the region, including employment, income, and fiscal characteristics.

3.13.4.1 Employment

Regional employment data for 1991–96 are summarized in Table 3-27. The 1998 average unemployment rate for the Region of Influence was 3.4%, ranging from 3.1% in Knox County to 5.0% in Roane County (Tennessee Department of Employment Security 1999).

Table 3-27. Region of Influence employment data, 1991–96

	Number employed		
County	1991	1996	Percent change
Anderson	37,395	41,001	9.64
Knox	185,704	210,506	13.36
Loudon	9,538	11,142	16.82
Roane	21,305	23,646	10.99
Region	253,942	28,6295	12.74

Source: Bureau of Economic Analysis 1999.

DOE-related facilities and contractor employment declined from 18,165 workers in 1995 to 14,534 in 1997, of which 13,154 lived in the four-county impact region (DOE 1996b, 1998b;

Bridgeman 1997; Neal 1998). Table 3-28 shows the distribution of ORR-related employment across the relevant counties in 1996. The distribution in 1997 was similar, although the later figures included Oak Ridge residents in both Anderson and Roane County totals. Knox County held the largest share of the region's ORR-related employment (45%), followed by Anderson County with 32%, and Roane County with 16%. Loudon County accounted for the remaining 6%.

Table 3-28. Distribution of DOE-related employment in Region of Influence, 1996

County	1996	
	Number employed	Percent
Anderson	4,956	32
Knox	6,939	45
Loudon	962	6
Roane	2,493	16
Region of Influence Total	15,350	100

DOE = U.S. Department of Energy.
Source: Bridgeman 1997.

Table 3-29 presents employment by industry for the Region of Influence with government, manufacturing, retail trade, and services being the principal economic sectors. Services employment is the largest employment sector in the region, although manufacturing is nearly as large in Loudon County.

Table 3-29. Employment distribution by industry for the four-county Region of Influence

Industry	Anderson County	Knox County	Loudon County	Roane County	Region of Influence	State of Tennessee
	Number employed by industry (1996)					
Farm	582	1,453	1,214	606	3,855	93,383
Agriculture Services	319	2,202	229	105	2,855	28,435
Mining	123	587	18	32	760	7,125
Construction	4,258	15,829	1068	981	22,136	187,246
Manufacturing	11,114	24,875	3,040	6,539	45,568	534,099
Transportation and Public Utility	1,838	12,244	811	633	15,526	165,715
Wholesale Trade	647	16,088	290	448	17,473	151,914
Retail Trade	(D)	46,614	2,180	(D)	48,794	545,934
Finance, Insurance, and Real Estate	2,177	17,554	894	713	21,338	212,589
Services	(D)	76,010	3,412	(D)	79,422	879,043
Government	5,421	37,474	1,733	4,067	48,695	405,205

(D) = Data withheld to avoid disclosure when there are less than four businesses in an industry classification.
Source: Bureau of Economic Analysis 1996.

3.13.4.2 Income

The total regional income in 1996 was approximately $12.0 billion. DOE-related payroll accounted for about 6% of that income ($725 million). In 1997, DOE-related payroll in the region declined to $680 million (DOE 1998c), reflecting a downward trend in DOE activities that is expected to continue. Per capita income data for the region and the state are presented in Table 3-30. Over the period from 1991 to 1996, the per capita incomes in the four-county Region of Influence grew between 23 and 26%. This growth rate was slightly below the statewide increase in income of 28%.

Table 3-30. Per capita income data for the four-county Region of Influence and the State of Tennessee

Area	Per Capita Income		Percent Increase
	1991 ($)	1996 ($)	
Anderson County	18,040	22,292	24
Knox County	18,970	23,952	26
Loudon County	15,697	19,341	23
Roane County	15,551	19,601	26
State of Tennessee	16,976	21,808	28

ORR = Oak Ridge Reservation.
Source: Bureau of Economic Analysis 1999.

Table 3-31 shows the percentage of persons whose incomes were below the poverty level in 1990 for the four-county Region of Influence. The percentage ranged from 13.4% in Loudon County to 15.8% in Roane County, compared to a state average of 15.7%.

Table 3-31. Percent of individuals with incomes below poverty line in the four-county Region of Influence and the State of Tennessee, 1990

Area	Percent
Anderson County	14.2
Knox County	13.6
Loudon County	13.4
Roane County	15.8
State of Tennessee	15.7

ORR = Oak Ridge Reservation.
Source: Bureau of the Census 1995.

3.13.4.3 Fiscal characteristics

Municipal and county general fund revenues in the Region of Influence are presented in Table 3-32. The general fund supports the ongoing operations of local governments, as well as community services, such as police protection and parks and recreation. The State of Tennessee does not have state or local personal income tax. Under Tennessee constitutional law, property taxes are assessed as follows:

- Residential property equals 25% of the appraised value.
- Commercial/industrial property equals 40% of the appraised value.
- Personal property equals 30% of the appraised value.

The largest revenue sources for the counties' general fund have traditionally been local taxes (which include taxes on property, real estate, hotel/motel receipts, and sales) and intergovernmental transfers from the federal or state government. Over 80% of the 1999 general fund revenue came from these combined sources (DOE 1999a).

Table 3-32. Municipal and county general fund revenues in the ORR region. Fiscal Year 1997

	Anderson County		Knox County		Loudon County		Roane County	
Revenue by source	($1,000)	%	($1,000)	%	($1,000)	%	($1,000)	%
Local taxes[a]	12,732	40	232,145	56	4,147	68	22,970	45
Licenses and permits	34	<1	1,633	<1	178	3	102	<1
Fines and forfeitures	56	<1	3,086	1	157	3	302	1
Charges for service	2,640	8	21,811	5	43	1	1,167	2
Intergovernmental[b]	14,483	45	145,582	35	638	11	22,826	45
Interest	1,285	4	10,982	3	—[c]	NA	1,183	2
Miscellaneous income	680	2	483	<1	911	14	2,474	5
Total	31,910	100	415,722	100	6,074	100	51,024	100

ORR = Oak Ridge Reservation
[a]Local taxes include real and personal property taxes, hotel/motel taxes, and local sales taxes.
[b]Intergovernmental includes state transfers and federal funds.
[c]Interest revenue not identified separately for Loudon County.
NA = not available.
Source: DOE 1999a.

3.14 ENVIRONMENTAL JUSTICE

Figure 3-22 illustrates the distribution of minority populations in the census tracts that immediately surround the ORR. A minority population consists of any census tract with a minority population proportion greater than the national average of 24.1% (Bureau of the Census 1990a). Minorities include individuals classified as Black not of Hispanic origin, Hispanic, Asian or Pacific Islander, and American Indian or Alaskan Native (CEQ 1997).

In 1990, African-Americans comprised 34.4% of the population in tract 201, and other minorities comprised 6.9% (Bureau of the Census 1990a). For all other Oak Ridge City tracts, minorities comprised 10% or less of the population. For comparison, minorities represented 24.1% of the population nationally and 17% of the population in Tennessee.

There are no federally recognized Native American groups within 80 km (50 miles) of the proposed site. DOE has consulted with Native American groups regarding the status of the ORR as a site of potential importance to Native Americans. While some isolated findings of arrowheads, pottery shards, and charcoal have been found in some project studies over the years, no tribe or group representing Native Americans has ever expressed interest in the ORR as a site of historical importance to Native Americans (Moore 1999). There are no known sensitive areas near the proposed project site. The closest Native American tribe is the Eastern Band of the Cherokee Indians in Cherokee, North Carolina, approximately 110 km (100 miles) southeast of the proposed site.

Figure 3-23 shows the location of low-income populations for the same area. In this analysis, a low-income population includes any census tract in which the percentage of persons with income below the poverty level is greater than the national average of 13.1%. The Tennessee state average is 15.7% (Bureau of the Census 1990b). The highest percentages are in tract 201 (22.9%) and tract 205 (20.4%). The lowest percentages are in tracts 206 (0.3%), 5802 (1.5%), and 301 (1.9%) (Bureau of the Census 1995).




Figure 3-22. Census tracts with a minority population greater than the national average of 24.1%.




Figure 3-23. Census tracts with a low-income population greater than the national average of 13.1%.

3.15 REFERENCES

Bechtel Jacobs (Bechtel Jacobs Company LLC) 1999. Database search of *AVS Report on Oak Ridge Reservation TRU Waste Streams* by Doug Nordstrom, Bechtel Jacobs Company LLC, Oak Ridge, Tennessee, May 4, 1999.

Blasing, T. J., R. A. Brown, G. F. Cada, C. Easterly, D. L. Feldman, C. W. Hagan, R. M. Harrington, R. O. Johnson, R. H. Ketelle, R. L. Kroodsma, L. N. McCold, W. J. Reich, P. A. Socolof, R. P. Taleyarkhan, and J. W. Van Dyke 1992. *Phase I Environmental Report for the Advanced Neutron Source at Oak Ridge National Laboratory*, ORNL/TM-12069, Martin Marietta Energy Systems, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

BOCA (Building Officials and Administrators International) 1990. *The BOCA National Building Code, 1990, 11th Ed.*, Country Club Hills, Illinois.

Bridgeman, R. 1997. "Area DOE Payroll Decreased in 1996," in *The Oak Ridger Online*, March 4, 1997, Website address: http://www.oakridger.com/stories/030497/doe.hml.

Bureau of Economic Analysis 1996. Regional Economic Information System, Website address: http://www.bea.doc.gov. Also available at http://govinfo.library.orst.edu.

Bureau of Economic Analysis 1999. Regional Accounts Data, Tables CA1-3, CA34, SA07, and SA27, Website address: http://www.bea.doc.gov.

Bureau of the Census 1990a. Website address: http://www.venus.census.gov. Also available at http://www.bea.doc.gov.

Bureau of the Census 1990b. "Census Historical Poverty Tables," Table CPH-L-162, available at http://www.census.gov/hhes/poverty/census/cphl162.html.

Bureau of the Census 1995. *TIGER/Line Data*, available from http://www.esri.com.

Bureau of the Census 1996. *USA Counties*, CD-ROM, available from http://govinfo.library.orst.edu.

Campbell, A. W., G. F. Cada, R. H. Ketelle, R. L. Kroodsma, R. R. Lee, and L. R. Pounds 1989. *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant*, ORNL/TM-10965, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

CEQ (Council on Environmental Quality) 1997. *Environmental Justice Under the National Environmental Policy Act*, CEQ, Office of the President, Washington, D.C., December 10, 1997.

CMI-FWIE (Conservation Management Institute–Fish and Wildlife Information Exchange) 1996. *(Draft)—Taxonomy, species mussel, pearly, mucket, pink.* Website address: http://fwie.fw.vt.edu/WWW/esis/e-404009.htm. Date 13 MAR 96. Conservation Management Institute, College of Natural Resources, Virginia Tech, Blacksburg, Virginia.

DOE (U.S. Department of Energy) 1979. *Preliminary Safety Analysis Report, Oak Ridge National Laboratory, New Hydrofracture Facility*, Oak Ridge, Tennessee, May 1979.

DOE 1995. *Remedial Investigation Report on Waste Area Grouping 5 at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1326&D2.

DOE 1996a. *Remedial Site Evaluation Report for the Waste Area Grouping 10 Wells Associated with the New Hydrofracture Facility at Oak Ridge National Laboratory, Oak Ridge, Tennessee: Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1471/V1&D1.

DOE 1996b. "Department of Energy/Contractor Payrolls Total Over $800 Million for 1995," press release dated March 8, 1996, Website address: http://www.e.doe.gov/pressrel/press6.htm.

DOE 1997a. *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee: Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1546/V1&D2.

DOE 1997b. *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement*, DOE/EIS-0026-S-2, U.S. Department of Energy, Washington, D.C., September 1997.

DOE 1997c. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1997d. *CAP-88, Version 2.0, Users Guide*, Germantown, Maryland, June 1997.

DOE 1998a. *Safety Analysis Report for the Gunite and Associated Tanks Project Remediation of the South Tank Farm, Facility 3507, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/ER-403, February 1998.

DOE 1998b. *Accelerating Cleanup—Paths to Closure*, DOE/EM-0362, U.S. Department of Energy, Office of Environmental Management, Washington, D.C., June 1998.

DOE 1998c. "DOE Payrolls Over $680 Million for 1997," press release dated March 5, 1998, Website address: http://www.oakridge.doe.gov/media_releases/r-98-010.htm.

DOE 1999a. *Final Environmental Impact Statement for the Construction and Operation of the Spallation Neutron Source*, DOE/EIS-0247, U.S. Department of Energy, Office of Science, Washington, D.C., April 1999.

DOE 1999b. *Final Environmental Assessment for the U.S. Department of Energy, Oak Ridge Operations Receipt and Storage of Uranium Materials from the Fernald Environmental Project Management Site*, DOE/EA-1299, U.S. Department of Energy, Washington, D.C., April 1999.

DOE 1999c. *Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement II Fact Sheet*; U.S. Department of Energy, Oak Ridge Operations handout at public scoping meetings held on February 11 and 16, 1999, in Oak Ridge, Tennessee

DOE-ORO (U.S. Department of Energy, Oak Ridge Operations Office) 1996. *Environmental Assessment–Lease of Parcel ED-1 of the Oak Ridge Reservation by the East Tennessee Economic Council*, DOE/EA-1113, U.S. Department of Energy, Oak Ridge, Tennessee, April 1996.

Dreier, R. B., D. K. Solomon, and C. M. Beaudoin 1987. "Fracture Characterization on the Unsaturateed Zones of a Shallow Land Burial Facility," in *Flow and Transport through Fractured Rock*, American Geophysical Union Monograph 42.

DuVall, G. D. 1992a. *An Archaeological Reconnaissance of the Remote-Handled Transuranic Waste Storage Bunker (RH-TRU WSB) and Melton Valley Storage Tank–Capacity Increase Project (MVST-CIP), Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D. 1992b. *An Archaeological Reconnaissance of the Remote-Handled Transuranic Waste Storage Area Within the ORNL Complex, Oak Ridge Reservation, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D. 1993a. *An Archaeological Reconnaissance of the Proposed Hydrofracture Facility Pipeline, Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D. 1993b. *An Archeological Reconnaissance and Evaluation of the Oak Ridge National Laboratory, Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D., and P. A. Souza 1996. *An Evaluation of Previously Recorded and Inventoried Archeological Sites on the Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, ORNL/M-4946, prepared for Lockheed Martin Energy Systems, Inc., Oak Ridge, Tennessee.

EDGE (Engineering, Design & Geosciences Group, Inc.) 1989. *Proposed Waste Handling and Packaging Plant, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, EDGE File No. 88-X832, prepared for Lockheed Martin Energy System, Inc., Oak Ridge, Tennessee.

EPA (U.S. Environmental Protection Agency) 2000. Pink mucket pearly mussel (*Lampsilis orbiculata*). U.S. Environmental Protection Agency, Office of Pesticide Programs, Sevier County, Arkansas. Web site (http://.www.epa.gov/espp/arkansas/seviert.htm)

Faulkner, C. H. 1988. "Archaeological Investigations of the Jenkins House Site (40RE188) and the Jones House Site (40RE189), Copper Ridge, Oak Ridge Reservation, Roane County, Tennessee," in *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant, Oak Ridge National Laboratory, Oak Ridge, Tennessee.*

Hatcher, R. D., P. J. Lemiszki, R. B. Dreier, R. H. Ketelle, R. R. Lee, D. A. Leitzke, W. M. McMaster, J. L. Foreman, and S. Y. Lee 1992. *Status Report on the Geology of the Oak Ridge Reservation*, ORNL/TM-12074, Martin Marietta Energy Systems, Inc., Oak Ridge National Laboratory, Oak Ridge, Tennessee.

ICRP (International Commission on Radiological Protection) 1991. *Recommendations of the International Commission on Radiological Protection*, ICRP Publication 60, Pergammon Press, New York.

Jacobs and Rosensteel (Jacobs Environmental Management Team and Barbara A. Rosensteel) 1999. *Findings of Wetland Delineation on the Proposed Transuranic Waste Facility Site in Melton Valley, Oak Ridge Reservation, Oak Ridge Tennessee*. August 25, 1999, 9 pp. plus appendix.

Johnston, A. C., Reinbold, D. J., and Brewer, S. I. 1985. "Seismotectonics of the Southern Appalachians," *Bulletin of the Seismological Society of America*, **75**:291–312.

Ketelle, R. H., and R. R. Lee 1992. *Migration of a Groundwater Contaminant Plume by Stratabound Flow in Waste Area Grouping 1 and Oak Ridge National Laboratory, Oak Ridge Tennessee.* ORNL/ER-126.

Lee, R. R., and R. H. Ketelle 1987. *Stratigraphic Influence on Deep Groundwater Flow in the Knox Group Copper Ridge Dolomite on the West Chestnut Ridge Site*, ORNL/TM-10479.

Lee, R.R., R. H. Ketelle, J. M. Bownds, and T. A. Rizk 1992. "Aquifer Analysis and Modeling in a Fractured, Heterogeneous Medium," *Ground Water* **30**(4), July-August.

LMER and LMES (Lockheed Martin Energy Research Corp. and Lockheed Martin Energy Systems, Inc.) 1998. *Comprehensive Integrated Planning: A Process for the Oak Ridge Reservation, Oak Ridge, Tennessee*, ES/EN/SFP-49, Oak Ridge, Tennessee, January 1998.

LMES (Lockheed Martin Energy Systems, Inc.) 1995a. *The Common Ground Process–A Report to the U.S. Department of Energy on Recommended Future Uses of the Oak Ridge Reservation*, ES/EN/SFP-43, Oak Ridge, Tennessee, December 1995.

LMES 1995b. *Transportation Work Instructions for Shipment of Solid Low-Level Waste to The Nevada Test Site*, Lockheed Martin Energy Systems Waste Management Organization, Oak Ridge, Tennessee, March 1995.

LMES 1996. *Environmental Restoration Program Management Action Process Document on the U.S. Department of Energy Oak Ridge Reservation*, DOE/OR/01-1431&D1, prepared for the U.S. Department of Energy–Office of Environmental Management, Oak Ridge, Tennessee, April 1996.

McWilliams, T. 1999. Personal communication between Tom McWilliams, ES&H and QA Manager for the DOE Oak Ridge Water Treatment Facility, and Wayne Tolbert, Science Applications International Corporation, on October 8, 1999.

Mitchell, J. M., E. R. Vail, J. W. Webb, J. W. Evans, A. L. King, and P. A. Hamlett 1996. *Survey of Protected Vertebrates on the Oak Ridge Reservation*, ES/ER/TM-188/R1, Oak Ridge, Tennessee.

MMES (Martin Marietta Energy Systems, Inc.) 1989. *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/TM-10965, Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

MMES 1994. *Draft Oak Ridge Reservation Technical Site Information*, ES/EN/SFP-23, Martin Marietta Energy Systems–Site and Facilities Planning Department, Oak Ridge, Tennessee, August 1994.

Moore, R. 1999. Personal communication between Ray Moore, Department of Energy-Oak Ridge Operations Natural Resources Specialist, and Wayne Tolbert, Science Applications International Corporation, on September 6, 1999.

National Oceanic and Atmospheric Administration (NOAA) 1997. *Oak Ridge Meteorological Data*, Website address: http://www.atdd.noaa.gov/ormet/ormet_frame.html.

NRC (Nuclear Regulatory Commission) 1997. *Calculation of Annual Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Evaluating Compliance with 10 CFR 50, Regulatory Guide 1.109*, Appendix I, Revision 1, NRC Office of Standards Development. Nuclear Regulatory Commission, Washington, D.C.

Neal, M. N. 1998. "DOE had 2,500 fewer jobs in '97," *The Oak Ridger Online*, March 6, 1998, Website address: http://www.oakridger.com/stories/030698/new_doe.html.

ORNL (Oak Ridge National Laboratory) 1995. *Programmatic Environmental Impact Statement Installation Descriptions*, ORNL-6841, Oak Ridge, Tennessee, April 1995.

ORNL 1998. *Oak Ridge Reservation Annual Site Environmental Report for 1997*, ES/ESH-78, Oak Ridge, Tennessee, October 1998.

ORNL 1999a. *Oak Ridge Reservation Annual Site Environmental Report for 1998*, DOE/ORO/2091, December 1999.

ORNL 1999b. Injury/Illness Historical Performance Report, Oak Ridge National Laboratory Safety Information Database Module, Oak Ridge, Tennessee, January 1, 1999, through December 31, 1999.

Pounds, L. R., P. D. Parr, and M. G. Ryon 1993. *Resource Management Plan for the Oak Ridge Reservation, Volume 30: Oak Ridge National Environmental Research Park Natural Areas and Reference Areas–Oak Ridge Reservation Environmentally Sensitive Sites Containing Special Plants, Animals, and Communities*, ORNL/NERP-8, Oak Ridge National Laboratory, Oak Ridge, Tennessee, August 1993.

Powell, C. A., Bollinger, G. A., Chapman, M. C., Johnson, A. C., and Wheeler, R. L., 1994. "A Seismotectonic Model for the 300-kilometer-long Eastern Tennessee Seismic Zone," *Science*, **264**: 686–688.

Saylor, R. E., D. G. Jernigan, B. D. Lasley, M. A. Mitckes, L. K. Mann, S. M. Schexnayder, M. Schweitzer, W. P. Staub, V. R. Tolbert, J. W. Van Dyke, J. P. Witherspoon, and A. K. Wolfe 1990. *Data Package for the Atomic Vapor Laser Isotope Separation (AVLIS) Plant Environmental Impact Statement*, ORNL/TM-11482, Oak Ridge National Laboratory, Oak Ridge, Tennessee, February 1990.

Scott, C. 1999. Personal communication between Chris Scott, Operations Manager for Liquid Low-Level Waste Systems at Oak Ridge National Laboratory, Waste Management Inc., and Keith Jefferies, Science Applications International Corporation, September 29, 1999.

Solomon, D. K., G. K. Moore, L. E. Toran, R. B. Dreier, and W. M. McMaster 1992. *Status Report: A Hydrological Framework for the Oak Ridge Reservation*, ORNL/TM-12026, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

TEDC (Tennessee Economic Development Center) 1994–1997. *Tennessee County Profiles*, Website address: http://www.tnedc.org/counties.

Tennessee Department of Education 1997. *Annual Statistical Report, 1996/97*, Website address: http://www.state.tn.us/empsec/publications.htm.

Tennessee Department of Employment Security 1999. *Annual Averages—Labor Force and Nonagricultural Estimates*, Website address: http://www.state.tn.us/empsec/publications.htm.

The American Hospital Directory, Inc. 1999. *American Hospital Directory*, Website address: http://www.ahd.com.

USGS (United States Geologic Survey) 1999. National Earthquake Information Center, World Data Center for Seismology Website (http://www.neic.cr.usgs.gov).

THIS PAGE INTENTIONALLY LEFT BLANK

4. ENVIRONMENTAL CONSEQUENCES

Chapter 4 presents the environmental impacts and consequences associated with implementing each alternative for the proposed action. The proposed action is the construction of a facility to treat legacy TRU waste stored at ORNL, followed by disposal at the Waste Isolation Pilot Plant, a facility designated in the Record of Decision for the *Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (WM SEIS-II). Disposal of low-level waste is consistent with the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000). The Low-Temperature Drying Alternative, which involves waste stabilization and volume reduction through treatment by a low-temperature drying process for tank sludge and supernate, and sorting and compaction for the solid waste, is the preferred alternative.

The Low-Temperature Drying Alternative is the preferred alternative based on both the results of the procurement process for treatment of TRU waste and the impacts analysis presented in this EIS. DOE selected the low-temperature drying proposal during the procurement process as the preferred technology based on a combination of environmental and cost considerations. The analysis in this Chapter indicates that the Low-Temperature Drying Alternative would have lower waste volumes, less utility usage, fewer transportation shipments, and lower associated transportation risks than the other action alternatives. Emissions from this alternative would be minor during treatment operations. Waste treatment would result in a reduction in risk in Melton Valley at ORNL due to the treatment of the TRU wastes stored in the SWSA 5 North trenches, which currently release contaminants into the environment, and the threat of accidental release of liquid wastes from the Melton Valley Storage Tanks.

The methods used to determine the impacts and consequences are discussed at the beginning of each resource area. The assumptions and factors used in the analysis and prediction of the impacts are discussed for each resource area and in the appendices. The impacts or consequences for the No Action Alternative and each action alternative are then described. In addition, a comparison of the impacts of the alternatives is presented for each resource area. A summary of the environmental impacts for all of the alternatives is found at the end of Chapter 2.

DOE assumed, for purposes of analysis, 100 years of institutional control, after which there would be a loss of institutional control. Because waste would be treated under the Treatment and Waste Storage at ORNL Alternative, impacts after loss of institutional control would be bounded by the impacts after loss of institutional control under the No Action Alternative.

4.1 LAND USE IMPACTS

This section discusses the impacts of the alternatives on land use and land use classification, and aesthetic and scenic resources in the nearby areas.

4.1.1 Methodology

Methods used to determine the environmental impacts for each of the alternatives on land use are listed below.

- Compared the facility footprint including any shielding requirement (in hectares and acreage) for each alternative.
- Determined if a change to the existing land use classification is required due to the implementation of an alternative.
- Identified changes to the scenic and aesthetic resources of the area.

4.1.2 No Action Alternative

The No Action Alternative would result in no change to the existing land or land use classification during the assumed 100-year institutional control period. The Melton Valley Storage Tanks would continue to store liquid and sludge waste, and the existing solid waste storage facilities would continue to store contact-handled and remote-handled TRU solids. Retrievable TRU and alpha low-level wastes would continue to be stored in the trenches in SWSA 5 North. Scenic and aesthetic resources in the area would remain unchanged.

For purposes of analysis, DOE has also evaluated potential impacts after loss of institutional control. After loss of institutional control, containment for the Melton Valley Storage Tanks, the storage bunkers and trenches, and metal buildings at SWSA 5 North is assumed to fail, releasing radiological and chemical contaminants into the environment. Such releases would permanently commit land near both the Melton Valley Storage Tanks and SWSA 5 North areas to waste storage.

4.1.3 Low-Temperature Drying Alternative

The Low-Temperature Drying Alternative would result in land use impacts, compared to no land use impacts for the No Action Alternative. About 2 ha (5 acres) of land west and adjacent to the Melton Valley Storage Tanks would be altered from forest to direct industrial use due to the construction of the proposed waste treatment facility. The site would be revegetated after D&D of the facility.

The proposed facility site has been designated for industrial land use. The construction, operation, and D&D of the facility would require no change to the overall land use classification for the area.

The proposed site is isolated from the main plant area at ORNL and is not visible to the general public; however, 2 ha (5 acres) of forest would be cleared, impacting the scenic resources in the immediate area. The construction, operation, and D&D activities would be visible to workers at the site and to personnel traveling the Old Melton Valley Road (High Flux Isotope Reactor access road), which would become the main road to the proposed treatment facility.

4.1.4 Vitrification Alternative

The Vitrification Alternative would result in land use impacts, compared to no land use impacts for the No Action Alternative. Approximately 2.8 ha (7 acres) of land west and adjacent to the Melton Valley Storage Tanks would be altered from forest to direct industrial use due to the construction of a vitrification waste treatment facility. The site would be revegetated after D&D of the facility. The proposed facility site has been designated for industrial land use. The construction, operation, and D&D of the facility would require no change to the overall land use classification for the area.

The proposed site is isolated from the main plant area at ORNL and is not visible to the general public; however, about 2.8 ha (7 acres) of forest would be cleared, impacting the scenic resources in the immediate area. The construction, operation, and D&D activities would be visible to workers at the site and to personnel traveling the Old Melton Valley Road, which would become the main road to the proposed treatment facility.

4.1.5 Cementation Alternative

The Cementation Alternative would result in land use impacts, compared to no land use impacts for the No Action Alternative. About 2 ha (5 acres) of land west and adjacent to the Melton Valley Storage Tanks would be altered from forest to direct industrial use due to the construction of a cementation waste treatment facility. The site would be revegetated after D&D of the facility.

The proposed facility site has been designated for industrial land use. The construction, operation, and D&D of the facility would require no change to the overall land use classification for the area.

The proposed site is isolated from the main plant area at ORNL and is not visible to the general public; however, 2 ha (5 acres) of forested land would be cleared, impacting the scenic resources in the immediate area. The cementation waste treatment facility would be visible to workers at the site and to personnel traveling the Old Melton Valley Road during construction, operation, and D&D activities.

4.1.6 Treatment and Waste Storage at ORNL Alternative

This alternative would result in land use impacts, as compared to no land use impacts for the No Action Alternative. About 2 to 2.8 ha (5 to 7 acres) of land west and adjacent to the Melton Valley Storage Tanks would be altered from forest to direct industrial use for the construction of a waste treatment facility (either low-temperature drying, vitrification, or cementation treatment facility). In addition, waste storage facilities would be required to store the treated wastes, further impacting the land. Based on the assumption that the existing solid waste storage facilities (Buildings 7572, 7574, 7842, 7878, and 7879 for contact-handled waste, and Buildings 7855 and 7883 for remote-handled waste) could be used for storage of the treated wastes, an additional 0.3 to 0.8 ha (0.75 to 2 acres) of land would still be required for the construction of additional waste storage facilities, depending on the treatment method selected. The land required for storage of treated waste onsite by the treatment alternatives would be: 0.3 ha (0.75 acres) for treatment by low-temperature drying, 0.6 ha (1.5 acres) for treatment by vitrification, and 0.8 ha (2 acres) for treatment by cementation.

The proposed facility site and storage areas have been designated for industrial land use. The construction, operation, and D&D of the treatment facility, and the construction of waste storage facilities, would require no change to the overall land use classification for the area.

The proposed site is isolated from ORNL's main plant area and not visible to the general public; however, 2 to 2.8 ha (5 to 7 acres) of forested land would be cleared for the waste treatment facility,

and an additional 0.3 to 0.8 ha (0.75 to 2 acres) of land would be required for the construction of waste storage facilities, thus impacting the scenic resources in the immediate area. The waste treatment facility would be visible to workers at the site and to personnel traveling the Old Melton Valley Road during construction, operation, and D&D activities. The waste storage facilities would continue to be visible to workers in the area for an indefinite period of time.

4.1.7 Land Use Impacts Summary

There would be no change in land use with the implementation of the No Action Alternative. By comparison, approximately 2 to 2.8 ha (5 to 7 acres) of currently forested land would be developed for a waste treatment facility if any of the alternatives that include waste treatment are implemented. An additional 0.3 to 0.8 ha (0.75 to 2 acres) of land would be required for the construction of waste storage facilities if the Treatment and Waste Storage at ORNL Alternative is implemented.

There would be no change in the current land use classification resulting from the implementation of any of the alternatives; the land, currently classified as industrial, would remain industrial.

The No Action Alternative would result in no change to the existing scenic resources. If a treatment alternative is chosen, the scenic resources of the area would be impacted by the clearing of the currently forested land.

4.2 CULTURAL AND HISTORIC RESOURCES

This section discusses potential impacts to the cultural or historic resources in the area, which includes the Jenkins Site and the Jones Site described in Chapter 3, Section 3.2. The Jenkins Site, located east of the proposed TRU Waste Treatment Facility site, is a pre-1942 homestead site consisting of a deteriorated house and outbuilding (Figure 3-1). A late 1980s evaluation of its eligibility for listing as a historic place by the University of Tennessee concluded that the site was not eligible for listing on the National Register of Historic Places (Campbell et al. 1989). The Jones Site, located east of the proposed TRU Waste Treatment Facility site, dates from 1820 and was recommended for inclusion on the National Historic Register (Campbell et al. 1989). DOE consulted with the Tennessee State Historic Preservation Officer under the provisions of the National Historic Preservation Act regarding any potential adverse consequences associated with the proposed action and the alternatives. The Deputy State Historic Preservation Officer concluded that no properties eligible for the National Register of Historic Places would be affected and had no objections to the TRU Waste Treatment Facility (Appendix E).

4.2.1 Methodology

Impacts to cultural and historic resources were assessed by determining where activities would occur for each of the alternatives. Potential impacts, such as destruction of resources by bulldozing and other site preparation activities, were identified by determining if sensitive resources were present in the area to be disturbed. This presence/absence of cultural and historic resources is based on several reconnaissance-level (walk-down) surveys conducted from 1988 through 1996 (Faulkner 1988; Duvall, 1992, 1993, and 1996) on and near the sites included in each alternative.

4.2.2 No Action Alternative

No archeological, cultural, or historical resources have been identified immediately next to the Melton Valley Storage Tanks, or the legacy TRU solid waste storage facilities. In addition, the

No Action Alternative would have no impact on the historic resources identified in the general area, i.e., the Jones Site and Jenkins Site.

4.2.3 Low-Temperature Drying Alternative

The proposed 2-ha (5-acre) site for a low-temperature drying waste treatment facility has no known archaeological, cultural, or historical resources within or contiguous to its boundaries; thus, no impacts are expected. It is conceivable that surface or subsurface resources may be identified during construction activities, such as the use of heavy equipment for land clearing, grading, and other construction-related work. Appropriate measures such as avoidance, where possible, or data recovery operations, including detailed recording of surface features and/or archaeological excavation, would be implemented to mitigate any identified effects on these resources. The Low-Temperature Drying Alternative would not impact the Jones and Jenkins Sites.

4.2.4 Vitrification Alternative

The proposed 2.8-ha (7-acre) site for a vitrification waste treatment facility has no known archaeological, cultural, or historical resources within or contiguous to its boundaries; thus, no impacts are expected. It is possible that surface or subsurface resources may be identified during construction activities, and appropriate measures such as avoidance, where possible, or data recovery operations, including detailed recording of surface features and/or archaeological excavation, would be implemented to mitigate any identified effects on these resources. The Vitrification Alternative would not impact the Jones and Jenkins Sites.

4.2.5 Cementation Alternative

The proposed 2-ha (5-acre) site for a cementation waste treatment facility has no known archaeological, cultural, or historical resources within or contiguous to its boundaries; thus, no impacts are expected. It is conceivable that surface or subsurface resources may be identified during construction activities, such as the use of heavy equipment for land clearing, grading, and other construction-related work. Appropriate measures such as avoidance, where possible, or data recovery operations, including detailed recording of surface features and/or archaeological excavation, would be implemented to mitigate any identified effects on these resources. The Cementation Alternative would not impact the Jones and Jenkins Sites.

4.2.6 Treatment and Waste Storage at ORNL Alternative

The proposed 2- to 2.8-ha (5- to 7-acre) site for the waste treatment facility, and the 0.3- to 0.8-ha (0.75- to 2-acre) area needed for the waste storage facilities required for the implementation of this alternative, have no known archaeological, cultural, or historical resources within or contiguous to its boundaries; thus, no impacts are expected. It is conceivable that surface or subsurface resources may be identified during construction activities, such as the use of heavy equipment for land clearing, grading, and other construction-related work. Appropriate measures such as avoidance, where possible, or data recovery operations, including detailed recording of surface features and/or archaeological excavation, would be implemented to mitigate any identified effects on these resources. The Treatment and Waste Storage at ORNL Alternative would not impact the Jones and Jenkins Sites.

4.2.7 Cultural and Historic Resource Impacts Summary

There are no known archaeological or cultural resources within the area of the proposed site. None of the alternatives would impact any properties registered, or eligible for registration, in the National

Register of Historic Places. The alternatives that include waste treatment would take appropriate measures (avoidance, data recovery, etc.) if any surface or subsurface archeological, cultural, or historic resources were detected during construction, operation, or D&D of the proposed treatment facility.

4.3 ECOLOGICAL RESOURCES

This section discusses impacts to the ecological resources of the area, including flora and fauna, that would result from the implementation of each of the alternatives. Field surveys conducted in the summer of 1999 (Appendices C.2 and C.3) indicated that there were no Federal or Tennessee State-listed sensitive plant species, aquatic resources, or threatened or endangered animal species identified on the proposed facility site. In addition, DOE also consulted with the U.S. Fish and Wildlife Service and the TDEC (Appendix E) regarding the potential presence of Federally- or State-listed threatened or endangered species on or near the proposed TRU Waste Treatment Facility. The U.S. Fish and Wildlife Service indicated that the gray bat and pink mucket pearly mussel (both Federally-listed endangered species) are known to occur near the project area, and that potential habitat for the Indiana bat (Federally-listed endangered) might be present near the project area. DOE also prepared a draft Biological Assessment for those three species (Appendix E).

Although the pink mucket pearly mussel is known to occur in the Clinch River in Tennessee, the species is unlikely to be present in Melton Branch, White Oak Creek, or White Oak Lake near the proposed facility because these bodies of water do not provide proper habitat. Because there is no suitable habitat for this species present on or near the proposed site, there would be no direct or indirect impacts to the pink mucket pearly mussel.

The nearest potential roosting habitat (cave) for the gray bat is at least a mile away from the proposed TRU Waste Treatment Facility boundary. Because the gray bats generally feed near water, and the caves that are approximately 4 miles of the proposed TRU Waste Treatment Facility are close to streams, the gray bats would not be dependent on habitat at the proposed site for feeding (Appendix E). Although the proposed TRU Waste Treatment Facility could potentially contain suitable trees for summer nesting by the Indiana bat, any potential adverse impacts to the species during nesting would be avoided by making sure not to cut any trees onsite during May–September.

Thus, as a result of the field surveys from 1999, consultations with U.S. Fish and Wildlife Service, and evaluation of the habitat requirements for the gray bat and pink mucket pearly mussel, no direct or indirect adverse impacts to sensitive plant species, aquatic biota (including the pink mucket pearly mussel), gray bats, or wildlife species In Need of Management are expected.

Woodland habitats are present on knolls, ridges, and more upland areas. Several types of woodlands, such as deciduous oak-hickory, or transitional woodlands with a mixture of deciduous and pines, would be suitable for sensitive terrestrial animal species. The trees on the proposed site are young to mid-aged with diameter at breast height mostly under 1.5 ft, which is consistent with the size requirements for maternity trees for the Indiana bat. However, no hollow trees, dead or alive, were observed on the site.

4.3.1 *Methodology*

Methods used to determine impacts from the implementation of the proposed action are listed below.

- Quantified changes to the environment, such as the destruction of vegetation and wildlife habitat associated with construction of any facilities.
- Conducted field surveys to determine the presence or absence of sensitive animal (Appendix C.2) and plant species (Appendix C.3), and consulted with appropriate agencies.
- Determined the potential impact of process and sanitary wastewater discharges to the area's biota. The effects to biota from fugitive dust are discussed in Section 4.5.1.3.
- Qualitatively discussed changes to the environment due to human activities, such as traffic and noise.

4.3.2 No Action Alternative

During institutional control, the implementation of the No Action Alternative would include long-term continued storage of TRU wastes in their present locations and would not result in the clearing of any land, nor loss of habitat. The No Action Alternative would continue to impact terrestrial plant, animal, and aquatic species in the SWSA 5 North trench area, as the site would continue to exist in the present state. TRU and alpha low-level wastes currently stored in the below-grade trenches at SWSA 5 North are a source of radionuclide contamination to soils, groundwater, surface water, and the biota. This contamination source would continue if this alternative were implemented.

Potential impacts to aquatic biota and fish over the next 10,000 years due to loss of institutional control could come from release of radionuclides and non-radionuclides from sources such as the Melton Valley Storage Tanks, as well as trenches and buildings at the SWSA 5 North area, etc. These potential impacts were evaluated semi-quantitatively for a scenario in which the Melton Valley Storage Tanks leak gradually into White Oak Lake, and qualitatively for releases from all other sources. For the Melton Valley Storage Tanks, it was assumed that the tanks all leak at a constant rate of 1% of their volume per year. Therefore, the entire liquid contents of the tanks are assumed to be transferred to White Oak Lake over a period of 100 years.

To estimate exposure in White Oak Lake from the Melton Valley Storage Tanks, it was assumed that the concentration of radionuclides would reach steady-state when the radionuclide activity leaking into the lake was the same as the rate of loss from the lake. The daily leakage rate was calculated by multiplying the assumed volume of 50,000 gal per tank by 8 tanks and 3.78 L/gal. The total volume was multiplied by 1% per year and divided by 365.25 days/year, resulting in a leakage rate or flow (designated F_{tank}) of 41 L/day. The average concentration (designated C_{tank}) of each radionuclide in the tanks was calculated using analytical data from the tanks (Keller et al. 1996). Rapid mixing into White Oak Lake was assumed. It was assumed that the flow from White Oak Lake (designated F_{lake}) is 1.3×10^6 ft^3/d = 4.6×10^{10} L/d (Loar 1992). At steady-state, the mass entering the lake ($C_{tank} \times F_{tank}$) equals the mass leaving the lake ($C_{lake} \times F_{lake}$). Therefore,

$$C_{lake} = C_{tank} \times F_{tank}/F_{lake} = 41/4.6\times10^{10} = C_{tank} \times 9.02 \times 10^{-10}.$$

Average concentrations of radionuclides in the tanks and steady-state concentrations are shown below:

Radionuclide	Average tank concentration (C_{tank})Bq/mL	Steady-state lake concentration (C_{lake})Bq/mL
Cesium-134	1.93E+04	1.74E-05
Cesium-137	8.13E+05	7.34E-04
Cobalt-60	1.15E+03	1.03E-06
Europium-152	4.13E+02	3.73E-07
Europium-154	2.98E+02	2.69E-07
Europium-155	1.28E+03	1.66E-06
Iodine-129	1.19E-01	1.08E-10
Plutonium-238	1.40E+00	1.26E-09
Plutonium-239/240	1.09E+00	9.80E-10
Plutonium-242	5.23E-01	4.72E-10
Strontium-90	4.87E+04	4.40E-05
Technetium-99	7.70E+02	6.95E-07
Uranium-233	1.54E+01	1.39E-08
Uranium-234	1.00E-01	9.02E-11
Uranium-235	1.00E-01	9.02E-11
Uranium-236	1.00E-01	9.02E-11
Uranium-238	5.00E-01	4.51E-10

The steady-state concentrations of all radionuclides were compared to benchmarks for aquatic biota (Bechtel Jacobs 1998) by dividing the concentration by the benchmark to calculate hazard quotients. The benchmarks correspond to the widely used National Council on Radiation Protection and Measurements recommended limit of 1 rad/day for aquatic organisms. Radiation hazards to herons were calculated for internal radiation as a result of ingesting water and fish and for external radiation from water. Methods are described in Appendix F.2 and are similar to those described by Bechtel Jacobs (1998).

The sum of hazard quotients for aquatic biota at steady-state was 7.0×10^{-7}, indicating that there would be no hazard to aquatic populations from leakage of the Melton Valley Storage Tanks at the assumed rate. The sum of hazard quotients for herons was 1×10^{-6}, indicating no hazard to fish-eating predators. Note that the assumed exposures do not take into account possible accumulation of some radionuclides in sediment. They also are conservative because they do not account for loss of activity by radioactive decay. For example, the half-life of cobalt-60 is 5.27 years, so in 100 years, the activity of cobalt-60 would have decreased from 1.03×10^{-6} Bq/mL to 2×10^{-12} Bq/mL, and the average exposure over 100 years would be approximately 700-fold less than the estimated exposure. Similarly, cesium-134, cesium-137, strontium-90, europium-154, and europium-155 would all have decayed substantially. Europium-152 would almost all have been converted to gadolinium-152, an alpha emitter with a long half-life. Therefore, assuming immediate leakage of the tanks as described above provides the largest possible exposure. Thus, the negligible hazard to biota from leakage from the Melton Valley Storage Tanks during the first 100 years after loss of institutional control would only continue to decrease during the remainder of the 10,000 years.

Although releases from the Melton Valley Storage Tanks do not appear to pose adverse impacts of aquatic biota during the next 10,000 years under the assumptions described above, potential risks to biota as described in the Remedial Investigation Report on the Melton Valley Watershed (DOE 1997a) are likely to continue and possibly increase due to larger uncontrolled releases from the SWSA 5 North trenches and other upstream sources.

4.3.3 Low-Temperature Drying Alternative

The clearing of trees and vegetation in preparation of the 2-ha (5-acre) site for facility construction would impact the area habitats. The habitat is young to mid-successional forest. The area of proposed

disturbance is small in relation to the surrounding similar habitat, 2 ha (5 acres) in comparison to 14,569 ha (36,000 acres) included in the ORR; therefore, impacts on terrestrial plant and animal species habitat are expected to be small. The most affected animal species are small vertebrates such as mice and amphibians, which have home ranges less than 2 ha (5 acres); thus, clearing this land would result in complete loss of their habitat.

The proposed facility site contains few aquatic biota (except for some aquatic invertebrates, such as insects or worms, as well as aquatic microorganisms such as algae and diatoms) because there is so little permanent aquatic habitat onsite. Streams downstream from the proposed facility site, such as Melton Branch and White Oak Creek, as well as White Oak Lake, contain larger numbers and variety of aquatic organisms due to better habitat. The proposed low-temperature drying facility would not treat or release wastewater; thus, there would be no impact to the area's aquatic biota from wastewater discharges. In addition, treatment of the waste in the SWSA 5 North trenches would positively impact terrestrial and aquatic biota in this area when the contamination sources from these trenches is removed.

In addition to the loss of habitat, construction noise and increased area activity would cause temporary displacement of local wildlife populations. These wildlife populations are expected to return once activities are completed at the proposed site. Estimated impacts outside of the fenced facility area are expected to be minimal because of restricted employee access and limited anticipated activities outside the defined facility area. Impacts resulting from increased vehicular traffic could be represented by small animal displacement, instances of road kills, and a shift in vegetation composition to more disturbance-tolerant species. These impacts would be primarily associated with increased vehicular traffic on the Old Melton Valley Road.

Impacts resulting from the D&D of the facility would be very similar, although less intense, to the early clearing, construction, and operation of the proposed treatment facility. Site cleanup, breakdown of equipment, dismantling of the facility, and final waste transportation out of the area are activities that would be expected during the D&D project phase. After completion of the D&D activities, the site would be revegetated, in order to re-establish animal and plant species.

4.3.4 Vitrification Alternative

The clearing of trees and vegetation in preparation of the 2.8-ha (7-acre) site for facility construction would impact area habitats. The construction, operation, and D&D of the proposed treatment facility, and increased human presence, would also result in impacts from the implementation of this alternative. These anticipated impacts would be similar to the impacts discussed for the Low-Temperature Drying Alternative. An additional 0.8 ha (2 acres) of land would be disturbed, since this alternative requires a slightly larger facility area than the other alternatives.

Because the facility would not treat or release process or sanitary wastewater, the aquatic biota would not be impacted by wastewater discharges. Steam may be a byproduct of the vitrification process but, due to placement of engineering controls within the treatment system, harmful contaminants should be extracted from the steam; thus, there are no anticipated impacts from temperature changes in the surrounding area due to the release of steam or heat from the facility. Correct implementation of treatment procedures would not result in any additional measurable impacts to terrestrial flora or fauna of the area. The treatment of the waste in the SWSA 5 North trenches would positively impact terrestrial and aquatic biota in this area when the contamination sources from the trenches is removed. Air emissions such as fugitive dust are discussed in Section 4.5.

Following closure and D&D of the vitrification facility, the site would be revegetated in order to reestablish animal and plant species.

4.3.5 Cementation Alternative

The clearing of trees and vegetation in preparation of the 2-ha (5-acres) site for facility construction would impact the area habitats. The anticipated impacts resulting from the implementation of the Cementation Alternative would include impacts associated with clearing of the proposed site, construction of the treatment facility, and increased human presence, which are similar to those impacts discussed for the Low-Temperature Drying Alternative.

The Cementation Alternative would not treat or release process or sanitary wastewater, and no waste discharge resulting from waste treatment is expected; thus, aquatic biota would not be impacted from wastewater discharge. The treatment of the waste in the SWSA 5 North trenches would positively impact terrestrial and aquatic biota in this area when the contamination sources from the trenches is removed. Air emissions such as fugitive dust are discussed in Section 4.5.

Following closure and D&D of the cementation facility, the site would be revegetated in order to reestablish animal and plant species.

4.3.6 Treatment and Waste Storage at ORNL Alternative

The impacts resulting from implementation of this alternative are associated with clearing the proposed site, construction of the proposed treatment facility and waste storage units, and increased human presence, as discussed previously for the three alternatives that involve waste treatment (low-temperature drying, vitrification, and cementation). A total of 0.3 to 0.8 ha (0.75 to 2 acres) of habitat would be lost due to the construction of the additional and waste storage facilities. These new facilities would be located adjacent to the Melton Valley Storage Tanks storage area (see Figure 2-4) and at SWSA 5 North.

The additional waste storage facilities would be required for the treated wastes, because under this alternative the treated wastes would continue to be stored at ORNL rather than shipped to an off-site disposal facility. It is assumed for analyses purposes that the existing storage facilities for contact-handled and remote-handled TRU waste would be the storage location of some of the treated wastes; however, additional land would be required for the construction of waste storage facilities, the size of which is dependent on the type of treatment selected. An additional 0.3 ha (0.75 acre) of land would be required for the Low-Temperature Drying Alternative, and 0.6 ha (1.5 acres) would be required for the Vitrification Alternative. The Cementation Alternative would require an additional 0.8 ha (2.0 acres) of land for waste storage. This land is relatively low-quality habitat consisting of cleared industrial areas for the existing waste storage facilities or wooded areas adjacent to the existing cleared storage sites. This habitat would be permanently lost to the flora and fauna that currently use it.

After loss of institutional control, waste constituents would eventually be released into the environment. While impacts to biota are bounded by the No Action Alternative, impacts are expected to be less severe for this alternative because wastes are treated and better contained.

4.3.7 Ecological Impacts Summary

Impacts to terrestrial and aquatic biota due to the continued storage of TRU and alpha low-level wastes in the below-grade trenches in SWSA 5 North would continue under the No Action Alternative.

The four action alternatives would result in this waste being treated and the primary source of contamination in SWSA 5 North would be removed.

The No Action Alternative would not involve the clearing of any land or loss of habitat; however, over the long term after loss of institutional control, the wastes would eventually be released into the environment and would pose a threat to biota. Alternatives that include waste treatment would involve the construction of a single, compact process building affecting approximately 2 to 2.8 ha (5 to 7 acres) of young to mid-successional forested habitat, depending on the treatment selected. The Treatment and Waste Storage at ORNL Alternative would require an additional 0.3 to 0.8 ha of land (0.75 to 2 acres) for the construction of storage facilities needed to implement this alternative. Some construction-related wildlife displacement would be likely, and there is a potential for an increase in road kills during the construction, operations, and D&D activities.

There have been no sensitive plant species, either Federal- or State-listed, identified to occur exclusively in the proposed site area. Therefore, the land clearing and increased area activity that would result from implementation of the four alternatives that include waste treatment would not result in the loss of compatible habitat for any listed plant species. No threatened or endangered species, either State or Federal, were identified at the proposed site during a survey conducted in the summer of 1999. No impacts to threatened and endangered species or aquatic biota are expected from the implementation of any of the treatment alternatives.

4.4 GEOLOGY AND SEISMICITY IMPACTS

The potential impacts to geology and seismicity were analyzed for each alternative for the proposed TRU Waste Treatment Facility.

4.4.1 Methodology

Methods used to determine the environmental impacts for each alternative are listed below.

- Identified activities that could affect near-surface geology (pile driving, blasting, etc.) or deep geology.
- Identified major load-bearing structures that could potentially affect geologic faults.
- Identified the seismic zone for the proposed facility location and required building requirements.
- Quantified the amount of soil disturbed.

4.4.2 No Action Alternative

There would be no construction under the No Action Alternative; therefore, no soils would be disturbed. However, impacts from the ongoing release of contaminants into soils would continue.

The waste stored in the SWSA 5 North trenches would continue to be a source of primary contamination to soils and secondary contamination to soils and groundwater in the SWSA 5 North area. Approximately 14,000 curies of radiation is estimated in the waste contained in these trenches.

The TRU and alpha low-level waste contained in the trenches is stored in 4-inch-thick concrete casks, or a combination of wood and metal boxes. Radioactive contaminants have been identified in the

soil and groundwater in SWSA 5 North, and over the 100-year life of this alternative, the waste would continue to impact the soils in this area.

The TRU waste currently stored in the Melton Valley Storage Tanks, and the various storage buildings and bunkers, poses little threat to the site soils or geology during the institutional control period. The nature of the sludge and supernate waste currently contained within the Melton Valley Storage Tanks, and the 0.5-inch-thick stainless steel construction of these tanks, suggest a breach in tank integrity is unlikely in the near future. Likewise, the materials stored in the various buildings and bunkers are primarily solids, and although the individual containment vessels (drums, rolloff boxes, etc.) lack the overall integrity of the Melton Valley Storage Tanks, a release is not expected during this time.

The No Action Alternative would not affect geologic faults or regional seismicity, as there would be no construction.

After loss of institutional control, not only would releases continue from the SWSA 5 North trenches, but the wastes in the buildings and bunkers at SWSA 5 North would be released due to containment failure (building and bunker collapse and drum and cask failures) and would contaminate the soil, surface water, and groundwater. Eventually, the wastes in all eight Melton Valley Storage Tanks would be released via some form of tank failure. These wastes would also contaminate the soils near the tanks, assuming that failure of a single tank results in 0.55 ha of land being contaminated (Appendix F). While it is not possible to reliably predict if all tanks would fail at once or would be spread out over a period of many years, wastes would contaminate soils over several hectares and would constitute a source of contamination to the environment for many years after release.

4.4.3 Low-Temperature Drying Alternative

The activities associated with the Low-Temperature Drying Alternative proposed facility construction, operation, or D&D activities would be expected to have a small impact on the immediate site area geology and soils. No blasting or pile driving are expected to be required. The proposed facility has been designed to take advantage of the existing topography contours of the site, in order to minimize the amount of cut and fill (less than 22,937 m^3 or 30,000 yd^3) during construction of the proposed facility, based on the facility design discussed in Chapter 2.

No significant removal or addition to the indigenous soils from the site is expected; however, 2 ha (5 acres) would be graded and the soils disturbed during construction of the low-temperature drying waste treatment facility. Further, the removal of the TRU waste from the SWSA 5 North trenches would beneficially impact the area by removing the primary source of contamination to the soils.

Upon competition of the facility D&D activities, the original site contours would be largely restored. The impacts from erosion and other undesirable downhill or downstream effects of storm water runoff are expected to be negligible due to the proposed site layout plan, including passive diversion and hold-up features (see Section 4.5.1.3 for a discussion of soil erosion and dust control). Essentially no change would be made to the current storm water flows, directions, or collection points beyond the boundaries of the facility due to soil disturbance.

The Low-Temperature Drying Alternative would not affect geologic faults or regional seismicity. The proposed facility for the Low-Temperature Drying Alternative is located in Seismic Zone 2, and would be designed with consideration to the Uniform Building Code (UBC) requirements of Seismic Zone 2 facilities. The low-temperature drying waste treatment facility has a projected life of 11 years, and would be designated as a non-reactor nuclear facility as defined in DOE Order 5480.23, which

dictates two containment barriers to the release of contamination during waste treatment operations and shielding/confinement for worker protection and contamination control. The facility would be compact, cubic in dimensions, and heavily shielded, all of which facilitate meeting the required standards.

4.4.4 Vitrification Alternative

The activities associated with the vitrification facility construction, operation, or D&D activities would be expected to have a small impact on immediate site geology and soils. No blasting or driving would be required; therefore, on-site activities should not impact the local subsurface materials. However, 2.8 ha (7 acres) would be graded and the soils disturbed during construction of the vitrification waste treatment facility. Erosion impacts are expected to be negligible and are discussed further in Section 4.5.1.4.

The Vitrification Alternative would not affect geologic faults or regional seismicity. Since the proposed facility for the Vitrification Alternative is located in Seismic Zone 2, it would be designed with consideration to the UBC requirements of Seismic Zone 2 facilities. The facility would be designated as a non-reactor nuclear facility as defined in DOE Order 5480.23, which dictates two containment barriers to the release of contamination during waste treatment operations and shielding/confinement for worker protection and contamination control. The facility would be compact, cubic in dimensions, and heavily shielded, all of which facilitate meeting the required standards.

The removal of the TRU waste from the SWSA 5 North trenches would beneficially impact the area by removing the primary source of contamination to the soils. Following completion of the scheduled project D&D activities, the site contours would be largely returned to pre-existing conditions.

4.4.5 Cementation Alternative

The activities associated with the cementation facility construction, operation, or D&D activities would be expected to have a small impact on the immediate site geology and soils. No blasting or pile driving would be required; therefore, on-site activities should not impact the local subsurface materials. However, 2 ha (5 acres) would be graded and the soils disturbed during construction of the cementation waste treatment facility. No significant removal or addition to the indigenous soils from the site is expected.

The Cementation Alternative would not affect geologic faults or regional seismicity. The proposed facility would be located in Seismic Zone 2, and designed with consideration to the UBC requirements of Seismic Zone 2 facilities. The facility would be designated as a non-reactor nuclear facility as defined in DOE Order 5480.23, which dictates two containment barriers to the release of contamination during waste treatment operations and shielding/confinement for worker protection and contamination control. The facility would be compact, cubic in dimensions, and heavily shielded, all of which facilitate meeting the required standards.

Impacts from erosion and other undesirable downhill or downstream effects of storm water runoff are expected to be negligible due to the proposed site layout plan (see further discussion in Section 4.5.1.5). The removal of the TRU waste from the SWSA 5 North trenches would beneficially impact the area by removing the primary source of contamination to the soils. Following completion of the scheduled project D&D activities, the site contours would be largely returned to preexisting conditions.

4.4.6 Treatment and Waste Storage at ORNL Alternative

Small impacts to site geology and soils would be expected with the implementation of the Treatment and Waste Storage at ORNL Alternative. This alternative would involve treatment by low-temperature drying, vitrification, or cementation. These impacts are discussed in the previous sections. Following treatment, the waste would be stored onsite at ORNL in the existing storage facilities for contact-handled and remote-handled TRU waste or new waste storage facilities as required to handle the volume of treated wastes. The new waste storage facilities would require an additional 0.3 to 0.8 ha (0.75 to 2 acres) of land depending on the selected treatment method.

4.4.7 Geology and Seismicity Impacts Summary

None of the alternatives would impact deep or near-surface geology because there would be no blasting or pile driving involved with any of the alternatives. None of the alternatives would impact the regional seismicity. Under the No Action Alternative the waste from the trenches in SWSA 5 North would continue to release radiological contamination to the soils from these unlined trenches. The four action alternatives would treat the waste that is the primary source of soil contamination in the SWSA 5 North area, but some contaminated soils would likely remain in place until addressed under a CERCLA action. Each alternative that includes waste treatment would disturb soils due to construction and demolition activities; however, the impacts are expected to be small because no significant removal or addition of soils at the site is expected and the proposed facility would take advantage of site contours. By comparison, no soil disturbance would occur under the No Action Alternative. However, after the loss of institutional control under No Action, wastes from the Melton Valley Storage Tanks and wastes in the trenches, bunkers, and buildings at SWSA 5 North would contaminate soils.

4.5 WATER AND WATER QUALITY IMPACTS

The impacts to surface water (Section 4.5.1) and groundwater (Section 4.5.2), and wetlands and floodplain resources (Section 4.5.3), were analyzed for all alternatives to the proposed action.

4.5.1 Surface Water Impacts

This section discusses the environmental impacts to the proposed area's surface water resources. Impacts from the construction, operation, and D&D phases of the proposed facilities are discussed, as applicable, for each alternative. Water use is evaluated in the Utility Requirements Impacts, Section 4.9.

4.5.1.1 Surface water impacts methodology

Methods used to determine potential impacts to surface water for each alternative are listed below.

- Determined changes in surface water quality due to runoff or contamination releases.
- Estimated potential sediment loading using the Revised Universal Soil Loss Equation (Toy and Foster 1998).
- Described storm water control and monitoring measures.
- Calculated the amount of sanitary wastewater and process wastewater volumes and compared these volumes to the capacity of the existing wastewater systems expected to process these waste waters.

4.5.1.2 No Action Alternative

Currently, the SWSA 5 North trenches and nearby areas in this watershed sub-basin release 6% of the total measured strontium-90 and 3.6% of the total measured cesium-137 to the surface waters of the Melton Valley Watershed, which is part of the White Oak Creek Watershed [*Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge Tennessee, Volume 1,* DOE/OR/02-1546/V1&D2 (DOE 1997a)]. The No Action Alternative would continue to impact the surface waters of White Oak Creek and waters downstream from White Oak Lake due to the continued storage of the waste in the SWSA 5 North trenches, which contain 14,000 curies of activity (including americium-241 and curium-244). If the No Action Alternative were implemented, the rate of long-lived radionuclide release could increase over time potentially affecting downstream waters. The long-lived nature of the radionuclides in the solid waste and their high curie content would result in long-term contamination.

Continued storage of the wastes in the Melton Valley Storage Tanks is not expected to result in a release to the surface waters in Melton Branch, White Oak Creek, White Oak Lake, and the unnamed tributary west of the Melton Valley Storage Tanks under normal operations during institutional control. The existing sludge and supernate inventories are stored in corrosion-resistant 304 SS tanks that have secondary containment provided by 304 SS-lined concrete vaults. The Melton Valley Storage Tanks undergo annual integrity assessments, which are required by RCRA, and must maintain their release detection monitoring capabilities. Results of these annual assessments continue to demonstrate that the Melton Valley Storage Tanks are not releasing hazardous constituents or radionuclides to the environment.

In addition, the No Action Alternative would not generate wastewater. Any wastewater that results from spill clean-ups in the vaults would be managed as mixed wastes, or bottled and transported to the low-level waste evaporator at ORNL. Storm water runoff from the Melton Valley Storage Tanks area would continue to be collected in open channels and storm water culverts and diverted to Melton Branch.

Potential impacts to surface water over the next 10,000 years, after loss of institutional control, could come from the release of radionuclides and non-radionuclides from sources such as the Melton Valley Storage Tanks, as well as trenches and buildings and bunkers at the SWSA 5 North area. These potential impacts were evaluated semi-quantitatively for a scenario in which the Melton Valley Storage Tanks leak gradually into White Oak Lake, and qualitatively for releases from all other sources. For this scenario, it was assumed that the tanks all leak at a constant rate of 1% of their volume per year. Therefore, the entire liquid contents of the tanks are assumed to be transferred to White Oak Lake over

a period of 100 years, as previously described in Section 4.3.2. This scenario results in the daily release of only 41 liters of liquid waste per day from the combined tanks, which equates to a steady-state concentration in White Oak Lake that is described by the following equation:

$$C_{lake} = C_{tank} \times F_{tank}/F_{lake} = 41/4.6 \times 10^{10} = C_{tank} \times 9.02 \times 10^{-10}.$$

Average concentrations of radionuclides in the tanks and steady-state concentration were presented in Section 4.3.2. Examination of the non-radionuclide concentrations in the Melton Valley Storage Tanks reveals that their steady-state concentrations would not exceed current State of Tennessee Water Quality Criteria or Federal Ambient Water Quality Criteria. Thus, releases from the Melton Valley Storage Tanks should have negligible adverse impacts to surface water quality.

However, it is likely that most, if not all, of the contents of the SWSA 5 North trenches and buildings and bunkers in this area would be released to the environment during the 10,000 years following the loss of institutional control. Accurate estimation of the impacts to surface water from those sources is difficult because of the uncertainties associated with the nature and rates of the releases. However, there are likely to be releases from SWSA 5 North trenches, at least as much as current levels, and from the bunkers and buildings. These releases would adversely affect water quality. Contaminant releases over time are partially offset by radioactive decay of waste constituents during the 10,000 years after the loss of institutional control.

4.5.1.3 Low-Temperature Drying Alternative

Impacts to White Oak Creek, Melton Branch, and White Oak Lake during the construction period are expected to be negligible because soil erosion and dust control measures would be implemented (silt fences, planting vegetative cover, storm drainage controls, etc.). However, if soil erosion and fugitive dust were not controlled during the construction period, surface water quality (and associated aquatic biota) would be impacted from increased siltation and turbidity. Soil erosion rates are based on the general climatic conditions for eastern Tennessee, the soil types, the length and slope of the construction cut, and the amount of time the soil would be exposed. The Revised Universal Soil Loss Equation (Toy and Foster 1998) estimates approximately 405 metric tonnes/ha/year (181 tons/acre/year) of soil loss in the absence of controls (Appendix F.1 contains the detailed calculations and assumptions used for these data). Normal soil loss for unexposed but similar soils would be at a rate of approximately 6.7 metric tonnes/ha/year (3 tons/acre/year) (Moneymaker 1981). For instance, the clearing of approximately 2 ha (5 acres), and digging the foundation for the low-temperature drying waste treatment facility, could potentially result in soil erosion from wind and specially precipitation runoff.

The unnamed tributary to White Oak Creek that flows along the eastern edge of the proposed facility boundary would likely experience some increased siltation during construction in order to route this tributary through a culvert. Impacts should be minor because the tributary is small with very little actual flow. Soil erosion, especially during rain events, could be deposited onto the floodplains for Melton Branch and White Oak Creek, causing increased short-term siltation and turbidity in the streams and White Oak Lake.

Impacts to Melton Branch, White Oak Creek, and White Oak Lake resulting from the operation of a low-temperature drying waste treatment facility are expected to be negligible for the reasons described below. During operations, the facility would not treat process and sanitary wastewater onsite and no wastewater would be released to surface waters. Sanitary wastewater would be contained and transported by vendors for disposal at an NPDES-permitted wastewater treatment plant. Any excess water that may be generated from the facility would be collected, contained, and transported by tanker

truck offsite by vendors for treatment and/or disposal at an appropriate permitted facility. The total amount of sanitary wastewater that would be generated for this alternative is estimated to be 1,560 m^3 (412,000 gal) (Roy 1999). NPDES-permitted wastewater treatment plants that potentially could be used to treat this wastewater include plants located on the ORR (ORNL, Y-12, or ETTP), or those located offsite such as the City of Oak Ridge or the Kingston wastewater treatment plants. These wastewater treatment plants have capacities to treat sanitary wastewater that range from 681,000 m^3/day [180,000,000 gal per day (gpd)] at the ORNL plant, to 22,200 m^3/day (5,870,000 gpd) at the city of Oak Ridge plant. All of these wastewater treatment plants are operating below their design capacities, so the impact of this additional waste stream from the low-temperature drying waste treatment facility would be negligible to the sanitary wastewater systems. Water usage is discussed in Section 4.9.

The treatment of the wastes removed from the SWSA 5 North trenches would have a positive impact on the surface waters of the Melton Valley and White Oak Creek Watersheds by reducing the amount of radionuclides that could be released to the surface waters.

During facility operations, storm water would be controlled and monitored according to the requirements of the facility's storm water permit to minimize any potential impacts. For example, storm water runoff originating outside the facility boundary would be directed either beneath or around the site (Section 2.4.1). Both off-site and on-site storm water would be managed, so the volumes, rate of flow, direction, or final destination of these flows would not significantly be changed. The facilities' paved areas and parking lots would generally drain west to a detention basin, and the basin outlet would drain through a gate valve to a drainage ditch along the main access road to the facility and eventually cross to the north via an existing culvert under the road. The facility roof and eastern edge of the facility's paved area would drain east to a catch basin that is also equipped with a gate valve. This flow would be directed through a culvert under the Old Melton Valley Road to an existing drainage area located on the north side of this road. The storm water flow from this ditch would eventually reach White Oak Creek. Although the storm water falling on the site would travel more quickly to the retention ditches and areas, the design and hold-up capacity for the retention ditches and areas would result in a rate and location of discharge that is comparable to the pre-development characteristics. In the unlikely event of an outdoor spill or leak of hazardous materials, the gate valves would be closed to contain the event during its cleanup. Storm water drainage off the Melton Valley Storage Tanks vault roof would be captured and diverted to an eastern, gated drainage culvert to be installed for the proposed facility.

The impacts to surface water from D&D activities of the proposed facility are expected to be negligible, and generally similar to those discussed for construction and operation activities. No discharges of wastewater would take place during the facility's D&D activities. Mitigation measures to control soil erosion and fugitive dust during D&D activities would be used to minimize the transport of soil to surface water.

4.5.1.4 Vitrification Alternative

The impacts to White Oak Creek, Melton Branch, and White Oak Lake during the construction phase are expected to be negligible because soil erosion and fugitive dust control measures would be implemented (described in Section 4.5.1.3). In the absence of such controls, potential construction-related soil loss is estimated at a rate of 405 metric tonnes/ha/year (181 tons/acre/year) (Appendix F.1), and the impacts would be similar to those described in Section 4.5.1.3.

The impacts to Melton Branch, White Oak Creek, and White Oak Lake from the 3-year operations of the proposed facility are also expected to be negligible. No sanitary wastewater or process wastewater would be discharged directly to the environment. The amount of sanitary wastewater

generated over the life of the vitrification facility would be 6,283 m^3 (1.66 million gal). There is a slightly higher probability that contaminants could be released into the environment because of additional treatment of process wastewater for this alternative. Process wastewater would be recycled to the extent possible, but occasional "bleeding" of excess water in the system would be required. The process wastewater that is occasionally drawn off the system would be sent to an evaporator, with the condensate sent to a wastewater treatment facility for discharge into an NPDES-approved outfall. The extra step of sending excess process wastewater to the evaporator slightly increases the risk of releasing contaminants to the environment. The condensate would meet applicable NPDES permit limits, and should not have any adverse impacts to surface water. The concentrate left in the evaporator would be mixed with grout binders to form a stabilized waste form that would have no impacts to the surface water quality.

The removal of the wastes from the SWSA 5 North trenches would have a positive impact on the surface waters of the Melton Valley and White Oak Creek Watersheds by reducing the amount of radionuclides that could be released to the surface waters.

Storm water would be managed similar to the methods discussed previously for the Low-Temperature Drying Alternative. The impacts of treating the additional wastewaters at the chosen wastewater treatment plant should be negligible for the same reasons discussed for the Low-Temperature Drying Alternative.

The impacts to surface water from D&D activities for the Vitrification Alternative are expected to be negligible and generally similar to those discussed for construction and operation phase activities. No discharges of wastewater would take place during the D&D phase, and overall impacts to surface water during the approximate 2-year D&D phase should be negligible.

4.5.1.5 Cementation Alternative

Impacts to the surface waters of White Oak Creek, Melton Branch, and White Oak Lake during the construction phase are expected to be negligible because soil erosion and dust control measures would be implemented as described in Section 4.5.1.3. In the absence of such controls, soil loss at a rate of approximately 405 metric tonnes/ha/year (181 tons/acre/year) (Appendix F.1) could be expected, and the impacts would be similar to those described in Section 4.5.1.3.

The impacts to Melton Branch, White Oak Creek, and White Oak Lake associated with facility operations are also expected to be negligible. The proposed facility would not release process and sanitary wastewater, and no sanitary water or process wastewater would be discharged directly to the environment. The total amount of sanitary wastewater generated over the life of the cementation facility would be 5,020 m^3 (1.33 million gal). The impacts of treating the additional wastewater at area wastewater treatment plants should be negligible for the same reasons discussed for the Low-Temperature Drying Alternative. Storm water would be managed similar to the methods Low-Temperature Drying Alternative.

The removal of the wastes from the SWSA 5 North trenches would have a positive impact on the surface waters of the Melton Valley and White Oak Creek Watersheds by reducing the amount of radionuclides that could be released to the surface waters of the area.

The impacts to surface water from D&D activities are expected to be negligible and generally similar to those discussed for construction and operations phase activities. No discharges of wastewater would take place during the D&D phase, and overall impacts to surface water during the D&D activities should be negligible.

4.5.1.6 Treatment and Waste Storage at ORNL Alternative

Impacts to White Oak Creek, Melton Branch, and White Oak Lake from the construction of waste treatment and storage facilities required for this alternative are expected to be negligible because soil erosion and dust control measures would be implemented during the construction of these facilities. In the absence of effective soil erosion controls, soil loss would be at a rate of 405 metric tonnes/ha/year (181 tons/acre/year) for this alternative (Appendix F.1), which would result in similar impacts to those described in Section 4.5.1.3.

The impacts to Melton Branch, White Oak Creek, and White Oak Lake during the facility operations of the waste treatment and storage facilities are also expected to be negligible. No sanitary wastewater or process wastewater would be discharged directly to the environment, with the exception of the vitrification treatment process wastewater, as discussed in Section 4.5.1.4. The impact of treating the additional waste at area wastewater treatment plants should be negligible for the reasons stated for the Low-Temperature Drying Alternative. Storm water would be managed as discussed for each of the previous treatment alternatives.

During institutional control, the interim storage of the TRU, remote-handled low-level, low-level, and mixed waste residuals in the new and existing waste storage facilities at ORNL should have no adverse impacts to the surface water because the wastes would be contained. The treatment of wastes removed from the SWSA 5 North trenches would have a beneficial impact on the surface waters of the Melton Valley and White Oak Creek Watersheds by reducing the amount of radionuclides released to surface water. However, after the loss of institutional control, waste constituents would eventually be released into the surface water. Impacts would be bounded by the No Action Alternative (Section 4.5.1.2), because the waste would be treated and better contained.

The impacts to surface water from D&D activities are expected to be negligible and generally similar to those discussed for construction and operations phase activities. No discharges of wastewater would take place during the D&D phase. Thus, overall impacts to surface water during D&D activities should be negligible.

4.5.1.7 Summary of Surface Water Impacts

The surface waters of the Melton Valley watershed would continue to be negatively impacted with the implementation of the No Action Alternative. Currently, the trenches in SWSA 5 North account for 6% of the strontium-90 and 3.6% of the cesium-137 in the surface waters measured at White Oak Dam for the Melton Valley Watershed (ORNL et al. 1997). The No Action Alternative would not involve any waste treatment, and the continued release of contaminants in the SWSA 5 North trenches would be a continuing source of contamination to the surface waters of the Melton Valley and White Oak Creek Watersheds. By comparison the treatment alternatives would treat the primary source of contamination that impact the surface waters of the Melton Valley Watershed. Facility operation impacts to surface water quality would be negligible for any of the treatment alternatives. Wastewater would not be treated onsite under the Low-Temperature Drying and Cementation Alternatives. The process wastewater from the vitrification facility would be occasionally drawn off the system and sent to an evaporator, with the condensate sent to a wastewater treatment facility for discharge into an NPDES-approved outfall. The extra step of sending excess process wastewater to the evaporator slightly increases the risk of releasing contaminants to the environment. Some construction-related erosion and storm water runoff would occur, but it is expected to be a minor influence on White Oak Creek and White Oak Lake.

4.5.2 Groundwater Impacts

This section discusses the environmental impacts to the area's groundwater resources. None of the alternatives would use groundwater as a direct source of water; therefore, impacts to groundwater quantity from usage were not evaluated. Water usage is discussed in Section 4.9.

4.5.2.1 Methodology

Methods used to analyze the impacts to groundwater conditions are listed below.

- Identified pathways through which groundwater contamination could occur.
- Quantified the types and levels of existing groundwater contamination.

4.5.2.2 No Action Alternative

Under the No Action Alternative, waste storage in the unlined trenches at SWSA 5 North would continue. The trenches have infiltration and seasonal inundation of groundwater, and have a "bathtubbing" effect intermittently throughout the year. These trenches are a source of contamination to groundwater and would continue to impact the groundwater in the Melton Valley and White Oak Creek Watersheds. The volume of contaminated groundwater is estimated to be approximately 1.3E+05 ft^3. Well samples in the area indicate elevated levels of americium-241 and curium-244 ranging up to 5,940 pCi/L [*Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge, Tennessee* (DOE 1997a)].

Under the No Action Alternative, the TRU waste contained in the Melton Valley Storage Tanks and the various storage buildings and bunkers poses little threat to groundwater. A breach in tank integrity is unlikely in the near future under normal operating conditions, due to the nature of the sludge and supernate waste currently contained within the Melton Valley Storage Tanks and the 0.5-inch-thick 304 SS construction of these tanks. The materials stored in the various buildings and bunkers are primarily solids, and although the individual containment vessels (drums, rolloff boxes, etc.) lack the overall integrity of the Melton Valley Storage Tanks, an impact to groundwater is not expected.

After loss of institutional control, wastes in the trenches, bunkers, and buildings at SWSA 5 North and wastes in the Melton Valley Storage Tanks could enter the soils and eventually the groundwater due to containment failure.

4.5.2.3 Low-Temperature Drying Alternative

No direct groundwater impacts are anticipated from the construction, operation, and D&D activities of a low-temperature drying waste treatment facility, as the only discharge would be storm water runoff. Facility containment systems would keep spills (if they occur) from leaving the facility or site and percolating into the ground. Most loading and unloading of waste materials would be performed in paved areas that are not exposed to the weather or storm water runoff.

Groundwater elevation data obtained from an ORNL monitoring well located almost directly in the center of the proposed treatment facility site indicate that the groundwater is well below the foundation level of the facility. Due to very impervious material (silty clay); however, a potential of perched groundwater exists during wet-weather seasons. Any perched groundwater buildup behind the retaining wall and the south wall of the building would be relieved and diverted to the modified drainage area implemented for this alternative.

In addition. the facility would treat wastes contained in the SWSA 5 North trenches, thereby reducing the primary source of contamination in the SWSA 5 North area. As a result, the operation of this facility would have a beneficial impact on the groundwater of the area.

4.5.2.4 Vitrification Alternative

No direct impacts to groundwater would be expected from the construction, operation, and D&D activities of the vitrification facility, as the only discharge would be storm water runoff. Containment systems incorporated into the facility design would keep spills (if they occur) from leaving the facility or site and percolating into the ground. Most loading and unloading of waste materials would be performed in paved areas that are not exposed to the weather or storm water runoff.

Groundwater elevation data obtained from an ORNL monitoring well located almost directly in the center of the proposed treatment facility site indicate that the groundwater is well below the foundation level of the facility. Due to very impervious material (silty clay); however, a potential of perched groundwater exists during wet-weather seasons. Any perched groundwater buildup would be relieved and diverted to the modified drainage area implemented for this alternative.

In addition, the vitrification facility would treat the wastes contained in the SWSA 5 North trenches and thereby reduce the primary source of contamination in the SWSA 5 North area. As a result, the operation of this facility would have a beneficial impact on the groundwater of the area.

4.5.2.5 Cementation Alternative

No direct impacts to groundwater would be expected as a result from the construction, operation, and D&D activities of a cementation facility, as the only discharge from the facility would be storm water runoff. Containment systems are incorporated into the facility design, which would keep spills (if they occur) from leaving the facility or site and percolating into the ground. Most loading and unloading of waste materials would be performed in paved areas that are not exposed to the weather or storm water runoff.

Groundwater elevation data obtained from an ORNL monitoring well located almost directly in the center of the proposed treatment facility site indicate that the groundwater is well below the foundation level of the facility. Due to very impervious material (silty clay); however, a potential of perched groundwater exists during wet-weather seasons. Any perched groundwater buildup would be relieved and diverted to the modified drainage area implemented for this alternative.

In addition, the cementation facility would treat the waste contained in the SWSA 5 North trenches, thus reducing the primary source of contamination in the SWSA 5 North area. As a result, the operation of this facility would have a beneficial impact on the groundwater of the area.

4.5.2.6 Treatment and Waste Storage at ORNL Alternative

No direct impacts to groundwater would be expected from the construction, operation, and D&D activities of a treatment facility, or the construction and operation of storage facilities under this alternative, as the only discharge would be storm water runoff. Containment systems incorporated into the design for each facility would keep spills, if they occur, from leaving the facility or site and percolating into the ground. Most loading and unloading of waste materials would be performed in paved areas that are not exposed to the weather or storm water runoff.

The existing TRU waste bunkers are partially underground and are constructed in a manner to facilitate potential containment vessel failure. New waste storage facilities required for interim storage of the treated waste at ORNL would be constructed in a similar manner, so there would be no impact to the groundwater under normal waste storage conditions. In addition, a waste treatment facility would treat the waste contained in the SWSA 5 North trenches and thereby eliminate the primary source of contamination in the SWSA 5 North area. The impacts are expected to be primarily beneficial in light of attempts to remove the waste, treat, and store onsite. However, after the loss of institutional control, waste constituents would eventually be released into the groundwater. While impacts are bounded by the No Action Alternative, they are expected to be less because the waste would be treated and better contained.

4.5.2.7 Summary of Groundwater Impacts

No groundwater would be pumped for any of the alternatives; therefore, there are no impacts to groundwater quantity expected as a result of any action alternative. The implementation of the No Action Alternative would result in the continued release of radioactive contaminants from the SWSA 5 North trenches, especially strontium-90, into the near-surface groundwater and eventually into the surface water of White Oak Creek. After loss of institutional control all wastes from the Melton Valley Storage Tanks and the bunkers and buildings at SWSA 5 North could also be released. By comparison, the four action alternatives would remove and treat these wastes, eliminating a primary source of groundwater contamination in the SWSA 5 North area, and resulting in a beneficial effect on the environment. Under the Treatment and Waste Storage at ORNL Alternative however, contaminants could be released after the loss of institutional control. The impacts would be less than the impacts after loss of institutional control under No Action because the waste would be treated and better contained.

4.5.3 Wetlands and Floodplains Impacts

This section discusses the environmental consequences and impacts to wetlands and floodplains that would result from the implementation of the alternatives for the proposed action.

4.5.3.1 Methodology

Methods used to analyze the impacts to wetlands and floodplains are listed below.

- Determined whether a floodplain or wetland assessment was needed by:
  - — determining the 100-year or 500-year floodplain from Federal Emergency Management Agency (FEMA) maps for the Melton Valley watershed;
  - — identifying and mapping wetlands during a field survey performed in 1999 (Appendix C.1); and
  - — comparing the locations of wetlands and floodplains with the areas expected to be disturbed by the construction, operations, and D&D activities of the treatment facility.
- Prepared as needed, a floodplain or wetland assessment.
- Evaluated whether stormwater runoff would affect wetlands or floodplains.

4.5.3.2 No Action Alternative

The TRU and alpha low-level waste currently stored in the Melton Valley Storage Tanks and the RCRA-permitted storage facilities under the No Action Alternative would not impact the six wetlands

(Figure 4-1) located in the area, nor the Melton Branch and White Oak Creek floodplains. Because essentially no wastes would be released from these facilities. no impacts to the wetlands and floodplains in the area would result from continued normal operations of this facility.

Radionuclide migration from the TRU and alpha low-level wastes stored in the unlined trenches at SWSA 5 North would continue to impact the floodplain in the SWSA 5 North area. The soils around the trenches and White Oak Creek indicated gamma contamination at the surface equal to 50 µrem/hour (DOE 1997a), which would continue to exist in the White Oak Creek floodplain.

Waste releases from the Melton Valley Storage Tanks and trenches, bunkers, and buildings at SWSA 5 North after loss of institutional control would eventually contaminate wetlands in the area.

4.5.3.3 Low-Temperature Drying Alternative

There would be an impact to Wetland B associated with the implementation of the Low-Temperature Drying Alternative. Wetland B, located on the eastern edge of the project site, would be adversely affected by construction of the proposed facility. Wetland B (Figure 4-1) is a 0.012-ha (0.03-acre) intermittent stream/seep that would be eliminated by construction, since installation of a culvert in this area would effectively drain this wetland. A wetlands assessment for this wetland (Appendix C.6) was performed per 10 *CFR* 1022, and coordination is ongoing with the State of Tennessee regarding possible mitigation for Wetland B.

Impacts to Wetlands D, E, and F (Figure 4-1) should be negligible as long as soil erosion is successfully controlled during construction. However, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely impacted temporarily by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C (Figure 4-1) should be negligible because their locations are outside the areas to be cleared for construction and, due to mitigation measures, they would not be affected by siltation.

Under this alternative, there would be no construction in the Melton Branch and White Oak Creek 100-year and 500-year floodplains, and a floodplains assessment per 10 *CFR* 1022 is not required. Secondary impacts related to construction (sediment runoff) to the floodplains of Melton Branch and White Oak Creek are expected to be small as long as soil erosion measures are successfully instituted, as described for surface water (Section 4.5.1.3). Some deposition of soil would occur, but the impacts are only likely to be adverse if the soil erosion is unchecked.

Impacts to wetlands and floodplains from the operation and D&D of the proposed treatment facility are expected to be negligible. These impacts would be similar to those discussed for the construction and operation phase activities for surface water in Section 4.5.1.3.

The TRU and alpha low-level wastes stored in the unlined trenches at SWSA 5 North would be removed for treatment in the proposed facility. The removal of this waste would eliminate the primary source of contamination to the White Oak Creek floodplain in the area; however, secondary contamination from the soil and groundwater would continue to impact the White Oak Creek floodplain in the SWSA 5 North area. The soils around the trenches and White Oak Creek indicated gamma contamination at the surface equal to 50 µrem/hour (DOE 1997a), which would continue to exist in the White Oak Creek floodplain. This soil contamination would have to be remediated as a separate CERCLA action.

4.5.3.4 Vitrification Alternative

There would be an impact to Wetland B associated with the implementation of the Vitrification Alternative. Under this alternative, Wetland B (Figure 4-1) would also be eliminated by facility construction, since the installation of a culvert in this area would drain the wetland. A wetlands assessment (Appendix C.6) was performed per 10 *CFR* 1022, and coordination is ongoing with the State of Tennessee regarding possible mitigation for Wetland B. Impacts to Wetlands D, E, and F (Figure 4-1) should be negligible as long as soil erosion is successfully controlled during construction. However, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely impacted temporarily by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C (Figure 4-1) should be negligible because their locations are outside the areas to be cleared for construction and, due to mitigation measures, they would not be impacted by excess siltation.

Under this alternative, there would be no construction in the Melton Branch and White Oak Creek floodplains, and a floodplains assessment per 10 *CFR* 1022 is not required. The construction impacts to the floodplains of Melton Branch and White Oak Creek are expected to be small as long as soil erosion measures are successfully instituted, as described for surface water (Section 4.5.1.3). Some deposition of soil would occur, but the impacts to the floodplain would only be adverse if the soil erosion is unchecked.

Impacts to wetlands and floodplains from the operation and D&D activities of the treatment facility are expected to be negligible. These impacts would be similar to those discussed for the construction and operation phase activities for surface water in Section 4.5.1.3.

The TRU and alpha low-level wastes stored in the unlined trenches at SWSA 5 North would be removed for treatment in the proposed facility. The removal of this waste would eliminate the primary source of contamination to the White Oak Creek floodplain in the area; however, secondary contamination from the soil and groundwater would continue to impact the White Oak Creek floodplain in the SWSA 5 North area. The soils around the trenches and White Oak Creek indicated gamma contamination at the surface equal to 50 μrem/hour (DOE 1997a), which would continue to have an impact on the White Oak Creek floodplain. This soil contamination would have to be remediated as a separate CERCLA action.

4.5.3.5 Cementation Alternative

There would be an impact to Wetland B associated with the implementation of the Cementation Alternative, since Wetland B (Figure 4-1) would be eliminated by facility construction. Installation of a culvert in this area would effectively drain this wetland. A wetlands assessment (Appendix C.6) was performed per 10 *CFR* 1022, and coordination is ongoing with the State of Tennessee regarding possible mitigation for Wetland B. Impacts to Wetlands D, E, and F (Figure 4-1) should be negligible as long as soil erosion is successfully controlled during construction. However, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely impacted temporarily by excessive siltation. Impacts to Wetlands A and C (Figure 4-1) should be negligible because their locations are outside the areas to be cleared for construction and, due to mitigation measures, they would not be impacted by excess siltation.




Figure 4-1. Wetlands near the proposed TRU Waste Treatment Facility site.

Under this alternative, there would be no construction in the Melton Branch and White Oak Creek 100- or 500-year floodplain; therefore, a floodplain assessment per 10 *CFR* 1022 is not required. The construction impacts to the floodplains of Melton Branch and White Oak Creek are expected to be small as long as soil erosion measures are successfully instituted, as described for surface water (Section 4.5.1.3). Some deposition of soil is likely to occur, but the impacts are only likely to be adverse if the soil erosion is unchecked.

Impacts to wetlands and floodplains from the operations and D&D activities of the treatment facility are expected to be negligible. These impacts would be similar to those discussed for the construction and operations and D&D phase activities for surface water in Section 4.5.1.3.

The TRU and alpha low-level wastes stored in the unlined trenches at SWSA 5 North would be removed for treatment in the proposed facility. The removal of this waste would eliminate the primary source of contamination to the White Oak Creek floodplain in the area; however, secondary contamination from the soil and groundwater would continue to impact the White Oak Creek floodplain in the SWSA 5 North area. The soils around the trenches and White Oak Creek indicated gamma contamination at the surface equal to 50 μrem/hour (DOE 1997a), which would continue to have an impact on the White Oak Creek floodplain. This soil contamination would have to be remediated as a separate CERCLA action under the FFA (See Section 8.2).

4.5.3.6 Treatment and Waste Storage at ORNL Alternative

Impacts to floodplains and wetlands during the institutional control period would be dependent on the treatment option selected. These impacts, which are discussed in Sections 4.5.3.3, 4.5.3.4, and 4.5.3.5, would include the elimination of Wetland B. The construction of additional waste storage facilities required for the interim storage of the treated wastes at ORNL should not impact any wetlands or floodplains. It is assumed that these facilities would be located in the same area as the existing solid waste storage facilities in Melton Valley. After the loss of institutional control, waste constituents would eventually be released into the ground and surface water affecting the floodplains and wetlands near SWSA 5 North. Impacts are bounded by the No Action Alternative, but releases should be less because waste would be treated and better contained.

4.5.3.7 Wetlands and Floodplains Impacts Summary

Under the treatment alternatives, Wetland B (Figure 4-1) would be eliminated due to construction. Installation of a culvert in this area would effectively drain the wetland if any of the treatment alternatives is implemented. A field survey to characterize this and other wetlands (Appendix C.1) was performed per 10 *CFR* 1022.11. In addition, a wetlands assessment for Wetland B (Appendix C.6) was conducted, and coordination is ongoing with the State of Tennessee regarding possible mitigation measures for this wetland.

There would be no construction in a floodplain, and a floodplain assessment under 10 *CFR* 1022 would not be required. Floodplain impacts would be small. The No Action Alternative would continue to impact the White Oak Creek floodplain due to radionuclide migration from the SWSA 5 North trenches during the institutional control period. After the loss of institutional control, loss of containment for all the wastes in both the Melton Valley Storage Tanks and the trenches, buildings, and bunkers at the SWSA 5 North area is assumed. These releases would adversely impact floodplains and wetlands in the White Oak Creek area.

4.6 WASTE MANAGEMENT AT ORNL

This section discusses the environmental impacts of the alternatives for the waste management operations at ORNL. Under the treatment alternatives, wastes included in the proposed action are:

- 900 m^3 of remote-handled TRU sludge,
- 1,600 m^3 of low-level supernate associated with the TRU sludges,
- 550 m^3 of remote-handled TRU waste/alpha low-level waste, and
- 1,000 m^3 of contact-handled TRU waste/alpha low-level waste.

The sludge and supernate contained in the Melton Valley Storage Tanks, which are highly mobile in the environment if spilled, would be changed to a much more environmentally benign waste form. Solid remote-handled and contact-handled solid wastes, and the wastes contained in the unlined trenches in SWSA 5 North, would be repackaged and compacted for off-site disposal.

Table 4-1 provides a comparison and summary of the estimated volumes of treated waste generated for each waste type for each alternative. Waste volumes were calculated by summing the wastes generated for the various waste categories for each treatment alternative shown in Tables 4-2, 4-3, and 4-4.

Table 4-1. Comparison of waste volumes generated by the alternatives that include waste treatment

Waste type	Low-Temperature Drying Alternative waste volumes (m^3)	Vitrification Alternative waste volumes (m^3)	Cementation Alternative waste volumes (m^3)
TRU	607	1,060	1,793
Remote-handled low-level waste	0	0	2,540
Low-level waste - primary	788	87	0
Low-level waste - secondary/D&D	1,990	4,893	2,833
Low-level waste/mixed - secondary	23	4	3
Sanitary wastes	1,760	7,201	7,437
Construction wastes	5,550	20,760	14,143
Recycle/reuse	115	120	77
TOTAL	10,833	34,128	28,826

m^3 = cubic meters.
D&D = decontamination and decommissioning.
TRU = transuranic.

The impacts of disposal of these wastes were evaluated separately [*Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, May 1997 (DOE 1997e), and *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement*, DOE/EIS-0026-S-2, September 1997d)].

Table 4-2. Summary of projected waste volumes for the Low-Temperature Drying Alternative (the total of each waste category is summarized in Table 4-1)

Waste stream	Category	Projected volume out[a]	Treatment requirement
Primary Waste Streams			
Sludge (RH)	TRU	180 m^3	Dry, stabilize
Supernate/sludge wash water	Low-level waste	588 m^3	Dry, stabilize
CH solids	TRU	324 m^3	Various
RH solids	TRU	99 m^3	Various
Solids	Low-level waste	200 m^3	Various
Secondary Waste Streams			
Primary waste containers			
RH casks	Low-level waste	1,217 m^3	None
CH drums and boxes	Low-level waste	44 m^3	Compaction
Construction debris	Sanitary	~200 m^3	None
PPE (gloves, booties, etc.)	Low-level waste	214 m^3	Compaction
HEPA filters	Low-level waste	88 m^3	Compaction
Consumables (rags, towels, etc.)	Low-level waste	272 m^3	Compaction
Mechanical parts	Low-level waste/TRU	4 m^3	None
Aqueous waste filter media	Low-level waste	<20 m^3	Compaction
Steam from wet processing	N/A	N/A	Condense/HEPA filter
Changing/maintenance fluids	Low-level waste/mixed waste	<1 m^3	Stabilize, if required
Laboratory solvents and residues	Low-level waste/mixed waste/TRU	1 m^3	Thermal, none
Laboratory acid digistatis	Mixed waste	<20 m^3	Neutralize/stabilize
Sanitary wastewater	Sanitary	1,560 m^3	Capture
Decontamination and Decommissioning Waste Streams			
Category C, Concrete rubble	Construction debris	5,510 m^3	None
Category A, Free release materials	Recycle, reuse	115 m^3	None
Category B, Non-contaminated materials	Construction debris	30 m^3	None
Category B, Contaminated materials	Low-level waste	135 m^3	Compaction
Category D, Miscellaneous	Construction debris	<10 m^3	None
Category E, Special materials	Low-level waste/mixed waste	<1 m^3	Stabilize

[a]Volumes are waste product volumes in final disposal containers based on total inventory of waste (base + optional volumes) expected to be processed at the facility.

CH - contact-handled.
HEPA - High-Efficiency Particulate Air.
PPE - personal protective equipment.
RH - remote-handled.
TRU - transuranic.
~ - approximately.

Table 4-3. Summary of projected waste volumes for the Vitrification Alternative (the total of each waste category is summarized in Table 4-1)

Waste stream	Category	Projected Volume Out[a]	Treatment Requirement
Primary Waste Streams			
Sludge/Supernate	TRU	577 m^3	Vitrification
CH solids	TRU	260 m^3	Various
RH solids	TRU	116 m^3	Various
RH solids	Low-level waste	87 m^3	Various
Secondary Waste Streams			
Primary waste containers			
RH casks	Low-level waste	946 m^3	Volume reduction
CH drums and boxes	Low-level waste	44 m^3	Volume reduction
Construction debris	Sanitary	200 m^3	None
PPE (gloves, booties, etc.)[b]	Low-level waste	315 m^3	Volume reduction
HEPA filters[b]	Low-level waste	82 m^3	Volume reduction
Consumables (rags, towels, etc.)[b]	Low-level waste	181 m^3	Volume reduction
Mechanical/maintenance items	Low-level waste/TRU	97 m^3	Volume reduction
Industrial waste water	Low-level waste/ sanitary	1,108 m^3	Capture
Evaporator concentrate	Low-level waste	326 m^3	Cementation
Laboratory solvents and residues	Low-level waste/mixed waste/TRU	2 m^3	Vitrification, stabilization
Sanitary solids	Sanitary	718 m^3	Capture
Sanitary wastewater	Sanitary	6,283 m^3	Capture
Decontamination and Decommissioning Waste Streams			
Concrete rubble	Construction debris	20,712 m^3	None
Free release materials	Recycle, reuse	120 m^3	None
Non-contaminated materials	Construction debris	48 m^3	None
Contaminated materials	Low-level waste	1,894 m^3	Volume reduction
Vitrified and residual material	TRU	10 m^3	None
Special materials	Low-level waste/mixed waste	2 m^3	Stabilize, special treatment

[a]Volumes are waste product volumes in the final disposal containers.
[b]If the waste is determined to be hazardous, the waste would also be macroencapsulated.
CH - contact-handled. RH - remote-handled.
HEPA - High-Efficiency Particulate Air. TRU - transuranic.
PPE - personal protective equipment.

Table 4-4. Summary of projected waste volumes for the Cementation Alternative (the total of each waste category is summarized in Table 4-1)

Waste stream	Category	Projected Volume Out[a]	Treatment Requirement
		Primary Waste Streams	
Sludge	TRU	1,287 m^3	Cementation
Supernate	RH low-level waste	2,453 m^3	Cementation
CH solids	TRU	260 m^3	Various
RH solids	TRU	116 m^3	Various
RH solids	RH low-level waste	87 m^3	Various
		Secondary Waste Streams	
Primary waste containers			
RH casks	Low-level waste	946 m^3	Volume reduction
CH drums and boxes	Low-level waste	36 m^3	Volume reduction
Construction debris	Sanitary	200 m^3	None
PPE (gloves, booties, etc.)[b]	Low-level waste	384 m^3	Volume reduction
HEPA filters[b]	Low-level waste	83 m^3	Volume reduction
Consumables (rags, towels, etc.)[b]	Low-level waste	257 m^3	Volume reduction
Mechanical/maintenance items	Low-level waste/TRU	130 m^3	Volume reduction
Laboratory solvents and residues	Low-level waste/ mixed waste/TRU	2 m^3	Vitrification, stabilization
Sanitary solids	Sanitary	2,217 m^3	Capture
Sanitary wastewater	Sanitary	5,020 m^3	Capture
		Decontamination and Decommissioning Waste Streams	
Concrete rubble	Construction debris	14,111 m^3	None
Free release materials	Recycle, reuse	77 m^3	None
Non-contaminated materials	Construction debris	32 m^3	None
Contaminated materials	Low-level waste	1,127 m^3	Volume reduction
Special materials	Low-level waste/ mixed waste	1 m^3	Stabilize, special treatment

[a]Volumes are waste product volumes in the final disposal containers.
[b]If the waste is determined to be hazardous, the waste would also be macroencapsulated.

CH - contact-handled.
HEPA - High-Efficiency Particulate Air.
PPE - personal protective equipment.
RH - remote-handled.
TRU - transuranic.

4.6.1 Methodology

Methods used to analyze the impacts of each alternative are listed below.

- Determined the estimated waste volumes and waste classifications for each alternative (Appendix B)].

- Determined available solid waste storage capacity and calculated additional waste storage needs, as appropriate.

4.6.2 No Action Alternative

The No Action Alternative assumes institutional control of the wastes defined in the proposed action for 100 years, during which surveillance, maintenance, and tracking activities would be required for the wastes. Under the No Action Alternative, legacy sludge and supernate would continue to be stored in the Melton Valley Storage Tanks. Remote-handled and contact-handled TRU solid wastes would continue to be stored in the existing solid waste storage facilities for TRU waste.

- Buildings 7855 and 7883 are bunkers, which would continue to store remote-handled TRU waste. Building 7855 is at capacity, with 157.2 m^3 (5552 ft^3) of remote-handled TRU waste in storage. Building 7883 currently stores 10.7 m^3 (377 ft^3) of remote-handled TRU solids and has an available storage capacity of 146.7 m^3 (5179 ft^3);

- Buildings 7572, 7574, 7842, 7878, and 7879 are metal buildings that would continue to store contact-handled TRU waste. These storage buildings currently store over 906 m^3 (32,000 ft^3) of contact-handled TRU wastes. Building 7842 is at capacity, but the other buildings have a combined available storage capacity of 722 m^3 about (25,500 ft^3) for contact-handled TRU wastes.

- The below-grade concrete cells in SWSA 5 North (Buildings 7826 and 7834) currently store about 68 m^3 (2,400 ft^3) of remote-handled TRU and contact-handled TRU wastes, but are not RCRA permitted. This waste is scheduled to be moved to the appropriate existing storage facilities described above as a legacy waste action under CERCLA in Fiscal Year 2000, reducing the amount of available storage space in these facilities.

- Solid TRU waste would continue to be buried in 23 trenches and 8 auger holes used for the retrievable storage of TRU waste in SWSA 5 North.

Removal, treatment, and disposal of the retrievable TRU waste from portions of SWSA 5 North is considered a major component of the selected remedy for the Melton Valley Watershed at ORNL according to the Draft Record of Decision for the Melton Valley Watershed (*Record of Decision for the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1826&D1). In addition, an Interim Record of Decision (issued in connection with the FFA among EPA, TDEC, and DOE under CERCLA) and an Action Memorandum require the TRU waste from the Gunite and Associated Tanks Remediation Project (DOE 1997b) and from the Old Hydrofracture Facility Tanks Remediation Project (DOE 1997c), respectively, to be treated and disposed of along with the TRU waste from the Melton Valley Storage Tanks. This tank waste is included in the total waste volume slated for treatment in the TRU Waste Treatment Facility. If the No Action Alternative were implemented, these two Interim Records of Decision for the ORNL tanks, the Draft Record of Decision for the Melton Valley Watershed, and potentially the upcoming Draft Record of Decision for the Bethel Valley Watershed at ORNL could be affected, and would require amendments and renegotiations with stakeholders and the appropriate regulatory agencies.

There are also legal mandates that require DOE to address legacy TRU waste management needs. DOE has been directed by the TDEC and the EPA to address environmental issues including disposal of its legacy TRU waste. DOE is under a TDEC Commissioner's Order (September 1995) to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and disposal of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin treating legacy TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant in New Mexico by January 2003. The No Action Alternative would result in noncompliance with the ORNL Site Treatment Plan and the TDEC Commissioner's Order, which requires TRU waste treatment and off-site storage. Under RCRA, Section 3008(a), DOE could be fined up to $25,000 per day per noncompliance, in addition to any fines that could accumulate from the State if this legacy TRU waste is not treated and disposed offsite.

4.6.3 Low-Temperature Drying Alternative

The implementation of the Low-Temperature Drying Alternative would have a positive impact on waste management operations at ORNL. Since the treated wastes would be disposed offsite, the beneficial impact of this alternative on ORNL is a substantial reduction in the amount of waste stored onsite. Impacts from continued storage of the wastes at ORNL would be significantly reduced once the project treats, packages, and transports the waste offsite for disposal. Under this alternative, certain nonradioactive construction, office, sanitary, industrial, and demolition wastes would be disposed of at appropriate local facilities. An estimated total of 10,833 m^3 of waste would be generated under this alternative (Table 4-1). This is the lowest total combined volume for the treatment alternatives analyzed. Table 4-2 details the volumes by waste type.

4.6.3.1 Primary waste

The Low-Temperature Drying Alternative would treat and package the primary waste streams identified in the proposed action and summarized in Section 4.6 for final disposition. Table 4-2 provides details on the types and quantities of wastes generated from the Low-Temperature Drying Alternative. For comparative purposes, these data were summarized and compared to similar data for the other action alternatives in Table 4-1.

4.6.3.2 Secondary and other wastes

In addition to the treated primary waste streams, there would be several other waste streams generated by the Low-Temperature Drying Alternative, including: secondary wastes generated from the treatment and management of the primary waste streams [includes HEPA filters, sanitary wastewater and solids, personal protective equipment (PPE), etc.]; and D&D waste (includes contaminated materials, free release materials, concrete rubble, etc.).

The Low-Temperature Drying Alternative includes measures to minimize the quantity of secondary and D&D wastes that would be generated. Waste minimization was incorporated into the planning, design, and operations of the low-temperature drying waste treatment facility. Materials, equipment, and systems were selected based on consideration for potential waste generation. For example, steel used for certain construction materials or shielding was chosen over concrete due to the

recycling opportunity and the reduction in volume of waste generated during D&D activities. Based on equipment design and facility operating requirements, other waste minimization techniques and objectives include:

- minimize contaminated work areas and spaces,
- reduce equipment maintenance requirements due to short service lives,
- avoid operations that lead to the spread of contamination,
- simplify segregated material handling and flow paths,
- limit work-in-progress waste inventories at the facility,
- minimize waste handling iterations at the facility, and
- use mechanical interfaces for contamination control.

During operations, secondary wastes such as consumables (e.g., PPE, step-off pads, rags, etc.) are generated and disposed of in packages being prepared for disposal at a low-level waste disposal facility. The solid waste containers used in delivering primary waste to the facility would also be considered secondary waste (e.g., drums, boxes, and concrete casks) and would be sized, volume reduced, and packaged for disposal. Volume-reduction (compaction, sorting, surveying, and segregation) techniques would be used to reduce the waste product volume prior to shipping and disposal.

Two nonradiological secondary waste streams generated during construction operations would be construction debris and sanitary waste. Sanitary waste would be generated at the highest rates during the construction phase of the project due to the number of personnel onsite. Sanitary wastewater would be routinely trucked offsite to a wastewater treatment plant. Only a minimal quantity of waste, generated through required maintenance and laboratory activities, has a potential for becoming a mixed low-level waste, thus requiring disposal at an appropriate mixed waste disposal facility.

D&D wastes would be generated following closure of the low-temperature drying waste treatment facility. Much of the equipment used for waste treatment would be classified as low-level waste and would require disposal at the Nevada Test Site. The surfaces of the treatment facility and most equipment would be kept relatively clean throughout the life of the facility. Therefore, although contamination would include TRU activity, the concentrations of the TRU radionuclides would be considerably less than the upper limit for low-level waste. Whenever safely and economically feasible, equipment and building components originating from the D&D activities of the low-temperature drying facility would be released for reuse or recycle for another waste remediation project. Uncontaminated building concrete would be sent to a construction debris landfill for permanent disposal.

Treatment of the legacy TRU waste and disposal offsite would result in compliance with the legal mandates regarding management of this waste. Once treatment is complete, existing solid waste storage facilities may be closed reducing the "mortgage" expenses required for maintaining these facilities. Upon completion of the project, the Melton Valley Storage Tanks would be returned to DOE control.

4.6.4 Vitrification Alternative

The implementation of the Vitrification Alternative would have a positive impact on waste management operations at ORNL. Since the treated wastes would be disposed offsite, the beneficial impact of the Vitrification Alternative on ORNL is a substantial reduction in the amount of primary legacy waste stored at the site. Impacts from continued storage of the wastes at ORNL would be reduced once the project treats, packages, and transports the waste offsite for disposal. Under this

alternative, certain nonradioactive construction, office, sanitary, industrial, and demolition waste would be disposed of at appropriate local facilities. An estimated total of 34,128 m^3 of waste would be generated under this alternative. This is the largest total combined waste volume for the treatment alternatives although much of the waste volume is due to construction, sanitary, and D&D wastes. Table 4-3 details the types and quantities of wastes generated from the Vitrification Alternative.

4.6.4.1 Primary waste

The Vitrification Alternative would treat and package the primary waste streams identified in the proposed action for final disposition (see Section 4.6). The sludge and supernate contained in the Melton Valley Storage Tanks, which are highly mobile in the environment if spilled, would be treated by vitrification and changed into a stabilized, environmentally benign, waste glass form. Solid remote-handled and contact-handled solid wastes, and the wastes contained in the unlined trenches in SWSA 5 North, would be compacted and repackaged for off-site disposal.

4.6.4.2 Secondary and other waste

Sanitary waste would be generated at similar rates during the construction and operating phases of the Vitrification Alternative. As shown in Table 4-1, sanitary waste generation is five times greater than the amount produced by the Low-Temperature Drying Alternative. Only a minimal quantity (4 m^3) of low-level/mixed waste is expected to be produced by this alternative.

This alternative would generate approximately 20,760 m^3 of construction wastes, the largest volume of construction debris under any of the treatment alternatives. In general, there would be a substantially greater quantity of low-level secondary and D&D wastes generated from the Vitrification Alternative (4,893 m^3) because of the larger process building and the additional equipment required for the vitrification process. It is expected that much of the melter would have to be cut up and disposed of as TRU waste.

Treatment of the legacy TRU waste and offsite disposal of the treated waste would result in compliance with the legal mandates regarding management of this waste. Once treatment is complete, existing solid waste storage facilities may be closed, reducing the "mortgage" expenses for maintaining these facilities. Upon completion of the project, the Melton Valley Storage Tanks would be returned to DOE control.

4.6.5 Cementation Alternative

The implementation of the Cementation Alternative would have a positive impact on waste management operations at ORNL. Because the treated, wastes would be disposed offsite, the beneficial impact of this alternative on ORNL is a substantial reduction in the amount of primary legacy waste stored at the site. Impacts from continued storage of the wastes at ORNL would be reduced once the project treats, packages, and transports the waste for off-site disposal. Under this alternative, certain nonradioactive construction, office, sanitary, industrial, and demolition wastes would be disposed of at appropriate local facilities. An estimated total of 28,826 m^3 of waste would be generated under this alternative (Table 4-1). Table 4-4 details the types and quantities of wastes generated from the Cementation Alternative.

4.6.5.1 Primary waste

The Cementation Alternative would treat and package the primary waste streams (Section 4.6.) for final disposition. The sludge and supernate contained in the Melton Valley Storage Tanks, which are

highly mobile in the environment if spilled, would be treated by cementation, which involves the mixing of the waste material with additives to form a stabilized, environmentally benign, cement-like waste product. Treatment by cementation would result in an increased volume of the primary waste stream (from 4,050 m^3 before treatment to 4,203 m^3 after treatment). By comparison, primary waste volumes are reduced by low-temperature drying from 4,050 m^3 to 1,391 m^3 and from 4,050 m^3 to 1,040 m^3 by vitrification. The treatment timeframe is longer for the Cementation Alternative in order to meet the requirements of the shipment capacity allotment given by Waste Isolation Pilot Plan to each approved shipper. Solid remote-handled and contact-handled solid wastes, and the wastes contained in the unlined trenches in SWSA 5 North, would be repackaged and compacted for off-site disposal.

4.6.5.2 Secondary and other waste

The Cementation Alternative requires more equipment than the Low-Temperature Drying Alternative and, therefore, would generate substantially more maintenance waste (130 m^3). In addition, the Cementation Alternative would produce 2,540 m^3 of remote-handled low-level waste compared to none for the other two treatment alternatives (Table 4-1). The D&D approach would be similar to the Vitrification Alternative (e.g., replace and remove the cementation process equipment). However, it is not expected that the processing equipment would be classified as TRU, so disposal at the Waste Isolation Pilot Plant should not be required.

Treatment of the legacy TRU waste followed by offsite disposal would result in compliance with the legal mandates regarding management of this waste. Once treatment is complete, existing solid waste storage facilities may be closed reducing the "mortgage" expenses for maintaining these facilities. Upon completion of the project, the Melton Valley Storage Tanks would be returned to DOE control.

4.6.6 Treatment and Waste Storage at ORNL Alternative

This alternative would consist of the treatment of the primary wastes followed by interim storage at ORNL. Due to volume reduction and other process differences, the lowest total waste volume (10,833 m^3) is associated with treatment by low-temperature drying. Treatment by vitrification would generate a total of 34,128 m^3 of wastes, and treatment by cementation would produce a total of 28,826 m^3 of wastes.

The construction of the additional storage facilities needed to handle the excess treated, secondary, and D&D wastes would have to coincide with the construction of the treatment facility in order to be ready for the receipt of the treated waste streams. If this alternative were chosen, it is assumed that the existing bunkers could be used to store treated remote-handled TRU wastes, and the new waste storage facilities would be located in the Melton Valley area of ORNL, preferably near the waste treatment facility. In addition, it is assumed that the storage facility footprint would be similar to the existing storage facilities and have a similar waste storage capacity (approximately 150 m^3 for remote-handled TRU waste, and 300 m^3 for other waste types). Existing storage facilities for storage of contact-handled TRU waste, which have a combined capacity of 1,631 m^3 (57,632 ft^3), could be used for storage of treated low-level waste. The building footprint used for these calculations also includes any shielding requirements. Table 4-5 provides a summary of the volumes of treated waste generated by each treatment alternative, and the space required for construction of additional waste storage facilities.

Following construction of the additional waste storage facilities, there would also be surveillance, maintenance, and tracking required to properly manage this waste and the associated facilities if this alternative were implemented.

There are also legal mandates that require DOE to address legacy TRU waste management needs. DOE has been directed by the TDEC and the EPA to address environmental issues including disposal of its legacy TRU waste. DOE is under a TDEC Commissioner's Order (September 1995) to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and disposal of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin treating legacy TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant in New Mexico by January 2003. The Treatment and Waste Storage at ORNL Alternative would result in noncompliance with the ORNL Site Treatment Plan and the TDEC Commissioner's Order, which requires TRU waste treatment and off-site storage. Under RCRA, Section 3008(a), DOE could be fined up to $25,000 per day per noncompliance, in addition to any fines that could accumulate from the State if this legacy TRU waste is not treated and disposed offsite.

4.6.7 Waste Management Impacts Summary

The waste volumes discussed in the proposed action and summarized in Section 4.6 would remain in their current state with the implementation of the No Action Alternative. This alternative would result in continued surveillance, maintenance, and tracking activities for the waste. This alternative and the Treatment and Waste Storage at ORNL Alternative would also be in violation of the ORNL Site Treatment Plan and the TDEC Commissioner's Order (September 1995) requiring the treatment and off-site disposal of legacy TRU waste, which could result in large monetary fines for DOE, as compared to the alternatives that include waste treatment and off-site disposal (low-temperature drying, vitrification, and cementation), which would help DOE meet its regulatory requirements.

Table 4-5. Summary of the TRU, mixed low-level, remote-handled low-level, and low-level waste volumes (including D&D wastes), the resulting new storage space required for each treatment alternative, and the land area required for additional storage facilities

	Low-Temperature Drying	Vitrification	Cementation
Table 4-5a. Summary of the TRU, mixed low-level, and remote-handled low-level waste volumes and new storage space required			
Treated TRU waste volume (m^3)[d]	607	1,060	1,793
Mixed low-level waste volume (m^3)	23	4	3
Treated remote-handled low-level waste volume (m^3)	–	–	2,540[a]
Total TRU, mixed, and remote-handled low-level waste requiring on-site storage (m^3)	630	1,064	4,336
Existing waste bunkers storage capacity (m^3)	320	320	320
New storage capacity needed (m^3)[b]	310	744	4,016
Assumed capacity of single new waste bunker (m^3)	150	150	150
Number of new waste bunkers needed	3	5	27
Assumed area of new waste bunker (m^2)	234	234	234
Total Storage Facility Area required for TRU, mixed, and remote-handled low-level wastes (m^2)	702	1,161	6,265
Table 4-5b. Summary of low-level waste volumes and new storage space required			
Total low-level waste requiring on-site storage (m^3)	2,778[a]	4,983[a]	2,833[a]
Existing storage capacity (metal building)	1,631	1,631	1,631
New storage capacity needed (m^3)[b]	1,147	3,352	1,202
Assumed capacity of single new metal building (m^3)	300	300	300
Number of new metal buildings needed	4	11	4
Area of new metal buildings (m^2)	375	375	375
Total area required for low-level wastes (m^2)	1,434	4,190	1,503
Table 4-5c. Total area required for all waste types and the associated land requirements for the new storage facilities			
TOTAL FACILITY SPACE REQUIRED FOR ALL WASTE TYPES (m^2)	**2,136**	**5,351**	**7,768**
TOTAL HECTARES REQUIRED FOR NEW WASTE STORAGE FACILITIES[c]	**0.3**	**0.6**	**0.8**

[a]Total waste volumes include alpha-low-level waste.
[b]Determined by subtracting available capacity from resulting waste volume and dividing by assumed storage capacity of new facility (150 m^3 for TRU, mixed, and remote-handle low-level wastes, and 300 m^3 for low-level wastes).
[c]Determined by summing storage space required for all waste types, for each treatment method, and converting to hectares.
[d]TRU waste volumes include both remote-handled and contact-handled waste.

For the alternatives that include waste treatment, secondary wastes would be generated during the construction, treatment, and D&D activities. Because of the volume reduction associated with the treatment method, the Low-Temperature Drying Alternative would result in the lowest total volume (10,833 m^3) of treated, secondary, and D&D wastes of the treatment alternatives. The Vitrification Alternative would produce a total of 34,128 m^3, and the Cementation Alternative would generate a total of 28,826 m^3 of wastes. These wastes would be disposed off-site in an appropriate permitted disposal facility for the treatment alternatives that include disposal. If the Treatment and Waste Storage at

ORNL Alternative were implemented, additional waste storage facilities would be required (total space ranging from 0.3 to 0.8 ha or 0.75 to 2.0 acres) depending upon the treatment process selected.

4.7 AIR QUALITY

This section discusses the impacts to air quality resulting from the construction, operation, and D&D of the proposed treatment facility. Because the alternatives would take place in an attainment area for all criteria air pollutants, no Clean Air Act conformity determination is required. There are no sensitive human populations such as children, the elderly, or hospital patients within five miles of the proposed facility. There are no known species of biota which are particularly sensitive to air emissions near the facility. Human health impacts from air emissions are addressed in Section 4.10. Impacts associated with accidental releases of air pollutants are addressed in Section 4.11.

4.7.1 Methodology

Methods used to determine the impacts from the alternatives are listed below.

- Qualitatively discussed vehicle and dust emissions.
- Calculated air emissions using mass balances for the treatment alternatives (Appendix B).
- Compared the projected air emissions to the National Ambient Air Quality Standards, and qualitatively to the Class I prevention-of-significant deterioration (PSD) areas.
- Calculated radiological emissions based on an assumed HEPA filter efficiency of 99% each for two filters used in sequence.
- Calculated metals emissions based on an assumed HEPA filter efficiency of 99% each for two filters used in sequence.
- Assumed organic constituents were completely emitted to provide a conservative estimate of total air emissions.
- Computed dose rates for the nearest off-site locations for the maximally exposed individual (MEI) using projected emission rates (Appendix B) and CAP88 model.

4.7.2 No Action Alternative

Under the No Action Alternative no air emissions are expected from the TRU waste storage at ORNL.

4.7.3 Low-Temperature Drying Alternative

Potential air contaminants would include vehicle emissions and fugitive dust from construction, which are both easily mitigated using proper equipment and control measures or techniques. During facility operations, air pollutants could potentially be emitted from the proposed facility (stationary source), and would be emitted by vehicles driven by workers, or used to transport waste to the facility and from the facility (mobile sources).

The Low-Temperature Drying Alternative is not expected to adversely impact air quality during facility operations. The emissions from the proposed treatment facility were estimated by considering all the constituents of the waste that would be processed in the facility. Calculations indicate that the air emissions from a low-temperature drying waste treatment facility during normal operations would be below the State of Tennessee limits for air permitting exemptions (Table 4-6). The estimated emissions would be 62% to 86% of the allowable exemption.

Table 4-6. Estimated air emissions from the proposed Low-Temperature Drying treatment facility and State of Tennessee permit exemptions

Compound	Emission	Exemption	Regulatory citation
Volatile organics	0.062 lb/h	0.1 lb/h	1200-3-9-.04(h)
Particulate matter	0.086 lb/h	0.1 lb/h	1200-3-9-.04(I)
Radionuclides	0.063 mrem/year	0.1 mrem/year	1200-3-9-.04(I)

The concentrations of hazardous air pollutants, except for uranium, projected for off-site locations are generally several orders of magnitude below recently measured concentrations (Table 4-7) at the same locations and, therefore, do not measurably contribute to the ambient air concentration. These treatment emissions were calculated based on the chemical and physical characteristics of the waste and the efficiency of removal by the HEPA filters. Uranium is projected to cause a small, but possibly detectable increase (less than 50%) in the measured ambient air concentrations of hazardous air pollutants.

Table 4-7. Average concentrations of hazardous air pollutants measured at ORR and projected maximum concentrations from the Low-Temperature Drying Alternative

Hazardous air pollutant	Measured ORR average concentration ($\mu g/m^3$)	Low-Temperature Drying Alternative projected maximum concentration ($\mu g/m^3$)
Arsenic	6×10^{-4}	1×10^{-8}
Cadmium	2.7×10^{-4}	5.2×10^{-9}
Chromium	8×10^{-4}	1.9×10^{-7}
Lead	3.4×10^{-3}	2.5×10^{-7}
Uranium	7×10^{-5}	2.7×10^{-5}

The conservative total estimated radiological emissions of 5.44-03 curies/year for the Low-Temperature Drying Alternative is based upon a HEPA filter efficiency of only 99% for each filter in a series of two, instead of the design efficiency of 99.97% for each filter for very small particles. Higher efficiencies are likely for larger particles. CAP 88 was used to calculate doses. This emission rate yields a maximum dose of 0.063 mrem/year at about 100 m (328 ft) southwest of the stack and about 0.023 mrem/year at 1,250 m (4,101ft) southwest of the stack (closest off-site location) and 0.019 mrem/year at 1,250 m (4,101 ft) northeast of the site. The off-site dose of 0.023 mrem/year should be compared to the MEI of the general public from airborne radionuclides from the ORR, or 0.41 mrem/year. The maximum estimated dose resulting from the Low-Temperature Drying Alternative based on the conservative emission rates, is generally within the uncertainty of the dose to the MEI of the general public from airborne radionuclides. The use of HEPA efficiencies closer to the design efficiency would further reduce the estimated dose from the facility.

Virtually all of the radionuclides in the TRU waste are nonvolatile and would only be released during D&D activities as part of demolition dust and debris. The potential concentrations of radionuclides in the demolition dust would depend upon the contamination resulting from operations, the effectiveness of facility decontamination, and the demolition processes used for the D&D of the proposed facility.

4.7.4 Vitrification Alternative

Potential air contaminants for the Vitrification Alternative, during construction, would include vehicle emissions and fugitive dust, which are both easily mitigated using proper equipment and control measures or mitigation techniques. These potential releases during normal facility operations and during D&D activities include radionuclide emissions, particulate matter emissions, and volatile organic emissions (associated only with tank waste treatment).

The primary means of mitigating treatment-related air emissions is an effective off-gas system. The Vitrification Alternative off-gas consists of a complex mixture of entrained particulates, gases, and vapors that result from the thermal processes occurring in the melter. The vitrification off-gas system would exhaust gases from the melter plenum, maintain the melter at a negative pressure in relation to the cell, and clean the off-gas-to-stack discharge. Off-gas treatment for this alternative would be accomplished with two systems. The primary off-gas system for the Vitrification Alternative consists of three components: a film cooler, an off-gas quencher, and a high-efficiency mist eliminator (HEME) with condensate tank and scrubber. The primary off-gas system would be designed to provide a total decontamination factor of at least 2.5E+12 and a decontamination factor for semivolatile/condensing products of at least 8E+08. The decontamination factors were provided by personnel in the DOE Savannah River Plant design group who are working on a vitrification design (Savannah River Plant 1999). The system, up to and including the HEMEs, would remove up to 99% of radionuclide activity.

The secondary off-gas treatment system would remove acid gases from off-gas and perform final filtration of particulates prior to stack discharge. The secondary off-gas system consists of a selective catalytic (NO_x) reduction (SCR) unit, HEPA filters, and a wet scrubber. The SCR uses a catalyst bed and ammonia to convert NO_x to nitrogen and water. The SCR is expected to remove about 90% of the NO_x. HEPA filters would remove about 99.97% of the remaining particulates in the off-gas stream. A wet scrubber would eliminate the release of any remaining acid gases and any unreacted ammonia. Collected material from the off-gas system would be recycled back through the vitrification facility for processing, eliminating it as a waste stream. Since emissions from the vitrification system with state-of-the-art off-gas treatment would be similar to the Low-Temperature Drying Alternative (except higher nitrogen oxide emissions would be expected), Low-Temperature Drying Alternative emissions are considered the bounding case.

The Vitrification Alternative is expected to comply with applicable air standards. Similar vitrification off-gas systems have been effectively employed for vitrification facilities at other DOE sites with emissions within exempted levels (Savannah River Plant 1999). Although highly unlikely, if emission exemption limits, as outlined in Table 4-6, could not be attained with the specific equipment, then air permits would be required.

4.7.5 Cementation Alternative

Potential air contaminants during construction of a cementation waste treatment facility would include vehicle emissions and fugitive dust, which are both easily mitigated. Most operational off-gas problems, and the associated environmental and health and safety risks, are eliminated with the cementation treatment method. These potential releases during normal operations, and to some extent during D&D activities, include radionuclide emissions, particulate matter emissions (primarily metals), and volatile organic emissions (associated only with process of tank wastes). The cementation mixing process has provisions for dust collection and filtration (i.e., a dust collection baghouse to prevent particulates and fine particles from entry into the building ventilation system). The dust collection baghouse would transfer the collected dust back into the cementation system by way of the mixer. With a properly designed dust and vapor collection system, the emissions from a cementation waste

treatment facility, based on engineering judgment, are assumed to be similar to those for the Low-Temperature Drying Alternative (except higher particulate emissions would be expected). The Low-Temperature Drying Alternative emissions are considered the bounding case. Therefore, the air emissions from the cementation facility during normal operations are projected to be below the State of Tennessee limits for air permitting exemptions, as indicated in Table 4-6.

4.7.6 Treatment and Waste Storage at ORNL Alternative

As discussed for the other treatment alternatives, potential air contaminants during construction would include vehicle emissions and fugitive dust, which are both easily mitigated. These potential releases during normal operations, and D&D activities, includes radionuclide emissions, particulate matter emissions (primarily metals), and volatile organic emissions (associated only with process of tank wastes). Air emissions from normal operations; and permit requirements (regulatory exemptions) would be the same as those discussed in the previous sections for the treatment alternatives (Sections 4.7.3, 4.7.4, and 4.7.5). Air quality is not expected to be impacted during storage of the treated waste.

4.7.7 Air Quality Impacts Summary

Under No Action, there are no known air emissions from the TRU waste in storage at ORNL. Construction and D&D activities associated with the other alternatives would result in minor, short-term fugitive dust emissions. Air emissions during normal operations of the proposed treatment facility would be below State of Tennessee permit exemption concentrations. Air quality is not expected to be impacted from storage of treated waste.

4.8 TRANSPORTATION IMPACTS

This section discusses the impacts and consequences associated with on-site retrieval and transport of solid waste to and from the treatment facility and the off-site transportation of treated waste for the action alternatives. It also addresses the construction of on-site storage facilities for the Treatment and Waste Storage at ORNL Alternative. The off-site truck transportation analysis was done using routing models following the general principle of minimizing distance and transportation time. They are representative of routes which serve to bound transportation impacts. They do not necessarily present actual routes. Actual routes would be determined in accordance with Federal and State authorities and DOE policy. Route changes constrained by regulation should not create a significant deviation in the effects described.

4.8.1 Methodology

4.8.1.1 Solid waste on-site retrieval and transport from trenches, bunkers, and buildings

Approximately 200 casks of remote-handled TRU solid waste stored in 23 trenches at SWSA 5 North would be retrieved. Additionally, approximately 100 casks of remote-handled TRU and 1,000 m^3 (five thousand 55-gal drum-equivalents or 250 shipments) of contact-handled TRU waste would be retrieved from aboveground buildings and bunkers at SWSA 5 North and transported to the proposed TRU Waste Treatment Facility.

Retrieval of Subsurface Remote-handled TRU Containers

Retrieval of subsurface remote-handled TRU casks would involve removal of about 5 ft of soil overburden and hand-rigging the casks with lifting cable so they can be retrieved from the trenches.

A temporary enclosure (e.g., a Rubb tent) equipped with negative-pressure ventilation for containment and HEPA filtration system would be required so that all excavation and retrieval activities would be conducted inside the enclosure. It is assumed that the size of the enclosure would accommodate the required equipment and allow four casks to be removed without moving the enclosure. Excavation would be accomplished by a combination of machine and hand excavation such that each cask can be totally exposed for inspection and proper rigging. The trench will require shoring for personnel protection while preparing the casks for retrieval.

Once the casks have been exposed, they would be banded, rigged, and transferred into an overpack using a mobile crane, or equivalent, still operating within the enclosure. The overpack approach envisioned for this estimate is an overpack that consists of a base plate that the cask can be moved onto, and a dome with an integral lifting fixture that will be placed over the overpack and fastened to the base plate. The overpack would then be lifted out of the trench and staged for loading for transport to the TRU Waste Treatment Facility site. It is assumed that all of the casks will require overpacking.

The dose rate of each cask when placed in the trenches and bunkers was monitored. The dose rate at the surface of the casks ranged from 1 mrem/h to 5,000 mrem/h with approximately 15% of the casks ranging from 1,000 to 5,000 mrem/h. Retrieval would use a staged/graded approach using shielding, distance, and time—depending on the dose rate. Procedures for retrieving casks with larger dose rates would be modified to ensure that worker exposure meets DOE requirements and As Low as Reasonably Achievable (ALARA) objectives.

Routine worker exposures are monitored by dosimeters. Workers are limited to 100 mrem/week and/or 2 rem/year. However, Bechtel Jacobs Company LLC, the on-site contractor, is committed to a dose of less than 1 rem/year for involved workers (Kelley 2000).

Retrieval of Remote-handled TRU Waste Containers from Bunkers

The concrete blocks that enclose the containers in the storage bunkers in SWSA 5 North would be removed to provide access to the casks. The blocks would remain in the bunker for disposition at a later date. Casks have already been palletized and would be ready to be loaded onto the transport trucks with forktrucks.

The waste containers and overpacks would be transported by truck from the trench area and the storage bunker locations to the TRU Waste Treatment Facility site. At least two potential routes have been identified from SWSA 5 North to the TRU Waste Treatment Facility site; one is approximately 0.5 miles, and the other is approximately 1.1 miles. The more conservative assumption of 1.1 miles is used for the calculation of travel distance, and a round trip of 2.2 miles for each load is used.

Transport of Remote-handled and Contact-handled TRU Solid Waste

The number of trips that would be made per day is based on the TRU Waste Treatment Facility site accepting a maximum of 1 cask per day. It is assumed that approximately 200 casks are retrieved from retrievable subsurface storage and 100 casks from storage bunkers. Including the time to build and move the temporary enclosure for the trench excavation as required, and allowing health, safety and inefficiency factors for working in protective clothing inside the enclosure, the total estimated time required to transport all 300 of the remote-handled TRU casks to the TRU Waste Treatment Facility site is approximately 37,000 man-hours. Crew sizes are 10 persons for cask removal and transport of waste from trenches, 8 persons for constructing and moving Rubb tent; and 7 persons for cask removal and transport of waste from bunkers. Assuming 300 round trips for 1 cask per trip, the total mileage for

transport of the remote-handled TRU waste to the TRU Waste Treatment Facility site is approximately 660 miles.

There are approximately 60 B-25 boxes and just under 3,000 drums of contact-handled TRU waste stored in aboveground metal buildings. A visual inspection would be made prior to movement of any container to ensure their structural integrity is adequate for them to be moved. It is assumed that 10% of the drums will be deteriorated enough to require overpacking prior to transport. Overpacking could require either placing the drums into commercial overpacks or emptying the waste from the deteriorated drums into the overpacks. For the basis of manhour estimates, it is assumed that all of the deteriorated drums will have to be repackaged into overpacks. The waste in the deteriorated drums would be emptied by hand onto Herculite, or equivalent material, the empty drum placed into the overpack, and the contents then placed into the overpack.

The drums, boxes, and overpacks will be loaded by forktrucks onto a transport truck and transported from the aboveground storage locations to the TRU Waste Treatment Facility site, approximately 1.1 miles away. Based on the assumption that the TRU Waste Treatment Facility site can accept a maximum of 20 each, 55-gal drum-equivalents per day, the 1,000 cubic meters of contact-handled TRU waste would require approximately 7,400 man-hours for a 5-person crew to load, overpack 10% of the waste, and transport waste, and the total mileage is approximately 540 miles. There would be 245 shipments contact-handled waste.

4.8.1.2 Transport from TRU Waste Treatment Facility Site to Interim Storage

For the Treatment and Waste Storage at ORNL Alternative, interim storage is required for all of the waste treated at the TRU Waste Treatment Facility site. Thus, approximately 7,768 m^2 (83,662 ft^2) of additional storage space would have to be constructed, using the Cementation Alternative as the bounding condition. The basis of estimating the transport distance from the TRU Waste Treatment Facility site to interim storage was the assumption that interim storage would be built in SWSA 5 N, which is 1.1 miles from the TRU Waste Treatment Facility site. The basis of the time required to construct interim storage space is that pre-fabricated metal buildings would be used, and administrative controls would be utilized to ensure personnel protection. The estimated time required to construct the 7,768 m^2 (83,662 ft^2) of interim storage is 20,000 hours. The time to load all of the containers of treated waste, transport them to interim storage, and unload them, which is estimated to require 3,339 round trips, is approximately 147,000 hours. Five and one-half full-time equivalents are assumed for the crew size.

Therefore, the total time required for building interim storage space and transporting all of the waste there is 167,000 hours, and the distance required for the transport of the waste containers is 7,346 miles.

4.8.1.3 Off-site Transportation

Methods used to determine off-site transportation impacts for each alternative are discussed below.

- Evaluated the impacts associated with the transportation of TRU waste using the analysis developed for the WIPP SEIS-II (DOE 1997d). Because the packaging requirements and routes are the same, all alternatives involving transportation to the Waste Isolation Pilot Plant in New Mexico would vary only by the number of shipments that would result from the implementation of the alternative.

- Evaluated truck accident statistics for each State, and by highway type. These were used to determine route-specific accident, injury, and fatality rates for the WIPP SEIS-II (DOE 1997d) analysis.

  — Obtained the route mileage through each State using HIGHWAY 3.1 model.

  — Multiplied the mileage by the State traffic, injury, or fatality rates.

  — Summed the products for the route, and divided the sums by the total route mileage.

  — With the exception of the State of New Mexico, the accident rate data for Federally aided interstate highways were used. For the New Mexico routes, the rate for Federally aided primary roads was used since the waste would primarily travel U.S. Highway 285.

  — Multiplied the route-specific accident, injury, and fatality rates by the number of shipments along each route to obtain the estimated number of accidents, injuries, and fatalities.

- Estimated transportation risks for routine operations and accidents were obtained from the WM PEIS (DOE 1997e). These risks were based on State data on the frequency of accidents for trucks per mile traveled. National average rural, suburban, and urban population densities were used. The WM PEIS (DOE 1997e) used an external dose rate of 1 mrem/hour at 1 meter for DOE low-level waste shipments.

- Incorporated analysis for radiological impacts from accidents from two types of analyses conducted for the WIPP SEIS-II (DOE 1997d).

  — The first type of analysis used the RADTRAN code, a model used to compute radiological accident impacts, to estimate the radiological impact from accidents during transport from each of the major DOE sites. This analysis took into account eight different severity categories, their probabilities of occurrence, the distance from each site, and the number of shipments.

  — The second type of accident analysis was an assessment of four bounding accidents. These are described more fully in Appendix E of the WIPP SEIS-II (DOE 1997d). Accident-free radiological impacts due to transportation of the TRU wastes were determined in the WIPP SEIS-II by using the RADTRAN code to estimate the impacts due to this radiation.

- Assumed that all on-site untreated waste shipments to the proposed TRU Waste Treatment Facility would occur on non-public, DOE-controlled roads. The impacts of traffic accidents not related to the radioactive material or hazardous chemicals being transported were assumed to be the same as impacts resulting from the transport of nonhazardous material.

The accident impacts calculated as a number of injuries and fatalities were calculated on a per-shipment basis. Calculations were based on data presented in the WIPP SEIS-II and the WM PEIS (DOE 1997d; 1997e). It was determined that transportation for the entire DOE Waste Management

Program to the Waste Isolation Pilot Plant could account for 56 accidents resulting in 5 fatalities. The ORR portion of this program was calculated as 8.1E-04 accidents per shipment and 1.1E-04 fatalities per shipment, which translates to a possibility that approximately 8 out of 10,000 shipments could potentially result in an accident, with the potential for 1 fatality occurring out of 10,000 shipments. Because the canisters are empty on the return trip, only half of these accidents would occur with a loaded canister. Most transportation accidents are unlikely to cause any radioactive material release, but very severe accidents may result in a release. A 1987 Nuclear Regulatory Commission study, cited in the WIPP SEIS-II (DOE 1997d), estimated that only 0.6% of accidents could cause a radiation hazard to the public.

Analysis of a hypothetical container breach assumed an accident occurred under conditions that maximized, within reasonable bounds, the impacts to exposed populations. The analysis concluded that, for the average concentration of radionuclides and hazardous chemicals in a TRUPACT II waste container, the estimated dose would result in three latent cancer fatalities (LCFs) in the exposed population. The estimated maximum individual dose would result in a 0.04 probability of a LCF. For a breached remote-handled 72B cask, the total population dose estimated would result in a 0.04 LCF in the exposed population. The estimated maximum individual dose would result in a 7E-04 probability of a LCF. Analysis of the ORR to Waste Isolation Pilot Plant route, which included both the probability of an accident and the consequences, estimated a total of 4E-03 LCFs for transuranic waste (WIPP SEIS-II, DOE 1997d).

The major routine risk to the public from truck transportation is from exposure during rest stops to travelers who are using the same rest stops. For the analysis of low-level waste, DOE assumed the average dose rate of each shipment would not exceed 1 mrem/hour at 1 m from the shipping container, which is consistent with DOE's historical practices. On the basis of typical low-level waste densities, roughly 80 drums with a 208-L (55-gal) capacity would be shipped per truck. The dose per shipment of low-level waste is estimated to be the same for all alternatives involving transportation. The dose to a MEI stuck in traffic for 30 minutes next to a low-level waste shipment is estimated to be 0.5 mrem, representing a lifetime risk of fatal cancer of 3.0E-07 (based on International Commission on Radiological Protection Publication 60 health risk conversion factors).

An accident of severity Category VIII was used to calculate the exposure to the public in the event of an accident. A Category VIII accident represents the most severe accident scenario and assumes the maximum magnitude of mechanical forces (impact) and thermal forces (fire) to which a waste package may be subjected during a truck accident. It would result in the largest releases of radioactive material. Accidents of this severity are extremely rare, occurring once in every 70,000-truck accidents. On the basis of national accident statistics (Saricks and Kvitek 1994) for every 1.6 km (1 mile) of shipment (loaded), the probability of an accident of this severity is 6E-12. The WM PEIS (DOE 1997e) assumed the route distance from the ORR to the Nevada Test Site was 2,151 miles. Thus, for each shipment to the Nevada Test Site, the probability of an accident of this severity is 1.3E-08. DOE concluded that no accident of such severity is expected to occur for the WM PEIS waste alternatives . The estimated consequences for this improbable accident are given in Table 4-8. Because a waste with the highest transportation accident dose was used in the analysis, the accident consequence results are extremely conservative. These results are at least a factor of 10 greater than those anticipated for ORNL low-level waste shipments (DOE 1997e).

Table 4-8. Estimated consequences for the most severe accidents involving shipments of low-level waste[a]

	Population		Maximally exposed individual	
	Dose (rem)	Risk (cancer fatalities)	Dose (rem)	Risk (cancer fatalities)
	Accident location (neutral conditions)			
Urban	8.3E+03	4.2E+00	7.7E-01	3.9E-04
Suburban	1.6E+03	8.0E-01	7.7E-01	3.9E-04
Rural	1.5E-01	8.0E-03	7.7E-01	3.9E-04

[a]Data taken from WM PEIS (DOE 1997e).

4.8.2 No Action Alternative

There would be no transportation of wastes under the No Action Alternative; therefore, no transportation impacts would occur.

4.8.3 Low-Temperature Drying Alternative

4.8.3.1 Waste Retrieval and On-site Transportation

Waste retrieval activities during the Low-Temperature Drying (and other) alternatives consist of exhuming 200 remote-handled waste containers from the SWSA 5 North trenches, removing 100 remote-handled waste containers from the SWSA 5 North aboveground bunkers and buildings, removing 5,000 55-gal drum equivalents of contact-handled waste from the buildings, and loading the containers on trucks. The containers would then be transported an average of approximately 1.1 miles to the treatment facility where they are unloaded within the facility. The retrieval activities at the trenches would be conducted within a temporary, negative-pressure enclosure with a HEPA-filtered exhaust. Workers within the enclosure are required to have suitable protective clothing and equipment with workplace monitoring to ensure radiological doses are within DOE and site guidelines and meet ALARA objectives.

The hazards of waste container retrieval and transportation operations include radioactive doses to facility workers during normal operations, radioactive doses to workers and the public due to facility accident releases, and non-radiological industrial accident and truck transportation accident consequences. In general, radiological doses to facility and transportation workers are controlled by protective clothing, distance from the source, shielding if required, equipment, and by DOE operating procedures. These procedures include requirements to promptly evacuate the immediate vicinity of an accident until the safety of reentering the area is evaluated. The consequences of these low-level doses to facility workers are not separately evaluated in this analysis. Risks to facility workers are bounded by industrial accident consequences. The radiological and non-radiological consequences of retrieval and transportation accidents are evaluated in the following paragraphs and in Table 4-15.

Waste Retrieval Accidents and Routine Exposures

The principal accidents expected to occur during the retrieval phase are container drop accidents, vehicle impact accidents, vehicle impact and consequential fire accidents, and general industrial accidents. Vehicle impact and container drop accidents may result in a release of radioactive material within the enclosure. However, non-involved workers and the public outside the enclosure are protected since the enclosure and the filtration system confine the released material. Within the enclosure, workers are protected by safety equipment and evacuation requirements.

A vehicle impact causing release of radioactive materials and a fire affecting these materials could burn through the enclosure releasing the suspended radionuclides to the environment. The frequency

and consequences of this accident have been evaluated in Section 4.11.6. The accident is estimated to occur in the 1E-04 to 1E-06/year frequency range. A non-involved (and unprotected) worker postulated to be 80 m from the release is estimated to receive a dose of 30 rem resulting in a 1.2E-02 probability of a latent fatal cancer (LCF). A public MEI at the site boundary is estimated to receive a dose of 0.28 rem resulting in a 1.4E-04 probability of LCF. The surrounding population within 50 miles of the release receives a total dose of 4,300 person-rem resulting in 2.1 LCF. Since the unsheltered on-site worker population is sparse, the worker population dose has not been separately estimated. However, consequences to the worker populations are included in the overall population dose consequence.

In addition to the radiological consequences, industrial accidents contribute to non-radiological impacts to workers. As listed in Section 4.8.1.1, a total of 44,400 person-hours are required to retrieve, load, and transport the contact-handled and remote-handled wastes. Based on a DOE industrial fatality rate of 3.4E-03 fatalities per 200,000 person-hours, 7.5E-04 fatalities are expected over the retrieval operations.

Routine exposure to involved workers would be controlled by DOE and Bechtel Jacobs procedures (Section 4.8.1.1). Workers constructing the Rubb tent are assumed not to be exposed. Assuming ten on-site workers full-time for waste retrieval operations and an exposure of less than 1 rem/year yields 10 rem/year to the involved workers. The worker exposure rate is 4.0E-04 LDFs/rem and the retrieval operations are estimated at two years. This yields 8.0E-03 LCFs for involved workers.

Waste Transportation Accidents

Large truck accidents sufficiently severe to release radioactive materials from containers are postulated to occur during transport of wastes to the treatment facility. Fatal large truck accidents are postulated to occur during transport to the treatment facility or during the return trip. The one-way mileage (270 miles) for contact-handled and remote-handled (330 miles) waste transport is estimated to be 600 miles as discussed in Section 4.8.1.1. One-way mileage is used when computing radiological accidents because waste (and thus accident risk) is hauled one way from the SWSA 5 North area to the treatment facility.

For off-site transportation of wastes to a disposal site (Section 4.8.3.2), a maximum-severity large truck highway accident is estimated to occur at a rate of 6E-12/vehicle-mile. However, for this on-site transportation evaluation, a fatal large truck highway accident is conservatively postulated to result in waste container failure and fire. Based on *Large Truck Crash Profile: The 1998 National Picture*, prepared by the Federal Motor Carrier Safety Administration, large truck fatal accidents occur at a rate of 2.3E-08/vehicle-mile. Based on this rate, 1.4E-05 accidents resulting in radioactive material release and fire and 2.8E-05 fatal accidents are expected to occur over the entire waste transportation operation.

The radiological consequences of waste transportation accidents are the same as those defined for the vehicle impact and fire accident during the retrieval operations. In addition, 1.2 fatalities are estimated to occur for each fatal large truck accident. This results in 3.3E-05 non-radiological fatalities occurring over the waste transportation operation.

Summary of Retrieval and On-site Transportation Risks

Accident risk is defined as the product of the likelihood of an accident and the consequence per accident. The industrial accident and fatal truck accident estimates incorporate both likelihood and consequence and are risk measures. The total frequency of the vehicle impact and fire accident during

retrieval is estimated to be 3E-05 based on the median frequency in the estimated range and a 3-year duration of operations. The accident risks and routine worker exposure risks are summarized below:

Accident/Consequence	Accident Risk (expected fatalities)
Retrieval Accidents	
Radiological	6.3E-05 LCF (public)
Non-radiological (Industrial)	7.5E-04 fatalities (involved workers)
Transportation Accidents	
Radiological	2.9E-05 LCF (public)
Non-radiological	3.3E-05 fatalities
Routine Exposure	**Accident Risk (expected fatalities)**
Waste Retrieval Operations	8.0E-03 LCF (involved workers)

The total risks to the non-involved worker and the public MEI at the site boundary due to both retrieval and transportation accidents are 5.3E-07 and 6.2E-09 probabilities of cancer fatality. These risks are small with respect to the risks summarized above.

4.8.3.2 Off-site Transportation

There would be an estimated 397 shipments of TRU waste to the Waste Isolation Pilot Plant resulting from the implementation of the Low-Temperature Drying Alternative.

Non-radiological effects of TRU waste shipments: The shipment of TRU waste would result in 1.7E-03 LCFs attributed to pollution health effects from the truck emissions. The WIPP SEIS-II (DOE 1997d) stated the probability of an accident as 8.1E-4 per shipment and the probability of a fatality as 1.1 E-04 per shipment. This would yield a calculated probability of 3.2 E-01 for accidents and a 4.4E-02 probability of a fatality associated with the TRU shipments for the Low-Temperature Drying Alternative.

Radiological effects of TRU waste shipments: Table 4-9 presents the calculated total population LCFs for the waste shipment to Waste Isolation Pilot Plant resulting from the implementation of the Low-Temperature Drying Alternative.

Table 4-9. Calculated non-accident radiological LCFs for the Low-Temperature Drying Alternative[a]

Oak Ridge to Waste Isolation Pilot Plant	Contact-handled TRU waste shipments (87)	Remote-handled TRU waste shipments (310)
LCFs	8.7E-03	3.1E-02

[a]Data in table were derived from exposure/shipment data presented in the *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS) (DOE 1997d).
LCFs = latent cancer fatalities.
TRU = transuranic.

Non-radiological effects of low-level waste shipments: The WM PEIS estimated fatalities with shipments of low-level waste as approximately one fatality per 16 million shipment miles. Using a representative route distance of 2,151 miles from Oak Ridge to the Nevada Test Site, there would be an

estimated 1.3 E-04 fatality per shipment. The Low-Temperature Drying Alternative represents 277 low-level waste shipments or 2.6E-01 accidents and 3.6E-02 accident fatalities.

Radiological effects of low-level waste shipments: The 277 shipments for this alternative represent a dose of 4.3E-06 person-rem and LCFs of 2.1E-09. The final waste disposal facility for low-level waste is consistent with the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site* (DOE 2000).

DOE would perform comprehensive waste certification before disposition of the waste to any disposal site. For each waste stream, the specific waste profile would be prepared in sufficient detail to provide reasonable assurance that the intended waste product, packaging, documentation, and shipping schedule meet the disposal site requirements and capacity. Table 4-10 shows the projected shipping schedule of waste for the Low-Temperature Drying Alternative. In nearly all cases, the waste generation projected for the Low-Temperature Drying Alternative is a small fraction of the disposal facility's capacity, or acceptance rate, for these wastes. The current national TRU program planning document anticipates, that the ORR would ship almost 16% of the total shipments of the remote-handled TRU waste to be disposed at the Waste Isolation Pilot Plant (DOE 1997d). The waste stream that demands the highest percentage of repository capacity from this alternative is the remote-handled TRU waste, and the projected number of shipments amounts to approximately 4% of the waste to be disposed of at the Waste Isolation Pilot Plant over the next 35 years.

The packaging and transportation equipment needed for safe transport is available to support the projected generation of all wastes. For example, the highest anticipated project usage rate for contact-handled TRU transport casks (TRUPACT II) is 70% of the casks made available to the ORR for this purpose (for only a 5-month period). Maximum demand for remote-handled TRU transport casks (72B) is only 35% of the casks available to the ORR for this purpose. The same is true for the low-level waste shipments projected from the facility; approximately 10% of the casks available commercially in the United States for this type of waste would be committed for approximately a 2-year period.

Table 4-10. Projected waste shipment schedule for the Low-Temperature Drying Alternative

	Calendar year and month																																				
	2003												2004												2005												2006	2007	
	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	Total	Total	Total
Waste Isolation Pilot Plant shipments																																							
72B Cask shipping container:																																							
Treated TRU sludge shipments	12	11	12	11	12	11	12	11	12	11	12	6	12	11	12	11	12	9																					200
Treated RH TRU solids shipments													2	3	3	3	3	3	3	3	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3	36	7[a]	110
Total	12	11	12	11	12	11	12	11	12	11	12	6	14	14	15	14	15	12	3	3	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3	36	7	310
TRUPACT II shipping container:																																							
Nuclear Fuel Services Drum shipments													12	13	13	13	8																							59
CH TRU solids shipments													1	2	2	2	2	2	2	2	1	1	1	1			1			1			1			1	4	1	28
Total													13	15	15	15	10	2	2	2	1	1	1	1			1			1			1			1	4	1	87
Total TRU Shipments													27	29	30	29	25	14	5	5	3	3	3	3	3	3	4	3	3	4	3	3	4	3	3	4	40	8	*397*
Nevada Test Site shipments*																																							
Treated low-level supernate shipments, (208 ft^3 liners)	4	5	4	5	4	5	4	5	4	5	4	2	5	5	5	5	5	5	10	10	10	8																	119
Low-level waste solids shipments (compacted empty casks)													1	2	2	3	3	4	4	4	4	4	4	3	4	4	4	3	4	4	4	3	4	4	4	3			139
Other secondary waste shipments		1		1		1		1		1		1		1		1		1		1		1						1					1			1			19
Total low-level waste shipments	4	6	4	6	4	6	4	6	4	6	4	3	6	8	7	9	8	10	14	15	14	13	4	4	4	4	4	4	4	4	4	3	5	4	4	4			*277*
Total all shipments																																							**674**

[a]Pattern unchanged through February 2007, with remainder in March 2007.

*The final waste disposal facility for low-level waste will be consistent with the Record of Decision of the WM PEIS for low-level waste (e.g., the Nevada Test Site or another designated disposal facility)

RH = Remote-handled

CH = Contact-handled.

The largest volume of locally disposed material, approximately 5,500 m^3 of concrete rubble from the facility demolition, equates to approximately 275 truckloads over a removal period of several weeks. This demand is easily satisfied by local transportation contractors. The handling and transportation systems necessary to remove and transfer the remaining project waste streams are common commercial equipment, readily available and entirely adequate to satisfy the needs of this alternative.

4.8.4 Vitrification Alternative

4.8.4.1 Waste Retrieval and On-site Transportation

The impacts would be identical to those described for the Low-Temperature Drying Alternative in Section 4.8.3.1.

4.8.4.2 Off-site Transportation

Non-radiological effects of TRU waste shipments: The Vitrification Alternative would result in an estimated 989 shipments of TRU waste. The pollution health effects resulting from vehicle emissions are determined to be 4.4E-03 LCFs, with an estimated 8.0E-01 accidents and 1.1E-01 fatalities.

Radiological effects of TRU waste shipments: Table 4-11 presents the LCFs calculated for the representative Oak Ridge to Waste Isolation Pilot Plant route, based on 989 shipments.

Table 4-11. Calculated non-accident radiological LCFs for the Vitrification Alternative[a]

ORNL to Waste Isolation Pilot Plant	Contact-handled TRU waste shipments (53)	Remote-handled TRU waste shipments (936)
LCFs	5.3E-03	9.3E-02

[a]Data in table were derived from exposure/shipment data presented in the *Final Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (WIPP SEIS) (DOE 1997d).
LCFs = latent cancer fatalities.
TRU = transuranic.

Non-radiological effects of low-level waste shipments: The effects of the transportation of low-level waste for the Vitrification Alternative are estimated as 281 shipments resulting in an estimated 2.6E-01 accidents and 3.6E-02 accident fatalities.

Radiological effects of low-level waste shipments: The 281 shipments correspond to a cumulative dose of 4.4E-06 rem to a person living along the ORR site entrance route. This represents a negligible lifetime risk (probability of cancer fatality) of 2.1E-09 for this alternative.

The waste stream that demands the highest percentage of repository capacity among any of the disposal pathways identified is the remote-handled TRU waste treated and packaged by the Vitrification Alternative. The projected shipments amount to approximately 12% (instead of the presently planned 16%) of this type of waste to be disposed at the Waste Isolation Pilot Plant over the next 35 years (DOE 1997d). The packaging and transportation equipment needed to effect the safe transport is available to support the projected generation of all wastes. For example, the highest anticipated project usage rate for contact-handled TRU transport casks (TRUPACT II) is 20% (approximately 1 shipment/week) of the casks made available (5 shipments/week) for this purpose (for a 16-month period). However, the minimal demand over the 3-year operating period for remote-handled TRU transport casks (72B) is 65% to 70% of the casks made available (8 casks/week)

to the ORR (over a period of 1 year), while the maximum demand is 100% of the casks available to the ORR (over a period of 1.5 years). Evaluation of the low-level waste shipments projected from the Vitrification Alternative facility indicates approximately 5% of the casks available commercially in the United States for this type of waste would be committed for approximately a 1-year period.

Shipping operations for this alternative are planned to require single-shift, 5-day-per-week operation. Since there is 100% utilization of available casks for a period of 1.5 years, it is likely that some of the processed waste would have to be shipped during the D&D phase of this alternative.

The largest volume of locally disposed material, approximately 21,000 m^3 of concrete rubble from the facility demolition, equates to approximately 1,250 truck loads over a period of several months. This demand is easily satisfied by local transportation contractors. The handling and transportation systems necessary to remove and transfer the remaining project waste streams are common commercial equipment, readily available and entirely adequate to satisfy the project's needs.

Construction traffic transportation impacts for the Vitrification Alternative are similar to those discussed for the Low-Temperature Drying Alternative (peak construction traffic is increased due to 2.5 times more workers than the Low-Temperature Drying Alternative), only the following transportation impacts are discussed in this section.

- Operations traffic impacts
  - — waste transfers to the facility from ORR;
  - — treated waste shipments; and
  - — worker and operations-related traffic; and
- D&D traffic impacts.

Waste shipments of treated primary waste products from the Vitrification Alternative facility would occur over a 3-year period. Table 4-12 provides the waste shipment schedule for the Vitrification Alternative.

The D&D phase of the project is expected to begin in 2006 and extend for 2 years. The D&D traffic profile would be similar to the construction phase of the project, although reversed. Worker traffic would be approximately one-half to a one-third the peak construction force, reducing in later stages. Truck traffic would peak to several 15.3-m^3 (60-ft^3) debris hauls per day midway through the D&D period.

Table 4-12. Projected shipment schedule for the Vitrification Alternative

	2003												2004												2005												2006	2007	
	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	Total[g,h]	Total[g,h]	Total
Waste Isolation Pilot Plant shipments																																							
72B Cask shipping container:																																							
Treated TRU sludge & supernate[a]				22	22	22	22	22	22	22	22	20	22	22	22	22	22	22	22	22	22	22	22	20	22	22	22	22	22	22	22	22	22	22	22	22			722
Treated RH TRU solids[b]																11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	4				202
D&D waste[c]																																					9	3	12
Total	0	0	0	22	22	22	22	22	22	22	22	20	22	22	22	33	33	33	33	33	33	33	33	31	33	33	33	33	33	33	33	33	33	26	22	22	9	3	936
TRUPACT II shipping container:																																							
CH solids[d]	2	3	4	3	4	3	4	3	4	3	4	3	4	3	4	2																							53
Total TRU shipments																																							*989*
Nevada Test Site shipments*																																							
RH low-level waste solids[e]																						2	2	2	2	2	2	2	2	2	2	2	2	2	1				27
Low-level waste solids[f]	2	4	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	96	38	254
Total low-level waste	2	4	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	3	3	4	5	5	6	5	5	6	5	5	6	5	5	6	5	4	4	96	38	*281*
Total all shipments																																							**1,270**

Notes:

*The final waste disposal facility for low-level waste will be consistent with the Record of Decision of the WM PEIS for low-level waste (e.g., the Nevada Test Site or another designated disposal facility).

[a]The sludge and supernate are put into HalfPACTs and then two HalfPACTs are placed into a 72B Cask. Each HalfPACT contains 0.4 m^3 of treated waste.

[b]Remote-handled (RH) solids that are being shipped to the Waste Isolation Pilot Plant are put into 55-gal drums which are then put into an RH Canister that is then placed in a 72B Cask.

[c]The decontamination and decommissioning (D&D) waste would be directly put into an RH Canister that would be placed into a 72B Cask.

[d]Contact-handled (CH) solids that are being shipped to the Waste Isolation Pilot Plant are put into 55-gal drums which are then put into a TRUPACT II. Although it is possible to have 14 drums per TRUPACT II and 3 TRUPACT II containers per shipment, it was assumed that only eight 55-gal drums could be placed into a TRUPACT II based upon weight limitations.

[e]RH low-level waste would be shipped in a Super Tiger shipping container, which limits the number of drums per shipment to 16.

[f]Other non-RH low-level waste would be shipped without a special shipping container, which would allow eight 55-gal drums per shipment.

[g]There would be approximately one 72B cask shipment per month from April 2006 to March 2007.

[h]There would be 8 Nevada Test Site shipments/month for the first 14 months in D&D, and then there would 6, 6, 5, and 5 shipments. All low-level waste shipments should be completed by June 2007.

RH = Remote-handled.

CH = Contact-handled.

4.8.5 Cementation Alternative

4.8.5.1 Waste Retrieval and On-site Transportation

The impacts would be identical to those described for the Low-Temperature Drying Alternative in Section 4.8.3.1.

4.8.5.2 Off-site Transportation

Non-radiological effects of TRU waste shipments: The Cementation Alternative is predicted to involve 2,425 shipments of TRU waste. This exceeds the total number of shipments to the Waste Isolation Pilot Plant from ORR as proposed in the WIPP SEIS-II and would result in 2.2 accidents and 3.0E-01 fatalities. The pollution health effects are estimated at 1.2E-02 LCFs due to transportation of the waste.

Radiological effects of TRU waste shipments: Table 4-13 presents the LCFs calculated for the representative Oak Ridge to the Waste Isolation Pilot Plant route.

Table 4-13. Calculated non-accident radiological LCFs for the Cementation Alternative[a]

ORNL to Waste Isolation Pilot Plant	Contact-handled TRU waste shipments (53)	Remote-handled TRU waste shipments (2,372)
LCFs	5.3E-03	2.7E-01

[a]Data in table were derived from exposure/shipment data presented in the *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (WIPP SEIS)(DOE 1997d).
LCFs = latent cancer fatalities.
TRU = transuranic.

Non-radiological effects of low-level waste shipments: The Cementation Alternative would result in 914 shipments of low-level waste and an estimated 8.8E-01 accidents and 1.2E-01 accident fatalities.

Radiological effects of low-level waste shipments: The potential cumulative dose to a person living along the ORR site entrance route for this alternative is estimated as 1.5E-05 person-rem corresponding to a calculated 7.5E-09 LCF.

The waste stream that demands the highest percentage of repository capacity among any of the disposal pathways identified is the remote-handled TRU waste packaged by the Cementation Alternative. The projected shipments amount to approximately 30% (instead of the presently planned 16%) of this type of waste to be sent to and disposed at the Waste Isolation Pilot Plant over the next 35 years (DOE 1997d). This amount of waste would greatly impact the Waste Isolation Pilot Plant remote-handled disposal capacity.

The packaging and transportation equipment needed to effect safe transport is available to support the projected generation of all wastes. For example, the highest anticipated project usage rate for contact-handled TRU transport casks (TRUPACT II) is 10% (approximately 5 shipments/week) of the casks made available for this purpose (for a 33-month period). However, the demand over the 6-year operating period for remote-handled TRU transport casks (72B) is 95% of the casks made available (8 casks/week) to the ORR. Evaluation of the remote-handled low-level waste shipments projected from the Cementation Alternative facility indicates approximately 70% of the casks currently available

commercially in the United States for this type of waste would be committed for approximately a 6-year period. This is a significant resource use.

Calculations show that the average TRU concentration for the treated sludge is between 200 and 300 nanocuries per gram which indicates that, due to the high variability in the concentration in the waste, it is likely that there could be treated waste that is not TRU. An alternative approach for treatment, which affects transportation, would be to directly fill remote-handled canisters instead of 55-gal drums for the cementation process. If this were done, the total number of remote-handled shipments would decrease to approximately 1,750 shipments. This would allow the treatment schedule to be reduced to 5 years (from 6 years).

Shipping operations are planned to require single-shift, 5-day-per-week operation. However, due to the increased number of shipments on a weekly basis over the Low-Temperature Drying Alternative, it is likely that shipping operations would extend to two shifts or would be conducted in a shift different from operations, or both.

The largest volume of locally disposed material, approximately 14,000 m^3 (45,932 ft^3) of concrete rubble from the facility demolition, equates to approximately 850 truck loads over a period of several months. This demand is easily satisfied by local transportation contractors.

Since the construction traffic transportation impacts for the Cementation Alternative are similar to the Low-Temperature Drying Alternative, only the following transportation impacts are discussed in this section.

- Operations traffic impacts due to
  - — waste transfers to the facility;
  - — treated waste shipments;
- D&D traffic impacts.

Waste shipments of waste products from the proposed facility would occur over a 6-year period. Table 4-14 provides the waste shipment schedule for the Cementation Alternative.

The D&D phase for the Cementation Alternative is expected to begin in 2009 and extend for 2 years. The D&D traffic profile would be approximately three times the profile of the Low-Temperature Drying Alternative. Truck traffic would peak to several 15.3 m^3 (20 yd^3) debris hauls per day during the first year in the D&D period.

4.8.6 Treatment and Waste Storage at ORNL Alternative

4.8.6.1 Waste Retrieval, On-site Transportation, and Interim Storage[1]

For the Treatment and Waste Storage at ORNL Alternative, the consequences and risks of waste retrieval and transportation to the treatment facility are the same as for the Low-Temperature Drying Alternative (Section 4.8.3.1). In addition, hazards are encountered due to the transportation of treated wastes to the interim storage facility and the industrial hazards of constructing the interim storage

[1]The 147,000 man-hours for loading and unloading the treated waste are included. In addition, the 20,000 man-hours needed to construct the interim storage facilities are included in "Interim Storage."

Table 4-14. Projected shipment schedule for the Cementation Alternative

	2003				2004				2005				2006				2007				2008				
	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	Total
Waste Isolation Pilot Plant shipments																									
72B cask shipping container:																									
Treated TRU sludge[a]	99	99	99	99	99	99	99	99	99	99	85	85	85	85	85	85	85	85	85	85	85	85	80	80	2170
RH TRU solids[b]											14	14	14	14	14	14	14	14	14	14	14	14	17	17	202
Total	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	99	97	97	*2,372*
TRUPACT II shipping container:																									53
CH solids[c]	3	5	5	5	5	5	5	5	5	5	5														
Total TRU shipments	102	104	104	104	104	104	104	104	104	104	104														*2,425*
Nevada Test Site shipments*																									
Treated RH low-level solids[d]																	3	3	3	3	3	3	3	3	27
Treated low-level supernate[e]	32	32	33	33	33	33	33	33	33	33	32	32	32	32	32	32	32	32	32	32	32	32	32	32	776
Low-level waste solids[f]	2	3	3	2	2	3	3	2	2	3	7	6	7	7	7	6	7	8	7	6	7	7	2	2	111
Total low-level waste	34	35	36	35	35	36	36	35	35	36	39	38	39	39	42	41	42	43	42	41	42	42	37	34	*914*
Total all shipments																									**3,339**

Notes:

*The final waste disposal facility for low-level waste will be consistent with the Record of Decision of the WM PEIS for low-level waste (e.g., the Nevada Test Site or another designated disposal facility).

[a]The sludge is put into a 50-gal liner, overpacked into a 55-gal drum, and then 3 55-gal drums are placed into a remote-handled (RH) canister and then a 72B Cask.

[b]Solids that are being shipped to the Waste Isolation Pilot Plant are put into 55-gal drums and three 55-gal drums are put into an RH canister and then a 72B Cask.

[c]Contact-handled (CH) solids that are being shipped to the Waste Isolation Pilot Plant are put into 55-gal drums, which are then put into a TRUPACT II. Although it is possible to have 14 drums per TRUPACT II and 3 TRUPACT II containers per shipment, it was assumed that only eight 55-gal drums could be placed into a TRUPACT II based upon weight limitations.

[d]RH low-level waste would be shipped in a Super Tiger (or similar) shipping container, which limits the number of drums per shipment to 16.

[e]The supernate is put into a 50-gal liner, overpacked into a 55-gal drum, and then placed into a Super Tiger (or similar shipping container).

[f]Other non-RH low-level waste would be shipped without a special shipping container, which would allow eighty 55-gal drums per shipment.

facility. In contrast to retrieval and initial transportation operations, the treated wastes are considered non-combustible and essentially non-dispersible. Therefore, the radiological consequences of these treated waste operations are negligible.

Using the cementation process as the bounding case, a total of 7.346 additional miles (3,339 miles roundtrip) will be traveled to transport the treated wastes to the interim storage facility. Based on the large truck fatal accident data used in Section 4.8.3.1, this operation results in an additional 2.0E-04 expected fatalities. An additional 147,000 person-hours would be required to load and unload the treated wastes, and 20,000 person-hours will be required to construct the interim storage facility. This labor results in a total of 2.8E-03 expected additional fatalities based on an industrial accident fatality rate of 3.4E-03 fatalities per 200,000 person-hours. The total risks of retrieving and transporting treated and untreated wastes, and storing the treated wastes are summarized in Table 4-15:

Table 4-15. Summary of Treatment and Waste Storage at ORNL Risks

Shipments	
Untreated waste shipments to the treatment facility	▪ 300 remote-handled shipments, and ▪ 250 contact-handled shipments
Treated waste shipments to interim onsite storage	▪ 3,339 shipments (cementation process assumed as bounding case)
Non-radiological effects	
Exposure/Accident	**Risk (expected fatalities)**
Industrial accidents during waste retrieval operations	7.5E-04 fatalities (involved workers)
Routine exposures during waste retrieval operations	8.0E-03 LCFs (involved workers)
Transportation accidents	2.3E-04 fatalities
Construction of interim storage facilities (industrial)	3.4E-04 fatalities (involved workers)
Loading and unloading of treated waste accidents	2.5E-03 fatalities (involved workers)
Radiological effects	
Exposure/Accident	**Risk (expected fatalities)**
Retrieval accident (vehicle impact/fire)	6.3E-05 LCF (public)
Transportation accident (vehicle impact/fire)	2.9E-05 LCF (public)

The risks to non-involved workers and the MEI at the site boundary are the same as those listed for the Low-Temperature Drying Alternative, Section 4.8.3.1.

4.8.6.2 Off-site Transportation

The Treatment and Waste Storage at ORNL Alternative does not involve the shipment of any TRU or low-level wastes offsite and would have no off-site transportation effects.

4.8.7 Transportation Impacts Summary

Waste retrieval would result in 6.E-05 LCFs to the public from a fire-related accident releasing radionuclides. Involved workers at SWSA 5 North during waste retrieval operations would experience 7.5E-04 industrial fatalities. An additional 2.3E-04 transportation fatalities and 2.9E-05 LCFs to the public from transportation-related accidents are expected during onsite transportation. These results are expected for all four action alternatives. For the Treatment and Waste Storage at ORNL Alternative, there are additional risks to workers from both the construction of an interim storage facility

(3.4E-04 fatalities) and from the loading and unloading of treated wastes (2.5E-03 fatalities), plus a larger onsite transportation accident risk (2.3E-04 fatalities) than the other action alternatives.

There would be no off-site transportation of TRU and low-level waste for the No Action and the Treatment and Waste Storage at ORNL Alternatives. A comparison of the Low-Temperature Drying, Vitrification, and Cementation Alternatives with regard to radiological and non-radiological effects of TRU and low-level waste shipments is presented in Table 4-16. As described in this table, the non-radiological probability of a fatality for shipment of TRU waste to the Waste Isolation Pilot Plant ranges from 4.4E-02 (Low-Temperature Drying Alternative) to 3.0E-01 (Cementation Alternative). The probability of a fatality due to the shipment of low-level waste to the Nevada Test Site was determined as a miles-traveled proportion of the national low-level waste program. Because cementation would result in more shipments of low-level waste, this alternative represents the highest probability of a non-radiological fatality, 1.2E-01.

Table 4-16. Comparison of alternatives (calculated transportation accidents/fatalities based on total off-site shipments)

Alternative	No Action Alternative; Treatment and On-site Storage at ORNL Alternative	Low-Temperature Drying Alternative		Vitrification Alternative		Cementation Alternative	
Waste type		**TRU**	**LLW**	**TRU**	**LLW**	**TRU**	**LLW**
Shipments	No off-site shipments	397	277	989	281	2,425	914
Non-radiological effects							
Probability of an accident[a,b]		3.2E-01		8.0E-01		2.2	
Fatality due to non-radiological accident		4.4E-02[a]	3.6E-02[b]	1.1E-01[a]	3.6E-02[b]	3.0E-01[a]	1.2E-01[b]
Pollution effects (public LCFs due to truck emissions)[a]		1.7E-03		4.4E-03		1.2 E-02	
Radiological effects to the public							
Dose (person-rem)		17.4 (CH) 62 (RH)		10.6 (CH) 180 (RH)		10.6 (CH) 540 (RH)	
Dose (rem)			4.3E-06[c]		4.4E-06[c]		1.5E-05[c]
LCF		8.7E-03 (CH) 3.1E-02 (RH)	2.1 E-09	5.3E-03 (CH) 9.3E-02 (RH)	2.1E-09	5.3E-03 (CH) 2 7E-01 (RH)	7.5E-09

[a] Analysis used route to Waste Isolation Pilot Plant.
[b] Calculated by mileage ratio.
[c] Dose to person at Oak Ridge Reservation site entrance.

LLW = low-level waste.
LCF = latent cancer fatalities.
ORNL = Oak Ridge National Laboratory.
CH = contact-handled.
RH = remote-handled.
TRU = transuranic.

In general, the radiological risks from routine transportation of radioactive materials are directly proportional to the external dose rate. Dose rates to the public are low and would typically be less than that of natural background radiation. The calculated LCFs for both TRU and low-level waste are shown in Table 4-16. TRU waste has been divided into contact-handled and remote-handled in the table.

4.9 UTILITY REQUIREMENT IMPACTS

This section discusses the impacts of the alternatives on utilities. There is currently 500 kW of electrical power available from the utilities lines in the vicinity of the proposed TRU Waste Treatment Facility Site. A 30-cm (12-inch) potable water main is available near the proposed facility for use. It is assumed for each alternative that involves waste treatment, that potable water, electricity, and telephones would be connected to sources on the adjacent Melton Valley Storage Tank facilities or other nearby locations. Water would be supplied for drinking, process needs, sanitation, and fire protection from the nearby water main. Electricity would be used for heating, lighting, and operations. Telephone service would be required for operations.

4.9.1 Methodology

The methods used to determine the utility requirement impacts for each alternative are listed below.

- Determined the projected electrical requirements for each alternative.
- Determined project water usage for each alternative.

4.9.2 No Action Alternative

The energy requirements associated with the No Action Alternative for continued storage of the waste are limited to the power demands associated with the operation of facility lighting, ventilation, and security systems. The annual energy-related usage resulting from the operation of these systems at the current waste storage facilities ranges from 12 to 32 MW. Using an assumed mid-point for the usage, the total power usage for the lifetime of this alternative (100 years) is estimated at 2,200 MW.

The No Action Alternative would not require the use of any groundwater. Water for drinking, sanitation, and fire protection would continue to be used at present levels. Water use for continued storage is minimal compared to the water availability and current uses in the Melton Valley area at ORNL and the ORR. Water use is estimated to be less than 200 gal per day for the current storage facilities. This is based on the use of 50 gal per non-resident worker per day (FTH EIS 1999), and approximately 3.5 full-time equivalent workers, working 5 days per week, stationed at the Melton Valley Storage Tanks, and the existing solid waste storage facilities (Roy 2000, personal communication). The implementation of the No Action Alternative would result in the continued use of approximately 50,000 gal of water per year, or 5 million gal over the assumed 100-year institutional control period.

4.9.3 Low-Temperature Drying Alternative

Utility requirements during construction, operations, and D&D activities of a low-temperature drying waste treatment facility are summarized in Table 4-17. These utilities would be used throughout the life of the Low-Temperature Drying Alternative, but peak loads and the highest average utilization would occur during the 2 years of projected tank waste retrieval and treatment operations (i.e., 2003–2004).

The available electrical service at the treatment facility site is limited to 500 kW, but at least one source for the additional 2.1-MW peak demand from the facility systems is located less than a mile from the facility (Figure 4-2). An aboveground power line would be installed as part of the project to provide the additional power required for the proposed facility. DOE has evaluated the proposed extension and connection of the proposed load at this point in its distribution system. It requires only a routine emplacement of poles and cable along the existing patrol road right-of-way to accomplish this effort. Projected use of 2.6 MW is unlikely at any one time for the Low-Temperature Drying Alternative; however, if it were to occur, it would only be approximately 2% of the current ORR load. The conversion and dissipation of this electrical energy would be primarily to heat energy, both latent (in the form of evaporated water) and sensible (warmed air emitted from the building stack). Estimated electrical usage is based on the treatment process and mass balances computed in Appendix B. Total electrical usage is estimated at 15,000 MW. Considering the ORR's total energy input, the facility's contribution to local or area temperature influences from this energy would be insignificant.

The bulk of the proposed facility's electrical energy demands arise from two process requirements: (1) evaporate water from the raw waste to meet disposal site criteria and shipping requirements, and (2) evaporate the water used to mobilize the sludge from the Melton Valley Storage Tanks.

The low-temperature drying waste treatment facility would employ a treatment process that would use a minimal quantity of nonhazardous additives for the stabilization of the RCRA metals found in the waste. The stabilization process is accomplished at ambient temperatures and pressures; thus, only minimal energy is needed to handle, store, and control the required additives. No additional mixing is required for the additives beyond that already needed to maintain the tank waste solids in suspension for pumping and homogeneity. Minimal additives also imply minimal expended energy to elevate the process temperature to evaporate water from the waste. No energy-intensive chemical processes would be used in the facility. No other treatment process steps require intensive energy or resource consumption. Water not removed by treatment would be stabilized before disposal (e.g., cementation, absorption, etc.).

Other energy and resource needs related to the project are limited by the relatively short operating life of the low-temperature drying waste treatment facility. While operator hours of productivity/m^3 of waste are fairly standardized in the industry (especially for remote sorting and segregation of the solids that result in the majority of operational hours at the facility), limiting the hours of plant operation reduces management, monitoring, maintenance, and support resources and associated energy needs. The Low-Temperature Drying Alternative would optimally lower the life-cycle cost by balancing the cost of creating capital equipment needed to accommodate the resources with the combined operations and maintenance and D&D costs of operating, and then dismantling the facility with the same resources.

No groundwater would be used for the Low-Temperature Drying Alternative. Table 4-17 identifies the utilities immediately available at the facility site, via a short extension and connection service. Specific energy requirements for the treatment facility operations are provided in Table 4-18. Actual usage would be a fraction of the peak demand. Water usage over the life of this alternative is estimated




Figure 4-2. Location of additional power source.

Table 4-17. Utility requirements of the Low-Temperature Drying Alternative facility

Utility	Requirements	Usage
Potable water	Fire protection, drinking, sanitation, and process	900 gpm (peak)
Electricity	Heating, lighting, and operations	2,600 kW
Telephone	On- and off-site communications	25 voice lines 1 data line
Sewage	Sanitation	Collected and removed by commercial vendor
Solid waste	Housekeeping	Collected in bins and removed by commercial vendor

gpm = gallons per minute.
kW = kilowatt.

Table 4-18. Facility energy requirements (connected load) for the Low-Temperature Drying Alternative

Consumer	hp	Electrical (kW)
Drying/filtration mechanical equipment	100	75
Sludge/supernate retrieval equipment	20	15
CH solids handling equipment	67	50
RH solids handling equipment	40	30
Process off-gas treatment	54	40
Process chillers	228	170
Shipping/receiving	40	30
Steam boiler	—	1,172
Steam boiler pumps	10	8
Instrument/plant air compressor	100	75
Building HVAC fans	200	149
HVAC chillers	335	250
Total operating	1,195	2,063
Total design	× 1.25 = 1,493	× 1.25 = 2,579

CH = contact-handled.
hp = horsepower.
HVAC = heating, ventilation, and air conditioning.
kW = kilowatt.
RH = remote-handled.

at 5 million gal (Jones 1999). On a daily basis, this treatment method would use less than 10% of the 1,000 gal per minute (gpm) DOE has allotted for the proposed TRU Waste Treatment Facility. This is a minimal amount compared to the 1.2 million gal per day used at ORNL.

4.9.4 Vitrification Alternative

The Vitrification Alternative would require 45,000 MW of power. Similar to the Low-Temperature Drying Alternative, the conversion and dissipation of this electrical energy would be primarily to heat energy, both latent (in the form of evaporated water) and sensible (warmed air emitted from the building stack). The bulk of electrical energy demands for the Vitrification Alternative would be from vitrification of the tank waste to meet the Waste Isolation Pilot Plant waste acceptance criteria and shipping requirements. Another significant consumer of energy would be the HVAC systems.

The other utility demands, and the sources for these utilities, would be similar to those previously discussed for the Low-Temperature Drying Alternative. Water use is projected at 7 million gal over the life of the Vitrification Alternative.

4.9.5 Cementation Alternative

The Cementation Alternative would require 11,250 MW. The substantial portion (25 to 30%) of electrical energy demands for the Cementation Alternative is from the HVAC systems. Water usage would be approximately 15 million gal, which is still insignificant compared to the available water.

4.9.6 Treatment and Waste Storage at ORNL Alternative

Energy and water usage for this alternative depends primarily on the treatment alternative selected, which are discussed in the preceding sections. The utility requirements for waste storage are assumed to be similar to the requirements for the existing waste storage facilities (using 2,200 MW and 5 million gal of water over the institutional control period for waste storage).

4.9.7 Utility Impacts Summary

None of the alternatives, including the No Action Alternative, would require the use of any groundwater. The No Action Alternative would require a total of 2,200 MW of electricity, compared to 15,000 MW for the Low-Temperature Drying Alternative; 45,000 MW for the Vitrification Alternative; and 11,250 MW for the Cementation Alternative. Water use would continue at present levels under the No Action Alternative, totaling 5 million gal over the assumed 100 years of institutional control. The treatment alternatives would involve water use as part of waste treatment. The Low-Temperature Drying Alternative would require 5 million gal of water, the Vitrification Alternative would require 7 million gal, and the Cementation Alternative would require 15 million gal, compared to 5 million gal for the No Action Alternative. The Treatment and Waste Storage at ORNL Alternative would require an additional 5 million gal of water and 2,200 MW of electricity for interim storage of the treated wastes onsite (conservative approach assumes institutional control for 100 years).

4.10 HUMAN HEALTH IMPACTS

This section discusses the potential human health risks associated with routine operations of the proposed treatment facility for the four waste streams identified in the proposed action.

Since the proposed treatment facility would be located on 2 to 2.8 ha (5 to 7 acres) in the Melton Valley area of ORNL, the population of concern is found in four Tennessee counties including: Anderson, Roane, Knox, and Loudon, which serve as the reference area for human health impacts. The nearest resident is located approximately 3.2 to 4.8 km (2 to 3 miles) from the proposed facility. The nearest sensitive subpopulation, such as children, is located at the residences surrounding the ORR, and the nearest high-risk receptors (e.g., nursing homes, hospitals, schools, or day care centers) are found in the city of Oak Ridge (population of 27,310) located northeast of the ORR. The nearest large metropolitan area within 80 km (50 miles) of the facility is Knoxville, Tennessee, (population of 165,000). Approximately 880,000 people live within 80 km (50 miles) of the ORR (ORNL 1995a).

The dose limit established by DOE for members of the general public from all sources of radiation (except natural background and radiation received as a medical patient) is 100 mrem/year. DOE recommends that remedial actions be sufficient enough that the likely potential dose to the public is

less than 30 mrem from one year of exposure. However, since the facility is located at the ORR on Federal property, institutional control would prevent exposure to private residents for many years.

4.10.1 Methodology

The methods used to determine the potential impacts to human health are discussed below.

- Performed risk assessment using CAP-88, Version 2.0, which provided an estimate of the adverse effects to the offsite affected (public) population and MEIs (involved worker, non-involved worker, and public). Fifty radionuclides from the predicted total emissions of all four waste streams were modeled. CAP-88 can model a maximum of 36 radionuclides in a single run, so two model runs were performed for each of the MEI and population assessments; the first run included 36 radionuclides, the second run included 14 radionuclides, and the totals were summed.

- Determined radionuclide concentrations in air, rates of deposition on ground surfaces, concentrations in food, and intake rates from ingestion.

- Modeled exposure pathways including inhalation, ingestion, and immersion in an airborne plume.

- Estimated the plume dispersion using meteorological data described in Section 3.7. The following parameters and assumptions used in the CAP-88 model for alternatives involving waste treatment are stated below.

  — stack height = 27.43 m (90 ft),
  — stack diameter = 1.52 m (5 ft),
  — plume rise = 12.7 m/s (42 ft/s),
  — mixing height = 1000 m (3,281 ft),
  — 5E-04 fatal cancers per rem were assumed for the general public, and
  — 4E-04 fatal cancers per rem were assumed for workers.

- Involved worker exposures from stack releases are 100 m or greater from the stack and probably are conservative for this release; involved workers are generally inside or near the treatment facility. Involved workers would have administrative controls in place for protection from emissions inside the facility.

- Computed the total exposure due to the combination of radionuclides and chemicals using the Industrial Source Complex Model Code, Version 3 (ISCST3), an EPA model that determines the dispersion of airborne pollutants. This model predicts atmospheric concentrations from a continuous point source based on a unit emission rate of 1 gram per second (g/s), and was used to estimate the exposures to the combined concentrations of radionuclides (pCi/m^3), particulates, and volatile organics (mg/m^3) at various locations near the proposed facility. ISCST3 uses the average hourly meteorological data records to define the conditions for plume rise, transport, diffusion, and deposition. Concentrations are estimated for each block in a circular grid comprising 16 directional sectors (e.g., north, northeast, north-northeast, etc.) at 10 radial distances within 80 km (50 miles) of the facility. The calculated concentration at each location was multiplied by the estimated emission of each contaminant (EPA 1995).

- Determined the dose to the public from residual radioactive contamination using the DOE model RESRAD, Version 5.82, in order to comply with DOE Order 5400.5. Residual radioactivity after site D&D was estimated from anticipated air emissions that would occur during operations at the proposed facility. The following assumptions were made when RESRAD was used in this evaluation.

  — Excluded radionuclides with a short half-life, and unlikely to present a risk following D&D of the proposed treatment facility.
  — Excluded radionuclides already present in the environment, if their activity due to emissions from the treatment facility was determined less than the uncertainty of the measurement.

- Estimated the dose to a family living on the proposed facility site immediately following D&D activities using RESRAD. The following assumptions were used in this analysis.

  — Drinking water was obtained from an on-site well.
  — Ingested vegetables were grown onsite.
  — Raised cattle onsite to obtain their milk and meat supply.
  — Default values were used as a conservative bound.

- Calculated the hazard index (non-carcinogenic contaminants), which is an indicator of the total additive, non-cancer toxicity from exposure to mixtures of hazardous contaminants. The hazard index is calculated by summing the hazard quotients for each noncarcinogen. A hazard index less than or equal to 1.0 indicates the exposure is unlikely to produce adverse toxic effects. As the hazard index approaches 1.0, concern about the potential hazard increases. The hazard index does not provide a statistical probability that a particular mixture at a particular exposure level will cause a particular adverse effect; it is an indicator of the relative potential for causing harm (ORNL 1995b,c).

- Calculated the LCF (carcinogenic contaminants). Cancer resulting from risks below 1E-06 cannot be distinguished from the normal cancer rate in an exposed population (EPA 1991).

4.10.2 Exposure pathways

The primary exposure pathways from the proposed treatment facility are ingestion and inhalation of contaminants from stack emissions. Stack emissions would occur during the 7,200 hours that the treatment facility is operational. For all treatment alternatives, air released from the stack would pass through a series of two HEPA filters, with a removal efficiency of more than 99%. It is anticipated that the total radioactive material that would be released is 5.48E-03 curies. The majority of the radioactive emissions will be strontium-90, cesium-137, and europium-152. The anticipated maximum release rate for volatile organic compounds is 0.062 lb/hour. The anticipated maximum release rate for particulate matter is 0.086 lb/hour. Secondary exposure pathways include immersion in the plume and external exposure due to ground surface contamination.

The facility operations for the treatment alternatives do not involve any water or wastewater discharges directly to the environment. Surface storm water runoff would enter Melton Branch or White Oak Creek, which are monitored under the ORR Environmental Monitoring Plan. Facility operations would not affect the groundwater, and no known drinking water supplies exist within 0.8 km (0.5 miles) of the facility. Therefore, contaminated surface water or groundwater was not considered as a potential exposure pathway when estimating radiation doses using the CAP-88 computer program. Waterborne pathways were considered when estimating the dose to a hypothetical family living on the land immediately after the facility D&D activities using the RESRAD computer program.

However, under the No Action Alternative, releases from the SWSA 5 North trenches pose a threat. After loss of institutional control, this threat increases due to the eventual release of radioactive contamination from the bunkers and buildings in the SWSA 5 North area and the Melton Valley Storage Tanks. See Section 4.5.1.2 regarding impacts to surface water after loss of institutional control.

4.10.3 No Action Alternative

The exposure to workers performing monitoring and maintenance activities during the 100-year institutional control period would result in 2E-02 LCFs for the population of involved workers. The LCF to the involved worker was calculated by assuming that 5 workers each receive the 100-mrem annual administrative control limit every year for 100 years multiplied by 4E-04 LCF/rem. While the workers are likely to work part-time at these facilities, it is assumed they receive all their administrative control limit dose here. There would be minimal risk to non-involved workers and the public during the institutional control period. See also Section 4.5.1.2.

After loss of institutional control, there would be continued releases from the SWSA 5 North trenches and contaminant releases from the buildings and bunkers at SWSA 5 North in addition to failure of the Melton Valley Storage Tanks. Assuming that all untreated wastes in these areas eventually release contaminants into the environment, human populations could be adversely affected. These releases would contaminate surface water and groundwater that could serve as drinking water sources and would likely affect potential food supplies as well. Human health impacts to the population would likely be significant over the long term. See also Section 4.5.1.2.

4.10.4 Low-Temperature Drying Alternative

4.10.4.1 Population of concern

The on-site population would vary depending on the project phase. There would be an estimated peak of 97 full-time equivalents during construction of the proposed facility, and a minimum of 17 full-time equivalents at the end of D&D activities. During operations, the number of full-time equivalents would range from 50 to 88, but only a fraction of these would be directly involved in the processing action.

4.10.4.2 Risk assessment

Radiation Exposure from Air - Maximally Exposed Individual

The maximally exposed involved worker would be located 100 m (328 ft) southwest of the stack, and the effective dose equivalent was calculated to be 6.4E-02 mrem. Based on the duration of stack emissions provided by Foster Wheeler for this alternative, the total exposure time would be 7,200 hours. The non-involved worker was assumed to be an average of 200 m (656 ft) southwest of the stack, which resulted in an effective dose equivalent of 5.5E-02 mrem. The nearest resident is approximately 3.2 to 4.8 km (2 to 3 miles) from the facility (ORNL 1995a). The off-site public MEI is located 1,250 m (4,101 ft) southwest of the facility, and the effective dose equivalent is 2.2E-02 mrem. The annual dose each person receives from natural background radiation is about 300 mrem, and the NESHAPs limit is 10 mrem/year. The total probability of cancer fatalities to the maximally exposed worker (involved and non-involved) and the off-site public MEI is 3E-08, 2E-08, and 1E-08, respectively.

Radiation Exposure - Affected Population

Risk analysis was performed for radiation exposure for the population within 80 km (50 miles) of the facility. The collective dose to the affected population would be 1.2E-01 person-rem. The total LCFs risk is 6E-5 fatalities per year. The doses and associated risks from radionuclide exposure are summarized in Table 4-19.

Table 4-19. Dose and risk due to radionuclide emissions from the Low-Temperature Drying Alternative

Receptor	Effective dose equivalent	Cancer fatalities
Maximally exposed individual (involved worker)	6.4E-02 mrem	3E-08 (probability)
Maximally exposed individual (non-involved worker)	5.5E-02 mrem	2E-08 (probability)
Maximally exposed individual (off-site)	2.2E-02 mrem	1E-08 (probability)
Population	1.2E-01 person-rem	6E-05 (deaths/year)

Radiation Exposure - Facility Worker

In order to protect workers, the facility walls would be designed to maintain exposures per ALARA objectives. The two primary gamma emitters present in the waste are cobalt-60 (half-life of 5.27 years) and cesium-137 (half-life of 30.17 years). The wall thickness or shielding material would reduce the dose rate to 0.5 mrem/h in normally occupied radiological areas and to 0.25 mrem/h in normally occupied non-radiological areas. It is stated in 10 *CFR* 835 that radiological operations shall be controlled so that the annual total effective dose equivalent (TEDE) limit of 5 rem to radiological workers is not exceeded. The TEDE for any member of the public shall not exceed 100 mrem in a year. The ORR imposes an administrative control that limits doses to 20% of the DOE-allowable dose limit. Assuming a facility worker receives the maximum administrative control limit dose of 100 mrem in a year, the associated 70-year risk using an incidence rate of 4E-04 fatal cancers per rem is a 3E-03 probability of fatal cancer.

Total Exposure Due to Radionuclides and Chemicals from Air

The ISCST3 model, as described in Section 4.10.1, was used to analyze the combined concentrations of radionuclides, particulate matter, and organic emissions. Estimated concentrations are determined for each block in a circular grid comprising 16 directional sectors (e.g., north, northeast, north-northeast, etc.) at 10 radial distances within 80 km (50 miles) of the proposed facility. The calculated concentration at each location was multiplied by the estimated emission of each contaminant (EPA 1995). The total exposure time was assumed to be equivalent to the operational time of the facility, or 7,200 hours. Like CAP-88, ISCST3 also uses the Gaussian plume equation to determine the dispersion of pollutants and includes the same assumptions and limitations discussed in Section 3.10.2. Table 4-20 summarizes the endpoints (health effects) that were estimated for the anticipated airborne emissions from the facility.

Table 4-20. Summary of health effect endpoints

Type of contaminant	Endpoint
Noncarcinogen	Hazard index[a]
Chemical carcinogen	Cancer incidence[a]
Radionuclide	Cancer fatality[b]

[a]Estimated with ISCST3.
[b]Estimated with CAP-88.

The results from the ISCST3 modeling were used to determine the hazard index at various locations near the facility. In all cases, the hazard index was zero. The data and parameters used in the ISCST3 code are provided in Appendix E of "Required Information for the National Environmental Policy Act for the Treating of Transuranic/Alpha Low-Level Waste at ORNL" (Foster Wheeler 1999).

The lifetime risk of cancer was estimated, and the highest-risk occupied area was 1,500 m (4,921 ft) northeast of the facility with a cancer risk of 4E-11. Cancer incidence resulting from risks below 1E-06 cannot be distinguished from the normal cancer rate in an exposed population and is considered acceptable by EPA (EPA 1991).

Residual Contamination After D&D

The pathways modeled by RESRAD, Version 5.82 were inhalation, ingestion of milk, ingestion of meat, vegetation, aquatic animals, drinking water, and inadvertent soil ingestion. The highest total dose from all exposure pathways was estimated to be 2.28 mrem, approximately 5 years after D&D of the facility. The data and parameters used in the RESRAD code are provided in Appendix F of "Required Information for the National Environmental Policy Act for the Treating of Transuranic/Alpha Low-Level Waste at ORNL" (Foster Wheeler 1999).

4.10.5 Vitrification Alternative

Emissions of concern for the Vitrification Alternative include radionuclides, particulates, and volatile organics. Mitigation of potential emissions is discussed in Section 4.7.4. It is anticipated that the use of off-gas treatment systems would result in compliance with applicable air standards. CAP-88 was used to estimate the dose and risk from radionuclide emissions from the proposed facility using the same assumptions and parameters discussed in Section 4.10.1. The maximally exposed involved worker was assumed to be located 300 m (984 ft) southwest of the stack. The dose and risk to the MEIs and the surrounding population are shown in Table 4-21.

The average annual particulate and metal emissions using the Vitrification Alternative are significantly less than those from the Low-Temperature Drying Alternative. The impacts from non-radiological emissions would be negligible. The dose due to residual contamination after D&D is anticipated to be approximately equivalent to that for the Low-Temperature Drying Alternative since the total anticipated radionuclide emissions are approximately the same.

Table 4-21. Dose and risk due to radionuclide emissions from the Vitrification Alternative

Receptor	Effective dose equivalent	Cancer fatalities
Maximally exposed individual (involved worker)	2.2E-01 mrem	9E-08 (probability)
Maximally exposed individual (non-involved worker)	1.8E-01 mrem	7E-08 (probability)
Maximally exposed individual (offsite)	9.8E-02 mrem	5E-08 (probability)
Population	6.8E-01 person-rem	3E-09 (deaths/year)

4.10.6 Cementation Alternative

Emissions of concern for the Cementation Alternative include radionuclides, particulates, and volatile organics. Contaminant emissions and human health impacts would be expected to be similar to than the Low-Temperature Drying Alternative. CAP-88 was used to estimate the dose and risk from radionuclide emissions from the proposed facility using the same assumptions and parameters discussed in Section 4.10.1. The maximally exposed involved worker was assumed to be located 100 m (328 ft) southwest of the stack. The dose and risk to the MEIs and the surrounding population are shown in Table 4-22.

Table 4-22. Dose and risk due to radionuclide emissions from the Cementation Alternative

Receptor	Effective dose equivalent	Cancer fatalities
Maximally exposed individual (involved worker)	1.6E-02 mrem	6E-09 (probability)
Maximally exposed individual (non-involved worker)	1.3E-02 mrem	5E-09 (probability)
Maximally exposed individual (offsite)	5.1E-03 mrem	3E-09 (probability)
Population	2.8E-02 person-rem	1E-05 (deaths/year)

The average annual particulate and metal emissions using the Cementation Alternative are significantly less than those from the Low-Temperature Drying Alternative. The impacts from non-radiological emissions would be negligible. The dose due to residual contamination after D&D is anticipated to be approximately equivalent to that for the Low-Temperature Drying Alternative since the total anticipated radionuclide emissions are approximately the same.

4.10.7 Treatment and Waste Storage at ORNL Alternative

The impact to public health from this alternative would be dependent on the treatment alternative selected and would be equivalent to the impact for that alternative, as previously summarized in Tables 4-19, 4-21, and 4-22. Storage of the waste onsite at ORNL following treatment would not result in additional risk to the public or to non-involved workers during institutional control. There would be an additional risk to the involved worker population due to radiological exposure, since the stored waste would be inspected and routine surveillance and maintenance performed. Involved workers are currently performing maintenance and surveillance tasks and are currently in compliance with the

annual administrative control dose limit of 100 mrem/person/year. Similarly, it is anticipated that the administrative control limit will be met over the 100-year institutional control period for waste storage. Assuming the total number of involved workers over the 100-year period averages 5 per year, and the 100 mrem annual administrative control limit is maintained, the total dose to the involved worker population would be 50 person-rem, and the associated LCF would be 2E-02.

After loss of institutional control, waste constituents would eventually be released into the environment. Human health impacts are likely but risks are expected to be less than those associated with the No Action Alternative because wastes are treated and better contained.

4.10.8 Human Health Impacts Summary

There would be minimal risks to non-involved workers and the public for the No Action Alternative during the 100-year institutional control period. Involved workers would continue to receive the exposure they currently receive during surveillance and maintenance activities. Over the 100-year institutional control period for on-site waste storage, this would result in 2E-02 LCFs. However, after loss of institutional control, waste constituents from the Melton Valley Storage Tanks and the SWSA 5 North trenches, bunkers, and buildings would be released into the environment with potential adverse health consequences. Table 4-23 summarizes the probability of cancer fatalities for the treatment alternatives.

Table 4-23. Total probability of cancer fatality summary table for the treatment alternatives during institutional control[a]

Alternative	On-site maximally exposed worker	Non-involved maximally exposed worker	Off-site MEI (public)
No Action	NA	Negligible	Negligible
Low-Temperature Drying	3E-08	2E-08	1E-08
Vitrification	9E-08	7E-08	5E-08
Cementation	6E-09	5E-09	3E-09

[a]For the Treatment and Waste Storage at ORNL Alternative, risks would be dependent on the treatment method selected, although there would be no additional risk to non-involved workers or the public. Involved workers for both the No Action and Treatment and Waste Storage at ORNL Alternatives would have 2E-02 LCFs due to 100-year surveillance and maintenance activities.

MEI = maximally exposed individual.
NA = not applicable.

The collective dose to the population from the Low-Temperature Drying Alternative would be 0.12 person-rem and 6E-05 deaths/year. The collective dose to the population for the Vitrification Alternative would be 6.8E-01 person-rem and would result in 3E-04 deaths/year. The collective dose to the population from the Cementation Alternative would be 2.8E-02 person-rem and 1E-05 deaths/year. For the Treatment and Waste Storage at ORNL Alternative, there would be some additional exposure due to the storage of the treated wastes onsite at ORNL.

4.11 ACCIDENT IMPACTS

This section addresses potential accident scenarios caused by equipment failures, human errors, or natural phenomena, which could result in the release of radiation, radioactive or hazardous materials, and have adverse effects on environment and the health of workers and the public. Accident scenarios were evaluated for each of the alternatives. The types of accident scenarios evaluated include:

- A breach of the Melton Valley Storage Tanks resulting in waste released to the environment.
- A breach of the transfer line between the Melton Valley Storage Tanks and the proposed TRU Waste Treatment Facility resulting in waste releases to the environment.
- Failure of a waste slurry line inside the proposed TRU Waste Treatment Facility.
- Failure of a waste slurry line and HEPA filters inside the proposed TRU Waste Treatment Facility.
- Failure of contact-handled or remote-handled solid waste containers before, during, and after waste treatment.
- Accidents unique to each alternative.
- Industrial accidents occurring during operations of the TRU Waste Treatment Facility or storage.

The scenarios analyzed represent the range of potential hazards associated with each alternative. Seismic risk to the Melton Valley Storage Tanks is more important for the No Action Alternative than the other alternatives, due to the long-term storage (100 years institutional control) of the untreated waste in the tanks. The analysis assumes that all of the accidents would occur within the proposed TRU Waste Treatment Facility, with the exception of a breach of the Melton Valley Storage Tanks, a breach of the transfer line between the Melton Valley Storage Tanks and the proposed TRU Waste Treatment Facility, or waste containers stored before and after treatment.

4.11.1 Methodology

The estimated accident consequences were based on the inventories and material characteristics of the waste contained in the Melton Valley Storage Tanks and the solid TRU wastes stored on the ORNL site. Atmospheric and surface water transport characteristics were obtained from the *Safety Analysis Report for the Liquid Low-Level Waste Management Systems* (Bechtel Jacobs 1999). Methods used to evaluate the significance of the potential adverse effects from the described accidents are listed below.

- Estimated the frequencies of potential accidents occurring for each alternative.
  - — "anticipated" accidents have a frequency of greater than 1 in 100 per year (>1E-02 per year);
  - — "unlikely" accidents have a frequency ranging between 1 in 100 to 1 in 10,000 per year (1E-02 to 1E-04 per year); and
  - — "extremely unlikely" accidents have a frequency ranging between 1 in 10,000 to 1 in 1,000,000 per year (1E-04 to 1E-06 per year). These accidents were not considered credible as evaluation basis events, and were not evaluated.

- Quantified the estimated amount of any release to the environment (air or surface water) resulting from an accident.

- Quantified the radiological dose to an MEI at the ORR boundary, and the radiological does to the surrounding public populations due to the releases. There is no public MEI for the ingestion pathway.

- Evaluated the radiological effects of accidents on workers:

  — Quantified the ingestion doses to the MEI and worker population at ETTP (the only workers assumed to ingest the contaminated water released in an accident are those at ETTP with a downstream potable water intake).

  — Quantified the inhalation doses to maximally exposed, non-involved workers at 80 m (or more) from the release point. For elevated releases from the 27-m-high stack, the maximum ground level concentration and dose occur at the site boundary and are equal to those for the public MEI at the ORR boundary.

- Qualitatively evaluated the accident effects on involved facility workers:

  — Building design physically separates workers from the drying process area.

  — Leaks/fires in process areas are expected to be exhausted directly (via filters) and to not affect unprotected workers in other treatment building areas.

  — Administrative controls would be in place to protect workers.

  — Workers in process areas are expected to have appropriate breathing and other protective clothing and equipment. These workers are expected to evacuate the vicinity of an accident without significant consequence.

  — Workers outside the treatment building are considered non-involved unless they are performing specific tasks with appropriate protective equipment.

Based on these assumptions, the risk to involved workers is maintained acceptably low by the use of appropriate protective equipment and risk is not analyzed or discussed further.

- Determined the health consequences associated with the doses in terms of "Latent Cancer Fatalities" (LCF) for populations and probability of cancer fatalities for individuals that would result from the exposures and doses. Cancer fatality consequences to the affected populations were based on the fatal cancer incidence rates of 4E-04 LCF per person-rem in the worker populations and 5E-04 LCF per person-rem in the off-site public population as described in Chapter 3, Affected Environment. These risk factors also were applied to MEI and maximally exposed non-involved worker doses. The product of the dose and the fatal cancer incident rate is an estimate of the probability the exposed individual will experience a cancer fatality.

- Risk was measured as the average consequence that accounts for both the consequence and likelihood of an accident. For example, an accident with a low likelihood and high consequence can have the same risk as an accident with a high likelihood and low consequence. For the comparison of accidents affecting the No Action and treatment alternatives, the risk measure selected is total expected fatalities. This risk is computed as the product of the accident frequency, the time period in which the accident can occur, and the computed consequence. The risk is used to compare the expectation of fatalities for the no action and treatment alternatives on a consistent basis.

$$Risk = Total\ Expected\ Fatalities = \frac{Accidents}{Year} \times \frac{Years}{Alternative} \times \frac{Cancer\ fatalities}{Accident}$$

- The likelihood of industrial injuries, fatalities, and risks was estimated based upon the labor estimates discussed in Section 4.13, Socioeconomic Impacts.

The evaluation of each of the accidents scenarios follow. The consequences and likelihoods of process and storage accidents are based on those defined for the Melton Valley Storage Tanks in the *Safety Analysis Report for the Liquid Low-Level Waste Management Systems* (Bechtel Jacobs 1999). An accident scenario and associated assumptions are presented first, followed by the impacts for each alternative. A summary is provided at the end of each accident scenario to provide an easy comparison of the alternatives.

4.11.2 Accidental Breach of the Melton Valley Storage Tanks

An accidental breach of the Melton Valley Storage Tanks could result in the release of TRU sludge and its associated low-level liquid waste into the secondary containment of the Melton Valley Storage Tanks facility and potentially into the environment. The impacts associated with the alternatives were based on the assumption that the Melton Valley Storage Tanks and their secondary containment could withstand the evaluation basis earthquake (0.2g ground acceleration) (Bechtel Jacobs 1999) that occurs with a frequency of 1E-03 per year over a 10- to 20-year period. For facility operating periods of approximately 20 years or less, it is reasonable to assume that only evaluation basis-type accidents and natural phenomena and limited accident consequences would occur.

4.11.2.1 No Action Alternative

For the analysis of the No Action Alternative, it was assumed that the radioactive liquid wastes would be stored in the Melton Valley Storage Tanks without treatment for the 100 years of institutional control, and that a more severe, "Beyond Evaluation Basis" accident would occur. The No Action Alternative is assumed to begin after current Melton Valley Storage Tanks waste consolidation operations are terminated. Within this storage period, an earthquake with approximately double the intensity of the evaluation basis earthquake could occur with equal likelihood (i.e., 10 years × 1E-03 per year = 100 years × 1E-04 per year = 0.01). If a "Beyond Evaluation Basis" earthquake were to occur, there is a potential for the Melton Valley Storage Tanks and their secondary containment to fail causing the liquid wastes to be discharged via White Oak Creek to the Clinch River. The affected populations would include the workers at ETTP and the off-site population in Kingston, Tennessee, that use the Clinch River as a drinking water source.

A "Beyond Evaluation Basis Accident" resulting in liquid waste release from the Melton Valley Storage Tanks and a limited failure of the secondary containment was addressed in the *Safety Analysis Report for the Liquid Low-Level Waste Management Systems* (Bechtel Jacobs 1999). In this accident, the total volume of liquid released to the environment was assumed to be limited to 50,000 gal, and it was also assumed that the use of this water as a drinking water supply was not banned. The resulting consequence was estimated to range between 4 and 28 rem to a MEI at ETTP (assumed to drink 1 liter of this water), depending on the dilution flow rate in the Clinch River. For purposes of this analysis, the midpoint of 16 rem was assumed as the dose from ingestion at ETTP.

The human health consequences of an accidental release due to an earthquake were based on the airborne and waterborne pathways, doses, and a fatal cancer incidence rate (4E-04 LCF/person-rem for workers and 5E-04 LCF/person-rem for the public). The 16 rem accidental dose to the MEI at ETTP

due to a release from the Melton Valley Storage Tanks is a factor of 107,000 times higher than would occur due to expected releases from ORNL (0.15 mrem) (ORNL et al. 1997). By proportion, the corresponding affected population doses (assuming a limited ingestion of 1 L/person of contaminated water) are 31,000 person-rem (0.29 person-rem due to normal releases) to the ETTP population and 160,000 person-rem (1.5 person-rem due to normal releases) to the Kingston population (ORNL et al. 1997). The projected consequences are 12 LCFs in the ETTP worker population and 80 LCF in the Kingston population due to ingestion of contaminated drinking water (Table 4-24).

Airborne releases from ORNL occurring in 1997 resulted in a 0.38 mrem dose to the off-site MEI and a collective dose of 5.8 person-rem to the surrounding population of 879,546 within 80 km (50 miles). The corresponding affected population doses due to an accidental release from the Melton Valley Storage Tanks due to an earthquake under the No Action Alternative were obtained by proportion. The ratio of the "Beyond Evaluation Basis" earthquake site boundary MEI inhalation dose of 2.12 rem to the 1997 ORNL MEI site boundary dose is 5,600. Comparably, the affected population inhalation dose for the earthquake scenario is 5,600 times the 5.8 person-rem 1997 population dose, or 32,000 person-rem. The inhalation dose consequence to the surrounding population due to the earthquake is 16 LCF in addition to the ingestion consequence. The corresponding consequence to the 2.1 rem MEI dose is a 1.1E-03 probability of a cancer fatality.

Table 4-24. Frequencies and consequences of the No Action Alternative for Melton Valley Storage Tanks storage accidents

Accident	Accident frequency	MEI accident boundary doses[a] (rem)	Affected population dose per accident (person-rem)	Total LCF per accident
Beyond Evaluation Basis Earthquake	1E-04 per year	Ingestion - 16	Ingestion -	
			(ETTP) 31,000	12
			(Kingston) 160,000	80
		Inhalation - 2.1	Inhalation - 32,000	16
			Total	108

[a]Accident frequencies and maximally exposed individual (MEI) boundary doses based on Bechtel Jacobs 1999. Inhalation boundary doses are at the Oak Ridge Reservation boundary (public MEI), and the ingestion boundary doses are at East Tennessee Technology Park (non-involved worker).

LCF = latent cancer fatality.

The inhalation dose to a non-involved worker 80 m from the ground-level release point is computed based on the 2.1 rem ORR MEI boundary dose (Bechtel Jacobs 1999), and the ratio of the χ/Q values at 80 m and the ORR boundary (1,439 m). For F-stability conditions and a wind speed of 1 m/s, the ratio of the χ/Q values is 108 (Turner 1969). The resulting dose to the non-involved worker is 230 rem. The corresponding consequence is a 0.092 probability of a cancer fatality.

The associated risk computed for the "Beyond Evaluation Basis" earthquake accident is 1.1 expected fatalities based on the 108 LCF, the 1E-04/year frequency, and the 100-year institutional period of control. The risks to the MEI and non-involved worker are 1.1E-05 and 9.2E-04 expected fatalities, respectively.

A breach of the Melton Valley Storage Tanks from an earthquake resulting in a 50,000 gal release of radioactive waste would contaminate approximately 0.56 ha (1.37 acres) of land and 24,526 m^3 (32,083 yd^3) of soil. Complete calculations and assumptions are presented in Appendix F.3. Until an environmental cleanup could occur, and the waste and impacted soil be removed, the land use would be significantly altered from its present condition and would be unusable for other purposes. Aquatic biota in a 1-kilometer (0.6-mile) reach of Melton Branch and White Oak Creek would be killed by chemical

toxicity, perhaps by high pH, and possibly by acute external radiation exposure (Appendix F.2). Recolonization of this reach would take up to a year. Herons and other fish-eating biota could be harmed by acute external radiation exposure if they remain in close proximity to the released water. The contaminants would likely move quickly downstream to White Oak Creek, where radiation toxicity is also probable. Dilution of the non-radioactive contaminants in White Oak Lake would rapidly (in a few days) reduce the concentrations of contaminants below levels causing chemical toxicity, and the pH would probably change to non-toxic levels. However, chronic radiation doses to aquatic biota and fish-eating predators in White Oak Lake would remain above benchmarks for acceptable chronic radiation levels for a few days to a few weeks. The predominant exposures are to cesium-137 from Melton Valley Storage Tank W-26, or to cesium-137, cobalt-60, and strontium-90 from Melton Valley Storage Tank W-28. Dilution of contaminants by their release into the Clinch River would reduce radiation doses to aquatic biota and fish-eating predators to acceptable levels.

In this accident scenario for the No Action Alternative, with 189,250 L (50,000 gal) of liquid waste released to the environment, there is a potential impact to the soil and groundwater. (Appendix F.3 details the evaluation of the impacts of such a release). For evaluation purposes, it was assumed that liquid waste would leak from the secondary containment in a band as wide as 45.72 m (150 ft) across the lower front edge of the vault, in a zone parallel to slope down to the Melton Branch. Furthermore, it is assumed that the waste would initially leak through the unsaturated overburden impacting a volume of soil 45.72 × 22.86 × 3.96 m (150 × 75 × 13 ft) prior to reaching the groundwater surface. Once the waste reaches the water table/groundwater surface, it is further assumed that waste would mix with the shallow groundwater and ultimately discharge out to Melton Branch approximately 121.92 m (400 ft) away. Details of this conceptual model are depicted in Appendix F.3, Figure 1. Such a release could potentially impact 0.557 ha (1.3 acres) of area and 24,526 m^3 (866,160 ft^3) of soil.

The impacts to the groundwater from a breach of the Melton Valley Storage Tanks under the No Action Alternative included the assumption that Melton Valley Storage Tank W-28 would breach and spill its entire contents (approximately 189,250 L or 50,000 gal). The strontium-90 concentrations in this tank were reported to be 1.5 E+05 Becquerels/mL (Keeler 1996). This concentration in tank W-28 indicates that strontium-90 accounts for approximately 15% of the total radioactive material in that tank (as measured in Becquerels). Assuming that the concentrations reported are accurate for all the waste in tank W-28, approximately 766 curies of strontium-90 would be released to the environment from this accident scenario. If the mass of strontium-90 were evenly distributed across the potentially impacted area described above, the concentrations in the soil and groundwater would equate to 2.08E+07 pCi/kg and 1.04E+06 pCi/L, respectively. Based on assumed soil/water partitioning interactions, the maximum values that could be expected would be equal to 8.09E+10 pCi/kg in the soil and 4.05E+09 pCi/L in the groundwater. All calculations are detailed in Appendix F.3.

These resulting concentrations in the soil and groundwater would be significant if this accident scenario were to occur, since little to any previous impact for strontium-90 has been reported for the soil and groundwater near the proposed TRU Waste Treatment Facility and south of the Melton Branch. Furthermore, these concentrations reflect an apparent driver for remediation when compared to the 10^{-6} residential risk scenario values of 0.014 pCi/kg and 0.85 pCi/L for soil and water (RAIS, 1/11/2000). If remediation (soil removal and replacement) is assumed, then over 24,526 m^3 of contaminated soil would have to be removed and stored onsite. This would require approximately 2.4 ha (6 acres) of storage space based on the storage volumes presented in Table 2-4 for similar waste. In addition, the 100-year and 500-year floodplains and wetlands between the Old Melton Valley Road and Melton Branch would be adversely impacted by both the contaminant plume (Figure 1, Appendix F.3) and the earthmoving associated with remediation.

Following the 100-year institutional control period addressed above, loss of institutional control is assumed for analysis purposes. If an accident has not occurred by this time, the wastes are assumed to continue to remain in place. As a bounding accident health impact for the No Action Alternative, the hypothetical consequences and risks of releasing the contents of all Melton Valley Storage Tanks (1,514,000 L or 400,000 gal) over an indefinitely long period of time (e.g., 10,000 years) are computed.

After 100 years, most of the activity in the Melton Valley Storage Tanks (95% of the strontium-90 and cesium-137) will have decayed. However, the total activity in the larger waste volume released increases by a factor of 4.26 over the total activity in the previously assumed release of the highest activity, 189,250 L or 50,000 gal (based on current radionuclide distributions). Thus, over the 100- to 200-year period, the consequence of a large release, earthquake accident would decrease by a factor of approximately 4 to 26 LCF, and the risk over this period would decrease to 0.26 expected fatalities (combined ETTP and Kingston populations).

Over an indefinite time period, all of the waste in the tanks will be released (with a probability of 1.0 assuming no maintenance of the steel tanks and reinforced concrete containment). If the population distribution and surface water transport paths remain the same, the consequence of this release is an estimated 11 LCF, and the risk is 11 expected fatalities over the very large time period.

4.11.2.2 Low-Temperature Drying Alternative

Since the Low-Temperature Drying Alternative would be completed in less than 10 years, the probability of a "Beyond Evaluation Basis" earthquake occurring is small, and therefore was not evaluated.

4.11.2.3 Vitrification Alternative

Since the Vitrification Alternative would be completed in less than 10 years, the probability of a "Beyond Evaluation Basis" earthquake occurring is small, and therefore was not evaluated.

4.11.2.4 Cementation Alternative

Since the Cementation Alternative would be completed in less than 10 years, the probability of a "Beyond Evaluation Basis" earthquake occurring is small, and therefore was not evaluated.

4.11.2.5 Treatment and Waste Storage at ORNL Alternative

Since waste treatment under this alternative would be completed in less than 10 years, the probability of a " Beyond Evaluation Basis" earthquake occurring is small, and therefore was not evaluated.

4.11.3 Breach of the Transfer Line Between the Melton Valley Storage Tanks and the Proposed TRU Waste Treatment Facility

The frequency and consequences of a transfer line failure between the Melton Valley Storage Tanks and the proposed TRU Waste Treatment Facility are the same for all of the alternatives that include waste treatment. This type of accident has been evaluated in the *Safety Analysis Report for the Liquid Low-Level Waste Management Systems* (Bechtel Jacobs 1999); two accidents were evaluated:

Accident	MEI Inhalation dose	Ingestion dose[a]
Component failure during sludge transfer	2.1 rem	0
Tank overfill during sludge transfer	Approximately 0	6.1 rem

[a]Inhalation boundary doses are at the ORR boundary (public MEI) and the ingestion boundary doses are at East Tennessee Technology Park (non-involved workers).
MEI = maximally exposed individual

Due to Melton Valley Storage Tanks operational and design considerations, these two accidents do not result from a single cause. However, during waste transfer operations, both accidents could result from a complete line failure and direct release to the air and surface waters.

4.11.3.1 No Action Alternative

Since construction of a waste treatment facility would not be implemented for this alternative, this accident scenario was not analyzed.

4.11.3.2 Low-Temperature Drying Alternative

A breach of the transfer line between the Melton Valley Storage Tanks and the proposed waste treatment facility was estimated to occur in the "extremely unlikely" frequency range, 1E-04 to 1E-06 per year (Bechtel Jacobs 1999). Since sludge transfers to the proposed treatment facility are expected to be semi-continuous, the estimated frequency category is increased to the "unlikely" frequency range (1E-02 to 1E-04 per year).

To present a bounding analysis, the maximally exposed non-involved worker at ETTP is assumed to ingest surface waters and receive the bounding 6.1-rem dose. Based on the 6.1-rem boundary dose, the affected ETTP population ingestion dose is 12,000 person-rem and the corresponding consequence is 4.7 LCF. The public population at Kingston receives a dose of 61,000 person-rem with a consequence of 31 LCF.

The public MEI at the ORR boundary would be exposed to the airborne release and receive the bounding 2.1 rem dose. The inhalation dose to the public population within 50 miles, based on the ORR MEI boundary dose, is 32,000 person-rem. The corresponding consequence to this population is 16 LCF. The consequence of the 2.1 rem MEI dose is 1.1E-03 probability of a cancer fatality.

The ORR MEI (public) boundary inhalation dose for the transfer line failure is the same as that for the tank rupture accident, 2.1 rem. Therefore, the inhalation dose and consequence to the non-involved worker is also the same, 230 rem and 0.092 probability of a cancer fatality.

The estimated frequency for this accident is in the range of 1E-02 to 1E-04 per year for this accident; the midpoint frequency of 1E-03 per year was used to calculate the risk. The risk estimate is based on a total of 35 LCF due to ingestion in the ETTP and Kingston populations, and 16 LCF due to inhalation in the surrounding population within 50 miles. The total calculated risk is 0.16 expected fatalities. The risks to the public MEI and non-involved worker are 3.2E-06 and 2.8E-04 expected fatalities.

4.11.3.3 Vitrification Alternative

The frequency, consequences, and risks of a transfer line failure between the Melton Valley Storage Tanks and the proposed waste treatment facility are the same as those determined for the Low-Temperature Drying Alternative.

4.11.3.4 Cementation Alternative

The frequency and consequences of a transfer line failure between the Melton Valley Storage Tanks and the proposed waste treatment facility are the same as those determined for the Low-Temperature Drying Alternative. However, due to the increased period of the tank waste treatment under this alternative (6 years), the calculated risk is 0.31 expected fatalities in all affected populations. The risks to the public MEI and non-involved worker are 6.3E-06 and 5.5E-04 expected fatalities, respectively.

4.11.3.5 Treatment and Waste Storage at ORNL Alternative

The frequency and consequences of a transfer line failure between the Melton Valley Storage Tanks and the proposed waste treatment facility are the same as those determined for the Low-Temperature Drying Alternative. However, due to the variation of the tank processing period from 3 to 6 years, depending on the treatment method, the risk ranges from a total of 0.16 to 0.31 expected fatalities in all affected populations.

4.11.4 A Slurry Line Failure Within the TRU Waste Treatment Facility

The slurry line failure within the proposed TRU Waste Treatment Facility is similar to the transfer line failure between the Melton Valley Storage Tanks and the treatment facility, except this accident scenario assumes that major leaks would be confined within the proposed treatment facility and would be detected more rapidly (1 hour vs. 2 hours). This accident could potentially occur during any of the treatment alternatives. The HEPA filters are assumed to be degraded but still provide a factor of 100 reduction.

4.11.4.1 No Action Alternative

Since construction of a waste treatment facility would not be implemented for this alternative, this accident scenario was not analyzed.

4.11.4.2 Low-Temperature Drying Alternative

The slurry line failure accident within the proposed treatment facility is estimated to occur in the per year "unlikely" frequency range (1E-02 to 1E-04 per year).

Since the proposed facility would be designed as a "zero-release" facility, no direct release to surface waters would be possible. Any airborne releases would occur via HEPA filters and the 27-m (89-ft)-high stack. The shorter exposure reduces the dose by a factor of 2 and the elevated (versus ground level) release reduces the dose by a factor of 3 (χ/Q = 1.2E-04 s/m^3 vs. 3.7E-04 s/m^3) (Turner 1969). The resulting ORR boundary dose becomes 3.4E-03 rem.

$$\text{Dose} = 2.1\ \text{rem} \times \frac{1\ \text{h}}{2\ \text{h}} \times 0.01 \times \frac{1.2\text{E}-04}{3.7\text{E}-04} = 0.0034\ \text{rem}$$

Since the suspended radionuclides are released for the stack at an elevation of 27 m, the maximum ground-level dose occurs at the ORR boundary. Therefore, the maximum non-involved worker dose is equal to the public MEI dose at the ORR boundary. The corresponding consequences are 1.7E-06 and 1.4E-06 probabilities of a cancer fatality for the public MEI and non-involved worker, respectively.

The corresponding affected population inhalation dose resulting from this release is 52 person-rem to the surrounding population within 50 miles and a resulting consequence of 0.026 LCF. The corresponding risk, based on a 3-year risk period (corresponds to the tank waste treatment period), is 7.8E-05 expected fatalities. The risks to the MEI and non-involved worker are negligible.

4.11.4.3 Vitrification Alternative

The slurry line failure inside the proposed treatment facility would result in the same impacts as those calculated for the Low-Temperature Drying Alternative.

4.11.4.4 Cementation Alternative

The slurry line failure inside the proposed treatment facility would result in the same dose and consequence to the surrounding population within 50 miles as those calculated for the Low-Temperature Drying Alternative. The risk increases to 1.6E-04 expected fatalities due to the longer tank waste treatment period of six years. The risks to the public MEI and non-involved worker are negligible.

4.11.4.5 Treatment and Waste Storage at ORNL Alternative

The slurry line failure inside the proposed treatment facility would result in the same dose and consequence to the surrounding population within 50 miles as those calculated for the Low-Temperature Drying Alternative. The risk ranges from 7.8E-05 to 1.6E-04 expected fatalities depending on the tank waste treatment period for the selected treatment process. The risks to the MEI and non-involved worker are negligible.

4.11.5 Failure of the Slurry Line and the HEPA Filters in the Proposed TRU Waste Treatment Facility

This slurry line failure within the proposed TRU Waste Treatment Facility is similar to the slurry line failure discussed above, except this accident scenario assumes that the filters are in a failed state. It is assumed that the HEPA filters are damaged, or removed and not replaced, and a slurry line accident occurred in the building. The suspended hazardous particles in the air are assumed exhausted without filtration. This accident could potentially occur during any of the treatment alternatives.

4.11.5.1 No Action Alternative

Since construction of a waste treatment facility would not be implemented for this alternative, this accident scenario was not analyzed.

4.11.5.2 Low-Temperature Drying Alternative

Since the filter failure and the line failure are not coupled events, the estimated frequency of the combined events is estimated to be in the per year "extremely unlikely" (1E-04 to 1E-06) frequency range. A dose of 0.34 rem to a MEI at the ORR boundary would result if this accident occurred while the HEPA filters were in a failed state since the HEPA filters would not be able to provide the reduction factor of 100 assumed in the slurry line failure accident. Based on this ORR boundary dose, an inhalation dose of 5200 person-rem in the surrounding population within 50 miles in estimated. The corresponding consequence and risk in this population are 2.6 LCF and 7.8E-05 expected fatalities.

As with the slurry line failure with filtration, the maximum dose to the MEI and non-involved worker occurs at the ORR boundary and is equal to 0.34 rem. The corresponding consequences are 1.7E-04 and 1.4E-04 probabilities of a cancer fatality. The risks are the same as for the slurry line failure risks and are negligible for the public MEI and non-involved worker.

4.11.5.3 Vitrification Alternative

The slurry line failure and HEPA filters failure inside the proposed treatment facility would result in the same impacts as those calculated for the Low-Temperature Drying Alternative.

4.11.5.4 Cementation Alternative

The slurry line failure and HEPA filters failure inside the proposed treatment facility would result in the same dose and consequence to the surrounding population within 50 miles as those calculated for the Low-Temperature Drying Alternative. The risk increases to 1.6E-04 expected fatalities due to the longer tank waste treatment period of six years. The risks to the public MEI and non-involved worker would be negligible.

4.11.5.5 Treatment and Waste Storage at ORNL Alternative

The slurry line failure and HEPA filters failure inside the proposed treatment facility would result in the same dose and consequence to the surrounding population within 50 miles as those calculated for the Low-Temperature Drying Alternative. The corresponding risk ranges from 7.8E-05 to 1.6E-04 expected fatalities depending on the length of the tank waste treatment period. The risks to the public MEI and non-involved worker would be negligible.

4.11.6 Failure of Contact-Handled or Remote-Handled Solid Waste Containers Before, During, and After Waste Treatment

The failure of contact-handled or remote-handled solid waste containers before, during, and after waste treatment includes several accident scenarios. The contact-handled and remote-handled solids are stored within steel containers and casks in their current storage facilities. The risk of storage is expected to be small because the wastes are not in a dispersible form; they are confined within waste packages. Releases occurring as a result of postulated accidents would be confined within the storage buildings. However, bounding estimates of the frequency categories and consequences of accidents have been made. Three types of accidents were evaluated for the pre-treated wastes stored in the existing waste storage facilities. These include a vehicle impact (e.g. a forklift truck accident), earthquake, and a vehicle impact/fire. During waste treatment, the solid wastes would be sorted and repackaged. Three types of accidents were evaluated that could occur during solid waste treatment: vehicle impact, a vehicle impact/fire, and a processing fire with degraded filters. Following waste treatment, a vehicle impact/fire was evaluated for the alternatives. Pretreatment activities for contact-handled and remote-handled waste are identified for all action alternatives. Waste retrieval and on-site transportation risks are addressed in Section 4.8.

The following assumptions are made to estimate accident consequences:

- The contact-handled wastes have an average concentration of 8.1 Ci/m^3 equivalent plutonium-239, and the remote-handled wastes have an average concentration of 0.62 Ci/m^3equivalent plutonium-239. (An equivalent curie of plutonium-239 is the inhaled activity of the mixture of radionuclides that produces the same radiological dose as the inhaled dose of the mixture of other radionuclides.) These concentrations were calculated based on data in the *TRU Waste Baseline Inventory Report* (1997) (see Appendix B for data summary). However, in all consequence calculations involving these wastes, the bounding concentration of 8.1 Ci/m^3 is used.

- The total volume of contact-handled solid wastes to be processed is 1,000 m^3, and the total remote-handled solid waste volume is 550 m^3.

- For the vehicle impact and earthquake accidents, damage to the affected waste packages is expected, but the waste packages are not completely destroyed. Under these conditions, it is assumed that 10% of the radionuclides are released from the base waste materials as a powder, a fraction of 6E-04 of the powder is suspended as a respirable aerosol, and 10% of the aerosol is released from the waste package(s) (DOE 1994).

- In the event of a postulated local fire (e.g., a forklift accident and ignition of the fuel), 50% of the contents of the waste packages affected are assumed combustible. A bounding estimated fraction of 5E-04 of packaged combustible wastes becomes suspended as a respirable aerosol in a fire.

- None of the released radionuclides is held up in the storage buildings.

- The distance from each waste site to the ORR boundary is assumed to average 1,439 m (4,721 ft), the distance from the Melton Valley Storage Tanks to the ORR boundary (Bechtel Jacobs 1999). Using F-stability conditions and 1 m/s wind velocities, the computed χ/Q is 3.7E-04 s/m^3 (Turner 1969). The χ/Q at the non-involved worker, 80 m from the release, is 4E-02 s/m^3 as previously discussed.

- The inhalation dose to the surrounding population within 80 km (50 miles) is computed based on the airborne pathway model discussed in Section 3 (ORNL et al. 1997).

4.11.6.1 No Action Alternative

Since there would be no treatment under the No Action Alternative, only three accident scenarios are postulated to affect the remote-handled and contact-handled waste packages that would continue to be stored in the existing storage facilities. Due to the expected infrequent vehicle activity, significant vehicle accidents are estimated to occur in the 1E-02 to 1E-04 per year "unlikely" frequency range. The combination of a vehicle accident and a fire reduces the frequency by one category to 1E-04 to 1E-06 per year ("extremely unlikely" frequency range). The evaluation basis earthquake occurs in the 1E-02 to 1E-04 per year category.

A vehicle impact accident (without an assumed fire) is postulated to affect 1% of the contact-handled stored wastes (10 m^3 or four ST-90 boxes). An earthquake (without an assumed fire) is postulated to affect 10% of the stored wastes (155 m^3 or 57 ST-90 boxes). A vehicle impact and fuel ignition accident is postulated to affect the contents of one contact-handled ST-90 box (2.7 m^3 containing 50% combustible wastes). In the vehicle impact/fire accident, 1% of the wastes are also affected due to the mechanical impact. However, due to the noncombustible waste containers, the spread of fire to other containers is not considered likely.

The radiological dose to the public MEI standing on the ORR site boundary in the center of the plume is computed as the product of the respirable source term (Assumptions 1 to 5), a χ/Q of 3.7E-04 s/m^3 (Assumption 6), a breathing rate of 1.2 m^3/h or 3.3E-04 m^3/s (Bechtel Jacobs 1999), and an inhalation dose conversion factor of 5.1E+08 rem/Ci for plutonium-239 (DOE/EH-0071) (DOE 1998a). The estimated source terms and risks for each accident scenario are listed in Tables 4-25 and 4-26, respectively.

Table 4-25. Estimated source terms for the No Action Alternative contact-handled and remote-handled waste storage accidents

Accident	Volume of waste affected (m^3)	Total suspension fraction	Respirable aerosol source term (Ci plutonium-239)
Vehicle impact	10	6E-06	4.9E-04
Earthquake	155	6E-06	5.1E-03
Vehicle impact/fire			
Effect of impact	10	6E-06	4.9E-04
Effect of fire	1	5E-04	4.1E-03
Total source term			4.5E-03

Table 4-26. Estimated frequencies and consequences for the No Action Alternative contact-handled and remote-handled waste storage accidents

Accident	Public MEI site boundary dose (rem)	Population dose (person-rem/ accident)	Consequence (LCF/accident)	Frequency range	Risk to population (expected fatalities)[a]
Vehicle impact	0.031	470	0.24	1E-02 to 1E-04 per year	0.024
Earthquake	0.32	4,900	2.4	1E-02 to 1E-04 per year	0.24
Vehicle impact/ fire	0.28	4,300	2.1	1E-04 to 1E-06 per year	0.0021

[a]The risk computations are based on the midpoint frequency in the frequency range.

Consequences to the surrounding population within 80 km (50 miles) due to airborne releases are estimated as described for the Melton Valley Storage Tanks accidents, based on the pathway modeling and the incidence rate of 5E-04 LCF per person-rem described in Section 3. Consequences to the non-involved worker are based on an incidence rate of 4E-04 cancer fatalities per person rem (ORNL et al. 1997).

The doses to the non-involved worker 80 m from the release point are estimated based on the MEI ORR boundary doses in Table 4-26 and the ratio of the χ/Q values of 108. The non-involved worker doses for the vehicle impact, earthquake, and vehicle impact/fire are 3.3, 35, and 30 rem, respectively.

The risks to the public MEI are 1.6E-06, 1.6E-05, and 1.4E-07 expected fatalities for the three accidents. The corresponding risks to the non-involved worker are 1.4E-04, 1.4E-03, and 1.2E-05 expected fatalities. The risks are based on the midpoint of the annual frequency range over the 100-year period of institutional control.

4.11.6.2 Low-Temperature Drying Alternative

Table 4-27 presents the frequency, consequences, and risks of the various accident scenarios for the Low-Temperature Drying Alternative.

Table 4-27. Frequency and consequences of contact-handled and remote-handled solid waste treatment accidents for the Low-Temperature Drying Alternative

Accident	Frequency range	Public MEI site boundary dose (rem/ accident)	Inhalation population dose (person-rem/ accident)	Consequence (cancer fatalities/ accident)	Risk to population (expected fatalities)[a]
Bounding storage accidents before waste treatment					
Vehicle impact	1E-02 to 1E-04 per year	0.031	470	0.24	7.1 E-04
Earthquake	1E-02 to 1E-04 per year	0.32	4900	2.4	7.2E-03
Vehicle impact/fire	1E-04 to 1E-06 per year	0.28	4300	2.1	6.3E-05
Bounding accidents during waste treatment					
Vehicle impact	1E-02 to 1E-04 per year	<0.001	<15	<0.0075	2.3E-05
Vehicle impact/fire	1E-04 to 1E-06 per year	<0.001	<15	<0.0075	2.3E-05
Processing fire with degraded filters	1E-04 to 1E-06 per year	0.022	340	0.17	5.1E-06
Bounding accidents after waste treatment					
Vehicle impact/fire	1E-04 to 1E-06 per year	0.28	4300	2.1	6.3E-05

[a]The risk computations are based on the midpoint frequency in the frequency range and a treatment time of 3 years.

As shown, the population risks are a factor of 30 smaller than for the No Action Alternative due to much smaller time periods at risk (3 vs. 100 years). The risks to the MEI are 4.7E-08, 4.8E-07, and 4.2E-09 expected fatalities for the three accidents. The corresponding risks to the non-involved worker are 4.0E-06, 4.1E-05, and 3.6E-07 expected fatalities.

Once the solid waste packages are brought into the proposed treatment facility, the consequences of accidents are reduced due to HEPA filtration and elevated release point. Within the facility, the wastes are sorted, repackaged, and macroencapsulated; it is anticipated the waste packages will be placed in storage or shipped. The maximum release and suspension of radionuclides can result from accidents occurring while the wastes are being sorted in an unconfined state. Once the solid wastes are treated and encapsulated, the consequences of non-fire accidents are expected to be decreased by a factor at least 10 to 100 since the macroencapsulants effectively prevent suspension of respirable aerosols. For the vehicle impact/fire accident, a reduction in consequences is expected even with combustible macroencapsulants since the reduced waste surface area prevents self-sustained combustion. For conservatism, however, it is assumed that treated packaged wastes with combustible macroencapsulants have the same consequence as the untreated packaged wastes.

As a bounding case, it is assumed that after contact-handled wastes are removed from their waste package, a fire affecting 2.7 m^3 (95 ft^3) of waste (50% combustible) occurs. It is further assumed that the fire damages all HEPA filters, resulting in a combined efficiency of 99% (1% bypass). For unconfined contaminated cellulose and plastic wastes in a fire, 1% of the contaminants will be suspended. The inhalation dose to the public MEI at the ORR boundary is computed as:

Dose = 2.7 m^3 × 8.11 curies plutonium-239 equivalent /m^3 × 50% combustible × 0.01 × 0.01 × 1.2E-04 s/m^3 × 3.3E-04 m^3/s × 5.1E+08 rem/Ci = 0.022 rem

The corresponding affected population inhalation dose and consequence are 340 person-rem and 0.17 LCF. The likelihood of this accident depends on the probability that a relatively small fire can degrade multiple-series filters to a total estimated efficiency of 99% (from an initial efficiency of more than 99.9% for each filter stage). The frequency of the fire, given the lack of significant ignition sources, is estimated to be in the "unlikely" frequency range (1E-02 to 1E-04 per year). The probability of significant degradation of multiple-filter banks decreases this frequency to the "extremely unlikely" frequency range (1E-04 to 1E-06 per year) or lower.

Due to the elevated release point, the dose to the non-involved worker is the same as for the MEI at the ORR boundary, 0.022 rem. The risks to the MEI and non-involved worker are a factor of a thousand lower than the population risk and are considered negligible.

4.11.6.3 Vitrification Alternative

A drop or impact of the bare solidified glass matrix could result in a very small quantity of suspended respirable-sized particles (DOE 1994). With the metal casing enclosing the matrix, the quantity suspended is negligible. The solidified glass matrix is not combustible or susceptible to suspension due to an external fire. The consequences of this event are negligible. The contact-handled and remote-handled solid waste repackaging processes are comparable to the Low-Temperature Drying Alternative. The principal difference is the use of a noncombustible macroencapsulant (grout) for remote-handled and contact-handled solids in the Vitrification Alternative. This eliminates the small consequence of the vehicle/fire accident involving processed waste packages resulting in negligible consequence and risk after treatment.

4.11.6.4 Cementation Alternative

Similar to the Vitrification Alternative, the consequences of accidents affecting solid waste containers are considered negligible.

4.11.6.5 Treatment and Waste Storage at ORNL Alternative

Similar to the Low-Temperature Drying Alternative, the consequences of accidents affecting solid waste containers during treatment are considered negligible. It is assumed that combustible macroencapsulant is used, so the bounding accident dose to the public MEI at the ORR boundary is 0.28 rem for the vehicle impact/fire accident after waste treatment. This dose is based on the conservative assumption that the release in a fire involving a treated package is the same as the release from an untreated package. The corresponding inhalation dose and consequence to the surrounding population within 50 miles are 4,300 person-rem and 2.1 LCF. For a midpoint frequency of 1E-05 accidents per year, and an assumed risk period of 100 years (based on indefinite waste storage at ORNL), the risk is 2.1E-03 expected fatalities in the surrounding population within 50 miles. The risks to the public MEI and non-involved worker would be 1.4E-07 and 1.2E-05 probabilities of fatalities.

4.11.7 Accidents Unique to An Alternative

4.11.7.1 No Action Alternative

No unique accidents were identified for this alternative with the exception of the breach of the Melton Valley Storage Tanks, which was previously addressed in Section 4.11.2.1.

4.11.7.2 Low-Temperature Drying Alternative

No unique accidents were identified for this alternative.

4.11.7.3 Vitrification Alternative

Loss of Cooling Water to Quench Scrubber

In the event of a complete loss of cooling water, high-temperature melter off-gases (300 to 400°C) would be exhausted through the HEPA filters to the 27-m-high stack. Filter failure is assumed. The following source terms have been estimated to result from the melter off-gas release (the source terms were calculated based on mass balance estimates presented in Appendix B):

Radionuclides: 5.3 curies equivalent plutonium-239 processed over 3 years or
2.0E-04 curies equivalent plutonium-239/per hour

NO_X: 60,000 kg NO_2/3 years or
634 mg NO_2/s

Assuming a 1-hour release/exposure, χ/Q of 1.2E-04 s/m^3, a breathing rate of 3.33E-04 m^3/s (1.2 m^3/h), and a dose conversion factor of 5.1E+08 rem/Ci, the resulting dose to the public MEI at the ORR boundary is:

Dose = 2.0E-04 curies × 1.2E-04 s/m^3 × 3.3E-04 m^3/s × 5.1E+08 rem/Ci
= 0.0040 rem

The corresponding affected population inhalation dose in the surrounding population within 50 miles is 61 person-rem resulting in 0.031 LCF.

The peak nitrogen dioxide concentration (C) at the ORR site boundary is:

C = 700 mg NO_2/s × 1.2E-04 s/m^3
= 0.076 mg NO_2/m^3

This value is well below continuous exposure limits for NO_2 (1.9 mg/m^3 time-weighted average) and shorter duration exposure limits such as the Emergency Response Planning Guideline–Level 2 (ERPG-2) concentration of 29 mg/m^3.

Since both the radiological contaminants and the NO_2 are released via the 27-m-high stack, the maximum doses to the non-involved worker are the same as the public MEI dose at the ORR boundary.

This accident is estimated to occur in the 1E-02 to 1E-04 per year "unlikely" frequency range depending on the types of controls and interlocks incorporated into the design. Assuming the midpoint frequency of 1E-03 per year, a consequence of 0.031 probability of cancer fatalities, and a risk period of 3 years, the corresponding risk for this accident scenario is 9.3E-05 expected fatalities. The risks to the MEI and non-involved worker are negligible.

Failure of the Melter Exhaust

Failure of the building HEPA filters would not result in any direct release since the hazardous constituents are not suspended in the building air. However, the filters in the melter exhaust path actively filter particulates on a continuous basis. This accident is assumed to occur in the E-02 to

E-04 per year "unlikely" frequency range. The source term at the outlet of the mist eliminators defines the release for this accident:

Source Term = 0.62 curies equivalent plutonium-239/3 years (waste treatment period)
= 2.4E-05 curies equivalent plutonium-239 per hour.

For a 1-hour release, the estimated inhalation dose to the public MEI at the ORR boundary is:

Dose = 2.4E-05 curies × 1.2E-04 s/m^3 × 3.3E-04 m^3/s (respiration rate) × 5.1E+08 rem/Ci
= 4.9E-04 rem.

Since the radionuclides are released via the 27-m (88-ft)-high stack, the maximum dose to the non-involved worker is the same as the MEI dose at the ORR boundary.

The corresponding inhalation dose and consequence in the surrounding population within 50 miles are 7.5 person-rem, and the consequence is 3.8E-03 LCF. The accident is estimated to occur in the 1E-02 to 1E-04 per year "unlikely" frequency range. Based on the midpoint of the frequency range, 1E-03/year and a risk period of three years (based on the tank waste treatment period) the risk is 1.1E-05 expected fatalities. The risks to the public MEI and non-involved worker are negligible.

Release of Molten Waste Glass

Unspecified failures in the melter subsystem could result in a release of molten glass to the treatment facility. The direct hazard of the release is the potential to ignite local fires. This is considered a standard industrial hazard. It is assumed that materials in the vicinity of the melter are noncombustible and a general building fire will not result. In addition, it is assumed that wastes would continue to be fed to the melter and released into the building. It is not expected that significant amounts of NO_2 will be generated, or that the building HEPA filters will fail as a result of the accident. However, the presence of the molten glass and other hot surfaces is estimated to increase the fraction of radionuclides suspended by a factor of 10 over the "Slurry Line Failure within Treatment Facility" accident. The resulting dose to the public MEI at the ORR boundary is:

Dose = 0.003 rem × 10 = 0.03 rem.

Because the radionuclides are released via the 27-m (88-ft)-high stack, the maximum dose to the non-involved worker is the same as the public MEI dose at the ORR boundary.

The inhalation dose and consequence to the surrounding population within 50 miles are 460 person-rem and 0.23 LCF. This accident is estimated to occur in the 1E-04 to 1E-06 per year "extremely unlikely" frequency range. Using the midpoint of the frequency range1E-05/year, results in a risk to the surrounding population of 6.9E-06 expected fatalities. The risks to the MEI and non-involved worker are negligible.

4.11.7.4 Cementation Alternative

An accident involving catastrophic failure of the centrifuge is postulated. It is assumed that rotating elements within the centrifuge fail and have sufficient energy to penetrate the centrifuge casing. Due to the higher internal fluid pressures, a higher fraction of slurry is suspended as a respirable aerosol in the event of containment failure. A bounding respirable suspension fraction of 2E-03 is applied to this accident, a factor of 20 higher than the factor for low-pressure releases (DOE 1994),

resulting in a public MEI dose of 0.06 rem at the ORR boundary. The corresponding inhalation dose and consequence to the surrounding population within 50 miles are 920 person-rem, with a consequence of 0.46 LCF. The potential for catastrophic failure of the centrifuge is estimated to be one frequency category lower than for piping failures, or "extremely unlikely" frequency range (1E-04 to 1E-06 per year). Using the frequency midpoint of 1E-05/year and a 6-year risk period, the risk to the surrounding population is 2.8E-05 expected fatalities.

Since the radionuclides are released via the 27-m (88-ft)-high stack, the maximum dose to the non-involved worker is the same as the public MEI dose at the ORR boundary, 0.06 rem. The risks to the public MEI and non-involved worker are negligible.

4.11.7.5 Treatment and Waste Storage at ORNL Alternative

Unique accidents for this alternative are described in the previous sections, since this alternative would involve waste treatment by either low-temperature drying, vitrification, or cementation.

4.11.8 Industrial Accidents

The risks of industrial accidents in each treatment alternative are computed in terms of expected injuries and expected fatalities. These risks are computed directly from the estimated labor (person-hours) per labor category in each treatment alternative defined in Section 4.13, Socioeconomic Impacts, and DOE estimates of the injuries and fatalities per person-hour (DOE 1999).

4.11.8.1 No Action Alternative

The only expected activity occurring during the No Action Alternative is surveillance requiring approximately 2 full-time equivalents or 4,000 person-hours/year. The DOE injury rate for operations is 3.7/200,000 person-hours, and the fatality rate is 3.4E-03/200,000 person-hours (DOE 1999). Assuming institutional control for 100 years, the No Action Alternative results in industrial risks of 7.4 injuries and 6.8E-03 fatalities.

4.11.8.2 Low-Temperature Drying Alternative

The manpower plan for the Low-Temperature Drying Alternative is shown in Section 4.13, "Socioeconomic Impacts" (Table 4-32). The labor expended during the design phase is principally office work and is not counted toward the industrial accident totals. During construction, treatment, and D&D operations, it is assumed that 10% of the technical labor is spent in the field and counted toward the industrial accident totals.

The DOE injury rate for construction is 6.4/200,000 person-hours (versus 3.7/200,000 for operations). The construction fatality rate for this alternative is the same as operations, 3.4E-03/200,000 person-hours. The weighted total labor (including 10% of technical labor) over the 2-year construction phase and 4-year treatment and D&D phase is 470,000 person-hours. The expected industrial risks for the Low-Temperature Drying Alternative are 11 injuries and 8.0E-03 fatalities.

4.11.8.3 Vitrification Alternative

The manpower plan for the Vitrification Alternative is shown in Section 4.13, "Socioeconomic Impacts" (Table 4-35). The assumptions made to estimate the industrial accident risks have been described in Section 4.11.8.2 for the Low-Temperature Drying Alternative. The weighted total labor over the 2-year construction phase and 5-year processing and D&D phases is 1,400,000 person-hours,

approximately three times higher than the Low-Temperature Drying Alternative totals. The expected industrial risks for the Vitrification Alternative are 32 injuries and 0.024 fatalities.

4.11.8.4 Cementation Alternative

The manpower plan for the Cementation Alternative is shown in Section 4.13, "Socioeconomic Impacts" (Table 4-38). The assumptions made to estimate the industrial accident risks have been described in Section 4.11.8.2 for the Low-Temperature Drying Alternative. The weighted total labor over the 2-year construction phase and 8-year processing and D&D phases is 920,000 person-hours, approximately two times higher than the Low-Temperature Drying Alternative totals. The expected industrial risks for the Cementation Alternative are 20 injuries and 0.016 fatalities.

4.11.8.5 Treatment and Waste Storage at ORNL Alternative

The incremental labor required for surveillance and maintenance activities is approximately 4000 person-hours/year, the same as the No Action Alternative. Based on this labor rate, the incremental industrial accident risks for the Treatment and Waste Storage at ORNL Alternative are 0.074 injuries/year and 6.8E-05 fatalities/year. For calculation purposes, it was assumed that storage at ORNL would continue for 100 years resulting in 7.4 injuries and 6.8E-03 fatalities. Adding these incremental risks to the treatment risks of the selected treatment alternative yields the total industrial risks of this alternative. The total injuries range from 18 to 39 and the total fatalities range from 0.015 to 0.031. After loss of institutional control, the breach of the Melton Valley Storage Tanks by an earthquake accident is not applicable because the waste in the tanks would have been treated and put in interim storage.

4.11.9 Summary of Accident Analysis Results

The five alternatives to the proposed action have been analyzed to assess the risks to the public and ETTP populations, the public MEI at the ORR boundary, and the maximally exposed non-involved worker associated with the postulated accidents. The accident consequences and frequencies of each alternative are summarized in Table 4-28.

The risk in total expected fatalities to the surrounding public and ETTP populations has been calculated for each alternative and is summarized in Table 4-29. As shown, the overall risks for the treatment alternatives are comparable. The accident risks calculated for the No Action Alternative are higher than those calculated for the three action alternatives (Low-Temperature Drying, Vitrification, or Cementation). It should be noted that the risk of the No Action Alternative was estimated over 100 years. After loss of institutional control, the Melton Valley Storage Tanks and their secondary containment can be expected to fail, potentially resulting in 11 LCF.

Table 4-30 provides a summary of the maximum consequences and risks to the public MEI on the site boundary and the non-involved worker 80 m (262 ft) or more from the treatment facility and Melton Valley Storage Tanks. These consequences and risks result from inhalation; ingestion consequences are not defined for a public MEI at ETTP.

Table 4-28. Summary of accident consequences and frequencies for the alternatives[a]

Alternative/bounding accident	Accident frequency	Population dose[b] (person-rem)	Consequence (LCF/ accident)
No Action Alternative			
• Earthquake: Melton Valley Storage Tanks and confinement failure	1E-04 per year	ETTP - 31,000 Public - 192,000	108
• Earthquake (stored solid wastes)	1E-02 to 1E-04 per year	4,900	2.4
• Vehicle impact/fire	1E-04 to 1E-06 per year	4,300	2.1
Low-Temperature Drying, Vitrification, and Cementation Alternatives			
• Melton Valley Storage Tanks transfer line failure	1E-02 to 1E-04 per year	ETTP - 12,000 Public - 93,000	52
• Earthquake (stored solid wastes until processed)	1E-02 to 1E-04 per year	4,900	2.4
Treatment and Waste Storage at ORNL Alternative			
• Vehicle impact/fire (following Low-Temperature Drying Alternative only)	1E-04 to 1E-06 per year	4,300	2.1

[a]Accidents listed are those with a risk greater than 1E-03 expected fatalities.
[b]East Tennessee Technology Park ingestion dose and public ingestion dose combined.
LCF = latent cancer fatality.
ORNL = Oak Ridge National Laboratory.

The estimated cancer fatality consequences to individuals are computed as the product of the dose and the cancer fatality rates: 5E-04 cancer fatality /rem to the MEI and 4E-04 cancer fatality/rem to the non-involved worker. The risks are computed the same as the population risks: the product of the accident frequency, the operating period, and the cancer fatality consequence.

Table 4-31 provides a summary of the accident frequencies and consequences for the three treatment alternatives associated with waste treatment.

Table 4-29. Summary of total risks to the surrounding public and ETTP populations for the alternatives

Alternative/bounding accident[c]	Average accident frequency[a] (accidents/year)	Accident consequences (fatalities/accident)	Operating period (years)	Risk[c] (total expected fatalities)
No Action Alternative				
Breach of the Melton Valley Storage Tanks due to an earthquake	1E-04	108	100	1.1
Contact-handled and remote-handled solid waste container accidents				
Vehicle impact	1E-03	0.24	100	0.024
Earthquake	1E-03	2.4	100	0.24
Vehicle impact/fire	1E-05	2.1	100	0.0021
Industrial accidents	[b]	[b]	100	0.007
Low-Temperature Drying Alternative				
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	52	3	0.16
Contact-handled and remote-handled solid waste container accidents				
Earthquake - stored solid wastes prior to processing	1E-03	2.4	3	0.0072
Industrial accidents	[b]	[b]	6	0.008
Vitrification Alternative				
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	52	3	0.16
Contact-handled and remote-handled solid waste container accidents				
Earthquake stored solid wastes (prior to processing)	1E-03	2.4	3	0.0072
Industrial accidents	[b]	[b]	7	0.024
Cementation Alternative				
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	52	6	0.31
Contact-handled and remote-handled solid waste container accidents				
Earthquake - stored solid wastes (prior to processing)	1E-03	2.4	6	0.014
Industrial accidents	[b]	[b]	10	0.016
Treatment and Waste Storage at ORNL Alternative				
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	52	3-6	0.16 0.31
Contact-handled and remote-handled solid waste container accidents				
Earthquake - stored solid wastes (prior to processing)	1E-03	2.4	3-6	0.0072 0.014
Vehicle impact/fire-after processing	1E-05	2.1	100	0.0021
Industrial accidents	[b]	[b]	100	0.015 0.031

[a]Accident frequencies are midpoint values in the estimated ranges for process accidents
[b]Individual accident frequencies and fatalities/accident are not defined. The risk is computed as the product of the labor hours over the operating period and the expected fatalities per labor hour
[c]Accidents with risks <1E-03 expected fatalities are considered negligible and are not listed
ORNL = Oak Ridge National Laboratory

Table 4-30. Summary of risks for the public MEI and non-involved worker

Alternative/bounding accident[b]	Average accident frequency[a] (accidents/year)	Operating period (years)	Public MEI		Non-involved worker	
			Inhalation dose (rem)	Risk (probability of cancer fatality)	Inhalation dose (rem)	Risk (probability of cancer fatality)
No Action Alternative						
Breach of the Melton Valley Storage Tanks due to an earthquake	1E-04	100	2.1	1.1E-05	230	9.2E-04
Contact-handled and remote-handled solid waste container accidents						
Vehicle	1E-03	100	0.031	1.6E-06	3.3	1.4E-04
Earthquake	1E-03	100	0.32	1.6E-05	35	1.4E-03
Vehicle impact/fire	1E-05	100	0.28	1.4E-07	30	1.2E-05
Low-Temperature Drying Alternative						
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	3	2.1	3.2E-06	230	2.8E-04
Contact-handled and remote-handled solid waste container accidents						
Earthquake - stored solid wastes prior to processing	1E-03	3	0.32	4.8E-07	35	4.1E-05
Vitrification Alternative						
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	3	2.1	3.2E-06	230	2.8E-04
Contact-handled and remote-handled solid waste container accidents						
Earthquake - stored solid wastes (prior to processing)	1E-03	3	0.32	4.8E-07	35	4.1E-05
Cementation Alternative						
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	6	2.1	6.3E-06	230	5.5E-04
Contact-handled and remote-handled solid waste container accidents						
Earthquake - stored solid wastes (prior to processing)	1E-03	6	0.32	9.6E-07	35	8.3E-05
Treatment and Waste Storage at ORNL Alternative						
Transfer line failure between the Melton Valley Storage Tanks and Proposed treatment facility	1E-03	3-6	2.1	3.2E-06 to 6.3E-06	230	2.8E-04 to 5.5E-04
Contact-handled and remote-handled solid waste container accidents						
Earthquake - stored solid wastes (prior to processing)	1E-03	3-6	0.32	4.8E-07 to 9.6E-07	35	4.1E-05 to 8.3E-05
Vehicle impact/fire-after processing	1E-05	100	0.28	1.4E-07	30	1.2E-05

[a]Accident frequencies are median values in the estimated ranges for process accidents and average fatal accident frequencies (assuming an average number of person/years and 1 fatality/accident) for industrial accidents.

[b]Accidents with population risks <1E-03 expected fatalities are considered negligible and are not listed.

MEI = maximally exposed individual.

ORNL = Oak Ridge National Laboratory.

Table 4-31. Summary of the treatment alternatives accident frequencies and consequences

Accident	Accident frequency range	MEI site boundary dose (rem/ accident)	Population dose (person-rem/ accident)	Accident consequences (LCF/accident)
Low-Temperature Drying Alternative				
Melton Valley Storage Tanks transfer line failure	1E-02 to 1E-04 per year	6.1 - Ingestion 2.1 - Inhalation	ETTP - 12,000 Kingston - 61,000 32,000	4.7 31 16
Slurry line failure within process building	1E-02 to 1E-04 per year	0.003	46	0.023
Solid waste container failure	--	Negligible	Negligible	Negligible
Solid waste container impact/fire	--	Negligible	Negligible	Negligible
Building filtration failure: Building filters plus slurry line failure	1E-04 to 1E-06 per year	0.3	4600	2.3
Vitrification Alternative				
Melton Valley Storage Tanks transfer line failure	1E-02 to 1E-04 per year	6.1 - Ingestion 2.1 - Inhalation	ETTP - 12,000 Kingston - 61,000 32,000	4.7 31 16
Slurry line failure within process building	1E-02 to 1E-04 per year	0.003 rem	46	0.023
Loss of cooling water to quench scrubber	1E-02 to 1E-04 per year	0.004 rem 0.084 mg NO_2/m^3	61	0.031
Release of molten waste glass	1E-04 to 1E-06 per year	0.03 rem	460	0.23
Solid waste container impact	--	Negligible	Negligible	Negligible
Solid waste container impact/fire	--	Negligible	Negligible	Negligible
Building filtration failure: Off-gas flow path Building filters plus slurry line failure	1E-02 to 1E-04 per year 1E-04 to 1E-06 per year	5E-04 rem 0.3 rem	7.5 4,600	0.0038 2.3
Cementation Alternative				
Melton Valley Storage Tanks transfer line failure	1E-02 to 1E-04 per year	6.1 - Ingestion 2.1 - Inhalation	ETTP - 12,000 Kingston - 61,000 32,000	4.7 31 16
Slurry line failure within process building	1E-02 to 1E-04 per year	0.003 rem	46	0.023
Catastrophic release of slurry from centrifuge	1E-04 to 1E-06 per year	0.06 rem	920	0.46
Solid waste container impact	--	Negligible	Negligible	Negligible
Solid waste container impact/fire	--	Negligible	Negligible	Negligible
Building filtration failure: Building filters plus slurry line failure	1E-04 to 1E-06 per year	0.3	4600	2.3

MEI = maximally exposed individual.
LCF = latent cancer fatality.
ETTP = East Tennessee Technology Park.

4.12 NOISE IMPACTS

This section discusses noise impacts that would result from the implementation and the alternatives.

4.12.1 Methodology

Methods used to determine the noise impacts from each alternative are listed below.

- Determined construction-related noise using noise data collected from a noise survey of the site (Appendix C.4), assuming the noise levels would be comparable to those measured during construction of the Old Melton Valley Road.

- Determined operations-related noise levels.

4.12.2 No Action Alternative

The site would be expected to experience noise ranging from rural to light industrial (50 to 60 dBA Leq).

4.12.3 Low-Temperature Drying Alternative

Construction and operation of the proposed treatment facility, and traffic of construction workers and operations personnel would be comparable to currently noise levels (70 dB during construction, and 50 to 60 dB during operations) due to the road construction near the site. D&D would also result in construction-related noise level increases. However, all these noise impacts are temporary and relatively minor. Noise effects on wildlife would be negligible.

4.12.4 Vitrification Alternative

Noise impacts are expected to be up to 70 dB during construction and D&D activities, and 50 to 60 dB during operations. Noise associated with operations would last 3 years

4.12.5 Cementation Alternative

Noise impacts are expected to be up to 70 dB during construction, and 50 to .60 dB during operations. Noise associated with operations would last 6 years. The Cementation Alternative would result in more traffic noise for a longer period, which is associated with the larger volume of waste shipments off-site.

4.12.6 Treatment and Waste Storage at ORNL Alternative

Noise impacts are expected to be similar to the various treatment alternatives during construction and operations. There would be no off-site transportation-related noise. However, continued storage of the waste on-site would require transportation of the treated wastes within the ORNL boundaries.

4.12.7 Noise Impacts Summary

Noise levels for the No Action Alternative should range from rural to light industrial (50 to 60 daily dBA Leq). For the treatment alternatives, noise levels would be very similar to the noise levels experienced during construction of the Old Melton Valley Road, or 50 to 70 daily dBA Leq. For the

Treatment and Waste Storage at ORNL Alternative, construction noise would be 50 to 70 dBA, with noise in the 50 to 60 dBA range during long-term storage at ORNL.

4.13 SOCIOECONOMIC IMPACTS

Socioeconomic impacts resulting from the implementation of the alternatives are discussed in this section. The socioeconomic impacts analyses assumes that all impacts would occur within the four-county region of influence, which includes Roane, Anderson, Knox, and Loudon counties. This assumption was used to identify the maximum potential socioeconomic impact. The employment and earnings impacts were based on an input-output analysis using the Bureau of Economic Analysis Regional Input-Output Modeling System (RIMS II) (Bureau of Economic Analysis 1999). The RIMS II analysis identifies the indirect employment and earnings effects that result from changes in economic activity through purchases made in the local economy by both the facility and the facility's employees and their dependents (wage and salary expenditures). A more detailed discussion of RIMS II is included in Appendix D. In general, no significant employment or earnings impacts were identified for any of the alternatives; the impacts represented less than 1% of baseline economic activity for all of the alternatives. As a result, fiscal impacts are also assumed to be negligible for all alternatives.

The socioeconomic impacts analyses also assumed that employees for any new facility would come from within the region of influence. Therefore, no significant change in population is anticipated, and no impact on housing, schools, or other infrastructure within the region is expected. Utility usage (electricity and water) is discussed in Section 4.9.

4.13.1 Methodology

Methods used to determine socioeconomic impacts for each alternative are listed below.

- Determined the direct employment based on the manpower plan for the alternative.
- Obtained industry-specific RIMS II multipliers from the Bureau of Economic Analysis for the four-county Region of Influence.
- Determined indirect employment impacts by applying RIMS II input-output multipliers to the direct employment.
- Estimated the direct earnings based on direct employment for each phase of the treatment alternative, and average DOE-related wage in the Region of Influence for the design and operations periods and Tennessee average wage for heavy construction during the construction and D&D periods.
- Determined indirect earnings impacts by applying the RIMS II earning multipliers to direct earnings, and
- Computed the percentage change in employment and earnings impacts with respect to the No Action Alternative.

4.13.2 No Action Alternative

Under the No Action Alternative, there would be no change in economic activity and, therefore, no change in population, housing, infrastructure, or economic environment.

4.13.3 Low-Temperature Drying Alternative

The employment and earnings impacts for the Low-Temperature Drying Alternative for the years 2000 to 2010 are discussed below.

4.13.3.1 Employment

Table 4-32 shows the estimated direct employment associated with the Low-Temperature Drying Alternative. Table 4-33 estimates the total employment impact and compares it to an employment baseline calculated for each year from 2000 to 2010. This alternative would have no significant impact on region of influence employment. Estimated impacts in each year total less than 0.1% of baseline wage and salary employment for the duration of the proposed action. No employment effects would carry over beyond project completion in 2006.

Table 4-32. Manpower plan for the Low-Temperature Drying Alternative[a]

	Design											Construction								Operations												D&D		
	1998			1999				2000				2001				2002				2003				2004				2005				2006		
	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3
Technical	27	35	38	38	38	35	35	35	32	27	27	18	18	18	21	24	23	19	12	12	13	12	13	12	13	13	13	13	13	13	13	13	13	9
Craft/Operators	0	0	0	0	0	0	0	0	0	0	0	4	6	6	14	62	61	56	24	47	63	27	27	63	36	36	36	47	20	8	5	5	0	0
Non-Tech	3	3	3	3	3	3	3	3	3	3	3	11	11	11	11	11	11	17	11	11	12	11	11	12	11	11	11	11	11	11	11	11	8	8
Total	30	38	41	41	41	38	38	38	35	30	30	33	35	35	46	97	95	92	47	70	88	50	51	87	60	60	60	71	44	32	29	29	21	17

[a]Full-time equivalents.

Table 4-33. Estimated region of influence employment impacts by year for the Low-Temperature Drying Alternative

Year	Employment base[a]	Direct employment impact[b]	Indirect employment impact
2000	280,357	33.25	30.9
2001	281,704	37.3	38.0
2002	283,057	82.8	84.4
2003	284,416	64.8	100.3
2004	285,782	66.8	103.4
2005	287,154	44.3	35.2
2006	288,533	16.8	13.4
2007	289,919	0.0	0.0
2008	291,312	0.0	0.0
2009	292,711	0.0	0.0
2010	294,116	0.0	0.0

[a]Based on Tables 3-21 and 3-27. Assumes wage and salary employment grows at the same rate as population and that growth rate is constant from 1996–2000 and 2000–2010.
[b]Annual average full-time equivalents based on quarterly totals in Table 4-32.

4.13.3.2 Earnings

Direct earnings for the Low-Temperature Drying Alternative were based on the direct employment estimates presented in Table 4-32. Table 4-34 shows the estimated direct and indirect earnings associated with the employment figures in Section 4.13.2.1 and compares them with the region-of-influence baseline income for each year. The income calculation uses the conservative assumption that real per capita income remains at the 1996 level in order to determine the maximum potential impact. Any increase in real per capita income during the analysis period would reduce the relative economic impact. As the table shows, there would be no significant impact associated with this alternative. Earnings for all years represent less than 0.1% of income for the region.

Table 4-34. Estimated region of influence earnings impacts by year for the Low-Temperature Drying Alternative

Year	Direct earnings[a] ($000)	Indirect earnings ($000)	Total earnings ($000)	ROI baseline income[b] ($000)	Percent of ROI income
2000	$1,578	$986	$2,563	$11,775,954	0.02%
2001	$1,149	$1,130	$2,279	$11,832,509	0.02%
2002	$2,552	$2,510	$5,062	$11,889,336	0.04%
2003	$3,072	$3,306	$6,378	$11,946,436	0.05%
2004	$3,167	$3,408	$6,575	$12,003,810	0.05%
2005	$1,365	$985	$2,349	$12,061,459	0.02%
2006	$517	$508	$1,025	$12,119,386	0.01%
2007	$0	$0	$0	$12,177,590	0.00%
2008	$0	$0	$0	$12,236,074	0.00%
2009	$0	$0	$0	$12,294,839	0.00%
2010	$0	$0	$0	$12,353,887	0.00%

[a]Based on Table 4-33 and the following assumptions: average U.S. Department of Energy-related wage ($47,445) for Phases I and III; Tennessee average wage for heavy construction ($30,839) for Phases II and IV.
[b]Assumes constant population growth rate from 2000 to 2010 and average per capita income for the region of influence (ROI) in 1996 ($22,982).

4.13.4 Vitrification Alternative

The employment and earnings impacts for Vitrification for the years 2000 to 2010 are discussed below.

4.13.4.1 Employment

Expected direct employment is shown for the Vitrification Alternative in full-time equivalents for each quarter in Table 4-35. Table 4-36 shows the total estimated employment impact and compares it to an employment baseline calculated for each year from 2000 to 2010. This alternative would have no significant impact on region of influence employment. Estimated impacts in each year total less than 0.1% of baseline wage and salary employment for the duration of the alternative. No employment effects would carry over beyond completion of the alternative in 2007.

4.13.4.2 Earnings

Direct earnings for this alternative were based on the direct employment estimates in Table 4-35. Table 4-37 shows the estimated direct and indirect earnings associated with the employment figures in Section 4.13.3.1 and compares them with region-of-influence baseline income for each year. The income calculation uses the conservative assumption that real per capita income remains at the 1996 level in order to determine the maximum potential impact. Any increase in real per capita income during the analysis period would reduce the relative economic impact. As the table shows, there would be no significant impact associated with this alternative. Earnings for all years represent less than 0.2% of income for the region.

4.13.5 Cementation Alternative

The project schedule for the Cementation Alternative is the longest, generating the largest cumulative impact of the alternatives discussed. The employment and earnings impacts for the Cementation Alternative for the years 2000 to 2010 are discussed below.

4.13.5.1 Employment

Table 4-38 shows the estimated direct employment associated with the Cementation Alternative. Table 4-39 estimates the total employment impact and compares it to an employment baseline calculated for each year from 2000 to 2010. This alternative would have no significant impact on region of influence employment. Estimated impacts in each year total less than 0.1% of baseline wage and salary employment for the duration of the alternative. No employment effects would carry over beyond project completion in 2010.

Table 4-35. Manpower plan for the Vitrification Alternative[a]

	Design										Construction								Operations												D&D							
	1998		1999				2000				2001				2002				2003				2004				2005				2006				2007			
	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Technical	52	65	71	71	71	65	65	58	58	52	39	48	58	58	58	48	39	33	49	49	36	36	24	24	22	22	22	22	22	22	22	22	20	20	19	19	17	17
Craft/Operators	0	0	0	0	0	0	0	0	0	0	16	32	96	192	192	192	102	76	103	103	97	97	92	92	92	92	82	82	77	66	50	62	62	50	50	37	37	25
Non-Tech	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	17	17	14	14	14	14	14	14	14	14	17	17	14	14	14	14	14	14	9	9
Total	59	72	78	78	78	72	72	65	65	59	62	87	161	257	257	247	148	116	169	169	147	147	130	130	128	128	118	118	116	105	86	98	96	84	83	70	63	51

[a]Full-time equivalents.

Table 4-36. Estimated region of influence employment impacts by year for the Vitrification Alternative

Year	Employment base[a]	Direct employment impact[b]	Indirect employment impact	Total employment impact	Percent of employment base
1996	286,295				
2000	280,357	62.5	58.2	120.7	0.04
2001	281,704	141.8	144.5	286.2	0.10
2002	283,057	192.0	195.7	387.7	0.14
2003	284,416	158.0	244.7	402.7	0.14
2004	285,782	129.0	199.8	328.8	0.12
2005	287,154	114.3	177.0	291.2	0.10
2006	288,533	91.0	72.3	163.3	0.06
2007	289,919	66.8	53.0	119.8	0.04
2008	291,312				
2009	292,711				
2010	294,116				

[a]Based on Tables 3-21 and 3-27. Assumes wage and salary employment grows at the same rate as population and that growth rate is constant from 1996–2000 and 2000–2010.

[b]Annual average full-time equivalents based on quarterly totals in Table 4-35.

Table 4-37. Estimated region of influence earnings impacts by year for the Vitrification Alternative

Year	Direct earnings[a] ($000)	Indirect earnings ($000)	Total earnings ($000)	ROI baseline income[b] ($000)	Percent of ROI income
2000	$2,966	$1,853	$4,820	$11,775,954	0.04
2001	$4,371	$4,300	$8,672	$11,832,509	0.07
2002	$5,921	$5,825	$11,746	$11,889,336	0.10
2003	$7,496	$8,066	$15,562	$11,946,463	0.13
2004	$6,120	$6,586	$12,706	$12,003,810	0.11
2005	$5,421	$5,833	$11,253	$12,061,459	0.09
2006	$2,806	$2,761	$5,567	$12,119,386	0.05
2007	$2,050	$2,025	$4,083	$12,177,590	0.03
2008	$0	$0	$0	$12,236,074	0.00
2009	$0	$0	$0	$12,294,839	0.00
2010	$0	$0	$0	$12,353,887	0.00

[a]Based on Table 4-36 and the following assumptions: (1) average U.S. Department of Energy-related wage ($47,445) for Phases I and III; and (2) Tennessee average wage for heavy construction ($30,839) for Phases II and IV.

[b]Assumes constant population growth rate from 2000 to 2010 and average per capita income for the region of influence (ROI) in 1996 ($22,982).

Table 4-38. Manpower plan for the Cementation Alternative[a]

	Design										Construction								Operations																			
	1998		1999				2000				2001				2002				2003				2004				2005				2006				2007				2008			
	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Technical	30	37	41	41	41	41	41	37	37	30	20	22	25	25	22	22	20	17	25	25	18	18	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12
Craft/Operators	0	0	0	0	0	0	0	0	0	0	8	16	24	48	64	64	54	44	39	39	39	39	39	39	39	58	38	38	38	38	38	38	38	57	38	38	38	38	38	38	26	26
Non-Tech	5	5	5	5	5	5	5	5	5	5	12	12	12	12	12	12	12	12	12	12	12	12	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	12	12
Total	35	42	46	46	46	46	46	42	42	35	40	50	61	85	98	98	86	73	76	76	69	69	61	61	61	80	60	60	60	60	60	60	60	79	60	60	60	60	60	60	50	50

	D&D							
	2009				2010			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Technical	12	12	9	9	7	7	7	5
Craft/Operators	40	36	27	13	9	4	0	0
Non-Tech	12	12	9	9	7	7	7	5
Total	64	60	45	31	23	18	14	10

[a]Full-time equivalents.

Table 4-39. Estimated region of influence employment impacts by year for the Cementation Alternative

Year	Employment base[a]	Direct employment impact[b]	Indirect employment impact	Total employment impact	Percent of employment base
1996	286.295				
2000	280.357	41.3	38.4	79.6	0.03%
2001	281,704	59.0	60.1	119.1	0.04%
2002	283.057	88.8	90.5	179.2	0.06%
2003	284,416	72.5	112.3	184.8	0.06%
2004	285,782	65.8	101.8	167.6	0.06%
2005	287,154	60.0	92.9	152.9	0.05%
2006	288,533	64.8	100.3	165.0	0.06%
2007	289,919	60.0	92.9	152.9	0.05%
2008	291,312	55.0	85.2	140.2	0.05%
2009	292,711	50.0	39.7	89.7	0.03%
2010	294.116	16.3	12.9	29.2	0.01%

[a]Based on Tables 3-21 and 3-27. Assumes wage and salary employment grows at the same rate as population and that growth rate is constant from 1996–2000 and 2000–2010.

[b]Annual average full-time equivalents based on quarterly totals in Table 4-38.

4.13.5.2 Earnings

Direct earnings for the Cementation Alternative were based on the direct employment estimates presented in Table 4-38. Table 4-40 shows the estimated direct and indirect earnings associated with the employment figures in Section 4.13.5.1 and compares them with baseline income for each year. The income calculation uses the conservative assumption that real per capita income remains at the 1996 level in order to determine the maximum potential impact. Any increase in real per capita income during the analysis period would reduce the relative economic impact. As the table shows, there would be no significant impact associated with this alternative. Earnings for all years represent less than 0.1% of income for the region.

Table 4-40. Estimated region of influence earnings impacts by year for the Cementation Alternative

Year	Direct earnings[a] ($000)	Indirect earnings ($000)	Total earnings ($000)	ROI baseline income[b] ($000)	Percent of ROI income
2000	$1.957	$1.223	$3.180	$11.775.954	0.03
2001	$1,820	$1,790	$3,609	$11,832,509	0.03
2002	$2.737	$2,692	$5,429	$11,889,336	0.05
2003	$3.440	$3.701	$7.141	$11.946.463	0.06
2004	$3,120	$3,357	$6,476	$12,003,810	0.05
2005	$2,847	$3,063	$5,910	$12,061,459	0.05
2006	$3,072	$3,306	$6,378	$12,119,386	0.05
2007	$2,847	$3,063	$5,910	$12.177,590	0.05
2008	$2,609	$2,808	$5,417	$12,236,074	0.04
2009	$1,542	$1,517	$3,059	$12,294,839	0.02
2010	$501	$493	$994	$12.353.887	0.01

[a]Based on Table 4-39 and the following assumptions: (1) average U.S. Department of Energy-related wage ($47,445) for Phases I and III; and (2) Tennessee average wage for heavy construction ($30,839) for Phases II and IV.

[b]Assumes constant population growth rate from 2000 to 2010 and average per capita income for the region of influence (ROI) in 1996 ($22.982)

4.13.6 Treatment and Waste Storage at ORNL Alternative

4.13.6.1 Employment

This alternative would have no significant impact on the region-of-influence employment, which includes Anderson, Roane, Knox, and Loudon counties. Table 4-41 provides the estimated employment impact and compares it to an employment baseline calculated for each year from 2000 to 2010. Table 4-41 provides the estimated direct employment data associated with the Treatment and Waste Storage at ORNL Alternative. The estimated impacts in each year total less than 0.1% of baseline wage and salary employment for the duration of this alternative. This alternative would require continued monitoring activities of the treated waste following the D&D of the proposed treatment facility. The current monitoring requirements associated with the TRU waste slated for treatment at the proposed facility is estimated at 1 to 2 full-time equivalents. It is assumed that the post-treatment monitoring for the waste, which would continue to be stored onsite at ORNL, would have similar monitoring requirements, resulting in no net change in employment following D&D of the proposed treatment facility.

4.13.6.2 Earnings

There would be no significant impact with respect to earnings associated with the Treatment and Waste Storage at ORNL Alternative. The earnings for all years represent less than 0.1% of income for the four county region of influence. The direct earnings for this alternative were based on the estimated direct employment data presented in Table 4-42. Table 4-43 provides information on the estimated direct and indirect earnings associated with the employment figures provided in Table 4-41, and compares them with baseline income for each year. The income calculation uses the conservative assumption that real per capita income remains at the 1996 level in order to determine the maximum potential impact. Any increase in real per capita income during the analysis period would reduce the relative economic impact.

Table 4-41. Estimated employment impacts by year for the Treatment and Waste Storage at ORNL Alternative for the region-of-influence

Year	Employment base[a]	Direct employment impact[b]	Indirect employment impact	Total employment impact	Percent of employment base
2000	280,357	33.25	30.9	64.2	0.02
2001	281,704	37.3	38.0	75.2	0.03
2002	283,057	82.8	84.4	167.1	0.06
2003	284,416	64.8	100.3	165.0	0.06
2004	285,782	66.8	103.4	170.1	0.06
2005	287,154	44.3	35.2	79.4	0.03
2006	288,533	16.8	13.4	30.1	0.01
2007	289,919	0.0	0.0	0.0	0.00
2008	291,312	0.0	0.0	0.0	0.00
2009	292,711	0.0	0.0	0.0	0.00
2010	294,116	0.0	0.0	0.0	0.00

[a]Based on Tables 3-21 and 3-27. Assumes wage and salary employment grows at the same rate as population and that growth rate is constant from 1996–2000 and 2000–2010.

[b]Annual average full-time equivalents based on quarterly totals in Table 4-42.

Table 4-42. Manpower plan for the Treatment and Waste Storage at ORNL Alternative[a]

	Design											Construction								Operations								D&D							
	1998			1999				2000				2001				2002				2003				2004				2005				2006			
	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	
Technical	27	35	38	38	38	35	35	35	32	27	27	18	18	18	21	24	23	19	12	12	13	12	13	12	13	13	13	13	13	13	13	13	13	13	9
Craft/Operators	0	0	0	0	0	0	0	0	0	0	0	4	6	6	14	62	61	56	24	47	63	27	27	63	36	36	36	47	20	8	5	5	0	0	
Non-Tech	3	3	3	3	3	3	3	3	3	3	3	11	11	11	11	11	11	17	11	11	12	11	11	12	11	11	11	11	11	11	11	11	8	8	
Total	30	38	41	41	41	38	38	38	35	30	30	33	35	35	46	97	95	92	47	70	88	50	51	87	60	60	60	71	44	32	29	29	21	17	

[a]Full-time equivalents.

Table 4-43. Estimated earnings impacts by year for the Treatment and Waste Storage at ORNL Alternative for the region-of-influence

Year	Direct earnings[a] ($000)	Indirect earnings ($000)	Total earnings ($000)	ROI baseline income[b] ($000)	Percent of ROI income
2000	$1,578	$986	$2,563	$11,775,954	0.02
2001	$1,149	$1,130	$2,279	$11,832,509	0.02
2002	$2,552	$2,510	$5,062	$11,889,336	0.04
2003	$3,072	$3,306	$6,378	$11,946,463	0.05
2004	$3,167	$3,408	$6,575	$12,003,810	0.05
2005	$1,365	$985	$2,349	$12,061,459	0.02
2006	$517	$508	$1,025	$12,119,386	0.01
2007	$0	$0	$0	$12,177,590	0.00
2008	$0	$0	$0	$12,236,074	0.00
2009	$0	$0	$0	$12,294,839	0.00
2010	$0	$0	$0	$12,353,887	0.00

ROI = Region of Influence.

[a]Based on Table 4-41 and the following assumptions. (1) average U.S. Department of Energy-related wage ($47,445) for Phases I and III; and (2) Tennessee average wage for heavy construction ($30,839) for Phases II and IV.

[b]Assumes constant population growth rate from 2000 to 2010 and average per capita income for the ROI in 1996 ($22,982).

4.13.7 Summary of Socioeconomic Impacts

For the No Action Alternative there would no change in economic activity. For the treatment alternatives, economic activity in the region-of-influence would increase very slightly (0.1% for the Low-Temperature Drying, and Cementation and Treatment and Waste Storage Alternatives, and 0.2% for the Vitrification Alternative.

4.14 ENVIRONMENTAL JUSTICE

This section describes environmental justice impacts, which involve high and adverse human health or environmental impacts that have a disproportionate effect on minority or low-income populations. Each resource area was evaluated to determine if potential pathways would exist which could affect human populations in general and low-income and/or minority populations in particular. For example, land use impacts of the various alternatives were evaluated for significance and to determine if low-income or minority populations would be disproportionately affected. Likewise, biota (such as deer or fish) contaminated by project-related releases were considered in evaluating the relationship between ecological resources and environmental justice. Human health and accidents would have the largest potential impact on human populations. The other resource areas were insignificant for all alternatives and are not discussed further.

4.14.1 Methodology

Methods used to determine the environmental justice impacts for each alternative are listed below.

- Using the census tract maps and considering any special pathways (e.g. subsistence farming), determined for each resource area whether there would be any potential significant adverse impacts on the minority or low-income populations.

- If there would be any potential significant adverse impacts on the minority or low-income populations, determined if the impacts would be disproportionately high and adverse, when compared to the impacts to the general population.

4.14.2 No Action Alternative

Under the No Action Alternative, there are no significant impacts to low-income or minority populations during normal operations. The largest potential impacts involve human health effects. As discussed in Section 4.10, the maximum potential human health effects under normal operations are too small to constitute a significant impact. As discussed in Section 4.11.2 an accident could result in significant human health impacts to the general population, including low-income or minority populations. However, in all of the accidents evaluated, public exposure would result from either surface water transport or airborne release, and impacts are likely to be the same for minority or low-income populations as for the general public, as discussed below.

The surface water exposure would affect populations south and west of the ORR along the Clinch River. Census tracts in this direction include no minority populations and a mixture of low-income and higher income populations (Figures 4-3 and 4-4); therefore, a disproportionate impact on low-income or minority populations from such a release is unlikely. The airborne release pathway is similarly unlikely to have disproportionate effects on minority/low-income populations. Prevailing winds follow the general topography of the ridges. Daytime winds come from the southwest up the valley, and




Figure 4-3. Census tracts with a minority population greater than the national average of 24.1%. All residences are restricted to locations outside the ORR boundaries, even though the tract boundaries shown on this map include portions of the ORR.




Figure 4-4. Census tracts with a low-income population greater than the national average of 13.1%. All residences are restricted to locations outside the ORR boundaries, even though the tract boundaries shown on this map include portions of the ORR.

nighttime winds come down the valley from the northeast (DOE 1998b, p. 5-36). As in the case of a release via surface water, a nighttime release would affect all populations south and west of the ORR, and would be unlikely to affect minority or low-income populations more than others. A daytime release is likely to have similar effects on both minority and nonminority populations north and east of the ORR. Therefore, even in the unlikely event of an accident, there would be no disproportionately high and adverse impacts on low-income or minority populations.

4.14.3 Low-Temperature Drying Alternative

As in the No Action Alternative, under normal operations environmental impact and risk to low income and minority populations would be minimal. Human health impacts of potential accidents are discussed in Section 4.11.3; in all of the accidents evaluated, public exposure would result from either surface water transport or airborne release. As discussed in Section 4.14.2, release via either of these pathways is unlikely to have disproportionate effects on minority or low-income populations, and therefore no environmental justice impacts would occur.

4.14.4 Vitrification Alternative

As in the No Action Alternative, contaminant emissions and human health impacts under normal operations for the Vitrification Alternative are expected to be minimal. Human health impacts of potential accidents are discussed in Section 4.11.4; in all of the accidents evaluated, public exposure would result from either surface water transport or airborne release. As discussed in Section 4.14.2, release via either of these pathways is unlikely to have disproportionate effects on minority or low-income populations, and therefore no environmental justice impacts would occur.

4.14.5 Cementation Alternative

Contaminant emissions and human health impacts under normal operations for the Cementation Alternative are expected to be minimal. Human health impacts of potential accidents are discussed in Section 4.11.5; in all of the accidents evaluated, public exposure would result from either surface water transport or airborne release. As discussed in Section 4.14.2, release via either of these pathways is unlikely to have disproportionate effects on minority or low-income populations, and therefore no environmental justice impacts would occur.

4.14.6 Treatment and Waste Storage at ORNL Alternative

As in the No Action Alternative, contaminant emissions and human health impacts under normal operations for the Vitrification Alternative are expected to be minimal. Human health impacts of potential accidents are discussed in Section 4.11.6; in all of the accidents evaluated, public exposure would result from either surface water transport or airborne release. As discussed in Section 4.14.2, release via either of these pathways is unlikely to have disproportionate effects on minority or low-income populations, and therefore no environmental justice impacts would occur.

4.14.7 Summary of Environmental Justice Impacts

There would be no disproportionately high and adverse impacts to minority or low-income populations associated with any of the alternatives.

4.15 REFERENCES

Bechtel Jacobs (Bechtel Jacobs Company LLC) 1998. *Radiological Benchmarks for Screening Contaminants of Potential Concern for Effects on Aquatic Biota at the Oak Ridge National Laboratory, Oak Ridge, Tennessee*, BJC/OR-80, Bechtel Jacobs Company LLC, Oak Ridge, Tennessee.

Bechtel Jacobs (Bechtel Jacobs Company LLC) 1999. *Safety Analysis Report for the Liquid Low-Level Waste Management Systems*, WM-LGWO-LLW-SAR, Rev. 0-1, Bechtel Jacobs Company LLC, Oak Ridge, Tennessee, January 26, 1999.

Bureau of Economic Analysis 1999. *RIMS II Multipliers for Eastern Tennessee (Anderson, Knox, Loudon, and Roane Counties)*, Department of Commerce, Bureau of Economic Analysis, May 1999.

Campbell, A. W., G. F. Cada, R. H. Ketelle, R. L. Kroodsma, R. R. Lee, L. R. Pounds. 1989. *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant*, ORNL/TM-10965, Oak Ridge National Laboratory, Oak Ridge, Tennessee, March.

DOE (U.S. Department of Energy) 1989. *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant*, Oak Ridge, Tennessee, March 1989.

DOE 1994. *Airborne Release Fractions/Rates and Respirable Fractions for Nonreactor Nuclear Facilities*, DOE-HDBK-3010-94, October 1994.

DOE 1995. *Remedial Investigation Report on Waste Area Grouping 5 at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1326&D2.

DOE 1997a. *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee: Volume 1. Evaluation, Interpretation, and Data Summary*, DOE/OR/01-1546/V1&D2.

DOE 1997b. *Record of Decision for Interim Action: Sludge Removal from the Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/OR2-1591&D3, August 1997.

DOE 1997c. *Action Memorandum for the Old Hydrofracture Facility Tanks and Impoundment, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1751&D3.

DOE 1997d. *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact* Statement, DOE/EIS-0026-S-2, U.S. Department of Energy, Washington, D.C., September 1997.

DOE 1997e. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1998a. *Internal Dose Conversion Factors for Calculation of Dose to the Public*, DOE/EH-0071, July 1998.

DOE 1998b. *Draft Environmental Impact Statement, Construction and Operation of the Spallation Neutron Source Facility*, DOE/EIS-0247, U.S. Department of Energy, Office of Science, December 1998.

DOE 1999. *Advanced Mixed Waste Treatment Project Final Environmental Impact Statement*, DOE/EIS-0290, U.S. Department of Energy, Idaho National Engineering and Environmental Laboratory, Idaho Falls, Idaho, January 1999.

DOE 2000. *Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-Level and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site, Federal Register*, Vol. 65, No. 38, 10061–10066, February 25, 2000.

DuVall, G. D. 1992. *An Archaeological Reconnaissance of the Remote-Handled Transuranic Waste Storage Bunker (RH-TRU WSB) and Melton Valley Storage Tank–Capacity Increase Project (MVST-CIP), Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D. 1993. *An Archeological Reconnaissance and Evaluation of the Oak Ridge National Laboratory, Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, prepared for Martin Marietta Energy Systems, Inc., Oak Ridge, Tennessee.

DuVall, G. D., and P. A. Souza 1996. *An Evaluation of Previously Recorded and Inventoried Archeological Sites on the Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*, ORNL/M-4946, prepared for Lockheed Martin Energy Systems, Inc., Oak Ridge, Tennessee.

EPA (U.S. Environmental Protection Agency) 1991. *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual, Supplemental Guidance, Standard Default Exposure Factors, Interim Final*, EPA Office of Emergency and Remedial Response. OSWER DIR: 9285.6-03, Washington, D.C.

EPA 1995. *User's Guide for the Industrial Source Complex (ISC3) Dispersion Models, Volume I: User's Instructions*, EPA-454/B-95-003a, Office of Air Quality Planning and Standards, Research Triangle Park, North Carolina.

Faulkner, C. H. 1988. "Archaeological Investigations of the Jenkins House Site (40RE188) and the Jones House Site (40RE189), Copper Ridge, Oak Ridge Reservation, Roane County, Tennessee," in *Site Characterization Report for the Proposed Transuranic Waste Handling and Packaging Plant, Oak Ridge National Laboratory, Oak Ridge, Tennessee.*

Foster Wheeler (Foster Wheeler Environmental Corporation) 1999. *Required Information for the National Environmental Policy Act for the Treating of Transuranic/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Rev. 1*, Contract No. DE-AC098OR22516, Oak Ridge, Tennessee.

FTH EIS (Fort Huachuca Environmental Impact Statement) 1999. *Final Environmental Impact Statement for the Fort Huachuca Master Plan*, Environmental and Natural Resources Division, Directorate of Installation Support, U.S. Army Garrison, Fort Huachuca, Arizona, May 1999.

Jones, D. 1999. Personal communication between David Jones, Foster Wheeler Corporation, and Wayne Tolbert, Science Applications International Corporation, on October 8, 1999.

Keeler, J. M., J. M. Giaquinto, and A. M. Meeks 1996. *Characterization of the MVST Waste Tanks Located at ORNL*, ORNL/TM-13357, Lockheed Martin Energy Research Corp., Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Kelley, E. 2000. Personal communication from Ed Kelley, Bechtel Jacobs Company LLC with Norm Durfee, Science Applications International Corporation, June 8, 2000.

Moneymaker, R. H. 1981. *Soil Survey of Anderson County, Tennessee*, U.S. Department of Agriculture, Soil Conservation Service in cooperation with Tennessee Agricultural Experiment Station, 165 pp. plus maps.

ORNL (Oak Ridge National Laboratory) 1995a. *Programmatic Environmental Impact Statement Installation Descriptions*, ORNL-6841, Oak Ridge National Laboratory, Oak Ridge, Tennessee, April 1995.

ORNL 1995b. *DOE Public and On-site Population Health Risk Evaluation Methodology for Assessing Risks Associated with Environmental Restoration and Waste Management*, ORNL-6832, Oak Ridge National Laboratory, Oak Ridge, Tennessee, May 1995.

ORNL 1995c. *WM PEIS Methodology for Estimating Human Health Risks Associated with Waste Management*, ORNL-6864, Oak Ridge National Laboratory, Oak Ridge, Tennessee, May 1995.

ORNL et al. (Oak Ridge National Laboratory, Oak Ridge Y-12 Plant, and East Tennessee Technology Park) 1997. *Oak Ridge Reservation Annual Site Environmental Report for 1996*, ES/ESH-73, Oak Ridge, Tennessee, October 1997.

RAIS 2000. *Risk Assessment Information System*, 1/11/2000. Information as located on the world wide web (http:/risk/lsd.ornl.gov/prg/prg_search.html).

Roy, B. 1999. Personal communication between Bryan Roy, Foster Wheeler Environmental Corporation, and Wayne Tolbert, Science Applications International Corporation, on September 13, 1999.

Roy, B. 2000. Personal communication between Bryan Roy, Foster Wheeler Environmental Corporation, and Wayne Tolbert, Science Applications International Corporation, on January 14, 2000.

Saricks, C., and T. Kvitek 1994. *Longitudinal Review of State-Level Accident Statistics for Carriers of Interstate Freight*, ANL/ESD/TM-68, Argonne National Laboratory, Argonne, Illinois. July 1994.

Savannah River Plant 1999. Personal communication between Savannah River Plant Design Group personnel and Robert Garber, Parallax, Inc., in January 1999.

Toy, T. J., and G. R. Foster 1998. *Guidelines for the Use of the Revised Universal Soil Loss Equation (RUSLE), Version 1.06. U.S. on Mined Lands, Construction Sites, and Reclaimed Lands*, Department of Interior, Office of Surface Mining, Denver, Colorado.

Turner, D. Bruce 1969. *Workbook of Atmospheric Dispersion Estimates*, U.S. Department of Health, Education, and Welfare.

5. CUMULATIVE IMPACTS

This section summarizes the potential cumulative environmental impacts for treating TRU/alpha low-level waste at the ORNL. Cumulative impacts result

> "... from the incremental impact of the action when added to past, present, and reasonably foreseeable future actions regardless of what agency (Federal or non-Federal) or person undertakes such actions. Cumulative impacts can result from individually minor but collectively significant actions taking place over a period of time" (40 *CFR* 1508.7).

The proposed action is to treat and repackage TRU/alpha low-level waste by one of three treatment methods and to ship the waste offsite, or for one alternative to treat and store the waste onsite. The evaluation of cumulative impacts adds the impacts of the proposed action for each resource area with impacts from past and existing operations and reasonably foreseeable future actions. Cumulative impacts are analyzed for the bounding case alternative for each resource area. The general methodology used to determine if a potential cumulative impact might result from implementation of the proposed action was to first determine if either an adverse or beneficial impact was documented (Chapter 4) for a given resource area. If none would occur (which is the case for cultural and archaeological resources for example) then, by definition, a cumulative impact could not exist for this resource area. Next, past, present, and reasonably foreseeable future projects that are affecting, have affected, or could affect the Region of Influence for each resource area were evaluated and their impacts were added to the impacts of the bounding case alternative.

Potential cumulative impacts to resource areas are discussed in Sections 5.1 through 5.7. Table 5-1 presents the past, present, and reasonably foreseeable future actions that have the potential for producing cumulative impacts.

Table 5-1. Past, present, and reasonably foreseeable future actions with potential for cumulative impacts

Past, present, or reasonably foreseeable future actions	Location	Description	Applicable resource area
Construction and Operation of the Spallation Neutron Source[a]	To be located approximately 4 km (2.5 miles) from the proposed TRU Waste Treatment Facility site, northeast between ORNL and the Y-12 Plant	This high-energy physics facility would increase employment by 1,700 persons and affect the ORR land use by developing 45 ha (110 acres) of land.	Applicable to land use, socioeconomics, and human health.
Construction and Operation of the Joint Institute for Neutron Science[a]	To be located at ORNL approximately 1.6 km (1 mile) east of the proposed TRU Waste Treatment Facility site	This facility, which was originally planned to be open in 2000 but is currently delayed, would provide office space, meeting rooms, and hotel accommodations for visiting scientists. The facility would require about 4 ha (10 acres).	Applicable to land use.
Construction and Operation of the Laboratory for Comparative and Functional Genomics[a]	To be located at ORNL approximately 2.0 km (1.25 miles) east of the TRU Waste Treatment Facility site	This would be a genetic research laboratory. About 2 ha (10 acres) would be needed for the buildings and parking lots.	Applicable to land use.
Relocate ORNL Personnel at Y-12 Plant back to ORNL[b]	ORNL	This effort would relocate 300 to 320 ORNL staff currently housed at the Y-12 Plant back to ORNL. Office, laboratory, and parking space would require approximately 10 ha (25 acres).	Applicable to land use and socioeconomics.
Implementation of the White Oak Embayment Project[c]	Located at the mouth of White Oak Creek approximately 2.1 km (1.3 miles) west of the TRU Waste Treatment Facility site	A CERCLA project completed in 1992, which resulted in construction of a coffer dam on White Oak Creek. Purpose was to renew and retain sediment in White Oak Lake, covering exposed cesium-137 sediments.	Applicable to water resources.
Old Melton Valley Road (High Flux Isotope Reactor access road) Upgrade Construction[d]	Immediately west of the TRU Waste Treatment Facility site and Melton Valley Storage Tanks	This 1.8-km (1.1-mile) road upgrade project completed in 1999 affected approximately 4 ha (10 acres) along the south side of White Oak Creek.	Applicable to water, air, and ecological resources.
Waste Area Grouping (WAG) 5 Seep C and D Remediation[e]	Seep D is approximately 0.3 km (.19 miles) northeast of the TRU Waste Treatment Facility site; Seep C is 0.14 km (0.09 miles) north	These two CERCLA actions, completed in the mid-1990s, significantly reduced strontium-90 releases to the White Oak Creek watershed.	Applicable to soils, water resources, and ecological resources.

Table 5-1. Past, present, and reasonably foreseeable future actions with potential for cumulative impacts (continued)

Past, present, or reasonably foreseeable future actions	Location	Description	Applicable resource area
Waste Area Group 4 Seeps Remediation[c]	These seeps are approximately 0.75 km (0.5 miles) north of the TRU Waste Treatment Facility site	This CERCLA action, completed in 1996, helped reduce strontium-90 releases into the White Oak Creek watershed.	Applicable to soils, water resources, and ecological resources.
Old Hydrofracture Tanks Remediation[c]	Located approximately 0.10 km (0.06 miles) east of the TRU Waste Treatment Facility site	This project is an ongoing CERCLA action, but the TRU wastes in these tanks have already been transferred to the Melton Valley Storage Tanks.	Applicable to water resources and waste management.
WAG 13 Cesium Test Plots Remediation[c]	Located approximately 2.1. km (1.32 miles) west of the TRU Waste Treatment Facility site on the banks of the Clinch River	This CERCLA action, completed in the mid-1990s, reduced cesium-137 releases into the Clinch River.	Applicable to soils and water resources.
Molten Salt Reactor Experiment (MSRE) Facility Remediation[c]	Located approximately 1.6 km (1.0 mile) east of the TRU Waste Treatment Facility site	An ongoing CERCLA action intended to reduce the risk of nuclear criticality.	Potentially applicable to waste management.
WAG 6 SWSA 6 Monitoring	WAG 6 is adjacent to the north-northwest portion of White Oak Lake. SWSA 6 is the major portion of WAG 6.	No official CERCLA decision document was signed, but all monitoring activities are based on a Record of Agreement signed by the FAA managers for DOE, TDEC, and EPA.	Applicable to water resources and ecological resources.
Transfer of TRU debris waste from Paducah to Oak Ridge	Paducah, Kentucky	Approximately 15 m^3 (20 yd^3) of TRU debris waste could be sent to ORNL in 2005	Waste management.
Operation of the TSCA Incinerator	Located at ETTP (formerly K-25 Site) approximately 7 km (4.4 miles) from TRU Waste Treatment Facility Site	Future plans are to phase out entirely the operation of this incinerator, thus eliminating a source of airborne radionuclides.	Applicable to air quality.
Operation of the TVA Steam Plants[c]	Bull Run Steam Plant is a 900-MW plant approximately 8 km (5 miles) east of ORNL; Kingston Steam Plant is a 1,640-MW plant approximately 48 km (30 miles) northwest of ORNL	Both electric-generating plants are coal-fired with emissions typical of such plants. These plants are major air pollutant sources for NO_x, SO_2, CO_2, lead, and particulates.	Applicable to air quality.

Table 5-1. Past, present, and reasonably foreseeable future actions with potential for cumulative impacts (continued)

Past, present, or reasonably foreseeable future actions	Location	Description	Applicable resource area
Construction and Operation of the ETTP Reindustrialization Projects[f]	Located at ETTP	Three reindustrialization projects (ETTP, ED-1, and ED-3) would increase area employment by up to 17,700 direct jobs. The three projects, involving approximately 2,025 ha (5,000 acres) of DOE land leased to the Community Reuse Organization of East Tennessee, are intended to spur economic development as DOE reduces direct employment in the Oak Ridge, Tennessee, area.	Applicable to socioeconomics and land use.
Macedonia Industrial Park in Roane County[f]	A private industrial park in Roane County off the ORR	This 280-ha (700-acre) site is expected to employ approximately 3,500 workers.	Applicable to socioeconomics and land use.

[a]DOE 1999. *Final Environmental Impact Statement, Construction and Operation of the Spallation Neutron Source*, U.S. Department of Energy, Office of Science, DOE/EIS-0247, April 1999.

[b]Personal communication with Tony Medley, ORNL Capital Assets Manager, January 7, 2000.

[c]DOE 1999. *Remedial Effectiveness Report for the U.S. Department of Energy Oak Ridge Reservation, Oak Ridge, Tennessee*, DOE OR/01-1790&D0.

[d]DOE 1998. *Categorical Exclusion for Construction/Relocation of Access Road at Oak Ridge National Laboratory*, CX-TRU-98-007, Oak Ridge, Tennessee.

[e]TVA internet web site.

[f]DOE 1999. *Draft Environmental Assessment, Lease of Parcel ED-3 of the Oak Ridge Reservation to the Community Reuse Organization of East Tennessee*, U.S. Department of Energy, Oak Ridge Operations Office, Oak Ridge, Tennessee.

5.1 LAND USE

The proposed action's incremental contributions to land use classification changes or land use practices (Chapter 4, Section 4.1), when combined with past, present, and reasonable foreseeable future classifications and practices, are evaluated. The zoning of ORR land for future use is the same as the current land use pattern, as reflected in the *ORNL Land and Facilities Use Plan* (LMER and LMES 1998). DOE plans to use the land in ways compatible with the current pattern of use. A number of mission-related projects are now planned for the ORR. These projects, with some likelihood of cumulatively affecting land use, would be at or near ORNL. These include the Spallation Neutron Source, the Joint Institute for Neutron Science, the Laboratory for Comparative and Functional Genomics (Hall 2000), and Relocation of ORNL Personnel from the Y-12 Plant (Medley 2000). These projects would require development of 45, 4, 2, and 10 ha, respectively (111, 9.9, 4.9, 24.7 acres, respectively), as described in Table 5-1. Because of the relatively large scale of development, the ETTP reindustrialization

projects and the Macedonia Industrial Park are also considered (Table 5-1). Two of the ETTP projects (ED-1 and ED-3) would involve developing industrial land zoned as industrial but not currently developed.

The proposed action would be consistent with the existing industrial land use classification in Melton Valley. Construction and operation of a waste treatment and repackaging facility adjacent to the Melton Valley Storage Tanks would help continue the trend of industrial development at ORNL. The bounding alternative would be the Treatment and Waste Storage at ORNL Alternative using vitrification as the treatment process. The proposed facility would require 3.4 ha (8.5 acres) for the treatment facility and additional on-site storage space. The cumulative impact on land use would be small.

5.2 ECOLOGICAL RESOURCES

Forested and other undeveloped lands used by wildlife are rapidly being converted to residential, commercial, and industrial uses throughout the Tennessee Valley. The ORR, and ORNL specifically, by virtue of land use planning and restricted access, provide a refuge where habitat and species of wildlife are especially abundant. The proposed action would slightly reduce wildlife habitat at ORNL. The Old Melton Valley Road upgrade (Table 5-1) resulted in approximately 4 ha (10 acres) of forest habitat being permanently lost to wildlife. This disturbance is immediately adjacent to the proposed treatment site. The Old Melton Valley Road upgrade construction will contribute to the cumulative impacts associated with the project. As a result of evaluating impacts related to the project, a decision was made to relocate the road in order to minimize the impacts to the State-listed plant species, Pursh's Wild Petunia (*Ruellia purshiana*). A copy of the "Report for Rare Plant Survey Proposed Melton Valley Access Road" and the categorical exclusion (CX) for the Old Melton Valley Road upgrade have been included in Appendix G. The bounding alternative would be the Treatment and Waste Storage at ORNL Alternative using vitrification as the treatment process. The proposed facility would require 2.8 ha (7 acres) of forested land for the treatment facility and an additional 0.6 ha (1.5 acres) of cleared and/or forested land for on-site storage space. This wildlife habitat would be lost for a period of at least a decade, thereby resulting in a small incremental increase in the loss of habitat in the lower reaches of Melton Valley.

Waste removal from the SWSA 5 North trenches would, when combined with remediation of the Waste Area Group 5 Seeps C and D and Waste Area Group 4 seeps, result in a beneficial cumulative impact to area biota.

5.3 WATER RESOURCES

Potential cumulative impacts to water resources in the defined Region of Influence, the White Oak Creek Watershed, are evaluated by combining the impacts identified in Section 4.5 with other impacts occurring in that watershed. To the extent known, specific projects such as the five completed projects (the White Oak Creek Embayment Project, Waste Area Group 5 Seep C, WAG 5 Seep D, WAG 4 Seeps, and WAG 13 Cesium Test Plots) and two ongoing CERCLA cleanup actions (Old Hydrofracture Facility Tanks and Molten Salt Reactor Experiment projects) in the Melton Valley Watershed (Figure 5-1), and other actions or activities, are identified (Table 5-1). The impacts of these projects are then combined with those of the bounding alternative for the proposed action to determine the cumulative impact to water resources that would be expected to result if the proposed action were implemented.




Figure 5-1. Melton Valley Watershed Remedial Investigation site map with proposed Treatment Site Location.

5.3.1 White Oak Creek Embayment Project

Cesium-137 concentrations in the near-surface sediments of White Oak Lake are thought to be a potential human health and ecological risk. Erosion of lake bed sediments from water surging into and out of White Oak Lake was caused by daily releases of water from Melton Hill Dam and storm water flows, especially during the winter months when the lake was at low-pool elevation. Loss of the surface sediment, which served as a physical barrier for the buried radionuclides, exposed the cesium-137-bearing layers. In 1992, DOE completed a CERCLA action resulting in the construction of a coffer dam at the mouth of White Oak Creek to help retain and renew sediment deposition in White Oak Lake (DOE 1999a).

The proposed action would contribute some sediment loading into White Oak Creek and White Oak Lake, although best management practices would be followed to minimize soil erosion and sedimentation in surface waters. Potentially beneficial cumulative impacts could result from inadvertent or unpreventable releases of sediments that would incrementally contribute to sediment renewal in White Oak Lake.

5.3.2 Old Melton Valley Road Upgrade

This road upgrade contributes to cumulative impacts resulting from the project, as minor erosion-related sediment releases from the Old Melton Valley Road upgrade have already occurred into the surface waters of White Oak Lake. This road upgrade was evaluated for environmental impacts by DOE; however, a CX was prepared for it. The CX concluded that the project would pose no threat of significant individual or cumulative effects to environmentally sensitive resources such as archaeological or historic sites, potential habitats of threatened or endangered species, floodplains, wetlands, Federally- or State-designated wilderness areas, national parks, natural landmarks, wild and scenic rivers, wildlife sanctuaries, prime agricultural lands, or special sources of water such as sole source aquifers.

Storm water runoff from the proposed TRU Waste Treatment Facility contributes to sediment releases in the White Oak Creek/White Oak Lake watershed. As mentioned above, while best management practices, such as the use of silt fences, would be followed during construction of the treatment facility, some minor additional siltation of White Oak Creek and White Oak Lake is likely from project activities.

5.3.3 Waste Area Group 5 Seep C and D

WAG 5 Seep C and Seep D (Figure 5-1) were determined to be major contributors to strontium-90 releases into White Oak Creek. In 1993-1994, Seep C contributed 30 to 40% of the total strontium-90 monitored at White Oak Dam, and Seep D contributed an additional 7% (DOE 1999a). CERCLA removal actions using ion-exchange technology were implemented to treat the groundwater discharge to Melton Branch. Removal efficiencies ranging from 90 to greater than 99% have been documented for both removal actions.

As part of the proposed action, low-level waste would be removed from the SWSA 5 North trenches, which are a significant source of strontium-90 and cesium-137 releases in the White Oak Creek Watershed presently (6% of the strontium-90 and 3.6% of the cesium-137 releases to the White Oak Creek Watershed in 1995). Approximately 14,000 curies of radiation is estimated to be in the waste in these trenches. To further clarify the improvements made in the watershed, Table 5-2 shows the yearly monitoring results of tritium and strontium-90 flux at White Oak Dam. The Seep C contribution to Melton Branch in 1998 is calculated at 86.4 pCi/L with a flux rate of 17.8 mCi, and Seep D's contribution is 12.1 pCi/L with a flux rate of 3.2 mCi. (DOE 1999a). Cumulatively, the proposed action would

Table 5-2. Tritium and strontium-90 flux measurements at White Oak Dam, 1993–1998[a]

Year[b]	White Oak Dam flux (Ci)	
	Tritium	Strontium-90
CY 1993	2,141	2.44
CY 1994	2,783	3.37
CY 1995	2,340	1.55
FY 1996	2,250	2.04
FY 1997	1,860	1.99
FY 1998	937	1.37

[a]DOE 1999. *Remedial Effectiveness Report for the U.S. Department of Energy, Oak Ridge Reservation, Oak Ridge, Tennessee*, DOE/OR/01-1790&D0.

[b]In past years estimates have been made for the 12-month calendar year (CY). Since 1996, estimates are provided for the 12-month fiscal year (FY) (October 1997 through September 1998).

contribute to recent efforts to improve the groundwater and surface water quality in this watershed by treating the waste containing strontium-90 and cesium-137 in the SWSA 5 North trenches.

5.3.4 Waste Area Group 4 Seeps

The WAG 4 seeps (Figure 5-1) were determined to contribute approximately 25% of the strontium-90 measured at White Oak Dam in 1996. As noted above, the total flux rates at White Oak Dam are presented in Table 5-2. The WAG 4 Seeps contribute to these fluxes. The CERCLA remedy implemented in 1996 was to grout several trenches in WAG 4 to improve their physical stability and reduce hydraulic conductivity. DOE estimates that the trench grouting will reduce strontium-90 releases from these trenches by 75% over 10 years (DOE 1999a). The proposed action would treat wastes that are removed under this CERCLA cleanup action thereby reducing the strontium-90 source.

5.3.5 Other CERCLA Actions

Other CERCLA actions in the general vicinity of Melton Valley area that may impact water resources include the Old Hydrofracture Facility Tanks and the WAG 13 Cesium Test Plots. The Old Hydrofracture Facility Tanks Removal Action (Figure 5-1) is not complete, but the TRU waste in these tanks has already been transferred to the Melton Valley Storage Tanks and is part of the waste inventory to be treated under the proposed action. The completed WAG 13 Cesium Test Plots Project resulted in the reduction of cesium releases near the Clinch River (DOE 1999a). The WAG 13 area is substantially downstream from the proposed TRU Waste Treatment Facility site. Both of the actions are expected to have beneficial impacts on ground and surface water resources. There would be little cumulative impact from the proposed action.

5.3.6 Waste Area Group 6 SWSA 6 Monitoring

WAG 6 is located at the westernmost end of the Melton Valley Watershed, immediately adjacent to the north-northwest border of White Oak Lake. SWSA 6 is the major portion of WAG 6, covering approximately 27.5 ha (68 acres) (SAIC 1998). SWSA 6 includes over 400 waste trenches, 220 auger holes, and silos, with wastes including both high- and low-activity wastes, animal carcasses, RCRA wastes, and solvents. Although WAG 6 is downstream (west) of the proposed facility site, White Oak Lake is within the Region of Influence. Although no official CERCLA decision document has been signed for WAG 6, a Record of Agreement was signed by the FAA managers for DOE, TDEC, and EPA. The Record of Agreement states that releases from WAG 6 currently pose minimal potential risk to

human health and the environment compared to releases from other ORNL WAGs, but ongoing monitoring of surface water and groundwater at the site will be continued until active source controls are implemented. For 1997, surface water fluxes of strontium-90 and tritium from WAG 6 into White Oak Lake normalized to baseflows were 1.35E-02 Ci and 8.52E+01 Ci, respectively. The 1997 data were somewhat higher than the baseline values from 1996 (SAIC 1998). The proposed action should have little if any impact regarding the cumulative impacts from WAG 6 because potential risks to human health and the environment are already minimal from WAG 6 releases and the proposed facility site does not or would not increase strontium-90 or tritium into surface water.

5.3.7 Summary of Water Resource Impacts

Cumulatively, impacts to water resources in the White Oak Creek watershed are expected to be mostly beneficial. By implementing the proposed action waste in the SWSA 5 North trenches would be treated and the strontium-90 and cesium-137 releases would be reduced. Sedimentation, while expected to be small because of use of best management practices, would tend to be greatest for the Treatment and Waste Storage at ORNL Alternative using vitrification as the treatment process. Sedimentation would help renew the depleted sediment in the White Oak Embayment.

5.4 WASTE MANAGEMENT

Melton Valley has several waste storage facilities including the Melton Valley Storage Tanks, the Melton Valley Storage Tanks – Capacity Increase Project Tanks, and eight WAGs located along an east-west axis in Melton Valley. The Record of Decision for the Melton Valley Watershed (DOE 1997a) at ORNL addresses the cleanup of the Melton Valley Watershed under CERCLA. The actions conducted as part of the Melton Valley Watershed Record of Decision, in conjunction with the TRU waste treatment and disposal conducted as part of the proposed action would have beneficial impacts on the Melton Valley Watershed, by the cleanup of the majority of contamination in this valley. In addition to the cleanup actions implemented under the Record of Decision for the Melton Valley Watershed, the Molten Salt Reactor Experiment remediation project is ongoing, and efforts are being directed at reducing the risk of nuclear criticality (DOE 1999a).

Approximately 15 m^3 (20 yd^3) of TRU debris waste may be transferred from DOE's Paducah Plant to ORNL in 2005. Thus, a small amount of off-site waste would be added to the local inventory for treatment and disposal. If the DOE Paducah site, or any other DOE site, ships any TRU waste to ORNL for treatment, DOE would need to conduct further NEPA review as appropriate. This additional waste would add 0.6% to the 2,450 m^3 of TRU/alpha low-level waste inventory at ORNL, a minimal impact to waste management operations.

The Treatment and Waste Storage at ORNL Alternative, using the cementation process as the bounding condition, would produce 34,128 m^3 of waste. An additional on-site storage space of 0.8 hectares (2 acres) would be required. There are 65 ha (160 acres) of area in Melton Valley devoted to waste storage and operation (DOE 1997c). Given the extensive space already devoted to waste storage in Melton Valley, this would not be cumulatively significant.

5.5 AIR QUALITY

ORNL is an attainment area for all criteria pollutants including particulates. In 1997, the maximum 24-hour particulate concentration was 69.0 $\mu g/m^3$ which is 46% of the 150 $\mu g/m^3$ National Ambient Air Quality Standard. The annual concentration of 33 $\mu g/m^3$ was 66% of the 50 $\mu g/m^3$ standard. Past

activities, such as construction of the Old Melton Valley Road upgrade, contributed to fugitive dust emissions during construction; however, these emissions were small and temporary. Future projects involving ground disturbance activities that would likely result in fugitive dust emissions include the proposed Spallation Neutron Source. Emissions from this source would be negligible. The Treatment and Waste Storage at ORNL Alternative using the vitrification treatment process as the bounding alternative would result in the greatest impacts because vitrification would require the most land for construction of the treatment facility (2.8 ha or 7 acres) and onsite storage (0.6 ha or 1.5 acres), and would also result in construction-related fugitive dust emissions. Construction would result in short-term, elevated levels of particulate matter in the localized area around the construction site. There would also be temporary, elevated levels of air pollutant emissions from worker and construction vehicles. However, emissions are estimated to be negligible. Since the access road is complete, construction schedules would not overlap. The distance between the Spallation Neutron Source and the TRU Waste Treatment Facility would minimize any cumulative effects, even assuming that construction periods of the projects overlapped. Cumulatively, deposition of particulates from the proposed action combined with emissions from the Old Melton Valley Road upgrade and other large construction projects, such as the Spallation Neutron Source, could indirectly affect vegetation by coating leaves with dust. Such impacts would be very localized, relatively minor, and temporary.

The background off-site (public maximally exposed individual) airborne radionuclide dose from the ORR is 0.41 mrem/year. The radionuclide dose of 0.23 mrem/year to the public maximally exposed individual from the Low-Temperature Drying Alternative is the bounding case. Cumulatively, the total public MEI dose would be 0.64 mrem/year.

The TSCA Incinerator at the ETTP, the Bull Run Steam Plant (8 km or 5 miles) east of ORNL, and the Kingston Steam Plant [approximately 48 km (30 miles) northwest of ORNL] near Kingston, Tennessee, are major emission sources in the region which affect the air quality at ORNL. The TSCA Incinerator is a source of radionuclide emissions at the ETTP. The Incinerator emits several non-radionuclides (metals, chlorine, and particulates) but actual emissions in 1998 ranged from <1% to 7% of the emissions allowed by permit (ORNL 1999). The various alternatives considered under the proposed action would contribute a small amount to the overall emissions in the airshed.

5.6 TRANSPORTATION

DOE estimates the transportation of waste by truck, from DOE facilities nationwide, to result in a combined total of between 12 and 69 fatalities for the shipment of low-level mixed wastes, low-level wastes, TRU wastes, high-level wastes, and hazardous wastes. The majority of these fatalities would result from physical trauma directly related to potential accidents and truck fuel emissions. These fatalities from physical trauma are independent of the shipment contents (WM PEIS, DOE 1997b). The Oak Ridge contribution to these accidents and fatalities would be 8.1E-04 accidents per shipment and 1.1E-04 fatalities per shipment. Comparatively, from 1971 through 1993, over one million persons were killed in vehicular accidents in the United States (WM PEIS, DOE 1997b).

Cumulatively, the non-DOE transport of radioactive material accounts for approximately 80% of the collective dose to workers and the public. At ORR, DOE has estimated the effects of waste transportation over a 10-year period to be a radiation dose to the off-site MEI of 3.2E-07 to 1.4E-04 fatalities per shipment (WM PEIS, DOE 1997b). Because off-site waste shipment is not part of either the No Action or the Treatment and Waste Storage at ORNL Alternatives, no cumulative off-site transportation impacts would occur for these alternatives.

5.7 HUMAN HEALTH

The ORR has a number of radiological sources including the Melton Valley Storage Tanks. These DOE sources, combined with natural background, help constitute the radiological baseline for the area. As noted in Section 5.3, DOE has an active cleanup program under way under CERCLA. This program is designed to reduce radiological and other contaminant sources and releases in Melton Valley. Using 1998 effective dose equivalent data for the ORR (ORNL 1999), the LCFs risk computed for population within 80 km (50 miles) of the ORR is 6.6E-03. The Treatment and Waste Storage at ORNL Alternative using the vitrification process as the bounding alternative would result in 6.8E-01 person-rem to the affected public population and a corresponding 3E-04 LCFs risk to that population. The LCFs risk attributed to the Spallation Neutron Source project is 3.0E-01 (DOE 1999b). Cumulatively, the LCFs risk from all these sources would be 3.1E-01.

When the wastes associated with the proposed action are treated and shipped offsite, the total expected fatalities (public population), the MEI (public) probability of cancer fatality and non-involved worker probability of cancer fatality associated with potential accidental releases from a breach of the Melton Valley Storage Tanks would be eliminated. The projected risk to the affected public population from both inhalation and ingestion from a release of untreated wastes from a tank breach would be 1.1 total expected fatalities; the maximally exposed individual (public) probability of cancer fatality would be 1.1E-05 and the non-involved worker probability of cancer fatality would be 9.2E-04. These risks would be eliminated by adopting any of the treatment options under the proposed action. The most significant accident associated with waste treatment would be the breach of the Melton Valley Storage Tank transfer line during treatment operations for the Cementation Alternative. Risks from this type of accident would be 0.31 total expected fatalities. Risks from this type of accident would vary by treatment process for the Treatment and Waste Storage at ORNL Alternative but would be greatest if the cementation process were used.

5.8 SOCIOECONOMICS

The cumulative socioeconomic impacts from this project are determined by adding the impacts identified in Section 4.13 with expected future development project effects on employment and wages. Projected changes over the next 10 years in the future DOE and contractor workforce in Oak Ridge are factored into the analysis. As noted in Chapter 4, the TRU Waste Treatment Facility would contribute very little to the regional economy and the overall employment picture regardless of the alternative selected. However, the Treatment and Waste Storage at ORNL Alternative would be the bounding case. These impacts must be viewed in context. Several planned re-industrialization projects at ETTP (Table 5-1) would, under full realization, produce up to 14,700 direct and indirect jobs, or 5% of 1996 Region of Influence employment. In addition, Roane County is working on plans for the Macedonia Industrial Park (Table 5-1) near the ETTP site, which would be located off the ORR.

The potential gains in employment from these regional projects are likely to be offset by the large cuts in DOE-related jobs during the same time period. An estimated 4,000 direct and indirect jobs were lost between 1996 and 1998, and more jobs could be lost in the next 10 years. If we assume that 5,000 direct jobs are lost during this period, the cumulative total direct and indirect jobs lost from 1996 to 2010 would total 10,950. This exceeds the lower-bound estimate of total jobs created by the ETTP initiatives. When we subtract this from the upper bound, the net new jobs created would represent roughly 1% of the 1996 region of influence employment. Even if other DOE employment (such as construction-related employment for the Spallation Neutron Source and Y-12 Modernization) is considered, the incremental increase in employment from the proposed action would be minor. The proposed action

would contribute very little additional employment, and the project's contribution to cumulative socioeconomics impacts regardless of the treatment process would be very small.

5.9 REFERENCES

DOE (U.S. Department of Energy) 1997a. *Record of Decision for the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/01-1826&D1.

DOE 1997b. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1997c. *Remedial Investigation Report on the Melton Valley Watershed at Oak Ridge National Laboratory, Oak Ridge, Tennessee: Volume 1, Evaluation, Interpretation, and Data Summary*. DOE/OR/01-1546 V1&D2.

DOE 1998. *Categorical Exclusion for Construction/Relocation of Access Road at Oak Ridge National Laboratory*, CX-TRU-98-007, Oak Ridge, Tennessee.

DOE 1999a. *Remedial Effectiveness Report for the U.S. Department of Energy Oak Ridge Reservation, Oak Ridge, Tennessee*, DOE/OR/01-1790&D0.

DOE 1999b. *Final Environmental Impact Statement—Construction and Operation of the Spallation Neutron Source*, DOE/EIS-0247, U.S. Department of Energy, Office of Science, April 1999.

Hall, J. 2000. Personal communication with Wayne Tolbert, Science Applications International Corporation, January 7, 2000, from James Hall, Oak Ridge National Laboratory National Environmental Policy Act Coordinator.

LMER and LMES (Lockheed Martin Energy Research Corp. and Lockheed Martin Energy Systems, Inc.) 1998. *Comprehensive Integrated Planning: A Process for the Oak Ridge Reservation, Oak Ridge, Tennessee*, ES/ENSFP-49, Oak Ridge, Tennessee, January 1998.

Medley, T. 2000. Personal communication with Wayne Tolbert, Science Applications International Corporation, January 7, 2000, from Tony Medley, Oak Ridge National Laboratory Capital Assets Manager.

ORNL (Oak Ridge National Laboratory) 1999. *Oak Ridge Reservation Annual Site Environmental Report for 1998*, DOE/ORO/2091.

SAIC (Science Applications International Corporation) 1998. *Integrated Water Quality Program Annual Report for the U.S. Department of Energy, Oak Ridge Reservation, Oak Ridge, Tennessee*, BJC/OR-32. Prepared by Science Applications International Corporation, Oak Ridge, Tennessee, for U.S. Department of Energy under Subconctract 78B-99421C.

6. MITIGATION MEASURES

A variety of design features were built into the various alternatives to help minimize adverse environmental impacts. These best management practices serve to reduce or eliminate potentially harmful secondary waste streams. Further, it is generally assumed that best management practices would be followed regarding erosion control, minimization of secondary waste, and safe handling of materials to minimize accidents or the effect of accidents. Specific mitigation measures are described below.

Impacts to cultural and archaeological resources are best minimized by avoidance. Although no such resources have been identified in the project site area, should any cultural or archaeological resources be encountered, construction would be immediately stopped, and the appropriate DOE personnel and the Tennessee State Historic Preservation Officer would be notified. Specific mitigation would follow the advice and guidance of these individuals.

Erosion control measures, such as silt fences, combined with timely construction of buildings and parking lots would reduce the potential for increased siltation and turbidity in White Oak Creek and White Oak Lake from runoff. Also, proper maintenance of drainage culverts, gate valves, and the detention basin would reduce the likelihood of soil erosion from storm water overflows.

Air quality mitigation measures that may be used during the construction phase to control dust include:

- use of water or chemicals during site clearing, digging, and grading;
- application of asphalt, concrete, water, or grass seed on roadways, fill stockpiles, and other surfaces that can yield dust; and
- covering of open truck beds.

Impacts of vehicular exhaust may be reduced by refraining from unnecessary idling of equipment and implementation of transportation controls that reduce work-related vehicle miles to the minimum required to the task (WM PEIS, DOE 1997a).

Impacts from waste treatment processes utilize efficient emission controls designed for the specific process as described above.

Inspecting and maintaining the trucks transporting waste on a regular basis would mitigate transportation impacts. Drivers would be required to meet strict selection and training criteria. Planning of specific transportation routes using DOT routing guidelines would minimize risk. The TRANSCOM system would be used to monitor shipments to the Waste Isolation Pilot Plant. Extensive emergency response capability exists and would be maintained at DOE, the trucking contractor, and in communities along the transportation routes (WIPP SEIS-II, DOE 1997b).

A 0.016-ha (0.03-acre) wetland on the proposed project site is expected to be destroyed by construction. Potential mitigation measures include avoidance, minimization, or compensation. Redesigning the layout of the TRU waste treatment facility could potentially avoid or minimize impact to this wetland. Should this not be practical, then compensatory mitigation such as new method construction could be done. Redesign of the sediment/storm water detention basin could result in a constructed wetland. Under NEPA, mitigation refers

to measures to reduce impacts produced by the proposed action. Mitigation measures to achieve no-net-loss of wetlands will be provided in a Mitigation Action Plan to State regulators.

TDEC has responsibility for "Waters of the State." Although Aquatic Resource Alteration Permits are not expected (no stream crossings), TDEC has interests in wetland disturbance, and coordination between DOT and TDEC is ongoing on this matter regarding appropriate mitigating measures.

6.1 REFERENCES

DOE 1997a. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1997b. *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact* Statement, DOE/EIS-0026-S-2, U.S. Department of Energy, Washington. D.C., September 1997.

7. UNAVOIDABLE ADVERSE IMPACTS AND IRREVERSIBLE IRRETRIEVABLE COMMITMENT OF RESOURCES

7.1 UNAVOIDABLE ADVERSE IMPACTS

Despite the mitigation measures identified in Chapter 6, there would be some unavoidable adverse impacts resulting from the implementation of the proposed action alternatives. These include the clearing of 2 to 2.8 ha (5 to 7 acres) of forested land resulting from the construction of the proposed waste treatment facility and loss of this habitat by plants and animals for a period of at least a decade (Sections 4.1 and 4.3). The area would be revegetated after closure and D&D of the proposed facility. An additional 0.3 to 0.8 ha (0.75 to 2 acres) of land would be required indefinitely if the Treatment and Waste Storage at ORNL Alternative is implemented. This land would be used for the waste storage facilities, which would be required for this alternative.

Some secondary wastes and emissions would be created despite best efforts at source reduction, recycling, and other best management practices (Section 4.6). The potential for transportation and other accidents can be reduced by best management practices but not entirely eliminated. Some potential risks are unavoidable as a function of the treatment and transportation process (Section 4.10). Some slight, temporary increases in noise are also unavoidable (Section 4.12).

7.2 IRREVERSIBLE AND IRRETRIEVABLE COMMITMENT OF RESOURCES

The proposed action would involve the irreversible or irretrievable commitment of land, energy, and materials. The commitment of a resource is irreversible if its primary or secondary impacts limit future options for the resource. An irretrievable commitment refers to the use or consumption of resources that are neither renewable nor recoverable for later use by future generations. Construction, operation, and eventual D&D would result in a permanent commitment of materials such as steel and concrete, and would consume energy in forms such as gasoline, diesel fuel, and electricity. Water use would support construction, operation and D&D. There would be an irreversible and irretrievable commitment of current natural resources.

The 11,250 to 45,000 MW of electrical energy would be required for the project, depending on the alternative selected, and would be committed and consumed (Section 4.9). Some building materials, steel and concrete, for the process building and related facility support would be used. Some portion of these materials cannot be reused. Waste packaging and storage materials would also be irreversibly committed to this use.

Depending on the treatment alternative selected, land indefinitely committed as storage space would be approximately 0.3 ha (0.75 acres) for the low-temperature drying process, 0.6 ha (1.5 acres) for the vitrification process, or 0.8 ha (2.0 acres) for the cementation process (Section 4.1). This would constitute an irreversible and irretrievable commitment of this land. The land, which is forested, would be permanently converted to industrial use. In addition, 0.012 ha (0.03 acre) of wetland would be irreversibly lost when it is drained. There would, however, be no losses of federally protected threatened or endangered species or critical habitat (Section 4.5.3).

Although not directly related to this proposed action, the Old Melton Valley Road upgrade, which provides access to both the High Flux Isotope Reactor and the proposed site, also resulted in an

irreversible and irretrievable commitment of 4 ha (10 acres) of formerly forest habitat to industrial use. This action was evaluated under a separate NEPA action, and a CX was prepared (see Appendix G).

8. APPLICABLE LAWS AND REGULATIONS

This section identifies and summarizes the major laws, regulations, and requirements that may apply to the different alternatives analyzed in this TRU Waste Treatment Facility EIS. Section 8.1 first lists those laws, regulations, and requirements and describes how those requirements may apply to this project specifically. In addition to laws, regulations, and requirements discussed below, there may be additional project-specific contractual requirements in any contract entered into between DOE and Foster Wheeler if the preferred alternative is selected. The rules and regulations that govern the transportation of all goods and commodities on our nation's highways can be found in 49 *CFR* §100–199 and the Western Governor's Association Waste Isolation Pilot Plant Program Implementation Guide.

8.1 FEDERAL AND STATE ENVIRONMENTAL STATUTES AND REGULATIONS

***National Environmental Policy Act of 1969* (NEPA), as amended (42 U.S.C. §4321 et seq.), the Council on Environmental Quality Implementing Regulations (40 *CFR* §1500 et seq.), and DOE Implementing Regulations (10 *CFR* §1021 et seq.).** This EIS is being prepared to comply with NEPA—the Federal law that requires agencies of the Federal government to study the possible environmental impacts of major Federal actions significantly affecting the quality of the human environment. Although the proposed project is envisioned as one that would be executed primarily by a private entity, this EIS assesses potential impacts before DOE decides whether to proceed with the project. The unique process described in §1021.216 allows DOE to compare potential environmental impacts between approaches suggested by competing offerors when in the process of a private sector procurement. DOE compares these impacts in an Environmental Critique. Those environmental considerations that are detailed in the Critique are made available to the Source Evaluation Board considering the procurement and become a part of the technical criteria against which the competing offerors are evaluated during the procurement process. An Environmental Synopsis (Appendix A.2.), based on the Environmental Critique, was issued and is available to the public. The synopsis documents the considerations given to the environmental factors and environmental consequences from the reasonable alternatives evaluated in the procurement process.

As a result of this competition and the comparison of potential environmental impacts associated with the competing proposals, the Source Evaluation Board chose Foster Wheeler as the winning contractor for Phase I of the project.

This EIS considers whether Foster Wheeler should be allowed to continue with the remainder of the project as it was proposed to DOE, or whether one of the various alternative courses of action is the better decision for DOE. As required by NEPA, the potential environmental impacts of each alternative are analyzed and are being considered in this EIS.

***Atomic Energy Act of 1954* (AEA), as amended (42 U.S.C. §2011 et seq.).** The AEA is the statute that requires DOE to establish standards to protect health and safety with respect to atomic materials. Ordinarily, this is accomplished through DOE orders, standards, and procedures to ensure the safe operation of its facilities. In the project under consideration in this EIS, because the proposed TRU Waste Treatment Facility would not be considered a DOE facility, but instead would be a privately owned and operated facility, DOE orders, standards, and procedures are not necessarily applicable. Nonetheless, DOE remains ultimately responsible for its atomic or nuclear materials. Thus, the environmental, safety, and health standards that would apply to this project are those established in the contract between DOE

and Foster Wheeler, particularly those set out in the Environmental Safety and Health Program Operating Plan that would result from negotiations between Foster Wheeler and DOE.

***Clean Air Act* (CAA), as amended (42 U.S.C. §7401 et seq.).** This Federal statute and its regulations are important to this proposed project and its alternatives. In addition, the Tennessee statute and regulations promulgated under the CAA authority are also important. The heart of the CAA is the National Ambient Air Quality Standards (NAAQS). These are national standards set by the EPA for certain pervasive pollutants; the standards are set at a level designed to protect human health with a conservative margin of safety. States have the primary responsibility of assuring that the air quality within state borders is maintained at a level that meets the NAAQS. This is achieved by states through the establishment of source-specific state requirements that are described in State Implementation Plans. Also under the Federal law is the requirement that new sources of air pollutants meet established New Source Performance Standards (NSPS) set by EPA. These NSPS can be described as design standards, equipment standards, work practices, or operational standards, in addition to the other approach of numerical emissions limitations.

***Resource Conservation and Recovery Act* (RCRA), as amended (42 U.S.C. §6901 et seq.).** This body of law regulates the treatment, storage, and disposal of hazardous wastes. Regulation under these laws is by permit, meaning that the State of Tennessee and EPA study the alternative chosen by DOE and then establish a permit specific to the project that describes how the project is to be carried out. Whether DOE chooses the No Action Alternative, or any other alternative under consideration in this EIS, some type of RCRA permit will be required. As with the CAA discussion above, the discussion in Section 8.3 considers each alternative and the likely RCRA permitting scheme that would exist for each alternative.

***Comprehensive Environmental Response, Compensation, and Liability Act* (CERCLA), as amended (42 U.S.C. §9601 et seq.).** This body of law does not play a predominant role in the proposed project. However, after the removal of the waste from the SWSA 5 North trenches, residual contamination in the surrounding media (soils and groundwater) may still need to be addressed under a subsequent CERCLA action. In addition, from a cumulative impacts perspective, the proposed action would contribute beneficially to the CERCLA cleanup of the Melton Valley Watershed which is an operable unit under the FFA.

***Emergency Planning and Community Right-to-Know Act of 1986* (EPCRA), as amended (42 U.S.C. §11001 et seq.).** This statute requires that inventories of specific chemicals used or stored in either the storage facility or the proposed TRU Waste Treatment Facility would be communicated to the State of Tennessee for purposes of emergency response planning. If DOE chooses the No Action Alternative, the responsibility for this reporting activity will lie with the management and operating (M&O) contractor for the ORNL. Alternatively, if DOE chooses one of the "action" alternatives, Foster Wheeler, or another contractor, will have the responsibility of reporting to the State and preparing emergency response plans.

***Occupational Safety and Health Act of 1970*, as amended (29 U.S.C. §651 et seq.).** If DOE chooses any of the "action" alternatives, compliance with the Occupational Safety and Health Act will be the responsibility of Foster Wheeler, or another contractor, according to Occupational Safety and Health Act standards. If DOE chooses the No Action Alternative, protection of the workforce will remain with the M&O contractor and DOE. The occupational safety requirements of the U.S. Department of Labor's Occupational Safety and Health Administration (OSHA) are not directly applicable to DOE's government-owned, contractor-operated facilities by virtue of Section 4(b)(i) of the Occupational Safety and Health Act of 1970. However, DOE requires a written worker protection program that integrates all requirements contained in DOE 440.1:29 *CFR* Part 1960, *Basic Program Elements for Federal Employee*

Occupational Safety and Health Programs and Related Matters, and other related site-specific worker protection activities.

National Historic Preservation Act of 1966, as amended. Section 106 of the National Historic Preservation Act (NHPA) requires that Federal agencies take into account the effects of their undertakings on properties included in or eligible for inclusion in the *National Register of Historic Places*. To comply with Section 106 of the NHPA, and its implementing regulations at 36 *CFR* 800, DOE-ORO ratified a programmatic agreement among DOE-ORO, the Tennessee State Historic Preservation Officer (SHPO), and the Advisory Council on Historic Preservation concerning management of historical and cultural resources and properties on the ORR. As part of the programmatic agreement, DOE-ORO has developed a cultural resources management plan for the ORR and conducted surveys to identify significant historical properties on the ORR. Compliance with NHPA at the DOE Oak Ridge facilities is achieved and maintained in conjunction with NEPA compliance. The scope of proposed actions is reviewed in accordance with the programmatic agreement and, if warranted, consultation is initiated with the SHPO and the Advisory Council on Historic Preservation, and the appropriate level of documentation is prepared and submitted. Consultation was performed for this project. While no cultural resources are known from the proposed site, should any resources be discovered, the reporting and coordination requirements under this Act would continue to be implemented.

Clean Water Act of 1970, as amended. The various alternatives were examined to ensure that no dredge or fill material would be produced and surface water bodies in the area would not receive any dredge or fill materials. Thus, Section 404(r) of the Act was determined not to apply. The Melton Valley Storage Tanks are classified as wastewater treatment units under the TDEC-administered water program.

Endangered Species Act of 1973, as amended (16 U.S.C. 1931 et seq.). This federal statute and its regulations are important and applicable to the proposed project and its alternatives because three Federally-listed endangered species (gray bat, Indiana bat, and pink mucket pearly mussel) are known to occur near the project area. The Endangered Species Act requires that any threatened or endangered species, and the ecosystems upon which those species depend, be protected from harm. Informal consultations are ongoing with the U.S. Fish and Wildlife Service on those species and the Indiana bat, which has been found in the Cherokee National Forest.

8.2 OTHER PERTINENT REQUIREMENTS

Federal Facility Agreement (FFA). DOE, EPA, and the Tennessee Department of Environment and Conservation (TDEC) entered into the ORR FFA on January 1, 1992. The FFA coordinates remediation activities undertaken on the ORR pursuant to the requirements of CERCLA, RCRA, and NEPA. The FFA established a mechanism to ensure that environmental impacts associated with ORR are thoroughly investigated and remediated, as necessary to protect the public health and welfare and the environment. It is a binding agreement that governs the total processes by which the corrective actions and remedial actions are conducted, from the investigation of individual units through their remediation, and describes procedures for the parties to set annual work priorities and schedules for each process. As such, the FFA is designed to integrate the CERCLA response action process with the corrective measures provisions of Sections 3002(u) and (v) of RCRA, as well as to ensure that remedial actions are in compliance with appropriate, relevant, and applicable requirements (ARARs).

Tennessee Department of Environment and Conservation (TDEC): Commissioner's Order (September 1995). DOE is required to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the treatment and shipment of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin treating legacy TRU sludge

in order to make the first shipment to the Waste Isolation Pilot Plant (a DOE transuranic waste disposal facility) in New Mexico by January 2003.

Executive Order 12898: Environmental Justice. This Executive Order is applicable to DOE for any of the alternatives being considered; therefore, an analysis of the possible impacts to minority and low-income populations has been done in the EIS (Section 4.13).

Executive Order 11988: Floodplain Management. This Executive Order is applicable to DOE for any alternatives being considered; therefore, an analysis of possible impacts to floodplain function has been performed in this EIS (Section 4.5).

Executive Order 11990: Protection of Wetlands. This Executive Order is applicable to DOE for any alternatives being considered; therefore, an analysis of possible impacts to wetlands has been performed in this EIS (Section 4.5).

Executive Order 12088: Federal Compliance with Pollution Control Standards. This Executive Order is applicable to DOE for any alternatives being considered; therefore, pollution control standards were integrated into the various treatment alternatives considered in this EIS.

Executive Order 13007: Indian Sacred Sites. This Executive Order is applicable to DOE for any of the alternatives being considered; therefore, and analysis of the possible impacts to land use, cultural resources, and environmental justice, has been completed in the EIS (Sections 4.1, 4.3, and 4.14).

8.3 REGULATORY COMPARISONS BETWEEN ALTERNATIVES

If the No Action Alternative were selected, DOE is potentially subject to fines and penalties due to noncompliance with the TDEC Commissioner's Order. Any modification to the timeframes specified within the Order for treatment and disposal of the radioactive mixed waste have to be negotiated with TDEC. RCRA permits would likely not be necessary, provided that the Melton Valley Storage Tanks were maintained as wastewater treatment units, which are specifically excluded from RCRA permitting requirements pursuant to 40 *CFR* (c)(2)(v).

Selection of the Preferred Alternative (low-temperature drying) would require an RCRA permit to treat and store the waste. The treatment permit would cover the low-temperature drying operation with additional submissions for storage required. Wastes to be treated consist of characteristic hazardous wastes regulated under RCRA. Due to this fact the LDR standards require that the applicable waste be treated not only for the hazardous characteristic constituents, but also for any underlying constituents found in the universal treatment standards. In addition, a permit for emissions might be required depending upon potential emissions of radionuclides or other contaminants from the operation. In any event a permit to construct will be required under RCRA prior to construction.

TDEC has responsibility for "Waters of the State." Although Aquatic Resource Alteration Permits are not expected (no stream crossings), TDEC has interests in wetland disturbance, and coordination between DOT and TDEC is ongoing on this matter regarding appropriate mitigating measures. TDEC has also been consulted by DOE regarding threatened, endangered, and State-protected species and on archeological and cultural resources.

If DOE selects the Vitrification Alternative, a RCRA permit would be required for operation of the vitrification unit and storage of wastes similar to those required in the discussion relating to the Preferred

Alternative above. Pre-construction permits would also be required prior to construction of the unit(s). The LDR standards applicable to the wastes would have to be addressed as outlined above.

The Cementation Alternative would also require a RCRA permit for treatment and storage of hazardous wastes under RCRA. The LDR standards would address the TDEC Commissioner's Order (dated September 1995). An evaluation of emissions would be required to determine if modification of the ORR NESHAPs permit would be required.

Should the Treatment and Waste Storage at ORNL Alternative be undertaken, a RCRA permit would still be applicable for waste treatment unless the treatment occurred as a part of the wastewater treatment system regulated under the Clean Water Act. In any event modification of the TDEC Commissioner's Order would be required, as the Order requires wastes to be treated and disposed of offsite. In addition, new waste storage units would be required in order to accommodate the treated wastes. Since it is assumed that treatment will render the wastes non-hazardous and meet the requirements of the applicable LDR standards, the wastes, after treatment, would not be required to be stored in a permitted hazardous waste storage unit.

THIS PAGE INTENTIONALLY LEFT BLANK

9. LIST OF PREPARERS

Name	Degree/discipline	Area of expertise
Sharon Bell	M.S. Economics	Socioeconomics and Environmental Justice
Eric Bergman	M.A. English	Community Relations
Karen Billingsley	B.S. Engineering	Waste Management and Environmental Remediation
Bill Cahill	B.S. Geology	U.S. Department of Energy Program Manager
Karen Caywood	Ph.D. Nuclear Engineering	Risk Assessment and Human Health
Michael Deacon	B.S. Environmental Health/ Environmental Studies	Cultural Resources
Lynn Fuson	B.S. Communications	Electronic Document Production
Robert Garber	Ph.D. Chemistry	Air Quality
Sandra Garber	M.S. Chemistry	Transportation
James Groton	M.S. Forestry	Soils and Wetlands
James Hollars	M.S. Geology	Geology and Ground Water
Keith Jefferies	B.S. Chemical Engineering	Alternatives
Arthur McBride	M.S. Mechanical Engineering	Accident Analysis
Diane McDaniel	B.S. Wildlife and Fisheries Science	Terrestrial Ecology
Stephen Mitz	M.S. Aquatic Toxicology	Surface Water and Aquatic Ecology
Douglas Outlaw	Ph.D. Nuclear Physics	Environmental Impact Statement Review
Gary Riner	M.S. Metallurgical Engineering	U.S. Department of Energy Program Manager
Mike Spinazzola	B.S. Chemistry	Alternatives Development
Kathy Spence	A.S. Business Administration	Technical Editing and Document Preparation
Wayne Tolbert	Ph.D. Ecology	Project Manager; Land Use and Cumulative Impacts

THIS PAGE INTENTIONALLY LEFT BLANK

10. DISTRIBUTION

DOE-Oak Ridge Distribution:

Ms. Lorene Sigal
Oak Ridge, TN 37830

Michael Skougard (4)
Department of Energy
Nevada Operations Office
P.O. Box 98518
Las Vegas, NV 89193-8518

Harold Johnson (2)
U.S. Department of Energy
P.O. Box 3090 (Mail Stop GS-224)
Carlsbad, NM 88221

Mr. and Mrs. Ken Campbell
Harriman, TN 37748

Mr. Lynn Noey
City Planning Commission
115 Oklahoma Avenue
Oak Ridge, TN 37830

Dr. Amy S. Fitzgerald
City of Oak Ridge
Assistant Manager for Public Affairs
P.O. Box 1
Oak Ridge, TN 37830

Parker Hardy
Oak Ridge Chamber of Commerce
1400 Oak Ridge Turnpike
Oak Ridge, TN 37830

Lawrence Young
CROET
P.O. Box 2110
Oak Ridge, TN 37830

Frank Munger
The Knoxville News Sentinel
100 Tulsa Road, Suite 21
Oak Ridge, TN 37830

Mr. Paul Carter
Save Our Cumberland Mountains
625 Tarwater Street
Rockwood, TN 37854

Mayor Stanley Justice
Town of Oliver Springs
P.O. Box 303
Oliver Springs, TN 37840

Ted Morton
Mayor, City of Kingston
125 W. Cumberland
Kingston, TN 37763

Joe Wagovich
Director, Public Affairs
Oak Ridge National Laboratory
P.O. Box 2008, MS 6266
Oak Ridge, TN 37831-6266

Dr. Susan Gawarecki
Oak Ridge Local Oversight Committee
136 S. Illinois Avenue, Suite 208
Oak Ridge, TN 37831

David R. Allen
U.S. Department of Energy
Oak Ridge Operations
P.O. Box 2001, SE-32
Oak Ridge, TN 37831

Josh Johnson
c/o Oak Ridge Local Oversight Committee
136 S. Illinois Avenue, Suite 208
Oak Ridge, TN 37831

Larissa Brass
The Oak Ridger
785 Oak Ridge Turnpike
Oak Ridge, TN 37830

The Honorable Dennis Ferguson
23 Legislative Plaza
Nashville, TN 37243

Michael Mobley
TDEC, Division of Radiological Health
L&C Tower, 3rd Floor Annex
Nashville, TN 37243

William Issel
City of Oak Ridge
Community Development Department
P.O. Box 1
Oak Ridge, TN 37831

Kenneth E. Yager
County Executive, Roane County
P.O. Box 643
Kingston, TN 37763

Toye Heape, Executive Director
Tennessee Commission of Indian Affairs
7th Floor, L & C Annex
401 Church Street
Nashville, TN 37243-0439

Ray Emanuel
Native Indian Association
211 Union Street, Suite 932
Nashville, TN 37201

Rex Lynch
County Executive, Anderson County
County Courthouse
100 N. Main Street
Clinton, TN 37716

Carl Scarbrough
Anderson County Commission Chair
County Courthouse
100 N. Main Street
Clinton, TN 37716

Thomas H. Schumpert
County Executive, Knox County
400 Main Avenue
Knoxville, TN 37902

Walter Perry
Community Relations Manager
U.S. Department of Energy
Public Affairs Office
P.O. Box 2001, M-4
Oak Ridge, TN 37831-8502

Herbert Harper
Tennessee Historical Commission
2941 Lebanon Road
Nashville, TN 37214

Paul Boyer
City Manager
P.O. Box 1
Oak Ridge, TN 37831

Mayor Jerry Kuhaida
City of Oak Ridge
P.O. Box 1
Oak Ridge, TN 37831

Mini Rosenthal
League of Women Voters
124 Carnegie Drive
Oak Ridge, TN 37830

Martha Lux
Oak Ridge Public Library
P.O. Box 1
Oak Ridge, TN 37830

Robert Meccia
Foster Wheeler Environmental Corporation
111 Union Valley Road
Oak Ridge, TN 37830

Thomas A. Wojtalik
Tennessee Valley Authority
1101 Market Street
Chattanooga, TN 37402-2801

Ken Arney
State Forester
Department of Agriculture, Forestry Division
P.O. Box 40627
Melrose Station
Nashville, TN 37204

U.S. Department of Energy Reading Room (3)
Oak Ridge Operations Office
Suite 300
230 Warehouse Road
Building 1916-T2
Oak Ridge, TN 37831

Jim Elmore
U.S. Department of Energy
Oak Ridge Operations
P.O. Box 2001, SE-32
Oak Ridge, TN 37831

James C. Widlak
U.S. Fish and Wildlife Service
Endangered Species Consultation
446 Neal Street
Cookeville, TN 38501

Bryan Roy
FWG
Lenoir City, TN 37771

Senator Randy McNally
Tennessee State Senate
302 War Memorial Building
Nashville, TN 37922

James Zitzman
Anderson County Board of Education
District 9
Oak Ridge, TN 37830

Harold M. Draper
TVA NEPA Administration
400 W. Summit Hill Drive, WT 8C-K
Knoxville, TN 37902

Norman Mulvenon
Oak Ridge, TN 37830-7126

Roger Macklin
Tennessee Department of Environment and
Conservation
Division of Radiological Health
Oak Ridge, TN 37830

The Honorable M. Gene Caldwell
113 War Memorial Building
Nashville, TN 37243

Patricia Parr
Oak Ridge National Laboratory
P.O. Box 2008, MS-6038
Oak Ridge, TN 37831-6038

The Honorable H. E. Bittle
115 War Memorial Building
Nashville, TN 37243

J. L. Hampton
Knoxville, TN 37922

Bill Childres
TDEC-DOE-Oversight Office
761 Emory Valley Road
Oak Ridge, TN 37830

David Stair
Tetra Tech NUS
A-600 Oak Ridge Turnpike
Oak Ridge, TN 37830

Craig Turnbow
Knoxville, TN 37922

Herman Weeren
Oak Ridge, TN 37830

Wayne Human
Kingston, TN 37763

Mildred Sears
Oak Ridge, TN 37830

Marc Wendell
Caldwell, NJ 07006

Dottie Eger
Powell, TN 37849

Kevin Meyer
Knoxville, TN 37932

Kathy Hall
Oliver Springs, TN 37840

Rick Arnseth
Knoxville, TN 37922

Leon Jones, Principal Chief
Eastern Band of the Cherokee Indians
P.O. Box 455
Cherokee, NC 28719

Chad Smith
Cherokee Nation Principal Chief
P.O. Box 9192
Tulsa, OK 74157-0192

John Ross, Principal Chief
United Keetoowah Band of Cherokee Indians
P.O. Box 746
Tahlequah, OK 74465-0746

Melissa Copelan
Field Representative
Office of U.S. Representative Zach Wamp
200 Administration Road, #100
Oak Ridge, TN 37830

Jack Copeland
Field Director
Office of U.S. Representative Zach Wamp
200 Administration Road, #100
Oak Ridge, TN 37830

Lincoln Davis
Tennessee State Senator
6-A Legislative Plaza
Nashville, TN 37243

J. B. Hill
Chairman
Scarboro Environmental Justice Oversight Committee
Oak Ridge Branch NAACP
P.O. Box 6165
Oak Ridge, TN 37831-6165

Al Brooks
Oak Ridge Environmental Justice Committee
100 Wiltshire Drive
Oak Ridge, TN 37830-4504

Sandra Reid
Oak Ridge Health Liaison
12 Asbury Lane
Oak Ridge, TN 37830

Jacqueline O. Kittrell
General Counsel
American Environmental Health Studies Project
318 Lynnwood Drive
Knoxville, TN 37918

Janice Stokes
Citizens for Better Health
465 Miller Road
Clinton, TN 37716

Steve Kopp
Chairman
Oak Ridge Site-Specific Advisory Board
P.O. Box 2001
EM-90
Oak Ridge, TN 37831

Luther Gibson
Oak Ridge Site-Specific Advisory Board
P.O. Box 2001
EM-90
Oak Ridge, TN 37831

Randy Gordon
Oak Ridge Site-Specific Advisory Board
P.O. Box 2001
EM-90
Oak Ridge, TN 37831

Ellen Smith
Chair
Oak Ridge Environmental Quality Advisory Board
116 Morningside Drive
Oak Ridge, TN 37830

Joey Brown
President Elect
East Tennessee Environmental Business Association (ETEBA)
P.O. Box 5483
Oak Ridge, TN 37831-5483

Laura Hofman
President
East Tennessee Environmental Business Association (ETEBA)
P.O. Box 5483
Oak Ridge, TN 37831-5483

Gary Santini
Business Development Director
East Tennessee Environmental Business Association (ETEBA)
P.O. Box 5483
Oak Ridge, TN 37831-5483

Dev Joslin
Chair
Advocates for the Oak Ridge Reservation
112 Newcrest Lane
Oak Ridge, TN 37830

William Fulkerson
President
Friends of Oak Ridge National Laboratory
1052 West Outer Drive
Oak Ridge, TN 37830

Harry Williams
President
Coalition for a Healthy Environment
12410 Buttermilk Road
Knoxville, TN 37932

Janet Michel
Coordinator
Coalition for a Healthy Environment
1120 Melton Hill Drive
Clinton, TN 37716

Susana Navarro-Valenti
President
East Tennessee Hispanic Business Association
P.O. Box 9650
Oak Ridge, TN 37831

Rafael Graza Rivers
President
East Tennessee Chapter
Society of Hispanic Professional Engineers
P.O. Box 4042
Oak Ridge, TN 37831

Ed Strain
Roane County Environmental Review Board
198 Mainsail Road
Kingston, TN 37763

Jim Campbell
East Tennessee Economic Council
P.O. Box 5957
Oak Ridge, TN 37831-5957

Jack Barkenbus
Executive Director
Energy, Environment, and Resources Center
University of Tennessee
311 Conference Center Building
Knoxville, TN 37996-4134

Martha Knowles
Information Resource Center (2)
105 Broadway Avenue
Oak Ridge, TN 37830

Center for Environmental Management
Information
P.O. Box 23769
Washington, DC 20026

Chuck Jenkins
Public Affairs Office
Bechtel Jacobs Company
P.O. Box 4699
Oak Ridge, TN 37831

DOE-Headquarters Distribution:

Mr. Andrew Thibadeau
Information Officer
Defense Nuclear Facilities Safety Board
625 Indiana Avenue, N.W., Suite 700
Washington, DC 20004

Mr. Willie R. Taylor
Director
Office of Environmental Policy and Compliance
U.S. Department of the Interior
1849 C Street, N.W., Mailstop 2340
Washington, DC 20240

Mr. Ralph Hutchison
Coordinator
Oak Ridge Environmental Peace Alliance
100 Tulsa Road, Suite 4A
Oak Ridge, TN 37830

Mr. Wayne McCurdy
Director
Nashville Peace Action
P.O. Box 121333
Nashville, TN 37212

Mr. Ronald Lamb
Coalition for Health Concern
10990 Ogden Landing Road
Kevil, KY 42053

Ms. Maureen Eldredge
Program Director
Alliance for Nuclear Accountability
1001 10th Street, N.W., Suite G-2
Washington, DC 20009

Ms. Susan Gordon
Director
Alliance for Nuclear Accountability
1914 North 34th Street, Suite 407
Seattle, WA 98103

Ms. Janet Greenwald
Citizens for Alternatives to Radioactive Dumping
144 Harvard Street, S.E.
Albuquerque, NM 87106

Mr. Jay Coghlan
Program Director
Concerned Citizens for Nuclear Safety
107 Cienega Street
Santa Fe, NM 87501

Mr. Greg Mello
Los Alamos Study Group
212 East Marcy Street, Suite 7
Santa Fe, NM 87501

Dr. Thomas V. Cochran
Director, Nuclear Programs
Natural Resources Defense Council, Inc.
1200 New York Avenue, N.W., Suite 400
Washington, DC 20005

Ms. Kafi Watlington-MacLeod
Los Angeles Office
Natural Resources Defense Council
6310 San Vicente Boulevard, Suite 250
Los Angeles, CA 90048

Mr. Don Hancock
Southwest Research & Information Center
P.O. Box 4524
Albuquerque, New Mexico 87106

Ms. Carolyn C. Drake
Director
Southern States Energy Board
Washington, D.C., Office
P.O. Box 34606
Washington, DC 20043

Ms. Jo Ann Chase
Executive Director
National Congress of American Indians
1301 Connecticut Avenue, N.W., 2nd Floor
Washington, DC 20036

Ms. Camille Mittleholtz
Environmental Team Leader
Office of Transportation Policy
U.S. Department of Transportation
Room 10309, 400 7th Street, S.W.
Washington, DC 20590-001

Ms. Sheree Black
SSAB Coordinator
Oak Ridge Reservation Environmental
Management Site-Specific Advisory Board
P.O. Box 2001, EM-90
55 Jefferson Avenue
Oak Ridge, TN 37831

Mr. Heinz Mueller
Chief, Office of Environmental Assessment
Environmental Accountability Division
Region 4
U.S. Environmental Protection Agency
Atlanta Federal Center
61 Forsyth Street, S.W.
Atlanta, GA 30303

Mr. Michael P. Jansky
Regional Environmental Review Coordinator
Office of Planning and Coordination
Region 6
U.S. Environmental Protection Agency
Mail Code 6EN-XP, 1445 Ross Avenue
Dallas, TX 75202-2733

The Honorable William L. Jenkins
U.S. House of Representatives
1708 Longworth HOB
Washington, DC 20515

The Honorable John J. Duncan, Jr.
U.S. House of Representatives
2400 Rayburn HOB
Washington, DC 20515

The Honorable Zach Wamp
U.S. House of Representatives
423 Cannon HOB
Washington, DC 20515

The Honorable Van Hilleary
U.S. House of Representatives
114 Cannon HOB
Washington, DC 20515

The Honorable Bob Clement
U.S. House of Representatives
2229 Rayburn HOB
Washington, DC 20515

The Honorable Ed Bryant
U.S. House of Representatives
408 Cannon HOB
Washington, DC 20515

The Honorable John S. Tanner
U.S. House of Representatives
1127 Longworth HOB
Washington, DC 20515

The Honorable Harold E. Ford, Jr.
U.S. House of Representatives
325 Cannon HOB
Washington, DC 20515

The Honorable Bart Gordon
U.S. House of Representatives
2368 Rayburn HOB
Washington, DC 20515

The Honorable Ed Whitfield
U.S. House of Representatives
236 Cannon HOB
Washington, DC 20515

The Honorable Ron Lewis
U.S. House of Representatives
223 Cannon HOB
Washington, DC 20515

The Honorable Anne M. Northrup
U.S. House of Representatives
1004 Longworth HOB
Washington, DC 20515

The Honorable Ken Lucas
U.S. House of Representatives
1237 Longworth HOB
Washington, DC 20515

The Honorable Harold Rogers
U.S. House of Representatives
2470 Rayburn HOB
Washington, DC 20515

The Honorable Ernie Fletcher
U.S. House of Representatives
1117 Longworth HOB
Washington, DC 20515

The Honorable Duncan L. Hunter
Chairman, Subcommittee on Military Procurement
Committee on Armed Services
U.S. House of Representatives
Washington, DC 20515

The Honorable Norman Sisisky
Ranking Minority Member
Subcommittee on Military Procurement
Committee on Armed Services
U.S. House of Representatives
Washington, DC 20515

The Honorable Floyd Spence
Chairman, Committee on Armed Services
U.S. House of Representatives
Washington, DC 20515

The Honorable Ike Skelton
Ranking Minority Member
Committee on Armed Services
U.S. House of Representatives
Washington, DC 20515

The Honorable C. W. Bill Young
Chairman, Committee on Appropriations
U.S. House of Representatives
Washington, DC 20515

The Honorable David R. Obey
Ranking Minority Member
Committee on Appropriations
U.S. House of Representatives
Washington, DC 20515

The Honorable Ron Packard
Chairman, Subcommittee on Energy and Water Development
Committee on Appropriations
U.S. House of Representatives
Washington, DC 20515

The Honorable Peter J. Visclosky
Ranking Minority Member
Subcommittee on Energy and Water Development
Committee on Appropriations
U.S. House of Representatives
Washington, DC 20515

The Honorable Thomas J. Bliley, Jr.
Chairman, Committee on Commerce
U.S. House of Representatives
Washington, DC 20515

The Honorable John D. Dingell
Ranking Minority Member
Committee on Commerce
U.S. House of Representatives
Washington, DC 20515

The Honorable Fred Upton
Chairman, Subcommittee on Oversight and Investigations
Committee on Commerce
U.S. House of Representatives
Washington, DC 20515

The Honorable Ron Klink
Ranking Minority Member
Committee on Commerce
Subcommittee on Oversight and Investigations
U.S. House of Representatives
Washington, DC 20515

The Honorable Joe Skeen
U.S. House of Representatives
2302 Rayburn HOB
Washington, DC 20515

The Honorable Heather Wilson
U.S. House of Representatives
226 Cannon HOB
Washington, DC 20515

The Honorable Tom Udall
U.S. House of Representatives
502 Cannon HOB
Washington, DC 20515

The Honorable Shelley Berkley
U.S. House of Representatives
1505 Longworth HOB
Washington, DC 20515

The Honorable Jim Gibbons
U.S. House of Representatives
100 Cannon HOB
Washington, DC 20515

The Honorable William Frist
United States Senate
567 Dirksen Senate Office Building
Washington, DC 20510

The Honorable Fred Thompson
United States Senate
523 Dirksen Senate Office Building
Washington, DC 20510

The Honorable Jim Bunning
United States Senate
818 Hart Senate Office Building
Washington, DC 20510

The Honorable Mitch McConnell
United States Senate
361-A Russell Senate Office Building
Washington, DC 20510

The Honorable Jeff Bingaman
United States Senate
703 Hart Senate Office Building
Washington, DC 20510

The Honorable Pete V. Domenici
United States Senate
328 Hart Senate Office Building
Washington, DC 20510

The Honorable Richard Bryan
United States Senate
269 Russell Senate Office Building
Washington, DC 20510

The Honorable Harry Reid
United States Senate
528 Hart Senate Office Building
Washington, DC 20510

The Honorable Ted Stevens
Chairman, Committee on Appropriations
United States Senate
Washington, DC 20510

The Honorable Robert C. Byrd
Ranking Minority Member
Committee on Appropriations
United States Senate
Washington, DC 20510

The Honorable Pete V. Domenici
Chairman, Subcommittee on Energy and Water Development
Committee on Appropriations
United States Senate
Washington, DC 20510

The Honorable Wayne Allard
Chairman, Subcommittee on Strategic Forces
Committee on Armed Services
United States Senate
Washington, DC 20510

The Honorable Harry Reid
Ranking Minority Member
Subcommittee on Energy and Water Development
Committee on Appropriations
United States Senate
Washington, DC 20510

The Honorable John W. Warner
Chairman, Committee on Armed Services
United States Senate
Washington, DC 20510

The Honorable Carl Levin
Ranking Minority Member
Committee on Armed Services
United States Senate
Washington, DC 20510

The Honorable Mary L. Landrieu
Ranking Minority Member
Subcommittee on Strategic Forces
Committee on Armed Services
United States Senate
Washington, DC 20510

The Honorable Frank H. Murkowski
Chairman, Committee on Energy and Natural Resources
United States Senate
Washington, DC 20510

The Honorable Jeff Bingaman
Ranking Minority Member
Committee on Energy and Natural Resources
United States Senate
Washington, DC 20510

The Honorable Don Nickles
Chairman, Subcommittee on Energy Research and Development
Committee on Energy and Natural Resources
United States Senate
Washington, DC 20510

The Honorable Bob Graham
Ranking Minority Member
Subcommittee on Energy Research and Development
Committee on Energy and Natural Resources
United States Senate
Washington, DC 20510

The Honorable Reginald Pasqual
Governor
Pueblo of Acoma
P.O. Box 309
Acomita, NM 87034

The Honorable Fred Lujan
Governor
Pueblo of Isleta
5 Tribal Rd. 64
Isleta, NM 87022

The Honorable Roland Johnson
Governor
Pueblo of Laguna
P.O. Box 194
Laguna, NM 87026

The Honorable Gary Johnson
Governor of New Mexico
State Capitol Building
Santa Fe, NM 87503

The Honorable Paul E. Patton
Governor of Kentucky
100 State Capitol
Frankfort, KY 40601

The Honorable Kenny Guinn
Governor of Nevada
101 North Carson Street
Carson City, NV 89701

The Honorable Don Sundquist
Governor of Tennessee
State Capitol
Nashville, TN 37243-0001

Mr. Roy Bernal
Chairman
All Indian Pueblo Council
3939 San Pedro, N.E.
Suite E
Albuquerque, NM 87190

Mr. Justin P. Wilson
Deputy to the Governor for Policy
ATTN: Ms. Ellen Williams
Tennessee Department of Environment and Conservation
21st Floor, L & C Tower
401 Church Street
Nashville, TN 37243-0435

Mr. Earl Leming (3)
DOE Oversight
Tennessee Department of Environment and Conservation
761 Emory Valley Road
Oak Ridge, TN 37830-7072

Mr. Peter Maggiore
Secretary
New Mexico Environment Department
1190 St. Francis Drive
P.O. Box 26110
Santa Fe, NM 87502

Mr. James E. Bickford
Secretary, Kentucky Cabinet for Natural Resources and Environmental Protection
Capital Plaza Tower, Fifth Floor
Frankfort, KY 40601

Mr. Bob Logan
Commissioner, Department for Environmental Protection
14 Reilly Road
Frankfort, KY 40601

Ms. Heather K. Elliot
Clearinghouse Coordinator, Nevada State Clearinghouse
Department of Administration
209 East Musser Street, Room 200
Carson City, NV 89701-4298


Mr. Joel Hirshhorn
Policy Studies Director
Natural Resources Policy Studies
National Governors' Association
Hall of the States
444 North Capitol Street, N.W.
Washington, DC 20001-1512

Ms. Elizabeth G. Schneider
Executive Director
Southern Governors' Association
Hall of the States
444 North Capitol Street, N.W., #200
Washington, DC 20001

THIS PAGE INTENTIONALLY LEFT BLANK

11.ORGANIZATIONAL CONFLICTS OF INTEREST STATEMENT

I hereby certify (or as a representative of my organization I hereby certify) that, to the best of my knowledge and belief, no facts exist relevant to any past, present, or currently planned interest or activity (financial, contractual, personal, organizational, or otherwise) which relate to the proposed work; and bear on whether I have (or the organization has) a possible conflict of interest with respect to (1) being able to render impartial, technically sound, and objective assistance or advice, or (2) being given an unfair competitive advantage

Signature: 

Date: October 2, 1998


Name: Yvette Cantrell

Organization: Science Applications International Corporation

Title: Contracts Representative

Organizational Conflicts of Interest Statement

I hereby certify (or as a representative of my organization I hereby certify) that, to the best of my knowledge and belief, no facts exist relevant to any past, present, or currently planned interest or activity (financial, contractual, personal, organizational, or otherwise) which relate to the proposed work; and bear on whether I have (or the organization has) a possible conflict of interest with respect to (1) being able to render impartial, technically sound, and objective assistance or advice, or (2) being given an unfair competitive advantage.

Signature: 

Date: January 14, 2000

Name: Reginald Hall

Organization: Advanced Integrated Management Services, Inc.

Title: President/CEO

INDEX

Accidents, S-24, S-36, 2-45, 3-50, 4-44, 4-45, 4-46, 4-47, 4-48, 4-57, 4-71, 4-73, 4-74, 4-77, 4-82, 4-83, 4-84, 4-87, 4-88, 4-89, 4-90, 4-92, 4-111, 9-1

Aquatic Resources, 3-7, 3-9, 4-74, 4-109, 6-2, 8-4, 9-1

Atmospheric Dispersion, 3-75, 4-71, 4-110, 4-111

Cementation, S-10, S-16, S-17, S-19, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, S-38, 2-5, 2-17, 2-23, 2-24, 2-25, 2-26, 2-27, 2-28, 2-29, 2-30, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 4-3, 4-5, 4-10, 4-13, 4-18, 4-19, 4-21, 4-24, 4-27, 4-29, 4-30, 4-34, 4-35, 4-37, 4-40, 4-43, 4-54, 4-55, 4-56, 4-57, 4-58, 4-63, 4-69, 4-70, 4-76, 4-78, 4-79, 4-80, 4-84, 4-86, 4-88, 4-89, 4-90, 4-91, 4-92, 4-93, 4-98, 4-101, 4-102, 4-105, 4-108, 5-11, 8-5

Clean Air Act, 3-45, 3-57, 4-38, 8-2

Code of Federal Regulations, S-7, S-8, S-11, S-20, S-23, 1-4, 1-7, 2-2, 2-19, 2-31, 3-46, 3-47, 3-52, 3-76, 4-23, 4-24, 4-26, 4-67, 5-1, 8-1, 8-2, 8-3, 8-4

Common Ground Process, 3-75

Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), S-6, S-11, S-23, S-27, S-28, S-29, S-38, S-40, 1-6, 2-6, 2-36, 2-37, 2-38, 3-2, 3-41, 4-14, 4-24, 4-26, 4-31, 5-2, 5-3, 5-5, 5-7, 5-8, 5-9, 5-11, 8-2, 8-3

Construction, S-8, S-11, S-14, S-38, 1-10, 1-11, 2-3, 2-10, 2-17, 2-24, 2-29, 2-47, 3-45, 3-67, 3-73, 4-27, 4-28, 4-29, 4-30, 4-41, 4-52, 4-57, 4-93, 4-96, 4-99, 4-101, 4-104, 4-109, 4-111, 5-2, 5-4, 5-5, 5-10, 5-12, 7-1

Cultural Resources, S-21, 9-1

Current Land Use, 3-1

Decontamination and Decommissioning, S-6, S-7, S-8, S-13, S-15, S-16, S-19, S-21, S-27, S-31, S-35, S-39, 1-3, 1-7, 2-1, 2-2, 2-3, 2-8, 2-10, 2-15, 2-17, 2-24, 2-28, 2-29, 2-30, 2-36, 2-40, 2-44, 3-1, 4-2, 4-3, 4-4, 4-6, 4-9, 4-10, 4-11, 4-12, 4-13, 4-14, 4-17, 4-18, 4-19, 4-20, 4-21, 4-22, 4-23, 4-24, 4-26, 4-27, 4-28, 4-29, 4-30, 4-32, 4-33, 4-34, 4-35, 4-37, 4-38, 4-39, 4-40, 4-41, 4-52, 4-53, 4-55, 4-57, 4-60, 4-65, 4-66, 4-68, 4-69, 4-87, 4-88, 4-93, 4-94, 4-96, 4-99, 4-101, 4-103, 4-104, 7-1

Demographic Characteristics, 3-60

Department of Energy (DOE), S-1, S-2, S-3, S-4, S-5, S-6, S-7, S-8, S-9, S-10, S-11, S-12, S-13, S-15, S-16, S-18, S-20, S-21, S-22, S-38, S-40, S-4, 1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 1-7, 1-8, 1-9, 1-10, 1-11, 2-1, 2-2, 2-3, 2-4, 2-5, 2-6, 2-7, 2-8, 2-11, 2-12, 2-13, 2-19, 2-20, 2-23, 2-26, 2-28, 2-29, 2-31, 2-32, 2-47, 3-1, 3-2, 3-4, 3-8, 3-15, 3-17, 3-21, 3-23, 3-25, 3-31, 3-35, 3-36, 3-41, 3-43, 3-45, 3-46, 3-47, 3-50, 3-51, 3-52, 3-53, 3-58, 3-59, 3-60, 3-64, 3-66, 3-67, 3-68, 3-69, 3-72, 3-73, 3-75, 3-76, 4-1, 4-2, 4-4, 4-6, 4-8, 4-12, 4-13, 4-15, 4-20, 4-23, 4-24, 4-26, 4-27, 4-31, 4-32, 4-33, 4-34, 4-35, 4-36, 4-40, 4-41, 4-42, 4-44, 4-45, 4-46, 4-47, 4-48, 4-49, 4-51, 4-54, 4-60, 4-62, 4-63, 4-65, 4-67, 4-81, 4-82, 4-84, 4-86, 4-87, 4-94, 4-97, 4-100, 4-102, 4-104, 4-108, 4-109, 4-110, 4-111, 5-3, 5-4, 5-7, 5-8, 5-9, 5-10, 5-11, 5-12, 6-1, 6-2, 8-1, 8-2, 8-3, 8-4, 9-1, 10-1, 10-2, 10-3, 10-6, 10-10

Discharge, 1-4, 3-25, 3-27, 3-28, 3-29

DOE Orders, 2-6, 3-8, 4-12, 4-13, 4-65

East Tennessee Technology Park (ETTP), S-1, S-38, 1-1, 3-1, 3-2, 3-31, 3-47, 3-55, 3-56, 3-57, 4-17, 4-72, 4-73, 4-74, 4-76, 4-77, 4-88, 4-89, 4-90, 4-92, 4-111, 5-3, 5-4, 5-10, 5-11

Ecological Resources, S-21, 4-6, 4-105, 5-2, 5-3

Education, 3-2, 3-65, 3-76, 4-111, 10-3

Effluent Discharges, 1-4, 3-25, 3-27, 3-28, 3-29

Electricity, S-34, 2-43, 4-59, 4-62

Employment, 3-66, 3-67, 3-77, 4-95, 4-97, 4-98, 4-100, 4-102, 4-103

Environmental Justice, S-37, 2-46, 3-69, 3-72, 4-105, 4-108, 8-4, 9-1, 10-4

Environmental Protection, S-2, 1-2, 3-74, 4-110, 10-7, 10-10

Exposure Pathways, 3-51

Facility Description, 2-5, 2-7, 2-15, 2-23, 2-28

Federal Facilities Agreement, S-6, S-40, 1-4, 1-6, 4-26, 4-31, 8-2, 8-3

Federal Register, S-3, S-6, S-7, S-41, 1-7, 1-8, 1-11, 2-47, 4-110

Floodplains and Wetlands, S-30, 2-39, 3-39, 3-40, 3-41, 3-74, 4-22, 4-23, 4-24, 4-25, 4-26, 8-4, 9-1

Groundwater, S-22, S-29, 2-38, 3-28, 3-31, 3-36, 3-39, 3-52, 3-75, 4-20, 4-21, 4-22

High Flux Isotope Reactor, S-4, 2-3, 3-2, 4-2, 5-2, 7-1

Housing, 3-65

Human Health, S-23, S-34, 2-43, 4-70, 4-110, 4-111, 9-1

Income, 3-67, 3-68

Infrastructure, 3-65

Land Use, S-21, 3-2, 4-4, 9-1

Latent Cancer Fatalities, S-23, S-24, S-32, S-34, S-36, 2-41, 2-43, 2-45, 4-45, 4-47, 4-48, 4-54, 4-57, 4-58, 4-65, 4-66, 4-70, 4-72, 4-73, 4-74, 4-76, 4-77, 4-79, 4-82, 4-84, 4-85, 4-86, 4-87, 4-88, 4-89, 4-92

Low-Temperature Drying Alternative, S-5, S-11, S-12, S-13, S-14, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, 1-9, 2-7, 2-8, 2-9, 2-10, 2-11, 2-12, 2-13, 2-14, 2-29, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 4-1, 4-2, 4-5, 4-8, 4-9, 4-10, 4-12, 4-16, 4-18, 4-19, 4-20, 4-23, 4-27, 4-28, 4-32, 4-34, 4-35, 4-37, 4-38, 4-39, 4-40, 4-41, 4-46, 4-48, 4-49, 4-50, 4-51, 4-52, 4-54, 4-55, 4-57, 4-58, 4-60, 4-62, 4-63, 4-66, 4-67, 4-68, 4-69, 4-70, 4-76, 4-77, 4-78, 4-79, 4-80, 4-82, 4-83, 4-84, 4-85, 4-87, 4-88, 4-89, 4-90, 4-91, 4-92, 4-93, 4-95, 4-96, 4-97, 4-108, 5-10

Maximally Exposed Individual, S-32, S-34, S-36, 2-41, 2-43, 2-45, 4-38, 4-39, 4-45, 4-47, 4-48, 4-57, 4-64, 4-66, 4-70, 4-72, 4-73, 4-74, 4-77, 4-78, 4-79, 4-80, 4-82, 4-83, 4-84, 4-85, 4-86, 4-87, 4-88, 4-89, 4-91, 4-92, 5-10, 5-11

Mitigation, S-39, 4-17, 4-68, 6-2

National Ambient Air Quality Standards, S-24, 3-43, 3-45, 4-38, 8-2

National Emission Standards for Hazardous Air Pollutants, 3-46, 3-51, 3-52, 3-53, 4-66, 8-5

National Environmental Policy Act (NEPA), S-4, S-5, S-7, S-8, 1-6, 1-7, 1-8, 1-10, 2-1, 2-3, 2-6, 2-7, 3-72, 4-68, 4-110, 5-9, 5-12, 6-1, 7-2, 8-1, 8-3, 10-3

Native Americans, S-21, 3-4, 3-69

No Action Alternative, S-4, S-11, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, S-40, 1-8, 2-5, 2-6, 2-7, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 4-1, 4-2, 4-3, 4-4, 4-5, 4-7, 4-10, 4-11, 4-12, 4-14, 4-15, 4-19, 4-20, 4-22, 4-23, 4-26, 4-31, 4-32, 4-36, 4-38, 4-46, 4-58, 4-59, 4-63, 4-66, 4-70, 4-71, 4-73, 4-74, 4-75, 4-76, 4-77, 4-78, 4-79, 4-81, 4-82, 4-83, 4-84, 4-87, 4-88, 4-89, 4-90, 4-91, 4-93, 4-94, 4-105, 4-108, 8-2, 8-4

Noise, S-24, S-35, 2-44, 3-62, 4-93

Oak Ridge National Laboratory (ORNL), S-1, S-2, S-3, S-4, S-5, S-6, S-7, S-8, S-9, S-10, S-11, S-17, S-18, S-20, S-21, S-22, S-23, S-24, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, S-38, S-39, S-40, S-41, 1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 1-7, 1-8, 1-10, 1-11, 2-1, 2-2, 2-3, 2-4, 2-5, 2-6, 2-7, 2-28, 2-29, 2-31, 2-32, 2-33, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 2-47, 3-1, 3-2, 3-3, 3-5, 3-7, 3-8, 3-11, 3-15, 3-21, 3-23, 3-25, 3-27, 3-28, 3-30, 3-31, 3-41, 3-42, 3-43, 3-44, 3-45, 3-46, 3-48, 3-49, 3-50, 3-51, 3-52, 3-53, 3-54, 3-55, 3-56, 3-57, 3-58, 3-59, 3-60, 3-66, 3-72, 3-73, 3-74, 3-75, 3-76, 4-1, 4-2, 4-3, 4-4, 4-5, 4-10, 4-11, 4-14, 4-15, 4-17, 4-19, 4-20, 4-21, 4-22, 4-26, 4-27, 4-31, 4-32, 4-33, 4-34, 4-35, 4-36, 4-38, 4-41, 4-43, 4-45, 4-51, 4-54, 4-55, 4-57, 4-58, 4-59, 4-62, 4-63, 4-65, 4-66, 4-68, 4-69, 4-70, 4-71, 4-74, 4-76, 4-78, 4-79, 4-80, 4-81, 4-82, 4-84, 4-87, 4-88, 4-89, 4-90, 4-91, 4-93, 4-94, 4-103, 4-104, 4-108, 4-109, 4-110, 4-111, 5-1, 5-2, 5-3, 5-4, 5-5, 5-9, 5-10, 5-11, 5-12, 7-1, 8-2, 8-3, 8-5, 10-1, 10-3, 10-5

Oak Ridge Operations, 1-2, 1-9, 2-3, 2-47, 3-3, 3-4, 3-9, 3-73, 3-76, 5-4, 5-12, 8-3, 10-1, 10-3

Oak Ridge Reservation, S-1, S-2, S-6, S-7, S-22, S-23, S-24, S-38, S-41, 1-1, 1-2, 1-6, 1-10, 2-1, 2-2, 2-7, 3-1, 3-2, 3-3, 3-4, 3-6, 3-9, 3-10, 3-11, 3-12, 3-13, 3-15, 3-16, 3-18, 3-19, 3-21, 3-22, 3-24, 3-25, 3-30, 3-31, 3-32, 3-34, 3-35, 3-41, 3-43, 3-45, 3-46, 3-47, 3-50, 3-51, 3-52, 3-53, 3-54, 3-55, 3-56, 3-57, 3-59, 3-60, 3-63, 3-64, 3-65, 3-66, 3-67, 3-68, 3-69, 3-72, 3-73, 3-74, 3-75, 3-76, 4-9, 4-17, 4-39, 4-45, 4-49, 4-51, 4-52, 4-54, 4-58, 4-59, 4-60, 4-63, 4-64, 4-65, 4-67, 4-72, 4-74, 4-77, 4-78, 4-79, 4-80, 4-81, 4-82, 4-83, 4-84, 4-85, 4-86, 4-87, 4-88, 4-105, 4-106, 4-107, 4-108, 4-110, 4-111, 5-2, 5-4, 5-5, 5-8, 5-10, 5-11, 5-12, 8-3, 8-5, 10-5, 10-7

Operations, S-2, S-24, 2-20, 2-47, 3-46, 3-57, 3-73, 3-75, 3-76, 4-48, 4-52, 4-55, 4-96, 4-99, 4-101, 4-104, 10-1

Parks, Preserves, and Recreational Resources, 3-2

Past Land Use, 3-1

Permits and Consultations, 1-4, 3-25, 3-27, 3-28, 3-46, 3-57, 6-2, 8-3, 8-4, 10-3

Probability of Cancer Fatality, S-34, S-36, 2-43, 2-45

Proposed Action, S-6, S-39, 2-1, 2-15

Radiation, 4-8, 4-66, 4-67

Regulations, S-7, S-39, 8-1

Resource Conservation and Recovery Act (RCRA), S-2, S-3, S-9, S-10, S-11, S-13, S-14, S-15, S-16, S-40, 1-2, 1-3, 1-4, 1-5, 1-7, 2-3, 2-4, 2-5, 2-6, 2-8, 2-10, 2-11, 2-12, 2-13, 2-15, 2-16, 2-17, 2-19, 2-33, 3-51, 4-15, 4-23, 4-31, 4-32, 4-36, 4-60, 5-8, 8-2, 8-3, 8-4, 8-5

Roads, 3-17

Safety, 3-59, 3-72, 3-73, 3-76, 4-47, 4-71, 4-73, 4-76, 4-109, 8-2, 10-6

Seismicity, S-22, 1-4, 3-20, 3-21, 3-23, 3-76, 4-12, 4-13, 4-14, 4-71

Soils, 3-15, 3-17, 3-18, 9-1

Solid Waste Storage Area 5 North, S-6, S-11, S-22, S-27, S-28, S-29, S-30, S-31, S-38, S-40, 1-5, 1-6, 2-5, 2-6, 2-36, 2-37, 2-38, 2-39, 2-40, 3-15, 3-36, 3-39, 4-1, 4-2, 4-7, 4-8, 4-9, 4-10, 4-11, 4-12, 4-13, 4-14, 4-15, 4-16, 4-17, 4-18, 4-19, 4-20, 4-21, 4-22, 4-23, 4-24, 4-26, 4-27, 4-31, 4-34, 4-35, 4-41, 4-42, 4-46, 4-47, 4-57, 4-66, 4-70, 5-5, 5-7, 5-8, 5-9, 8-2

State Historic Preservation Officer (SHPO), S-21, 3-4, 4-4, 6-1, 8-3

Steam, S-38, 2-10, 3-28, 3-57, 4-9, 4-28, 4-62, 5-3, 5-10

Storage, S-3, S-4, S-5, S-6, S-7, S-8, S-9, S-10, S-11, S-12, S-14, S-16, S-18, S-19, S-20, S-21, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, S-38, S-39, S-40, S-41, 1-3, 1-4, 1-5, 1-6, 1-7, 1-8, 1-10, 1-11, 2-2, 2-3, 2-5, 2-6, 2-7, 2-8, 2-9, 2-10, 2-11, 2-15, 2-17, 2-18, 2-23, 2-24, 2-28, 2-30, 2-31, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 2-47, 3-1, 3-2, 3-18, 3-39, 3-41, 3-60, 3-73, 3-74, 4-1, 4-2, 4-3, 4-4, 4-5, 4-7, 4-8, 4-10, 4-11, 4-12, 4-14, 4-15, 4-16, 4-17, 4-19, 4-20, 4-21, 4-22, 4-23, 4-26, 4-27, 4-31, 4-33, 4-34, 4-35, 4-36, 4-37, 4-41, 4-43, 4-55, 4-57, 4-58, 4-59, 4-60, 4-63, 4-66, 4-69, 4-70, 4-71, 4-73, 4-74, 4-75, 4-76, 4-77, 4-78, 4-79, 4-80, 4-81, 4-82, 4-84, 4-87, 4-88, 4-89, 4-90, 4-91, 4-92, 4-93, 4-94, 4-103, 4-104, 4-105, 4-108, 4-109, 4-110, 5-2, 5-3, 5-5, 5-8, 5-9, 5-10, 5-11, 5-12, 6-2, 7-1, 8-3, 8-4, 8-5

Stratigraphy, 3-12, 3-34

Structure, 3-13

Surface Water, 3-23, 4-14, 4-19, 9-1

Tennessee Ambient Air Quality Standards, 3-45

Tennessee Department of Environment and Conservation, S-2, S-4, S-5, S-6, S-10, S-11, S-18, S-23, S-40, 1-2, 1-4, 1-5, 1-6, 1-8, 2-1, 2-4, 2-28, 3-43, 3-45, 3-46, 3-57, 3-64, 4-31, 4-32, 4-36, 5-3, 5-8, 6-2, 8-3, 8-4, 8-5, 10-2, 10-3

Tennessee Valley Authority, S-23, 3-3, 3-50, 5-3, 10-2, 10-3

Terrestrial Resources, 3-4

Threatened and Endangered (T&E) Species, 3-6, 3-9

Toxic Substances Control Act, S-38, 3-57, 5-3, 5-10

Transportation, S-11, S-23, S-32, S-33, 1-5, 2-41, 2-42, 3-46, 3-47, 3-48, 3-49, 3-50, 3-67, 3-75, 4-41, 4-44, 4-46, 4-47, 4-48, 4-51, 4-54, 4-55, 4-57, 9-1, 10-6

Transuranic, S-2, S-3, S-4, S-5, S-6, S-7, S-8, S-10, S-11, S-12, S-13, S-14, S-15, S-16, S-17, S-18, S-19, S-20, S-21, S-22, S-23, S-31, S-33, S-36, S-38, S-39, S-40, S-41, 1-2, 1-3, 1-5, 1-6, 1-7, 1-8, 1-10, 1-11, 2-1, 2-3, 2-4, 2-5, 2-6, 2-7, 2-8, 2-10, 2-11, 2-12, 2-13, 2-15, 2-17, 2-19, 2-24, 2-26, 2-28, 2-29, 2-30, 2-31, 2-32, 2-40, 2-42, 2-45, 2-47, 3-1, 3-2, 3-3, 3-4, 3-5, 3-6, 3-7, 3-9, 3-11, 3-12, 3-13, 3-15, 3-17, 3-18, 3-21, 3-23, 3-24, 3-25, 3-26, 3-30, 3-34, 3-36, 3-39, 3-40, 3-41, 3-42, 3-43, 3-46, 3-47, 3-50, 3-60, 3-61, 3-62, 3-72, 3-74, 3-75, 4-1, 4-2, 4-4, 4-6, 4-7, 4-10, 4-11, 4-12, 4-13, 4-14, 4-19, 4-20, 4-22, 4-23, 4-24, 4-25, 4-26, 4-27, 4-28, 4-29, 4-30, 4-31, 4-32, 4-33, 4-34, 4-35, 4-36, 4-37, 4-38, 4-39, 4-41, 4-42, 4-43, 4-44, 4-48, 4-49, 4-50, 4-51, 4-53, 4-54, 4-55, 4-56, 4-57, 4-58, 4-59, 4-62, 4-68, 4-71, 4-73, 4-75, 4-76, 4-78, 4-79, 4-81, 4-103, 4-109, 4-110, 5-1, 5-2, 5-3, 5-4, 5-7, 5-8, 5-9, 5-10, 5-11, 5-12, 6-1, 8-1, 8-2, 8-3

Vitrification, S-4, S-10, S-14, S-15, S-16, S-19, S-26, S-27, S-28, S-29, S-30, S-31, S-32, S-33, S-34, S-35, S-36, S-37, S-39, 1-8, 2-5, 2-15, 2-16, 2-17, 2-20, 2-21, 2-22, 2-24, 2-26, 2-28, 2-29, 2-30, 2-35, 2-36, 2-37, 2-38, 2-39, 2-40, 2-41, 2-42, 2-43, 2-44, 2-45, 2-46, 4-3, 4-5, 4-9, 4-10, 4-13, 4-17, 4-18, 4-21, 4-24, 4-27, 4-29, 4-30, 4-33, 4-34, 4-35, 4-37, 4-40, 4-51, 4-52, 4-53, 4-58, 4-62, 4-63, 4-68, 4-69, 4-70, 4-76, 4-77, 4-79, 4-80, 4-84, 4-85, 4-87, 4-88, 4-89, 4-90, 4-91, 4-92, 4-93, 4-98, 4-99, 4-100, 4-105, 4-108, 8-4

Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement, S-2, S-7, S-21, S-41, 1-7, 1-10, 1-11, 2-32, 2-47, 3-47, 3-73, 4-1, 4-44, 4-45, 4-48, 4-51, 4-54, 6-1

Waste Management, S-6, S-7, S-10, S-21, S-23, S-31, S-41, 1-7, 1-10, 1-11, 2-4, 2-7, 2-8, 2-19, 2-32, 2-40, 2-47, 3-47, 3-73, 3-75, 3-76, 4-1, 4-27, 4-36, 4-44, 4-49, 4-71, 4-73, 4-76, 4-109, 4-110, 4-111, 5-12, 6-2, 9-1

Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste, S-7, S-10, S-38, S-41, 1-7, 1-10, 1-11, 2-4, 2-47, 3-47, 4-44, 4-45, 4-46, 4-48, 4-50, 4-53, 4-56, 4-111, 5-10, 6-1

Water Quality, S-22, 4-16, 5-12

Wetlands, S-30, 2-39, 3-39, 3-40, 3-41, 3-74, 4-22, 4-23, 4-24, 4-25, 4-26, 8-4, 9-1

White Oak Creek, S-22, S-29, S-30, S-38, 1-2, 1-5, 2-38, 2-39, 3-7, 3-8, 3-9, 3-17, 3-23, 3-24, 3-25, 3-26, 3-30, 3-31, 3-36, 3-39, 3-41, 3-55, 4-6, 4-9, 4-15, 4-16, 4-17, 4-18, 4-19, 4-20, 4-22, 4-23, 4-24, 4-26, 4-65, 4-73, 4-75, 5-2, 5-3, 5-5, 5-7, 5-9, 6-1

White Oak Creek Embayment, 3-23, 5-5, 5-7

White Oak Lake, S-22, 3-7, 3-8, 3-9, 3-23, 3-25, 3-30, 3-31, 3-36, 3-41, 3-55, 4-6, 4-7, 4-9, 4-15, 4-16, 4-17, 4-18, 4-19, 4-75, 5-2, 5-3, 5-7, 5-8, 6-1

APPENDIX A

NOTICE OF INTENT, ENVIRONMENTAL SYNOPSIS, AND PUBLIC ISSUES

THIS PAGE INTENTIONALLY LEFT BLANK

Appendix A contains a copy of the Notice of Intent to prepare this Environmental Impact Statement, a copy of the Environmental Impact Statement, a copy of the Environmental Synopsis which was prepared as part of the selection process for Foster Wheeler and the preferred alternative of low-temperature drying proposed by Foster Wheeler, and a summary of issues raised during the public scoping process for this Environmental Impact Statement.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX A.1

NOTICE OF INTENT

THIS PAGE INTENTIONALLY LEFT BLANK

format (*e.g.*, Braille, large print, audiotape, or computer diskette) on request to the contact person listed in the preceding paragraph.

Individuals with disabilities may obtain a copy of the application package in an alternate format, also, by contacting that person. However, the Department is not able to reproduce in an alternate format the standard forms included in the application package.

Electronic Access to This Document

You may view this document, as well as all other Department of Education documents published in the **Federal Register**, in text or portable document format (pdf) on the Internet at either of the following sites:

http://ocfo.ed.gov/fedreg.hmt
http://www.ed.gov/news.html

To use the pdf you must have the Adobe Acrobat Reader Program with Search, which is available free at either of the previous sites. If you have any questions about using the pdf, call the U.S. Government Printing Office at (202) 512-1530, or, toll free at 1-888-293-6498.

Dated: January 22, 1999.

Gerald N. Tirozzi,

Assistant Secretary for Elementary and Secondary Education.

[FR Doc. 99-1866 Filed 1-26-99; 8:45 am]

BILLING CODE 4000-01-M

DEPARTMENT OF ENERGY

Notice of Intent To Prepare an Environmental Impact Statement for a Transuranic Waste Treatment Facility at Oak Ridge, TN

AGENCY: Department of Energy.

ACTION: Notice of Intent.

SUMMARY: The U. S. Department of Energy (DOE) intends to prepare an Environmental Impact Statement (EIS) under the National Environmental Policy Act (NEPA) and its implementing regulations on the proposed construction, operation, and decontamination/decommissioning of a Transuranic (TRU) Waste Treatment Facility at Oak Ridge, Tennessee. The four types of TRU waste that would be treated at the facility are remote-handled (RH)-TRU waste sludge, low-level radioactive waste supernatant associated with the sludge, contact-handled (CH)-TRU/alpha low-level radioactive waste solids, and RH-TRU/alpha low-level radioactive waste solids. Because much of the waste displays Resource Conservation and Recovery Act (RCRA) characteristics, the proposed facility would be permitted under RCRA. All the waste DOE proposes to treat currently is stored at Oak Ridge National Laboratory (ORNL) in Oak Ridge, Tennessee. The proposed site for the treatment facility is adjacent to the Melton Valley Storage Tanks, where the waste sludge and supernatant are being stored.

DOE invites the public, organizations, and agencies to present oral or written comments concerning the scope of the EIS, including the issues the EIS should address and the alternatives it would analyze.

DATES: The public scoping period begins on the date of this publication and continues until February 26, 1999. Written comments submitted by mail should be postmarked by the closing date to ensure consideration. Comments mailed after that date will be considered to the extent practicable.

DOE will conduct public scoping meetings to assist in defining the appropriate scope of the EIS and to identify significant environmental issues to be addressed. These meetings will be held at the following time(s) and location:

February 11, 1999, American Museum of Science and Energy, 300 South Tulane Avenue, Oak Ridge, Tennessee 37830; Time: 6:30-9:30 p.m.

February 16, 1999, American Museum of Science and Energy, 300 South Tulane Avenue, Oak Ridge, Tennessee 37830; Time: 6:30-9:30 p.m.

ADDRESSES: Please direct comments or suggestions on the scope of the EIS, requests to speak at the public scoping meetings, requests for special accommodations to enable participation at scoping meetings (e.g., interpreter for the hearing-impaired), and questions concerning the project to: Gary L. Riner, U.S. Department of Energy, Oak Ridge Operations Office, P.O. Box 2001, Oak Ridge, Tennessee 37831, telephone: (423) 241-3498, facsimile: (423) 576-5333, or e-mail rinerg@oro.doe.gov.

For general information on the DOE NEPA process, please contact: Carol M. Borgstrom, Director, Office of NEPA Policy and Assistance, EH-42, U.S. Department of Energy, 1000 Independence Avenue, SW, Washington, D.C. 20585-0119, telephone: (202) 586-4600 or leave a message at (800) 472-2756.

SUPPLEMENTARY INFORMATION:

Background

Research and development activities supporting national defense and energy initiatives have been performed at ORNL since its construction in eastern Tennessee in 1943, generating radioactive and hazardous waste legacies that now pose environmental concerns. Meeting the cleanup challenges associated with legacy TRU waste is a high priority for the DOE, Tennessee Department of Environment and Conservation (TDEC), and stakeholders. The TRU waste treatment project at the ORNL will be an important component of DOE cleanup efforts at the site.

TRU waste is radioactive waste that is not classified as high-level radioactive waste and that contains more than 100 nanocuries per gram of alpha-emitting transuranic (atomic numbers greater than 92) isotopes with half-lives greater than 20 years. Alpha low-level radioactive waste contains alpha-emitting transuranic isotopes with half-lives greater than 20 years at concentrations less than 100 nanocuries per gram.

The TRU waste to be treated also contains beta- and gamma-emitting isotopes in addition to alpha-emitting isotopes, which result in its classification as either CH (surface dose rate of 200 mrem/hr or less) or RH (surface dose rate of greater than 200 mrem/hr).

Solid waste at ORNL is a heterogeneous mixture consisting of paper, glass, rubber, cloth, plastic, and metal from glove boxes, fuel processing, hot cells, and reactors. Solid waste is currently packaged in metal boxes, drums and concrete overpacks, and stored in RCRA permitted facilities. Most of the solid waste containers do not meet current Department of Transportation regulations and would require repackaging prior to shipment.

Based on generator records, the solid waste has been classified as either TRU or alpha low-level radioactive waste. However, because the nature of the solid waste can only be confirmed after retrieval and characterization, solid wastes addressed in this Notice of Intent are characterized as "TRU/alpha low-level radioactive waste" to note the current uncertainty. The solid waste may contain RCRA characteristic metals, but generator records do not indicate the presence of any RCRA listed constituents. The supernatant, the liquid layer covering the sludge in the tanks, is considered a low-level waste but is not considered hazardous under the RCRA definitions.

Approximately 62 percent of the legacy TRU wastes are currently stored in 50 year-old tanks. The remaining 38 percent of the legacy TRU wastes are currently stored in subsurface trenches, vaults, and metal buildings.

Approximate quantities of the four primary waste streams needing

treatment are: 900 m^3 of RH–TRU sludge, located in the tanks; 1600 m^3 of low-level supernatant, located in tanks; 550 m^3 of RH–TRU waste/alpha low-level radioactive waste solids in vaults and trenches; and 1,000 m^3 of CH–TRU waste/alpha low-level radioactive waste solids in metal buildings.

Purpose and Need for Agency Action

The DOE needs to ensure the safe and efficient retrieval, processing, certification, and disposition of legacy TRU waste at ORNL. There are legal mandates for DOE to address TRU waste management needs. DOE has been directed by the TDEC and the U. S. Environmental Protection Agency (EPA) to address environmental issues including disposal of its legacy TRU waste. DOE is under a Commissioner's Order issued by the State of Tennessee (September 1995) to implement the Site Treatment Plan, under the Federal Facility Compliance Act, that mandates specific requirements for the processing and disposal of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin processing TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant (WIPP) (a DOE transuranic waste disposal facility) in New Mexico by January 2003. In addition, two Records of Decision issued in connection with the Federal Facility Agreement among EPA, TDEC, and DOE, under the Comprehensive Environmental Response, Compensation, and Liability Act, mandate that the waste from the Gunite and Associated Tanks Project (in Bethel Valley) and the Old Hydrofracture Facility Tanks Project (in Melton Valley) be processed and disposed of along with the TRU waste from the Melton Valley Storage Tanks.

Waste retrieval operations are currently underway to prepare ORNL TRU waste storage tanks for closure, and the waste removed from the Bethel Valley tanks will be consolidated in the Melton Valley Storage Tanks before processing. After processing, TRU waste must be certified for shipment to and disposal at WIPP, and any low-level radioactive waste resulting from TRU waste processing must be certified for shipment to and disposal at the DOE site(s) to be selected in a Record of Decision for the Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste (WM PEIS) (DOE/EIS–0200–F, May 1997). No facilities for processing TRU/alpha low level radioactive waste exist at the Oak Ridge Reservation.

Proposed Action and Alternatives

Proposed Action

Under the proposed action, a waste treatment facility for the ORNL legacy TRU waste would be constructed, operated, and decontaminated/decommissioned under a contract awarded to the Foster Wheeler Environmental Corporation. Under the contract, the action would be carried out in four phases: Phase I, Licensing and Permitting (currently in process, includes DOE's NEPA analysis and contractor design activities); Phase II, Construction and Pre-Operational Testing; Phase III, Treatment and Packaging; Phase IV, Decontamination and Decommissioning. If the current NEPA review results in the selection of an alternative other than the proposed action, Phase II (Construction and Pre-Operational Testing) of the contract would not be executed. Waste volume reduction would be a major component of the processing in order to minimize waste generation and costs and to conserve resources. After processing, the waste would be certified for disposal as either low-level radioactive, alpha low-level radioactive, or TRU waste, as discussed above.

All activities associated with the proposed action must be performed safely and in compliance with applicable Federal and state regulatory requirements. Foster Wheeler Environmental Corporation would be responsible for achieving compliance with all applicable environmental, safety and health laws and regulations, and regulatory agencies would be responsible for monitoring the Corporation's compliance. The State of Tennessee and EPA would regulate the Corporation according to permits under their purview. DOE would regulate occupational safety and health and nuclear safety according to specific environment, safety and health requirements.

DOE would lease the Melton Valley Storage Tanks, subject to notification of EPA and the State of Tennessee, and an adjacent land area totaling approximately 10 acres to Foster Wheeler Environmental Corporation for construction of the facility. The Melton Valley Storage Tanks are separate from ORNL's main plant area. The proposed treatment facility would be fenced, with controlled access to Tennessee State Highway 95.

Foster Wheeler Environmental Corporation has proposed a process of evaporating and drying the sludges and supernatant that is flexible enough to address a wide range of waste properties. The low temperature treatment would reduce waste volume, generate additional waste as a result of treatment, and meet specified waste acceptance criteria. To ensure that the waste would meet RCRA Land Disposal Restrictions (LDR) standards, additives that reduce the solubility of the RCRA metals in the waste would be added to form stable compounds. The dried stabilized sludge would pass the Toxic Characteristic Leaching Procedures and no longer exhibit a RCRA characteristic. The relatively inexpensive stabilization process could be easily performed during the overall treatment process and would result in waste that meets the LDR treatments standards and could be stored on site, if necessary, pending disposal. The supernatant would be dried for final disposal at an approved DOE low-level radioactive waste disposal site consistent with a WM PEIS Record of Decision yet to be issued for low-level radioactive waste. Segregation of the supernatant from the sludge would result in significant life-cycle cost avoidance when compared to disposal at WIPP.

The proposed action includes no treatment for the bulk of the solid waste that is not regulated under RCRA other than repackaging with some compaction to meet the 50% volume reduction required by the contract. The solid waste would be better characterized during the repackaging effort to achieve final waste form certification before disposal. RCRA characteristic items would be isolated for macroencapsulation or other processing techniques to comply with applicable RCRA LDRs. This would ensure that alpha low-level radioactive waste would meet non-RCRA low-level waste disposal requirements and comply with RCRA LDRs if interim storage is required on site.

Alternatives

DOE will consider alternatives to the proposed action, such as shipment of TRU wastes to other DOE sites for processing, alternative technologies for sludge waste, and no action. Under a shipment alternative, DOE would ship CH-TRU/alpha low-level and RH–TRU/alpha low-level radioactive waste solids to other DOE site(s) for processing. Most of the solid waste containers do not meet current Department of Transportation regulations and would require repackaging prior to shipment. After processing, the waste would be certified for disposal as either low-level radioactive, alpha low-level radioactive, or TRU waste and transported to appropriate disposal facilities. Under a treatment alternative, DOE would process RH–TRU sludge waste and the

low-level radioactive waste supernatant associated with the sludge by using vitrification or grouting technology. This alternative would include no treatment for the bulk of the solid waste that is not regulated under RCRA other than repackaging with some compaction. The solid waste would be better characterized during the repackaging effort to achieve final waste form certification before disposal. RCRA characteristic items would be isolated for macroencapsulation or other processing techniques to comply with applicable RCRA LDRs. This would ensure that alpha low-level radioactive waste would meet non-RCRA low-level waste disposal requirements and comply with RCRA LDRs if interim storage is required on site.

As required by the Council on Environmental Quality's (CEQ's) Regulations for Implementing the Procedural Provisions of NEPA (40 CFR Parts 1500–1508), a no action alternative will be evaluated. Under this alternative, DOE would continue to store the TRU waste in tanks, subsurface trenches, vaults, and metal buildings, as discussed in the Background section, above.

Preliminary Environmental Analysis

DOE incorporated environmental information very early in the project planning. Prior to selection of the contractor, DOE held two public meetings with stakeholders, had ongoing discussions with regulators, prepared a characterization report for the site of the proposed action, and sponsored an independent study of treatment technologies and contracting alternatives known as the Parallax study (ORNL/M–4693, Feasibility Study for Processing ORNL TRU Waste in Existing and Modified Facilities, September 15, 1995) (available in the public reading rooms listed below). Bidders were required to submit environmental data, and DOE prepared an environmental critique (under 10 CFR 1021.216) for consideration in the procurement process. A synopsis of this critique has been filed with the EPA and made available to the public.

NEPA Process

The EIS for the proposed project will be prepared according to the National Environmental Policy Act of 1969, the CEQ NEPA regulations, and DOE's NEPA Implementing Procedures (10 CFR Part 1021).

Through the NEPA process begun with this Notice of Intent, DOE will continue to analyze environmental impacts and evaluate alternative actions while Phase I of the awarded contract is underway. The EIS for the proposed TRU waste treatment will incorporate pertinent analyses performed as part of the DOE's WIPP Disposal Phase Supplemental Environmental Impact Statement (DOE/EIS–0026–S–2, September, 1997) and the WM PEIS. Processing the ORNL TRU waste in Oak Ridge is consistent with the Records of Decision issued for management of the transuranic waste for the aforementioned Environmental Impact Statements (63 FR 3624 and 3629, respectively, January 23, 1998). The disposal of low-level radioactive waste included in this contract will be consistent with the WM PEIS ROD for low-level waste that is yet to be issued.

The contract allows DOE and Foster Wheeler Environmental Corporation to identify during Phase I other potential waste streams for processing at this facility. Any such waste streams would be considered in this EIS and subject to further NEPA review, as appropriate.

Preliminary Identification of EIS Issues

DOE intends to address the following issues when assessing the potential environmental impacts of the alternatives in this EIS. DOE invites comment on these and any other issues that should be addressed in the EIS.

—Potential effects on air, soil, and water quality from normal operations and reasonably foreseeable accidents.
—Potential effects on the public, including minority and low-income populations, and workers from exposure to radiological and hazardous materials from normal operations and reasonably foreseeable accidents.
—Compliance with applicable Federal, state, and local requirements and agreements.
—Pollution prevention, waste minimization, and energy and water use reduction technologies to eliminate or reduce use of energy, water, and hazardous substances and to minimize environmental impacts.
—Potential socioeconomic impacts, including potential impacts associated with the workforce needed for operations.
—Potential cumulative environmental impacts of past, present, and reasonably foreseeable future operations, including impacts from using the proposed facility for potential waste streams other than those currently being proposed.
—Potential irreversible and irretrievable commitment or resources.

Related NEPA Reviews

Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste (DOE/EIS–0200–F, May 1997); Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement (DOE/EIS–0026–S–2, September 1997); and Advanced Mixed Waste Treatment Project at the Idaho National Engineering and Environmental Laboratory Environmental Impact Statement (DOE/EIS–0290–F, to be issued January 1999).

Scoping Meetings

The purpose of this NOI is to encourage early public involvement in the EIS process and to solicit public comments on the proposed scope of the EIS, including the issues and alternatives it would analyze. DOE plans to hold public scoping meetings in Oak Ridge to solicit both oral and written comments from interested parties. See **DATES** and **ADDRESSES**, above, for the times and locations of these meetings.

DOE will designate a presiding officer for the scoping meetings. The scoping meetings will not be conducted as evidentiary hearings, and there will be no questioning of the commentors.

However, DOE personnel may ask for clarification of statements to ensure that they fully understand the comments and suggestions. The presiding officer will establish the order of speakers. At the opening of each meeting, the presiding officer will announce any additional procedures necessary for the conduct of the meetings. If necessary to ensure that all persons wishing to make a presentation are given the opportunity, a five-minute limit may be applied for each speaker, except for public officials and representatives of groups who would be allotted ten minutes each. Comment cards will also be available for those who would prefer to submit written comments.

DOE will make transcripts of the scoping meetings and other environmental and project-related materials available for public review in the following reading rooms:

U.S. Department of Energy, Freedom of Information Public Reading Room, Forrestal Building, Room 1 E–190, 1000 Independence Avenue, SW, Washington, DC 20585, Telephone: (202) 586–3142

U.S. Department of Energy, Oak Ridge Operations Office, 200 Administration Road, Room G–217, Oak Ridge, Tennessee 37831, Telephone: (423) 241–4780.

EIS Schedule

The draft EIS is scheduled to be published by August 1999. A 45-day comment period on the draft EIS is planned, and public hearings to receive comments will be held approximately one month after issuance. Availability of the draft EIS, the dates of the public comment period, and information about the public hearings will be announced in the **Federal Register** and in the local news media.

The final EIS, which will incorporate public comments received on the draft EIS, is scheduled for January 2000. A Record of Decision would be issued no sooner than 30 days after a notice of availability of the final EIS is published in the **Federal Register**.

Signed in Washington, DC, this 21st day of January 1999.

Peter N. Brush,

Principal Deputy Assistant Secretary Environment, Safety and Health.

[FR Doc. 99-1856 Filed 1-26-99; 8:45 am]

BILLING CODE 6450-01-P

DEPARTMENT OF ENERGY

Federal Energy Regulatory Commission

[Docket No. CP99-156-000]

Columbia Gas Transmission Corporation; Notice of Request Under Blanket Authorization

January 21, 1999.

Take notice that on January 14, 1999, Columbia Gas Transmission Corporation (Columbia), 12801 Fair Lakes Parkway, Fairfax, Virginia 22030-1046, filed in Docket No. CP99-156-000 a request pursuant to Sections 157.205 and 157.216, of the Commission's Regulations under the Natural Gas Act (18 CFR 157.205, 157.216) for authorization to abandon approximately 0.05 miles of 4- and 8-inch pipeline and a point of delivery under Columbia's blanket certificate issued in Docket No. CP83-76-000 pursuant to Section 7 of the Natural Gas Act, all as more fully set forth in the request that is on file with the Commission and open to public inspection.

Columbia requests authorization to abandon approximately 0.05 miles of 4- and 8-inch pipeline and a point of delivery to Columbia Gas of Pennsylvania, Inc. (CPA), all located in Elk County, Pennsylvania. Columbia states that the pipeline will be abandoned in place and all above ground facilities will be removed. CPA states that it no longer requires service from this point of delivery.

Any person or the Commission's staff may, within 45 days after issuance of the instant notice by the Commission, file pursuant to Rule 214 of the Commission's Procedural Rules (18 CFR 385.214) a motion to intervene or notice of intervention and pursuant to Section 157.205 of the Regulations under the Natural Gas Act (18 CFR 157.205) a protest to the request. If no protest is filed within the time allowed therefor, the proposed activity shall be deemed to be authorized effective the day after the time allowed for filing a protest. If a protest is filed and not withdrawn within 30 days after the time allowed for filing a protest, the instant request shall be treated as an application for authorization pursuant to Section 7 of the Natural Gas Act.

David P. Boergers,

Secretary.

[FR Doc. 99-1819 Filed 1-26-99; 8:45 am]

BILLING CODE 6717-01-M

DEPARTMENT OF ENERGY

Federal Energy Regulatory Commission

[Docket No. CP99-155-00]

Columbia Gas Transmission Corporation; Notice of Application

January 21, 1999.

Take notice that on January 13, 1999, Columbia Gas Transmission Corporation (Columbia), filed in Docket No. CP99-155-000 an application pursuant to Section 7(b) of the Natural Gas Act for permission and approval to abandon natural gas service currently provided by Columbia to Orange and Rockland Utilities, Inc. (O&R) and UGI Corporation (UGI) under its Rate Schedule X-124, and to abandon the operation of two segments of pipeline owned by O&R and UGI, all as more fully set forth in the application on file with the Commission and open to public inspection.

Specifically, Columbia proposes to abandon: (i) the transportation service currently provided under its Rate Schedule X-124 and, (ii) the certificate authority to operate the facilities located in Steuben and Allegany Counties, New York, that were constructed to provide the service proposed to be abandoned. Columbia states that its Rate Schedule X-124 provided for firm transportation service by Columbia to O&R for 4,600 Dth/d and to UGI Utilities, Inc., the successor in interest to UGI, for 22,400 Dth/d. Columbia states that the service, facilities and Columbia's authorization to lease and operate the facilities were approved by the Commission on June 28, 1984 in Docket No. CP83-478. Columbia also states that as it does not own the subject facilities, no facilities will be physically abandoned or removed by Columbia as a result of the proposed abandonment.

Any person desiring to be heard or to make any protest with reference to said application should on or before February 11, 1999, file with the Federal Energy Regulatory Commission, 888 First Street, NE, Washington, DC 20426, a motion to intervene or a protest in accordance with the requirements of the Commission's Rules of Practice and Procedure (18 CFR 385.214 or 385.211) and the Regulations under the Natural Gas Act (18 CFR 157.10). All protests filed with the Commission will be considered by it in determining the appropriate action to be taken but will not serve to make the protestants parties to the proceeding. Any person wishing to become a party to a proceeding or to participate as a party in any hearing therein must file a motion to intervene in accordance with the Commission's Rules.

Take further notice that, pursuant to the authority contained in and subject to the jurisdiction conferred upon the Federal Energy Regulatory Commission by Sections 7 and 15 of the Natural Gas Act and the Commission's Rules of Practice and Procedure, a hearing will be held without further notice before the Commission or its designee on this application if no motion to intervene is filed within the time required herein, if the Commission on its own review of the matter finds that permission and approval for the proposed abandonment are required by the public convenience and necessity. If a motion for leave to intervene is timely filed, or if the Commission on its own motion believes that a formal hearing is required, further notice of such hearing will be duly given.

Under the procedure herein provided for, unless otherwise advised, it will be unnecessary for Columbia to appear or be represented at the hearing.

David P. Boergers,

Secretary.

[FR Doc. 99-1820 Filed 1-26-99; 8:45 am]

BILLING CODE 6717-01-M

APPENDIX A.2

DOE ENVIRONMENTAL SYNOPSIS FOR THE TRANSURANIC WASTE TREATMENT PROJECT JANUARY 1999

THIS PAGE INTENTIONALLY LEFT BLANK



U.S. Department of Energy
Oak Ridge Operations
Environmental Management Division

ENVIRONMENTAL SYNOPSIS FOR THE TRANSURANIC WASTE TREATMENT PROJECT AT THE OAK RIDGE RESERVATION

January 1999

THIS PAGE INTENTIONALLY LEFT BLANK

Table of Contents

Table of Contents ..... *i*

Acronyms and Abbreviations ..... *ii*

1. INTRODUCTION 1

2. ASSESSMENT METHODS 3

3. DESCRIPTION OF THE PROPOSALS 4

   3.1 Offeror #1 Proposal 5

   3.2 Offeror #2 Proposal 5

4. EVALUATION OF POTENTIAL ENVIRONMENTAL IMPACTS 5

   4.1 Land Use 6

   4.2 Cultural and Historic Resources 6

   4.3 Habitat and Wildlife 6

   4.4 Floodplain and Wetlands 7

   4.5 Geology and Seismicity 7

   4.6 Water and Water Quality 7

   4.7 Air Quality 8

   4.8 Transportation 9

   4.9 Energy Requirements 9

   4.10 Health Effects 9

   4.11 Noise 10

   4.12 Socioeconomics 10

   4.13 Accidents 10

5. SUMMARY 11

Abbreviations and Acronyms

CAA	Clean Air Act
CFR	Code of Federal Regulations
CH	Contact Handled
DOE	Department of Energy
DOT	Department of Transportation
EIS	Environmental Impact Statement
FR	Federal Register
gpm	gallons per minute
kVA	thousand volt amps
m^3	cubic meters
MVST	Melton Valley Storage Tanks
NEPA	National Environmental Policy Act
NPDES	National Pollution Discharge Elimination System
NTS	Nevada Test Site
ORNL	Oak Ridge National Laboratory
ORO	Oak Ridge Operations
ORR	Oak Ridge Reservation
RCRA	Resource Conservation and Recovery Act
RFP	Request for Proposal
RH	Remote Handled
ROD	Record of Decision
SEIS	Supplemental Environmental Impact Statement
SWTF	Solid Waste Treatment Facility
TRU	Transuranic
TWTF	Tank Waste Treatment Facility
WAC	Waste Acceptance Criteria
WIPP	Waste Isolation Pilot Plant
WM PEIS	Waste Management Programmatic Environmental Impact Statement

U.S. Department of Energy - Oak Ridge Operations Office

ENVIRONMENTAL SYNOPSIS FOR THE TRANSURANIC WASTE TREATMENT PROJECT AT THE OAK RIDGE RESERVATION

1. INTRODUCTION

The U.S. Department of Energy (DOE), as a Federal agency, must comply with the National Environmental Policy Act of 1969 (NEPA) by considering potential environmental issues associated with its actions prior to undertaking the actions. DOE regulations for NEPA implementation provide directions specific to procurement actions that DOE may undertake or fund [10 *Code of Federal Regulation* (CFR) Section 1021.216] before completing the NEPA process. Per these regulations, an environmental critique shall be prepared to support the procurement selection process. A synopsis of the environmental critique shall then be published to inform the public of the findings of the critique while protecting confidential information regarding proposals from offerors.

This document is a synopsis of the environmental critique prepared to identify and evaluate potential environmental impacts associated with the submitted proposals to treat and package transuranic (TRU) mixed wastes at Oak Ridge National Laboratory (ORNL) and ship the treated waste to an approved disposal site. These wastes would be processed as part of the TRU Waste Treatment Project, which would be located in Melton Valley at ORNL in eastern Tennessee. A contract was awarded by the DOE Oak Ridge Operations (ORO) in August of 1998 for construction and operation of a facility to treat the TRU waste.

TRU waste is radioactive waste that is not classified as high-level radioactive waste and that contains more than 100 nanocuries per gram of alpha-emitting transuranic (atomic numbers greater than 92) isotopes with half-lives greater than 20 years. Alpha low-level radioactive waste contains alpha-emitting transuranic isotopes with half-lives greater than 20 years at concentrations less than 100 nanocuries per gram.

The TRU waste to be treated also contains beta- and gamma- emitting isotopes in addition to alpha-emitting isotopes, which result in its classification as either contact-handled (CH) (surface dose rate of 200 mrem/hr or less) or remote-handled (RH) (surface dose rate of greater than 200 mrem/hr).

Solid waste at ORNL is a heterogeneous mixture consisting of paper, glass, rubber, cloth, plastic, and metal from glove boxes, fuel processing, hot cells, and reactors. Solid waste is currently packaged in metal boxes, drums and concrete overpacks, and stored in Resource Conservation and Recovery Act (RCRA) permitted facilities. Most of the solid waste containers do not meet current Department of Transportation regulations and would require repackaging prior to shipment.

Based on generator records, the solid waste has been classified as either TRU or alpha low-level radioactive waste. However, because the nature of the solid waste can only be confirmed after retrieval and characterization, solid wastes addressed in this synopsis are characterized as "TRU/alpha low-level radioactive waste" to note the current uncertainty. The solid waste may contain RCRA characteristic metals, but generator records do not indicate the presence of any RCRA listed constituents. The supernatant, the liquid layer covering the sludge in the tanks, is considered a low-level waste but is not considered hazardous under the RCRA definitions.

Approximately 62 percent of the legacy TRU wastes are currently stored in 50 year-old tanks. The remaining 38 percent of the legacy TRU wastes are currently stored in subsurface trenches, vaults, and metal buildings.

Approximate quantities of the four primary waste streams needing treatment are: 900 m^3 of RH-TRU sludge, located in the tanks; 1600 m^3 of low-level supernatant, located in tanks; 550 m^3 of RH-TRU waste/alpha low-level radioactive waste solids in vaults and trenches; and 1,000 m^3 of CH-TRU waste/alpha low-level radioactive waste solids in metal buildings.

For the near term, the waste is safely contained and stored. However, it is essential to accurately characterize, process and repackage the waste so that it can be transported off the Oak Ridge Reservation (ORR) to a final disposal site. The processed waste must meet the applicable disposal site waste acceptance criteria (WAC) for the disposal facility and the Department of Transportation (DOT) requirements.

DOE ORO is currently operating under a Site Treatment Plan with set goals and milestones for processing legacy mixed waste that was mandated by the State of Tennessee in 1995. There are no TRU mixed waste disposal facilities currently operating in the United States. The Department decided to dispose of TRU waste at the Waste Isolation Pilot Plant (WIPP) (a DOE transuranic waste disposal facility located in southeastern New Mexico), in the Record of Decision (ROD) for the WIPP Supplemental Environmental Impact Statement (SEIS) (63 *Federal Register* (FR) 3624, January 23, 1998).

An independent preliminary study, known as the Parallax study (ORNL/M-4693, Feasibility Study for Processing ORNL TRU Waste in Existing and Modified Facilities, September 15, 1995) was conducted to look at viable alternatives for the safe and cost-effective processing of TRU waste. This study determined that waste processing by the private sector was a viable option that could provide significant savings compared to traditional cost plus contracting approach. The TRU Waste Treatment Project procurement at Oak Ridge will secure TRU waste processing by a private sector contractor.

Construction and operation of a TRU waste treatment facility constitutes a "major federal action" and appears to fall within those classes of actions normally requiring an Environment Impact Statement (EIS). Therefore, DOE will prepare an EIS for the project. Two DOE NEPA documents will be used for information on baseline data for the project-specific EIS, the *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (DOE/EIS-0200-F, May 1997) and the *Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (DOE/EIS-0026-S-2, September 1997).

2. ASSESSMENT METHODS

In accordance with DOE's NEPA regulations, the request for proposal (RFP) required that each offeror provide environmental data and analyses, as available, for each proposal submitted. The RFP listed the type of necessary environmental data, as well as the level of detail that was required for the preparation of a critique (Section L.f. of the RFP). The RFP also required each offeror to clearly identify all site, process, or system information that was not specified at that time of the proposal. This information was submitted as a separate package.

Much of the information submitted and presented by the offerors was preliminary as it was based on anticipated events, such as approval of a permit or planned activities, and successful completion of process setup. Following contract award, DOE will monitor project progress and address any deviation from the proposal information.

Only the environmental data and analyses submitted by the two offerors determined to be in the competitive range were used to prepare the critique. The information in the critique provides the basis for this synopsis. The offerors evaluated in this synopsis are designated as Offeror #1 and Offeror #2 to protect business confidential information. Evaluations for this procurement considered the reasonably foreseeable environmental impacts that could arise from each offeror's proposed approach to waste treatment, repackaging, and shipment to a designated waste disposal site (see Section 4). The evaluations also identified aspects of each offeror's proposed activities that were not adequately described for purposes of analyzing possible environmental impacts at the time. The evaluations identified differences between the offerors' proposed approaches and impacts, and where the offerors provided insufficient data.

Additional information for the evaluation included the data submitted in the proposals and the revised "Best and Final" offers. Various documents written by DOE and ORNL that describe the overall environment in the Melton Valley were also used. The environmental impacts of TRU waste at ORR will be further analyzed in an EIS as discussed in Section 1.

3. DESCRIPTION OF THE PROPOSALS

The proposals submitted by the offerors are not available for review by the public as they contain confidential business information. The descriptions of each proposal in this synopsis does not contain business, confidential, trade secrets, or other information that can not be disclosed pursuant to the competitive procure process.

The proposals include information on the personnel, facilities, equipment, materials, supplies, vehicles, other services required for the treatment, packaging of the TRU wastes at ORNL, and the shipment of the wastes from ORNL to a designated disposal site.

Each offeror proposed to use treatment processes that include:

- physical processes for solid waste volume reduction,
- low-temperature drying and chemical immobilization of sludge and supernate, and
- stabilization and encapsulation techniques for RCRA material.

These processes would produce a treated waste (TRU, TRU mixed, and LLW) that complies with DOT requirements and, for purposes of submitting a proposal, would meet the WAC for TRU and LLW necessary for disposal at WIPP and NTS, respectively.

Each offeror proposed using low-temperature thermal treatment for the tank wastes with minor variations. Offeror #1 would treat the tank waste as a single waste stream, use sulfide additives to immobilize RCRA metals in the tank wastes, and use macroencapsulation for the solid wastes. Offeror #2 would use separate treatment lines for the tank supernate and sludge, and use sulfide additives only on the sludge portion of the tank wastes to immobilize RCRA metals. A wider array of potential technologies may be used for the solid wastes.

Each offeror suggested they would use the RCRA "Debris Rule" to minimize waste volumes triggering waste-specific treatment requirements under RCRA. In short, the rule allows some waste materials that are contaminated with more than one hazardous constituent to be categorized as "debris" thereby not triggering some treatment requirements under the RCRA land disposal restrictions at 40 CFR Part 268. Offeror #1 would use the rule to facilitate streamlining treatment of solids, using only macroencapsulation. Offeror #2 was less clear how the rule would influence the proposed treatment process.

The MVST consist of eight 50,000 gallon tanks located in a concrete underground vault. Since their construction, these tanks have received filtrate from the ORNL liquid low-level waste

system. Each offeror proposed constructing the waste treatment facility west and adjacent to the MVST in Melton Valley, thus the environmental baseline for the analyses of possible significant environmental impacts due to the proposed site location was identical for each offeror. However, the location of the proposed waste treatment facility varied slightly in relation to its environmental impacts associated with facility construction and the acreage (3 acres versus 3.5 acres) each offeror expected to affect. Offeror #1 did not propose to alter the topography of the site. Offeror #2 proposed to cut into the hillside to construct a two-lane ramp to the upper floor of its facility.

3.1 Offeror #1 Proposal

Offeror #1 proposed to construct and operate a 10,400 ft^2 waste processing building that would contain the Tank Waste Treatment Facility (TWTF) and the Solid Waste Treatment Facility (SWTF), a 150 ft long shielded transfer line to the MVST, and ancillary buildings. Two treatment trains would be developed with separate hot cell facilities. The TWTF would process sludge and supernate currently stored in the MVST. The SWTF would first process CH-TRU wastes and then RH-TRU solid wastes. The TWTF and the SWTF would share infrastructure and support operations. There would be a single Clean Air Act (CAA) permitted ventilation stack and a single National Pollution Discharge Elimination System (NPDES) permitted outfall for process water discharges and storm water. The facility would operate under a Part B RCRA permit.

3.2 Offeror #2 Proposal

Offeror #2 would construct and operate a 37,000 ft^2 waste processing facility, a 120 ft long shielded transfer line from the MVST, and ancillary buildings. Four treatment trains would be developed to separately process the wastes. The sludge and the supernate currently stored in the MVST, and the CH-TRU and RH-TRU solid wastes would each have a separate treatment train. The facilities would be co-located in a multi-level building and share many infrastructure and support operations. There would be a CAA permitted ventilation stack, but no process water discharges, therefore a Clean Water Act permit for storm water discharges would be required. The facility would operate under a Part B RCRA permit.

4. EVALUATION OF POTENTIAL ENVIRONMENTAL IMPACTS

The ORR occupies about 34,500 acres of federal land within the corporate limits of the city of Oak Ridge, and within Roane and Anderson counties in eastern Tennessee. In 1989, the three main plant complexes, including ORNL, the East Tennessee Technology Park, and the Y-12 Plant encompassed a fenced area of 24,400 acres, with the remaining acreage designated as a National Environmental Research Park. The region is relatively hilly and averages 54 inches of precipitation annually. Although there are both perennial and intermittent streams near the proposed treatment site, the site does not contain any surface water bodies or wetlands. Mixed hardwoods and pines dominate the area. No state listed, federally listed, or candidate species

have been observed at the proposed site. A locked gate at the junction of the access road to the proposed site and the State Highway 95 restricts public access to the area. The proposed site is approximately 1.25 miles from this junction. Other important nearby highways include I-40, I-75 and State Highways 62 and 162. Nearby local communities range from urban to rural.

4.1 Land Use

The specific facility location (within a 32 acre parcel identified by DOE in the Request for Proposal) selected by both offerors does not appear to have been previously disturbed. The proximity of the location to the MVST lessens the amount of impact associated with utility construction and minimizes handling and transport of the liquid wastes. Potential adverse land use effects include the loss of habitat for wildlife and loss of the area for other potential uses while the facility is in operation. The facility could have a visual impact outside the fenced boundary due to its height. The potential impacts to visual resources by this action is not expected to be significant due to the hillside to the north, abundant vegetation, and restrictions to public access. Both proposals minimize some of the possible land use effects, particularly infrastructure, by locating their facilities within the current ORNL boundary. Both offerors proposed adding a driveway that loops around the facility, and planned to take advantage of the local topography to gravity feed the tank wastes to the treatment building. There were no significant differences between the two offerors with respect to proposed land use.

4.2 Cultural and Historic Resources

Potential effects to cultural and historic resources were tied to the location of the facility and are, therefore, the same. Both offerors proposed to limit impacts to cultural resources by training workers to avoid a nearby homestead, which would be outside the facility fence line. DOE has a programmatic agreement with the State Historic Preservation Officer for ORR and ORNL that would include a Phase I survey prior to disturbing the proposed treatment site. The impacts analysis for the EIS would be based on findings of this survey.

4.3 Habitat and Wildlife

One impact of the proposed treatment facility would be the loss of land and associated habitat that could be used by plants and animals. This would lead to displacement and disturbance of some individual animals. This loss of land and habitat alone would not be likely to have a significant environmental effect on local wildlife or plant populations. There could be adverse impacts on breeding potential due to stress from construction or interference in the reproductive cycles of local fauna. The impacts are not expected to be significant to the area because the habitat is not unique, nor does it create a new barrier to free ranging animals. The proposed treatment facility would contribute incrementally to potential indirect cumulative effects to habitat and wildlife including a loss of biodiversity on the ORR.

Both offerors would limit environmental impacts by using a site adjacent to other disturbed areas, minimizing the footprint of the buildings, and eliminating the need to transfer tank contents using trucks. The site would be revegetated after the facility is decommissioned.

4.4 Floodplain and Wetlands

Offeror #2 identified the proposed site as being just above the United States Geological Service 100-year maximum floodplain [10 CFR 1022.4(b)]. This means that there is minimal danger of flooding the facility. Both offerors indicated that the dangers of flooding would be reduced due to existing flood capacity at White Oak Lake. The same assumptions can be made for Offeror #1's facility since it would be constructed in the same location, however this was not stated in the proposal. Both proposals indicated that the proposed facility location would be within the 500-year maximum floodplain [10 CFR 1022.4(I)]. The presence of the facility would have a minimal effect on the local capacity for floodwater attenuation, dispersion, or control. There would be no impact to wetlands because there are no wetlands in the immediate area.

4.5 Geology and Seismicity

The proposed site has underlying layers of shale, limestone, and siltstone lithologies of the Cambrian Conasauga Group. The White Oak Creek fault is in the middle of Melton Valley. The earthquake design for the 50-year facility life, with a 100-year seismic event return period, is 0.06g-peak ground acceleration. Because both offerors need to build the proposed facility to code to withstand seismic events, there is no significant difference in this regard between the proposals. The source terms, both hazardous and radioactive, associated with this waste do not change and the potential release pathways would remain the same.

4.6 Water and Water Quality

The only process identified that could impact water quality during normal operation of the facility would be the discharge of treated process waters to White Oak Creek proposed by Offeror #1. Offeror #1 stated that 1 part per billion of mercury would meet permit release criteria, however, the basis for this statement was not referenced. This level is above the State of Tennessee ambient water quality criteria of 12 parts per trillion of mercury, which would apply to White Oak Creek. Offeror #2 did not address the possibility that condensate water from drying the tank contents might have quantities of mercury but also did not indicate any discharges to local waters. Offeror #2 stated the waste treatment facility would have no liquid effluent discharges.

Storm water management could impact water quality and both offerors would have storm water pollution prevention plans to meet their regulatory requirements. Offeror #2 proposed extensive diversion ditches and a retention basin to capture and sample any overland flow of storm water before it reaches White Oak Creek.

Both proposals contained data relating to water use, however, it was not evident how the data compared. Offeror #1 expected to require less than 900 gallons per minute (gpm) flow rate based on the design assumptions that they would process enough TRU waste to fill three WIPP TRU waste containers and an unspecified amount of solids each week. Offeror #2 expected to require approximately 1000 gpm flow rate based on the design assumption that they would process enough TRU waste to fill four WIPP TRU waste containers and an unspecified amount of solids each week. The expected water requirements for both offerors included fire protection water. The water requirement data were not certain or detailed and did not indicate why Offeror #1 would have half the production rate for a similar amount of water. Because the processes proposed by both offerors were similar, the explanation may be that Offeror #2 planned to run four treatment lines simultaneously, while Offeror #1 would run only two at a time. Cooling was not a major component of water usage because high temperature thermal treatment was not proposed.

Offeror #2 proposed a closed water system that would minimize the opportunity of groundwater or surface water contamination. The storm water pollution prevention measures proposed by Offeror #2 were more extensive than those proposed by Offeror #1, but may be more than what is required for worst case storm or accident scenarios. Offeror #1 requires a permit for the discharge of treated process water to White Oak Creek. Both offerors would recycle process water within their treatment trains for the MVST.

4.7 Air Quality

Both offerors proposed using low-temperature treatment processes on the same total volume of waste. The primary means of mitigating process related air emissions is an effective off-gas system, which was identified in both proposals. In addition, both offerors would conduct most of the retrieval and process operation in an enclosed building. Continuous air monitoring was a component of both proposals. Offeror #1's proposal contained a table of anticipated total emissions, but did not include information as to the rate of emissions. Offeror #2 provided little specific information on anticipated emissions, however, because the treatment processes are similar, the emissions are likely be similar to Offeror #1. Neither offeror mentioned how their off-gas systems would function in case of emergency, nor was there any contingency plan for this event. Air emissions would be regulated through air quality standards and permits which both offerors planned to obtain.

Dust would be generated during the construction phase of the project. The potential for fugitive emissions would be more extensive for Offeror #2 because it proposes cutting into the hillside and would have more extensive ground disturbance during the construction phase. The operation of equipment and trucks would generate hydrocarbon related emissions that could incrementally increase cumulative air impacts. Construction and traffic related air emissions could be controlled and minimized with wetting techniques to prevent dust, and by properly maintaining equipment and vehicles.

4.8 Transportation

Because of increased use of the roads near the proposed site, there would be increased fuel usage and a need for additional road maintenance. Transportation from the proposed site could present some hazards for public exposure to radiation due to accidents, as discussed in section 4.13. The estimated number of trips to the final disposal sites was not clear in the proposals, so no comparison could be made. Both proposals discuss optimizing waste shipments.

Offeror #2 proposed employing more workers and constructing a larger facility that would result in greater, but not significant, transportation impacts than Offeror #1's proposal. The effect of commuter transportation should not be significant because the number of workers is relatively small in both proposals. Transportation activities, transport of materials during waste processing, and traffic control measures were not adequately addressed in either proposal. The delivery of solid waste from ORNL to the waste treatment facility would be the same for both offerors.

4.9 Energy Requirements

The proposals did not contain enough specific information to draw a conclusion on energy consumption. Offeror #1 would require 1,000 thousand-volt amps (kVA) of power, and Offeror #2 would require 2,600 kVA of power. This was a potentially significant difference in energy requirements and efficiency between the two offerors, but a definitive comparison could not be made. The proposals did not contain adequate information on the total system or individual system power requirements, nor did they discuss the energy required to support transportation. DOE has proposed providing 500 kVA of power to the site, so both offerors would need to obtain a supplemental power supply. Neither offeror discussed power or minimizing energy consumption. Potential adverse effects resulting from the use of energy to operate the waste treatment facility have not yet been considered.

4.10 Health Effects

Both offerors proposed to meet industry standards and adopt acceptable administrative controls for exposure to radioactive and hazardous waste. However, neither proposal contained any details on specific administration controls. There should not be a significant difference between the two offerors with respect to effects on health, since both offerors must satisfy regulations regarding worker safety and radiation exposure for employees and the public. In theory, Offeror #2 might place more workers at risk because they proposed involving 50 more people than Offeror #1. Offeror #2's proposal also described more treatment and processing units, which could increase the potential for an accident or break in the system. Alternatively, the multiple units offer processing flexibility in the event of breakdowns so that processing might be more quickly restored. The proposals did not contain specific information regarding radiation or hazardous chemical exposure, so a comparison could not be made of long-term, low-dose

exposure for increased cancer or birth defect risks. Both offerors would be required to integrate "As Low As Reasonably Achievable" considerations into the radiological safety program, and provide detailed plans of access control, facility design, safety analysis, inspection and surveillance prior to facility start up. For purposes of comparison, there was no quantifiable difference between the proposals.

4.11 Noise

The proposals contained no information on occupational noise levels, so a comparison could not be made between the offerors. Both offerors stated they did not anticipate noise impacts to the environment, but their statements were not substantiated and the potential impacts to the environment could not be evaluated.

4.12 Socioeconomics

An overall decline in employment at the ORR region of influence is anticipated. The employment levels proposed by both offerors were not significantly different, and the impact on total employment levels for the region would not be great. Offeror #2 would have a slightly greater positive effect by employing an average of 90 people compared to Offeror #1's plan to employ an average of 40 people. The project would have some economic benefit during the construction phase of the project.

4.13 Accidents

Due to the radioactive and hazardous substances involved with this project, there is a potential for adverse environmental effects if an accident were to occur. The general nature of the information provided precluded detailed calculations on the probability of accidents taking place. However, the humid environment, the close proximity to surface water bodies, and shallow groundwater provides greater than average opportunities for contamination migration should a release escape the building containment.

Operations in Offeror #1's proposal were based on the ground floor, and vertical range would occur within, but not between, processes. Treatment trains were developed for two basic waste streams, so the facility required fewer liquid holding/mixing tanks. Because liquids migrate more rapidly than solids, this reduces the inventory of mobile contaminants should an accident occur.

Offeror #2's proposal included more treatment steps and associated process units, and a greater number of treatment trains operating concurrently. The ramped roadway leading to the upper deck of the waste treatment facility loading area for solid waste could be more susceptible to an accident than a level driveway. The vertical staging area of the treatment trains could provide greater potential for cross contamination if an accidental release occurred. The ramped

roadway and vertical equipment arrangement do reduce the number and frequency of waste container lifts and movements, a significant offsetting benefit of both features.

Facility-specific accidents, such as nuclear criticality or an explosion, were considered while reviewing the proposed approaches. Processes and equipment have an individual probability for failure or accident and the greater the number of process units and equipment lines, the greater the probability of some failure or accident occurrence. Differences between the two proposals might lead to differences in accident probability, however, the likelihood of a significant release of hazardous and radioactive substances due to an accident seemed quite low under both proposals.

5. SUMMARY

Based on the information provided by each offeror, there were a number of resource areas where there was no discernible difference. Such areas included: socioeconomic, geology and seismicity, wildlife and habitat, and wetlands and floodplains. The proposals did not provide enough information to define or analyze differences for other resource areas such as noise, water usage and quality, transportation, utility requirements, safety precautions, and waste minimizations.

Despite the uncertainties and insufficient information for a full analysis of some topics, some distinctions between the proposals regarding differences in environmental impacts could be made. One such distinction relates to energy usage. Offeror #2 appeared to use approximately 2.6 times the energy as Offeror #1 (2,600 vs. 1,000 kVA, respectively). Facility size also differed. The facility that was proposed by Offeror #2 was more than 3 times as large than the facility proposed by Offeror #1 (37,000 vs. 10,400 ft^2, respectively). The facility proposed by Offeror #2 also had more extensive construction related to a ramp roadway, surface water controls, and a retention basin. However, the footprint of the two proposed facilities did not vary significantly. Offeror #1 had a greater potential to affect water quality with planned discharges of treated water to White Oak Creek, requiring an NPDES permit, and the more limited degree of controls for storm water.

Both offerors would be required to obtain a CAA permit. Because the treatment processes are similar, however, there were no expected differences between the proposed processes regarding air emissions. Both offerors would use vacuum dryers and planned to utilize closed systems with multiple filters and a single emission stack.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX A.3

PUBLIC ISSUES AND COMMENTS

THIS PAGE INTENTIONALLY LEFT BLANK

Public Scoping Meetings Issues for the Oak Ridge Operations Transuranic Waste Treatment Project

No.	*Comments by*	*Issue*	*Answer*
1	Herman Weeren	Terminology – saying that this project is processing all of the TRU waste, when in actuality, all waste will be processed with the exception of the TRU waste mixed with grout and injected approximately 1000 ft underground by hydrofracture.	Issue acknowledged by Gary Riner.
2	Barbara Walton	Where will time-certified TRU waste from REDC be processed, and is it from a DOD mission?	WIPP – will accept TRU waste regardless of the type of project it came from. The proposed waste treatment facility will be used to treat legacy waste; newly generated waste will be time certified and shipped directly to WIPP and will not require processing at the proposed facility.
3	Craig Turnbow	Is the Bethel Valley Evaporator Service Tanks waste removal complete?	Three tanks are completed , the other two are in process; waste was successfully retrieved from tanks similar in construction to the Melton Valley Storage Tanks (MVSTs) – Riner, Monk.
4	Herman Weeren	Clarification - OHF is only the surface facility?	Referring to the OHF tanks and their contained wastes which are now empty following successful waste retrieval – Riner.
5	Herman Weeren	Should comments on the EIS be written or spoken?	Either send in written comments, or leave a message at the listed telephone number, and the message will be transcribed – Wayne Tolbert. Comments from tonight's meeting will go on record also – in the transcript – Riner.
6	Barbara Walton	▪ Does construction of the facility wait until the Record of Decision? ▪ Are there terms to deal with inflation? ▪ Is the contract Fixed Price?	▪ Yes – Riner. ▪ Yes, the contract was set up so that phase 1 (a 2 ½-year period) allowed for permitting the facility and the completion of the EIS. Yes – so long as we stay within the timeframe for phase 1, we're okay.

No.	Comments by	Issue	Answer
7	Marilyn Green	Federal Register note says scoping ends February 26th.	Committing tonight to extend period until March 18th – Riner.
8	Barbara Walton	Concern over obtaining a copy.	Hard copies will be available – Riner.
9	Herman Weeren	What is the temperature for drying the tank waste?	180 to 190 degrees Fahrenheit – Bryan Roy.
10	Herman Weeren	What happens to the sodium nitrate?	It's a predominate compound that becomes part of the waste and goes to the repository.
11	Herman Weeren	Is the stuff hydroscopic ?	Yes, it will absorb water – Riner.
12	Herman Weeren	Is there any possibility for explosion in the processing of the waste – referring to an incident in Texas City with ammonium nitrate, and that nitrates are not the most stable compounds in the world.	After review of the process, it was not thought a hazard – Riner.
13	Mildred Sears	Expressed that ammonium had not been analyzed, and even though there might not be a lot there, she felt some additional tests were needed.	
14	Unidentified Speaker	Does Alternative 2 presuppose that shipments will be made to WIPP?	Shipments will be made to both WIPP and a low-level waste repository, which will be finally decided as part of the ROD.
15	Barbara Walton	Have they moved forward with the RH-TRU waste containers? Last she'd heard they weren't approved yet.	The 72B canister has been approved – Riner.
16	Barbara Walton	Is the canister approved for CH-TRU?	No – it's different; you're talking about the 72B cast – Riner.
17	Barbara Walton	The approval comes from whom – are you not involved with the approval?	The NRC to the DOE and, no, it's up to the NRC.
18	Herman Weeren	What is the cost advantage of drying the waste over cementation of the waste?	Drying the waste is the ultimate waste minimization and reduces the amount of waste shipped to WIPP from 1500 m^3 to 200 m^3 – cost for disposal at WIPP is $20,000 per cubic meter - Riner, Roy.
19	Herman Weeren	If you use cement and dilute the waste until it is no longer TRU, what is the advantage – you no longer have to ship to WIPP – what does this do?	Low-level waste could be shipped to NTS or possibly Hanford. Cost at the NTS is approximately $1000 per cubic meter, and there would be a lot more shipments.
20	Barbara Walton	It's in our budget rather than the WIPP budget.	Good point – Riner.
21	Herman Weeren	Is a comparison of this type going to be part of the EIS?	These kinds of comparisons will be analyzed – Riner.

No.	Comments by	Issue	Answer
22	Unidentified Speaker	Are these all the alternatives?	Yes – if there are other things you think we should look at, then that's why we're here tonight – Riner.
23	Herman Weeren	You will look at what you would do if you don't send it to WIPP?	Alternative 1 deals with that – Riner.
24	Herman Weeren	I was referring to alternative 4 – grouting the tank waste.	Yes, it will look at the type of final waste form we have and it still may be TRU after it's grouted – I don't know that, but if it comes out as LLW after the analysis, we will make a comparison – Riner.
25	Herman Weeren	Are you looking at that analysis?	Yes – Riner.
26	Barbara Walton	Questions about alternative 3 (Vitrification) – the waste is also diluted to some extent – is it diluted as much as with grout?	You get higher waste loafing with vitrification than you do with grout.
27	Barbara Walton	It could be diluted out of being TRU under alternative 3?	We would have to analyze it – Riner.
28	Barbara Walton	Was this process bid on by one of the bidders?	Yes – Riner.
29	Barbara Walton	Were they in the competitive range?	No – Riner.
30	Mildred Sears	▪ What are we going to do about the smaller, inactive tanks that contain TRU waste residuals – taking into account that waste retrievals for those tank sludges were cancelled – two tanks in my analysis contained TRU waste (WC-5 and WC-10). C-20 has never been analyzed but received waste from the REDC, and also tanks T-1 and T-2. ▪ What about TRU waste generated during D&D of contaminated buildings 10 years down the road?	What two tanks are those? – Riner. There is TRU waste in those tanks, at a much higher activity than had ever been measured before. The FFA tanks program still has funding, and we are in dispute with the State of Tennessee over cleanup of those tanks and possibly other tanks. Tank WC-14 recently had all of the TRU waste and PCBs removed. Tanks that contain PBCs will not be commingled with other tank waste. Any waste that meets the WAC for the LLLW system will be transferred to the MVST – Riner, Monk.
31	Herman Weeren	If you go through the procedure and go ahead with the preferred alternative based on the assumption that WIPP will open, and then it doesn't, where does this lead you?	We have a commitment from the State of Tennessee to process this waste under a site treatment plan, and if it's processed to meet RCRA Land Disposal Requirements (LDRs), it falls out from under RCRA and can be stored on the site for eternity – Riner. WIPP is not the driver; our driver is the RCRA site treatment plan and complying with RCRA requirements whether WIPP opens or not – Riner.

No.	Comments by	Issue	Answer
32	Herman Weeren	Are you going to look at the risks from the hydrofracture wells?	No – Riner. We propose building the facility next to the MVSTs so that we don't have the environmental impact of having a long run of pipeline if we build the facility elsewhere on the reservation – Riner. There are no hydrofracture or other wells that we are aware of within the proposed building area for the facility – Roy.
33	Herman Weeren	What about damage to the wells from vehicles, and there is a well located up the hill; contamination can easily migrate.	You would have a hard time getting a truck into the area – Riner. Only about 25ft would be excavated from the knoll – Roy. The people preparing the Melton Valley ROD are looking at the hydrofracture wells, as of now there is no effect either way – Riner. We will look into effects in terms of the construction of the facility, but there should be no effects since they're are hundreds of feet away. The wells would be undamaged, during and after construction of the facility, and will still be there after D&D of the processing facility.
34	Herman Weeren	What about the roads in? There are 4 wells by the existing road.	AVISCO was awarded the contract for upgrading the road, and they have a tentative layout for the road, which does not impact any hydrofracture wells – Riner. The upgraded road will be south of the existing gravel road. The road was surveyed along the route and verified with existing drawings from the Environmental Sciences Division at ORNL – we have stayed away from all wells – Monk.
35	Herman Weeren	Which way is south?	Up the hill? – Monk.

No.	Comments by	Issue	Answer
36	Lorene Sigal	Is the existing road within the floodplain of the embankment and the creek, and are you covering up contaminated soils or sediments?	No, and it is not within the 500-year floodplain – Riner, Roy. The road also serves as an emergency exit for HFIR and is documented under several operational safety reviews – we are moving forward on the road under a NEPA category exclusion, CX. The contract has been let and the road will not be analyzed as part of this EIS – we want to get the road done before construction begins.
37	Lorene Sigal	You're justifying the exclusion on the basis that the road serves other purposes?	Yes – and the fact that there is a road already there – Riner.
38	Lorene Sigal	How much wider is the new road?	About twice as wide – so that 2 vehicles or 2 tractor trailers can pass – Riner.
39	Lorene Sigal	Does the existing road provide roadbed for the new road?	No – Monk.
40	Lorene Sigal	So you're really building a brand new road – not just upgrading the existing road?	The elevation of the new road is higher than the existing road, so they are going up higher and taking the excavated dirt, moving it down, and raising the whole elevation rather than having to haul a lot of dirt away – Riner. Also, the existing road had washouts earlier this year – and rendered the emergency route from HIFR impassible. Also, we didn't want heavy trucks on a road directly adjacent to the lake for obvious reasons – Monk.
41	Barbara Walton	How much more does it cost to do 4 alternatives instead of 2 (referring to the EIS analysis)?	About $100,000 an alternative – Riner.
42	Barbara Walton	The other alternative would cost a lot more than the contract we have?	I don't think that's a considering factor.
43	Herman Weeren	Are you talking about adding alternatives – I would strongly oppose omitting alternative 4.	No – I think she was talking about doing away with alternatives 3 & 4 and, therefore, the need to have them analyzed.
44	Josh Johnson	Do you know how many curies we're getting rid of by going through all of this?	The tank waste is roughly 135,000 curies. On the solid waste it's hard to quantify curies – Riner. Its on the order of 50,000 to 60,000 curies for the solid waste – but it's a skewed distribution – Monk.

No.	Comments by	Issue	Answer
45	Josh Johnson	You have about a million gallons of water a day for processing; what is all the water used for? Is this recycled? You won't be bringing that in and discharging it.	That's the consumption for all uses, fire protection and so forth. The water won't be discharged.
46	Lorene Sigal	I recommend you get rid of alternative 3 – why are you going to assess something that doesn't make very much sense?	It could be looked at as a raised and dismissed alternative - Riner.
47	Unidentified speaker	Can you provide the information from the bid package?	No – it's proprietary information.
48	Barbara Walton	Have you considered the location of your MEI (Most Exposed Individuals)?	They would be ORNL workers across the fence for short-term exposure. Long-term exposure would be workers across the ridge in downtown ORNL – Riner. The highest exposure is in the woods to the southeast of the facility, but no one is there – Roy. We are going to bound this EIS to real-world conditions.
49	Barbara Walton	Where, what your credible accident scenarios might be? – Do you have accident scenarios on the other alternatives? Is the worst hazard a pipe rupturing? And the time it takes to shut down?	We could think of liquid release due to earthquakes, pressure breaking the transfer line, tornadoes, and internal fire – Roy.
50	Herman Weeren	How about floods?	The facility is designed with a lot of drainage between the MVSTs and the facility – we will examine floods that are reasonable. Herman, what are you requesting? – We will examine floods and the potential impact for them.
51	Lorene Sigal	Have you done anything to protect from a break in the pipeline?	Yes – Roy. Secondary containment is seismically designed – Riner.
52	Lorene Sigal	You talk about the general public – the general public doesn't read these documents – and most of the comments you get are from people who have an understanding of the reservation.	That's right – most of the people who come to these meetings are the ones who read them and comment – Riner.
53	Lorene Sigal	I agree that the EIS should be reader friendly, but don't make it so simplified that you miss the technical issues.	We will address the technical issues – Riner.
54	Dr. Gawarecki	You talk about geology and seismicity and the White Oak Creek fault – but this is not an active fault?	Right – Riner.

No.	Comments by	Issue	Answer
55	Mr. Mulvenon	Have details on the amount of energy to be used been worked out?	We don't have a full-blown analysis – but vitrification will take more energy, cementation will take less, and somewhere in the middle will be the drying alternative.
56	Mr. Mulvenon	In the synopsis it mentions 2.6 megawatts and 80% of that going to water evaporation – that energy is not being parted on the waste as much as the water, but it is in the waste?	Right?
57	Mr. Mulvenon	Have we got the utilities to do that?	We have 500 kW near the HFIR reactor, which is where we are going to get the power for the facility – Foster Wheeler has to get the power to the facility.
58	Mr. Mulvenon	Is there any waste water associated with this drying process?	100% No water effluent – Riner.
59	Dr. Gawarecki	Is there any tritium in the water vapor?	There was no analysis for tritium – Riner. We assumed all the tritium would be released, but it is a very small amount as it is a fairly small contributor to the waste – Roy.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX B

EMISSIONS AND MATERIALS BALANCE DATA FOR THE PROPOSED ACTION AND THE VITRIFICATION AND CEMENTATION ALTERNATIVES

THIS PAGE INTENTIONALLY LEFT BLANK

Appendix B contains details and data relevant to the proposed action and alternatives. Specifically, this appendix contains information on emissions associated with the proposed action, materials balance and emissions for the vitrification process, and similar material for the cementation alternative. Floor plans for the proposed action/preferred alternative are also included.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX B.1

SUMMARIES OF TRU WASTE REMEDIATION

THIS PAGE INTENTIONALLY LEFT BLANK

Table B.1-1. Summary of annualized radionuclide emissions (Ci/year) for the Proposed Action

Radionuclide	Sludge emissions	Supernate emissions	Solids emissions	Total emissions
Ac-227	0.00E+00	0.00E+00	6.55E-13	6.55E-13
Ag-110	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ag-110m	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Am-241	0.00E+00	4.99E-10	4.12E-07	4.12E-07
Am-243	0.00E+00	0.00E+00	8.37E-09	8.37E-09
Au-196	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Au-198	8.10E-06	0.00E+00	0.00E+00	810E-06
Bk-249	0.00E+00	0.00E+00	2.30E-11	2.30E-11
C-14	0.00E+00	1.24E-07	1.36E-13	1.24E-07
Ce-144	2.31E-05	1.60E-08	0.00E+00	2.31E-05
Cf-249	0.00E+00	0.00E+00	1.20E-11	1.20E-11
Cf-252	8.30E-08	6.80E-10	9.69E-09	9.34E-08
Cm-240	0.00E+00	0.00E+00	1.25E-39	1.25E-39
Cm-242	0.00E+00	0.00E+00	5.27E-08	5.27E-08
Cm-243	2.24E-05	0.00E+00	0.00E+00	2.24E-05
Cm-244	7.89E-05	9.40E-07	1.74E-06	8.16E-05
Cm-245	0.00E+00	0.00E+00	2.46E-12	2.46E-12
Cm-246	0.00E+00	0.00E+00	8.00E-15	8.00E-15
Cm-248	0.00E+00	0.00E+00	2.11E-11	2.11E-11
Co-60	7.27E-05	5.47E-07	2.36E-09	7.33E-05
Cs-134	1.06E-05	1.99E-06	0.00E+00	1.26E-05
Cs-137	1.25E-03	3.16E-04	2.36E-06	1.57E-03
Es-253	0.00E+00	0.00E+00	2.79E-44	2.79E-44
Es-254m	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Eu-152	2.85E-04	3.94E-06	3.71E-13	2.89E-04
Eu-154	1.51E-04	1.41E-06	0.00E+00	1.53E-04
Eu-155	4.59E-05	6.29E-07	0.00E+00	4.65E-05
Fe-59	0.00E+00	0.00E+00	1.74E-25	1.74E-25
Gd-153	0.00E+00	0.00E+00	0.00E+00	0.00E+00
H-3	7.53E-08	1.64E-07	0.00E+00	2.40E-07
I-129	0.00E+00	1.95E-10	0.00E+00	1.95E-10
I-131	0.00E+00	0.00E+00	2.28E-100	2.28E-100
Nb-95	4.98E-06	5.29E-24	0.00E+00	4.98E-06
Ni-63	0.00E+00	0.00E+00	8.49E-14	8.49E-14
Np-237	1.69E-08	0.00E+00	6.73E-10	1.75E-08
Pa-231	0.00E+00	0.00E+00	2.52E-10	2.52E-10
Pm-147	0.00E+00	0.00E+00	6.54E-10	6.54E-10
Po-209	0.00E+00	0.00E+00	1.53E-15	1.53E-15
Pu-238	1.34E-05	5.27E-09	3.03E-06	1.65E-05
Pu-239	6.58E-06	4.53E-09	8.25E-07	7.41E-06
Pu-240	2.06E-06	4.41E-09	7.70E-07	2.84E-06
Pu-241	2.32E-05	6.74E-08	4.58E-05	6.91E-05
Pu-242	4.45E-09	2.21E-10	1.91E-10	4.86E-09
Pu-244	4.12E-10	2.60E-11	0.00E+00	4.38E-10
Ra-223	0.00E+00	0.00E+00	8.83E-76	8.83E-76
Ra-226	0.00E+00	0.00E+00	1.29E-09	1.29E-09
Ru-106	3.96E-05	8.58E-08	0.00E+00	3.97E-05
Sb-125	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Sr-90	4.01E-03	1.26E-05	1.46E-06	4.03E-03
Tc-99	8.08E-07	1.50E-06	1.37E-07	2.44E-06

Table B.1-1 (continued)

Radionuclide	Sludge Emissions	Supernate Emissions	Solids Emissions	Total Emissions
Te-123	0.00E+00	0.00E+00	2.08E-14	2.08E-14
Te-123m	0.00E+00	0.00E+00	5.71E-19	5.71E-19
Th-230	0.00E+00	0.00E+00	9.63E-15	9.63E-15
Th-232	5.61E-08	5.20E-11	1.43E-12	5.62E-08
U-232	0.00E+00	2.47E-08	2.36E-10	2.49E-08
U-233	4.64E-06	1.86E-07	8.45E-08	4.91E-06
U-234	2.06E-06	3.77E-09	1.33E-08	2.08E-06
U-235	5.39E-08	1.56E-10	5.95E-12	5.41E-08
U-236	4.49E-09	9.11E-11	7.78E-14	4.58E-09
U-238	2.05E-06	4.97E-09	3.48E-11	2.05E-06
U-239	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Y-90	0.00E+00	0.00E+00	2.65E-286	2.65E-286
Zn-65	0.00E+00	0.00E+00	2.44E-15	2.44E-15
Zr-95	5.71E-05	1.85E-16	0.00E+00	5.71E-05
Total radionuclides	6.12E-03	3.40E-04	5.67E-05	6.52E-03

Ci = curie.

Table B.1-2. Estimated radionuclide emissions for TRU waste treatment of sludge for the Proposed Action

Radionuclide	Radionuclide composition[a] (Bq/g)	(Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide Emissions (Ci)	Radionuclide emissions after control: Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	0		2.18E+01				0.00E+00
Ag-110	0		7.80E-07				0.00E+00
Ag-110m	0		6.84E-01				0.00E+00
Am-241			4.32E+02		0.00E+00	0.00E+00	0.00E+00
Am-243	0		7.37E+03				0.00E+00
Au-196	0		1.69E-02				0.00E+00
Au-198	3732.39	1.01E-07	7.38E-03	1.01E-07	1.01E-01	1.01E-05	8.10E-06
Bk-249	0		8.76E-01				0.00E+00
C-14	0		5.73E+03				0.00E+00
Ce-144	10647.08	2.88E-07	7.80E-01	2.88E-07	2.89E-01	2.89E-05	2.31E-05
Cf-249	0		3.51E+02				0.00E+00
Cf-252	38.27	1.03E-09	2.65E+00	1.03E-09	1.04E-03	1.04E-07	8.30E-08
Cm-240	0		7.39E-02				0.00E+00
Cm-242	0		1.63E+02				0.00E+00
Cm-243	10330.07	2.79E-07	2.91E+01	2.79E-07	2.80E-01	2.80E-05	2.24E-05
Cm-244	36370.20	9.83E-07	1.81E+01	9.83E-07	9.86E-01	9.86E-05	7.89E-05
Cm-245	0		8.50E+03				0.00E+00
Cm-246	0		4.73E+03				0.00E+00
Cm-248	0		3.40E+05				0.00E+00
Co-60	33519.35	9.06E-07	5.27E+00	9.06E-07	9.09E-01	9.09E-05	7.27E-05
Cs-134	4893.24	1.32E-07	2.06E+00	1.32E-07	1.33E-01	1.33E-05	1.06E-05
Cs-137	577076.13	1.56E-05	3.01E+01	1.56E-05	1.56E+01	1.56E-03	1.25E-03
Es-253	0		5.60E-02				0.00E+00
Es-254m	0		4.48E-03				0.00E+00
Eu-152	131531.25	3.55E-06	1.35E+01	3.55E-06	3.57E+00	3.57E-04	2.85E-04
Eu-154	69723.86	1.88E-06	8.59E+00	1.88E-06	1.89E+00	1.89E-04	1.51E-04
Eu-155	21166.34	5.72E-07	4.76E+00	5.72E-07	5.74E-01	5.74E-05	4.59E-05
Fe-59	0		1.22E-01				0.00E+00
Gd-153	0		6.61E-01				0.00E+00
H-3	34.73	9.39E-10	1.23E+01	9.39E-10	9.42E-04	9.42E-08	7.53E-08
I-129	0		1.57E+07				0.00E+00
I-131	0		2.20E-02				0.00E+00
Nb-95	2296.02	6.21E-08	9.58E-02	6.21E-08	6.23E-02	6.23E-06	4.98E-06
Ni-63	0		1.00E+02				0.00E+00
Np-237	7.77	2.10E-10	2.14E+06	2.10E-10	2.11E-04	2.11E-08	1.69E-08
Pa-231	0		3.28E+04				0.00E+00
Pm-147	0		2.62E+00				0.00E+00
Po-209	0		1.02E+02				0.00E+00
Pu-238	6198.78	1.68E-07	8.77E+01	1.68E-07	1.68E-01	1.68E-05	1.34E-05
Pu-239	3031.95	8.19E-08	2.41E+04	8.19E-08	8.22E-02	8.22E-06	6.58E-06
Pu-240	950.28	2.57E-08	6.56E+03	2.57E-08	2.58E-02	2.58E-06	2.06E-06
Pu-241	10716.94	2.90E-07	1.44E+01	2.90E-07	2.91E-01	2.91E-05	2.32E-05
Pu-242	2.05	5.54E-11	3.73E+05	5.54E-11	5.56E-05	5.56E-09	4.45E-09
Pu-244	0.19	5.14E-12	8.00E+05	5.14E-12	5.15E-06	5.15E-10	4.12E-10
Ra-223	0		3.13E-02				0.00E+00
Ra-226	0		1.60E+03				0.00E+00
Ru-106	18256.71	4.93E-07	1.02E+00	4.93E-07	4.95E-01	4.95E-05	3.96E-05
Sb-125	0		2.76E+00				0.00E+00
Sr-90	1850860.69	5.00E-05	2.88E+01	5.00E-05	5.02E+01	5.02E-03	4.01E-03
Tc-99	372.46	1.01E-08	2.11E+05	1.01E-08	1.01E-02	1.01E-06	8.08E-07
Te-123	0		1.00E+08				0.00E+00
Te-123m	0		3.28E-01				0.00E+00
Th-230	0		7.54E+04				0.00E+00
Th-232	25.88	6.99E-10	1.41E+10	6.99E-10	7.02E-04	7.02E-08	5.61E-08
U-232	0		6.89E+01				0.00E+00
U-233	2136.82	5.78E-08	1.59E+05	5.78E-08	5.79E-02	5.79E-06	4.64E-06
U-234	950.46	2.57E-08	2.46E+05	2.57E-08	2.58E-02	2.58E-06	2.06E-06

Table B.1-2 (continued)

Radionuclide	Radionuclide composition[a] (Bq/g)	(Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide Composition (Ci/g)	Uncontrolled[c,d] radionuclide Emissions (Ci)	Radionuclide emissions after control: Project life[e] (Ci)	Annualized[f] (Ci/year)
U-235	24.86	6.72E-10	3.80E+06	6.72E-10	6.74E-04	6.74E-08	5.39E-08
U-236	2.07	5.59E-11	2.34E+07	5.59E-11	5.61E-05	5.61E-09	4.49E-09
U-238	943.56	2.55E-08	4.47E+09	2.55E-08	2.56E-02	2.56E-06	2.05E-06
U-239	0		4.46E-05				0.00E+00
Y-90	0		7.31E-03				0.00E+00
Zn-65	0		6.69E-01				0.00E+00
Zr-95	26302.35	7.11E-07	1.75E-01	7.11E-07	7.13E-01	7.13E-05	5.71E-05
Total							6.12E-03

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Number ORNL/TM-13351.

[b]The amount of curies present for each radionuclide is reduced by the corresponding half life to account for the species decay. The equation for estimating radionuclide decay is:

$$A = A_o \times \exp -[\ln(2) / t_{1/2} * T] .$$

The half-life of each radionuclide was obtained from the web site www.dne.bnl.gov/CoN/index.html.

T is the time between the time of sample analysis (December 1996) to the time of process startup (January 2003):

$$T = 6.08 \text{ years.}$$

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Sludge Processing Rate × Emissions Factor × Composition.

The processing rate and the operating schedule obtained from the FWEC proposal are:

Total Sludge Processing Rate = 1,003,256 kg for 15 months
Total Project Life = 15 months life

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

High-Efficiency Particulate Air (HEPA)
Filters System 1 Adjustment Factor = 0.01
HEPA Filters System 2 Adjustment Factor = 0.01

[f]The annualized emissions are calculated by the following equation:

Annualized Emissions = Total Emissions × 12 months/Total Project Life.

*Emissions of ^{241}Am were calculated as a decay product of ^{241}Pu by the following equation:

$$A_{Am241} = \frac{\lambda_{Am241} \times A_{Pu241} \times \left(e^{-\lambda_{Pu241}T} - e^{-\lambda_{Am241}T}\right)}{\lambda_{Am241} - \lambda_{Pu241}}$$

where $\lambda = \ln(2)/t_{1/2}$.

Bq = becquerel

Ci = curie.

g = gram.

TRU = transuranic.

Table B.1-3. Estimated radionuclide emissions for waste treatment of supernate for the Proposed Action

Radionuclide	Radionuclide composition[a] (Bq/mL)	(Bq/g)	(Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control: Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	0			2.18E+01				0.00E+00
Ag-110	0			7.80E-07				0.00E+00
Ag-110m	0			6.84E-01				0.00E+00
Am-241				4.32E+02		6.24E-06	6.24E-10	4.99E-10
Am-243	0			7.37E+03				0.00E+00
Au-196	0			1.69E-02				0.00E+00
Au-198	0			7.38E-03				0.00E+00
Bk-249	0			8.76E-01				0.00E+00
C-14	95.45	83.00	2.24E-09	5.73E+03	2.24E-09	1.55E-03	1.55E-07	1.24E-07
Ce-144	1305.38	1135.11	3.07E-08	7.80E-01	2.89E-10	2.00E-04	2.00E-08	1.60E-08
Cf-249	0			3.51E+02				0.00E+00
Cf-252	2.07	1.80	4.86E-11	2.65E+00	1.23E-11	8.50E-06	8.50E-10	6.80E-10
Cm-240	0			7.39E-02				0.00E+00
Cm-242	0			1.63E+02				0.00E+00
Cm-243	0			2.91E+01				0.00E+00
Cm-244	883.44	768.21	2.08E-08	1.81E+01	1.70E-08	1.18E-02	1.18E-06	9.40E-07
Cm-245	0			8.50E+03				0.00E+00
Cm-246	0			4.73E+03				0.00E+00
Cm-248	0			3.40E+05				0.00E+00
Co-60	838.97	729.54	1.97E-08	5.27E+00	9.89E-09	6.84E-03	6.84E-07	5.47E-07
Cs-134	8903.12	7741.84	2.09E-07	2.06E+00	3.59E-08	2.49E-02	2.49E-06	1.99E-06
Cs-137	273946.86	238214.66	6.44E-06	3.01E+01	5.70E-06	3.95E+00	3.95E-04	3.16E-04
Es-253	0			5.60E-02				0.00E+00
Es-254m	0			4.48E-03				0.00E+00
Eu-152	3959.72	3443.23	9.31E-08	1.35E+01	7.11E-08	4.92E-02	4.92E-06	3.94E-06
Eu-154	1651.86	1436.40	3.88E-08	8.59E+00	2.54E-08	1.76E-02	1.76E-06	1.41E-06
Eu-155	1037.85	902.48	2.44E-08	4.76E+00	1.14E-08	7.86E-03	7.86E-07	6.29E-07
Fe-59	0			1.22E-01				0.00E+00
Gd-153	0			6.61E-01				0.00E+00
H-3	169.53	147.42	3.98E-09	1.23E+01	2.97E-09	2.05E-03	2.05E-07	1.64E-07
I-129	0.15	0.13	3.53E-12	1.57E+07	3.53E-12	2.44E-06	2.44E-10	1.95E-10
I-131	0			2.20E-02				0.00E+00
Nb-95	129.69	112.77	3.05E-09	9.58E-02	9.55E-26	6.61E-20	6.61E-24	5.29E-24
Ni-63	0			1.00E+02				0.00E+00
Np-237	0			2.14E+06				0.00E+00
Pa-231	0			3.28E+04				0.00E+00
Pm-147	0			2.62E+00				0.00E+00
Po-209	0			1.02E+02				0.00E+00
Pu-238	4.22	3.67	9.92E-11	8.77E+01	9.51E-11	6.58E-05	6.58E-09	5.27E-09
Pu-239	3.48	3.03	8.18E-11	2.41E+04	8.18E-11	5.66E-05	5.66E-09	4.53E-09
Pu-240	3.39	2.95	7.97E-11	6.56E+03	7.96E-11	5.51E-05	5.51E-09	4.41E-09
Pu-241	66.80	58.09	1.57E-09	1.44E+01	1.22E-09	8.43E-04	8.43E-08	6.74E-08
Pu-242	0.17	0.15	4.00E-12	3.73E+05	4.00E-12	2.76E-06	2.76E-10	2.21E-10
Pu-244	0.02	0.02	4.70E-13	8.00E+05	4.70E-13	3.25E-07	3.25E-11	2.60E-11
Ra-223	0			3.13E-02				0.00E+00
Ra-226	0			1.60E+03				0.00E+00
Ru-106	2314.29	2012.43	5.44E-08	1.02E+00	1.55E-09	1.07E-03	1.07E-07	8.58E-08
Sb-125	0			2.76E+00				0.00E+00
Sr-90	11018.92	9581.67	2.59E-07	2.88E+01	2.28E-07	1.58E-01	1.58E-05	1.26E-05
Tc-99	1149.98	999.98	2.70E-08	2.11E+05	2.70E-08	1.87E-02	1.87E-06	1.50E-06
Te-123	0			1.00E+08				0.00E+00
Te-123m	0			3.28E-01				0.00E+00
Th-230	0			7.54E+04				0.00E+00
Th-232	0.04	0.03	9.40E-13	1.41E+10	9.40E-13	6.51E-07	6.51E-11	5.20E-11
U-232	20.00	17.39	4.70E-10	6.89E+01	4.46E-10	3.09E-04	3.09E-08	2.47E-08
U-233	143.14	124.47	3.36E-09	1.59E+05	3.36E-09	2.33E-03	2.33E-07	1.86E-07
U-234	2.90	2.52	6.82E-11	2.46E+05	6.82E-11	4.72E-05	4.72E-09	3.77E-09
U-235	0.12	0.10	2.82E-12	3.80E+06	2.82E-12	1.95E-06	1.95E-10	1.56E-10
U-236	0.07	0.06	1.65E-12	2.34E+07	1.65E-12	1.14E-06	1.14E-10	9.11E-11
U-238	3.82	3.32	8.98E-11	4.47E+09	8.98E-11	6.21E-05	6.21E-09	4.97E-09
U-239	0			4.46E-05				0.00E+00
Y-90	0			7.31E-03				0.00E+00

Table B.1-3 (continued)

Radionuclide	Radionuclide composition[a] (Bq/mL)	(Bq/g)	(Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control: Project life[e] (Ci)	Annualized[f] (Ci/year)
Zn-65	0			6.69E-01				0.00E+00
Zr-95	147.69	128.43	3.47E-09	1.75E-01	3.34E-18	2.31E-12	2.31E-16	1.85E-16
Total								3.40E-04

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Supernatant Liquids at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Number ORNL/TM-13551, Addendum 1. An average density value for supernate was obtained from Table 4.1, p. 3, of the above report to calculate a mass faction for each metal.

Supernate Density = 1.15 g/mL.

[b]The amount of curies present for each radionuclide is reduced by the corresponding half-life to account for the species decay. The equation for estimating radionuclide decay is:

$$A = A_o \times \exp -[\ln(2) / t_{1/2} * T].$$

The half-life of each radionuclide was obtained from the web site www.dne.bnl.gov/CoN/index.html.

T is the time between the time of sample analysis (October 1997) to the time of process startup (January 2003):

T = 5.25 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Sludge Processing Rate × Emissions Factor × Composition.

The processing rate and the operating schedule obtained from the FWEC proposal are:

Total Supernate Processing Rate = 692,000 kg for 15 months
Total Project Life = 15 months life

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

High-Efficiency Particulate Air (HEPA)
Filters System 1 Adjustment Factor = 0.01
HEPA Filters System 2 Adjustment Factor = 0.01

[f]The annualized emissions are calculated by the following equation:

Annualized Emissions = Total Emissions × 12 months/Total Project Life.

*Emissions of ^{241}Am were calculated as a decay product of ^{241}Pu by the following equation:

$$A_{Am241} = \frac{\lambda_{Am241} \times A_{Pu241} \times \left(e^{-\lambda_{Pu241}T} - e^{-\lambda_{Am241}T}\right)}{\lambda_{Am241} - \lambda_{Pu241}}$$

where $\lambda = \ln(2)/t_{1/2}$.

Bq = becquerel.
Ci = curie.
g = gram.
mL = milliliter.

Table B.1-4. Estimated radionuclide emissions for TRU waste treatment of solids for the Proposed Action

Radionuclide	Radionuclide[a] composition (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	1.01E-03	2.18E+01	8.19E-04	8.19E-07	8.19E-13	6.55E-13
Ag-110	0.00E+00	7.80E-07				0.00E+00
AG-110m	0.00E+00	6.84E-01				0.00E+00
Am-241		4.32E+02		5.14E-01	5.14E-07	4.12E-07
Am-243	1.05E+01	7.37E+03	1.05E+01	1.05E-02	1.05E-08	8.37E-09
Au-196	0.00E+00	1.69E-02				0.00E+00
Au-198	0.00E+00	7.38E-03				0.00E+00
Bk-249	5.25E+00	8.76E-01	2.87E-02	2.87E-05	2.87E-11	2.30E-11
C-14	1.70E-04	5.73E+03	1.70E-04	1.70E-07	1.70E-13	1.36E-13
Ce-144	0.00E+00	7.80E-01				0.00E+00
Cf-249	1.52E-02	3.51E+02	1.50E-02	1.50E-05	1.50E-11	1.20E-11
Cf-252	6.80E+01	2.65E+00	1.21E+01	1.21E-02	1.21E-08	9.69E-09
Cm-240	1.00E-03	7.39E-02	1.56E-30	1.56E-33	1.56E-39	1.25E-39
Cm-242	6.77E+01	1.63E+02	6.59E+01	6.59E-02	6.59E-08	5.27E-08
Cm-243	0.00E+00	2.91E+01				0.00E+00
Cm-244	2.79E+03	1.81E+01	2.17E+03	2.17E+00	2.17E-06	1.74E-06
Cm-245	3.07E-03	8.50E+03	3.07E-03	3.07E-06	3.07E-12	2.46E-12
Cm-246	1.00E-05	4.73E+03	9.99E-06	9.99E-09	9.99E-15	8.00E-15
Cm-248	2.63E-02	3.40E+05	2.63E-02	2.63E-05	2.63E-11	2.11E-11
Co-60	7.01E+00	5.27E+00	2.95E+00	2.95E-03	2.95E-09	2.36E-09
Cs-134	0.00E+00	2.06E+00				0.00E+00
Cs-137	3.43E+03	3.01E+01	2.95E+03	2.95E+00	2.95E-06	2.36E-06
Es-253	8.00E+00	5.60E-02	3.49E-35	3.49E-38	3.49E-44	2.79E-44
Es-254m	1.09E+01	4.48E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Eu-152	6.50E-04	1.35E+01	4.64E-04	4.64E-07	4.64E-13	3.71E-13
Eu-154	0.00E+00	8.59E+00				0.00E+00
Eu-155	0.00E+00	4.76E+00				0.00E+00
Fe-59	4.01E+00	1.22E-01	2.18E-16	2.18E-19	2.18E-25	1.74E-25
Gd-153	0.00E+00	6.61E-01				0.00E+00
H-3	0.00E+00	1.23E+01				0.00E+00
I-129	0.00E+00	1.57E+07				0.00E+00
I-131	5.00E-01	2.20E-02	2.84E-91	2.84E-94	2.84E-100	2.28E-100
Nb-95	0.00E+00	9.58E-02				0.00E+00
Ni-63	1.11E-04	1.00E+02	1.06E-04	1.06E-07	1.06E-13	8.49E-14
Np-237	8.41E-01	2.14E+06	8.41E-01	8.41E-04	8.41E-10	6.73E-10
Pa-231	3.15E-01	3.28E+04	3.15E-01	3.15E-04	3.15E-10	2.52E-10
Pm-147	4.65E+00	2.62E+00	8.17E-01	8.17E-04	8.17E-10	6.54E-10
Po-209	2.00E-06	1.02E+02	1.91E-06	1.91E-09	1.91E-15	1.53E-15
Pu-238	3.99E+03	8.77E+01	3.79E+03	3.79E+00	3.79E-06	3.03E-06
Pu-239	1.03E+03	2.41E+04	1.03E+03	1.03E+00	1.03E-06	8.25E-07
Pu-240	9.63E+02	6.56E+03	9.63E+02	9.63E-01	9.63E-07	7.70E-07
Pu-241	7.86E+04	1.44E+01	5.72E+04	5.72E+01	5.72E-05	4.58E-05
Pu-242	2.39E-01	3.73E+05	2.39E-01	2.39E-04	2.39E-10	1.91E-10
Pu-244	0.00E+00	8.00E+05				0.00E+00
Ra-223	2.20E-03	3.13E-02	1.10E-66	1.10E-69	1.10E-75	8.83E-76
Ra-226	1.61E+00	1.60E+03	1.61E+00	1.61E-03	1.61E-09	1.29E-09
Ru-106	0.00E+00	1.02E+00				0.00E+00
Sb-125	0.00E+00	2.76E+00				0.00E+00
Sr-90	2.13E+03	2.88E+01	1.82E+03	1.82E+00	1.82E-06	1.46E-06
Tc-99	1.71E+02	2.11E+05	1.71E+02	1.71E-01	1.71E-07	1.37E-07
Te-123	2.60E-05	1.00E+08	2.60E-05	2.60E-08	2.60E-14	2.08E-14
Te-123m	7.95E-04	3.28E-01	7.14E-10	7.14E-13	7.14E-19	5.71E-19
Th-230	1.20E-05	7.54E+04	1.20E-05	1.20E-08	1.20E-14	9.63E-15
Th-232	1.79E-03	1.41E+10	1.79E-03	1.79E-06	1.79E-12	1.43E-12
U-232	3.15E-01	6.89E+01	2.95E-01	2.95E-04	2.95E-10	2.36E-10
U-233	1.06E+02	1.59E+05	1.06E+02	1.06E-01	1.06E-07	8.45E-08
U-234	1.67E+01	2.46E+05	1.67E+01	1.67E-02	1.67E-08	1.33E-08
U-235	7.44E-03	3.80E+06	7.44E-03	7.44E-06	7.44E-12	5.95E-12
U-236	9.73E-05	2.34E+07	9.73E-05	9.73E-08	9.73E-14	7.78E-14
U-238	4.35E-02	4.47E+09	4.35E-02	4.35E-05	4.35E-11	3.48E-11
U-239	0.00E+00	4.46E-05				0.00E+00
Y-90	3.40E-06	7.31E-03	3.31E-277	3.31E-280	3.31E-286	2.65E-286

Table B.1-4 (continued)

Radionuclide	Radionuclide[a] composition (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed[b] radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control: Project life[e] (Ci)	Radionuclide emissions after control: Annualized[f] (Ci/year)
Zn-65	2.80E-03	6.69E-01	3.05E-06	3.05E-09	3.05E-15	2.44E-15
Zr-95	0.00E+00	1.75E-01				0.00E+00
Total						5.67E-05

[a]Composition data obtained from U.S. Department of Energy Memorandum: "TRU Waste Baseline Inventory Report for Oak Ridge," June 1996.

[b]The amount of curies present for each radionuclide is reduced by the corresponding half-life to account for the species decay. The equation for estimating radionuclide decay is:

$$A = A_o \times \exp -[\ln(2) / t_{1/2} * T].$$

The half-life of each radionuclide was obtained from the web site www.dne.bnl.gov/CoN/index.html.

T is the time between the time of sample analysis (June 1996) to the time of process startup (January 2003):

T = 6.58 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Glovebox/Hot Cell High-Efficiency Particulate Air (HEPA) Filters Adjustment Factor	= 0.01
Glovebox/Hot Cell Carbon Filters Adjustment Factor	= 0.10
HEPA Filters System 1 Adjustment Factor	= 0.01
HEPA Filters System 2 Adjustment Factor	= 0.01

Note that no emissions reduction credit is taken for the carbon system, since this factor only applied to iodine gas and no iodine is present in the solid waste.

[f]The annualized emissions are calculated by the following equation:

Annualized Emissions = Total Emissions × 12 months/15-month Project Life

*Emissions of ^{241}Am were calculated as a decay product of ^{241}Pu by the following equation:

$$A_{Am241} = \frac{\lambda_{Am241} \times A_{Pu241} \times \left(e^{-\lambda_{Pu241}T} - e^{-\lambda_{Am241}T}\right)}{\lambda_{Am241} - \lambda_{Pu241}}$$

where $\lambda = \ln(2) / t_{1/2}$.

Ci = curie.

TRU = transuranic.

Table B.1-5. CAP.88-PC Exposure modeling results summary for the Proposed Action

Radionuclide	Total emissions (Ci/year)	Effective dose equivalent (mrem/year)	Total lifetime fatal cancer risk
Ac-227	6.55E-13	8.97E-11	5.80E-16
Ag-110	0.00E+00	0.00E+00	0.00E+00
Ag-110m	0.00E+00	0.00E+00	0.00E+00
Am-241	5.58E-07	7.63E-05	3.87E-10
Am-243	8.37E-09	1.17E-06	6.24E-12
Au-196	0.00E+00		
Au-198	5.25E-254		
Bk-249	2.30E-11		
C-14	1.24E-07	4.35E-10	1.06E-14
Ce-144	1.20E-07	6.59E-08	9.17E-13
Cf-249	1.20E-11		
Cf-252	2.72E-08	8.45E-07	9.51E-12
Cm-240	1.25E-39		
Cm-242	5.27E-08	1.84E-07	1.82E-12
Cm-243	1.94E-05	1.84E-03	1.20E-08
Cm-244	6.52E-05	4.60E-03	2.76E-08
Cm-245	2.46E-12	3.56E-10	1.95E-15
Cm-246	8.00E-15	1.10E-12	5.30E-18
Cm-248	2.11E-11	1.07E-08	5.19E-14
Co-60	3.32E-05	8.37E-04	2.04E-08
Cs-134	3.37E-06	3.77E-05	9.40E-10
Cs-137	1.41E-03	4.90E-03	1.28E-07
Es-253	2.79E-44		
Es-254m	0.00E+00		
Eu-152	2.13E-04	5.34E-03	1.27E-07
Eu-154	9.40E-05	1.85E-03	4.42E-08
Eu-155	1.96E-05	1.44E-05	3.09E-10
Fe-59	1.74E-25	7.92E-26	1.78E-30
Gd-153	0.00E+00		
H-3	2.18E-07	1.31E-11	3.55E-16
I-129	1.95E-10	6.42E-09	3.74E-14
I-131	2.28E-100	0.00E+00	0.00E+00
Nb-95	5.66E-24	2.19E-24	3.61E-29
Ni-63	8.49E-14	2.56E-15	4.58E-20
Np-237	1.75E-08	2.44E-06	1.24E-11
Pa-231	2.52E-10	3.76E-08	1.31E-13
Pm-147	6.54E-10	2.21E-11	3.14E-16
Po-209	1.53E-15		
Pu-238	1.59E-05	1.74E-03	9.63E-09
Pu-239	7.41E-06	9.00E-04	4.70E-09
Pu-240	2.83E-06	3.43E-04	1.80E-09
Pu-241	6.32E-05	1.50E-04	5.68E-10
Pu-242	4.86E-09	5.62E-07	2.93E-12
Pu-244	4.38E-10	5.01E-08	2.66E-13
Ra-223	8.83E-76	0.00E+00	0.00E+00
Ra-226	1.29E-09	4.50E-08	2.49E-13
Ru-106	7.28E-07	5.19E-07	8.24E-12
Sb-125	0.00E+00	0.00E+00	0.00E+00
Sr-90-	3.48E-03	3.98E-02	6.70E-07
Tc-99	2.44E-06	5.04E-06	1.83E-10

Table B.1-5 (continued)

Radionuclide	Total emissions (Ci/year)	Effective dose equivalent (mrem/year)	Total lifetime fatal cancer risk
Te-123	2.08E-14		
Te-123m	5.71E-19		
Th-230	9.63E-15	2.46E-13	1.42E-18
Th-232	5.62E-08	1.69E-06	7.95E-12
U-232	2.49E-08	2.51E-06	1.40E-11
U-233	4.91E-06	1.74E-04	1.16E-09
U-234	2.08E-06	7.32E-05	4.86E-10
U-235	5.41E-08	2.43E-06	2.66E-11
U-236	4.58E-09	1.52E-07	1.01E-12
U-238	2.05E-06	6.47E-05	4.56E-10
U-239	0.00E+00		
Y-90	2.65E-286	0.00E+00	0.00E+00
Zn-65	2.44E-15	7.45E-15	1.93E-19
Zr-95	2.22E-15	8.36E-16	1.78E-20
Totals	5.44E-03	6.28E-02	1.05E-06

Ci = curie.
mrem = millirem.

Table B.1-6. Summary of TRU waste treatment hourly particulate emissions (lbs/h) for the Proposed Action

Particulate contaminant	Classification	Average hourly emissions (lbs/h)				Maximum[a] hourly emissions (lbs/h)	Average[b] annual emissions (tons/year)
		Sludge	Supernate	Solids	Total		
TSP		3.43E-01	3.43E-01	3.43E-03	6.89E-01	8.61E-01	2.07E+00
Total HAP		3.81E-04	4.83E-06	2.23E-08	3.86E-04	4.82E-04	1.16E-03
Antimony (Sb)	HAP	9.36E-06	2.95E-07	0.00E+00	9.66E-06	1.21E-05	2.90E-05
Arsenic (As)	HAP	5.89E-06	5.99E-07	0.00E+00	6.49E-06	8.11E-06	1.95E-05
Beryllium (Be)	HAP	6.27E-07	2.98E-09	0.00E+00	6.30E-07	7.88E-07	1.89E-06
Cadmium (Cd)	HAP	3.15E-06	1.16E-07	2.02E-09	3.27E-06	4.09E-06	9.82E-06
Chromium (Cr)	HAP	1.16E-04	2.03E-06	0.00E+00	1.18E-04	1.47E-04	3.53E-04
Cobalt (Co)	HAP	1.25E-06	4.77E-08	0.00E+00	1.30E-06	1.62E-06	3.89E-06
Lead (Pb)	HAP	1.58E-04	7.54E-07	1.82E-08	1.59E-04	1.99E-04	4.78E-04
Manganese (Mn)	HAP	3.57E-05	9.84E-08	0.00E+00	3.58E-05	4.48E-05	1.07E-04
Mercury (Hg)	HAP	2.25E-05	2.36E-07	2.02E-09	2.27E-05	2.84E-05	6.82E-05
Nickel (Ni)	HAP	2.17E-05	3.67E-07	0.00E+00	2.21E-05	2.76E-05	6.63E-05
Selenium (Se)	HAP	6.42E-06	2.80E-07	0.00E+00	6.70E-06	8.38E-06	2.01E-05
Aluminum (Al)		2.75E-03	4.20E-06	0.00E+00	2.75E-03	3.44E-03	8.25E-03
Barium (Ba)		3.21E-05	5.46E-07	0.00E+00	3.27E-05	4.08E-05	9.80E-05
Bismuth (Bi)		0.00E+00	8.05E-07	0.00E+00	8.05E-07	1.01E-06	2.41E-06
Boron (B)		4.29E-06	3.76E-07	0.00E+00	4.66E-06	5.83E-06	1.40E-05
Calcium (Ca)		8.26E-03	4.07E-04	0.00E+00	8.67E-03	1.08E-02	2.60E-02
Cerium (Ce)		0.00E+00	1.10E-07	0.00E+00	1.10E-07	1.38E-07	3.31E-07
Cesium (Cs)		1.36E-06	5.37E-07	0.00E+00	1.89E-06	2.37E-06	5.68E-06
Copper (Cu)		1.83E-05	2.56E-07	0.00E+00	1.86E-05	2.33E-05	5.58E-05
Gallium (Ga)		0.00E+00	9.84E-08	0.00E+00	9.84E-08	1.23E-07	2.95E-07
Iodine (I)		0.00E+00	4.41E-06	0.00E+00	4.41E-06	5.51E-06	1.32E-05
Iron (Fe)		1.48E-03	3.25E-06	0.00E+00	1.48E-03	1.86E-03	4.45E-03
Lanthanum (La)		0.00E+00	1.19E-08	0.00E+00	1.19E-08	1.49E-08	3.58E-08
Lithium (Li)		0.00E+00	7.96E-06	0.00E+00	7.96E-06	9.95E-06	2.39E-05
Magnesium (Mg)		1.39E-03	5.32E-05	0.00E+00	1.44E-03	1.80E-03	4.33E-03
Molybdenum (Mo)		0.00E+00	3.70E-07	0.00E+00	3.70E-07	4.62E-07	1.11E-06
Niobium (Nb)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Phosphorus (P)		4.51E-03	2.08E-05	0.00E+00	4.53E-03	5.67E-03	1.36E-02
Potassium (K)		2.19E-03	3.38E-03	0.00E+00	5.57E-03	6.96E-03	1.67E-02
Rubidium (Rb)		0.00E+00	3.52E-07	0.00E+00	3.52E-07	4.40E-07	1.06E-06
Silicon (Si)		7.79E-04	1.64E-05	0.00E+00	7.96E-04	9.95E-04	2.39E-03
Silver (Ag)		2.70E-06	5.96E-08	4.77E-10	2.76E-06	3.45E-06	8.29E-06
Sodium (Na)		1.50E-02	1.63E-02	0.00E+00	3.14E-02	3.92E-02	9.42E-02
Strontium (Sr)		3.04E-05	3.84E-06	0.00E+00	3.43E-05	4.28E-05	1.03E-04
Thallium (Th)		2.01E-03	3.28E-06	0.00E+00	2.02E-03	2.52E-03	6.05E-03
Thallium (Tl)		4.13E-06	5.28E-07	0.00E+00	4.66E-06	5.82E-06	1.40E-05
Tin (Sn)		0.00E+00	1.13E-07	0.00E+00	1.13E-07	1.42E-07	3.40E-07
Titanium (Ti)		0.00E+00	1.52E-07	0.00E+00	1.52E-07	1.90E-07	4.56E-07
Tungsten (W)		0.00E+00	1.37E-07	0.00E+00	1.37E-07	1.71E-07	4.11E-07
Uranium (U)		1.65E-02	1.30E-04	0.00E+00	1.66E-02	2.08E-02	4.99E-02
Vanadium (V)		9.87E-07	2.68E-08	0.00E+00	1.01E-06	1.27E-06	3.04E-06
Zinc (Zn)		4.57E-05	4.14E-06	0.00E+00	4.98E-05	6.23E-05	1.49E-04
Zirconium (Zr)		0.00E+00	8.94E-09	0.00E+00	8.94E-09	1.12E-08	2.68E-08

[a]Maximum hourly is estimated by multiplying the average hourly by 1.25.
[b]Average annual emissions are the average hourly emissions multiplied by 6000 h/year.
h = hour.
HAP = hazardous air pollutant.
lb = pound.
TRU = transuranic.

Table B.1-7. Estimated metals emissions for TRU/sludge waste treatment for the Proposed Action

Metals	Metals[a] composition (mg/kg)	Metals mass fraction (g/total g)	Metals[b] concentration (g/dscf)	Uncontrolled metal[c] emissions for the project		Emissions after[d] control for the project		Average[e] hourly emissions (lbs/h)
				(g)	(lbs)	(g)	(lbs)	
TSP			1.30E-01	1.12E+09	2 47E+06	1,120,731	2468.57	3.43E-01
Silver (Ag)	7.88	7.88E-06	1.02E-06	8.83E+03	1.95E+01	8.83E+00	1.95E-02	2 70E-06
Aluminum (Al)	8012.46	8.01E-03	1.04E-03	8.98E+06	1.98E+04	8.98E+03	1.98E+01	2.75E-03
Arsenic (As)	17.18	1.72E-05	2.23E-06	1.93E+04	4.24E+01	1.93E+01	4.24E-02	5.89E-06
Boron (B)	12.51	1.25E-05	1.62E-06	1.40E+04	3.09E+01	1.40E+01	3.09E-02	4.29E-06
Barium (Ba)	93.65	9.37E-05	1.21E-05	1.05E+05	2.31E+02	1.05E+02	2.31E-01	3.21E-05
Beryllium (Be)	1.83	1.83E-06	2.37E-07	2.05E+03	4.52E+00	2.05E+00	4.52E-03	6 27E-07
Bismuth (Bi)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Calcium (Ca)	24100.46	2.41E-02	3.13E-03	2.70E+07	5.95E+04	2.70E+04	5.95E+01	8.26E-03
Cadmium (Cd)	9.20	9.20E-06	1.19E-06	1.03E+04	2.27E+01	1.03E+01	2.27E-02	3.15E-06
Cerium (Ce)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Cobalt (Co)	3.64	3.64E-06	4.72E-07	4.08E+03	8.99E+00	4.08E+00	8.99E-03	1.25E-06
Chromium (Cr)	337.40	3.37E-04	4.38E-05	3.78E+05	8.33E+02	3.78E+02	8.33E-01	1.16E-04
Cesium (Cs)	3.96	3.96E-06	5.14E-07	4.44E+03	9.78E+00	4.44E+00	9.78E-03	1.36E-06
Copper (Cu)	53.51	5.35E-05	6.94E-06	6.00E+04	1.32E+02	6.00E+01	1.32E-01	1.83E-05
Iron (Fe)	4319.89	4.32E-03	5.60E-04	4.84E+06	1.07E+04	4.84E+03	1.07E+01	1.48E-03
Gallium (Ga)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00	0.00E+00
Mercury (Hg)	65.61	6.56E-05	8.51E-06	7.35E+04	1.62E+02	7.35E+01	1.62E-01	2.25E-05
Iodine (I)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Potassium (K)	6381.12	6.38E-03	8.28E-04	7.15E+06	1.58E+04	7.15E+03	1.58E+01	2.19E-03
Lanthanum (La)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lithium (Li)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Magnesium (Mg)	4052.20	4.05E-03	5.26E-04	4.54E+06	1.00E+04	4.54E+03	1.00E+01	1.39E-03
Manganese (Mn)	104.16	1.04E-04	1.35E-05	1.17E+05	2.57E+02	1.17E+02	2.57E-01	3.57E-05
Molybdenum (Mo)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00	0 00E+00	0.00E+00
Sodium (Na)	43892.46	4.39E-02	5.69E-03	4.92E+07	1.08E+05	4.92E+04	1.08E+02	1.50E-02
Niobium (Nb)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	63.42	6.34E-05	8.23E-06	7.11E+04	1.57E+02	7.11E+01	1.57E-01	2.17E-05
Phosphorus (P)	13158.71	1.32E-02	1.71E-03	1.47E+07	3.25E+04	1.47E+04	3.25E+01	4 51E-03
Lead (Pb)	462.24	4.62E-04	6.00E-05	5.18E+05	1.14E+03	5.18E+02	1.14E+00	1.58E-04
Rubidium (Rb)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00
Antimony (Sb)	27.30	2.73E-05	3.54E-06	3.06E+04	6.74E+01	3 06E+01	6.74E-02	9.36E-06
Selenium (Se)	18.73	1.87E-05	2.43E-06	2.10E+04	4.62E+01	2.10E+01	4.62E-02	6 42E-06
Silicon (Si)	2272.82	2.27E-03	2.95E-04	2.55E+06	5.61E+03	2.55E+03	5 61E+00	7.79E-04
Tin (Sn)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00	0.00E+00	0 00E+00
Strontium (Sr)	88.75	8.88E-05	1.15E-05	9.95E+04	2.19E+02	9.95E+01	2.19E-01	3.04E-05
Thallium (Th)	5867.64	5.87E-03	7.61E-04	6.58E+06	1.45E+04	6.58E+03	1.45E+01	2.01E-03
Titanium (Ti)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Thallium (Tl)	12.05	1.21E-05	1.56E-06	1.35E+04	2.97E+01	1.35E+01	2.97E-02	4 13E-06
Uranium (U)	48161.88	4.82E-02	6.25E-03	5.40E+07	1.19E+05	5 40E+04	1.19E+02	1.65E-02
Vanadium (V)	2.88	2.88E-06	3.74E-07	3.23E+03	7.11E+00	3.23E+00	7.11E-03	9.87E-07
Tungsten (W)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00	0.00E+00	0 00E+00
Zinc (Zn)	133.22	1.33E-04	1.73E-05	1.49E+05	3.29E+02	1.49E+02	3.29E-01	4.57E-05
Zirconium (Zr)		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Number ORNL/TM-13351.

[b]The amount of total suspended particulate (TSP) matter reaching the first exhaust system High-Efficiency Particulate Air (HEPA) filter is assumed to be:

Airborne Particulate Conc. = 2 0 gr/dscf.

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Exhaust Stream Flowrate × TSP Concentration × Metal Mass Fraction

Operating schedule data were obtained from the FWENC proposal:

Air Flow Rate	=	20,000 dscfm assumed rate from sludge process
Project Operating Schedule	=	15 months life 4 weeks/month 5 d/week 24 h/d
Calculated Operating Hours	=	7,200 h for the 15 months

[d]The two HEPA filtration systems are assumed to have the following removal efficiencies:

HEPA Filter 1 Removal = 99%
HEPA Filter 2 Removal = 90%

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

d = day.
dscf = dry standard cubic foot.
dscfm = dry standard cubic feet per minute.
g = gram.
gr/dscf = grains per dry standard cubic foot.
h = hour.
lb = pound.
kg = kilogram.
mg = milligram.
TRU = transuranic.

Table B.1-8. Estimated metals emissions for supernate waste treatment for the Proposed Action

Metals	Metals[a] composition (mg/L)	Metals[b] composition (g/total g)	Metals[c] concentration (g/dscf)	Uncontrolled metal[d] for the project (g)	Uncontrolled metal[d] for the project (lbs)	Emissions after[e] control for the project (g)	Emissions after[e] control for the project (lbs)	Average[f] hourly emissions (lbs/h)
TSP			1.30E-01	1.12E+09	2.47E+06	1,120,731	2468.57	3.43E-01
Silver (Ag)	0.20	1.74E-07	2.26E-08	1.95E+02	4.29E-01	1.95E-01	4 29E-04	5.96E-08
Aluminum (Al)	14.08	1.22E-05	1.59E-06	1.37E+04	3.02E+01	1.37E+01	3.02E-02	4.20E-06
Arsenic (As)	2.01	1.75E-06	2.27E-07	1.96E+03	4.31E+00	1.96E+00	4.31E-03	5.99E-07
Boron (B)	1.26	1.10E-06	1.42E-07	1.23E+03	2.70E+00	1.23E+00	2.70E-03	3.76E-07
Barium (Ba)	1.83	1.59E-06	2.06E-07	1.78E+03	3.93E+00	1.78E+00	3.93E-03	5 46E-07
Beryllium (Be)	0.01	8.70E-09	1.13E-09	9.75E+00	2.15E-02	9.75E-03	2.15E-05	2.98E-09
Bismuth (Bi)	2.70	2.35E-06	3.05E-07	2.63E+03	5.80E+00	2.63E+00	5.80E-03	8.05E-07
Calcium (Ca)	1363.88	1.19E-03	1.54E-04	1.33E+06	2.93E+03	1.33E+03	2.93E+00	4.07E-04
Cadmium (Cd)	0.39	3.39E-07	4.40E-08	3.80E+02	8.37E-01	3.80E-01	8.37E-04	1.16E-07
Cerium (Ce)	0.37	3.22E-07	4.17E-08	3.61E+02	7.94E-01	3.61E-01	7.94E-04	1.10E-07
Cobalt (Co)	0.16	1.39E-07	1.80E-08	1.56E+02	3.43E-01	1.56E-01	3.43E-04	4.77E-08
Chromium (Cr)	6.82	5.93E-06	7.69E-07	6.65E+03	1.46E+01	6.65E+00	1 46E-02	2.03E-06
Cesium (Cs)	1.80	1.57E-06	2.03E-07	1.75E+03	3.86E+00	1.75E+00	3.86E-03	5.37E-07
Copper (Cu)	0.86	7.48E-07	9.70E-08	8.38E+02	1.85E+00	8.38E-01	1.85E-03	2.56E-07
Iron (Fe)	10.89	9.47E-06	1.23E-06	1.06E+04	2.34E+01	1.06E+01	2.34E-02	3.25E-06
Gallium (Ga)	0.33	2.87E-07	3.72E-08	3.22E+02	7.08E-01	3.22E-01	7.08E-04	9 84E-08
Mercury (Hg)	0.79	6.87E-07	8.91E-08	7.70E+02	1.70E+00	7.70E-01	1.70E-03	2.36E-07
Iodine (I)	14.79	1.29E-05	1.67E-06	1.44E+04	3.17E+01	1.44E+01	3.17E-02	4.41E-06
Potassium (K)	11335.07	9.86E-03	1.28E-03	1.10E+07	2.43E+04	1.10E+04	2 43E+01	3.38E-03
Lanthanum (La)	0.04	3.48E-08	4.51E-09	3.90E+01	8.59E-02	3.90E-02	8.59E-05	1 19E-08
Lithium (Li)	26.69	2.32E-05	3.01E-06	2.60E+04	5.73E+01	2.60E+01	5 73E-02	7.96E-06
Magnesium (Mg)	178.49	1.55E-04	2.01E-05	1.74E+05	3.83E+02	1.74E+02	3.83E-01	5 32E-05
Manganese (Mn)	0.33	2.87E-07	3.72E-08	3.22E+02	7.08E-01	3.22E-01	7.08E-04	9 84E-08
Molybdenum (Mo)	1.24	1.08E-06	1.40E-07	1.21E+03	2.66E+00	1.21E+00	2.66E-03	3 70E-07
Sodium (Na)	54828.38	4.77E-02	6.18E-03	5.34E+07	1.18E+05	5.34E+04	1.18E+02	1.63E-02
Niobium (Nb)	0.00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0 00E+00	0.00E+00	0 00E+00
Nickel (Ni)	1.23	1.07E-06	1.39E-07	1.20E+03	2.64E+00	1.20E+00	2.64E-03	3.67E-07
Phosphorus (P)	69.88	6.08E-05	7.88E-06	6.81E+04	1.50E+02	6.81E+01	1.50E-01	2 08E-05
Lead (Pb)	2.53	2.20E-06	2.85E-07	2.47E+03	5.43E+00	2.47E+00	5.43E-03	7 54E-07
Rubidium (Rb)	1.18	1.03E-06	1.33E-07	1.15E+03	2.53E+00	1.15E+00	2 53E-03	3.52E-07
Antimony (Sb)	0 99	8.61E-07	1.12E-07	9 65E+02	2.13E+00	9.65E-01	2.13E-03	2.95E-07
Selenium (Se)	0.94	8.17E-07	1.06E-07	9.16E+02	2.02E+00	9 16E-01	2.02E-03	2 80E-07
Silicon (Si)	55.11	4.79E-05	6.22E-06	5.37E+04	1.18E+02	5.37E+01	1 18E-01	1 64E-05
Tin (Sn)	0.38	3.30E-07	4.29E-08	3.70E+02	8.16E-01	3 70E-01	8 16E-04	1.13E-07
Strontium (Sr)	12.87	1.12E-05	1.45E-06	1.25E+04	2.76E+01	1 25E+01	2.76E-02	3.84E-06
Thallium (Th)	11.01	9.57E-06	1.24E-06	1.07E+04	2.36E+01	1 07E+01	2 36E-02	3 28E-06
Titanium (Ti)	0.51	4.43E-07	5.75E-08	4.97E+02	1.09E+00	4 97E-01	1 09E-03	1.52E-07
Thallium (Tl)	1.77	1.54E-06	2.00E-07	1.72E+03	3.80E+00	1.72E+00	3 80E-03	5 28E-07
Uranium (U)	434 76	3.78E-04	4 90E-05	4.24E+05	9.33E+02	4.24E+02	9 33E-01	1 30E-04
Vanadium (V)	0.09	7.83E-08	1.02E-08	8.77E+01	1.93E-01	8.77E-02	1 93E-04	2 68E-08
Tungsten (W)	0.46	4.00E-07	5.19E-08	4.48E+02	9.87E-01	4 48E-01	9 87E-04	1 37E-07
Zinc (Zn)	13.89	1.21E-05	1.57E-06	1.35E+04	2.98E+01	1 35E+01	2 98E-02	4 14E-06
Zirconium (Zr)	0.03	2.61E-08	3.38E-09	2.92E+01	6.44E-02	2 92E-02	6 44E-05	8 94E-09

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Supernate Liquids at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Number ORNL/TM-13551, Addendum 1

[b]An average density value was obtained from Table 4.1, p. 3, of the above report to calculate a mass faction for each metal

Supernate Density = 1.15 g/mL.

[c]The amount of total suspended particulate (TSP) matter reaching the first exhaust system High-Efficiency Particulate Air (HEPA) filter is assumed to be

Airborne Particulate Conc. = 2.0 gr/dscf.

[d]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Exhaust Stream Flowrate × TSP Concentration × Metal Mass Fraction

Operating schedule data were obtained from the FWENC proposal:

Air Flow Rate	=	20,000 dscfm assumed rate from supernate process
Project Operating Schedule	=	15 months life 4 weeks/month 5 d/week 24 h/d
Calculated Operating Hours	=	7,200 h for the 15 months

'The two HEPA filtration systems are assumed to have the following removal efficiencies:

HEPA Filter 1 Removal = 99%
HEPA Filter 2 Removal = 99%

'The average hourly emissions are calculated by the following expression:

Average Hourly	=	Pounds Emitted for Project/Project Operating Hours
Airborne Particulate Conc.	=	2.0 gr/dscf
Project Operating Schedule	=	15 months life 4 weeks/month 5 d/week 24 h/d

d = day.

dscf = dry standard cubic foot.

dscfm = dry standard cubic feet per minute.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

L = liter.

lb = pound.

mg = milligram.

Table B.1-9. Metal emissions for TRU/RH solid wastes tretment for the Proposed Action using 40 *CFR* 61 Appendix D calculation procedures

Metal	Mass of[a] metals in waste (kg)	Uncontrolled[b,c] metals emissions (g)	(lbs)	Metals emissions[d] after control (g)	(lbs)	Average[e] hourly emissions (lbs/h)
Silver (Ag)	20	2.00E+01	4.41E-02	2.00E-04	4.41E-07	1.10E-10
Cadmium (Cd)	100	1.00E+02	2.20E-01	1.00E-03	2.20E-06	5.51E-10
Mercury (Hg)	100	1.00E+02	2.20E-01	1.00E-03	2.20E-06	5.51E-10
Lead (Pb)	980	9.80E+02	2.16E+00	9.80E-03	2.16E-05	5.40E-09
Total	1200					

	Concentration[f] (g/dscf)	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly (lbs/h)
TSP Hot Cell	0.13	3.11E+08	6.86E+05	3.11E+03	6.86E+00	1.71E-03

[a]Quantities are based on U.S. Department of Energy analysis and knowledge of process for the Resource Conservation and Recovery Act metals in the solid wastes.

[b]An emissions factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.001 fraction of the amount used.

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Metals Mass in Waste × Emissions Factor.

The operating schedule was obtained from the FWENC proposal:

Project Operating Schedule = 80 h/week
50 weeks/year

Calculated Operating Hours = 4000 h total

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Glovebox/Hot Cell High-Efficiency Particulate Air (HEPA) Filters Adjustment Factor	=	0.01
Glovebox/Hot Cell Carbon Filters Adjustment Factor	=	0.10
HEPA Filters System 1 Adjustment Factor	=	0.01
HEPA Filters System 2 Adjustment Factor	=	0.10

Note that no emissions reduction credit is taken for the carbon system, since this factor only applied to iodine gas and no iodine is present in the solid waste.

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project / Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system.

Exhaust Flowrate = 10,000 dscf assumed for hot cell.

dscf = dry standard cubic foot.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

kg = kilogram.

lb = pound.

RH = remote handled.

TRU = transuranic.

Table B.1-10. Metal emissions for TRU/CH solid wastes treatment for the Proposed Action using 40 *CFR* 61 Appendix D of NESHAP calculation procedures

Metal	Mass of[a] metals in waste (kg)	Uncontrolled[b,c] metals emissions (g)	(lbs)	Metals emissions[d] after control (g)	(lbs)	Average[e] hourly emissions (lbs/h)
Silver (Ag)	100	1.00E+02	2.20E-01	1.00E-03	2.20E-06	3.67E-10
Cadmium (Cd)	400	4.00E+02	8.81E-01	4.00E-03	8.81E-06	1.47E-09
Mercury (Hg)	400	4.00E+02	8.81E-01	4.00E-03	8.81E-06	1.47E-09
Lead (Pb)	3500	3.50E+03	7.71E+00	3.50E-02	7.71E-05	1.28E-08
Total	4400					

	Concentration[f] (g/dscf)	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly (lbs/h)
TSP Glove Box	0.13	4.67E+08	1.03E+06	4.67E+03	1.03E+01	1.71E-03

[a]Quantities are based on U.S. Department of Energy analysis and knowledge of process for the Resource Conservation Recovery Act metals in the solid wastes.

[b]An emissions factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.
Emission Factor = 0.001 fraction of the amount used.

[c]The uncontrolled emissions are estimated by the following expression:
Uncontrolled Rate = Metals Mass in Waste × Emissions Factor.

The operating schedule was obtained from the FWENC proposal:
Project Operating Schedule = 120 h/week
50 weeks/year
Calculated Operating Hours = 6000 h total

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Glovebox/Hot Cell High-Efficiency Particulate Air (HEPA) Filters Adjustment Factor	= 0.01
Glovebox/Hot Cell Carbon Filters Adjustment Factor	= 0.10
HEPA Filters System 1 Adjustment Factor	= 0.01
HEPA Filters System 2 Adjustment Factor	= 0.10

Note that no emissions reduction credit is taken for the carbon system, since this factor only applied to iodine gas and no iodine is present in the solid waste.

[e]The average hourly emissions are calculated by the following expression:
Average Hourly = Pounds Emitted for Project/Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system.
Exhaust Flowrate = 10,000 dscf assumed for hot cell.

CH = contact handled.
dscf = dry standard cubic foot.
g = gram.
gr/dscf = grains per dry standard cubic foot.
h = hour.
kg = kilogram.
lb = pound.
NESHAP = National Emission Standards for Hazardous Air Pollutants.
TRU = transuranic.

Table B.1-11. Particulate emissions from TRU solid wastes treatment (lbs/h) for the Proposed Action

Metal	RH waste emissions	CH waste emissions	Particulate emissions from solid waste
TSP	1.71E-03	1.71E-03	3.43E-03
Silver (Ag)	1.10E-10	3.67E-10	4.77E-10
Cadmium (Cd)	5.51E-10	1.47E-09	2.02E-09
Mercury (Hg)	5.51E-10	1.47E-09	2.02E-09
Lead (Pb)	5.40E-09	1.28E-08	1.82E-08

CH = contact handled.
h = hour.
lb = pound.
RH = remote handled.
TRU = transuranic.
TSP = total suspended particulate.

Table B.1-12. Summary of volatile organic emissions for the Proposed Action

	Sludge organic emissions		Supernate organic emissions		Total hourly organic emissions	
Tank farm	(lbs)	(lbs/h)	(lbs)	(lbs/h)	(lbs)	(lbs/h)
Bethel Valley	89.10	0.062	0.15	1.06E-04	89.25	0.062
GAAT	21.86	0.013	6.71	7.14E-04	28.57	0.014
Melton Valley	150.18	0.039	7.01	4.36E-04	157.30	0.039
OHF	1.48	0.007	1.40	6.61E-05	2.88	0.007
Total	**262.62**		**15.28**		**277.89**	

GAAT = Gunite and Associate Tanks.
h = hour.
lb = pound.
OHF = Old Hydrofracture Facility.

Table B.1-13. Estimated total organic emissions for the Proposed Action

Air contaminant	Classified as: VOC	HAP	Maximum[a] hourly emissions (lbs/h)	Average[b] hourly emissions (lbs/h)	Average[c] annual emissions (tons/year)
Total VOC			6.21E-02	5.18E-02	0.11
Total HAP			1.33E-03	1.11E-03	0.01
2-Butanone (MEK)	Yes	Yes	1.22E-06	1.02E-06	1.80E-04
Benzene	Yes	Yes	0.00E+00	0.00E+00	1.33E-06
Bis-(2-ethylhexyl)phthalate	Yes	Yes	0.00E+00	0.00E+00	7.80E-03
Bromomethane	Yes	Yes	5.07E-04	4.23E-04	2.90E-04
Carbon tetrachloride	Yes	Yes	0.00E+00	0.00E+00	1.47E-04
Chlorobenzene	Yes	Yes	0.00E+00	0.00E+00	8.60E-07
Chloroform	Yes	Yes	0.00E+00	0.00E+00	4.88E-06
Chloromethane	Yes	Yes	6.73E-06	5.61E-06	1.55E-06
Di-n-butylphthalate	Yes	Yes	7.02E-04	5.85E-04	2.17E-03
Ethylbenzene	Yes	Yes	0.00E+00	0.00E+00	1.42E-07
Hexachlorobenzene	Yes	Yes	0.00E+00	0.00E+00	2.97E-04
Methyl alcohol	Yes	Yes	0.00E+00	0.00E+00	1.95E-03
Methylene chloride	No	Yes	0.00E+00	0.00E+00	9.22E-06
Naphthalene	Yes	Yes	0.00E+00	0.00E+00	2.88E-04
Polychlorinated biphenyls	Yes	Yes	1.10E-04	9.13E-05	6.31E-05
Tetrachloroethene	Yes	Yes	0.00E+00	0.00E+00	6.84E-06
Toluene	Yes	Yes	0.00E+00	0.00E+00	3.71E-06
Trichloroethane	Yes	Yes	0.00E+00	0.00E+00	6.71E-08
Trichloroethene	Yes	Yes	0.00E+00	0.00E+00	2.94E-06
1,2-Dichoroethene	Yes	No	0.00E+00	0.00E+00	9.84E-07
1-Decanol	Yes	No	2.63E-04	2.19E-04	1.52E-04
1-Docosene	Yes	No	0.00E+00	0.00E+00	1.76E-04
1-Dotriacontanol	Yes	No	0.00E+00	0.00E+00	1.76E-04
1-Hexanol, 2-ethyl	Yes	No	2.37E-03	1.97E-03	1.50E-03
1-Methyldecyl-benzene	Yes	No	9.43E-04	7.86E-04	5.43E-04
1-Methylundecyl-benzene	Yes	No	7.23E-04	6.03E-04	4.17E-04
1-Nonadecanol	Yes	No	2.15E-04	1.79E-04	4.13E-04
1-Octanamine, N-nitroso-*n*-octyl-	Yes	No	0.00E+00	0.00E+00	1.88E-04
1-Propyl alcohol	Yes	No	0.00E+00	0.00E+00	1.89E-04
2,4,5-Trichlorophenol	Yes	No	0.00E+00	0.00E+00	7.71E-07
2,4-Dichlorophenol	Yes	No	0.00E+00	0.00E+00	1.61E-06
2-Butanamine	Yes	No	0.00E+00	0.00E+00	1.16E-06
2-Ethyl-1-hexanol	Yes	No	4.28E-06	3.57E-06	9.87E-07
2-Hexanone	Yes	No	0.00E+00	0.00E+00	1.14E-06
2-Methylnaphalene	Yes	No	0.00E+00	0.00E+00	6.72E-05
2-Nitrophenol	Yes	No	0.00E+00	0.00E+00	2.74E-05
4-Methyl-2-pentanone	Yes	No	0.00E+00	0.00E+00	6.18E-05
Benzene, 1,3-*bis*(1-methylethyl)-	Yes	No	0.00E+00	0.00E+00	8.05E-04
Benzene, diethyl-	Yes	No	0.00E+00	0.00E+00	1.78E-03
Benzenesulfonamide, *N*-butyl	Yes	No	0.00E+00	0.00E+00	1.73E-05
Benzo(*a*)anthrecene	Yes	No	0.00E+00	0.00E+00	5.72E-05
Benzo(*a*)pyrene	Yes	No	0.00E+00	0.00E+00	7.66E-05
Benzo(*b*)fluoroanthene	Yes	No	0.00E+00	0.00E+00	8.13E-05
Benzo(*g,h,i*)perylene	Yes	No	0.00E+00	0.00E+00	6.05E-05
Benzoic Acid	Yes	No	0.00E+00	0.00E+00	2.94E-04
Benzophenone	Yes	No	0.00E+00	0.00E+00	4.11E-04
Bromodichloromethane	Yes	No	0.00E+00	0.00E+00	7.52E-08
Chrysene	Yes	No	0.00E+00	0.00E+00	5.21E-05

Table B.1-13 (continued)

Air contaminant	Classified as: VOC	HAP	Maximum[a] hourly emissions (lbs/h)	Average[b] hourly emissions (lbs/h)	Average[c] annual emissions (tons/year)
Dibromonitrophenol	Yes	No	0.00E+00	0.00E+00	1.39E-04
Diethyl benzene	Yes	No	1.67E-03	1.39E-03	1.66E-03
Diethylphthalate	Yes	No	0.00E+00	0.00E+00	1.22E-04
dimethyl sulfone	Yes	No	0.00E+00	0.00E+00	1.51E-06
Di-n-octylphthalate	Yes	No	0.00E+00	0.00E+00	2.13E-03
Dodecane	Yes	No	4.49E-03	3.74E-03	3.69E-03
Ethanone, 1-(2,3,4-trimethylphenyl)-	Yes	No	1.15E-03	9.59E-04	6.63E-04
Ethanone, 1-(4-ethylphenyl)-	Yes	No	2.50E-04	2.08E-04	3.26E-04
Ethyl alcohol	Yes	No	0.00E+00	0.00E+00	3.82E-04
Ethylphenylethanone	Yes	No	8.55E-04	7.12E-04	4.92E-04
Fluoroanthene	Yes	No	0.00E+00	0.00E+00	2.19E-04
Hepatanone	Yes	No	7.15E-05	5.96E-05	4.22E-05
Heptadecane	Yes	No	0.00E+00	0.00E+00	1.58E-04
Heptanal	Yes	No	0.00E+00	0.00E+00	1.63E-06
Heptane, 4-ethyl-2,2,6,6-tetrameethyl	Yes	No	0.00E+00	0.00E+00	6.21E-04
Hexadecanoic acid	Yes	No	0.00E+00	0.00E+00	2.12E-04
n-Butyl alcohol	Yes	No	0.00E+00	0.00E+00	2.40E-04
Nonadecane	Yes	No	0.00E+00	0.00E+00	1.70E-04
Octadecane	Yes	No	0.00E+00	0.00E+00	2.11E-04
Pentadecane	Yes	No	2.32E-04	1.94E-04	3.04E-04
Phenanthrene	Yes	No	0.00E+00	0.00E+00	3.16E-04
Phosphoric acid, *tris*-(2-ethylhexyl)-	Yes	No	2.71E-03	2.26E-03	1.56E-03
Pyrene	Yes	No	0.00E+00	0.00E+00	2.11E-04
Tetradecane	Yes	No	6.15E-03	5.12E-03	5.33E-03
Tetrahydrofuran	Yes	No	0.00E+00	0.00E+00	9.30E-07
Tributyl phosphate	Yes	No	5.16E-03	4.30E-03	5.05E-03
Tridecane	Yes	No	1.04E-02	8.70E-03	8.17E-03
Trimethyl decane	Yes	No	5.48E-04	4.57E-04	3.16E-04
Tris(ethylhexyl)phosphate	Yes	No	9.67E-04	8.06E-04	5.57E-04
Undecane	Yes	No	1.62E-03	1.35E-03	2.00E-03
Total unknowns	Yes	No	2.00E-02	1.66E-02	5.27E-02

[a]The maximum hourly emissions are those for the Bethel Valley tank farm, which had the highest calculated hourly emissions for sludge and supernate.

[b]The average hourly emissions are estimated by scaling down the maximum hourly emissions by the ratio of 6000 annual operating hours over the 7200-h project life.

h = hour.

HAP = hazardous air pollutant.

lb = pound.

VOC = volatile organic compound.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX B.2

SUMMARIES OF MATERIAL BALANCE FOR VITRIFICATION PROCESS

THIS PAGE INTENTIONALLY LEFT BLANK

Table B.2-1. Material balance for vitrificatio

Stream No.	Units	1 Sludge/ supernate in MVSTs	2 Mobilized sludge/ supernate	3 Mixed sludge/ supernate	4 To melter feed preparation	5 Melter feed	6 Glass from melter	7 Contain-erized glass	8 Glass to certifi-cation	I
										Metals/ox
Ag/Ag2O	kg	10	10	10	10	10	10	10	10	
Al/Al2O3	kg	17,756	17,755	17,755	17,755	17,755	17,578	17,578	17,578	
As/As2O3	kg	31	31	31	31	31	30	30	30	
B/B2O3	kg	54	54	54	54	54	53	53	53	
Ba/BaO	kg	126	126	126	126	126	124	124	124	
Be/BeO	kg	6	6	6	6	6	6	6	6	
Bi/Bi2O3	kg	5	5	5	5	5	5	5	5	
Ca/CaO	kg	42,507	42,507	42,507	42,507	320,409	314,001	314,001	314,001	
Cd/CdO	kg	13	13	13	13	13	13	13	13	
Ce/Ce2O3	kg	1	1	1	1	1	1	1	1	
Co/CoO	kg	6	6	6	6	6	6	6	6	
Cr/Cr2O3	kg	593	593	593	593	593	587	587	587	
Cs/Cs2O	kg	11	11	11	11	11	10	10	10	
Cu/CuO	kg	80	80	80	80	80	79	79	79	
Fe/Fe2O3	kg	7,251	7,251	7,251	7,251	7,251	7,179	7,179	7,179	
Ga/Ga2O3	kg	1	1	1	1	1	1	1	1	
Hg/HgO	kg	84	84	84	84	84	0	0	0	
I/I2O5	kg	31	31	31	31	31	0	0	0	
K/K2O	kg	30,840	30,840	30,840	30,840	30,840	30,531	30,531	30,531	
La/La2O3	kg	0	0	0	0	0	0	0	0	
Li/Li2O	kg	92	92	92	92	92	91	91	91	
Mg/MgO	kg	8,335	8,335	8,335	8,335	8,335	8,251	8,251	8,251	
Mn/MnO	kg	280	280	280	280	280	278	278	278	
Mo/MoO3	kg	3	3	3	3	3	3	3	3	
Na/Na2O	kg	187,475	187,475	187,475	187,475	187,475	185,600	185,600	185,600	
Nb/NbO	kg	0	0	0	0	0	0	0	0	
Ni/NiO	kg	97	97	97	97	97	96	96	96	
P/P2O5	kg	35,533	35,533	35,533	35,533	35,533	35,178	35,178	35,178	
Pb/PbO	kg	587	587	587	587	587	581	581	581	
Rb/Rb2O	kg	2	2	2	2	2	2	2	2	
Sb/Sb2O3	kg	40	40	40	40	40	40	40	40	
Se/SeO	kg	28	28	28	28	28	28	28	28	
Si/SiO2	kg	5,878	5,877	5,877	5,877	874,564	857,072	857,072	857,072	
Sn/SnO2	kg	1	1	1	1	1	1	1	1	
Sr/SrO	kg	147	147	147	147	147	146	146	146	
Th/ThO2	kg	7,832	7,832	7,832	7,832	7,832	7,754	7,754	7,754	
Ti/TiO2	kg	1	1	1	1	1	1	1	1	
Tl/Tl2O5	kg	20	20	20	20	20	20	20	20	
U/U2O5	kg	66,631	66,631	66,631	66,631	66,631	65,964	65,964	65,964	
V/VO	kg	5	5	5	5	5	5	5	5	
W/WO3	kg	1	1	1	1	1	1	1	1	
Zn/ZnO	kg	222	222	222	222	222	219	219	219	
Zr/ZrO2	kg	0	0	0	0	0	0	0	0	
Grout binder	kg									

ocess in the Vitrification Alternative

9	10	11	12	13	14	15	16	17	18	19
into cask	Ship to WIPP	Non-debris solid waste	Glass former blend	Melter off-gas	Air leakage into melter	Film cooler air	To quencher/ scrubber	Off-gas from CH/RH special wastes	Off-gas to mist eliminator	Off-gas from mist eliminator
0	10	0	0	0			0	0	0	0
578	17,578	0	0	178			178	0	36	4
0	30	0	0	0			0	0	0	0
3	53	0	0	1			1	0	0	0
4	124	0	0	1			1	0	0	0
	6	0	0	0			0	0	0	0
	5	0	0	0			0	0	0	0
001	314,001	0	277,902	6,408			6,408	0	1,282	128
3	13	0	0	0			0	0	0	0
	1	0	0	0			0	0	0	0
	6	0	0	0			0	0	0	0
7	587	0	0	6			6	0	1	0
0	10	0	0	1			1	0	0	0
9	79	0	0	1			1	0	0	0
79	7,179	0	0	73			73	0	15	1
	1	0	0	0			0	0	0	0
	0	0	0	84			84	0	17	2
	0	0	0	31			31	0	6	1
531	30,531	0	0	308			308	0	62	6
	0	0	0	0			0	0	0	0
1	91	0	0	1			1	0	0	0
51	8,251	0	0	83			83	0	17	2
8	278	0	0	3			3	0	1	0
	3	0	0	0			0	0	0	0
600	185,600	0	0	1,875			1,875	0	375	37
	0	0	0	0			0	0	0	0
6	96	0	0	1			1	0	0	0
178	35,178	0	0	355			355	0	71	7
1	581	0	0	6			6	0	1	0
	2	0	0	0			0	0	0	0
0	40	0	0	0			0	0	0	0
3	28	0	0	0			0	0	0	0
072	857,072	0	868,686	17,491			17,491	0	3,498	350
	1	0	0	0			0	0	0	0
6	146	0	0	1			1	0	0	0
54	7,754	0	0	78			78	0	16	2
	1	0	0	0			0	0	0	0
0	20	0	0	0			0	0	0	0
964	65,964	0	0	666			666	0	133	13
	5	0	0	0			0	0	0	0
	1	0	0	0			0	0	0	0
9	219	0	0	2			2	0	0	0
	0	0	0	0			0	0	0	0

Stream No.	Units	1 Sludge/ supernate in MVSTs	2 Mobilized sludge/ supernate	3 Mixed sludge/ supernate	4 To melter feed preparation	5 Melter feed	6 Glass from melter	7 Contain-erized glass	8 Glass to certifi-cation	L 7
										Anions
CO3-	kg	0	0	0	0	0	0	0	0	
Br-	kg	5,400	5,400	5,400	5,400	5,400	0	0	0	
CO3--	kg	188	188	188	188	188	0	0	0	
Cl-	kg	10,610	10,610	10,610	10,610	10,610	5,305	5,305	5,305	
CrO4--	kg	3,857	3,857	3,857	3,857	3,857	2,314	2,314	2,314	
F-	kg	1,674	1,674	1,674	1,674	1,674	1,172	1,172	1,172	
OH-	kg	515	515	515	515	515	0	0	0	
NO3-	kg	27,781	27,781	27,781	27,781	27,781	5,556	5,556	5,556	
NO2-	kg	300,200	300,199	300,199	300,199	300,199	60,040	60,040	60,040	
PO4-	kg	8,047	8,047	8,047	8,047	8,047	4,828	4,828	4,828	
SO4--	kg	6,682	6,682	6,682	6,682	6,682	4,009	4,009	4,009	
CN-	kg	4,106	4,106	4,106	4,106	4,106	0	0	0	
C2H3O2-	kg	0	0	0	0	0	0	0	0	
C6H5O7---	kg	397	397	397	397	397	0	0	0	
HCO2-	kg	142	142	142	142	142	0	0	0	
C2O4--	kg	301	301	301	301	301	0	0	0	
Phthalates	kg	390	390	390	390	390	0	0	0	
										Water and g
H2O	kg	2,212,350	2,212,350	2,212,350	2,212,350	2,287,080	0	0	0	
Ar	kg		0	0	0	0	0	0	0	
CO2	kg		0	0	0	0	0	0	0	
N2	kg		0	0	0	0	0	0	0	
NH3	kg		0	0	0	0	0	0	0	
O2	kg		0	0	0	0	0	0	0	
HBr (gas)	kg		0	0	0	0	0	0	0	
HCl (gas)	kg		0	0	0	0	0	0	0	
HF (gas)	kg		0	0	0	0	0	0	0	
NOx (gas)	kg		0	0	0	0	0	0	0	
SO2 (gas)	kg		0	0	0	0	0	0	0	
										Totals
Carbon	kg	13,879	13,879	13,879	13,879	13,879	0	0	0	
Metal oxides	kg	412,613	412,613	412,613	412,613	1,559,201	1,531,544	1,531,544	1,531,544	1,5
Anions	kg	370,290	370,289	370,289	370,289	370,289	83,225	83,225	83,225	8
Dry gases	kg	0	0	0	0	0	0	0	0	
H20	kg	2,212,350	2,212,350	2,212,350	2,212,350	2,287,080	0	0	0	
Mass	kg	3,009,132	3,009,131	3,009,131	3,009,131	4,230,449	1,614,769	1,614,769	1,614,769	1,6
										Miscellaneo
Flowrate	kg/h	155.29	155.29	155.29	155.29	218.32	83.33	83	83	
Flowrate	gpm	0.568	0.568	0.568	0.568	0.598	0.131	0	0	
Flowrate	scfm									
Flowrate	acfm									
Temperature	°C	25	25	25	25	25	25	25	25	
Specific gravity		1.20	1.20	1.20	1.20	1.61	2.80	3	3	
Density	lb/ft^3	75.14	75.16	75.16	75.16	100.33	174.80	175	175	

ıued)

into ask	10 Ship to WIPP	11 Non-debris solid waste	12 Glass former blend	13 Melter off-gas	14 Air leakage into melter	15 Film cooler air	16 To quencher/ scrubber	17 Off-gas from CH/RH special wastes	18 Off-gas to mist eliminator	19 Off-gas from mist eliminator
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
5	5,305	0	0	0			0	0	0	0
4	2,314	0	0	1,543			1,543	0	309	31
2	1,172	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
5	5,556	0	0	0			0	0	0	0
0	60,040	0	0	0			0	0	0	0
3	4,828	0	0	3,219			3,219	0	644	322
)	4,009	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	0	0	0			0	0	0	0
	0	74,730	0	2,938,108	650,514	334,446	3,272,554	0	6,340,079	6,340,079
	0	0	0	48,221	48,221	24,791	73,012	0	73,012	73,012
	0	0	0	61,251	1,704	876	62,127	0	62,127	62,127
	0	0	0	4,097,532	4,031,327	2,072,607	6,170,140	0	6,170,140	6,170,140
	0	0	0	0			0	0	0	0
	0	0	0	1,142,094	1,081,402	555,976	1,698,070	0	1,679,338	1,675,069
	0	0	0	5,467			5,467	0	1,093	1,093
	0	0	0	5,455			5,455	0	545	273
	0	0	0	529			529	0	53	26
	0	0	0	95,991			95,991	0	67,194	60,474
	0	0	0	1,782			1,782	0	178	89
	0	0	0	0	0	0	0	0	0	0
4	1,531,544	0	1,146,588	27,657	0	0	27,657	0	5,531	553
	83,225	0	0	4,762	0	0	4,762	0	952	353
	0	0	0	5,458,321	5,162,654	2,654,251	8,112,572	0	8,053,681	8,042,304
	0	74,730	0	2,938,108	650,514	334,446	3,272,554	0	6,340,079	6,340,079
9	1,614,769	74,730	1,146,588	8,428,848	5,813,167	2,988,696	11,417,544	0	14,400,244	14,383,289
	83		59.17	434.99	300.00	154.24	589.22	0.00	743.15	742.28
	0	0.000	0.098	478.298	1,115.294	573.401	1,051.699		2,000.234	2,000.234
	25	25	25	529	25	25	350		25	25
	3	1.00	2.67	0.0040	0.0012	0.0012	0.0025		0.0016	0.0016
	175	1.00	166.37	0.2500	0.0739	0.0739	0.1540	0.0000	0.1021	0.1020

Stream No.	Units	1 Sludge/ supernate in MVSTs	2 Mobilized sludge/ supernate	3 Mixed sludge/ supernate	4 To melter feed preparation	5 Melter feed	6 Glass from melter	7 Contain-erized glass	8 Glass to certifi-cation	L 7
										Radiochemical cons
Au-198		7.43E-257	7.43E-257	7.43E-257	7.43E-257	7.43E-257	7.35E-257	7.35E-257	7.35E-257	7
Bk-249			0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0
C-14		4.12E+00	4.12E+00	4.12E+00	4.12E+00	4.12E+00	4.08E+00	4.08E+00	4.08E+00	4
Ce-144		1.42E+00	1.42E+00	1.42E+00	1.42E+00	1.42E+00	1.40E+00	1.40E+00	1.40E+00	1
Cf-252		2.48E-01	2.48E-01	2.48E-01	2.48E-01	2.48E-01	2.45E-01	2.45E-01	2.45E-01	2
Cm-243		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0
Cm-244		9.32E+02	9.31E+02	9.31E+02	9.31E+02	9.31E+02	9.22E+02	9.22E+02	9.22E+02	9
Co-60		4.76E+02	4.76E+02	4.76E+02	4.76E+02	4.76E+02	0.00E+00	0.00E+00	0.00E+00	0
Cs-134		6.41E+01	6.40E+01	6.40E+01	6.40E+01	6.40E+01	5.76E+01	5.76E+01	5.76E+01	5
Cs-137		2.60E+04	2.60E+04	2.60E+04	2.60E+04	2.60E+04	2.34E+04	2.34E+04	2.34E+04	2
Eu-152		1.24E+02	1.24E+02	1.24E+02	1.24E+02	1.24E+02	1.22E+02	1.22E+02	1.22E+02	1
Eu-154		4.28E+01	4.28E+01	4.28E+01	4.28E+01	4.28E+01	4.24E+01	4.24E+01	4.24E+01	4
Eu-155		1.78E+01	1.78E+01	1.78E+01	1.78E+01	1.78E+01	1.76E+01	1.76E+01	1.76E+01	1
H-3		5.13E+00	5.12E+00	5.12E+00	5.12E+00	5.12E+00	0.00E+00	0.00E+00	0.00E+00	0
I-129		6.48E-03	6.48E-03	6.48E-03	6.48E-03	6.48E-03	6.41E-03	6.41E-03	6.41E-03	6
Nb-95		7.21E-20	7.20E-20	7.20E-20	7.20E-20	7.20E-20	7.13E-20	7.13E-20	7.13E-20	7
Pu-238		1.73E-01	1.73E-01	1.73E-01	1.73E-01	1.73E-01	1.72E-01	1.72E-01	1.72E-01	1
Pu-239		1.50E-01	1.50E-01	1.50E-01	1.50E-01	1.50E-01	1.49E-01	1.49E-01	1.49E-01	1
Pu-240		1.46E-01	1.46E-01	1.46E-01	1.46E-01	1.46E-01	1.45E-01	1.45E-01	1.45E-01	1
Pu-241		2.13E+00	2.13E+00	2.13E+00	2.13E+00	2.13E+00	2.11E+00	2.11E+00	2.11E+00	2
Pu-242		7.35E-03	7.34E-03	7.34E-03	7.34E-03	7.34E-03	7.27E-03	7.27E-03	7.27E-03	7
Pu-244		8.64E-04	8.63E-04	8.63E-04	8.63E-04	8.63E-04	8.55E-04	8.55E-04	8.55E-04	8
Ru-106		1.35E+00	1.35E+00	1.35E+00	1.35E+00	1.35E+00	1.34E+00	1.34E+00	1.34E+00	1
Sr-90		4.09E+02	4.08E+02	4.08E+02	4.08E+02	4.08E+02	4.04E+02	4.04E+02	4.04E+02	4
Tc-99		4.97E+01	4.96E+01	4.96E+01	4.96E+01	4.96E+01	2.48E+01	2.48E+01	2.48E+01	2
Th-232		1.73E-03	1.73E-03	1.73E-03	1.73E-03	1.73E-03	1.71E-03	1.71E-03	1.71E-03	
U-233		6.19E+00	6.18E+00	6.18E+00	6.18E+00	6.18E+00	6.12E+00	6.12E+00	6.12E+00	6
U-234		1.25E-01	1.25E-01	1.25E-01	1.25E-01	1.25E-01	1.24E-01	1.24E-01	1.24E-01	1
U-235		5.19E-03	5.18E-03	5.18E-03	5.18E-03	5.18E-03	5.13E-03	5.13E-03	5.13E-03	5
U-236		3.03E-03	3.02E-03	3.02E-03	3.02E-03	3.02E-03	2.99E-03	2.99E-03	2.99E-03	2
U-238		1.65E-01	1.65E-01	1.65E-01	1.65E-01	1.65E-01	1.63E-01	1.63E-01	1.63E-01	1
Zr-95		8.25E-11	8.24E-11	8.24E-11	8.24E-11	8.24E-11	8.16E-11	8.16E-11	8.16E-11	8
TRU activity		7.26E-01	2.60E+00	2.60E+00	2.60E+00	2.60E+00	2.58E+00	2.58E+00	2.58E+00	2

Stream No.	Units	20 Off-gas to HEPAs	21 Off-gas to stack discharge	22 Clean sluicing water	23 Decanted supernate	24 Water to quencher/ scrubber	25 Quencher/ scrubber blowdown	26 Water to mist eliminator	27 Mist elimina blowdo
									Metals
Ag/Ag2O	kg	0.002	0.000	0	0	0	0	0	0
Al/Al2O3	kg	3.569	0.000	0	0	0	142	0	32
As/As2O3	kg	0.006	0.000	0	0	0	0	0	0
B/B2O3	kg	0.011	0.000	0	0	0	0	0	0
Ba/BaO	kg	0.025	0.000	0	0	0	1	0	0
Be/BeO	kg	0.001	0.000	0	0	0	0	0	0

tinued)

9	10	11	12	13	14	15	16	17	18	19
d into 3 cask	Ship to WIPP	Non-debris solid waste	Glass former blend	Melter off-gas	Air leakage into melter	Film cooler air	To quencher/ scrubber	Off-gas from CH/RH special wastes	Off-gas to mist eliminator	Off-gas from mist eliminator
ients (in Ci)										
5E-257	7.35E-257		0.00E+00	7.43E-259	0.00E+00	0.00E+00	7.43E-259		1.49E-259	1.49E-260
0E+00	0.00E+00		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		0.00E+00	0.00E+00
8E+00	4.08E+00		0.00E+00	4.12E-02	0.00E+00	0.00E+00	4.12E-02		8.24E-03	4.12E-03
0E+00	1.40E+00		0.00E+00	1.42E-02	0.00E+00	0.00E+00	1.42E-02		2.83E-03	2.83E-04
5E-01	2.45E-01		0.00E+00	2.48E-03	0.00E+00	0.00E+00	2.48E-03		4.96E-04	4.96E-05
0E+00	0.00E+00		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		0.00E+00	0.00E+00
2E+02	9.22E+02		0.00E+00	9.31E+00	0.00E+00	0.00E+00	9.31E+00		1.86E+00	1.86E-01
0E+00	0.00E+00		0.00E+00	4.76E+02	0.00E+00	0.00E+00	4.76E+02		9.52E+01	9.52E+00
6E+01	5.76E+01		0.00E+00	6.40E+00	0.00E+00	0.00E+00	6.40E+00		1.28E+00	6.40E-01
4E+04	2.34E+04		0.00E+00	2.60E+03	0.00E+00	0.00E+00	2.60E+03		5.19E+02	2.60E+02
2E+02	1.22E+02		0.00E+00	1.24E+00	0.00E+00	0.00E+00	1.24E+00		2.47E-01	1.24E-02
4E+01	4.24E+01		0.00E+00	4.28E-01	0.00E+00	0.00E+00	4.28E-01		8.56E-02	4.28E-03
6E+01	1.76E+01		0.00E+00	1.78E-01	0.00E+00	0.00E+00	1.78E-01		3.56E-02	1.78E-03
0E+00	0.00E+00		0.00E+00	5.12E+00	0.00E+00	0.00E+00	5.12E+00		2.56E+00	2.56E+00
1E-03	6.41E-03		0.00E+00	6.48E-05	0.00E+00	0.00E+00	6.48E-05		1.30E-05	1.30E-06
3E-20	7.13E-20		0.00E+00	7.20E-22	0.00E+00	0.00E+00	7.20E-22		1.44E-22	1.44E-23
2E-01	1.72E-01		0.00E+00	1.73E-03	0.00E+00	0.00E+00	1.73E-03		3.47E-04	3.47E-05
9E-01	1.49E-01		0.00E+00	1.50E-03	0.00E+00	0.00E+00	1.50E-03		3.00E-04	3.00E-05
5E-01	1.45E-01		0.00E+00	1.46E-03	0.00E+00	0.00E+00	1.46E-03		2.93E-04	2.93E-05
1E+00	2.11E+00		0.00E+00	2.13E-02	0.00E+00	0.00E+00	2.13E-02		4.25E-03	4.25E-04
7E-03	7.27E-03		0.00E+00	7.34E-05	0.00E+00	0.00E+00	7.34E-05		1.47E-05	1.47E-06
5E-04	8.55E-04		0.00E+00	8.63E-06	0.00E+00	0.00E+00	8.63E-06		1.73E-06	1.73E-07
4E+00	1.34E+00		0.00E+00	1.35E-02	0.00E+00	0.00E+00	1.35E-02		2.71E-03	2.71E-04
4E+02	4.04E+02		0.00E+00	4.08E+00	0.00E+00	0.00E+00	4.08E+00		8.17E-01	4.08E-02
8E+01	2.48E+01		0.00E+00	2.48E+01	0.00E+00	0.00E+00	2.48E+01		4.96E+00	4.96E-02
1E-03	1.71E-03		0.00E+00	1.73E-05	0.00E+00	0.00E+00	1.73E-05		3.45E-06	3.45E-07
2E+00	6.12E+00		0.00E+00	6.18E-02	0.00E+00	0.00E+00	6.18E-02		1.24E-02	1.24E-03
4E-01	1.24E-01		0.00E+00	1.25E-03	0.00E+00	0.00E+00	1.25E-03		2.50E-04	2.50E-05
3E-03	5.13E-03		0.00E+00	5.18E-05	0.00E+00	0.00E+00	5.18E-05		1.04E-05	1.04E-06
9E-03	2.99E-03		0.00E+00	3.02E-05	0.00E+00	0.00E+00	3.02E-05		6.04E-06	6.04E-07
3E-01	1.63E-01		0.00E+00	1.65E-03	0.00E+00	0.00E+00	1.65E-03		3.30E-04	3.30E-05
6E-11	8.16E-11		0.00E+00	8.24E-13	0.00E+00	0.00E+00	8.24E-13		1.65E-13	1.65E-14
8E+00	2.58E+00	0.00E+00	0.00E+00	2.60E-02	0.00E+00	0.00E+00	2.60E-02	0.00E+00	5.21E-03	5.21E-04

	28	29	30	31	32	33	34	35	36	37
r n	Wastewater from blowdowns	Wastewater for sluicing	Wastewater to treatment	Wastewater evaporator condensate	Evaporator concentrate	Treated concentrate	Binder	HEPA filters	Half-PACT canisters	Tank vents
ides										
0	0.000	0.100	0.000	0.100	0.100		0.002		0.000	
174	0.000	174.004	0.000	174.004	174.004		3.568		0.018	
0	0.000	0.302	0.000	0.302	0.302		0.006		0.000	
1	0.000	0.525	0.000	0.525	0.525		0.011		0.000	
1	0.000	1.231	0.000	1.231	1.231		0.025		0.000	
0	0.000	0.059	0.000	0.059	0.059		0.001		0.000	

Stream No.	Units	20 Off-gas to HEPAs	21 Off-gas to stack discharge	22 Clean sluicing water	23 Decanted supernate	24 Water to quencher/ scrubber	25 Quencher/ scrubber blowdown	26 Water to mist eliminator	27 Mist eliminat blowdo
Bi/Bi2O3	kg	0.001	0.000	0	0	0	0	0	0
Ca/CaO	kg	128.206	0.013	0	0	0	5,127	0	1,153
Cd/CdO	kg	0.003	0.000	0	0	0	0	0	0
Ce/Ce2O3	kg	0.000	0.000	0	0	0	0	0	0
Co/CoO	kg	0.001	0.000	0	0	0	0	0	0
Cr/Cr2O3	kg	0.119	0.000	0	0	0	5	0	1
Cs/Cs2O	kg	0.022	0.000	0	0	0	1	0	0
Cu/CuO	kg	0.016	0.000	0	0	0	1	0	0
Fe/Fe2O3	kg	1.457	0.000	0	0	0	58	0	13
Ga/Ga2O3	kg	0.000	0.000	0	0	0	0	0	0
Hg/HgO	kg	1.685	0.000	0	0	0	67	0	8
I/I2O5	kg	0.622	0.000	0	0	0	25	0	0
K/K2O	kg	6.199	0.001	0	0	0	247	0	56
La/La2O3	kg	0.000	0.000	0	0	0	0	0	0
Li/Li2O	kg	0.018	0.000	0	0	0	1	0	0
Mg/MgO	kg	1.675	0.000	0	0	0	67	0	15
Mn/MnO	kg	0.056	0.000	0	0	0	2	0	1
Mo/MoO3	kg	0.001	0.000	0	0	0	0	0	0
Na/Na2O	kg	37.682	0.004	0	0	0	1,500	0	337
Nb/NbO	kg	0.000	0.000	0	0	0	0	0	0
Ni/NiO	kg	0.019	0.000	0	0	0	1	0	0
P/P2O5	kg	7.142	0.001	0	0	0	284	0	64
Pb/PbO	kg	0.118	0.000	0	0	0	5	0	1
Rb/Rb2O	kg	0.000	0.000	0	0	0	0	0	0
Sb/Sb2O3	kg	0.008	0.000	0	0	0	0	0	0
Se/SeO	kg	0.006	0.000	0	0	0	0	0	0
Si/SiO2	kg	349.831	0.035	0	0	0	13,993	0	3,148
Sn/SnO2	kg	0.000	0.000	0	0	0	0	0	0
Sr/SrO	kg	0.030	0.000	0	0	0	1	0	0
Th/ThO2	kg	1.574	0.000	0	0	0	63	0	14
Ti/TiO2	kg	0.000	0.000	0	0	0	0	0	0
Tl/Tl2O5	kg	0.004	0.000	0	0	0	0	0	0
U/U2O5	kg	13.393	0.001	0	0	0	533	0	120
V/VO	kg	0.001	0.000	0	0	0	0	0	0
W/WO3	kg	0.000	0.000	0	0	0	0	0	0
Zn/ZnO	kg	0.045	0.000	0	0	0	2	0	0
Zr/ZrO2	kg	0.000	0.000	0	0	0	0	0	0
Grout binder	kg								
									Anion
CO3-	kg	0.000	0.000	0	0	0	0	0	0
Br-	kg	0.005	0.000	0	0	0	4,320	0	0
CO3--	kg	0.000	0.000	0	0	0	0	0	0
Cl-	kg	0.011	0.000	0	0	0	4,775	0	265
CrO4--	kg	30.858	0.003	0	0	0	1,234	0	278
F-	kg	0.002	0.000	0	0	0	452	0	25
OH-	kg	0.001	0.000	0	0	0	0	0	0
NO3-	kg	0.028	0.000	0	0	0	46,705	0	10,898
NO2-	kg	0.300	0.000	0	0	0	235	0	55
PO4-	kg	321.899	0.032	0	0	0	2,575	0	322

nued)

28	29	30	31	32	33	34	35	36	37
Wastewater from blowdowns	Wastewater for sluicing	Wastewater to treatment	evaporator condensate	Evaporator concentrate	Treated concentrate	Binder	HEPA filters	Half-PACT canisters	Tank vents
0	0.000	0.047	0.000	0.047	0.047		0.001		0.000
6,280	0.000	6280.011	0.000	6280.011	6,280.011		128.193		0.043
0	0.000	0.127	0.000	0.127	0.127		0.003		0.000
0	0.000	0.007	0.000	0.007	0.007		0.000		0.000
0	0.000	0.056	0.000	0.056	0.056		0.001		0.000
6	0.000	5.811	0.000	5.811	5.811		0.119		0.001
1	0.000	1.080	0.000	1.080	1.080		0.022		0.000
1	0.000	0.785	0.000	0.785	0.785		0.016		0.000
71	0.000	71.061	0.000	71.061	71.061		1.457		0.007
0	0.000	0.007	0.000	0.007	0.007		0.000		0.000
76	0.000	75.826	0.000	75.826	75.826		1.685		0.000
25	0.000	24.898	0.000	24.898	24.898		0.622		0.000
302	0.000	302.230	0.000	302.230	302.230		6.198		0.031
0	0.000	0.001	0.000	0.001	0.001		0.000		0.000
1	0.000	0.901	0.000	0.901	0.901		0.018		0.000
82	0.000	81.679	0.000	81.679	81.679		1.675		0.008
3	0.000	2.748	0.000	2.748	2.748		0.056		0.000
0	0.000	0.029	0.000	0.029	0.029		0.001		0.000
1,837	0.000	1837.251	0.000	1837.251	1,837.251		37.679		0.187
0	0.000	0.000	0.000	0.000	0.000		0.000		0.000
1	0.000	0.950	0.000	0.950	0.950		0.019		0.000
348	0.000	348.226	0.000	348.226	348.226		7.141		0.036
6	0.000	5.752	0.000	5.752	5.752		0.118		0.001
0	0.000	0.020	0.000	0.020	0.020		0.000		0.000
0	0.000	0.393	0.000	0.393	0.393		0.008		0.000
0	0.000	0.276	0.000	0.276	0.276		0.006		0.000
17,141	0.000	17,141	0.000	17141.448	17,141		349.796		0.006
0	0.000	0.008	0.000	0.008	0.008		0.000		0.000
1	0.000	1.442	0.000	1.442	1.442		0.030		0.000
77	0.000	76.753	0.000	76.753	76.753		1.574		0.008
0	0.000	0.013	0.000	0.013	0.013		0.000		0.000
0	0.000	0.198	0.000	0.198	0.198		0.004		0.000
653	0.000	652.982	0.000	652.982	652.982		13.391		0.067
0	0.000	0.045	0.000	0.045	0.045		0.001		0.000
0	0.000	0.009	0.000	0.009	0.009		0.000		0.000
2	0.000	2.172	0.000	2.172	2.172		0.045		0.000
0	0.000	0.001	0.000	0.001	0.001		0.000		0.000
					268.030	268.030			
0	0	0	0.000	0	0		0.000		0.000
4,320	0	4,320	0.000	4,320	4,320		0.005		0.005
0	0	0	0.000	0	0		0.000		0.000
5,040	0	5,040	0.000	5,040	5,040		0.011		0.011
1,512	0	1,512	0.000	1,512	1,512		30.855		0.004
477	0	477	0.000	477	477		0.002		0.002
0	0	0	0.000	0	0		0.001		0.001
57,603	0	57,603	0.000	57,603	57,603		0.028		0.028
289	0	289	0.000	289	289		0.300		0.300
2,897	0	2,897	0.000	2,897	2,897		321.866		0.008

Stream No.	Units	20 Off-gas to HEPAs	21 Off-gas to stack discharge	22 Clean sluicing water	23 Decanted supernate	24 Water to quencher/ scrubber	25 Quencher/ scrubber blowdown	26 Water to mist eliminator	27 Mis elimin blowd
SO4--	kg	0.007	0.000	0	0	0	2,406	0	134
CN-	kg	0.004	0.000	0	0	0	0	0	0
C2H3O2-	kg	0.000	0.000	0	0	0	0	0	0
C6H5O7---	kg	0.000	0.000	0	0	0	0	0	0
HCO2-	kg	0.000	0.000	0	0	0	0	0	0
C2O4--	kg	0.000	0.000	0	0	0	0	0	0
Phthalates	kg	0.000	0.000	0	0	0	0	0	0
									Water a
H2O	kg	7,586,847	7,586,847	0	0	3,334,267	266,741	152,797	152,797
Ar	kg	165,431	165,431	0	0	0	0	0	0
CO2	kg	65,392	65,392	0	0	0	0	0	0
N2	kg	13,896,536	13,896,536	0	0	0	0	0	0
NH3	kg		0	0	0	0	0	0	0
O2	kg	3,747,672	3,747,672	0	0	0	0	0	0
HBr (gas)	kg	1,093	1,093	0	0	0	0	0	0
HCl (gas)	kg	273	273	0	0	0	0	0	0
HF (gas)	kg	26	26	0	0	0	0	0	0
NOx (gas)	kg	60,474	60,474	0	0	0	0	0	0
SO2 (gas)	kg	89	89	0	0	0	0	0	0
									Tot
Carbon	kg	0	0	0	0	0	0	0	0
Metal oxides	kg	554	0	0	0	0	22,126	0	4,966
Anions	kg	353	0	0	0	0	62,701	0	11,976
Dry gases	kg	17,936,987	17,936,987	0	0	0	0	0	0
H20	kg	7,586,847	7,586,847	0	0	3,334,267	266,741	152,797	152,797
Mass	kg	25,524,741	25,523,835	0	0	3,334,267	351,568	152,797	169,740
									Miscell
Flowrate	kg/hr	1,317.25	1,317.21			172.07	18.14	7.89	8.76
Flowrate	gpm	4,137.794	4,137.794			0.758	0.208	0.035	0.035
Flowrate	scfm								
Flowrate	acfm								
Temperature	°C	25	25			25	80	25	25
Specific gravity		0.0014	0.0014			1.00	1.32	1.00	1.11
Density	lb/ft^3	0.0875	0.0875			62.43	82.28	62.43	69.35
									Radiochemical co
Au-198		8.92E-260	1.49E-264			0.00E+00	5.94E-259	0.00E+00	1.34E-25
Bk-249		0.00E+00	0.00E+00			0.00E+00	0.00E+00	0.00E+00	0.00E+00
C-14		8.24E-03	4.12E-07			0.00E+00	3.29E-02	0.00E+00	4.12E-03
Ce-144		1.70E-03	2.83E-08			0.00E+00	1.13E-02	0.00E+00	2.55E-03
Cf-252		2.98E-04	4.96E-09			0.00E+00	1.98E-03	0.00E+00	4.46E-04
Cm-243		0.00E+00	0.00E+00			0.00E+00	0.00E+00	0.00E+00	0.00E+00
Cm-244		1.12E+00	1.86E-05			0.00E+00	7.45E+00	0.00E+00	1.68E+00
Co-60		1.00E+01	9.52E-04			0.00E+00	3.81E+02	0.00E+00	8.57E+01
Cs-134		7.05E-01	6.40E-05			0.00E+00	5.12E+00	0.00E+00	6.40E-01
Cs-137		2.86E+02	2.60E-02			0.00E+00	2.08E+03	0.00E+00	2.60E+02
Eu-152		1.36E-01	1.24E-06			0.00E+00	9.88E-01	0.00E+00	2.35E-01
Eu-154		4.71E-02	4.28E-07			0.00E+00	3.42E-01	0.00E+00	8.13E-02
Eu-155		1.96E-02	1.78E-07			0.00E+00	1.43E-01	0.00E+00	3.39E-02

ıued)

28	29	30	31	32	33	34	35	36	37
Wastewater from blowdowns	Wastewater for sluicing	Wastewater to treatment	evaporator condensate	Evaporator concentrate	Treated concentrate	Binder	HEPA filters	Half-PACT canisters	Tank vents
2,539	0	2,539	0.000	2,539	2,539		0.007		0.007
0	0.000	0.000	0.000	0.000	0		0.004		0.004
0	0.000	0.000	0.000	0.000	0		0.000		0.000
0	0.000	0.000	0.000	0.000	0		0.000		0.000
0	0.000	0.000	0.000	0.000	0		0.000		0.000
0	0.000	0.000	0.000	0.000	0		0.000		0.000
0	0.000	0.000	0.000	0.000	0		0.000		0.000
ıses									
419,539	0.000	419,539	209,769	209,769	209,769		0.000		1,246,768
0	0.000	0.000	0.000	0.000	0		0.000		92,419
0	0.000	0.000	0.000	0.000	0		0.000		3,265
0	0.000	0.000	0.000	0.000	0		0.000		7,726,396
0	0.000	0.000	0.000	0.000	0		0.000		
0	0.000	0.000	0.000	0.000	0		0.000		2,072,603
0	0.000	0.000	0.000	0.000	0		0.000		
0	0.000	0.000	0.000	0.000	0		0.000		
0	0.000	0.000	0.000	0.000	0		0.000		
0	0.000	0.000	0.000	0.000	0		0.000		
0	0.000	0.000	0.000	0.000	0		0.000		
0	0	0	0	0	0		0		0
27,091	0	27,091	0	27,091	295,122		553		0
74,677	0	74,677	0	74,677	74,677		353		0
0	0	0	0	0	0		0	0	9,894,684
419,539	0	419,539	209,769	209,769	209,769		0	0	1,246,768
521,307	0	521,307	209,769	311,538	579,568		907	0	11,141,452
ous									
26.90	0.00	26.90	10.83	16.08	29.91		0.05		402
0.095	0.000	0.095	0.048	0.047	0.069				1,496
									200
25	25	25					25		25
1.25	1.25	1.25	1.00	1.50	1.90		1.50		0.0012
78.07	78.07	78.07	62.43	93.92	118.61		93.64		0.0739
ituents (in Ci)									
7.28E-259	0.00E+00	7.28E-259	0.00E+00	0.000	7.28E-259		1.48E-260		7.43E-260
0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.000	0.00E+00		0.00E+00		0.00E+00
3.71E-02	0.00E+00	3.71E-02	0.00E+00	0.037	3.71E-02		4.12E-03		4.12E-03
1.39E-02	0.00E+00	1.39E-02	0.00E+00	0.014	1.39E-02		2.83E-04		1.42E-03
2.43E-03	0.00E+00	2.43E-03	0.00E+00	0.002	2.43E-03		4.96E-05		2.48E-04
0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.000	0.00E+00		0.00E+00		0.00E+00
9.12E+00	0.00E+00	9.12E+00	0.00E+00	9.123	9.12E+00		1.86E-01		9.32E-01
4.66E+02	0.00E+00	4.66E+02	0.00E+00	466.479	4.66E+02		9.52E+00		4.76E-01
5.76E+00	0.00E+00	5.76E+00	0.00E+00	5.764	5.76E+00		6.40E-01		6.41E-02
2.34E+03	0.00E+00	2.34E+03	0.00E+00	2337.282	2.34E+03		2.60E+02		2.60E+01
1.22E+00	0.00E+00	1.22E+00	0.00E+00	1.223	1.22E+00		1.24E-02		1.24E-01
4.24E-01	0.00E+00	4.24E-01	0.00E+00	0.424	4.24E-01		4.28E-03		4.28E-02
1.76E-01	0.00E+00	1.76E-01	0.00E+00	0.176	1.76E-01		1.78E-03		1.78E-02

Stream No.	Units	20 Off-gas to HEPAs	21 Off-gas to stack discharge	22 Clean sluicing water	23 Decanted supernate	24 Water to quencher/ scrubber	25 Quencher/ scrubber blowdown	26 Water to mist eliminator	27 Mist eliminat blowdo
H-3		2.57E+00	2.56E-04			0.00E+00	2.56E+00	0.00E+00	0.00E+00
I-129		7.78E-06	1.30E-10			0.00E+00	5.18E-05	0.00E+00	1.17E-05
Nb-95		8.65E-23	1.44E-27			0.00E+00	5.76E-22	0.00E+00	1.30E-22
Pu-238		2.08E-04	3.47E-09			0.00E+00	1.39E-03	0.00E+00	3.12E-04
Pu-239		1.80E-04	3.00E-09			0.00E+00	1.20E-03	0.00E+00	2.70E-04
Pu-240		1.76E-04	2.93E-09			0.00E+00	1.17E-03	0.00E+00	2.63E-04
Pu-241		2.55E-03	4.25E-08			0.00E+00	1.70E-02	0.00E+00	3.83E-03
Pu-242		8.81E-06	1.47E-10			0.00E+00	5.87E-05	0.00E+00	1.32E-05
Pu-244		1.04E-06	1.73E-11			0.00E+00	6.91E-06	0.00E+00	1.55E-06
Ru-106		1.63E-03	2.71E-08			0.00E+00	1.08E-02	0.00E+00	2.44E-03
Sr-90		4.50E-01	4.08E-06			0.00E+00	3.27E+00	0.00E+00	7.76E-01
Tc-99		9.93E-02	4.96E-06			0.00E+00	1.99E+01	0.00E+00	4.91E+00
Th-232		2.07E-06	3.45E-11			0.00E+00	1.38E-05	0.00E+00	3.11E-06
U-233		7.42E-03	1.24E-07			0.00E+00	4.94E-02	0.00E+00	1.11E-02
U-234		1.50E-04	2.50E-09			0.00E+00	1.00E-03	0.00E+00	2.25E-04
U-235		6.22E-06	1.04E-10			0.00E+00	4.14E-05	0.00E+00	9.33E-06
U-236		3.63E-06	6.04E-11			0.00E+00	2.42E-05	0.00E+00	5.44E-06
U-238		1.98E-04	3.30E-09			0.00E+00	1.32E-03	0.00E+00	2.97E-04
Zr-95		9.90E-14	1.65E-18			0.00E+00	6.59E-13	0.00E+00	1.48E-13
TRU activity		3.13E-03	5.21E-08	0.00E+00	0.00E+00	0.00E+00	2.08E-02	0.00E+00	4.69E-03

CH = contact handled.
Ci = curie.
gpm = gallons per minute.
h = hour.
HEPA = high-efficiency particulate air.
kg = kilogram.
lb = pound.
MVST = Melton Valley Storage Tank.
RH = remote handled.
scfm = standard cubic feet per minute.
TRU = transuranic.
WIPP = Waste Isolation Pilot Plant (New Mexico).

ued)

28	29	30	31	32	33	34	35	36	37
Wastewater from blowdowns	Wastewater for sluicing	Wastewater to treatment	evaporator condensate	Evaporator concentrate	Treated concentrate	Binder	HEPA filters	Half-PACT canisters	Tank vents
2.56E+00	0.00E+00	2.56E+00	0.00E+00	2.562	2.56E+00		2.56E+00		5.13E-03
6.35E-05	0.00E+00	6.35E-05	0.00E+00	0.000	6.35E-05		1.30E-06		6.48E-06
7.06E-22	0.00E+00	7.06E-22	0.00E+00	0.000	7.06E-22		1.44E-23		7.21E-23
1.70E-03	0.00E+00	1.70E-03	0.00E+00	0.002	1.70E-03		3.47E-05		1.73E-04
1.47E-03	0.00E+00	1.47E-03	0.00E+00	0.001	1.47E-03		3.00E-05		1.50E-04
1.43E-03	0.00E+00	1.43E-03	0.00E+00	0.001	1.43E-03		2.92E-05		1.46E-04
2.08E-02	0.00E+00	2.08E-02	0.00E+00	0.021	2.08E-02		4.25E-04		2.13E-03
7.19E-05	0.00E+00	7.19E-05	0.00E+00	0.000	7.19E-05		1.47E-06		7.35E-06
8.46E-06	0.00E+00	8.46E-06	0.00E+00	0.000	8.46E-06		1.73E-07		8.64E-07
1.33E-02	0.00E+00	1.33E-02	0.00E+00	0.013	1.33E-02		2.71E-04		1.35E-03
4.04E+00	0.00E+00	4.04E+00	0.00E+00	4.044	4.04E+00		4.08E-02		4.09E-01
2.48E+01	0.00E+00	2.48E+01	0.00E+00	24.774	2.48E+01		4.96E-02		4.97E-02
1.69E-05	0.00E+00	1.69E-05	0.00E+00	0.000	1.69E-05		3.45E-07		1.73E-06
6.06E-02	0.00E+00	6.06E-02	0.00E+00	0.061	6.06E-02		1.24E-03		6.19E-03
1.23E-03	0.00E+00	1.23E-03	0.00E+00	0.001	1.23E-03		2.50E-05		1.25E-04
5.08E-05	0.00E+00	5.08E-05	0.00E+00	0.000	5.08E-05		1.04E-06		5.19E-06
2.96E-05	0.00E+00	2.96E-05	0.00E+00	0.000	2.96E-05		6.04E-07		3.03E-06
1.62E-03	0.00E+00	1.62E-03	0.00E+00	0.002	1.62E-03		3.30E-05		1.65E-04
8.07E-13	0.00E+00	8.07E-13	0.00E+00	0.000	8.07E-13		1.65E-14		8.25E-14
2.55E-02	0.00E+00	2.55E-02	0.00E+00	2.55E-02	2.55E-02		5.21E-04	0.00E+00	2.61E-03

Table B.2-2. ORNL RH solid waste stream, OR-W106, volume/mass balance

Stream No.	301	302	303	306	307	308	309	310	311	312	314	315	316	317	319
Source	Feed	Removed waste	Debris	After size reduce	45-gal drums	To com-paction	To buffer storage	Pucks to 55-gal drums	55-gal drums	Grouted drums	To certifi-cation	Pack to ship	Grout feed	Grout wash	Process waste water
						Component volume (m^3)									
Grout						0.0	0.0	0.0	0.0	14.9	14.9	14.9	16.4	1.5	1.5
Liquid	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	9.9	9.9
Solids (i.e., misc.)	369.0	369.0	369.0	369.0	0.0	295.2	157.5	157.5	0.0	157.5	157.5	157.5	0.0	0.0	0.0
Metal debris	0.0	0.0	0.0	0.0	4.1	4.1	4.1	4.1	0.0	4.1	4.1	4.1	0.0	0.0	0.0
Glass debris	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Plastic/rubber debris	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Paper/cloth debris	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Electronic equipment	9.5	9.5	9.5	9.5	0.0	7.6	5.0	5.0	0.0	5.0	5.0	5.0	0.0	0.0	0.0
Total volume (m^3)	378.5	378.5	378.5	378.5	4.1	306.9	166.6	166.6	0.0	181.6	181.6	181.6	16.4	11.4	11.4
Density (kg/m^3)	619	619	619	619	7,800	868	1,599	1,599	0	1,615	1,615	1,615	1,800	1,105	1,105
Net mass (kg)	234,150	234,150	234,150	234,150	32,278	266,428	266,428	266,428	0	293,266	293,266	293,266	29,521	12,585	12,585
						Activities									
Total activity (Ci)	283	283	283	283	0	283	283	283	0	283	283	283	0	0	0
Total TRU activity (Ci)	19.4	19.4	19.4	19.4	0.0	19.4	19.4	19.4	0.0	19.4	19.4	19.4	0	0	0
TRU Concentration(nCi/g)	82.9	82.9	82.9	82.9	0.0	72.8	72.8	72.8		66.2	66.2	66.2			

Notes per Stream No:

Defer to Notes in Table B.2-3 unless otherwise specified.

301: The remote-handled (RH) Solids are contained in 91 C4 casks, 87 C6 casks, 19 C12 casks, 13 wood boxes, and three 55-gal drums per the Transuranic Waste Baseline Inventory Report (TWBIR).

306: No size reduction was assumed since the specific gravity was at 0.6.

311: Due to inconsistencies in puck sizes and no requirement for grout (non-Resource Conservation and Recovery Act), there will be ~15% more 55-gal drums than needed by volume.

ORNL = Oak Ridge National Laboratory.

TRU = transuranic.

Table B.2-3. ORNL RH solid waste (excluding OR-W106) volume/mass balance

Stream No.	301	302	303	306	307	308	309	310	311	312	314	315	316	317	319
Source	Feed	Removed waste	Debris	After size reduce	45-gal drums	To compaction	To buffer storage	Pucks to 55-gal drums	55-gal drums	Grouted drums	To certification	Pack to ship	Grout feed	Grout wash	Process waste water
						Component volume (m^3)									
Grout						0.0	0.0	0.0	0.0	5.6	5.6	5.6	6.2	0.6	0.6
Liquid	1.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2.5	2.5
Solids (i.e., misc.)	137.9	137.9	137.9	137.9	0.0	69.0	33.4	33.4	0.0	33.4	33.4	33.4	0.0	0.0	0.0
Metal debris	4.1	4.1	4.1	3.0	1.2	2.7	1.8	1.8	0.0	1.8	1.8	1.8	0.0	0.0	0.0
Glass debris	3.1	3.1	3.1	3.1	0.0	1.6	0.6	0.6	0.0	0.6	0.6	0.6	0.0	0.0	0.0
Plastic/rubber debris	9.7	9.7	9.7	9.7	0.0	4.9	1.2	1.2	0.0	1.2	1.2	1.2	0.0	0.0	0.0
Paper/cloth debris	9.3	9.3	9.3	9.3	0.0	4.7	1.2	1.2	0.0	1.2	1.2	1.2	0.0	0.0	0.0
Electronic equipment	6.4	6.4	6.4	6.4	0.0	3.2	1.6	1.6	0.0	1.6	1.6	1.6	0.0	0.0	0.0
Total volume (m^3)	171.5	171.5	170.5	169.5	1.2	85.9	39.8	39.8	0.0	45.4	45.4	45.4	6.2	3.0	3.0
Density (kg/m^3)	311	311	313	315	7,800	726	1,569	1,569	0	1,598	1,598	1,598	1,800	1,148	1,148
Net mass (kg)	53,366	53,366	53,366	53,366	9,036	62,402	62,402	62,402	0	72,518	72,518	72,518	11,128	3,487	3,487
						Activities									
Total activity (Ci)	425	425	425	425	0	425	425	425	0	425	425	425	0	0	0.00E+0
TRU activity (Ci)	56	56	56	56	0	56	56	56	0	56	56	56	0	0	0.00E+0
TRU conc. (nCi/g)	1,040	1,040	1,040	1,040	0	889	889	889		765	765	765			

Notes per Stream No.:

Defer to notes for worksheet "RH" unless otherwise specified in worksheet "RH 106" or in this worksheet.

ORNL = Oak Ridge National Laboratory.

RH = remote handled.

TRU = transuranic.

Table B.2-4. Summary of annualized radionuclide emissions for the Vitrification Alternative (Ci/year)

Radionuclide	Sludge/ supernate emissions	CH solids emissions	RH solids emissions	Total solids emissions	Total emissions
Ac-227	0.00E+00	7.16E-18	5.80E-16	3.19E-16	3.19E-16
AG-110	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
AG-110m	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Am-241	4.56E-06	4.74E-10	2.65E-11	2.30E-10	4.56E-06
Am-243	0.00E+00	9.26E-12	6.66E-17	4.21E-12	4.21E-12
Au-196	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Au-198	2.76E-264	0.00E+00	0.00E+00	0.00E+00	2.76E-264
Bk-249	0.00E+00	2.53E-14	2.72E-19	1.15E-14	1.15E-14
C-14	1.65E-07	1.50E-16	0.00E+00	6.82E-17	1.65E-07
Ce-144	5.26E-08	0.00E+00	0.00E+00	0.00E+00	5.26E-08
Cf-249	1.80E-10	1.32E-14	9.89E-15	1.14E-14	1.80E-10
Cf-252	9.02E-09	2.98E-12	4.47E-12	3.80E-12	9.03E-09
Cm-240	6.76E-07	1.39E-42	0.00E+00	6.31E-43	6.76E-07
Cm-242	3.46E-05	5.80E-11	0.00E+00	2.64E-11	3.46E-05
Cm-243	2.33E-06	0.00E+00	0.00E+00	0.00E+00	2.33E-06
Cm-244	9.79E-04	1.60E-09	2.47E-10	8.61E-10	9.79E-04
Cm-245	4.51E-08	2.71E-15	0.00E+00	1.23E-15	4.51E-08
Cm-246	1.56E-08	8.82E-18	0.00E+00	4.01E-18	1.56E-08
Cm-248	6.47E-09	2.32E-14	0.00E+00	1.06E-14	6.47E-09
Co-60	2.66E-05	1.45E-15	1.86E-12	1.01E-12	2.66E-05
Cs-134	2.33E-06	0.00E+00	0.00E+00	0.00E+00	2.33E-06
Cs-137	9.46E-04	2.28E-09	7.43E-11	1.08E-09	9.46E-04
Es-253	1.26E-10	3.01E-47	0.00E+00	1.37E-47	1.26E-10
Es-254m	1.09E-10	0.00E+00	0.00E+00	0.00E+00	1.09E-10
Eu-152	1.14E-04	4.09E-16	0.00E+00	1.86E-16	1.14E-04
Eu-154	4.97E-05	0.00E+00	0.00E+00	0.00E+00	4.97E-05
Eu-155	1.03E-05	0.00E+00	0.00E+00	0.00E+00	1.03E-05
Fe-59	6.29E-13	2.06E-28	0.00E+00	9.35E-29	6.29E-13
Gd-153	9.85E-10	0.00E+00	0.00E+00	0.00E+00	9.85E-10
H-3	3.63E-07	0.00E+00	0.00E+00	0.00E+00	3.63E-07
I-129	1.81E-07	0.00E+00	0.00E+00	0.00E+00	1.81E-07
I-131	1.25E-12	0.00E+00	2.42E-120	1.32E-120	1.25E-12
Nb-95	4.51E-09	0.00E+00	0.00E+00	0.00E+00	4.51E-09
Ni-63	9.09E-11	9.36E-17	0.00E+00	4.26E-17	9.09E-11
Np-237	8.94E-09	5.65E-13	1.33E-13	3.29E-13	8.94E-09
Pa-231	2.20E-12	2.78E-13	0.00E+00	1.26E-13	2.32E-12
Pm-147	1.20E-10	7.20E-13	0.00E+00	3.27E-13	1.20E-10
Po-209	6.00E-20	1.69E-18	0.00E+00	7.67E-19	8.27E-19
Pu-238	6.79E-06	3.23E-09	1.85E-11	1.48E-09	6.79E-06
Pu-239	3.49E-06	9.00E-10	4.87E-12	4.12E-10	3.49E-06
Pu-240	1.10E-06	8.50E-10	6.05E-18	3.86E-10	1.10E-06
Pu-241	9.16E-06	1.86E-09	4.24E-12	8.47E-10	9.16E-06
Pu-242	2.63E-09	2.11E-13	0.00E+00	9.59E-14	2.63E-09
Pu-244	2.50E-10	0.00E+00	0.00E+00	0.00E+00	2.50E-10
Ra-223	0.00E+00	5.51E-79	3.68E-91	2.51E-79	2.51E-79
Ra-226	0.00E+00	1.42E-12	0.00E+00	6.44E-13	6.44E-13

Table B.2-4 (continued)

Radionuclide	Sludge/ supernate emissions	CH solids emissions	RH solids emissions	Total solids emissions	Total emissions
Ru-106	3.35E-07	0.00E+00	0.00E+00	0.00E+00	3.35E-07
Sb-125	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Sr-90	1.84E-03	1.36E-09	2.67E-11	6.31E-10	1.84E-03
Tc-99	2.42E-06	1.57E-11	0.00E+00	7.14E-12	2.42E-06
Te-123	0.00E+00	2.30E-17	0.00E+00	1.04E-17	1.04E-17
Te-123m	0.00E+00	6.42E-22	0.00E+00	2.92E-22	2.92E-22
Th-230	0.00E+00	1.06E-17	0.00E+00	4.81E-18	4.81E-18
Th-232	2.98E-08	6.98E-16	7.43E-16	7.23E-16	2.98E-08
U-232	3.01E-08	2.60E-13	0.00E+00	1.18E-13	3.01E-08
U-233	2.69E-06	8.92E-11	3.01E-12	4.22E-11	2.69E-06
U-234	1.10E-06	1.47E-11	0.00E+00	6.70E-12	1.10E-06
U-235	2.88E-08	6.29E-15	2.87E-16	3.02E-15	2.88E-08
U-236	2.49E-09	8.57E-17	0.00E+00	3.90E-17	2.49E-09
U-238	1.09E-06	3.83E-14	6.66E-17	1.75E-14	1.09E-06
U-239	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Y-90	0.00E+00	1.71E-280	0.00E+00	7.77E-281	7.77E-281
Zn-65	0.00E+00	2.71E-18	0.00E+00	1.23E-18	1.23E-18
Zr-95	3.94E-16	0.00E+00	0.00E+00	0.00E+00	3.94E-16

Ci = curie.
CH = contact handled.
RH = remote handled.

Table B.2-5. Estimated radionuclide emissions for remediation of sludge and supernate by the Vitrification Alternative[a]

Radionuclide	Sludge (Bq/g)	Supernate (Bq/g)	Sludge and supernate (Ci/g)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled radionuclide emissions[c,d] (Ci)	Process radionuclide emissions[e] (Ci)	Radionuclide emissions after control	
								Project life[f] (Ci)	Annualized[g] (Ci/year)[g]
Ac-227	0.00E+00	0.00E+00	0.00E+00	2.18E+01				0.00E+00	0.00E+00
AG-110	0.00E+00	0.00E+00	0.00E+00	7.80E-07				0.00E+00	0.00E+00
AG-110m	0.00E+00	0.00E+00	0.00E+00	6.84E-01				0.00E+00	0.00E+00
Am-241[h]	0.00E+00	0.00E+00	0.00E+00	4.32E+02		1.25E-01	1.49E-260	1.25E-05	4.56E-06
Am-243	0.00E+00	0.00E+00	0.00E+00	7.37E+03				0.00E+00	0.00E+00
Au-196	0.00E+00	0.00E+00	0.00E+00	1.69E-02				0.00E+00	0.00E+00
Au-198	3.73E+03	0.00E+00	3.92E-08	7.38E-03	2.47E-266	7.44E-260	1.49E-260	7.58E-264	2.76E-264
Bk-249	0	0	0	8.76E-01		0.00E+00	0.00E+00	0.00E+00	0.00E+00
C-14	0.00E+00	8.30E+01	1.37E-09	5.73E+03	1.37E-09	4.12E-03	4.12E-03	4.54E-07	1.65E-07
Ce-144	1.06E+04	1.14E+03	1.31E-07	7.80E-01	4.71E-10	1.42E-03	2.83E-04	1.45E-07	5.26E-08
Cf-249	0.00E+00	0.00E+00	0.00E+00	3.51E+02		0.00E+00	4.96E-05	4.96E-10	1.80E-10
Cf-252	3.83E+01	1.80E+00	4.32E-10	2.65E+00	8.25E-11	2.48E-04	0.00E+00	2.48E-08	9.02E-09
Cm-240	0.00E+00	0.00E+00	0.00E+00	7.39E-02		0.00E+00	1.86E-01	1.86E-06	6.76E-07
Cm-242	0.00E+00	0.00E+00	0.00E+00	1.63E+02		0.00E+00	9.52E+00	9.52E-05	3.46E-05
Cm-243	1.03E+04	0.00E+00	1.09E-07	2.91E+01		0.00E+00	6.40E-01	6.40E-06	2.33E-06
Cm-244	3.64E+04	7.68E+02	3.95E-07	1.81E+01	3.10E-07	9.32E-01	2.60E+02	2.69E-03	9.79E-04
Cm-245	0.00E+00	0.00E+00	0.00E+00	8.50E+03		0.00E+00	1.24E-02	1.24E-07	4.51E-08
Cm-246	0.00E+00	0.00E+00	0.00E+00	4.73E+03		0.00E+00	4.28E-03	4.28E-08	1.56E-08
Cm-248	0.00E+00	0.00E+00	0.00E+00	3.40E+05		0.00E+00	1.78E-03	1.78E-08	6.47E-09
Co-60	3.35E+04	7.30E+02	3.64E-07	5.27E+00	1.58E-07	4.77E-01	2.56E+00	7.33E-05	2.66E-05
Cs-134	4.89E+03	7.74E+03	1.79E-07	2.06E+00	2.13E-08	6.41E-02	1.30E-06	6.41E-06	2.33E-06
Cs-137	5.77E+05	2.38E+05	1.00E-05	3.01E+01	8.64E-06	2.60E+01	1.44E-23	2.60E-03	9.46E-04
Es-253	0.00E+00	0.00E+00		5.60E-02		0.00E+00	3.47E-05	3.47E-10	1.26E-10
Es-254m	0.00E+00	0.00E+00		4.48E-03		0.00E+00	3.00E-05	3.00E-10	1.09E-10
Eu-152	1.32E+05	3.44E+03	1.44E-06	1.35E+01	1.04E-06	3.13E+00	2.93E-05	3.13E-04	1.14E-04
Eu-154	6.97E+04	1.44E+03	7.56E-07	8.59E+00	4.54E-07	1.37E+00	4.25E-04	1.37E-04	4.97E-05
Eu-155	2.12E+04	9.02E+02	2.37E-07	4.76E+00	9.44E-08	2.84E-01	1.47E-06	2.84E-05	1.03E-05
Fe-59	0.00E+00	0.00E+00	0.00E+00	1.22E-01	0.00E+00	0.00E+00	1.73E-07	1.73E-12	6.29E-13
Gd-153	0.00E+00	0.00E+00	0.00E+00	6.61E-01	0.00E+00	0.00E+00	2.71E-04	2.71E-09	9.85E-10
H-3	3.47E+01	1.47E+02	2.80E-09	1.23E+01	1.96E-09	5.90E-03	4.08E-02	9.98E-07	3.63E-07
I-129	0.00E+00	1.30E-01	2.15E-12	1.57E+07	2.15E-12	6.48E-06	4.96E-02	4.97E-07	1.81E-07
I-131	0.00E+00	0.00E+00	0.00E+00	2.20E-02	0.00E+00	0.00E+00	3.45E-07	3.45E-12	1.25E-12
Nb-95	2.30E+03	1.13E+02	2.60E-08	9.58E-02	3.34E-28	1.01E-21	1.24E-03	1.24E-08	4.51E-09
Ni-63	0.00E+00	0.00E+00	0.00E+00	1.00E+02	0.00E+00	0.00E+00	2.50E-05	2.50E-10	9.09E-11
Np-237	7.77E+00	0.00E+00	8.16E-11	2.14E+06	8.16E-11	2.46E-04	1.04E-06	2.46E-08	8.94E-09
Pa-231	0.00E+00	0.00E+00	0.00E+00	3.28E+04	0.00E+00	0.00E+00	6.04E-07	6.04E-12	2.20E-12
Pm-147	0.00E+00	0.00E+00	0.00E+00	2.62E+00	0.00E+00	0.00E+00	3.30E-05	3.30E-10	1.20E-10
Po-209	0.00E+00	0.00E+00	0.00E+00	1.02E+02	0.00E+00	0.00E+00	1.65E-14	1.65E-19	6.00E-20
Pu-238	6.20E+03	3.67E+00	6.52E-08	8.77E+01	6.20E-08	1.87E-01	5.21E-04	1.87E-05	6.79E-06
Pu-239	3.03E+03	3.03E+00	3.19E-08	2.41E+04	3.19E-08	9.60E-02	3.00E-05	9.60E-06	3.49E-06
Pu-240	9.50E+02	2.95E+00	1.00E-08	6.56E+03	1.00E-08	3.02E-02	2.93E-05	3.02E-06	1.10E-06
Pu-241	1.07E+04	5.81E+01	1.14E-07	1.44E+01	8.37E-08	2.52E-01	4.25E-04	2.52E-05	9.16E-06
Pu-242	2.05E+00	1.48E-01	2.40E-11	3.73E+05	2.40E-11	7.22E-05	1.47E-06	7.23E-09	2.63E-09
Pu-244	1.90E-01	1.74E-02	2.28E-12	8.00E+05	2.28E-12	6.87E-06	1.73E-07	6.89E-10	2.50E-10

Table B.2-5 (continued)

Radionuclide	Sludge (Bq/g)	Supernate (Bq/g)	Sludge and supernate (Ci/g)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled radionuclide emissions[c,d] (Ci)	Process radionuclide emissions[e] (Ci)	Radionuclide emissions after control: Project life[f] (Ci)	Radionuclide emissions after control: Annualized[g] (Ci/year)[g]
Ra-223	0.00E+00	0.00E+00	0.00E+00	3.13E-02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ra-226	0.00E+00	0.00E+00	0.00E+00	1.60E+03	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ru-106	1.83E+04	2.01E+03	2.25E-07	1.02E+00	3.05E-09	9.17E-03	2.71E-04	9.20E-07	3.35E-07
Sb-125	0.00E+00	0.00E+00	0.00E+00	2.76E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Sr-90	1.85E+06	9.58E+03	1.96E-05	2.88E+01	1.68E-05	5.07E+01	4.08E-02	5.07E-03	1.84E-03
Tc-99	3.72E+02	1.00E+03	2.04E-08	2.11E+05	2.04E-08	6.15E-02	4.96E-02	6.65E-06	2.42E-06
Te-123	0.00E+00	0.00E+00	0.00E+00	1.00E+08	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Te-123m	0.00E+00	0.00E+00	0.00E+00	3.28E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Th-230	0.00E+00	0.00E+00	0.00E+00	7.54E+04	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Th-232	2.59E+01	3.48E-02	2.72E-10	1.41E+10	2.72E-10	8.20E-04	3.45E-07	8.20E-08	2.98E-08
U-232	0.00E+00	1.74E+01	2.87E-10	6.89E+01	2.70E-10	8.11E-04	1.62E-04	8.27E-08	3.01E-08
U-233	2.14E+03	1.24E+02	2.45E-08	1.59E+05	2.45E-08	7.37E-02	1.24E-03	7.39E-06	2.69E-06
U-234	9.50E+02	2.52E+00	1.00E-08	2.46E+05	1.00E-08	3.02E-02	2.50E-05	3.02E-06	1.10E-06
U-235	2.49E+01	1.04E-01	2.63E-10	3.80E+06	2.63E-10	7.91E-04	1.04E-06	7.91E-08	2.88E-08
U-236	2.07E+00	6.09E-02	2.28E-11	2.34E+07	2.28E-11	6.85E-05	6.04E-07	6.85E-09	2.49E-09
U-238	9.44E+02	3.32E+00	9.97E-09	4.47E+09	9.97E-09	3.00E-02	3.30E-05	3.00E-06	1.09E-06
U-239	0.00E+00	0.00E+00	0.00E+00	4.46E-05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Y-90	0.00E+00	0.00E+00	0.00E+00	7.31E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Zn-65	0.00E+00	0.00E+00	0.00E+00	6.69E-01	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Zr-95	2.63E+04	1.28E+02	2.78E-07	1.75E-01	3.60E-18	1.08E-11	1.65E-14	1.08E-15	3.94E-16
TRU Activity	1.02E+04	1.16E+01	1.08E-07	2.90E+06	1.04E-07	4.39E-01	1.90E-02	4.41E-05	1.60E-05

[a]The data were obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Nos. ORNL/TM/-13351 and ORNL/TM-13351, Addendum 1. The radionuclide concentration was then calculated for the elapsed time (6.33 years) from when the data were analyzed and the startup of the treatment process (April 1001) based on radionuclide decay. Also, an average density of 1.3 g/mL was used for the sludge which was calculated from sludge data provided in ORNL/TM-13351. An average density of 1.15 g/mL was obtained for the supernate from Table 4.1, p. 3, of ORNL/TM-13351, Addendum 1.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp - [\ln(2)/t_{1/2} * T] ,$$

where:

A = decayed radionuclide composition;
Ao = the original concentration in Ci/g;
$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the website www.dnc.bnl.gov/CoN/index.html,
T = the time between sample analysis (December 1996) to the time of process startup (April 2003), which is 6.33 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D of 40 *Code of Federal Regulations* (*CFR*) 61:

Emissions Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors form Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Demister Adjustment Factor	= 0.10
First High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor	= 0.01
Second HEPA Filter Adjustment Factor	= 0.01

The demister is only applicable for the gas from the vitrifier. The tank vents bypass the demister.

[f]A density of 2.6 g/mL was used for the treated waste (Spence 1998).

[g]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the sludge/supernate will be processed (2.5 years).

[h]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Bq = becquerel. mL = milliliter.
Ci = curie. TRU = transuranic.
g = gram.

Table B.2-6. Estimated radionuclide emissions for remediation of CH solids for the Vitrification Alternative

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci)	Uncontrolled radionuclide emissions[c,d] (Ci)	Radionuclide emissions: After control project life[e] (Ci)	Radionuclide emissions: Annualized[f] (Ci/year)
Ac-227	1.10E-05	2.18E+01	8.95E-06	8.95E-12	8.95E-18	7.16E-18
Ag-110		7.80E-07				
Ag-110m		6.84E-01				
Am-241[g]	5.77E+02	4.32E+02	5.92E+02	5.92E-04	5.92E-10	4.74E-10
Am-243	1.16E+01	7.37E+03	1.16E+01	1.16E-05	1.16E-11	9.26E-12
Au-196		1.69E-02				
Au-198		7.38E-03				
Bk-249	5.77E+00	8.76E-01	3.16E-02	3.16E-08	3.16E-14	2.53E-14
C-14	1.88E-04	5.73E+03	1.87E-04	1.87E-10	1.87E-16	1.50E-16
Ce-144		7.80E-01				
Cf-249	1.68E-02	3.51E+02	1.66E-02	1.66E-08	1.66E-14	1.32E-14
Cf-252	2.09E+01	2.65E+00	3.73E+00	3.73E-06	3.73E-12	2.98E-12
Cm-240	1.10E-03	7.39E-02	1.73E-30	1.73E-36	1.73E-42	1.39E-42
Cm-242	7.46E+01	1.63E+02	7.25E+01	7.25E-05	7.25E-11	5.80E-11
Cm-243		2.91E+01				
Cm-244	2.57E+03	1.81E+01	2.00E+03	2.00E-03	2.00E-09	1.60E-09
Cm-245	3.39E-03	8.50E+03	3.39E-03	3.39E-09	3.39E-15	2.71E-15
Cm-246	1.10E-05	4.73E+03	1.10E-05	1.10E-11	1.10E-17	8.82E-18
Cm-248	2.90E-02	3.40E+05	2.90E-02	2.90E-08	2.90E-14	2.32E-14
Co-60	4.30E-03	5.27E+00	1.81E-03	1.81E-09	1.81E-15	1.45E-15
Cs-134		2.06E+00				
Cs-137	3.31E+03	3.01E+01	2.84E+03	2.84E-03	2.84E-09	2.28E-09
Es-253	8.83E+00	5.60E-02	3.76E-35	3.76E-41	3.76E-47	3.01E-47
Es-254m	1.20E+01	4.48E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Eu-152	7.17E-04	1.35E+01	5.12E-04	5.12E-10	5.12E-16	4.09E-16
Eu-154		8.59E+00	0.00E+00			
Eu-155		4.76E+00				
Fe-59	4.42E+00	1.22E-01	2.57E-16	2.57E-22	2.57E-28	2.06E-28
Gd-153		6.61E-01				
H-3		1.23E+01				
I-129		1.57E+07				
I-131		2.20E-02				
Nb-95		9.58E-02				
Ni-63	1.22E-04	1.00E+02	1.17E-04	1.17E-10	1.17E-16	9.36E-17
Np-237	7.06E-01	2.14E+06	7.06E-01	7.06E-07	7.06E-13	5.65E-13
Pa-231	3.48E-01	3.28E+04	3.48E-01	3.48E-07	3.48E-13	2.78E-13
Pm-147	5.13E+00	2.62E+00	9.00E-01	9.00E-07	9.00E-13	7.20E-13
Po-209	2.21E-06	1.02E+02	2.11E-06	2.11E-12	2.11E-18	1.69E-18
Pu-238	4.26E+03	8.77E+01	4.04E+03	4.04E-03	4.04E-09	3.23E-09
Pu-239	1.13E+03	2.41E+04	1.13E+03	1.13E-03	1.13E-09	9.00E-10
Pu-240	1.06E+03	6.56E+03	1.06E+03	1.06E-03	1.06E-09	8.50E-10
Pu-241	3.19E+03	1.44E+01	2.32E+03	2.32E-03	2.32E-09	1.86E-09
Pu-242	2.64E-01	3.73E+05	2.64E-01	2.64E-07	2.64E-13	2.11E-13
Pu-244		8.00E+05				
Ra-223	1.32E-03	3.13E-02	6.89E-67	6.89E-73	6.89E-79	5.51E-79

Table B.2-6 (continued)

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci)	Uncontrolled radionuclide emissions[c,d] (Ci)	Radionuclide emissions: After control project life[e] (Ci)	Radionuclide emissions: Annualized[f] (Ci/year)
Ra-226	1.78E+00	1.60E+03	1.77E+00	1.77E-06	1.77E-12	1.42E-12
Ru-106		1.02E+00				
Sb-125		2.76E+00				
Sr-90	1.99E+03	2.88E+01	1.70E+03	1.70E-03	1.70E-09	1.36E-09
Tc-99	1.96E+01	2.11E+05	1.96E+01	1.96E-05	1.96E-11	1.57E-11
Te-123	2.87E-05	1.00E+08	2.87E-05	2.87E-11	2.87E-17	2.30E-17
Te-123m	8.77E-04	3.28E-01	8.02E-10	8.02E-16	8.02E-22	6.42E-22
Th-230	1.32E-05	7.54E+04	1.32E-05	1.32E-11	1.32E-17	1.06E-17
Th-232	8.73E-04	1.41E+10	8.73E-04	8.73E-10	8.73E-16	6.98E-16
U-232	3.48E-01	6.89E+01	3.25E-01	3.25E-07	3.25E-13	2.60E-13
U-233	1.11E+02	1.59E+05	1.11E+02	1.11E-04	1.11E-10	8.92E-11
U-234	1.84E+01	2.46E+05	1.84E+01	1.84E-05	1.84E-11	1.47E-11
U-235	7.87E-03	3.80E+06	7.87E-03	7.87E-09	7.87E-15	6.29E-15
U-236	1.07E-04	2.34E+07	1.07E-04	1.07E-10	1.07E-16	8.57E-17
U-238	4.79E-02	4.47E+09	4.79E-02	4.79E-08	4.79E-14	3.83E-14
U-239		4.46E-05				
Y-90	1.99E+03	7.31E-03	2.14E-268	2.14E-274	2.14E-280	1.71E-280
Zn-65	3.09E-03	6.69E-01	3.38E-06	3.38E-12	3.38E-18	2.71E-18
Zr-95		1.75E-01				
TRU Activity	7.06E+03		6.84E+03	6.84E-03	6.84E-09	5.47E-09

[a]Composition data obtained from U.S. Department of Energy Memorandum: *TRU Waste Baseline Inventory Report for Oak Ridge*, June 1996. The data were then scaled up from 906.22m^3 to 1000m^3.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp - [\ln(2)/t_{1/2} * T] ,$$

where:

A = Decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the website www.dne.bnl.gov/CoN/index.html;

T = the time between sample analysis (June 1996) to the time remote-handled (RH) processing begins (January 2003), which is 6.58 years.

[c]An emissions factor of the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61:

Emissions Factor = .000001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor	=	0.01
Hot Cell GAC Adjustment Factor	=	0.10
First HEPA Filter Adjustment Factor	=	0.01
Second HEPA Filter Adjustment Factor	=	0.01

The demister is only applicable for the gas from the vitrifier. The tank vents bypass the demister.

[f]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the contact-handled (CH) solids will be processed (1.25 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Ci = curie.

TRU = transuranic.

Table B.2-7. Estimated radionuclide emissions for TRU waste remediation of RH solids for the Vitrification Alternative

Radionuclide	Radionuclide Composition[a] (Ci)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci)	Uncontrolled radionuclide emissions[c,d] (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	1.12E-03	2.18E+01	8.69E-04	8.69E-10	8.69E-16	5.80E-16
Ag-110		7.80E-07				
Ag-110m		6.84E-01				
Am-241[h]	4.02E+01	4.32E+02	3.97E+01	3.97E-05	3.97E-11	2.65E-11
Am-243	9.99E-05	7.37E+03	9.99E-05	9.99E-11	9.99E-17	6.66E-17
Au-196		1.69E-02				
Au-198		7.38E-03				
Bk-249	2.00E-04	8.76E-01	4.07E-07	4.07E-13	4.07E-19	2.72E-19
C-14		5.73E+03				
Ce-144		7.80E-01				
Cf-249	1.51E-02	3.51E+02	1.48E-02	1.48E-08	1.48E-14	9.89E-15
Cf-252	5.20E+01	2.65E+00	6.71E+00	6.71E-06	6.71E-12	4.47E-12
Cm-240		7.39E-02				
Cm-242		1.63E+02				
Cm-243		2.91E+01				
Cm-244	4.99E+02	1.81E+01	3.70E+02	3.70E-04	3.70E-10	2.47E-10
Cm-245		8.50E+03				
Cm-246		4.73E+03				
Cm-248		3.40E+05				
Co-60	7.81E+00	5.27E+00	2.79E+00	2.79E-06	2.79E-12	1.86E-12
Cs-134		2.06E+00				
Cs-137	1.33E+02	3.01E+01	1.11E+02	1.11E-04	1.11E-10	7.43E-11
Es-253		5.60E-02				
Es-254m		4.48E-03				
Eu-152		1.35E+01				
Eu-154		8.59E+00				
Eu-155		4.76E+00				
Fe-59		1.22E-01				
Gd-153		6.61E-01				
H-3		1.23E+01				
I-129		1.57E+07				
I-131	5.00E-01	2.20E-02	3.63E-108	3.63E-114	3.63E-120	2.42E-120
Nb-95		9.58E-02				
Ni-63		1.00E+02				
Np-237	2.00E-01	2.14E+06	2.00E-01	2.00E-07	2.00E-13	1.33E-13
Pa-231		3.28E+04				
Pm-147		2.62E+00				
Po-209		1.02E+02				
Pu-238	2.94E+01	8.77E+01	2.77E+01	2.77E-05	2.77E-11	1.85E-11
Pu-239	7.31E+00	2.41E+04	7.31E+00	7.31E-06	7.31E-12	4.87E-12
Pu-240	9.08E-06	6.56E+03	9.08E-06	9.08E-12	9.08E-18	6.05E-18
Pu-241	9.27E+00	1.44E+01	6.36E+00	6.36E-06	6.36E-12	4.24E-12
Pu-242		3.73E+05				
Pu-244		8.00E+05				
Ra-223	1.12E-03	3.13E-02	5.52E-79	5.52E-85	5.52E-91	3.68E-91

Table B.2-7 (continued)

Radionuclide	Radionuclide Composition[a] (Ci)	Radionuclide half life, $t_{1/2}$[b] (year)	Decayed radionuclide composition (Ci)	Uncontrolled radionuclide emissions[c,d] (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ra-226		1.60E+03				
Ru-106		1.02E+00				
Sb-125		2.76E+00				
Sr-90	4.83E+01	2.88E+01	4.00E+01	4.00E-05	4.00E-11	2.67E-11
Tc-99		2.11E+05				
Te-123		1.00E+08				
Te-123m		3.28E-01				
Th-230		7.54E+04				
Th-232	1.12E-03	1.41E+10	1.12E-03	1.12E-09	1.12E-15	7.43E-16
U-232		6.89E+01				
U-233	4.51E+00	1.59E+05	4.51E+00	4.51E-06	4.51E-12	3.01E-12
U-234		2.46E+05				
U-235	4.30E-04	3.80E+06	4.30E-04	4.30E-10	4.30E-16	2.87E-16
U-236		2.34E+07				
U-238	9.99E-05	4.47E+09	9.99E-05	9.99E-11	9.99E-17	6.66E-17
U-239		4.46E-05				
Y-90	4.83E+01	7.31E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Zn-65		6.69E-01				
Zr-95		1.75E-01				
TRU Activity	7.71E+01		7.49E+01	7.49E-05	7.49E-11	4.99E-11

[a]Composition data obtained from U.S. Department of Energy Memorandum: *TRU Waste Baseline Inventory Report for Oak Ridge*, June 1996.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp - [\ln(2)/t_{1/2} * T] ,$$

where:

A = decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the website www.dne.bnl.gov/CoN/index.html.

T = the time between sample analysis (June 1996) to the time remote-handled (RH) processing begins (January 2004), which is 7.83 years.

[c]An emissions factor of the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61:

Emissions Factor = 0.000001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Facto	=	0.01
Hot Cell GAC Adjustment Factor	=	0.10
First HEPA Filter Adjustment Factor	=	0.01
Second HEPA Filter Adjustment Factor	=	0.01

The demister is only applicable for the gas from the vitrifier. The tank vents bypass the demister.

[f]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the contact-handled (CH) solids will be processed (1.5 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Ci = curie.

TRU = transuranic.

Table B.2-8. Summary of TRU waste remediation hourly particulate emissions (lbs/h) for the Vitrification Alternative

Metals	Classification	Average hourly emissions (lbs/h) Sludge and supernate	CH solids	RH solids	CH/RH solids	Total	Maximum hourly emissions[a] (lbs/h)	Average annual emissions[b] (tons/year)
TSP		6.86E-04	1.71E-04	1.71E-04	1.71E-04	7.78E-04	9.72E-04	2.43E-03
Total HAP		3.02E-07	5.13E-04	5.13E-04	5.12E-04	2.76E-04	3.45E-04	3.13E-04
Silver (Ag)		2.17E-09	1.71E-04	1.71E-04	1.71E-04	9.18E-05	1.15E-04	1.04E-04
Aluminum (Al)		2.14E-06				2.14E-06	2.68E-06	2.43E-06
Arsenic (As)	HAP	5.31E-09				5.31E-09	6.64E-09	6.03E-09
Boron (B)		3.79E-09				3.79E-09	4.74E-09	4.30E-09
Barium (Ba)		2.56E-08				2.56E-08	3.20E-08	2.91E-08
Beryllium (Be)	HAP	4.91E-10				4.91E-10	6.14E-10	5.58E-10
Bismuth (Bi)		9.84E-10				9.84E-10	1.23E-09	1.12E-09
Calcium (Ca)		6.92E-06				6.92E-06	8.65E-06	7.85E-06
Cadmium (Cd)	HAP	2.59E-09	1.71E-04	1.71E-04	1.71E-04	9.18E-05	1.15E-04	1.04E-04
Cerium (Ce)		1.35E-10				1.35E-10	1.69E-10	1.53E-10
Cobalt (Co)	HAP	1.03E-09				1.03E-09	1.29E-09	1.17E-09
Chromium (Cr)	HAP	9.24E-08				9.24E-08	1.16E-07	1.05E-07
Cesium (Cs)		1.71E-09				1.71E-09	2.14E-09	1.94E-09
Copper (Cu)		1.46E-08				1.46E-08	1.82E-08	1.65E-08
Iron (Fe)		1.16E-06				1.16E-06	1.44E-06	1.31E-06
Gallium (Ga)		1.20E-10				1.20E-10	1.50E-10	1.36E-10
Mercury (Hg)	HAP	1.78E-08	1.71E-04	1.71E-04	1.71E-04	9.18E-05	1.15E-04	1.04E-04
Iodine (I)		5.39E-09				5.39E-09	6.74E-09	6.12E-09
Potassium (K)		5.83E-06				5.83E-06	7.29E-06	6.62E-06
Lanthanum (La)		1.46E-11				1.46E-11	1.82E-11	1.65E-11
Lithium (Li)		9.73E-09				9.73E-09	1.22E-08	1.10E-08
Magnesium (Mg)		1.15E-06				1.15E-06	1.43E-06	1.30E-06
Manganese (Mn)	HAP	2.79E-08				2.79E-08	3.49E-08	3.16E-08
Molybdenum (Mo)		4.52E-10				4.52E-10	5.65E-10	5.13E-10
Sodium (Na)		3.17E-05				3.17E-05	3.96E-05	3.59E-05
Niobium (Nb)		0.00E+00				0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	HAP	1.74E-08				1.74E-08	2.17E-08	1.97E-08
Phosphorus (P)		3.53E-06				3.53E-06	4.42E-06	4.01E-06
Lead (Pb)	HAP	1.24E-07	1.71E-04	1.71E-04	1.71E-04	9.20E-05	1.15E-04	1.04E-04
Rubidium (Rb)		4.30E-10				4.30E-10	5.38E-10	4.88E-10
Antimony (Sb)	HAP	7.64E-09				7.64E-09	9.55E-09	8.66E-09
Selenium (Se)	HAP	5.33E-09				5.33E-09	6.67E-09	6.05E-09
Silicon (Si)		6.26E-07				6.26E-07	7.82E-07	7.10E-07
Tin (Sn)		1.39E-10				1.39E-10	1.73E-10	1.57E-10
Strontium (Sr)		2.83E-08				2.83E-08	3.54E-08	3.22E-08
Thorium (Th)		1.57E-06				1.57E-06	1.96E-06	1.78E-06
Titanium (Ti)		1.86E-10				1.86E-10	2.32E-10	2.11E-10
Thallium (Th)		3.86E-09				3.86E-09	4.82E-09	4.38E-09
Uranium (U)		1.30E-05				1.30E-05	1.62E-05	1.47E-05
Vanadium (V)		8.00E-10				8.00E-10	1.00E-09	9.08E-10
Tungsten (W)		1.68E-10				1.68E-10	2.10E-10	1.90E-10
Zinc (Zn)		4.06E-08				4.06E-08	5.07E-08	4.60E-08
Zirconium (Zr)		1.09E-11				1.09E-11	1.37E-11	1.24E-11

[a]Maximum hourly is estimated by multiplying average hourly rate by 1.25.
[b]Average annual emissions are the average hourly emissions multiplied by the operational hours and then divided by 2.75 years.
CH = contact handled. lb = pound. TRU = transuranic.
h = hour. RH = remote handled.
HAP = hazardous air pollutant. TSP = total suspended particulate.

Table B.2-9. Estimated metals emissions for remediation of sludge and supernate waste for the Vitrification Alternative

Metals	Metals mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
TSP		1.30E-01	5.34E+07	1.18E+05	5.34E+03	1.18E+01	6.86E-04
Silver (Ag)	3.17E-06	4.11E-07	1.69E+02	3.73E-01	1.69E-02	3.73E-05	2.17E-09
Aluminum (Al)	3.12E-03	4.05E-04	1.67E+05	3.67E+02	1.67E+01	3.67E-02	2.14E-06
Arsenic (As)	7.75E-06	1.00E-06	4.13E+02	9.12E-01	4.13E-02	9.12E-05	5.31E-09
Boron (B)	5.53E-06	7.17E-07	2.95E+02	6.51E-01	2.95E-02	6.51E-05	3.79E-09
Barium (Ba)	3.74E-05	4.84E-06	1.99E+03	4.40E+00	1.99E-01	4.40E-04	2.56E-08
Beryllium (Be)	7.17E-07	9.29E-08	3.83E+01	8.43E-02	3.83E-03	8.43E-06	4.91E-10
Bismuth (Bi)	1.44E-06	1.86E-07	7.66E+01	1.69E-01	7.66E-03	1.69E-05	9.84E-10
Calcium (Ca)	1.01E-02	1.31E-03	5.39E+05	1.19E+03	5.39E+01	1.19E-01	6.92E-06
Cadmium (Cd)	3.78E-06	4.90E-07	2.02E+02	4.45E-01	2.02E-02	4.45E-05	2.59E-09
Cerium (Ce)	1.97E-07	2.55E-08	1.05E+01	2.31E-02	1.05E-03	2.31E-06	1.35E-10
Cobalt (Co)	1.50E-06	1.94E-07	8.01E+01	1.76E-01	8.01E-03	1.76E-05	1.03E-09
Chromium (Cr)	1.35E-04	1.75E-05	7.19E+03	1.59E+01	7.19E-01	1.59E-03	9.24E-08
Cesium (Cs)	2.50E-06	3.23E-07	1.33E+02	2.94E-01	1.33E-02	2.94E-05	1.71E-09
Copper (Cu)	2.13E-05	2.75E-06	1.13E+03	2.50E+00	1.13E-01	2.50E-04	1.46E-08
Iron (Fe)	1.68E-03	2.18E-04	8.99E+04	1.98E+02	8.99E+00	1.98E-02	1.16E-06
Gallium (Ga)	1.75E-07	2.27E-08	9.36E+00	2.06E-02	9.36E-04	2.06E-06	1.20E-10
Mercury (Hg)	2.59E-05	3.36E-06	1.38E+03	3.05E+00	1.38E-01	3.05E-04	1.78E-08
Iodine (I)	7.86E-06	1.02E-06	4.20E+02	9.25E-01	4.20E-02	9.25E-05	5.39E-09
Potassium (K)	8.51E-03	1.10E-03	4.54E+05	1.00E+03	4.54E+01	1.00E-01	5.83E-06
Lanthanum (La)	2.13E-08	2.76E-09	1.13E+00	2.50E-03	1.13E-04	2.50E-07	1.46E-11
Lithium (Li)	1.42E-05	1.84E-06	7.57E+02	1.67E+00	7.57E-02	1.67E-04	9.73E-09
Magnesium (Mg)	1.67E-03	2.16E-04	8.91E+04	1.97E+02	8.91E+00	1.97E-02	1.15E-06
Manganese (Mn)	4.07E-05	5.27E-06	2.17E+03	4.78E+00	2.17E-01	4.78E-04	2.79E-08
Molybdenum (Mo)	6.59E-07	8.54E-08	3.52E+01	7.76E-02	3.52E-03	7.76E-06	4.52E-10
Sodium (Na)	4.62E-02	5.99E-03	2.47E+06	5.44E+03	2.47E+02	5.44E-01	3.17E-05
Niobium (Nb)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	2.53E-05	3.28E-06	1.35E+03	2.98E+00	1.35E-01	2.98E-04	1.74E-08
Phosphorus (P)	5.15E-03	6.68E-04	2.75E+05	6.06E+02	2.75E+01	6.06E-02	3.53E-06
Lead (Pb)	1.81E-04	2.35E-05	9.66E+03	2.13E+01	9.66E-01	2.13E-03	1.24E-07
Rubidium (Rb)	6.27E-07	8.13E-08	3.35E+01	7.38E-02	3.35E-03	7.38E-06	4.30E-10
Antimony (Sb)	1.11E-05	1.44E-06	5.94E+02	1.31E+00	5.94E-02	1.31E-04	7.64E-09
Selenium (Se)	7.78E-06	1.01E-06	4.15E+02	9.15E-01	4.15E-02	9.15E-05	5.33E-09
Silicon (Si)	9.13E-04	1.18E-04	4.87E+04	1.07E+02	4.87E+00	1.07E-02	6.26E-07
Tin (Sn)	2.02E-07	2.62E-08	1.08E+01	2.38E-02	1.08E-03	2.38E-06	1.39E-10
Strontium (Sr)	4.13E-05	5.36E-06	2.21E+03	4.86E+00	2.21E-01	4.86E-04	2.83E-08
Thorium (Th)	2.29E-03	2.96E-04	1.22E+05	2.69E+02	1.22E+01	2.69E-02	1.57E-06
Titanium (Ti)	2.71E-07	3.51E-08	1.45E+01	3.19E-02	1.45E-03	3.19E-06	1.86E-10
Thallium (Th)	5.62E-06	7.29E-07	3.00E+02	6.62E-01	3.00E-02	6.62E-05	3.86E-09
Uranium (U)	1.90E-02	2.46E-03	1.01E+06	2.23E+03	1.01E+02	2.23E-01	1.30E-05

Table B.2-9 (continued)

Metals	Metals mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Vanadium (V)	1.17E-06	1.51E-07	6.23E+01	1.37E-01	6.23E-03	1.37E-05	8.00E-10
Tungsten (W)	2.45E-07	3.17E-08	1.31E+01	2.88E-02	1.31E-03	2.88E-06	1.68E-10
Zinc (Zn)	5.92E-05	7.67E-06	3.16E+03	6.96E+00	3.16E-01	6.96E-04	4.06E-08
Zirconium (Zr)	1.59E-08	2.07E-09	8.51E-01	1.88E-03	8.51E-05	1.88E-07	1.09E-11

[a]The data were obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document Nos. ONRL/TM-13351 and ORNL/TM-13351, Addendum 1. An average density of 1.3 g/mL was used for the sludge which was calculated from sludge data provided in ORNL/TM-13351. Given the volume stated in the request for proposal (RFP) of 900 m^3 of sludge, there is 1,700,000 kg of sludge mass. An average density of 1.15 g/mL was obtained for the supernate from Table 4.1, p. 3, of ORNL/TM-13351, Addendum 1. Given the volume stated in the RFP of 1600 m^3 of supernate, there is 1,840,000 kg of supernate mass.

[b]The amount of total suspended particulate (TSP) matter reaching the first exhaust system High-Efficiency Particulate Air (HEPA) filter is assumed to be:

Airborne Particulate Concentration = 2.0 gr/dscf = 0.1296 g/dscf.

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Exhaust Stream Flowrate × TSP Concentration × Metal Mass Fraction.

The operating schedule was presented from Sect. 2.3 of this Environmental Impact Statement:

Air Flow Rate	=	400 dscfm (calculated from a first pass material balance of the vitrification process)
Process Operating Schedule	=	2,175 years life; 260 d/year; 24 h/d; and 60 min/h
Calculated Operating Hours	=	17,160 h

[d]The two HEPA filtration systems are assumed to have the following removal efficiencies:

First HEPA Filter Removal	=	99%.
Second HEPA Filter Removal	=	99%.

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pound Emitted for Project/Project Operating Hours.

d = day.
dscf = dry standard cubic foot.
dscfm = dry standard cubic feet per minute.
g = gram.
gr/dscf = grains per dry standard cubic foot.
h = hour.
kg = kilogram.
lb = pound.
m = meter.
mL = milliliter.

Table B.2-10. Metal emissions for remediation of TRU/RH solid wastes using 40 *CFR* 61 Appendix D calculation procedures for the Vitrification Alternative

Metals	Mass of metals in waste[a] (kg)	Uncontrolled metals emissions[b,c] (g)	(lbs)	Metals emissions after control[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Silver (Ag)	20	2.00E-02	4.41E-05	2.00E-08	4.41E-11	8.75E-15
Cadmium (Cd)	100	1.00E-01	2.20E-4	1.00E-07	2.20E-10	4.37E-14
Mercury (Hg)	100	1.00E-01	2.20E-04	1.00E-07	2.20E-10	4.37E-14
Lead (Pb)	980	9.80E-01	2.16E-03	9.80E-07	2.16E-09	4.29E-13
Total	1200					
	Concentration (g/dscf)[f]	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly emissions (lbs/h)
TSP	0.1296	3.92E+08	8.64E+05	3.92E+02	8.64E-01	1.71E-04

[a]Quantities are based on U.S. Department of Energy analysis and process knowledge of the Resource Conservation and Recovery Act metals in solid wastes.

[b]An emission factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emissions Factor = 0.000001 fraction of the amount used (since this is solid waste).

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Metal Mass in Waste × Emissions Factor.

The operating schedule was presented from Sect. 2.3 of this Environmental Impact Statement:

Process Operating Schedule = 1.5 years life; 210 d/year; 16 h/d; and 60 min/h

Calculated Operating Hours = 5040 h

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor	=	0.01
First HEPA Filter Adjustment Factor	=	0.01
Second HEPA Filter Adjustment Factor	=	0.01

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf (0.13 g/dscf) to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system which is based on obtaining one complete volume change of air in the hot cell every 15 min. Given that the hot cell is approximately 50 ft wide × 100 ft long × 30 ft high (due to the bay area for overhead cranes), the exhaust flowrate is 10,000 dscfm.

d = day.

dscf = dry standard cubic foot.

ft = foot.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

kg = kilogram.

lb = pound.

min = minutes.

RH = remote handled.

TRU = transuranic.

Table B.2-11. Metal emissions for remediation of TRU/CH solid wastes using 40 *CFR* Appendix D calculation procedures for the Vitrification Alternative

Metals	Mass of metals in waste[a] (kg)	Uncontrolled metals emissions[b,c] (g)	(lbs)	Metals emissions after control[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Silver (Ag)	100	1.00E-01	2.20E-04	1.00E-07	2.20E-10	3.50E-14
Cadmium (Cd)	400	4.00E-01	8.82E-04	4.00E-07	8.82E-10	1.40E-13
Mercury (Hg)	400	4.00E-01	8.82E-04	4.00E-07	8.82E-10	1.40E-13
Lead (Pb)	3500	3.50E+00	7.72E-03	3.50E-06	7.72E-09	1.22E-12
Total	1200					

	Concentration[f] (g/dscf)	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly emissions (lbs/h)
TSP	0.1296	4.90E+08	1.08E+06	4.90+02	1.08E-00	1.71E-04

[a]Quantities are based on U.S. Department of Energy analysis and process knowledge of the Resource Conservation and Recovery Act metals in solid wastes.

[b]An emission factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emissions Factor = 0.000001 fraction of the amount used (since this is solid waste).

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Metal Mass in Waste × Emissions Factor.

The operating schedule was presented from Sect. 2.3 of this Environmental Impact Statement:

Process Operating Schedule = 1.25 years life; 210 d/year; 16 h/d; and 60 min/h

Calculated Operating Hours = 4200 h

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor	=	0.01
First HEPA Filter Adjustment Factor	=	0.01
Second HEPA Filter Adjustment Factor	=	0.01

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf (0.13 g/dscf) to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system which is based on obtaining one complete volume change of air in the hot cell every 15 min. Given that the hot cell is approximately 50 ft wide × 100 ft long × 30 ft high (due to the bay area for overhead cranes), the exhaust flowrate is 10,000 dscfm.

CH = contact handled.

d = day.

dscf = dry standard cubic foot.

ft = foot.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

kg = kilogram.

lb = pound.

min = minute.

TRU = transuranic.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX B.3

SUMMARIES OF MATERIAL BALANCE FOR CEMENTATION PROCESS

THIS PAGE INTENTIONALLY LEFT BLANK

Table B.3-1. Material balance for the cementation process in the Cementation Alternative for sludge

Stream No.	Units	101[a] Sludge in MVSTs	102 Stabilization additives	103 Setting additives	104[b] Decon water	105 Treated sludge	106 To 55-gal drums	108 Pack for shipping	110 pH Adj. additive	111 Cement dust
							6507 Drums	2170 72B Casks		
					Metals					
Ag	kg	9.2			0	9.2	9.2	9.2	0	0
Al	kg	9,374.6			0	9,374.6	9,374.6	9,374.6	0	0
As	kg	20.1			0	20.1	20.1	20.1	0	0
B	kg	14.6			0	14.6	14.6	14.6	0	0
Ba	kg	109.6			0	109.6	109.6	109.6	0	0
Be	kg	2.1			0	2.1	2.1	2.1	0	0
Bi	kg	0.0			0	0.0	0.0	0.0	0	0
Ca	kg	28,197.5			0	28,197.5	28,197.5	28,197.5	0	0
Cd	kg	10.8			0	10.8	10.8	10.8	0	0
Ce	kg	0.0			0	0.0	0.0	0.0	0	0
Co	kg	4.3			0	4.3	4.3	4.3	0	0
Cr	kg	394.8			0	394.8	394.8	394.8	0	0
Cs	kg	4.6			0	4.6	4.6	4.6	0	0
Cu	kg	62.6			0	62.6	62.6	62.6	0	0
Fe	kg	5,054.3			0	5,054.3	5,054.3	5,054.3	0	0
Ga	kg	0.0			0	0.0	0.0	0.0	0	0
Hg	kg	76.8			0	76.8	76.8	76.8	0	0
I	kg	0.0			0	0.0	0.0	0.0	0	0
K	kg	7,465.9			0	7,465.9	7,465.9	7,465.9	0	0
La	kg	0.0			0	0.0	0.0	0.0	0	0
Li	kg	0.0			0	0.0	0.0	0.0	0	0
Mg	kg	4,741.1			0	4,741.1	4,741.1	4,741.1	0	0
Mn	kg	121.9			0	121.9	121.9	121.9	0	0
Mo	kg	0.0			0	0.0	0.0	0.0	0	0
Na	kg	51,354.2			0	51,354.2	51,354.2	51,354.2	0	0
Nb	kg	0.0			0	0.0	0.0	0.0	0	0
Ni	kg	74.2			0	74.2	74.2	74.2	0	0
P	kg	15,395.7			0	15,395.7	15,395.7	15,395.7	0	0
Pb	kg	540.8			0	540.8	540.8	540.8	0	0
Rb	kg	0.0			0	0.0	0.0	0.0	0	0
Sb	kg	31.9			0	31.9	31.9	31.9	0	0
Se	kg	21.9			0	21.9	21.9	21.9	0	0
Si	kg	2,659.2			0	2,659.2	2,659.2	2,659.2	0	0
Sn	kg	0.0			0	0.0	0.0	0.0	0	0
Sr	kg	103.8			0	103.8	103.8	103.8	0	0
Th	kg	6,865.1			0	6,865.1	6,865.1	6,865.1	0	0
Ti	kg	0.0			0	0.0	0.0	0.0	0	0
Tl	kg	14.1			0	14.1	14.1	14.1	0	0
U	kg	56,349.4			0	56,349.4	56,349.4	56,349.4	0	0
V	kg	3.4			0	3.4	3.4	3.4	0	0
W	kg	0.0			0	0.0	0.0	0.0	0	0
Zn	kg	155.9			0	155.9	155.9	155.9	0	0
Zr	kg	0.0			0	0.0	0.0	0.0	0	0
					Concrete additives					
IRPC	kg		85,528			81,455	81,455	81,455	0	4,073
Perlite	kg			213,819		203,637	203,637	203,637	0	10,182
Fly Ash	kg		204,316			194,587	194,587	194,587	0	9,729

Table B.3-1 (continued)

Stream No.	Units	101[a] Sludge in MVSTs	102 Stabilization additives	103 Setting additives	104[b] Decon water	105 Treated sludge	106 To 55-gal drums	108 Pack for shipping	110 pH Adj. additive	111 Cement dust
Slag	kg		353,989			337,133	337,133	337,133	0	16,857
Cement	kg		213,819			203,637	203,637	203,637	0	10,182
					Anions					
CO3-	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
Br-	kg	592.8			0	592.8	5.93E+02	5.93E+02	0	0
CO3--	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
Cl-	kg	550.7			0	550.7	5.51E+02	5.51E+02	0	0
CrO4--	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
F-	kg	1,639.3			0	1,639.3	1.64E+03	1.64E+03	0	0
OH-	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
NO3-	kg	22,816.3			0	22,816.3	2.28E+04	2.28E+04	0	0
NO2-	kg	1,767.6			0	1,767.6	1.77E+03	1.77E+03	0	0
PO4-	kg	3,185.9			0	3,185.9	3.19E+03	3.19E+03	0	0
SO4--	kg	4,465.8			0	4,465.8	4.47E+03	4.47E+03	0	0
CN-	kg	6.3			0	6.3	6.32E+00	6.32E+00	0	0
C2H3O2-	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
C6H5O7---	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
HCO2-	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
C2O4--	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
Phthlates	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
					Totals					
Carbon	kg	12,401				12,401	12,401	12,401	0	0
Metal	kg	189,234	0	0	0	189,234	189,234	189,234	0	0
Concrete	kg	0	857,652	213,819	0	1,020,449	1,020,449	1,020,449	0	51,022
Anions	kg	35,025	0	0	0	35,025	35,025	35,025	0	0
H20	kg	945,741	0	0	0	945,741	945,741	945,741	0	0
Mass	kg	1,244,450	857,652	213,819	0	2,264,899	2,190,449	2,190,449	0	51,022
SpG		1.3				1.76	1.76	1.76		
					Radioisotopic activity					
Au-198	Ci	1.17E-246	0	0	0	1.17E-246	1.17E-246	1.17E-246	0	0
Ce-144	Ci	1.52E+00	0	0	0	1.52E+00	1.52E+00	1.52E+00	0	0
Cf-252	Ci	2.47E-01	0	0	0	2.47E-01	2.47E-01	2.47E-01	0	0
Cm-243	Ci	2.83E+02	0	0	0	2.83E+02	2.83E+02	2.83E+02	0	0
Cm-244	Ci	9.11E+02	0	0	0	9.11E+02	9.11E+02	9.11E+02	0	0
Co-60	Ci	4.76E+02	0	0	0	4.76E+02	4.76E+02	4.76E+02	0	0
Cs-134	Ci	2.00E+01	0	0	0	2.00E+01	2.00E+01	2.00E+01	0	0
Cs-137	Ci	1.59E+04	0	0	0	1.59E+04	1.59E+04	1.59E+04	0	0
Eu-152	Ci	3.04E+03	0	0	0	3.04E+03	3.04E+03	3.04E+03	0	0
Eu-154	Ci	1.35E+03	0	0	0	1.35E+03	1.35E+03	1.35E+03	0	0
Eu-155	Ci	2.76E+02	0	0	0	2.76E+02	2.76E+02	2.76E+02	0	0
H-3	Ci	7.80E-01	0	0	0	7.80E-01	7.80E-01	7.80E-01	0	0
Nb-95	Ci	5.70E-18	0	0	0	5.70E-18	5.70E-18	5.70E-18	0	0
Np-237	Ci	2.46E-01	0	0	0	2.46E-01	2.46E-01	2.46E-01	0	0
Pu-238	Ci	1.87E+02	0	0	0	1.87E+02	1.87E+02	1.87E+02	0	0
Pu-239	Ci	9.59E+01	0	0	0	9.59E+01	9.59E+01	9.59E+01	0	0
Pu-240	Ci	3.00E+01	0	0	0	3.00E+01	3.00E+01	3.00E+01	0	0
Pu-241	Ci	2.53E+02	0	0	0	2.53E+02	2.53E+02	2.53E+02	0	0
Pu-242	Ci	6.48E-02	0	0	0	6.48E-02	6.48E-02	6.48E-02	0	0
Pu-244	Ci	6.01E-03	0	0	0	6.01E-03	6.01E-03	6.01E-03	0	0
Ru-106	Ci	9.27E+00	0	0	0	9.27E+00	9.27E+00	9.27E+00	0	0

Table B.3-1 (continued)

Stream No.	Units	101[a] Sludge in MVSTs	102 Stabilization additives	103 Setting additives	104[b] Decon water	105 Treated sludge	106 To 55-gal drums	108 Pack for shipping	110 pH Adj. additive	111 Cement dust
Sr-90	Ci	5.06E+04	0	0	0	5.06E+04	5.06E+04	5.06E+04	0	0
Tc-99	Ci	1.18E+01	0	0	0	1.18E+01	1.18E+01	1.18E+01	0	0
Th-232	Ci	8.18E-01	0	0	0	8.18E-01	8.18E-01	8.18E-01	0	0
U-233	Ci	6.76E+01	0	0	0	6.76E+01	6.76E+01	6.76E+01	0	0
U-234	Ci	3.01E+01	0	0	0	3.01E+01	3.01E+01	3.01E+01	0	0
U-235	Ci	7.86E-01	0	0	0	7.86E-01	7.86E-01	7.86E-01	0	0
U-236	Ci	6.55E-02	0	0	0	6.55E-02	6.55E-02	6.55E-02	0	0
U-238	Ci	2.98E+01	0	0	0	2.98E+01	2.98E+01	2.98E+01	0	0
Zr-95	Ci	2.89E-08	0	0	0	2.89E-08	2.89E-08	2.89E-08	0	0
TRU Act.	Ci	5.66E+02	0	0	0	5.66E+02	5.66E+02	5.66E+02	0	0

[a]Stream No. 101: The mass includes the remote-handled/contact-handled (RH/CH) Non-Debris Waste Stream.
[b]Stream No. 104: Decontaminated waste water would be processed with the supernate.
Ci = curie.
MVST = Melton Valley Storage Tank.
TRU = transuranic.

Table B.3-2. Material balance for the cementation process in the Cementation Alternative for supernate

Stream No.	Units	151 Supernate in MVSTs	152 Stabilization additives	153 Setting additives	154[a] Decon water	155 Treated supernate	156 To 55-gal drums	158 Pack for shipping	160 pH Adj. additive	161 Cement dust
							12,403 Drums	776 Super Tigers		
					Metals					
Ag	kg	0.3			0	0.3	0.3	0.3	0	0
Al	kg	22.5			0	22.5	22.5	22.5	0	0
As	kg	3.2			0	3.2	3.2	3.2	0	0
B	kg	2.0			0	2.0	2.0	2.0	0	0
Ba	kg	2.9			0	2.9	2.9	2.9	0	0
Be	kg	0.0			0	0.0	0.0	0.0	0	0
Bi	kg	4.3			0	4.3	4.3	4.3	0	0
Ca	kg	2,182.2			0	2,182.2	2,182.2	2,182.2	0	0
Cd	kg	0.6			0	0.6	0.6	0.6	0	0
Ce	kg	0.6			0	0.6	0.6	0.6	0	0
Co	kg	0.3			0	0.3	0.3	0.3	0	0
Cr	kg	10.9			0	10.9	10.9	10.9	0	0
Cs	kg	2.9			0	2.9	2.9	2.9	0	0
Cu	kg	1.4			0	1.4	1.4	1.4	0	0
Fe	kg	17.4			0	17.4	17.4	17.4	0	0
Ga	kg	0.5			0	0.5	0.5	0.5	0	0
Hg	kg	1.3			0	1.3	1.3	1.3	0	0
I	kg	23.7			0	23.7	23.7	23.7	0	0
K	kg	18,136.1			0	18,136.1	18,136.1	18,136.1	0	0
La	kg	0.1			0	0.1	0.1	0.1	0	0
Li	kg	42.7			0	42.7	42.7	42.7	0	0
Mg	kg	285.6			0	285.6	285.6	285.6	0	0
Mn	kg	0.5			0	0.5	0.5	0.5	0	0
Mo	kg	2.0			0	2.0	2.0	2.0	0	0
Na	kg	87,725.4			0	87,725.4	87,725.4	87,725.4	0	0
Nb	kg	0.0			0	0.0	0.0	0.0	0	0
Ni	kg	2.0			0	2.0	2.0	2.0	0	0
P	kg	111.8			0	111.8	111.8	111.8	0	0
Pb	kg	4.0			0	4.0	4.0	4.0	0	0
Rb	kg	1.9			0	1.9	1.9	1.9	0	0
Sb	kg	1.6			0	1.6	1.6	1.6	0	0
Se	kg	1.5			0	1.5	1.5	1.5	0	0
Si	kg	88.2			0	88.2	88.2	88.2	0	0
Sn	kg	0.6			0	0.6	0.6	0.6	0	0
Sr	kg	20.6			0	20.6	20.6	20.6	0	0
Th	kg	17.6			0	17.6	17.6	17.6	0	0
Ti	kg	0.8			0	0.8	0.8	0.8	0	0
Tl	kg	2.8			0	2.8	2.8	2.8	0	0
U	kg	695.6			0	695.6	695.6	695.6	0	0
V	kg	0.1			0	0.1	0.1	0.1	0	0
W	kg	0.7			0	0.7	0.7	0.7	0	0
Zn	kg	22.2			0	22.2	22.2	22.2	0	0
Zr	kg	0.0			0	0.0	0.0	0.0	0	0
					Concrete Additives					
IRPC	kg		0			0	0	0	0	0

Table B.3-2 (continued)

Stream No.	Units	151 Supernate in MVSTs	152 Stabilization additives	153 Setting additives	154[a] Decon water	155 Treated supernate	156 To 55-gal drums	158 Pack for shipping	160 pH Adj. additive	161 Cement dust
Perlite	kg			93,989		89,513	89,513	89,513	0	4,476
Fly Ash	kg		380,901			362,763	362,763	362,763	0	18,138
Slag	kg		999,247			951,664	951,664	951,664	0	47,583
Cement	kg		999,247			951,664	951,664	951,664	0	47,583
					Anions					
CO3-	kg	0.0			0	0.0	0.00E+00	0.00E+00	0	0
Br-	kg	4,806.9			0	4,806.9	4.81E+03	4.81E+03	0	0
CO3--	kg	188.3			0	188.3	1.88E+02	1.88E+02	0	0
Cl-	kg	10,059.6			0	10,059.6	1.01E+04	1.01E+04	0	0
CrO4--	kg	3,856.8			0	3,856.8	3.86E+03	3.86E+03	0	0
F-	kg	34.4			0	34.4	3.44E+01	3.44E+01	0	0
OH-	kg	514.6			0	514.6	5.15E+02	5.15E+02	0	0
NO3-	kg	4,965.1			0	4,965.1	4.97E+03	4.97E+03	0	0
NO2-	kg	298,431.9			0	298,431.9	2.98E+05	2.98E+05	0	0
PO4-	kg	4,861.4			0	4,861.4	4.86E+03	4.86E+03	0	0
SO4--	kg	2,216.5			0	2,216.5	2.22E+03	2.22E+03	0	0
CN-	kg	4,099.8			0	4,099.8	4.10E+03	4.10E+03	0	0
C2H3O2-	kg	0.1			0	0.1	1.12E-01	1.12E-01	0	0
C6H5O7---	kg	396.6			0	396.6	3.97E+02	3.97E+02	0	0
HCO2-	kg	141.9			0	141.9	1.42E+02	1.42E+02	0	0
C2O4--	kg	301.1			0	301.1	3.01E+02	3.01E+02	0	0
Phthlates	kg	389.9			0	389.9	3.90E+02	3.90E+02	0	0
					Totals					
Carbon	kg	1,478				1,478	1,478	1,478	0	0
Metal	kg	109,442	0	0	0	109,442	109,442	109,442	0	0
Concrete	kg	0	2,379,396	93,989	0	2,355,604	2,355,604	2,355,604	0	117,780
Anions	kg	335,265	0	0	0	335,265	335,265	335,265	0	0
H20	kg	1,395,293	0	0	220,000	1,615,293	1,395,293	1,395,293	0	0
Mass	kg	1,840,000	2,379,396	93,989	220,000	4,415,604	4,195,604	4,195,604	0	117,780
SpG		1.3			1	1.8	1.8	1.8		
					Radioisotopic Activity					
C-14	Ci	4.12E+00	0	0	0	4.12E+00	4.12E+00	4.12E+00	0	0
Ce-144	Ci	5.31E-01	0	0	0	5.31E-01	5.31E-01	5.31E-01	0	0
Cf-252	Ci	2.27E-02	0	0	0	2.27E-02	2.27E-02	2.27E-02	0	0
Cm-244	Ci	3.12E+01	0	0	0	3.12E+01	3.12E+01	3.12E+01	0	0
Co-60	Ci	1.82E+01	0	0	0	1.82E+01	1.82E+01	1.82E+01	0	0
Cs-134	Ci	6.58E+01	0	0	0	6.58E+01	6.58E+01	6.58E+01	0	0
Cs-137	Ci	1.05E+04	0	0	0	1.05E+04	1.05E+04	1.05E+04	0	0
Eu-152	Ci	1.31E+02	0	0	0	1.31E+02	1.31E+02	1.31E+02	0	0
Eu-154	Ci	4.68E+01	0	0	0	4.68E+01	4.68E+01	4.68E+01	0	0
Eu-155	Ci	2.09E+01	0	0	0	2.09E+01	2.09E+01	2.09E+01	0	0
H-3	Ci	5.45E+00	0	0	0	5.45E+00	5.45E+00	5.45E+00	0	0
Nb-95	Ci	1.79E-16	0	0	0	1.79E-16	1.79E-16	1.79E-16	0	0
Pu-238	Ci	1.75E-01	0	0	0	1.75E-01	1.75E-01	1.75E-01	0	0
Pu-239	Ci	1.50E-01	0	0	0	1.50E-01	1.50E-01	1.50E-01	0	0
Pu-240	Ci	1.47E-01	0	0	0	1.47E-01	1.47E-01	1.47E-01	0	0
Pu-241	Ci	2.24E+00	0	0	0	2.24E+00	2.24E+00	2.24E+00	0	0
Pu-242	Ci	7.35E-03	0	0	0	7.35E-03	7.35E-03	7.35E-03	0	0
Pu-244	Ci	8.65E-04	0	0	0	8.65E-04	8.65E-04	8.65E-04	0	0
Ru-106	Ci	2.82E+00	0	0	0	2.82E+00	2.82E+00	2.82E+00	0	0

Table B.3-2 (continued)

Stream No.	Units	151 Supernate in MVSTs	152 Stabilization additives	153 Setting additives	154[a] Decon water	155 Treated supernate	156 To 55-gal drums	158 Pack for shipping	160 pH Adj. additive	161 Cement dust
Sr-90	Ci	4.20E+02	0	0	0	4.20E+02	4.20E+02	4.20E+02	0	0
Tc-99	Ci	4.97E+01	0	0	0	4.97E+01	4.97E+01	4.97E+01	0	0
Th-232	Ci	1.73E-03	0	0	0	1.73E-03	1.73E-03	1.73E-03	0	0
U-233	Ci	6.19E+00	0	0	0	6.19E+00	6.19E+00	6.19E+00	0	0
U-234	Ci	1.25E-01	0	0	0	1.25E-01	1.25E-01	1.25E-01	0	0
U-235	Ci	5.19E-03	0	0	0	5.19E-03	5.19E-03	5.19E-03	0	0
U-236	Ci	3.03E-03	0	0	0	3.03E-03	3.03E-03	3.03E-03	0	0
U-238	Ci	1.65E-01	0	0	0	1.65E-01	1.65E-01	1.65E-01	0	0
Zr-95	Ci	5.95E-09	0	0	0	5.95E-09	5.95E-09	5.95E-09	0	0
TRU Act.	Ci	2.72E+00	0	0	0	2.72E+00	2.72E+00	2.72E+00	0	0

[a]Stream No. 154: Includes grout washings and decon. from sludge and supernate processing - assumed to be ~3 gal/drum.
Ci = curie.
kg = kilogram.
MVST = Melton Valley Storage Tank.
TRU = transuranic.

Table B.3-3. Summary of annualized radionuclide emissions for the Cementation Alternative (Ci/year)

Radionuclide	Sludge emissions	Supernate emissions	CH solids emissions	RH solids emissions	Total solids emissions	Total emissions
Ac-227	0.00E+00	0.00E+00	3.58E-18	2.78E-16	1.54E-16	1.54E-16
Ag-110	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Ag-110m	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Am-241	3.55E-08	2.97E-10	2.37E-10	1.32E-11	1.15E-10	3.59E-08
Am-243	0.00E+00	0.00E+00	4.63E-12	3.33E-17	2.11E-12	2.11E-12
Au-196	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Au-198	1.95E-254	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.95E-254
Bk-249	0.00E+00	0.00E+00	1.27E-14	5.05E-20	5.75E-15	5.75E-15
C-14	0.00E+00	7.37E-08	7.50E-17	0.00E+00	3.41E-17	7.37E-08
Ce-144	2.53E-08	9.49E-09	0.00E+00	0.00E+00	0.00E+00	3.48E-08
Cf-249	0.00E+00	0.00E+00	6.62E-15	4.93E-15	5.70E-15	5.70E-15
Cf-252	4.11E-09	4.05E-10	1.49E-12	1.61E-12	1.56E-12	4.52E-09
Cm-240	0.00E+00	0.00E+00	6.94E-43	0.00E+00	3.15E-43	3.15E-43
Cm-242	0.00E+00	0.00E+00	2.90E-11	0.00E+00	1.32E-11	1.32E-11
Cm-243	4.71E-06	0.00E+00	0.00E+00	0.00E+00	0.00E+00	4.71E-06
Cm-244	1.52E-05	5.58E-07	7.99E-10	1.18E-10	4.27E-10	1.57E-05
Cm-245	0.00E+00	0.00E+00	1.35E-15	0.00E+00	6.16E-16	6.16E-16
Cm-246	0.00E+00	0.00E+00	4.41E-18	0.00E+00	2.00E-18	2.00E-18
Cm-248	0.00E+00	0.00E+00	1.16E-14	0.00E+00	5.28E-15	5.28E-15
Co-60	7.94E-06	3.25E-07	7.24E-16	7.89E-13	4.31E-13	8.26E-06
Cs-134	3.33E-07	1.18E-06	0.00E+00	0.00E+00	0.00E+00	1.51E-06
Cs-137	2.64E-04	1.87E-04	1.14E-09	3.61E-11	5.37E-10	4.52E-04
Es-253	0.00E+00	0.00E+00	1.50E-47	0.00E+00	6.83E-48	6.83E-48
Es-254m	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Eu-152	5.07E-05	2.34E-06	2.05E-16	0.00E+00	9.30E-17	5.31E-05
Eu-154	2.25E-05	8.35E-07	0.00E+00	0.00E+00	0.00E+00	2.33E-05
Eu-155	4.60E-06	3.73E-07	0.00E+00	0.00E+00	0.00E+00	4.98E-06
Fe-59	0.00E+00	0.00E+00	1.03E-28	0.00E+00	4.67E-29	4.67E-29
Gd-153	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
H-3	1.30E-08	9.74E-08	0.00E+00	0.00E+00	0.00E+00	1.10E-07
I-129	0.00E+00	1.16E-10	0.00E+00	0.00E+00	0.00E+00	1.16E-10
I-131	0.00E+00	0.00E+00	0.00E+00	9.51E-138	5.19E-138	5.19E-138
Nb-95	9.50E-26	3.19E-24	0.00E+00	0.00E+00	0.00E+00	3.28E-24
Ni-63	0.00E+00	0.00E+00	4.68E-17	0.00E+00	2.13E-17	2.13E-17
Np-237	4.09E-09	0.00E+00	2.82E-13	6.66E-14	1.65E-13	4.10E-09
Pa-231	0.00E+00	0.00E+00	1.39E-13	0.00E+00	6.32E-14	6.32E-14
Pm-147	0.00E+00	0.00E+00	3.60E-13	0.00E+00	1.64E-13	1.64E-13
Po-209	0.00E+00	0.00E+00	8.44E-19	0.00E+00	3.84E-19	3.84E-19
Pu-238	3.11E-06	3.13E-09	1.62E-09	9.14E-12	7.40E-10	3.12E-06
Pu-239	1.60E-06	2.69E-09	4.50E-10	2.43E-12	2.06E-10	1.60E-06
Pu-240	5.01E-07	2.62E-09	4.25E-10	3.03E-18	1.93E-10	5.03E-07
Pu-241	4.22E-06	4.01E-08	9.29E-10	2.00E-12	4.24E-10	4.26E-06
Pu-242	1.08E-09	1.31E-10	1.05E-13	0.00E+00	4.80E-14	1.21E-09
Pu-244	1.00E-10	1.54E-11	0.00E+00	0.00E+00	0.00E+00	1.16E-10
Ra-223	0.00E+00	0.00E+00	2.76E-79	1.75E-103	1.25E-79	1.25E-79
Ra-226	0.00E+00	0.00E+00	7.09E-13	0.00E+00	3.22E-13	3.22E-13
Ru-106	1.54E-07	5.04E-08	0.00E+00	0.00E+00	0.00E+00	2.05E-07
Sb-125	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Sr-90	8.43E-04	7.50E-06	6.78E-10	1.29E-11	3.15E-10	8.50E-04
Tc-99	1.96E-07	8.88E-07	7.86E-12	0.00E+00	3.57E-12	1.08E-06

Table B.3-3 (continued)

Radionuclide	Sludge emissions	Supernate emissions	CH solids emissions	RH solids emissions	Total solids emissions	Total emissions
Te-123	0.00E+00	0.00E+00	1.15E-17	0.00E+00	5.22E-18	5.22E-18
Te-123m	0.00E+00	0.00E+00	3.21E-22	0.00E+00	1.46E-22	1.46E-22
Th-230	0.00E+00	0.00E+00	5.30E-18	0.00E+00	2.41E-18	2.41E-18
Th-232	1.36E-08	3.09E-11	3.49E-16	3.72E-16	3.61E-16	1.37E-08
U-232	0.00E+00	1.46E-08	1.30E-13	0.00E+00	5.92E-14	1.46E-08
U-233	1.13E-06	1.11E-07	4.46E-11	1.50E-12	2.11E-11	1.24E-06
U-234	5.01E-07	2.24E-09	7.37E-12	0.00E+00	3.35E-12	5.03E-07
U-235	1.31E-08	9.27E-11	3.15E-15	1.43E-16	1.51E-15	1.32E-08
U-236	1.09E-09	5.41E-11	4.29E-17	0.00E+00	1.95E-17	1.14E-09
U-238	4.97E-07	2.95E-09	1.92E-14	3.33E-17	8.73E-15	5.00E-07
U-239	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Y-90	0.00E+00	0.00E+00	8.55E-281	0.00E+00	3.89E-281	3.89E-281
Zn-65	0.00E+00	0.00E+00	1.35E-18	0.00E+00	6.15E-19	6.15E-19
Zr-95	4.82E-16	1.06E-16	0.00E+00	0.00E+00	0.00E+00	5.88E-16

Ci = curie.
CH = contact handled.
RH = remote handled.

Table B.3-4. Estimated radionuclide emissions for TRU waste remediation of sludge for the Cementation Alternative

Radionuclide	Radionuclide (Bq/g)	Composition[a] (Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
						Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227			2.18E+01			0.00E+00	0.00E+00
Ag-110			7.80E-07			0.00E+00	0.00E+00
Ag-110m			6.84E-01			0.00E+00	0.00E+00
Am-241[g]			4.32E+02		2.13E-03	2.13E-07	3.55E-08
Am-243			7.37E+03			0.00E+00	0.00E+00
Au-196			1.69E-02			0.00E+00	0.00E+00
Au-198	3732.39	1.01E-07	7.38E-03	1.00E-255	1.17E-249	1.17E-253	1.95E-254
Bk-249	0		8.76E-01		0.00E+00	0.00E+00	0.00E+00
C-14	0		5.73E+03		0.00E+00	0.00E+00	0.00E+00
Ce-144	10647.08	2.88E-07	7.80E-01	1.30E-09	1.52E-03	1.52E-07	2.53E-08
Cf-249	0		3.51E+02		0.00E+00	0.00E+00	0.00E+00
Cf-252	38.27	1.03E-09	2.65E+00	2.11E-10	2.47E-04	2.47E-08	4.11E-09
Cm-240	0		7.39E-02		0.00E+00	0.00E+00	0.00E+00
Cm-242	0		1.63E+02		0.00E+00	0.00E+00	0.00E+00
Cm-243	10330.07	2.79E-07	2.91E+01	2.42E-07	2.83E-01	2.83E-05	4.71E-06
Cm-244	36370.20	9.83E-07	1.81E+01	7.79E-07	9.11E-01	9.11E-05	1.52E-05
Cm-245	0		8.50E+03		0.00E+00	0.00E+00	0.00E+00
Cm-246	0		4.73E+03		0.00E+00	0.00E+00	0.00E+00
Cm-248	0		3.40E+05		0.00E+00	0.00E+00	0.00E+00
Co-60	33519.35	9.06E-07	5.27E+00	4.07E-07	4.76E-01	4.76E-05	7.94E-06
Cs-134	4893.24	1.32E-07	2.06E+00	1.71E-08	2.00E-02	2.00E-06	3.33E-07
Cs-137	577076.13	1.56E-05	3.01E+01	1.36E-05	1.59E+01	1.59E-03	2.64E-04
Es-253	0		5.60E-02		0.00E+00	0.00E+00	0.00E+00
Es-254m	0		4.48E-03		0.00E+00	0.00E+00	0.00E+00
Eu-152	131531.25	3.55E-06	1.35E+01	2.60E-06	3.04E+00	3.04E-04	5.07E-05
Eu-154	69723.86	1.88E-06	8.59E+00	1.15E-06	1.35E+00	1.35E-04	2.25E-05
Eu-155	21166.34	5.72E-07	4.76E+00	2.36E-07	2.76E-01	2.76E-05	4.60E-06
Fe-59	0		1.22E-01		0.00E+00	0.00E+00	0.00E+00
Gd-153	0		6.61E-01		0.00E+00	0.00E+00	0.00E+00
H-3	34.73	9.39E-10	1.23E+01	6.66E-10	7.80E-04	7.80E-08	1.30E-08
I-129	0		1.57E+07		0.00E+00	0.00E+00	0.00E+00
I-131	0		2.20E-02		0.00E+00	0.00E+00	0.00E+00
Nb-95	2296.02	6.21E-08	9.58E-02	4.87E-27	5.70E-21	5.70E-25	9.50E-26
Ni-63	0		1.00E+02		0.00E+00	0.00E+00	0.00E+00
Np-237	7.77	2.10E-10	2.14E+06	2.10E-10	2.46E-04	2.46E-08	4.09E-09
Pa-231	0		3.28E+04		0.00E+00	0.00E+00	0.00E+00
Pm-147	0		2.62E+00		0.00E+00	0.00E+00	0.00E+00
Po-209	0		1.02E+02		0.00E+00	0.00E+00	0.00E+00
Pu-238	6198.78	1.68E-07	8.77E+01	1.60E-07	1.87E-01	1.87E-05	3.11E-06
Pu-239	3031.95	8.19E-08	2.41E+04	8.19E-08	9.59E-02	9.59E-06	1.60E-06
Pu-240	950.28	2.57E-08	6.56E+03	2.57E-08	3.00E-02	3.00E-06	5.01E-07
Pu-241	10716.94	2.90E-07	1.44E+01	2.16E-07	2.53E-01	2.53E-05	4.22E-06
Pu-242	2.05	5.54E-11	3.73E+05	5.54E-11	6.48E-05	6.48E-09	1.08E-09
Pu-244	0.19	5.14E-12	8.00E+05	5.14E-12	6.01E-06	6.01E-10	1.00E-10
Ra-223	0		3.13E-02		0.00E+00	0.00E+00	0.00E+00
Ra-226	0		1.60E+03		0.00E+00	0.00E+00	0.00E+00
Ru-106	18256.71	4.93E-07	1.02E+00	7.92E-09	9.27E-03	9.27E-07	1.54E-07
Sb-125	0		2.76E+00		0.00E+00	0.00E+00	0.00E+00
Sr-90	1850860.69	5.00E-05	2.88E+01	4.32E-05	5.06E+01	5.06E-03	8.43E-04
Tc-99	372.46	1.01E-08	2.11E+05	1.01E-08	1.18E-02	1.18E-06	1.96E-07
Te-123	0		1.00E+08		0.00E+00	0.00E+00	0.00E+00
Te-123m	0		3.28E-01		0.00E+00	0.00E+00	0.00E+00
Th-230	0		7.54E+04		0.00E+00	0.00E+00	0.00E+00

Table B.3-4 (continued)

Radionuclide	Radionuclide (Bq/g)	Composition[a] (Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
						Project life[e] (Ci)	Annualized[f] (Ci/year)
Th-232	25.88	6.99E-10	1.41E+10	6.99E-10	8.18E-04	8.18E-08	1.36E-08
U-232	0		6.89E+01		0.00E+00	0.00E+00	0.00E+00
U-233	2136.82	5.78E-08	1.59E+05	5.78E-08	6.76E-02	6.76E-06	1.13E-06
U-234	950.46	2.57E-08	2.46E+05	2.57E-08	3.01E-02	3.01E-06	5.01E-07
U-235	24.86	6.72E-10	3.80E+06	6.72E-10	7.86E-04	7.86E-08	1.31E-08
U-236	2.07	5.59E-11	2.34E+07	5.59E-11	6.55E-05	6.55E-09	1.09E-09
U-238	943.56	2.55E-08	4.47E+09	2.55E-08	2.98E-02	2.98E-06	4.97E-07
U-239	0		4.46E-05		0.00E+00	0.00E+00	0.00E+00
Y-90	0		7.31E-03		0.00E+00	0.00E+00	0.00E+00
Zn-65	0		6.69E-01		0.00E+00	0.00E+00	0.00E+00
Zr-95	26302.35	7.11E-07	1.75E-01	2.47E-17	2.89E-11	2.89E-15	4.82E-16

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document No. ORNL/TM-13351.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp -[\ln(2)/ t_{1/2} * T] ,$$

where:

A = the decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the web site www.dne.bnl.gov/CoN_index.html;

T = the time between sample analysis (December 1996) to the time of process startup (January 2003), which is 6.08 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61:

Emissions Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Cementation High-Efficiency Particulate Air (HEPA)
Filters System 1 Adjustment Factor = 0.01
Cementation HEPA Filters System 2 Adjustment Factor = 0.01

[f]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the remote-handled (RH) sludges will be processed (6 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Bq = becquerel.

Ci = curie.

g = gram.

TRU = transuranic.

Table B.3-5. Estimated radionuclide emissions for waste remediation of supernate for the Cementation Alternative

Radionuclide	Radionuclide composition[a] (Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227		2.18E+01			0.00E+00	0.00E+00
Ag-110		7.80E-07			0.00E+00	0.00E+00
Ag-110m		6.84E-01			0.00E+00	0.00E+00
Am-241[g]		4.32E+02		1.66E-05	1.66E-09	2.97E-10
Am-243		7.37E+03			0.00E+00	0.00E+00
Au-196		1.69E-02			0.00E+00	0.00E+00
Au-198		7.38E-03		0.00E+00	0.00E+00	0.00E+00
Bk-249		8.76E-01		0.00E+00	0.00E+00	0.00E+00
C-14	2.24E-09	5.73E+03	2.24E-09	4.12E-03	4.12E-07	7.37E-08
Ce-144	3.07E-08	7.80E-01	2.89E-10	5.31E-04	5.31E-08	9.49E-09
Cf-249		3.51E+02		0.00E+00	0.00E+00	0.00E+00
Cf-252	4.86E-11	2.65E+00	1.23E-11	2.27E-05	2.27E-09	4.05E-10
Cm-240		7.39E-02		0.00E+00	0.00E+00	0.00E+00
Cm-242		1.63E+02		0.00E+00	0.00E+00	0.00E+00
Cm-243		2.91E+01		0.00E+00	0.00E+00	0.00E+00
Cm-244	2.08E-08	1.81E+01	1.70E-08	3.12E-02	3.12E-06	5.58E-07
Cm-245		8.50E+03		0.00E+00	0.00E+00	0.00E+00
Cm-246		4.73E+03		0.00E+00	0.00E+00	0.00E+00
Cm-248		3.40E+05		0.00E+00	0.00E+00	0.00E+00
Co-60	1.97E-08	5.27E+00	9.88E-09	1.82E-02	1.82E-06	3.25E-07
Cs-134	2.09E-07	2.06E+00	3.58E-08	6.58E-02	6.58E-06	1.18E-06
Cs-137	6.44E-06	3.01E+01	5.71E-06	1.05E+01	1.05E-03	1.87E-04
Es-253		5.60E-02		0.00E+00	0.00E+00	0.00E+00
Es-254m		4.48E-03		0.00E+00	0.00E+00	0.00E+00
Eu-152	9.31E-08	1.35E+01	7.11E-08	1.31E-01	1.31E-05	2.34E-06
Eu-154	3.88E-08	8.59E+00	2.54E-08	4.68E-02	4.68E-06	8.35E-07
Eu-155	2.44E-08	4.76E+00	1.14E-08	2.09E-02	2.09E-06	3.73E-07
Fe-59		1.22E-01		0.00E+00	0.00E+00	0.00E+00
Gd-153		6.61E-01		0.00E+00	0.00E+00	0.00E+00
H-3	3.98E-09	1.23E+01	2.96E-09	5.45E-03	5.45E-07	9.74E-08
I-129	3.53E-12	1.57E+07	3.53E-12	6.49E-06	6.49E-10	1.16E-10
I-131		2.20E-02		0.00E+00	0.00E+00	0.00E+00
Nb-95	3.05E-09	9.58E-02	9.71E-26	1.79E-19	1.79E-23	3.19E-24
Ni-63		1.00E+02		0.00E+00	0.00E+00	0.00E+00
Np-237		2.14E+06		0.00E+00	0.00E+00	0.00E+00
Pa-231		3.28E+04		0.00E+00	0.00E+00	0.00E+00
Pm-147		2.62E+00		0.00E+00	0.00E+00	0.00E+00
Po-209		1.02E+02		0.00E+00	0.00E+00	0.00E+00
Pu-238	9.92E-11	8.77E+01	9.51E-11	1.75E-04	1.75E-08	3.13E-09
Pu-239	8.18E-11	2.41E+04	8.18E-11	1.50E-04	1.50E-08	2.69E-09
Pu-240	7.97E-11	6.56E+03	7.96E-11	1.47E-04	1.47E-08	2.62E-09
Pu-241	1.57E-09	1.44E+01	1.22E-09	2.24E-03	2.24E-07	4.01E-08
Pu-242	4.00E-12	3.73E+05	4.00E-12	7.35E-06	7.35E-10	1.31E-10
Pu-244	4.70E-13	8.00E+05	4.70E-13	8.65E-07	8.65E-11	1.54E-11
Ra-223		3.13E-02		0.00E+00	0.00E+00	0.00E+00
Ra-226		1.60E+03		0.00E+00	0.00E+00	0.00E+00
Ru-106	5.44E-08	1.02E+00	1.53E-09	2.82E-03	2.82E-07	5.04E-08

Table B.3-5 (continued)

Radionuclide	Radionuclide composition[a] (Ci/g)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci/g)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Sb-125		2.76E+00		0.00E+00	0.00E+00	0.00E+00
Sr-90	2.59E-07	2.88E+01	2.28E-07	4.20E-01	4.20E-05	7.50E-06
Tc-99	2.70E-08	2.11E+05	2.70E-08	4.97E-02	4.97E-06	8.88E-07
Te-123		1.00E+08		0.00E+00	0.00E+00	0.00E+00
Te-123m		3.28E-01		0.00E+00	0.00E+00	0.00E+00
Th-230		7.54E+04		0.00E+00	0.00E+00	0.00E+00
Th-232	9.40E-13	1.41E+10	9.40E-13	1.73E-06	1.73E-10	3.09E-11
U-232	4.70E-10	6.89E+01	4.46E-10	8.20E-04	8.20E-08	1.46E-08
U-233	3.36E-09	1.59E+05	3.36E-09	6.19E-03	6.19E-07	1.11E-07
U-234	6.82E-11	2.46E+05	6.82E-11	1.25E-04	1.25E-08	2.24E-09
U-235	2.82E-12	3.80E+06	2.82E-12	5.19E-06	5.19E-10	9.27E-11
U-236	1.65E-12	2.34E+07	1.65E-12	3.03E-06	3.03E-10	5.41E-11
U-238	8.98E-11	4.47E+09	8.98E-11	1.65E-04	1.65E-08	2.95E-09
U-239		4.46E-05		0.00E+00	0.00E+00	0.00E+00
Y-90		7.31E-03		0.00E+00	0.00E+00	0.00E+00
Zn-65		6.69E-01		0.00E+00	0.00E+00	0.00E+00
Zr-95	3.47E-09	1.75E-01	3.23E-18	5.95E-12	5.95E-16	1.06E-16

[a]Composition data obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-Level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document No. ORNL/TM-13351, Addendum 1.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp -[\ln(2)/ t_{1/2} * T] ,$$

where:

A = the decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the web site www.dne.bnl.gov/CoN/index.html,

T = the time between sample analysis (October 1997) to the time of process startup (January 2003), which is 5.25 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CRF)* 61:

Emissions Factor = 0.001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Cementation High-Efficiency Particulate Air (HEPA) Filters System 1 Adjustment Factor = 0.01

Cementation HEPA Filters System 2 Adjustment Factor = 0.01

[f]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the remote-handled (RH) sludges will be processed (6 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Ci = curie.

g = gram.

Table B.3-6. Estimated radionuclide emissions TRU waste remediation of CH solids for the Cementation Alternative

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	1.10E-05	2.18E+01	8.95E-06	8.95E-12	8.95E-18	3.58E-18
Ag-110		7.80E-07				
Ag-110m		6.84E-01				
Am-241[g]	5.77E+02	4.32E+02	5.92E+02	5.92E-04	5.92E-10	2.37E-10
Am-243	1.16E+01	7.37E+03	1.16E+01	1.16E-05	1.16E-11	4.63E-12
Au-196		1.69E-02				
Au-198		7.38E-03				
Bk-249	5.77E+00	8.76E-01	3.16E-02	3.16E-08	3.16E-14	1.27E-14
C-14	1.88E-04	5.73E+03	1.87E-04	1.87E-10	1.87E-16	7.50E-17
Ce-144		7.80E-01				
Cf-249	1.68E-02	3.51E+02	1.66E-02	1.66E-08	1.66E-14	6.62E-15
Cf-252	2.09E+01	2.65E+00	3.73E+00	3.73E-06	3.73E-12	1.49E-12
Cm-240	1.10E-03	7.39E-02	1.73E-30	1.73E-36	1.73E-42	6.94E-43
Cm-242	7.46E+01	1.63E+02	7.25E+01	7.25E-05	7.25E-11	2.90E-11
Cm-243		2.91E+01				
Cm-244	2.57E+03	1.81E+01	2.00E+03	2.00E-03	2.00E-09	7.99E-10
Cm-245	3.39E-03	8.50E+03	3.39E-03	3.39E-09	3.39E-15	1.35E-15
Cm-246	1.10E-05	4.73E+03	1.10E-05	1.10E-11	1.10E-17	4.41E-18
Cm-248	2.90E-02	3.40E+05	2.90E-02	2.90E-08	2.90E-14	1.16E-14
Co-60	4.30E-03	5.27E+00	1.81E-03	1.81E-09	1.81E-15	7.24E-16
Cs-134		2.06E+00				
Cs-137	3.31E+03	3.01E+01	2.84E+03	2.84E-03	2.84E-09	1.14E-09
Es-253	8.83E+00	5.60E-02	3.76E-35	3.76E-41	3.76E-47	1.50E-47
Es-254m	1.20E+01	4.48E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Eu-152	7.17E-04	1.35E+01	5.12E-04	5.12E-10	5.12E-16	2.05E-16
Eu-154		8.59E+00	0.00E+00			
Eu-155		4.76E+00				
Fe-59	4.42E+00	1.22E-01	2.57E-16	2.57E-22	2.57E-28	1.03E-28
Gd-153		6.61E-01				
H-3		1.23E+01				
I-129		1.57E+07				
I-131		2.20E-02				
Nb-95		9.58E-02				
Ni-63	1.22E-04	1.00E+02	1.17E-04	1.17E-10	1.17E-16	4.68E-17
Np-237	7.06E-01	2.14E+06	7.06E-01	7.06E-07	7.06E-13	2.82E-13
Pa-231	3.48E-01	3.28E+04	3.48E-01	3.48E-07	3.48E-13	1.39E-13
Pm-147	5.13E+00	2.62E+00	9.00E-01	9.00E-07	9.00E-13	3.60E-13
Po-209	2.21E-06	1.02E+02	2.11E-06	2.11E-12	2.11E-18	8.44E-19
Pu-238	4.26E+03	8.77E+01	4.04E+03	4.04E-03	4.04E-09	1.62E-09
Pu-239	1.13E+03	2.41E+04	1.13E+03	1.13E-03	1.13E-09	4.50E-10
Pu-240	1.06E+03	6.56E+03	1.06E+03	1.06E-03	1.06E-09	4.25E-10
Pu-241	3.19E+03	1.44E+01	2.32E+03	2.32E-03	2.32E-09	9.29E-10
Pu-242	2.64E-01	3.73E+05	2.64E-01	2.64E-07	2.64E-13	1.05E-13
Pu-244		8.00E+05				
Ra-223	1.32E-03	3.13E-02	6.89E-67	6.89E-73	6.89E-79	2.76E-79
Ra-226	1.78E+00	1.60E+03	1.77E+00	1.77E-06	1.77E-12	7.09E-13
Ru-106		1.02E+00				

Table B.3-6 (continued)

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Sb-125		2.76E+00				
Sr-90	1.99E+03	2.88E+01	1.70E+03	1.70E-03	1.70E-09	6.78E-10
Tc-99	1.96E+01	2.11E+05	1.96E+01	1.96E-05	1.96E-11	7.86E-12
Te-123	2.87E-05	1.00E+08	2.87E-05	2.87E-11	2.87E-17	1.15E-17
Te-123m	8.77E-04	3.28E-01	8.02E-10	8.02E-16	8.02E-22	3.21E-22
Th-230	1.32E-05	7.54E+04	1.32E-05	1.32E-11	1.32E-17	5.30E-18
Th-232	8.73E-04	1.41E+10	8.73E-04	8.73E-10	8.73E-16	3.49E-16
U-232	3.48E-01	6.89E+01	3.25E-01	3.25E-07	3.25E-13	1.30E-13
U-233	1.11E+02	1.59E+05	1.11E+02	1.11E-04	1.11E-10	4.46E-11
U-234	1.84E+01	2.46E+05	1.84E+01	1.84E-05	1.84E-11	7.37E-12
U-235	7.87E-03	3.80E+06	7.87E-03	7.87E-09	7.87E-15	3.15E-15
U-236	1.07E-04	2.34E+07	1.07E-04	1.07E-10	1.07E-16	4.29E-17
U-238	4.79E-02	4.47E+09	4.79E-02	4.79E-08	4.79E-14	1.92E-14
U-239		4.46E-05				
Y-90	1.99E+03	7.31E-03	2.14E-268	2.14E-274	2.14E-280	8.55E-281
Zn-65	3.09E-03	6.69E-01	3.38E-06	3.38E-12	3.38E-18	1.35E-18
Zr-95		1.75E-01				
TRU Activity	7.06E+03		6.84E+03	6.84E-03	6.84E-09	2.74E-09

[a]Composition data obtained from U.S. Department of Energy Memorandum, "TRU Waste Baseline Inventory Report for Oak Ridge," June 1996. The data were then scaled up from 906.22 m^3 to 1000 m^3.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp -[\ln(2)/ t_{1/2} * T] ,$$

where:

A = the decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the web site www.dne.bnl.gov/CoN/index.html;

T = the time between sample analysis (June 1996) to the time remote-handled (RH) processing begins (January 2003), which is 6.58 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CRF)* 61:

0.000001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Glovebox/Hot Cell High-Efficiency Particulate Air (HEPA) Filters Adjustment Factor	= 0.01
Glovebox/Hot Cell HEPA Filters Adjustment Factor	= 0.10
Primary HEPA Filters Adjustment Factor	= 0.01
Secondary HEPA Filters Adjustment Factor	= 0.01

[f]The annualized emissions are calculated by taken the controlled emissions from the project life and dividing by the length of time (in years) the contact-handled (CH) solids will be processed (2.5 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Ci = curie.

TRU = transuranic.

Table B.3-7. Estimated radionuclide emissions for waste remediation of RH solids for the Cementation Alternative

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control	
					Project life[e] (Ci)	Annualized[f] (Ci/year)
Ac-227	1.12E-03	2.18E+01	8.35E-04	8.35E-10	8.35E-16	2.78E-16
Ag-110		7.80E-07			0.00E+00	0.00E+00
Ag-110m		6.84E-01			0.00E+00	0.00E+00
Am-241[g]	4.02E+01	4.32E+02	3.96E+01	3.96E-05	3.96E-11	1.32E-11
Am-243	9.99E-05	7.37E+03	9.98E-05	9.98E-11	9.98E-17	3.33E-17
Au-196		1.69E-02			0.00E+00	0.00E+00
Au-198		7.38E-03			0.00E+00	0.00E+00
Bk-249	2.00E-04	8.76E-01	1.52E-07	1.52E-13	1.52E-19	5.05E-20
C-14		5.73E+03			0.00E+00	0.00E+00
Ce-144		7.80E-01			0.00E+00	0.00E+00
Cf-249	1.51E-02	3.51E+02	1.48E-02	1.48E-08	1.48E-14	4.93E-15
Cf-252	5.20E+01	2.65E+00	4.84E+00	4.84E-06	4.84E-12	1.61E-12
Cm-240		7.39E-02			0.00E+00	0.00E+00
Cm-242		1.63E+02			0.00E+00	0.00E+00
Cm-243		2.91E+01			0.00E+00	0.00E+00
Cm-244	4.99E+02	1.81E+01	3.53E+02	3.53E-04	3.53E-10	1.18E-10
Cm-245		8.50E+03			0.00E+00	0.00E+00
Cm-246		4.73E+03			0.00E+00	0.00E+00
Cm-248		3.40E+05			0.00E+00	0.00E+00
Co-60	7.81E+00	5.27E+00	2.37E+00	2.37E-06	2.37E-12	7.89E-13
Cs-134		2.06E+00			0.00E+00	0.00E+00
Cs-137	1.33E+02	3.01E+01	1.08E+02	1.08E-04	1.08E-10	3.61E-11
Es-253		5.60E-02			0.00E+00	0.00E+00
Es-254m		4.48E-03			0.00E+00	0.00E+00
Eu-152		1.35E+01			0.00E+00	0.00E+00
Eu-154		8.59E+00			0.00E+00	0.00E+00
Eu-155		4.76E+00			0.00E+00	0.00E+00
Fe-59		1.22E-01			0.00E+00	0.00E+00
Gd-153		6.61E-01			0.00E+00	0.00E+00
H-3		1.23E+01			0.00E+00	0.00E+00
I-129		1.57E+07			0.00E+00	0.00E+00
I-131	5.00E-01	2.20E-02	2.85E-125	2.85E-131	2.85E-137	9.51E-138
Nb-95		9.58E-02			0.00E+00	0.00E+00
Ni-63		1.00E+02			0.00E+00	0.00E+00
Np-237	2.00E-01	2.14E+06	2.00E-01	2.00E-07	2.00E-13	6.66E-14
Pa-231		3.28E+04			0.00E+00	0.00E+00
Pm-147		2.62E+00			0.00E+00	0.00E+00
Po-209		1.02E+02			0.00E+00	0.00E+00
Pu-238	2.94E+01	8.77E+01	2.74E+01	2.74E-05	2.74E-11	9.14E-12
Pu-239	7.31E+00	2.41E+04	7.30E+00	7.30E-06	7.30E-12	2.43E-12
Pu-240	9.08E-06	6.56E+03	9.08E-06	9.08E-12	9.08E-18	3.03E-18
Pu-241	9.27E+00	1.44E+01	5.99E+00	5.99E-06	5.99E-12	2.00E-12
Pu-242		3.73E+05			0.00E+00	0.00E+00
Pu-244		8.00E+05			0.00E+00	0.00E+00
Ra-223	1.12E-03	3.13E-02	5.25E-91	5.25E-97	5.25E-103	1.75E-103
Ra-226		1.60E+03			0.00E+00	0.00E+00
Ru-106		1.02E+00			0.00E+00	0.00E+00

Table B.3-7 (continued)

Radionuclide	Radionuclide composition[a] (Ci)	Radionuclide[b] half life, $t_{1/2}$ (year)	Decayed radionuclide composition (Ci)	Uncontrolled[c,d] radionuclide emissions (Ci)	Radionuclide emissions after control Project life[e] (Ci)	Annualized[f] (Ci/year)
Sb-125		2.76E+00			0.00E+00	0.00E+00
Sr-90	4.83E+01	2.88E+01	3.88E+01	3.88E-05	3.88E-11	1.29E-11
Tc-99		2.11E+05			0.00E+00	0.00E+00
Te-123		1.00E+08			0.00E+00	0.00E+00
Te-123m		3.28E-01			0.00E+00	0.00E+00
Th-230		7.54E+04			0.00E+00	0.00E+00
Th-232	1.12E-03	1.41E+10	1.12E-03	1.12E-09	1.12E-15	3.72E-16
U-232		6.89E+01			0.00E+00	0.00E+00
U-233	4.51E+00	1.59E+05	4.51E+00	4.51E-06	4.51E-12	1.50E-12
U-234		2.46E+05			0.00E+00	0.00E+00
U-235	4.30E-04	3.80E+06	4.30E-04	4.30E-10	4.30E-16	1.43E-16
U-236		2.34E+07			0.00E+00	0.00E+00
U-238	9.99E-05	4.47E+09	9.99E-05	9.99E-11	9.99E-17	3.33E-17
U-239		4.46E-05			0.00E+00	0.00E+00
Y-90	4.83E+01	7.31E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Zn-65		6.69E-01			0.00E+00	0.00E+00
Zr-95		1.75E-01			0.00E+00	0.00E+00

[a]Composition data obtained from U.S. Department of Energy Memorandum, "TRU Waste Baseline Inventory Report for Oak Ridge," June 1996.

[b]The equation for estimating radionuclide decay is:

$$A = Ao \times \exp -[\ln(2)/ t_{1/2} * T],$$

where:

A = the decayed radionuclide composition;

Ao = the original concentration in Ci/g;

$t_{1/2}$ = the half-life of the specific radionuclide as obtained from the web site www.dne.bnl.gov/CoN/index.html.

T = the time between sample analysis (June 1996) to the time remote-handled (RH) processing begins (July 2005), which is 9.08 years.

[c]An emissions factor for the amount of airborne radionuclides is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61:

Emissions Factor = 0.000001 fraction of the amount used.

[d]The uncontrolled emissions are estimated by the following equation:

Uncontrolled Rate = Retrievable Curies × Emissions Factor.

[e]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Glovebox/Hot Cell High-Efficiency Particulate Air (HEPA) Filters Adjustment Factor	= 0.01
Glovebox/Hot Cell HEPA Filters Adjustment Factor	= 0.10
Primary HEPA Filters Adjustment Factor	= 0.01
Secondary HEPA Filters Adjustment Factor	= 0.01

[f]The annualized emissions are calculated by taking the controlled emissions from the project life and dividing by the length of time (in years) the RH solids will be processed (1.5 years).

[g]Emissions of ^{241}Am were calculated based on decay of the radionuclide composition and as a decay product of ^{241}Pu.

Ci = curie.

Table B.3-8. Summary of TRU waste remediation hourly particulate emissions (lb/h) for the Cementation Alternative

		Average hourly emissions (lbs/h)								
Metals	Class.	Sludge	Supernate	Sludge and supernate	CH solids	RH solids	CH/RH solids	Total	Maximum hourly emissions[a] (lbs/h)	Average annual emissions[b] (tons/year)
TSP		4.29E-03	4.29E-03	4.29E-03	1.71E-04	1.71E-04	1.71E-04	4.29E-03	5.37E-03	3.31E-03
Total HAP		4.76E-06	6.04E-08	1.75E-06	2.26E-12	5.16E-13	1.31E-12	4.57E-06	5.72E-06	1.29E-06
Silver (Ag)		3.38E-08	7.45E-10	1.26E-08	5.25E-14	8.75E-15	2.86E-14	3.25E-08	4.06E-08	9.34E-09
Aluminum (Al)		3.43E-05	5.25E-08	1.24E-05				3.30E-05	4.13E-05	9.16E-06
Arsenic (As)	HAP	7.36E-08	7.49E-09	3.13E-08				7.08E-08	8.84E-08	2.31E-08
Boron (B)		5.36E-08	4.70E-09	2.23E-08				5.15E-08	6.44E-08	1.65E-08
Barium (Ba)		4.01E-07	6.82E-09	1.49E-07				3.86E-07	4.82E-07	1.10E-07
Beryllium (Be)	HAP	7.84E-09	3.73E-11	2.84E-09				7.54E-09	9.42E-09	2.10E-09
Bismuth (Bi)		0.00E+00	1.01E-08	6.45E-09				0.00E+00	0.00E+00	4.77E-09
Calcium (Ca)		1.03E-04	5.08E-06	4.04E-05				9.93E-05	1.24E-04	2.99E-05
Cadmium (Cd)	HAP	3.94E-08	1.45E-09	1.51E-08	2.10E-13	4.37E-14	1.19E-13	3.79E-08	4.74E-08	1.12E-08
Cerium (Ce)		0.00E+00	1.38E-09	8.83E-10				0.00E+00	0.00E+00	6.54E-10
Cobalt (Co)	HAP	1.56E-08	5.96E-10	5.99E-09				1.50E-08	1.87E-08	4.43E-09
Chromium (Cr)	HAP	1.45E-06	2.54E-08	5.36E-07				1.39E-06	1.74E-06	3.97E-07
Cesium (Cs)		1.70E-08	6.71E-09	1.04E-08				1.63E-08	2.04E-08	7.69E-09
Copper (Cu)		2.29E-07	3.20E-09	8.45E-08				2.20E-07	2.75E-07	6.25E-08
Iron (Fe)		1.85E-05	4.06E-08	6.68E-06				1.78E-05	2.22E-05	4.94E-06
Gallium (Ga)		0.00E+00	1.23E-09	7.88E-10				0.00E+00	0.00E+00	5.83E-10
Mercury (Hg)	HAP	2.81E-07	2.94E-09	1.03E-07	2.10E-13	4.37E-14	1.19E-13	2.70E-07	3.38E-07	7.62E-08
Iodine (I)		0.00E+00	5.51E-08	3.53E-08				0.00E+00	0.00E+00	2.61E-08
Potassium (K)		2.73E-05	4.22E-05	3.69E-05				2.63E-05	3.29E-05	2.73E-05
Lanthanum (La)		0.00E+00	1.49E-10	9.55E-11				0.00E+00	0.00E+00	7.07E-11
Lithium (Li)		0.00E+00	9.95E-08	6.37E-08				0.00E+00	0.00E+00	4.71E-08
Magnesium (Mg)		1.74E-05	6.65E-07	6.67E-06				1.67E-05	2.09E-05	4.93E-06
Manganese (Mn)	HAP	4.46E-07	1.23E-09	1.61E-07				4.29E-07	5.36E-07	1.19E-07
Molybdenum (Mo)		0.00E+00	4.62E-09	2.96E-09				0.00E+00	0.00E+00	2.19E-09
Sodium (Na)		1.88E-04	2.04E-04	1.98E-04				1.81E-04	2.26E-04	1.47E-04
Niobium (Nb)		0.00E+00	0.00E+00	0.00E+00				0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	HAP	2.72E-07	4.58E-09	1.01E-07				2.61E-07	3.27E-07	7.45E-08
Phosphorus (P)		5.64E-05	2.60E-07	2.04E-05				5.42E-05	6.77E-05	1.51E-05
Lead (Pb)	HAP	1.98E-06	9.43E-09	7.18E-07	1.84E-12	4.29E-13	1.07E-12	1.90E-06	2.38E-06	5.31E-07
Rubidium (Rb)		0.00E+00	4.40E-09	2.82E-09				0.00E+00	0.00E+00	2.08E-09
Antimony (Sb)	HAP	1.17E-07	3.69E-09	4.44E-08				1.12E-07	1.41E-07	3.29E-08
Selenium (Se)	HAP	8.03E-08	3.50E-09	3.11E-08				7.71E-08	9.64E-08	2.30E-08
Silicon (Si)		9.74E-06	2.05E-07	3.63E-06				9.36E-06	1.17E-05	2.69E-06
Tin (Sn)		0.00E+00	1.42E-09	9.07E-10				0.00E+00	0.00E+00	6.71E-10
Strontium (Sr)		3.80E-07	4.80E-08	1.67E-07				3.66E-07	4.57E-07	1.24E-07
Thorium (Th)		2.51E-05	4.10E-08	9.07E-06				2.42E-05	3.02E-05	6.71E-06
Titanium (Ti)		0.00E+00	1.90E-09	1.22E-09				0.00E+00	0.00E+00	9.01E-10
Thallium (Th)		5.16E-08	6.60E-09	2.28E-08				4.96E-08	6.20E-08	1.69E-08
Uranium (U)		2.06E-04	1.62E-06	7.52E-05				1.98E-04	2.48E-04	5.57E-05
Vanadium (V)		1.23E-08	3.35E-10	4.65E-09				1.19E-08	1.48E-08	3.44E-09
Tungsten (W)		0.00E+00	1.71E-09	1.10E-09				0.00E+00	0.00E+00	8.13E-10
Zinc (Zn)		5.71E-07	5.18E-08	2.38E-07				5.49E-07	6.86E-07	1.76E-07
Zirconium (Zr)		0.00E+00	1.12E-10	7.16E-11				0.00E+00	0.00E+00	5.30E-11

[a]Maximum hourly is estimated by multiplying the average hourly rate by 1.25.
[b]Average annual emissions are the average hourly emissions multiplied by the operational hours and then divided by 6 years.
h = hour. HAP = hazardous air pollutant. lb = pound. TRU = transuranic. TSP = total suspended particulate.

Table B.3-9. Estimated metals emissions for remediation of the TRU sludge for the Cementation Alternative

Metals	Metals[a] mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
TSP		1.30E-01	6.21E+07	1.37E+05	6.21E+03	1.37E+01	4.29E-03
Silver (Ag)	7.88E-06	1.02E-06	4.89E+02	1.08E+00	4.89E-02	1.08E-04	3.38E-08
Aluminum (Al)	8.01E-03	1.04E-03	4.97E+05	1.10E+03	4.97E+01	1.10E-01	3.43E-05
Arsenic (As)	1.72E-05	2.23E-06	1.07E+03	2.35E+00	1.07E-01	2.35E-04	7.36E-08
Boron (B)	1.25E-05	1.62E-06	7.76E+02	1.71E+00	7.76E-02	1.71E-04	5.36E-08
Barium (Ba)	9.37E-05	1.21E-05	5.81E+03	1.28E+01	5.81E-01	1.28E-03	4.01E-07
Beryllium (Be)	1.83E-06	2.37E-07	1.14E+02	2.50E-01	1.14E-02	2.50E-05	7.84E-09
Bismuth (Bi)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Calcium (Ca)	2.41E-02	3.12E-03	1.50E+06	3.30E+03	1.50E+02	3.30E-01	1.03E-04
Cadmium (Cd)	9.20E-06	1.19E-06	5.71E+02	1.26E+00	5.71E-02	1.26E-04	3.94E-08
Cerium (Ce)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Cobalt (Co)	3.64E-06	4.72E-07	2.26E+02	4.98E-01	2.26E-02	4.98E-05	1.56E-08
Chromium (Cr)	3.37E-04	4.37E-05	2.09E+04	4.62E+01	2.09E+00	4.62E-03	1.45E-06
Cesium (Cs)	3.96E-06	5.13E-07	2.46E+02	5.42E-01	2.46E-02	5.42E-05	1.70E-08
Copper (Cu)	5.35E-05	6.93E-06	3.32E+03	7.32E+00	3.32E-01	7.32E-04	2.29E-07
Iron (Fe)	4.32E-03	5.60E-04	2.68E+05	5.91E+02	2.68E+01	5.91E-02	1.85E-05
Gallium (Ga)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Mercury (Hg)	6.56E-05	8.50E-06	4.07E+03	8.98E+00	4.07E-01	8.98E-04	2.81E-07
Iodine (I)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Potassium (K)	6.38E-03	8.27E-04	3.96E+05	8.73E+02	3.96E+01	8.73E-02	2.73E-05
Lanthanum (La)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Lithium (Li)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Magnesium (Mg)	4.05E-03	5.25E-04	2.51E+05	5.54E+02	2.51E+01	5.54E-02	1.74E-05
Manganese (Mn)	1.04E-04	1.35E-05	6.46E+03	1.42E+01	6.46E-01	1.42E-03	4.46E-07
Molybdenum (Mo)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Sodium (Na)	4.39E-02	5.69E-03	2.72E+06	6.00E+03	2.72E+02	6.00E-01	1.88E-04
Niobium (Nb)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	6.34E-05	8.22E-06	3.94E+03	8.68E+00	3.94E-01	8.68E-04	2.72E-07
Phosphorus (P)	1.32E-02	1.71E-03	8.17E+05	1.80E+03	8.17E+01	1.80E-01	5.64E-05
Lead (Pb)	4.62E-04	5.99E-05	2.87E+04	6.32E+01	2.87E+00	6.32E-03	1.98E-06
Rubidium (Rb)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Antimony (Sb)	2.73E-05	3.54E-06	1.69E+03	3.73E+00	1.69E-01	3.73E-04	1.17E-07
Selenium (Se)	1.87E-05	2.43E-06	1.16E+03	2.56E+00	1.16E-01	2.56E-04	8.03E-08
Silicon (Si)	2.27E-03	2.95E-04	1.41E+05	3.11E+02	1.41E+01	3.11E-02	9.74E-06
Tin (Sn)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Strontium (Sr)	8.88E-05	1.15E-05	5.51E+03	1.21E+01	5.51E-01	1.21E-03	3.80E-07
Thorium (Th)	5.87E-03	7.60E-04	3.64E+05	8.03E+02	3.64E+01	8.03E-02	2.51E-05
Titanium (Ti)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Thallium (Th)	1.21E-05	1.56E-06	7.48E+02	1.65E+00	7.48E-02	1.65E-04	5.16E-08
Uranium (U)	4.82E-02	6.24E-03	2.99E+06	6.59E+03	2.99E+02	6.59E-01	2.06E-04
Vanadium (V)	2.88E-06	3.73E-07	1.79E+02	3.94E-01	1.79E-02	3.94E-05	1.23E-08
Tungsten (W)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

Table B.3-9 (continued)

Metals	Metals[a] mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Zinc (Zn)	1.33E-04	1.73E-05	8.27E+03	1.82E+01	8.27E-01	1.82E-03	5.71E-07
Zirconium (Zr)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

[a]The data were obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document No. ORNL/TM-13351. An average density of 1.3 g/mL was used for the sludge. Given the volume stated in the request for proposal of 900 m^3 of sludge, there is 1,170,000 kg of sludge mass.

[b]The amount of total suspended particulate (TSP) matter reaching the first exhaust system High-Efficiency Particulate Air (HEPA) filter is assumed to be:

Airborne Particulate Concentration = 1.0 gr/dscf = 0.1296 g/dscf.

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Exhaust Stream Flowrate × TSP Concentration × Metal Mass Fraction.

The operating schedule was presented from Sect. 2.4. of this Environmental Impact Statement:

The exhaust flow rate is based on obtaining one complete volume change of air in the cementation processing area every 15 min. Given that the hot cell is approximately 50 ft wide × 50 ft long × 15 ft high, the exhaust flowrate is 2500 dscfm.

Air Flow Rate = 2500 dscfm
Process Operating Schedule = 6 years life; 118.5 d/year, 8 h/d; and 60 min/h
Calculated Operating Hours = 5688 h

[d]The two HEPA filtration systems are assumed to have the following removal efficiencies:

HEPA Filter 1 Removal = 99%
HEPA Filter 2 Removal = 99%

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

d = day.

dscf = dry standard cubic foot.

dscfm = dry standard cubic feet per minute.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

TRU = transuranic.

Table B.3-10. Estimated metals emissions for remediation of supernate waste for the Cementation Alternative

Metals	Metals mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
TSP		1.30E-01	1.11E+08	2.44E+05	1.11E+04	2.44E+01	4.29E-03
Silver (Ag)	1.74E-07	2.25E-08	1.92E+01	4.24E-02	1.92E-03	4.24E-06	7.45E-10
Aluminum (Al)	1.22E-05	1.59E-06	1.35E+03	2.98E+00	1.35E-01	2.98E-04	5.25E-08
Arsenic (As)	1.75E-06	2.27E-07	1.93E+02	4.26E-01	1.93E-02	4.26E-05	7.49E-09
Boron (B)	1.10E-06	1.42E-07	1.21E+02	2.67E-01	1.21E-02	2.67E-05	4.70E-09
Barium (Ba)	1.59E-06	2.06E-07	1.76E+02	3.88E-01	1.76E-02	3.88E-05	6.82E-09
Beryllium (Be)	8.70E-09	1.13E-09	9.62E-01	2.12E-03	9.62E-05	2.12E-07	3.73E-11
Bismuth (Bi)	2.35E-06	3.04E-07	2.60E+02	5.72E-01	2.60E-02	5.72E-05	1.01E-08
Calcium (Ca)	1.19E-03	1.54E-04	1.31E+05	2.89E+02	1.31E+01	2.89E-02	5.08E-06
Cadmium (Cd)	3.39E-07	4.40E-08	3.75E+01	8.27E-02	3.75E-03	8.27E-06	1.45E-09
Cerium (Ce)	3.22E-07	4.17E-08	3.56E+01	7.84E-02	3.56E-03	7.84E-06	1.38E-09
Cobalt (Co)	1.39E-07	1.80E-08	1.54E+01	3.39E-02	1.54E-03	3.39E-06	5.96E-10
Chromium (Cr)	5.93E-06	7.69E-07	6.56E+02	1.45E+00	6.56E-02	1.45E-04	2.54E-08
Cesium (Cs)	1.57E-06	2.03E-07	1.73E+02	3.82E-01	1.73E-02	3.82E-05	6.71E-09
Copper (Cu)	7.48E-07	9.69E-08	8.27E+01	1.82E-01	8.27E-03	1.82E-05	3.20E-09
Iron (Fe)	9.47E-06	1.23E-06	1.05E+03	2.31E+00	1.05E-01	2.31E-04	4.06E-08
Gallium (Ga)	2.87E-07	3.72E-08	3.17E+01	7.00E-02	3.17E-03	7.00E-06	1.23E-09
Mercury (Hg)	6.87E-07	8.90E-08	7.60E+01	1.67E-01	7.60E-03	1.67E-05	2.94E-09
Iodine (I)	1.29E-05	1.67E-06	1.42E+03	3.14E+00	1.42E-01	3.14E-04	5.51E-08
Potassium (K)	9.86E-03	1.28E-03	1.09E+06	2.40E+03	1.09E+02	2.40E-01	4.22E-05
Lanthanum (La)	3.48E-08	4.51E-09	3.85E+00	8.48E-03	3.85E-04	8.48E-07	1.49E-10
Lithium (Li)	2.32E-05	3.01E-06	2.57E+03	5.66E+00	2.57E-01	5.66E-04	9.95E-08
Magnesium (Mg)	1.55E-04	2.01E-05	1.72E+04	3.78E+01	1.72E+00	3.78E-03	6.65E-07
Manganese (Mn)	2.87E-07	3.72E-08	3.17E+01	7.00E-02	3.17E-03	7.00E-06	1.23E-09
Molybdenum (Mo)	1.08E-06	1.40E-07	1.19E+02	2.63E-01	1.19E-02	2.63E-05	4.62E-09
Sodium (Na)	4.77E-02	6.18E-03	5.27E+06	1.16E+04	5.27E+02	1.16E+00	2.04E-04
Niobium (Nb)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Nickel (Ni)	1.07E-06	1.39E-07	1.18E+02	2.61E-01	1.18E-02	2.61E-05	4.58E-09
Phosphorus (P)	6.08E-05	7.88E-06	6.72E+03	1.48E+01	6.72E-01	1.48E-03	2.60E-07
Lead (Pb)	2.20E-06	2.85E-07	2.43E+02	5.36E-01	2.43E-02	5.36E-05	9.43E-09
Rubidium (Rb)	1.03E-06	1.33E-07	1.13E+02	2.50E-01	1.13E-02	2.50E-05	4.40E-09
Antimony (Sb)	8.61E-07	1.12E-07	9.52E+01	2.10E-01	9.52E-03	2.10E-05	3.69E-09
Selenium (Se)	8.17E-07	1.06E-07	9.04E+01	1.99E-01	9.04E-03	1.99E-05	3.50E-09
Silicon (Si)	4.79E-05	6.21E-06	5.30E+03	1.17E+01	5.30E-01	1.17E-03	2.05E-07
Tin (Sn)	3.30E-07	4.28E-08	3.65E+01	8.06E-02	3.65E-03	8.06E-06	1.42E-09
Strontium (Sr)	1.12E-05	1.45E-06	1.24E+03	2.73E+00	1.24E-01	2.73E-04	4.80E-08
Thorium (Th)	9.57E-06	1.24E-06	1.06E+03	2.33E+00	1.06E-01	2.33E-04	4.10E-08
Titanium (Ti)	4.43E-07	5.75E-08	4.90E+01	1.08E-01	4.90E-03	1.08E-05	1.90E-09
Thallium (Th)	1.54E-06	1.99E-07	1.70E+02	3.75E-01	1.70E-02	3.75E-05	6.60E-09
Uranium (U)	3.78E-04	4.90E-05	4.18E+04	9.22E+01	4.18E+00	9.22E-03	1.62E-06
Vanadium (V)	7.83E-08	1.01E-08	8.65E+00	1.91E-02	8.65E-04	1.91E-06	3.35E-10

Table B.3-10 (continued)

Metals	Metals mass fraction[a] (g/total g)	Metals concentration[b] (g/dscf)	Uncontrolled metal emissions for the project[c] (g)	(lbs)	Emissions after control for the project[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Tungsten (W)	4.00E-07	5.18E-08	4.42E+01	9.75E-02	4.42E-03	9.75E-06	1.71E-09
Zinc (Zn)	1.21E-05	1.57E-06	1.34E+03	2.94E+00	1.34E-01	2.94E-04	5.18E-08
Zirconium (Zr)	2.61E-08	3.38E-09	2.88E+00	6.36E-03	2.88E-04	6.36E-07	1.12E-10

[a]The data were obtained from U.S. Department of Energy Report, *Statistical Description of Liquid Low-level Waste System Transuranic Wastes at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, Document No. ORNL/TM-13351, Addendum 1. An average density of 1.15 g/mL was obtained for the supernate from Table 4.1, p. 3 of ORNL/TM-13351, Addendum 1. Given the volume stated in the request for proposal of 1600 m^3 of supernate, there is 1,840,000 kg of supernate mass.

[b]The amount of total suspended particulate (TSP) matter reaching the first exhaust system High-Efficiency Particulate Air (HEPA) filter is assumed to be:

Airborne Particulate Concentration = 2.0 gr/dscf = 0.1296 g/dscf.

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Exhaust Stream Flowrate × TSP Concentration × Metal Mass Fraction.

The operating schedule was presented from Sect. 2.4. of this Environmental Impact Statement:

The exhaust flow rate is based on obtaining one complete volume change of air in the cementation processing area every 15 min. Given that the hot cell is approximately 50 ft wide × 50 ft long × 15 ft high, the exhaust flowrate is 2500 dscfm.

Air Flow Rate	= 2500 dscfm
Process Operating Schedule	= 6 years life; 118.5 d/year, 8 h/d; and 60 min/h
Calculated Operating Hours	= 5688 h

[d]The two HEPA filtration systems are assumed to have the following removal efficiencies:

HEPA Filter 1 Removal = 99%
HEPA Filter 2 Removal = 99%

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

d = day.

dscf = dry standard cubic foot.

dscfm = dry standard cubic feet per minute.

g = gram.

gr/dscf = grains per dry standard cubic foot.

h = hour.

lb = pound.

Table B.3-11. Metal emissions for remediation of TRU/CH solid wastes using 40 *CFR* 61 Appendix D calculation procedures for the Cementation Alternative

Metals	Mass of metals in waste[a] (kg)	Uncontrolled metals emissions[b,c] (g)	(lbs)	Metals emissions after control[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Silver (Ag)	100	1.00E-01	2.20-04	1.00E-07	2.20E-10	5.25E-14
Cadmium (Cd)	400	4.00E-01	8.82E-04	4.00E-07	8.82E-10	2.10E-13
Mercury (Hg)	400	4.00E-01	8.82E-04	4.00E-07	8.82E-10	2.10E-13
Lead (Pb)	3,500	3.50E+00	7.72E-03	3.50E-06	7.72E-09	1.84E-12
Total	4,400					

	Concentration[f] (g/dscf)	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly emissions (lbs/h)
TSP	0.1296	3.27E+08	7.20E+05	3.27E+02	7.02E-01	1.71E-04

[a]Quantities are based on U.S. Department of Energy analysis and process knowledge of the Resource Conservation and Recovery Act metals in solid wastes.

[b]An emission factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.000001 fraction of the amount used (since this is solid waste).

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Metal Mass in Waste × Emissions Factor.

The operating schedule was presented from Sect. 2.4 of this Environmental Impact Statement:

Process Operating Schedule = 3 years life; 210 d/year; 8 h/d; and 60 min/h
Calculated Operating Hours = 5040 h

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor = 0.01
First HEPA Filter Adjustment Factor = 0.01
Second HEPA Filter Adjustment Factor = 0.01

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf (0.13 g/dscf) to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system which is based on obtaining one complete volume change of air in the hot cell every 15 min. Given that the hot cell is approximately 50 ft wide × 100 ft long × 30 ft high (due to the bay area for overhead cranes), the exhaust flowrate is 10,000 dscfm.

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

CH = contact handled.
dscf = dry standard cubic foot.
dscfm = dry standard cubic feet per minute.
g = gram.
gr/dscf = grains per dry standard cubic foot.
h = hour.
lb = pound.
TRU = transuranic.

Table B.3-12. Metal emissions for remediation of TRU/CH solid wastes using 40 *CFR* 61 Appendix D calculation procedures for the Cementation Alternative

Metals	Mass of metals in waste[a] (kg)	Uncontrolled metals emissions[b,c] (g)	(lbs)	Metals emissions after control[d] (g)	(lbs)	Average hourly emissions[e] (lbs/h)
Silver (Ag)	20	2.00E-02	4.41E-05	2.00E-08	4.41E-11	8.75E-15
Cadmium (Cd)	100	1.00E-01	2.20E-04	1.00E-07	2.20E-10	4.37E-14
Mercury (Hg)	100	1.00E-01	2.20E-04	1.00E-07	2.20E-10	4.37E-14
Lead (Pb)	980	9.80E-01	2.16E-03	9.80E-07	2.16E-09	4.29E-13
Total	1200					

	Concentration[f] (g/dscf)	Uncontrolled TSP emissions (g)	(lbs)	TSP emissions after control (g)	(lbs)	Average hourly emissions (lbs/h)
TSP	0.1296	3.92E+08	8.64E+05	3.92E+02	8.64-01	1.71E-04

[a]Quantities are based on U.S. Department of Energy analysis and process knowledge of the Resource Conservation and Recovery Act metals in solid wastes.

[b]An emission factor for the amount of airborne metals is obtained from Appendix D to 40 *Code of Federal Regulations (CFR)* 61.

Emission Factor = 0.000001 fraction of the amount used (since this is solid waste).

[c]The uncontrolled emissions are estimated by the following expression:

Uncontrolled Rate = Metal Mass in Waste × Emissions Factor.

The operating schedule was presented from Sect. 2.4 of this Environmental Impact Statement:

Process Operating Schedule = 3 years life; 210 d/year; 8 h/d; and 60min/h
Calculated Operating Hours = 5040 h

[d]The emissions after control are estimated by using the U.S. Environmental Protection Agency adjustment factors from Table 1 of Appendix D to 40 *CFR* 61. The adjustment factors are:

Hot Cell High-Efficiency Particulate Air (HEPA) Filter Adjustment Factor = 0.01
First HEPA Filter Adjustment Factor = 0.01
Second HEPA Filter Adjustment Factor = 0.01

[e]The average hourly emissions are calculated by the following expression:

Average Hourly = Pounds Emitted for Project/Project Operating Hours.

[f]The total suspended particulate (TSP) emissions from the hot cell are calculated based on an assumed inlet concentration of 2 gr/dscf (0.13 g/dscf) to the HEPA filter system on the cell exhaust. The TSP emissions are calculated using an assumed exhaust flow rate for this closed system which is based on obtaining one complete volume change of air in the hot cell every 15 min. Given that the hot cell is approximately 50 ft wide × 100 ft long × 30 ft high (due to the bay area for overhead cranes), the exhaust flowrate is 10,000 dscfm.

Average Hourly = Pounds Emitted for Project/Project Operating Hours.


CH = contact handled.
dscf = dry standard cubic foot.
dscfm = dry standard cubic feet per minute.
g = gram.
gr/dscf = grains per dry standard cubic foot.
h = hour.
lb = pound.
TRU = transuranic.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX B.4

FLOOR PLANS FOR THE PROPOSED LOW-TEMPERATURE DRYING WASTE TREATMENT FACILITY

THIS PAGE INTENTIONALLY LEFT BLANK


8
7
6
5
N
CONTROL ROOM
PERSONNEL FACILITIES
RH CONTAINER STORAGE
RH CASKS
CASK STAGING AREA
MAINTENANCE ROOM
LINER LOADOUT AREA
CANISTER HANDLING ROOM
72-B CASK LOADOUT AREA
BUFFER STORAGE
TRUPACT II LOADOUT AREA
LEGEND (FROM PART A PERMIT APPLICATION):
T01 = TANK TREATMENT
T04 = MISCELLANEOUS UNIT
S01 = CONTAINER STORAGE
S02 = TANK STORAGE
1ST FLOOR PLAN
SCALE: 3/32"=1'-0"





Figure B.4-1. 1st floor plan/Preferred Alternative.


8
7
6
5
PERSONNEL FACILITIES
N
CH CONTAINER STORAGE
CH DRUMS PROCESSING AREA
MACROENCAPSULATION AND AMALGAMATION FOR CH SOLID WASTE
CHEMICAL STORAGE
CH BOXES
LEGEND (FROM PART A PERMIT APPLICATION):
T01 = TANK TREATMENT
T04 = MISCELLANEOUS UNIT
S01 = CONTAINER STORAGE
S02 = TANK STORAGE
2ND FLOO





Figure B.4-2. 2nd floor plan/Preferred Alternative.


8
7
6
5
N
SLUDGE COLLECTION/
DECANT TANKS
HVAC
LEGEND (FROM PART A PERMIT APPLICATION):
T01 = TANK TREATMENT
T04 = MISCELLANEOUS UNIT
S01 = CONTAINER STORAGE
S01 = TANK STORAGE
3RD FLOOR




Figure B.4-3. 3rd floor plan/Preferred Alternative.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX C

FINDINGS OF SURVEYS FOR WETLANDS, TERRESTRIAL ANIMALS, RARE PLANTS, BASELINE NOISE, AND RADIOLOGICAL CONTAMINATION

THIS PAGE INTENTIONALLY LEFT BLANK

Appendix C contains the survey findings for wetland delineation, sensitive terrestrial animals, rare plants, baseline noise monitoring (draft report), and radiological contamination prepared by the Bechtel Jacobs Company Environmental Management Team and Foster Wheeler Environmental Corporation for the proposed Transuranic Waste Treatment Project site.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX C.1

FINDINGS OF WETLAND DELINEATION ON THE PROPOSED TRU WASTE FACILITY SITE

THIS PAGE INTENTIONALLY LEFT BLANK

FINDINGS OF WETLAND DELINEATION ON THE PROPOSED TRANSURANIC WASTE FACILITY SITE IN MELTON VALLEY, OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

August 25, 1999

prepared for:

Bechtel Jacobs Company LLC
under contract DE-AC05-98OR22700

prepared by:

Jacobs Environmental Management Team
and
Barbara A. Rosensteel
Wetlands and Watersheds Consulting

THIS PAGE INTENTIONALLY LEFT BLANK

CONTENTS

1. INTRODUCTION 1

2. WETLAND DELINEATION METHOD 2

3. WETLAND DELINEATION FINDINGS 3

4. SUMMARY 6

5. REFERENCES 7

APPENDIX A: WETLAND DATA SHEETS A-1

FIGURE

1 Wetlands delineated on or near the proposed TRU Waste Treatment Facility Site boundary 4

THIS PAGE INTENTIONALLY LEFT BLANK

1. INTRODUCTION

Executive Order 11990 (May 24, 1977), Protection of Wetlands, requires federal agencies to avoid, to the extent possible, adverse impacts associated with the destruction and modification of wetlands, and that they avoid direct and indirect support of wetlands development when there is a practicable alternative. In accordance with U.S. Department of Energy (DOE) Regulations for Compliance with Floodplains and Wetlands Environmental Review Requirements [10 *Code of Federal Regulations* (CFR) 1022.11], wetlands on the proposed Transuranic (TRU) Waste Treatment Facility Site (the site) in Melton Valley were identified and the jurisdictional boundaries determined. As required by the Energy and Water Development Appropriations Act of 1992, wetlands were identified using the criteria and methods set forth in the *Wetlands Delineation Manual* [U.S. Army Corps of Engineers (USACE) 1987]. Wetlands identified in this survey were classified according to the system developed by Cowardin et al. (1979) for wetland and deepwater habitats of the United States.

The site is a wooded area immediately west of the Oak Ridge National Laboratory (ORNL) hydrofracture facility. The majority of the site consists of a second-growth forest stand dominated by Virginia pine, oaks, and other hardwoods on moderate slopes. An upgrade of the Melton Valley Access Road is being constructed at the northern boundary of the site and some land has been cleared in that area. An intermittent, headwater stream flows along the eastern boundary of the site, immediately outside of the hydrofracture facility fence. Another intermittent stream is located at the western site boundary. The site drains to White Oak Creek near the head of White Oak Lake.

One small wetland was delineated on the site (wetland B) and two other wetlands were delineated beyond the southern boundary of the site (wetlands A and C). The boundary of an additional wetland, located on the site, (wetland D) was recently delineated for the Melton Valley Road Upgrade project and, thus, was not re-delineated during wetland delineation of the site. However, a description of wetland D, based on data collected during an April 1992 field survey by B. Rosensteel, is included in this report.

Wetland A is located in the riparian zone of the western site boundary intermittent stream beyond the southwest corner of the TRU Waste Facility site. Wetland B is a very small wetland located in the riparian zone of the intermittent stream within the eastern boundary of the site. Wetland C is in a seep area in a maintained, grassy area outside of the hydrofracture facility fence beyond the southeast corner of the TRU Waste Facility site. Wetland D is located in the riparian zone of the western site boundary stream in a small section between the "old" and recently upgraded portion of Melton Valley Road. All of the wetlands delineated during this survey are located in areas of prior disturbance.

2. WETLAND DELINEATION METHOD

Wetland determination was performed using the USACE methodology (1987). According to this methodology, three parameters—hydrophytic vegetation, hydric soils, and wetland hydrology—must be present for an area to be identified as a wetland. With the exception of certain atypical or problem situations, an area must possess all of the following attributes to be positively identified as a wetland:

1. The vegetation is characterized by a prevalence of macrophytes typically adapted to wetland soil and hydrological conditions. Hydrophytic vegetation is considered to be present when greater than 50 percent of the vegetation in each strata have an indicator status of obligate wetland (OBL), facultative wetland (FACW), and/or facultative (FAC) (USFWS 1996 revised).

2. The substrate is undrained hydric soil. Hydric soils are soils that are saturated, flooded, or ponded long enough during the growing season to develop anaerobic conditions in a major part of the root zone. Several indicators, including soil color and presence of mottles, are used to determine if a soil is hydric.

3. The area is inundated either permanently or periodically at depths less than 6.6 ft, or the soil is saturated to the surface at some time during the growing season of the prevalent vegetation. Evidence includes direct observations of inundation or soil saturation and indirect observations such as flood drift lines and silted leaf litter.


Wetlands described in this report have been classified according to the system developed by Cowardin et al. (1979). This hierarchical system describes wetlands by system, class, and subclass. Additional modifiers are added for hydrologic regime, soil, and disturbances. The majority of the wetlands in the region of the Oak Ridge Reservation (ORR) are in the palustrine system (indicated by the letter "P"), and in either the forested (FO), scrub-shrub (SS), or emergent (EM) classes. The number "1" following these designations indicates broad-leaved deciduous vegetation (in the FO and SS classes), and vegetation with parts that persist aboveground after the growing season (in the EM class). The typical water regime modifiers for wetlands on the ORR are temporarily flooded (A), saturated (B), seasonally flooded (C), semipermanently flooded (F), and permanently flooded (H).

3. WETLAND DELINEATION FINDINGS

Four small wetlands have been identified and delineated on or adjacent to the site (Fig. 1). Wetlands A, B, and C were delineated during the current field survey. Wetland D was initially identified by B. Rosensteel during an April 1992 field survey (Martin Marietta Energy Systems, Inc. internal correspondence from B. Rosensteel to R. Saylor) and others recently delineated the wetland boundary for the Melton Valley Access Road upgrade. Data for each wetland is presented in a modification of the USACE routine wetland determination data sheets (USACE 1987) in Appendix A. Data presented for wetland D was collected during the April 1992 survey. Although, data was not collected for wetland D during the current work, visual observation of this wetland during the current survey confirmed that wetland criteria are still present.

Wetland A is a saturated and temporarily flooded, palustrine emergent wetland (PEM1A/B) located in a clearing in the intermittent stream drainage beyond the southwestern corner of the site. The stream begins farther upslope near the base of Copper Ridge and flows through a clearing where wetlands have developed around seeps that contribute to stream flow. In the wetland, water flow is across the surface and through shallow channels. At the northern end of the wetland, the diffuse surface and subsurface flows converge in a well-defined, steep-banked reach of the stream. On the day of the delineation, there was water flowing across the surface, the soil was saturated throughout the wetland, and there was free water in several of the soil borings at a depth less than 10 in. from the surface. A small portion of the downslope end of the wetland extends into a wooded area along the stream and includes an area around a wellhead.

The dominant vegetation species include sweetflag (*Acorus calamus*; OBL), mountain mint (*Pycnanthemum* sp.), shrubby St. Johns wort (*Hypericum densiflorum*; FACW-), soft rush (*Juncus effusus*; FACW+), microstegium (*Microstegium vimineum*; FAC), and poison ivy (*Toxicodendron radicans*; FAC). Other commonly occurring species include silky dogwood (*Cornus amomum*; FACW+); saplings of box elder (*Acer negundo*; FACW), green ash (*Fraxinus pennsylvanica*; FACW), and black willow (*Salix nigra*; OBL); monkey flower (*Mimulus ringens*; OBL); bugleweed (*Lycopus virginicus*; OBL); cattail (*Typha latifolia*; OBL); *Juncus biflorus*; FACW+; and an unidentified grass (*Panicum* sp.) Soil examined from several locations in the wetland exhibited a low chroma color matrix, mottles, and oxidized rhizospheres.


Wetland A = 0.36 Acres
Wetland B = 0.03 Acres
Wetland C = 0.09 Acres
Wetland D = 0.04 Acres
Existing Building 7830
Centerline of Culvert
Centerline of Culvert
One New 24" CMP Culvert
761 Access Road
Proposed Site Boundary
A
B
C
D
0
150
Scale in Feet
Wetlands delineated on or near
The proposed TRU Waste Treatment Facility Site boundary
DOE – Oak Ridge Reservation– Oak Ridge Tennessee
Fig. 1.

Surrounding wetland A are upland open-canopy forested areas on the west and south side and a dense sapling-vine thicket on the east side. Vegetation species include red cedar (*Juniperus virginiana*), redbud (*Celtis occidentalis*), red maple (*Acer rubrum*), Virginia pine (*Pinus virginiana*), tulip poplar (*Liriodendron tulipifera*), flowering dogwood (*Cornus florida*), Japanese honeysuckle (*Lonicera japonica*), and blackberry (*Rubus* sp.). These areas, in turn, are flanked by second-growth pine-hardwood forest, which includes Virginia pine, beech (*Fagus americana*), black cherry (*Prunus serotina*), white oak (*Quercus alba*), and tulip poplar.

Wetland B is a very small, temporarily flooded and saturated, palustrine scrub-shrub wetland (PSS1A/B) in an alluvial area in the intermittent stream on the eastern side of the site. The soil is saturated and the wetland may be flooded following rainfall. The primary cause of the riparian zone saturation and flooding is an old road-crossing culvert that is on the downstream side of this wetland area and acts to slow and retain stream flow. The dominant species include sweetgum (*Liquidambar styriciflua*; FAC) and green ash saplings, silky dogwood, sedges (*Carex* spp.; *Scirpus* spp.), and a herbaceous species that could not be identified as it had recently emerged and lacked flowers. The soil included a fine gravel alluvium, and a silt loam with a low chroma matrix, mottles, and partially decomposed plant fragments. The wetland is flanked by the hydrofracture facility to the east and second-growth pine-hardwood forest to the west.

Wetland C is a saturated, palustrine emergent wetland (PEM1B) located in a disturbed, grassy area upslope and outside of the hydrofracture facility fence beyond the southeast corner of the site. Although currently there is no evidence of a stream channel through the wetland area, the wetland is in a topographic low area that may have contained a section of the intermittent stream prior to land disturbance and hydrologic alterations. Water discharges from seeps in the wetland and reenters the ground at the downslope end of the wetland near the fence. The intermittent stream adjacent to the hydrofracture facility fence is a short distance downslope of this wetland, and may receive some of the water that flows through the wetland area. The hydrofracture facility to the north, a continuation of the maintained grassy area to the east, and second-growth pine-hardwood forest to the south and west flank the wetland.

Wetland D is a saturated emergent wetland (PEM1B) located on the stream at the western side of the site, and lies between the old section and recently upgraded section of Melton Valley Access Road. The wetland has developed in a seep area; however, the persistence of wetland hydrology in this small area appears to be at least partially due to the slowing of stream and groundwater flow by a culvert under the old Melton Valley Road. On the day of this field visit, there were standing and flowing water in this wetland. Dominant plant species identified in the April 1992 survey included black willow, soft rush, monkey flower, cattail, fox sedge (*Carex vulpinoidea*; OBL), shallow sedge (*Carex lurida*; OBL), and rice cutgrass (*Leersia oryzoides*; OBL). The soil matrix color was described in May 1992 as dark gray (10YR 4/1) and grayish brown (10YR 5/2) with strong brown (7.5YR 5/8) and very dark gray (10YR 3/1) mottles.

4. SUMMARY

The boundaries of three jurisdictional wetlands (wetlands A, B, and C) were delineated according to the U.S. Army Corps of Engineers criteria on the site in Melton Valley April 20, 1999. An additional wetland (wetland D) had been initially identified in April 1992 by B. Rosensteel, and the boundary recently rechecked by the Tennessee Department of Environment and Conservation for the Melton Valley Access Road upgrade.

Wetland A is a palustrine emergent wetland (PEM1A/B) located in a seep area in an intermittent stream drainage beyond the southwest corner of the project site boundary. Wetland B is a very small scrub-shrub wetland (PSS1A/B) in an alluvial area in an intermittent stream near the eastern site boundary, just outside of the existing hydrofracture facility fence. Wetland C is an isolated, emergent wetland (PEM1A/B) in a previously disturbed, grassy area upslope and outside of the existing hydrofracture facility fence beyond the southeast corner of the site. Wetland D is located in the riparian zone of an intermittent stream in the northwest corner of the site, in a small stream section situated between the "old" and the recently upgraded portion of Melton Valley Access Road. All of the wetlands occur in previously cleared and disturbed areas. Wetland C continues to receive occasional disturbance from periodic mowing.

5. REFERENCES

Cowardin, L. M., V. Carter, F. C. Golet, and E. T. LaRoe. 1979. Classification of wetland and deepwater habitats of the United States. FWS/OBX-79/31. U.S. Fish and Wildlife Service, Washington, D.C.

U.S. Army Corps of Engineers. 1987. Wetlands Delineation Manual. Technical Report Y-87-1. Waterways Experiment Station, Vicksburg, Mississippi.

U.S. Fish and Wildlife Service. 1996. Draft revision of the National List of Plant Species that Occur in Wetlands.

Martin Marietta Energy Systems internal correspondence from B. Rosenteel to R. Saylor. May 1992. "Wetland delineation report—RHTRU Waste Storage Bunker."

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX A
WETLAND DETERMINATION DATA FORMS

Wetland Delineation Data Sheets

Project site: TRU Facility Site, Oak Ridge Reservation Date: 20 April 1999

State: TN County: Anderson

Wetland ID: Wetland A Location: Clearing in seep area around intermittent stream

Wetland Class: PEM1A/B

VEGETATION

SPECIES	Indicator Status	SPECIES	Indicator Status
TREES AND SAPLINGS		**HERBACEOUS and VINES**	
Acer negundo	FACW+	Acorus calamus	OBL
Fraxinus pennsylvanica	FACW	Pycnanthemum sp.	
Salix nigra	OBL	Juncus effusus	FACW+
SHRUBS		Toxicodendron radicans	FAC
Cornus amomum	FACW+	Juncus biflorus	FACW+
Rubus sp. (blackberry)		Lycopus virginicus	OBL
		Eulalia viminea	FAC

% of species that are OBL, FACW, and/or FAC: 100%

Hydrophytic Vegetation: YES

SOILS

Depth	Matrix	Mottles	Texture/Other
0-9"	10YR 5/1	7.5YR 4/6	Silty clay loam
9-12"	10YR 5/1	7/5YR 4/6	Clay loam
0-7"	10YR 3/1		Very silty loam
7-12"	10YR 5/1		Gravelly silt loam
0-9"	10YR 5/1	7.5YR 4/6	Silt loam

Hydric Soils: YES Basis: Low chroma matrix and mottles

HYDROLOGY

Inundated:	Partially	Water depth: 1-3" flowing water	
Saturated:	Yes	Depth to saturated soil:	Saturated to surface
Other indicators:	Oxidized rhizospheres		

Wetland Hydrology: YES

Atypical Situation: NO Normal Circumstances: YES

Is this a Jurisdictional Wetland?: YES

Comments:

Determined by: B. A. Rosensteel, PWS

Wetland Delineation Data Sheets

Project site: TRU Facility Site, Oak Ridge Reservation		Date: 20 April 1999	
State: TN	County: Anderson		
Wetland ID: Wetland B			
Wetland Class: PFO1A/B	Location:	Small alluvial area on intermittent stream	
VEGETATION			
SPECIES	**Indicator Status**	**SPECIES**	**Indicator Status**
TREES AND SAPLINGS		**HERBACEOUS and VINES**	
Liquidambar styriciflua	FAC	Sedges (could not be identified to species due to immaturity of specimens)	Unknown, but likely to be OBL or FACW
Fraxinus pennsylvanica	FACW		
SHRUBS			
Cornus amomum	FACW+	Unidentified herbaceous species - could not be identified due to immaturity of specimens)	Unknown
% of Dominant Species that are OBL, FACW, and/or FAC: **100% in tree/shrub strata; Uncertain in herbaceous strata.** **Hydrophytic Vegetation: YES**			

SOILS			
Depth	Matrix	Mottles	Texture/Other
0-9"	10YR 5/2	7.5YR 4/6	silt loam containing partially decomposed plant material
Hydric Soils: YES		Basis: Low chroma matrix with mottles	

HYDROLOGY			
Inundated:	Partially	Water depth: flowing water in stream; water in soil boring at 3" near wetland outer edge.	
Saturated:	Yes		
Other indicators:	Oxidized rhizospheres	Depth to saturated soil:	Saturated to surface
Wetland Hydrology: YES			

Atypical Situation: NO Normal Circumstances: YES

Is this a Jurisdictional Wetland?: Yes

Comments:

Determined by: B. A. Rosensteel, PWS

Wetland Delineation Data Sheets

Project site: TRU Facility Site, Oak Ridge Reservation Date: 20 April 1999
State: TN County: Anderson
Wetland ID: Wetland C
Wetland Class: PEM1B Location: Isolated seeps in maintained grassy area

VEGETATION

SPECIES	Indicator Status	SPECIES	Indicator Status
TREES AND SAPLINGS		**HERBACEOUS and VINES**	
Salix nigra	OBL	Festuca arundinacea	FAC-
Liquidambar styriciflua	FAC	Juncus effusus	FACW+
		Sedges (could not be identified to species due to immaturity of specimens)	Likely to be FACW or OBL
SHRUBS			
None		Scirpus cyperinus	OBL
		Typha latifolia	OBL
		Mimulus ringens	OBL

% of Dominant Species that are OBL, FACW, and/or FAC: 100%

Hydrophytic Vegetation: YES

SOILS

Depth	Matrix	Mottles	Texture/Other
0-8"	10YR 4/1		Oxidized rhizospheres
0-8"	2.5Y 5/2	7/5YR 4/6	Oxidized rhizospheres

Hydric Soils: YES Basis: Low chroma matrix and mottles in most samples

HYDROLOGY

Inundated:	No	Water depth: 1-3" flowing water	
Saturated:	Yes	Depth to saturated soil:	Saturated to surface
Other indicators:	Oxidized rhizospheres		

Wetland Hydrology: YES

Atypical Situation: NO Normal Circumstances: YES

Is this a Jurisdictional Wetland?: YES

Comments: This area, possibly including a headwater stream, was altered in the past. The soil may consist partially or wholly of fill soils. The wetland in isolated in that seeps discharge water which then re-enters the soil at the downslope end of the wetland before reaching a stream or other surface water. It is on a slope in a grassed area that is maintained by periodic mowing.

Determined by: B. A. Rosensteel, PWS

Wetland Delineation Data Sheets

Project site: TRU Facility Site, Oak Ridge Reservation		Date: April 1992	
State: TN	County: Anderson		
Wetland ID: Wetland B	Location:	Riparian seep area between the old and	
Wetland Class: PEM1A		new Melton Valley Road	

VEGETATION

SPECIES	Indicator Status	SPECIES	Indicator Status
TREES AND SAPLINGS		**HERBACEOUS and VINES**	
Salix nigra	OBL	Typha latifolia	OBL
		Leersia oryzoides	OBL
		Carex lurida	OBL
SHRUBS		Juncus effusus	FACW+
		Carex vulpinoidea	OBL
		Mimulus ringens	OBL

% of Dominant Species that are OBL, FACW, and/or FAC: 100%

Hydrophytic Vegetation: YES

SOILS

Depth	Matrix	Mottles	Texture/Other
	10YR 4/1	7.5YR 5/8 10YR 3/1	

Hydric Soils: YES Basis: Low chroma matrix with mottles

HYDROLOGY

Inundated:	Partially	Water depth: flowing water in stream; water in soil	
Saturated:	Yes	boring within a few inches of surface	
Other indicators:		Depth to saturated soil:	Saturated to surface

Wetland Hydrology: YES

Atypical Situation: NO Normal Circumstances: YES

Is this a Jurisdictional Wetland?: Yes

Comments: This wetland area was initially identified in April 1992 by B. Rosensteel and the boundary recently delineated by others. Data is from 1992 survey.
Determined by: B. A. Rosensteel, PWS

APPENDIX C.2

FINDINGS OF SURVEY FOR SENSITIVE TERRESTRIAL ANIMAL SPECIES AT THE PROPOSED TRU WASTE FACILITY SITE

THIS PAGE INTENTIONALLY LEFT BLANK

FINDINGS OF THE SURVEY FOR SENSITIVE TERRESTRIAL ANIMAL SPECIES AT THE PROPOSED TRANSURANIC WASTE TREATMENT FACILITY SITE IN MELTON VALLEY, OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

August 25, 1999

prepared for:

Bechtel Jacobs Company LLC
under contract number DE-AC05-98O22700

prepared by:

Jacobs Environmental Management Team
and
Wayne H. Schacher

CONTENTS

1. INTRODUCTION 1
1.1 DESCRIPTIVE OVERVIEW OF HABITAT 1

2. METHODS 2
2.1 SPECIES POTENTIALLY PRESENT ON SITE 2
2.2 SITE HABITAT SUITABILITY FOR SPECIES POTENTIALLY PRESENT 2
2.3 CAPTURE AND OBSERVATION METHODS 11

3. RESULTS 14

4. CONCLUSIONS 20

5. REFERENCES 21

TABLES

1 State and federally listed terrestrial animal species in Tennessee, with projected geographic range and habitat suitability relationships for the TRU parcel 3

2 Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee 15

THIS PAGE INTENTIONALLY LEFT BLANK

1. INTRODUCTION

Approximately five acres have been identified as a lease parcel for a proposed Transuranic (TRU) Waste Treatment Facility (the site) in Melton Valley at the Oak Ridge National Laboratory (ORNL) in Oak Ridge, Tennessee. A survey for sensitive terrestrial animal species on the Oak Ridge Reservation (ORR) was conducted in 1996, but did not cover the site (ORNL/ER/TM-188/R1 1996). Complete and accurate identification of all resources on the site is needed to support proper planning, documentation, and management of the site. A survey of sensitive terrestrial animal species at the site will complete this requirement for animals.

1.1 DESCRIPTIVE OVERVIEW OF HABITAT

Past disturbance within the 5-acre land parcel proposed for the site near Oak Ridge, Tennessee has shifted cover type vegetation toward younger woodland compositions, with sections of the parcel in early successional, herbaceous vegetation.

Woodland habitats are present on knolls, ridges and more upland areas. Existing cover types that would be suitable for sensitive terrestrial animal species include woodlands with a deciduous oak-hickory composition; transitional woodlands with a mixture of deciduous, pine (shortleaf, white and loblolly) species, and small cedars in the canopy; and pine-dominant woodlands. Each of these cover types is composed of young to mid-age trees with DBH rarely in excess of 1.5 ft. No hollow trees living or dead were observed on the parcel.

Areas of closed canopy and partially open canopy are present in woodlands, and both deciduous and coniferous species are present in the subcanopy and understory. A thin layer of deciduous leaf litter accompanies slash, moss-covered surface debris and small rocks on the soil surface. The soil surface is firm and gravelly, with a minimal buildup of organic matter. Some rotting stumps and logs are present. Beneath breaks in the woodland canopy, and along an old logging road, herbaceous vegetation forms the ground cover. No caves or large rock outcrops are present in the parcel.

Small, ephemeral streams flow down slope from the wooded uplands toward the access road. One stream is partially blocked by a logging road mid-way down slope, and forms a small wet habitat with herbaceous ground cover within the woodland. Downstream of this wet habitat, the stream channel is defined, with silt, gravel, rootwads and small rocks. The second stream flows from the woodland through a disturbed, slash and early successional habitat to form a pool of standing water resulting from the access road bed. This small, open-water impoundment creates a wetland appearance, and contains young growths of water-tolerant tree (black willow) and herbaceous (rushes) species.

2. METHODS

An initial terrestrial survey was conducted on April 20, 1999, to characterize land use, cover type and habitat contained within the 5-acre site. Field notes indicating general habitat types were made, and specific habitat locations were noted on field maps. Notations indicated the presence or absence of unique features (rock outcrops, hollow trees), communities (canebrakes, seeps, streams, wetlands) or quality habitat types (mature woodlands, old fields, etc.).

2.1 SPECIES POTENTIALLY PRESENT ON SITE

This information was used to evaluate habitats present on the site and their relative suitability to support state and federally listed terrestrial animal species (Table 1). These assessments resulted in identification of targeted sensitive species in the four vertebrate classes that could occur on the site. A narrative of these sensitive species that could be present, a discussion of its habitat requirements relevant to the site, and indication of survey methods that were employed to determine its presence or absence from the site follows Table 1.

2.2 SITE HABITAT SUITABILITY FOR SPECIES POTENTIALLY PRESENT

Following the initial survey, "suitable habitat" determinations were projected for sensitive (Tennessee or federal classifications) terrestrial animal species in the Classes Amphibia, Reptilia, Aves and Mammalia. These projections were based upon the geographical range of the species being inclusive of lands in Melton Valley, and the existence of habitat deemed suitable for the respective species (Harvey 1992; Choate, Jones and Jones 1994; Wilson 1995; Redmond and Scott 1996; Nicholson 1997; Whitaker and Hamilton 1998).

Amphibia

Hemidactylium scutatum (four-toed salamander)—Tennessee 'In Need of Management'

Habitat for this species includes woodland swamps, shallow ponds, sphagnum bogs, and slow-moving streams with abundant moss, sedges or similar herbaceous growth, adjacent to woodlands. Habitat existing on the site was considered to be "marginal." Potential habitats include the small woodland streams present, the low, wet, wooded and herbaceous depressions and the herbaceous wetland near the main access road. Survey methods employed were qualitative searches, use of artificial ground covers and construction of drift fence and pitfall arrays.

Table 1. State and federally listed terrestrial animal species in Tennessee, with projected geographic range and habitat suitability relationships for the TRU parcel

Scientific name	Common name	TN Status	In geographic range	Suitable habitat present
CLASS AMPHIBIA				
AMBYSTOMA TALPOIDEUM	SALAMANDER	NMGT	NO	
CRYPTOBRANCHUS A. ALLEGANIENSIS	EASTERN HELLBENDER	NMGT	YES	NO
DESMOGNATHUS AENEUS	SEEPAGE SALAMANDER	NMGT	NO	
DESMOGNATHUS QUADRAMACULATUS	BLACK-BELLIED SALAMANDER	NMGT	NO	
DESMOGNATHUS WELTERI	BLACK MOUNTAIN SALAMANDER	NMGT	YES	NO
DESMOGNATHUS WRIGHTI	PIGMY SALAMANDER	NMGT	NO	
EURYCEA JUNALUSKA	JUNALUSKA SALAMANDER	NMGT	NO	
GYRINOPHILUS PALLEUCUS	TENNESSEE CAVE SALAMANDER	THR	NO	
HEMIDACTYLIUM SCUTATUM	FOUR-TOED SALAMANDER	NMGT	YES	MARGINAL
HYLA GRATIOSA	BARKING TREEFROG	NMGT	NO	
PLETHODON WEHRLEI	WEHRLE'S SALAMANDER	NMGT	NO	
PLETHODON WELLERI	WELLER'S SALAMANDER	NMGT	NO	
RANA CAPITO	GOPHER FROG	POTL	NO	
CLASS AVES:				
ACCIPITER COOPERII	COOPER'S HAWK	NMGT	YES	YES
ACCIPITER STRIATUS	SHARP-SHINNED HAWK	NMGT	YES	YES
AEGOLIUS ACADICUS	NORTHERN SAW-WHET OWL	NMGT	WINTER ONLY	NO
AIMOPHILA AESTIVALIS	BACHMAN'S SPARROW	END	YES	MARGINAL
AMMODRAMUS SAVANNARUM	GRASSHOPPER SPARROW	NMGT	YES	MARGINAL
ANHINGA ANHINGA	ANHINGA	NMGT	MARGINAL	NO
AQUILA CHRYSAETOS	GOLDEN EAGLE	THR	WINTER ONLY	NO
CASMERODIUS ALBUS	GREAT EGRET	NMGT	YES	NO
CHONDESTES GRAMMACUS	LARK SPARROW	THR	YES	MARGINAL
CIRCUS CYANEUS	NORTHERN HARRIER	NMGT	WINTER ONLY	FORAGE ONLY
CONTOPUS BOREALIS	OLIVE-SIDED FLYCATCHER	NMGT	NO	
CORVUS CORAX	COMMON RAVEN	THR	NO	
EGRETTA CAERULEA	LITTLE BLUE HERON	NMGT	YES	NO
EGRETTA THULA	SNOWY EGRET	NMGT	YES	NO

Table 1. State and federally listed terrestrial animal species in Tennessee, with projected geographic range and habitat suitability relationships for the TRU parcel (continued)

Scientific name	Common name	TN Status	In geographic range	Suitable habitat present
FALCO PEREGRINUS	PEREGRINE FALCON	END / LE	YES	NO
GRUS CANADENSIS	SANDHILL CRANE	NMGT	WINTER ONLY	NO
HALIAEETUS LEUCOCEPHALUS	BALD EAGLE	THR / LT	YES	NO
ICTINIA MISSISSIPPIENSIS	MISSISSIPPI KITE	NMGT	NO	
IXOBRYCHUS EXILIS	LEAST BITTERN	NMGT	YES	
LIMNOTHLYPIS SWAINSONII	SWAINSON'S WARBLER	NMGT	YES	NO
PANDION HALIAETUS	OSPREY	THR	YES	NO
PHALACROCORAX AURITUS	DOUBLE-CRESTED CORMORANT	NMGT	YES	NO
PICOIDES BOREALIS	RED-COCKADED WOODPECKER	END / LE	MARGINAL	NO
POOECETES GRAMINEUS	VESPER SPARROW	NMGT	YES	MARGINAL
RALLUS ELEGANS	KING RAIL	NMGT	YES	NO
SPHYRAPICUS VARIUS	YELLOW-BELLIED SAPSUCKER	NMGT	WINTER ONLY	YES
STERNA ANTILLARUM	LEAST TERN	END	NO	
THRYOMANES BEWICKII ALTUS	APPALACHIAN BEWICK'S WREN	THR	NO	
THRYOMANES BEWICKII BEWICKII	BEWICK'S WREN	THR	YES	MARGINAL
TYTO ALBA	COMMON BARN-OWL	NMGT	YES	FORAGE ONLY
CLASS REPTILIA:				
ANOLIS CAROLINENSIS	GREEN ANOLE	NMGT	MARGINAL	NO
CLEMMYS MUHLENBERGII	BOG TURTLE	THR / LT	NO	
EUMECES A. ANTHRACINUS	NORTHERN COAL SKINK	NMGT	MARGINAL	MARGINAL
EUMECES ANTHRACINUS PLUVIALIS	SOUTHERN COAL SKINK	NMGT	MARGINAL	MARGINAL
MACROCLEMYS TEMMINCKII	ALLIGATOR SNAPPING TURTLE	NMGT	NO	
NERODIA CYCLOPION	MISSISSIPPI GREEN WATER SNAKE	NMGT	NO	
OPHISAURUS ATTENUATUS	EASTERN SLENDER GLASS LIZARD	NMGT	YES	YES
PITUOPHIS M. MELANOLEUCUS	NORTHERN PINE SNAKE	THR	YES	MARGINAL
SISTRURUS MILIARIUS STRECKERI	WESTERN PIGMY RATTLESNAKE	THR	NO	

Table 1. State and federally listed terrestrial animal species in Tennessee, with projected geographic range and habitat suitability relationships for the TRU parcel (continued)

Scientific name	Common name	TN Status	In geographic range	Suitable habitat present
CLASS MAMMALIA:				
CANIS RUFUS	RED WOLF	END / NX	NO	
CONDYLURA CRISTATA PARVA	STAR-NOSED MOLE	NMGT	MARGINAL	MARGINAL
CORYNORHINUS RAFINESQUII	EASTERN BIG-EARED BAT	NMGT	YES	MARGINAL
FELIS CONCOLOR	MOUNTAIN LION	END / LE	HISTORICAL	NO
GLAUCOMYS SABRINUS COLORATUS	CAROLINA NOR. FLYING SQUIRREL	END / LE	MARGINAL	NO
LUTRA CANADENSIS	RIVER OTTER	THR*	YES	
MICROTUS CHROTORRHINUS CAROLINENSIS	SOUTHERN ROCK VOLE	NMGT	NO	
MYOTIS GRISESCENS	GRAY BAT	END / LE	YES	NO
MYOTIS LEIBII	EASTERN SMALL-FOOTED BAT	NMGT	YES	MARGINAL
MYOTIS SODALIS	INDIANA MYOTIS	END / LE	YES	MARGINAL
NAPAEOZAPUS INSIGNIS	WOODLAND JUMPING MOUSE	NMGT	MARGINAL	NO
NEOTOMA FLORIDANA HAEMATOREIA	SOU. APPALACHIAN WOODRAT	NMGT	NO	
NEOTOMA FLORIDANA ILLINOENSIS	EASTERN WOODRAT	NMGT	NO	
NEOTOMA MAGISTER	ALLEGHENY WOODRAT	NMGT	YES	NO
PARASCALOPS BREWERI	HAIRY-TAILED MOLE	NMGT	YES	YES
SOREX CINEREUS	COMMON SHREW	NMGT	YES	NO
SOREX DISPAR BLITCHI	LONG-TAILED SHREW	NMGT	YES	NO
SOREX FUMEUS	SMOKY SHREW	NMGT	YES	NO
SOREX LONGIROSTRIS	SOUTHEASTERN SHREW	NMGT	YES	YES
SOREX PALUSTRIS PUNCTULATUS	SOUTHERN WATER SHREW	NMGT	YES	NO
SYNAPTOMYS COOPERI	SOUTHERN BOG LEMMING	NMGT	YES	YES
ZAPUS HUDSONIUS	MEADOW JUMPING MOUSE	NMGT	YES	MARGINAL

LE = Federal, endangered
LT = Federal, threatened
NMGT = Tennessee, In Need of Management
THR = Tennessee, Threatened
END = Tennessee, Endangered
NX = Federal, natural population extirpated
POTL = Tennessee, Potential Listed
PT = Federal, Potential Threatened

Reptilia

Eumeces anthracinus anthracinus (northern coal skink)—Tennessee 'In Need of Management'

Habitat for this species includes humid, mesic wooded or rocky hillsides, usually near water, where it is found under logs, rocks and leaf litter. Habitat existing on the site was considered to be "marginal." Potential habitats include the mixed woodlands on hillsides or wooded knobs near streams. Survey methods employed were qualitative searches, use of artificial ground covers and construction of drift fence and pitfall arrays.

Eumeces anthracinus pluvialis (southern coal skink)—Tennessee 'In Need of Management'

Habitat for this species includes humid, mesic wooded or rocky hillsides, usually near water, where it is found under logs, rocks and leaf litter. Habitat existing on the site was considered to be "marginal." Potential habitats include the mixed woodlands on hillsides or wooded knobs near streams. Survey methods employed were qualitative searches, use of artificial ground covers and construction of drift fence and pitfall arrays.

Ophiosaurus attenuatus longicaudus (eastern slender glass lizard)—Tennessee 'In Need of Management'

Habitat for this species includes grassy fields, woodland margins, brushy, cut-over woodlands or dry pine-oak woodlands with loose, friable soils. Suitable habitat for this species was felt to be present on the site, though the gravel/clay soils might limit the presence of this fossorial species. Likely habitats for this species would include the upland mixed woodlands. The fossorial nature of this species makes collection extremely difficult. Survey methods employed were qualitative searches and the use of artificial ground covers.

Pituophis melanoleucus melanoleucus (northern pine snake)—Tennessee 'Threatened'

Habitat for this species includes xeric, pine-oak woodlands with sandy soils, and dry ridge tops. Habitat existing on the site was considered to be "marginal", since the gravel/clay soils might limit the presence of this highly fossorial species. Potential habitats include the mixed woodlands on the ridges and knobs. The fossorial nature of this species makes collection extremely difficult. Survey methods employed were qualitative searches and the use of artificial ground covers.

Aves

Accipiter cooperii *(Cooper's hawk)—Tennessee 'In Need of Management'*

Foraging and nesting habitat for this species includes deciduous woodlands interrupted by clearing or fields, or woodland edges. This adaptable species will also utilize wooded parks, rural woodlots, or suburban habitats. This species strongly prefers deciduous trees as nesting sites. Suitable nesting and foraging habitat for this species was felt to be present on the site. Survey methods employed were direct observation, and a systematic nest search.

Accipiter striatus (Sharp-shinned hawk)—Tennessee 'In Need of Management'

Foraging and nesting habitat for this species includes dense coniferous forests, occasionally mixed or deciduous woodlands, semi-open woodlands and woodland edges. Nest sites are almost always in coniferous trees. Suitable nesting and foraging habitat for this species was felt to be present on the site. Survey methods employed were direct observation, and a systematic nest search.

Aimophila aestivalis (Bachman's sparrow)—Tennessee 'Endangered'

Traditional habitat for this species is open, oak woodlands with herbaceous groundcover, or grassy openings in mature pine woodlands. This species can also be found in old fields, eroded hillsides, clear-cuts replanted with young pines or edge habitats with scattered large pines. This species places its nest on the ground at the base of grass clumps. Habitat existing on the site was considered to be "marginal" at best. The only herbaceous, old field type of habitat present was eliminated during road grading and construction activities. None of the other habitats are present, except possibly the edge habitat with scattered large pines. Survey methods employed were direct observation and species-specific vocalizations.

Ammodramus savannarum (Grasshopper sparrow)—Tennessee 'In Need of Management'

Habitat for this ground-nesting species is open, grassy, or weedy meadows, hayfields or lightly grazed pastures with a minimal intrusion of woody shrubs. The "marginal" habitat for the site was given for the band of herbaceous, weedy vegetation near the access road that was eliminated, following the initial field survey, by road grading and construction in another project. No habitat for this species remained on the site.

Chondestes grammacus (Lark sparrow)—Tennessee 'Threatened'

Habitat for this ground-nesting species is bare, old fields with sparse vegetation and heavily grazed pastures with patches of bare soil and sparse shrub growth. The "marginal" habitat

for the site was given for the band of herbaceous, weedy vegetation near the access road that was eliminated, following the initial field survey, by road grading and construction in another project. No habitat for this species remained on the site.

Circus cyaneus (Northern harrier)—Tennessee 'In Need of Management'

Only wintertime migrants of this species are present in Tennessee. Foraging habitat for this species includes broad, open uplands and brushy lowland fields and idle grasslands. The only suitable foraging habitat for this species on the site was the band of herbaceous, weedy vegetation near the access road that was eliminated, following the initial field survey, by road grading and construction in another project. No suitable foraging habitat for this species remained on the site.

Pooecetes gramineus (Vesper sparrow)—Tennessee 'In Need of Management'

Habitat for this ground-nesting species includes fields, pastures, roadsides or other short grass habitats with scattered shrubs, used as singing perches. The "marginal" habitat for the site was given for the band of herbaceous, weedy vegetation near the access road that was eliminated, following the initial field survey, by road grading and construction in another project. No habitat for this species remained on the site.

Sphyrapicus varius (Yellow-bellied sapsucker)—Tennessee 'In Need of Management'

This late fall, winter, and early spring species utilizes mature deciduous or mixed woodlands with canopy openings, also woodlots and orchards. Suitable foraging habitat for this species existed on the site. Survey methods included direct observation.

Thryomanes bewickii bewickii (Bewick's wren)—Tennessee 'Threatened'

Habitat for this species includes thickets, brush piles, and fence rows in otherwise open or semiopen terrain. This species will also use second growth scrub habitats, brushy forest openings, and forest clearcuts. This species nest in cavities or thick vegetation or brush piles. Habitat existing on the site was considered to be "marginal" at best and included the partially wooded wetland near the access road and possibly some scrub, second growth habitats. Survey methods employed were direct observation, and species-specific vocalizations.

Tyto alba (Common barn owl)—Tennessee 'In Need of Management'

Foraging habitat for this species includes woodland edges and clearings, rural and urban open grasslands, marshes and hayfields. Nesting habitat for this species includes caves, hollow trees, or other manmade or natural cavities. There was no suitable nesting habitat present on the

site. Suitable foraging habitat included the band of herbaceous, weedy vegetation near the access road that was eliminated, following the initial field survey, by road grading and construction in another project. Other suitable forging habitat would be the sparsely wooded, herbaceous wetland, the herbaceous road beds and woodland edge habitats present. Survey methods included direct observation.

Mammalia

Condylura cristata (Star-nosed mole)—Tennessee 'In Need of Manag*ement'*

Suitable habitat for this species includes low, moist woodlands and meadows, marshes or wetland habitats, where the soil is soft and suitable for burrowing and foraging. Suitable habitat on the site was considered "marginal", and would include the herbaceous wetland near the access road, and the wet, herbaceous or wooded depressions in the stream riparian corridors. Survey methods employed were direct observation of burrows or other 'sign', qualitative searches, use of artificial ground covers and construction of drift fence and pitfall arrays.

Corynorhinus rafinesquii (Eastern big-eared bat)—Tennessee 'In Need of Management'

Winter roosting habitat for this colonial species includes caves and abandoned mines. Summer roosting habitat includes hollow trees, abandoned buildings, rock crevices, and areas beneath sloughing tree bark. This species forages along wooded streams or wooded hillsides adjacent to streams. On the site, there was no winter or summer roosting habitat for this species, and the small, probably wet-weather character of the streams on the site rendered foraging habitats both ephemeral and "marginal" in quality.

Myotis leibii (Eastern small-footed bat)—Tennessee 'In Need of Management'

Winter roosting habitat for this colonial species includes caves and abandoned mines. Summer roosting habitat includes abandoned buildings, beneath rocks or in holes in hillsides. This species forages over streams, ponds and along cliffs, ledges or mixed woodlands. On the site, there is no winter roosting habitat, and very "marginal" summer roosting habitat. Foraging habitat over the small streams on the site was both ephemeral and "marginal" in quality, but could exist for this species within the mixed woodlands.

Myotis sodalis (Indiana bat)—Federal and Tennessee 'Endangered'

Winter roosting habitat for this colonial species includes caves and abandoned mines. Summer roosting habitat includes large, hollow trees, and areas beneath sloughing tree bark. This species forages along streams or in the canopy of mature deciduous, riparian woodlands. On the

site, there was neither winter nor summer roosting habitat, nor suitable foraging habitat for this species, due to the absence of caves, large hollow trees and mature woodlands.

Parascalops breweri (Hairy-tailed mole)—Tennessee 'In Need of Management'

Suitable habitat for this species is woodlands, pastures and other well-drained sites with loose, sandy or loamy soils. This species avoids wet depressions, or areas with clay soils. Following the initial field survey, suitable habitat for this species was felt to be present on the site. Subsequently, the lack of sandy or loose, well-drained soils in upland areas, and prevalence of gravel/clay soils would strongly act against the presence of this species. This lack of suitable habitat and the fossorial nature of this species make collection extremely difficult. Survey methods employed were qualitative searches and the use of artificial ground covers.

Sorex longirostris (Southeastern shrew)—Tennessee 'In Need of Management'

This species utilizes a wide variety of habitats, ranging from marshes and wetlands, to upland grass and old field habitats, to dry upland hardwood woodlands and thickets. Virtually all of the site was considered suitable habitat for this species. Survey methods employed were drift fences and pitfall arrays, pitfalls in association with downed or rotting logs, and free-standing pitfalls in low, wet stream riparian habitats.

Synaptomys cooperi (Southern bog lemming)—Tennessee 'In Need of Management'

Suitable habitat for this species includes bogs, marshes, wetlands, mesic grasslands, shrub habitats and woodlands. This species prefers dense growths of herbaceous (sedge, grass, broomsedge) ground cover. This species builds both surface and underground runways. Suitable habitat on the site would include the herbaceous wetland near the access road, and the wet, herbaceous, shrubby or wooded depressions in the stream riparian corridors. Survey methods employed were direct observation of burrows or other 'sign', Sherman live-traps, use of artificial ground covers, and construction of drift fence and pitfall arrays.

Zapus hudsonius (Meadow jumping mouse)—Tennessee 'In Need of Management'

Suitable habitat for this species includes thick vegetation near stream and pond margins, open grassy fields, shrubby woodland clearings or edges, and herbaceous marshes. On the site, some habitat was lost when the band of herbaceous, weedy vegetation near the access road that was eliminated by road grading and construction in another project. Remaining habitat on the site would be the herbaceous wetland near the access road, and the wet, herbaceous or shrubby depressions in the stream riparian corridors. Survey methods employed were Sherman live-traps and construction of drift fence and pitfall arrays.

2.3 CAPTURE AND OBSERVATION METHODS

Direct Observation of Species, or Species-Specific Sign

During field activities conducted on the site, notations were made in field notes and in project databases when sensitive terrestrial animal species in the vertebrate classes of Mammalia, Aves, Reptilia and Amphibia were observed, or when species-specific sign (tracks, vocalizations, fur, feathers, skeletal remains, etc) was identified.

Species Capture Methods

Drift Fence—Pitfall Array: A vertically staked, 3-ft high, fabric silt fence was used to construct a drift fence within the herbaceous/scrub-shrub/young deciduous wetland located immediately north of Melton Branch Road. This fence was placed to extend across the wetland, encompassing portions of herbaceous, emergent vegetation and scrub-shrub/young deciduous sapling habitat within the lentic surface water. A perpendicular wing of drift fence was placed to encompass adjacent, more upland terrestrial habitat. The ground-contact edge of the fence and wing were buried, and posthole diggers were used to install seven pitfall traps (large coffee cans) at intervals along the base on each side of the main fence and wing. During noncollection periods, the arrays were deactivated by covering the cans. This array was targeted to resident amphibian, reptile and small mammal species. Species collected or observed were recorded in field notes, and included in databases.

Natural Barrier Pitfall Arrays: At eight locations in deciduous upland, mixed (deciduous and pine) upland, mixed riparian, and deciduous riparian woodlands, and at one location within a cane-herbaceous wetland, natural barriers (rotting logs in full contact with the ground) were utilized as natural drift fences. At the base on each side of the natural barrier, between two and four 16-oz cups were buried to ground level. At a tenth location, in the cane-herbaceous wetland adjacent to a small stream, six cups were buried at ground level within, or spanning natural runways within the herbaceous ground cover. During noncollection periods, the natural barrier arrays were deactivated providing a means for escape from the cup. These arrays were targeted to resident amphibian, reptile and small mammal species. Species collected or observed were recorded in field notes, and included in databases.

Artificial Ground Covers: Two sheets of 4 ft × 8 ft plywood were cut into eight equal 2 ft × 4 ft sections. Individual sections were placed directly on the ground within deciduous upland, mixed (deciduous and pine) upland, mixed riparian, and deciduous riparian woodland habitats, within the cane-herbaceous wetland, and in the herbaceous/scrub-shrub/young deciduous wetland. The ground covers remained active continuously and were inspected for small mammal, reptilian and/or amphibian species usage at periodic intervals.

Sherman Live Traps: During two 3-day trapping periods, three and five-trap clusters of aluminum, Sherman live traps were set at various locations within deciduous upland, mixed (deciduous and pine) upland, mixed riparian, and deciduous riparian woodlands, and within scrub-shrub, herbaceous, woody slash and cane-herbaceous wetland habitats. These trap clusters were baited using combinations of peanut butter, rolled oats, and cracked corn, and were targeted to small mammal species. Species collected or observed were recorded in field notes, and included in databases. Traps were inspected daily. Captures were identified to genus and released.

Qualitative Survey - Minnow Traps: Two standard metal minnow traps were set within the standing water of the herbaceous/scrub-shrub/young deciduous wetland, located immediately north of the Melton Branch Road. These traps were set during three 3-day intervals, and were inspected daily for amphibian, reptilian and/or small mammal species captures. Captures were identified to genus and released.

Qualitative Survey—Dip-Netting Melton Branch Road Wetland Pool: Multiple dip-net sampling was conducted in the surface water pool to sample for adult and/or larval forms of amphibians and reptiles within the herbaceous/scrub-shrub/young deciduous wetland, located immediately north of the Melton Branch Road. Submerged and emergent, herbaceous vegetation within the wetland pond were dip-netted, including the leaf detrital substrate.

Qualitative Survey—Disturbance of Natural and Artificial Surface Debris: Natural surface debris (rocks, rotting logs, terrestrial and aquatic leaf packs) was disturbed in a variety of available habitats to identify vertebrate species use as refugia. Habitats sampled included the small woodland stream in the culvert location, deciduous and mixed woodlands in riparian and upland areas, and streams associated with the cane/herbaceous wetland. These searches were targeted to resident amphibian, reptile and small mammal species. Species collected or observed were recorded in field notes, and included in databases.

Qualitative Survey—Avian Vocalizations

To coincide with the establishment of nesting territories, six 30- to 45-minute microcassette recordings were made during early summer months to record species-specific vocalizations made by avian species within selected habitats on the site. These recordings targeted two sensitive avian species, *Aimophila aestivalis* (Bachman's sparrow) and *Thryomanes bewickii bewickii* (Bewick's wren), whose presence was considered "marginal" based on site habitat availability.

Qualitative Survey—Avian Nest Search

To coincide with the establishment of nesting territories for two sensitive avian species, a comprehensive search of deciduous and coniferous woodland habitats was conducted during the late spring and early summer months. The avian species targeted by this search were *Accipiter cooperii* (Cooper's hawk) and *Accipiter striatus* (Sharp-shinned hawk).

3. RESULTS

The schedule of field activities, including results of all species survey methods used for surveying sensitive terrestrial animal species, is provided in Table 2. No sensitive animal species were captured or observed.

Table 2. Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee

Method	Locale/ Habitate	Date(s) operative	Individual trap-nights	Cumulative trap-nights	Target species	Target species captures, collections, observations	Comments—Non-target species collected or observed
Drift Fence and Pitfall Arrays (7 pitfalls)	Herbaceous wetland at Melton Branch Road	Apr. 20-23, '99 Apr. 23-26,'99 Apr. 27-29,'99 May 10-13,'99	7,7,7,7	21,21, 21,21	Four-toed salamander; Star-nosed mole, Southeastern shrew, Southern bog lemming	none	Decapoda (2)
Qualitative Survey; Minnow Traps (2 traps)	Herbaceous Wetland@Road	Apr. 20-23, '99 Apr. 23-26, '99 Apr.27-29,'99	2,2,2	6,6,6	Four-toed salamander; Star-nosed mole	none	Upland chorus frog (1), Dragonfly nymph
Ground Cover (2 boards)	Herbaceous Wetland@Road	Apr. 23, 26,'99 Apr. 27-29, '99 May 10-13, '99 June 1-2, '99	2,2,6,8,4	2,2,6,8,4	Four-toed salamander; Star-nosed mole	none	Various invertebrates; Decapoda chimneys
Ground Cover (1 board)	Wooded Wet Depression along streambed	Apr. 23,26, '99 Apr. 27-29, '99 May 10-13, '99 June 1-2, '99	1,1,3,4,2	1,1,3,4,2	Four-toed salamander; Star-nosed mole	none	Various invertebrates
Ground Cover (1 board)	Herbaceous road bed	Apr. 23,26, '99 Apr. 27-29, '99 May 10-13, '99	1,1,3,4	1,1,3,4	Eastern slender glass lizard, Southern bog lemming	none	Various invertebrates
Ground Cover (2 boards)	Ridge Top, Mixed Deciduous-Pine Woodland	Apr. 23,26, '99 Apr. 27-29, '99 May 10-13, '99 June 1-2, '99	2,2,6,8,4	2,2,6,8,4	Northern pine snake, Eastern slender glass lizard, Northern & Southern coal skinks, Hairy-tailed mole	none	Various invertebrates
Ground Cover (1 board)	Riparian Deciduous Woodland	Apr. 23,26, '99 Apr. 27-29, '99 May 10-13, '99 June 1-2, '99	1,1,3,4,2	1,1,3,4,2	Eastern slender glass lizard, Hairy-tailed mole, Northern & Southern coal skinks	none	Various invertebrates

Table 2. Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee (continued)

Method	Locale/ Habitate	Date(s) operative	Individual trap-nights	Cumulative trap-nights	Target species	Target species captures, collections, observations	Comments—Non-target species collected or observed
Sherman traps #1 (3 trap cluster)	Wooded stream riparian zone	Apr. 26-27, '99	3	3	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none (see comments)	All disturbed by raccoon, reset to woodland tangle
Sherman traps #1 (3 trap cluster)	Woody tangle in low, wet area in deciduous woodland	Apr. 27-29, '99	3	6	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	
Sherman traps #2 (3 trap cluster)	Partial woodland, above road at wet pool	Apr. 26-29,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	
Sherman traps #3 (3 trap cluster)	Herbaceous roadbed	Apr. 26-29,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	*Peromyscus Sp.* (1)
Sherman traps #4 (3 trap cluster)	Deciduous/Pine woodland on ridge top	Apr. 26-29,'99	3	9	Southeastern shrew, Southern bog lemming	none	
Sherman traps #5 (3 trap cluster)	Riparian deciduous/pine flatwoods	Apr. 26-29,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	One trap disturbed by raccoon
Sherman traps #6 (3 trap cluster)	Cane/herbaceous wetland near stream	Apr. 26-29,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	One trap disturbed by raccoon

Table 2. Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee (continued)

Method	Locale/ Habitate	Date(s) operative	Individual trap-nights	Cumulative trap-nights	Target species	Target species captures, collections, observations	Comments—Non-target species collected or observed
Sherman traps #1 (5 trap cluster)	Woody debris tangle at low, wet, wooded depression (culvert site)	May 10-14,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	*Peromyscus Sp.* (5); Two trap disturbed by raccoon
Sherman traps #2 (5 trap cluster)	Deciduous woodland on knob below fence cut	May 10-14,'99	3	9	Southeastern shrew, Southern bog lemming	none	*Peromyscus Sp.* (1); Two trap disturbed by raccoon
Sherman traps #3 (5 trap cluster)	Young deciduous woodland downslope of knob	May 10-14,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	
Sherman traps #4 (5 trap cluster)	Herbaceous, shrub, cane wetland	May 10-14,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	
Natural Pitfall Array (4 cups)	Deciduous upland above road	Apr. 26-29,'99 May 10-13,'99	3,3	12,12	Four-toed salamander, Southeastern shrew, Southern bog lemming	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (2 cups)	Deciduous/Pine woodland on ridge top	Apr. 26-29,'99 May 10-13,'99	2,2	6,6	Southeastern shrew, Southern bog lemming	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (4 cups)	Riparian deciduous/pine flatwoods	Apr. 26-29,'99 May 10-13,'99	4,4	12,12	Four-toed salamander, Southeastern shrew, Southern bog lemming, Star-nosed mole	none	One cup dug up by raccoon, replaced; Annelida, Millipedes, Coleoptera

Table 2. Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee (continued)

Method	Locale/ Habitate	Date(s) operative	Individual trap-nights	Cumulative trap-nights	Target species	Target species captures, collections, observations	Comments—Non-target species collected or observed
Natural Pitfall Array (3 cups)	Cane/herbaceous wetland near stream	Apr. 26-29,'99 May 10-13,'99	3,3	9,9	Four-toed salamander, Southeastern shrew, Southern bog lemming, Star-nosed mole	none	Annelida, Millipedes, Coleoptera, Decapoda
Natural Pitfall Array (2 cups)	Deciduous woodland in facility site	Apr. 26-29,'99 May 10-13,'99	2,2	6,6	Southeastern shrew, Southern bog lemming	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (3 cups)	Deciduous woodland in facility site	Apr. 26-29,'99 May 10-13,'99	3,3	9,9	Southeastern shrew, Southern bog lemming	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (2 cups)	Deciduous woodland at culvert site	Apr. 26-29,'99 May 10-13,'99	2,2	6,6	Four-toed salamander, Southeastern shrew, Southern bog lemming, Star-nosed mole	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (3 cups)	Along road in young Pine/deciduous woodland	May 10-13,'99	3	9	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (4 cups)	Stream riparian woodland	May 10-13,'99	4	16	Southeastern shrew, Southern bog lemming, Meadow jumping mouse	none	Annelida, Millipedes, Coleoptera
Natural Pitfall Array (6 cups)	Herbaceous, shrub, cane wetland	May 10-13,'99	6	36	Four-toed salamander, Southeastern shrew, Southern bog lemming, Star-nosed mole	none	No natural drift structures; set in runways; Decapoda

Table 2. Terrestrial animal species collection/observation results at the TRU Waste Treatment Facility Site in Melton Valley, Oak Ridge, Tennessee (continued)

Method	Locale/ Habitate	Date(s) operative	Individual trap-nights	Cumulative trap-nights	Target species	Target species captures, collections, observations	Comments—Non-target species collected or observed
Qualitative Searches – Surface Debris, Logs, Rocks	Conducted throughout site by lifting/disturbing surface cover in Aquatic, Riparian and Upland Terrestrial Habitats	June 1-2, 1999	N/A	N/A	Four-toed salamander, Northern & Southern coal skinks, Northern pine snake, Eastern slender glass lizard, Southern bog lemming, Star-nosed mole, Hairy-tailed mole	none	Upland chorus frog, Dusky salamander, Northern slimy salamander, American toad, Brown snake, Smooth earth snake, Worm snake, Five-lined skink, Ground skink,
Qualitative Search – Dip-net Wetland Pool; 30-minute interval	Conducted in wetland pool at Melton Branch Road, 50 dips in lentic water associated with emergent vegetation and leaf detritus	June 1, 1999	N/A	N/A	Four-toed salamander	none	Decapoda, Upland chorus frog tadpoles, Odonata nymphs, 'waterboatmen'
Qualitative Search – Avian Nests	Conducted within all deciduous and pine woodlands, including buffer	June 1-2, 1999	N/A	N/A	Cooper's hawk, Sharp-shinned hawk	none	Whip-poor-will female with 2 nestlings
Avian Vocalizations	Recordings conducted at three locations on successive days in habitat most suitable, each 30-45 min.	June 1-2, 1999	N/A	N/A	Bachman's sparrow, Bewick's wren	none	Mourning dove, Blue jay, Crow, Wood thrush, Red-eyed vireo, Hooded warbler, Northern cardinal, Song sparrow, Carolina wren

4. CONCLUSIONS

A total of 461 capture-nights, accumulated through multiple survey methods (constructed and natural barrier pitfall arrays, ground covers, live-trap clusters, minnow traps) were targeted at sensitive terrestrial animal species potentially present on the site. No sensitive terrestrial animal species were captured or observed during the course of this survey effort.

Timed-interval recordings and thorough qualitative search methods were employed to survey sensitive terrestrial animal species potentially present on the site. No sensitive terrestrial animal species were captured or observed during the course of this survey effort.

Several factors combine to minimize the suitability of the site for use by sensitive terrestrial animal species. First, the acreage within the project site was relatively small. Secondly, there were both limited diversity and quality of habitats suitable for use by sensitive terrestrial animal species. Finally, the habitats present on the project site have undergone land use disturbances, both past and present.

5. REFERENCES

Choate, J. R., J. K. Jones, J. R. Jones, and C. Jones. 1994. Handbook of Mammals of the South-Central States. LSU Press. Baton Rouge, La., and London. 304 pp.

Harvey, M. J. 1992. Bats of the Eastern U.S. Arkansas Game and Fish Commission/USFWS/ TTU. 46 pp.

Mitchell, J. M., E. R. Vail, J. W. Webb, J. W. Evans, A. L. King, and P. A. Hamlett. 1996. Survey of Protected Terrestrial Vertebrates of the Oak Ridge Reservation. Final Report. Lockheed Martin Energy Systems for U.S. Department of Energy. ES/ER/TM-188/R1. 62 pp.

Nicholson, C. P. 1997. Atlas of the Breeding Birds of Tennessee. The University of Tennessee Press. Knoxville, Tenn. 426 pp.

Redmond, W. H. and A. F. Scott. 1996. Atlas of Amphibians in Tennessee. Miscellaneous Publication No. 12. Austin Peay State University. Clarksville, Tenn. 94 pp.

Stokes, D. and L. Stokes. 1996. Field Guide to Birds—Eastern Region. Little, Brown and Company. Boston, New York, Toronto, and London. 471 pp.

Whitaker, J. O., Jr. and W. J. Hamilton, Jr. 1998. Mammals of the Eastern United States. Third edition. Cornell University Press. Comstock Publishing Associates. Ithaca and London. 583 pp.

Wilson, L. A. 1995. Land Manager's Guide to the Amphibians and Reptiles of the South. The Nature Conservancy, SE Region. Chapel Hill, N.C. 324 pp. + Appendices.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX C.3

FINDINGS OF SURVEY FOR RARE PLANTS ON THE PROPOSED TRU WASTE FACILITY SITE

THIS PAGE INTENTIONALLY LEFT BLANK

FINDINGS OF THE SURVEY FOR RARE PLANTS ON THE PROPOSED TRANSURANIC WASTE TREATMENT FACILITY SITE IN MELTON VALLEY, OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

August 25, 1999

prepared for:

Bechtel Jacobs Company LLC
under contract number DE-AC05-98OR22700

prepared by:

Jacobs Environmental Management Team
and
Larry Pounds

CONTENTS

1. INTRODUCTION 1

2. METHODOLOGY 3

3. RARE PLANT SURVEY RESULTS 6

4. CONCLUSIONS 7

5. REFERENCES 8

TABLES

1 Vascular plant species reported on ORR that are listed by state or federal agencies 4

2 Additional rare plant species reported near ORR that might be present on the site based on available habitat 5

THIS PAGE INTENTIONALLY LEFT BLANK

1. INTRODUCTION

Approximately five acres have been identified as a lease parcel for a proposed Transuranic (TRU) Waste Treatment Facility (the site) in Melton Valley at the Oak Ridge National Laboratory (ORNL) in Oak Ridge, Tennessee. A rare plant survey of vascular plants on the Oak Ridge Reservation (ORR) was conducted in 1996 but did not focus on the site (ORNL 1996). Complete and accurate identification of all resources on the site is needed to support proper planning, documentation, and management. A survey for rare plants at the site will complete this requirement for plants.

DESCRIPTIVE OVERVIEW OF SITE

The site is at the base of Copper Ridge on the northwest side and includes part of a small side ridge off Copper Ridge, a drainage to the west of the side ridge, a drainage to the east of the side ridge, and an area within an existing fence on the northeast portion of the site. The Nolichucky Shale (Carver and Slater 1994) outcrops in upland areas. Partial clearing along two site boundaries for upgrading the access road and for fence relocation has left part of the site unvegetated; most of the 5-acre site is still vegetated. Trees are generally young and presumably most of the site started succession to the present forest at the creation of ORR in 1942.

The flat area along Melton Valley Access Road has been cleared of vegetation as well as a strip along the future fence location on the south side of the site. Little of the west drainage is within the site boundaries. Most of the west drainage was subject to "beetle cut" several years ago and is now cleared. There is a small, mostly open wetland in this drainage near Melton Valley Access Road. There is some black willow (*Salix nigra*) and young green ash (*Fraxinus pennsyvanica*) in the wetland. See the wetland report on this site for more information on this area.

Virginia pine (*Pinus virginiana*) is dominant in the western slope area. The Virginia pines drop out toward the eastern part of the slope. Some white pines are present in the middle section. As the pines fade out, sugar maple (*Acer saccharum*) and various oaks become more common. The dominant trees in the eastern drainage area are red bud (*Cercis canadensis*), tulip poplar (*Liriodedron tulipifera*), red maple (Acer rubrum) and box elder (*Acer negundo*). Soft rush (*Juncus effusus*} occurs in wetter areas here. An old jeep road is in this drainage area. The exotic species Japanese honeysuckle (Lonicera japonica) and Nepal grass (*Microstegium virmineum*) are common in the drainage. The drainage has been blocked at one point by a dirt road creating a small pool of water. Black willow grows on the edge of the pool and a sedge in the pool. The upper middle slope has an incomplete canopy covering. Rock outcrops at the

surface in this area. Oaks are most common here but there are many tree species including yellow pine. Several small trees or shrubs including blueberries (*Vaccinium arboreum* and *Vaccinium stamineum*), rusty viburnum (*Viburnum rufidulum*), juneberry (*Amelanchier* sp.) and hop hornbeam (*Ostrya virginiana*) also occur here. A small fenced area on the eastern edge of the site contains buildings, paved areas and lawns, but no native vegetation.

2. METHODOLOGY

The project site was surveyed by walking the entire site, a buffer zone of approximately 75 ft, and some adjacent areas with transects 20 ft apart, but varying depending on the visibility of land between the lines walked. This method is described in more detail in *Survey of Protected Vascular Plants on the Oak Ridge Reservation, Oak Ridge, Tennessee* (ORNL 1996). A rare plant survey was conducted (ORNL 1988) over an area that includes part of the site and no listed plants were found. Awl (ORNL 1996) recommended new surveys be performed if the previous survey is more than 5 years old.

Target species for this survey were developed from Sect. 3.4 in ORNL 1996 and current, updated state and federal listings (TDEC 1999). Target species included all state-listed plants reported on ORR and surrounding areas. No federally listed plant species have been reported on ORR or surrounding areas. Table 1 lists target species reported on ORR and Table 2 lists target species known only from surrounding areas. Two state-listed species, Pursh's wild-petunia (*Ruellia purshiana*) and river bulrush (*Scirpus fluviatilis*) have been reported in the Melton Valley area but were not targets in the 1988 survey. These species had not been reported on the ORR or even in the state of Tennessee in 1988. They were added as target species for this survey.

The project site was surveyed for rare plants April 20, 1999. A second visit to the site was made May 12, 1999, to determine if purple fringeless orchid (*Platanthera peramoena)* and/or river bulrush might have been overlooked because of their immaturity during the first visit. No other visits were made because no target species could not have been observed during April and May.

Table 1. Vascular plant species reported on ORR that are listed by state or federal agencies

Species	Common name	Habitat on ORR	Status code
Aureolaria patula	Spreading false-foxglove	River bluff	(C2), T
Carex gravida	Heavy sedge	Dry woods, open areas	S
Carex oxylepis var. pubescense[a]	Hairy sharp-scaled sedge	Shaded wetlands	S
Cimicifuga rubifolia	Appalachian bugbane	River slope	(C2), T
Cypripedium acaule	Pink lady's slipper	Dry to rich woods	E-CE
Delphinum exaltatum	Tall larkspur	Barren, open woods	(C2), E
Diervilla lonicera	Northern bush-honeysuckle	River bluff	T
Draba ramosissima	Branching whitlow-grass	Limestone cliff	S
Elodea nuttallii	Nuttall waterweed	Pond, embayment	S
Fothergilla major	Mountain witch-alder	Woods	T
Hydrastis canadensis	Golden seal	Rich woods	S-CE
Juglans cinerea	Butternut	Slope near stream	(C2),T
Lilium canadense	Canada lily	Moist areas in woods or at woods edge	T
Lilum michiganense[b]	Michigan lily	Moist woods	T
Liparis loeselii	Fen orchid	Forested wetland	E
Panax quinquifolius	Ginseng	Rich woods	S-CE
Platanthera flava var. herbiola	Tuberculed rein-orchid	Forested wetland	T
Plantanthera peramoena	Purple fringeless orchid	Wet meadow	S
Ruellia purshiana	Push's wild-petunia	Dry, open, rocky woods	S
Saxifraga careyana	Carey saxifrage	Moist, shaded rock outcrops	S
Scirpus fluviatilis	River bulrush	Wetland	S
Spiranthes lucida	Shining ladies-tresses	Boggy wetland	T
Thuja occidentalis	Northern white cedar	Rocky river bluffs	S
Viola tripartita var tripartita	Three-parted violet	Rocky, moist woods	S

[a] *Carex oxylepis var. pubescens* has not been relocated during recent surveys.
[b] *Lilium michiganense* is believed to have been extirpated from ORR by the Melton Hill impoundment.

(C2) = special concern for the U.S. Fish and Wildlife Service (listed under the formerly used C2 candidate designation)
E = endangered in Tennessee
T = threatened in Tennessee
S = special concern in Tennessee
CE = status due to commercial exploitation

Table 2. Additional rare plant species reported near ORR that might be present on the site based on available habitat

Species	Common name	Habitat on ORR	Status code*
Agalinis auriculata	Earleaf false-foxglove	Calcareous barren	(C2), E
Berberis canadensis	American barberry	Rocky bluff, creek bank	S
Gnaphalium helleri	Catfoot	Dry woodland edge	S
Liatris cylindracea	Slender blazing star	Calcareous barren	E
Lonicera dioica	Mountain honeysuckle	Rocky river bluff	S
Meehania cordata	Heartleaf meehania	Moist calcareous woods	T
Pedicularis lanceolata	Swamp lousewort	Calcareous wet meadow	T
Solidago ptarmicoides	Prairie goldenrod	Calcareous barren	E
*Pycnanthemum torrei***	Torrey's mountain-mint	Calcareous barren edge	**
*Allium burdickii or A. tricoccom****	Ramps	Moist woods	S-CE

[a]Carl Nordman, state botantist (personal communication) plans to list *P. torrei* with the status S. pending consideration by the scientific advisory committee.
[b]Ramps have been reported near ORR, but there is not sufficient information to determine which of the two species is present or if the occurrence may have been introduced by planting. Both species of ramps have the same state status.

(C2) = special concern for the U.S. Fish and Wildlife Service; listed under the formerly used C2 candidate designation
CE = status due to commercial exploitation
E = endangered in Tennessee
T = threatened in Tennessee
S = special concern in Tennessee

3. RARE PLANT SURVEY RESULTS

The following target species have been reported on ORR and had potential habitats on the site. These species could have been detected on the site during the site visits but they were not found.

1. *Carex gravida*—dry woods or open areas
2. *Cypripedium acaule*—pine or mixed pine hardwood
3. *Juglans cinerea*—deciduous forest
4. *Lilium canadense*—moist, shaded drainages
5. *Platanthera peramoena*—opens wetlands or meadows
6. *Scirpus fluviatilis*—open wetland

Panax quinquefolius may rarely be found in forests as immature as that on the site and could have been detected at the times of the visits, but was not found.

4. CONCLUSIONS

No state or federal listed species are on or adjacent to the site. Therefore, no impacts to listed plant species would be anticipated from implementation of the proposed action.

5. REFERENCES

Carver, M., and M. Slater. 1994. *Architectural/Historical Assessment of the Oak Ridge National Laboratory, Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*

ORNL (Oak Ridge National Laboratory). 1996. Awl, D. J., L. R. Pounds, B. A. Rosensteel, A. L. King, and P. A. Hamlett. *Survey of Protected Vascular Plants on the Oak Ridge Reservation, Oak Ridge, Tennessee.* ES/ER/TM-194.

TDEC (Tennessee Department of Environment and Conservation). 1999. Nordman, Carl. Tennessee Natural Heritage Program Rare Plant List.

APPENDIX C.4

BASELINE NOISE MONITORING IN MELTON VALLEY FOR THE PROPOSED TRU WASTE FACILITY SITE

DRAFT

BASELINE NOISE MONITORING IN MELTON VALLEY, OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

September 27, 1999

prepared for:

Bechtel Jacobs Company LLC
under contract number DE-AC05-98OR22700

prepared by:

Jacobs Environmental Management Team
and
S. Brooks

CONTENTS

1. INTRODUCTION 1

2. METHODS 2
2.1 MONITOR LOCATIONS 2
2.2 MONITOR SETUP 4
2.3 INSTRUMENTATION 4

3. RESULTS 5

4. CONCLUSIONS 18

5. REFERENCES 19

ADDITIONAL BACKGROUND NOTES 20

FIGURES

1 Noise monitoring locations on or near the proposed TRU Waste Treatment Project site boundary 3
2 Noise Levels at Location 1, events a and b, in Melton Valley 6
3 Noise Levels at Location 2, events a, b, and c, in Melton Valley 7
4 Noise Levels at Location 3, events a, b, and d, in Melton Valley 8
5 Noise Levels at Location 4, events a, b, and c, in Melton Valley 9
6 Noise Levels at Location 5, events a and b, in Melton Valley 10
7 Noise Levels at Location 6, event e, in Melton Valley 11
8 Noise Levels at Location 7, events c and e, in Melton Valley 12
9 Noise Levels at Location 8, event d, in Melton Valley 13
10 Noise Levels at Location 9, events d and e, in Melton Valley 14
11 Noise Levels at Location 10, events d and e, in Melton Valley 15
12 Noise Levels at Location 11, event d, in Melton Valley 16

TABLES

1 Noise monitoring data for Melton Valley proposed TRU waste facility 17

THIS PAGE INTENTIONALLY LEFT BLANK

Baseline Noise Monitoring
In Melton Valley for the
Proposed TRU Waste Facility Site

1. INTRODUCTION

This noise monitoring program was implemented to provide baseline data for evaluation of noise levels that may be caused by construction, operation, and decommissioning of a transuranic (TRU) Waste Treatment Facility in Melton Valley on the Oak Ridge Reservation in Oak Ridge, Tennessee. Two primary anthropogenic noise sources currently exist near the proposed lease site (the site) and are captured by this monitoring program. The two anthropogenic sources are: (1) motor vehicle traffic and (2) industrial activities, equipment, fans, generators, fans, etc. Non-anthropogenic noise sources in Melton Valley include wildlife vocalizations, running water, and noise related to wind. It is anticipated that some increase in the anthropogenic noise sources would take place as a result of the proposed action.

The design of this noise monitoring program was based on the requirements of the Noise Control Act of 1972 [23 *Code of Federal Regulations* (CFR) 722], the Federal-aid Highway Act of 1970 (23 *CFR* 722), and the site topography and currently ongoing site-related activities. The primary considerations in selecting monitoring locations and detection parameters was that comparable data could be collected during and after the proposed action, if needed, and that the data be usable for evaluating current conditions.

2. METHODS

2.1 MONITORING LOCATIONS

Monitoring locations encompassed the proposed lease site and the transportation corridor that will be used by the facility. The locations were representative of: the highway, new access road, site perimeter, and topographic gradients which can influence sound transmission. Two locations were near wetlands to consider sensitive resources if desired. Locations that would be replicable after construction were selected should post-action monitoring ever be desired.

A total of eleven monitoring locations were chosen for this program and are described below and depicted on Figure 1.

1. Centering the new access road where it intersects Highway 95 at the existing fence line.

2. Approximately halfway between Highway 95 and the proposed site, near a triple well assembly, between new road and old road.

3. Approximately 32 feet south of the southwest corner of the proposed site fence line.

4. At peak of proposed site on the south fence line immediately south of the fence post with diagonal supports east and west of it.

5. On the northwest corner of a flat gravel pad immediately east of the emergency generator (#7882), within the Melton Valley Tanks fenced area and above the grade/elevation of the generator and existing fence line.

6. Immediately south of the old Melton Valley Access Rd. near construction map location stake 1.5:1 C-0.26.

7. Immediately west of existing culvert at northwest corner of the proposed site fence line, immediately south of old Melton Valley Access Road.

8. Directly on the southeast corner of the proposed site fence line.

9. Immediately south of old Melton Valley Access Road and west of 781 Access Road, near construction map location stake 21.6.

10. Approximately halfway between locations 3 and 4; south of fence line at post supported with diagonal supports east and west of it.

11. Approximately halfway up the east fence line dividing the proposed site from the existing Melton Valley Tanks area; north and below wetlands B.




Fig. 1. Noise monitoring locations on or near the proposed TRU Waste Treatment Project site boundary.

2.2 MONITOR SETUP

Monitors were placed 1.5 m aboveground and without impediment such as trees that might brush against them. Tripods were used to standardize microphone height to approximately 1.5 m as much as possible. When appropriate, they were approximately 15 m from the road centerline. This setup was in accordance with U.S. Department of Transportation (DOT) guidelines, should comparison with their criteria ever be desired, and provided consistency for the non-roadway locations.

2.3 INSTRUMENTATION

The instruments used were Metrosonics Inc. db-3080 noise monitors with the standard available microphone and windscreen accessories. This met Federal Highway Administration Program recommendation that monitors be an ANSI S1.4-1983, TYPE II device or better.

Detection limits. The typical operating range for these instruments is between 40 and 140 decibels (dB) with amplitude linearity of ±0.7 dB, and amplitude resolution of 0.1 dB. The lowest sound levels recorded at any time or sample point were over 40 dB so instrument sensitivity was not a problem. Most low noise level times were approximately 45 dB or greater. The monitors are capable of detecting frequencies between 0.125 kHz and 10 kHz. The data logging was weighted for frequencies in the "A" range. Selection of a frequency weighting was intrinsic to use of the monitors, and the "A" range weighting was selected because it is representative of human hearing.

Data logging. Data were collected over a 24-hour (diurnal) period using 5 instruments concurrently during each collection event. This should allow discrimination between differences due to location versus differences due to time (different day). Some monitoring locations were sampled more than once to observe variations in weather, animal, and construction activity. The instruments were set up with a response rate of 16 samples per second, a 3 dB exchange rate, and 1-hour time history intervals. The data logger within each monitor automatically integrated these measurements into noise levels for a chosen time period (e.g., minute, hour, day) with the logarithmic aspect of decibel measurement incorporated into the integration.

Data reporting. For this survey, a Leq on an hourly basis was used to illustrate the diurnal runs at each sample location. Hourly Leqs are the expression used for DOT noise abatement criteria, and were also the most suitable basis for evaluation of diurnal patterns. Raw data files also include the following information: Lav (= Leq at 3 dB exchange rate with this instrument), Lmax, Lpeak, and amplitudes at 0.0, 10.0, 50.0, and 99.9%. A 3dB exchange rate is used in DOT criteria and for Leq calculations. Occupational Safety and Health Act (OSHA) requirements utilize a 5 dB exchange rate so the Leq data should not be applied to OSHA evaluations. The Lav/Leq, Lmax, and Lpeak are available for the 24-hour period as a whole and for each hour during that sampling run.

Field information. Climatic conditions were noted for each sampling event along with any known ambient noise sources or unique events. Temperatures ranged from the low 60s (°F) to the low 90s, humidity varied from 57-100%, winds were calm, and the barometer was at 30 during the monitoring program.

3. RESULTS

Figures 2 through 12 illustrate noise levels at each monitoring location on a diurnal basis. The hourly Leqs and the Lmax Lav for each event are presented in Table 1. Raw data files are provided as Attachment 1.

Data Anomalies. In a few instances, the data logger recorded only 23 Leqs during a 24-hour run. This occurred due to minor variations in the internal clocks of the monitors that resulted in monitor shutdown just before the last hour of data was integrated in the logger. As can be seen in Attachment 1, data from the first diurnal event were reported as Leq on a minute basis necessitating separate manipulation of these data to derive the hourly Leq. Finally, although five monitors were programmed and placed in the field during each monitoring event, battery failure resulted in the failure of three monitors during event "c."




Figure 2. Noise Levels at Location 1, events a and b, in Melton Valley.




Figure 3. Noise Levels at Location 2, events a, b, and e, in Melton Valley.




Figure 4. Noise Levels at Location 3, events a, b, and d, in Melton Valley.




Figure 5. Noise Levels at Location 4, events a, b, and c, in Melton Valley.




Figure 6. Noise Levels at Location 5, events a and b, in Melton Valley.




Figure 7. Noise Levels at Location 6, event e, in Melton Valley.




Figure 8. Noise Levels at Location 7, events c and e, in Melton Valley.




Figure 9. Noise Levels at Location 8, event d, in Melton Valley.




Figure 10. Noise Levels at Location 9, events d and e, in Melton Valley




Figure 11. Noise Levels at Location 10, events d and e, in Melton Valley.




Figure 12. Noise Levels at Location 11, event d, in Melton Valley.

Table 1. Noise monitoring data for Melton Valley proposed TRU waste facility
[noise levels (Leq per hour) in Melton Valley, Oak Ridge, Tennessee]

Location number and sample event	1a	1b	2a	2b	2e	3a	3b	3d	4a	4b	4c	5a	5b	6e	7c	7e	8d	9d	9e	10d	10e	11d
Hour (military)																						
0	60.5	61.9	53.1	53.5	55.4	56.1	61.2	58.2	58.4	58.7	59.3	59.6	59.0	57.4	55.9	63.6	63.1	60.5	59.9	57.2	58.8	62.6
1	59.0	60.3	51.7	51.3	54.5	53.3	54.5	57.4	55.8	55.5	57.7	58.6	58.2	56.0	53.8	58.6	60.5	59.4	58.9	56.3	57.6	61.5
2	56.7	56.6	49.4	48.7	53.3	50.1	50.4	55.1	52.3	51.1	55.3	57.8	56.9	54.5	51.9	57.9	59.3	58.0	57.9	54.1	55.3	60.4
3	52.7	55.9	46.6	46.6	51.3	49.3	49.9	53.1	50.6	49.5	51.3	57.3	56.4	52.9	49.8	56.2	58.5	54.0	55.2	51.0	51.6	57.1
4	52.9	57.5	42.9	42.4	47.6	47.6	48.2	47.3	49.1	48.2	48.9	57.1	56.2	54.2	48.0	56.4	57.6	48.8	53.5	46.9	52.9	55.0
5	60.9	64.6	43.4	43.2	46.6	46.6	48.5	45.1	48.2	47.9	47.8	57.1	55.9	47.5	47.0	53.2	57.1	48.5	49.1	42.5	43.5	54.6
6	60.6	68.4	45.6	45.3	47.0	50.6	50.5	58.8	49.3	48.1	50.3	56.6	56.3	48.3	51.8	57.6	60.8	57.3	49.3	61.7	43.5	61.4
7	59.4	67.8	45.8	66.2	71.0	50.4	52.5	52.1	49.6	51.1	49.6	56.8	57.1	49.0	56.7	50.0	58.4	54.5	51.2	52.8	43.4	57.9
8	58.9	66.3	44.8	73.1	72.5	50.3	52.5	55.1	49.9	53.0	51.8	57.3	57.0	51.8	72.6	55.2	59.3	56.0	59.2	56.5	46.9	60.7
9	55.6	64.9	43.9	78.2	74.7	50.0	52.4	51.3	50.1	51.4	53.5	58.0	56.8	50.9	77.4	52.7	57.7	51.0	57.0	49.8	52.1	57.3
10	54.0	63.1	43.8	69.6	71.7	49.8	50.2	47.1	49.0	52.3	58.2	57.7	57.2	54.2	80.7	55.6	57.0	52.4	59.0	47.5	54.5	55.3
11	55.9	64.7	45.8	48.5	65.0	49.5	51.3	46.1	49.2	51.3	54.0	57.8	56.7	51.9	71.2	50.7	56.3	48.4	56.5	45.3	51.8	56.5
12	55.8	63.5	44.9	46.4	59.4	51.6	50.1	50.3	51.2	49.9	58.7	58.0	56.8	49.3	51.9	51.1	57.2	55.8	55.3	51.8	50.5	56.8
13	55.6	64.0	63.5	47.4	70.3	50.4	49.8	50.8	49.7	49.9	53.6	57.8	57.2	48.6	51.9	51.2	56.1	56.2	55.1	51.0	51.1	58.4
14	56.4	64.0	54.7	55.8	61.7	50.8	49.7	48.9	50.5	49.0	53.0	57.2	56.5	50.7	50.8	52.5	55.4	54.2	54.5	48.2	51.6	55.4
15	59.7	67.7	46.3	54.5	77.2	49.9	48.9	49.6	49.4	48.8	52.3	56.9	56.4	49.4	57.1	46.3	54.7	64.2	50.3	49.7	47.4	57.7
16	59.7	67.0	46.4	49.7		49.4	47.6	59.0	49.6	48.5	52.4	57.1	56.2	51.1	52.3		56.1	53.2		54.3	46.4	54.9
17	63.1	67.1	45.6	49.3	49.4	48.1	46.0	58.6	48.5	48.3	49.4	57.0	56.3	53.4	47.3	46.4	55.0	53.3	47.8	53.7	44.7	53.3
18	61.7	64.3	44.1	46.2	49.8	47.8	47.1	42.4	48.9	48.3	47.7	57.4	56.4	49.0	44.8	45.6	55.7	45.8	44.1	41.1	42.9	53.0
19	60.8	64.2	43.3	43.7	50.3	47.7	46.3	43.2	48.7	48.3	47.9	57.6	56.9	51.2	44.7	44.5	56.1	43.9	46.1	42.0	42.6	52.8
20	58.1	61.5	45.3	43.8	56.5	48.0	49.0	47.5	48.8	49.5	48.9	57.8	57.3	52.2	46.1	47.4	57.1	48.7	49.4	46.1	48.8	54.6
21	63.0	65.2	50.6	52.7	57.2	55.4	58.1	58.8	55.8	57.7	59.2	60.2	59.5	60.1	57.9	61.8	62.8	60.7	61.0	57.7	58.5	64.6
22	62.3	64.7	54.9	56.2	57.0	59.1	60.4	60.4	60.1	60.5	61.1	61.1	59.9	59.7	63.5	65.7	62.6	62.1	62.5	58.9	60.2	65.4
23	57.9	63.4	53.8	55.0	57.0	58.1	59.8	59.9	59.8	59.4	60.4	60.4	59.4	58.6	59.0	66.7	61.8	61.3	62.2	57.9	59.6	63.8
daily Leq	61.1	64.7	61.0	66.4	67.3	52.7	53.6	55.4	53.6	53.7	55.5	58.2	57.4	54.3	69.4	58.7	58.9	57.0	57.1	54.5	54.1	59.7
Lmax	87.6	90.0	87.8	104.4	96.8	70.0	64.8	78.8	72.1	73.2	75.9	74.4	68.0	81.5	90.5	82.7	81.6	93.0	88.8	90.1	81.7	82.5

For locations, see Fig. 3.20 and text descriptions.

Sample Events:
- a - 7/13-14/99
- b - 7/14-15/99
- c - 7/15-16/99
- d - 7/19-20/99
- e - 7/20-21/99

4. CONCLUSIONS

Although the scope of this survey did not include evaluation or interpretation of the data, a few points are worth noting. Diurnal variations in noise levels were observed during the dawn and dusk periods commonly associated with increased levels of wildlife activity. None of the locations had routine increases in noise levels on a diurnal pattern that could be associated with increased human activity, e.g., work shifts or commuter traffic. Daytime noise levels did increase on days when a construction crew was working on the new Melton Valley Access Road, particularly at Location 2. The highway location (Location 1) had the least variation in noise levels on a diurnal basis, while monitoring locations in vegetated areas had the most noticeable diurnal noise variations. Background noise levels did not fall below 40 dB at any location (the equivalent of a dripping faucet, whispered speech, or a quiet home). Noise levels were often in the 50 to 60 dB range, but did go as high as 98 dB.

5. REFERENCES

Bohrer, P. S., MD. "Effects of Noise Pollution." Sonoma County Medical Association News. May 1997.

Cohen, Y. E. and Knudson, E. I. "Representation of Frequency in the Primary Auditory Field of the Barn Owl Forebrain." The American Physiological Society. APStracts 3:0168N, 1996.

Kowalski, N., Versnel, H., and Shamma, S. "Comparison of Responses in the Anterior and Primary Auditory Fields of the Ferret Cortex." University of Maryland Technical Reports. TR 94-51. 1994.

U.S. Department of Transportation, Federal Highway Administration. Highway Traffic Noise in the United States, Problem and Response.
From **http://www.nonoise.org/library/highway/probresp.htm**.

U.S. Department of Transportation, Federal Highway Administration, Office of Environment and Planning, Noise and Air Quality Branch. Highway Traffic Noise Analysis and Abatement Policy and Guidance. Washington, D.C. June 1995.

ADDITIONAL BACKGROUND NOTES FOR EIS USE (not part of baseline report)

Motor vehicle noise

Noise Control Act of 1972 (23 *CFR* 722) regulates noise levels for:
- Maximum per truck is 80 or 83 dBA depending upon truck type
- Measured 15 m from traffic centerline

Federal-aid Highway Act of 1970 set noise abatement criteria (NAC) by land use type and human activities (23 *CFR* 722). These are unacceptable levels and are used to determine impact, not a target level for reduction.
- NAC for the outdoors range from 57 dBA to 75 dBA
- NAC for parks (most similar to NRERP) is 67 dBA
- NAC for developed areas is 72 dBA


NAC are measured using hourly A-weighted sound levels for "Leq(h)" or "L10"

A noise impact occurs if:
- Projected noise levels approach or exceed NAC, or
- Projected noise levels substantially increase over existing noise levels in the area (a change of 10 dBA for highways)

These regulatory levels and criteria for vehicular traffic were developed on the basis of impacts to humans. Effects on wildlife or vegetation were not considered in them. Also, vibration was not directly considered.

Noise abatement

Noise mitigation can be provided by noise barriers such as traffic walls, vegetation, buffer zones, insulation in buildings, and management of traffic schedules.



APPENDIX C.5

RADIOLOGICAL SURVEY OF FOSTER WHEELER TRU FACILITY SITE

THIS PAGE INTENTIONALLY LEFT BLANK

C.5. RADIOLOGICAL SURVEY OF FOSTER WHEELER TRU FACILITY SITE

I. A radiological survey was conducted on the Foster Wheeler TRU facility site. Kurt Marcotte (BJC Project Lead Health Physicist for Legacy Waste) requested this survey. The site consisted of approximately 5 acres of land, which borders the existing evacuation road from ORNL's HFIR reactor. Measurements showed the site measured approximately 400 feet on east border; 700 feet on south border; 75 feet on west border; 730 feet on north border.

Parameters given for this survey are:

- 40' grid established, resulting in 123 points on vault.
- Waist high, general area gamma dose rates taken at each point.
- An alpha probe reading taken at each point.
- Beta-Gamma background obtained from average background of site.
- Use of a 10% efficiency for Beta-Gamma dpm conversions.

II. Instruments used for this survey included the following:

- Ludlum Model 2221 frisker with 43-5 probe (Alpha); K30394I
- Ludlum Model 2221 frisker with 44-9 probe (Beta-Gamma); K30237I
- Bicron micro-Rem Dose Rate instrument; K33530I

III. Summary of Results

A total of 123 grid locations were surveyed during this survey along with three monitoring wells on the site. All locations showed no significant increase over background for Beta-Gamma or Alpha. Several areas between grid points were found to have deer droppings, which were above 1000 dpm/100 cm^2. A total of three monitoring wells were identified on the site. Each well was scanned for the presence of radioactive contamination (Alpha/Beta-Gamma) with all readings having no elevated activity. All dose rates on site measured <0.1 mR/h approximately three feet above ground at each survey location.

IV. Conclusion

The data gathered in this survey suggest that there is no gross amount of radioactive surface contamination on the site. All readings taken at each grid location showed no significant increase over the established background. However, Radcon should be notified of any intrusive work that is to be conducted. This survey is in no way a clearance survey of the site.

Radiation / Contamination Survey

Facility: Foster Wheeler TRU Site Room:_____ Date: _____ Time: _____

Instruments Used:		Smear Counter N/A	
Alpha: K303941	Beta: K302371	Alpha	Beta
LLD 261.73 DPM/100cm^2	LLD 990 DPM/100cm^2	LLD _____ DPM/100cm^2	LLD _____ DPM/100cm^2
Lc 48.23 DPM/100cm^2	Lc 496.3 DPM/100cm^2	Lc _____ DPM/100cm^2	Lc _____ DPM/100cm^2
Dose Rate Inst. K335301			


RWP#: N/A RCT/Badge#: Reviewed by:

Point No.	Alpha Probe Reading (dpm/100cm2)	Beta-Gamma Probe Reading (dpm/100cm2)	Dose Rate (mR/hr)	Point No.	Alpha Probe Reading (dpm/100cm2)	Beta-Gamma Probe Reading (dpm/100cm2)	Dose Rate (mR/hr)
1	<48.23	<1000	<0.1	31	<48.23	<1000	<0.1
2	<48.23	<1000	<0.1	32	<48.23	<1000	<0.1
3	<48.23	<1000	<0.1	33	<48.23	<1000	<0.1
4	<48.23	<1000	<0.1	34	<48.23	<1000	<0.1
5	<48.23	<1000	<0.1	35	<48.23	<1000	<0.1
6	<48.23	<1000	<0.1	36	<48.23	<1000	<0.1
7	<48.23	<1000	<0.1	37	<48.23	<1000	<0.1
8	<48.23	<1000	<0.1	38	<48.23	<1000	<0.1
9	<48.23	<1000	<0.1	39	<48.23	<1000	<0.1
10	<48.23	<1000	<0.1	40	<48.23	<1000	<0.1
11	<48.23	<1000	<0.1	41	<48.23	<1000	<0.1
12	<48.23	<1000	<0.1	42	<48.23	<1000	<0.1
13	<48.23	<1000	<0.1	43	<48.23	<1000	<0.1
14	<48.23	<1000	<0.1	44	<48.23	<1000	<0.1
15	<48.23	<1000	<0.1	45	<48.23	<1000	<0.1
16	<48.23	<1000	<0.1	46	<48.23	<1000	<0.1
17	<48.23	<1000	<0.1	47	<48.23	<1000	<0.1
18	<48.23	<1000	<0.1	48	<48.23	<1000	<0.1
19	<48.23	<1000	<0.1	49	<48.23	<1000	<0.1
20	<48.23	<1000	<0.1	50	<48.23	<1000	<0.1
21	<48.23	<1000	<0.1	51	<48.23	<1000	<0.1
22	<48.23	<1000	<0.1	52	<48.23	<1000	<0.1
23	<48.23	<1000	<0.1	53	<48.23	<1000	<0.1
24	<48.23	<1000	<0.1	54	<48.23	<1000	<0.1
25	<48.23	<1000	<0.1	55	<48.23	<1000	<0.1
26	<48.23	<1000	<0.1	56	<48.23	<1000	<0.1
27	<48.23	<1000	<0.1	57	<48.23	<1000	<0.1
28	<48.23	<1000	<0.1	58	<48.23	<1000	<0.1
29	<48.23	<1000	<0.1	59	<48.23	<1000	<0.1
30	<48.23	<1000	<0.1	60	<48.23	<1000	<0.1

Point No.	Alpha Probe Reading (dpm/100cm2)	Beta-Gamma Probe Reading (dpm/100cm2)	Dose Rate (mR/hr)	Point No.	Alpha Probe Reading (dpm/100cm2)	Beta-Gamma Probe Reading (dpm/100cm2)	Dose Rate (mR/hr)
61	<48.23	<1000	<0.1	93	<48.23	<1000	<0.1
62	<48.23	<1000	<0.1	94	<48.23	<1000	<0.1
63	<48.23	<1000	<0.1	95	<48.23	<1000	<0.1
64	<48.23	<1000	<0.1	96	<48.23	<1000	<0.1
65	<48.23	<1000	<0.1	97	<48.23	<1000	<0.1
66	<48.23	<1000	<0.1	98	<48.23	<1000	<0.1
67	<48.23	<1000	<0.1	99	<48.23	<1000	<0.1
68	<48.23	<1000	<0.1	100	<48.23	<1000	<0.1
69	<48.23	<1000	<0.1	101	<48.23	<1000	<0.1
70	<48.23	<1000	<0.1	102	<48.23	<1000	<0.1
71	<48.23	<1000	<0.1	103	<48.23	<1000	<0.1
72	<48.23	<1000	<0.1	104	<48.23	<1000	<0.1
73	<48.23	<1000	<0.1	105	<48.23	<1000	<0.1
74	<48.23	<1000	<0.1	106	<48.23	<1000	<0.1
75	<48.23	<1000	<0.1	107	<48.23	<1000	<0.1
76	<48.23	<1000	<0.1	108	<48.23	<1000	<0.1
77	<48.23	<1000	<0.1	109	<48.23	<1000	<0.1
78	<48.23	<1000	<0.1	110	<48.23	<1000	<0.1
79	<48.23	<1000	<0.1	111	<48.23	<1000	<0.1
80	<48.23	<1000	<0.1	112	<48.23	<1000	<0.1
81	<48.23	<1000	<0.1	113	<48.23	<1000	<0.1
82	<48.23	<1000	<0.1	114	<48.23	<1000	<0.1
83	<48.23	<1000	<0.1	115	<48.23	<1000	<0.1
84	<48.23	<1000	<0.1	116	<48.23	<1000	<0.1
85	<48.23	<1000	<0.1	117	<48.23	<1000	<0.1
86	<48.23	<1000	<0.1	118	<48.23	<1000	<0.1
87	<48.23	<1000	<0.1	119	<48.23	<1000	<0.1
88	<48.23	<1000	<0.1	120	<48.23	<1000	<0.1
89	<48.23	<1000	<0.1	121	<48.23	<1000	<0.1
90	<48.23	<1000	<0.1	122	<48.23	<1000	<0.1
91	<48.23	<1000	<0.1	123	<48.23	<1000	<0.1
92	<48.23	<1000	<0.1	124			

RADIOLOGICAL SURVEY OF FOSTER WHEELER TRU FACILITY SITE

(Numbers represent survey points using 40' grid)



RADIOLOGICAL SURVEY OF FOSTER WHEELER TRU FACILITY SITE Survey Performed by the following technicians			
No.	Print Name	Signature	Badge Number
1	Jacob E May	Jacob E May	616884
2	M Sessions	M Sessions	701258
3	Ricky Nelson	Ricky Nelson	34327
4	MIKE KALAHAN	Mike Kalahan	33948
5	CHERYL WALKER	Cheryl Walker	625833
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX C.6

WETLANDS ASSESSMENT FOR CONSTRUCTION OF A NEW TRANSURANIC WASTE TREATMENT FACILITY OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE

THIS PAGE INTENTIONALLY LEFT BLANK

WETLANDS ASSESSMENT FOR CONSTRUCTION OF A NEW TRANSURANIC WASTE TREATMENT FACILITY OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE

Prepared by
Science Applications International Corporation
Engineering and Environmental Management Operation
P.O. Box 2502
Oak Ridge, Tennessee 37831

Prepared for
U.S. Department of Energy
Office of Environmental Management and Enrichment Facilities
Oak Ridge, Tennessee 37831-7101

December 1999

SCIENCE APPLICATIONS INTERNATIONAL CORPORATION
OAK RIDGE, TENNESSEE

contributed to the preparation of this document
and should not be considered an eligible contractor for its review.

CONTENTS

FIGURES C.6-iv
ACRONYMS C.6-iv
PREFACE C.6-v

1. INTRODUCTION AND BACKGROUND C.6-1
   1.1 INTRODUCTION C.6-1
   1.2 BACKGROUND C.6-2
   1.3 WASTE STORAGE AT ORNL C.6-2
   1.4 PURPOSE AND NEED FOR DOE ACTION C.6-2

2. PROPOSED ACTION AND ALTERNATIVES C.6-5
   2.1 SCOPE OF THE PROPOSED ACTION C.6-5
   2.2 NO ACTION ALTERNATIVE C.6-6
      2.2.1 Facility Description C.6-6
   2.3 LOW-TEMPERATURE DRYING ALTERNATIVE C.6-6
      2.3.1 Facility Description C.6-6
      2.3.2 Waste Processing Description C.6-6
   2.4 VITRIFICATION ALTERNATIVE C.6-7
      2.4.1 Facility Description C.6-7
      2.4.2 Waste Processing Description C.6-7
   2.5 CEMENTATION ALTERNATIVE C.6-7
      2.5.1 Facility Description C.6-7
      2.5.2 Waste Treatment Description C.6-7
   2.6 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE C.6-7

3. SITE DESCRIPTION C.6-9
   3.1 PROPOSED TRU WASTE TREATMENT FACILITY SITE C.6-9
      3.1.1 Wetlands C.6-9

4. EFFECTS ON WETLANDS C.6-13
   4.1 WETLAND EFFECTS C.6-13
   4.2 NO ACTION ALTERNATIVE C.6-13
   4.3 LOW-TEMPERATURE DRYING ALTERNATIVE C.6-13
   4.4 VITRIFICATION ALTERNATIVE C.6-13
   4.5 CEMENTATION ALTERNATIVE C.6-14
   4.6 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE C.6-14

5. MITIGATION C.6-17

6. SUMMARY AND CONCLUSIONS C.6-19

7. REFERENCES C.6-21

FIGURES

1-1 Location of Oak Ridge National Laboratory in relation to the city of Oak Ridge, other DOE facilities in the area, and the State of Tennessee. C.6-1
2-1 General site location on the Oak Ridge Reservation. C.6-5
3-1 Wetlands near the proposed Melton Valley transuranic waste treatment site. C.6-10

ACRONYMS

CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
D&D	decontamination and decommissioning
DOE	U.S. Department of Energy
EIS	Environmental Impact Statement
EPA	U.S. Environmental Protection Agency
FFA	Federal Facilities Agreement
FR	*Federal Register*
ha	hectare
LDRs	land disposal restrictions
NEPA	National Environmental Policy Act
NRCS	Natural Resource Conservation Service
ORNL	Oak Ridge National Laboratory
ORO	Oak Ridge Operations
ORR	Oak Ridge Reservation
RCRA	Resource Conservation and Recovery Act
SCS	Soil Conservation Service
TDEC	Tennessee Department of Environment and Conservation
TRU	transuranic
USDA	U.S. Department of Agriculture

PREFACE

This Wetlands Assessment has been prepared in accordance with the *Code of Federal Regulations* Title 10, Part 1022, for the purpose of fulfilling the U.S. Department of Energy's responsibilities under Executive Order 11990, Wetlands Protection.

The Executive Order encourages measures to preserve and enhance the natural and beneficial functions of wetlands. This order also requires federal agencies to take action to minimize or mitigate the destruction, loss, and degradation of wetlands. The sequence of mitigation measures should emphasize the importance of:

- avoiding new construction or work in wetlands, unless there is no practicable alternative to that action; and

- minimizing the harm should the only practicable alternative require the proposed action to take place in a wetland.

Finally, the Executive Order seeks to provide early and adequate opportunities for public review of plans and proposals involving new construction or similar projects in wetlands.

The wetlands assessment serves to inform the public of proposed site remediation activities and to present measures or alternatives to the proposed action that will lessen or mitigate adverse effects. This wetlands assessment evaluates actions associated with the construction of a new Transuranic Waste Treatment Facility in Melton Valley at Oak Ridge National Laboratory that would affect wetlands. Information on the following topics is presented: project description, site description, effects on wetlands, alternatives, and mitigation.

THIS PAGE INTENTIONALLY LEFT BLANK

1. INTRODUCTION AND BACKGROUND

1.1 INTRODUCTION

U.S. Department of Energy (DOE) facilities have performed nuclear energy research and radiochemical production since the early 1940s. The Oak Ridge National Laboratory (ORNL) was constructed during World War II as a pilot-scale plant to support nuclear energy research and the construction of larger plutonium production facilities at Hanford, Washington. ORNL is located on approximately 1174 hectares (ha) (2900 acres), 40 km (25 miles) northwest of the city of Knoxville, in eastern Tennessee (Figure 1-1). The site is located in a water-rich environment that contains numerous small tributaries that flow into the Clinch River located south and west of the site. ORNL is located in the Tennessee Valley between the Great Smoky Mountains (located approximately 80 km or 50 miles east) and the Cumberland Plateau (about 45 km or 25 miles west).




Figure 1-1. Location of Oak Ridge National Laboratory in relation to the city of Oak Ridge, other DOE facilities in the area, and the State of Tennessee.

ORNL continues to be used for DOE operations and is internationally known as a premier research facility. Research and development activities support national defense and energy initiatives. Ongoing waste management and environmental management activities continue to address legacy and newly generated low-level radioactive, transuranic (TRU), and hazardous wastes resulting from research and development activities. These wastes pose environmental concerns, and management of these wastes is a common problem. Risk, cost, and contamination pathway models prove the wastes need to be safely contained and disposed. Meeting the cleanup challenges associated with legacy and newly generated wastes at ORNL is a high priority for the DOE Oak Ridge Operations (ORO), the Tennessee Department of Environment and Conservation (TDEC), and stakeholders. The TRU Waste Treatment Project at ORNL would be an important component of the DOE cleanup efforts at the site.

1.2 BACKGROUND

The waste included in this TRU Waste Treatment Project Environmental Impact Statement (EIS) is classified as three separate types: alpha low-level waste, TRU waste, and low-level waste. Much of the waste displays Resource Conservation and Recovery Act (RCRA) characteristics and, therefore, may be classified as mixed waste. ORNL currently has the largest inventory of remote-handled TRU waste in the DOE complex and a smaller portion of the contact-handled TRU waste. These wastes were generated from the various research and development activities conducted at ORNL.

1.3 WASTE STORAGE AT ORNL

Legacy TRU solid waste is currently stored in subsurface trenches, vaults, and metal buildings. Approximately 30% of the legacy TRU tank wastes are currently stored in aging, underground storage tanks. The remainder of the tank waste is contained in the Melton Valley Storage Tanks. Sampling and analysis has been performed on all of the tank waste. The radiological and chemical properties of the sludge and supernate have been measured, and a bounding analysis was performed on each constituent to provide a range of waste characteristics.

1.4 PURPOSE AND NEED FOR DOE ACTION

DOE is preparing an EIS under the National Environmental Policy Act (NEPA) and its implementing regulations (10 *CFR* 1021) on the proposed construction, operation, and decontamination/decommissioning (D&D) of a TRU Waste Treatment Facility at ORNL in Oak Ridge, Tennessee. The four types of TRU waste that would be treated at the facility are: remote-handled TRU waste sludge; low-level radioactive waste supernate associated with the sludge; contact-handled TRU/alpha low-level radioactive waste solids; and remote-handled TRU/alpha low-level radioactive waste solids. Because much of the radioactive and hazardous waste displays RCRA characteristics, the proposed facility would be permitted under RCRA.

DOE needs to ensure the safe and efficient retrieval, processing, certification, and disposition of legacy TRU waste at ORNL. There are legal mandates that require DOE to address TRU waste management needs. DOE has been directed by the TDEC and the U.S. Environmental Protection Agency (EPA) to address environmental issues including disposal of its legacy TRU waste. DOE is under a Commissioner's Order issued by the State of Tennessee (September 1995) to implement the Site Treatment Plan (under the Federal Facility Compliance Act) that mandates specific requirements for the processing and disposal of ORNL's TRU waste. The primary milestone in the Commissioner's Order is that DOE begin processing TRU sludge in order to make the first shipment to the Waste Isolation Pilot Plant (a DOE transuranic waste disposal facility) in New Mexico by January 2003. In addition, two

Records of Decision [issued in connection with the Federal Facilities Agreement (FFA) among EPA, TDEC, and DOE under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)] require the waste from the Gunite and Associated Tanks Project (DOE 1998) and the Old Hydrofracture Facility Tanks Project to be processed and disposed of along with the TRU waste from the Melton Valley Storage Tanks.

Waste retrieval operations are currently under way to prepare ORNL TRU waste storage tanks for closure. The waste removed from tanks in Bethel Valley at ORNL will be consolidated into the Melton Valley Storage Tanks prior to processing. Following the processing operations, DOE will certify the TRU waste for shipment and disposal at the Waste Isolation Pilot Plant. Low-level radioactive waste resulting from TRU waste processing must be certified by DOE for shipment and disposal at the DOE site(s) selected in a Record of Decision for the *Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, May 1997 (DOE 1997). Currently, no facilities exist at ORNL, or on the Oak Ridge Reservation (ORR), for processing TRU/alpha low-level radioactive waste.

THIS PAGE INTENTIONALLY LEFT BLANK

2. PROPOSED ACTION AND ALTERNATIVES

DOE will evaluate five alternatives associated with the treatment and disposal of four waste streams at ORNL facilities in Oak Ridge, Tennessee, as part of the EIS. DOE proposes to construct, operate, and decontaminate/decommission a TRU Waste Treatment Facility at ORNL, located in Oak Ridge, Tennessee. The four waste types that would be treated at the proposed facility are remote-handled TRU waste sludge; supernate associated with the sludge; contact-handled TRU/alpha low-level waste solids; and remote-handled TRU/alpha low-level waste solids. Since much of the waste displays RCRA characteristics, the proposed facility would be permitted under RCRA [*Federal Register* (*FR*) 64, Number 17, 1999]. Most of the waste is currently in the Melton Valley area of ORNL in underground waste storage tanks, bunkers, metal buildings, and subsurface trenches.

2.1 SCOPE OF THE PROPOSED ACTION

Under the proposed action, a waste treatment facility would be constructed, operated, and decontaminated/decommissioned under a contract awarded to the Foster Wheeler Environmental Corporation (Foster Wheeler) for the ORNL legacy TRU waste. DOE would lease the Melton Valley Storage Tanks and an adjacent land area totaling approximately 2 ha (5 acres) to Foster Wheeler for construction of the facility (Figure 2-1), subject to notification of the EPA and the State of Tennessee. The Melton Valley Storage Tanks are located in Melton Valley, separated from the main plant area at ORNL by the Haw Ridge. The proposed treatment facility would be fenced, with controlled access to Tennessee State Highway 95 located west of the proposed site.




Figure 2-1. General site location on the Oak Ridge Reservation.

The following five alternatives were evaluated in detail:

1. No Action.

2. Low-Temperature Drying for the tank wastes (Melton Valley Storage Tank sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU heterogeneous debris). (Proposed Action/Preferred Alternative)

3. Vitrification for the tank wastes (Melton Valley Storage Tank sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU heterogeneous debris).

4. Cementation for the tank wastes (Melton Valley Storage Tank sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU heterogeneous debris).

5. On-site Treatment and Storage at Oak Ridge Reservation would provide treatment by one of the above action alternatives and continued storage at ORNL following treatment.

2.2 NO ACTION ALTERNATIVE

Under the No Action Alternative, DOE would continue to store TRU waste in tanks, subsurface trenches, vaults, and metal buildings at ORNL. The use of this long-term storage approach is not permissible under RCRA, which does not allow for the storage of untreated hazardous wastes indefinitely.

2.2.1 Facility Description

Initially, no facility would be constructed under the No Action Alternative. However, the generation of additional waste from environmental remediation activities and on-going research and development activities at ORNL would eventually require the installation of more waste storage tanks for the storage of untreated liquid waste, and additional facilities for the storage of remote-handled and contact-handled solids.

2.3 LOW-TEMPERATURE DRYING (PROPOSED ACTION/PREFERRED) ALTERNATIVE

2.3.1 Facility Description

The Low-Temperature Drying (Proposed Action/Preferred) Alternative would involve the construction of a three-and-one-half-story waste treatment and processing facility approximately 37 m (120 ft) west of the Melton Valley Storage Tank area. The proposed facility would be located close to the tank waste in order to avoid transportation of highly radioactive liquid waste across the ORNL site or public roads.

2.3.2 Waste Processing Description

Low-Temperature Drying provides a process of evaporating and drying the sludges and supernates that is flexible enough to cover a wide range of waste properties. The low-temperature drying process would substantially reduce the waste volume, generate minimal amounts of secondary wastes, and meet the waste acceptance criteria of the final disposal facilities. All waste streams would be treated to meet

the waste acceptance criteria of the Waste Isolation Pilot Plant or the Nevada Test Site disposal sites, as well as the RCRA land disposal restrictions (LDRs) in case interim on-site storage of the waste is required.

2.4 VITRIFICATION ALTERNATIVE

The Vitrification Alternative has similar objectives, scheduling constraints, and facility constraints as the Low-Temperature Drying Alternative.

2.4.1 Facility Description

The facility for the Vitrification Alternative would be located on 2 to 2.8 ha (5 to 7 acres) in the same vicinity as the facility for the Low-Temperature Drying Alternative. The overall design and infrastructure of the Vitrification facility would generally be similar to the Low-Temperature Drying facility, with a three-and-one-half-story structure.

2.4.2 Waste Processing Description

The Vitrification Alternative waste processing consists of sorting, compaction, grouting, and vitrification to treat the waste. The vitrification system would be expected to treat liquids, soils, sludges, and other material of a size less than the RCRA definition of debris.

2.5 CEMENTATION ALTERNATIVE

This alternative presents a processing approach that features sludge/supernate separation by hydrocyclone/centrifuge pre-treatment, and subsequent cementation for the tank wastes, and segregation and supercompaction for the contact-handled and remote-handled wastes.

2.5.1 Facility Description

The facility for the Cementation Alternative would be located within an approximate 2-ha (5-acre) plot of land located in the same vicinity as the facility for the Low-Temperature Drying Alternative, with the justification for the location based on the same factors. The overall design and infrastructure of this Cementation facility would generally be similar to the Low-Temperature Drying facility.

2.5.2 Waste Treatment Description

The cementation technology is based on proven process operations conducted at DOE's Hanford faclity near Richland, Washington, and information provided in a feasiblity study. The Cementation Alternative would divert storm water around the facility, and gate valves would be installed in the diversion basins, in the event of a spill, as pollution prevention measures. The off-gas system would minimize air emisions, and liquid used for the decontamination of the cementation treatment system would be transferred back into the cementation treatment system as waste minimization measures.

2.6 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE

This alternative would entail waste processing by any of the three previous action alternatives and indefinite waste storage at ORNL rather than shipment to the Waste Isolation Pilot Plant or the Nevada Test Site. The residual wastes are remote-handled wastes, and their associated doses would remain

sufficiently elevated that remote handling would be necessary during storage onsite at ORNL. After processing, the remote-handled TRU and remote-handled low-level waste residuals would be stored onsite in a new storage facility designed to handle the treated remote-handled waste.

3. SITE DESCRIPTION

3.1 PROPOSED TRU WASTE TREATMENT FACILITY SITE

The proposed TRU Waste Treatment Facility would be located on a 2- to 2.8-ha (5- to 7-acre) site adjacent to the Melton Valley Storage Tanks.

3.1.1 Wetlands

There are six wetlands within 0.8 km (0.5 mile) of the proposed TRU waste treatment facility site, herein labeled as Wetlands A, B, C, D, E, and F (Figure 3-1). The wetlands were identified using three sources of information, including: (1) a report on wetland delineation on the proposed TRU waste treatment facility site (Jacobs and Rosensteel 1999); (2) an on-site reconnaissance by wetland scientists from SAIC on June 2, 1999; and (3) review of National Wetland Inventory maps. The six wetlands are briefly described below.

Jacobs and Rosensteel (1999) identified and delineated four small wetlands (Wetlands A, B, C, and D) on or adjacent to the TRU Waste Treatment Facility site (Figure 3-1). A copy of the report, which contains detailed descriptions of the wetlands along with copies of the field data sheets, is presented in Appendix C and, thus, will only be summarized here. Wetlands A, B, and C were delineated during the author's field survey of the TRU Waste Treatment Facility site on April 20, 1999. Wetland D was initially identified in April 1992 by B. Rosensteel and was not delineated again.

Wetland A is approximately 0.146 ha (0.36 acre) and is located approximately 91 m (298 ft) south of the southwest corner of the TRU Waste Treatment Facility site (Figure 3-1). It is a saturated, temporarily flooded, palustrine emergent wetland in an intermittent stream drainage. The stream originates upslope near the base of Copper Ridge and flows through a clearing where the wetland has developed around seeps that contribute to the stream flow.

Wetland B is only 0.012 ha (0.03 acre) and is located in an intermittent stream along the eastern side of the proposed site (Figure 3-1). According to Jacobs and Rosensteel (1999), this wetland is temporarily flooded and saturated and is palustrine scrub-shrub. An old road-crossing culvert located downstream from the site acts to slow and retain stream flow, thereby causing the riparian zone saturation at the wetland.

Wetland C is 0.036 ha (0.09 acre) and is located approximately 91 m (298 ft) south of the TRU Waste Treatment Facility's southeast corner (Figure 3-1). Jacobs and Rosensteel (1999) classified the wetland as saturated, palustrine emergent, located in a disturbed, grassy area upslope. Wetland C is periodically mowed, so the wetland is in a topographic low area that might have contained a section of intermittent stream prior to land disturbance and hydrological alterations. Water discharges from seeps in the wetland and then re-enters the ground at the downslope end of the wetland.

Wetland D is 0.016 ha (0.04 acre) and is located in the northwest corner of the proposed TRU Waste Treatment Facility site (Figure 3-1). This wetland is a saturated, emergent wetland located on the western side of the site. The wetland has developed in a seep area, but there is wetland hydrology due to slowing of the water flow by a culvert under the old Melton Valley Road. Standing and flowing water were present in the wetland during the April 1999 site visit.




Figure 3-1. Wetlands near the proposed Melton Valley transuranic waste treatment site.

Wetland E includes most of the floodplain of Melton Branch north of the road along the northern perimeter of the proposed TRU Waste Treatment Facility (Figure 3-1). This wetland covers several hectares (acres). Because of potential radiological contamination of the floodplain soils, walkover and intrusive sampling of the floodplain area was not performed by Jacobs and Rosensteel (1999) or by SAIC in June 1999. This wetland was identified from National Wetland Inventory maps, which depict the area as palustrine forested wetland dominated by broad-leaved deciduous trees.

Wetland F includes the shoreline and upper reaches of White Oak Lake and covers several hectares (Figure 3-1). National Wetland Inventory maps depict this area as lacustrine wetland. The shoreline includes a mixture of trees, shrubs, and persistent and nonpersistent wetland plants.

THIS PAGE INTENTIONALLY LEFT BLANK

4. EFFECTS ON WETLANDS

4.1 WETLAND EFFECTS

This section discusses the environmental consequences to wetlands from the five alternatives evaluated for the proposed TRU Waste Treatment Project facility. Impacts from the construction, operation, and closure phases are discussed, as applicable, for each alternative.

4.2 NO ACTION ALTERNATIVE

Construction and closure phases are not applicable to the No Action Alternative; therefore, only potential impacts from the operation phase are discussed for this alternative.

Impacts to the six wetland systems should be negligible because essentially no wastes from the Melton Valley Storage Tanks would be released to reach the wetlands. In addition, no other activities would be conducted that would adversely impact the structure or functioning of the wetlands. However, radionuclide migration from waste in the unlined trenches at Solid Waste Storage Area 5 North (SWSA-5N) would potentially continue to pose some threat to Wetland F.

4.3 LOW-TEMPERATURE DRYING ALTERNATIVE

Environmental consequences for wetlands and floodplains for the Low-Temperature Drying Alternative include those associated with the construction phase, operations phase, and D&D phase. The environmental consequences associated with each phase are discussed below.

The construction phase impacts to Wetland B would be severe, and would result in a loss of 0.012 ha (0.03 acre) of wetland habitat. Current construction plans include diversion of the drainageway feeding Wetland B through a culvert, thereby removing the hydrologic source of the wetland. The wetland functions as a wet-weather or possibly permanent seep discharging into a small ravine. The small size and limited function suggest a relatively low value for the wetland. Impacts to Wetlands D, E, and F should be negligible as long as soil erosion is successfully controlled. In the worst case, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely affected short-term by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C should be negligible because their locations are outside the areas to be cleared for construction and should not receive much deposition from soil erosion.

Impacts to wetlands from the D&D of the facility are expected to be negligible and generally similar to, or less than, those discussed for the construction and operation phase activities as long as on-site erosion is adequately controlled and no sediment migrates offsite.

4.4 VITRIFICATION ALTERNATIVE

Environmental consequences for wetlands and floodplains for the Vitrification Alternative include those associated with the construction phase, operations phase, and D&D phase. The environmental consequences associated with each phase are discussed below.

The construction phase impacts to Wetland B would be severe, and would result in a loss of 0.012 ha (0.03 acre) of wetland habitat. Current construction plans include diversion of the drainageway feeding Wetland B through a culvert, thereby removing the hydrologic source of the wetland. Impacts to Wetlands D, E, and F should be negligible as long as soil erosion is successfully controlled. In the worst case, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely affected short-term by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C should be negligible because their locations are outside the areas to be cleared for construction and should not receive much deposition from soil erosion.

Impacts to wetlands from the D&D of the facility are expected to be negligible and generally similar to, or less than, those discussed for the construction and operation phase activities as long as on-site erosion is adequately controlled and no sediment migrates offsite.

4.5 CEMENTATION ALTERNATIVE

Environmental consequences for wetlands and floodplains for the Cementation Alternative include those associated with the construction phase, operations phase, and D&D phase. The environmental consequences associated with each phase are discussed below.

The construction phase impacts to Wetland B would be severe, and would result in a loss of 0.012 ha (0.03 acre) of wetland habitat. Current construction plans include diversion of the drainageway feeding Wetland B through a culvert, thereby removing the hydrologic source of the wetland. Impacts to Wetlands D, E, and F should be negligible as long as soil erosion is successfully controlled. In the worst case, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely affected short-term by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C should be negligible because their locations are outside the areas to be cleared for construction and should not receive much deposition from soil erosion.

Impacts to wetlands from the D&D of the facility are expected to be negligible and generally similar to, or less than, those discussed for the construction and operation phase activities as long as on-site erosion is adequately controlled and no sediment migrates offsite.

4.6 TREATMENT AND WASTE STORAGE AT ORNL ALTERNATIVE

Environmental consequences for wetlands and floodplains for the Treatment and Off-site Storage Alternative include those associated with the construction phase, operations phase, and D&D phase. The environmental consequences associated with each phase are discussed below.

The construction phase impacts to Wetland B would be severe, and would result in a loss of 0.012 ha (0.03 acre) of wetland habitat. Current construction plans include diversion of the drainageway feeding Wetland B through a culvert, thereby removing the hydrologic source of the wetland. Impacts to Wetlands D, E, and F should be negligible as long as soil erosion is successfully controlled. In the worst case, if soil erosion is not controlled during the construction phase, Wetlands D, E, and F could be adversely affected short-term by excessive siltation, which would be detrimental to aquatic biota in the wetlands. Impacts to Wetlands A and C should be negligible because their locations are outside the areas to be cleared for construction and should not receive much deposition from soil erosion.

Impacts to wetlands from the D&D of the facility are expected to be negligible and generally similar to, or less than, those discussed for the construction and operation phase activities as long as on-site erosion is adequately controlled and no sediment migrates offsite.

THIS PAGE INTENTIONALLY LEFT BLANK

5. MITIGATION

Proposed mitigation measures to lessen the impact of construction in wetlands at the TRU Waste Treatment Facility site include standard construction practices, such as sediment control fences, to control and minimize erosion, runoff, and siltation of floodplain, wetland, and other water resources. DOE would identify and employ best management practices that would minimize adverse impacts during construction, including prevention of erosion and siltation into the wetlands and streams in accordance with standard U.S. Department of Agriculture (USDA) Natural Resource Conservation Service (NRCS), formerly Soil Conservation Service (SCS), methods or the equivalent. If needed, tracked excavating vehicles and pressure-reducing mats would be used to reduce the risk of compacting sediment or soil. Areas located in the wetlands adjacent to the TRU Waste Treatment Facility site would not be used for temporary or permanent storage purposes. However, adjacent areas within the wetland buffer zone may be used for temporary storage of excavated material and rubble awaiting final disposal at an appropriate facility. Upon completion of the remediation activities, all affected areas in wetlands, and the wetland buffer zone would be backfilled, regraded, and revegetated with noninvasive, native plant species.

Proposed construction would result in the draining of 0.016 ha (0.03 acre) in Wetland B. Mitigation for the loss of this wetland habitat may require compensatory mitigation. If needed, the sediment/stormwater detention basins could be designed as a constructed wetland to compensate for the loss of Wetland B.

THIS PAGE INTENTIONALLY LEFT BLANK

6. SUMMARY AND CONCLUSIONS

The preferred treatment action, Alternative 2, Low-Temperature Drying, proposed for the new TRU Waste Treatment Facility at the Melton Valley site would result in long-term impacts to one small wetland at the site. Construction of the new facility would effectively drain Wetland B, which covers an area of 0.016 ha (0.03 acre). Similar impacts to Wetland B would result from the implementation of Alternative 3, Vitrification; Alternative 4, Cementation; or Alternative 5, Treatment and Storage Elsewhere at ORNL.

If compensatory mitigation is required for the loss of this wetland, the sediment control/stormwater detention basin for the project can be designed as a wetland to replace loss wetland habitat and functions at the site. If this is not suitable mitigation would be accomplished through the development of replacement wetlands either elsewhere at ORNL or other Oak Ridge Reservation sites, or through wetlands banking. The use of best management practices to control erosion at the site should prevent any indirect adverse impacts from affecting other wetlands at the site.

Alternative 1, No Action, would not result in any direct adverse impacts to any of the wetlands associated with TRU Waste Treatment Facility site. However, radionuclide migration from waste in the unlined trenches at SWSA-5N would potentially continue to pose some threat to Wetland F.

THIS PAGE INTENTIONALLY LEFT BLANK

7. REFERENCES

DOE (U.S. Department of Energy) 1997. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

DOE 1998. *Safety Analysis Report for the Gunite and Associated Tanks Project Remediation of the South Tank Farm, Facility 3507, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/ER-403, February 1998.

Federal Register 1999. Vol. 64, No. 17, pp. 4079–82.

Jacobs and Rosensteel (Jacobs Environmental Management Team and Barbara A. Rosensteel) 1999. *Findings of Wetland Delineation on the Proposed Transuranic Waste Facility Site in Melton Valley, Oak Ridge Reservation, Oak Ridge Tennessee.* August 25, 1999, 9 pp. plus appendix.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX D

RIMS II INPUT-OUTPUT METHODOLOGY

THIS PAGE INTENTIONALLY LEFT BLANK

RIMS II INPUT-OUTPUT METHODOLOGY

The Regional Input-Output Modeling System II (RIMS II) relies on an accounting framework called input-output (I-O) analysis, which focuses on identifying the linkages (inputs purchased and outputs sold) among the industries within an economy. For example, the impact of a new sports facility would include both its direct employment and sales, and its indirect effects through purchases from other industries (food for concessions, insurance, utilities, etc.) and the additional purchases households make with the money it pays them. RIMS II uses these linkages to trace the impacts of specific changes on detailed sectors of the economy and calculates multipliers for each industry included in the model. This provides an advantage over other models that rely on "aggregate" multipliers for the entire economy.

The U.S. Department of Commerce, Bureau of Economic Analysis (BEA), maintains a detailed I-O model of the national economy. RIMS II multipliers are based on this national model and BEA's regional economic accounts, which are used to adjust the national table to account for a region's industrial structure and trading patterns. The multipliers used in this analysis were based on the 1992 national I-O tables and the 1995 BEA regional accounts data—the most recent figures available at this time. They were developed specifically for the four-county region (Anderson, Knox, Loudon, and Roane Counties) defined as the economic region of influence for this analysis.

Each phase of the project involves a different type of activity and, therefore, a different industry multiplier. For the purposes of this analysis, the phases and the associated industries are identified below. Where there was some question about the most appropriate industrial category, the analysis used the industry with the larger multiplier in order to identify the maximum potential impacts. In no case was the difference in multipliers large enough to affect the relative size of the economic impacts or the conclusions drawn from the analysis.

Table D.1. Industrial categories used in economic analysis

Project phase	Industry
I. Licensing	73.0302 Engineering, architectural, and surveying services
II. Construction	11.0900 Other new construction
III. Operation	68.0302 Sanitary Services, steam supply, and irrigation1
IV. Decontamination and Decommissioning	12.0300 Other maintenance and repair construction

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX E

AGENCIES CONTACTED

THIS PAGE INTENTIONALLY LEFT BLANK

Department of Energy

Oak Ridge Operations Office
P.O. Box 2001
Oak Ridge, Tennessee 37831

June 2, 1999

Mr. Reginald Reeves, Director
Division of Natural Heritage
State of Tennessee
Department of Environment and Conservation
401 Church Street
Nashville, Tennessee 37243-0443

Dear Mr. Reeves:


INFORMAL CONSULTATION UNDER THE ENDANGERED SPECIES ACT FOR THE PROPOSED TRANSURANIC WASTE TREATMENT PROJECT AT THE OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

The United States Department of Energy (DOE) needs to ensure the safe and efficient retrieval, processing, certification, and disposition of legacy transuranic (TRU) waste at Oak Ridge National Laboratory (ORNL). The regional location of ORNL is shown in Figure 1. Waste retrieval operations are currently underway to prepare ORNL TRU waste for processing.

Under the proposed action, a waste treatment facility for the ORNL legacy TRU waste would be constructed, operated for approximately six years, and decontaminated/decommissioned under a contract awarded to the Foster Wheeler Environmental Corporation. DOE would lease the Melton Valley Storage Tanks and adjacent land area totaling approximately 10 acres for construction of the facility. The proposed 37,000 square foot treatment facility would be located within an approximate 5 acre plot of land, fenced, and have controlled access to Tennessee State Highway 95 located 1.25 miles away. The first shipment of treated waste to the Waste Isolation Pilot Plant (WIPP) facility for disposal would be expected in 2003. The proposed construction area is shown in Figure 2.

The area can currently be described as second growth forest that consists of mixed hardwoods and pine plantations. This area is small in comparison to the almost 3,600 acres that comprise ORNL. In a 1988 survey of the surrounding area, executed for a formerly proposed treatment facility, no federally or State listed or candidate plant or animal species were observed adjacent to this site. Two species listed by the State of Tennessee as in need of management, the red-shouldered hawk and black vulture, may occur at the site but have not been documented as nesting there. Field surveys are currently ongoing at the proposed project site for both protected/rare plant and animal species. No rare plant species or federally protected animal species have been identified, although the animal survey has not yet been completed.

This letter is intended to serve as informal consultation under the Endangered Species Act. In this regard, DOE requests an updated list of protected species and habitat on or near the project site and solicits your recommendations and comments about the potential effects of this proposed action. Your input will be used in the preparation of an environmental impact statement for this action pursuant to the National Environmental Policy Act.


PROPOSED
SITE LOCATION
Bethel Cem
Burns Cem
Thacker Cem
Vann Cem
Sewage Disposal Plant
Gaging Station
Water Tank
Whitebark Lake
Jones Island
Figure 1



500 FT
WHITE OAK CREEK
R = 1000'
MELTON BRANCH
TRU WASTE REMEDIATION FACILITY
MELTON VALLEY STORAGE TANKS
EXISTING EDGE OF ACCESS ROAD
PROPOSED ROAD WIDENING (BY OTHERS)
MELTON VALLEY CAPACITY INCREASE STORAGE TANKS
E 27,000
E 27,500
E 28,000

Figure 2

If you need further information on this request, please do not hesitate to call me at (423) 576-0938.

Sincerely,

James L. Elmore, Ph.D.
Alternate NEPA Compliance Officer

Enclosures

cc:
Gary L. Riner, EM-92
Wayne Tolbert, SAIC

Department of Energy

Oak Ridge Operations Office
P O Box 2001
Oak Ridge, Tennessee 37831—

June 2, 1999

Dr Lee Barclay
U.S. Fish and Wildlife Service
446 Neal Street
Cookeville, Tennessee 37501

Dear Dr. Barclay:

INFORMAL CONSULTATION UNDER SECTION 7 OF THE ENDANGERED SPECIES ACT FOR THE PROPOSED TRANSURANIC WASTE TREATMENT PROJECT AT THE OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

The United States Department of Energy (DOE) needs to ensure the safe and efficient retrieval, processing, certification, and disposition of legacy transuranic (TRU) waste at Oak Ridge National Laboratory (ORNL). The regional location of ORNL is shown in Figure 1. Waste retrieval operations are currently underway to prepare ORNL TRU waste for processing.

Under the proposed action, a waste treatment facility for the ORNL legacy TRU waste would be constructed, operated for approximately six years, and decontaminated/decommissioned under a contract awarded to the Foster Wheeler Environmental Corporation. DOE would lease the Melton Valley Storage Tanks and adjacent land area totaling approximately 10 acres for construction of the facility. The proposed 37,000 square foot treatment facility would be located within an approximate 5 acre plot of land, fenced, and have controlled access to Tennessee State Highway 95 located 1.25 miles away. The first shipment of treated waste to the Waste Isolation Pilot Plant (WIPP) facility for disposal would be expected in 2003. The proposed construction area is shown in Figure 2.

The area can currently be described as second growth forest that consists of mixed hardwoods and pine plantations. This area is small in comparison to the almost 3,600 acres that comprise ORNL. In a 1988 survey of the surrounding area, executed for a formerly proposed treatment facility, no federally or State listed or candidate plant or animal species were observed adjacent to this site. Two species listed by the State of Tennessee as in need of management, the red-shouldered hawk and black vulture, may occur at the site but have not been documented as nesting there. Field surveys are currently ongoing at the proposed project site for both protected/rare plant and animal species. No rare plant species or federally protected animal species have been identified, although the animal survey has not yet been completed.

This letter is intended to serve as informal consultation under Section 7 of the Endangered Species Act. In this regard, DOE requests an updated list of protected species and habitat on or near the project site and solicits your recommendations and comments about the potential effects of this proposed action. Your input will be used in the preparation of an environmental impact statement for this action pursuant to the National Environmental Policy Act.



PROPOSED
SITE LOCATION
Gaging Station
Sewage Disposal Plant
Monitoring Tower
Water Tank
Water Tanks
Valve Station
Reservoir
Substa
Visitors Overlook
Bethel Cem
Burns Cem
Thacker Cem
Vann Cem
Waller Cem
Carter Cem
Rifle Range
Melton Hill
Jones Island
Whitlock Lake
Bethel Valley Road
Melton Valley
Ridge
Creek
Branch
Boat Ramp
Mile 20
ELEV 741
BM CO 101 778
BM CO 97 748
BM CO 97 785

Figure 1



500 FT
WHITE OAK CREEK
R = 1000'
MELTON BRANCH
TRU WASTE REMEDIATION FACILITY
MELTON VALLEY STORAGE TANKS
EXISTING EDGE OF ACCESS ROAD
PROPOSED ROAD WIDENING (BY OTHERS)
MELTON VALLEY CAPACITY INCREASE STORAGE TANKS
E 27,000
E 27,500
E 28,000
E 28,500

Figure 2

If you need further information on this request, please do not hesitate to call me at (423) 576-0956.

Sincerely,

James L. Elmore, Ph.D
Alternate NEPA Compliance Officer

Enclosures

cc:
Gary Riner, EM-92
Wayne Tolbert, SAIC

United States Department of the Interior

FISH AND WILDLIFE SERVICE
446 Neal Street
Cookeville, TN 38501

July 8, 1999

Mr. James L. Elmore, Ph.D.
U.S. Department of Energy
Oak Ridge Operations Office
P.O. Box 2001
Oak Ridge, Tennessee 37831

Dear Dr. Elmore:

Thank you for your letter and enclosures of June 2, 1999, regarding the preparation of an Environmental Impact Statement (EIS) for the construction of a transuranic legacy waste treatment facility at the Oak Ridge Reservation in Roane County, Tennessee. U.S. Fish and Wildlife Service (Service) personnel have reviewed the information submitted and offer the following comments for consideration.

According to our records, the following federally listed endangered species are known to occur near the potential project impact area:

gray bat	(*Myotis grisescens*)
pink mucket pearlymussel	(*Lampsilis abrupta*)

Qualified biologists should assess potential impacts and determine if the proposed project may affect the species. We recommend that you submit a copy of your assessment and finding to this office for review and concurrence. A finding of "may affect" could require the initiation of formal consultation procedures.

These constitute the comments of the U.S. Department of the Interior in accordance with provisions of the Endangered Species Act (87 Stat. 884, as amended: 16 U.S.C. 1531 et seq.). We appreciate the opportunity to comment. Should you have any questions or need further assistance, please contact Steve Alexander of my staff at 931/528-6481, ext. 210.

Sincerely,

Timothy B. Merritt

for Lee A. Barclay, Ph.D.
Field Supervisor

OFFICIAL FILE COPY
AMESQ
Log No. C 0902
Date Received JUL 12 1999
File Code



Department of Energy

Oak Ridge Operations Office
P O Box 2001
Oak Ridge, Tennessee 37831—

June 28, 1996

Mr. Joseph Garrison
Tennessee Historical Commission
Department of Environment and Conservation
2941 Lebanon Road
Nashville, Tennessee 37243-0442

Dear Mr. Garrison:

NATIONAL HISTORIC PRESERVATION ACT, SECTION 106 COMPLIANCE, TRANSURANIC WASTE TREATMENT FACILITY, OAK RIDGE NATIONAL LABORATORY, OAK RIDGE TENNESSEE

Enclosed is a Project Summary for the proposed construction, operation, and decontamination/decommission of a Transuranic (TRU) Waste Treatment Facility, Roane County, Tennessee. The Department of Energy Oak Ridge Operations (DOE ORO) has determined that the proposed project would have no affect on historical, archeological, or cultural resources included or eligible for inclusion in the National Register of Historic Places (National Register). This determination is included with the Project Summary. The proposed project is addressed in the *Programmatic Agreement Among The Department Of Energy Oak Ridge Operations Office The Tennessee State Historic Preservation Officer And The Advisory Council On Historic Preservation Concerning The Management Of Historical And Cultural Properties At The Oak Ridge Reservation (PA) at Section III.D.1.*

DOE ORO requests documentation of your concurrence with DOE ORO's determination for this proposed project If you have questions or need additional information related to this proposed project please call me at (423) 576-9574.

Sincerely,

Ray T. Moore

Ray T. Moore
DOE ORO Cultural Resources
Management Coordinator

Enclosure

cc w/enclosure
E C Document Center, Y-12, Bldg. 9734, MS-8130

cc w/o enclosure.
See Page 2

cc w/o enclosure:
Gary Riner, EM-91
Mark Belvin, FR-EM, ORNL Site Office
James Hall, LMER, Bldg. 6026, MS-6395
Sheila Thornton, Bechtel Jacobs, Bldg. K-1550-E, MS 7235
Jennifer Webb, LMES, Bldg. 9115, MS 8219, Y-12
Mick Wiest, LMES, Bldg. 9116, MS 8098, Y-12
Jack Newman, Bechtel Jacobs, 55 Jefferson, Room 117, MS 7604
Wayne Tolbert, SAIC, 800 Oak Ridge Turnpike, Oak Ridge, TN 37831

United States Government | Department of Energy

Oak Ridge Operations Office

memorandum

DATE: July 21, 1999

REPLY TO ATTN OF: SE-32:Moore

SUBJECT: NATIONAL HISTORIC PRESERVATION ACT, SECTION 106 COMPLIANCE, TRANSURANIC WASTE TREATMENT FACILITY, OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE

TO: Gary L. Riner, Program Manager, Transuranic Waste Treatment Facility, EM-921

Attached is a letter from the Tennessee State Historic Preservation Officer (SHPO) that concurs with the Department of Energy Oak Ridge Operations (DOE ORO) determination that the proposed construction, operation, and decontamination/decommission of a Transuranic (TRU) Waste Treatment Facility, Roane County, Tennessee, would have no adverse affect to properties included or eligible for inclusion in the National Register of Historic Places. With the SHPO's determination, DOE ORO has complied with Section 106 of the National Historic Preservation Act for this proposed project.

If you have questions or need additional information please call me at (423) 576-9574.

Ray T. Moore

Ray T. Moore
DOE ORO Cultural Resources
Management Coordinator

Attachment

cc w/attachment:
E.C. Document Center, Y-12, Bldg. 9734, MS-8130

cc w/o attachments:
Mark Belvin, ER-11, ORNL Site Office
James Hall, LMER, Bldg. 6026, MS-6395
Sheila Thornton, Bechtel Jacobs, Bldg. K-1550-E, MS 7235
Jennifer Webb, LMES, Bldg. 9115, MS 8219, Y-12
Mick Wiest, LMES, Bldg. 9116, MS 8098, Y-12
Wayne Tolbert, SAIC, 800 Oak Ridge Turnpike, Oak Ridge, TN 37831
Jack Newman, Bechtel Jacobs, 55 Jefferson, Room 117, MS 7604

TENNESSEE HISTORICAL COMMISSION
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
2941 LEBANON ROAD
NASHVILLE, TN 37243-0442
(615) 532-1550

July 2, 1999

Mr. Ray T. Moore
USDOE/Oak Ridge Operations
Post Office Box 2001
Oak Ridge, Tennessee 37831-8739

RE: DOE, TRANSURANIC WASTE TREATMENT FAC., OAK RIDGE, ROANE COUNTY

Dear Mr. Moore:

Pursuant to your request received by this office on Wednesday, June 30, 1999, this office has reviewed documentation concerning the above-referenced undertaking. This review is a requirement of Section 106 of the National Historic Preservation Act for compliance by the participating federal agency or applicant for federal assistance. Procedures for implementing Section 106 of the Act are codified at 36 CFR 800 (RIN3010-AA04: June 17, 1999), and an Agreement Document.

Considering available information, we find that the project as currently proposed will not adversely affect any property that is eligible for listing in the National Register of Historic Places. Therefore, this office has no objection to the implementation of this project.. Please direct questions and comments to Joe Garrison (615)532-1559. We appreciate your cooperation.

Sincerely,

Herbert L. Harper
Executive Director and
Deputy State Historic
Preservation Officer

HLH/jyg

OFFICIAL FILE COPY
ORNSO
C 0884
JUL 07 1999
2182.2

Department of Energy

Oak Ridge Operations Office
P.O. Box 2001
Oak Ridge, Tennessee 37831—

May 24, 2000

Dr. Lee A. Barclay, Ph.D.
Field Supervisor
Fish and Wildlife Service
446 Neal Street
Cookeville, Tennessee 38501

Dear Dr. Barclay:

ADDITIONAL INFORMAL CONSULTATION UNDER SECTION 7 OF THE ENDANGERED SPECIES ACT FOR THE PROPOSED TRANSURANIC WASTE TREATMENT PROJECT AT THE OAK RIDGE RESERVATION, OAK RIDGE, TENNESSEE

Thank you for your prompt reply to my letter dated June 2, 1999 concerning the proposed transuranic waste treatment project. As you requested, the Department of Energy (DOE) has prepared a Biological Assessment (BA) of the two federally listed species identified in your July 8, 1999 letter. Furthermore, one additional species mentioned in comments from the U.S. Department of the Interior (DOI), dated April 11, 2000 on the Draft Environmental Impact Statement (DEIS) was included in the BA.

The enclosed BA is submitted for your review and concurrence. Based on the BA, DOE has determined that the proposed project would not adversely affect any of the listed species during either the construction or operation activities. DOE will ensure that any potentially occurring Indiana bats are protected by not performing tree clearing during May through September when the bats are using their summer roosts. Results of the BA will be summarized in the text of the Final Environmental Impact Statement (FEIS) for the project and the BA will be appended to the FEIS.

Following your review of the BA, please check the appropriate concurrence block and sign below. Please fax your concurrence to me at (865)576-0746 as soon as possible, so that we may expeditiously complete the FEIS. If you need further information or wish to discuss the BA, please call me at (865)576-0938. Thank you in advance for your prompt reply.

Sincerely,

James L. Elmore

James L. Elmore, Ph.D.
Alternate NEPA Compliance Officer

☐ This Biological Assessment supports the conclusion that the proposed construction and operation of the transuranic waste treatment facility would not adversely impact federally listed protected species and/or habitat. With this BA, DOE has satisfied consultation requirements of Section 7 of the Endangered Species Act.

☐ This Biological Assessment does not support the conclusion that the proposed construction and operation of the transuranic waste treatment facility would not adversely impact federally listed protected species and/or habitat. DOE has not satisfied consultation requirements of Section 7 of the Endangered Species Act.

_____

Signature Date

Enclosure

cc:
Bill Cahill, EM-92
Wayne Tolbert, SAIC
Warren Webb, Bldg. 1505, MS-6036

THIS PAGE INTENTIONALLY LEFT BLANK

Endangered Species Act

BIOLOGICAL ASSESSMENT

Treating Transuranic (TRU)/Alpha Low-level Waste at the

Oak Ridge National Laboratory,

Oak Ridge, Tennessee

U.S. Department of Energy
Oak Ridge Operations Office
Oak Ridge, Tennessee 37831

May 2000

BIOLOGICAL ASSESSMENT FOR THREATENED AND ENDANGERED SPECIES UNDER SECTION 7 OF THE ENDANGERED SPECIES ACT FOR THE TREATING TRANSURANIC (TRU)/ALPHA LOW-LEVEL WASTE PROJECT AT THE OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE

SUMMARY

This biological assessment (BA) assesses potential impacts on three federally listed animal species that could result from the construction and operation of the Transuranic (TRU)/Alpha Low-level Waste Treatment Facility by the U.S. Department of Energy (DOE) on the preferred location in the Melton Valley watershed on the Oak Ridge Reservation (ORR). The species discussed in this BA are those mentioned in a letter from the U.S. Fish and Wildlife Service (FWS) to DOE, dated July 8, 1999 (FWS 1999a), as well as a species mentioned in comments from the U.S. Department of the Interior, dated April 11, 2000, on the *Draft Environmental Impact Statement (DEIS) for Treating Transuranic (TRU)/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee* (DOE 2000). The three species include two endangered mammals (gray bat and Indiana bat) and one endangered mollusk (pink mucket pearly mussel). None of the three species appears likely to be present on the proposed site, and proposed or designated critical habitats for the species are not present on or near the proposed site. However, caves that could provide potential roosting habitat for the gray bat are present within 4 miles of the proposed site. Suitable roosting habitat for the Indiana bat is also present within the vicinity of the proposed project. In addition, the Clinch River, lower White Oak Creek, and White Oak Lake, located adjacent to the proposed site, provide suitable foraging habitat for the gray bat and Indiana bat.

DOE staff conclude, based on the information presented in this BA, that the TRU Waste Treatment Facility is not likely to adversely affect any of the listed species during the construction or operation activities. Because the proposed site contains no proposed or designated critical habitat for the gray bat, Indiana bat, or pink mucket mussel, none would be affected. In addition, any potential adverse impacts to the Indiana bat would be eliminated by not cutting down any trees during the Indiana bat's summer roosting season from May through September. Such actions should prevent the loss of any bats that otherwise might be using the trees for rearing young and should eliminate the need for mist netting or detailed surveys. Although the project would require removal of suitable and potentially suitable roost trees, there are adequate numbers of suitable and potentially suitable roost trees available immediately adjacent to the proposed impact area. Construction activities would also not directly impact any of the potential foraging habitat that exists in the vicinity. Construction would occur only during the day, so any foraging by Indiana bats would not be disrupted. Activities associated with the operation of the proposed facility would also primarily occur during the day and would not disrupt any foraging Indiana bats near the site. DOE requests the concurrence of the FWS with these conclusions.

INTRODUCTION AND PROJECT DESCRIPTION

DOE proposes to proceed with construction and operation of the TRU Waste Treatment Facility at the preferred location in the Melton Valley watershed on the ORR (Fig. 1). The Preferred Alternative would involve construction of a three-and-one-half-story TRU Waste Treatment Facility on a trapezoid-shaped plot of land containing approximately 2 ha (5 acres). Dimensions of the 2-ha (5-acre) plot include a maximum length of approximately 214 m (703 ft), a maximum width of 114 m (375 ft), and a minimum width of 36 m (118 ft). Stormwater drainage would be directed around the facility by a series of culverts and drainage ditches. Construction of the TRU Waste Treatment Facility and the stormwater drainage ditches and culverts would result in the clearing of trees and other vegetation from much of the 2-ha (5-acre) site. Excavation of approximately 22,937 m^3 (30,000 yd^3) of soil would also be required during the construction activities. A pre-existing single-lane road that ran from Tennessee State Route 95 to the proposed facility [approximately 2 km (1.25 miles) in length] has already been upgraded to become the main access road. The road upgrade was completed after a categorical exclusion under the National Environmental Policy Act was completed [CX-TRU-98-007, *Construction/Relocation of Access Road at Oak Ridge National Laboratory, Oak Ridge, Tennessee* (DOE 1999)].

THIS PAGE INTENTIONALLY LEFT BLANK

ECOLOGICAL DESCRIPTION OF THE SITE

Past disturbances within the 2-ha (5-acre) site have shifted the types of terrestrial vegetation cover toward younger woodland compositions, with some sections of the parcel in early successional, herbaceous stages. The site also contains some cleared areas; two small, ephemeral streams; and two small wetlands. This section of the BA briefly describes each of these components. The sources of information summarized in this section include Jacobs and Pounds (1999), Jacobs and Rosensteel (1999), and Jacobs and Schacher (1999).

Woodland habitats are present on the knolls, ridges, and upland portions of the site. The site is at the base of Copper Ridge on the northwest side, with drainages to the east and west of a small side ridge off Copper Ridge. The Nolichucky Shale outcrops in upland areas. There is partial clearing along two of the site boundaries, but most of the site is still vegetated. Trees on the site are generally young.

Virginia pine (*Pinus virginiana*) is dominant in the western slope area, but drop out toward the eastern part of the slope. There are some white pines (*P. strobus*) in the middle section of the slope. Sugar maple (*Acer saccharrum*) and various oaks (*Quercus* sp.) become more common as the pines fade out. On the eastern drainage area, red bud (*Cercis canadensis*), tulip poplar (*Liriodendron tulipifera*), red maple (*Acer rubrum*), and box elder (*Acer negundo*) are dominant. Soft rush (*Juncus effusus*) and two exotics, Japanese honeysuckle (*Lonicera japonica*) and Nepal grass (*Microstegium virmineum*), are common herbaceous vegetation in the eastern drainage. In the upper middle portion of the eastern drainage, deciduous trees (oaks) and pines are common, along with shrubs such as blueberries (*Vaccinium arboreum* and *V. stamineum*), rusty viburnum (*Viburnum rufidulum*), juneberry (*Amelanchier sp.*), and hop hornbeam (*Ostrya virginiana*). There are areas of closed canopy and partially open canopy in the woodland areas. The soil surface is firm and gravelly, with minimal buildup of organic matter. There are no caves or large rock outcrops on the site.

On the western and eastern boundaries of the site, small, ephemeral streams flow down from the wooded uplands toward the access road. The stream channel on the eastern slope is well-defined, with silt, gravel, rootwads, and small rocks. The stream on the western boundary flows from the woodland through a disturbed, slash, and early successional habitat to form a small pool with growths of young black willow (*Salix nigra*) and herbaceous vegetation. Both streams have small wetlands associated with them, which are described below.

A palustrine scrub-shrub wetland (PSS1A/B) exists in the ephemeral stream on the eastern side of the site. The soil is temporarily flooded and saturated, mostly due to an old road-crossing culvert that is on the downstream side of the wetland. The culvert acts to slow and retain stream flow. The dominant vegetation in the wetland includes sweetgum (*Liquidambar styraciflua*), green ash (*Fraxinus pennsylvanica*) saplings, silky dogwood (*Cornus* sp.), sedges (*Carex* sp.), and various herbaceous species. The soil includes fine gravel alluvium and a silt loam with low chroma matrix, mottles, and partially decomposed plant fragments.

A palustrine, saturated, emergent wetland (PEM1B) is located on the ephemeral stream on the western side of the site. The wetland developed in a seep area, but the hydrology is at least partially due to the slowing of stream and groundwater flow by a culvert under the old Melton Valley Road, which forms a small pool. Dominant vegetation identified during a survey in April 1992 included black willow, soft rush, cattails (*Typha latifolia*), fox sedge (*Carex vulpinoidea*), shallow sedge (*C. lurida*), and rice cutgrass (*Leersia oryzoides*).

ECOLOGICAL DESCRIPTION AND POTENTIAL IMPACTS OF THE PROJECT ON LISTED SPECIES

The general ecology of federally listed species that are known to occur near the site and the expected potential impacts on them from the project are summarized below. Unless otherwise noted, general biological information on the species is derived from the published literature, reports, and Internet resources listed under each species heading.

Gray Bat (*Myotis grisescens*)

Unless otherwise noted or referenced, the following general biological information on the gray bat is derived from FWS (1991), Harvey (1992), and Kentucky Bat Working Group (KBWG) (2000). The core range of the endangered gray bat encompasses the cave regions of Alabama, northern Arkansas, Kentucky, Missouri, and Tennessee, but a few occur in northwestern Florida, western Georgia, southwestern Kansas, south Indiana, south and southwestern Illinois, northeastern Oklahoma, northeastern Mississippi, western Virginia, and possibly western North Carolina. Gray bats are restricted to caves or cave-like habitats, and few caves meet their specific roost requirements. These restrictions result in about 95% of the populations hibernating in only eight or nine caves. For hibernation, the roost site must have an average temperature of 5.6°C to 11.1°C (42°F to 52°F). Most of the caves used by gray bats for hibernation have deep vertical passages with large rooms that function as cold air traps. Summer caves must be warm, between 13.9°C to 25.0°C (57°F and 77°F), or have small rooms or domes that can trap the body heat of roosting bats. Summer caves are normally located close to rivers or lakes where the bats feed. Gray bats have been known to fly as far as 12 miles or more from their colony to feed.

Gray bats roost, breed, rear young, and hibernate in caves year round. They migrate between summer and winter caves and will use transient or stopover caves along the way. One-way migrating distance between winter and summer caves may vary from as little as 16.09 km (10 miles) to well over 321.8 km (200 miles). Mating occurs as bats return to winter caves in September and October. By November most gray bats are hibernating. Adult females begin to emerge in late March, followed by juveniles and adult males. Females store sperm over the winter and become pregnant the following spring. A few hundred to many thousands of pregnant females congregate to form maternity colonies. Males and nonreproductive females gather in smaller groups to form what are known as bachelor colonies. A single pup is born in late May or early June. The young begin to fly 20 to 25 days after birth. Gray bats primarily feed on flying insects over lakes, rivers, and streams. Aquatic insects, particularly mayflies, make up most of their diet.

Information about the occurrence of gray bats on the ORR is limited. In November 1994, a single, dead gray bat was found in a display cabinet in Building 9204-3 at the Oak Ridge Y-12 Plant. The bat was probably an isolated individual juvenile that became lost, disoriented, and trapped. Mist netting for bats was conducted on the lower East Fork Poplar Creek and its tributaries in May 1992 and again in May–June 1997 (Harvey 1997). The 1997 survey included portions of lower Bear Creek near its confluence with lower East Fork Poplar Creek. The creeks in this area provided good gray bat foraging habitat at the time of the surveys. No gray bats were recorded among the six species captured. More than 20 caves have been identified on the ORR. Seven of the caves (Copper Ridge, Flashlight Heaven, Walker Branch, Big Turtle, Little Turtle, Pinnacle, and Bull Bluff) were surveyed by Mitchell et al. (1996), but no gray bats were found. There is an unverified report of ten gray bats roosting in Little Turtle Cave in September 1996. These bats were observed roosting and were not further disturbed; therefore, a definite, in-the-hand identification was not made (Webb 1996). Examination of photographs taken of the roosting bats indicate that they appeared to be *Myotis* and more than likely were gray bats, but the species could not be positively determined [Major (2000) and Henry (2000)].

Although no caves are present within the area of the proposed project, several caves are located within 6.4 km (4 miles) of the proposed site location and two of the caves are located within 2.4 km (1.5 miles). None of the caves has been completely and systematically surveyed for bats, except for the limited surveys reported in Mitchell et al. (1996) and the 1996 report of *Myotis* roosting in Little Turtle Cave. The caves within the vicinity of the project area may not provide adequate hibernacula for gray bats, but they could provide transient or stopover roosting habitat for migrating gray bats. Suitable foraging habitat for gray bats within the vicinity of the proposed facility includes the Clinch River, lower White Oak Creek, and White Oak Lake. Upper White Oak Creek, the unnamed tributary to White Oak Creek, and Melton Branch are narrow, small streams and are considered suboptimal for frequent foraging for gray bats. No caves would be disturbed during the construction of the proposed facility, and construction activities would also not directly impact any of the potential foraging habitat that exists in the vicinity. Construction would occur only during the day, so any foraging by gray bats would not be disrupted. Activities associated with the operation of the proposed facility would also primarily occur during the day and would not disrupt any gray bats that might forage near the site. In addition, no significant emissions or effluents would be produced by the facility that could directly impact foraging gray bats or indirectly affect aquatic insect fauna on which the gray bats would prey. Thus, the proposed project is unlikely to adversely affect the gray bat or its habitat.

Pink mucket pearly mussel (*Lampsilis arbrupta* Say-1831; also called *L. orbiculata* Hildreth-1828)
(http://fwie.fw.vt.edu/WWW/esis/lists/e404009.htm)
(EPA 2000; http://www/epa/gov/espp/arkansas/seviert.htm)

The endangered pink mucket pearly mussel [41 FR 24062; June 14, 1976] is a bivalve aquatic mollusk in the Unionidae family with an elliptical-shaped shell. The species is generally about 10.2 cm (4 in.) long, 6.1 cm (2.4 in.) wide, and 7.6 cm (3 in.) high. The valves are heavy and thick. The species is sexually dimorphic, with both males and females having rounded anterior margins, but males having a pointed posterior margins and females a truncated, expanded posterior to accommodate the gravid condition. Young mussels have a yellow to brown shell that is smooth and glossy with green rays, while older specimens are dull brown. The nacre color varies from white to pink, with the posterior margin iridescent. The early life stage of the mussel, glochidia, is an obligate parasite on the gills or fins of fish, but the required fish host species are unknown. The adult mussels are filter feeders and consume particulate matter that is suspended in the water column. Identifiable stomach contents from mussels invariably include mud, desmids, diatoms, protozoa, and zooplankton. However, studies on the food habits for this species have not been conducted, so its specific food requirements are not known. The species has no known commercial value. The reproductive cycle of the pink mucket is presumed to be similar to that of other freshwater mussels. Males release sperm into the water column, which is then taken up by the females during siphoning and results in the eggs being fertilized. The embryos develop into the glochidia inside the female and are then released into the water column. The glochidia must then attach to a suitable fish host for metamorphosis to the free-living juvenile stage. There is no information on the population biology for this species.

The pink mucket is found in medium to large rivers. It seems to prefer larger rivers with moderate to fast-flowing water, at depths from 0.5 to 8.0 m (1.6 to 26.2 ft). The species has been found in substrates including gravel, cobble, sand, or boulders. Silt clogs the species' siphon, so silty substrates and water columns are not conducive to the species being present. Habitat of the glochidia is initially within the gills of the female, then in the water column, and finally attached to a suitable fish host. Habitat requirements for the juvenile stage are unknown. Any alteration of the life-stage-specific habitats during the pink mucket's lifecycle would likely affect the long-term success of a population. In addition, impoundments and surface water contaminants are known to adversely affect this species and contribute to its decline in numbers.

Currently, the pink mucket is known in 16 rivers and tributaries from 7 states, with the greatest concentrations in the Tennessee (TN, AL) and Cumberland (TN, KY) rivers and in the Osage and Meramec rivers in Missouri. Smaller populations have been found in the Clinch River (TN); Green River (KY); Kwanawha River (WV); Big, Black and Little Black, and Gasconde rivers (MO); and Current and Spring rivers (AR). The FWS indicated that the pink mucket is known to occur near the project area (FWS 1999a). However, pink muckets have not been observed on the proposed site for the TRU Waste Treatment Facility. Furthermore, the aquatic habitat in the bodies of water closest to the proposed facility (Melton Branch, White Oak Creek, and White Oak Lake) is not appropriate to support the pink mucket. Melton Branch is a small stream with low flow. White Oak Creek is somewhat larger, but still relatively small and has slow flow due to the impoundment (White Oak Lake) into which it flows. White Oak Creek and White Oak Lake also receive contaminant inputs from several sources, as described in the Cumulative Impacts section in the DEIS (DOE 2000). White Oak Lake is an impoundment of White Oak Creek. As mentioned above, impoundments and water contaminants are known to be adverse for pink muckets. Therefore, the combination of unsuitable stream sizes, improper habitat (impoundment), and presence of contaminants leads DOE to conclude that the presence of pink mucket pearly mussel on or nearby the proposed TRU Waste Treatment Facility site is extremely unlikely.

Indiana bat (*Myotis sodalis*)

Unless otherwise noted or referenced, the following general biological information on the Indiana bat is derived from FWS (1991, 1999b, 1999c, 2000), Harvey (1992), and KBWG (1997, 2000). The Indiana bat is a migratory species found throughout much of the eastern half of the United States from Oklahoma, Iowa, and Wisconsin east to Vermont and south to northwestern Florida. For hibernation, Indiana bats prefer limestone caves with stable temperatures of 3.3°C to 6.1°C (38°F to 43°F) and high relative humidity. As with the gray bat, few caves meet the specific roost requirements of the species. Subsequently, more than 85% of the population hibernates in only nine sites. However, Indiana bats have been found hibernating in a few abandoned mines, a tunnel, and a hydroelectric dam. The bats hibernate from October to April, depending on climatic conditions. Density in tightly packed clusters is usually estimated at 3228 bats per square meter (300 bats per square foot), although as many as 5165 bats per square meter (480 per square foot) have been reported.

Female Indiana bats depart hibernation caves before males and arrive at summer maternity roosts in mid-May. A single offspring is born between late June and early July. The young bats can fly within a month of birth. Early researchers considered floodplain and riparian forest to be the primary roosting and foraging habitats used during the summer by the Indiana bat, and these forest types unquestionably are important. More recently, upland forest has been shown to be used by Indiana bats for roosting. Within the range of the species, the existence of Indiana bats in a particular area may be governed by the availability of natural roost structures, primarily standing dead trees with loose bark. The suitability of any tree as a roost site is determined by (1) its condition (dead or alive), (2) the quantity of loose bark, (3) the tree's solar exposure and location in relation to other trees, and (4) the tree's spatial relationship to water sources and foraging areas. The most important characteristic of roost trees is probably not species but structure (i.e., exfoliating bark with space for bats to roost between the bark and the bole of the tree). To a limited extent, tree cavities and crevices are also used for roosting. Maternity colonies use multiple primary roost trees, which are used by a majority of the bats most of the summer, and a number of "secondary" roosts, which are used intermittently and by fewer bats, especially during periods of precipitation or extreme temperatures. The summer roost of adult males is often near maternity roosts, but where most spend the day is unknown. Others remain near the hibernaculum, and a few males are found in other caves during summer. Researchers have found that primary roosts are generally in openings or at the edge of forest stands, while alternate roosts can be either in the open or in the interior of the forest stands. Indiana bats use roosts in the spring and fall similar to those selected during the summer. During

the fall, when Indiana bats swarm and mate at their hibernacula, male bats roost in trees nearby during the day and fly to the cave during the night.

Indiana bats forage in and around the tree canopy of floodplain, riparian, and upland forest. In riparian areas, Indiana bats primarily forage around and near riparian and floodplain trees (e.g., sycamore, cottonwood, black walnut, black willow, and oaks), and solitary trees and forest edge on the floodplain. Streams, associated floodplain forests, and impounded bodies of water (e.g., ponds, wetlands, and reservoirs) are preferred foraging habitat for pregnant and lactating Indiana bats, some of which may fly up to 1.5 miles from upland roosts. Indiana bats also forage within the canopy of upland forests, over clearings with early successional vegetation (e.g., old fields), along the borders of croplands, along wooded fencerows, and over farm ponds in pastures. Indiana bats return nightly to their foraging areas. Indiana bats feed strictly on flying insects, and their selection of prey items reflects the environment in which they forage. Both aquatic and terrestrial insects are consumed. Moths, caddisflies, flies, mosquitoes, and midges are major prey items. Other prey include bees, wasps, flying ants, beetles, leafhoppers, and treehoppers. During September, the bats depart for hibernation caves.

Information about the occurrence of Indiana bats on the ORR is limited. Mist netting for bats was conducted on lower East Fork Poplar Creek and its tributaries in May 1992 and again in May–June 1997 (Harvey 1997). The 1997 survey included portions of lower Bear Creek near its confluence with lower East Fork Poplar Creek. The creeks in this area provided Indiana bat summer roosting and foraging habitat at the time of the surveys. No Indiana bats were recorded among the six species captured.

In Tennessee, the nearest hibernating population of Indiana bats exists in White Oak Blowhole Cave, located in Blount County in the western end of the Great Smoky Mountains National Park. This cave has been designated as critical habitat for this species. A few Indiana bats also hibernate in Bull Cave, also located in Blount County. No maternity roosts have been located on the ORR, or as yet in Tennessee. However, in July 1999 a small colony of Indiana bats was discovered roosting in a dead hemlock tree on the Cheoah Ranger District of the Nantahala National Forest in Graham County, North Carolina. This discovery represents the first record of a reproductive female Indiana bat being found south of Kentucky. Recent collections of individual Indiana bats have also been recorded from the Cherokee National Forest near Tellico Lake in Monroe County, Tennessee. These reports indicate that summer colonies of the species may be present in east Tennessee. The habitat from which these individuals were collected is similar to suitable habitat found on the ORR.

Suitable habitat for the Indiana bat is present within the vicinity of the proposed project location. A site inspection conducted by FWS personnel as part of the Melton Valley Remedial Investigation/Feasibility Study noted that Class 1 and Class 2 tree species of suitable sizes to support primary and secondary maternity roosting habitat for the Indiana bat existed adjacent to the new access road to the proposed facility. Suitable tree species for maternity roosting habitat is also present on the site proposed for the facility. Information provided by the FWS on the components of suitable habitat for the Indiana bat is provided in Attachment 1. Suitable foraging habitat for Indiana bats within the vicinity of the proposed facility includes the Clinch River, lower White Oak Creek, and White Oak Lake. Upper White Oak Creek, the unnamed tributary to White Oak Creek, and Melton Branch are narrow, small streams and are considered suboptimal for frequent foraging for Indiana bats. Although unlikely, a maternity colony, an adult male colony, or individual Indiana bats could use roosting habitat located in the vicinity of the proposed project. Any potential adverse impacts to the Indiana bat would be eliminated by not cutting down any trees during the Indiana bat's summer roosting season from May through September. Such actions should prevent the loss of any bats that otherwise might be using the trees for rearing young and should also eliminate the need for mist netting or detailed surveys. Although the project would require removal of suitable and potentially suitable roost trees, there are adequate numbers of suitable and potentially suitable roost trees available immediately adjacent to the proposed impact area. Construction

activities would also not directly impact any of the potential foraging habitat that exists in the vicinity. Construction would occur only during the day, so any foraging by Indiana bats would not be disrupted. Activities associated with the operation of the proposed facility would also primarily occur during the day and would not disrupt any foraging Indiana bats near the site. In addition, no significant emissions or effluents would be produced by the facility that could directly impact foraging Indiana bats or indirectly affect aquatic insect fauna that the Indiana bats would prey on.

REFERENCES

CMI-FWIE (Conservation Management Institute-Fish and Wildlife Information Exchange). 1996. *(Draft)—Taxonomy Species Mussel, Pearly, Mucket, Pink Species, Id. ESIS404009*, Web site: http://fwie.fw.vt.edu/WWW/esis/lists/404009.htm. Date 13 MAR 96. Conservation Management Institute, College of Natural Resources, Virginia Tech, Blacksburg, Virginia.

DOE (U.S. Department of Energy). 2000. *Draft Environmental Impact Statement (DEIS) for Treating Transuranic (TRU)/Alpha Low-level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee.* Prepared for the U.S. Department of Energy by Science Applications International Corporation, Oak Ridge, Tennessee.

DOE. 1999. *Construction/Relocation of Access Road at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, CX-TRU-98-007, U.S. Department of Energy, Oak Ridge Operations Office, Oak Ridge, Tennessee.

EPA (U.S. Environmental Protection Agency). 2000. "Pink mucket pearly mussel [*Lampsilis orbiculata*]." Office of Pesticide Programs. Available at <http://www/epa.gov/espp/arkansas/seviert.htm>.

FWS (U.S. Fish and Wildlife Service). 1991. *Endangered and Threatened Species of the Southeastern United States (The Red Book)*, FWS Region 4. February 1991.

FWS. 1999a. Letter from Dr. Lee A. Barclay, U.S. Fish and Wildlife Service, Cookeville, Tennessee, to Dr. James L. Elmore, U.S. Department of Energy, Oak Ridge, Tennessee, July 8, 1999.

FWS. 1999b. *Indiana Bat*. Asheville Field Office. August 1999.

FWS. 1999c. *Agency Draft Indiana Bat* (Myotis sodalis) *Revised Recovery Plan*. Fort Snelling, Minnesota. 53 pp.

FWS. 2000. *The Indiana Bat in Western North Carolina, A Status Summary Update*. Asheville Field Office. April.

Harvey, Michael J. 1992. *Bats of the Eastern United States*. Arkansas Game and Fish Commission and U.S. Fish and Wildlife Service. February. 46 pp.

Harvey, Michael J. 1997. *Survey for Endangered and Threatened Bats on Parcel ED-1, Oak Ridge Reservation*. July. 24 pp.

Henry, Hill. 2000. Personal communication from Hill Henry, Tennessee Valley Authority, to Mike Deacon, Science Applications International Corporation, May 4, 2000.

Jacobs (Jacobs Environmental Management Team) and L. Pounds. 1999. *Findings of the Survey for Rare Plants on the Proposed Transuranic Waste Facility Site in Melton Valley, Oak Ridge Reservation, Oak Ridge, Tennessee*. Prepared for Bechtel Jacobs Company LLC under Contract No. DE-AC05-98OR22700. 8 pp.

Jacobs (Jacobs Environmental Management Team) and B. A. Rosensteel. 1999. *Findings of Wetland Delineation on the Proposed Transuranic Waste Facility Site in Melton Valley, Oak Ridge Reservation, Oak Ridge, Tennessee*. Prepared for Bechtel Jacobs Company LLC under Contract No. DE-AC05-98OR22700. 8 pp.

Jacobs (Jacobs Environmental Management Team) and W. H. Schacher. 1999. *Findings of the Survey for Sensitive Terrestrial Animal Species at the Proposed Transuranic Waste Facility Site in Melton Valley, Oak Ridge Reservation, Oak Ridge, Tennessee*. Prepared for Bechtel Jacobs Company LLC under Contract No. DE-AC05-98OR22700. 22 pp.

KBWG (Kentucky Bat Working Group). 1997. "Protection and Enhancement Plan for the Indiana Bat." Available at <http://www.biology.eku.edu/bats/indbat-recmanageplan.htm>. June 1997.

KBWG. 2000. "The Bats of Kentucky." Available at <http://www.biology.eku.edu/bats>.

Major, Smoot. 2000. Personal communication from Smoot Major, Tennessee Department of Environment and Conservation, Division of Natural Heritage, to Mike Deacon, Science Applications International Corporation, May 4, 2000.

Mitchell, J. M., E. R. Vail, J. W. Webb, J. W. Evans, A. L. King, P. A. Hamlett. 1996. *Survey of Protected Terrestrial Vertebrates on the Oak Ridge Reservation*, ES/ER/TM-188/R1, Final Report. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Webb, Warren. 1996. Personal communication with Deborah Awl, JAYCOR , September 18, 1996.

APPENDIX F

CALCULATIONS PACKAGES

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX F.1

UNIVERSAL SOIL LOSS CALCULATIONS

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX F.1

UNIVERSAL SOIL LOSS CALCULATIONS

Erosion at the proposed Transuranic (TRU) Waste Treatment Project site was modeled using the Revised Universal Soil Loss Equation (RUSLE), Version 1.06 (Toy and Foster 1998). RUSLE is a set of mathematical equations that estimate soil loss resulting from interrill and rill erosion (Lal 1994). RUSLE utilizes the basic formula of the Universal Soil Loss Equation as developed by Wischmeier and Smith (1978):

$$A = R * K * LS * C * P$$

where:

A = average annual soil loss in tons per acre,
R = rainfall/runoff erosivity,
K = soil erodibility,
LS = hillside length and steepness,
C = cover management,
P = soil conservation practices.

For the purposes of this analysis, the RUSLE was run assuming three scenarios. For each of the three scenarios, the R, K, and LS factors values did not vary. The R factor (180) used the climatic database for Knoxville, Tennessee. The initial K factor (0.37) was selected from soils mapped in Anderson County, Tennessee (Moneymaker 1981), with similar lithology and parent material to soils mapped at the TRU site. The RUSLE further modifies the initial K values based on variations in climatic data (R factor) through the year. The LS value was calculated from RUSLE using a slope with a total length of 91.5 m (300 ft) and a 30% slope.

The first scenario assumed a worst-case condition, in which virtually no cover management practices were utilized to protect bare soils at the proposed construction site from the erosive energy of precipitation. The second-case scenario was run under the assumption that minimal cover management and conservation practices (some mulching to protect bare soil from precipitation) were utilized to provide a small amount of erosion prevention. The third scenario assumed intensive conservation practices (mulching, silt fences, and sediment basins) to provide maximum protection from erosion.

Results of the model runs for scenarios 1, 2, and 3 are displayed in Table 1 below. Based on Scenario 1 (no cover management practices), predicted soil loss could be expected to be as high as 404.7 metric tons per hectare per year (180.5 tons per acre per year). The tolerable soil loss published for similar soils is 6.7 metric tons per hectare per year (3 tons per acre per year) (Moneymaker 1981). Based on Scenario 2 (minimal cover management practices), predicted soil loss would be somewhat less than for Scenario 1, but could still as high as 188.8 metric tons per hectare per year (84.2 tons per acre per year). The predicted soil loss is still much higher than the published tolerance value. In Scenario 3 (intensive cover management practices), predicted soil loss would be further reduced to 2.2 metric tons per hectare per year (1.0 ton per acre per year), well within the published tolerable limits.

Table 1. Predicted soil loss at proposed TRU waste facility under varying degrees of cover management practices

Scenario	R factor	K factor	LS factor	C factor	P factor	A
1	180	0.359	12.53	0.2229	1.00	180.5
2	180	0.359	12.53	0.1040	1.00	84.2
3	180	0.359	12.53	0.0011	1.00	1.0

REFERENCES

Lal, R. 1994. *Soil Erosion Research Methods*, Soil and Water Conservation Society, Ames, Iowa, and St. Lucie Press, Del Ray, Florida, second edition, 340 pp.

Moneymaker, R. H. 1981. *Soil Survey of Anderson County, Tennessee*, U.S. Department of Agriculture, Soil Conservation Service in cooperation with Tennessee Agricultural Experiment Station, 165 pp. plus maps.

Toy, T. J., and G. R. Foster. *Guidelines for the Use of the Revised Universal Soil Loss Equation (RUSLE) (Version 1.06) on Mined Lands, Construction Sites, and Reclaimed Lands*, Department of Interior, Office of Surface Mining, Denver, Colorado.

Wischmeier, W. H., and D. D. Smith 1978. *Predicting Rainfall Erosion Losses – a Guide to Conservation Planning*, U.S. Department of Agriculture, Agriculture handbook No. 537, 58 pp.

APPENDIX F.2

ECOLOGICAL IMPACTS FROM A SEISMICALLY INDUCED BREACH OF THE MELTON VALLEY STORAGE TANKS

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX F.2

IMPACTS TO AQUATIC BIOTA FROM A SEISMICALLY INDUCED BREACH OF THE MELTON VALLEY STORAGE TANKS

ASSUMPTIONS

As a reasonable worst case, it was assumed that the release from the ruptured tank is rapid, so the tank contents would rapidly be transported to Melton Branch. Therefore, undiluted concentrations of radionuclides were used for the initial exposure and risk calculations. Releases of radionuclides were evaluated for two tanks, Tank 26, which has the highest gross beta/gamma, and Tank 28, which has the highest gross alpha (Keeler et al. 1996). It was assumed that White Oak Lake, with an area of 6 to 8 hectares (ha) (Loar 1992), has a volume of approximately 3 to 6 million cubic feet and an average daily flow of 1.3 million cubic feet. The tank volume of 50,000 gal is equal to approximately 6,400 cubic feet, resulting in a dilution factor of about 450 to 900 in White Oak Lake.

Radiological benchmarks for exposure of aquatic biota to radionuclides in water and sediment have been developed by Bechtel Jacobs (1998) and were used to evaluate exposure of aquatic biota to radionuclides in water from the Melton Valley tanks. Dietary and ingestion rate information for herons is presented in Table 1. Radionuclide decay energies and absorption factors are presented in Table 2.

Table 1. Receptor Parameters for Great Blue Heron

Parameter	Definition	Receptor: Great blue heron *(Ardea herodias)*	
		Value	Reference/Notes
BW	Body weight (kg)	2.39	Arithmetic mean, adult, both sexes, location not stated (EPA 1993)
HR	Home range (km)	3.1	Foraging distance, mean, adults, both sexes, South Dakota, stream (EPA 1993)
TUF	Temporal use factor	1	Will be 1 unless a specific value exists for a receptor
IR_F	Food ingestion rate (g/g-d = kg/kgBW/d)[a]	0.18	EPA (1993)
PF	Plant fraction	0	None listed as dietary intake in EPA (1993)
AF	Animal fraction	1	98% Aquatic vertebrates, lower Michigan, river (EPA 1993)
SF	Soil fraction	0	Not reported in EPA (1993); assumed to be negligible
IR_w	Water ingestion rate (g/g-d = L/kgBW/d)	0.045	Estimated (EPA 1993)

[a]Food ingestion rate (g/g-d) reexpressed as kg/kgBW/d is assumed not to include ingested soil; therefore, PF+AF = 1.0.
EPA = U.S. Environmental Protection Agency.

The acceptable chronic dose of radiation to aquatic biota is 1 rad/d (NCRP 1991), and it is assumed that an acute dose 100 times that number is also acceptable. For birds, the acceptable chronic dose is 0.1 rad/d (IAEA 1992), while acute doses of 10 rad/d appear unlikely to cause long-term deleterious effects (IAEA 1992).

Table 2. Radiological Exposure Parameters for Ecological Radiological Constituents of Potential Concern

Ecological constituent of potential concern		Decay energy and absorption parameters					
	DCF[a]	$E_a n_a$[b]	F[c]	$E_b n_b$[d]	F[e]	$E_g n_g$[f]	F[e]
Radionuclides							
Cesium-134	9.50E-14	0.00E+00	1.00E+00	1.64E-01	1.00E+00	1.56E+00	4.10E-02
Cesium-137	1.29E-15	0.00E+00	1.00E+00	1.87E-01	1.00E+00	0.00E+00	1.00E+00
Cobalt-60	2.37E-11	0.00E+00	1.00E+00	9.70E-02	1.00E+00	2.50E+00	4.00E-02
Iodine-129	7.70E-14	0.00E+00	1.00E+00	6.40E-02	1.00E+00	2.50E-02	2.20E-01
Strontium-90	1.26E-15	0.00E+00	1.00E+00	1.96E-01	1.00E+00	0.00E+00	1.00E+00
Technetium-99	2.71E-16	0.00E+00	1.00E+00	1.01E-01	1.00E+00	0.00E+00	1.00E+00
Uranium-233	3.14E-15	4.82E+00	1.00E+00	1.30E-02	1.00E+00	2.00E-03	9.40E-01
Uranium-238	6.87E-16	4.19E+00	1.00E+00	1.00E-02	1.00E+00	1.00E-03	9.40E-01

[a]Dose conversion factor for immersion in water (Table III.2, Eckerman and Ryman 1993, converted to Sv/d per Bq/m^3).

[b]Alpha energy of the radionuclide (MeV) × proportion of disintegrations producing an a-particle (Table A.1, Eckerman and Ryman 1993).

[c]Absorbed fraction of energy E_a (assumed to be 1.0 for alpha radiations).

[d]Beta energy of the radionuclide (MeV) × proportion of disintegrations producing a b-particle (Table A.1, Eckerman and Ryman 1993).

[e]Absorbed fraction of energy E_b or E_g (Blaylock, Frank, and O'Neal 1993; DOE 1997).

[f]Photon energy emitted during transition from a higher to a lower energy state (MeV) × proportion of disintegrations producing a g-particle (Table A.1, Eckerman and Ryman 1993).

AQUATIC BIOTA

The concentrations of potassium, sodium, and nitrate are high. The combined concentrations of these ions (ionic strengths) are 10.4 M (mole/L, where mole is defined as a number of grams equal to the molecular weight of the constituent) in Tank 26 and 14.1 M in Tank 28. Concentrations are similar in the other tanks. The pH in Tanks 26 and 28 is 8.4 and 7.3, respectively, but the pH in Tank 31 is 10 and in the other tanks is above 12. These ionic strengths and the pH in all tanks other than Tanks 26 and 28 would be immediately lethal to aquatic biota [the toxicity benchmark for sodium is ~0.03 M (Suter and Tsao 1996)]. Sufficient dilution and neutralization to prevent lethality are not likely before the slug of contaminants reaches White Oak Lake. Therefore, an approximately 1-km (0.6-mile) stretch of Melton Branch and White Oak Creek would be depopulated of aquatic biota. The slug of contaminants would probably pass into White Oak Lake in a day or two. Recovery and repopulation of the creek stretches would likely require up to one year as contaminants are flushed out by cleaner water from upstream.

External radiological exposures to water were estimated as described by Bechtel Jacobs (1998). Concentrations of radionuclides in tank water were divided by benchmark values for exposure of aquatic biota (or a benchmark for I-129 derived by the same methods). The hazard quotient (HQ) was calculated for each radionuclide and summed to determine the hazard index (HI) for each tank. These calculations are shown in Table 3. The HIs were approximately 8,900 for Tank 26 and 3,700 for Tank 28. However, the benchmarks were derived for chronic exposure, and the calculated exposures were predominantly internal, resulting from bioconcentration of radionuclides and ingestion of contaminated biota. Acute external exposures to water alone in Melton Branch would be negligible (Table 3).

Table 3. Radiological Exposure of Aquatic Biota to Radionuclides in Storage Tanks 26 and 28

Ecological constituent of potential concern	Tank 26					Tank 28			
	Bench-mark pCi/L	Tank conc. (Bq/mL)	RME (pCi/L)	HQ RME/ Bench-mark	External Dose[a] (rad/d)	Tank conc. (Bq/mL)	RME (pCi/L)	HQ RME/ Benchmark	External Dose (rad/d)
Radionuclides									
Cesium-134	5.98E+03	2.00E+04	7.40E+05	1.24E+02	5.64E-02	2.40E+03	8.88E+04	1.48E+01	6.77E-03
Cesium-137	5.93E+03	1.40E+06	5.18E+07	8.74E+03	0.00E+00	5.70E+05	2.11E+07	3.56E+03	0.00E+00
Cobalt-60	5.31E+03	2.20E+03	8.14E+04	1.53E+01	1.00E-02	3.70E+03	1.37E+05	2.58E+01	1.68E-02
Iodine-129	3.35E+05	7.80E-02	2.89E+00	8.62E-06	2.88E-09	1.90E-02	7.03E-01	2.10E-06	7.01E-10
Strontium-90	5.77E+04	2.50E+04	9.25E+05	1.60E+01	0.00E+00	1.50E+05	5.55E+06	9.62E+01	0.00E+00
Technetium-99	1.94E+06	1.90E+03	1.94E+06	1.00E+00	0.00E+00	4.10E+02	1.52E+04	7.82E-03	0.00E+00
Uranium-233	4.00E+03	3.80E+00	1.41E+02	3.52E-02	8.62E-10	6.08E+01	2.25E+03	5.62E-01	1.38E-08
Uranium-238	4.55E+03	1.00E-01	3.70E+00	8.13E-04	1.13E-11	1.80E+00	6.66E+01	1.46E-02	2.04E-10
			Sum	8.89E+03	6.64E-02			3.69E+03	2.36E-02

[a]External dose = $5.11 \times 10^{-8} \times E_\gamma n_\gamma \times (1-\Phi_\gamma) \times$ RME (Bechtel Jacobs 1998).
HQ = hazard quotient.
RME = reasonable maximum exposure.

Dilution of the contaminants in White Oak Lake would result (after complete mixing) in HIs of approximately 10 to 20 for Tank 26 and 4 to 8 for Tank 28. Therefore, chronic radiation toxicity to aquatic biota in White Oak Lake is likely. If the radionuclides were not retained by White Oak Dam and the downstream containment system, they would rapidly be diluted in the Clinch River below levels of concern for aquatic biota.

The time required to dilute contaminants in White Oak Lake can be estimated from the estimated flow rate and volume of the lake, assuming rapid mixing and a constant flow rate. The rate of loss of total mass of radionuclides (-dM/dt) is the product of the flow rate and the concentration at any given time (FxC, where F is the flow rate and C is the concentration). C is defined as mass divided by volume, i.e., C = M/V (where V is the total volume of the lake). Therefore, -dM/dt = FxM/V. This formula is rearranged and integrated to find the mass (M) at any given time (t) relative to the starting mass (Mo):

$$\ln(M/Mo) = -t \times F/V ,$$

and

$$t = -\ln(M/Mo)/(F/V) .$$

Because F is assumed to be 1.3×10^6 ft^3/d and V is assumed to be 3 to 6×10^6 ft^3, F/V ranges between 0.2 and 0.4. To reduce the HI, which ranged from 8 to 20, to 1 requires a reduction of total mass to 1/4 to 1/20 of the initial mass, i.e., M/Mo ranges from 0.05 to 0.25. Substituting into the second equation above, the time t required to dilute the contaminants in White Oak Lake below the radiological benchmark is from 3 to 15 days. If mixing with fresh water entering the lake is slow, parts of the lake will require longer for concentrations to drop below benchmark levels.

HERONS

Radiological doses to herons were estimated by using methods described by Sample et al. (1997). Chronic and acute external radiation doses were assumed to result from standing in or near the contaminated water for half of each day. Chronic internal radiation doses were assumed to result from ingestion of fish contaminated by uptake of radionuclides from contaminated water. It was assumed that acute internal doses would not occur because uptake of radionuclides to levels described by the bioaccumulation factor (BCF) is a result of chronic exposure.

Results of exposure calculations are shown in Table 4 for Tank 26 and Table 5 for Tank 28. The calculations showed that external radiation would provide doses of 11 and 19 rad/d to herons standing for half of the day in or at the edge of the water. These doses are above the nominal acute dose of 10 rad/d that is assumed (IAEA 1992) not to cause adverse reproductive effects to birds. The likelihood that a heron would spend half a day exposed to this spill is probably low, but sufficient exposure to cause some harm seems to be possible.

The chronic benchmark for birds is 0.1 rad/d (IAEA 1992). Combined external and internal radiation HIs were about 1,900 for Tank 26 and 3,850 for Tank 28. Dilution of the contaminants in White Oak Lake would reduce radionuclide HIs to approximately 2 to 4 for Tank 26 and 4 to 8 for Tank 28. Therefore, chronic radiation toxicity to herons and other fish-eating predators in White Oak Lake is possible. If the radionuclides were not retained by White Oak Dam and the downstream containment system, they would rapidly be diluted in the Clinch River below levels of concern for herons and other fish-eating predators.

Using the equation developed for aquatic biota and a required reduction in mass of radionuclides of 1/2 to 1/8, the time required to bring HIs in White Oak Lake below 1 would be 2 to 10 days, or longer if mixing with clean water entering the lake is not rapid.

SUMMARY AND CONCLUSIONS

If one of the Melton Valley TRU-waste storage tanks ruptures and releases 50,000 gal of liquid radioactive waste into Melton Branch, aquatic biota would be killed by chemical toxicity, perhaps by high pH, and possibly by acute external radiation exposure. Herons and other fish-eating biota could be harmed by acute external radiation exposure if they remain in close proximity to the released water, which seems unlikely since the rapidly flowing nature of the water would not provide suitable conditions for a predator to fish.

The contaminants would likely move quickly downstream to White Oak Creek, where radiation toxicity is also probable. Dilution of the non-radioactive contaminants in White Oak Lake would rapidly reduce the concentrations of contaminants below levels causing chemical toxicity, and the pH would probably change to non-toxic levels. However, chronic radiation doses to aquatic biota and fish-eating predators in White Oak Lake would remain above benchmarks for acceptable chronic radiation levels for a few days to a few weeks. The predominant exposures are to cesium-137 from Tank 26 or cesium-137, cobalt-60, and strontium-90 from Tank 28.

Dilution of contaminants by release into the Clinch River would reduce radiation doses to aquatic biota and fish-eating predators to acceptable levels.

Table 4. Radiological Exposure of Great Blue Herons to Radionuclides in Storage Tank 26

Ecological constituent of potential concern	Tank conc. (Bq/mL)	RME (pCi/L)	BCF (L/kg)	BAFv	ADDA (pCi/gBW/d) RME × BCF × IA /1,000	ADDW (pCi/gBW/d) RME × IRW /1,000	ADDtotal (pCi/gBW/d) ADDP + ADDA + ADDS	Internal Dose (rad/d)	External Dose (rad/d)	Total Dose (rad/d) Internal + External	TRV (rad/d)	Site HQ ADD total / TRV
Radionuclides												
Cesium-134	2.00E+04	7.40E+05	2.00E+03	1.00E+00	2.66E+05	3.33E+01	2.66E+05	3.11E+00	4.16E-01	3.52E+00	1.00E-01	3.52E+01
Cesium-137	1.40E+06	5.18E+07	2.00E+03	1.00E+00	1.86E+07	2.33E+03	1.87E+07	1.79E+02	3.95E-01	1.79E+02	1.00E-01	1.79E+03
Cobalt-60	2.20E+03	8.14E+04	3.30E+02	1.00E+00	4.84E+03	3.66E+00	4.84E+03	4.88E-02	1.14E+01	1.15E+01	1.00E-01	1.15E+02
Iodine-129	7.80E-02	2.89E+00	5.00E+01	3.50E-01	2.60E-02	1.30E-04	2.61E-02	3.25E-08	1.32E-06	1.35E-06	1.00E-01	1.35E-05
Strontium-90	2.50E+04	9.25E+05	5.00E+01	1.50E-02	8.33E+03	4.16E+01	8.37E+03	1.26E-03	6.91E-03	8.17E-03	1.00E-01	8.17E-02
Technetium-99	1.90E+03	1.94E+06	1.50E+01	4.25E-01	5.24E+03	8.73E+01	5.33E+03	1.17E-02	3.12E-03	1.48E-02	1.00E-01	1.48E-01
Uranium-233	3.80E+00	1.41E+02	5.00E+01	1.00E-02	1.27E+00	6.33E-03	1.27E+00	6.27E-05	2.62E-06	6.54E-05	1.00E-01	6.54E-04
Uranium-238	1.00E-01	3.70E+00	5.00E+01	1.00E-02	3.33E-02	1.67E-04	3.35E-02	1.44E-06	1.50E-08	1.45E-06	1.00E-01	1.45E-05
											HI =	1.94E+03

RME = Reasonable maximum exposure.

BCF = Water-to-animal bioconcentration factor (Bechtel Jacobs 1998).

BAFv = Food-to-predator bioaccumulation factor (Baes et al. 1984).

ADDA = Average daily ingestion rate of animal tissue.

1,000 = Conversion from kilogram to gram body weight.

IA (kg/kgBW/d) = Animal ingestion rate.

ADDW = Average daily ingestion rate; drinking water.

IRW (L/kgBW/d) = Water ingestion rate.

ADDtotal = Average daily ingestion rate; total.

Internal Dose (rad/d) = $CF1 \times ADD_{total} \times [(20 \times E_a n_a) + (E_b n_b \times F_b) + (E_g n_g \times F_g)]$.

External Dose (rad/d) = $RME \times F_{above} \times DCF \times CF2 \times 2$.

CF = Conversion factor, 5.11×10^{-8}.

F_{above} = Fraction of time spent at or in proximity to the water surface = 0.5.

CFa = Conversion factor, 5.92×10^{6}.

2 = Conversion factor for closer proximity of heron to external source than of humans, for whom parameters were derived (Bechtel Jacobs 1998).

TRV = Toxicity reference value.

HQ = Hazard quotient.

HI = Hazard index.

Table 5. Radiological Exposure of Great Blue Herons to Radionuclides in Storage Tank 28

Ecological constituent of potential concern	Tank conc. (Bq/mL)	RME (pCi/L)	BCF	BAFv	ADDA (pCi/gBW/d) RME × BCF × IA /1,000	ADDW (pCi/gBW/d) RME × IRW /1,000	ADDtotal (pCi/gBW/d) ADDP + ADDA + ADDS	Internal Dose (rad/d)	External Dose (rad/d)	Total Dose (rad/d) Internal + External	TRV (rad/d)	Site HQ ADD total/ TRV
Radionuclides												
Cesium-134	2.40E+03	8.88E+04	1.00E+04	1.00E+00	1.60E+05	4.00E+00	1.60E+05	1.86E+00	5.00E-02	1.91E+00	1.00E-01	1.91E+01
Cesium-137	5.70E+05	2.11E+07	1.00E+04	1.00E+00	3.80E+07	9.49E+02	3.80E+07	3.63E+02	1.61E-01	3.64E+02	1.00E-01	3.64E+03
Cobalt-60	3.70E+03	1.37E+05	1.50E+03	1.00E+00	3.70E+04	6.16E+00	3.70E+04	3.73E-01	1.92E+01	1.96E+01	1.00E-01	1.96E+02
Iodine-129	1.90E-02	7.03E-01	2.00E+02	3.50E-01	2.53E-02	3.16E-05	2.53E-02	3.16E-08	3.20E-07	3.52E-07	1.00E-01	3.52E-06
Strontium-90	1.50E+05	5.55E+06	3.00E+02	1.50E-02	3.00E+05	2.50E+02	3.00E+05	4.52E-02	4.14E-02	8.66E-02	1.00E-01	8.66E-01
Technetium-99	4.10E+02	1.52E+04	1.00E+02	4.25E-01	2.73E+02	6.83E-01	2.74E+02	6.02E-04	2.44E-05	6.26E-04	1.00E-01	6.26E-03
Uranium-233	6.08E+01	2.25E+03	5.00E+01	1.00E-02	2.02E+01	1.01E-01	2.03E+01	1.00E-03	4.19E-05	1.05E-03	1.00E-01	1.05E-02
Uranium-238	1.80E+00	6.66E+01	5.00E+01	1.00E-02	5.99E-01	3.00E-03	6.02E-01	2.58E-05	2.71E-07	2.61E-05	1.00E-01	2.61E-04
											HI =	3.85E+03

RME = Reasonable maximum exposure.

BCF = Water-to-animal bioconcentration factor (Bechtel Jacobs 1998).

BAFv = Food-to-predator bioaccumulation factor (Baes et al. 1984).

ADDA = Average daily ingestion rate of animal tissue.

1,000 = Conversion from kilogram to gram body weight.

IA (kg/kgBW/d) = Animal ingestion rate.

ADDW = Average daily ingestion rate; drinking water.

IRW (L/kgBW/d) = Water ingestion rate.

ADDtotal = Average daily ingestion rate; total.

Internal Dose (rad/d) = $CF1 \times ADD_{total} \times [(20 \times E_{\alpha}n_{\alpha}) + (E_{\beta}n_{\beta} \times \Phi_{\beta}) + (E_{\gamma}n_{\gamma} \times \Phi_{\gamma})]$.

External Dose (rad/d) = $RME \times F_{above} \times DCF \times CF2 \times 2$.

CF = Conversion factor, 5.11×10^{-8}.

F_{above} = Fraction of time spent at or in proximity to the water surface = 0.5.

CFa = Conversion factor, 5.92×10^{6}.

2 = Conversion factor for closer proximity of heron to external source than of humans, for whom parameters were derived (Bechtel Jacobs 1998).

TRV = Toxicity reference value.

HQ = Hazard quotient.

HI = Hazard index.

REFERENCES

Baes, C. F., III, R. D. Sharp, A. L. Sjoren, and R. W. Shor 1994. *A Review and Analysis of Parameters for Assessing Transport of Environmentally Released Radionuclides through Agriculture*, ORNL-5786, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Bechtel Jacobs (Bechtel Jacobs Company LLC) 1998. *Radiological Benchmarks for Screening Contaminants of Potential Concern for Effects on Aquatic Biota at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, BJC/OR-80, Bechtel Jacobs Company LLC, Oak Ridge, Tennessee.

Blaylock, B. G., M. L. Frank, and B. R. O'Neal 1993. *Methodology for Estimating Radiation Dose Rates to Freshwater Biota Exposed to Radionuclides in the Environment*, ES/ER/TM-78, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

DOE (U.S. Department of Energy) 1997. *Report on the Remedial Investigation of Bear Creek Valley at the Oak Ridge Y-12 Plant, Oak Ridge, Tennessee*, DOE/OR/01-1455/V6&D2.

Eckerman, K. F., and J. C. Ryman 1993. *External Exposure to Radionuclides in Air, Water, and Soil*, EPA 402-R-93-081, Federal Guidance Report No. 12, Office of Radiation and Indoor Air, U.S. Environmental Protection Agency, Washington, D.C.

EPA (U.S. Environmental Protection Agency) 1993. *Wildlife Exposure Factors Handbook*, Volume I, EPA/600/R-93/187a, Office of Research and Development, Washington, D.C.

IAEA (International Atomic Energy Agency) 1992. *Effects of Ionizing Radiation on Plants and Animals at Levels Implied by Current Radiation Protection Standards*, IAEA Technical Report Series 332, Vienna, Austria.

Keeler, J. M., J. M. Giaquinto, and A. M. Meeks 1996. *Characterization of the MVST Waste Tanks Located at ORNL*, ORNL/TM-13357, Lockheed Martin Energy Research Corp., Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Loar, J. M., et al. 1992. *First Annual Report on the Biological Monitoring and Abatement Program at the Oak Ridge National Laboratory*, ORNL/TM 10399, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

NCRP (National Council on Radiation Protection) 1991. *Effects of Ionizing Radiation on Aquatic Organisms*, NCRP Report No. 109, National Council on Radiation Protection and Measurements, Bethesda, Maryland.

Sample, B. E., M. S. Aplin, R. A. Efroymson, G. W. Suter II, and C. J. E Welsh 1997. *Methods and Tools for Estimation of the Exposure of Terrestrial Wildlife to Contaminants*, ORNL/TM-13391, Environmental Sciences Division, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Suter, G. W. II, and C. L. Tsao 1996. *Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Aquatic Biota: 1996 Revision*, ES/ER/TM-96/R2, Lockheed Martin Energy Systems, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX F.3

IMPACTS TO SOIL AND GROUNDWATER FROM A SEISMICALLY INDUCED BREACH OF THE MELTON VALLEY STORAGE TANKS

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX F.3

IMPACTS TO SOIL AND GROUNDWATER BY A SEISMICALLY INDUCED BREACH OF THE MELTON VALLEY STORAGE TANKS

1. CONCENTRATION CONVERSIONS

Strontium-90 was considered a representative constituent of concern (COC) to evaluate under the potential release scenario. Strontium-90 is a major COC and has significant environmental impact. Furthermore, strontium-90 in Tank W28, one tank with more heavily impacted wastes, accounts for approximately 15% of the total radioactive material (with respect to curies) in the tank. According to Keeler et al. (1996), strontium-90 concentrations in Tank W28 are **1.5E5 Becquerel/mL.** Assuming the analytical results reported in Keeler et al. (1996) are representative of the entire 50,000-gallon waste volume, this can be converted via equations taken from the U.S. Department of Health, Education and Welfare (1970):

1.5E5 B/mL × 2.7E-11 curies/1B × 1 g/141 curies
= 2.87E-8 g/mL × 1,000 mL/L
= 2.87E-5 g/L
= 2.87E-2 mg/L

2. ESTIMATE TOTAL MASS OF RELEASE

Total Mass = 2.87E-2 mg/L × 50,000 gallons released × 3.7859 L/gal
= 5,432.7665 mg
= 5.433 grams of strontium-90 or 766 curies

3. HOLDING CAPACITY OF THE SOIL

Assuming a reasonable worst-case scenario with respect to impact to the soil and groundwater, the extent of contaminant loading to the soil can be estimated. This can be done by evaluating the partitioning effect between the solute (waste) and the aquifer material. For such a calculation, it will be assumed that flow from the release would move as porous media flow and at such a rate that the system kinetics would allow the system to remain in chemical equilibrium (the conceptual model for the release scenario along with the potential resulting area of impacted soils is detailed in Figure 1).

To evaluate the partitioning relationship, consider the aquifer or soil media's distribution coefficient (Kd):

Kd = concentration of the COC on the solid/concentration of the COC in solution.

For strontium-90, a value of **20 L/kg** was used as suggested by Sheppard and Thibault (1990) for loam soils.




Figure 1. Conceptual Model for Melton Valley Storage Tank Release Scenario

Can the estimated area of contaminated soil adsorb the estimated quantity of strontium-90 that would be released? What is the soil's holding capacity?

As from the previous equation,

Concentration of the COC on the solid = Kd × concentration of the COC in solution
Holding capacity = 20 L/kg × 2.87E-2 mg/L
= **0.574 mg/kg** (this is also the max. concentration to be expected in the soil)

if, as indicated on Figure 1, we could potentially have **866,250 ft^3** of impacted soils, then:

kilograms of potentially impacted soil = 866,250 ft^3 × 93.65 lb/ft^3 × 0.45359 kg/lb
= 3.68E7 kilograms (assuming a bulk density of 1.5 g/cm^3)

Effective Holding Capacity of the soil
= maximum concentration of the COC on the solid × total mass of potentially impacted soil
= 0.574 mg/kg × 3.68E7 kg
= 2.11E7 mg
= 2.11E4 g
= **21.12 kg**

Based on past release information from the Melton Valley Storage Tanks area, such a release would greatly increase the level of localized impact.

4. FIRST-ORDER DECAY RATES FOR AN INDICATIVE CONSTITUENT OF CONCERN

As demonstrated previously, the rate of groundwater flushing from the impacted soil can be determined from the Kd equation. However, such a calculation is greatly dependent upon contaminant distribution, groundwater recharge, and flow rates. The concentration in the soil will also be directly dependent upon the radio decay coefficient of the constituent of concern (**29 years** for strontium-90 as referenced by Walton 1985).

The resulting concentration 100 years after release can be predicted by the following equation:

Resulting mass = original mass e^{-lt}
Where: l = -0.6931/ 29
= -0.0239
t = 100 years

Therefore, resulting mass = 5.433 g × $e^{-2.92}$
= **0.498 g** (over a 90% reduction in total mass in 100 years).

Consequently, the radioactive decay process alone will greatly impact the strontium-90 mass and, correspondingly, soil and groundwater concentration after 100 years.

5. RESULTING CONCENTRATIONS IN SOIL AND GROUNDWATER

Based on the previously outlined assumptions, it is possible to calculate a reasonable maximum concentration in both groundwater and soil as well as average concentrations if the strontium-90 is evenly distributed across the suspected area of impact.

	Soil:	**Groundwater:**
Average	5.433 g/3.68E7 kg	= soil conc. / Kd
	= 1.476E-7 g/kg	= 1.476E-4 mg/kg / 20 L/kg
	= 1.476E-4 mg/kg	= 7.38E-6 mg/L
	= 1.476E-4 mg/kg × 141 Ci/g	= 7.38E-9 g/L × 141 Ci/g
	= 2.08E-5 Ci/kg	= 1.04E-6 Ci/L
	= 2.08E7 pCi/kg	**= 1.04E6 pCi/L**
Maximum	0.574 mg/kg	= soil conc. / Kd
	= 5.74E-4 g/kg × 141 Ci/g	= 0.574 mg/kg / 20 L/kg
	= 8.09E-2 Ci/kg	= 0.0287 mg/L
	= 8.09E10 pCi/kg	= 2.87E-5g/L × 141 Ci/g
		= 4.05E-3 Ci/L
		= 4.05E9 pCi/L

6. NARRATIVE AND CONCLUSIONS

In the event of the rupture and subsequent release of the contents of one of the eight Melton Valley Storage Tanks, up to 50,000 gallons of liquid waste could be released to the environment. In this appendix, the consequential impacts of such a release have been evaluated with respect to potential impact to the soil and groundwater. To evaluate such a release scenario, it was assumed that waste would leak from the vault in a band as wide as 150 ft across the lower front edge of the vault, in a zone parallel to slope down to Melton Branch. Furthermore, it was assumed that the waste would initially leak through the unsaturated overburden impacting an area of soil (150 ft × 75 ft × 13 ft) prior to reaching the groundwater surface. Once the waste reaches the water table/groundwater surface, it is further assumed that waste would mix with the shallow groundwater and ultimately discharge out to Melton Branch approximately 400 ft away. Details of this conceptual model are depicted in Figure 1. Such a release could potentially impact 5573.6 m^2 (0.557 hectares) of area and 24,526 m^3 of soil.

In order to assess the environmental impact, it was assumed that one of the more heavily impacted tanks, W28, would breach and spill its entire contents (approximately 50,000 gallons). Strontium-90 concentrations in this tank were reported in Keeler et al. (1996) to be 1.5E5 Becquerel/mL. This concentration in Tank W28 indicates that strontium-90 reflects approximately 15% of the total radioactive material in that tank (as measured in Becquerels). Assuming the concentrations reported are accurate for all the waste in Tank W28, 766 curies of strontium-90 would be released to the environment. If that mass of strontium-90 were evenly distributed across the potentially impacted area, concentrations in soil and groundwater would equate to 2.08E7 pCi/kg and 1.04E6 pCi/L, respectively. Based on assumed soil/water partitioning interactions, the maximum values that could be expected in soil and groundwater would equal 8.09E10 pCi/kg and 4.05E9 pCi/L, respectively. All calculations are detailed in this appendix.

These resulting concentrations are significant, as little to any previous impact for strontium-90 has been reported for the soil and groundwater near the proposed transuranic (TRU) waste treatment facility and South of Melton Branch. Furthermore, these concentrations reflect an apparent driver for remediation when compared to the 10^{-6} residential risk scenario values of 0.014 pCi/kg and 0.85 pCi/L for soil and water (RAIS 2000).

7. REFERENCES

Walton, W. 1985. *Practical Aspects of Ground Water Modeling*, Second Edition, National Water Well Association, Worthington, Ohio.

Sheppard, M. I., and D. H. Thibault 1990. "Default Soil Solid/Liquid Partition Coefficient, Kd's for Four Major Soil Types, A Compendium," *Health Physics* **59(4)**.

Keeler, J. M., J. M. Giaquinto, and A. M. Meeks 1996. *Characterization of the MVST Waste Tanks Located at Oak Ridge National Laboratory*, ORNL/TM-13357, Contract No. DE-AC05-96OR22464, Lockheed Martin Energy Research Corp., Oak Ridge, Tennessee.

U.S. Department of Health, Education and Welfare 1970. *Radiological Health Handbook*, Public Health Service, Food and Drug Administration, Bureau of Radiological Health, Rockville, Maryland.

RAIS 2000. *Risk Assessment Information System*, 1/11/2000. Information as located on the world wide web (http:/risk/lsd.ornl.gov/prg/prg_search.html).

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX G

CATEGORICAL EXCLUSION FOR CONSTRUCTION/RELOCATION OF ACCESS ROAD AT OAK RIDGE NATIONAL LABORATORY OAK RIDGE, TENNESSEE

THIS PAGE INTENTIONALLY LEFT BLANK

CATEGORICAL EXCLUSION FOR CONSTRUCTION/RELOCATION OF ACCESS ROAD AT OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE

PROPOSED ACTION: Upgrade/relocate access road at the Oak Ridge National Laboratory (ORNL) in Oak Ridge, Tennessee.

LOCATION: An existing road is located in Melton Valley of ORNL at the U.S. Department of Energy (DOE) Oak Ridge Reservation in Oak Ridge, Tennessee. The road begins near the south end of White Oak Dam on the east side of state Route 95 just north of the Clinch River and extends parallel to the Melton Valley Branch of White Oak Creek to, and beyond, the Melton Valley Storage Tank Facility in Roane County, Tennessee.

DESCRIPTION OF PROPOSED ACTION: The DOE Oak Ridge Operations (ORO) Office proposes to upgrade an existing access road by providing a paved road with two 3.6-m (12-ft) lanes, a shoulder of undetermined width, and possibly a guardrail. Currently, the road is a single lane gravel road that is badly eroded and in need of repair. A portion of the road may require relocation from the existing roadway to comply with the policy for establishing minimum "sight distance" at intersections ("A Policy on Geometric Design of Highways and Streets 1990," published by the American Association of State Highway and Transportation Officials). According to this policy, the minimum sight distance for the road will be approximately 170 m (550 ft). The primary purpose of this action is to provide a competent road for continued vehicular traffic and to allow access by transport trucks and emergency use vehicles. Access to monitoring wells located along the existing road and emergency egress from Melton Valley will be maintained at all times during construction.

The proposed activity could involve the road for a distance of approximately 2 km (1.25 mile). The proposed action would involve excavation of approximately 19,700–33,800 m^3 (25,700–44,200 yd^3) of soil, depending upon where the new junction of the road with state Route 95 is located. Exact route and associated volume of excavated soil will be determined as part of the roadway design.

Ancillary activities associated with the road upgrade will include (1) installation of security fencing as needed to restrict access to areas of ORNL, (2) plugging and abandonment or modification of existing monitoring wells located in the path of the upgraded road (an action also covered under GEN CX-292), (3) upgrade of existing culverts as necessary and addition of new culverts for stormwater flow to match the stormflow generated by a 25-year storm, (4) replacement of a security gate where the road joins state Route 95 and installation of a second gate at the other end of the upgraded road, and (5) installation of a metered water tie-in to an existing water line.

Wastes generated during this action will be primarily Resource Conservation and Recovery Act of 1976 Subtitle D (e.g., nonhazardous) solid wastes. All wastes will be disposed of in accordance with applicable regulations. No liquid wastes will be generated, stored, or disposed of as part of the proposed action. Air emissions will include emissions from burning vegetation after clearing the widened road corridor, vehicular emissions, and emissions from the paving process. All will be within regulatory limits.

Two homesteads located near the existing road were surveyed to determine if they were eligible for listing as historic properties[1]. One of the homesteads, the Jenkins site was determined to be eligible for listing as a historic property. Neither site will be disturbed as a result of this action and no adverse effects are anticipated. The only potentially sensitive resource identified near the road was White Oak Creek, which is north and downgradient from the site. A runoff and erosion control plan will be prepared, approved, and implemented to protect the creek from erosion and runoff during implementation of the action.

The Tennessee Department of Transportation will review and approve designs for the intersection of the road and state Route 95 to ensure that it meets requirements for traffic safety. An erosion control plan for construction activities will be prepared to satisfy requirements under *Rules of the Tennessee Department of Environment and Conservation*, Chapter 1200-4-10-.05, to minimize any potential impacts from erosion caused by stormwater flow.

This project will pose no threat of significant individual or cumulative environmental effects.

REGULATORY CONSIDERATIONS: The proposed action will be conducted under DOE authorities pursuant to the Atomic Energy Act of 1954 and will be consistent with current and future actions at the site. The proposed action meets the eligibility criteria for conditions that are integral elements of actions eligible for categorical exclusion (CX) as stated in 10 *Code of Federal Regulations* (CFR) 1021:

1. The proposed action will not threaten a violation of applicable statutory, regulatory, or permit requirements for environment, safety, and health, including requirements of DOE and/or Executive Orders.

2. The proposed action will not require siting and construction or major expansion of waste storage, disposal, recovery, or treatment facilities (including incinerators), but the proposal may include categorically excluded waste storage, disposal, recovery, or treatment actions.

3. The proposed action will not disturb hazardous substances, pollutants, contaminants or Comprehensive Environmental Response, Compensation, and Liability Act of 1980-excluded petroleum and natural gas products that preexist in the environment such that there would be uncontrolled or unpermitted releases.

4. The proposed action will not adversely affect environmentally sensitive resources including: archaeological or historic sites; potential habitats of threatened or endangered species; floodplains, wetlands; areas having special designations such as federally or state-designated wilderness areas, national parks, natural landmarks, wild and scenic rivers, wildlife sanctuaries, prime agricultural lands, special sources of water such as sole source aquifers, tundra, coral reefs, or rain forests. The proposed action would occur largely in a previously disturbed/ developed area, although some second growth upland habitat would likely also be disturbed. A survey for sensitive resources will be conducted along the road route once it has been more

[1] Carver, M. And M. Slater. 1994. *Architectural/Historical Assessment of the Oak Ridge tional Laboratory, Oak Ridge Reservation, Anderson and Roane Counties, Tennessee*. ORNL/M-3244, NL, Oak Ridge, Tennessee.

clearly identified and prior to disturbance of any vegetation. Appropriate mitigation measures will be taken in the event that any sensitive resources are identified.

There are no extraordinary circumstances related to the proposal that may affect the significance of the environmental effects of the proposal, and the proposal is not precluded by 40 CFR 1506.1 or 10 CFR 1021.211.

The estimated cost for this action is approximately $1 - 3 million, and it will take approximately 9 months to 1 year to complete.

CX TO BE APPLIED: DOE National Environmental Policy Act of 1969 (NEPA) Implementing Procedures, 10 CFR 1021, Subpart D, Appendix B, actions that "Normally Do Not Require EAs or EISs."

B.1.13, "Construction, acquisition, and relocation of onsite pathways and short access roads and railroads."

B.1.11, "Installation of fencing, including that for border marking, that will not adversely affect wildlife movements or surface water flow."

B.1.15, "Siting, construction (or modification), and operation of support buildings and structures ..."

I have concluded that the proposed action meets the requirements for the CX referenced above. Therefore, I recommend that the proposed action be categorically excluded from further NEPA review and documentation.

_____ _____

Gary Riner Date
DOE-ORO Program Manager

Based upon my review and recommendations of the DOE ORO Program Manager, I have determined that the proposed action is categorically excluded from further NEPA documentation and review.

_____ _____

David Allan Date
DOE-ORO NEPA Compliance Officer

Tolbert, Wayne W. (Oak Ridge)

From: Cahill, William J [CahillWJ@oro.doe.gov]
Sent: Monday, April 03, 2000 10:19 AM
To: 'wayne.w.tolbert@saic.com'
Subject: FW: CX for Melton Valley Access Road Repair and Upgrade

Importance: High



> ----Original Message----
> From: Elmore, James L
> Sent: Monday, April 03, 2000 10:18 AM
> To: Cahill, William J
> Subject: FW: CX for Melton Valley Access Road Repair and Upgrade
> Importance: High
>
> Bill,
>
> Below is the CX for the access road. It was approved by E-mail.
>
> Jim
>
> ----Original Message----
> From: Allen, David R
> Sent: Tuesday, November 24, 1998 11:44 AM
> To: Kopotic, James D
> Cc: Elmore, James L
> Subject: FW: CX for Melton Valley Access Road Repair and Upgrade
> Importance: High
>
> Your cx is approved.
>
> David A.
>
> ----Original Message----
> From: Elmore, James L
> Sent: Tuesday, November 24, 1998 10:04 AM
> To: Allen, David R
> Cc: Moore, Ray T
> Subject: FW: CX for Melton Valley Access Road Repair and Upgrade
> Importance: High
>
> Dave,
>
> This CX looks OK to me. I told them we could approve it over e-mail.
>
> Jim
>
> ----Original Message----
> From: Kopotic, James D
> Sent: Tuesday, November 24, 1998 9:35 AM
> To: Allen, David R; Elmore, James L
> Cc: Riner, Gary; 'anne.dickie@jacobs.com'
> Subject: FW: CX for Melton Valley Access Road Repair and Upgrade
> Importance: High
>

Science Applications International Corporation
An Employee-Owned Company

380.19990216.011

February 16, 1999

Mr. Billy E. Reid, Jr.
Project Manager
AVISCO, Inc.
100 Tulsa Rd., Suite 28
Oak Ridge, TN 37830

SUBJECT: Report For Rare Plant Survey Proposed Melton Valley Access Road

Dear Mr. Reid:

On Wednesday February 10, 1999, Maureen Cunningham, a botanist, and Jimmy Groton, an environmental scientist, from Science Applications International Corporation (SAIC) performed a rare plant species survey for the proposed Melton Valley Access Road, which runs from Highway 95 to the Melton Valley Storage Tank Facility on the Oak Ridge Reservation (ORR). During the survey no federal or state listed endangered or threatened plant species were observed in the proposed roadway corridor. A state plant species of special concern, Pursh's wild-petunia (*Ruellia purshiana*) has been observed in what is known as Oak Ridge National Laboratory (ORNL) Natural Area 56 in the extreme western end of the proposed roadway near the proposed intersection with State Route (SR) 95. Approximately one acre of potential Pursh's wild-petunia habitat would be impacted by the current alignment of the proposed Melton Valley Access Road. Although DOE is not specifically obligated to consider state-listed species, it has generally been DOE policy in the past to avoid actions that would impact state-listed species.

Since this survey was unavoidably conducted in the middle of February when most plants are dormant, a survey during the growing season would better enable us to identify, report, comment on, and make recommendations on avoiding disturbance to sensitive species. Please do not hesitate to call us for further clarifications on this report.

Sincerely,

SCIENCE APPLICATIONS INTERNATIONAL CORPORATION

James Groton
Environmental Scientist

800 Oak Ridge Turnpike, P.O. Box 2502, Oak Ridge, Tennessee 37831 • (423) 482-3628 • Fax: (423) 482-7257
Other SAIC Offices: Albuquerque, Colorado Springs, Dayton, Falls Church, Huntsville, Las Vegas, Los Altos, Los Angeles, McLean, Oak Ridge, Orlando, San Diego, Seattle, Tucs

Report For Rare Plant Survey Proposed Melton Valley Access Road

On Wednesday February 10, 1999, Maureen Cunningham, a botanist, and Jimmy Groton, an environmental scientist, from Science Applications International Corporation (SAIC) performed a rare plant species survey for the proposed Melton Valley Access Road, which runs from Highway 95 to the Melton Valley Storage Tank Facility on the Oak Ridge Reservation (ORR). During the survey no federal or state listed endangered or threatened plant species were observed in the proposed roadway corridor. A state plant species of special concern, Pursh's wild-petunia (*Ruellia purshiana*) has been observed in the extreme western end of the proposed roadway in the area around the proposed intersection of the proposed Melton Valley Access Road with State Route (SR) 95. This population was first identified, described, and documented by Dr. Larry Pounds, a botanist working for the Oak Ridge National Laboratory (ORNL) Environmental Sciences Division. The area where the plant was found is known as ORNL Natural Area 56. It is not known whether other populations of Pursh's wild-petunia exist at ORNL or elsewhere on the ORR. Although DOE is not specifically obligated to consider state-listed species, in the past DOE has generally tried to avoid actions that would impact state-listed species.

The survey area consisted of a linear strip approximately 50-ft wide and 6,000 ft in length (Fig. 1); the area was delineated in the field with pink flagging. AVISCO staff also provided some on-site guidance and clarification on boundaries of the proposed roadway. Through much of its length the proposed roadway follows the course of or parallels an existing gravel road between the Melton Valley Storage Tank Facility and SR 95; however, there are several areas where the new roadway diverges into mature forest.


Because the survey was conducted in winter and the stems, flowers, and leaves of most herbaceous plants are generally not persistent above ground, this survey focused primarily on woody vegetation, habitats observed in the proposed roadway corridor, and published information about rare plant species on the ORR. Our approach was to use knowledge of the rare plant species known to occur on the ORR and survey for habitat that could support these species. We also consulted with other botanists who have conducted rare species surveys in some parts of the project area in the past several years. A survey during the growing season would better enable us to identify, report, comment on, and make recommendations on avoiding disturbance to sensitive species.

White Oak Lake borders the existing gravel road to the north for about half its length. Most of the area within 50-ft to the south of the existing roadway is pine forest and has many fallen trees, which looked to be the result of windfall. Areas further than 50-ft south of the road were mixed pine-cedar-hardwood forest. Steep slopes prevail through much of the area, especially in the western third of the proposed road corridor. The upper portions of the slopes support a mature forest of chestnut oak, northern red oak and tulip tree. Several deep coves support a mature forest with buckeye and tulip tree dominating. Limestone rock outcrops were present from the ridge crest down to the existing gravel road. Several streams with running water were also present. Only one of these is depicted as a blue line stream on the S-16A map of the ORR.

The areas most likely to contain rare herbaceous species are the mixed juniper-hardwood forest near Hwy 95 and the forested slopes above the existing gravel road (see Fig. 1). A state plant species of special concern, Pursh's wild-petunia grows along the roadway of State Route 95 in the area of the intersection of the proposed access road. It likely occurs at the edge of the woods in that area also. A precise estimate of the population of this species of *Ruellia* present at this or other sites on the ORR is not available. A maximum area of about 1 acre of potential *Ruellia* habitat would be affected by the proposed road in its current alignment.

Other rare plant species known to occur on the ORR that could inhabit the forested slopes on the southern part of the proposed road corridor include ginseng, (*Panax quinquefolium*), goldenseal (*Hydrastis canadensis*), pink lady slipper (*Cypripedium acaule*), and whorled mountain-mint (*Pycnanthemum verticillatum*). Ginseng, goldenseal, and pink lady slipper are listed as state endangered species because of commercial exploitation. The whorled mountain-mint is listed as state endangered and possibly extirpated (the plant has not been seen in Tennessee for the past 20 years and may no longer occur in Tennessee). None of these species has federal status.

On Wednesday, February 10, 1999, scientists from Science Applications International Corporation (SAIC) performed a rare plant species survey for the proposed Melton Valley Access Road, which runs from Highway 95 to the Melton Valley Storage Tank Facility on the Oak Ridge Reservation (ORR). During the survey no federal or state listed endangered or threatened plant species were observed in the proposed roadway corridor. A state plant species of special concern, Pursh's wild-petunia has been observed in the extreme western end of the proposed roadway in the area around the proposed intersection of the proposed Melton Valley Access Road with State Route (SR) 95. This population was first identified, described, and documented by Dr. Larry Pounds, a botanist working for the Oak Ridge National Laboratory (ORNL) Environmental Sciences Division. The area where the plant was found is known as ORNL Natural Area 56. The proposed Melton Valley Access Road would impact approximately one acre of potential Pursh's wild-petunia habitat.


State Route 95
Melton Valley Storage Facility
Proposed corridor for new Melton Valley Access Road
General location of existing Pursh's wild-petunia (Ruellia purshiana) population, State plant species of special concern
HFIR
TSF
Figure 1.
Location of rare plant survey for proposed Melton Valley Access Road
Scale 1:24000
0
1/2
1 mile

Additional Resources and Contacts:

The Pursh's wild-petunia was first identified, described, and documented by Dr. Larry Pounds, a botanist working for the ORNL Environmental Sciences Division. Dr. Pounds can be reached at 483-8635.

For more information about Pursh's wild-petunia, natural areas, and other rare plants at ORNL, please contact Ms. Pat Parr at 576-8123. Ms. Parr is the ORNL Area Manager.

For more information about the regulatory status of plant species of special concern, please contact Ms. Andrea Shea at (615) 532-0439. Ms. Shea is the Endangered Species Program Manager with the Division of Natural Heritage of the Tennessee Department of Environment and Conservation in Nashville.

THIS PAGE INTENTIONALLY LEFT BLANK

DOE/EIS-0305-F

FINAL
ENVIRONMENTAL IMPACT STATEMENT
FOR TREATING
TRANSURANIC (TRU)/ALPHA LOW-LEVEL WASTE
AT THE OAK RIDGE NATIONAL LABORATORY
OAK RIDGE, TENNESSEE



RECEIVED
JUL 03 2000
OSTI

VOLUME 2

COMMENT RESPONSE DOCUMENT

June 2000

COVER SHEET

RESPONSIBLE AGENCY: U.S. Department of Energy (DOE)

TITLE: Final Environmental Impact Statement for Treating Transuranic (TRU)/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee (DOE/EIS-0305)

RECEIVED
JUL 03 2000
OSTI

CONTACT: For further information concerning the Final EIS, contact

Dr. Clayton Gist, Waste Management Integration Team Leader
U.S. Department of Energy
Oak Ridge Operations
55 Jefferson Avenue
P.O. Box 2001
Oak Ridge, TN 37831
Telephone: (865) 241-3498 • Facsimile (865) 576-5333 • E-Mail: gistcs@oro.doe.gov

For general information on DOE's National Environmental Policy Act (NEPA) process, contact:

Ms. Carol M. Borgstrom, Director
Office of NEPA Policy and Assistance (EH-42)
U.S. Department of Energy
1000 Independence Avenue, SW
Washington, DC 20585
Telephone: (202) 586-4600, or leave a message at (800) 472-2756

ABSTRACT: The DOE proposes to construct, operate, and decontaminate/decommission a transuranic (TRU) Waste Treatment Facility in Oak Ridge, Tennessee. The four waste types that would be treated at the proposed facility would be remote-handled TRU mixed waste sludge, liquid low-level waste associated with the sludge, contact-handled TRU/alpha low-level waste solids, and remote-handled TRU/alpha low-level waste solids. The mixed waste sludge and some of the solid waste contain metals regulated under the Resource Conservation and Recovery Act and may be classified as mixed waste.

This document analyzes the potential environmental impacts associated with five alternatives—No Action, the Low-Temperature Drying Alternative (Preferred Alternative), the Vitrification Alternative, the Cementation Alternative, and the Treatment and Waste Storage at Oak Ridge National Laboratory (ORNL) Alternative.

PUBLIC COMMENTS: The Draft environmental impact statement (EIS) was issued to the public for review and comment on March 3, 2000. The public comment period ended on April 17, 2000. All comments were considered in preparation of the Final EIS. The DOE will use the analysis in this Final EIS and prepare a Record of Decision on the treatment of TRU and alpha low-level wastes at ORNL. This decision will be made no sooner than 30 days after the U.S. Environmental Protection Agency (EPA) Notice of Availability of the Final EIS appears in the *Federal Register*.



THIS PAGE INTENTIONALLY LEFT BLANK

COMMENTS AND RESPONSES TO FINAL ENVIRONMENTAL IMPACT STATEMENT CONTENTS

1. PUBLIC COMMENT PROCESS CRD-1
   - 1.1 INTRODUCTION CRD-1
   - 1.2 PUBLIC HEARING FORMAT CRD-1
   - 1.3 CHANGES TO THE DRAFT EIS CRD-1
   - 1.4 NEXT STEPS CRD-2

2. SUMMARY OF COMMENTS AND RESPONSES CRD-3
   - 2.1 ALTERNATIVES CRD-3
   - 2.2 TRANSPORTATION CRD-3
   - 2.3 THREATENED AND ENDANGERED SPECIES CRD-3
   - 2.4 ACCIDENTS CRD-4

3. COMMENT DOCUMENTS AND RESPONSES CRD-5
   - 3.1 INTRODUCTION CRD-5
   - 3.2 COMMENTS CRD-5
     - 3.2.1 Oak Ridge Site Specific Advisory Board CRD-7
     - 3.2.2 City of Oak Ridge CRD-23
     - 3.2.3 Oak Ridge Reservation Local Oversight Committee CRD-33
     - 3.2.4 State of Tennessee Department of Environment and Conservation CRD-36
     - 3.2.5 U.S. Department of Interior CRD-44
     - 3.2.6 U.S. Environmental Protection Agency CRD-54
     - 3.2.7 Public Hearings CRD-59
     - 3.2.8 Other Written Comments Received CRD-112

ACRONYMS AND ABBREVIATIONS

Note: These acronyms and abbreviations represent a combined list for both Volume 1 and Volume 2. Acronyms and abbreviations may not all be used in each volume. Less familiar acronyms are sometimes redefined within the document to enhance readability for the general public.

AEA	Atomic Energy Act of 1954
ALARA	as low as reasonably achievable
ANS	Advanced Neutron Source
BA	Biological Assessment
CAA	Clean Air Act
CBOD	carbonaceous biochemical oxygen demand
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	*Code of Federal Regulations*
CH	contact-handled
CRD	Comment Response Document
CX	categorical exclusion
D&D	decontamination and decommissioning
DOE	U.S. Department of Energy
DOI	U.S. Department of the Interior
DOT	U.S. Department of Transportation
DSSI	Diversified Scientific Services, Inc.
EA	environmental assessment
EDE	effective dose equivalent
EHEPA	extreme HEPA
EMWMF	Environmental Management Waste Management Facility
EIS	environmental impact statement
EM	Environmental Management
EPA	U.S. Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act of 1986
ETTP	East Tennessee Technology Park
FFA	Federal Facilities Agreement
Foster Wheeler	Foster Wheeler Environmental Corporation
FR	*Federal Register*
FSAR	Final Safety Analysis Report
HEME	high-efficiency mist eliminator
HEPA	high-efficiency particulate air
HVAC	heating, ventilation, and air conditioning
ICRP	International Commission on Radiological Protection
ISCST3	Industrial Source Complex Modeling Code, Version 3
INEEL	Idaho National Engineering and Environmental Laboratory
LCF	latent cancer fatality
LDR	Land Disposal Restriction
MVST	Melton Valley Storage Tank
NAAQS	National Ambient Air Quality Standards
NEPA	National Environmental Policy Act
NESHAPs	National Emission Standards for Hazardous Air Pollutants
NFS	Nuclear Fuel Services
NHPA	National Historic Preservation Act

NPDES	National Pollutant Discharge Elimination System
NRC	Nuclear Regulatory Commission
NTS	Nevada Test Site
ORNL	Oak Ridge National Laboratory
ORO	Oak Ridge Operations
ORR	Oak Ridge Reservation
ORSSAB	Oak Ridge Site Specific Advisory Board
PAAA	Price Anderson Amendment Act
PCB	polychlorinated biphenyl
PCF	probability of cancer fatality
PPE	personal protective equipment
PSD	prevention of significant deterioration
PVC	polyvinyl chloride
QA/QC	quality assurance/quality control
Rad-NESHAP	National Emission Standards for Hazardous Air Pollutants for Radionuclides
RCRA	Resource Conservation and Recovery Act
REDC	Radiological Engineering Development Center
RH	remote-handled
RIMS II	Regional Input-Output Modeling System II
ROD	Record of Decision
ROI	Region of Influence
RWP	Radiological Work Permit
SCR	selective catalytic reduction
SS	stainless steel
SWSA	solid waste storage area
SWSA 5 North	Solid Waste Storage Area 5 North
TAAQS	Tennessee Ambient Air Quality Standards
TCLP	Toxicity Characteristic Leaching Procedure
TDEC	Tennessee Department of Environment and Conservation
TEDE	total effective dose equivalent
TMI	Three-mile Island
TPDES	Tennessee Pollutant Discharge Elimination System
TRC	total residual chlorine
TRU	transuranic
TSCA	Toxic Substances Control Act
TSP	total suspended particulates
TVA	Tennessee Valley Authority
UBC	uniform building code
U.S.C.	United States Code
UTS	Universal Treatment Standard
WAC	Waste Acceptance Criteria
WAG	Waste Area Group
WIPP	Waste Isolation Pilot Plant
WM PEIS	*Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste* (DOE/EIS-0200-F, May 1997)
WIPP SEIS-II	*Waste Isolation Pilot Plant Disposal Phase Supplemental Environmental Impact Statement* (DOE/EIS-0026-S-2, September 1997)

UNITS OF MEASURE

Bq	becquerel
Bq/g	becquerels per gram
C	Celsius
Ci	curie
Ci/g	curies per gram
cm	centimeter
dBA	decibel
dscf	dry standard cubic foot
dscfm	dry standard cubic feet per minute
F	Fahrenheit
ft	feet
ft^2	square feet
ft^3	cubic feet
gal	gallon
gpd	gallons per day
gpm	gallons per minute
gr/dscf	grains per dry standard cubic foot
Gy/d	gray (absorbed dose, energy) per day
h	hour
ha	hectare
hr	hour
in	inch
km	kilometer
kV	kilovolt
kW	kilowatt
L	liter
lb	pound
lb/ft^3	pounds per cubic foot
lbs/h	pounds per hour
Leq	equivalent sound or noise level
m	meter
m^3	cubic meters
mg/L	milligrams per liter
mph	miles per hour
mrem	millirem (one thousandth of a rem)
mrem/h	millirem per hour
MW	megawatt
nCi/g	nanocuries per gram
ng/L	nanograms per liter
pCi/g	picocuries (one trillionth of a curie) per gram
ppm	parts per million
psig	pounds per square inch gauge
rad/d	rads per day
rem	roentgen equivalent man
rpm	revolutions per minute
wt %	weight percent
$\mu g/m^3$	micrograms per cubic meter
µR	microroentgen

Metric Conversion Chart

To Convert From U.S. Customary Into Metric			To Convert From Metric Into U.S. Customary		
If you know	**Multiply by**	**To get**	**If you know**	**Multiply by**	**To get**
Length					
inches	2.540	centimeters	centimeters	0.3937	inches
feet	30.48	centimeters	centimeters	0.03281	feet
feet	0.3048	meters	meters	3.281	feet
yards	0.9144	meters	meters	1.094	yards
miles	1.609	kilometers	kilometers	0.6214	miles
Area					
square inches	6.452	square centimeters	square centimeters	0.1550	square inches
square feet	0.09290	square meters	square meters	10.76	square feet
square yards	0.8361	square meters	square meters	1.196	square yards
acres	0.4047	hectares	hectares	2.471	acres
square miles	2.590	square kilometers	square kilometers	0.3861	square miles
Volume					
fluid ounces	29.57	milliliters	milliliters	0.03381	fluid ounces
gallons	3.785	liters	liters	0.2642	gallons
cubic feet	0.02832	cubic meters	cubic meters	35.3	cubic feet
cubic yards	0.7646	cubic meters	cubic meters	1.308	cubic yards
Weight					
ounces	28.35	grams	grams	0.03527	ounces
pounds	0.4536	kilograms	kilograms	2.205	pounds
short tons	0.9072	metric tons	metric tons	1.102	short tons
Temperature					
Fahrenheit (°F)	subtract 32, then multiply by 5/9	Celsius (°C)	Celsius (°C)	multiply by 9/5, then add 32	Fahrenheit (°F)
kelvin (°k)	subtract 273.15	Celsius (°C)	kelvin (°k)	multiply by 9/5, then add 306.15	Fahrenheit (°F)
Note: 1 sievert = 100 rems					

Metric Prefixes

Prefix	Exponent Converted to Whole Numbers	Prefix	Exponent Converted to Whole Numbers
pico	$10^{-12} = 0.000,000,000,001$	dekta-	$10^{1} = 10$
nano-	$10^{-9} = 0.000,000,001$	hecto-	$10^{2} = 100$
micro-	$10^{-6} = 0.000,001$	kilo-	$10^{3} = 1,000$
milli	$10^{-3} = 0.001$	mega-	$10^{6} = 1,000,000$
centi	$10^{-2} = 0.01$	giga-	$10^{9} = 1,000,000,000$
deci-	$10^{-1} = 0.1$	tetra-	$10^{12} = 1,000,000,000,000$
Note: $10^{0} = 1$			

1. PUBLIC COMMENT PROCESS

1.1 INTRODUCTION

The U.S. Department of Energy (DOE) has prepared this Environmental Impact Statement (EIS) in accordance with the *National Environmental Policy Act of 1969* (NEPA) [42 United States Code (U.S.C.) Section 4321] to examine the environmental impacts associated with five alternatives for the treatment and storage of transuranic (TRU) and alpha low-level waste at Oak Ridge National Laboratory (ORNL), Oak Ridge, Tennessee. An important part of the NEPA process was the solicitation of public comments on a Draft EIS and consideration of those comments in the preparation of the Final EIS. DOE distributed copies of the Draft EIS to those who were known to have an interest in the Oak Ridge Reservation (ORR) in addition to those who asked for a copy.

DOE issued the Draft EIS in February 2000 for review and comment by the State of Tennessee, Native American tribes, local governments, other federal agencies, and the general public. The formal public comment period lasted 45 days, ending April 17, 2000. DOE considered all comments received to evaluate the accuracy and adequacy of the Draft EIS and gave equal weight to written comments and to oral comments provided at the public hearing.

Chapter 3 of this volume contains copies of all comments received on the Draft EIS. All comments, whether received by letter, electronic mail, orally during the public hearing, or by other means, have been reproduced on the left side of the pages in Chapter 3 of this volume. Individual comments are marked with a sidebar to the right of the corresponding text and given a unique alphanumeric comment identifier. Responses to the comment can be identified by the alphanumeric identifier.

1.2 PUBLIC HEARING FORMAT

On March 21, 2000, a public hearing was held in the Oak Ridge Mall at 6:30 p.m. Oral comments made during the public hearing were recorded by a court reporter, and a transcript of the hearing was made. The public hearing held on the Draft EIS was conducted using an informal format. This format allowed for a two-way interaction between DOE and the public. A brief summary of the Draft EIS using viewgraphs was provided by DOE to help direct and clarify discussions and comments. Every commentor was given time to formally present comments. Cards were also handed out so that the public could provide written comments at the hearing or mail them later.

Organization of this comment response document is as follows:

- *Chapter 1*—Describes the public comment process, the Comment Response Document (CRD), and the changes made in the EIS.
- *Chapter 2*—Presents a summary of the comments received on the Draft EIS.
- *Chapter 3*—Presents the copies of the original comments received from the public during the public comment period. Responses to these comments are provided alongside to the extent feasible.

Due to the relatively small number of comments, comments are addressed individually.

1.3 CHANGES TO THE DRAFT EIS

DOE revised the Draft EIS in response to the comments received. The text was changed to provide additional information, correct inaccuracies, make editorial corrections, and clarify technical discussions. In addition, DOE updated information due to events or decisions made in other documents since publication of the Draft EIS in February 2000.

New analyses were added to Chapter 4 that address on-site handling and transportation of solid waste. Also, new analyses were added that address impacts after the loss of institutional control which, for analyses purposes, is assumed to occur after 100 years. Changes to the Draft EIS made in the Final EIS are indicated by a vertical bar in the margin.

1.4 NEXT STEPS

The EIS Record of Decision (ROD), which DOE will publish no sooner than 30 days after the U.S. EPA issues the Notice of Availability of the Final EIS, will explain all factors, including environmental impacts, that DOE considered in reaching its decision. Generally, DOE considers environmental impacts of the various alternatives, regulations and other legal drivers, cost, implementability and other factors in reaching a decision.

2. SUMMARY OF COMMENTS AND RESPONSES

This section contains an overview of comments and responses on the Draft EIS. This section discusses those areas for which DOE received multiple comments. This section does not capture all the specific comments, but is intended to provide the reader with a sense of public concerns on the Draft EIS.

2.1 ALTERNATIVES

Many commentors supported DOE's proposed action, although some were concerned that the processes for treating the wastes in the Melton Valley Storage Tanks (MVSTs) may not have been done before at this scale or by the selected contractor. Some commentors were concerned about the uncertainty of using the various treatment processes (e.g., technical implementability), especially Vitrification. While DOE acknowledges that there is some uncertainty in treating TRU waste in using any of the technologies, there are successful examples of these specific technologies being used in similar situations. Examples of drying technology include the Hanford 200 Area evaporator, the Palo Verde Nuclear Generating Station, and Three-Mile Island-2 Evaporation Project. Examples of solidification are solidification of Melton Valley Storage Tank Waste at ORNL, and DOE's Hanford, Rocky Flats, and Savannah sites using hydraulic cement. Examples of DOE use of vitrification include Savannah River M-Area, the Fernald Minimum Additive Waste Unit and the West Valley Vitrification Plant.

Some commentors took issue with the Treatment and Waste Storage at ORNL Alternative (Alternative 5), maintaining that 100 years of institutional control was an insufficient timeframe for analysis of impacts, and that the alternative was contrary to a Tennessee Department of Environment and Conservation (TDEC) Commissioner's Order to ship treated waste offsite, thus the alternative was not reasonable under NEPA. DOE is required to evaluate all reasonable alternatives for a proposed action, and because DOE believes it is reasonable to consider storage, the Treatment and Waste Storage at ORNL Alternative has been kept in this evaluation. Other commentors noted that the alternative should not be for 100 years, but that 30 years was the maximum DOE should consider for interim storage. Some commentors indicated that the impacts associated with the No Action Alternative were also understated because the impact analysis period was limited to 100 years. DOE believes it is reasonable, in accordance with the Council on Environmental Quality's NEPA regulations [40 *Code of Federal Regulations* (*CFR*) 1502.14], to analyze the impacts of potential storage of treated waste, e.g., in the event disposal capacity is unavailable. DOE has provided additional analysis in the Final EIS for the No Action Alternative that examined potential impacts from loss of institutional control, assumed to occur for analysis purposes, after 100 years. A 30-year timeframe as compared to a 100-year timeframe would show lower impacts for both utilities and involved worker exposure; other impacts would be similar.

2.2 TRANSPORTATION

Several commentors stated that DOE unduly restricted the impact analysis by omitting analysis of on-site transport of the wastes to the treatment facility. DOE agrees and has added several subsections in Section 4.8 to the transportation analysis in Chapter 4 of the Final EIS. These sections address the impacts of routine operations on involved workers and the impacts of accidents on involved workers, non-involved workers, and the public from the (1) exhumation or removal of wastes from trenches, buildings, and bunkers, and (2) transport of wastes to the proposed treatment facility.

2.3 THREATENED AND ENDANGERED SPECIES

The U.S. Department of the Interior (DOI) asked for additional information on protected species, including the Indiana Bat. DOE has submitted to DOI a draft Biological Assessment (BA) based on information in the Draft EIS and from site walkovers and will continue informal consultation under the Endangered Species Act. A copy of the draft BA is included in Appendix E of the Final EIS.

2.4 ACCIDENTS

One commentor questioned the adequacy of the accident analysis for the Low-Temperature Drying Alternative, pointing out that for high-level waste, explosions and criticality are typically evaluated. DOE considered a wide range of accident scenarios and selected for detailed analysis those that were determined to be credible.

Because low-temperature drying is a low-energy process and is conducted in small, 1 m^3 batches, an explosion would be unlikely. Further, this waste treatment process would be performed in an area with 2-ft-thick walls for radiological protection. Workers are not allowed in the area when treatment is occurring. As a result, there is little risk to involved and non-involved workers.

With regard to criticality accidents, DOE has no process knowledge suggesting that any enriched materials would be part of the waste stream. In addition, administrative and process controls would be followed that avoid criticality.

3. COMMENT DOCUMENTS AND RESPONSES

3.1 INTRODUCTION

This chapter presents the comments submitted to DOE during the public comment period on the Draft EIS, including the transcript of the public hearing held on the Draft EIS.

Comment letters are scanned copies of the originals, with the exception of e-mail transmittals, which were printed as received. One comment provided on a blue card was typed because the blue card did not reproduce well. Some comment documents are reproduced at a reduced scale.

Individual comments are marked in the right margin with a sidebar and given a unique alphanumeric identifier. Responses can be cross-referenced to each comment using the alphanumeric identifier. As appropriate, the response will provide references to specific sections of the Final EIS, particularly those sections that have been modified.

3.2 COMMENTS

Comments from six agencies and public groups, the public hearing comments, and three private individuals follow in this section. DOE responses are provided for each comment.

THIS PAGE INTENTIONALLY LEFT BLANK

3.2.1 Oak Ridge Site Specific Advisory Board

Many Voices Working for the Community

Oak Ridge
Site Specific Advisory Board

April 11, 2000

Mr. Rod Nelson
Assistant Manager for Environmental Management
DOE-ORO
P.O. Box 2001
Oak Ridge, TN 37831

Dear Mr. Nelson:

Recommendations and Comments on the *Draft Environmental Impact Statement for Treating Transuranic/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE-EIS-0305-D, February 2000

At our April 5, 2000, Board meeting, the Oak Ridge Site Specific Advisory Board reviewed and approved the attached recommendations and comments on the subject document.

While the Board agrees with selection of the preferred alternative, the document, in general, does not meet our expectations in regard to other public documents from the Environmental Management Program. The Executive Summary alone contains enough simple errors (see attached comments) that it leads one to question if there are more complex errors buried in the technical sections. We are also concerned that an alternative (number 5) has been presented that includes permanent storage of transuranic waste in Melton Valley—an option that we find unacceptable..

We appreciate the opportunity to comment on the document and look forward to receiving your written response to our recommendations and comments.

Sincerely,

Steven H. Kopp, Chair

SHK/plo

cc: Bill Cahill, DOE-ORO
Susan Gawarecki, LOC
Clayton Gist, DOE-ORO
John Hankinson, EPA
Earl Leming, TDEC
Teresa Perry, DOE-ORO
Bryan Westich, DOE-ORO

P O Box 2001, EM 90, Oak Ridge, TN 37831 • Phone 865-241-3665, 1-800-382-6938 • Fax 865-576-5333
E-mail blackskl@ornl.doe.gov • Web http://www.oakridge.doe.gov/em/ssab

ORSSAB-1

Response to Comment ORSSAB-1

Comment noted. Specific responses to comments are addressed in detail below.

Oak Ridge Site Specific Advisory Board
Recommendations and Comments
on the *Draft Environmental Impact Statement*
for Treating Transuranic/Alpha Low-Level Waste
at the Oak Ridge National Laboratory, Oak Ridge, Tennessee,
DOE-EIS-0305-D, February 2000

RECOMMENDATIONS

Road Construction
The issue of a new road to the Transuranic (TRU) Waste Treatment Facility was raised at the February 1999 scoping meeting. At that time, DOE said it was moving forward on the road under a categorical exclusion. We find no categorical exclusion applicable to construction of a two-lane, 1.4-mile road (suitable for two vehicles or two tractor-trailers to pass) through undisturbed woodland. We believe that DOE violated the National Environmental Policy Act (NEPA) and its DOE NEPA Implementing Procedures [10 *Code of Federal Regulations (CFR)* Part 1021] by (1) not preparing an environmental assessment for the construction of the road or (2) not including construction of the road in the Draft Environmental Impact Statement (EIS) for Treating TRU/Alpha Low-Level Waste (DOE-EIS-0305-D). Since the road is completed, the Oak Ridge Site Specific Advisory Board (ORSSAB) recommends that DOE at least include the impacts of road construction in the cumulative impacts section of the final EIS.

Alternative 5
This comment is confined to Alternative 5 [treatment of the TRU waste by vitrification, cementation, or drying and storage of the resulting product at some unspecified location in Melton Valley for a long-term (indefinite) period of time (see Table 5-3)].

The public has been led to believe that TRU waste will be treated on site, and following treatment, the product will be transported to the Waste Isolation Pilot Plant (WIPP) for disposal [Records of Decision (RODs) for the WIPP Site-Wide EIS II (DOE 1998) and the Waste Management Programmatic EIS (WM PEIS) (DOE 1998c) and various public SSAB meetings]. We recognize that some of the treated remote-handled TRU waste may remain on site until waste acceptance criteria at WIPP are determined. However, such short-term storage of part of the treated TRU waste is qualitatively quite different from a decision to keep all treated waste in Oak Ridge indefinitely.

We find Alternative 5 unacceptable for the following reasons, and even if the assessment were adequate, we believe the public would reject long-term storage of TRU waste on site for these reasons as well:

- a feasible stewardship plan for long-term storage is lacking;
- the costs and funding of long-term monitoring and maintenance are not addressed;
- the effects on future land use and on community image are not correctly considered;
- the more expensive vitrification process would likely be required in order to decrease any impacts to human health and the environment during indefinite storage without maintenance.

1

ORSSAB-2

ORSSAB-3

Response to Comment ORSSAB-2

DOE determined that a categorical exclusion was the appropriate level of NEPA review for the construction/relocation of the access road to the High Flux Isotope Reactor (Old Melton Valley Road) based on the requirements of 10 *CFR* 1021, Subpart D. DOE evaluated whether the proposed action would meet the conditions for applying a categorical exclusion found at 10 *CFR* 1021.410(b), i.e., that the proposed action fits within the classes of actions listed in Appendix B, that there were no extraordinary circumstances related to the proposal, and that the proposal was not connected to other actions with potentially significant impact. DOE determined that the proposed action did fit within categorical exclusions listed in Appendix B to 10 *CFR* 1021, Subpart D (i.e., B1.13 Construction/acquisition/ relocation of on-site pathways, short on-site access roads/railroads; B1.11 – Fencing, no adverse effect on wildlife movement/surface water flow; and B1.15 – Siting/construction/ operations of support buildings/support structures, e.g., security post). (Also, see next paragraph.) DOE also determined that the proposal did not present any extraordinary circumstances and was not connected to other actions with potentially significant impacts. While the road upgrades could provide access to the proposed Transuranic Waste Treatment Facility analyzed in this EIS, at the time the categorical exclusion was evaluated, the upgrades to the Old Melton Valley Road were needed to facilitate emergency access to the High Flux Isotope Reactor.

As part of determining whether the proposed action fits the categorical exclusions, DOE evaluated whether the proposed

action would meet all the integral elements listed in Appendix B, to 10 *CFR* 1021, Subpart D. A rare plant survey was performed for the access road upgrade. A copy of the categorical exclusion (CX-TRU-98-007) and the rare plant survey has been added to Appendix G of the Final EIS. As a result of the survey, DOE adjusted the location of the road to minimize, to the extent practical, the impacts to a State-protected plant species, the Pursh's Wild Petunia (*Rubellia purshiana*). DOE also evaluated whether the proposed action would pose a threat of significant individual or cumulative effects on environmentally sensitive resources such as archeological or historic sites, potential habitats for threatened or endangered species, floodplains, wetlands, Federally or State-designated wilderness areas, natural landmarks, wildlife sanctuaries, primer agricultural lands, or special sources of water such as sole-source aquifers. Based on this information, DOE determined that applying the categorical exclusions for upgrading the Old Melton Valley Road was appropriate.

The upgrades to the access road were listed in Table 5-1, as an action with the potential to contribute to cumulative impacts. The impacts associated with the upgrades to the access road were discussed in Sections 5.2, 5.3.2, and 5.5 of the Cumulative Impacts Chapter in the Draft EIS. In the Final EIS, additional discussion has been added to Sections 5.2 and 5.3.2, to describe how the Old Melton Valley Road upgrades potentially contribute to the cumulative impacts to ecological and water resources (i.e., siltation of White Oak Creek and White Oak Lake). The discussion of this action in Section 5.5 (related to air quality impacts) has been revised because construction of the access road is complete. Impacts from particulate matter emissions during road construction were evaluated quantitatively.

Response to Comment ORSSAB-3

DOE does plan to ship treated waste offsite for disposal as soon as the waste is treated. The description of Alternative 5

(Treatment and Waste Storage at ORNL) has been clarified to better reflect this intent. However, in considering its responsibility to protect human health and the environment, DOE believes it is reasonable, in accordance with the Council on Environmental Quality's NEPA regulations (40 *CFR* 1502.14) to analyze the impacts of potential storage of treated waste (e.g., in the event disposal capacity is unavailable).

In order to bound potential environmental impacts from storage of the treated waste while under DOE's control, the EIS presented impacts for a 100-year time period. Because it is inappropriate to rely primarily on institutional control for long-term protection, DOE customarily chooses 100 years as the limit for institutional controls in conducting an analysis of any of its activities on its sites. The analysis of loss of institutional control that is presented under the No Action Alternative in Chapter 4 for untreated waste would bound the potential impacts from loss of institutional control for treated waste in storage. However, in the event of long-term storage of the treated waste, DOE would monitor and maintain the waste as long as necessary.

The commentor indicated that the Treatment and Waste Storage at ORNL Alternative was unacceptable for several reasons, as discussed below. First, the commentor stated the EIS lacked a feasible stewardship plan for long-term storage. The Department is currently developing national and local stewardship reports and plans that will address details of DOE's stewardship responsibilities. Should the Treatment and Waste Storage at ORNL Alternative be selected, the scope of long-term stewardship activities related to the Treatment and Waste Storage at ORNL Alternative would be included as part of the local Oak Ridge Stewardship Plan.

Second, the commentor noted that the EIS lacked information about costs and funding of long-term monitoring and maintenance. The Department did not include information about costs or funding for any alternatives in the EIS because these issues are not part of the environmental review. In the ROD to be issued after the Final EIS is completed, DOE will

identify all relevant factors (such as economic, environmental, and other considerations) that were considered in deciding on an alternative.

Third, the commentor noted that the EIS did not correctly consider the effects on future land use and on community image. The impacts on future land use from the Treatment and Waste Storage at ORNL Alternative are addressed in Section 4.1.6 of the EIS. With regard to impacts on community image, it is well established that the perception of risk of adverse impacts (such as speculation about negative community image) is outside the sphere of topics that are subject to examination under the NEPA. How factors that may contribute to community image are interpreted depends on the value system of individuals. DOE does note, however, that storage of the treated waste onsite under the Treatment and Waste Storage at ORNL Alternative would present less of a threat to public health and safety, and the environment, than the untreated waste would currently present. Further, DOE is not accepting large volumes of off-site waste but rather is treating existing on-site waste to reduce risk, as this waste may have to be stored at ORNL.

Fourth, the commentor indicated that without maintenance, vitrification of the waste would likely be needed in order to decrease any impacts to human health and the environment during the storage period under the Treatment and Waste Storage and ORNL Alternative. The EIS analyzed treatment using any one of the three technologies (i.e., low-temperature drying, vitrification, and cementation) before storage of the waste onsite. Each of these treatment approaches would treat the waste to meet land disposal restriction (LDR) standards under the Resource Conservation and Recovery Act (RCRA), in case the waste would need to be stored onsite before transport offsite for disposal. Maintenance and surveillance would be an integral part of DOE's storage efforts under the Treatment and Waste Storage at ORNL Alternative, regardless of the treatment technology used. DOE will ensure that the treated waste, using any of the treatment technologies, would either be compatible with the container type proposed in the EIS, or DOE will, as laboratory data become available, determine the type of container that would be needed.

Finally, the commentor also suggested that the Treatment and Waste Storage at ORNL Alternative be deleted from the EIS or be modified to cover only 30 years. As noted above, DOE is required to evaluate all reasonable alternatives for a proposed action, and because DOE believes it is reasonable to consider storage, the Treatment and Waste Storage at ORNL Alternative has been kept in this evaluation. Section 2.7, which describes Treatment and Waste Storage at ORNL, explains that DOE assumed a maximum 100-year institutional control period for analyzing the Treatment and Waste Storage at ORNL Alternative and presented impacts cumulatively over that time. To help the commentor understand differences between the impacts presented in the Draft EIS and those for a 30-year timeframe, or on an annual basis, a brief description of how the impacts would differ is provided below.

- Impacts on utility usage and involved workers from the surveillance and maintenance of stored waste would increase linearly with time under the Treatment and Waste Storage at ORNL Alternative. Considering a 30-year timeframe as compared to a 100-year timeframe would show lower impacts for both utilities and worker exposure. For example, utility usage for the Treatment and Waste Storage at ORNL Alternative over a 30-year timeframe would total 1.5 million gallons of water and 750 MW of electricity. By comparison, utility usage for the Treatment and Waste Storage at ORNL Alternative over a 100-year storage timeframe (excluding processing usage) would total 5 million gallons of water and 2,500 MW of electricity.
- In terms of involved worker exposure, the EIS estimates that an average of five workers per year would be used to perform maintenance and surveillance during on-site storage. Assuming the 100 mrem annual administrative limit, the annual dose to the worker population is 0.5 person-rem resulting in 2E-04 latent cancer fatalities (LCFs), and the total dose to the involved worker population over a 30-year timeframe is 15 person-rem, resulting in 6E-03 LCFs. By comparison, over a 100-year timeframe, the involved worker exposure is estimated to result in a total dose of 50 person-rem

and 2E-02 LCFs. Health impacts to non-involved workers and the public, beyond those described in Section 4.10.7 for the treatment processes, are not expected from the on-site storage of the treated waste pending off-site disposal.

- The analysis in the EIS indicates that other impacts from the proposed action (e.g., land use; ecological, water, and air resources; and accidents) are not expected to be different when analyzed under a 30-year timeframe as compared to a 100-year timeframe, because most impacts would be associated with the waste treatment process.

Thus, ORSSAB recommends that.

- Alternative 5 be deleted from the final EIS or be altered to provide for only short-term (temporary) storage in Melton Valley for a period of no more than 30 years,
- the final EIS find the current Alternative 5 unacceptable, or
- the inherent problems associated with Alternative 5 be fully assessed in the final EIS.

The retention of an alternative that includes long-term (permanent) storage of TRU waste on site is also likely to be costly in terms of public trust.

GENERAL COMMENTS

ORSSAB is inclined to agree with selection of the preferred alternative of low-temperature drying for the Melton Valley Storage Tank wastes (sludge and supernate) and segregation for the solid wastes [contact-handled and remote-handled TRU/alpha low-level heterogeneous debris], assuming that the relative differences in impacts of the alternatives for the proposed action remain as presented.

That the preferred alternative will actually achieve Resource Conservation and Recovery Act land disposal restriction standards in the event that WIPP is not accepting remote-handled TRU waste in time to meet the Tennessee Department of Environment and Conservation Commissioner's Order is of somewhat concern. It is understood that testing is underway, with results possibly not available until after a ROD is reached selecting the alternative.

Throughout the document, the subject of the WM PEIS and its associated ROD is addressed in the future tense. These references should all be revised to reflect the fact that the ROD has been issued, and the impact of that ROD should be described.

The issues of extraction of buried waste for treatment and transportation on the Oak Ridge Reservation (ORR) need to be addressed in some detail. Relying on other documents for this documentation does not allow the reader to understand the operations. It is a common observation that interface problems between two systems, e.g., transportation and facility, are often the most problematic aspects of a waste handling operation.

We would like to know if the three treatment options have ever been used on a large scale for materials similar to these waste. History shows that there are always unanticipated problems associated with start up of new technologies. If the technology is unproven, that should be acknowledged, and discussion of how to handle unexpected problems should be included.

The document, in general, is not particularly user-friendly. It does not meet the expectations of the public in regard to other public documents from the Environmental Management (EM) Program. In fact, there are enough simple errors in the Executive Summary alone (see the following specific comments) that it leads one to question if there are more complex errors buried in the technical sections; i.e., the non-technical errors lead to a question of overall credibility.

SPECIFIC COMMENTS

Page viii- Page numbers of Sects. 9, 10, and 11 are wrong. They should be 9-1, 10-1, and 11-1 respectively.

ORSSAB-3

(cont.)

ORSSAB-4

ORSSAB-5

ORSSAB-6

ORSSAB-7

ORSSAB-8

ORSSAB-9

ORSSAB-10

Response to Comment ORSSAB-4

Comment noted.

Response to Comment ORSSAB-5

DOE determined that it would be prudent to treat wastes to achieve LDR standards in the event DOE cannot ship the waste offsite as intended and interim on-site storage is required.

The purpose of the testing mentioned by the commentor is to help ensure that the waste treated by the Low-Temperature Drying Alternative would meet Waste Isolation Pilot Plant (WIPP) requirements.

While low-temperature drying does not itself accomplish LDRs, as it functions only to remove water from the waste, treatment is done by treatment of the waste with additives to convert the heavy metals to less leachable compounds. This would result in a waste stream that can meet LDRs.

Response to Comment ORSSAB-6

When DOE issued the Draft TRU Waste Treatment EIS, the ROD for low-level waste under the *Waste Management Programmatic Environmental Impact Statement* (WM PEIS) had not yet been issued. The analysis in the TRU Waste Treatment EIS is based on disposal of low-level waste at the Nevada Test Site (NTS). As a result, the analysis in the TRU Waste Treatment EIS would not change. Low-level waste resulting from the treatment processes would be certified by DOE for disposal at the Nevada Test Site selected in the *Record of Decision for the Department of Energy's Waste Management*

Program: Treatment and Disposal of Low-level and Mixed Low-level Waste; Amendment of the Record of Decision for the Nevada Test Site (DOE 2000).

Response to Comment ORSSAB-7

Discussion of the impacts from accidents related to the exhumation, handling, and on-site waste transport have been added to Section 4.8 (specifically, Sections 4.8.1.1, 4.8.1.2, 4.8.3.1, 4.8.4.1, 4.8.5.1, and 4.8.6.1). Also see response to comment NM-1 in Section 3.2.7.

Response to Comment ORSSAB-8

By "large scale" for materials similar to these wastes, DOE assumes that the commentor means a scale comparable to the proposed project and wastes that exhibit comparable radiological content and matrix characteristics. Several examples of existing technologies are provided below:

- Drying
  - The Hanford's 200 Area evaporator (near Richland, Washington) routinely processes sodium nitrate solutions to a dry solid consistency.
  - The Palo Verde Nuclear Generating Station (outside Phoenix, Arizona), dries and packages the evaporator concentrate and tank sludge.
  - The Three-mile Island – 2 Evaporation Project (near Harrisburg, Pennsylvania) evaporated and dried water containing boron, sodium, corrosion products, and sludge.

- Solidification
  - The Oak Ridge site solidified supernate liquids from the MVSTs at ORNL into concrete monoliths.
  - The Hanford, Rocky Flats, and Savannah River sites have solidified large quantities of high-nitrite wastes using hydraulic cements over the last 20 years.
- Vitrification
  - The Savannah River M-Area processes high-level wastes.
  - The Fernald, Ohio Minimum Additive Waste Unit processes low-level wastes.
  - The West Valley (New York) Vitrification Plant processes high-level wastes.

Response to Comment ORSSAB-9

Comments on the Summary and other parts of the Draft EIS are addressed individually below. Editorial corrections have been made in the Final EIS. The process flow charts were clarified and explanatory footnotes were added to Tables S-3 and 2-6 to make the document more user friendly. DOE recognizes that the Draft EIS contained errors as noted by the commentor. A thorough quality assurance/quality control (QA/QC) review has been conducted of the Final EIS (technical and nontechnical) to address these concerns.

Response to Comment ORSSAB-10

The page numbering in the Table of Contents has been corrected.

Page S-1: The map of the ORR does not show the city boundaries of Oak Ridge, although it implies that it does visually. Change per the Site Specific Advisory Board recommendation on the topic, R04/01/98.10, *Accuracy in Describing Relationships Between ORR, City of Oak Ridge, and Surrounding Populated Areas* (see attachment), as agreed to by DOE-EM. Same comment on page 1-1.

Page S-2: Line 7, add "EPA" to the list of those who have a high priority for cleanup.

Page S-3: Second paragraph, last sentence - This implies complete, item-by-item characterizations of all solid waste to determine the presence of Resource Conservation and Recovery Act materials. Is this intended? If so, is it addressed in the technical analysis.

Page S-3: Sect. S1.2.2, first sentence - Is 30 percent of the legacy tank waste still in Bethel Valley? The impression is that most of the Gunite Tanks have been cleaned out.

Page S-5: First paragraph - With all the cited documents requiring disposal of these wastes, how can alternatives 1 and 5 be considered?

Page S-6: Third paragraph - First reference to WM PEIS ROD in the future tense.

Page S-7: Last sentence above photograph - To what standards will decontamination and decommissioning (D&D) be conducted? Who is responsible for any residual contamination at the facility site?

Page S-8: Preferred alternative is "Drying" not "During."

Page S-9: First paragraph: What are the "specified waste acceptance criteria?" Are they established now? They could have large impacts on performance, costs, etc.

Page S-10: Sect. S1.4.2.2 does not mention the impacts of the facility access road. We believe that the use of a Categorical Exclusion is not proper for this action.

Page S-10: Second paragraph, first sentence should read "...evaporating the free liquids and drying the TRU mixed waste sludges... ." You cannot evaporate sludges which include solids.

Page S-11: Figure S-5 does not agree with descriptive text. It does not show the option of supernate transfer of the evaporator before mixing/sampling, nor does it show condensate reuse in sludge retrieval.

Page S-11: Second paragraph - The topic of retrieval and delivery of solid wastes to the facility needs to be treated in this EIS.

Page S-12: First paragraph - What happens if DOE does not find the compacted waste to be certifiable? Must it be recycled, and is the facility capable of that?

Page S-12: Second paragraph - The conversion of units has an error. If 10,833 m^3 = 3,843,546 ft^3 then 5,550 m^3 does not equal 19,423 ft^3 or vice versa.

Page S-18: Table S-1 - This table is difficult to compare with other numbers in the text. Also, is D&D waste from the facility included? Does such waste go to the on-site disposal cell?

ORSSAB-11

ORSSAB-12

ORSSAB-13

ORSSAB-14

ORSSAB-15

ORSSAB-16

ORSSAB-17

ORSSAB-18

ORSSAB-19

ORSSAB-20

ORSSAB-21

ORSSAB-22

ORSSAB-23

ORSSAB-24

ORSSAB-25

ORSSAB-26

Response to Comment ORSSAB-11

The purpose of the map referenced by the commentor was to show the location of the proposed treatment facility site in relation to ORNL, other DOE plants in the area, and the City of Oak Ridge. Figures S-3, 1-1, and 2-1 have been modified as requested to show the city boundary.

Response to Comment ORSSAB-12

DOE acknowledges that cleanup at the ORR is a high priority for EPA. The ORR is listed on the National Priorities List (as of November 1989). Text in Sections S1.1 and 1.1 was modified.

Response to Comment ORSSAB-13

The degree of characterization required for the solid waste would be driven by the project's RCRA permit and the applicable disposal site's waste acceptance criteria (WAC), which do not require item-by-item characterization.

Response to Comment ORSSAB-14

The Draft EIS presented a snapshot in time. The inactive tanks at ORNL are undergoing waste retrieval operations, which are scheduled to be completed by the end of fiscal year 2001.

Response to Comment ORSSAB-15

Under NEPA, the No Action Alternative must be evaluated (40 *CFR* 1502.14). DOE is also obligated to evaluate all reasonable alternatives (40 *CFR* 1502.14). DOE believes that Treatment and Waste Storage at ORNL is a reasonable alternative under NEPA because of the possible need for interim storage. Also see the response to comment ORSSAB-3.

Response to Comment ORSSAB-16

Text in Section S1.4.1 modified.

Response to Comment ORSSAB-17

For the Low-Temperature Drying Alternative, decontamination and decommissioning (D&D) would be performed in accordance with a plan that would be proposed by the Foster Wheeler Environmental Corporation (Foster Wheeler) and approved by DOE. Although specific standards have not been identified, Foster Wheeler is responsible for removing contamination to pre-project levels per stipulations in the contingent contract with DOE.

Response to Comment ORSSAB-18

Typographical error in Section S1.4.2 corrected.

Response to Comment ORSSAB-19

The specified WAC are established now. The WAC for WIPP and NTS involve physical, radiological, and chemical characterization data requirements for TRU and low-level waste respectively. These WAC's are available at:
http://www.wipp.carlsbad.nm.us/library/caolib.htm, and
http://www.NV.DOE.gov/programs/envmgmt/rwap/ntswac.htm.

Response to Comment ORSSAB-20

As discussed in the response to comment ORSSAB-2, DOE determined that the upgrade of the Old Melton Valley Road could be categorically excluded.

Response to Comment ORSSAB-21

The intent of the text is to indicate that supernate and liquid in the sludges would be dried, leaving a solid waste. Text in Section S1.4.2.2 modified.

Response to Comment ORSSAB-22

Comment noted. The figure is a simplified diagram of the process. The EIS discussion is more detailed than the figures might suggest in some cases.

Response to Comment ORSSAB-23

Discussion and analysis of exhumation, handling, and on-site transportation have been added to Section 4.8.

Response to Comment ORSSAB-24

DOE certification is to ensure the treated waste meets the appropriate WAC of the disposal facility. DOE's contract with Foster Wheeler, if exercised, states that waste must be treated to meet the WAC. If it does not, Foster Wheeler would be required to retreat the waste.

Response to Comment ORSSAB-25

Text in Section S1.4.2.2 has been corrected.

Response to Comment ORSSAB-26

The total TRU and low-level waste volumes reported in Table S-1 are derived from the alternative-specific waste volumes presented in Tables 2-1 (low-temperature drying), 2-2 (vitrification), and 2-3 (cementation). The total waste volume estimates presented in Table S-1 include alternative-specific waste streams entitled primary, secondary, and D&D. The Table S-1 total volumes do not include sanitary wastewater or nonhazardous waste (e.g., construction debris). D&D waste is included. Depending on the contaminant levels and other characteristics, D&D waste would be disposed of at locations appropriate to its disposal. TRU-contaminated D&D waste would be shipped to WIPP and is included in the transportation impacts evaluated in Section 4.8 of the Final EIS. Likewise, low-level waste may be shipped to the NTS; D&D waste with hazardous constituents would likely be sent to Envirocare in Utah, and uncontaminated construction debris and sanitary waste would go to local landfills. DOE does not plan to dispose of any D&D wastes from this project in the on-site disposal facility.

Page S-19 Add to the difficulties with the Idaho National Engineering and Environmental Laboratory the fact that there is an agreement with the State of Idaho not to ship such waste to that state

Page S-20 Sect. S1.6.3 - Fauna list is probably not inclusive, e.g., skunk, possum.

Page S-22: Sect. S1.6.9 - Water is supplied by the City of Oak Ridge Water Treatment Facility, not DOE.

Page S-22: Sect. S1.6.10 - It is not clear whether these data (Table S-2) are for 1997 or for the period of plant operation. Also, should this operation not be separated from Oak Ridge National Laboratory (ORNL) calculations since there are two different contractors?

Page S-23 Sect. S1.6.13 - Intuitively, the number of 7,500 people seems to be low for 5 miles from the center of ORR. It may be true for 5 miles from the center of ORNL.

Page S-28. Table S-3 (Transportation) - There is no mention of the transportation of D&D waste, or of on-site transport of wastes to the facility.

Page S-32: Paragraph 5 - Is ground disturbance fugitive emission from the EM Waste Management Facility spoils pit included? If not, why?

In Sect. 4.7.3, the air quality impacts of the low-temperature drying alternative are presented with a conclusion that the proposed emissions are below the State of Tennessee limits for air permitting exemptions. This assumption and recent changes in the regulations cited along with any consequences of ORNL being issued a Title V Operating Permit under the Clean Air Act during this time frame should be more closely evaluated. Continuous sampling that will be required for at least some radionuclides is not discussed.

Appendix B provides emissions and materials balance data for the preferred alternative and the vitrification and the cementation alternatives. Generally for radionuclides and metals, the methodology of Appendix D to 40 *CFR* Part 61 – Methods for Estimating Radionuclide Emissions – is applied. The procedure involves multiplying the amount used by a factor which depends on the physical state of the radionuclide (1 for gases, 10^{-3} for liquids and particulate solids, and 10^{-4} for solids). Additional adjustment factors are provided for effluent controls. For high-efficiency particulate air (HEPA) filters (plural), an adjustment factor to emissions of 0.01 is provided for particulate radionuclides. There may be some question, even though the factor is conservative, that it may be applied for each of multiple HEPA filters in series. Appendix D to Part 61 also states that if any nuclide is heated to a temperature of 100°C (212°F) or more that it must be considered a gas. The temperature of the low-temperature drying alternative is not apparent from any process descriptions in the document except in response to a question from the public scoping meeting summarized in Appendix A.3, where it was said to be 180–190°F. The temperature for vitrification is expected to be higher; therefore, the uncontrolled radionuclide emissions would be the amounts used in the process unless an additional assumption is made and validated. The Appendix D approach to calculating metals emissions may be questionable for mercury and possibly other metals with volatility such as lead. Finally, the basis for assumed inlet particulate concentrations (in grains per cubic foot) reaching the exhaust system HEPA filters is not clear. Citation of additional data in terms of percent or fraction carryover from the process may be a helpful benchmark.

For the vitrification alternative, the treatment flow diagram (Figs. S-7 and 2-8) is presented in an over-simplified manner if a selective catalytic reduction unit is included for control of NO_x emissions

4

ORSSAB-27

ORSSAB-28

ORSSAB-29

ORSSAB-30

ORSSAB-31

ORSSAB-32

ORSSAB-33

ORSSAB-34

ORSSAB-35

ORSSAB-36

Response to Comment ORSSAB-27

DOE is not currently legally prohibited from shipping waste to Idaho National Engineering and Environmental Laboratory (INEEL) to be treated so long as the waste is treated and leaves INEEL within a specified time period; however, additional concerns related to shipping waste to INEEL are addressed in Section 2.8.1.

Response to Comment ORSSAB-28

Text in Section S1.6.3 has been modified to be more inclusive.

Response to Comment ORSSAB-29

The Summary and related sections in the Final EIS have been modified to indicate that the City of Oak Ridge Water Treatment Facility would provide water.

Response to Comment ORSSAB-30

The table presents human health data from the ORR Site Environmental Report for 1997, to characterize the affected environment. Table S-2 does not include data for the period of plant operation because the facility has not been built. DOE believes the data are appropriately presented because information from both ORR and ORNL is presented, and the proposed facility would be located at ORNL on the ORR.

Response to Comment ORSSAB-31

There are approximately 7,500 people within a 5-mile radius of the proposed treatment facility at ORNL. Text in the Summary and related sections in the Final EIS have been modified.

Response to Comment ORSSAB-32

On-site waste transportation is addressed in Tables S-3 and 2-6 and Section 4.8 of the Final EIS. See response to ORSSAB-26 for D&D waste.

Response to Comment ORSSAB-33

Yes. The Environmental Management (EM) Waste Management Facility spoils pit emissions are part of the environmental baseline in the Affected Environment (Section 3.7).

Response to Comment ORSSAB-34

DOE will comply with air quality laws and regulations in force at the time, should the proposed facility be constructed and operated. At the present time, Foster Wheeler has a Permit to Construct an Air Contaminant Source for the TRU Waste Treatment Facility (Permit #950877P) granted by TDEC on March 24, 1999. The permit requires monitoring and testing per 40 *CFR* 61.93(a) + (b). Monitoring is "continuous" per the regulation cited. Even though the projected air emissions would be below the state standards, TDEC required a permit for this facility. Emissions from the proposed facility would be so low that for practical purposes the facility would not affect ORNL's Title V permit.

Response to Comment ORSSAB-35

DOE believes the methodology used is appropriate and conservative for particulate emissions (radiological or metals). High-efficiency particulate air (HEPA) filters can be used in series to achieve a very high (>99.97%) efficiency; however, for purposes of impact analysis, DOE assumed a 99% efficiency. The preferred alternative is a Low-Temperature Drying Alternative in which drying is accomplished at less than 100°C or less than 212°F. This temperature does not justify the consideration of non-gaseous radionuclides as gaseous. The temperature of vitrification is much higher; however, there is a gas-cooling liquid scrubber system with associated high-efficiency mist eliminator that removes liquid droplets from the scrubber and cools the gases to less than 100°C before final HEPA filtration. This cooling process permits the use of the HEPA filter efficiency for impact analysis.

Response to Comment ORSSAB-36

Comment noted. As noted in the response to ORSSAB-22, the flow diagrams are presented in a simplified manner and additional detail is provided in the text.

RECOMMENDATION 10, DATED 4/1/98

ACCURACY IN DESCRIBING RELATIONSHIPS BETWEEN OAK RIDGE RESERVATION, CITY OF OAK RIDGE, AND SURROUNDING POPULATED AREAS

BACKGROUND

ORR borders Knox and Loudon counties and lies almost entirely within the City of Oak Ridge. The basic situation has not changed since the city incorporated in 1959, though some areas have been annexed and the populations of nearby areas continue to rise. Many documents prepared for DOE-ORO speak in some way of the distance from the reservation to nearby Oak Ridge and reflect other cities as dots on compressed maps. While occasional flaws are anticipated in draft documents, populations near the reservations need to be properly represented.

RECOMMENDATION

ORREMSSAB recommends that DOE-ORO EM routinely notify contractors of the actual geographic boundaries of the ORR and the City of Oak Ridge. On an appropriate scale, the geographical extent of nearby cities should also be shown. Accuracy is required in describing the relation of operations on the ORR to any municipal entity.

As for properly representing the relationship of any ORR release points to the surrounding population, basic population maps need to be prepared. Broader scale maps showing the smallest census units could be shaded to illustrate the varying population density. Enlarged fine-scale maps could roughly represent streets and/or dwelling units, providing approximate shading related to population. At every map scale an appropriate wind rose should be printed, obtained at a stated position and altitude, to indicate the prevailing air movement patterns. In any case the reader should be encouraged to appreciate the density of the nearby population. Streams should also be clearly indicated.

DOE RESPONSE, DATED 4/29/98

DOE has advised all the DOE Oak Ridge programs of the Board's request to make proper references to the City of Oak Ridge boundaries and populations near the reservation on future DOE maps. Additionally, all contractor and subcontractor organizations will be provided a copy of the Board's recommendation.

See response to comment ORSSAB-11.

3.2.2 City of Oak Ridge

CITY OF
OAK RIDGE

OFFICE OF THE MAYOR

POST OFFICE BOX 1 • OAK RIDGE, TENNESSEE 37831-0001

April 11, 2000

Dr. Clayton Gist, Waste Management
Integration Team Leader
U. S. Department of Energy
Oak Ridge Operations
55 Jefferson Avenue
P. O. Box 2001
Oak Ridge, TN 37831

DOE's Draft Environmental Impact Statement for Treating Transuranic (TRU)/Alpha Low-Level Waste at Oak Ridge National Laboratory

Dear Dr. Gist:

Enclosed is a memorandum to the Oak Ridge City Council from Ellen D. Smith, Chairperson of the Environmental Quality Advisory Board of the City of Oak Ridge, transmitting the Board's comments on the above-referenced Environmental Impact Statement.

The Oak Ridge City Council, during its regular meeting on April 10, 2000, received the memorandum and attachment for the record and directed that they be transmitted to the Department of Energy as comments from the Environmental Quality Advisory Board.

Very truly yours,

David R. Bradshaw

David R. Bradshaw
Mayor Pro Tem

jb

Attachment

cc: Ellen D. Smith

ENVIRONMENTAL MANAGEMENT
DIVISION FILE CODE NUMBER

[illegible]
[illegible]
[illegible]

CITY OF
OAK RIDGE

April 5 2000

To Honorable Mayor and Members, Oak Ridge City Council

From Ellen D Smith, Environmental Quality Advisory Board

Subject DOE EIS for Treating Transuranic Waste and Alpha Low-Level Waste at ORNL

The Environmental Quality Advisory Board (EQAB) has reviewed the Department of Energy (DOE) Draft Environmental Impact Statement (EIS) for Treating Transuranic (TRU) Alpha Low-Level Waste at Oak Ridge National Laboratory (ORNL)

DOE proposes to build a TRU waste treatment facility in the Melton Valley area and to use the facility to treat TRU and alpha low-level radioactive and mixed waste currently stored in the Melton Valley Storage Tanks and other ORNL waste management facilities Very small amounts of waste from other DOE sites might also be accepted for treatment, following additional review Under DOE's preferred alternative, wastes would be treated primarily by drying After treatment, the wastes could be shipped offsite for disposal, the TRU waste to the Waste Isolation Pilot Plant (WIPP) in New Mexico and the alpha low-level waste (LLW) to the Nevada Test Site (NTS)

EQAB supports the implementation of the proposed action Successful completion of this project would benefit our community by eliminating the environmental liability and potential risks associated with the legacy wastes it would treat According to the EIS analyses, the community would not experience significant adverse environmental impacts from operation of the proposed facility For example, radioactive releases to the air would be minimized by use of HEPA filters

However, we have some concerns about the EIS, as detailed in our attached comments

- The EIS may understate some potential impacts from the proposed waste management operation
- The EIS does not effectively communicate the need for the project or fully disclose the magnitude of the potential adverse consequences in Oak Ridge if wastes must remain in storage Wastes would need to be kept in storage either if the project is not completed (the "no-action" alternative) or if WIPP and NTS are unable to receive Oak Ridge's treated wastes for disposal This is not a theoretical concern although WIPP is open, it is not yet authorized to receive remote-handled TRU waste and there is some uncertainty as to its capacity to handle all of DOE's TRU waste

We recommend that our comments be submitted to DOE to aid in preparing a final EIS that better presents the implications of the proposal

cc Paul Boyer, City Manager
Amy Fitzgerald, City of Oak Ridge
Susan Gawarecki, Local Oversight Committee

COR-1

COR-2

COR-3

Response to Comment COR-1

Comment noted.

Response to Comment COR-2

DOE has added an analysis of waste exhumation, handling, and on-site transport in Section 4.8 and expanded analysis in Chapter 4 to address impacts after loss of institutional control. See responses to comments below.

Response to Comment COR-3

See response to comments COR-6 and COR–7.

Environmental Quality Advisory Board Comments on
DOE Draft EIS for Treating Transuranic (TRU)/Alpha Low-Level Waste
at Oak Ridge National Laboratory

Major Concerns

1 Some of the primary potential impacts to the environment and general public from the proposed treatment action seem to have been overlooked by this draft EIS because the scope of the analysis is unduly restricted. The action that is considered in the EIS seems to begin when the waste is "delivered by DOE" to the TRU Waste Treatment Facility. As a result, the proposed action as defined in the draft EIS fails to capture a significant component of the overall risk that bringing the ORR's inventory of TRU waste to proper disposition will entail. This is the risk involved in getting highly radioactive wastes (particularly solid wastes, which are approximately 40% of the total inventory proposed for treatment) to the treatment facility: retrieving wastes from storage or burial and transporting them to the facility. It may have been assumed that this part of the process does not require NEPA review because waste is transported routinely on-site at ORNL, but the retrieval of waste containers in various conditions after many years of storage may involve significant hazards. Only 30% of the waste has been characterized, so there is a potential for encountering unexpected hazards in retrieving and transporting it. A particular concern is the exhumation of buried remote-handled wastes in containers of unknown integrity after as much as, or more than, 25 years of interment – this is definitely not routine. Once waste arrives at the treatment facility, there is a possibility that the facility operator (Foster Wheeler) could refuse to accept it for treatment if it does not meet waste acceptance criteria. The possible need to manage wastes that are not accepted for treatment creates an additional set of safety and environmental concerns.

The potential impacts of the proposed waste treatment action cannot be meaningfully evaluated if the evaluation is restricted to the piece of the action that would be undertaken by Foster Wheeler in the proposed waste treatment facility. DOE's EIS must consider the potential impacts of the entire DOE action to manage these wastes, not just that part of the action that would be done at the proposed Foster Wheeler treatment facility. The transfer of waste to the facility is integrally connected to the proposed treatment action, so the final EIS needs to address the potential environmental consequences of this process. Analysis should include (1) routine exposures to workers and the public, (2) the probability and consequences of potential accidents, and (3) safety and environmental consequences associated with management of any wastes that are not accepted by the facility.

2 The EIS fails to effectively communicate the need for this action. The document emphasizes the legal mandates that would not be met in the absence of this action, but it says little about the adverse consequences that might ensue if DOE does not take action. In particular, the analysis of environmental impacts reported in Chapter 4 and elsewhere does not convey the seriousness of the potential impacts of the "no action" alternative, the contrast between the proposed action and "no action," or the potential consequences of "treatment and waste storage at ORNL" (which is what would happen if the WIPP and NTS are unable to receive the treated waste).

There appear to be several reasons that the EIS analysis fails to effectively convey the seriousness of these impacts. One reason is that potential exposures to contaminated water are not

1

COR-4

COR-5

COR-6

COR-7

Response to Comment COR-4

DOE has included discussion and analysis of exhuming, waste handling, and on-site transportation in the Final EIS.

Response to Comment COR-5

With regard to solid waste, Foster Wheeler can refuse waste that does not conform to the waste characteristics in its contract or permits (e.g., its RCRA Permit). Foster Wheeler and DOE are developing WAC that are clear and well-communicated and contingency plans should any waste be rejected. In the event that any waste is rejected, DOE would implement appropriate corrective measures for ensuring waste acceptance and treatment. These measures may include actions required by DOE (external decontamination, repacking, etc.) or if appropriate, modification of the Foster Wheeler contract to accommodate out-of-scope activities.

Response to Comment COR-6

The discussion and analysis associated with exhumation, handling, and on-site transportation of waste have been evaluated and added to Tables S-3, 2-6, and Section 4.8 of the Final EIS. This new analysis includes:

- Routine and accident exposures and consequences to workers and the public are addressed here, as are safety and environmental concerns.
- The probability and consequences of potential accidents.

Contingency plans will be developed to manage any wastes that are not compliant with the facility acceptance criteria.

evaluated for drinking water sources located more than one-half mile from the facility, so impacts to downstream water users are ignored Another reason is that analysis is arbitrarily truncated after 100 years These types of arbitrary limitations on the scope of the analysis do not result in a useful assessment To help decision-makers and the public appreciate the potential adverse impacts of not implementing this proposal or of not being able to ship the wastes offsite, the final EIS needs to fully assess the potential consequences of the no-action alternative and of "treatment and storage at ORNL " This includes assessing potential consequences for a longer period of time (including consequences after the cessation of active maintenance and failure of institutional controls) and assessing the potential population-level consequences to people who live downstream and drink water or eat fish from the Clinch and Tennessee Rivers.

Under the no-action alternative, waste trenches would continue to leak, releasing additional contamination to Melton Valley groundwater and eventually to surface streams that would carry it offsite The EIS notes that strontium-90 would continue to leak into groundwater and White Oak Creek, but it should also acknowledge that the release rates could increase over time and that longer-lived transuranic radionuclides would also reach surface waters (groundwater concentrations of americium-241 and curium-244 reportedly range up to 5,940 pCi/L near the buried wastes) and be carried downstream to offsite populations Although exposures to individual members of the public probably would be negligibly small due to dilution, total population exposures and resulting health effects could be much larger and need to be explored

In both the no-action alternative and "treatment and storage at ORNL" there would be continuing radiation exposures to workers involved in surveillance and maintenance activities The consequences of exposures to workers involved in continued storage need to be explored

It is probably incorrect to say that the no-action alternative would have "no land use impacts" (as stated in Sections 4 1 3 through 4 1 6) While the action alternatives would eventually return the treatment facility site and tanks area to some other land use, under the no-action alternative the current waste storage areas could never be returned to another use

There are undoubtedly other potential consequences from No Action that need to be explored more fully in the final EIS

3 EQAB members expressed concern about the quality of the EIS presentation Reviewers who were not already somewhat familiar with this proposal found that the EIS did not "stand alone" to inform them about the proposal and the need it is intended to address An EIS should be able to stand alone, and it should not rely on technical jargon to communicate concepts Also, members noted many writing errors in the EIS, a few of which are described in our specific comments These flaws need to be corrected in the final EIS

Specific Comments

Page xv, Acronyms and Abbreviations – Acronyms that are used in the EIS but do not appear on this list include LLW (low-level waste), CH (contact-handled), RH (remote-handled), MVST (Melton Valley Storage Tanks), SS (stainless steel), and WIPP (although WIPP SEIS-II is defined)

Page S-2, Section S1 2 1 – The waste types listed here do not include contact-handled (CH) mixed waste, but this waste type is mentioned in section S1 3

2

COR-7

(cont.)

COR-8

COR-9

COR-10

COR-11

COR-12

COR-13

Response to Comment COR-7

Water-related human health information for exposure pathways is addressed in Section 3.10.1. This section has been clarified to indicate that residential wells are across the Clinch River from ORO and are hydrologically separate from the Melton Valley Watershed. DOE evaluated drinking water sources in the EIS at East Tennessee Technology Park (ETTP) and Kingston, Tennessee, under reasonable worst-case accident conditions. The predicted results to human health and biota are discussed in Section 4.11.

Analysis of impacts of the No Action Alternative has been expanded to include impacts after loss of institutional control, assumed to occur, for analysis purposes, after 100 years. Analysis and discussion of impacts associated with ecological resources, surface water, and human health after the loss of institutional control are included in Sections 4.3, 4.5.1, and 4.10, respectively. Impacts after loss of institutional control for the Treatment and Waste Storage at ORNL Alternative are bounded by impacts under the No Action Alternative after the loss of institutional control, because the waste would have been treated.

Response to Comment COR-8

Text in Section 4.5.1.2 has been modified to address the 14,000 curies of activity in the trenches.

Response to Comment COR-9

Sections 4.10.3 and 4.10.7 address the impacts from exposure to the workers for the No Action and Treatment and Waste Storage at ORNL Alternatives, respectively.

Response to Comment COR-10

In Section 4.1.2, the EIS states that No Action would result in no change to the existing land or land-use classification during institutional control. DOE measured land use impacts by physical changes to the land or changes to land use classification. After loss of institutional control the land would be permanently committed to waste storage.

Sections 4.1.3 through 4.1.6 deal with various action alternatives (not No Action) and identify land-use impacts for these alternatives. DOE agrees with the comment that under no action this land would be permanently committed to waste storage.

Response to Comment COR-11

DOE recognizes that the Draft EIS contained errors as noted by the commentor. DOE has conducted a thorough QA/QC review of the FEIS to address these errors.

DOE appreciates the commentor's concern about the ability of the EIS to stand alone. DOE routinely summarizes and incorporates analysis and results from other NEPA documents in accordance with Council on Environmental Quality regulations (40 *CFR* 1502.21), in order to be efficient and reduce paperwork. To provide a more comprehensive evaluation of the impacts of the proposed action, the EIS now incorporates new analysis for on-site waste transportation and long-term effects after loss of institutional control.

Response to Comment COR-12

These acronyms have been added to the acronyms and abbreviations list.

Response to Comment COR-13

Comment noted. It is not known if any of these wastes are mixed wastes. Section S1.3 acknowledges the possibility that some of the contact- and remote-handled solids may contain mixed waste.

Page S-8, Section S1 4 2 – In the title of Alternative 2, "During" should be "Drying "

COR-14

Page S-9, next to last paragraph in Section S1 4 2 – This is one of several discussions of possible contingencies if the WM PEIS record of decision (ROD) on LLW disposal selects a disposal site other than NTS These discussions should be revised to reflect the fact that the ROD has been issued, selecting the NTS as the site for centralized disposal of DOE LLW and mixed waste

COR-15

Page S-9, last paragraph in Section S1 4 2 – Please specify where and how additional RCRA treatment would be done, so that the impacts of this treatment can be evaluated

COR-16

Page S-11, second paragraph – This paragraph says that alpha low-level waste would be compacted for a 50% volume reduction The significance of this percentage figure is unclear Is this the minimum volume reduction, maximum volume reduction, or simply the volume reduction efficiency that was assumed for the purpose of analysis?

COR-17

Page S-12, last paragraph – The total project duration is stated to be 11.5 years, with a treatment time of 5 years Is there any provision to allow acceleration of the project to coordinate with WIPP schedules or if containers are found to be more deteriorated than expected?

COR-18

Page S-13, last paragraph, page 4-56, first line – Here and elsewhere, it is stated that the facility would have an off-gas system, including HEPA filters, that would remove "over 99%" of the off-gas particulates This suggests that the proposed facility and alternatives would be equipped with standard HEPA filters, rather than state-of-the-art extreme HEPA filters with greater design efficiency The EIS should evaluate the potential benefits and impacts (such as increased cost and energy use) of improving filtration efficiency by using state-of-the-art HEPA filters (such as EHEPA filters) to further reduce releases of radionuclides.

COR-19

Page S-28, Table S-3 - In the Climate and Air Quality row, it is probably accurate to say that "minor emissions" are predicted for all treatment alternatives, but the emissions are not the "same" for all alternatives. Please describe how air emissions differ between the different alternatives

COR-20

Page S-29, Table S-3 - Under "Human Health, the no action alternative is described as "risk to public to be negligible " The word "negligible" begs definition – risks may be very small during the several-year period that it would take to treat the wastes, but risks from no action would be much higher over the long term

COR-21

Page S-31, Table S-3 - These shorthand descriptions of accident scenarios and their impacts are very difficult to follow

COR-22

Page 2-11, first paragraph in Section 2 4 2 1 - Please indicate whether the double-contained above-ground pipeline would be equipped with sensors to detect leakage

COR-23

3

Response to Comment COR-14

This correction has been made in Section S1.4.2.

Response to Comment COR-15

Text in Section S1.4.2 has been modified to reflect the fact that the ROD has been issued.

Response to Comment COR-16

Macroencapsulation of RCRA wastes would be performed at the proposed TRU Waste Treatment Facility. (Figure S-6 and Section S1.4.2.2 describe RCRA treatment.)

Response to Comment COR-17

The 50% volume reduction figure is a performance requirement as stipulated in Foster Wheeler's contingent contract with DOE and was used for purposes of analysis in the EIS.

Response to Comment COR-18

There is some capacity to accelerate or at least shorten the project, particularly the length of operation. The project's start of waste processing in late 2002 is designed to coincide with WIPP's projected capacity to begin to accept remote-handled waste from Oak Ridge. Therefore, we do not expect to accelerate the start date at this time.

Response to Comment COR-19

Use of extreme high-efficiency particulate air filters (a term used by the commentor which DOE interprets to mean a HEPA filter with higher collection efficiency than a standard HEPA filter) and other technology improvements is not precluded. For purposes of the impacts analysis (Section 4.7), standard HEPA filters are assumed because this approach results in a conservative, bounding analysis.

Response to Comment COR-20

In the Climate and Air Quality section (Section 4.7), "minor emissions" are predicted for all treatment alternatives, even though the emissions would not be the same. With the appropriate air pollution control equipment, including the sequential HEPA filters, it is likely that emissions would be similar. Although the differences in emissions are small, the volatile organic emissions would probably be slightly higher for the Low-Temperature Drying Alternative than either the Cementation or Vitrification Alternative because drying would release the organics by volatilization. Particulate emissions would probably be highest with the Cementation Alternative since cement is high in particulates. Nitrogen oxide emissions would probably be highest with the Vitrification Alternative because the high temperature of vitrification would tend to produce more nitrogen oxide.

Response to Comment COR-21

Human health risks for the No Action Alternative under the period of institutional control conditions are small. The risks to the public and non-involved worker would be negligible under the No Action Alternative because if the waste is not treated, there will be no emissions, and, therefore, there would be minimal risk to everyone but involved workers (2E-02 LCFs). Since the waste will be inspected and monitored on a routine basis, the risk of contamination or leakage is small. Under accident conditions (Section 4.11), however, the risks to human health are estimated to be much higher (11 LCFs).

Analysis and discussion has been added to address human health impacts after the loss of institutional control (Sections 4.5 and 4.10). The risk to the public from the No Action Alternative would be significant over the long term (Section 4.10.3).

Response to Comment COR-22

A detailed discussion of these scenarios is presented in Section 4.11. Tables 4-28, 4-29, 4-30, and 4-31 provide detailed information on the accident scenarios. In addition, a text box has been added to Tables S-3 and 2-6 to improve clarity.

Response to Comment COR-23
The pipe would be equipped with sensors to detect a loss of containment.

Page 2-16, second bullet in list of bullets near bottom of page – Not many readers are likely to understand what is meant by "cold cap" in the statement "a cold cap would be maintained on the molten glass " Technical concepts should be explained in plain English wherever possible

COR-24

Page 3-45, Table 3-13 – Because some of the ambient air quality data in this table are from nonlocal sites that are near sources of criteria air pollutants, Oak Ridge air quality is probably better than the table suggests For nitrogen dioxide, please replace or supplement the measurement from A.E. Staley's Loudon plant with values measured in Oak Ridge The EPA AIRS database gives an annual average NO_2 value of 0.006 ppm for a station at 1500 Bear Creek Road in Oak Ridge (report obtained from http://www.epa.gov/airsdata/monvals.htm , showing data extracted on January 28, 2000) When no data are available for locations near site, please say so and tell us whether the data that are reported are considered to be representative of the Melton Valley site Please point out that the "Roane County" lead measurements in the table are from Rockwood. The Rockwood lead data are probably particularly unrepresentative of Oak Ridge, because the measurements were made near an important emitter of airborne lead Similarly, the carbon monoxide data from Knox County come from a city street in downtown Knoxville and do not represent conditions in Oak Ridge. The lower carbon monoxide values measured at A.E Staley in Loudon and included in the AIRS database are probably more similar to conditions in Oak Ridge

COR-25

Page 3-73, last item on page The first author of this report is named "Dreier," not "Drier " This also needs to be corrected in the text where the reference is called out.

COR-26

Page 4-18, Section 4.5.2.7 – The first sentence does not make sense and should be revised It is not evident that impacts to groundwater quality can be avoided by not pumping groundwater

COR-27

Pages 4-54 to 4-60, Section 4.10 – This section contains extensive information on the potential human health impacts of the three alternative treatment technologies, but it provides very little comparative information about the impacts of the no-action alternative, and it says very little about the additional long-term impacts from storing treated wastes if they cannot be shipped off-site for disposal The FEIS should provide comparable information on all alternatives For example, for the no-action alternative and long-term storage of treated wastes, estimate the collective dose to the worker and offsite populations from surveillance and maintenance and from exposure to contaminants released from stored wastes. For the no-action alternative, provide estimates for the duration of the treatment process and for longer time periods such as 100 years and 1000 years. (For long-term storage, only the longer-term estimates are appropriate) It would also be informative to provide comparative estimates of exposures and health effects to residents who move onto the site near the waste storage area.

COR-28

Page 4-56, Section 4 10.3 – This section gives a quantitative estimate of latent cancer fatalities (LCFs) resulting from involved-worker exposure under the no-action alternative, but there is no indication of where the estimate comes from How many workers would be involved? What are their estimated doses? Where are these values derived or discussed?

COR-29

4

Response to Comment COR-24

Text in Section 2.5.2 has been clarified to define cold caps.

Response to Comment COR-25

These background data are TDEC data and were also used as representative of the ORR in the recently issued *Final Environmental Impact Statement, Construction and Operation of the Spallation Neutron Source Facility*, DOE/EIS-0247 (DOE 1999c). Table 3-13 has been modified to acknowledge that lead data were taken from Kingston, Tennessee, and carbon monoxide data were taken from Knoxville.

Response to Comment COR-26

Corrections have been made.

Response to Comment COR-27

Text has been modified in Section 4.5.2.7 to indicate no groundwater is being pumped under any of the alternatives and there are no releases to groundwater; therefore, no negative impact to groundwater quantity or quality would be expected. The removal of the TRU waste from the trenches would have a beneficial impact on groundwater quality.

Response to Comment COR-28

No Action Alternative—The dose and corresponding risk to the involved worker population under normal operating conditions during the institutional control period were estimated to be 50 person-rem over the 100-year period and 2E-02 LCF. There would be minimal risk to the non-involved worker and the off-site population since there will be no emissions and the waste will be routinely inspected and monitored.

For the No Action Alternative, there is no "duration of the treatment process" since wastes are not treated. Impacts are presented for a 100-year institutional control period, and new impacts analyses are presented in Chapter 4 for a period after loss of institutional controls (approximately 10,000 years). In Sections 4.5.1.2, 4.5.2.2 and 4.10.3, the Final EIS provides a qualitative discussion of potential health effects to persons affected by long-term releases. Impacts could be significant if wastes are not treated.

Treatment and Waste Storage at ORNL Alternative—The total risk would depend on the treatment process used, but impacts would be less than the No Action Alternative in which wastes are left untreated. DOE intends to ship the waste offsite as soon as practical after waste treatment. However, this EIS analyzes long-term storage impacts for the No Action Alternative after the loss of institutional controls. The impacts from No Action are expected to bound the impacts of the Treatment and Waste Storage at ORNL Alternative because the wastes would be treated and better contained.

Response to Comment COR-29

The LCF to the involved worker was calculated by assuming that 5 workers each receive the 100-mrem annual administrative control limit every year for 100 years, multiplied by 4E-04 LCF/rem. Five workers is approximately the number currently involved in maintenance and surveillance activities at Solid Waste Storage Area 5 North (SWSA 5 North) and the MVST area. Text in Section 4.10.3 has been modified to better explain how these calculations were derived.

3.2.3 Oak Ridge Reservation Local Oversight Committee

LOC INC
Oak Ridge Reservation
Local Oversight Committee

April 14, 2000

Dr Clayton Gist
Waste Management Integration Team Leader
U. S. Department of Energy
P O Box 2001
Oak Ridge, TN 37831

Subject Draft Environmental Impact Statement (DEIS) for Treating Transuranic (TRU)/Alpha Low-level Waste at the Oak Ridge National Laboratory in Oak Ridge, Tennessee (DOE/EIS-0303-D)

Dear Dr. Gist:

The Citizens' Advisory Panel (CAP) of the Local Oversight Committee (LOC) has carefully reviewed the subject Draft EIS. The CAP supports the preferred alternative of Low Temperature Drying.

We have a number of concerns about the quality of the DEIS and how well it documents DOE's decision. Attached are our comments, which should lead to a more mature Final EIS should DOE choose to incorporate the suggestions Because there has been intensive stakeholder evaluation of the DEIS, the CAP is submitting only our general comments. The CAP fully endorses the specific comments submitted by the City of Oak Ridge Environmental Quality Advisory Board as transmitted by the Oak Ridge City Council.

The LOC is a non-profit regional organization funded by the State of Tennessee and established to provide local government and citizen input into the environmental management and operation of the DOE Oak Ridge Reservation. The Board of Directors of the LOC is composed of elected and appointed officials from the City of Oak Ridge and the seven counties surrounding and downstream of the ORR, and the chair of the CAP The CAP has up to 20 members with diverse backgrounds who represent the greater ORR region and who study and make recommendations on DOE Environmental Management technical and policy issues.

Sincerely,

Norman A. Mulvenon
Chair, LOC Citizens' Advisory Panel

cc: LOC Document Registry
LOC CAP
LOC Board
Leah Dever, Manager, DOE ORO
Steve Kopp, Chair, ORSSAB
Earl Leming, Director, TDEC DOE-O
Joe Sanders, General Counsel, TDEC
Camilla Warren, DOE Section Chief, Federal Facilities Branch, USEPA Region 4
Carol Borgstrom, Director, NEPA Oversight, DOE HQ

ENVIRONMENTAL MANAGEMENT DIVISION FILE COPY RECEIVED
1210

1c1346

'00 APR 21 P2:25

Anderson • Meigs • Rhea • Roane • City of Oak Ridge • Knox • Loudon • Morgan

136 S Illinois Avenue, Suite 208 • Oak Ridge, Tennessee 37830 • Phone (423) 483-1333 • Fax (423) 482-6572 • E mail loc@icx net

LOC-1

Response to Comment LOC-1

Specific comments are addressed in detail below.

LOCAL OVERSIGHT COMMITTEE CITIZENS' ADVISORY PANEL
COMMENTS ON THE DRAFT
ENVIRONMENTAL IMPACT STATEMENT (DEIS)
FOR TREATING
TRANSURANIC (TRU)/ALPHA LOW-LEVEL WASTE
AT THE OAK RIDGE NATIONAL LABORATORY
OAK RIDGE, TENNESSEE

General Comments

1 The document has an unusually large number of errors and inaccuracies. It does not measure up to the editorial standard that the public has come to expect from DOE's Environmental Management program. The quality of the document needs to be improved by adding clarity without excessive technical jargon and making the necessary corrections of errors and inaccuracies, many of which are the same ones the CAP has commented on in past NEPA documents.

2 There is a substantial lack of information on the transportation of all waste currently in storage to the treatment facility. Of special concern is the waste from the trenches of SWASA 5 North. The analysis seems to start when the waste is "delivered by DOE" to the TRU Waste Treatment Facility This waste is in a variety of containers from concrete casks through metal barrels to wooden boxes. The variable integrity of these containers after many years of interment presents possible unexpected hazards during retrieval and transportation. The final EIS should adequately address potential hazards of the entire DOE action, not just the treatment facility portion. Further analysis should include exposures to workers as well as the public, potential accidents, and the management of wastes not accepted by the Foster Wheeler treatment facility because of failure to meet the waste acceptance criteria.

3. DOE has not presented a compelling rationale for the need to take any action with regards to the TRU wastes, although those who have followed the process are aware of the importance of the TRU Waste Treatment Facility with respect to DOE's plans for cleanup of the reservation. However, to otherwise uninformed stakeholders, the "no action" alternative does not appear unreasonable. This alternative should be evaluated with considerably more attention to detail, including the negative consequences of the failure to treat and dispose of Oak Ridge Reservation's TRU waste.

4. In general, the DEIS does not include enough detail to support the preferred alternative nor to appropriately evaluate the environmental and health impacts of the alternatives. The document needs to explain the outside circumstances that might drive DOE to a particular decision—including the Melton Valley Record of Decision, waste acceptance criteria at the Waste Isolation Pilot Project (WIPP), and if disposal options at WIPP become otherwise restricted. The scope of the DEIS seems unreasonably limited by assumptions such as restricting analysis of groundwater impacts to downstream water users only (White Oak Creek and the Clinch River are waters of the state and must meet standards appropriate to their potential uses) and limiting the analysis period to only 100 years. The EIS must clearly evaluate all of the alternatives with respect to a longer period of time appropriate for the radionuclides in question, and properly assess potential impacts on people who live downstream with access to the water and fish. In addition, the list of potential consequences seems incomplete: other impacts should be evaluated in the final EIS.

1 of 1

LOC-2

LOC-3

LOC-4

LOC-5

LOC-6

Response to Comment LOC-2

Errors and inaccuracies have been corrected in the Final EIS. A thorough QA/QC review has been conducted of the Final EIS (technical and nontechnical) to address these concerns.

Response to Comment LOC-3

DOE has revised the EIS (Section 4.8) to include the impacts from the exhumation, handling, and on-site transportation of wastes. Available information on the inventory of the SWSA 5 North area (casks in trenches, casks in bunkers, and B-25 boxes and drums in the metal buildings) would be transported to the proposed treatment facility. For the 23 trenches at SWSA 5 North, only casks would be retrieved.

Response to Comment LOC-4

DOE has clearly indicated that the No Action Alternative is not compliant with the TDEC Commissioner's Order regarding waste removal. Further, the EIS documents the adverse environmental impacts, especially the severe consequences associated with an accidental release of wastes from the MVSTs. The continuing releases of radionuclides from SWSA 5 North and impacts from those releases are discussed in Chapter 4. As described in Chapter 4, DOE has analyzed the impacts that would occur if institutional control ended, which is assumed for purposes of analysis to be after 100 years.

Response to Comment LOC-5

Impacts of the various alternatives are analyzed in Chapter 4. DOE has added additional analyses in Chapter 4 to address longer impacts after loss of institutional control under on the No Action Alternative and the Treatment and Waste Storage at ORNL Alternative, and on on-site waste retrieval and transport. In addition to health risks and other impacts discussed in Chapter 4, DOE has a legal driver (the Tennessee Department of Environment and Conservation Commissioner's Order to ship waste—see Sections S1.4.2.1, 1.3, 4.6.2, and 8.3). Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) documentation has also indicated the need to address waste in Melton Valley (see Sections S1.3 and 1.3). Regarding the WIPP site, DOE has determined that this site is the disposal location for TRU waste.

The commentor was also concerned that DOE did not have sufficient information to support the preferred alternative. The designation of the Low-Temperature Drying Alternative as the preferred alternative was based on both the results of the procurement process for treatment of TRU waste and the impacts analysis presented in the Draft EIS. During the procurement process, DOE obtained proposals from qualified bidders on several treatment processes. DOE selected the low-temperature drying proposal during the procurement process as the preferred technology based on a combination of environmental and cost considerations. The analysis in the Draft EIS showed that low-temperature drying would have lower waste volumes, less utility usage, fewer transportation shipments, and lower associated transportation risks than other action alternatives.

Response to Comment LOC-6

Impacts of the alternatives are presented and compared in Chapter 4. DOE has added to the EIS an analysis of impacts after loss of institutional control, assumed for this analysis to be 100 years. Impacts to biota, surface water, groundwater, and human populations are addressed in Sections 4.3, 4.5.1, 4.5.2, and 4.10 of Chapter 4.

Downstream water users are identified at both the ETTP and in Kingston, Tennessee, and the human health consequences of accidental waste releases are evaluated in Section 4.11. DOE has added on-site transportation analysis and impacts associated with loss of institutional control. The EIS addresses all impacts expected from implementation of the No Action and all action alternatives.

3.2.4 State of Tennessee Department of Environment and Conservation

STATE OF TENNESSEE
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DOE OVERSIGHT DIVISION
761 EMORY VALLEY ROAD
OAK RIDGE, TENNESSEE 37830-7072

April 12, 2000

Dr. Clayton Gist, Waste Management Integration Team Leader
US Department of Energy
Oak Ridge Operations
PO Box 2001, EM-921
Oak Ridge TN 37831

Dear Dr. Gist

Document NEPA Review: Draft Environmental Impact Statement (EIS) for Treating Transuranic (TRU)/Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, Tennessee.

The Tennessee Department of Environment and Conservation, DOE Oversight Division (TDEC/DOE-O) has reviewed the subject document in accordance with the requirements of the National Environmental Policy Act (NEPA) and associated regulations of 40 CFR 1500-1508 and 10 CFR 1021 as implemented.

General Comments

In consideration of the treatment alternatives, TDEC supports the preferred alternative of the low-temperature drying method for the treatment of the Melton Valley Storage Tanks wastes (sludge and supernate) and segregation and compaction for the solid wastes (contact-handled and remote-handled TRU/alpha low-level heterogeneous debris). This alternative is presented as the most economical with respect to the resources needed for transportation and disposal, as well as the minimum impact to the environment.

It should be noted that the No Action Alternative is not a viable option due to a TDEC Commissioner's order requiring the initiation of shipments of the RH-TRU wastes to WIPP by January 2003.

Specific Comments

Page S-12, Section S1.4.2.2, Low-Temperature Drying Alternative
The text does not explain where the total amount of waste volume would come from. The conversions from square meters to square feet are not consistent, and the figures do not match the information on the chart on page S-18.

'00 APR 20 -7:56

TDEC-1

TDEC-2

TDEC-3

Response to Comment TDEC-1

Comment noted.

Response to Comment TDEC-2

The Final EIS acknowledges that the No Action Alternative (as well as the Treatment and Waste Storage at ORNL Alternative) is not compliant with the TDEC Commissioner's Order (Sections S1.4.2.1, 4.6.2, and 8.3). It should be noted that the Treatment and Waste Storage at ORNL Alternative would not be compliant either.

Response to Comment TDEC-3

Text has been added to Section S1.4.2.2 to indicate that the total volume of waste is the sum of primary, secondary, and D&D waste. Waste volume conversion errors have been corrected. Typically DOE used English units, converted to metric units, and rounded up. Table S-1 identifies the new storage space required for TRU and low-level waste only, since other wastes would not require special storage. Therefore, all waste volumes described for each treatment alternative are not provided in Table S-1, only those for TRU waste

and low-level waste. See Table 2-1 for a listing of all waste streams.

Page 1-10, Section 1.7, References,Third Reference
The sentence that has "tot he" should be changed to read "to the."

TDEC-4

Page 2-7, Section 2.4.1, Facility Description
The sentence *"The proposed site would encompass 2 ha (5 acres), the approximately 4 ha (10 acres) that would be included in the lease."* The sentence should state *"The proposed site would encompass 2 ha (5 acres) of the approximately 4 ha (10 acres) that would be included in the lease."*

TDEC-5

Page 3-14, Figure 3-5
The geologic map in figure 3-5 shows a formation called the Maryville Limestone. The Stratigraphic column Figure 3-4 page 3-13 calls the formation the Dismal Gap Formation (formerly the Maryville Limestone). The text on page 3-34 mentions the Maryville Limestone and throughout the geology and groundwater sections there is no mention of the Dismal Gap Formation. The formation nomenclature should be consistent.

TDEC-6

Page 3-20, Figure 3-7
"Rough Creek Grabem" should read "Rough Creek Graben."

TDEC-7

Page 3-21, Paragraph 2, Line 7
The document describes the Oak Ridge Reservation as a location with a moderate risk for seismic damage. Do the construction/design plans include taking into account earthquake construction standards?

TDEC-8

Page 3-23, Section 3.5.1, Surface Water, First Paragraph
It is the State's understanding that the stream in question, a "wet weather tributary" has been determined to be Waters of the State. Please reflect this in the next version.

TDEC-9

Page 3-30, Table 3-10, Locations, Frequency
Change Mitchell Branch to Melton Branch.

TDEC-10

Page 3-33, Figure 3-13
TDEC DOE-O has in the past disputed the 90% groundwater flux in the stormflow zone for areas outside Melton Valley. The testing to arrive at the 90% number was conducted in the Nolichucky Shale in Melton Valley. However the percentage of water entering the bedrock is greater than 10% for those formations other than the Nolichucky Shale.

TDEC-11

Page 3-51, Section 3.10.1, Exposure Pathways, Third Paragraph
Some residents in close proximity to ORNL and the Melton Valley facility do receive their potable supplies from groundwater. DOE has in the recent past conducted sampling of some of the residential wells in this area. DOE-O continues to sample residential wells in this area. This should be reflected in the text.

TDEC-12

Response to Comment TDEC-4

This typographical error has been corrected.

Response to Comment TDEC-5

Text in Section 2.4.1 has been modified as suggested.

Response to Comment TDEC-6

Both Figure 3-5 and text in Sections 3.4.1 and 3.5.2.1 have been changed to be consistent.

Response to Comment TDEC-7

Figure 3-7 has been corrected.

Response to Comment TDEC-8

Earthquake construction standards will be taken into account during the design and construction of the facility.

Response to Comment TDEC-9

Text in Section 3.5.1 has been modified to identify all surface waters in the area of the proposed facility as "Waters of the State."

Response to Comment TDEC-10

Table 3-10 has been corrected.

Response to Comment TDEC-11

While the comment is correct, no changes were made to the document. It is important to note that the proposed TRU Waste Treatment Facility site is located over the Nolichucky Shale of the Conasauga Group. The purpose of Table 3-13 is to outline a conceptual model of flow and not for quantification of actual flux.

Response to Comment TDEC-12

There are no groundwater wells on the ORR that are used for drinking water purposes. Text in Section 3.10.1 has been modified to indicate that residential wells are offsite the ORR. The residential wells mentioned in the comment are across the Clinch River and are hydrogeologically separated from the Melton Valley Watershed.

Page 4-6, Section 4.3.3, Low - Temperature Drying Alternative, Second Paragraph
This sentence states "There are no aquatic biota..."
This is a very broad statement. Due to the presence of a flowing stream, it seems likely there are at least a few taxa of organisms present (insects, micro-organisms, etc.), even though they may not be listed as Threatened and Endangered. | TDEC-13

Page 4-13, Section 4.5.13, Low-Temperature Drying Alternative
The document states that sanitary wastewater would be contained and transported offsite by vendors for treatment/disposal. Please provide information on storage, treatment, disposal and transportation, and other pertinent information on the facility with respect to this phase of the operation. | TDEC-14

Page 4-51, Section 4.9.3, Low-Temperature Drying Alternative
Impacts resulting from the proposed power line placement are not discussed, and no proposed route is presented. | TDEC-15

Page 4-55, Section 4.10, Human Health Impacts
This section should be modified with Tritium added as a component of the stack emissions. | TDEC-16

Page 4 - 61, Section 4.11, Accident Impacts
The nature of the supernates and sludges are not completely known. There is no discussion of the criticality controls that will be deployed as the wastes are treated and/or stored. In addition, it is recommended that this section be expanded to include an evaluation of possible releases due to the potential failure of the condenser/ventilation/air emission control system. | TDEC-17

Page 5-2, Table 5-1, Past, Present and Reasonably Future Actions with Potential for Cumulative Impacts
The road construction is completed, and the Cumulative Impacts should be changed accordingly. | TDEC-18

Page 5-5, Section 5.3 Water Resources
There is no analysis as to how the waste at SWSA 6 will impact White Oak Lake with respect to the facility. SWSA 6 should be addressed as to its possible impact to White Oak Lake. Wags 4, 5, and 13 are mentioned without the presence of SWSA 6/Wag 6 being acknowledged. | TDEC-19

Cumulative impacts to Water Resources are not well defined. The section indicates that impacts will occur, but presents no explanation or measures to mitigate the impacts. | TDEC-20

Page 5-7, Section 5.3.2, Old Melton Valley Access Road Upgrade
The road upgrade has been completed, and additional sediment/erosion control measures are being planned. | TDEC-21

Page 6-1, Chapter 6, Mitigating Measures
TDEC recommends adding references concerning the roles of Federal, State, and other regulatory agencies in the formation/approval of mitigating measures. | TDEC-22

Response to Comment TDEC-13

Text in Section 4.4 has been clarified to indicate that few aquatic biota are actually present onsite due to very little permanent aquatic habitat.

Response to Comment TDEC-14

Treatment and disposal of the liquid waste are described in Section 4.5.1.3.

Response to Comment TDEC-15

Figure 4-2 shows the location of the electric feeder pole and the proposed facility location. Routine emplacement of poles and overhead cable along the existing patrol road right-of-way would be required; however, only very minor impacts are expected. The text has been modified in Section 4.9.3.

Response to Comment TDEC-16

Tritium was included in the stack emissions. (See Appendix B.)

Response to Comment TDEC-17

While there is some uncertainty regarding full characterization of the supernate and sludges, analytical data and process knowledge indicate that no enriched materials are part of the tank waste. In addition, administrative and process controls (such as nondestructive assays) would be followed that avoid establishing a process scenario that would present a criticality concern.

With regard to the potential failure of the condenser/ventilation/air emissions filter system, the failure of the ventilation/air emissions system is addressed by the slurry line accident with HEPA filter failure in Section 4.11.5.

Response to Comment TDEC-18

The referenced table in Chapter 5 has been modified as suggested.

Response to Comment TDEC-19

DOE agrees that the impacts from SWSA 6 should be discussed as part of cumulative impacts. A new Section 5.3.6 has been added to identify major inputs (radionuclides) from Waste Area Group (WAG) 6 at SWSA 6.

Response to Comment TDEC-20

Sections 5.3.1 and 5.3.7 state that the cumulative impacts from the White Oak Creek Embayment Project mostly provide beneficial impacts by reducing contaminant and radionuclide loading to White Oak Creek and White Oak Lake. Some reductions are quantified and best management practices are expected to be used (Section 5.3.7) to mitigate impacts. Mitigating measures are addressed in Chapter 6.

Response to Comment TDEC-21

The text in Section 5.3.2 has been modified.

Response to Comment TDEC-22

Section 8.3 has been modified to address the State of Tennessee's role in resource management, including the approval of mitigation measures (for example wetlands mitigation). The U.S. Fish and Wildlife Service's role is also included in Section 8.1.

Page 8-1, Chapter 8, Federal and State Environmental Statutes and Regulations
This section omitted the Endangered Species Act that is pertinent to this document.

Page 8-4, Section 8-3, Regulatory Comparisons Between Alternatives
TDEC responsibility pertaining to resource management. Aquatic Resources Alteration Permits issuance/approval, and other resource management responsibilities should be referenced.

Page 10-1, DOE-Oak Ridge Distribution
The list of Preparers is on page 9-1.


Page 7, Appendix A.2, Section 4.4, Floodplain and Wetlands
This section erroneously states that there are no wetlands in the area. Elsewhere, for example in the Affected Environment Section, the document references several wetlands, one of which will probably require mitigation.

Page 7, Appendix A.1, Section 4.6, Water and Water Quality
The section infers that effluent would exceed the State ambient water quality criteria of 12 parts per trillion applicable to White Oak Creek for Mercury. However, no conclusions or recommendations for mitigation and the aspect of potential violation were discussed.

Page E-11, Appendix E
The letter from the United States Fish and Wildlife Service recommends that a Biological Assessment be performed, and forwarded to their office. The EIS does not state that the assessment was performed, or indicated the results of the assessment.

If you have any questions concerning these comments, please contact me at (865) 481-0995

Sincerely



Earl C Leming
Director

xc: Dodd Galbreath - TDEC
Mike Apple - TDEC
Rodney Nelson - DOE
Steven Alexander - FWS
Jim Elmore - DOE/NEPA

Ec1522.99

TDEC-23

TDEC-24

TDEC-25

TDEC-26

TDEC-27

TDEC-28

Response to Comment TDEC-23

A description of the Endangered Species Act has been added to Section 8.1 of the Final EIS.

Response to Comment TDEC-24

Text has been added to Section 8.3 of the Final EIS to address the State of Tennessee's role in resource management, including Aquatic Resources Alteration Permits.

Response to Comment TDEC-25

The comment refers to an error in the Table Contents, which has been corrected.

Response to Comment TDEC-26

The commentor is referring to a report entitled the *Environmental Synopsis for the Transuranic Waste Treatment Project at the Oak Ridge Reservation* (January 1999) in the Appendix (A.2). The synopsis compared environmental information provided to DOE through the procurement process and did not include detailed information developed as a result of the preparation of the EIS.

During the development of the EIS for this project, DOE identified two small wetlands within the area to be used for the proposed TRU Waste Treatment Facility. One wetland would be impacted by the proposed action; the other would not. These wetlands, along with others in the vicinity, are documented in the EIS. DOE is coordinating with TDEC on wetland mitigation. Information on potential mitigation measures is included in Chapter 6.

Response to Comment TDEC-27

The synopsis included as Appendix A.2 refers to proposals by two offerors to DOE to treat the waste discussed in this EIS. Offeror #1's proposal cited an exceedance of the 12 parts per trillion water quality criterion. Offeror #1's proposal was not

accepted by DOE; Foster Wheeler's proposal was accepted and evaluated as the preferred alternative. Offeror #2 (Foster Wheeler) proposed to have no liquid effluent discharge.

Response to Comment TDEC-28

A draft BA has been prepared (Appendix E) and will be submitted to the U.S. Fish and Wildlife Service. DOE is continuing the informal consultation process with U.S. Fish and Wildlife Service.

3.2.5 U.S. Department of Interior

United States Department of the Interior

OFFICE OF THE SECRETARY
OFFICE OF ENVIRONMENTAL POLICY AND COMPLIANCE
Richard B. Russell Federal Building
75 Spring Street, S.W.
Atlanta, Georgia 30303

April 11, 2000

ER-00/171

Dr. Clayton Gist
U. S Department of Energy
Oak Ridge Operations
P. O Box 2001
Oak Ridge, TN 37831

Dear Dr. Gist:

The Department of the Interior has reviewed the Draft EIS for Treating Transuranic (TRU) Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, TN, as requested.

General Comments

The DEIS describes the action alternatives being considered, all of which involve treatment of the wastes, followed by (1) shipment to an appropriate disposal facility, or (2) storage at the Oak Ridge National Laboratory. However, the water-related impacts of all four action alternatives are equivalent. Therefore, the specific rationale for selecting the preferred alternative should be clearly stated as justification for the waste treatment method ultimately selected in this proposed project

USDOI-1

Seismic hazards are also inadequately discussed in the Draft EIS Current methodology used to evaluate the seismic hazards, and the East Tennessee seismic zone, which is important to the Oak Ridge site, should be discussed in more detail.

USDOI-2

The U S Fish and Wildlife Service (FWS) reviewed the scoping document for this DEIS and provided comments to the U S. Department of Energy on July 8, 1999 The FWS suggested that qualified biologists assess potential impacts to the Federally endangered gray bat (*Myotis grisescens*) and pink mucket pearly mussel (*Lampsilis abrupta*) The sensitive plant and animal surveys conducted in April and May, 1999, for this project did not include mistnetting efforts for bats potentially present at or near the site or an evaluation of potential impacts to the pink mucket pearly mussel.

USDOI-3

On July 14, 1999, a site visit of the project area was conducted by FWS personnel. Significant clearing and grubbing activities had occurred for the construction of an access road from State Route 95 to the proposed TRU facility The DEIS did not discuss in detail the access road construction or potential impacts to sensitive species This construction activity was granted a categorical exclusion

USDOI-4

'00 APR 17 P2:10

[illegible]
[illegible] 60319

Response to Comment USDOI-1

The water-related impacts from all the treatment alternatives are minimal. Water-related impacts, which are discussed in Section 4.5 of the EIS, were not a discriminating factor for selection of the preferred alternative. DOE evaluated and compared the impacts of each alternative (Chapter 4 and Tables S-3 and 2-6).

DOE obtained proposals from qualified bidders on several treatment processes. Low-temperature drying was initially selected by DOE as the preferred alternative based on a combination of environmental and cost considerations. The analysis in this EIS showed low-temperature drying has lower waste volumes, less utility usage, fewer transportation shipments, and lower associated risks than the other action alternatives.

Response to Comment USDOI-2

Additional information on seismic hazard is provided in Section 3.4.

Response to Comment USDOI-3

Qualified biologists did a site walkover in the fall of 1998. No habitat for the gray bat was identified, and this information is included in the EIS. Additional information on the pink mucket pearly mussel is also added in Section 4.3. Because no suitable habitat for either species was found, DOE determined that no adverse impacts were likely.

Additional field studies for wetlands, terrestrial animals, and rare plants were conducted in May 1999. DOE is continuing informal consultation with the U.S. Fish and Wildlife Service, including addressing the question of mist netting.

Response to Comment USDOI-4

A draft BA has been prepared (Appendix E) under provisions of the Endangered Species Act and has been submitted to the U.S. Fish and Wildlife Service. The draft BA discusses sensitive plant and animal surveys that were conducted within the Melton Valley Watershed prior to construction of the access road. The draft BA also discusses any information related to the presence of the Indiana bat and gray bat and potential habitat for either species in the project area and surrounding areas. Informal consultation between DOE and the U.S. Fish and Wildlife Service will continue with regard to what further action, if any, should be taken near the project area.

DOE has provided information to the U.S. Fish and Wildlife Service on threatened and endangered species surveys conducted over the past several years (1992 and 1997). Mist netting results for bats on Lower East Fork Poplar Creek were provided. Approximately seven caves on the ORR were surveyed for bats in 1996, with negative results for protected species. There are no caves within the area to be leased for the TRU Waste Treatment Facility, although two caves are within 1.5 miles. DOE reported a single dead gray bat found at the Y-12 Plant in 1994.

A copy of the categorical exclusion for the Old Melton Valley Road Upgrade is included in Appendix G. The rare plant survey conducted as part of that categorical exclusion is included in Appendix G. The road was relocated to minimize impacts to rare plant species. (See also response to comment ORSSAB-2.)

pursuant to the National Environmental Policy Act (CX-TRU-98-007, Categorical Exclusion for Construction/Relocation of Access Road at Oak Ridge National Laboratory)(DOE-ORO 1998)

While the FWS did not provide the Federally endangered Indiana bat (*Myotis sodalis*) as a potential species in comments to the scoping document, recent collection records in East Tennessee suggest suitable habitat exists on the Oak Ridge Reservation. It was noted during the site inspection that both Class 1 and Class 2 tree species of suitable sizes to support primary and secondary maternity roosting habitat for the Indiana bat existed adjacent to the road construction corridor. This road construction may have constituted an irreversible and irretrievable commitment of resources which does not appear to have been properly and thoroughly evaluated The Final EIS should include a discussion of sensitive plant and animal surveys conducted within the Melton Valley watershed prior to construction of the access road. Also, we would also encourage the DOE to conduct thorough mistnetting surveys for bats within the project corridor and White Oak Creek, the unnamed tributary to White Oak Creek, Melton Branch, and White Oak Lake near the proposed facility. While the gray bat may not be a permanent resident in the Melton Valley watershed as stated in the DEIS, it may forage over these waterbodies and could occur within the impact area of the proposed project

The DOE should make a determination of effect and coordinate the findings with the FWS's Cookeville, Tennessee, office for review and concurrence. The FWS contact in Cookeville, TN is contact Steve Alexander at 931/528-6481 (ext 210) or via e-mail at steven_alexander@fws gov

Specific Comments

Page S-7, Section S1.4.1, 2nd paragraph - Upon decontamination and decommissioning of the treatment facility, ownership and care of the facility and the leased land will revert to the Department of Energy (DOE). Noting the long half-lives of many radio nuclides, the DOE plans for monitoring and/or remediating any related environmental problems over the long term, i.e the half-life of the longest lived radio nuclide, should be identified. Additionally, the Draft EIS does not identify any mitigation technology if a chemical/radioactive waste spill were to occur

Page S-8, Section S1.4.2, Alternatives - Alternative number 2 should be labeled "Low-Temperature Drying" instead of "Low-Temperature During."

Page 2-9, Figure 2-3 - This figure must be a reduced version of a larger figure It is an important figure, but almost impossible to read. A new readable figure needs to be presented in the Draft EIS

Page 3-9, Section 3.4, Geology and Seismicity - In the second paragraph, a statement is made that the tectonic activity 300-250 million years ago is responsible for the landforms This is incorrect This activity is responsible for the structures Differential erosion is responsible for the landforms, as correctly noted later in the paragraph.

2

USDOI-4

(cont.)

USDOI-5

USDOI-6

USDOI-7

USDOI-8

USDOI-9

Response to Comment USDOI-5

DOE is consulting with the U.S. Fish and Wildlife Service regarding future actions.

Response to Comment USDOI-6

Foster Wheeler is required to D&D the facility if the Low-Temperature Drying Alternative is selected. The contractor is required to restore the site to near its original condition per stipulations in the contingent contract with DOE. Section 4.11.2.1 states that soil removal and replacement would be the mitigation technology in the event of a spill from the MVSTs.

Although present in small amounts, some radionuclides have half-lives exceeding a million years. DOE acknowledges its responsibilities for long-term stewardship for the wastes for as long as necessary to protect human health and the environment.

Response to Comment USDOI-7

The correction has been made in Section S1.4.2.

Response to Comment USDOI-8

Figure 2-3 has been enlarged.

Response to Comment USDOI-9

Text in Section 3.4 has been modified to clarify role of tectonic activity in producing structure and resulting topography.

Page 3-12, Section 3.4.1, Stratigraphy - In the first paragraph, fault movements are discussed For clarity, a statement is needed to explain that these faults are very old and inactive

Page 3-13, Figure 3-4 - The "LITHOLOGY" column is impossible to understand without an explanation or legend. Also, the left-hand column under "FORMATION" shows letter codes for the formations. These codes are not unique, and therefore, are confusing. These shortcomings should be rectified.

Page 3-14, Figure 3-5 - In Figure 3-4, the small print states that the Dismal Gap Formation is formerly known as the Maryville Limestone. Yet in Figure 3-5, it is labeled Maryville Limestone The names of the formations should be consistent and current. The same problem affects the Friendship Formation, formerly Rutledge Limestone Maryville Limestone is used in the discussion in paragraph three of section 3.4.1 instead of the Dismal Gap Formation.

Additionally, the legend shows "ORNL North" and "true north." In other figures "ORNL grid north" is used. An explanation of these terms is needed.

Page 3-15, Section 3.4.2, Structure - In the second paragraph, it says saprolites "tend to have a clay content." This statement is unclear. The percentage of clay content in saprolites would be more helpful. The fourth paragraph begins "Tectonic activity has also produced extensive fracturing and ..". This statement is misleading. We suggest the sentence read "Ancient tectonic activity . "

Page 3-16, Figure 3-6 - Label where Figure 3-5 is on Figure 3-6.

Page 3-18, Section 3.4 4, Site Stability - A more up-to-date earthquake catalog is needed here This can be found at http://eqhazards.cr.usgs.gov/eq/html/catdec.shtml and is explained in Mueller et al (1997)

The term "Richter Scale" is inappropriately used quite often in the report. "Magnitude" is the term to use If a specific magnitude scale is used, then it needs to be used correctly and can be used with "body-wave," "mb," or other designation. But none of these is strictly a Richter magnitude.

In the last sentence of paragraph 2, the document states that high magnitude earthquakes may not equate to high intensity " ..if they occur in an unpopulated, remote location where very little measurable damage to human structure occurs." This is incorrect. A measure of the intensity may be difficult in such places, but the intensity is the intensity. What may affect intensity are site conditions, distance, and how fast the energy is lost with distance in the region (i e , the attenuation)

Page 3-19, Table 3-6 - Remove "Richter Scale ." and replace with "Effects near the epicenter of earthquake magnitude." It is misleading as it stands

Page 3-20, Section 3.4 4, Site Stability and Figure 3-7 - In the first complete paragraph, there is a discussion about the New Madrid "fault," which is incorrect usage since there are no certain faults The New Madrid is referred to as a seismic zone The earthquakes there were in 1811 and 1812, not

3

USDOI-10

USDOI-11

USDOI-12

USDOI-13

USDOI-14

USDOI-15

USDOI-16

USDOI-17

USDOI-18

USDOI-19

USDOI-20

Response to Comment USDOI-10

Text in Section 3.4 has been modified to indicate these faults have been largely inactive in recent geologic time.

Response to Comment USDOI-11

The legend to Figure 3-4 has been modified to identify lithology, and clarify formation terminology.

Response to Comment USDOI-12

Changes have been incorporated into Figure 3-4 to explain that the Dismal Gap Formation is known locally as the Maryville Limestone Formation.

Response to Comment USDOI-13

Figure 3-5 has been modified to show OR Administrative Grid.

Response to Comment USDOI-14

Text in Section 3.4.2 modified to indicate a high clay content. Also sentence in the fourth paragraph in Section 3.4.2 was changed to reflect ancient tectonic activity.

Response to Comment USDOI-15

The location of TRU Waste Project Site location is identified in the geologic cross-section map (Figure 3-6). This figure has a note indicating that a generalized plan view of the project site may be found in Figure 3-5.

Response to Comment USDOI-16

The site-specific information referenced in Section 3.4.4 is preferable to the more generic site stability information available at this web site.

Response to Comment USDOI-17

In accordance with the comments, the references to older "Richter scale" earthquake classification have been removed except on Table 3-6, where they have been left for comparison purposes because most members of the general public are familiar with the Richter scale for earthquake classification.

Response to Comment USDOI-18

Text has been modified in the second paragraph of Section 3.4.4 to delete any reference to comparing earthquake magnitude to levels of earthquake intensity.

Response to Comment USDOI-19

Because the general public thinks of earthquakes in terms of the Richter scale, Table 3-6 was not modified.

just 1812. It is unclear what the five earthquakes are, unless two of them are the 1843 and 1895 events

Figure 3-7 is completely confusing and the magnitudes are mixed. The caption says "Richter Scale," the figure legend says "mb" It is one or the other, but mb (body-wave magnitude) is correct but not very useful because it saturates at high magnitudes. The 1811 and 1812 earthquakes were nearly magnitude 8, but mb cannot measure that high. See Johnston (1996) for current discussion of the magnitude issue for New Madrid.

The second most active seismic zone in the eastern U.S is the East Tennessee seismic zone, where earthquakes occur under the overthrusts. There is very little discussion of this area. A thorough discussion of this seismic zone is needed here Johnston et al. (1985) and Powell et al (1994) can be used as references for this zone.


Page 3-21, Section 3.4.4, Site Stability - In the first complete paragraph, the discussion of capable faults is a bit misleading because, again, all earthquakes in the Appalachians and most of New Madrid are occurring on buried faults. This does not mean they are not capable, just that we cannot determine this by the same methodology as used in California, for example.

Pages 3-22-23, Figure 3-8 and Table 3-8 - Both this Figure and Table show the Peak Ground Acceleration in "g," which is correct, but then describe g as 1 g force equaling the force of earth's gravity on a mass at sea level This is incorrect. It is the acceleration due to gravity at sea level. "Force" is an inappropriate term for this concept.

The National Hazard Mapping web pages of the USGS at http://eqhazards.cr.usgs.gov/eq/ provide a more modern approach to looking at the seismic hazard (Frankel et al., 1996) The web page shows the peak ground acceleration for Oak Ridge and the values are actually lower than in Table 3-8 (page 3-23). However, if you download the disaggregation of hazard for nearby Knoxville (see attached), it is clear that local Appalachian earthquakes drive much of the hazard, which is not well reflected in the report

If you have any questions concerning fish and wildlife resources, contact Bruce Bell at the FWS at 404/679-7089 If there are questions concerning geology comments, contact James Devine, U. S Geological Survey at 703/648-4423. You can reach me at 404/331-4524

Sincerely,



James H. Lee
Regional Environmental Officer

4

USDOI-20 (cont.)

USDOI-21

USDOI-22

USDOI-23

USDOI-24

USDOI-25

Response to Comment USDOI-20

The text has been modified in Section 3.4.4 in accordance with the comment, and detailed reference to the timing of any other seismic activity along the New Madrid seismic zone was deleted to avoid confusion.

Response to Comment USDOI-21

The caption for Figure 3-7 has been modified to delete any reference to "Richter Scale" to make figure data consistent with caption.

Response to Comment USDOI-22

Section 3.4.4 has been modified to include a discussion of the East Tennessee seismic zone.

Response to Comment USDOI-23

Clarifications were made in Section 2.44 as suggested. The information from Blasing et al. 1992 regarding capable faults in the vicinity of the ORR remains because it is directly applicable.

Response to Comment USDOI-24

Text has been modified in Figure 3-8 and Table 3-8 to reflect acceleration due to gravity at sea level.

Response to Comment USDOI-25

Table 3-8 was not modified because data in this table are from site-specific monitoring rather than regional Appalachian data as referenced by the commentor. As mentioned in the comment, Frankel et al. 1996 suggest the ground acceleration for Oak Ridge may actually be lower than that reflected by the site-specific data.

REFERENCES:


Frankel, A., Mueller, C., Barnhard, T., Perkins, D., Leyendecker, E. V., Dickman, N., Hanson, S., and Hopper, M., 1996, National Seismic-Hazard Maps: Documentation U.S. Geological Survey Open-File Report 96-532

Johnston, A. C., 1996, Seismic moment assessment of earthquakes in stable continental regions-III. New Madrid 1811-1812, Charleston 1886 and Lisbon 1755.

Johnston, A. C., Reinbold, D. J., and Brewer, S. I., 1985, Seismotectonics of the southern Appalachians. Bulletin of the Seismological Society of America, v. 75, p. 291-312.

Mueller, C., Hopper, M., and Frankel, A., 1997, Preparation of earthquake catalogs for the National Seismic-Hazard Maps: contiguous 48 States: U.S. Geological Survey Open-File Report 97-464

Powell, C. A., Bollinger, G. A., Chapman, M. C., Johnston, A. C., and Wheeler, R. L., 1994, A seismotectonic model for the 300-Kilometer-long Eastern Tennessee seismic zone: Science, v. 264, p. 686-688.


Knoxville TN Disaggregated Seismic Hazard

3.2.6 U.S. Environmental Protection Agency

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 4
ATLANTA FEDERAL CENTER
61 FORSYTH STREET
ATLANTA, GEORGIA 30303-8960

April 17, 2000

4EAD

Dr. Clayton Gist, Waste Management Integration Team Leader
U.S. Department of Energy
Oak Ridge Operations
55 Jefferson Avenue
P.O. Box 2001
Oak Ridge, Tennessee 37831

RE: EPA Review and Comments on
Draft Environmental Impact Statement (DEIS) for Treating Transuranic (TRU)/ Alpha Low-Level Waste at the Oak Ridge National Laboratory, Oak Ridge, TN
CEQ No. 000059

Dear Dr. Gist:

Thank you for submitting the above-referenced document for our review. Pursuant to Section 102(2)(C) of the National Environmental Policy Act (NEPA) and Section 309 of the Clean Air Act, the U.S. Environmental Protection Agency (EPA) reviewed the subject Draft Environmental Impact Statement (DEIS). The document provides information to educate the public regarding general and project-specific environmental impacts and analysis procedures We appreciate your consistency with the public review and disclosure aspects of the NEPA process, and also appreciate the clarity and level of detail in the maps and figures in the document.

The Department of Energy proposes to construct, operate, and decontaminate/ decommission a TRU Waste Treatment Facility in Oak Ridge, Tennessee. The four waste types that would be treated at the proposed facility would be remote-handled TRU mixed waste sludge, liquid low-level waste associated with the sludge, contact-handled TRU/alpha low-level waste solids, and remote-handled TRU/alpha low-level waste solids.

The DEIS analyzes potential environmental impacts associated with five alternatives: No Action, Low-Temperature Drying Alternative (Preferred Alternative), Vitrification Alternative, Cementation Alternative, and Treatment and Waste Storage at Oak Ridge National Laboratory Alternative.

Based on our review, we rate the document "EC-2," that is, we have environmental concerns about the issues of process releases and details of the preferred alternative. Page S-34 of the DEIS notes that, during the treatment and repackaging effort, some process releases and resulting risks to humans would occur. These risks need to be explained. In addition,

'00 APR 24 P2:04

Internet Address (URL) • http://www.epa.gov
Recycled/Recyclable • Printed with Vegetable Oil Based Inks on Recycled Paper (Minimum 25% Postconsumer)

EPA-1

Response to Comment EPA-1

Section S1.8 discusses cumulative impacts. Regarding process releases and resulting human health risks, on page S-34 of the Draft EIS, DOE presented the cumulative impacts of the proposed action when combined with past, present, and reasonably foreseeable future actions, at ORR. The vitrification process was used as the bounding case because it would produce larger human health risks than either the low-temperature drying process or cementation. The latent cancer

clarification is needed regarding how the preferred alternative, using the current facilities at Melton Valley Storage Tanks, fits with the Record of Decision(s) for the proposed CERCLA actions. The relationship of the LLW and/or mixed waste generated to the proposed Mixed Waste disposal cell being proposed for the entire Oak Ridge Reservation also needs clarification.

Thank you for the opportunity to comment on this project. If you have any questions or require technical assistance, you may contact Ramona McConney of my staff at (404)562-9615.

Sincerely,

Heinz J. Mueller, Chief
Office of Environmental Assessment

Attachment

EPA-1 (cont.)

fatalities (LCFs) from the vitrification process (from air emissions), when combined with those computed for the Spallation Neutron Source (another project proposed for the ORR near ORNL), would cumulatively result in 3.1E-01 LCFs. Additional information can be found in Section 4.10.5 and Chapter 5.

Treatment of the MVST waste and SWSA 5 North waste would be consistent with the CERCLA ROD for Melton Valley. Additional information has been added to Chapter 4 addressing on-site waste transportation.

Clarifications relative to CERCLA RODs and the on-site disposal cell are provided in responses to EPA-3 and EPA-4, respectively.

Comments on
Draft Environmental Impact Statement (DEIS)
for Treating Transuranic (TRU)/ Alpha Low-Level Waste
at the Oak Ridge National Laboratory, Oak Ridge, TN
CEQ No. 000059

1. Overall, the DEIS is well-detailed and well-illustrated. The tables, maps, flow charts and figures are clear and useful.

EPA-2

2. Please clarify and explain how the preferred alternative, using the current facilities at Melton Valley Storage Tanks, fits with the Record of Decision(s) for the proposed CERCLA actions.

EPA-3

3. Please clarify the relationship of the LLW and/or mixed waste generated, to the proposed Mixed Waste disposal cell being proposed for the entire Oak Ridge Reservation. Please explain how the waste generated/managed for this action relates to it.

EPA-4

4. The preferred alternative would appear to meet the objectives for treating TRU and preparing it for WIPP disposal. What is the time frame for the waste being sent there, based on current operation schedules for all DOE sites?

EPA-5

5. Please clarify the method used to estimate waste volume on page S-12.

EPA-6

6. The document includes technical terms which may be unfamiliar to some public reviewers. Since this document is distributed to the public and non-technical reviewers, it would be helpful to further explain technical terms used in the DEIS, such as "contact-handled," "remote-handled," and "macroencapsulation."

EPA-7

7. Page S-33 notes that a 0.03-acre wetland on the proposed project site is expected to be eliminated by construction. The wetland area should be noted on a map in the EIS. EPA supports efforts to preserve wetlands, especially those of higher quality. Mitigative efforts and plans to offset unavoidable losses should be designed and implemented during the project; we note the potential mitigative measures listed in the DEIS.

EPA-8

8. Page S-34 notes that, during the treatment and repackaging effort, some process releases and resulting risks to humans would occur. Please clarify these risks. We note the off-gas system to minimize air emissions, and the cumulative effect of the Spallation Neutron Source Project.

EPA-9

9. Please clarify details of the Low-Temperature Drying process. What were the results of the existing precedents for this technology?

EPA-10

Response to Comment EPA-2

Comment noted.

Response to Comment EPA-3

The proposed action is linked to both previous and proposed actions taken or to be taken under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) process. The existing Melton Valley Storage Tanks (MVSTs) liquid and sludge waste volume was generated from three primary sources: the gunite and associated tanks, the Old Hydrofracture Facility Tanks Remediation Project, and the Inactive Tank Waste Program. Liquid waste volumes from the gunite tanks and the old hydrofracture tanks were transferred to the MVSTs via decisions that were made under the CERCLA process (i.e., interim ROD and action memorandum, respectively). The interim ROD was published by DOE in 1997 and is entitled *Record of Decision for Interim Action: Sludge Removal from Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, DOE/OR/OR2-1591&D3. The operation of the MVSTs and the treatment of liquid waste volumes contained therein are non-CERCLA activities.

In addition, there is also an indirect link between the proposed actions and future CERCLA actions to remediate the SWSA 5 North area. The TRU wastes presently stored in the trenches at SWSA 5 North are currently in an environment where an ongoing release of contamination has been identified. Information was added to Section 4.8 of the Final EIS explaining the impacts of exhuming 23 trenches of buried TRU waste casks and transporting them to the treatment facility for processing. The residual contamination left in the soils below and adjacent to the SWSA 5 North trenches will be addressed in the Draft Melton Valley Watershed ROD.

Response to Comment EPA-4

There is no relationship between the low-level waste that would be produced from the proposed action in this EIS and the on-site disposal cell currently being designed to provide disposal capacity for waste to be generated from cleanup actions on the ORR. The on-site disposal facility, the Environmental Management Waste Management Facility (EMWMF), was evaluated under CERCLA and is intended to provide disposal capacity for waste that will be generated from CERCLA remedial actions across the reservation. Low-level waste that would be generated from the treatment of the TRU waste is not eligible for disposal in the EMWMF because it is not CERCLA waste. Further, the disposition of low-level waste from this action was considered in the WM PEIS and its disposal would be governed by the ROD for low-level waste disposal (*Record of Decision for the Department of Energy's Waste Management Program: Treatment and Disposal of Low-Level Waste and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site—Federal Register* Vol. 65, No. 38, pp. 10061–1066, February 25, 2000).

Response to Comment EPA-5

DOE indicated in Table 4-10 of the Draft EIS that the waste shipment schedule is 58 months potentially starting as early as January 2003 and going until late 2007. The proposed schedule for the preferred alternative would meet the Site Treatment Plan milestones agreed to with the State of Tennessee. DOE has a coordinated shipment schedule with all TRU-waste-generating sites having an annual waste shipment allotment.

Response to Comment EPA-6

Waste volumes were summarized from data in Table 2-1, Section 2.4.2 of the EIS. Data were provided by Foster Wheeler and DOE has performed an independent review of the waste volume estimates for reasonableness.

Response to Comment EPA-7

"Contact-handled" and "remote-handled" are defined in footnotes in Section S1.4.2.2 and 2.4.2.2, as well as in the *Glossary of Terms Used in DOE NEPA Documents*

(DOE 1998) and on DOE's NEPA website at http://eis.doe.gov/nepa/. See also Sections S1.4.2.2 and 2.4.2.2.

Macroencapsulation refers to a process where waste materials are imbedded in inert material.

Response to Comment EPA-8

Wetlands near the site are discussed in Section S1.2.6.5, Table S-3, and in Sections 3.5.3 and 4.5.3 of the Final EIS. Maps of these wetlands are provided in the Final EIS (Figure 3-16 and Figure 4-1). A Wetlands Assessment was prepared for the site (Appendix C.6), and consultation is ongoing with the State of Tennessee on mitigation measures.

Response to Comment EPA-9

See response to Comment EPA-1.

Response to Comment EPA-10

The low-temperature drying process involves the use of a corkscrew-shaped or auger-type dryer to stir the waste under moderate vacuum conditions. The vacuum conditions reduce the boiling point of water in the waste to approximately 190°F. These types of dryers are used in numerous industrial and process applications. They have also been used to remove water from highly radioactive materials such as sump sludges, nitrate solutions, chemical drains, and ion-exchange resins. Also see response to Comment EM-1 for additional details of the treatment process.

3.2.7 Public Hearings

PUBLIC COMMENT HEARING ON THE DRAFT ENVIRONMENTAL IMPACT STATEMENT FOR TREATING TRANSURANIC/ALPHA LOW-LEVEL WASTE AT THE OAK RIDGE NATIONAL LABORATORY, OAK RIDGE, TENNESSEE, DOE-EIS-0305-D, February 2000

March 21, 2000

Conference Center, Oak Ridge Mall

BILL CAHILL: I'd like to get started, and we wanted to try to start as close to 6:30 as possible. We do have a couple of opening announcements. We are without the use of a PA system that works tonight, so I would ask that you either listen real closely or move up to some of the empty seats up closer. And if you can't hear anything that's said, please raise your hand and I will holler a little louder. For those of you who might be looking for the rest rooms, they're out the door, I understand, and to the left, as a public service announcement. We will go ahead and get things kicked off here.

My name is Bill Cahill. I am the NEPA document manager for the TRU Waste Treatment Project here in Oak Ridge. I want to do some introductions to the folks who have been running the project for a number of years. First of all, the TRU waste treatment program manager is Mr. Gary Riner, sitting here at the front. Another principal involved tonight with this evening's activities is Mr. Wayne Tolbert with SAIC, as a principal author on the document.

We have several visitors from headquarters that I'd like to recognize also. Mr. Jit Desai with the Office of Environmental Management, Jit, you want to raise your hand. And this is Mary Greene in the back with the Office of EH, Environmental Health and

Responses to Comments Made at Public Hearing

To the left is the transcript of the briefing portion of the public hearing held on March 21, 2000, in Oak Ridge, Tennessee. The first comment and DOE's response can be found on page CRD-77 of this CRD.

Headquarters. We also have with us this evening the operations manager for Foster Wheeler, Mr. Bryan Roy, sitting up here at the front.

If you want to write a comment tonight and mail it into us or you want to pick up some blue cards, please fill one of these out and feel free to mail it in and we will make sure that those comments get incorporated. .

We have a lot to cover tonight, so I'm going to try to go through the information as quickly as possible, and then we want to reserve as much time as possible to get everybody's comments made and the folks who have been the principals involved in this activity over a number of years will answer any questions that you guys have. Or to the extent that we can respond to the comments given tonight, we'll go ahead and do that.

Hopefully, I didn't miss anything. We do have two handouts. We have got the Summary of Impacts Tables that give you some details on the impact analysis that's been done. And we also have hard copies. They're all gone. I do have a couple more back here if you folks are interested in them. We also have copies of the briefing materials as well as if you didn't get a copy of the Draft Environmental Impact Statement and you want to have one, we have a couple here we can hand out tonight, also. If you need one, either get in contact with Gary or myself, and we

will make sure that you get a copy of those. So if no further ado, we will go ahead and get going with this evening.

We are here tonight to talk to you about the Draft Environmental Impact Statement for the treatment of TRU waste. We want to run through the alternatives that have been evaluated with you, give you an overview of the document in general. And most importantly, we want to get your comments, give you an opportunity to get your comments out on the table for us to make sure we can get it incorporated into the final that gets pulled together. We will give you some information about where to mail your comments and things like that towards the end of the evening.

The TRU Waste Treatment Project that we have here at Oak Ridge at ORNL is significant both to Oak Ridge and is a complex wide problem. Clearly one of the most significant challenges of the department today is to address the legacy waste that has been generated by past research and defense activities, liquid wastes that are stored in various tanks across the reservation that do present serious challenges to achieve a cost effective and safe, environmentally safe alternative for addressing those problems.

In terms of the scope that we have to

cover tonight in the Draft EIS, we are talking about the treatment of the stored legacy and newly generated waste at ORNL. We give a breakdown of the some of the volumes here for you to look at. We've got both contact-handled and remote-handled waste volumes. We have solid low-level waste and we also have liquid and sludge waste that we have to deal with. These are the volumes and these are the waste types that we're going to talk about tonight and talk about treating them.

This is, as Gary made a point to someone earlier this evening, this is one of the most hazardous waste streams that we've got here on the reservation. It does present one of the most significant health and safety problems that we have to address here on the reservation. This waste is considered by our regulators as a significant priority to be addressed. We have several different regulatory documents that have been put into place to address remediation or treatment of this waste. We've got a Tennessee commissioner's order and there have been several records of decision that have been put into place to address some of the smaller volumes of the TRU waste that are out there, specifically in the Melton Valley area.

We do want to take a couple of minutes to address several basic what we call TRU facts, if you will, a definition of TRU waste. We want to try to get that

straight before the evening got too much further down the road. TRU waste is not classified as high-level waste, as you can read here, but we're talking about radioactive isotopes or transuranic isotopes with an atomic number greater than 92 at concentrations greater than 100 nanocuries per gram. I think that's correct. Yes. And then you can read the half-lives.

Why is the TRU waste a health hazard here on the reservation? Why does it represent a significant health hazard on the reservation? Because of the alpha emitting particles. And although they're easily shielded, they do create some significant health problems if they're inhaled or ingested. So that's kind of a general definition of TRU waste for you.

Legacy waste has been another comment or questions that have come up in terms of legacy waste that we've got to deal with here. The legacy waste that we're talking about addressing in this document is waste that's generated from past research and development activities here on the reservation, and it's stored in solid waste tanks and facilities across Oak Ridge National Lab in bunkers and in trenches. Do we generate any TRU waste on the reservation currently? And the answer to that question is yes, we do. It's at the Radiochemical Development Facility, which is the only source of transcurium elements. This EIS, I did want

to make a point that this EIS does include addressing newly generated waste volumes, although we have a very small volume of that, and the greatest volume of waste that we have to deal with are the legacy volumes that are in the tanks that we talked about before and the solid waste volumes.

In terms of waste types, I mentioned a moment ago about the sludges that are included in the EIS document for analysis. They are currently consolidated. About 95 percent of all of the TRU waste sludges and liquids have been transferred and are consolidated now at the Melton Valley Storage Tanks. We have about 900 cubic meters of sludge waste, that's remote-handled. It does contain RCRA metals, so it is considered to be a mixed waste. We also have some liquids or supernates that the document addresses that is included with the sludge waste material that needs to be addressed.

In addition to the supernate or the liquids in the sludge, we also have some solid waste to deal with. We've got solid waste that is remote-handled and we've got solid waste that's contact-handled. Basically, the difference between those two different types of waste is the level of activity and the level of health and safety standards that have to be overlaid to make sure that we safely manage that waste.

In terms of the remote-handled solid low-level waste, we have about 550 cubic meters of material that may contain RCRA characteristic metals that are currently stored in the waste bunkers and trenches. They are in various boxes and overpacks. We also know that these overpacks are not approved right now for transportation, so they are not in any shape to pick up and move anywhere. So they need to be repackaged, which is one of the challenges that is related to dealing with this type of waste.

We also have contact-handled low-level waste to deal with. We have got about a thousand cubic meters of this type of waste that's stored in the metal buildings at Oak Ridge National Lab now. This material is stored in drums inside of these buildings. It also may contain some RCRA characteristic materials, metals, hazardous metals. Many of these containers also need to be repackaged, which presents a challenge for handling this type of waste.

I do want to talk about the distinction that we make in the Draft EIS now with regards to alpha low-level waste. Basically, when we talk about the management of alpha low-level waste or the disposal of alpha low-level waste in this document, we're talking about the same transuranic elements but at concentrations below the hundred nanocuries per gram. So we've got low-level waste,

basically, but it's alpha low-level waste. The same transuranic elements are involved but just at different concentrations. I wanted to make sure that we're clear on that.

The process that we have been following here for this evaluation basically is by using our NEPA implementation regs, 10 *CFR*, Part 1021, which basically has allowed us in this particular process to join together the procurement effort with the development of the NEPA process and the evaluation of our NEPA requirements. Basically, the benefit that that provides us in this particular project is one that essentially takes a lot of the guesswork out of the alternatives that we're evaluating, because it has allowed us to solicit specific environmental data and address it and incorporate that into the analysis that we're doing now, so we actually have real data as opposed to information that is our best guess.

We actually have contractor specific environmental data that we have included in this EIS package. We have awarded a contract in August of '98 to Foster Wheeler. That contract is contingent -- we want to make sure that that point is understood -- that contract is contingent on completion of this NEPA process and selection of the contractor's proposed treatment method, which is the Low-Temperature Drying Alternative.

Let me switch gears for a moment and talk a little bit now about the overview of the actual document that we're going to go into. Can everybody hear okay? Okay. We're going to talk about the alternatives that we evaluated and the impacts that go along with those alternatives. But, obviously, if you've had a chance to look through the document, there is more in there than just Chapter 4 that talks about the alternatives and the impacts. We've got Chapter 3 in there, which sets the stage for the affected environment. We have accumulative impacts to address, also. We have significant laws and regulations included in that document. So this is the meat and potatoes, if you will, of the analysis, but obviously there is a lot more to cover than what we have time or effort to go into tonight in detail.

In terms of alternatives that we've looked at, we have a No Action Alternative obviously, Low-Temperature Drying, Vitrification and Cementation. We also have included, I believe, since the Scoping Meeting, an alternative that evaluates treatment using one of the above noted methods and waste storage at ORNL.

Now, in terms of the No Action Alternative, basically, the definition of the No Action Alternative in the document is that the waste will remain in its current storage facilities, be it trenches or bunkers or

in the Melton Valley Storage Tanks. No treatment is involved and no final offsite disposal. We've also considered a hundred year institutional control period and some of the effort that goes along with that, also.

Now, the impacts associated with the No Action Alternative basically put us into a position to where we're non-compliant with the site treatment plan in terms of our obligation to treat and be ready to ship, make the first shipment for disposal of the TRU waste material. We would have continuing radiological releases from the SWSA 5 trenches, which would affect surface water and groundwater and biota.

The risk of earthquake becomes a credible event. We've provided a lot of information in the document relative to this potential risk scenario, where we would basically have a release from the Melton Valley Storage Tanks, which would be considered significant impacts related to contamination of White Oak Creek and White Oak Lake. We would have related fish kills and kills of other biota. We would wind up also contaminating downstream drinking water supplies at ETTP as well as Kingston, also. That's a brief overview of the risks related to the No Action Alternative.

We also have a Vitrification Alternative included in the document. Basically, we would wind up with vitrification, going out and building the treatment

facility, which would require about seven acres of land for the footprint of the vitrification treatment facility. We would vitrify or put into a molten glass form the waste types that we've been talking about, sort, treat and volume reduce the solid waste. We would take the liquids and the sludges and we would vitrify them, but the solid waste, the contact and remote-handled solid waste that we talked about, we would, DOE would deliver it to the facility, would sort it and characterize and volume reduce it and package it. DOE would also certify this material for offsite shipment to either WIPP or NTS.

The impacts related to the Vitrification Alternative can basically be summed up as we have done on this slide. It would require, relatively speaking, compared to the other alternatives, more land committed for the treatment facility construction. We would have the potential for the risk of a melter failure. We would also wind up using more electricity compared to the other alternatives. I think we wind up using 30,000 more megawatts of electricity when we compare vitrification to the other alternatives. Vitrification also winds up producing the most D&D waste debris, in terms of material that we have to deal with once we're done with the treatment project when we take the facility down.

Now, if we switch gears to the

Cementation Alternative, we basically go out and use up about five acres of land, footprint of about five acres to construct the facility. We would treat the sludges and the liquids using the cementation process, which basically involves pumping those materials over to the treatment facility from the Melton Valley Storage Tanks. The liquids and the sludges would then be separated and they would have the dry feed of cement and other additives added to that material and the liquid grout would be pumped directly into 55-gallon drums and then into the casks.

We would handle the solid waste similar to the way we talked about handling the solid waste material in the Vitrification Alternative. We would deliver it to the facility, sort it, volume reduce it. In the sorting process, incidentally, one of the things that I didn't point out was that we would pick up at that point in time, while we're sorting the waste and characterizing it, whether or not we have any RCRA materials. Those RCRA materials would be isolated and dealt with in another process. They would be microencapsulated and then packaged, and DOE certifies the final waste forms for offsite shipment, the same as the Vitrification Alternative, to WIPP or to NTS.

Now, impacts related to the cementation process can be summed up like this. We wind up creating the largest volume of treated TRU waste and alpha low-level

waste materials that we've been talking about tonight. The Cementation Alternative winds up giving us the most treated waste form to deal with. We would also, because we've got more waste volume to disposition off site, we would require about 3,000 offsite waste shipments to take care of those treated waste volumes that we generate. We also wind up using the most water. I think relatively speaking, we use up to 13 million more gallons of water for this alternative compared to the other alternatives.

Now, the Treatment and Waste Storage Alternative basically, as I mentioned a moment ago, incorporates the notion that you're going to use one of these treatment methods to treat the waste, either Low-Temperature, Vitrification or Cementation for the liquid material. We wind up packaging it and we wind up storing it onsite.

I do want to mention that for the analysis that we've done in the document for this alternative, we have to make sure that we have done a bounding analysis that considers the most impacts. We have identified vitrification as the treatment method that we used for the treatment as an onsite storage alternative to make sure that we have a bounding analysis and we're not missing any impacts related to one of the alternatives. Onsite waste storage also assumes the hundred year

institutional control period that we talked about a moment ago.

Now, the impacts associated with the Treatment and Storage Alternative basically consists of the same situation that we find ourselves in with the No Action Alternative in terms of noncompliance with the Commissioner's order for basically making our first shipment by FY 2003 of the TRU material. We would wind up having the greatest onsite adverse impacts when we look at this alternative compared to the other ones with regards to soils. We've got a bigger footprint area for the facility that we're going to wind up putting in. For biota, we're going to clear more land basically or lose resource area for the biota.

And land use, if we wind up going with this alternative, we don't have enough storage capacity, so we would have to create some more storage capacity to manage the waste volumes that we would generate. The upside of this particular situation is that there are no offsite transportation of any material or is no offsite transportation, and obviously no impacts related to that.

Now, the Low-Temperature Drying Alternative, which if you've had an opportunity to look at the draft document does identify this alternative as our preferred alternative. We wind up constructing the waste

treatment facility. We would need about five acres of land to do that. We treat the liquids and the sludges by low-temperature drying, which essentially consists of evaporating the liquids off of that material and consolidating the rest of the material that's left and packaging it. The solid waste material, we would deliver to the facility, characterize it, sort it and repackage it as we've talked about earlier. DOE would also certify any final waste stream that's generated for shipment later on to WIPP and to NTS.

Now, in terms of impacts related to the Low-Temperature Drying Alternative, basically, when compared to the other alternatives, we would have the least impacts when we look at all our different resource areas. We would result with the least volume of waste generated by using this alternative when compared to cementation or vitrification. We would result in the least number of offsite shipments related to this particular treatment alternative. So we've got, in terms of impacts for the low-temperature alternative, most of those are actually favorable. We would consider them as favorable impacts for this analysis.

Now, I want to step back for a moment and look at the impacts analysis that we've done in the draft document. And this is intended to give you an idea of the

resource areas that we've looked at over on the far left column. I'm not going to go through them all for you. Those are the resource areas that we've looked at.

As we move across any particular resource area, what we've tried to do is to present a relative comparison of the alternatives within any given resource area that's been evaluated. We've tried to color code this in terms of green being the least impact, yellow being a moderate impact, and relatively speaking, any red dot on here would indicate the most impact related to any particular alternative within that resource area.

Some of the general messages that you get when you summarize things in this fashion are that, basically, if you take the No Action Alternative or the Treatment and Storage Alternative, relatively speaking, when you look and compare them to the other alternatives, those are least favorable. Another observation that we can make is that we've got three viable treatment alternatives here. Low-Temperature, Vitrification and Cementation are all viable alternatives that have been analyzed in the document. Also, if you look at all the resource areas for the Low-Temperature Drying Alternative, you get an idea that when you compare all of the resource areas for low-temperature relative to the other alternatives that we've looked at, there are the least amount of impacts

related to low-temperature drying.

Now, one of the things that we talked about a moment ago was total waste volumes. All this does is give you an illustration that if we're dealing with vitrification, we're going to generate the most total waste followed by cementation and Low-Temperature Drying Alternative. But let's take that information and break it down a little bit more for you in terms of what's really important for us to look at. If you look at the two columns -- I'm not sure you can see that from sitting there; let me move this up here a little bit for you -- we take the total waste volumes and break them down for you in terms of TRU waste generated, low-level waste volumes and sanitary waste volumes and debris waste volumes specific to each of the treatment alternatives.

These two categories, the TRU waste and the low-level waste, are the volumes that we've got to manage and disposition offsite. Sanitary wastewater and this debris from D&D activities is what we would call sanitary waste and it could go to a sanitary landfill. It's not contaminated. This low-level waste or alpha low-level waste is what we have to disposition offsite as well as the TRU. If you keep the color code straight, you get the idea that cementation gives us the most low-level waste and TRU waste to deal with, followed by the Vitrification

Alternative and then the Low-Temperature Drying Alternative.

In terms of number of shipments that relate to those waste volumes -- again let me scoot that up a little bit for you -- low-level waste shipments for cementation, you can see the numbers speak for themselves basically. And TRU waste volumes and related waste shipments that need to be considered indicate that we wind up with a spectrum that's defined by Cementation Alternative as the highest number of shipments and the Low-Temperature Drying Alternative as the lowest number of shipments for both of those waste categories.

Now, in terms of where we go from here, the schedule of events looks a little bit like this. We've got the public comment period that's ongoing now, which started on March 3rd, will end on April 17th. We need to incorporate public comments that come in any form, written or comments that are given tonight. We need to distribute the Final EIS, and we're working towards a Record of Decision in the early July time frame.

Kind of what we're here tonight for is to solicit your comments basically. We want your comments on the table. We want to understand them to make sure that we address them clearly. This information is also provided in the draft document, but you can mail comments into Dr. Gist,

who is sitting in the back of the room, at this address, or E-mail comments, also, and his E-mail address is provided at the bottom there. The bottom line is, we want to understand and know your comments.

That concludes the briefing part of this evening in terms of an overview of the EIS, the alternatives and the impacts. Now, what we would like to do is basically open it up to a question and answer session. If you have any comments you want to share with us now, we will capture those. To the extent that we can respond to them here this evening with the resources that we have and Gary and Wayne and other folks, we can do that. Thank you very much. Anybody want to start off?

ROBERT PEELLE: In the case of the onsite, keeping the material onsite, you take a hundred year stewardship into account. Does that mean that it won't need stewardship after a hundred years or it's hard to compute the cost?

BILL CAHILL: Certainly, it doesn't mean that it won't need stewardship after a hundred years.

ROBERT PEELLE: This is long-life material.

BILL CAHILL: It is. The hundred year institutional control period was just a time frame that we used as an assumption for the analysis.

RP-1

RP-1 (cont.)

Response to Comment RP-1

DOE recognizes its obligation to take care of the waste as long as necessary. DOE used a 100-year institutional control period for the purposes of impacts analysis. This assumption is stated throughout the EIS. The 100-year period is used because this is the longest period of time for which DOE can assume control for purposes of analysis. DOE intends to manage the waste as long as is necessary to protect human health and the environment.

DOE has added analysis to Chapter 4 of impacts after loss of institutional control. The commentor is correct in recognizing that cost is a central issue in the long-term management of waste. However, the DOE does not include information about costs for any alternatives because this issue is not part of the environmental review.

MR. PEELLE: So one of the costs that you have trouble inventing is the institution to take care of it later? Even if this kind of cost might look small, you still haven't invented who can take care of it after a hundred years?

RP-1

RP-1 (cont.)

MR. CAHILL: Correct. Correct, if I'm understanding you right.

MR. TOLBERT: They need to state their names.

BILL CAHILL: I'm sorry. That's right. If you have a comment or question you would like to share, could you give us your name so we can capture that correctly on the record.

ROBERT PEELLE: I don't know if it was a comment. I'm Bob Peelle. 130 Oaklahoma. There was a comment. You have a hundred year problem; namely, you aren't listing the details of the cost. You don't even know how to do it. It's difficult.

RP-1

RP-1 (cont.)

BILL CAHILL: It's difficult.

ROBERT PEELLE: It's very hard.

BILL CAHILL: Mr. Weeren.

RP-1 (cont.)

HERMAN WEEREN: I am Herman Weeren. And some fifteen odd years ago I participated in the injection of 3 million gallons of legacy TRU waste down in the argillaceous shale. I see no mention of this. Opinion

HW-1

Response to Comment HW-1

DOE acknowledges that waste was injected into deep (approximately 1,000-ft-deep) formations in a process termed hydrofracture. That waste is not within the scope of this EIS.

seems to be divided whether it is necessary or not. But I would think that for completeness, just to show, put it all in proportion, this should at least be mentioned, even if you say, it was a good place, but we aren't going to do anything with it and it's beyond the scope of this report. But 3 million gallons of material that is running 150 nanocuries per gram is not trivial.

WILLIAM CAHILL: No, I would not consider that trivial either. We are aware of those other activities and those other waste volumes; however, the scope of this document is intended to cover the legacy waste that we have in storage, the liquid and the solid waste material.

HERMAN WEEREN: This is real fine. Just say, I think for completeness, as I say, just say this up front, one paragraph, it's there, but we aren't considering it in this report.

BILL CAHILL: Okay.

GARY RINER: No problem.

HERMAN WEEREN: I have another comment. I don't want to monopolize it and I can't see who else has their hand up. Back to the old subject of hydrofracture wells. There was a statement in the responses, Appendix A or whatever it was, that environmental science said that no hydrofracture wells are within the proposed building area. Now, I don't know if we're supposed to examine these

HW-1

HW-1 (cont.)

HW-1 (cont.)

HW-2

statements with great care along the line of it all depends on what you mean by "is", but there is a map of the thing.

GARY RINER: There is one well within the boundaries of the property, Herman. I went out there and walked it down, okay. There is one well within the boundaries.

MR. WEEREN: There are two. I don't know how deep the second one is. The numbers are there in red. What worries me about those is the right hand doesn't always know or seldom knows what the left hand is doing. I can see them coming in and grading out the culvert right next-door to that well, oh, what's this, just before they knock it down. That well goes down to the grout sheets.

BRYAN ROY: My name is Bryan Roy. Gary asked me what well was towards the center of the site. It is 1204. Is that the one you identified, Herman?

MR. WEEREN: It is not toward the center of the site. It is more commonly known as Steve Hass' (inaudible). They are a thousand feet out from the injection well. They go down a thousand feet. They are contaminated and they have had activity at least once or twice that made the news.

BRYAN ROY: 1204 is the only well that we've come close to that is open.

HERMAN WEEREN: This is 2955 and 2374. I

HW-2

(cont.)

HW-2

(cont.)

HW-2

(cont.)

Response to Comment HW-2

Wells in the general location are described below and are listed in the following table. DOE does not expect to disturb any of these wells. Well 1204 is the only well known to be within the proposed boundary of the Low-Temperature Drying or Cementation Alternative sites. The site development plan has carefully accommodated this well. DOE expects to leave it undisturbed within an area between a retaining wall and driveway. For the Vitrification Alternative, which has a larger footprint, wells 2374 and 2955 would be closer to the facility than the distances shown in the table below, but these wells are not expected to be disturbed.

Well No.	Description	Location
1204	PVC research/ monitoring well; 74-ft deep	Within the proposed site boundary
784	2-in. PVC research/ monitoring, 20-ft deep, nonessential well	Approximately 60 ft west of proposed facility entrance driveway
785	2-in. PVC research/ monitoring, 45-ft-deep, nonessential well	Approximately 60 ft west of proposed facility entrance driveway
1974	No data	Opposite side (north side) of access road and east of proposed facility construction
1975	No data	Opposite side (north side) of access road and east of proposed facility construction
*2374	Mostly 4.5-in.-diameter hydrofracture well to 1,275 ft deep	Along old access road shoulder 350 ft west of the site
*2955	Mostly 6-in.-diameter hydrofracture well to 1,063 ft deep; well is inside a shed	Along old access road shoulder 330 ft west of the site
1980	No data	Approximately 25 ft east of nearest proposed site grading activity; at least 50 ft from nearest facility feature
1981	No data	Inside Building 7877 approximately 150 ft east of proposed facility
1982	No data	Through the pad outside of Building 7877 ventilation system, approximately 130 ft east of proposed facility

*Hearing commentor specifically identified these wells.

never could keep up with their nomenclature, so it means nothing to me. But the whole business of the wells being contaminated, capable of being damaged on the surface sort of bothers me. I guess, primarily, I want you to be aware that there is a problem there. HW-2 (cont.)

WILLIAM J. CAHILL: Yes. Could you give me your name, please.

PAM WATSON: It's Pam Watson. PW-1

SUSAN DAVIS: Excuse me. I'm wondering if it would help if they stood. We're competing with across the way. I've asked them to turn down the music. Maybe if we stood up when we gave our comments, you could hear it a little bit better. The people back here can hardly hear. Sorry to do that to you, but we can't hardly hear.

BILL CAHILL: If you would rather not stand up, just give me the comment and I'll repeat it.

SUSAN DAVIS: Right.

PAM WATSON: I have several questions, so I'll just stand up and say the question, and you can answer it, and then I'll stand up again.

WILLIAM CAHILL: Okay.

PAM WATSON: I was curious about one of your slides. Why do all of the alternatives other than the No Action Alternative show a moderate impact to human health? Can you give us the details of that? What are the PW-1 (cont.)

Response to Comment PW-1

The moderate human health impacts for the action alternatives referred to by the commentor are related to the air emissions from normal operations during treatment (Section 4.7). Distinctions among the alternatives are discussed in Section 4.7

Under No Action, during the institutional control period, the waste sits where it is and there is little chance of human health impacts except in the case of accidents, which were

moderate impacts that we're talking about to human health? And also, why would the No Action Alternative not have an impact if, as you said, there were to be an earthquake and, you know, the material would go downstream to Kingston and contaminate the water supply and so forth?

BILL CAHILL: Let me try to give you an initial response and then I'll turn it over to somebody who's got more details on it than I.

HERMAN WEEREN: Could you slide that slightly so that the little green thing down there at the bottom left is visible. Thank you.

BILL CAHILL: The human health portion of the analysis, I believe, is generally captured in our Affected Environment, Chapter 3. The statement we're making here is in the context of this is a yellow as opposed to a red would be whether or not the particular treatment alternative winds up increasing or adding to the existing health baseline that we've documented in that chapter. I don't know if that makes that much sense. But Wayne, can you add to that?

WAYNE TOLBERT: Let me try. We basically looked at human health and accidents in the following way: First of all, human health was dealt with, when we're referring to it on this chart and in the chapter or in the

PW-1 (cont.)

Response to Comment PW-1 (cont.)

addressed in the accidents portion of the slide. (Section 4.11. of the Final EIS provides an analysis of an earthquake accident with corresponding downstream risks at Kingston in Section 4.11.2.1.)

When DOE begins to treat the TRU waste, there is a greater likelihood of affecting human health from an increase in industrial accidents or from processing emissions. In addition to normal operations of the various treatment alternatives, DOE evaluated the accident risks and consequences under an assumed 100-year institutional control period.

DOE also added analyses in Chapter 4 of the Final EIS that address impacts after loss of institutional control for the No Action and Treatment and Waste Storage at ORNL Alternatives. After loss of institutional control, impacts from the No Action Alternative could be significant to human health (Section 4.10.3).

section on impacts, we're looking mostly at operational activities as opposed to accidents. Under accidents, you do have a fairly significant evaluation, if you will, of human health effects.

So there are, if you're looking, for example, under accidents and no action, which I think is one of your questions, if I understood it correctly, why would there not be human health impact there, if you had an accident under no action, you, in fact, do have a fairly significant problem. In fact, that's the most significant accident in human health risk of all the activities, all the accidents that we've looked at, was associated with the breach of the Melton Valley Storage Tanks, or one of the Melton Valley Storage Tanks. We're looking at a loss of about 50,000 gallons from one of those tanks. That's where you end up with human health impacts. It's actually listed under the accidents part. That's how we organized the document.

PAMELA WATSON: So when you said the human health impacts are the result of operational activities, do you mean these are risks to the workers in the facility or to the public during transportation? You know, what are the human health impacts we're talking about here?

GARY RINER: I believe your question, on

PW-2

Response to Comment PW-2

Human health impacts include impacts to the workers and the public. Section 4.10 of the EIS addresses human health impacts under normal operating conditions. Impacts due to accidents and transportation of the wastes are addressed in later sections of the Final EIS. Section 4.11 deals with human health consequences from accidents, and Section 4.8 deals with human health impacts due to transportation exposures and accidents.

the human health one, no action, we just leave the waste sitting as it is today, we do not do anything with it, there is little human risk involved with it. Then as you start to process the waste, that risk threshold has to increase some, because you got the chance of dropping a drum on somebody, dropping one of these large concrete casks on somebody. So relatively speaking, that's what Bill tried to emphasize, was these color codes are relative.

PAMELA WATSON: To the workers.

GARY RINER: Relative to the workers. So that's where that yellow is coming in. Now you've increased their risk just in handling radioactive materials on a daily basis, repackaging and all that. I think that gets more to your question.

PAMELA WATSON: How many years do you estimate until all the waste that you intend to treat in this action is treated and how many years do you estimate until all the waste is shipped offsite or reaches its final storage place?

BILL CAHILL: The treatment period duration for low temperature, Gary, correct me if I'm wrong, is about five years. The project duration is eleven years. So when you throw in the design and D&D on either end of it, the treatment is five years. Now, offsite shipments, I don't know.

PW-2 (cont.)

PW-3

Response to Comment PW-3

The overall project durations are longer than the treatment periods. The schedule for each alternative includes a licensing and permitting phase, a construction and operational testing phase, a waste retrieval and treatment operations phase, and a D&D phase. It is assumed that shipment of waste offsite is done immediately after the waste is treated. Thus the shipment period is equivalent to the waste retrieval and treatment operations phase, which would vary according to the action alternatives: for Low-Temperature Drying about 5 years (Section 2.4.3, Figure 2-6), for Vitrification about 3 years (Section 2.5.3, Figure 2-10), and for Cementation about 6 years (Section 2.6.3, Figure 2-13).

DOE plans to have real-time shipments with minimal inventory of treated waste at the treatment facility.

GARY RINER: Offsite shipments is within that five-year period, assuming that the repositories where we plan to ship, WIPP mainly and the Nevada Test Site, are available to accept the waste, okay. That is probably one of the greater risks, WIPP being ready for our remote-handled waste. As the program is set right now, as the department is setting up their program, everything should be shipped in the five-year window.

PAMELA WATSON: So how many years for treatment? Five years to have it all shipped. PW-3 (cont.)

GARY RINER: Real time shipments; in other words, they never keep an inventory over a few cubic meters in their facility, stuff is packaged and shipped th next day. It continues to flow through the facility in that nature.

We looked at the possibility and added Alternative 5 having to do with interim storage on the reservation, because we know that risk is out there for Oak Ridge not to be able to ship this stuff immediately. And if that's the case, we'll have to store it for some interim time period. Can we define that time period? No, we can't. It's not in our control.

PAMELA WATSON: One more question and then a couple of comments. How many workers or do we have an estimate for the number of workers that will be required PW-4

Response to Comment PW-3 (cont.)

Treatment schedules are shown in Tables 4-10, 4-12, and 4-14. DOE did, however, evaluate an alternative in which treated waste would be stored at ORNL. In addition, short-term storage at existing ORNL facilities could occur should there be a temporary problem with shipping the treated waste offsite.

Response to Comment PW-4

For the preferred alternative, the number of workers differs depending on the phase of the project. Generally, the worker population by quarter would average approximately 35 for the design phase, 60 for the construction phase, 55 for the operations phase, and 20 for the D&D phase. Overall, the average for the project duration is about 50 workers.

for this facility? And will those be subcontractors to the environmental management contractor?

GARY RINER: Are you asking for the preferred alternative, assuming it goes forward, how many workers are we going to have?

PAMELA WATSON: Right. Do we have a ball park idea?

GARY RINER: Okay. I would ask Bryan.

BRYAN ROY: Ball park, fifty workers, all shifts, during the operational phase.

PAMELA WATSON: Those will likely be subcontractors to the environmental management contractor?

BRYAN ROY: They will be subcontractors or employees of Foster Wheeler.

PAMELA WATSON: Okay. Just two comments. Slides 24 and 25, I noticed, this is a minor thing, but it's irritating when you're sitting in the back and you can't read the text that's on the screen, slides 24 and 25. Slide 24, the text was too small to be readable by most people in the audience, I believe. And slide 25, the text at the bottom was too small to be readable by most of the audience, I believe.

BILL CAHILL: Okay. Thank you. Okay. Lorene.

LORENE SIGAL: I'm Lorene Sigal. A road

PW-4 (cont.)

PW-4 (cont.)

PW-5

Response to Comment PW-4 (cont.)

They would be subcontractors or employees of Foster Wheeler, if the preferred alternative were selected. Otherwise, the workers would be employees of another contractor that DOE would select to implement the other treatment alternatives.

For information on other alternatives see manpower Tables 4-35 and 4-38.

Response to Comment PW-5

Comment noted. Hard copies of the slide presentation were made available to meeting attendees. Also see ORSSAB-2.

has been built out to the Highway 58 from the proposed site?

BILL CAHILL: Yes.

LORENE SIGAL: Did you assess the impacts of that road?

LS-1

GARY RINER: It's out to 95.

LORENE SIGAL: All right. 95. Did you assess the impacts of that road? I don't see it in here.

LS-1 (cont.)

BILL CAHILL: No. In this Draft EIS we did not assess the impacts related to that road. It was a separate action, and I believe it was handled under a separate NEPA document. I think it was a categorical exclusion.

LORENE SIGAL: Categorical exclusion for sort of a major record?

LS-1 (cont.)

WAYNE TOLBERT: Correct.

GARY RINER: It's 1.45 miles. There was a gravel road already in the vicinity.

LORENE SIGAL: But you didn't use that gravel road as roadbed for the new road?

LS-1 (cont.)

GARY RINER: It did diverge from the gravel road once construction got underway. There is a small portion of the gravel road that's still left.

LORENE SIGAL: The road is what, two lanes?

Response to Comment LS-1

As noted in the EIS (Sections S1.2.3, 1.5, and 5.3.2), the Old Melton Valley Road (sometimes referred to as the High Flux Isotope Reactor access road) upgrade was evaluated and categorically excluded by DOE, *Categorical Exclusion for Construction/ Relocation of Access Road at Oak Ridge National Laboratory, Oak Ridge, Tennessee*, CX-TRU-98-007, (DOE 1998), a copy of this categorical exclusion is included in this Final EIS (Appendix G). A rare plant survey was performed for the proposed access road location (Appendix G) in an effort to minimize impacts to a rare plant species, Pursh's Wild Petunia (*Ruellia purshiana*), found in the area. As a result of the survey, the proposed road was relocated. The cumulative impacts chapter (Chapter 5) of the EIS has been updated to reflect the above and to provide additional information on the environmentally sensitive resources evaluated. Also see response to Comment ORSSSAB-2.

GARY RINER: Yes, in and out.

LORENE SIGAL: Seems to be it should have been analyzed in here as well and not categorically excluded. LS-1

BILL CAHILL: Anyone else, please.

MILDRED SEARS: Mildred Sears from Oak Ridge. In the case of Alternative 1, No Action, and Alternative 5, which involved long-term storage, possibly forever on the Oak Ridge Reservation, the document needs to strengthen this question of stewardship and the fact that there will be continuing long-term worker exposure for maintenance. And if you don't provide stewardship, and we're talking millions of years, we're not talking just a hundred years, in due course of time, your containers will rust out, your roof will be gone, an airplane will crash into it, you'll have an earthquake, and this stuff will be in the environment and in the creek. MS-1

I think that somehow the fact that in an environment like we have in East Tennessee where it's very wet, rains a lot, this needs to be emphasized, because in my judgment, the disposal of this waste at the Oak Ridge Reservation is not acceptable. I'm referring to both Alternative 1 and Alternative 5.

Now, also in Alternative 5 in your table on waste volume, I forget which page it's on, but it MS-2

Response to Comment MS-1

DOE has added analysis and discussion to Chapter 4 regarding the impacts after loss of institutional control, which for analysis purposes, would occur after 100 years. See also the response to comment ORSSAB-3.

Comment MS-2

A footnote has been added to Tables S-1, 2-4, and 4-5 to clarify that TRU waste is comprised of both remote-handled and contact-handled waste.

indicated that the cement one produced remote-handled waste, but low-temperature drying and vitrification did not. That's obviously an error, because if you start out with remote-handled waste and you concentrate it, it's going to be even more remote-handled than when you started. I'm not talking about the dry stuff, but I'm talking about the sludge.

MS-2

(cont.)

If you're shipping TRU waste to WIPP to a geologic repository where the disposal is very expensive, you obviously want to minimize volume. When you start talking about storage, even interim storage, you will have to provide shielding for all this remote-handled waste. That is going to increase the storage required. Now, I don't know how you choose to do this. One way to do it is if you buy a whole bunch of big thick concrete shielding casks and then you multiply your storage requirements, you know, appropriately, or you build, you know, a hot cell type of facility, shielded wall, cranes and all that sort of thing for handling.

MS-3

But this Alternative 5 has not been well thought through at all, even if you're talking about interim. Today, part of the shielding for this stuff is supplied because it's down in the ground. Part of it is supplied because it's in these tanks where the place, the vault where it's stored is in the ground and it has a big

Response to Comment MS-3

DOE considered the need for additional shielding when waste space requirements for additional storage capacity were calculated for this alternative. Text has been included to describe this assumption in Sections 2.7.1.2 and 4.6.1.6, and to address construction impacts of the storage facilities in Section 4.8.6.1.

thick concrete shield on the top. So once you pull it out, you're going to have to replace it.

Waste coming out from REDC, they have two types of casks. One type has 6-inch thick special concrete type walls; and then the second type has 12-inch. When we took a hundred gallons of sludge out of the Tank WC-14, and that's a pretty small quantity in comparison, that required a 12-inch thick shielding.

So there are a number of things here in connection with Alternative 5 that needs to be thought through, even if you're only talking interim storage. The one with cement, the volume of that won't go up as much as the volume would for the first two.

One other comment which I have on the preferred alternative has to do with the accident analysis that's been rather skimpy, because they haven't really considered the type of accidents that can happen. There are two examples which are classic accidents that are considered in processing plants. One is an explosion in the evaporator or an explosion in the calciner, if you have high-level waste. Although this is not legally high-level waste, because high-level waste only comes from first cycle solvent extraction in the fuel reprocessing plant. A research facility like ORNL does not legally generate high-level waste, but these wastes are like high-level waste. They're

MS-3 (cont.)

MS-4

Response to Comment MS-4

DOE considered a wide range of potential accident scenarios and selected those for detailed evaluation that seemed credible. With regard to the Low-Temperature Drying Alternative, DOE did consider the possibility of an explosion accident and concluded that further evaluation was not necessary based on a combination of the low consequence and probability of the explosion scenario. The low-temperature drying process, unlike a calciner process, is a low-energy evaporation process. The wastes would be treated in small (approximately 1 m^3) batches. The waste would be dried in an area separated from workers by a 2-ft-thick radiological shielding wall, and the area would have a separate ventilation system.

With regard to the second accident scenario suggested by the commentor, plugging the filters on the ventilation system, DOE did evaluate a fire accident with filter failure, and the radiological risks and consequences are provided in Section 4.11.

very hot. We're not talking about sludge down in the tank.
The second accident, which is a pretty classic accident, if you got a lot of particulates, you can plug your filters on your ventilation system and have pressure build up and stuff can blow out. There is other things, but these are things that need to be looked at a fairly early stage in the design so that when you're designing your plan, you include protection for these. You may still have to consider an accident analogy, but you put in at that point there are things that you hope will prevent them from happening, or if it happens, you know how you will deal with it.

A third one -- and this one is maybe not so likely -- what happens if somebody inadvertently wears some enriched material, you could have a criticality accident. I don't think you're supposed to get that kind of material, but there was unused radiator fuel samples from experiments that went out and cans were put in burial grounds. You know, whether all the records are good and whether everybody knows for sure, you know, where those things are, I don't know. I merely know that it went.

BILL CAHILL: Thank you. Any other comments? Before we go there, I appreciate those comments. We will definitely go back and make sure that we have thought through Alternative 5 in the context of the

MS-4

(cont.)

MS-5

Response to Comment MS-5

Regarding criticality of the solid wastes in the buildings, bunkers, and trenches, DOE has no process knowledge to suggest that enriched materials would be part of the waste. In addition, process procedures, to be developed after Foster Wheeler operational plans, will be followed that avoid criticality. For example, the first step in receiving waste in casks or containers will be to perform nondestructive assay of the waste to determine the presence of any enriched material.

additional shielding that may be required for the storage. We also recognize stewardship as a significant item to be dealt with regards to leaving this material in place for any length of time. We certainly will take that comment under consideration.

Any other comments, please? Norman.

NORMAN MULVENON: I'm Norman Mulvenon. I want to take a look at the transportation issue. This is for the preferred alternative or for any alternative where we're moving material onsite. When we were involved with the End Use Working Group, in particular we took a look at SWSA 5 North, and there were a variety of containers, concrete casks, metal barrels, wood boxes, and we were informed at that time that some of these containers had been breached. As a matter of fact, in the EIS there is an allusion to that by pointing out that there had been some leaking into the soil.

Now, what we're a little bit concerned about is that most of the discussion about transportation has been about offsite, and onsite transportation has been looked at primarily as no threat to the outsiders. And there is really not very much information there about how you're going to move the stuff from SWSA 5 North to the treatment facility. I went through that prologue in order to point out that it's been well documented that there is a

NM-1

Response to Comment NM-1

DOE has added discussion and analysis of on-site transportation in Section 4.8. In Section 4.8.1, the EIS describes the waste retrieval and on-site transportation activities in detail.

The program will include procedures to keep radiological exposure as low as reasonably achievable (ALARA). Completion and enforcement of Radiological Work Permits (RWPs) will be done. The RWP, developed by the prime contractor, is an administrative mechanism that is used to establish radiological controls for performing work in radiation areas. It is used to control entry into radiation areas, contamination areas, and airborne radioactivity areas. It provides workers information about the radiological conditions of a work area, stipulates entry requirements, and provides a mechanism to correlate specific work activities with worker exposure.

possibility that there are breached containers and that there has been leaking into the soil and we think this is kind of a tricky operation --

BILL CAHILL: Right.

NORMAN MULVENON: -- to move the material from SWSA 5 North to the treatment facility. We don't think that it's been covered very well in the EIS. As a matter of fact, it's rather a cavalier way of looking at it. We think it should include more discussion about that. What we're concerned about is safety to the workers. We agree that there should be no threat to outsiders because outsiders are not allowed in there and it will be protected from that standpoint. But we think there is a problem about the actual workers themselves in the movement of that material.

GARY RINER: You know that this document does not look at the actual retrieval of that material.

NORMAN MULVENON: I understand that.

GARY RINER: That was done under the CERCLA process. So the assumption that we took was that the material was safely packaged when we transported from that remediation effort to the facility.

NORMAN MULVENON: Is that true?

BILL CAHILL: The analysis, as Gary indicated, in the document begins at the loading dock of the processing plant with the material delivered there. The

NM-1 (cont.)

NM-1 (cont.)

NM-1 (cont.)

NM-1 (cont.)

Response to Comment NM-1 (cont.)

Specifically, the permit includes a description of the work; the area radiological conditions; and training, protective clothing, respiratory protection, and dosimetry required for the work area. Additionally, measures to control the time that workers are allowed to work in the radiological area are stipulated in the RWP. The lead group responsible for conducting work in the area initiates the RWP, and it is reviewed and approved by the DOE's facility's Radiological Control Organization.

Requirements include exposure prediction prior to the work, daily briefings, monitoring as needed, etc. External dosimetry consisting primarily of thermoluminescent dosimeters will be used. Internal dosimetry consisting primarily of urinalysis for radionuclides will be used. Radiation surveys of the workplace to detect any contamination outside controlled areas will be conducted. Surveys of equipment and vehicles leaving controlled areas to establish handling and use requirements will be required. Personal protective equipment per Selection and Use of personal protective equipment or equivalent will be required. Retrieval accidents would result in 6.3E-05 LCFs to the public and 7.5E-04 fatalities to involved workers from industrial accidents.

The waste would be hauled by truck from the SWSA 5 North area over a 1.1-mile gravel road to the proposed treatment facility. On-site transportation would result in 2.9E-05 LCFs to the public and 3.3E-05 traffic fatalities.

exhuming of the material from storage in the trenches or the bunkers will most likely come under an operational activity with related health and safety plans and other oversight of those activities that would cover worker safety and was not included as part of this document, correct.

BILL CAHILL: But the Melton Valley proposed plan had documented all the retrieval of the waste that we were going to retrieve out of SWSA 5 North. All of that was covered under CERCLA. All we did was allow for that volume to be processed in this facility if, in fact, the Record of Decision indicates to dig it up. This EIS didn't really address going and digging any of that waste up. That's all in the Melton Valley proposed plan.

NORMAN MULVENON: All I'm talking about is transportation. What is the containerization? Does anybody know? What is the packaging?

GARY RINER: The packaging of the containers that are supposed to be retrieved are the concrete casks. Regulators have agreed not to go after any of the wooden boxes or any of those things that the risk to the workers would exceed any risk that we might ever have for potential offsite releases.

NORMAN MULVENON: Okay. Thank you.

GARY RINER: We will take a look and revisit what we did for onsite transportation.

NM-2

NM-2 (cont.)

Response to Comment NM-2

The containers to be retrieved from the trenches are concrete casks. The regulators have agreed not to require DOE to remove wooden boxes or other material from the trenches for which the risks to worker safety may outweigh the benefit of removal of the waste. Section 4.8.1.1, **Retrieval of subsurface remote-handled TRU containers**, describes in detail the process assumed for excavation and overpacking the buried containers in preparation for loading and shipment to the treatment facility. In the bunkers and buildings, wastes are in drums or metal B-25 boxes.

NORMAN MULVENON: It is mentioned in here, but in a rather cavalier way.

GARY RINER: We assumed when we picked up the package that the package was sound and we hauled it over to the building; not with the details of where you're going. But I understand your issue.

BILL CAHILL: Mr. Weeren, I think the lady in back of you had a comment and then we'll get to you.

PAMELA WATSON: You couldn't see. I thought of a couple of other questions. I'm Pam Watson.

One, has Foster Wheeler done this kind of work before in other locations? And if so, where?

BRYAN ROY: This work expands a lot of different activities. Therefore, it would expand or extend a lot of projects we've done. Actually processing the transuranic RH-waste to WIPP, this is a first-time endeavor for anybody within the system. Certain aspects are new. None of the techniques necessarily are new in containment. Some of the steps, some integration of the steps of our first shipment of RH-waste to WIPP.

PAMELA WATSON: The other question is in regard to things that are in the burial grounds. Isn't it true that in a lot of cases DOE really does not know what is buried in some places or even where it is buried in some places in some cases?

NM-2 (cont.)

PW-6

PW-7

Response to Comment PW-6

The treatment of TRU waste using the low-temperature drying method is a first-time endeavor for Foster Wheeler; however, Foster Wheeler has performed many of the process steps in a low-temperature drying process on other projects. The low-temperature drying process proposed for this project, however, will have some new steps that Foster Wheeler has not performed. In addition, the integration of all these steps into this specific process has not been previously performed by Foster Wheeler.

Response to Comment PW-7

For the 23 trenches considered for this EIS, DOE has fairly good information on the waste, including surface dose readings of the casks when they were placed into the trenches.

BILL CAHILL: For the SWSA 5 trenches that we're talking about, in terms of the material that's buried or stored, there are existing records for waste that went into those trenches and very good records for the material that are in the bunkers and the storage buildings, from what I understand. The trenches, Gary probably has more information on that.

GARY RINER: Those 23 trenches that they're talking about exhuming are just a minor subset of the buried waste on the Oak Ridge Reservation. You're right, I think, in your comment that there are some places where over the years records have been lost or whatnot. But with the 23 trenches that are being proposed under the Melton Valley ROD to be exhumed and then processed in this facility, there are pretty good records. Most of that waste actually came from the REDC facility, where a large portion of our inventory waste also came from. So they have only done a limited number of -- and Mildred can comment on this -- they have done a very limited number of experiments ever in the REDC facility. So the waste that has been generated over the decades has been basically the same kind of waste.

PAMELA WATSON: For those 23 trenches, you say the records are pretty good. And can we have access to those records?

PW-8

Response to Comment PW-8

Unclassified information on wastes in the 23 trenches, the casks in the bunkers, and the drum wastes in the metal buildings would be available to the public under CERCLA as part of the administrative record of the Melton Valley Watershed.

The Melton Valley Watershed, situated just south of ORNL, encompasses approximately 1062 acres. ORNL historic missions—plutonium production during World War II and nuclear technology development during the postwar era—produced a diverse legacy of contaminated inactive facilities, research areas, and waste disposal areas in Melton Valley. The major problems identified in Melton Valley are the presence of high inventories of short-half-life radiological wastes, contaminant releases to surface water, and widespread contamination in secondary media. Principal contaminated areas being addressed under the CERCLA process in the Melton Valley Watershed include buried wastes, landfills, tanks, impoundments, seepage pits and trenches, hydrofracture wells and associated grout sheets, buried liquid waste transfer pipelines, leak and spill sites, surface structures, and contaminated soil and sediment.

GARY RINER: I guess so. I hate to throw out yeah, you can, when it's not my authority to say. I don't see why not. Those records should be clearly in the Melton Valley proposed plan. It should be delineated very specifically, because it is one of the streams that's going to be exhumed under that Record of Decision, and it should be all delineated there.

BILL CAHILL: Herman.

HERMAN WEEREN: I'm Herman Weeren again. And I would like to expound on my prejudices against vitrification. We did a study once upon a time of vitrifying the wastes that were in the gunite tanks, which essentially is the same thing he's talking about. Engineering called me up twice a week. We found an off gas stream you have to analyze for. We have nitrates coming up, we have mercury coming up, cesium (inaudible). That off gas stream kept growing and growing and growing and growing, and it got exceedingly complex.

The treatment given here is very quick and off the board, and I don't think you have even a hint of the complexity. And also, if any amount of cesium volatilizes and plates out on the off gas system, you're going to have a real hard time moving it. I don't know if you're going to move it without endangering health, welfare and the roads and everything else, which wasn't covered

HW-3

Response to Comment HW-3

DOE acknowledges that some uncertainty exists with all of the treatment processes including vitrification. However, vitrification technology has and is being used successfully at other DOE sites such as West Valley, Savannah River, and Fernald.

either.

I think vitrification sounds nice, but I don't really believe it's a practical way to handle anything like this. It almost has to be done on the waste level because you can't take something that worked at Hanford for totally different waste and apply it here.

BILL CAHILL: Thank you.

GARY RINER: Let me ask, Herman, your comment is on the vitrification process, not the proposed alternative, right?

HERMAN WEEREN: Right.

GARY RINER: Okay.

BILL CAHILL: Thank you.

HERMAN WEEREN: Vitrification.

BILL CAHILL: I think Ms. Sears.

MILDRED SEARS: This is an added comment to Herman's about volatilization with the vitrification. In the analytical laboratory, when we analyzed these samples, when they tried one of the standard procedures for measuring gross alpha and beta, which involved drying samples on a plate, we found we were losing 50 percent of the cesium. We had to go to a different method, which did not require heating.

So this is merely, you know, providing added support to his comment for things to volatilize. I

HW-3 (cont.)

HW-3 (cont.)

HW-3 (cont.)

MS-6

Response to Comment MS-6

DOE's preferred alternative for treating the MVST waste is low-temperature drying, not vitrification. DOE acknowledges that some uncertainty exists with volatilization and decomposition associated with the high temperatures of the vitrification process. DOE estimated the amount of various compounds that would volatilize during vitrification (technicium-99 approximately 50%, cesium about 10%, etc.) This information is provided in Appendix B of the EIS and was used in computing emission impacts.

think you may well have other compounds in there, too, that during vitrification will be a complication. For example, there is a lot of uranium there, uranyl nitrate can be composed to nitric acid (inaudible) in the off gas. There is just a lot of things. Herman probably knows more of these. You have lots of things and then they can plate out in the off gas line and cause you problems. With some of these you can also get stuff that's picked up and just plain carried over in the early stages of it.

MS-6

(cont.)

BILL CAHILL: Thank you. Yes.

SUSAN GARAWECKI: I'm Susan Garawecki, and I'm the executive director of the Local Offsite Committee. My questions have more to do with the end of the process where the waste is shipped, particularly the Waste Isolated Pilot Plant. We'll call it WIPP for short.

SG-1

BILL CAHILL: Okay.

SUSAN GARAWECKI: Currently, there is a problem with the RCRA portion of their permit from the State of New Mexico. If that is not resolved in DOE's favor, is that going to influence which of the treatment alternatives you might use?

SG-1

(cont.)

BILL CAHILL: Let me start off by saying, and Wayne, correct me if I'm wrong, all three of the viable treatment alternatives that we've looked at will treat LDR'S. And we treat LDRs so that if WIPP does not open, we

Response to Comment SG-1

DOE evaluated an alternative in which the waste is treated and stored onsite at ORNL (Treatment and Waste Storage at ORNL). The wastes would be treated to LDR standards to allow on-site storage at ORNL if the WIPP is not able to accept waste from the TRU Waste Treatment Facility as the waste is treated. DOE plans, however, to ship treated waste offsite as soon as disposal space is available.

can store for some undetermined period. But if it's not worked out to DOE's favor, Gary, do you have any other information on WIPP and the status of how things are going there with the WAK?

GARY RINER: Well, certainly the RCRA permit does not include provisions to accept remote-handled waste, if that's what you're referring to.

SUSAN GARAWECKI: Well, also implied in the beginning they want basically every disposal container tested for the hazardous constituents.

GARY RINER: We're a little bit ahead of the game there. We were actually doing 100 percent repackaging. That's the way our project was set up. So that doesn't have as large a ramifications on us as them not being able to accept remote-handled waste because we don't have a permit for it.

Both Bryan and I are flying to New Mexico Monday to meet with the manager out there to talk about remote-handled waste, to talk about where they need to get their program to be in line with ours. Hopefully, the department will move towards getting that incorporated into the RCRA permit. We've talked to the state about having a state to state and DOE to DOE meeting where both the New Mexico and Tennessee regulators will sit down and talk to each other about the aspects of handling remote-handled

SG-2

Response to Comment SG-2

The proposed action would result in 100% repackaging of waste. DOE would comply with the WAC for WIPP prior to any waste being shipped to this site.

waste. New Mexico really doesn't have any experience in that area, so they're fearful of putting it into the permit. So we're looking at a plan to start some communications on the regulator aspect level to try to get that put into the permit. So whether that comes to fruition, Susan, who knows. But Oak Ridge is making a concerted effort to make it happen. We're being very proactive in pushing WIPP.

SUSAN GARAWECKI: It sounds like there is a possible contingency for a mixed alternative where you end up storing perhaps the remote-handled and shipping.

GARY RINER: Sure. One of the concerns is if you end up with a dried product or vitrified product versus a grouted product and you do have to store it long-term, a hundred year stewardship. We want to be careful that whatever waste form we choose to do that with, it's a sound waste form and it's something that's not going to cause us all kinds of maintenance nightmares that was alluded to earlier.

We believe that the dried product is going to be fine. It is right now planned in the baseline to be placed in carbon steal containers and immediately shipped to WIPP. If we decide that, in fact, it's not going to be able to be shipped to WIPP, we are going to upgrade to stainless steel containers. That's the only thing that

SG-3

Response to Comment SG-3

Under Treatment and Waste Storage at ORNL, DOE examined the impacts of treating and storing all the treated waste at ORNL. The impacts analyses for this alternative would bound the possible situation described by the commentor in which a portion of the waste is shipped offsite, while some is stored onsite at ORNL.

makes sense to store long term in this humid environment and all that we've got. It is going to require some design of a shielded device, and we're looking right now, Mildred, at concrete sleeves to actually put 72-B liners in to provide the shielding that you referred to. So we are looking at contingency planning if, in fact, WIPP does not open to meet our schedule. We're also pushing WIPP and trying to get them to move forward as well.

SUSAN GARAWECKI: I guess I had one other question. At what point does this EIS end and the WIPP, I guess, EIS pick up as far as the worker safety? Because certainly the form in which it's shipped and the number of shipments, one is more compact than another, might have an impact on worker safety of WIPP, although it might not, that particular impact might not be worked into this EIS.

BILL CAHILL: Let me take a shot at that, and then Wayne can give us some additional information. In terms of worker safety, this analysis took into account both involved and non-involved workers related to focusing on the processing plant and the vicinity of the processing plan.

In the transportation portion of the analysis, we've looked at risks, both radiological and non-radiological risks related to just the bulk of the volume going across the roadways. I would imagine, although I can't state this for a fact, that certainly the WIPP EIS

SG-4

Response to Comment SG-4

The TRU Waste Treatment EIS summarized transportation impacts from treated TRU and low-level wastes from Oak Ridge to WIPP and NTS, respectively. Worker safety concerns at WIPP and NTS are addressed in *Waste Isolation Pilot Plant Disposal Final Supplemental Impact Statement*, DOE/EIS-0026-S-2, U.S. Department of Energy, Washington, D.C., September 1997, and *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal for Radioactive and Hazardous Waste*, DOE/EIS-0200-F, U.S. Department of Energy, Washington, D.C., May 1997.

As long as shipments from ORO, as a certified waste shipper, meet the WIPP WAC, the impacts to workers would have been bounded by the analysis in the WIPP SEIS.

would evaluate involved and non-involved workers related to those operational activities. Fill in the gaps here, guys.

WAYNE TOLBERT: We did not. This EIS did not deal with worker safety, if you will, at WIPP or NTS. We looked at this information and the impacts associated with that, but when it got there, we assumed that in essence, that's where one ended and the other one picked up.

GARY RINER: WIPP pays for the transportation to their facility. They're totally responsible for that transportation crew that they're going to have. And both in their EIS and their supplemental EIS that was analyzed. That's a huge, humongous Environmental Impact Statement. They did look at those activities. I don't know what kind of bounding analysis they did to assume we had dried product or vitrified product or grout product. So I don't think the risk to a worker or to a citizen by virtue of the 72-B cask is dependent upon waste form.

SUSAN GARAWECKI: Your waste form may determine how many of those go on the road?

GARY RINER: Right. Which we have those numbers pretty well articulated.

BILL CAHILL: That does for sure make a difference.

SUSAN GARAWECKI: Okay. Thank you.

MILDRED SEARS: Going back to the

SG-5

Response to Comment SG-5

The commentor's statement that the waste form will determine the type of shipping containers needed and the number of shipments is correct. This information is presented in Section 4.8.7, Table 4-15, of the Final EIS.

preferred alternative. Sodium -- a good quite a bit of sodium nitrate is a dried product. Sodium nitrate is called hygroscopic. That means it picks up moisture very readily from the air. And once you start picking up moisture, it's going to be corrosive on your container. I don't know what the lifetime is for sodium nitrate in stainless steel cans, but you may want to look a little more at how industrial production companies store their sodium nitrate.

I believe that it says that the waste product is to meet RCRA LDR, which stands for land disposal restrictions, and one of those requirements have to do with leachability. I'm not aware of there having been any laboratory scale test run with an actual sample with a pH adjusted to whatever pH you plan to process that, and then dry and leached to determine whether the sample passes the LDR with respect to leaching. I know that our compliance people at ORNL says that in their experience that lead concentrations as high as we had in the sludge, they generally flunk. That doesn't mean it's going to flunk. It merely means that they were warning me that we should be prepared for the probability that it might flunk.

As far as additives, the additives that I know of were developed for soluble heavy metals in slightly contaminated water. They weren't really developed for high salt content material. And yet they may or may not work on

MS-7

MS-8

Response to Comment MS-7

The carbon steel containers proposed for on-site transportation are treated for corrosion prevention/ resistance (for use in humid ambient conditions). After treatment, the wastes would not be corrosive if kept dry. However, the potential for corrosion remains due to the hydroscopic nature of these materials. The hydroscopic nature of these materials will need to be addressed for interim storage. Storage of these wastes in a humid environment may result in the need to address moisture buildup inside the container. One option available to handle this potential is to use stainless steel containers and possibly one-way temporary check valves or vents to eliminate moisture buildup.

Response to Comment MS-8

Section 9(a)(1) of the WIPP Land Withdrawal Act exempts TRU mixed waste for disposal at WIPP from LDR standards. DOE is currently undertaking small-scale treatment of the actual samples of sludges to see if they meet LDRs.

the supernate, but I would say that there is a risk that if the sludge and dried solids don't pass initially, I think your chances of the additives working are slim. And in a manner of speaking, this is Foster Wheeler's problem, but it becomes the community's problem if they don't pass the LDR, and for that reason WIPP won't take it. I'm basically saying I think some properly planned and conducted experiments might be very worthwhile.

Secondly, you have to do them on real sludge. You cannot do them on surrogates. And because there is considerable variation from tank to tank to tank, and you certainly won't empty all the tanks at one time, you're going to have to check out several different sludges. You can't work on one sample.

UNIDENTIFIED VOICE: Have the experiments been done?

GARY RINER: They are being done as we speak. We had it planned to do it on actual samples. Foster Wheeler is not paying for that. I'm paying for that because I had the same concern that you had, Mildred. If they fail, then we've all failed. It's a problem with the department. So in conjunction with the EM-50, we are doing some testing, planned later this year, on actual sludge. I'm tired of surrogates. I'm like you. We got to go for the real thing and see what it actually does, whether or not

MS-8
(cont.)

it meets the LDR requirements are not.
Let me clarify something here. Most of these sludges are remote-handled TRU. It does not have to meet LDR to be shipped to WIPP. It doesn't even have to be treated for its RCRA constituents. We, as a department, chose to specify in the contract treatment to LDR's in case we get stuck with the waste here in Oak Ridge. We wanted it to be LDR compliant so we could safely store the stuff under RCRA provisions, okay. But to ship it to WIPP, it doesn't matter if it meets LDR or not. They don't care. There is a distinction there that we needed to clarify.
Now, with the supernates, our plan is to send them to the Nevada Test Site, by all means, they must meet LDR, because they don't accept mixed waste.
MILDRED SEARS: May I suggest that Foster Wheeler get some input in planning so that they're operating under something that sort of matches.
GARY RINER: Foster Wheeler has been in the meetings with us, as has the laboratory, Jack Novathal from DOE, Bryan, we have together put together the matrix. We don't want to do something that they're not going to do in the real world. So we're trying to make this as much a real life situation as we possibly can.
BILL CAHILL: Go ahead.
BRYAN ROY: I'm Bryan Roy. I'll add,

MS-9

Response to Comment MS-9

Foster Wheeler is coordinating closely with DOE and the laboratory performing the tests in the event that the Low-Temperature Drying Alternative is selected.

Mildred, that we're generally trying to wash (inaudible) nitrate to supernate to a filtrate side, and the solids, the non-dissolved metal (inaudible) you were referring to will generally be washed with most of the nitrate so we don't have that competition that you mentioned. That is part of what Roger --

GARY RINER: Roger Spence.

BRYAN ROY: -- he's taking that into account.

BILL CAHILL: Other questions, please? Bob.

ROBERT PEELLE: Bob Peelle again. I'd like to drive another nail into Alternative 5. We've already complained about the need for handling the stuff on long term. There is one additional aspect to that, however. I presume the long-term storage would be someplace in Melton Valley. Of course, you hadn't said that.

BILL CAHILL: Correct.

ROBERT PEELLE: Assuming that's true -- I shouldn't have used that word. Assuming it is in Melton Valley, the Melton Valley proposed plan and the ROD that we hope will be signed soon and all the analysis in the public, has assumed this material is gone, let's talk about what will happened in 100, 300 years.

BILL CAHILL: Correct.

RP-2

RP-2 (cont.)

Response to Comment RP-2

This information is in the EIS. Should interim storage be required, the waste would be kept in Melton Valley near the existing bunkers and metal storage buildings at SWSA 5 North. See also response to comment ORSSAB-3.

ROBERT PEELLE: And your Alternative 1 or 5, those are invalid, and suppositions upon which those are based, fail. So you cannot have a ROD which is based on the removal of this material and an EIS that has Alternative 5. I don't think they can exist together. So I think you have to drop 5 or something else fairly fancy, because you can't have two conflicting documents, I hope.

BILL CAHILL: Good comment. Thank you, Bob. Any other comments, please? Questions? Everybody is ready to go home.

Let me do a couple of things then. First of all, thank you for your time for spending this evening talking about this. We appreciate your comments and we'll certainly take them to heart when we go about the business of producing the Final EIS.

The second thing is, if you did not get a hard copy of the hand-out or the impact evaluation, I do have a couple of extra copies. You can come up and see me and I'll get those to you. We also have several copies of the draft document here this evening. If you did not get a copy, we would like you to have one.

UNIDENTIFIED VOICE: Is it on the Web and what is the easiest way to find it?

BILL CAHILL: It is on the Web. The easiest way to find it would be -- Wayne.

RP-2 (cont.)

Response to Comment RP-2 (cont.)

DOE is required under the Council on Environmental Quality's NEPA regulations (40 *CFR* 1500–1508) to evaluate the No Action Alternative. DOE evaluated the Treatment and Waste Storage at ORNL Alternative because the Department believes it is reasonable, in accordance with the Council on Environmental Quality's NEPA regulations (40 *CFR* 1502.14), to analyze the impacts of potential storage of treated waste (e.g., in the event disposal capacity is unavailable).

In conclusion, decisions made as part of the CERCLA process do not preclude DOE from considering on-site alternatives in the EIS.

WAYNE TOLBERT: Under the DOE web site and look under the NEPA and follow the path under the NEPA. It's DOE headquarters.

PAMELA WATSON: Go to NEPA.

WAYNE TOLBERT: Then follow the menu. I don't remember precisely.

GARY RINER: Mary, do you know the menu?

MARY GREENE: I don't know the address.

GARY RINER: If you have trouble, call Bill or I, and we'll make sure you get in there.

BILL CAHILL: Thank you very much. This meeting will stand adjourned.

(Meeting adjourned)

- - - -

C E R T I F I C A T E

I do hereby certify that the foregoing is a true, complete and accurate record of the Public Meeting held on March 21, 2000.

I do hereby further certify that I am of neither kin, counsel nor interest to any party hereto.

LORENE SIGAL-Please include a copy of the CX for the 1.4 mile road from the proposed site to Hwy 95 in the Final EIS.

LS-2

MAL HUMPHREYS (via e-mail) -An issue regarding the Transuranic Waste Remediation Facility EIS and Air Permit Application has arisen from the March TRU EIS PUBLIC MEETING.

In both documents, the actual effective dose equivalent (EDE) rather than the potential EDE was used to compare to the 0.1 mrem/yr limit (which represents the air permit exemption limit under TAPCR 1200-3-9-.04(4)(d)9, and the limit above which continuous stack monitoring is required under

TAPCR 1200-3-11-.08(6)-incorporated EPA Reg 40 *CFR* 61.93(b)). The potential EDE is calculated from the potential radionuclide emission rate of the source, which is defined under 40 *CFR* 61.93(b)(4) and TAPCR1200-3-9-.04(4)(d)9 as the "release rate that would result if all pollution control equipment did not exist, but the facility operations were otherwise normal". Recalculation of the potential radionuclide emission rate and resulting potential EDE without using the HEPA filter removal efficiencies will most likely yield a potential EDE greater than the 0.1 mrem/year threshold. This source will therefore most likely need to be permitted and continuous radionuclide stack monitoring will most likely be required (as per TAPCR 1200-3-11-.08(6)-incorporated EPA Reg 40 *CFR* 61.93(b)).

MH-1

Response to Comment LS-2

A copy of the categorical exclusion for the road is included as Appendix G to the Final EIS.

Response to Comment MH-1

The values presented in the EIS are believed to be very conservative. Calculating the emission rate with control systems indicates an emission rate of radionuclides that would result in a dose rate of up to 6.3 mrem/year and 8.6 lbs/hour for particulate matter. If the unit, when built, does exceed the threshold limits, a Clean Air Act permit will be obtained before it is operated.

EARL McDANIEL (via e-mail)- In principle drying the sodium nitrate supernate from the MVST is a good idea. However, that is all it is an idea. What Foster Wheeler proposes to do is not supported by similar work published in the open literature. It is not based on a treatability study and on an engineering scale validation. It is only a good idea, which is cost effective (or cheap). Dried and powdered sodium nitrate may well pose a great safety hazard not only during processing but storage and shipment even if it "meets requirements." EM-1 EM-2

As to drying the sludge, this is even worse. The sludge contains all the TRU isotopes and most of the characteristically hazardous metals. Again, there is no data to support the Foster Wheeler approach. If Universal Treatment Standards (UTS) apply, it may not be possible to meet UTS without some sort of solidification/ stabilization. This needs to be determined on both a lab and engineering scale. Again, dried powder containing TRU isotopes is a very dangerous material. A little plutonium goes a long way. Once the plutonium gets out it is difficult to recover it. What I hear does not give me confidence that this project is safe or will be successful. One would think that DOE learned a lesson with the K-25 sludge problem. It appears not to be so. EM-3 EM-4 EM-5

Response to Comment EM-1

The Low-Temperature Drying Alternative uses the knowledge of the waste characteristics and treatment techniques to produce a waste acceptable for transport to and disposal at the identified waste disposal locations.

Foster Wheeler provided technical literature and experience documentation to substantiate its approach, available either in the open literature or from experienced industry sources. DOE reviewed the completeness of this information, independent of cost considerations, prior to contractor selection. An independent project assessment was also accomplished by DOE in early 1999 to assess this and other risks. TDEC also reviewed the proposed process as part of the applicant's RCRA permit, which has been granted. In 2002, prior to waste handling, both WIPP and NTS will also audit and affirm the project's capability to provide an acceptable waste product.

The commentor is correct in stating that the wastes from the MVSTs have not previously been treated in this manner. While all the proposed treatment alternatives evaluated in this EIS involve some uncertainties, in the case of the preferred alternative, the following factors were considered:

1. Industry experience drying similar materials and wastes.
2. Testing of surrogates in the proposed drying equipment by Foster Wheeler, another bidder that advocated drying, and ORNL some years ago.
3. Extensive characterization testing of the MVST wastes.
4. Full reversibility of the physical drying process.

Containment of the radionuclide content of the supernate solids is certainly the primary challenge involved with any treatment alternative.

Supernate wastes, which consist of sodium and potassium nitrate salts dissolved in water that is also contaminated with less than 2% (by mass) of several other soluble compounds and radionuclides, is not considered characteristically toxic under the federal hazardous waste (RCRA) regulations. Salts of similar composition, but not radioactive, are routinely dried in industries worldwide. Radioactively contaminated salts of similar composition have also been dried, but much less frequently, in the United States and Europe.

Response to comment EM-2

Sodium nitrate may pose a safety hazard with regard to explosions. DOE considered the possibility of explosion and concluded it was not a credible accident. DOE evaluated potential accident scenarios associated with this proposed treatment process. See response to comment MS-4 for details on potential explosion accidents. DOE evaluated credible transportation accidents and associated risks (Section 4.8).

Response to comment EM-3

With regard to drying the sludge, the data and experience upon which the Low-Temperature Drying Alternative approach was based included the following:

1. Nuclear industry experience drying sump sludges.
2. Testing of surrogates in proposed equipment.
3. Extensive characterization testing of the MVST wastes.
4. Full reversibility of the physical drying process.
5. Toxic chemical fixation in industrial, waste waters.

At this time, the UTSs, which are RCRA treatment standards applicable to listed wastes, are not expected to be applied to these sludge wastes because they are characteristically hazardous. The proposed treatment technology will render the RCRA-characteristic hazardous sludges nonhazardous by removing their hazardous