

Waste Disposition on the Hanford Plateau Remediation Contract

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

Contractor for the U.S. Department of Energy
under Contract DE-AC06-08RL14788



P.O. Box 1600
Richland, Washington 99352

Approved for Public Release;
Further Dissemination Unlimited

Waste Disposition on the Hanford Plateau Remediation Contract

D. J. Moak
CH2M HILL Plateau Remediation Company

G. C. Triner
M. S. Waters
CH2M HILL Plateau Remediation Company

Date Published
May 2009

To Be Presented at
Contractors Transportation Management Association

DOE
Melbourne, FL 32903

6/8/09 thru 6/12/09

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

Contractor for the U.S. Department of Energy
under Contract DE-AC06-08RL14788




**P.O. Box 1600
Richland, Washington**

Copyright License

By acceptance of this article, the publisher and/or recipient acknowledges the U.S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper.


Release Approval


Date


**Approved for Public Release;
Further Dissemination Unlimited**

LEGAL DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced from the best available copy.
Available in paper copy.

Printed in the United States of America



Waste Disposition on the Hanford Plateau Remediation Contract

Presented to: Contractors Transportation
Management Association
2009 Workshop

Presented by: Don Moak, M&EC/PF
Glen Triner, M&EC/PF
Mike Waters, Cavanagh's Services Group



The 2015 Vision

Hanford Site Cleanup

Richland Operations Office

Safe and Effective Cleanup that Protects the Columbia River

- Reduces the Active Site Footprint of Cleanup to 75 Square Miles (586 to 75)
- Significantly Reduces Long-Term Mortgage Costs
- At Completion, Shifts Emphasis and Resources to Full Scale Cleanup of the Central Plateau (75 square miles)
- Reduces Costs by "Right Sizing" Hanford's Infrastructure via a Mission Support Contract
- Minimizes Injury to Natural Resources

B & C Area

- ✓ Interim Safe Storage of C Reactor Complete
- ✓ B Reactor Designated as a Museum or Interim Safe Storage Complete
- ✓ All B & C Area Final ROD Remedial Actions Complete
- ✓ All B & C Area Groundwater Remedies Implemented
- ✓ 6 Facilities Demolished
- ✓ 40 Waste Sites Remediated
- ✓ ~381,000 Tons of Soil Removed

N Area

- ✓ Interim Safe Storage of N Reactor Complete
- ✓ All N Area Final ROD Remedial Actions Complete and TSD Units Closed
- ✓ All N Area Groundwater Remedies Implemented
- ✓ 108 Facilities Demolished
- ✓ 61 Waste Sites Remediated
- ✓ ~157,000 Tons of Soil Removed

D & H Area

- ✓ Interim Safe Storage of D, DR, and H Reactors Complete
- ✓ All D & H Area Final ROD Remedial Actions Complete
- ✓ All D & H Area Groundwater Remedies Implemented
- ✓ 16 Facilities Demolished
- ✓ 56 Waste Sites Remediated
- ✓ ~1,700,000 Tons of Soil Removed

IU2 & IU6 Area

- ✓ Interim Safe Storage of F Reactor Complete
- ✓ All IU2 & IU6 Area Final ROD Remedial Actions Complete
- ✓ All IU2 & IU6 Area Final ROD Groundwater Remedial Actions Complete
- ✓ 1 Facility Demolished
- ✓ 50 Waste Sites Remediated
- ✓ ~962,000 tons of Soil Removed

K Area

- ✓ K East Basin Demolished
- ✓ Interim Safe Storage of K East Reactor Complete
- ✓ K West Sludge Removed from the River Corridor
- ✓ Interim Safe Storage of K West Reactor Initiated
- ✓ All K Area Final ROD Remedial Actions Complete and TSD Units Closed with the exception of those associated with K West
- ✓ All K Area Groundwater Remedies Implemented
- ✓ 2300 Tons of Scrap Nuclear Fuel Removed
- ✓ 109 Facilities Demolished
- ✓ 2 Waste Sites Remediated
- ✓ ~351,000 Tons of Soil Removed

Plutonium Finishing Plant Complex

- ✓ All Special Nuclear Material Shipped Offsite
- ✓ Slightly Irradiated Fuel Shipped to the Canister Storage Building for Safe Guarding
- ✓ PFPC Complex Reduced to Slab on Grade
- ✓ 18 Facilities Demolished

400 Area

- ✓ Fast Flux Test Facility in Surveillance and Maintenance

Central Plateau Cleanup

- ✓ All 200 West Carbon Tetrachloride, Uranium and Technetium 99 Groundwater Remedies Implemented
- ✓ Conduct Additional Cleanup as Funds Become Available

300 Area

- ✓ All 300 Area Final ROD Remedial Actions Complete and TSD Units Closed
- ✓ All 300 Area Groundwater Remedies Implemented
- ✓ 185 Facilities Demolished
- ✓ 95 Waste Sites Remediated
- ✓ ~923,000 Tons of Soil Removed
- ✓ Final Remediation of 613-10 B, 613-11 Burial Grounds Complete

* Does not reflect all work

IU = Isolated Unit
ROD = Record of Decision
TSD = Treatment, Storage, Disposal

CHPRC Waste Management Team



- CHPRC — Waste & Fuels Management
- Cavanagh Services — Transportation/Shippers
- M&EC — Waste Support Services, Burial
Grounds, Central Waste Complex,
T Plant, Nuclear Facility Operations

CHPRC Waste Management Staffing Issues



- Total ARRA Scope will require over 400 professionals and 150 bargaining unit personnel to support the CHPRC.
- Normal attrition and work-scope already strains resource capacity of Waste Management professionals.
- Shippers, Waste Management representatives, Engineers and support functions are in high demand.
- Issues include salaries, relocation expenses, “retreads”, experience.


Waste Specific Staff Needs Support ARRA




- Total \approx 100
 - 50 Engineers, Waste Specialists, Field Supervisors, and Craft.
 - 12 Radcon
 - 12 Program Support
 - 8 Shipping Support
 - 7 Safety/QA
 - 15 Infrastructure Support

Life Cycle Work Scope


Waste and Fuels Management Project Work Scope *Treatment, Storage, Disposal, and Transportation Services*




Retrievably Stored Waste Management Logic




Low Level Waste Management Logic



Mixed Low Level Waste Management Logic



Liquid Waste Processing and Disposal Logic



Container Shipments (to Date)



- 223 Box Shipments
- 446 Drum Shipments
- 24 Unique Shipments
 - 3 DSWC Shipments (FFTF).
 - 233S SWB (T Plant)
 - 66 m³ Box (CWC)
 - 2 IP2 Glovebox (PFP)
 - Transformer (FFTF)
 - Large box Rail Shipment (CWC)
 - IXC & Sand Filter Monoliths (KBC)


Offsite TSDs Shipped To



- **PESI (DSSI)** – Oak Ridge, TN., Incinerator for destroying organic (liquids) hazardous constituents. Recently permitted to treat TSCA wastes.
- **M&EC** - Oak Ridge, TN., Vacuum thermal absorption for destroying organic (solids) hazardous constituents.
- ***EnergySolutions*** - Clive, UT., Non-thermal treatment including macroencapsulation. Limited to NRC Class A Waste.
- **PFNW** - Richland, WA., Macro, Volume Reduction, Stabilization and Neutralization of MLLW and LLW.



CASE EXAMPLES



66m³ Box



- Waste Generated on 9/25/95
- Contains two (complete) portable air exhauster units used to ventilate underground storage tanks.
- Stored from 9/29/95 to 2/24/09 due to a lack of a readily identifiable treatment path for oversize containers and limited funding.
- Disposition Options
 - Offsite cut, segregate, grout, and return to Hanford for onsite disposal.
 - Limitations: Physical acceptance and cost.
 - In-Trench Macroencapsulation at MW Trench or ERDF.
 - Limitation: Disposition of potential non conforming items (if any were noted).
 - Offsite shipment for bulk macroencapsulation & disposal (process utilized).
 - Advantage: Meets Off-site acceptance criteria and most cost effective process.

66m³ Box Photos


M&EC
Materials & Energy Corporation
A Subsidiary of Perma-Fix Environmental Services



66 m3 Box Movement
(Lifting Limitations Due to Lighting)



66 m3 Box Movement
(Lifting Limitations Due to Lighting)



66 m3 Box Staged for Loading



66 m3 Box Arrival @ TSD



66 m3 Box Placement

K-Basin Clarifier



- 100KW basin water clarifier
- “Overpacked” into IP-1 steel box (2.9 m x 3.2 m x 6.2 m)
- Gross weight - 6600 kg
- Internally shielded to meet Hanford Site dose rate limits
- Shipped via Hanford Risk-Based Transportation Safety Document as package not DOT compliant
- Transported from 100KW to Hanford Site Central Waste Complex; awaiting identification of a disposition path.

K-Basin Clarifier Box Photos



Loaded Clarifier Box



Off-Loading and Receipt inspection



Shielding Used to Control Dose


Disposition of Additional Wastes



KBC Sand Filter and IXC Monoliths (KBC to ERDF)

Concrete TRU Box From 4C Burial Grounds to CWC

M&EC
Materials & Energy Corporation
A Subsidiary of PermaFix Environmental Services




CH2MHILL
Plateau Remediation Company

Low Level Legacy Waste Shipment From W5 to PFNW

M&EC
Materials & Energy Corporation
A Subsidiary of Perma-Tix Environmental Services



Activated Metals Shipped From FFTF TO ERDF (Within Disposal Solid Waste Cask)



Backlog Soil Drums Staged Shipment to ERDF

M&EC
Materials & Energy Corporation
A Subsidiary of Perma-Fix Environmental Services



U.S. DEPARTMENT OF
ENERGY



CH2MHILL
Plateau Remediation Company